

CEMENTING PROGRAM

Moore #25-R

Surface:

Preflush	80 bbl.	Fresh Water	
Slurry 1	550 sk	Standard Cement	650 cu. ft.
TOC@Surface		+ 2% CaCl ₂	
		+ 1/4 lb/sk flocele	

Slurry Properties:	density (lb/gal)	yield (ft ³ /sk)	water (gal/sk)
slurry1	15.60	1.18	5.20

Casing Equipment: (Halliburton)

- 1 Type M Guide Shoe
- 1 Insert Float w Auto Fill
- 1 Weld A
- 4 S-4 Centralizer
- 1 Top Wooden Plug

Notes: If boulders or loss of circulation is encountered, then pump the following:

Preflush	60 bbl.	Fresh Water
	20 bbl.	Superflush 102
	10 bbl.	Fresh Water
Slurry 1	750 sk	Standard Cement
TOC@Surface		+ 2% CaCl ₂
		+ 1/4 lb/sk flocele