

Submit
District
District
1625
District
811 Se
District
1000
District
2040:

MAKE Correction

& RTN.

- wrong Name

- " Pool

- doesn't have "CSG Set."

[Signature]


State of New Mexico
Minerals and Natural Resources

Form C-103
Revised March 25, 1999

CONSERVATION DIVISION

2040 South Pacheco

Santa Fe, NM 87505



WELL API NO. 30-045-30601	
5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>	
6. State Oil & Gas Lease No. B-11242-47 & V-4832	
7. Lease Name or Unit Agreement Name <i>Ropco 8 #2</i> WF State 16	
8. Well No. #2	
9. Pool name or Wildcat Basin Fruitland Coal/Larper Hill ER Sand PC Ext.	

(DO
DIF
PROPOSALS.)

1. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	
2. Name of Operator Richardson Operating Company #019219	
3. Address of Operator 1700 Lincoln Street, Suite 1700, Denver, CO 80203	
4. Well Location Unit Letter <u>E</u> : <u>1438</u> feet from the <u>North</u> line and <u>1210</u> feet from the <u>WEST</u> line Section <u>8</u> Township <u>29N</u> Range <u>14W</u> NMPM San Juan County	
10. Elevation (Show whether DR, RKB, RT, GR, etc.) 5264 GR	

11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

- | | |
|--|--|
| <input type="checkbox"/> PERFORM REMEDIAL WORK | <input type="checkbox"/> PLUG AND ABANDON |
| <input type="checkbox"/> TEMPORARILY ABANDON | <input type="checkbox"/> CHANGE PLANS |
| <input type="checkbox"/> PULL OR ALTER CASING | <input type="checkbox"/> MULTIPLE COMPLETION |
| <input type="checkbox"/> OTHER: | |

SUBSEQUENT REPORT OF:

- | | |
|--|---|
| <input type="checkbox"/> REMEDIAL WORK | <input type="checkbox"/> ALTERING CASING |
| <input checked="" type="checkbox"/> COMMENCE DRILLING OPNS. | <input type="checkbox"/> PLUG AND ABANDONMENT |
| <input checked="" type="checkbox"/> CASING TEST AND CEMENT JOB | |
| <input type="checkbox"/> OTHER: | |

12. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompilation.

6/4/2001 MIRU AND SPUD WELL. Drill 8 3/4" hole to 140'. POOH. RIH w/3 jt 7" 20# K-55 surface casing.
Pump 30 sx cmt. Displaced with 4 bbls water. SDFC.

6/5/2001 Install BOP and test casing. Drill 6 1/2" hole to 760'.

6/6/2001 Circulate hole clean. LDDP. RIH w/ 4 1/2" float shoe, float collar, 18 jt 4 1/2" 10.5# J-55 casing.
Ran 4 centralizers. Circulate hole clean. Mix and pump 10 sx class B 2% c-lite, 100 sx class B 1/4# Cello.
Displaced with 12 bbl water and bump plug. Circulated 5 bbls cmt to surface.
CSG SHOE @ 760'. *sk*

9-23-99

where is CSG Set?

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE *John Whisler* TITLE OPERATIONS MANAGER DATE DEC. 12, 2001

Type or print name JOHN WHISLER Telephone No. 303-830-8000
(This space for State use)

APPROVED

BY _____ TITLE _____ DATE _____

Conditions of approval, if any:

K