

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE
(One - Instructions on re-
verse side)

Form approved
Bureau Order No. 40-11424
5. LEASE DESIGNATION AND SERIAL NO.

SF 077730

6. IS INDIAN, ALLEGED OR TRUE NAME

SUNDY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL ☐ GAS ☒ WELL ☐ VENT ☒ OTHER	7. UNIT AGREEMENT NAME
2. NAME OF OPERATOR El Paso Natural Gas Company	8. FARM OR LEASE NAME Sunray E
3. ADDRESS OF OPERATOR PO Box 996, Farmington, NM 87401	9. WELL NO. 5
4. LOCATION OF WELL (Give location clearly and in accordance with any State requirements. See also space 14 below) At surface 1850'N, 1640'W	10. FIELD AND NAME OF VEIN Blanco Pictured Cliffs
14. PERMIT NO.	11. SEC., T., R., M., QUARTER, AND SURVEY OR AREA Sec. 9, T-30-N, R-10-W NMPM
15. ELEVATIONS (Show whether DE, RT, CR, etc.) 6346'GL	12. COUNTY OR PARISH AND STATE San Juan New Mexico

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON* ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☒

FRACTURE TREATMENT ☒

SHOOTING OR ACIDIZING ☐

(Other) ☐

REPAIRING WELL ☐

ALTERING CASING ☐

ABANDONMENT* ☐

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)


17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

5-21-72

T.D. 3118'. Ran 99 joints 2 7/8", 6.4#, J-55 production casing, 3108' set at 3118'. Baffle set at 3108'. Cemented with 578 cu.ft. cement. WOC 18 hours. Top of cement at 2240'.

6-12-72

PBTD 3108'. Perf'd 3002-3014', 3024-3030' with 24 shots per zone. Fraced with 20,000# 10/20 sand and 18,750 gallons treated water. Dropped one set of 24 balls. Flushed with 800 gallons water.



18. I hereby certify that the foregoing is true and correct

SIGNED

John H. Wood

TITLE Petroleum Engineer

DATE June 14, 1972

(This space for Federal or State office use)

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE