

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form approved by
Budget, Circular No. 47, RIA-1

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other ☐
2. NAME OF OPERATOR
El Paso Natural Gas Company
3. ADDRESS OF OPERATOR
P. O. Box 990, Farmington, New Mexico
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1100' N, 810' W
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF
FRACTURE TREAT
SHOOT OR ACIDIZE
REPAIR WELL
PULL OR ALTER CASING
MULTIPLE COMPLETE
CHANGE ZONES
ABANDON*
(other)

☒
☒
☐
☐
☐
☐
☐
☐
☐

5. LEASE
NM 012647
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
Riddle D.
9. WELL NO.
4A
10. FIELD OR WILDCAT NAME
Blanco Mesa Verde
11. SECTION, R. M., OR B. K. AND SURVEY OF AREA
Sec. 22, T-31 N, R-9-W
NMPM
12. COUNTY OR PARISH
San Juan
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DE. NDS. AND VE.
6239' GL)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent data, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

6-10-77 T.D. 3513'. Ran 84 joints 7", 20#, K-55 intermediate casing, 3500' set at 3513'. Cemented with 393 cu. ft. cement. WOC 12 hours, held 1200#/30 minutes. Top of cement at 1900'.

6-14-77 T.D. 5716'. Ran 72 joints 4 1/2", 10.5#, K-55 casing liner, 2353' set 3363-5716'. Float collar set at 5699'. Cemented with 410 cu. ft. cement. WOC 18 hours.

11-22-77 PBTD 5699'. Tested casing to 3500#, ok. Perfed 5291, 5296, 5302, 5308, 5314, 5320, 5326, 5332, 5338, 5344, 5367, 5376, 5381, 5422, 5447, 5497, 5539, 5571, 5603, 5610, 5629, 5662' with 1 shot per zone. Fraced with 71,000#--20/40 sand and 76,000 gallons water. Flushed with 7010 gallons water. Perfed 4899, 4905, 4917, 4925, 4931, 4939, 4951, 4957, 4967, 4995, 5007, 5035, 5042, 5049, 5072, 5095, 5103, 5111, 5121, 5142, 5176, 5201, 5210, 5218 with 1 shot per zone. Fraced with 86,000#--20/40 sand and 86,000 gal. water. Flushed w/6720 gal. wtr. Set @ _____ ft.

Subsurface Safety Valve: Manu. and Type _____

18. I hereby certify that the foregoing is true and correct

SIGNED L. H. Blum TITLE Drilling Clerk DATE November 23, 1977


(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

*See Instructions on Reverse Side



RECEIVED

NOV 28 1977

U.S. Geological Survey
Farmington, N.M.