

**UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY**

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well gas well other _____

2. NAME OF OPERATOR
El Paso Natural Gas Company

3. ADDRESS OF OPERATOR
Box 289, Farmington, New Mexico 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1720'S, 1630'E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

5. LEASE
NM 04240

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Kelly

9. WELL NO.
2BA (PM)

10. FIELD OR WILDCAT NAME
Blanco Mesa Verde, Blanco PC

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 7535 T-30-N, R-10-W N.M.P.M.


12. COUNTY OR PARISH | 13. STATE
San Juan | New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6147' GL

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input checked="" type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) _____	



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1-18-80: PBTB 5421'. Tested casing to 3500#, OK. Perfed P.L. 4898,4903,4908,4924,4929, 4935,4940,4945,4950,4962,4968,4974,4980,4992,5006,5013,5020,5080,5133,5194,5250, 5257,5281' W/1 SPZ. Fraced w/76,670# 20/40 sand, 151,420 gal. wtr. Flushed w/ 6790 gal. wtr.

1-19-80: Perfed Men. & C.H. 4204,4274,4280,4302,4309,4316,4324,4351,4372,4380,4388,4396, 4404,4412,4420,4624,4641,4650,4742,4762,4770,4778' w/1 SPZ. Fraced w/91,600# 20/40 sand, 176,360 gal. wtr. Flushed w/ 6180 gal. wtr.
Perfed P.C. 2657-2680,2700-2714,2718-2730,2740-2750' W/16 SPZ. Fraced w/ 60,530# 10/20 sand, 65,420 gal. wtr. Dropped 3 sets of 16 balls each. Flushed w/4590 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.


18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Drilling Clerk DATE January 2, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

NMOCC



*See Instructions on Reverse Side