

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT--" for such proposals

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.
NM 28277

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.
ARBOLES 29 A #1

9. API Well No.
30-039-23272

10. Field and Pool, or Exploratory Area
Basin Fruitland Coal

11. County or Parish, State
RIO ARRIBA COUNTY, NM

SUBMIT IN TRIPLICATE

070 FARMINGTON, NM

1. Type of Well

☐ Oil ☒ Gas
☐ Well ☒ Well ☐ Other

2. Name of Operator


VASTAR RESOURCES, INC.

3. Address and Telephone No.

1816 E. MOJAVE ST., FARMINGTON, NM 87401 (505) 599-4300

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1525' FSL, 1540' FWL, SECTION 29, T32N, R4W



12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other REENTRY OPERATIONS

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The following re-entry was performed from 9-1-00 to 9-20-00:

Drill out cement plug from surface to 225' and cement plug from 2133' to 3800'. Set 5-1/2" whipstock at 3798', mill window, and drill 4-3/4" Fruitland Coal sidetrack to 4175' TD. Underream to 6" across interval 3802'-4143'. Had severe lost circulation and pipe sticking problems - abandoned sidetrack as per verbal approval from Jim Lavato. Pumped 80 sx cement plug from 4174' to 3750'. WOC and tag at 3784'. Pump 25 sx cement plug from 3784' to 3750'. WOC and tag at 3765' with 5-1/2" CIBP. Set CIBP at 3765' and RIH with whipstock oriented to 270 degrees (due west - 90 degrees from original sidetrack). Set whipstock 3758' and mill window in 5-1/2" casing (top of window @ 3744'). Drill new 4-3/4" sidetrack through Fruitland Coal to 4150' TD. Underream interval 3895' to 4150' to 6" diameter. Ran 4" 11.60# L-80 Hydril 521 FJ casing to 4149' KB. Cemented with 122 sx (303 cu. ft.) class H with 2% econolite followed by 120 sx (276 cu. ft.) 50/50/H/POZ with 2% gel, 5#/sx Gilsonite, 1/4#/sx FC, and 0.4% HALAD 344. Circulated 12 BBLS cement to surface. ND BOP, NU Wellhead, RD.

cc: BLM, Farmington (Or + 3)

N. Hall

Well File

14. I hereby certify that the foregoing is true and correct

Signed Charles W. Kugler

Title Engineer 505 599 4308

ACCEPTED FOR RECORD
Date 9-22-00

(This space for Federal or State office use)

Approved by _____

Title _____

Date NOV 30 2000

Conditions of approval, if any:

FARMINGTON FIELD OFFICE
BY [Signature]

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side