
Form 3160-5 (June 1990)	UNITED STATES DEPARTMENT OF THE INTERIOR	FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993
	BUREAU OF LAND MANAGEMENT	5. Lease Designation and Serial No.
Do not use this fo	SUNDRY NOTICES AND REPORTS ON WELLS orm for proposals to drill or to deepen or reentry to a different reservoir Jse "APPLICATION FOR PERMIT—" for such proposals	NM 0560427 6. If Indian, Allottee or Tribe Name
SUBMIT IN TRIPLICATE		7. If Unit or CA, Agreement Designation
1. Type of Well Oil Gas Well Other		La Plata Mancos 8. Well Name and No.
2. Name of Operator		- -
Benson-Montin-Greer Drilling Corp.		2 (I-6) 9. API Well No.
3. Address and Telephone No.		30-045-20314
4900 College Blvd., Farmington, NM 87402 (505) 325-8874		10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 2050' FSL, 635' FEL, Sec. 6, T 31 N, R 13 W		La Plata Gallup 11. County or Parish, State
	· · · · · · · · · · · · · · · · · · ·	San Juan, New Mexico
12. CHECK	APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPO	
TYPE OF	SUBMISSION TYPE OF ACTION	V
XX Notice o	f Intent D E C E V E Akandonment	Change of Plans
	Recompletion	New Construction
Subseque	ent Report III JUN 2 0 1997 LE Plugging Back	Non-Routine Fracturing
Π	Casing Repair	Water Shut-Off
Final Ab	pandonment Notice O CO No D Altering Casing	Conversion to Injection
	DIST 3	Dispose Water (Note: Report results of multiple completion on Well
13. Describe Proposed or Cor	mpleted Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starti	Completion or Recompletion Report and Log form.)
give subsurface loca	tions and measured and true vertical depths for all markers and zones pertinent to this work.)*	ing any proposed work. If wen is directionally drifted
Plugging F	Procedure:	
#1	Set bridge plug at 4200'. Cap with 12 sacks cement.	
#2	Spot cement plug from 4011' to 3616' (approx. 51 sacks cement).	
#3	Spot cement plug from 1475 ' to 1375 ' inside and outside $7.5/8$ " casing (approx. 34 sacks inside and 29 sacks outside).	
#4	Spot cement plug from 323' to surface inside and ou	tside 7 5/8" casing.
14. I hereby contify that the f	opegoing is true and correct	
Signed / MAN	Title Vice-President	Date 06/17/97
(This space for Federal o	_	
Approved by Conditions of approval, is	S/ Duane W. Spencer Title	Date <u>JUN 8 1997</u>

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Formation Tops: Lewis Slide - surface Mesa Verde - 1425' Mancos - 2620' Gallup - 3755'

WELL __ La Plata Mancos Unit #2 (I-6) SEC. <u>6</u> TWNSHP 31N RANGE 13W COUNTY San Juan STATE New Mexico



Cemented inside and outside

Top 5 1/2" Liner @ 3666' Cemented Bottom to 3700'

Cement top inside of 5 1/2" and 7 5/8" overlap Cement at 3700' by temp. survey

7 5/8" 26.40# N-80 Intermediate Casing @ 3961' Cemented w/

Perforations from 4240' to 4260' and 4292' to 4302'

5 1/2" 15.5# J-55 Shoe @ 4394'

TD 4394'

