

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)


1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
Northwest Pipeline Corporation
3. ADDRESS OF OPERATOR
P.O. Box 90, Farmington, N.M. 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 920' FSL & 1080' FEL
AT TOP PROD. INTERVAL: Same as above
AT TOTAL DEPTH: Same as above
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:


- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☒ Drld Operations.

SUBSEQUENT REPORT OF:

- ☐
☐
☐
☐
☐
☐
☐
☐
☐
☒



5. LEASE
SF 078998
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
San Juan 32-7 Unit
8. FARM OR LEASE NAME
San Juan 32-7 Unit
9. WELL NO.
#68
10. FIELD OR WILDCAT NAME
Basin Dakota
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec 34, T32N, R7W
12. COUNTY OR PARISH
San Juan
13. STATE
New Mexico
14. API NO.
80-045-24776
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6715' GR



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1-21-81 Drld ahead w/ gas.

1-22-81 & 1-23-81 GO ran IES/GR SNP/CDL Logs. Ran 217 jts (8293') of 4-1/2" (1636' of 11.6# & 6657' of 10.5#) K-55, ST&C set at 8307' KB. Dowell cemented w/ 260 sx Cl "B" w/ 8% gel, 12-1/2# fine gils/sx & 0.4% D-13. Tailed w/ 100 sx Cl "B" w/ 1/4# tuf-plug/sx & 0.4% D-13. Plug displaced w/ 131 bbls & down at 2215 hrs 1-22-81. Rig released at 0200 hrs 1-23-81. Wilson ran temp survey & found cement top at 3400' w/ PBTD at 8235'.

NOW WAITING ON COMPLETION.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Donna J. Brace TITLE Production Clerk DATE Feb 4, 1981

RECEIVED FOR RECORD

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

BY BW FARMINGTON DISTRICT

NMOCC