

CONFIDENTIALForm 3160-3
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**APPLICATION FOR PERMIT TO DRILL OR REENTER**FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014**HOBBS OCD**

JUL 5 2016

RECEIVED5. Lease Serial No.
BHL: NMLC061863A / SHL: NMLC061873
6. If Indian, Allottee or Tribe Name1a. Type of work: ☒ DRILL ☐ REENTER

7. If Unit or CA Agreement, Name and No.

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone8. Lease Name and Well No.
Cotton Draw Unit 313H (300635)

2. Name of Operator Devon Energy Production Company, L.P. (6137)

9. API Well No.
30-025-433433a. Address 333 West Sheridan Avenue
Oklahoma City, OK 73102-50103b. Phone No. (include area code)
405-552-655810. Field and Pool, or Exploratory
WC-025 G-06 S253206M; Bone Spring [97899] KZ

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface Unit P, 474' FSL 1225' FEL PP: 435' FSL, 790' FEL

At proposed prod. zone Unit A, 330' FNL 440' FEL

11. Sec., T. R. M. or Blk. and Survey or Area
Sec 7-T25S-R32E14. Distance in miles and direction from nearest town or post office*
Approximately 21.5 miles SE of Malaga, NM.12. County or Parish
Lea13. State
NM15. Distance from proposed*
location to nearest
property or lease line, ft.
(Also to nearest drig. unit line, if any)
See attached map16. No. of acres in lease
SHL: 319.730 Acres
BHL: 1882.600 Acres17. Spacing Unit dedicated to this well
160 Acres18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft. See attached map19. Proposed Depth
16,410' MD / 11,690' TVD20. BLM/BIA Bond No. on file
CO-110421. Elevations (Show whether DF, KDB, RT, GL, etc.)
3431.4' GL22. Approximate date work will start*
1/20/201723. Estimated duration
45 Days**24. Attachments**

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature *Linda Good*Name (Printed/Typed)
Linda GoodDate Revised
4/29/2016

Title

Regulatory Compliance Specialist

Approved by (Signature) **James A. Amos**

Name (Printed/Typed)

Date JUN 22 2016

Title

FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.**APPROVAL FOR TWO YEARS**Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section
States any false, fictitious or fraudulent statements or rSee attached NMOCD
Conditions of Approval

ke to any department or agency of the United

(Continued on page 2)

*(Instructions on page 2)

Padded w/CDU 312H/319H/320H/321H/

Carlsbad Controlled Water BasinKZ
07/09/16**SEE ATTACHED FOR
CONDITIONS OF APPROVAL****Approval Subject to General Requirements
& Special Stipulations Attached**

KZ

Devon Energy, Cotton Draw Unit 313H

1. Geologic Formations

TVD of target	11,690'	Pilot hole depth	N/A
MD at TD:	16,410'	Deepest expected fresh water:	190

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	675	Water	
Top of Salt	1,050	Salt	
Base of Salt	4,195	Salt	
Lamar	4,435	Barren	
Bell Canyon	4,472	Oil/Gas	
Cherry Canyon	5,295	Oil/Gas	
Brushy Canyon	6,705	Oil/Gas	
Lwr Brushy Canyon	8,135	Oil/Gas	
Bone Spring	8,350	Oil/Gas	
Middle Leonard	8,465	Oil/Gas	
Lower Leonard	8,865	Oil/Gas	
Basal Leonard	9,102	Oil/Gas	
1st BSPG Sand	9,410	Oil/Gas	
2nd BSPG Lime	9,625	Oil/Gas	
2nd BSPG Sand	10,035	Oil/Gas	
2nd BSPG Sand Upr	10,135	Oil/Gas	
2nd BSPG Sand Lwr	10,467	Oil/Gas	
3rd BSPG Lime	10,560	Oil/Gas	
3rd BSPG Sand	11,295	Oil/Gas	
3rd BSPG Sand Lwr	11,610	Target Zone	
Wolfcamp	11,765	Oil/Gas	

*H₂S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

See COA

Hole Size	Casing Interval		Csg Size	Weight	Grade	Conn	Safety Factors		
	From	To					Burst	Collapse	Tension
17 1/2	0	705 785'	13 3/8	54.5	J-55	BTC	1.82	3.67	6.80
12 1/4	0	4,300 4400'	9 5/8	40	J-55	LTC	1.67	1.15	2.11
8 3/4	0	12,000	7	29	HCP-110	BTC	1.22	1.30	2.46
6 1/8	11,000	16,410	4 1/2	13.5	P-110	BTC	1.37	1.91	3.90
BLM Minimum Safety Factor							1.00	1.125	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

See COA →

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing	# Sks	Wt. lb/gal	H ₂ O gal/sk	Yld ft ³ /sack	500# Comp. Strength (hours)	Slurry Description
13-3/8" Surf	760	14.8	6.32	1.33	6	Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
9-5/8" Inter.	900	12.9	9.81	1.85	14	Lead: (65:35) Class C Cement: Poz (Fly Ash): 6% BWOC Bentonite + 5% BWOW Sodium Chloride + 0.125 lbs/sack Poly-E-Flake
	430	14.8	6.32	1.33	6	Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
7" Inter.	400	11	14.81	2.55	14	Lead: Tuned Light® Cement + 0.125 lb/sk Pol-E-Flake
	400	14.5	5.31	1.2	25	Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
7" Inter. Two Stage	380	11	14.81	2.55	22	1 st Stage Lead: Tuned Light® Cement + 0.125 lb/sk Pol-E-Flake
	400	14.5	5.31	1.2	25	1 st Stage Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
	DV Tool = 4350ft					
	10	11	14.81	2.55	22	2 nd Stage Lead: Tuned Light® Cement + 0.125 lb/sk Pol-E-Flake
	20	14.8	6.32	1.33	6	2 nd Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
4-1/2" Prod. Liner	670	14.5	5.31	1.2	25	Primary: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
13-3/8" Surface	0'	100%
9-5/8" Intermediate	0'	75%
7" Intermediate	4100'	25%
7" Intermediate Two Stage	1 st Stage = 4350' / 2 nd Stage = 4100'	25%
4-1/2" Production Liner	11000'	15%

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
12-1/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	x	
			Other*		
8-3/4"	13-5/8"	3M	Annular	x	50% testing pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	x	
			Other*		
6-1/8"	13-5/8"	5M	Annular	x	5M
			Blind Ram		
			Pipe Ram		
			Double Ram	x	
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

See COA	Y	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
	Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
See COA	Y	Are anchors required by manufacturer?

A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.

- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 5M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 5,000 psi high pressure test. The 5,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.

After running the 9-5/8' intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 5M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 5,000 psi WP.

Devon's proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.

SEE
COA

	See attached schematic.
--	-------------------------

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	705' 785'	FW Gel	8.6-8.8	28-34	N/C
705'	4,300' 4400'	Saturated Brine	10.0-10.2	28-34	N/C
4,300'	16,410'	Cut Brine	8.5-9.3	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures — See COA

Logging, Coring and Testing.	
x	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
-----------	------------------------------

Devon Energy, Cotton Draw Unit 313H

BH Pressure at deepest TVD	5653 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S Plan attached

8. Other facets of operation

Is this a walking operation? No.

Will be pre-setting casing? No.

Attachments

☒ Directional Plan

☐ Other, describe