

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*5. Lease Serial No.
NMNM132073

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
BRIARD 22 FEDERAL STATE COM 2H9. API Well No.
30-025-43398-00-X110. Field and Pool or Exploratory Area
ANTELOPE RIDGE-BONE SPRING, W11. County or Parish, State
LEA COUNTY, NM

SUBMIT IN TRIPLICATE - Other instructions on page

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator
MEWBOURNE OIL COMPANYContact: JILL LATHAN
E-Mail: jlathan@mewbourne.com3a. Address
P O BOX 5270
HOBBS, NM 882413b. Phone No. (include area code)
Ph: 575-393-5905

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec 22 T23S R34E SESW 200FSL 1700FWL

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ Notice of Intent☐ Subsequent Report☐ Final Abandonment Notice☐ Acidize☐ Alter Casing☐ Casing Repair☐ Change Plans☐ Convert to Injection☐ Deepen☐ Hydraulic Fracturing☐ New Construction☐ Plug and Abandon☐ Plug Back☐ Production (Start/Resume)☐ Reclamation☐ Recomplete☐ Temporarily Abandon☐ Water Disposal☐ Water Shut-Off☐ Well Integrity☒ Other
Change to Original A
PD

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

Mewbourne Oil Company has an approved APD for the above well. Mewbourne requests approval to make the following changes:

- 1) Change well interval to 3rd Bone Springs & TVD to 11,438'.
- 2) Change target zone to 3rd Bone Springs & TVD to 11,438'.
- 3) Change BHL to 100' FNL & 1700' FWL.
- 4) Change csg depth and cement to suit new plan.
- 5) Change wellhead to multi-bowl type wellhead.
- 6) Request variance for the use of a flexible choke line.

Please see attachments for C-102, wellhead schematic, new drilling plan, casing & cement information.

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #427656 verified by the BLM Well Information System

For MEWBOURNE OIL COMPANY, sent to the Hobbs

Committed to AFMS for processing by PRISCILLA PEREZ on 07/23/2018 (18PP1479SE)

Name (Printed/Typed) ROBERT TALLEY

Title ENGINEER

Signature (Electronic Submission)

Date 07/17/2018

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By ZOTA STEVENS

Title PETROLEUM ENGINEER

Date 07/24/2018

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office Hobbs

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **

Additional data for EC transaction #427656 that would not fit on the form

. Additional remarks, continued

Please contact Robert Talley with any questions.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number 30-025-43398		2 Pool Code 2209		3 Pool Name ANTELOPE RIDGE BONE SPRING	
4 Property Code		5 Property Name Gazelle 22 B3NC Fed Com			6 Well Number 1H
7 GRID NO. 14744		8 Operator Name MEWBOURNE OIL COMPANY			9 Elevation 3471'

10 Surface Location									
UL or lot no. N	Section 22	Township 23S	Range 34E	Lot Idn	Feet from the 200	North/South line SOUTH	Feet From the 1700	East/West line WEST	County LEA

11 Bottom Hole Location If Different From Surface									
UL or lot no. C	Section 22	Township 23S	Range 34E	Lot Idn	Feet from the 100	North/South line NORTH	Feet from the 1700	East/West line WEST	County LEA
12 Dedicated Acres		13 Joint or Infill		14 Consolidation Code		15 Order No.			

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

<p>16</p> <p>1700'</p> <p>B. H. 100'</p> <p>PROJECT AREA</p> <p>PRODUCING AREA</p> <p>WELL PATH</p> <p>1700'</p> <p>S. L. 200'</p> <p>17</p>		<p>18</p> <p>GEODETIC DATA NAD 83 GRID - NM EAST</p> <p>SURFACE LOCATION N: 467929.0 - E: 810928.6 LAT: 32.2833976° N LONG: 103.4609719° W</p> <p>BOTTOM HOLE N: 472910.6 - E: 810884.2 LAT: 32.2970908° N LONG: 103.4609845° W</p> <p>CORNER DATA NAD 83 GRID - NM EAST</p> <p>A: FOUND BRASS CAP "1918" N: 467715.6 - E: 809230.7</p> <p>B: FOUND BRASS CAP "1918" N: 470357.7 - E: 809207.0</p> <p>C: FOUND BRASS CAP "1918" N: 472997.8 - E: 809183.6</p> <p>D: FOUND BRASS CAP "1918" N: 4730178 - E: 811823.8</p> <p>E: FOUND BRASS CAP "1918" N: 473037.5 - E: 814463.3</p> <p>F: FOUND BRASS CAP "1918" N: 470396.6 - E: 814487.5</p> <p>G: CALCULATED CORNER N: 467756.2 - E: 814507.6</p> <p>H: FOUND BRASS CAP "1918" N: 467736.6 - E: 811871.1</p>		<p>17 OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature <u>Robert Talley</u> Date <u>7/17/2018</u></p> <p>Printed Name ROBERT TALLEY</p> <p>E-mail Address BTALLEY@MEWBOURNE.COM</p> <p>18 SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>4-2-18 Date of Survey</p> <p>Signature and Seal of Professional Surveyor</p> <p>19680 Certificate Number</p> <p>7/17/18 - SL/BH</p>	
--	--	--	--	--	--

RRC-Job No.: LS1804421

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H
Sec 22, T23S, R34E
SL: 200' FSL & 1700' FWL
BHL: 100' FNL & 1700' FWL

1. Geologic Formations

TVD of target	11438'	Pilot hole depth	NA
MD at TD:	16407'	Deepest expected fresh water:	300'

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface		
Rustler	970		
Top of Salt	2035		
Base of Salt	4325		
Yates			
Seven Rivers		Oil/Gas	
Lamar	5075	Oil/Gas	
Bell Canyon	5100	Oil/Gas	
Cherry Canyon	5845	Oil/Gas	
Brushy Canyon	7270	Oil/Gas	
Bone Spring	8575	Oil/Gas	
1 st Bone Spring Sand	9650	Oil/Gas	
2 nd Bone Spring Sand	10175	Oil/Gas	
3 rd Bone Spring Sand	11130	Target Zone	
Abo			
Wolfcamp			
Devonian			
Fusselman			
Ellenburger			
Granite Wash			

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H
Sec 22, T23S, R34E
SL: 200' FSL & 1700' FWL
BHL: 100' FNL & 1700' FWL

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	1045'	13.375"	48	H40	STC	1.61	3.62	6.42	10.79
12.25"	0'	3453'	9.625"	36	J55	LTC	1.13	1.96	2.43	3.03
12.25"	3453'	4393'	9.625"	40	J55	LTC	1.13	1.73	8.40	10.18
12.25"	4393'	5000'	9.625"	40	N80	LTC	1.19	2.21	30.36	37.74
8.75"	0'	11716'	7"	26	HCP110	LTC	1.41	1.80	2.14	2.72
6.125"	10963'	16407'	4.5"	13.5	P110	LTC	1.79	2.09	4.60	5.74
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H

Sec 22, T23S, R34E

SL: 200' FSL & 1700' FWL

BHL: 100' FNL & 1700' FWL

3. Cementing Program

Casing	# Sk	Wt. lb/ gal	Yld ft³/ sack	H₂O gal/ sk	500# Comp. Strength (hours)	Slurry Description
Surf.	565	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Inter.	840	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Prod.	390	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	400	15.6	1.18	5.2	10	Tail: Class H + Retarder + Fluid Loss + Defoamer
Liner	225	11.2	2.97	18	16	Class C + Salt + Gel + Fluid Loss + Retarder + Dispersant + Defoamer + Anti-Settling Agent

A copy of cement test will be available on location at time of cement job providing pump times & compressive strengths.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	25%
Production	4800'	25%
Liner	10963'	25%

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H
Sec 22, T23S, R34E
SL: 200' FSL & 1700' FWL
BHL: 100' FNL & 1700' FWL

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	5M	Annular	X	2500#
			Blind Ram	X	5000#
			Pipe Ram	X	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The system may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. • Provide description here: See attached schematic.

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H
Sec 22, T23S, R34E
SL: 200' FSL & 1700' FWL
BHL: 100' FNL & 1700' FWL

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0'	1045'	FW Gel	8.6-8.8	28-34	N/C
1045'	5000'	Saturated Brine	10.0	28-34	N/C
5000'	10960'	Cut Brine	8.6-9.7	28-34	N/C
10960'	11438'	OBM	8.6-10.0	30-40	<10cc

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Visual Monitoring
---	-------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from KOP (10963') to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
X	Gamma Ray	10963' (KOP) to TD
	Density	
	CBL	
	Mud log	
	PEX	

Mewbourne Oil Company, Gazelle 22 B3NC Fed Com #1H
Sec 22, T23S, R34E
SL: 200' FSL & 1700' FWL
BHL: 100' FNL & 1700' FWL

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	5948 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers in surface hole.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? If yes, describe.

Will be pre-setting casing? If yes, describe.

Attachments

___ Directional Plan

___ Other, describe

Mewbourne Oil Company

Lea County, New Mexico NAD 83

Gazelle 22 B3NC Fed Com #1H

Sec 22, T23S, R34E

SL: 200' FSL & 1700' FWL

BHL: 100' FNL & 1700' FWL

Plan: Design #1

Standard Planning Report

13 July, 2018

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Gazelle 22 B3NC Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3498.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	MD Reference:	WELL @ 3498.0usft (Original Well Elev)
Site:	Gazelle 22 B3NC Fed Com #1H	North Reference:	Grid
Well:	Sec 22, T23S, R34E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 100' FNL & 1700' FWL		
Design:	Design #1		

Project	Lea County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Gazelle 22 B3NC Fed Com #1H				
Site Position:		Northing:	467,930.00 usft	Latitude:	32.2834002
From:	Map	Easting:	810,929.00 usft	Longitude:	-103.4609705
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.47 °

Well	Sec 22, T23S, R34E					
Well Position	+N/-S	0.0 usft	Northing:	467,930.00 usft	Latitude:	32.2834002
	+E/-W	0.0 usft	Easting:	810,929.00 usft	Longitude:	-103.4609705
Position Uncertainty		0.0 usft	Wellhead Elevation:	3,498.0 usft	Ground Level:	3,471.0 usft

Wellbore	BHL: 100' FNL & 1700' FWL				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2010	7/13/2018	6.66	60.08	47,955

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.0	0.0	0.0	359.49

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,075.0	0.00	0.00	5,075.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,169.0	1.88	179.40	5,168.9	-1.5	0.0	2.00	2.00	0.00	179.40	
10,869.1	1.88	179.40	10,866.1	-188.5	2.0	0.00	0.00	0.00	0.00	
10,963.1	0.00	0.00	10,960.0	-190.0	2.0	2.00	-2.00	0.00	180.00	KOP @ 10960'
11,716.0	90.24	359.49	11,438.0	290.0	-2.3	11.99	11.99	0.00	-0.51	
16,407.2	90.24	359.49	11,418.0	4,981.0	-44.0	0.00	0.00	0.00	0.00	BHL: 100' FNL & 1700'

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Gazelle 22 B3NC Fed Com #1H
 Well: Sec 22, T23S, R34E
 Wellbore: BHL 100' FNL & 1700' FWL
 Design: Design #1

Local Co-ordinate Reference: Site Gazelle 22 B3NC Fed Com #1H
 TVD Reference: WELL @ 3498.0usft (Original Well Elev)
 MD Reference: WELL @ 3498.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
SL: 200' FSL & 1700' FWL										
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00	
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00	
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00	
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,075.0	0.00	0.00	5,075.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,100.0	0.50	179.40	5,100.0	-0.1	0.0	-0.1	2.00	2.00	0.00	

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Gazelle 22 B3NC Fed Com #1H
 Well: Sec 22, T23S, R34E
 Wellbore: BHL: 100' FNL & 1700' FWL
 Design: Design #1

Local Co-ordinate Reference: Site Gazelle 22 B3NC Fed Com #1H
 TVD Reference: WELL @ 3498.0usft (Original Well Elev)
 MD Reference: WELL @ 3498.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,169.0	1.88	179.40	5,168.9	-1.5	0.0	-1.5	2.00	2.00	0.00
5,200.0	1.88	179.40	5,200.0	-2.6	0.0	-2.6	0.00	0.00	0.00
5,300.0	1.88	179.40	5,299.9	-5.8	0.1	-5.8	0.00	0.00	0.00
5,400.0	1.88	179.40	5,399.9	-9.1	0.1	-9.1	0.00	0.00	0.00
5,500.0	1.88	179.40	5,499.8	-12.4	0.1	-12.4	0.00	0.00	0.00
5,600.0	1.88	179.40	5,599.8	-15.7	0.2	-15.7	0.00	0.00	0.00
5,700.0	1.88	179.40	5,699.7	-19.0	0.2	-19.0	0.00	0.00	0.00
5,800.0	1.88	179.40	5,799.6	-22.2	0.2	-22.2	0.00	0.00	0.00
5,900.0	1.88	179.40	5,899.6	-25.5	0.3	-25.5	0.00	0.00	0.00
6,000.0	1.88	179.40	5,999.5	-28.8	0.3	-28.8	0.00	0.00	0.00
6,100.0	1.88	179.40	6,099.5	-32.1	0.3	-32.1	0.00	0.00	0.00
6,200.0	1.88	179.40	6,199.4	-35.4	0.4	-35.4	0.00	0.00	0.00
6,300.0	1.88	179.40	6,299.4	-38.6	0.4	-38.6	0.00	0.00	0.00
6,400.0	1.88	179.40	6,399.3	-41.9	0.4	-41.9	0.00	0.00	0.00
6,500.0	1.88	179.40	6,499.3	-45.2	0.5	-45.2	0.00	0.00	0.00
6,600.0	1.88	179.40	6,599.2	-48.5	0.5	-48.5	0.00	0.00	0.00
6,700.0	1.88	179.40	6,699.2	-51.7	0.5	-51.7	0.00	0.00	0.00
6,800.0	1.88	179.40	6,799.1	-55.0	0.6	-55.0	0.00	0.00	0.00
6,900.0	1.88	179.40	6,899.1	-58.3	0.6	-58.3	0.00	0.00	0.00
7,000.0	1.88	179.40	6,999.0	-61.6	0.6	-61.6	0.00	0.00	0.00
7,100.0	1.88	179.40	7,098.9	-64.9	0.7	-64.9	0.00	0.00	0.00
7,200.0	1.88	179.40	7,198.9	-68.1	0.7	-68.1	0.00	0.00	0.00
7,300.0	1.88	179.40	7,298.8	-71.4	0.8	-71.4	0.00	0.00	0.00
7,400.0	1.88	179.40	7,398.8	-74.7	0.8	-74.7	0.00	0.00	0.00
7,500.0	1.88	179.40	7,498.7	-78.0	0.8	-78.0	0.00	0.00	0.00
7,600.0	1.88	179.40	7,598.7	-81.3	0.9	-81.3	0.00	0.00	0.00
7,700.0	1.88	179.40	7,698.6	-84.5	0.9	-84.5	0.00	0.00	0.00
7,800.0	1.88	179.40	7,798.6	-87.8	0.9	-87.8	0.00	0.00	0.00
7,900.0	1.88	179.40	7,898.5	-91.1	1.0	-91.1	0.00	0.00	0.00
8,000.0	1.88	179.40	7,998.5	-94.4	1.0	-94.4	0.00	0.00	0.00
8,100.0	1.88	179.40	8,098.4	-97.7	1.0	-97.7	0.00	0.00	0.00
8,200.0	1.88	179.40	8,198.4	-100.9	1.1	-100.9	0.00	0.00	0.00
8,300.0	1.88	179.40	8,298.3	-104.2	1.1	-104.2	0.00	0.00	0.00
8,400.0	1.88	179.40	8,398.2	-107.5	1.1	-107.5	0.00	0.00	0.00
8,500.0	1.88	179.40	8,498.2	-110.8	1.2	-110.8	0.00	0.00	0.00
8,600.0	1.88	179.40	8,598.1	-114.1	1.2	-114.1	0.00	0.00	0.00
8,700.0	1.88	179.40	8,698.1	-117.3	1.2	-117.3	0.00	0.00	0.00
8,800.0	1.88	179.40	8,798.0	-120.6	1.3	-120.6	0.00	0.00	0.00
8,900.0	1.88	179.40	8,898.0	-123.9	1.3	-123.9	0.00	0.00	0.00
9,000.0	1.88	179.40	8,997.9	-127.2	1.3	-127.2	0.00	0.00	0.00
9,100.0	1.88	179.40	9,097.9	-130.4	1.4	-130.5	0.00	0.00	0.00
9,200.0	1.88	179.40	9,197.8	-133.7	1.4	-133.7	0.00	0.00	0.00
9,300.0	1.88	179.40	9,297.8	-137.0	1.4	-137.0	0.00	0.00	0.00
9,400.0	1.88	179.40	9,397.7	-140.3	1.5	-140.3	0.00	0.00	0.00
9,500.0	1.88	179.40	9,497.7	-143.6	1.5	-143.6	0.00	0.00	0.00
9,600.0	1.88	179.40	9,597.6	-146.8	1.5	-146.9	0.00	0.00	0.00
9,700.0	1.88	179.40	9,697.5	-150.1	1.6	-150.1	0.00	0.00	0.00
9,800.0	1.88	179.40	9,797.5	-153.4	1.6	-153.4	0.00	0.00	0.00
9,900.0	1.88	179.40	9,897.4	-156.7	1.6	-156.7	0.00	0.00	0.00
10,000.0	1.88	179.40	9,997.4	-160.0	1.7	-160.0	0.00	0.00	0.00
10,100.0	1.88	179.40	10,097.3	-163.2	1.7	-163.2	0.00	0.00	0.00
10,200.0	1.88	179.40	10,197.3	-166.5	1.8	-166.5	0.00	0.00	0.00
10,300.0	1.88	179.40	10,297.2	-169.8	1.8	-169.8	0.00	0.00	0.00
10,400.0	1.88	179.40	10,397.2	-173.1	1.8	-173.1	0.00	0.00	0.00

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Gazelle 22 B3NC Fed Com #1H
 Well: Sec 22, T23S, R34E
 Wellbore: BHL: 100' FNL & 1700' FWL
 Design: Design #1

Local Co-ordinate Reference:
 TVD Reference:
 MD Reference:
 North Reference:
 Survey Calculation Method:

Site Gazelle 22 B3NC Fed Com #1H
 WELL @ 3498.0usft (Original Well Elev)
 WELL @ 3498.0usft (Original Well Elev)
 Grid
 Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,500.0	1.88	179.40	10,497.1	-176.4	1.9	-176.4	0.00	0.00	0.00
10,600.0	1.88	179.40	10,597.1	-179.6	1.9	-179.6	0.00	0.00	0.00
10,700.0	1.88	179.40	10,697.0	-182.9	1.9	-182.9	0.00	0.00	0.00
10,800.0	1.88	179.40	10,797.0	-186.2	2.0	-186.2	0.00	0.00	0.00
10,869.1	1.88	179.40	10,866.1	-188.5	2.0	-188.5	0.00	0.00	0.00
10,900.0	1.26	179.40	10,896.9	-189.3	2.0	-189.3	2.00	-2.00	0.00
10,963.1	0.00	0.00	10,960.0	-190.0	2.0	-190.0	2.00	-2.00	0.00
KOP @ 10960'									
11,000.0	4.42	359.49	10,996.9	-188.6	2.0	-188.6	11.99	11.99	0.00
11,100.0	16.41	359.49	11,095.0	-170.5	1.8	-170.5	11.99	11.99	0.00
11,200.0	28.40	359.49	11,187.3	-132.5	1.5	-132.5	11.99	11.99	0.00
11,261.3	35.74	359.49	11,239.2	-100.0	1.2	-100.0	11.99	11.99	0.00
FTP: 100' FSL & 1700' FWL									
11,300.0	40.38	359.49	11,269.7	-76.1	1.0	-76.1	11.99	11.99	0.00
11,400.0	52.37	359.49	11,338.6	-3.9	0.3	-3.9	11.99	11.99	0.00
11,500.0	64.36	359.49	11,390.9	81.1	-0.4	81.1	11.99	11.99	0.00
11,600.0	76.34	359.49	11,424.5	175.1	-1.2	175.1	11.99	11.99	0.00
11,700.0	88.33	359.49	11,437.8	274.0	-2.1	274.0	11.99	11.99	0.00
11,716.0	90.24	359.49	11,438.0	290.0	-2.3	290.0	11.99	11.99	0.00
LP: 490' FSL & 1700' FWL									
11,800.0	90.24	359.49	11,437.6	374.0	-3.0	374.0	0.00	0.00	0.00
11,900.0	90.24	359.49	11,437.2	474.0	-3.9	474.0	0.00	0.00	0.00
12,000.0	90.24	359.49	11,436.8	574.0	-4.8	574.0	0.00	0.00	0.00
12,100.0	90.24	359.49	11,436.4	674.0	-5.7	674.0	0.00	0.00	0.00
12,200.0	90.24	359.49	11,435.9	774.0	-6.6	774.0	0.00	0.00	0.00
12,300.0	90.24	359.49	11,435.5	874.0	-7.5	874.0	0.00	0.00	0.00
12,400.0	90.24	359.49	11,435.1	974.0	-8.4	974.0	0.00	0.00	0.00
12,500.0	90.24	359.49	11,434.7	1,074.0	-9.2	1,074.0	0.00	0.00	0.00
12,600.0	90.24	359.49	11,434.2	1,174.0	-10.1	1,174.0	0.00	0.00	0.00
12,700.0	90.24	359.49	11,433.8	1,274.0	-11.0	1,274.0	0.00	0.00	0.00
12,800.0	90.24	359.49	11,433.4	1,374.0	-11.9	1,374.0	0.00	0.00	0.00
12,900.0	90.24	359.49	11,433.0	1,474.0	-12.8	1,474.0	0.00	0.00	0.00
13,000.0	90.24	359.49	11,432.5	1,574.0	-13.7	1,574.0	0.00	0.00	0.00
13,100.0	90.24	359.49	11,432.1	1,674.0	-14.6	1,674.0	0.00	0.00	0.00
13,200.0	90.24	359.49	11,431.7	1,774.0	-15.5	1,774.0	0.00	0.00	0.00
13,300.0	90.24	359.49	11,431.2	1,874.0	-16.4	1,874.0	0.00	0.00	0.00
13,400.0	90.24	359.49	11,430.8	1,974.0	-17.3	1,974.0	0.00	0.00	0.00
13,500.0	90.24	359.49	11,430.4	2,074.0	-18.1	2,074.0	0.00	0.00	0.00
13,600.0	90.24	359.49	11,430.0	2,173.9	-19.0	2,174.0	0.00	0.00	0.00
13,700.0	90.24	359.49	11,429.5	2,273.9	-19.9	2,274.0	0.00	0.00	0.00
13,800.0	90.24	359.49	11,429.1	2,373.9	-20.8	2,374.0	0.00	0.00	0.00
13,900.0	90.24	359.49	11,428.7	2,473.9	-21.7	2,474.0	0.00	0.00	0.00
14,000.0	90.24	359.49	11,428.3	2,573.9	-22.6	2,574.0	0.00	0.00	0.00
14,100.0	90.24	359.49	11,427.8	2,673.9	-23.5	2,674.0	0.00	0.00	0.00
14,200.0	90.24	359.49	11,427.4	2,773.9	-24.4	2,774.0	0.00	0.00	0.00
14,300.0	90.24	359.49	11,427.0	2,873.9	-25.3	2,874.0	0.00	0.00	0.00
14,400.0	90.24	359.49	11,426.6	2,973.9	-26.1	2,974.0	0.00	0.00	0.00
14,500.0	90.24	359.49	11,426.1	3,073.9	-27.0	3,074.0	0.00	0.00	0.00
14,600.0	90.24	359.49	11,425.7	3,173.9	-27.9	3,174.0	0.00	0.00	0.00
14,700.0	90.24	359.49	11,425.3	3,273.9	-28.8	3,274.0	0.00	0.00	0.00
14,800.0	90.24	359.49	11,424.9	3,373.9	-29.7	3,374.0	0.00	0.00	0.00
14,900.0	90.24	359.49	11,424.4	3,473.9	-30.6	3,474.0	0.00	0.00	0.00
15,000.0	90.24	359.49	11,424.0	3,573.9	-31.5	3,574.0	0.00	0.00	0.00

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Gazelle 22 B3NC Fed Com #1H
 Well: Sec 22, T23S, R34E
 Wellbore: BHL: 100' FNL & 1700' FWL
 Design: Design #1

Local Co-ordinate Reference:
 TVD Reference:
 MD Reference:
 North Reference:
 Survey Calculation Method:

Site Gazelle 22 B3NC Fed Com #1H
 WELL @ 3498.0usft (Original Well Elev)
 WELL @ 3498.0usft (Original Well Elev)
 Grid
 Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,100.0	90.24	359.49	11,423.6	3,673.9	-32.4	3,674.0	0.00	0.00	0.00
15,200.0	90.24	359.49	11,423.1	3,773.9	-33.3	3,774.0	0.00	0.00	0.00
15,300.0	90.24	359.49	11,422.7	3,873.9	-34.2	3,874.0	0.00	0.00	0.00
15,400.0	90.24	359.49	11,422.3	3,973.9	-35.0	3,974.0	0.00	0.00	0.00
15,500.0	90.24	359.49	11,421.9	4,073.9	-35.9	4,074.0	0.00	0.00	0.00
15,600.0	90.24	359.49	11,421.4	4,173.8	-36.8	4,174.0	0.00	0.00	0.00
15,700.0	90.24	359.49	11,421.0	4,273.8	-37.7	4,274.0	0.00	0.00	0.00
15,800.0	90.24	359.49	11,420.6	4,373.8	-38.6	4,374.0	0.00	0.00	0.00
15,900.0	90.24	359.49	11,420.2	4,473.8	-39.5	4,474.0	0.00	0.00	0.00
16,000.0	90.24	359.49	11,419.7	4,573.8	-40.4	4,574.0	0.00	0.00	0.00
16,100.0	90.24	359.49	11,419.3	4,673.8	-41.3	4,674.0	0.00	0.00	0.00
16,200.0	90.24	359.49	11,418.9	4,773.8	-42.2	4,774.0	0.00	0.00	0.00
16,300.0	90.24	359.49	11,418.5	4,873.8	-43.0	4,874.0	0.00	0.00	0.00
16,400.0	90.24	359.49	11,418.0	4,973.8	-43.9	4,974.0	0.00	0.00	0.00
16,407.2	90.24	359.49	11,418.0	4,981.0	-44.0	4,981.2	0.00	0.00	0.00


BHL: 100' FNL & 1700' FWL

Design Targets


Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SL: 200' FSL & 1700' FV - plan hits target center - Point	0.00	0.00	0.0	0.0	0.0	467,930.00	810,929.00	32.2834002	-103.4609705
KOP @ 10960' - plan hits target center - Point	0.00	0.00	10,960.0	-190.0	2.0	467,740.00	810,931.00	32.2828779	-103.4609690
FTP: 100' FSL & 1700' F - plan hits target center - Point	0.00	0.00	11,239.2	-100.0	1.2	467,830.00	810,930.20	32.2831253	-103.4609692
BHL: 100' FNL & 1700' F - plan hits target center - Point	0.00	0.00	11,418.0	4,981.0	-44.0	472,911.00	810,885.00	32.2970917	-103.4609817
LP: 490' FSL & 1700' FV - plan hits target center - Point	0.00	0.00	11,438.0	290.0	-2.3	468,220.02	810,926.73	32.2841974	-103.4609702

Gazelle 22 B3NC Fed Com #1H


South(-)/North(+) (1500 usft/in)



True Vertical Depth (3000 usft/in)




Gazelle 22 B3NC Fed Com #1H
Intermediate Casing



Casing	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
36# J-55	1.13	1.96	2.43	3.03
40# J-55	1.13	1.73	8.40	1018.00
40# N-80	1.19	2.21	30.36	37.74



5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale


Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.

Hydril "GK"
13 5/8" 5M




Hydril "GK"


Cameron Type U
13 5/8" 5M




4 1/2" x 5 7/8" VBR



BLIND RAMS




MUD CROSS




7" RAMS





13 5/8" 5M



13 5/8" 5M



13 5/8" 5M






CAMERON

A Schlumberger Company

13-5/8" MN-DS Wellhead System



Lapping flange 57" conductor cut-off
79

C7585
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER

Product Description: 10K3.548.0CK4.1/1610KFLGE/E LE


End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY	Production:	PRODUCTION
Date :	4/30/2015	Date :	4/30/2015
Signature :		Signature :	

Form PTC - 01 Rev.02





Hydrogen Sulfide Drilling Operations Plan
Mewbourne Oil Company

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H₂S were found. MOC will have on location and working all H₂S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
 - A. Choke manifold with minimum of one adjustable choke/remote choke.
 - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
 - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H₂S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H₂S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment
Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.
4. Visual Warning Systems
 - A. Wind direction indicators as indicated on the wellsite diagram.
 - B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. Mud Program

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. Metallurgy

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. Communications

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. Well Testing

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. Emergency Phone Numbers

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Carlsbad Fire Dept	911 or 575-885-2111
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility - Columbia Medical Center of Carlsbad	575-492-5000

Mewbourne Oil Company	Hobbs District Office	575-393-5905
	Fax	575-397-6252
	2nd Fax	575-393-7259

District Manager	Robin Terrell	575-390-4816
Drilling Superintendent	Frosty Lathan	575-390-4103
	Bradley Bishop	575-390-6838
Drilling Foreman	Wesley Noseff	575-441-0729

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Mewbourne Oil Company
LEASE NO.:	NMNM132073
WELL NAME & NO.:	Gazelle 22 B3NC Fed Com 1H
SURFACE HOLE FOOTAGE:	200'/S & 1700'/W
BOTTOM HOLE FOOTAGE:	100'/N & 1700'/W
LOCATION:	Section 22, T.23 S., R.34 E., NMPM
COUNTY:	Lea County, New Mexico

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **1045** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength,

whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

- Cement to surface. If cement does not circulate see B.1.a, c-d above. **Additional cement maybe required. Excess calculates to 24%.**

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

3. The minimum required fill of cement behind the 7 inch production casing is: Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification. **Additional cement maybe required. Excess cement maybe required.**

4. The minimum required fill of cement behind the 4-1/2 inch production liner is: Cement should tie-back 100' into the previous casing. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive

strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating.

Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test

plug. The results of the test shall be reported to the appropriate BLM office.

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 072418

In a Lesser Prairie-Chicken section.

13 3/8	surface csg in a	17 1/2	inch hole.	Design Factors			SURFACE		
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"	48.00	H 40	ST&C	6.42	1.61	0.67	1,045	50,160	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 755				Tail Cmt	does not	circ to sfc.	Totals:	1,045	50,160
Comparison of Proposed to Minimum Required Cement Volumes									
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
17 1/2	0.6946	765	1466	781	88	8.80	1497	2M	1.56
Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.									

9 5/8	casing inside the	13 3/8	Design Factors			INTERMEDIATE			
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"	36.00	J 55	LT&C	2.43	1.13	0.61	3,453	124,308	
"B"	40.00	J 55	LT&C	8.40	1.13	0.69	940	37,600	
"C"	40.00	N 80	LT&C	30.35	1.19	1	607	24,280	
"D"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig:				Totals:			5,000	186,188	
The cement volume(s) are intended to achieve a top of				0	ft from surface or a		1045	overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
12 1/4	0.3132	1040	2049	1651	24	10.00	3247	5M	0.81
Burst Frac Gradient(s) for Segment(s): A, B, C, D = 1.02, 0.9, c, d All > 0.70, OK. ALT. BURST PRESSURE IS GOOD.									

7	casing inside the	9 5/8	Design Factors			PRODUCTION			
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"	26.00	HCP 110	LT&C	2.33	1.41	1.73	10,960	284,960	
"B"	26.00	HCP 110	LT&C	4.64	1.24	1.73	756	19,656	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,411				Totals:			11,716	304,616	
B would be:				55.76	1.35	if it were a vertical wellbore.			
No Pilot Hole Planned				MTD	Max VTD	Csg VD	Curve KOP	Dogleg°	Severity°
				11716	11438	11438	10960	90	12
The cement volume(s) are intended to achieve a top of				4800	ft from surface or a		200	overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
8 3/4	0.1503	790	1363	1052	30	9.70	3425	5M	0.55
Class 'H' tail cmt yld > 1.20									

4 1/2	Liner w/top @	10963	Design Factors			LINER			
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"	13.50	P 110	LT&C	2.93	1.62	2.09	753	10,166	
"B"	13.50	P 110	LT&C	2.35	1.80	2.09	4,691	63,329	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,512				Totals:			5,444	73,494	
A Segment Design Factors would be:				2.19	1.8	if it were a vertical wellbore.			
0475				MTD	Max VTD	Csg VD	Curve KOP	Dogleg°	Severity°
				16407	11438	11418	10963	90	12
The cement volume(s) are intended to achieve a top of				10963	ft from surface or a		753	overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
6 1/8	0.0942	225	668	456	47	10.00			0.56
Class 'H' tail cmt yld > 1.20 Capitan Reef est top XXXX.									