

**NM OIL CONSERVATION
ARTESIA DISTRICT**

Form 3160-3
(June 2015)

OCT 25 2019

**RECEIVED UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

APPLICATION FOR PERMIT TO DRILL OR REENTER

**FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone			5. Lease Serial No. NMNM090587 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. LOST TANK 30-19 FEDERAL COM 1H (722423)	
2. Name of Operator OXY USA INCORPORATED (16696)			9. API Well No. 30-025-46474	
3a. Address 5 Greenway Plaza, Suite 110 Houston TX 77046		3b. Phone No. (include area code) (713)386-5716		10. Field and Pool, or Exploratory WILSON RIDGE; BONE SPRING (97366)
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface LOT 1 / 128 FNL / 1235 FWL / LAT 32.3839079 / LONG -103.7189474 At proposed prod. zone LOT 4 / 20 FSL / 990 FWL / LAT 32.3552658 / LONG -103.7197224			11. Sec., T. R. M. or Blk. and Survey or Area SEC 19 / T22S / R32E / NMP	
14. Distance in miles and direction from nearest town or post office* 8 miles			12. County or Parish LEA	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 20 feet		16. No of acres in lease 343.55		17. Spacing Unit dedicated to this well 320
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 35 feet		19. Proposed Depth 9851 feet / 20684 feet		20. BLM/BIA Bond No. in file FED: ESB000226
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3616 feet		22. Approximate date work will start* 11/08/2019		23. Estimated duration 15 days
24. Attachments				

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) David Stewart / Ph: (432)685-5717	Date 05/09/2019
Title Sr. Regulatory Advisor		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 10/18/2019
Title Assistant Field Manager Lands & Minerals		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

OCP Rec 10/25/19

APPROVED WITH CONDITIONS
Approval Date: 10/18/2019

Ka
11/04/19



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

10/22/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: David Stewart

Signed on: 05/09/2019

Title: Sr. Regulatory Advisor

Street Address: 6001 Deauville Blvd

City: Midland

State: TX

Zip: 79706

Phone: (432)685-5717

Email address: david_stewart@oxy.com

Field Representative

Representative Name: Jim Wilson

Street Address: 6001 Deauville

City: Midland

State: TX

Zip: 79706

Phone: (575)631-2442

Email address: jim_wilson@oxy.com



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

10/22/2019

APD ID: 10400041724

Submission Date: 05/09/2019

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - General

APD ID: 10400041724

Tie to previous NOS?

Submission Date: 05/09/2019

BLM Office: CARLSBAD

User: David Stewart

Title: Sr. Regulatory Advisor

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM090587

Lease Acres: 343.55

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: OXY USA INCORPORATED

Operator letter of designation:

Operator Info

Operator Organization Name: OXY USA INCORPORATED

Operator Address: 5 Greenway Plaza, Suite 110

Zip: 77046

Operator PO Box:

Operator City: Houston

State: TX

Operator Phone: (713)366-5716

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: LIVINGSTON
RIDGE; BONE SPRING

Pool Name: BONE SPRING

Is the proposed well in an area containing other mineral resources? POTASH

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Is the proposed well in an area containing other mineral resources? POTASH

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** NO **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: LOST **Number:** 1H

Well Class: HORIZONTAL

TANK 30-19 FEDERAL COM

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 8 Miles

Distance to nearest well: 35 FT

Distance to lease line: 20 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: LostTank30_19FdCom1H_SitePlan_20190509121112.pdf

LostTank30_19FdCom1H_C102_20190509153104.pdf

Well work start Date: 11/08/2019

Duration: 15 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
SHL Leg #1	128	FNL	123 5	FWL	22S	32E	19	Lot 1	32.38390 79	- 103.7189 474	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	361 6	0	0	
KOP Leg #1	50	FNL	990	FWL	22S	32E	19	Lot 1	32.38411 89	- 103.7197 409	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 576 1	943 7	937 7	

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	7	FNL	994	FWL	22S	32E	30	Lot 1	32.36976	- 103.719732	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 6235	15414	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.3839815	- 103.7197408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 6235	10237	9851	

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
PPP Leg #1	100	FNL	990	FWL	22S	32E	19	Lot 1	32.38398 15	- 103.7197 408	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 090587	- 623 5	102 37	985 1	
EXIT Leg #1	100	FSL	990	FWL	22S	32E	30	Lot 4	32.35548 57	- 103.7197 226	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 623 5	206 04	985 1	
BHL Leg #1	20	FSL	990	FWL	22S	32E	30	Lot 4	32.35526 58	- 103.7197 224	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 106915	- 623 5	206 84	985 1	



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

10/22/2019

APD ID: 10400041724

Submission Date: 05/09/2019

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	RUSTLER	3616	856	856	ANHYDRITE, SHALE, DOLOMITE	USEABLE WATER	N
2	SALADO	2466	1150	1150	HALITE, ANHYDRITE, SHALE, DOLOMITE	OTHER : SALT	N
3	CASTILE	746	2870	2870	ANHYDRITE	OTHER : salt	N
4	LAMAR	-971	4587	4587	LIMESTONE, SILTSTONE, SANDSTONE	OTHER, NATURAL GAS, OIL : BRINE	N
5	BELL CANYON	-1054	4670	4670	SILTSTONE, SANDSTONE	USEABLE WATER, OTHER, NATURAL GAS, OIL : BRINE	N
6	CHERRY CANYON	-1884	5500	5509	SILTSTONE, SANDSTONE	OTHER, NATURAL GAS, OIL : BRINE	N
7	BRUSHY CANYON	-3116	6732	6760	LIMESTONE, SILTSTONE, SANDSTONE	OTHER, NATURAL GAS, OIL : BRINE	N
8	BONE SPRING	-4866	8482	8537	LIMESTONE, SILTSTONE, SANDSTONE	NATURAL GAS, OIL	Y
9	BONE SPRING 1ST	-5957	9573	9641	LIMESTONE, SILTSTONE, SANDSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 9851

Equipment: 13-5/8" 5/10M Annular, Blind Ram, Double Ram

Requesting Variance? YES

Variance request: Request for the use of a flexible choke line from the BOP to Choke Manifold.

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Choke Diagram Attachment:

LostTank30_19FdCom1H_ChkManifold_20190509123357.pdf

BOP Diagram Attachment:

LostTank30_19FdCom1H_BOP_20190509123412.pdf

LostTank30_19FdCom1H_FlexHoseCert_20190509123424.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	906	0	906			906	J-55	54.5	BUTT	1.125	1.2	BUOY	1.4	BUOY	1.4
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	5550	0	5541			5550	J-55	36	BUTT	1.125	1.2	BUOY	1.4	BUOY	1.4
3	PRODUCTION	8.5	5.5	NEW	API	N	0	20684	0	9851			20684	P-110	20	OTHER - DQX/SFTO RQ/DQWTO RQ	1.125	1.2	BUOY	1.4	BUOY	1.4

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

LostTank30_19FdCom1H_CsgCriteria_20190509124001.pdf

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Casing Attachments

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

LostTank30_19FdCom1H_CsgCriteria_20190509123937.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

LostTank30_19FdCom1H_CsgCriteria_20190509123625.pdf

LostTank30_19FdCom1H_5.5_20_P110CY_TMKUPDQWTORQ_20190509123638.pdf

LostTank30_19FdCom1H_5.5_20_P110_DQX_20190509123639.pdf

LostTank30_19FdCom1H_5.5_20_P110HC_TMKUPSFTORQ_20190509123639.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead					1.33					

INTERMEDIATE	Lead					2.71					
--------------	------	--	--	--	--	------	--	--	--	--	--

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Tail										
PRODUCTION	Lead					2.71					
PRODUCTION	Tail										

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CaCl₂.

Describe the mud monitoring system utilized: PVT/MD Totco/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
906	5550	OTHER : Saturated Brine Based Mud	9.8	10							
5550	2068 4	OTHER : Water-Based and/or Oil-Based Mud	8	9.6							
0	906	WATER-BASED MUD	8.6	8.8							

Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

GR from TD to surface (horizontal well – vertical portion of hole). Mud Log from intermediate shoe to TD.

List of open and cased hole logs run in the well:

GR,MUDLOG

Coring operation description for the well:

No coring is planned at this time.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4918

Anticipated Surface Pressure: 2750.78

Anticipated Bottom Hole Temperature(F): 159

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

LostTank30_19FdCom1H_H2S1_20190509124428.pdf

LostTank30_19FdCom1H_H2S2_20190509124442.pdf

LostTank30_19FdCom1H_EmergencyContactList_20190509124453.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

LostTank30_19FdCom1H_DirectPlan_20190509124925.pdf

LostTank30_19FdCom1H_DirectPlot_20190509124936.pdf


Other proposed operations facets description:



Operator Name: OXY USA INCORPORATED

Well Name: LOST TANK 30-19 FEDERAL COM

Well Number: 1H



Other proposed operations facets attachment:

LostTank30_19FdCom1H_SpudRigData_20190509125105.pdf

LostTank30_19FdCom1H_GasCapPlan_20190509153534.pdf

LostTank30_19FdCom1H_DrillPlanAmd_20190904131651.pdf

Other Variance attachment:


LostTank30_19FdCom1H_OfflineCmtgDetail_20190830125441.pdf


5/10M BOP Stack

Mud Cross Valves:

5. 10M Check Valve
6. Outside 10M Kill Line Valve
7. Inside 10M Kill Line Valve
8. Outside 10M Kill Line Valve
9. 10M HCR Valve

*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side





13-5/8" 5K MN-DS



Name: Brandon	Date: 5-10-17	Working Pressure: #	1505172
---------------	---------------	---------------------	---------



Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H₂S) gas.

While drilling this well, it is possible to encounter H₂S bearing formations. At all times, the first barrier to control H₂S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H₂S is detected. All H₂S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
3. Provide proper evacuation procedures to cope with emergencies.
4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to <u>commence</u> .
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H₂S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H₂S detection.
4. Proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan.

H₂S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H₂S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H₂S training has been taken.

Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H₂S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground. Remotely operated choke.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
 - Rig floor and trailers.
 - Vehicle.

3. Hydrogen sulfide sensors and alarms

- A. H2S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H2S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

- A. One sign located at each location entrance with the following language:

**Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization**

Wind sock – wind streamers:

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

Condition flags

- A. One each condition flag to be displayed to denote conditions.

green – normal conditions
yellow – potential danger
red – danger, H2S present

- B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H2S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H2S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H2S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H2S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

- A. In the event of any evidence of H₂S level above 10 ppm, take the following steps:
 - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
 - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
 - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
 - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
 - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
 - 6. Take steps to determine if the H₂S level can be corrected or suppressed and, if so, proceed as required.
- B. If uncontrollable conditions occur:
 - 1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
3. Notify public safety personnel of safe briefing / muster area.
4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

1. Designated personnel.
 - a. Shall be responsible for the total implementation of this plan.
 - b. Shall be in complete command during any emergency.
 - c. Shall designate a back-up.

- | | |
|----------------------------|--|
| All personnel: | <ol style="list-style-type: none"> 1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw 2. Check status of personnel (buddy system). 3. Secure breathing equipment. 4. Await orders from supervisor. |
| Drill site manager: | <ol style="list-style-type: none"> 1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area. 2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system). 3. Determine H2S concentrations. 4. Assess situation and take control measures. |
| Tool pusher: | <ol style="list-style-type: none"> 1. Don escape unit Report to up nearest upwind designated safe briefing / muster area. 2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system). 3. Determine H2S concentration. 4. Assess situation and take control measures. |
| Driller: | <ol style="list-style-type: none"> 1. Don escape unit, shut down pumps, continue |

rotating DP.

2. Check monitor for point of release.
3. Report to nearest upwind designated safe briefing / muster area.
4. Check status of personnel (in an attempt to rescue, use the buddy system).
5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.

Derrick man
Floor man #1
Floor man #2

1. Will remain in briefing / muster area until instructed by supervisor.

Mud engineer:

1. Report to nearest upwind designated safe briefing / muster area.
2. When instructed, begin check of mud for ph and H2S level. (Garett gas train.)

Safety personnel:

1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H2S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H2S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H2S detection system hooked up and tested.
9. H2S alarm system hooked up and tested.
10. Hand operated H2S detector with tubes on location.
11. 1 – 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H2S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H2S equipment shall be noted on the IADC report.

Checked by: _____ Date: _____

Procedural check list during H2S events

Perform each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that it is in proper working order.
3. Make sure all the H2S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
2. BOP skills (well control drills).
3. Check supply pressure on BOP accumulator stand by source.
4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
6. Confirm pressure on all supply air bottles.
7. Perform breathing equipment drills with on-site personnel.
8. Check the following supplies for availability.
 - A. Emergency telephone list.
 - B. Hand operated H2S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H₂S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company or contractor safety personnel that have been trained in the use of H₂S detection equipment and self-contained breathing equipment will monitor H₂S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions

Well blowout – if emergency

1. Evacuate all personnel to “Safe Briefing / Muster Areas” or off location if needed.
2. If sour gas – evacuate rig personnel.
3. If sour gas – evacuate public within 3000 ft radius of exposure.
4. Don SCBA and shut well in if possible using the buddy system.
5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.
2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H2S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So2	2.21	5 ppm	-	1000 ppm
Chlorine	Cl2	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co2	1.52	5000 ppm	5%	10%
Methane	Ch4	0.55	90,000 ppm	Combustible above 5% in air	

- 1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit – concentration that will cause death with short-term exposure.
- 3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

<u>Percent (%)</u>	<u>Ppm</u>	<u>Concentration</u> Grains <u>100 std. Ft3*</u>	<u>Physical effects</u>
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 - 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60°f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
2. SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
4. Maintenance and care of SCBA's:
 - a. A program for maintenance and care of SCBA's shall include the following:
 1. Inspection for defects, including leak checks.
 2. Cleaning and disinfecting.
 3. Repair.
 4. Storage.
 - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
 1. Fully charged cylinders.
 2. Regulator and warning device operation.
 3. Condition of face piece and connections.
 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
 - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
6. SCBA's should be worn when:
 - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H₂S.

- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H₂S exists.
- D. When working in areas where over 10 ppm H₂S has been detected.
- E. At any time there is a doubt as to the H₂S level in the area to be entered.

Rescue
First aid for H₂S poisoning

Do not panic!

Remain calm – think!

1. Don SCBA breathing equipment.
2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H₂S gas poisoning – no matter how remote the possibility is.
6. Notify emergency room personnel that the victim(s) has been exposed to H₂S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012

OXY Permian Delaware NM Basin Drilling & Completions Incident Reporting

OXY Permian Crisis Team Hotline Notification

Person	Location	Office Phone	Cell/Mobile Phone
--------	----------	--------------	-------------------

Drilling & Completions Department			
Drilling & Completions Manager: John Willis	Houston	(713) 366-5556	(713) 259-1417
Drilling Superintendent: Simon Benavides	Houston	(713) 215-7403	(832) 528-3547
Completions Superintendent: Chris Winter	Houston	(713) 366-5212	(806) 239-8774
Drilling Eng. Supervisor: Diego Tellez	Houston	(713) 350-4602	(713) 303-4932
Drilling Eng. Supervisor: Randy Neel	Houston	(713) 215-7987	(713) 517-5544
Completions Eng. Supervisor: Evan Hinkel	Houston	(713) 366-5436	(281) 236-6153
Drilling & Completions HES Lead. Ryan Green	Houston	713-336-5753	281-520-5216
Drilling & Completions HES Advisor:Kenny Williams	Carlsbad	(432) 686-1434	(337) 208-0911
Drilling & Completions HES Advisor:Kyle Holden	Carlsbad	(432) 686-1435	(661) 369-5328
Drilling & Completions HES Advisor Sr:Dave Schmidt	Carlsbad		(559) 310-8572
Drilling & Completions HES Advisor. :Seth Doyle	Carlsbad		(337) 499-0756

HES / Enviromental & Regulatory Department	Location	Office	Cell Phone
--	----------	--------	------------

Jon Hamil-HES Manager	Houston	(713) 497-2494	(832) 537-9885
Mark Birk-HES Manager	Houston	(713) 350-4615	(949) 413-3127
Austin Trammell	Midland	(432) 699-4208	(575) 499-4919
Rico Munoz	Midland	(432) 699-8366	(432) 803-4116
Amber DuckWorth	Midland		(832) 966-1879
Kelley Montgomery- Regulatory Manager	Houston	(713) 366-5716	(832) 454-8137
Sandra Musallam -Regulatory Lead	Houston	+1 (713) 366-5106	+1 (713) 504-8577
Bishop, Steve-DOT Pipeline Coordinator	Midland	432-685-5614	
Wilson, Dusty-Safety Advisor	Midland	432-685-5771	(432) 254-2336
John W Dittrich Eniromental Advisor	Midland		(575) 390-2828
William (Jack) Calhoun-Environmental Lead	Houston	+713 (350) 4906	(281) 917-8571
Robert Barrow-Risk Engineer Manager	Houston	(713) 366-5611	(832) 867-5336
Sarah Holmes-HSE Cordinator	Midland	432-685-5758	
Administrative			
	Location	Office	
Sarah Holmes	Midland	432-685-5830	
Robertson, Debbie	Midland	432-685-5812	
Laci Hollaway	Midland	(432) 685-5716	(432) 631-6341
Administrative			
	Location	Office	
Rosalinda Escajeda	Midland	432-685-5831	

Person	Location	Office Phone	Cell/Mobile Phone
Moreno, Leslie (contract)	Hobbs	575-397-8247	
Sehon, Angela (contractor)	Levelland	806-894-8347	
Vasquez, Claudia (contractor)	North Cowden	432-385-3120	
XstremeMD	Location	Office	
Medical Case Management	Orla, TX	(337) 205-9314	
Axiom Medical Consulting	Location	Office	
Medical Case Management		(877) 502-9466	
Regulatory Agencies			
Bureau of Land Management	Carlsbad, NM	(505) 887-6544	
Bureau of Land Management	Hobbs, NM	(505) 393-3612	
Bureau of Land Management	Roswell, NM	(505) 393-3612	
Bureau of Land Management	Santa Fe, NM	(505) 988-6030	
DOT Juisdictional Pipelines-Incident Reporting New Mexico Public Regulaion Commission	Santa Fe, NM	(505) 827-3549 (505) 490-2375	
DOT Juisdictional Pipelines-Incident Reporting Texas Railroad Commission	Austin, TX	(512) 463-6788	
EPA Hot Line	Dallas, Texas	(214) 665-6444	
Federal OSHA, Area Office	Lubbock, Texas	(806) 472-7681	
National Response Center	Washington, D. C.	(800) 424-8802	
National Infrastructure Coordinator Center		(202) 282-9201	
New Mexico Air Quality Bureau	Santa Fe, NM	(505) 827-1494	
New Mexico Oil Conservation Division	Artesia, NM	(505) 748-1283	After Hours (505) 370-7545
New Mexico Oil Conservation Division	Hobbs, NM	(505) 393-6161	
New Mexico Oil Conservation Division	Santa Fe, NM	(505) 471-1068	
New Mexico OCD Environmental Bureau	Santa Fe, NM	(505) 476-3470	
New Mexico Environmental Department	Hobbs, NM	(505) 827-9329	
NM State Emergency Response Center	Santa Fe, NM	(505) 827-9222	
Railroad Commission of TX	District 1 San Antonio,	(210) 227-1313	
Railroad Commission of TX	District 7C San Angelo	(325) 657-7450	
Railroad Commission of TX	District 8, 8A Midland	(432) 684-5581	
Texas Emergency Response Center	Austin, TX	(512) 463-7727	
TCEQ Air	Region 2 Lubbock, TX	(806) 796-3494	
TCEQ Water/Waste/Air	Region 3 Abilene, TX	(325) 698-9674	
TCEQ Water/Waste/Air	Region 7 Midland, TX	(432) 570-1359	
TCEQ Water/Waste/Air	Region 9 San Antonio,	(512) 734-7981	
TCEQ Water/Waste/Air	Region 8 San Angelo	(325) 655-9479	
Medical Facilities			
Abernathy Medical Clinic	Abernathy, TX	(806) 298-2524	
Alliance Hospital	Odessa, TX	(432) 550-1000	
Artesia General Hospital	Artesia, NM	(505) 748-3333	
Brownfield Regional Medical Center	Brownfield, TX	(806) 637-3551	

Person	Location	Office Phone	Cell/Mobile Phone
Cogdell Memorial Hospital	Snyder, TX	(325) 573-6374	
Covenant Hospital Levelland	Levelland, TX	(806) 894-4963	
Covenant Medical Center	Lubbock, TX	(806) 725-1011	
Covenant Medical Center Lakeside	Lubbock, TX	(806) 725-6000	
Covenant Family Health	Snyder, TX	(325) 573-1300	
Crockett County Hospital	Ozona, TX	(325) 392-2671	
Guadalupe Medical Center	Carlsbad, NM	(505) 887-6633	
Lea Regional Hospital	Hobbs, NM	(505) 492-5000	
McCamey Hospital	McCamey, TX	(432) 652-8626	
Medical Arts Hospital	Lamesa, TX	(806) 872-2183	
Medical Center Hospital	Odessa, TX	(432) 640-4000	
Medi Center Hospital	San Angelo, TX	(325) 653-6741	
Memorial Hospital	Ft. Stockton	(432) 336-2241	
Memorial Hospital	Seminole, TX	(432) 758-5811	
Midland Memorial Hospital	Midland, TX	(432) 685-1111	
Nor-Lea General Hospital	Lovington, NM	(505) 396-6611	
Odessa Regional Hospital	Odessa, TX	(432) 334-8200	
Permian General Hospital	Andrews, TX	(432) 523-2200	
Reagan County Hospital	Big Lake, TX	(325) 884-2561	
Reeves County Hospital	Pecos, TX	(432) 447-3551	
Shannon Medical Center	San Angelo, TX	(325) 653-6741	
Union County General Hospital	Clayton, NM	(505) 374-2585	
University Medical Center	Lubbock, TX	(806) 725-8200	
Val Verde Regional Medical Center	Del Rio, TX	(830) 775-8566	
Ward Memorial Hospital	Monahans, TX	(432) 943-2511	
Yoakum County Hospital	Denver City, TX	(806) 592-5484	
Law Enforcement - Sheriff			
Andrews Cty Sheriff's Department	Andrews County(Andr	(432) 523-5545	
Crane Cty Sheriff's Department	Crane, County (Crane)	(432) 558-3571	
Crockett Cty Sheriff's Department	Crockett County (Ozor	(325) 392-2661	
Dawson Cty Sheriff's Department	Dawson County (Lame	(806) 872-7560	
Ector Cty Sheriff's Department	Ector County (Odessa)	(432) 335-3050	
Eddy Cty Sheriff's Department	Eddy County (Artesia)	(505) 746-2704	
Eddy Cty Sheriff's Department	Eddy County (Carlsbad	(505) 887-7551	
Gaines Cty Sheriff's Department	Gaines County (Semin	(432) 758-9871	
Hockley Cty Sheriff's Department	Hockley County(Level	(806) 894-3126	
Kent Cty (Jayton City Sheriff's Dept.)	Kent County(Jayton)	(806) 237-3801	
Lea Cty Sheriff's Department	Lea County (Eunice)	(505) 384-2020	
Lea Cty Sheriff's Department	Lea County (Hobbs)	(505) 393-2515	
Lea Cty Sheriff's Department	Lea County (Lovington	(505) 396-3611	
Lubbock Cty Sheriff's Department	Lubbock Cty (Abernati	(806) 296-2724	
Midland Cty Sheriff's Department	Midland County (Midl	(432) 688-1277	

Person	Location	Office Phone	Cell/Mobile Phone
Pecos Cty Sheriff's Department	Pecos County (Iraan)	(432) 639-2251	
Reeves Cty Sheriff's Department	Reeves County (Pecos)	(432) 445-4901	
Scurry Cty Sheriff's Department	Scurry County (Snyder)	(325) 573-3551	
Terry Cty Sheriff's Department	Terry County (Brownf)	(806) 637-2212	
Union Cty Sheriff's Department	Union County (Clayton)	(505) 374-2583	
Upton Cty Sheriff's Department	Upton County (Rankin)	(432) 693-2422	
Ward Cty Sheriff's Department	Ward County (Monaha)	(432) 943-3254	
Yoakum City Sheriff's Department	Yoakum Co. (Denever)	(806) 456-2377	
Law Enforcement - Police			
Abernathy City Police	Abernathy, TX	(806) 298-2545	
Andrews City Police	Andrews, TX	(432) 523-5675	
Artesia City Police	Artesia, NM	(505) 746-2704	
Brownfield City Police	Brownfield, TX	(806) 637-2544	
Carlsbad City Police	Carlsbad, NM	(505) 885-2111	
Clayton City Police	Clayton, NM	(505) 374-2504	
Denver City Police	Denver City, TX	(806) 592-3516	
Eunice City Police	Eunice, NM	(505) 394-2112	
Hobbs City Police	Hobbs, NM	393-2677	
Jal City Police	Jal, NM	(505) 395-2501	
Jayton City Police	Jayton, TX	(806) 237-3801	
Lamesa City Police	Lamesa, TX	(806) 872-2121	
Levelland City Police	Levelland, TX	(806) 894-6164	
Lovington City Police	Lovington, NM	(505) 396-2811	
Midland City Police	Midland, TX	(432) 685-7113	
Monahans City Police	Monahans, TX	(432) 943-3254	
Odessa City Police	Odessa, TX	(432) 335-3378	
Seminole City Police	Seminole, TX	(432) 758-9871	
Snyder City Police	Snyder, TX	(325) 573-2611	
Sundown City Police	Sundown, TX	(806) 229-8241	
Law Enforcement - FBI			
FBI	Albuquerque, NM	(505) 224-2000	
FBI	Midland, TX	(432) 570-0255	
Law Enforcement - DPS			
NM State Police	Artesia, NM	(505) 746-2704	
NM State Police	Carlsbad, NM	(505) 885-3137	
NM State Police	Eunice, NM	(505) 392-5588	
NM State Police	Hobbs, NM	(505) 392-5588	
NM State Police	Clayton, NM	(505) 374-2473; 911	
TX Dept of Public Safety	Andrews, TX	(432) 524-1443	
TX Dept of Public Safety	Big Lake, TX	(325) 884-2301	

Person	Location	Office Phone	Cell/Mobile Phone
TX Dept of Public Safety	Brownfield, TX	(806) 637-2312	
TX Dept of Public Safety	Iraan, TX	(432) 639-3232	
TX Dept of Public Safety	Lamesa, TX	(806) 872-8675	
TX Dept of Public Safety	Levelland, TX	(806) 894-4385	
TX Dept of Public Safety	Lubbock, TX	(806) 747-4491	
TX Dept of Public Safety	Midland, TX	(432) 697-2211	
TX Dept of Public Safety	Monahans, TX	(432) 943-5857	
TX Dept of Public Safety	Odessa, TX	(432) 332-6100	
TX Dept of Public Safety	Ozona, TX	(325) 392-2621	
TX Dept of Public Safety	Pecos, TX	(432) 447-3533	
TX Dept of Public Safety	Seminole, TX	(432) 758-4041	
TX Dept of Public Safety	Snyder, TX	(325) 573-0113	
TX Dept of Public Safety	Terry County TX	(806) 637-8913	
TX Dept of Public Safety	Yoakum County TX	(806) 456-2377	
Firefighting & Rescue			
Abernathy	Abernathy, TX	(806) 298-2022	
Amistad/Rosebud	Amistad/Rosebud, NM	(505) 633-9113	
Andrews	Andrews, TX	523-3111	
Artesia	Artesia, NM	(505) 746-5051	
Big Lake	Big Lake, TX	(325) 884-3650	
Brownfield-Administrative & other calls	Brownfield, TX	(816) 637-4547	
Brownfield emergency only	Brownfield, TX	-911	
Carlsbad	Carlsbad, NM	(505) 885-3125	
Clayton	Clayton, NM	(505) 374-2435	
Cotton Center	Cotton Center, TX	(806) 879-2157	
Crane	Crane, TX	(432) 558-2361	
Del Rio	Del Rio, TX	(830) 774-8650	
Denver City	Denver City, TX	(806) 592-3516	
Eldorado	Eldorado, TX	(325) 853-2691	
Eunice	Eunice, NM	(505) 394-2111	
Garden City	Garden City, TX	(432) 354-2404	
Goldsmith	Goldsmith, TX	(432) 827-3445	
Hale Center	Hale Center, TX	(806) 839-2411	
Halfway	Halfway, TX		
Hobbs	Hobbs, NM	(505) 397-9308	
Jal	Jal, NM	(505) 395-2221	
Jayton	Jayton, TX	(806) 237-3801	
Kermit	Kermit, TX	(432) 586-3468	
Lamesa	Lamesa, TX	(806) 872-4352	
Levelland	Levelland, TX	(806) 894-3154	
Lovington	Lovington, NM	(505) 396-2359	
Maljamar	Maljamar, NM	(505) 676-4100	

Person	Location	Office Phone	Cell/Mobile Phone
McCamey	McCamey, TX	(432) 652-8232	
Midland	Midland, TX	(432) 685-7346	
Monahans	Monahans, TX	(432) 943-4343	
Nara Visa	Nara Visa, NM	(505) 461-3300	
Notrees	Notress, TX	(432) 827-3445	
Odessa	Odessa, TX	(432) 335-4659	
Ozona	Ozona, TX	(325) 392-2626	
Pecos	Pecos, TX	(432) 445-2421	
Petersburg	Petersburg, TX	(806) 667-3461	
Plains	Plains, TX	(806) 456-8067	
Plainview	Plainview, TX	(806) 296-1170	
Rankin	Rankin, TX	(432) 693-2252	
San Angelo	San Angelo, TX	(325) 657-4355	
Sanderson	Sanderson, TX	(432) 345-2525	
Seminole	Seminole, TX	758-9871	
Smyer	Smyer, TX	(806) 234-3861	
Snyder	Snyder, TX	(325) 573-6215	
Sundown	Sundown, TX	911	
Tucumcari	Tucumcari, NM	911	
West Odessa	Odessa, TX	(432) 381-3033	
Ambulance			
Abernathy Ambulance	Abernathy, TX	(806) 298-2241	
Amistad/Rosebud	Amistad/Rosebud, NM	(505) 633-9113	
Andrews Ambulance	Andrews, TX	(432) 523-5675	
Artesia Ambulance	Artesia, NM	(505) 746-2701	
Big Lake Ambulance	Big Lake, TX	(325) 884-2423	
Big Spring Ambulance	Big Spring, TX	(432) 264-2550	
Brownfield Ambulance	Brownfield, TX	(806) 637-2511	
Carlsbad Ambulance	Carlsbad, NM	(505) 885-2111; 911	
Clayton, NM	Clayton, NM	(505) 374-2501	
Denver City Ambulance	Denver City, TX	(806) 592-3516	
Eldorado Ambulance	Eldorado, TX	(325) 853-3456	
Eunice Ambulance	Eunice, NM	(505) 394-3258	
Goldsmith Ambulance	Goldsmith, TX	(432) 827-3445	
Hobbs, NM	Hobbs, NM	(505) 397-9308	
Jal, NM	Jal, NM	(505) 395-2501	
Jayton Ambulance	Jayton, TX	(806) 237-3801	
Lamesa Ambulance	Lamesa, TX	(806) 872-3464	
Levelland Ambulance	Levelland, TX	(806) 894-8855	
Lovington Ambulance	Lovington, NM	(505) 396-2811	
McCamey Hospital	McCamey, TX	(432) 652-8626	
Midland Ambulance	Midland, TX	(432) 685-7499	

Person	Location	Office Phone	Cell/Mobile Phone
Monahans Ambulance	Monahans, TX	3731	
Nara Visa, NM	Nara Visa, NM	(505) 461-3300	
Odessa Ambulance	Odessa, TX	(432) 335-3378	
Ozona Ambulance	Ozona, TX	(325) 392-2671	
Pecos Ambulance	Pecos, TX	(432) 445-4444	
Rankin Ambulance	Rankin, TX	(432) 693-2443	
San Angelo Ambulance	San Angelo, TX	(325) 657-4357	
Seminole Ambulance	Seminole, TX	758-9871	
Snyder Ambulance	Snyder, TX	(325) 573-1911	
Stanton Ambulance	Stanton, TX	(432) 756-2211	
Sundown Ambulance	Sundown, TX	911	
Tucumcari, NM	Tucumcari, NM	911	
Medical Air Ambulance Service			
AEROCARE - Methodist Hospital	Lubbock, TX	(800) 627-2376	
San Angelo Med-Vac Air Ambulance	San Angelo, TX	(800) 277-4354	
Southwest Air Ambulance Service	Stanford, TX	(800) 242-6199	
Southwest MediVac	Snyder, TX	(800) 242-6199	
Southwest MediVac	Hobbs, NM	(800) 242-6199	
Odessa Care Star	Odessa, TX	(888) 624-3571	
NWTH Medivac	Amarillo, TX	(800) 692-1331	

OXY

PRD NM DIRECTIONAL PLANS (NAD 1983)

LOST TANK 30-19 FED

Lost Tank 30_19 Federal Com 1H

Wellbore #1

Plan: Permitting Plan

Standard Planning Report

08 April, 2019

Oxy Planning Report

Database:	HOPSPP	Local Co-ordinate Reference:	Well Lost Tank 30_19 Federal Com 1H
Company:	ENGINEERING DESIGNS	TVD Reference:	RKB=26.5' @ 3642.60ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	MD Reference:	RKB=26.5' @ 3642.60ft
Site:	LOST TANK 30-19 FED	North Reference:	Grid
Well:	Lost Tank 30_19 Federal Com 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Project	PRD NM DIRECTIONAL PLANS (NAD 1983)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		Using geodetic scale factor

Site		LOST TANK 30-19 FED			
Site Position:		Northing:	503,826.03 usft	Latitude:	32° 22' 22.416967 N
From:	Lat/Long	Easting:	0.00 usft	Longitude:	106° 5' 11.999469 W
Position Uncertainty:	50.00 ft	Slot Radius:	13.200 in	Grid Convergence:	-0.94 °

Well	Lost Tank 30_19 Federal Com 1H					
Well Position	+N/-S	115.76 ft	Northing:	503,941.82 usft	Latitude:	32° 23' 2.068326 N
	+E/-W	730,816.16 ft	Easting:	730,993.55 usft	Longitude:	103° 43' 8.210475 W
Position Uncertainty		2.00 ft	Wellhead Elevation:	0.00 ft	Ground Level:	3,616.10 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	4/8/2019	6.80	60.13	48,081

Design	Permitting Plan				
Audit Notes:					
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	180.99	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,550.00	0.00	0.00	4,550.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,049.88	10.00	339.76	5,047.35	40.82	-15.05	2.00	2.00	0.00	339.76	
8,451.89	10.00	339.76	8,397.70	594.98	-219.33	0.00	0.00	0.00	0.00	
9,436.62	10.00	179.64	9,377.14	589.63	-248.64	2.00	0.00	-16.26	-169.91	
10,236.62	90.00	179.64	9,850.60	25.39	-245.10	10.00	10.00	0.00	0.00	FTP (Lost Tank
20,684.07	90.00	179.64	9,850.60	-10,421.85	-179.52	0.00	0.00	0.00	0.00	PBHL (Lost Tank

Oxy Planning Report

Database: HOPSP
Company: ENGINEERING DESIGNS
Project: PRD NM DIRECTIONAL PLANS (NAD 1983)
Site: LOST TANK 30-19 FED
Well: Lost Tank 30_19 Federal Com 1H
Wellbore: Wellbore #1
Design: Permitting Plan

Local Co-ordinate Reference: Well Lost Tank 30_19 Federal Com 1H
TVD Reference: RKB=26.5' @ 3642.60ft
MD Reference: RKB=26.5' @ 3642.60ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,550.00	0.00	0.00	4,550.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	1.00	339.76	4,600.00	0.41	-0.15	-0.41	2.00	2.00	0.00
4,700.00	3.00	339.76	4,699.93	3.68	-1.36	-3.66	2.00	2.00	0.00
4,800.00	5.00	339.76	4,799.68	10.23	-3.77	-10.16	2.00	2.00	0.00
4,900.00	7.00	339.76	4,899.13	20.04	-7.39	-19.91	2.00	2.00	0.00
5,000.00	9.00	339.76	4,998.15	33.09	-12.20	-32.88	2.00	2.00	0.00
5,049.88	10.00	339.76	5,047.35	40.82	-15.05	-40.55	2.00	2.00	0.00
5,100.00	10.00	339.76	5,096.71	48.98	-18.06	-48.66	0.00	0.00	0.00

Oxy Planning Report

Database: HOPSPP
Company: ENGINEERING DESIGNS
Project: PRD NM DIRECTIONAL PLANS (NAD 1983)
Site: LOST TANK 30-19 FED
Well: Lost Tank 30_19 Federal Com 1H
Wellbore: Wellbore #1
Design: Permitting Plan

Local Co-ordinate Reference: Well Lost Tank 30_19 Federal Com 1H
TVD Reference: RKB=26.5' @ 3642.60ft
MD Reference: RKB=26.5' @ 3642.60ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,200.00	10.00	339.76	5,195.19	65.27	-24.06	-64.85	0.00	0.00	0.00
5,300.00	10.00	339.76	5,293.67	81.56	-30.07	-81.03	0.00	0.00	0.00
5,400.00	10.00	339.76	5,392.15	97.85	-36.07	-97.21	0.00	0.00	0.00
5,500.00	10.00	339.76	5,490.63	114.14	-42.07	-113.40	0.00	0.00	0.00
5,600.00	10.00	339.76	5,589.11	130.43	-48.08	-129.58	0.00	0.00	0.00
5,700.00	10.00	339.76	5,687.60	146.72	-54.08	-145.76	0.00	0.00	0.00
5,800.00	10.00	339.76	5,786.08	163.01	-60.09	-161.95	0.00	0.00	0.00
5,900.00	10.00	339.76	5,884.56	179.30	-66.09	-178.13	0.00	0.00	0.00
6,000.00	10.00	339.76	5,983.04	195.58	-72.10	-194.31	0.00	0.00	0.00
6,100.00	10.00	339.76	6,081.52	211.87	-78.10	-210.50	0.00	0.00	0.00
6,200.00	10.00	339.76	6,180.00	228.16	-84.11	-226.68	0.00	0.00	0.00
6,300.00	10.00	339.76	6,278.48	244.45	-90.11	-242.86	0.00	0.00	0.00
6,400.00	10.00	339.76	6,376.97	260.74	-96.12	-259.05	0.00	0.00	0.00
6,500.00	10.00	339.76	6,475.45	277.03	-102.12	-275.23	0.00	0.00	0.00
6,600.00	10.00	339.76	6,573.93	293.32	-108.13	-291.41	0.00	0.00	0.00
6,700.00	10.00	339.76	6,672.41	309.61	-114.13	-307.60	0.00	0.00	0.00
6,800.00	10.00	339.76	6,770.89	325.90	-120.14	-323.78	0.00	0.00	0.00
6,900.00	10.00	339.76	6,869.37	342.19	-126.14	-339.96	0.00	0.00	0.00
7,000.00	10.00	339.76	6,967.85	358.48	-132.15	-356.15	0.00	0.00	0.00
7,100.00	10.00	339.76	7,066.34	374.77	-138.15	-372.33	0.00	0.00	0.00
7,200.00	10.00	339.76	7,164.82	391.06	-144.15	-388.52	0.00	0.00	0.00
7,300.00	10.00	339.76	7,263.30	407.35	-150.16	-404.70	0.00	0.00	0.00
7,400.00	10.00	339.76	7,361.78	423.63	-156.16	-420.88	0.00	0.00	0.00
7,500.00	10.00	339.76	7,460.26	439.92	-162.17	-437.07	0.00	0.00	0.00
7,600.00	10.00	339.76	7,558.74	456.21	-168.17	-453.25	0.00	0.00	0.00
7,700.00	10.00	339.76	7,657.22	472.50	-174.18	-469.43	0.00	0.00	0.00
7,800.00	10.00	339.76	7,755.71	488.79	-180.18	-485.62	0.00	0.00	0.00
7,900.00	10.00	339.76	7,854.19	505.08	-186.19	-501.80	0.00	0.00	0.00
8,000.00	10.00	339.76	7,952.67	521.37	-192.19	-517.98	0.00	0.00	0.00
8,100.00	10.00	339.76	8,051.15	537.66	-198.20	-534.17	0.00	0.00	0.00
8,200.00	10.00	339.76	8,149.63	553.95	-204.20	-550.35	0.00	0.00	0.00
8,300.00	10.00	339.76	8,248.11	570.24	-210.21	-566.53	0.00	0.00	0.00
8,400.00	10.00	339.76	8,346.60	586.53	-216.21	-582.72	0.00	0.00	0.00
8,451.89	10.00	339.76	8,397.70	594.98	-219.33	-591.11	0.00	0.00	0.00
8,500.00	9.05	338.69	8,445.14	602.42	-222.15	-598.51	2.00	-1.97	-2.23
8,600.00	7.10	335.56	8,544.15	615.38	-227.56	-611.37	2.00	-1.95	-3.13
8,700.00	5.18	330.11	8,643.57	624.93	-232.37	-620.83	2.00	-1.92	-5.45
8,800.00	3.37	318.58	8,743.29	631.05	-236.57	-626.88	2.00	-1.82	-11.53
8,900.00	1.95	286.60	8,843.18	633.74	-240.14	-629.51	2.00	-1.42	-31.98
9,000.00	2.07	227.06	8,943.13	633.00	-243.10	-628.72	2.00	0.12	-59.54
9,100.00	3.57	198.89	9,043.01	628.82	-245.43	-624.50	2.00	1.50	-28.17
9,200.00	5.40	188.47	9,142.70	621.22	-247.13	-616.87	2.00	1.83	-10.43
9,300.00	7.33	183.39	9,242.08	610.19	-248.20	-605.83	2.00	1.92	-5.07
9,400.00	9.28	180.44	9,341.03	595.77	-248.64	-591.40	2.00	1.95	-2.96
9,436.62	10.00	179.64	9,377.14	589.63	-248.64	-585.26	2.00	1.97	-2.17
9,500.00	16.34	179.64	9,438.82	575.20	-248.55	-570.84	10.00	10.00	0.00
9,600.00	26.34	179.64	9,531.84	538.86	-248.33	-534.51	10.00	10.00	0.00
9,700.00	36.34	179.64	9,617.15	486.92	-248.00	-482.58	10.00	10.00	0.00
9,800.00	46.34	179.64	9,692.13	420.96	-247.59	-416.63	10.00	10.00	0.00
9,900.00	56.34	179.64	9,754.53	342.97	-247.10	-338.67	10.00	10.00	0.00
10,000.00	66.34	179.64	9,802.43	255.34	-246.55	-251.06	10.00	10.00	0.00
10,100.00	76.34	179.64	9,834.39	160.72	-245.95	-156.46	10.00	10.00	0.00
10,200.00	86.34	179.64	9,849.43	61.99	-245.33	-57.75	10.00	10.00	0.00
10,236.62	90.00	179.64	9,850.60	25.39	-245.10	-21.17	10.00	10.00	0.00

Oxy Planning Report

Database:	HOPSPP	Local Co-ordinate Reference:	Well Lost Tank 30_19 Federal Com 1H
Company:	ENGINEERING DESIGNS	TVD Reference:	RKB=26.5' @ 3642.60ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	MD Reference:	RKB=26.5' @ 3642.60ft
Site:	LOST TANK 30-19 FED	North Reference:	Grid
Well:	Lost Tank 30_19 Federal Com 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
10,300.00	90.00	179.64	9,850.60	-37.99	-244.70	42.19	0.00	0.00	0.00
10,400.00	90.00	179.64	9,850.60	-137.98	-244.08	142.17	0.00	0.00	0.00
10,500.00	90.00	179.64	9,850.60	-237.98	-243.45	242.14	0.00	0.00	0.00
10,600.00	90.00	179.64	9,850.60	-337.98	-242.82	342.11	0.00	0.00	0.00
10,700.00	90.00	179.64	9,850.60	-437.98	-242.19	442.08	0.00	0.00	0.00
10,800.00	90.00	179.64	9,850.60	-537.98	-241.57	542.06	0.00	0.00	0.00
10,900.00	90.00	179.64	9,850.60	-637.97	-240.94	642.03	0.00	0.00	0.00
11,000.00	90.00	179.64	9,850.60	-737.97	-240.31	742.00	0.00	0.00	0.00
11,100.00	90.00	179.64	9,850.60	-837.97	-239.68	841.97	0.00	0.00	0.00
11,200.00	90.00	179.64	9,850.60	-937.97	-239.06	941.95	0.00	0.00	0.00
11,300.00	90.00	179.64	9,850.60	-1,037.97	-238.43	1,041.92	0.00	0.00	0.00
11,400.00	90.00	179.64	9,850.60	-1,137.96	-237.80	1,141.89	0.00	0.00	0.00
11,500.00	90.00	179.64	9,850.60	-1,237.96	-237.17	1,241.86	0.00	0.00	0.00
11,600.00	90.00	179.64	9,850.60	-1,337.96	-236.54	1,341.83	0.00	0.00	0.00
11,700.00	90.00	179.64	9,850.60	-1,437.96	-235.92	1,441.81	0.00	0.00	0.00
11,800.00	90.00	179.64	9,850.60	-1,537.96	-235.29	1,541.78	0.00	0.00	0.00
11,900.00	90.00	179.64	9,850.60	-1,637.95	-234.66	1,641.75	0.00	0.00	0.00
12,000.00	90.00	179.64	9,850.60	-1,737.95	-234.03	1,741.72	0.00	0.00	0.00
12,100.00	90.00	179.64	9,850.60	-1,837.95	-233.41	1,841.70	0.00	0.00	0.00
12,200.00	90.00	179.64	9,850.60	-1,937.95	-232.78	1,941.67	0.00	0.00	0.00
12,300.00	90.00	179.64	9,850.60	-2,037.95	-232.15	2,041.64	0.00	0.00	0.00
12,400.00	90.00	179.64	9,850.60	-2,137.94	-231.52	2,141.61	0.00	0.00	0.00
12,500.00	90.00	179.64	9,850.60	-2,237.94	-230.89	2,241.59	0.00	0.00	0.00
12,600.00	90.00	179.64	9,850.60	-2,337.94	-230.27	2,341.56	0.00	0.00	0.00
12,700.00	90.00	179.64	9,850.60	-2,437.94	-229.64	2,441.53	0.00	0.00	0.00
12,800.00	90.00	179.64	9,850.60	-2,537.94	-229.01	2,541.50	0.00	0.00	0.00
12,900.00	90.00	179.64	9,850.60	-2,637.93	-228.38	2,641.48	0.00	0.00	0.00
13,000.00	90.00	179.64	9,850.60	-2,737.93	-227.76	2,741.45	0.00	0.00	0.00
13,100.00	90.00	179.64	9,850.60	-2,837.93	-227.13	2,841.42	0.00	0.00	0.00
13,200.00	90.00	179.64	9,850.60	-2,937.93	-226.50	2,941.39	0.00	0.00	0.00
13,300.00	90.00	179.64	9,850.60	-3,037.93	-225.87	3,041.37	0.00	0.00	0.00
13,400.00	90.00	179.64	9,850.60	-3,137.92	-225.24	3,141.34	0.00	0.00	0.00
13,500.00	90.00	179.64	9,850.60	-3,237.92	-224.62	3,241.31	0.00	0.00	0.00
13,600.00	90.00	179.64	9,850.60	-3,337.92	-223.99	3,341.28	0.00	0.00	0.00
13,700.00	90.00	179.64	9,850.60	-3,437.92	-223.36	3,441.26	0.00	0.00	0.00
13,800.00	90.00	179.64	9,850.60	-3,537.92	-222.73	3,541.23	0.00	0.00	0.00
13,900.00	90.00	179.64	9,850.60	-3,637.91	-222.11	3,641.20	0.00	0.00	0.00
14,000.00	90.00	179.64	9,850.60	-3,737.91	-221.48	3,741.17	0.00	0.00	0.00
14,100.00	90.00	179.64	9,850.60	-3,837.91	-220.85	3,841.14	0.00	0.00	0.00
14,200.00	90.00	179.64	9,850.60	-3,937.91	-220.22	3,941.12	0.00	0.00	0.00
14,300.00	90.00	179.64	9,850.60	-4,037.91	-219.60	4,041.09	0.00	0.00	0.00
14,400.00	90.00	179.64	9,850.60	-4,137.90	-218.97	4,141.06	0.00	0.00	0.00
14,500.00	90.00	179.64	9,850.60	-4,237.90	-218.34	4,241.03	0.00	0.00	0.00
14,600.00	90.00	179.64	9,850.60	-4,337.90	-217.71	4,341.01	0.00	0.00	0.00
14,700.00	90.00	179.64	9,850.60	-4,437.90	-217.08	4,440.98	0.00	0.00	0.00
14,800.00	90.00	179.64	9,850.60	-4,537.90	-216.46	4,540.95	0.00	0.00	0.00
14,900.00	90.00	179.64	9,850.60	-4,637.89	-215.83	4,640.92	0.00	0.00	0.00
15,000.00	90.00	179.64	9,850.60	-4,737.89	-215.20	4,740.90	0.00	0.00	0.00
15,100.00	90.00	179.64	9,850.60	-4,837.89	-214.57	4,840.87	0.00	0.00	0.00
15,200.00	90.00	179.64	9,850.60	-4,937.89	-213.95	4,940.84	0.00	0.00	0.00
15,300.00	90.00	179.64	9,850.60	-5,037.89	-213.32	5,040.81	0.00	0.00	0.00
15,400.00	90.00	179.64	9,850.60	-5,137.88	-212.69	5,140.79	0.00	0.00	0.00
15,500.00	90.00	179.64	9,850.60	-5,237.88	-212.06	5,240.76	0.00	0.00	0.00
15,600.00	90.00	179.64	9,850.60	-5,337.88	-211.43	5,340.73	0.00	0.00	0.00

Oxy Planning Report

Database:	HOPSPP	Local Co-ordinate Reference:	Well Lost Tank 30_19 Federal Com 1H
Company:	ENGINEERING DESIGNS	TVD Reference:	RKB=26.5' @ 3642.60ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	MD Reference:	RKB=26.5' @ 3642.60ft
Site:	LOST TANK 30-19 FED	North Reference:	Grid
Well:	Lost Tank 30_19 Federal Com 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
15,700.00	90.00	179.64	9,850.60	-5,437.88	-210.81	5,440.70	0.00	0.00	0.00
15,800.00	90.00	179.64	9,850.60	-5,537.88	-210.18	5,540.68	0.00	0.00	0.00
15,900.00	90.00	179.64	9,850.60	-5,637.88	-209.55	5,640.65	0.00	0.00	0.00
16,000.00	90.00	179.64	9,850.60	-5,737.87	-208.92	5,740.62	0.00	0.00	0.00
16,100.00	90.00	179.64	9,850.60	-5,837.87	-208.30	5,840.59	0.00	0.00	0.00
16,200.00	90.00	179.64	9,850.60	-5,937.87	-207.67	5,940.56	0.00	0.00	0.00
16,300.00	90.00	179.64	9,850.60	-6,037.87	-207.04	6,040.54	0.00	0.00	0.00
16,400.00	90.00	179.64	9,850.60	-6,137.87	-206.41	6,140.51	0.00	0.00	0.00
16,500.00	90.00	179.64	9,850.60	-6,237.86	-205.78	6,240.48	0.00	0.00	0.00
16,600.00	90.00	179.64	9,850.60	-6,337.86	-205.16	6,340.45	0.00	0.00	0.00
16,700.00	90.00	179.64	9,850.60	-6,437.86	-204.53	6,440.43	0.00	0.00	0.00
16,800.00	90.00	179.64	9,850.60	-6,537.86	-203.90	6,540.40	0.00	0.00	0.00
16,900.00	90.00	179.64	9,850.60	-6,637.86	-203.27	6,640.37	0.00	0.00	0.00
17,000.00	90.00	179.64	9,850.60	-6,737.85	-202.65	6,740.34	0.00	0.00	0.00
17,100.00	90.00	179.64	9,850.60	-6,837.85	-202.02	6,840.32	0.00	0.00	0.00
17,200.00	90.00	179.64	9,850.60	-6,937.85	-201.39	6,940.29	0.00	0.00	0.00
17,300.00	90.00	179.64	9,850.60	-7,037.85	-200.76	7,040.26	0.00	0.00	0.00
17,400.00	90.00	179.64	9,850.60	-7,137.85	-200.13	7,140.23	0.00	0.00	0.00
17,500.00	90.00	179.64	9,850.60	-7,237.84	-199.51	7,240.21	0.00	0.00	0.00
17,600.00	90.00	179.64	9,850.60	-7,337.84	-198.88	7,340.18	0.00	0.00	0.00
17,700.00	90.00	179.64	9,850.60	-7,437.84	-198.25	7,440.15	0.00	0.00	0.00
17,800.00	90.00	179.64	9,850.60	-7,537.84	-197.62	7,540.12	0.00	0.00	0.00
17,900.00	90.00	179.64	9,850.60	-7,637.84	-197.00	7,640.10	0.00	0.00	0.00
18,000.00	90.00	179.64	9,850.60	-7,737.83	-196.37	7,740.07	0.00	0.00	0.00
18,100.00	90.00	179.64	9,850.60	-7,837.83	-195.74	7,840.04	0.00	0.00	0.00
18,200.00	90.00	179.64	9,850.60	-7,937.83	-195.11	7,940.01	0.00	0.00	0.00
18,300.00	90.00	179.64	9,850.60	-8,037.83	-194.49	8,039.99	0.00	0.00	0.00
18,400.00	90.00	179.64	9,850.60	-8,137.83	-193.86	8,139.96	0.00	0.00	0.00
18,500.00	90.00	179.64	9,850.60	-8,237.82	-193.23	8,239.93	0.00	0.00	0.00
18,600.00	90.00	179.64	9,850.60	-8,337.82	-192.60	8,339.90	0.00	0.00	0.00
18,700.00	90.00	179.64	9,850.60	-8,437.82	-191.97	8,439.87	0.00	0.00	0.00
18,800.00	90.00	179.64	9,850.60	-8,537.82	-191.35	8,539.85	0.00	0.00	0.00
18,900.00	90.00	179.64	9,850.60	-8,637.82	-190.72	8,639.82	0.00	0.00	0.00
19,000.00	90.00	179.64	9,850.60	-8,737.81	-190.09	8,739.79	0.00	0.00	0.00
19,100.00	90.00	179.64	9,850.60	-8,837.81	-189.46	8,839.76	0.00	0.00	0.00
19,200.00	90.00	179.64	9,850.60	-8,937.81	-188.84	8,939.74	0.00	0.00	0.00
19,300.00	90.00	179.64	9,850.60	-9,037.81	-188.21	9,039.71	0.00	0.00	0.00
19,400.00	90.00	179.64	9,850.60	-9,137.81	-187.58	9,139.68	0.00	0.00	0.00
19,500.00	90.00	179.64	9,850.60	-9,237.80	-186.95	9,239.65	0.00	0.00	0.00
19,600.00	90.00	179.64	9,850.60	-9,337.80	-186.32	9,339.63	0.00	0.00	0.00
19,700.00	90.00	179.64	9,850.60	-9,437.80	-185.70	9,439.60	0.00	0.00	0.00
19,800.00	90.00	179.64	9,850.60	-9,537.80	-185.07	9,539.57	0.00	0.00	0.00
19,900.00	90.00	179.64	9,850.60	-9,637.80	-184.44	9,639.54	0.00	0.00	0.00
20,000.00	90.00	179.64	9,850.60	-9,737.79	-183.81	9,739.52	0.00	0.00	0.00
20,100.00	90.00	179.64	9,850.60	-9,837.79	-183.19	9,839.49	0.00	0.00	0.00
20,200.00	90.00	179.64	9,850.60	-9,937.79	-182.56	9,939.46	0.00	0.00	0.00
20,300.00	90.00	179.64	9,850.60	-10,037.79	-181.93	10,039.43	0.00	0.00	0.00
20,400.00	90.00	179.64	9,850.60	-10,137.79	-181.30	10,139.41	0.00	0.00	0.00
20,500.00	90.00	179.64	9,850.60	-10,237.78	-180.67	10,239.38	0.00	0.00	0.00
20,600.00	90.00	179.64	9,850.60	-10,337.78	-180.05	10,339.35	0.00	0.00	0.00
20,684.07	90.00	179.64	9,850.60	-10,421.85	-179.52	10,423.40	0.00	0.00	0.00

Oxy Planning Report

Database:	HOPSPP	Local Co-ordinate Reference:	Well Lost Tank 30_19 Federal Com 1H
Company:	ENGINEERING DESIGNS	TVD Reference:	RKB=26.5' @ 3642.60ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	MD Reference:	RKB=26.5' @ 3642.60ft
Site:	LOST TANK 30-19 FED	North Reference:	Grid
Well:	Lost Tank 30_19 Federal Com 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL (Lost Tank - hit/miss target - Shape - Point	0.00	0.00	9,850.60	-10,421.85	-179.52	493,520.51	730,814.04	32° 21' 18.956878 N	103° 43' 11.000666
FTP (Lost Tank 30_19 - plan hits target center - Point	0.00	0.00	9,850.60	25.39	-245.10	503,967.21	730,748.46	32° 23' 2.333486 N	103° 43' 11.066902


Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
4,550.00	4,550.00	0.00	0.00	Build 2.00°/100'	
5,049.88	5,047.35	40.82	-15.05	Hold 10.00° Tangent	
8,451.89	8,397.70	594.98	-219.33	Turn 2.00°/100'	
9,436.62	9,377.14	589.63	-248.64	KOP, Build 10.00°/100'	
10,236.62	9,850.60	25.39	-245.10	Landing Point	
20,684.07	9,850.60	-10,421.85	-179.52	TD at 20684.07' MD	



Project: PRD NM DIRECTIONAL PLANS (NAD 1983)
 Site: LOST TANK 30-19 FED
 Well: Lost Tank 30_19 Federal Com 1H
 Wellbore: Wellbore #1
 Design: Permitting Plan

PROJECT DETAILS: NM DIRECTIONAL PLANS (NAD 1983)

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: New Mexico Eastern Zone
 System Datum: Mean Sea Level





WELL DETAILS: Lost Tank 30_19 Federal Com 1H

+N/-S	+E/-W	North	Ground Level:	East	Latitude	Longitude
0.00	0.00	503941.82	3616.10	730993.55	32° 23' 2.088328 N	103° 43' 8.210475 W

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	Tface	Vsect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4550.00	0.00	0.00	4550.00	0.00	0.00	0.00	0.00	0.00	Build 2.00°/100'
5049.88	10.00	339.76	5047.35	40.82	-15.05	2.00	339.76	-40.55	Hold 10.00° Tangent
8451.89	10.00	339.76	8397.70	594.98	-219.33	0.00	0.00	-591.11	Turn 2.00°/100'
9436.62	10.00	179.64	9377.14	589.63	-248.64	2.00	-169.91	-585.26	KOP, Build 10.00°/100'
10238.82	90.00	179.64	9850.60	25.39	-245.10	10.00	0.00	-21.17	Landing Point
20684.07	90.00	179.64	9850.60	-10421.85	-179.52	0.00	0.00	10423.39	TD at 20684.07 MD



OXY USA Inc
APD ATTACHMENT: SPUDDER RIG DATA

OPERATOR NAME / NUMBER: OXY USA Inc

1. SUMMARY OF REQUEST:


Oxy USA respectfully requests approval for the following operations for the surface hole in the drill plan:

1. Utilize a spudder rig to pre-set surface casing for time and cost savings.

2. Description of Operations

1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
 - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
2. The wellhead will be installed and tested as soon as the surface casing is cut off and the WOC time has been reached.
3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. Spudder rig operations are expected to take 2-3 days per well on the pad.
5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
6. Drilling operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nipped up and tested on the wellhead before drilling operations resume on each well.
 - a. The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
 - b. The BLM will be contacted / notified 24 hours before the larger rig moves back on the pre-set locations.
7. Oxy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
8. Once the rig is removed, Oxy will secure the wellhead area by placing a guard rail around the cellar area.

Spudder Rig Layout



OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

1. Geologic Formations

TVD of target	9851'	Pilot Hole Depth	N/A
MD at TD:	20684'	Deepest Expected fresh water:	856'

Delaware Basin

Formation	TVD - RKB	Expected Fluids
Rustler	856	
Salado	1,150	Salt
Castile	2,870	Salt
Lamar/Delaware	4,587	Oil/Gas/Brine
Bell Canyon	4,670	Oil/Gas/Brine
Cherry Canyon	5,500	Oil/Gas/Brine
Brushy Canyon	6,732	Losses
Bone Spring	8,482	Oil/Gas
1st Bone Spring	9,573	Oil/Gas

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

Hole Size (in)	Casing Interval		Csg. Size (in)	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	Buoyant	Buoyant
	From (ft)	To (ft)							Body SF Tension	Joint SF Tension
17.5	0	906	13.375	54.5	J-55	BTC	1.125	1.2	1.4	1.4
12.25	0	5550	9.625	36	J-55	BTC	1.125	1.2	1.4	1.4
8.5	0	20684	5.5	20	P-110	DQX	1.125	1.2	1.4	1.4
SF Values will meet or Exceed										

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

*Oxy requests the option to set casing shallower yet still below the salts if losses or hole conditions require this. Cement volumes may be adjusted if casing is set shallower and a DV tool may be run in case hole conditions merit pumping a second stage cement job to comply with permitted top of cement. If cement circulated to surface during first stage, we will drop a cancellation cone and not pump the second stage.

*Oxy requests the option to run production casing with DQX, SF TORQ, and/or DQW TORQ connections to accommodate hole conditions or drilling operations.

OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

Annular Clearance Variance Request

As per the agreement reached in the Oxy/BLM meeting on Feb 22, 2018, Oxy requests permission to allow deviation from the 0.422" annular clearance requirement from Onshore Order #2 under the following conditions:

1. Annular clearance to meet or exceed 0.422" between intermediate casing ID and production casing coupling only on the first 500' overlap between both casings.
2. Annular clearance less than 0.422" is acceptable for the curve and lateral portions of the production open hole section.

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

3. Cementing Program

Casing String	# Sk	Wt. (lb/gal)	Yld (ft ³ /sack)	H ₂ O (gal/sk)	500# Comp. Strength (hours)	Slurry Description
Surface (Lead)	N/A	N/A	N/A	N/A	N/A	N/A
Surface (Tail)	958	14.8	1.33	6.365	5:26	Class C Cement, Accelerator
Intermediate (Lead)	840	11	2.71	16.51	22:00	Class C Cement, Retarder
Intermediate (Tail)	156	13.2	1.33	6.368	7:11	Class C Cement, Accelerator
Production (Lead)	394	11	2.71	16.51	22:00	Class C Cement, Retarder, Dispersant, Salt
Production (Tail)	2251	13.2	1.38	6.686	3:49	Class H Cement, Retarder, Dispersant, Salt

Casing String	Top (ft)	Bottom (ft)	% Excess
Surface (Lead)	N/A	N/A	N/A
Surface (Tail)	0	906	100%
Intermediate (Lead)	0	5050	50%
Intermediate (Tail)	5050	5550	20%
Production (Lead)	5050	8937	20%
Production (Tail)	8937	20684	15%

*OXY requests a variance to cement the 7-5/8" intermediate casing string offline, see attached for additional information.

OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
12.25" Hole	13-5/8"	3M	Annular	✓	70% of working pressure
		3M	Blind Ram	✓	250 psi / 3000 psi
			Pipe Ram		
			Double Ram	✓	
			Other*		
8.5" Hole	13-5/8"	3M	Annular	✓	70% of working pressure
		3M	Blind Ram	✓	250 psi / 3000 psi
			Pipe Ram		
			Double Ram	✓	
			Other*		

*Specify if additional ram is utilized.

Oxy will utilize a 5M annular with a 10M BOPE stack. The BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
	A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015. See attached schematics.

OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

BOP Break Testing Request

As per the agreement reached in the Oxy/BLM meeting on Feb 22, 2018, Oxy requests permission to allow BOP Break Testing under the following conditions:

- After a full BOP test is conducted on the first well on the pad.
- When skidding to drill an intermediate section that casing point is either shallower than the third Bone Spring or 10,000 feet TVD.
- Full BOP test will be required prior to drilling any production hole.

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From (ft)	To (ft)				
0	906	Water-Based Mud	8.6-8.8	40-60	N/C
906	5550	Saturated Brine- Mud	9.8-10.0	35-45	N/C
5550	20684	Saturated Brine-Based or Oil-Based Mud	8.0-9.6	38-50	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

What will be used to monitor the loss or gain of fluid?	PVT/MD Totco/Visual Monitoring
---	--------------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
Yes	Will run GR from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
No	Logs are planned based on well control or offset log information.
No	Drill stem test? If yes, explain
No	Coring? If yes, explain

Additional logs planned		Interval
No	Resistivity	
No	Density	
No	CBL	
Yes	Mud log	ICP - TD
No	PEX	

OXY USA Inc. - Lost Tank 30-19 Federal Com 1H – Amended Drill Plan

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4918 psi
Abnormal Temperature	No
BH Temperature at deepest TVD	159°F

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S Plan attached

8. Other facets of operation

	Yes/No
Will the well be drilled with a walking/skidding operation? If yes, describe. <ul style="list-style-type: none">We plan to drill the six well pad in batch by section: all surface sections, intermediate sections and production sections. The wellhead will be secured with a night cap whenever the rig is not over the well.	Yes
Will more than one drilling rig be used for drilling operations? If yes, describe. <ul style="list-style-type: none">Oxy requests the option to contract a Surface Rig to drill, set surface casing, and cement for this well. If the timing between rigs is such that Oxy would not be able to preset surface, the Primary Rig will MIRU and drill the well in its entirety per the APD. Please see the attached document for information on the spudder rig.	Yes

Total estimated cuttings volume: 2008.7 bbls.

9. Company Personnel

Name	Title	Office Phone	Mobile Phone
Ben Pelton	Drilling Engineer	713-497-2379	701-690-8645
William Turner	Drilling Engineer Supervisor	713-350-4951	661-817-4586
Simon Benavides	Drilling Superintendent	713-522-8652	281-684-6897
Diego Tellez	Drilling and Completions Manager	713-350-4602	713-303-4932

OXY USA Inc.
APD Attachment
Offline Cementing

OXY respectfully requests a variance to cement the 9-5/8" and/or 7-5/8" intermediate casing strings offline.

The summarized operational sequence will be as follows:

1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe).
2. Land casing.
3. Fill pipe with kill weight fluid, and confirm well is static.
 - a. If well is not static notify BLM and kill well.
 - b. Once well is static notify BLM with intent to proceed with nipple down and offline cementing.
4. Set and pressure test annular packoff.
5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange. If any barrier fails to test, the BOP stack will not be nipped down until after the cement job is completed.
6. Skid rig to next well on pad.
7. Confirm well is static before removing cap flange.
8. If well is not static notify BLM and kill well prior to cementing or nipping up for further remediation.
9. Install offline cement tool.
10. Rig up cement equipment.
 - a. Notify BLM prior to cement job.
11. Perform cement job.
12. Confirm well is static and floats are holding after cement job.
13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.