

CASING RUN

We propose to run the following strings of casing and to cement off as indicated:

Size of Hole	Size of Casing	Weight per Foot	New or Second Hand	Depth	Shots
15"	11 3/4"	42 & 23.72	New	350'	300
10 5/8"	8 5/8"	24 & 32	New	3300'	1650*
7 5/8"	2 7/8"	6.5	New	9050'	1600**

* 1500 sx. 1:1 Pozmix-Portland regular cement mixture with 8% gel, followed by 150 sx. Portland Neat.

** Externally clean & install centralizers & scratchers - 8100 - TD.
Cement with 500 sx. Class "C" 8% gel containing friction reducing agent followed by 800 sx. Class "C" 8% gel, followed by 300 sx. Class "C" 4% gel. Pump plug down with 400 gals. medium strength acetic acid followed by water.

FORMATION TOPS EXPECTED

Top of Anhydrite	1,720'
Top of Salt	1,890'
Base of Salt	3,005'
Top of Seven Rivers	3,285'
Top of San Andres	4,860'
Top of Abo Reef	8,160'
Total Depth	9,050'