

8 5/8" casing installation: 11"-5M BOP stack to be installed and tested by Yellow Jacket, Inc. to 3,000 psi before drilling the 8 5/8" casing shoe by Yellow Jacket, Inc. The BOP stack to consist of an annular BOP, blind ram BOP and one pipe ram BOP.

11. See Form 9-331C.

12. A. DST Program: (1) Bone Spring, (1) Wolfcamp

B. Core: None

C. Mud Logging: Two Man Unit 2920-TD

D. Wire Line Logs:

The following suite of logs will be run in both of the listed intervals:

Open hole: GR/CNL/Density	TD-2920' (GR-CNL to surf)
GR/Dual Laterolog-MSFL	TD-2920'

13. No abnormal pressures anticipated with bottom hole pressures at TD expected to be 4500 psi. Bottom hole temperature 167° F. No Hydrogen Sulfide expected in this known drilling area. No crooked hole or abnormal deviation problems.

14. Anticipated starting date to spud - on or before 2-19-86. Anticipated drilling time expected to be 33 days from surface to TD.

C. Nokes  
1/31/86

**RECEIVED**  
**MAR 12 1986**  
**C.C.D.**  
**HOBBS OFFICE**

**1**  
**2**  
**3**