

**POINT 7: ANTICIPATED RESERVOIR CONDITIONS**

Normal pressures are anticipated. Washout within the salt can be expected. No H<sub>2</sub>S is anticipated.

**POINT 8: OTHER PERTINENT INFORMATION**

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon Approval

13 days drilling operations

5 days completion operations