

GW - 032

**FACILITY WIDE
GW MONITORING
WORK PLAN
CORRESPONDENCE
2020**



Western Refining Southwest LLC

I-40 Exit 39 A subsidiary of Marathon Petroleum Corporation
Jamestown, NM 87347

March 25, 2021

Mr. Kevin Pierard, Chief
New Mexico Environment Department
Hazardous Waste Bureau
2905 Rodeo Park Drive East, Building 1
Santa Fe, New Mexico 87505

**RE: Approval with Modifications
Disapproval Facility Wide Ground Water Monitoring Work Plan – Updates for 2020
Western Refining Southwest LLC, Gallup Refinery
EPA ID #NMD000333211
HWB-WRG-20-012**

Dear Mr. Pierard,

Attached please find the response to the comments contained in the New Mexico Environment Department (NMED) Approval with Modifications Facility Wide Ground Water Monitoring Plan – Updates for 2020.

If you have any questions or comments regarding the information contained herein, please do not hesitate to contact Mr. John Moore of my staff at 505-879-7643.

Certification

I certify under penalty of law that this document and all attachments were prepared under my direction of supervision according to a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Sincerely,
Marathon Petroleum Company LP, Gallup Refinery

Robert S. Hanks

Robert S. Hanks
Refinery General Manager

Enclosure

cc: D. Cobrain, NMED HWB
M. Suzuki, NMED HWB
C. Chavez OCD
L. King, EPA Region 6
G. McCartney, Marathon Petroleum Company
K. Luka, Marathon Petroleum Company
J. Moore, Marathon Gallup Refinery
H. Jones, Trihydro Corporation

Response to Comments

**New Mexico Environment Department to Marathon Petroleum Company Comment Letter “Approval with Modifications
Disapproval Facility Wide Groundwater Water Monitoring Work Plan – Updates for 2020” (February 16, 2021)**

New Mexico Environment Department (NMED) Comment	Marathon Petroleum Company (MPC) Response
Comment 1: The response to NMED’s <i>Disapproval</i> Comment 5 states, “SPH will enter the well and depress the water table as the SPH tries to equilibrate with the SPH head in the soil column outside the monitoring well,” and “[t]he actual thickness of the SPH in the soil column may only be a few inches, but due to mobility of the SPH, the thickness in the monitoring well may be several feet.” Note that the mobility of SPH is much less than that of groundwater and a fluctuation of the groundwater elevation may significantly affect observed SPH thickness in a well. NMED agrees that observed SPH measurements may not accurately reflect site conditions. The Permittee only discusses the condition when the observed SPH thickness overestimates SPH thickness in the surrounding formation; however, does not discuss the condition when observed SPH thickness underestimates SPH thickness in the surrounding formation. For example, if the screened intervals of some pertinent wells are submerged below the water table and SPH thickness may be underestimated at these locations. Discuss conditions when observed SPH thickness can be underestimated in the surrounding formation in the revised Work Plan and provide replacement pages.	Response 1: Section 2.4.1.1 has been revised to state: SPH can be underestimated when the monitoring well screen is submerged in the groundwater. Under these conditions, because of the overlying groundwater head conditions, SPH will remain within the formation and is essentially trapped SPH. It will not possess enough mobility to enter a monitoring well with a submerged screen. These conditions also indicate that SPH is not mobile within the surrounding formation and thus cannot migrate laterally. In this case the use of the term “underestimated” may not be appropriate because the hydraulic head conditions with the formation dictate the movement of any SPH into a well screen. The replacement pages have been included in Attachment A.
Comment 2: The response to NMED’s <i>Disapproval</i> Comment 11 states, “[a] reference section has been added to the revised report and individual footnotes have been removed.” The reference section is appropriately added to the Work Plan; however, the Table of Contents is not updated to include the reference section. Include the reference section in the Table of Contents and provide replacement pages.	Response 2: The Table of Contents has been revised to include the reference section. The replacement pages have been included in Attachment A.

**New Mexico Environment Department to Marathon Petroleum Company Comment Letter “Approval with Modifications
Disapproval Facility Wide Groundwater Water Monitoring Work Plan – Updates for 2020” (February 16, 2021)**

Comment 3:	Response 3:
The response to NMED’s <i>Disapproval</i> Comment 17 states, “[t]he referenced chromium exceedance was an incorrect entry and the actual result for chromium is <0.006 mg/L.” Provide the laboratory report that shows the result of the chromium analysis for well NAPIS-2. In addition, although the response provides clarification for the direction provided by Comment 12 of NMED’s <i>Approval with Modifications Annual Ground Water Monitoring Report Gallup Refinery – 2018</i>, dated January 22, 2020, it does not address other comments that directed revisions to the monitoring program. To clarify, NMED’s <i>Disapproval</i> Comment 17 states, “[r]eference all relevant NMED’s comments that directed revisions to the monitoring program and provide a discussion in the revised Work Plan,”; therefore, the Permittee must reference NMED’s relevant comments that directed revisions to the monitoring program. The following are some examples. a) Comment 6 in NMED’s <i>Disapproval Natural Attenuation and Proposed Workplan for the Hydrocarbon Seep Area</i>, dated January 26, 2021, states, “[p]ropose to conduct sulfide analysis for pertinent wells in the next groundwater monitoring plan updated.” Address this comment in the 2020 Work Plan. b) NMED’s <i>Approval Hydrocarbon Seep Interim Measures 2020 First Quarter Status Report, and Hydrocarbon Seep Interim Measures 2020 Second Quarter Status Report</i>, dated November 23, 2020, states, “the frequency of the water level measurements must be increased to biquarterly in order to evaluate potential effects of idling operations.” NMED’s <i>Approval Hydrocarbon Seep Interim Measures 2020 Third Quarter Status Report</i>, dated December 11, 2020, subsequently approved proposed monthly gauging for all relevant wells. Since the gauging frequency will	The chromium analytical laboratory report for well NAPIS-2 is included in Attachment B. Additions to the 2020 groundwater monitoring program were requested by NMED in the following letters: • NMED’s <i>Approval Hydrocarbon Seep Interim Measures 2020 First Quarter Status Report, and Hydrocarbon Seep Interim Measures 2020 Second Quarter Status Report</i> (November 23, 2020) • <i>Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019</i> (November 23, 2020) • <i>Approval Hydrocarbon Seep Interim Measures 2020 Third Quarter Status Report</i> (December 11, 2020) • <i>Disapproval Natural Attenuation and Proposed Workplan for the Hydrocarbon Seep Area 2020</i> (January 26, 2021) These comments were submitted by NMED in November and December 2020 and January 2021 after most of the 2020 field activities had been completed. Because the 2020 calendar year has passed by the time the comments were received, the revisions are not relevant to work completed 2020. As requested by NMED, MPC will incorporate these comments into the 2021 work plan and will implement these changes in 2021.

**New Mexico Environment Department to Marathon Petroleum Company Comment Letter “Approval with Modifications
Disapproval Facility Wide Groundwater Water Monitoring Work Plan – Updates for 2020” (February 16, 2021)**

be increased in 2020, it is appropriate to update the monitoring frequency in the 2020 Work Plan.

c) Comment 13 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “propose to conduct 1,4-dioxane analysis using EPA Method 8270 SIM for the samples collected from the West LDU in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 7 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

d) Comment 13 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “propose to conduct 1,4-dioxane analysis using EPA Method 8270 SIM for wells OW-50 and OW-52 in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 13 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

e) Comment 22 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “propose to conduct 1,4-dioxane analysis using EPA Method 8270 SIM and 1,2-dibromoethane (EDB) using EPA Method 8011 for groundwater samples collected from well OW-11 in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 22 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

**New Mexico Environment Department to Marathon Petroleum Company Comment Letter “Approval with Modifications
Disapproval Facility Wide Groundwater Water Monitoring Work Plan – Updates for 2020” (February 16, 2021)**

f) Comment 25 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “[p]ropose to conduct pesticide analysis for the water samples collected from pond EP-2 using EPA Method 8081 in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 25 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

g) Comment 26 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery -2019*, dated November 23, 2020, states, “[p]ropose to discontinue pesticide analysis for the samples collected from ponds EP-3, EP-12A, and EP-12B in the 2020 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 26 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

h) Comment 30 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “[p]ropose to conduct PFAS analysis for the groundwater samples collected from OW-63 in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 30 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

i) Comment 52 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “[t]he Permittee must continue to conduct 1,4-dioxane analysis using EPA Method 8270 SIM for groundwater sample collected from well SMW-4. Propose to continue the

**New Mexico Environment Department to Marathon Petroleum Company Comment Letter “Approval with Modifications
Disapproval Facility Wide Groundwater Water Monitoring Work Plan – Updates for 2020” (February 16, 2021)**

analysis in the 2021 Facility-wide Groundwater Monitoring Work Plan...” Although Comment 52 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

j) Comment 52 in NMED’s *Disapproval Annual Groundwater Monitoring Report Gallup Refinery – 2019*, dated November 23, 2020, states, “[t]he Permittee must continue to conduct 1,4-dioxane analysis using EPA Method 8270 SIM for groundwater sample collected from well SMW-4. Propose to continue the analysis in the 2021 Facility-wide Groundwater Monitoring Work Plan.” Although Comment 52 directed the Permittee to address the comment in the 2021 Work Plan, this direction must be addressed in the 2020 Work Plan because the 2020 Work Plan requires other revisions and submittal of a revised Work Plan.

Attachment A – Revised Facility Wide Groundwater Monitoring Work Plan – Updates for 2020

11 AOCs (AOC 16, 17, 18, 24, 26, 27, 28, 29, 30, 31, and 34) being removed from the Permit and transferred to the Consent Order for further evaluation.

2.4 Summary of contaminant releases that could contribute to possible ground water contamination.

Spills and leaks are known to have occurred on the site in various locations. Although most hydrocarbons are immediately picked up for recovery and contaminated soil is removed, some of the liquids present in a spill may enter the subsurface. With precipitation, there is the possibility that some of the contaminants could leach and reach ground water.

2.4.1 Separate Phase Hydrocarbons

Separate phase hydrocarbons (SPH) have been found in multiple locations within the refinery. These locations include the Main Tank Farm, Hydrocarbon Seep Area, Aeration Basin, French Drain, Truck Loading Rack, and NAPIS Unit areas.

2.4.1.1 Main Tank Farm

Separate phase hydrocarbons (SPH) floating on shallow ground water was found in the mid-1990s at the northeast end of the facility in the main tank farm. A series of recovery wells were installed and SPH has been recovered since the initial discovery. Recovery through hand-bailing was conducted on a quarterly basis and in 2019 recovery pumps were installed. In March 2019, MPC proposed an interim recovery system using pumps in RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55. The interim system was proposed to recover SPH and dissolved-phase impacts within and down-gradient of the main tank farm. The *Interim Groundwater Recovery System Work Plan* was approved with modifications on August 6, 2019.

Observed SPH measurements may potentially under or overestimate SPH thicknesses in the soil. SPH can be underestimated when the monitoring well screen is submerged in the groundwater. Under these conditions, because of the overlying groundwater head conditions, SPH will remain within the formation and is essentially trapped SPH. It will not possess enough mobility to enter a monitoring well with a submerged screen. These conditions also indicate that SPH is not mobile



within the surrounding formation and thus cannot migrate laterally. In this case the use of the term “underestimated” may not be appropriate because the hydraulic head conditions with the formation dictate the movement of any SPH into a well screen.

SPH can be overestimated when SPH enters the well and depresses the water table as the SPH tries to equilibrate with the SPH head in the soil column outside the monitoring well. Therefore, if the SPH is not floating on the water table and is, instead, perched in a more permeable layer above the water table, the SPH in the monitoring well will appear to be thicker than the SPH in the surrounding soils. In other words, the SPH will flow into the well, and as long as there is sufficient SPH and pressure head, the SPH will rise within the well to the level of the perched SPH. It may also depress the water table within the monitoring well. The actual thickness of the SPH in the soil column may only be a few inches, but due to the mobility of the SPH, the thickness in the monitoring well may be several feet. Recovery wells in the main tank farm and the down-gradient area are listed as follows:

RECOVERY WELLS			
RW-1	RW-2	RW-5	RW-6
OW-14	OW-58	OW-30	OW-55

2.4.1.2 Hydrocarbon Seep

In June of 2013 during a routine inspection, a hydrocarbon seep was discovered in an isolated area approximately 100 yards west of Tank 101/102. A series of excavations were completed in the area of the seep including installation of six temporary sumps for bi-weekly hydrocarbon recovery. Through 2019 a total of 1,727,574 gallons of liquid (hydrocarbon and ground water) have been recovered from these sumps. To date a total of 49 permanent monitoring wells have been installed with an addition of one pre-existing well, which has been labeled as MKTF-45, and is located in the vicinity of the site investigation. SPH has been measured in Marketing Tank Farm (MKTF) wells located west and northwest of the truck loading rack and marketing tank farm, extending northwest to the location of the hydrocarbon seep. The Gallup Refinery continues to further characterize potential source areas, recovery of liquids from the temporary sumps, and continued sampling of the monitoring wells for characterization and delineation purposes. All 50 wells are

Attachment B – Revised Hall Environmental Analysis Laboratory, Inc. Report, 2nd Quarter 2018
Groundwater Sampling



Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

June 07, 2018

Jessica O'Brien
Andeavor Gallup
92 GIANT CROSSING RD
GALLUP, NM 87301
TEL:
FAX

RE: 2nd Quarter 2018 Groundwater Sampling (API)

OrderNo.: 1805106

Dear Jessica O'Brien:

Hall Environmental Analysis Laboratory received 11 sample(s) on 5/2/2018 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. To access our accredited tests please go to www.hallenvironmental.com or the state specific web sites. In order to properly interpret your results, it is imperative that you review this report in its entirety. See the sample checklist and/or the Chain of Custody for information regarding the sample receipt temperature and preservation. Data qualifiers or a narrative will be provided if the sample analysis or analytical quality control parameters require a flag. When necessary, data qualifiers are provided on both the sample analysis report and the QC summary report, both sections should be reviewed. All samples are reported, as received, unless otherwise indicated. Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH and residual chlorine are qualified as being analyzed outside of the recommended holding time.

Please don't hesitate to contact HEAL for any additional information or clarifications.

ADHS Cert #AZ0682 -- NMED-DWB Cert #NM9425 -- NMED-Micro Cert #NM0901

Sincerely,

A handwritten signature in black ink, appearing to read 'Andy Freeman', is written over a horizontal line.

Andy Freeman
Laboratory Manager
4901 Hawkins NE
Albuquerque, NM 87109

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: EB02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 9:20:00 AM

Lab ID: 1805106-001

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	ND	0.63	1.0		mg/L	1	5/3/2018 8:15:42 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 8:15:42 PM	37932
Surr: DNOP	142	0	76.7-135	S	%Rec	1	5/3/2018 8:15:42 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	ND	0.021	0.050		mg/L	1	5/5/2018 2:10:06 AM	G51045
Surr: BFB	84.7	0	69.3-150		%Rec	1	5/5/2018 2:10:06 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	ND	0.15	0.50		mg/L	5	5/11/2018 1:08:58 PM	R5122C
Chloride	0.57	0.15	2.5	J	mg/L	5	5/11/2018 1:08:58 PM	R5122C
Bromide	ND	0.13	0.50		mg/L	5	5/11/2018 1:08:58 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 1:08:58 PM	R5122C
Sulfate	ND	1.0	2.5		mg/L	5	5/11/2018 1:08:58 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 3:24:32 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	ND	0.00099	0.0020		mg/L	1	5/18/2018 11:10:38 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:10:38 AM	A51375
Calcium	ND	0.078	1.0		mg/L	1	5/18/2018 11:10:38 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:10:38 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:10:38 AM	A51375
Iron	ND	0.016	0.020		mg/L	1	5/18/2018 11:10:38 AM	A51375
Magnesium	ND	0.25	1.0		mg/L	1	5/18/2018 11:10:38 AM	A51375
Manganese	0.00041	0.00039	0.0020	J	mg/L	1	5/18/2018 11:10:38 AM	A51375
Potassium	ND	0.11	1.0		mg/L	1	5/18/2018 11:10:38 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:10:38 AM	A51375
Sodium	ND	0.16	1.0		mg/L	1	5/23/2018 2:18:36 PM	B51452
Zinc	0.0068	0.0021	0.010	J	mg/L	1	5/18/2018 11:10:38 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	ND	0.0010	0.0020		mg/L	1	5/31/2018 8:36:14 PM	37927
Cadmium	0.00082	0.00058	0.0020	J	mg/L	1	5/31/2018 8:36:14 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 8:36:14 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:36:14 PM	37927
Iron	ND	0.010	0.020		mg/L	1	6/5/2018 2:38:06 PM	37927
Manganese	0.0015	0.0011	0.0020	J	mg/L	1	5/31/2018 8:36:14 PM	37927
Silver	0.0033	0.0012	0.0050	J	mg/L	1	5/31/2018 8:36:14 PM	37927
Zinc	ND	0.0033	0.010		mg/L	1	5/31/2018 8:36:14 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	ND	0.00042	0.0010		mg/L	1	5/3/2018 2:53:56 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**Date Reported: **6/7/2018****CLIENT:** Andeavor Gallup**Client Sample ID:** EB02**Project:** 2nd Quarter 2018 Groundwater Sampling**Collection Date:** 4/30/2018 9:20:00 AM**Lab ID:** 1805106-001**Matrix:** AQUEOUS**Received Date:** 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								
							Analyst: DBK	
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 2:53:56 PM	B51024
Selenium	ND	0.00076	0.0010		mg/L	1	5/3/2018 2:53:56 PM	B51024
Uranium	ND	0.000096	0.00050		mg/L	1	5/3/2018 2:53:56 PM	B51024
200.8 ICPMS METALS:TOTAL								
							Analyst: ELS	
Arsenic	ND	0.00041	0.0010		mg/L	1	5/8/2018 12:10:25 PM	37927
Lead	ND	0.00023	0.00050		mg/L	1	5/8/2018 12:10:25 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:10:25 PM	37927
Uranium	ND	0.000068	0.00050		mg/L	1	5/8/2018 12:10:25 PM	37927
EPA METHOD 245.1: MERCURY								
							Analyst: rde	
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 5:44:16 PM	37992
EPA METHOD 8260B: VOLATILES								
							Analyst: DJF	
Benzene	ND	0.062	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Toluene	ND	0.064	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Ethylbenzene	ND	0.093	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Methyl tert-butyl ether (MTBE)	ND	0.24	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2,4-Trimethylbenzene	0.20	0.11	1.0	J	µg/L	1	5/10/2018 1:58:14 PM	W5119
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Naphthalene	ND	0.11	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1-Methylnaphthalene	ND	0.16	4.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
2-Methylnaphthalene	ND	0.15	4.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Acetone	3.6	0.82	10	J	µg/L	1	5/10/2018 1:58:14 PM	W5119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 1:58:14 PM	W5119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 1:58:14 PM	W5119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**Date Reported: **6/7/2018****CLIENT:** Andeavor Gallup**Client Sample ID:** EB02**Project:** 2nd Quarter 2018 Groundwater Sampling**Collection Date:** 4/30/2018 9:20:00 AM**Lab ID:** 1805106-001**Matrix:** AQUEOUS**Received Date:** 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 1:58:14 PM	W5119
Isopropylbenzene	ND	0.051	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 1:58:14 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
n-Butylbenzene	ND	0.13	3.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
n-Propylbenzene	ND	0.074	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
sec-Butylbenzene	ND	0.11	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 1:58:14 PM	W5119
Xylenes, Total	ND	0.32	1.5		µg/L	1	5/10/2018 1:58:14 PM	W5119
Surr: 1,2-Dichloroethane-d4	90.0	0	70-130		%Rec	1	5/10/2018 1:58:14 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: EB02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 9:20:00 AM

Lab ID: 1805106-001

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
Surr: 4-Bromofluorobenzene	116	0	70-130		%Rec	1	5/10/2018 1:58:14 PM	W5119
Surr: Dibromofluoromethane	94.7	0	70-130		%Rec	1	5/10/2018 1:58:14 PM	W5119
Surr: Toluene-d8	98.0	0	70-130		%Rec	1	5/10/2018 1:58:14 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: EAST LDU

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 1:50:00 PM

Lab ID: 1805106-002

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								
							Analyst: TOM	
Diesel Range Organics (DRO)	4.2	0.63	1.0		mg/L	1	5/3/2018 8:37:47 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 8:37:47 PM	37932
Surr: DNOP	119	0	76.7-135		%Rec	1	5/3/2018 8:37:47 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								
							Analyst: NSB	
Gasoline Range Organics (GRO)	5.1	0.42	1.0		mg/L	20	5/5/2018 2:33:26 AM	G51049
Surr: BFB	102	0	69.3-150		%Rec	20	5/5/2018 2:33:26 AM	G51049
EPA METHOD 200.7: DISSOLVED METALS								
							Analyst: pmf	
Barium	0.38	0.00099	0.0020		mg/L	1	5/18/2018 11:12:48 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:12:48 AM	A51375
Chromium	0.020	0.0013	0.0060		mg/L	1	5/18/2018 11:12:48 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:12:48 AM	A51375
Iron	0.080	0.016	0.020		mg/L	1	5/18/2018 11:12:48 AM	A51375
Manganese	0.11	0.00039	0.0020	*	mg/L	1	5/18/2018 11:12:48 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:12:48 AM	A51375
Zinc	0.010	0.0021	0.010		mg/L	1	5/18/2018 11:12:48 AM	A51375
EPA METHOD 200.7: TOTAL METALS								
							Analyst: pmf	
Barium	0.38	0.0010	0.0020		mg/L	1	5/31/2018 8:38:25 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:38:25 PM	37927
Chromium	0.050	0.0018	0.0060		mg/L	1	5/31/2018 8:38:25 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:38:25 PM	37927
Iron	0.20	0.010	0.020		mg/L	1	6/5/2018 2:40:16 PM	37927
Manganese	0.11	0.0011	0.0020	*	mg/L	1	5/31/2018 8:38:25 PM	37927
Silver	0.0013	0.0012	0.0050	J	mg/L	1	5/31/2018 8:38:25 PM	37927
Zinc	0.020	0.0033	0.010		mg/L	1	5/31/2018 8:38:25 PM	37927
EPA 200.8: DISSOLVED METALS								
							Analyst: DBK	
Arsenic	ND	0.00042	0.0010		mg/L	1	5/3/2018 2:56:14 PM	B51024
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 2:56:14 PM	B51024
Selenium	0.0024	0.00076	0.0010		mg/L	1	5/3/2018 2:56:14 PM	B51024
Uranium	ND	0.000096	0.00050		mg/L	1	5/3/2018 2:56:14 PM	B51024
200.8 ICPMS METALS:TOTAL								
							Analyst: ELS	
Arsenic	ND	0.00041	0.0010		mg/L	1	5/8/2018 12:17:17 PM	37927
Lead	ND	0.00023	0.00050		mg/L	1	5/8/2018 12:17:17 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:17:17 PM	37927
Uranium	ND	0.000068	0.00050		mg/L	1	5/8/2018 12:17:17 PM	37927
EPA METHOD 245.1: MERCURY								
							Analyst: rde	
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 5:46:35 PM	37992

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 5 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

CLIENT: Andeavor Gallup

Client Sample ID: EAST LDU

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 1:50:00 PM

Lab ID: 1805106-002

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260: VOLATILES SHORT LIST							Analyst: RAA	
Benzene	710	0.62	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
Toluene	37	0.64	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
Ethylbenzene	260	0.93	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
Methyl tert-butyl ether (MTBE)	ND	2.4	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
1,2,4-Trimethylbenzene	160	1.1	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
1,3,5-Trimethylbenzene	150	0.87	10		µg/L	10	5/11/2018 6:51:00 PM	SL5124
Xylenes, Total	600	3.2	15		µg/L	10	5/11/2018 6:51:00 PM	SL5124
Surr: 1,2-Dichloroethane-d4	107	0	70-130		%Rec	10	5/11/2018 6:51:00 PM	SL5124
Surr: 4-Bromofluorobenzene	110	0	70-130		%Rec	10	5/11/2018 6:51:00 PM	SL5124
Surr: Dibromofluoromethane	110	0	70-130		%Rec	10	5/11/2018 6:51:00 PM	SL5124
Surr: Toluene-d8	111	0	70-130		%Rec	10	5/11/2018 6:51:00 PM	SL5124

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 6 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: WEST LDU

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 2:15:00 PM

Lab ID: 1805106-003

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE						Analyst: TOM		
Diesel Range Organics (DRO)	9.4	0.63	1.0		mg/L	1	5/3/2018 8:59:47 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 8:59:47 PM	37932
Surr: DNOP	116	0	76.7-135		%Rec	1	5/3/2018 8:59:47 PM	37932
EPA METHOD 8015D: GASOLINE RANGE						Analyst: NSB		
Gasoline Range Organics (GRO)	5.8	0.42	1.0		mg/L	20	5/5/2018 2:56:45 AM	G51045
Surr: BFB	88.0	0	69.3-150		%Rec	20	5/5/2018 2:56:45 AM	G51045
EPA METHOD 200.7: DISSOLVED METALS						Analyst: pmf		
Barium	0.092	0.00099	0.0020		mg/L	1	5/18/2018 11:14:57 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:14:57 AM	A51375
Chromium	0.68	0.0013	0.0060	*	mg/L	1	5/18/2018 11:14:57 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:14:57 AM	A51375
Iron	0.31	0.016	0.020	*	mg/L	1	5/18/2018 11:14:57 AM	A51375
Manganese	1.7	0.0020	0.010	*	mg/L	5	5/18/2018 1:03:35 PM	A51375
Silver	0.0047	0.0018	0.0050	J	mg/L	1	5/18/2018 11:14:57 AM	A51375
Zinc	0.040	0.0021	0.010		mg/L	1	5/18/2018 11:14:57 AM	A51375
EPA METHOD 200.7: TOTAL METALS						Analyst: pmf		
Barium	0.094	0.0010	0.0020		mg/L	1	5/31/2018 8:40:41 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:40:41 PM	37927
Chromium	0.66	0.0018	0.0060	*	mg/L	1	5/31/2018 8:40:41 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:40:41 PM	37927
Iron	0.92	0.010	0.020	*	mg/L	1	6/5/2018 2:42:26 PM	37927
Manganese	1.4	0.0055	0.010	*	mg/L	5	6/5/2018 2:44:25 PM	37927
Silver	0.0074	0.0012	0.0050		mg/L	1	5/31/2018 8:40:41 PM	37927
Zinc	0.065	0.0033	0.010		mg/L	1	5/31/2018 8:40:41 PM	37927
EPA 200.8: DISSOLVED METALS						Analyst: DBK		
Arsenic	0.0050	0.0021	0.0050	J	mg/L	5	5/14/2018 5:49:35 PM	B51261
Lead	ND	0.00087	0.0025		mg/L	5	5/14/2018 5:49:35 PM	B51261
Selenium	0.0075	0.0038	0.0050		mg/L	5	5/14/2018 5:49:35 PM	B51261
Uranium	0.00058	0.00048	0.0025	J	mg/L	5	5/14/2018 5:49:35 PM	B51261
200.8 ICPMS METALS:TOTAL						Analyst: ELS		
Arsenic	0.0051	0.0021	0.0050		mg/L	5	5/8/2018 12:19:33 PM	37927
Lead	ND	0.0011	0.0025		mg/L	5	5/8/2018 12:19:33 PM	37927
Selenium	ND	0.0049	0.0050		mg/L	5	5/8/2018 12:19:33 PM	37927
Uranium	0.00069	0.00034	0.0025	J	mg/L	5	5/8/2018 12:19:33 PM	37927
EPA METHOD 245.1: MERCURY						Analyst: rde		
Mercury	0.000097	0.000037	0.00020	J	mg/L	1	5/8/2018 5:48:46 PM	37992

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 7 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: WEST LDU

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 2:15:00 PM

Lab ID: 1805106-003

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260: VOLATILES SHORT LIST							Analyst: RAA	
Benzene	2700	6.2	100		µg/L	100	5/11/2018 7:15:00 PM	SL5124
Toluene	16	0.64	10		µg/L	10	5/11/2018 7:39:00 PM	SL5124
Ethylbenzene	72	0.93	10		µg/L	10	5/11/2018 7:39:00 PM	SL5124
Methyl tert-butyl ether (MTBE)	ND	2.4	10		µg/L	10	5/11/2018 7:39:00 PM	SL5124
1,2,4-Trimethylbenzene	1.8	1.1	10	J	µg/L	10	5/11/2018 7:39:00 PM	SL5124
1,3,5-Trimethylbenzene	ND	0.87	10		µg/L	10	5/11/2018 7:39:00 PM	SL5124
Xylenes, Total	35	3.2	15		µg/L	10	5/11/2018 7:39:00 PM	SL5124
Surr: 1,2-Dichloroethane-d4	106	0	70-130		%Rec	10	5/11/2018 7:39:00 PM	SL5124
Surr: 4-Bromofluorobenzene	109	0	70-130		%Rec	10	5/11/2018 7:39:00 PM	SL5124
Surr: Dibromofluoromethane	106	0	70-130		%Rec	10	5/11/2018 7:39:00 PM	SL5124
Surr: Toluene-d8	111	0	70-130		%Rec	10	5/11/2018 7:39:00 PM	SL5124

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: FB02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 2:30:00 PM

Lab ID: 1805106-004

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	ND	0.63	1.0		mg/L	1	5/3/2018 9:21:55 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 9:21:55 PM	37932
Surr: DNOP	117	0	76.7-135		%Rec	1	5/3/2018 9:21:55 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	ND	0.021	0.050		mg/L	1	5/5/2018 3:19:53 AM	G51045
Surr: BFB	89.0	0	69.3-150		%Rec	1	5/5/2018 3:19:53 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	ND	0.15	0.50		mg/L	5	5/11/2018 1:33:48 PM	R5122C
Chloride	0.56	0.15	2.5	J	mg/L	5	5/11/2018 1:33:48 PM	R5122C
Bromide	ND	0.13	0.50		mg/L	5	5/11/2018 1:33:48 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 1:33:48 PM	R5122C
Sulfate	ND	1.0	2.5		mg/L	5	5/11/2018 1:33:48 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 3:36:56 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	ND	0.00099	0.0020		mg/L	1	5/18/2018 11:17:16 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:17:16 AM	A51375
Calcium	ND	0.078	1.0		mg/L	1	5/18/2018 11:17:16 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:17:16 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:17:16 AM	A51375
Iron	ND	0.016	0.020		mg/L	1	5/18/2018 11:17:16 AM	A51375
Magnesium	ND	0.25	1.0		mg/L	1	5/18/2018 11:17:16 AM	A51375
Manganese	ND	0.00039	0.0020		mg/L	1	5/18/2018 11:17:16 AM	A51375
Potassium	ND	0.11	1.0		mg/L	1	5/18/2018 11:17:16 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:17:16 AM	A51375
Sodium	ND	0.16	1.0		mg/L	1	5/23/2018 2:20:44 PM	B51452
Zinc	0.0077	0.0021	0.010	J	mg/L	1	5/18/2018 11:17:16 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	ND	0.0010	0.0020		mg/L	1	5/31/2018 8:42:43 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:42:43 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 8:42:43 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:42:43 PM	37927
Iron	ND	0.010	0.020		mg/L	1	6/5/2018 2:46:38 PM	37927
Manganese	ND	0.0011	0.0020		mg/L	1	5/31/2018 8:42:43 PM	37927
Silver	ND	0.0012	0.0050		mg/L	1	5/31/2018 8:42:43 PM	37927
Zinc	ND	0.0033	0.010		mg/L	1	5/31/2018 8:42:43 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	ND	0.00042	0.0010		mg/L	1	5/3/2018 3:05:30 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: FB02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 2:30:00 PM

Lab ID: 1805106-004

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS						Analyst: DBK		
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 3:05:30 PM	B51024
Selenium	0.0060	0.00076	0.0010		mg/L	1	5/3/2018 3:05:30 PM	B51024
Uranium	ND	0.000096	0.00050		mg/L	1	5/14/2018 5:55:38 PM	B51261
200.8 ICPMS METALS:TOTAL						Analyst: ELS		
Arsenic	ND	0.00041	0.0010		mg/L	1	5/8/2018 12:21:50 PM	37927
Lead	ND	0.00023	0.00050		mg/L	1	5/8/2018 12:21:50 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:21:50 PM	37927
Uranium	ND	0.000068	0.00050		mg/L	1	5/8/2018 12:21:50 PM	37927
EPA METHOD 245.1: MERCURY						Analyst: rde		
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 5:50:58 PM	37992
EPA METHOD 8260B: VOLATILES						Analyst: DJF		
Benzene	ND	0.062	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Toluene	0.078	0.064	1.0	J	µg/L	1	5/10/2018 2:27:40 PM	W5119
Ethylbenzene	ND	0.093	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Methyl tert-butyl ether (MTBE)	ND	0.24	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2,4-Trimethylbenzene	0.16	0.11	1.0	J	µg/L	1	5/10/2018 2:27:40 PM	W5119
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Naphthalene	ND	0.11	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1-Methylnaphthalene	ND	0.16	4.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
2-Methylnaphthalene	ND	0.15	4.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Acetone	1.4	0.82	10	J	µg/L	1	5/10/2018 2:27:40 PM	W5119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 2:27:40 PM	W5119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 2:27:40 PM	W5119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 10 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**Date Reported: **6/7/2018****CLIENT:** Andeavor Gallup**Client Sample ID:** FB02**Project:** 2nd Quarter 2018 Groundwater Sampling**Collection Date:** 4/30/2018 2:30:00 PM**Lab ID:** 1805106-004**Matrix:** AQUEOUS**Received Date:** 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 2:27:40 PM	W5119
Isopropylbenzene	ND	0.051	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 2:27:40 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
n-Butylbenzene	ND	0.13	3.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
n-Propylbenzene	ND	0.074	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
sec-Butylbenzene	ND	0.11	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 2:27:40 PM	W5119
Xylenes, Total	ND	0.32	1.5		µg/L	1	5/10/2018 2:27:40 PM	W5119
Surr: 1,2-Dichloroethane-d4	92.9	0	70-130		%Rec	1	5/10/2018 2:27:40 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 11 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: FB02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 2:30:00 PM

Lab ID: 1805106-004

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
Surr: 4-Bromofluorobenzene	115	0	70-130		%Rec	1	5/10/2018 2:27:40 PM	W5119
Surr: Dibromofluoromethane	94.4	0	70-130		%Rec	1	5/10/2018 2:27:40 PM	W5119
Surr: Toluene-d8	96.7	0	70-130		%Rec	1	5/10/2018 2:27:40 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-2

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:10:00 PM

Lab ID: 1805106-005

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	1.9	0.63	1.0		mg/L	1	5/3/2018 9:43:51 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 9:43:51 PM	37932
Surr: DNOP	115	0	76.7-135		%Rec	1	5/3/2018 9:43:51 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	0.59	0.021	0.050		mg/L	1	5/5/2018 3:43:01 AM	G51045
Surr: BFB	180	0	69.3-150	S	%Rec	1	5/5/2018 3:43:01 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	1.6	0.15	0.50		mg/L	5	5/11/2018 1:58:37 PM	R5122C
Chloride	220	0.59	10		mg/L	20	5/11/2018 2:11:02 PM	R5122C
Bromide	1.0	0.13	0.50		mg/L	5	5/11/2018 1:58:37 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 1:58:37 PM	R5122C
Sulfate	3.6	1.0	2.5		mg/L	5	5/11/2018 1:58:37 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 3:49:20 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	1.6	0.0049	0.010		mg/L	5	5/18/2018 1:05:45 PM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:25:48 AM	A51375
Calcium	66	0.078	1.0		mg/L	1	5/18/2018 11:25:48 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:25:48 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:25:48 AM	A51375
Iron	1.8	0.082	0.10	*	mg/L	5	5/18/2018 1:05:45 PM	A51375
Magnesium	13	0.25	1.0		mg/L	1	5/18/2018 11:25:48 AM	A51375
Manganese	0.91	0.00039	0.0020	*	mg/L	1	5/18/2018 11:25:48 AM	A51375
Potassium	0.27	0.11	1.0	J	mg/L	1	5/18/2018 11:25:48 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:25:48 AM	A51375
Sodium	360	0.82	5.0		mg/L	5	5/23/2018 2:22:51 PM	B51452
Zinc	0.0054	0.0021	0.010	J	mg/L	1	5/18/2018 11:25:48 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	2.2	0.0050	0.010	*	mg/L	5	6/5/2018 2:48:50 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:44:53 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 8:44:53 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:44:53 PM	37927
Iron	3.7	0.051	0.10	*	mg/L	5	6/5/2018 2:48:50 PM	37927
Manganese	0.94	0.0011	0.0020	*	mg/L	1	5/31/2018 8:44:53 PM	37927
Silver	0.0013	0.0012	0.0050	J	mg/L	1	5/31/2018 8:44:53 PM	37927
Zinc	0.0064	0.0033	0.010	J	mg/L	1	5/31/2018 8:44:53 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	0.0045	0.00042	0.0010		mg/L	1	5/3/2018 3:07:49 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 13 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-2

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:10:00 PM

Lab ID: 1805106-005

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS						Analyst: DBK		
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 3:07:49 PM	B51024
Selenium	0.0049	0.00076	0.0010		mg/L	1	5/3/2018 3:07:49 PM	B51024
Uranium	0.00016	0.000096	0.00050	J	mg/L	1	5/14/2018 5:58:39 PM	B51261
200.8 ICPMS METALS:TOTAL						Analyst: ELS		
Arsenic	0.0047	0.00041	0.0010		mg/L	1	5/8/2018 12:24:06 PM	37927
Lead	0.0012	0.00023	0.00050		mg/L	1	5/8/2018 12:24:06 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:24:06 PM	37927
Uranium	0.00029	0.000068	0.00050	J	mg/L	1	5/8/2018 12:24:06 PM	37927
EPA METHOD 245.1: MERCURY						Analyst: rde		
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 5:53:11 PM	37992
EPA METHOD 8260B: VOLATILES						Analyst: DJF		
Benzene	32	0.062	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Toluene	2.3	0.064	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Ethylbenzene	35	0.093	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Methyl tert-butyl ether (MTBE)	99	0.24	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
1,2,4-Trimethylbenzene	0.84	0.11	1.0	J	µg/L	1	5/10/2018 3:26:39 PM	W51119
1,3,5-Trimethylbenzene	0.20	0.087	1.0	J	µg/L	1	5/10/2018 3:26:39 PM	W51119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Naphthalene	7.8	0.11	2.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
1-Methylnaphthalene	11	0.16	4.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
2-Methylnaphthalene	1.7	0.15	4.0	J	µg/L	1	5/10/2018 3:26:39 PM	W51119
Acetone	9.7	0.82	10	J	µg/L	1	5/10/2018 3:26:39 PM	W51119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 3:26:39 PM	W51119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 3:26:39 PM	W51119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 3:26:39 PM	W51119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 14 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-2

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:10:00 PM

Lab ID: 1805106-005

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1-Dichloroethane	0.52	0.40	1.0	J	µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 3:26:39 PM	W5119
Isopropylbenzene	3.7	0.051	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 3:26:39 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
n-Butylbenzene	0.59	0.13	3.0	J	µg/L	1	5/10/2018 3:26:39 PM	W5119
n-Propylbenzene	3.7	0.074	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
sec-Butylbenzene	1.2	0.11	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
tert-Butylbenzene	0.25	0.10	1.0	J	µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 3:26:39 PM	W5119
Xylenes, Total	0.61	0.32	1.5	J	µg/L	1	5/10/2018 3:26:39 PM	W5119
Surr: 1,2-Dichloroethane-d4	94.4	0	70-130		%Rec	1	5/10/2018 3:26:39 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 15 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-2

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:10:00 PM

Lab ID: 1805106-005

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
Surr: 4-Bromofluorobenzene	108	0	70-130		%Rec	1	5/10/2018 3:26:39 PM	W5119
Surr: Dibromofluoromethane	94.6	0	70-130		%Rec	1	5/10/2018 3:26:39 PM	W5119
Surr: Toluene-d8	96.5	0	70-130		%Rec	1	5/10/2018 3:26:39 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: KA-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:40:00 PM

Lab ID: 1805106-006

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	0.65	0.63	1.0	J	mg/L	1	5/3/2018 10:06:04 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 10:06:04 PM	37932
Surr: DNOP	117	0	76.7-135		%Rec	1	5/3/2018 10:06:04 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	2.9	0.021	0.050		mg/L	1	5/5/2018 4:29:42 AM	G51045
Surr: BFB	167	0	69.3-150	S	%Rec	1	5/5/2018 4:29:42 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	0.79	0.15	0.50		mg/L	5	5/11/2018 2:48:16 PM	R5122C
Chloride	170	0.59	10		mg/L	20	5/11/2018 3:00:40 PM	R5122C
Bromide	1.4	0.13	0.50		mg/L	5	5/11/2018 2:48:16 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 2:48:16 PM	R5122C
Sulfate	18	1.0	2.5		mg/L	5	5/11/2018 2:48:16 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 4:01:44 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	1.2	0.0049	0.010		mg/L	5	5/18/2018 1:07:56 PM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:27:49 AM	A51375
Calcium	83	0.078	1.0		mg/L	1	5/18/2018 11:27:49 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:27:49 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:27:49 AM	A51375
Iron	0.046	0.016	0.020		mg/L	1	5/18/2018 11:27:49 AM	A51375
Magnesium	13	0.25	1.0		mg/L	1	5/18/2018 11:27:49 AM	A51375
Manganese	1.2	0.0020	0.010	*	mg/L	5	5/18/2018 1:07:56 PM	A51375
Potassium	0.36	0.11	1.0	J	mg/L	1	5/18/2018 11:27:49 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:27:49 AM	A51375
Sodium	300	0.82	5.0		mg/L	5	5/23/2018 2:25:04 PM	B51452
Zinc	0.0070	0.0021	0.010	J	mg/L	1	5/18/2018 11:27:49 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	1.3	0.0050	0.010		mg/L	5	5/31/2018 9:03:46 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:53:23 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 8:53:23 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:53:23 PM	37927
Iron	0.23	0.010	0.020		mg/L	1	6/5/2018 2:51:05 PM	37927
Manganese	1.2	0.0055	0.010	*	mg/L	5	5/31/2018 9:03:46 PM	37927
Silver	0.0019	0.0012	0.0050	J	mg/L	1	5/31/2018 8:53:23 PM	37927
Zinc	ND	0.0033	0.010		mg/L	1	5/31/2018 8:53:23 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	0.0022	0.00042	0.0010		mg/L	1	5/3/2018 3:10:07 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 17 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: KA-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:40:00 PM

Lab ID: 1805106-006

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								
						Analyst: DBK		
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 3:10:07 PM	B51024
Selenium	0.0036	0.00076	0.0010		mg/L	1	5/3/2018 3:10:07 PM	B51024
Uranium	0.0086	0.000096	0.00050		mg/L	1	5/14/2018 6:07:46 PM	B51261
200.8 ICPMS METALS:TOTAL								
						Analyst: ELS		
Arsenic	0.0025	0.00041	0.0010		mg/L	1	5/8/2018 12:26:23 PM	37927
Lead	0.00054	0.00023	0.00050		mg/L	1	5/8/2018 12:26:23 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:26:23 PM	37927
Uranium	0.0089	0.000068	0.00050		mg/L	1	5/8/2018 12:26:23 PM	37927
EPA METHOD 245.1: MERCURY								
						Analyst: rde		
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 5:55:24 PM	37992
EPA METHOD 8260B: VOLATILES								
						Analyst: RAA		
Benzene	590	0.62	10		µg/L	10	5/11/2018 8:03:00 PM	R51242
Toluene	510	0.64	10		µg/L	10	5/11/2018 8:03:00 PM	R51242
Ethylbenzene	54	0.093	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Methyl tert-butyl ether (MTBE)	32	0.24	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
1,2,4-Trimethylbenzene	11	0.11	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
1,3,5-Trimethylbenzene	3.1	0.087	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Naphthalene	8.2	0.11	2.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
1-Methylnaphthalene	3.5	0.16	4.0	J	µg/L	1	5/10/2018 3:56:09 PM	W51119
2-Methylnaphthalene	1.3	0.15	4.0	J	µg/L	1	5/10/2018 3:56:09 PM	W51119
Acetone	5.9	0.82	10	J	µg/L	1	5/10/2018 3:56:09 PM	W51119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 3:56:09 PM	W51119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 3:56:09 PM	W51119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 3:56:09 PM	W51119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 18 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: KA-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:40:00 PM

Lab ID: 1805106-006

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 3:56:09 PM	W5119
Isopropylbenzene	4.4	0.051	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
4-Isopropyltoluene	0.14	0.096	1.0	J	µg/L	1	5/10/2018 3:56:09 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 3:56:09 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
n-Butylbenzene	0.30	0.13	3.0	J	µg/L	1	5/10/2018 3:56:09 PM	W5119
n-Propylbenzene	3.2	0.074	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
sec-Butylbenzene	0.49	0.11	1.0	J	µg/L	1	5/10/2018 3:56:09 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
tert-Butylbenzene	0.16	0.10	1.0	J	µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 3:56:09 PM	W5119
Xylenes, Total	58	0.32	1.5		µg/L	1	5/10/2018 3:56:09 PM	W5119
Surr: 1,2-Dichloroethane-d4	95.2	0	70-130		%Rec	1	5/10/2018 3:56:09 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 19 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: KA-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 3:40:00 PM

Lab ID: 1805106-006

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Surr: 4-Bromofluorobenzene	115	0	70-130		%Rec	1	5/10/2018 3:56:09 PM	W5119
Surr: Dibromofluoromethane	97.4	0	70-130		%Rec	1	5/10/2018 3:56:09 PM	W5119
Surr: Toluene-d8	97.3	0	70-130		%Rec	1	5/10/2018 3:56:09 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:05:00 PM

Lab ID: 1805106-007

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								
							Analyst: TOM	
Diesel Range Organics (DRO)	ND	0.63	1.0		mg/L	1	5/3/2018 10:28:03 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 10:28:03 PM	37932
Surr: DNOP	113	0	76.7-135		%Rec	1	5/3/2018 10:28:03 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								
							Analyst: NSB	
Gasoline Range Organics (GRO)	0.80	0.021	0.050		mg/L	1	5/5/2018 4:53:02 AM	G51045
Surr: BFB	114	0	69.3-150		%Rec	1	5/5/2018 4:53:02 AM	G51045
EPA METHOD 300.0: ANIONS								
							Analyst: MRA	
Fluoride	0.62	0.15	0.50		mg/L	5	5/11/2018 3:13:04 PM	R5122C
Chloride	190	0.59	10		mg/L	20	5/11/2018 3:25:29 PM	R5122C
Bromide	1.4	0.13	0.50		mg/L	5	5/11/2018 3:13:04 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 3:13:04 PM	R5122C
Sulfate	47	1.0	2.5		mg/L	5	5/11/2018 3:13:04 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 4:14:09 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								
							Analyst: pmf	
Barium	0.093	0.00099	0.0020		mg/L	1	5/18/2018 11:29:56 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:29:56 AM	A51375
Calcium	14	0.078	1.0		mg/L	1	5/18/2018 11:29:56 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:29:56 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:29:56 AM	A51375
Iron	0.040	0.016	0.020		mg/L	1	5/18/2018 11:29:56 AM	A51375
Magnesium	2.6	0.25	1.0		mg/L	1	5/18/2018 11:29:56 AM	A51375
Manganese	0.14	0.00039	0.0020	*	mg/L	1	5/18/2018 11:29:56 AM	A51375
Potassium	1.6	0.11	1.0		mg/L	1	5/18/2018 11:29:56 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:29:56 AM	A51375
Sodium	500	0.82	5.0		mg/L	5	5/23/2018 2:33:35 PM	B51452
Zinc	0.0077	0.0021	0.010	J	mg/L	1	5/18/2018 11:29:56 AM	A51375
EPA METHOD 200.7: TOTAL METALS								
							Analyst: pmf	
Barium	0.090	0.0010	0.0020		mg/L	1	5/31/2018 8:55:37 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:55:37 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 8:55:37 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:55:37 PM	37927
Iron	0.074	0.010	0.020		mg/L	1	6/5/2018 2:53:15 PM	37927
Manganese	0.15	0.0011	0.0020	*	mg/L	1	5/31/2018 8:55:37 PM	37927
Silver	ND	0.0012	0.0050		mg/L	1	5/31/2018 8:55:37 PM	37927
Zinc	0.0053	0.0033	0.010	J	mg/L	1	5/31/2018 8:55:37 PM	37927
EPA 200.8: DISSOLVED METALS								
							Analyst: DBK	
Arsenic	0.0012	0.00042	0.0010		mg/L	1	5/3/2018 3:12:25 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:05:00 PM

Lab ID: 1805106-007

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 3:12:25 PM	B51024
Selenium	0.0029	0.00076	0.0010		mg/L	1	5/3/2018 3:12:25 PM	B51024
Uranium	0.022	0.000096	0.00050		mg/L	1	5/14/2018 6:10:47 PM	B51261
200.8 ICPMS METALS:TOTAL								Analyst: ELS
Arsenic	0.0012	0.00041	0.0010		mg/L	1	5/8/2018 12:28:39 PM	37927
Lead	ND	0.00023	0.00050		mg/L	1	5/8/2018 12:28:39 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:28:39 PM	37927
Uranium	0.023	0.000068	0.00050		mg/L	1	5/8/2018 12:28:39 PM	37927
EPA METHOD 245.1: MERCURY								Analyst: rde
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 6:02:15 PM	37992
EPA METHOD 8260B: VOLATILES								Analyst: RAA
Benzene	290	0.62	10		µg/L	10	5/11/2018 8:27:00 PM	R51242
Toluene	6.6	0.064	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Ethylbenzene	8.3	0.093	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Methyl tert-butyl ether (MTBE)	32	0.24	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
1,2,4-Trimethylbenzene	1.9	0.11	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
1,3,5-Trimethylbenzene	0.68	0.087	1.0	J	µg/L	1	5/10/2018 4:25:37 PM	W51119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Naphthalene	0.46	0.11	2.0	J	µg/L	1	5/10/2018 4:25:37 PM	W51119
1-Methylnaphthalene	0.51	0.16	4.0	J	µg/L	1	5/10/2018 4:25:37 PM	W51119
2-Methylnaphthalene	ND	0.15	4.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Acetone	3.2	0.82	10	J	µg/L	1	5/10/2018 4:25:37 PM	W51119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 4:25:37 PM	W51119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 4:25:37 PM	W51119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 4:25:37 PM	W51119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 22 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:05:00 PM

Lab ID: 1805106-007

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 4:25:37 PM	W5119
Isopropylbenzene	0.78	0.051	1.0	J	µg/L	1	5/10/2018 4:25:37 PM	W5119
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 4:25:37 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
n-Butylbenzene	ND	0.13	3.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
n-Propylbenzene	0.37	0.074	1.0	J	µg/L	1	5/10/2018 4:25:37 PM	W5119
sec-Butylbenzene	0.21	0.11	1.0	J	µg/L	1	5/10/2018 4:25:37 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 4:25:37 PM	W5119
Xylenes, Total	13	0.32	1.5		µg/L	1	5/10/2018 4:25:37 PM	W5119
Surr: 1,2-Dichloroethane-d4	92.2	0	70-130		%Rec	1	5/10/2018 4:25:37 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 23 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: NAPIS-3

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:05:00 PM

Lab ID: 1805106-007

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Surr: 4-Bromofluorobenzene	116	0	70-130		%Rec	1	5/10/2018 4:25:37 PM	W5119
Surr: Dibromofluoromethane	96.5	0	70-130		%Rec	1	5/10/2018 4:25:37 PM	W5119
Surr: Toluene-d8	95.8	0	70-130		%Rec	1	5/10/2018 4:25:37 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: OAPIS-1

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:50:00 PM

Lab ID: 1805106-008

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	8.9	0.63	1.0		mg/L	1	5/3/2018 10:50:06 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 10:50:06 PM	37932
Surr: DNOP	118	0	76.7-135		%Rec	1	5/3/2018 10:50:06 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	0.46	0.021	0.050		mg/L	1	5/5/2018 5:16:25 AM	G51045
Surr: BFB	183	0	69.3-150	S	%Rec	1	5/5/2018 5:16:25 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	1.4	0.15	0.50		mg/L	5	5/11/2018 3:37:53 PM	R5122C
Chloride	1500	5.9	100		mg/L	200	5/14/2018 5:16:13 PM	R5127C
Bromide	4.2	0.13	0.50		mg/L	5	5/11/2018 3:37:53 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 3:37:53 PM	R5122C
Sulfate	12	1.0	2.5		mg/L	5	5/11/2018 3:37:53 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 4:26:34 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	0.93	0.00099	0.0020		mg/L	1	5/18/2018 11:32:03 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:32:03 AM	A51375
Calcium	150	0.39	5.0		mg/L	5	5/18/2018 1:18:33 PM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:32:03 AM	A51375
Copper	0.0038	0.0032	0.0060	J	mg/L	1	5/18/2018 11:32:03 AM	A51375
Iron	0.98	0.082	0.10	*	mg/L	5	5/18/2018 1:18:33 PM	A51375
Magnesium	30	0.25	1.0		mg/L	1	5/18/2018 11:32:03 AM	A51375
Manganese	1.1	0.0020	0.010	*	mg/L	5	5/18/2018 1:18:33 PM	A51375
Potassium	3.7	0.11	1.0		mg/L	1	5/18/2018 11:32:03 AM	A51375
Silver	0.0020	0.0018	0.0050	J	mg/L	1	5/18/2018 11:32:03 AM	A51375
Sodium	1200	3.3	20		mg/L	20	5/22/2018 9:45:56 PM	A51451
Zinc	0.019	0.0021	0.010		mg/L	1	5/18/2018 11:32:03 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	1.2	0.0050	0.010		mg/L	5	5/31/2018 9:05:47 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:57:45 PM	37927
Chromium	0.0086	0.0018	0.0060		mg/L	1	5/31/2018 8:57:45 PM	37927
Copper	0.034	0.0041	0.0060		mg/L	1	5/31/2018 8:57:45 PM	37927
Iron	7.5	0.10	0.20	*	mg/L	10	6/5/2018 2:55:20 PM	37927
Manganese	1.3	0.0055	0.010	*	mg/L	5	5/31/2018 9:05:47 PM	37927
Silver	0.0026	0.0012	0.0050	J	mg/L	1	5/31/2018 8:57:45 PM	37927
Zinc	0.053	0.0033	0.010		mg/L	1	5/31/2018 8:57:45 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	0.0091	0.0021	0.0050		mg/L	5	5/16/2018 3:11:06 PM	A51316

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 25 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: OAPIS-1

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:50:00 PM

Lab ID: 1805106-008

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								
							Analyst: DBK	
Lead	0.0043	0.00087	0.0025		mg/L	5	5/16/2018 3:11:06 PM	A51316
Selenium	ND	0.0038	0.0050		mg/L	5	5/16/2018 3:11:06 PM	A51316
Uranium	0.047	0.00048	0.0025	*	mg/L	5	5/16/2018 3:11:06 PM	A51316
200.8 ICPMS METALS:TOTAL								
							Analyst: ELS	
Arsenic	0.011	0.0021	0.0050	*	mg/L	5	5/8/2018 12:30:56 PM	37927
Lead	0.013	0.0011	0.0025		mg/L	5	5/8/2018 12:30:56 PM	37927
Selenium	ND	0.0049	0.0050		mg/L	5	5/8/2018 12:30:56 PM	37927
Uranium	0.046	0.00034	0.0025	*	mg/L	5	5/8/2018 12:30:56 PM	37927
EPA METHOD 245.1: MERCURY								
							Analyst: rde	
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 6:04:28 PM	37992
EPA METHOD 8270C: SEMIVOLATILES								
							Analyst: DAM	
Acenaphthene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Acenaphthylene	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Aniline	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Anthracene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Azobenzene	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benz(a)anthracene	ND	26	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzo(a)pyrene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzo(b)fluoranthene	ND	36	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzo(g,h,i)perylene	ND	28	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzo(k)fluoranthene	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzoic acid	92	32	100	JD	µg/L	1	5/10/2018 3:07:21 PM	37947
Benzyl alcohol	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Bis(2-chloroethoxy)methane	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Bis(2-chloroethyl)ether	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Bis(2-chloroisopropyl)ether	ND	24	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Bis(2-ethylhexyl)phthalate	ND	40	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Bromophenyl phenyl ether	ND	35	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Butyl benzyl phthalate	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Carbazole	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Chloro-3-methylphenol	ND	28	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Chloroaniline	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Chloronaphthalene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Chlorophenol	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Chlorophenyl phenyl ether	ND	36	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Chrysene	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Di-n-butyl phthalate	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Di-n-octyl phthalate	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 26 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: OAPIS-1

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:50:00 PM

Lab ID: 1805106-008

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8270C: SEMIVOLATILES							Analyst: DAM	
Dibenz(a,h)anthracene	ND	28	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Dibenzofuran	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
1,2-Dichlorobenzene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
1,3-Dichlorobenzene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
1,4-Dichlorobenzene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
3,3'-Dichlorobenzidine	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Diethyl phthalate	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Dimethyl phthalate	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4-Dichlorophenol	ND	29	100	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4-Dimethylphenol	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4,6-Dinitro-2-methylphenol	ND	27	100	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4-Dinitrophenol	ND	19	100	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4-Dinitrotoluene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,6-Dinitrotoluene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Fluoranthene	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Fluorene	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Hexachlorobenzene	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Hexachlorobutadiene	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Hexachlorocyclopentadiene	ND	20	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Hexachloroethane	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Indeno(1,2,3-cd)pyrene	ND	35	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Isophorone	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
1-Methylnaphthalene	ND	35	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Methylnaphthalene	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Methylphenol	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
3+4-Methylphenol	ND	27	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
N-Nitrosodi-n-propylamine	ND	31	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
N-Nitrosodimethylamine	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
N-Nitrosodiphenylamine	ND	33	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Naphthalene	ND	25	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Nitroaniline	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
3-Nitroaniline	ND	34	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Nitroaniline	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Nitrobenzene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2-Nitrophenol	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
4-Nitrophenol	ND	28	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Pentachlorophenol	ND	26	100	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Phenanthrene	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Phenol	ND	30	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 27 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**Date Reported: **6/7/2018****CLIENT:** Andeavor Gallup**Client Sample ID:** OAPIS-1**Project:** 2nd Quarter 2018 Groundwater Sampling**Collection Date:** 4/30/2018 4:50:00 PM**Lab ID:** 1805106-008**Matrix:** AQUEOUS**Received Date:** 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8270C: SEMIVOLATILES							Analyst: DAM	
Pyrene	ND	33	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Pyridine	ND	27	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
1,2,4-Trichlorobenzene	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4,5-Trichlorophenol	ND	29	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
2,4,6-Trichlorophenol	ND	32	50	D	µg/L	1	5/10/2018 3:07:21 PM	37947
Surr: 2-Fluorophenol	40.5	0	15-114	D	%Rec	1	5/10/2018 3:07:21 PM	37947
Surr: Phenol-d5	32.7	0	15-97.9	D	%Rec	1	5/10/2018 3:07:21 PM	37947
Surr: 2,4,6-Tribromophenol	88.4	0	15-161	D	%Rec	1	5/10/2018 3:07:21 PM	37947
Surr: Nitrobenzene-d5	64.3	0	29.3-120	D	%Rec	1	5/10/2018 3:07:21 PM	37947
Surr: 2-Fluorobiphenyl	82.1	0	17.5-116	D	%Rec	1	5/10/2018 3:07:21 PM	37947
Surr: 4-Terphenyl-d14	66.2	0	21-92.2	D	%Rec	1	5/10/2018 3:07:21 PM	37947
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Benzene	68	0.062	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Toluene	0.66	0.064	1.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
Ethylbenzene	6.3	0.093	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Methyl tert-butyl ether (MTBE)	260	2.4	10		µg/L	10	5/14/2018 4:08:00 PM	R51274
1,2,4-Trimethylbenzene	1.6	0.11	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Naphthalene	0.74	0.11	2.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
1-Methylnaphthalene	4.7	0.16	4.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
2-Methylnaphthalene	0.36	0.15	4.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
Acetone	56	0.82	10		µg/L	1	5/11/2018 8:51:00 PM	R51242
Bromobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Bromoform	ND	0.21	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Bromomethane	ND	0.26	3.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
2-Butanone	4.4	1.1	10	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
Carbon disulfide	ND	0.40	10		µg/L	1	5/11/2018 8:51:00 PM	R51242
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Chloroethane	ND	0.23	2.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Chloroform	ND	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Chloromethane	ND	0.29	3.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 28 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: OAPIS-1

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:50:00 PM

Lab ID: 1805106-008

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Dibromomethane	ND	0.091	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1-Dichloroethane	1.1	0.40	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
2-Hexanone	ND	0.66	10		µg/L	1	5/11/2018 8:51:00 PM	R51242
Isopropylbenzene	0.73	0.051	1.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
4-Isopropyltoluene	0.33	0.096	1.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/11/2018 8:51:00 PM	R51242
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
n-Butylbenzene	0.21	0.13	3.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
n-Propylbenzene	0.76	0.074	1.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
sec-Butylbenzene	0.18	0.11	1.0	J	µg/L	1	5/11/2018 8:51:00 PM	R51242
Styrene	ND	0.16	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/11/2018 8:51:00 PM	R51242
Xylenes, Total	3.2	0.32	1.5		µg/L	1	5/11/2018 8:51:00 PM	R51242
Surr: 1,2-Dichloroethane-d4	103	0	70-130		%Rec	1	5/11/2018 8:51:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 29 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: OAPIS-1

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 4:50:00 PM

Lab ID: 1805106-008

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Surr: 4-Bromofluorobenzene	112	0	70-130		%Rec	1	5/11/2018 8:51:00 PM	R51242
Surr: Dibromofluoromethane	108	0	70-130		%Rec	1	5/11/2018 8:51:00 PM	R51242
Surr: Toluene-d8	113	0	70-130		%Rec	1	5/11/2018 8:51:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: STP-1-NW

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 5:20:00 PM

Lab ID: 1805106-009

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	ND	0.63	1.0		mg/L	1	5/3/2018 11:12:16 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 11:12:16 PM	37932
Surr: DNOP	121	0	76.7-135		%Rec	1	5/3/2018 11:12:16 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	ND	0.021	0.050		mg/L	1	5/5/2018 7:36:35 AM	G51045
Surr: BFB	90.1	0	69.3-150		%Rec	1	5/5/2018 7:36:35 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	ND	0.15	0.50		mg/L	5	5/11/2018 4:02:42 PM	R5122C
Chloride	2100	5.9	100		mg/L	200	5/21/2018 11:57:28 AM	R51421
Bromide	3.6	0.13	0.50		mg/L	5	5/11/2018 4:02:42 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 4:02:42 PM	R5122C
Sulfate	150	1.0	2.5		mg/L	5	5/11/2018 4:02:42 PM	R5122C
Nitrate+Nitrite as N	24	0.55	2.0	*	mg/L	10	5/21/2018 12:34:41 PM	R51421
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	0.10	0.00099	0.0020		mg/L	1	5/18/2018 11:34:15 AM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:34:15 AM	A51375
Calcium	73	0.078	1.0		mg/L	1	5/18/2018 11:34:15 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:34:15 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:34:15 AM	A51375
Iron	0.032	0.016	0.020		mg/L	1	5/18/2018 11:34:15 AM	A51375
Magnesium	10	0.25	1.0		mg/L	1	5/18/2018 11:34:15 AM	A51375
Manganese	ND	0.00039	0.0020		mg/L	1	5/18/2018 11:34:15 AM	A51375
Potassium	4.6	0.11	1.0		mg/L	1	5/18/2018 11:34:15 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:34:15 AM	A51375
Sodium	1400	3.3	20		mg/L	20	5/24/2018 7:55:47 PM	A51516
Zinc	0.0066	0.0021	0.010	J	mg/L	1	5/18/2018 11:34:15 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	0.11	0.0010	0.0020		mg/L	1	5/31/2018 8:59:46 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 8:59:46 PM	37927
Chromium	0.0030	0.0018	0.0060	J	mg/L	1	5/31/2018 8:59:46 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 8:59:46 PM	37927
Iron	0.51	0.010	0.020	*	mg/L	1	6/5/2018 2:57:30 PM	37927
Manganese	0.0087	0.0011	0.0020		mg/L	1	5/31/2018 8:59:46 PM	37927
Silver	0.0018	0.0012	0.0050	J	mg/L	1	5/31/2018 8:59:46 PM	37927
Zinc	0.0084	0.0033	0.010	J	mg/L	1	5/31/2018 8:59:46 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	0.0031	0.0021	0.0050	J	mg/L	5	5/3/2018 3:46:33 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 31 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: STP-1-NW

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 5:20:00 PM

Lab ID: 1805106-009

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								
						Analyst: DBK		
Lead	ND	0.00087	0.0025		mg/L	5	5/3/2018 3:46:33 PM	B51024
Selenium	0.0065	0.0038	0.0050		mg/L	5	5/16/2018 3:13:29 PM	A51316
Uranium	0.030	0.00048	0.0025	*	mg/L	5	5/16/2018 3:13:29 PM	A51316
200.8 ICPMS METALS:TOTAL								
						Analyst: ELS		
Arsenic	0.0035	0.0021	0.0050	J	mg/L	5	5/8/2018 12:43:57 PM	37927
Lead	ND	0.0011	0.0025		mg/L	5	5/8/2018 12:43:57 PM	37927
Selenium	0.0063	0.0049	0.0050		mg/L	5	5/8/2018 12:43:57 PM	37927
Uranium	0.029	0.00034	0.0025		mg/L	5	5/8/2018 12:43:57 PM	37927
EPA METHOD 245.1: MERCURY								
						Analyst: rde		
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 6:06:42 PM	37992
EPA METHOD 8260B: VOLATILES								
						Analyst: RAA		
Benzene	ND	0.062	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Toluene	0.32	0.064	1.0	J	µg/L	1	5/11/2018 9:15:00 PM	R51242
Ethylbenzene	ND	0.093	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Methyl tert-butyl ether (MTBE)	ND	0.24	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2,4-Trimethylbenzene	0.17	0.11	1.0	J	µg/L	1	5/11/2018 9:15:00 PM	R51242
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Naphthalene	ND	0.11	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1-Methylnaphthalene	ND	0.16	4.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
2-Methylnaphthalene	ND	0.15	4.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Acetone	ND	0.82	10		µg/L	1	5/11/2018 9:15:00 PM	R51242
Bromobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Bromoform	ND	0.21	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Bromomethane	ND	0.26	3.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
2-Butanone	ND	1.1	10		µg/L	1	5/11/2018 9:15:00 PM	R51242
Carbon disulfide	ND	0.40	10		µg/L	1	5/11/2018 9:15:00 PM	R51242
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Chloroethane	ND	0.23	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Chloroform	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Chloromethane	ND	0.29	3.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 32 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

Hall Environmental Analysis Laboratory, Inc.

CLIENT: Andeavor Gallup

Client Sample ID: STP-1-NW

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 5:20:00 PM

Lab ID: 1805106-009

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Dibromomethane	ND	0.091	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
2-Hexanone	ND	0.66	10		µg/L	1	5/11/2018 9:15:00 PM	R51242
Isopropylbenzene	ND	0.051	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/11/2018 9:15:00 PM	R51242
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
n-Butylbenzene	ND	0.13	3.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
n-Propylbenzene	ND	0.074	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
sec-Butylbenzene	ND	0.11	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Styrene	ND	0.16	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/11/2018 9:15:00 PM	R51242
Xylenes, Total	0.54	0.32	1.5	J	µg/L	1	5/11/2018 9:15:00 PM	R51242
Surr: 1,2-Dichloroethane-d4	106	0	70-130		%Rec	1	5/11/2018 9:15:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 33 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: STP-1-NW

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018 5:20:00 PM

Lab ID: 1805106-009

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Surr: 4-Bromofluorobenzene	111	0	70-130		%Rec	1	5/11/2018 9:15:00 PM	R51242
Surr: Dibromofluoromethane	110	0	70-130		%Rec	1	5/11/2018 9:15:00 PM	R51242
Surr: Toluene-d8	111	0	70-130		%Rec	1	5/11/2018 9:15:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: DUP02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018

Lab ID: 1805106-010

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015M/D: DIESEL RANGE								Analyst: TOM
Diesel Range Organics (DRO)	1.8	0.63	1.0		mg/L	1	5/3/2018 11:34:22 PM	37932
Motor Oil Range Organics (MRO)	ND	5.0	5.0		mg/L	1	5/3/2018 11:34:22 PM	37932
Surr: DNOP	121	0	76.7-135		%Rec	1	5/3/2018 11:34:22 PM	37932
EPA METHOD 8015D: GASOLINE RANGE								Analyst: NSB
Gasoline Range Organics (GRO)	0.61	0.021	0.050		mg/L	1	5/5/2018 7:59:53 AM	G51045
Surr: BFB	182	0	69.3-150	S	%Rec	1	5/5/2018 7:59:53 AM	G51045
EPA METHOD 300.0: ANIONS								Analyst: MRA
Fluoride	1.6	0.15	0.50		mg/L	5	5/11/2018 4:27:31 PM	R5122C
Chloride	210	0.59	10		mg/L	20	5/11/2018 4:39:55 PM	R5122C
Bromide	1.0	0.13	0.50		mg/L	5	5/11/2018 4:27:31 PM	R5122C
Phosphorus, Orthophosphate (As P)	ND	0.46	2.5	H	mg/L	5	5/11/2018 4:27:31 PM	R5122C
Sulfate	3.9	1.0	2.5		mg/L	5	5/11/2018 4:27:31 PM	R5122C
Nitrate+Nitrite as N	ND	0.27	1.0		mg/L	5	5/14/2018 4:51:23 PM	R5127C
EPA METHOD 200.7: DISSOLVED METALS								Analyst: pmf
Barium	1.6	0.0049	0.010		mg/L	5	5/18/2018 1:22:52 PM	A51375
Cadmium	ND	0.0010	0.0020		mg/L	1	5/18/2018 11:36:30 AM	A51375
Calcium	66	0.078	1.0		mg/L	1	5/18/2018 11:36:30 AM	A51375
Chromium	ND	0.0013	0.0060		mg/L	1	5/18/2018 11:36:30 AM	A51375
Copper	ND	0.0032	0.0060		mg/L	1	5/18/2018 11:36:30 AM	A51375
Iron	1.7	0.082	0.10	*	mg/L	5	5/18/2018 1:22:52 PM	A51375
Magnesium	12	0.25	1.0		mg/L	1	5/18/2018 11:36:30 AM	A51375
Manganese	0.92	0.00039	0.0020	*	mg/L	1	5/18/2018 11:36:30 AM	A51375
Potassium	0.25	0.11	1.0	J	mg/L	1	5/18/2018 11:36:30 AM	A51375
Silver	ND	0.0018	0.0050		mg/L	1	5/18/2018 11:36:30 AM	A51375
Sodium	340	0.82	5.0		mg/L	5	5/23/2018 2:37:39 PM	C51452
Zinc	0.0056	0.0021	0.010	J	mg/L	1	5/18/2018 11:36:30 AM	A51375
EPA METHOD 200.7: TOTAL METALS								Analyst: pmf
Barium	1.8	0.0050	0.010		mg/L	5	6/5/2018 3:06:07 PM	37927
Cadmium	ND	0.00058	0.0020		mg/L	1	5/31/2018 9:01:47 PM	37927
Chromium	ND	0.0018	0.0060		mg/L	1	5/31/2018 9:01:47 PM	37927
Copper	ND	0.0041	0.0060		mg/L	1	5/31/2018 9:01:47 PM	37927
Iron	3.1	0.051	0.10	*	mg/L	5	6/5/2018 3:06:07 PM	37927
Manganese	0.95	0.0011	0.0020	*	mg/L	1	5/31/2018 9:01:47 PM	37927
Silver	ND	0.0012	0.0050		mg/L	1	5/31/2018 9:01:47 PM	37927
Zinc	0.0034	0.0033	0.010	J	mg/L	1	5/31/2018 9:01:47 PM	37927
EPA 200.8: DISSOLVED METALS								Analyst: DBK
Arsenic	0.0043	0.00042	0.0010		mg/L	1	5/3/2018 3:39:38 PM	B51024

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: DUP02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018

Lab ID: 1805106-010

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA 200.8: DISSOLVED METALS								
							Analyst: DBK	
Lead	ND	0.00017	0.00050		mg/L	1	5/3/2018 3:39:38 PM	B51024
Selenium	0.0016	0.00076	0.0010		mg/L	1	5/3/2018 3:39:38 PM	B51024
Uranium	0.00016	0.000096	0.00050	J	mg/L	1	5/14/2018 6:19:50 PM	B51261
200.8 ICPMS METALS:TOTAL								
							Analyst: ELS	
Arsenic	0.0046	0.00041	0.0010		mg/L	1	5/8/2018 12:35:29 PM	37927
Lead	0.00078	0.00023	0.00050		mg/L	1	5/8/2018 12:35:29 PM	37927
Selenium	ND	0.00098	0.0010		mg/L	1	5/8/2018 12:35:29 PM	37927
Uranium	0.00023	0.000068	0.00050	J	mg/L	1	5/8/2018 12:35:29 PM	37927
EPA METHOD 245.1: MERCURY								
							Analyst: rde	
Mercury	ND	0.000037	0.00020		mg/L	1	5/8/2018 6:08:57 PM	37992
EPA METHOD 8260B: VOLATILES								
							Analyst: RAA	
Benzene	38	0.062	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Toluene	2.8	0.064	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Ethylbenzene	46	0.093	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Methyl tert-butyl ether (MTBE)	110	0.24	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2,4-Trimethylbenzene	0.88	0.11	1.0	J	µg/L	1	5/11/2018 9:39:00 PM	R51242
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Naphthalene	8.4	0.11	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1-Methylnaphthalene	13	0.16	4.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
2-Methylnaphthalene	2.4	0.15	4.0	J	µg/L	1	5/11/2018 9:39:00 PM	R51242
Acetone	17	0.82	10		µg/L	1	5/11/2018 9:39:00 PM	R51242
Bromobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Bromoform	ND	0.21	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Bromomethane	ND	0.26	3.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
2-Butanone	ND	1.1	10		µg/L	1	5/11/2018 9:39:00 PM	R51242
Carbon disulfide	ND	0.40	10		µg/L	1	5/11/2018 9:39:00 PM	R51242
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Chloroethane	ND	0.23	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Chloroform	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Chloromethane	ND	0.29	3.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 36 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**Date Reported: **6/7/2018****CLIENT:** Andeavor Gallup**Client Sample ID:** DUP02**Project:** 2nd Quarter 2018 Groundwater Sampling**Collection Date:** 4/30/2018**Lab ID:** 1805106-010**Matrix:** AQUEOUS**Received Date:** 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Dibromomethane	ND	0.091	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
2-Hexanone	ND	0.66	10		µg/L	1	5/11/2018 9:39:00 PM	R51242
Isopropylbenzene	4.5	0.051	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/11/2018 9:39:00 PM	R51242
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
n-Butylbenzene	0.79	0.13	3.0	J	µg/L	1	5/11/2018 9:39:00 PM	R51242
n-Propylbenzene	4.9	0.074	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
sec-Butylbenzene	1.6	0.11	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Styrene	ND	0.16	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
tert-Butylbenzene	0.36	0.10	1.0	J	µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/11/2018 9:39:00 PM	R51242
Xylenes, Total	3.0	0.32	1.5		µg/L	1	5/11/2018 9:39:00 PM	R51242
Surr: 1,2-Dichloroethane-d4	103	0	70-130		%Rec	1	5/11/2018 9:39:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 37 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: DUP02

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date: 4/30/2018

Lab ID: 1805106-010

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: RAA	
Surr: 4-Bromofluorobenzene	117	0	70-130		%Rec	1	5/11/2018 9:39:00 PM	R51242
Surr: Dibromofluoromethane	108	0	70-130		%Rec	1	5/11/2018 9:39:00 PM	R51242
Surr: Toluene-d8	110	0	70-130		%Rec	1	5/11/2018 9:39:00 PM	R51242

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	D	Sample Diluted Due to Matrix	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: TRIP BLANK

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date:

Lab ID: 1805106-011

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8015D: GASOLINE RANGE							Analyst: NSB	
Gasoline Range Organics (GRO)	ND	0.021	0.050		mg/L	1	5/5/2018 8:46:29 AM	G51045
Surr: BFB	93.0	0	69.3-150		%Rec	1	5/5/2018 8:46:29 AM	G51045
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
Benzene	ND	0.062	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Toluene	ND	0.064	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Ethylbenzene	ND	0.093	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Methyl tert-butyl ether (MTBE)	ND	0.24	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2,4-Trimethylbenzene	0.15	0.11	1.0	J	µg/L	1	5/10/2018 2:57:06 PM	W5119
1,3,5-Trimethylbenzene	ND	0.087	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2-Dichloroethane (EDC)	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2-Dibromoethane (EDB)	ND	0.13	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Naphthalene	ND	0.11	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1-Methylnaphthalene	ND	0.16	4.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
2-Methylnaphthalene	ND	0.15	4.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Acetone	ND	0.82	10		µg/L	1	5/10/2018 2:57:06 PM	W5119
Bromobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Bromodichloromethane	ND	0.18	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Bromoform	ND	0.21	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Bromomethane	ND	0.26	3.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
2-Butanone	ND	1.1	10		µg/L	1	5/10/2018 2:57:06 PM	W5119
Carbon disulfide	ND	0.40	10		µg/L	1	5/10/2018 2:57:06 PM	W5119
Carbon Tetrachloride	ND	0.11	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Chlorobenzene	ND	0.11	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Chloroethane	ND	0.23	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Chloroform	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Chloromethane	ND	0.29	3.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
2-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
4-Chlorotoluene	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
cis-1,2-DCE	ND	0.20	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
cis-1,3-Dichloropropene	ND	0.082	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2-Dibromo-3-chloropropane	ND	1.4	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Dibromochloromethane	ND	0.072	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Dibromomethane	ND	0.091	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2-Dichlorobenzene	ND	0.090	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,3-Dichlorobenzene	ND	0.15	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,4-Dichlorobenzene	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Dichlorodifluoromethane	ND	1.0	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1-Dichloroethane	ND	0.40	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1-Dichloroethene	ND	0.081	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	Page 39 of 63
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order **1805106**

Date Reported: **6/7/2018**

CLIENT: Andeavor Gallup

Client Sample ID: TRIP BLANK

Project: 2nd Quarter 2018 Groundwater Sampling

Collection Date:

Lab ID: 1805106-011

Matrix: AQUEOUS

Received Date: 5/2/2018 9:20:00 AM

Analyses	Result	MDL	PQL	Qual	Units	DF	Date Analyzed	Batch ID
EPA METHOD 8260B: VOLATILES							Analyst: DJF	
1,2-Dichloropropane	ND	0.10	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,3-Dichloropropane	ND	0.17	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
2,2-Dichloropropane	ND	0.16	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1-Dichloropropene	ND	0.093	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Hexachlorobutadiene	ND	0.80	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
2-Hexanone	ND	0.66	10		µg/L	1	5/10/2018 2:57:06 PM	W5119
Isopropylbenzene	ND	0.051	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
4-Isopropyltoluene	ND	0.096	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
4-Methyl-2-pentanone	ND	0.71	10		µg/L	1	5/10/2018 2:57:06 PM	W5119
Methylene Chloride	ND	0.11	3.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
n-Butylbenzene	ND	0.13	3.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
n-Propylbenzene	ND	0.074	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
sec-Butylbenzene	ND	0.11	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Styrene	ND	0.16	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
tert-Butylbenzene	ND	0.10	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1,1,2-Tetrachloroethane	ND	0.10	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1,2,2-Tetrachloroethane	ND	0.14	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Tetrachloroethene (PCE)	ND	0.13	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
trans-1,2-DCE	ND	0.18	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
trans-1,3-Dichloropropene	ND	0.22	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2,3-Trichlorobenzene	ND	0.12	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2,4-Trichlorobenzene	ND	0.14	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1,1-Trichloroethane	ND	0.073	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,1,2-Trichloroethane	ND	0.14	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Trichloroethene (TCE)	ND	0.11	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Trichlorofluoromethane	ND	0.18	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
1,2,3-Trichloropropane	ND	0.39	2.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Vinyl chloride	ND	0.18	1.0		µg/L	1	5/10/2018 2:57:06 PM	W5119
Xylenes, Total	ND	0.32	1.5		µg/L	1	5/10/2018 2:57:06 PM	W5119
Surr: 1,2-Dichloroethane-d4	94.0	0	70-130		%Rec	1	5/10/2018 2:57:06 PM	W5119
Surr: 4-Bromofluorobenzene	116	0	70-130		%Rec	1	5/10/2018 2:57:06 PM	W5119
Surr: Dibromofluoromethane	94.3	0	70-130		%Rec	1	5/10/2018 2:57:06 PM	W5119
Surr: Toluene-d8	96.1	0	70-130		%Rec	1	5/10/2018 2:57:06 PM	W5119

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank	
	D	Sample Diluted Due to Matrix	E	Value above quantitation range	
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	Page 40 of 63
	ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range	
	PQL	Practical Quantitative Limit	RL	Reporting Detection Limit	
	S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified	

1805106-008F OAPIS-1

Collected date/time: 04/30/18 16:50

SAMPLE RESULTS - 01

L991012

ONE LAB. NATIONWIDE.



Wet Chemistry by Method 4500CN E-2011

Analyte	Result	Qualifier	RDL	Dilution	Analysis	Batch
	mg/l		mg/l		date / time	
Cyanide	0.0848		0.00500	1	05/09/2018 18:32	WG110366Z

Tc

Ss

Cn

Sr

Qc

Gl

Al

Sc

ACCOUNT:

Hall Environmental Analysis Laboratory

PROJECT:

SDG:

L991012

DATE/TIME:

05/10/18 15:05

Method Blank (MB)

(MB) R3308393-1 05/09/18 17:59				
MB Result	MB Qualifier	MB MDL	MB RDL	
mg/l	mg/l	mg/l	mg/l	
U	0.00180	0.00500		
Analyte				
Cyanide				

L990138-02 Original Sample (OS) • Duplicate (DUP)

(OS) L990138-02 05/09/18 18:04 • (DUP) R3308393-4 05/09/18 18:05				
Original Result	DUP Result	Dilution	DUP RPD	DUP Qualifier
mg/l	mg/l	%	%	%
ND	0.000	1	0.000	20
Analyte				
Cyanide				

L990813-02 Original Sample (OS) • Duplicate (DUP)

(OS) L990813-02 05/09/18 18:21 • (DUP) R3308393-7 05/09/18 18:24				
Original Result	DUP Result	Dilution	DUP RPD	DUP Qualifier
mg/l	mg/l	%	%	%
ND	0.000	1	0.000	20
Analyte				
Cyanide				

Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3308393-2 05/09/18 18:00 • (LCSD) R3308393-3 05/09/18 18:01				
Spike Amount	LCS Result	LCSD Result	LCS Rec.	LCSD Rec.
mg/l	mg/l	mg/l	%	%
0.100	0.105	0.0956	105	95.6
Analyte				
Cyanide				
			Rec. Limits	RPD Limits
			%	%
			85.0-115	9.37
				20

L990235-02 Original Sample (OS) • Matrix Spike (MS)

(OS) L990235-02 05/09/18 18:06 • (MS) R3308393-5 05/09/18 18:07				
Spike Amount	Original Result	MS Result	MS Rec.	Dilution
mg/l	mg/l	mg/l	%	%
0.100	ND	0.0921	92.1	1
Analyte				
Cyanide				
			Rec. Limits	MS Qualifier
			%	
			75.0-125	

CP

Tc

Ss

Cn

Sr

Qc

Gl

Al

Sc



Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Abbreviations and Definitions

MDL	Method Detection Limit.
ND	Not detected at the Reporting Limit (or MDL where applicable).
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
U	Not detected at the Reporting Limit (or MDL where applicable).
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Original Sample	The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.

Qualifier	Description
-----------	-------------

The remainder of this page intentionally left blank, there are no qualifiers applied to this SDG.

Fe

Ss

Cn

Sr

Qc

Gl

Al

Sc

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	MB-A	SampType:	MBLK	TestCode:	EPA Method 200.7: Dissolved Metals					
Client ID:	PBW	Batch ID:	A51375	RunNo:	51375					
Prep Date:		Analysis Date:	5/18/2018	SeqNo:	1671729	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Barium	ND	0.0020								
Cadmium	ND	0.0020								
Calcium	ND	1.0								
Chromium	ND	0.0060								
Copper	ND	0.0060								
Iron	ND	0.020								
Magnesium	ND	1.0								
Manganese	ND	0.0020								
Potassium	ND	1.0								
Silver	ND	0.0050								
Zinc	ND	0.010								

Sample ID	LLCS-A	SampType:	LCSLL	TestCode:	EPA Method 200.7: Dissolved Metals					
Client ID:	BatchQC	Batch ID:	A51375	RunNo:	51375					
Prep Date:		Analysis Date:	5/18/2018	SeqNo:	1671730	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Barium	0.0018	0.0020	0.002000	0	88.0	50	150			J
Cadmium	0.0023	0.0020	0.002000	0	114	50	150			
Calcium	0.47	1.0	0.5000	0	94.7	50	150			J
Chromium	0.0057	0.0060	0.006000	0	95.7	50	150			J
Copper	0.0058	0.0060	0.006000	0	96.0	50	150			J
Iron	0.027	0.020	0.02000	0	135	50	150			
Magnesium	0.44	1.0	0.5000	0	88.3	50	150			J
Manganese	0.0021	0.0020	0.002000	0	104	50	150			
Potassium	0.49	1.0	0.5000	0	98.5	50	150			J
Silver	0.0050	0.0050	0.005000	0	100	50	150			
Zinc	0.0070	0.010	0.005000	0	140	50	150			J

Sample ID	LCS-A	SampType:	LCS	TestCode:	EPA Method 200.7: Dissolved Metals					
Client ID:	LCSW	Batch ID:	A51375	RunNo:	51375					
Prep Date:		Analysis Date:	5/18/2018	SeqNo:	1671731	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Barium	0.49	0.0020	0.5000	0	98.8	85	115			
Cadmium	0.51	0.0020	0.5000	0	101	85	115			
Calcium	50	1.0	50.00	0	99.9	85	115			
Chromium	0.49	0.0060	0.5000	0	98.6	85	115			
Copper	0.51	0.0060	0.5000	0	103	85	115			
Iron	0.52	0.020	0.5000	0	104	85	115			

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup
Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID LCS-A	SampType: LCS			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: LCSW	Batch ID: A51375			RunNo: 51375						
Prep Date:	Analysis Date: 5/18/2018			SeqNo: 1671731		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Magnesium	50	1.0	50.00	0	101	85	115			
Manganese	0.50	0.0020	0.5000	0	99.7	85	115			
Potassium	50	1.0	50.00	0	99.2	85	115			
Silver	0.11	0.0050	0.1000	0	108	85	115			
Zinc	0.49	0.010	0.5000	0	97.4	85	115			

Sample ID MB-A	SampType: MBLK			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: PBW	Batch ID: A51451			RunNo: 51451						
Prep Date:	Analysis Date: 5/22/2018			SeqNo: 1675221		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	ND	1.0								

Sample ID LLCS-A	SampType: LCSLL			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: BatchQC	Batch ID: A51451			RunNo: 51451						
Prep Date:	Analysis Date: 5/22/2018			SeqNo: 1675222		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	0.49	1.0	0.5000	0	97.9	50	150			J

Sample ID LCS-A	SampType: LCS			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: LCSW	Batch ID: A51451			RunNo: 51451						
Prep Date:	Analysis Date: 5/22/2018			SeqNo: 1675223		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	53	1.0	50.00	0	106	85	115			

Sample ID MB-B	SampType: MBLK			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: PBW	Batch ID: B51452			RunNo: 51452						
Prep Date:	Analysis Date: 5/23/2018			SeqNo: 1676345		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	ND	1.0								

Sample ID LCS-B	SampType: LCS			TestCode: EPA Method 200.7: Dissolved Metals						
Client ID: LCSW	Batch ID: B51452			RunNo: 51452						
Prep Date:	Analysis Date: 5/23/2018			SeqNo: 1676349		Units: mg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	53	1.0	50.00	0	107	85	115			

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LLLCS-B		SampType: LCSLL		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	BatchQC		Batch ID: B51452		RunNo: 51452					
Prep Date:			Analysis Date: 5/23/2018		SeqNo: 1676350		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	0.43	1.0	0.5000	0	86.0	50	150			J

Sample ID	MB-C		SampType: MBLK		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	PBW		Batch ID: C51452		RunNo: 51452					
Prep Date:			Analysis Date: 5/23/2018		SeqNo: 1676401		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	ND	1.0								

Sample ID	LLLCS-C		SampType: LCSLL		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	BatchQC		Batch ID: C51452		RunNo: 51452					
Prep Date:			Analysis Date: 5/23/2018		SeqNo: 1676402		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	0.49	1.0	0.5000	0	97.3	50	150			J

Sample ID	LCS-C		SampType: LCS		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	LCSW		Batch ID: C51452		RunNo: 51452					
Prep Date:			Analysis Date: 5/23/2018		SeqNo: 1676403		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	53	1.0	50.00	0	106	85	115			

Sample ID	MB-A		SampType: MBLK		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	PBW		Batch ID: A51516		RunNo: 51516					
Prep Date:			Analysis Date: 5/24/2018		SeqNo: 1679019		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	ND	1.0								

Sample ID	LLLCS-A		SampType: LCSLL		TestCode: EPA Method 200.7: Dissolved Metals					
Client ID:	BatchQC		Batch ID: A51516		RunNo: 51516					
Prep Date:			Analysis Date: 5/24/2018		SeqNo: 1679020		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	0.50	1.0	0.5000	0	99.4	50	150			J

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LCS-A	SampType:	LCS	TestCode:	EPA Method 200.7: Dissolved Metals					
Client ID:	LCSW	Batch ID:	A51516	RunNo:	51516					
Prep Date:		Analysis Date:	5/24/2018	SeqNo:	1679021	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Sodium	51	1.0	50.00	0	102	85	115			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LLLCS-37927		SampType: LCSLL		TestCode: EPA Method 200.7: Total Metals					
Client ID:	BatchQC		Batch ID: 37927		RunNo: 51094					
Prep Date:	5/3/2018		Analysis Date: 5/7/2018		SeqNo: 1660283		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Barium	0.0026	0.0020	0.002000	0	132	50	150			
Cadmium	0.0023	0.0020	0.002000	0	116	50	150			
Chromium	0.0053	0.0060	0.006000	0	88.5	50	150			J
Copper	0.0052	0.0060	0.006000	0	86.8	50	150			J
Iron	0.023	0.020	0.02000	0	115	50	150			
Manganese	0.0020	0.0020	0.002000	0	101	50	150			
Silver	0.0046	0.0050	0.005000	0	91.8	50	150			J
Zinc	0.0063	0.010	0.005000	0	127	50	150			J

Sample ID	LCS-37927		SampType: LCS		TestCode: EPA Method 200.7: Total Metals					
Client ID:	LCSW		Batch ID: 37927		RunNo: 51094					
Prep Date:	5/3/2018		Analysis Date: 5/7/2018		SeqNo: 1660284		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Barium	0.53	0.0020	0.5000	0	105	85	115			
Cadmium	0.54	0.0020	0.5000	0	107	85	115			
Chromium	0.50	0.0060	0.5000	0	100	85	115			
Copper	0.51	0.0060	0.5000	0	103	85	115			
Iron	0.49	0.020	0.5000	0	98.3	85	115			
Manganese	0.51	0.0020	0.5000	0	101	85	115			
Silver	0.11	0.0050	0.1000	0	106	85	115			
Zinc	0.50	0.010	0.5000	0	101	85	115			

Sample ID	MB-37927		SampType: MBLK		TestCode: EPA Method 200.7: Total Metals					
Client ID:	PBW		Batch ID: 37927		RunNo: 51094					
Prep Date:	5/3/2018		Analysis Date: 5/7/2018		SeqNo: 1660299		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Barium	ND	0.0020								
Cadmium	0.00064	0.0020								J
Chromium	ND	0.0060								
Copper	ND	0.0060								
Iron	ND	0.020								
Manganese	ND	0.0020								
Silver	ND	0.0050								
Zinc	ND	0.010								

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	MB	SampType: MBLK			TestCode: EPA 200.8: Dissolved Metals					
Client ID:	PBW	Batch ID: B51024			RunNo: 51024					
Prep Date:		Analysis Date: 5/3/2018			SeqNo: 1656782		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	ND	0.0010								
Lead	ND	0.00050								
Selenium	ND	0.0010								
Uranium	ND	0.00050								

Sample ID	LLCS		SampType: LCSLL		TestCode: EPA 200.8: Dissolved Metals					
Client ID:	BatchQC		Batch ID: B51024		RunNo: 51024					
Prep Date:			Analysis Date: 5/3/2018		SeqNo: 1656783		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.0010	0.0010	0.001000	0	102	50	150			
Lead	0.00047	0.00050	0.0005000	0	93.2	50	150			J
Selenium	0.0011	0.0010	0.001000	0	113	50	150			
Uranium	0.00047	0.00050	0.0005000	0	93.0	50	150			J

Sample ID	LCS		SampType: LCS		TestCode: EPA 200.8: Dissolved Metals					
Client ID:	LCSW		Batch ID: B51024		RunNo: 51024					
Prep Date:			Analysis Date: 5/3/2018		SeqNo: 1656784		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.025	0.0010	0.02500	0	100	85	115			
Lead	0.012	0.00050	0.01250	0	95.5	85	115			
Selenium	0.024	0.0010	0.02500	0	96.6	85	115			
Uranium	0.012	0.00050	0.01250	0	93.3	85	115			

Sample ID	MB	SampType: MBLK			TestCode: EPA 200.8: Dissolved Metals					
Client ID:	PBW	Batch ID: B51261			RunNo: 51261					
Prep Date:		Analysis Date: 5/14/2018			SeqNo: 1666235		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	ND	0.0010								
Lead	ND	0.00050								
Selenium	ND	0.0010								
Uranium	ND	0.00050								

Sample ID	LLCS		SampType: LCSLL		TestCode: EPA 200.8: Dissolved Metals					
Client ID:	BatchQC		Batch ID: B51261		RunNo: 51261					
Prep Date:			Analysis Date: 5/14/2018		SeqNo: 1666236		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup
Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID LLLCS	SampType: LCSLL		TestCode: EPA 200.8: Dissolved Metals							
Client ID: BatchQC	Batch ID: B51261		RunNo: 51261							
Prep Date:	Analysis Date: 5/14/2018		SeqNo: 1666236		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.00098	0.0010	0.001000	0	97.6	50	150			J
Lead	0.00049	0.00050	0.0005000	0	99.0	50	150			J
Selenium	0.00095	0.0010	0.001000	0	95.4	50	150			J
Uranium	0.00049	0.00050	0.0005000	0	98.3	50	150			J

Sample ID LCS	SampType: LCS		TestCode: EPA 200.8: Dissolved Metals							
Client ID: LCSW	Batch ID: B51261		RunNo: 51261							
Prep Date:	Analysis Date: 5/14/2018		SeqNo: 1666237		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.024	0.0010	0.02500	0	96.5	85	115			
Lead	0.012	0.00050	0.01250	0	97.9	85	115			
Selenium	0.024	0.0010	0.02500	0	95.9	85	115			
Uranium	0.012	0.00050	0.01250	0	96.3	85	115			

Sample ID 1805106-003CMS	SampType: MS		TestCode: EPA 200.8: Dissolved Metals							
Client ID: WEST LDU	Batch ID: B51261		RunNo: 51261							
Prep Date:	Analysis Date: 5/14/2018		SeqNo: 1666252		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.14	0.0050	0.1250	0.004987	106	70	130			
Lead	0.055	0.0025	0.06250	0	88.4	70	130			
Selenium	0.12	0.0050	0.1250	0.007517	87.3	70	130			
Uranium	0.063	0.0025	0.06250	0.0005835	100	70	130			

Sample ID MB	SampType: MBLK		TestCode: EPA 200.8: Dissolved Metals							
Client ID: PBW	Batch ID: A51316		RunNo: 51316							
Prep Date:	Analysis Date: 5/16/2018		SeqNo: 1669003		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	ND	0.0010								
Lead	ND	0.00050								
Selenium	ND	0.0010								
Uranium	ND	0.00050								

Sample ID LLLCS	SampType: LCSLL		TestCode: EPA 200.8: Dissolved Metals							
Client ID: BatchQC	Batch ID: A51316		RunNo: 51316							
Prep Date:	Analysis Date: 5/16/2018		SeqNo: 1669004		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LLLCS		SampType: LCSLL		TestCode: EPA 200.8: Dissolved Metals					
Client ID:	BatchQC		Batch ID: A51316		RunNo: 51316					
Prep Date:			Analysis Date: 5/16/2018		SeqNo: 1669004		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.00098	0.0010	0.001000	0	98.1	50	150			J
Lead	0.00049	0.00050	0.0005000	0	97.1	50	150			J
Selenium	0.00095	0.0010	0.001000	0	94.6	50	150			J
Uranium	0.00047	0.00050	0.0005000	0	94.2	50	150			J

Sample ID	LCS		SampType: LCS		TestCode: EPA 200.8: Dissolved Metals					
Client ID:	LCSW		Batch ID: A51316		RunNo: 51316					
Prep Date:			Analysis Date: 5/16/2018		SeqNo: 1669005		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.025	0.0010	0.02500	0	98.1	85	115			
Lead	0.012	0.00050	0.01250	0	98.3	85	115			
Selenium	0.024	0.0010	0.02500	0	96.8	85	115			
Uranium	0.012	0.00050	0.01250	0	96.5	85	115			

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	MB-37927		SampType: MBLK		TestCode: 200.8 ICPMS Metals:Total					
Client ID:	PBW		Batch ID: 37927		RunNo: 51113					
Prep Date:	5/3/2018		Analysis Date: 5/8/2018		SeqNo: 1660630		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	ND	0.0010								
Lead	ND	0.00050								
Selenium	ND	0.0010								
Uranium	ND	0.00050								

Sample ID	MSLLCS-37927		SampType: LCSLL		TestCode: 200.8 ICPMS Metals:Total					
Client ID:	BatchQC		Batch ID: 37927		RunNo: 51113					
Prep Date:	5/3/2018		Analysis Date: 5/8/2018		SeqNo: 1660631		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.00095	0.0010	0.001000	0	94.9	50	150			J
Lead	0.00051	0.00050	0.0005000	0	102	50	150			
Selenium	0.00090	0.0010	0.001000	0	90.3	50	150			J
Uranium	0.00053	0.00050	0.0005000	0	106	50	150			

Sample ID	MSLCS-37927		SampType: LCS		TestCode: 200.8 ICPMS Metals:Total					
Client ID:	LCSW		Batch ID: 37927		RunNo: 51113					
Prep Date:	5/3/2018		Analysis Date: 5/8/2018		SeqNo: 1660632		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Arsenic	0.023	0.0010	0.02500	0	93.3	85	115			
Lead	0.012	0.00050	0.01250	0	99.8	85	115			
Selenium	0.023	0.0010	0.02500	0	93.5	85	115			
Uranium	0.014	0.00050	0.01250	0	108	85	115			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	MB-37992	SampType:	MBLK	TestCode:	EPA Method 245.1: Mercury					
Client ID:	PBW	Batch ID:	37992	RunNo:	51126					
Prep Date:	5/8/2018	Analysis Date:	5/8/2018	SeqNo:	1660989	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	ND	0.00020								

Sample ID	LCS-37992	SampType:	LCS	TestCode:	EPA Method 245.1: Mercury					
Client ID:	LCSW	Batch ID:	37992	RunNo:	51126					
Prep Date:	5/8/2018	Analysis Date:	5/8/2018	SeqNo:	1660990	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Mercury	0.0049	0.00020	0.005000	0	97.7	80	120			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup
Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID MB	SampType: mblk		TestCode: EPA Method 300.0: Anions							
Client ID: PBW	Batch ID: R51220		RunNo: 51220							
Prep Date:	Analysis Date: 5/11/2018		SeqNo: 1664778		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	ND	0.10								
Chloride	ND	0.50								
Bromide	ND	0.10								
Phosphorus, Orthophosphate (As P	ND	0.50								
Sulfate	ND	0.50								

Sample ID LCS	SampType: lcs		TestCode: EPA Method 300.0: Anions							
Client ID: LCSW	Batch ID: R51220		RunNo: 51220							
Prep Date:	Analysis Date: 5/11/2018		SeqNo: 1664779		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Fluoride	0.52	0.10	0.5000	0	103	90	110			
Chloride	4.8	0.50	5.000	0	95.7	90	110			
Bromide	2.5	0.10	2.500	0	98.4	90	110			
Phosphorus, Orthophosphate (As P	4.8	0.50	5.000	0	96.8	90	110			
Sulfate	9.5	0.50	10.00	0	94.6	90	110			

Sample ID MB	SampType: mblk		TestCode: EPA Method 300.0: Anions							
Client ID: PBW	Batch ID: R51270		RunNo: 51270							
Prep Date:	Analysis Date: 5/14/2018		SeqNo: 1666618		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Chloride	ND	0.50								
Nitrate+Nitrite as N	ND	0.20								

Sample ID LCS	SampType: lcs		TestCode: EPA Method 300.0: Anions							
Client ID: LCSW	Batch ID: R51270		RunNo: 51270							
Prep Date:	Analysis Date: 5/14/2018		SeqNo: 1666619		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Chloride	4.7	0.50	5.000	0	93.1	90	110			
Nitrate+Nitrite as N	3.4	0.20	3.500	0	96.7	90	110			

Sample ID MB	SampType: mblk		TestCode: EPA Method 300.0: Anions							
Client ID: PBW	Batch ID: R51421		RunNo: 51421							
Prep Date:	Analysis Date: 5/21/2018		SeqNo: 1673451		Units: mg/L					
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Chloride	ND	0.50								
Nitrate+Nitrite as N	ND	0.20								

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LCS	SampType:	lcs	TestCode:	EPA Method 300.0: Anions					
Client ID:	LCSW	Batch ID:	R51421	RunNo:	51421					
Prep Date:		Analysis Date:	5/21/2018	SeqNo:	1673452	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Chloride	4.5	0.50	5.000	0	90.9	90	110			
Nitrate+Nitrite as N	3.3	0.20	3.500	0	94.4	90	110			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	LCS-37932		SampType: LCS		TestCode: EPA Method 8015M/D: Diesel Range					
Client ID:	LCSW		Batch ID: 37932		RunNo: 50978					
Prep Date:	5/3/2018		Analysis Date: 5/3/2018		SeqNo: 1656856		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Diesel Range Organics (DRO)	4.9	1.0	5.000	0	98.7	70	130			
Surr: DNOP	0.56		0.5000		112	76.7	135			

Sample ID	MB-37932		SampType: MBLK		TestCode: EPA Method 8015M/D: Diesel Range					
Client ID:	PBW		Batch ID: 37932		RunNo: 50978					
Prep Date:	5/3/2018		Analysis Date: 5/3/2018		SeqNo: 1656857		Units: mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Diesel Range Organics (DRO)	ND	1.0								
Motor Oil Range Organics (MRO)	ND	5.0								
Surr: DNOP	1.2		1.000		117	76.7	135			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	RB	SampType:	MBLK	TestCode:	EPA Method 8015D: Gasoline Range					
Client ID:	PBW	Batch ID:	G51049	RunNo:	51049					
Prep Date:		Analysis Date:	5/4/2018	SeqNo:	1658203	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Gasoline Range Organics (GRO)	ND	0.050								
Surr: BFB	18		20.00		90.8	69.3	150			

Sample ID	2.5UG GRO LCS	SampType:	LCS	TestCode:	EPA Method 8015D: Gasoline Range					
Client ID:	LCSW	Batch ID:	G51049	RunNo:	51049					
Prep Date:		Analysis Date:	5/4/2018	SeqNo:	1658204	Units:	mg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Gasoline Range Organics (GRO)	0.52	0.050	0.5000	0	105	79.5	127			
Surr: BFB	21		20.00		106	69.3	150			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	100ng lcs	SampType:	LCS	TestCode:	EPA Method 8260: Volatiles Short List					
Client ID:	LCSW	Batch ID:	SL51242	RunNo:	51242					
Prep Date:		Analysis Date:	5/11/2018	SeqNo:	1666418	Units:	µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	22	1.0	20.00	0	111	70	130			
Toluene	24	1.0	20.00	0	119	70	130			
Surr: 1,2-Dichloroethane-d4	11		10.00		106	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		112	70	130			
Surr: Dibromofluoromethane	11		10.00		108	70	130			
Surr: Toluene-d8	11		10.00		112	70	130			

Sample ID	rb	SampType:	MBLK	TestCode:	EPA Method 8260: Volatiles Short List					
Client ID:	PBW	Batch ID:	SL51242	RunNo:	51242					
Prep Date:		Analysis Date:	5/11/2018	SeqNo:	1666419	Units:	µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	0.070	1.0								J
Toluene	ND	1.0								
Ethylbenzene	ND	1.0								
Methyl tert-butyl ether (MTBE)	ND	1.0								
1,2,4-Trimethylbenzene	ND	1.0								
1,3,5-Trimethylbenzene	ND	1.0								
Xylenes, Total	ND	1.5								
Surr: 1,2-Dichloroethane-d4	11		10.00		106	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		111	70	130			
Surr: Dibromofluoromethane	11		10.00		109	70	130			
Surr: Toluene-d8	11		10.00		111	70	130			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	rb1	SampType:	MBLK	TestCode:	EPA Method 8260B: VOLATILES					
Client ID:	PBW	Batch ID:	W51196	RunNo:	51196					
Prep Date:		Analysis Date:	5/10/2018	SeqNo:	1663347	Units:	µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	ND	1.0								
Toluene	ND	1.0								
Ethylbenzene	ND	1.0								
Methyl tert-butyl ether (MTBE)	ND	1.0								
1,2,4-Trimethylbenzene	0.25	1.0								J
1,3,5-Trimethylbenzene	ND	1.0								
1,2-Dichloroethane (EDC)	ND	1.0								
1,2-Dibromoethane (EDB)	ND	1.0								
Naphthalene	ND	2.0								
1-Methylnaphthalene	ND	4.0								
2-Methylnaphthalene	ND	4.0								
Acetone	ND	10								
Bromobenzene	ND	1.0								
Bromodichloromethane	ND	1.0								
Bromoform	ND	1.0								
Bromomethane	ND	3.0								
2-Butanone	ND	10								
Carbon disulfide	ND	10								
Carbon Tetrachloride	ND	1.0								
Chlorobenzene	ND	1.0								
Chloroethane	ND	2.0								
Chloroform	ND	1.0								
Chloromethane	ND	3.0								
2-Chlorotoluene	ND	1.0								
4-Chlorotoluene	ND	1.0								
cis-1,2-DCE	ND	1.0								
cis-1,3-Dichloropropene	ND	1.0								
1,2-Dibromo-3-chloropropane	ND	2.0								
Dibromochloromethane	ND	1.0								
Dibromomethane	ND	1.0								
1,2-Dichlorobenzene	ND	1.0								
1,3-Dichlorobenzene	ND	1.0								
1,4-Dichlorobenzene	ND	1.0								
Dichlorodifluoromethane	ND	1.0								
1,1-Dichloroethane	ND	1.0								
1,1-Dichloroethene	ND	1.0								
1,2-Dichloropropane	ND	1.0								
1,3-Dichloropropane	ND	1.0								
2,2-Dichloropropane	ND	2.0								

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID rb1	SampType: MBLK			TestCode: EPA Method 8260B: VOLATILES						
Client ID: PBW	Batch ID: W51196			RunNo: 51196						
Prep Date:	Analysis Date: 5/10/2018			SeqNo: 1663347		Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
1,1-Dichloropropene	ND	1.0								
Hexachlorobutadiene	ND	1.0								
2-Hexanone	ND	10								
Isopropylbenzene	ND	1.0								
4-Isopropyltoluene	ND	1.0								
4-Methyl-2-pentanone	ND	10								
Methylene Chloride	ND	3.0								
n-Butylbenzene	ND	3.0								
n-Propylbenzene	ND	1.0								
sec-Butylbenzene	ND	1.0								
Styrene	ND	1.0								
tert-Butylbenzene	ND	1.0								
1,1,1,2-Tetrachloroethane	ND	1.0								
1,1,2,2-Tetrachloroethane	ND	2.0								
Tetrachloroethene (PCE)	ND	1.0								
trans-1,2-DCE	ND	1.0								
trans-1,3-Dichloropropene	ND	1.0								
1,2,3-Trichlorobenzene	ND	1.0								
1,2,4-Trichlorobenzene	ND	1.0								
1,1,1-Trichloroethane	ND	1.0								
1,1,2-Trichloroethane	ND	1.0								
Trichloroethene (TCE)	ND	1.0								
Trichlorofluoromethane	ND	1.0								
1,2,3-Trichloropropane	ND	2.0								
Vinyl chloride	ND	1.0								
Xylenes, Total	ND	1.5								
Surr: 1,2-Dichloroethane-d4	9.0		10.00		90.4	70	130			
Surr: 4-Bromofluorobenzene	12		10.00		116	70	130			
Surr: Dibromofluoromethane	9.3		10.00		93.3	70	130			
Surr: Toluene-d8	9.6		10.00		96.3	70	130			

Sample ID 100ng lcs	SampType: LCS			TestCode: EPA Method 8260B: VOLATILES						
Client ID: LCSW	Batch ID: W51196			RunNo: 51196						
Prep Date:	Analysis Date: 5/10/2018			SeqNo: 1663350		Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	19	1.0	20.00	0	94.8	70	130			
Toluene	19	1.0	20.00	0	93.5	70	130			
Chlorobenzene	18	1.0	20.00	0	89.0	70	130			

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup
Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID 100ng lcs	SampType: LCS			TestCode: EPA Method 8260B: VOLATILES						
Client ID: LCSW	Batch ID: W51196			RunNo: 51196						
Prep Date:	Analysis Date: 5/10/2018			SeqNo: 1663350		Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
1,1-Dichloroethene	19	1.0	20.00	0	96.2	70	130			
Trichloroethene (TCE)	17	1.0	20.00	0	84.4	70	130			
Surr: 1,2-Dichloroethane-d4	8.9		10.00		88.5	70	130			
Surr: 4-Bromofluorobenzene	12		10.00		117	70	130			
Surr: Dibromofluoromethane	9.2		10.00		91.7	70	130			
Surr: Toluene-d8	9.8		10.00		97.7	70	130			

Sample ID 100ng lcs	SampType: LCS			TestCode: EPA Method 8260B: VOLATILES						
Client ID: LCSW	Batch ID: R51242			RunNo: 51242						
Prep Date:	Analysis Date: 5/11/2018			SeqNo: 1665695		Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	22	1.0	20.00	0	111	70	130			
Toluene	24	1.0	20.00	0	119	70	130			
Chlorobenzene	24	1.0	20.00	0	119	70	130			
1,1-Dichloroethene	24	1.0	20.00	0	118	70	130			
Trichloroethene (TCE)	22	1.0	20.00	0	111	70	130			
Surr: 1,2-Dichloroethane-d4	11		10.00		106	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		112	70	130			
Surr: Dibromofluoromethane	11		10.00		108	70	130			
Surr: Toluene-d8	11		10.00		112	70	130			

Sample ID rb	SampType: MBLK			TestCode: EPA Method 8260B: VOLATILES						
Client ID: PBW	Batch ID: R51242			RunNo: 51242						
Prep Date:	Analysis Date: 5/11/2018			SeqNo: 1665696		Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	0.070	1.0								J
Toluene	ND	1.0								
Ethylbenzene	ND	1.0								
Methyl tert-butyl ether (MTBE)	ND	1.0								
1,2,4-Trimethylbenzene	ND	1.0								
1,3,5-Trimethylbenzene	ND	1.0								
1,2-Dichloroethane (EDC)	ND	1.0								
1,2-Dibromoethane (EDB)	ND	1.0								
Naphthalene	ND	2.0								
1-Methylnaphthalene	ND	4.0								
2-Methylnaphthalene	0.31	4.0								J
Acetone	ND	10								
Bromobenzene	ND	1.0								

Qualifiers:

* Value exceeds Maximum Contaminant Level.	B Analyte detected in the associated Method Blank
D Sample Diluted Due to Matrix	E Value above quantitation range
H Holding times for preparation or analysis exceeded	J Analyte detected below quantitation limits
ND Not Detected at the Reporting Limit	P Sample pH Not In Range
PQL Practical Quantitative Limit	RL Reporting Detection Limit
S % Recovery outside of range due to dilution or matrix	W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID rb		SampType: MBLK			TestCode: EPA Method 8260B: VOLATILES					
Client ID: PBW		Batch ID: R51242			RunNo: 51242					
Prep Date:		Analysis Date: 5/11/2018			SeqNo: 1665696		Units: µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Bromodichloromethane	ND	1.0								
Bromoform	ND	1.0								
Bromomethane	ND	3.0								
2-Butanone	ND	10								
Carbon disulfide	ND	10								
Carbon Tetrachloride	ND	1.0								
Chlorobenzene	0.12	1.0								J
Chloroethane	ND	2.0								
Chloroform	ND	1.0								
Chloromethane	ND	3.0								
2-Chlorotoluene	ND	1.0								
4-Chlorotoluene	ND	1.0								
cis-1,2-DCE	ND	1.0								
cis-1,3-Dichloropropene	ND	1.0								
1,2-Dibromo-3-chloropropane	ND	2.0								
Dibromochloromethane	ND	1.0								
Dibromomethane	ND	1.0								
1,2-Dichlorobenzene	ND	1.0								
1,3-Dichlorobenzene	ND	1.0								
1,4-Dichlorobenzene	ND	1.0								
Dichlorodifluoromethane	ND	1.0								
1,1-Dichloroethane	ND	1.0								
1,1-Dichloroethene	ND	1.0								
1,2-Dichloropropane	ND	1.0								
1,3-Dichloropropane	ND	1.0								
2,2-Dichloropropane	ND	2.0								
1,1-Dichloropropene	ND	1.0								
Hexachlorobutadiene	ND	1.0								
2-Hexanone	ND	10								
Isopropylbenzene	ND	1.0								
4-Isopropyltoluene	ND	1.0								
4-Methyl-2-pentanone	ND	10								
Methylene Chloride	ND	3.0								
n-Butylbenzene	ND	3.0								
n-Propylbenzene	ND	1.0								
sec-Butylbenzene	ND	1.0								
Styrene	ND	1.0								
tert-Butylbenzene	ND	1.0								
1,1,1,2-Tetrachloroethane	ND	1.0								

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	rb	SampType: MBLK			TestCode: EPA Method 8260B: VOLATILES					
Client ID:	PBW	Batch ID: R51242			RunNo: 51242					
Prep Date:		Analysis Date: 5/11/2018			SeqNo: 1665696		Units: µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
1,1,2,2-Tetrachloroethane	ND	2.0								
Tetrachloroethene (PCE)	ND	1.0								
trans-1,2-DCE	ND	1.0								
trans-1,3-Dichloropropene	ND	1.0								
1,2,3-Trichlorobenzene	ND	1.0								
1,2,4-Trichlorobenzene	ND	1.0								
1,1,1-Trichloroethane	ND	1.0								
1,1,2-Trichloroethane	ND	1.0								
Trichloroethene (TCE)	ND	1.0								
Trichlorofluoromethane	ND	1.0								
1,2,3-Trichloropropane	ND	2.0								
Vinyl chloride	ND	1.0								
Xylenes, Total	ND	1.5								
Surr: 1,2-Dichloroethane-d4	11		10.00		106	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		111	70	130			
Surr: Dibromofluoromethane	11		10.00		109	70	130			
Surr: Toluene-d8	11		10.00		111	70	130			

Sample ID	100ng lcs	SampType:	LCS	TestCode:	EPA Method 8260B: VOLATILES					
Client ID:	LCSW	Batch ID:	R51274	RunNo:	51274					
Prep Date:		Analysis Date:	5/14/2018	SeqNo:	1666778	Units:	%Rec			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: 1,2-Dichloroethane-d4	10		10.00		103	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		109	70	130			
Surr: Dibromofluoromethane	11		10.00		110	70	130			
Surr: Toluene-d8	11		10.00		110	70	130			

Sample ID	RB	SampType: MBLK			TestCode: EPA Method 8260B: VOLATILES					
Client ID:	PBW	Batch ID: R51274			RunNo: 51274					
Prep Date:		Analysis Date: 5/14/2018			SeqNo: 1666781		Units: µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Methyl tert-butyl ether (MTBE)	ND	1.0								
Surr: 1,2-Dichloroethane-d4	11		10.00		106	70	130			
Surr: 4-Bromofluorobenzene	11		10.00		114	70	130			
Surr: Dibromofluoromethane	11		10.00		112	70	130			
Surr: Toluene-d8	11		10.00		111	70	130			

Qualifiers:

* Value exceeds Maximum Contaminant Level.

D Sample Diluted Due to Matrix

H Holding times for preparation or analysis exceeded

ND Not Detected at the Reporting Limit

PQL Practical Quantitative Limit

S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank

E Value above quantitation range

J Analyte detected below quantitation limits

P Sample pH Not In Range

RL Reporting Detection Limit

W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	lcs-37947		SampType: LCS		TestCode: EPA Method 8270C: Semivolatiles					
Client ID:	LCSW		Batch ID: 37947		RunNo: 51189					
Prep Date:	5/4/2018		Analysis Date: 5/10/2018		SeqNo: 1663208		Units: µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Acenaphthene	77	10	100.0	0	77.4	39.7	103			
4-Chloro-3-methylphenol	170	10	200.0	0	84.3	40.5	108			
2-Chlorophenol	150	10	200.0	0	74.3	35	103			
1,4-Dichlorobenzene	68	10	100.0	0	68.3	24.7	93.7			
2,4-Dinitrotoluene	83	10	100.0	0	83.2	35.6	91.4			
N-Nitrosodi-n-propylamine	81	10	100.0	0	81.4	41.6	114			
4-Nitrophenol	140	10	200.0	0	71.4	20.7	74.3			
Pentachlorophenol	150	20	200.0	0	75.9	25.3	98.5			
Phenol	120	10	200.0	0	61.6	20.9	75.1			
Pyrene	78	10	100.0	0	78.5	45.6	108			
1,2,4-Trichlorobenzene	73	10	100.0	0	73.0	30.3	106			
Surr: 2-Fluorophenol	140		200.0		67.5	15	114			
Surr: Phenol-d5	120		200.0		59.6	15	97.9			
Surr: 2,4,6-Tribromophenol	180		200.0		91.4	15	161			
Surr: Nitrobenzene-d5	75		100.0		75.4	29.3	120			
Surr: 2-Fluorobiphenyl	79		100.0		79.2	17.5	116			
Surr: 4-Terphenyl-d14	110		100.0		108	21	92.2			S

Sample ID	mb-37947		SampType: MBLK		TestCode: EPA Method 8270C: Semivolatiles					
Client ID:	PBW		Batch ID: 37947		RunNo: 51189					
Prep Date:	5/4/2018		Analysis Date: 5/10/2018		SeqNo: 1663209		Units: µg/L			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Acenaphthene	ND	10								
Acenaphthylene	ND	10								
Aniline	ND	10								
Anthracene	ND	10								
Azobenzene	ND	10								
Benz(a)anthracene	ND	10								
Benzo(a)pyrene	ND	10								
Benzo(b)fluoranthene	ND	10								
Benzo(g,h,i)perylene	ND	10								
Benzo(k)fluoranthene	ND	10								
Benzoic acid	14	20								J
Benzyl alcohol	ND	10								
Bis(2-chloroethoxy)methane	ND	10								
Bis(2-chloroethyl)ether	ND	10								
Bis(2-chloroisopropyl)ether	ND	10								
Bis(2-ethylhexyl)phthalate	ND	10								

Qualifiers:

*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
D	Sample Diluted Due to Matrix	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	mb-37947		SampType:	MBLK		TestCode:	EPA Method 8270C: Semivolatiles			
Client ID:	PBW		Batch ID:	37947		RunNo:	51189			
Prep Date:	5/4/2018		Analysis Date:	5/10/2018		SeqNo:	1663209	Units:	µg/L	
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
4-Bromophenyl phenyl ether	ND	10								
Butyl benzyl phthalate	ND	10								
Carbazole	ND	10								
4-Chloro-3-methylphenol	ND	10								
4-Chloroaniline	ND	10								
2-Chloronaphthalene	ND	10								
2-Chlorophenol	ND	10								
4-Chlorophenyl phenyl ether	ND	10								
Chrysene	ND	10								
Di-n-butyl phthalate	ND	10								
Di-n-octyl phthalate	ND	10								
Dibenz(a,h)anthracene	ND	10								
Dibenzofuran	ND	10								
1,2-Dichlorobenzene	ND	10								
1,3-Dichlorobenzene	ND	10								
1,4-Dichlorobenzene	ND	10								
3,3'-Dichlorobenzidine	ND	10								
Diethyl phthalate	ND	10								
Dimethyl phthalate	ND	10								
2,4-Dichlorophenol	ND	20								
2,4-Dimethylphenol	ND	10								
4,6-Dinitro-2-methylphenol	ND	20								
2,4-Dinitrophenol	ND	20								
2,4-Dinitrotoluene	ND	10								
2,6-Dinitrotoluene	ND	10								
Fluoranthene	ND	10								
Fluorene	ND	10								
Hexachlorobenzene	ND	10								
Hexachlorobutadiene	ND	10								
Hexachlorocyclopentadiene	ND	10								
Hexachloroethane	ND	10								
Indeno(1,2,3-cd)pyrene	ND	10								
Isophorone	ND	10								
1-Methylnaphthalene	ND	10								
2-Methylnaphthalene	ND	10								
2-Methylphenol	ND	10								
3+4-Methylphenol	ND	10								
N-Nitrosodi-n-propylamine	ND	10								
N-Nitrosodimethylamine	ND	10								

Qualifiers:

* Value exceeds Maximum Contaminant Level.
D Sample Diluted Due to Matrix
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
PQL Practical Quantitative Limit
S % Recovery outside of range due to dilution or matrix

B Analyte detected in the associated Method Blank
E Value above quantitation range
J Analyte detected below quantitation limits
P Sample pH Not In Range
RL Reporting Detection Limit
W Sample container temperature is out of limit as specified

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1805106

07-Jun-18

Client: Andeavor Gallup

Project: 2nd Quarter 2018 Groundwater Sampling (API)

Sample ID	mb-37947		SampType: MBLK		TestCode: EPA Method 8270C: Semivolatiles					
Client ID:	PBW		Batch ID: 37947		RunNo: 51189					
Prep Date:	5/4/2018		Analysis Date: 5/10/2018		SeqNo: 1663209	Units: µg/L				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
N-Nitrosodiphenylamine	ND	10								
Naphthalene	ND	10								
2-Nitroaniline	ND	10								
3-Nitroaniline	ND	10								
4-Nitroaniline	ND	10								
Nitrobenzene	ND	10								
2-Nitrophenol	ND	10								
4-Nitrophenol	ND	10								
Pentachlorophenol	ND	20								
Phenanthrene	ND	10								
Phenol	ND	10								
Pyrene	ND	10								
Pyridine	ND	10								
1,2,4-Trichlorobenzene	ND	10								
2,4,5-Trichlorophenol	ND	10								
2,4,6-Trichlorophenol	ND	10								
Surr: 2-Fluorophenol	92		200.0		45.9	15	114			
Surr: Phenol-d5	62		200.0		31.2	15	97.9			
Surr: 2,4,6-Tribromophenol	180		200.0		90.8	15	161			
Surr: Nitrobenzene-d5	64		100.0		64.0	29.3	120			
Surr: 2-Fluorobiphenyl	65		100.0		65.3	17.5	116			
Surr: 4-Terphenyl-d14	64		100.0		64.3	21	92.2			

Qualifiers:

*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
D	Sample Diluted Due to Matrix	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits
ND	Not Detected at the Reporting Limit	P	Sample pH Not In Range
PQL	Practical Quantitative Limit	RL	Reporting Detection Limit
S	% Recovery outside of range due to dilution or matrix	W	Sample container temperature is out of limit as specified



Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

Sample Log-In Check List

Client Name: ANDEAVOR

Work Order Number: 1805106

RcptNo: 1

Received By: Isaiah Ortiz

5/2/2018 9:20:00 AM

IO

Completed By: Anne Thorne

5/2/2018 11:44:03 AM

Am Th

Reviewed By: ENM

5/3/18

LB: 20

Chain of Custody

1. Is Chain of Custody complete? Yes ☒ No ☐ Not Present ☐
2. How was the sample delivered? Courier

Log In

3. Was an attempt made to cool the samples? Yes ☒ No ☐ NA ☐
4. Were all samples received at a temperature of $>0^{\circ}\text{C}$ to 6.0°C ? Yes ☒ No ☐ NA ☐
5. Sample(s) in proper container(s)? Yes ☒ No ☐
6. Sufficient sample volume for indicated test(s)? Yes ☒ No ☐
7. Are samples (except VOA and ONG) properly preserved? Yes ☒ No ☐
8. Was preservative added to bottles? Yes ☐ No ☒ NA ☐
9. VOA vials have zero headspace? Yes ☒ No ☐ No VOA Vials ☐
10. Were any sample containers received broken? Yes ☐ No ☒
11. Does paperwork match bottle labels?
(Note discrepancies on chain of custody) Yes ☒ No ☐
12. Are matrices correctly identified on Chain of Custody? Yes ☒ No ☐
13. Is it clear what analyses were requested? Yes ☒ No ☐
14. Were all holding times able to be met?
(If no, notify customer for authorization.) Yes ☒ No ☐

of preserved
bottles checked
for pH: 30, 1
(3 or >10 unless noted)
Adjusted? NO
Checked by: IMO

Special Handling (if applicable)

15. Was client notified of all discrepancies with this order? Yes ☐ No ☐ NA ☒

Person Notified:		Date	
By Whom:		Via:	☐ eMail ☐ Phone ☐ Fax ☐ In Person
Regarding:			
Client Instructions:			

16. Additional remarks:

CUSTODY SEALS INTACT ON ALL SAMPLE BOTTLES/at 5/2/18

17. Cooler Information

Cooler No	Temp °C	Condition	Seal Intact	Seal No	Seal Date	Signed By
2	0.4	Good	Yes			

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: **92 Giant Crossing Road**

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)

☐ Other _____

☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)


Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: **0.4**



HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F,Cl,NO ₃ ,NO ₂ ,PO ₄ ,SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals(Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	0920	H ₂ O	EB02	40ml VOA-5	HCl	1805106			X							X				
				250 ml Amber-1	Neat				X											
				250 ml Plastic-1	HNO ₃													X		
				125 ml Plastic-1	HNO ₃													X	X	
				125 ml Plastic-1	H ₂ SO ₄														X	
				125 ml Plastic-1	Neat														X	

Date: 5/1/18	Time: 0700	Relinquished by:	Received by:	Date: 5/2/18	Time: 920
Date:	Time:	Relinquished by:	Received by:	Date:	Time:

Remarks: *** ANALYZE NO₂ & NO₃ FROM THE UNPRESERVED BOTTLE**

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: 92 Giant Crossing Road

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)☐ Other

X EDD (Type) EXCEL

Turn-Around Time:

☒ Standard ☐ Rush

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)

Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: 0.4

[illegible]

Chain-of-Custody Record

Client: **Andeavor****Gallup Refinery**Mailing Address: **92 Giant Crossing Road****Gallup, NM 87301**Phone #: **505-722-0287**email or Fax#: **Jessica.L.Obrien@Andeavor.com**


QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)☐ Other _____☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____Project Name: **2nd Quarter 2018****Groundwater Sampling (API)**

Project #:

Project Manager: **Jessica O'Brien**Sampler: **Tracy Payne**On Ice: ☒ Yes ☐ NoSample Temperature: **0.4****HALL ENVIRONMENTAL
ANALYSIS LABORATORY**

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F, Cl, NO ₃ , NO ₂ , PO ₄ , SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals (Total & Dissolved)	Air Bubbles (Y or N)
4/30/18	1415	H ₂ O	WEST EAST LDU	40ml VOA-5	HCl	1805186 203	X		X										
				250 ml Amber-1	Neat	203			X										
				250 ml Plastic-1	HNO ₃	203												X	
				125 ml Plastic-1	HNO ₃	203												X	
Date:	Time:	Relinquished by:	Received by:	Date	Time	Remarks:													
5/1/18	0700	<i>[Signature]</i>	<i>[Signature]</i>	5/2/18	920														
Date:	Time:	Relinquished by:	Received by:	Date	Time														

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: **92 Giant Crossing Road**

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)

☐ Other _____

☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)


Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: **0.4**



HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's (8021)	BTEX+MTBE+TPH (Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F, Cl, NO ₃ , NO ₂ , PO ₄ , SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals (Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	1430	H ₂ O	FB02	40ml VOA-5	HCl	1805106			X								X			
				250 ml Amber-1	Neat	204			X											
				250 ml Plastic-1	HNO ₃	204												X		
				125 ml Plastic-1	HNO ₃	204												X	X	
				125 ml Plastic-1	H ₂ SO ₄	204													X	
				125 ml Plastic-1	Neat	204													X	

Date: 5/1/18	Time: 0700	Relinquished by: [Signature]	Received by: [Signature]	Date: 5/2/18	Time: 920	Remarks: * ANALYZE NO ₂ & NO ₃ FROM THE UNPRESERVED BOTTLE
Date:	Time:	Relinquished by:	Received by:	Date:	Time:	

Chain-of-Custody Record

Client: **Andeavor****Gallup Refinery**Mailing Address: **92 Giant Crossing Road****Gallup, NM 87301**Phone #: **505-722-0287**email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)☐ Other _____☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____Project Name: **2nd Quarter 2018****Groundwater Sampling (API)**

Project #:


Project Manager: **Jessica O'Brien**Sampler: **Tracy Payne**On Ice: ☒ Yes ☐ NoSample Temperature: **0.4**

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's (8021)	BTEX+MTBE+TPH (Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F, Cl, NO ₃ , NO ₂ , PO ₄ , SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals (Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	1510	H ₂ O	NAPIS-2	40ml VOA-5	HCl	1805106 205			X							X				
				250 ml Amber-1	Neat	205			X											
				250 ml Plastic-1	HNO ₃	205												X		
				125 ml Plastic-1	HNO ₃	205												X	X	
				125 ml Plastic-1	H ₂ SO ₄	205													X	
				125 ml Plastic-1	Neat	205													X	

Date: 5/1/18 Time: 0700 Relinquished by: Received by:  Date: 5/2/18 Time: 920

Date: Time: Relinquished by:

Received by: Date: Time:

Remarks: *** ANALYZE NO₂ & NO₃ FROM THE UNPRESERVED BOTTLE****HALL ENVIRONMENTAL ANALYSIS LABORATORY**

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: **92 Giant Crossing Road**

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)

☐ Other _____

☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)


Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: **0.4**



HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F,Cl,NO ₃ ,NO ₂ ,PO ₄ ,SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals(Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	1540	H ₂ O	KA-3	40ml VOA-5	HCl	1805106			X							X				
				250 ml Amber-1	Neat	tdp			X											
				250 ml Plastic-1	HNO ₃	tdp												X		
				125 ml Plastic-1	HNO ₃	tdp												X	X	
				125 ml Plastic-1	H ₂ SO ₄	tdp													X	
				125 ml Plastic-1	Neat	tdp													X	

Date: **5/1/18** Time: **0700** Relinquished by:

Date: _____ Time: _____ Relinquished by: _____

Received by: Date: **5/2/18** Time: **920**

Received by: _____ Date: _____ Time: _____

Remarks: *** ANALYZE NO₂ & NO₃ FROM THE UNPRESERVED BOTTLE**

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: **92 Giant Crossing Road**

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)

☐ Other _____

☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)


Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: **09**



HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F,Cl,NO ₃ ,NO ₂ ,PO ₄ ,SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals(Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	1605	H ₂ O	NAPIS-3	40ml VOA-5	HCl	1805106			X							X				
				250 ml Amber-1	Neat	207			X											
				250 ml Plastic-1	HNO ₃	207												X		
				125 ml Plastic-1	HNO ₃	207												X	X	
				125 ml Plastic-1	H ₂ SO ₄	207													X	
				125 ml Plastic-1	Neat	207													X	

Date: **5/1/18** Time: **0700** Relinquished by: **[Signature]**

Date: _____ Time: _____ Relinquished by: _____

Received by: **Courier** Date: **5/2/18** Time: **920**

Received by: **[Signature]** Date: _____ Time: _____

Remarks: *** ANALYZE NO₂ & NO₃ FROM THE UNPRESERVED BOTTLE**

Chain-of-Custody Record

Client: **Andeavor****Gallup Refinery**Mailing Address: **92 Giant Crossing Road****Gallup, NM 87301**Phone #: **505-722-0287**email or Fax#: **Jessica.L.Obrien@Andeavor.com**


QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)☐ Other _____☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____Project Name: **2nd Quarter 2018****Groundwater Sampling (API)**

Project #:

Project Manager: **Jessica O'Brien**Sampler: **Tracy Payne**On Ice: ☒ Yes ☐ NoSample Temperature: **0.9****HALL ENVIRONMENTAL
ANALYSIS LABORATORY**

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 504.1)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F, Cl, NO ₃ , NO ₂ , PO ₄ , SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals(Total & Dissolved)	Major Cations/Anions*	CYANIDE	Air Bubbles (Y or N)
4/30/18	16:50	H ₂ O	OAPIS-1	40ml VOA-5	HCl	1805106			X							X					
				1 Liter Amber - 2	Neat	1805106											X				
				250 ml Amber-1	Neat	1805106			X												
				250 ml Plastic-1	HNO ₃	1805106												X			
				125 ml Plastic-1	HNO ₃	1805106												X	X		
				125 ml Plastic-1	H ₂ SO ₄	1805106													X		
				125 ml Plastic-1	Neat	1805106													X		
				500 ml Plastic-1	NAOH	1805106														X	
Date:	Time:	Relinquished by:	Received by:			Date	Time	Remarks: * ANALYZE NO ₂ & NO ₃ FROM THE UNPRESERVED BOTTLE													
5/1/18	0700	[Signature]	I. O. [Signature]			5/02/18	920														
Date:	Time:	Relinquished by:	Received by:			Date	Time														

Chain-of-Custody Record

Client: **Andeavor**

Gallup Refinery

Mailing Address: **92 Giant Crossing Road**

Gallup, NM 87301

Phone #: **505-722-0287**

email or Fax#: **Jessica.L.Obrien@Andeavor.com**

QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)

☐ Other _____

☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____

Project Name: **2nd Quarter 2018**

Groundwater Sampling (API)


Project #:

Project Manager: **Jessica O'Brien**

Sampler: **Tracy Payne**

On Ice: ☒ Yes ☐ No

Sample Temperature: **0.9**



HALL ENVIRONMENTAL ANALYSIS LABORATORY

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL No.	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F,Cl,NO ₃ ,NO ₂ ,PO ₄ ,SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals(Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	1720	H ₂ O	STP-1-NW	40ml VOA-5	HCl	1805106 209			X							X				
				250 ml Amber-1	Neat	209			X											
				250 ml Plastic-1	HNO ₃	209												X		
				125 ml Plastic-1	HNO ₃	209												X	X	
				125 ml Plastic-1	H ₂ SO ₄	209													X	
				125 ml Plastic-1	Neat	209													X	

Date: 5/1/18	Time: 0700	Relinquished by:	Received by:	Date: 5/2/18	Time: 920
Date:	Time:	Relinquished by:	Received by:	Date:	Time:

Remarks: *** ANALYZE NO₂ & NO₃ FROM THE UNPRESERVED BOTTLE**

Chain-of-Custody Record

Client: **Andeavor****Gallup Refinery**Mailing Address: **92 Giant Crossing Road****Gallup, NM 87301**Phone #: **505-722-0287**email or Fax#: **Jessica.L.Obrien@Andeavor.com**


QA/QC Package:

☐ Standard ☒ Level 4 (Full Validation)☐ Other _____☒ EDD (Type) **EXCEL**

Turn-Around Time:

☒ Standard ☐ Rush _____Project Name: **2nd Quarter 2018****Groundwater Sampling (API)**

Project #:

Project Manager: **Jessica O'Brien**Sampler: **Tracy Payne**On Ice: ☒ Yes ☐ NoSample Temperature: **0.4****HALL ENVIRONMENTAL
ANALYSIS LABORATORY**

www.hallenvironmental.com

4901 Hawkins NE - Albuquerque, NM 87109

Tel. 505-345-3975 Fax 505-345-4107

Analysis Request

Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	HEAL NO	BTEX+MTBE+TMB's(8021)	BTEX+MTBE+TPH(Gas only)	TPH 8015B (GRO/DRO/MRO)	TPH (Method 418.1)	EDB (Method 8011)	PAH (8310 or 8270SIMS)	RCRA 8 Metals	Anions (F, Cl, NO ₃ , NO ₂ , PO ₄ , SO ₄)	8081 Pesticides / 8082 PCB's	8260B	8270 (Semi-VOA)	WQCC Metals (Total & Dissolved)	Major Cations/Anions*	Air Bubbles (Y or N)
4/30/18	-	H ₂ O	DUPOZ	40ml VOA-5	HCl	1805106			X							X				
				250 ml Amber-1	Neat	010			X											
				250 ml Plastic-1	HNO ₃	010												X		
				125 ml Plastic-1	HNO ₃	010												X	X	
				125 ml Plastic-1	H ₂ SO ₄	010													X	
				125 ml Plastic-1	Neat	010													X	
4/30/18	-	H ₂ O	TRIP BLANK	40ml VOA-3	HCL	011										X				

Date: 5/1/18	Time: 0700	Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Date: 5/2/18	Time: 920	Remarks: * ANALYZE NO ₂ & NO ₃ FROM THE UNPRESERVED BOTTLE
Date:	Time:	Relinquished by:	Received by:	Date:	Time:	

**Western Refining Southwest LLC**

A subsidiary of Marathon Petroleum Corporation

212 N. Clark St.
El Paso, TX 79905

January 8, 2021

Mr. Kevin Pierard, Chief
New Mexico Environment Department
Hazardous Waste Bureau
2905 Rodeo Park Drive East, Building 1
Santa Fe, New Mexico 87505

**RE: Disapproval
Facility Wide Ground Water Monitoring Work Plan – Updates for 2020
Western Refining Southwest Inc., Gallup Refinery
EPA ID #NMD000333211
HWB-WRG-20-012**

Dear Mr. Pierard,

Attached please find the response to the comments contained in the New Mexico Environment Department (NMED) Disapproval Facility Wide Ground Water Monitoring Plan – Updates for 2020.

If you have any questions or comments regarding the information contained herein, please do not hesitate to contact Mr. John Moore of my staff at 505-879-7643.

Certification

I certify under penalty of law that this document and all attachments were prepared under my direction of supervision according to a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Sincerely,
Marathon Petroleum Company LP, Gallup Refinery

Robert S. Hanks

Robert S. Hanks
Refinery General Manager

Enclosure

cc: D. Cobrain, NMED HWB
M. Suzuki, NMED HWB
C. Chavez OCD
L. King, EPA Region 6
G. McCartney, Marathon Petroleum Company
J. Moore, Marathon Gallup Refinery
H. Jones, Trihydro Corporation

Printed on January 8, 2021

Page 1 of 1

Mr. Kevin Pierard
January 8, 2021
Page 1

New Mexico Environment Department (NMED) Comments:

NMED Comment 1:

In Section 2.1, *Historical and Current Site Use*, page 5, the Permittee states, "[a]s a result of these processing steps, the refinery produces a wide range of petroleum products including propane, butane, unleaded gasoline, diesel, and residual fuel." The ammonium thiosulfate and sulfur recovery units also produce fertilizer product and solid elemental sulfur. The refinery produces commercial products other than petroleum products. Clarify the statement for accuracy in the revised Work Plan.

Marathon Petroleum Company (MPC) Response 1:

Section 2.1 has been revised with the added statement, "The refinery also produces commercial fertilizer product and solid elemental sulfur."

NMED Comment 2:

In Section 2.1, *Historical and Current Site Use*, page 7, and Section 2.3, *Type and Characteristics of the Waste and Contaminants and any Known and Possible Sources*, page 10, the Permittee states, "[n]o waste water is discharged from the refinery to surface waters of the state," and "[d]isposal of waste water into open fields is not practiced at the Gallup Refinery." The *Hydrocarbon Seep interim Measures 2019 1st Quarter Status Report*, dated April 30, 2019, states, "[t]his [reverse osmosis reject water] line transmits approximately 45 gallons per minutes (gpm) of reject from the Boiler House area (near potable water well PW-3) to evaporation pond number 9 (Pond-9)." The evaporation ponds contain surface water and reverse osmosis reject water is waste water; therefore, the statement is not accurate. Clarify the statements for accuracy in the revised Work Plan. If the discharge to Pond-9 already ceased, provide information regarding the current status for how reverse osmosis reject water is handled at the facility in a response letter. Additionally, the title of Section 2.3 (Type and Characteristics of the Waste and Contaminants and any Known and Possible Sources) lacks clarity. Revise the title of Section 2.3 for clarity in the revised Work Plan.

MPC Response 2:

Section 2.1, *Historical and Current Site Use*, has been updated to state, "No waste water is currently discharged from the refinery to surface waters of the state. Historically, reverse osmosis reject water from the Boiler House area was discharged to Evaporation Pond 9."

Presently the refinery is in idle and discharge of reverse osmosis reject water to Pond-9 has ceased. When the refinery restarts operations, a detailed explanation of how the reverse osmosis reject water is handled will be added to the Work Plan.

The title of Section 2.3 was updated to "*Waste Contaminant Types, Characteristics, and Possible Sources*".

NMED Comment 3:

In Section 2.2, *Potential Receptors*, page 8, the Permittee states, "[c]urrently, PW-2 is sampled every three years, PW-4 is sampled semi-annually and PW-3 is sampled on an annual basis." According to Appendix B, *Table 1 Gallup Refinery—Ground Water Monitoring Schedule*, the sampling frequencies for wells PW-3 and PW-4 are indicated as quarterly. Resolve the discrepancy in the revised Work Plan.

Mr. Kevin Pierard
January 8, 2021
Page 2

MPC Response 3:

The text in section 2.2 was revised to match the Appendix B, *Table 1 Gallup Refinery — Ground Water Monitoring Schedule*. The text was updated to state, "Currently, PW-2 is sampled every three years and PW-3 and PW-4 are sampled on a quarterly basis."

NMED Comment 4:

Section 2.4.1, *Separate Phase Hydrocarbons*, page 12, must provide an introductory statement for subsequent discussions (e.g., Section 2.4.1.1 through 2.4.1.5). Provide brief introductory statement under Section 2.4.1 that discusses detections of separate phase hydrocarbons (SPH). Additionally, the subsequent sections discuss detections of SPH in the Main Tank Farm, Hydrocarbon Seep, Aeration Basin, French Drain Release, and Truck Loading Rack areas. However, the Permittee did not include a discussion regarding the detection of SPH in the NAPIS Unit area. SPH has been detected in well NAPIS-1 since 2017. Discuss the detection of SPH in the NAPIS Unit area in the revised Work Plan.

MPC Response 4:

Section 2.4.1, *Separate Phase Hydrocarbons*, has been updated to include the opening statement, "Separate phase hydrocarbons (SPH) have been found in multiple locations within the refinery. These locations include: the Main Tank Farm, Hydrocarbon Seep Area, Aeration Basin, French Drain, Truck Loading Rack, and NAPIS Unit areas."

Section 2.4.1.6, *NAPIS Unit Area*, has been added to the report and states, "SPH has been detected in NAPIS-1 since 2017. The source of the SPH is suspected to be an unspecified release from the refinery."

NMED Comment 5:

In Section 2.4.1.1, *Main Tank Farm*, page 12, the Permittee states, "[i]t is noted that observed SPH measurements may not accurately reflect site conditions." The statement seems to conflict with the purpose of groundwater monitoring. Provide a clarification for why observed SPH measurements may not accurately reflect site conditions in the revised Work Plan.

MPC Response 5:

The text has been revised to provide clarification. Observed SPH measurements potentially overestimates SPH thicknesses in the soil. SPH will enter the well and depress the water table as the SPH tries to equilibrate with the SPH head in the soil column outside the monitoring well. Therefore, if the SPH is not floating on the water table and is, instead, perched in a more permeable layer above the water table, the SPH in the monitoring well will appear to be thicker than the SPH in the surrounding soils. In other words, the SPH will flow into the well, and as long as there is sufficient SPH and pressure head, the SPH will rise within the well to the level of the perched SPH. It may also depress the water table within the monitoring well. The actual thickness of the SPH in the soil column may only be a few inches, but due to the mobility of the SPH, the thickness in the monitoring well may be several feet.

NMED Comment 6:

In Section 2.4.2, *Methyl Tert Butyl Ether*, page 14, the Permittee states, "New Mexico Environmental Department Hazardous Waste Bureau (NMEDHWB) requested two Work Plans to further investigate the known MTBE plume at the Facility and investigate a suspected plume north of the tank farm (SWMU 6)." Multiple MTBE plumes are present at various locations within and beyond the facility. NMED previously directed the Permittee to investigate the extent of MTBE plumes other than the one north of the tank farm. For example, the *[Revised] Work Plan 2015 Annual Groundwater Report NMED*

Mr. Kevin Pierard
January 8, 2021
Page 3

Comments, dated October 2019, states, "[t]o evaluate the potential migration of MTBE within the Sonsela aquifer, an additional well will be located approximately halfway between OW-12 and OW-13," and "to delineate the down-gradient extent of the [MTBE] plume detected at OW-1, a new Sonsela well will be installed approximately five hundred feet down-gradient to the west of OW-1." Include the description of all planned and ongoing MTBE plume investigations directed by NMED in the revised Work Plan.

MPC Response 6:

Section 2.4.2 *Methyl Tert Butyl Ether*, was updated to include the following:

"Additionally, NMED has approved the *Work Plan 2015 Annual Groundwater Report Comments* on January 12, 2020, which includes installing multiple OWs to assess MTBE. A new well is proposed northeast of OW-30 to determine the hydraulic gradient on the east side of the refinery and the lateral extent of MTBE, which has been detected at elevated concentrations in groundwater samples collected from OW-30. An additional well will be installed near OW-13 to address concerns that OW-13 may be a migration pathway for contaminations to move vertically downward to the Sonsela aquifer. OW-13 will be retained at this time to allow for further evaluation. To evaluate the potential migration of MTBE within the Sonsela aquifer, an additional well will be located approximately halfway between OW-12 and OW-13. The proposed locations are shown on Figure 4.2. To delineate the down-gradient extent of the plume detected at OW-1, a new Sonsela well will be installed approximately five hundred feet down-gradient to the west of OW-1. The proposed location is shown on Figure 4.3."

Figures 4.2 and 4.3 have been added to the revised Work Plan to show the locations of the proposed new OW wells.

NMED Comment 7:

In Section 2.4.4, *Aeration Basin*, page 17, the Permittee states, "both GWM-2 and GWM-3 have been included in the Aeration Basin Corrective Action Work Plan which began investigative soil and water sampling near the aeration basin in the third quarter of 2012 to support selection of a remedy for SWMU NO. 1 and determine the source of water detected in GWM-2 and GWM-3. Figure 4 shows the location of all of the active monitoring wells on the facility." Figure 4 does not present the location of SWMU 1 and the purpose of referencing Figure 4 in the statement is not clear. Although Figure 4 presents the location of wells GWM-2 and GWM-3, the former and latter sentences do not appear to connect one another. Provide a clarification in the response letter and revise the statement, as appropriate.

MPC Response 7:

For clarification, the statement referring to Figure 4, in Section 2.4.4, has been removed.

NMED Comment 8:

In Section 2.4.4, *Aeration Basin*, page 17, the Permittee states, "[t]he aeration lagoons and pond 1 (EP-1), are no longer in service." The Permittee did not include the description of more recent activities associated with SWMU 1. The Permittee submitted the *Solid Waste Management Unit 1 Investigation Report*, dated March 31, 2020, which evaluated the extent of excavation associated with SWMU 1, and the submittal is currently under NMED review. In the revised Work Plan, include a discussion of the more recent activities associated with SWMU 1.

Mr. Kevin Pierard
January 8, 2021
Page 4

MPC Response 8:

The following text was added to Section 2.4.4 to include a description of the sampling event that took place in January 2020.

“MPC submitted the *Solid Waste Management Unit 1 Investigation Report* on March 31, 2020, detailing a SWMU No. 1 sampling event that took place the week of January 13, 2020. The sampling was conducted for the purposes of soil and sediment volume determination and chemical characterization for future SWMU 1 excavation, disposal, and closure. In the response titled, *Disapproval SWMU-1 Investigation Report*, dated August 31, 2020, NMED requested a revised report and an additional workplan to further delineate horizontal and vertical extents of contamination in the area of SWMU No. 1. The revised report and response to comments will be submitted by December 31, 2020. A due date from the additional work plan will be determined upon approval of the revised report.”

NMED Comment 9:

In Section 3.0, *Site Conditions*, page 19, the Permittee states, “[t]he surrounding land is comprised primarily of public and private lands used for cattle and sheep grazing.”² The footnote states, “² See, for example, the web site of McKinley County at <http://www.co.mckinley.nm.us/>” The referenced website is not relevant to the statement. Remove the footnote from the revised Work Plan.

MPC Response 9:

The footnote has been removed.

NMED Comment 10:

In Section 3.2, *Drainages*, page 20, the Permittee states, “[a]t the new waste water treatment plant, there are three storm drains located on the south, southwest and west side of the waste water treatment plant which is connected to an underground storm culvert that exits on the northwest section of STP-1 into a conveyance ditch along the northern edge of pond 2 into a holding pond equipped with manual flow valves, located north of evaporation pond 3. The discharge from this holding pond then flows north-northwest towards the Outfall 001 area.” Section 2.4.1.4, *French Drain Release*, page 13, discusses the discovery of SPH at the stormwater drainage ditch south of STP-1 referred as “French Drain”. It is not clear whether the “French Drain” where SPH was discovered is connected to the Outfall 001 area through the stormwater drainage ditch. If SPH in the “French Drain” follows the ditch to the Outfall 001, the entire ditch can be contaminated with SPH. Provide a figure that depicts the location of the “French Drain” and the flow paths to the Outfall 001, as appropriate. Discuss whether an investigation of soil contamination associated with SPH for the ditch from the “French Drain” to the Outfall 001 is warranted in the response letter.

MPC Response 10:

The French Drain flows into a PVC pipe which drains to a frac tank. The fluid (SPH and water) from the frac tank is recovered using a vacuum truck, therefore, the SPH found in the French Drain does not follow the flow path toward Outfall 001 and no additional investigation is necessary. Figure 4.1 has been added to the revised workplan to show the locations of the French Drain and frac tank.

Section 2.4.1.4, *French Drain Release*, has been updated to state, “The drainage ditch fed into a small collection pond that was equipped with a drain valve. The valve was closed and no additional hydrocarbon was discharged from the pond. A catch basin was installed at the discharge point of the PVC pipe and now feeds to a frac tank. Facility personnel utilized a vacuum truck to transfer the discharge from the frac

Mr. Kevin Pierard
January 8, 2021
Page 5

tank back into the Gallup Refinery. The location of the French drain and frac tank are shown on Figure 4.1”.

NMED Comment 11:

In Section 3.5.1, *Soil Types and Associations*, page 21, the Permittee states, "most of the soils found at the surface in the locations where wells are located consist of the Gish-Mentmore complex.³" A footnote is provided to reference the source of the statement on the same page. Since there are several such references, it is more appropriate to create a reference section in the Work Plan and list all citations. Revise the Work Plan accordingly.

MPC Response 11:

A reference section has been added to the revised report and individual footnotes have been removed. In addition, the information in footnote 1 has been added to the text in Section 2.2 *Potential Receptors*, as it should not be included in the reference section.

NMED Comment 12:

In Section 4.0, *Investigation Methods*, page 23, the Permittee states, "Appendix A provides a thorough discussion on actual sampling methods that will be used." Actual field sampling methods must be discussed within the text of the Work Plan (see Permit Section IVI. 2.h). Revise the Work Plan accordingly.

MPC Response 12:

The statement in Section 4.0, *Investigation Methods*, has been revised to say, "Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures*, provides the basis for the investigation methods section that follows."

Information relevant to sample collection from Appendix A that was missing in the Work Plan, has been added to Section 4. Please see redline copy of the report edits.

NMED Comment 13:

In Section 4.1, *Ground Water Sampling Methodology*, page 23, the Permittee states, "Appendices C-2 and C-2.1 include well information for the non-MKTF wells and MKTF wells, respectively. The well information consists of the survey data, screened intervals, and stratigraphic unit in which the wells are screened. Appendix C-3 includes well information for artesian wells also known as Process or Production wells (PW)." Appendices C-2, C-2.1, and C-3 are not included in the Work Plan. Include these appendices in the revised Work Plan.

MPC Response 13:

Appendices C-2, C-2.1, and C-3 have been added to the Work Plan.

NMED Comment 14:

In Section 4.1.2, *Well Purging*, page 24, the Permittee states, "[w]ell purging and sampling will be performed using 1.5-inch x 3 foot and/or 3-inch x 3-foot disposable polyethylene bailers for ground water sampling and/or appropriately decontaminated portable sampling pumps." The Permittee must provide a table that presents a list of wells with a type of sampling device used to collect groundwater samples in future periodic groundwater monitoring reports. No revision is necessary.

Mr. Kevin Pierard
January 8, 2021
Page 6

MPC Response 14:

This comment is acknowledged. A table that presents a list of wells with a type of sampling device used will be added to future reports.

NMED Comment 15:

Section 4.2.1, *Sample Handling*, page 25, and Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Order of Collection*, page 3, lists volatile organic compounds (VOC) first among other analytes. The Permittee has been collecting nitrite samples for laboratory analysis in recent sampling events despite its short holding time. Refer to Comment 12 of NMED's *Approval with Modifications Investigation Report Sanitary Lagoon*, dated April 24, 2020, and Comment 11 of NMED's *Approval with Modifications Annual Ground Water Monitoring Report Gallup Refinery — 2018*, dated January 22, 2020 for references. If laboratory nitrite analysis is feasible for future sampling events, nitrite samples must be collected first in the order to accommodate its short holding time. If field nitrite analysis is conducted using a colorimeter as proposed in the *Response to Disapproval Facility Wide Ground Water Monitoring Work Plan - Updates for 2019*, dated September 11, 2019, include a section that discusses procedures for the field nitrite analysis in the revised Work Plan. Revise the Work Plan accordingly.

MPC Response 15:

Daily couriers were arranged with the lab to ensure that nitrate/nitrite holding times were met during 3rd quarter sampling. The order in which samples are collected have not been updated in the text, as samples were delivered to the lab within 24 hours. In addition, collecting nitrate/nitrite last gives more time to meet holding requirements. Collection of samples with short holding times are done in an effort to collect near the shipping pick up times to provide as much time as possible for the lab to process. At this time, field kits are not deemed necessary and Appendix E, *Field Method for Nitrite Analysis*, has been removed from the text.

NMED Comment 16:

In Section 4.4.6.1, *Blanks*, page 30, the Permittee states, "If contaminants are detected in field or laboratory blanks, the sample data will be qualified, as appropriate." The data quality must be discussed, and the implications must be identified if such data are qualified rather than rejected. Revise the Work Plan accordingly.

MPC Response 16:

Section 4.4.6.1, *Blanks*, has been revised to state, "If contaminants are detected in field or laboratory blanks, the sample data will be qualified or rejected, as appropriate. Methods and reasoning for the decision to qualify or reject sample data will be discussed in the Annual Groundwater Report. Furthermore, any impact to data quality and/or need to adjust methods will be addressed in the report."

NMED Comment 17:

Section 6.0, *Monitoring Program Revisions*, page 35, does not reference NMED's comments that directed revisions to the monitoring program. For example, Comment 12 of NMED's *Approval with Modifications Annual Ground Water Monitoring Report Gallup Refinery — 2018*, dated January 22, 2020, states, "If the causes are not known and the chromium level did not decline in 2019, include hexavalent chromium analysis for the groundwater samples collected from well NAPIS-2 in the two subsequent sampling events in 2020." Hexavalent chromium analysis for the groundwater samples collected from well NAPIS-2 is not proposed in Appendix B — Table 2, *Gallup Refinery — Requested/Approved Changes to the Ground Water Monitoring Schedule* or in Section 6.0. Section 6.0 must reference Comment 12 of the January 22,

Mr. Kevin Pierard
January 8, 2021
Page 7

2020 *Approval with Modifications* and include a discussion for why hexavalent chromium analysis was not proposed at this time. Reference all relevant NMED's comments that directed revisions to the monitoring program and provide a discussion in the revised Work Plan.

MPC Response 17:

The referenced chromium exceedance was an incorrect entry and the actual result for chromium is <0.006 mg/l. This error was addressed in *MPC Response to Comment 12, Response to Approval with Modifications Annual Ground Water Monitoring Report – 2018*, dated March 23, 2020.

NMED Comment 18:

Figure 5, *Sonsela Water Elevation Map — 2020*, presents the potentiometric surface for the Sonsela aquifer. Wells MW-1, MW-2, MW-4, MW-5, BW-1C, BW-2C, BW-3C, BW-5C, OW-01, OW-10, OW-11, OW-12, and OW-1 were presented; however, the groundwater elevation data for these wells were not included in the figure. Include the elevation data in the revised figure. In addition, the date on the figure is indicated as March 27, 2020. However, it is not clear whether the date represents actual gauging date or preparation date for the figure. Indicate the date when the gauging data was collected in the revised figure.

MPC Response 18:

Figure 5 has been updated to include elevation data and the gauging date has been added to the description.

NMED Comment 19:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Field Data Collection, Elevation and Purging*, page 1, the Permittee states, "Gallup does not have any recovery well pumps that need to be shut off and removed prior to water elevation measurements." Groundwater recovery pumps were installed in wells RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55 in August 2019. Comment 13 of the January 22, 2020 *Approval with Modifications* states, "since the groundwater level was depressed due to the fluid recovery operation, the Permittee must halt the pumping operation at least 48 hours prior to conducting depth measurements in these wells. Include the provision in the future groundwater monitoring events." These pumps must be shut off prior to water elevation measurements as required by Comment 13 of the letter. Revise the Work Plan accordingly.

MPC Response 19:

Appendix A have been updated to state, "There are groundwater recovery pumps installed in wells RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55, but they are inactive at this time. If MPC resumes recovery operations with these pumps, they must halt the pumping operation at least 48 hours prior to conducting depth measurements in these wells."

NMED Comment 20:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures Field Data Collection, Elevation and Purging*, page 1, the Permittee states, "the portable pump intake is lowered to the midpoint of the listed screened interval for each specific well using the markings identified on the pump hose which are set every ten feet." The pump hose is marked every ten feet to set the intake at the midpoint of screened intervals. A ten-foot increment on the hose may not allow accurate enough placement to position the pump intake at the midpoint of screened intervals. The increment must be small enough (e.g., one-foot) to allow more accurate placement. Revise the Work Plan accordingly.

Mr. Kevin Pierard
January 8, 2021
Page 8

MPC Response 20:

Appendix A has been updated to state, "The portable pump intake is lowered to the midpoint of the listed screened interval for each specific well using the markings identified on the pump hose which are set at one-foot intervals."

NMED Comment 21:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Field Data Collection, Elevation and Purging*, page 1, the Permittee states, "field water quality parameters measured during purging (pH, electrical conductivity, temperature, and dissolved oxygen), must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples from each well." Clarify whether purging is considered complete when one or all of these criteria is met in the revised Work Plan.

In addition, Section 4.1.2, *Well Purging*, page 24, includes oxidation-reduction potential (ORP) as one of stabilization criteria in addition to the water quality parameters listed in Appendix A. ORP readings must be included as one of stabilization criteria. The pH, electrical conductivity, temperature, dissolved oxygen, ORP data must be collected from all groundwater monitoring wells. Resolve the discrepancy in the revised Work Plan accordingly.

MPC Response 21:

Appendix A has been updated to state, "Field water quality parameters measured during purging are pH, electrical conductivity, temperature, dissolved oxygen (DO), and oxidation-reduction potential (ORP). One or more parameters must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples utilizing low-flow sampling techniques. When purging wells using a bailer, bailing will be considered complete when 3 well volumes have been removed from the wells. Field parameters will be measured and recorded while bailing, with the understanding that the process of hand-bailing may prevent stabilization of field parameters."

The discrepancy between Section 4.1.2 and Appendix A has been resolved with the preceding statement.

NMED Comment 22:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Field Data Collection, Elevation and Purging*, page 2, the Permittee states, "[t]he water level in the well, total depth of well and thickness of floating product (if any) will be measured using an oil/water interface meter. If product is present, a ground water sample is not obtained." Provide information regarding specific product thickness that allows or prevents groundwater sample collection in the revised Work Plan.

MPC Response 22:

For clarification, the statement has been revised to state, "If any product is present, regardless of thickness, a ground water sample is not obtained."

NMED Comment 23:

Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Sampling Equipment at Gallup Refinery*, pages 2 and 3, lists sampling equipment to be maintained in the facility. However, the list does not include an instrument for ORP, TDS and salinity measurements, nitrite field testing kit, or coarse (1.0 µm) filters for turbid waters as required by previous NMED correspondence.

Mr. Kevin Pierard
January 8, 2021
Page 9

Explain if the equipment will be maintained at the facility or provided by contractors in the revised Work Plan.

MPC Response 23:

Both the YSI and the IQ Scientific Instruments field parameter instruments, available onsite, measure all required parameters (pH, temperature, conductivity, TDS, salinity, DO, and ORP). Appendix A has been updated to include a parameter list for each instrument. While there are Hach Nitrate-Nitrite Test Kits onsite, shipping has been arranged with the lab so that they will not be necessary to maintain at the facility. An attempt has been made to obtain Pall Corporation Acro 50A 1.0 micron disposable filters, but the 50A series of filters has been discontinued. Sampling will be completed in the 4th quarter using the remaining 0.45 micron filters and alternate equipment and/or vendor will be proposed in the 2021 Groundwater Work Plan.

NMED Comment 24:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Filtration*, page 3, the Permittee states, "[t]he syringe is then used to force the sample water through a 0.45 micron pore filter into the proper sample bottle to collect dissolved metals samples." Refer to Comment 9 of NMED's January 22, 2020 *Approval with Modifications* for the direction how to handle groundwater samples with high level of total suspended solids. Use the sequential filtration process (e.g., 100 to 45 um filter) for dissolved metals sampling, where applicable. Include the provision in the revised Work Plan.

MPC Response 24:

An attempt has been made to obtain Pall Corporation Acro 50A 1.0 micron disposable filters, but the 50A series of filters has been discontinued. Sampling will be completed in the 4th quarter using the remaining 0.45 micron filters and alternate equipment and/or vendor will be proposed in the 2021 Groundwater Work Plan. Any deviations from using the 0.45 micron filters (i.e., run out of the remaining filters) will be discussed in the *Annual Ground Water Monitoring Report Gallup Refinery – 2020*.

NMED Comment 25:

In Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, Filtration*, page 4, the Permittee states, "[s]ampling personnel carry a cell phone when gathering ground water and other water samples. While sampling procedures are generally well known and the appropriate sample bottles are ordered to match each sampling event, occasional questions do arise from unforeseen circumstances which may develop during sampling. At such times, sampling personnel contact Hall Environmental Analytical Laboratory to verify that sampling is correctly performed." It is not clear under what circumstances personnel would call a laboratory to receive instructions during sampling events. Provide examples for the situation where personnel must call a laboratory amid sampling in the revised Work Plan.

MPC Response 25:

An example where personnel must call a laboratory would be if a well has run dry short of filling the last sample bottle and needing to know if enough water has been collected for analysis. The statement, "Examples would be if a well were to run dry short of filling the last sample bottle or to determine if there is enough water for sample analysis" has been added to the revised Work Plan.

Mr. Kevin Pierard
January 8, 2021
Page 10

NMED Comment 26:

Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures, General Well Sampling Procedures*, page 5, describes sampling procedures in a manner which appears to be directions for field personnel. Note that the Work Plan is submitted for NMED's formal review. Revise the Work Plan to describe the sampling procedures in a manner that does not constitute instructions.

MPC Response 26:

The sections, *General Well Sampling Procedures*, has been revised.

NMED Comment 27:

Appendix B includes *Table 1, Gallup Refinery— Ground Water Monitoring Schedule*, and *Table 2, Gallup Refinery — Requested/Approved Changes to the Ground Water Monitoring Schedule*. These tables do not include page numbers. Include page numbers in the revised tables.

MPC Response 27:

Page numbers have been added to the tables in Appendix B.

NMED Comment 28:

Appendix B, *Table 2, Gallup Refinery — Requested/Approved Changes to the Ground Water Monitoring Schedule*, and Appendix E, *Field Methods for Nitrite Analysis*, are included in the Work Plan; however, these appendices are not referenced within the text of the Work Plan. These appendices must be referenced in relevant sections and a discussion must be provided within the text of the Work Plan. Revise the Work Plan accordingly.

MPC Response 28:

This comment was addressed in MPC Response 15.

NMED Comment 29:

In Appendix C-1, *2019 Fluid Level Measurements*, page 8 of 8, the stratigraphic unit for the screened interval of well SMW-2 is not legible. Present a legible description in the revised Work Plan.

MPC Response 29:

The stratigraphic unit for the screened interval of well SMW-2 has been corrected in the revised report and is now clearly legible.

NMED Comment 30:

Appendix C-1, *2019 Fluid Level Measurements*, indicates that some wells were not gauged in 2019 due to the presence of elevated hydrogen sulfide gas in the ambient air. Comment 3 of NMED's *Approval with Modifications Annual Ground Water Monitoring Report Gallup Refinery —2018*, dated January 22, 2020, states, "[t]he Permittee must conduct the required sampling and change the scheduled sampling dates as necessary, if the H₂S concentrations are too high to allow personnel to conduct the sampling event on the scheduled sampling timeframe." The Permittee must collect required data from these wells in future gauging and sampling events. Reference the NMED's direction and include the provision in the revised Work Plan.

Mr. Kevin Pierard
January 8, 2021
Page 11

MPC Response 30:

The statement, "If samples cannot be collected from a location due refinery activity or environmental concerns, such as elevated H₂S, arrangements will be made to collect samples from the affected location(s) during the next sampling or gauging event" has been added to Section 5.0, Monitoring and Sampling Program, to address the issue of missing sample due to elevated H₂S.

Attachment A: Clean IWP Report



**Marathon
Petroleum Company LP**

Facility Wide Ground Water Monitoring Work Plan – Updates for 2020

**Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301
(505) 722-3833**

Submitted: April 8, 2020



Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision according to a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Robert S. Hanks
Refinery General Manager

Date

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

Executive Summary

Western Refining Southwest, Inc. conducts quarterly, semi-annual and annual ground water monitoring at its Gallup Refinery on a site wide basis. The Ground Water Monitoring Work Plan (Plan) documents any additions or revisions in ground water monitoring and also details the sampling procedures used.

This Plan divides the facility into six monitoring groups. Group A consists of the boundary wells situated along the northwest corner of the refinery property and monitoring wells around the land treatment area (LTU). Group B consists of a cluster of wells at the aeration basin and at the sanitary treatment pond 1 (STP-1) near the Waste Water Treatment Unit. Group C consists of the observation wells on the northeast section of the refinery including four product recovery wells. One new well (OW-58A) was installed in this area in 2019. Group D includes the process/production wells and the four observation wells located on the south-southwest section of the property. Group E includes 49 permanent monitoring wells installed to delineate the extent of a hydrocarbon plume associated with a seep discovered in 2013 directly west of the crude tanks (T-101, 102) and more recently any other potential releases within this area; included in this group is a pre-existing well located directly west of the truck loading terminal. Five new wells (MKTF-46, MKTF-47, MKTF-48, MKTF-49, and MKTF-50) were installed in this area in 2019. Group F includes the sampling requirements for the evaporation ponds and effluent from the sanitary treatment pond (STP-1).

The Gallup Refinery will periodically review facility-wide monitoring data and assess the monitoring program presented in this Plan. Revisions to the Plan, as necessary, will then be presented annually for agency review and approval. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target chemicals to be analyzed.

The Gallup Refinery follows the most current approved sampling/monitoring schedule from NMED: *Approval with Modifications Revised Facility-Wide Ground Water Monitoring Work Plan, Gallup Refinery – Updates for 2019*, HWB WRG 19-012, dated November 15, 2019.

Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

The Gallup Refinery has created a monitoring work plan with quality assurance practices and controls as well as standard procedures for sampling, and a schedule of activities to monitor ground water and surface water at select locations of the Gallup Refinery. The persons responsible for the implementation and oversight of this plan are:

Refinery General Manager

- Robert S. Hanks

Remediation Project Manager

- John Moore

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP****TABLE OF CONTENTS**

Executive Summary	iii
1.0 Introduction.....	1
1.1 Scope of Activities	1
1.2 Facility Ownership and Operation	2
2.0 Background Information.....	4
2.1 Historical and Current Site Use	4
2.2 Potential Receptors.....	8
2.3 Waste Contaminant Types, Characteristics, and Possible Sources	9
2.4 Summary of contaminant releases that could contribute to possible ground water contamination.....	12
2.4.1 Separate Phase Hydrocarbons.....	12
2.4.2 Methyl Tert Butyl Ether	15
2.4.3 NAPIS Unit	16
2.4.4 Aeration Basin	16
2.4.5 North Drainage Ditch	19
2.4.6 OW-14 Source Area.....	19
3.0 Site Conditions.....	20
3.1 Current site topography and location of natural and manmade structures	20
3.2 Drainages	20
3.3 Vegetation types	21
3.4 Erosion features	22
3.5 Subsurface conditions.....	22
3.5.1 Soil types and associations	22
3.5.2 Stratigraphy.....	22
3.5.3 Presence and flow direction of ground water	23
4.0 Investigation Methods.....	24
4.1 Ground Water Sampling Methodology.....	24
4.1.1 Well Gauging.....	24
4.1.2 Well Purging.....	25
4.2 Ground Water Sample Collection	26
4.2.1 Sample Handling	26
4.2.2 General Well Sampling Procedures	27
4.3 Analytical Methods	30
4.4 Quality Assurance Procedures	30
4.4.1 Equipment Calibration Procedures and Frequency.....	31
4.4.2 Field QA/QC Samples	31
4.4.3 Laboratory QA/QC Samples	32
4.4.4 Laboratory Deliverables.....	32

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

4.4.5 Review of Field and Laboratory QA/QC Data	33
4.4.6 Blanks, Field Duplicates, Reporting Limits and Holding Times	34
4.4.7 Representativeness and Comparability	35
4.4.8 Laboratory Reporting, Documentation, Data Reduction, and Corrective Action	36
5.0 Monitoring and Sampling Program	37
5.1 Group A Through Group F Sampling Locations.....	37
5.1.1 Sampling Locations	37
5.2 Evaporation Ponds, Outfalls	38
5.2.1 Sampling Locations	38
6.0 Monitoring Program Revisions.....	39
6.1 Requests for Modifications to Sampling Plan.....	39

List of Figures

Figure 1: Regional Map
 Figure 2: Topographic Map
 Figure 3: Generalized Relationship of Soils
 Figure 4: Facilities and Well Groups – 2020
 Figure 4.1: French Drain Location
 Figure 4.2: Proposed Monitoring Well Locations
 Figure 4.3: Proposed Monitoring Well Location
 Figure 5: Sonsela Water Elevation Map - 2020
 Figure 6: 2020 Alluvium/Chinle Gp Interface Water Elevation Map
 Figure 7: Stormwater Pollution Prevention Plan – Site Plan

List of Appendices

Appendix A: Gallup Refinery Field Sampling Collection and Handling Standard Procedures
 Appendix B: 2020 Ground Water Monitoring Schedule
 Appendix C: Well Data Tables, C-1, C-2, C-3
 Appendix D: Well Boring Logs
 Appendix E: Field Methods for Nitrite Analysis

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

List of Acronyms

AL	Aeration Lagoon
API	American Petroleum Institute
BMP	Best Management Practices
BS	Blank Spike
BSD	Blank Spike Duplicate
BTEX	Benzene, Toluene, Ethylbenzene, Xylene
CFR	Code of Federal Regulations
DQO	Data Quality Objective
DRO	Diesel Range Organics
DTB	Depth to Bottom
DTW	Depth to Water
EP	Evaporation Pond
EPA	Environmental Protection Agency
FT.	Foot
FWGWMP	Facility Wide Ground Water Monitoring Plan
GPM	Gallons per minute
GRO	Gasoline Range Organics
HNO ₃	Nitric Acid
HWB	Hazardous Waste Bureau
IDW	Investigation Derived Waste
LDU	Leak Detection Unit
LTU	Land Treatment Unit
ML	Milliliter
MCL	Maximum Contaminant Level
MS	Matrix Spike
MSD	Matrix Spike Duplicate
MTBE	Methyl Tert Butyl Ether
NAICS	North American Industry Classification System

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

List of Acronyms – Continued

NAPIS	New American Petroleum Institute Separator
NMAC	New Mexico Administrative Code
NMED	New Mexico Environment Department
NOI	Notice of Intent
OAPIS	Old American Petroleum Institute Separator
OW	Observation Well
OCD	Oil Conservation Division
ORP	Oxidation-Reduction Potential
PPE	Personal Protective Equipment
PPM	Parts per million
PSTB	Petroleum Storage Tank Bureau
PVC	Polyvinyl Chloride
PW	Process Well
QA	Quality Assurance
QC	Quality Control
RW	Recovery Well
RCRA	Resource Conservation and Recovery Act
SIC	Standard Industrial Classification
SOP	Standard Operating Procedure
SPH	Separate Phase Hydrocarbon
STP	Sanitary Treatment Pond
SVOC	Semi-volatile Organic Compound
SWMU	Solid Waste Management Unit
SWPP	Storm Water Pollution Prevention Program
TOC	Total Organic Content
VOC	Volatile Organic Compound
WQCC	Water Quality Control Commission
WWTP	Waste water treatment plant

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



1.0 Introduction

This Facility-Wide Ground Water Monitoring Work Plan (Plan) has been prepared for the implementation of a ground water monitoring program at the Gallup Refinery owned by Marathon Petroleum Company (MPC) and operated by Western Refining Southwest, Inc. ("Gallup Refinery," "Refinery," or "Facility").

1.1 Scope of Activities

This Plan has been prepared to collect data that will be used to characterize the nature and extent of potential impacts to ground water at the Gallup Refinery. The monitoring plan is designed to assist in evaluating any levels of contaminants that exceed compliance standards. This Plan divides the facility into six groups for periodic monitoring:

<u>GROUP A</u>	<u>GROUP B</u>	<u>GROUP C</u>	<u>GROUP D</u>	<u>GROUP E</u>	<u>GROUP F</u>
BW-1A, 1B, 1C	GWM-1, 2, 3	OW-13, 14, 29, OW-30	PW-2, 3, 4	MKTF-01 thru MKTF-50	EP-2, 3, 4, 5, 6, 7, 8, 9
BW-2A, 2B, 2C	NAPIS 1, 2, 3, KA-3, OW-62	OW-50, 52, 53, OW-54, 55, 56, OW-57, 58, OW-58A, 61, OW-63, 64, 65	OW-1, 10		EP-11, 12A, 12B
BW-3A, 3B, 3C BW-4A, 4B BW-5A, 5B, 5C	OAPIS-1 OW-59, 60	RW-1, 2, 5, 6	OW-11, 12		STP-1 to EP- 2, Boiler Water Inlet to EP-9
MW-1, 2, 4, 5	LDU (3)				
SMW-2, 4	STP1-NW, SW				

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Group A consists of the boundary wells situated along the northwest corner of the refinery property and the monitoring wells around the land treatment unit (LTU). Group B consists of a cluster of monitoring wells and leak detection units for the NAPIS at the aeration basin and at the sanitary treatment pond. Group C includes the observation wells located on the northeast section of the plant and includes recovery wells from which small quantities of free product has been continually removed. Group D includes the process/production wells and four observation wells located on the south, southwest section of the refinery property. Group E includes a total of 49 monitoring wells installed to delineate a hydrocarbon plume associated with a seep discovered west of the crude tank (Tank 101); included in this group is a pre-existing well located directly west of the truck loading terminal. Group F includes sampling requirements for the evaporation ponds and for the effluent from the sanitary treatment pond. Designated wells and sample points identified are monitored on a quarterly, semi-annual and annual basis following the procedures presented in this Plan.

The Gallup Refinery periodically reviews facility-wide monitoring data and evaluates the monitoring program presented in this Plan. Annual revisions to the Plan will be presented for agency review and approval. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target chemicals to be analyzed.

1.2 Facility Ownership and Operation

This Plan pertains to the Gallup Refinery located at Exit 39 on Interstate I-40. This refinery is located at Jamestown, New Mexico, approximately 17 miles east of Gallup. Figure 1 shows the regional location of the Gallup Refinery.

The owner is:

Marathon Petroleum Company (Parent Corporation)
539 South Main Street
Findlay, OH 45840

Operator: Western Refining Southwest Inc. (Postal Address)
Gallup Refinery
92 Giant Crossing Road
Gallup, New Mexico 87301

Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Western Refining Southwest Inc. (physical address)
Gallup Refinery
I-40, Exit 39 (17 Miles East of Gallup, NM)
Jamestown, New Mexico 87347

The following regulatory identification and permit governs the Gallup Refinery:

- SIC code 2911 (petroleum refining) and NAICS code 32411 apply to the Gallup Refinery;
- U.S. EPA ID Number NMD000333211;
- New Mexico OCD Abatement Plan Number AP-111; and
- 2015 NPDES MSGP, ID #NMR053168.

The facility status is corrective action/compliance. Quarterly, semi-annual and annual ground water sampling is conducted at the facility to evaluate present contamination.

The refinery is situated on an 810-acre irregular shaped tract of land that is largely located within the lower one quarter of Section 28 and throughout Section 33 of Township 15 North, Range 15 West of the New Mexico Prime Meridian. A small component of the property lies within the northeastern one quarter of Section 4 of Township 14 North, Range 15 West. Figure 2 is a topographic map showing the general layout of the refinery in comparison to the local topography.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



2.0 Background Information

2.1 Historical and Current Site Use

Built in the 1950's, the Gallup Refinery is located within a rural and sparsely populated section of McKinley County in Jamestown, New Mexico, 17 miles east of Gallup, New Mexico. The setting is a high desert plain on the western slope of the Continental Divide. The nearest population centers are the Pilot Flying J Travel Center (Travel Center) refueling plaza, the Interstate 40 highway corridor, and a small cluster of residential homes located on the south side of Interstate 40 approximately 2 miles southwest of the refinery (Jamestown). The surrounding land is comprised primarily of public lands and is used for cattle and sheep grazing.

The refinery is currently idled. When the refinery is operating, it primarily receives crude oil via two 6-inch diameter pipelines from the Four Corners Area, which enter the refinery property from the north. In addition, the refinery also received natural gasoline feed stock via a 4-inch diameter pipeline that comes in from the west along the Interstate 40 corridor from the Western Refining Southwest, Inc. - Wingate Plant (formerly Conoco gas plant). Crude oil and other products also arrived at the site via railroad cars. These feed stocks were then stored in tanks until refined into products.

The Gallup Refinery is a crude oil refining and petroleum products manufacturing facility. The Standard Industrial Classification (SIC) code is 2911 and the North American Industry Classification System Code (NAICS) is 32411. There are no organic chemicals, plastics, or synthetic fibers manufactured that contribute to our process flow of waste water. The Gallup Refinery does not manufacture lubricating oils.

The refinery incorporates various processing units that convert crude oil and natural gasoline into finished products. These units are briefly described as follows.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



- Crude Distillation Unit - separates crude oil into various fractions; including gas, naphtha, light oil, heavy oil, and residuum.
- Fluidized Catalytic Cracking Unit (FCCU) - dissociates long-chain hydrocarbon molecules into smaller molecules, and essentially converts heavier oils into naphtha and lighter oils.
- Alkylation Unit - combines specific types of hydrocarbon molecules into a high-octane gasoline blending component.
- Reforming Unit - breaks up and reforms low octane naphtha molecules to form high octane naphtha.
- Hydro-Treating Unit - removes undesirable sulfur and nitrogen compounds from intermediate feed stocks, and also saturates these feed stocks with hydrogen to make diesel fuel.
- Treater Unit - removes impurities from various intermediate and blending feed stocks to produce finished products that comply with sales specifications.
- Ammonium Thiosulfate Unit - accepts high H₂S and ammonia containing gas streams from the Amine and the Sour Water Stripper units, and converts these into a useful fertilizer product, ammonium thiosulfate.
- Sulfur Recovery Unit - converts and recovers various sulfur compounds from the gases and liquids produced in other processing units to create a solid elemental sulfur byproduct.
- Waste Water Treatment Plant - processes and treats refinery waste and storm water before releasing to treatment ponds.

As a result of these processing steps, the refinery produces a wide range of petroleum products including propane, butane, unleaded gasoline, diesel, and residual fuel. The refinery also produces commercial products of fertilizer and solid elemental sulfur. In addition to the aforementioned processing units, various other equipment and systems support the operation of the refinery and are briefly described as follows.

Storage tanks are used throughout the refinery to hold and store crude oil, natural gasoline, intermediate feed stocks, finished products, chemicals, and water, which are all located above ground. Capacity of these tanks range in size from 80,000 barrels to less than 1,000 barrels.

Pumps, valves, and piping systems are used throughout the refinery to transfer various liquids among storage tanks and processing units. A railroad spur track and a railcar loading rack are used to transfer feed stocks and products from refinery storage tanks into and out of railcars. Several tank truck loading racks are used at the refinery to load out finished products and also receive crude oil, other feed stocks, additives, and chemicals.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Gasoline and diesel are delivered to the Travel Center via tanker truck. An underground diesel pipeline exits between the refinery and the Travel Center. In 2013 the underground diesel line from Gallup Refinery to the Travel Center was replaced and put back in service on February 3, 2014, but was subsequently removed from service. The replaced line runs above ground from the marketing area of the refinery for approximately 150 feet and continues underground to the Travel Center.

A firefighting training facility is used to conduct employee firefighting training. Waste water from the facility, when training is conducted, is pumped into a tank which is then pumped out by a vacuum truck. The vacuum truck pumps the oily water into a process sewer upstream of the New API Separator (NAPIS).

The process waste water system is a network of curbing, paving, catch basins, and underground piping used to collect waste water from various processing areas within the refinery. The waste water effluent then flows into the equalization tanks and the NAPIS where the oil is separated from water based on the principle that, given a quiet surface, oil will float to the water surface where it can be skimmed off. The skimmed slop is passed to a collection chamber where it is pumped back into the refinery process. The clarified water is routed to a waste water treatment plant (WWTP) where benzene is removed via granular activated carbon (GAC) canisters that are placed at the effluent of the dissolved gas flotation (DGF) unit. WWTP operations alternate the configuration of these GAC canisters from a single setup to an in-series setup (i.e. primary and secondary canister). To help monitor the breakthrough of these GAC canisters, several waste water samples are taken at the effluent of the last GAC canister. Results from benzene analysis of the waste water samples are monitored to manage the breakthrough from the GAC canisters. When benzene values exceed 0.4 ppm, one or more of the following actions are taken: GAC canister configuration is modified to an in-series set-up; GAC canister is replaced with fresh carbon; GAC canister effluent is recirculated back through the WWTP. The treated water flows from the GAC canisters into pond STP-1. STP-1 consists of two bays, north and south and each bay is equipped with five aerators per bay. Effluent from STP-1 then flows into Evaporation Pond 2 and gravitated to the rest of the ponds.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



During episodes of unit upsets or major storm events, the waste water is held in one of the three equalization tanks, T-35, T-27 and T-28 which are used to handle large process and storm water flows allowing the flow to the NAPIS to be controlled. These tanks are also used to store waste water if problems are encountered with the downstream equipment, i.e., NAPIS and the WWTP.

The storm water system is a network of valves, gates, berms, embankments, culverts, trenches, ditches, natural arroyos, and retention ponds that collect, convey, control, and release storm water that falls within or passes through refinery property. Storm water that falls within the processing areas is considered equivalent to process waste water and is sent to tanks T-35, T-27 and T-28 when needed before it reaches the NAPIS, WWTP, STP-1 and into Evaporation Pond 2 where flow is gravitated to the rest of the ponds. Storm water discharge from the refinery is very infrequent due to the arid desert-like nature of the surrounding geographical areas.

At the evaporation ponds, waste water is converted into vapor via solar and mechanical wind-effect evaporation via two 80 gallons per minute electrically driven evaporation pond spraying snow machines located between ponds 4 and 5. Two additional 66 GPM (gallons per minute) evaporation pond sprayers were installed in October 2014 between ponds 3 and 4 for a total of four evaporators. No waste water is currently discharged from the refinery to surface waters of the state. Historically, reverse osmosis reject water from the Boiler House area was discharged to Evaporation Pond 9. In September 2015, Gallup Refinery submitted a Notice of Intent requesting continued coverage under the 2015 NPDES Multi-Sector General Permit which was approved on October 8, 2015 (NMR053168). The refinery maintains a Storm Water Pollution Prevention Plan (SWPPP) that includes Best Management Practices (BMPs) for effective storm water pollution prevention (updated September 2015). The refinery has constructed several new berms in various areas and improved outfalls (installed barrier dams equipped with gate valves) to minimize the possibility of potentially impacted runoff leaving the refinery property and also to minimize the stormwater run-on from the I-40 interchange and the Travel Center onto refinery property.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

2.2 Potential Receptors

Potential receptors at the facility also include those that may arise from future land uses. Currently, these include on-site workers, nearby residents, wildlife, and livestock. There is extensive and regular 24-hour patrolling by facility security personnel; therefore, the refinery can discount the possibility of an inadvertent or deliberate intruder becoming exposed to contamination in groundwater that has reached the surface in some form. The major route to exposure of humans would be from contaminants reaching a drinking water well. Other routes could be from showering, cooking, etc. with contaminated ground water, raising crops and vegetables with contaminated ground water, or getting exposed to or fishing in surface water that has commingled with shallow ground water. Exposure can also occur through contact with soils and/or plants that have become contaminated through contact with contaminated ground water. However, drinking water wells remain the primary route of possible exposure.

At this time, the nearest drinking water wells are located on-site at the southwest areas of the facility, at depths of approximately 1000 feet which are identified as process or production (PW) wells. These wells are designated as PW-2, PW-3, and PW-4 (See Figure 4 for location). These wells are operated by the facility to provide the refinery's process water and drinking water to nearby refinery-owned houses, to the refinery itself, and to the Travel Center. Currently, PW-2 is sampled every three years and PW-3 and PW-4 are sampled on a quarterly. The chemical analyses of these and all of the other water samples collected under this Work Plan are discussed in the Annual Facility-Wide Groundwater Monitoring Reports. Annual sampling results from 2009 through 2019 have indicated concentrations above screening levels of sulfate in samples collected at PW-3, a single detection of iron in a sample collected at PW-4, a single detection of Tetrachloroethene in a sample collected from PW-2, a single detection of phenol in a sample collected at PW-3, and two detections of bis(2-ethylhexyl phthalate) at PW-4. The chemical analyses of these and all of the other water samples collected under this Work Plan are discussed in the Annual Facility-Wide Groundwater Monitoring Reports.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Other than the on-site wells, there is no known drinking water wells located within a 4-mile radius of the site. The nearest drinking water wells that could be used by off-site residents are located to the northwest of the site at a distance slightly greater than 4-miles located within the Navajo community of Iyanbito (shown on the USGS Topographical Map - Gallup Quadrangle [Revised 1980]). These wells are northwest of the South Fork of the Puerco River which, flows towards the southwest from immediately north of the facility. The Cibola National Forest lies in the south-east direction and there are no wells or residents in this protected area.

Artesian conditions at some locations of the site lead to the possibility of ground water emerging onto the surface and thus being able to affect wildlife. No surface water on the site is used for human consumption or primary contact, such as immersion, or secondary contact, such as recreation. The man-made ponds on the site are routinely monitored and are a part of this Plan. Therefore, if they are in contact with shallow ground water that has exhibited elevated levels of contaminants, the Plan will detect any commingling of ground water and surface waters.

Fluctuating ground water elevations can smear contaminants into subsurface soil and rocks, and there is a possibility that plant roots could reach such contaminated soils and bio-concentrate contaminants creating another route of exposure to potential receptors, such as birds and animals that eat the plants. No food crops are currently grown on the site.

2.3 Waste Contaminant Types, Characteristics, and Possible Sources

The types of waste likely include volatile and semi-volatile organic compounds, primarily hydrocarbons, but could include various other industrial chemicals such as solvents, acids, spent caustic solutions, and heavy metals present in spent chemicals and waste water. These wastes could be in the form of waste water, spent chemicals destined for off-site shipping and disposal packed in drums, sludge, and dry solids.

Most of the wastes and contaminants that could possibly reach ground water have the characteristic that they would biodegrade and naturally attenuate. However, any heavy metals present in dirt and sludge could possibly leach into ground water and would not biodegrade. There

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



is a possibility also that certain long-lived chemicals would not biodegrade, or, if they did, it would be at a very slow rate. Possible sources include leaks from buried pipes, tanks, surface spills, and historical dumping of wastes in remote areas of the site.

All above-ground large tanks have leak detection or equivalent systems, such as radar gauges. Pumps that could leak hydrocarbons are within containment areas, and all tanks are located inside earthen bermed areas to contain spills. The NAPIS has double walls and a leak detection system installed.

Similarly, surface impoundments can serve as a source of possible ground water contamination. In the past, waste water from the railroad loading rack flowed to a settling and separation lagoon north of the rack and flow exited at the north end where water leaving the lagoon was distributed across a flat open site known as the fan-out area. The free flow of liquids led to subsurface soil contamination. This area is identified as SWMU No. 8 and has been cleaned up for a corrective action complete with controls status. Disposal of waste water into open fields is not practiced at the Gallup Refinery.

There are fourteen Solid Waste Management Units (SWMU) identified at the Gallup Refinery, and one closed land treatment area. On December 31, 2013, the RCRA Post-Closure Care Permit ("Permit") became effective under §20.4.1.901A(10) NMAC and identified an additional 20 Areas of Concern (AOCs) requiring corrective action as listed below.

RCRA (Resource Conservation and Recovery Act) Regulated Units

- Land Treatment Unit (LTU)

SWMUs (Solid Waste Management Units)

- SWMU 1 – Aeration Basin
- SWMU 2 – Evaporation Ponds
- SWMU 3 – Empty Container Storage Area
- SWMU 4 – Old Burn Pit
- SWMU 5 – Landfill Areas

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

- SWMU 6 – Tank Farm
- SWMU 7 – Fire Training Area
- SWMU 8 – Railroad Rack Lagoon
- SWMU 9 – Drainage Ditch and the Inactive Land farm
- SWMU 10 – Sludge Pits
- SWMU 11 – Secondary Oil Skimmer
- SWMU 12 – Contact Wastewater Collection System
- SWMU 13 – Drainage Ditch between North and South Evaporation Ponds
- SWMU 14 – API Separator

AOCs (Areas of Concern)

- AOC 15 – New API Separator
- AOC 16 – New API Separator Overflow Tanks
- AOC 17 – Railroad Loading/Unloading Facility
- AOC 18 – Asphalt Tank Farm (tanks 701-709, 713, 714)
- AOC 19 – East Fuel Oil Loading Rack
- AOC 20 – Crude Slop and Ethanol Unloading Facility
- AOC 21 – Main Loading Racks
- AOC 22 – Loading Rack Additive Tank Farm
- AOC 23 – Retail Fuel Tank Farm (tanks 1-7, 912, 913, 1001, 1002)
- AOC 24 – Crude Oil Tank Farm (tanks 101 and 102)
- AOC 25 – Tank 573 (Kerosene Tank)
- AOC 26 – Process Units
- AOC 27 – Boiler and Cooling Unit Area
- AOC 28 – Warehouse and Maintenance Shop Area
- AOC 29 – Equipment Yard and Drum Storage Area
- AOC 30 – Laboratory
- AOC 31 – Tanks 27 and 28
- AOC 32 – Flare and Ancillary Tanks (tanks Z85V2, Z85V3, Z84-T105)
- AOC 33 – Storm Water Collection System
- AOC 34 – Scrap Yard

Existing ground water monitoring wells effectively surround all of the above listed SWMUs and AOCs. The Permit was subsequently modified in September 2017, with SWMU 8 and AOCs 19 and 25 granted Corrective Action Complete status. AOC 32 was combined with SWMU 14 and AOC 33 was combined with SWMU 12. AOCs 20, 21, 22, and 23 are combined to make new AOC 35. The schedule in Appendix E, Table E-1 was amended to reflect prior submittals, revised due dates and deferral of other units. A new Consent Order was executed in January 2017 and this resulted in

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



11 AOCs (AOC 16, 17, 18, 24, 26, 27, 28, 29, 30, 31, and 34) being removed from the Permit and transferred to the Consent Order for further evaluation.

2.4 Summary of contaminant releases that could contribute to possible ground water contamination.

Spills and leaks are known to have occurred on the site in various locations. Although most hydrocarbons are immediately picked up for recovery and contaminated soil is removed, some of the liquids present in a spill may enter the subsurface. With precipitation, there is the possibility that some of the contaminants could leach and reach ground water.

2.4.1 Separate Phase Hydrocarbons

Separate phase hydrocarbons (SPH) have been found in multiple locations within the refinery. These locations include the Main Tank Farm, Hydrocarbon Seep Area, Aeration Basin, French Drain, Truck Loading Rack, and NAPIS Unit areas.

2.4.1.1 Main Tank Farm

Separate phase hydrocarbons (SPH) floating on shallow ground water was found in the mid-1990s at the northeast end of the facility in the main tank farm. A series of recovery wells were installed and SPH has been recovered since the initial discovery. Recovery through hand-bailing was conducted on a quarterly basis and in 2019 recovery pumps were installed. In March 2019, MPC proposed an interim recovery system using pumps in RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55. The interim system was proposed to recover SPH and dissolved-phase impacts within and down-gradient of the main tank farm. The *Interim Groundwater Recovery System Work Plan* was approved with modifications on August 6, 2019. Observed SPH measurements potentially overestimates SPH thicknesses in the soil. SPH will enter the well and depress the water table as the SPH tries to equilibrate with the SPH head in the soil column outside the monitoring well. Therefore, if the SPH is not floating on the water table and is, instead, perched in a more permeable layer above the water table, the SPH in the monitoring well will appear to be thicker than the SPH in the surrounding soils. In other words, the SPH will flow into the well, and as long as there is sufficient SPH and pressure head, the SPH will rise within the well to the level of

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

the perched SPH. It may also depress the water table within the monitoring well. The actual thickness of the SPH in the soil column may only be a few inches, but due to the mobility of the SPH, the thickness in the monitoring well may be several feet. Recovery wells in the main tank farm and the down-gradient area are listed as follows:

RECOVERY WELLS			
RW-1	RW-2	RW-5	RW-6
OW-14	OW-58	OW-30	OW-55

2.4.1.2 Hydrocarbon Seep

In June of 2013 during a routine inspection, a hydrocarbon seep was discovered in an isolated area approximately 100 yards west of Tank 101/102. A series of excavations were completed in the area of the seep including installation of six temporary sumps for bi-weekly hydrocarbon recovery. Through 2019 a total of 1,727,574 gallons of liquid (hydrocarbon and ground water) have been recovered from these sumps. To date a total of 49 permanent monitoring wells have been installed with an addition of one pre-existing well, which has been labeled as MKTF-45, and is located in the vicinity of the site investigation. SPH has been measured in Marketing Tank Farm (MKTF) wells located west and northwest of the truck loading rack and marketing tank farm, extending northwest to the location of the hydrocarbon seep. The Gallup Refinery continues to further characterize potential source areas, recovery of liquids from the temporary sumps, and continued sampling of the monitoring wells for characterization and delineation purposes. All 50 wells are included in the Ground Water Monitoring Schedule (see Appendix B), which includes the addition of five new wells (MKTF-46 through MKTF-50) in 2019. The well logs are provided in Appendix D.

Additional soil staining was observed north, northwest of the sumps and these sites were excavated of approximately 38.26 tons of soil, which was sent to the Painted Desert Landfill for disposal.

Temporary retention ditches were installed to recover liquids from this area. From April 1, 2016 through December 31, 2019, approximately 645,981 gallons of liquid (hydrocarbon and ground water) have been recovered from this area via vacuum truck.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP****RECOVERY WELLS****MKTF-01 THRU MKTF-50****2.4.1.3 Aeration Basin**

A measurable level of SPH was identified in GWM-1 during the third quarter sampling event in 2015 through October 2019.

2.4.1.4 French Drain Release

On February 6, 2018 a mixture of hydrocarbon and water was discovered flowing out of a 4-inch diameter PVC pipe that discharges into a stormwater drainage ditch south of STP-1. Sample analysis indicated the hydrocarbon was naphtha. The flow from the pipe was estimated to be 1.7 gallons per minute. The drainage ditch fed into a small collection pond that was equipped with a drain valve. The valve was closed and no additional hydrocarbon was discharged from the pond. A catch basin was installed at the discharge point of the PVC pipe and now feeds to a frac tank. Facility personnel utilized a vacuum truck to transfer the discharge from the frac tank back into the Gallup Refinery. The location of the French drain and frac tank are shown on Figure 4.1.

A subsurface investigation was conducted during March 2018. Five monitor wells (OW-61 thru OW-65) were installed in effort to delineate the hydrocarbon plume that was discharging from the PVC pipe. During the 2019 quarterly gauging, SPH was detected in three of the monitor wells (OW-61, OW-62 and OW-65) during each event and only during the first event in OW-64. All of these wells are screened within the Chinle/Alluvium Interface and measured water levels are consistent with other nearby wells also screened within the Chinle/Alluvium Interface.

2.4.1.5 Truck Loading Rack Underground Pipeline Gasoline Release

A release of gasoline was observed at the land surface on October 27, 2019 on the west side of the Truck Loading Rack. The source of the release was determined to be an underground transfer line on the north side of the Truck Loading Rack. Associated with this release, SPH was detected in MKTF-17, MKTF-19, and MKTF-36.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP****2.4.1.6 NAPIS Unit Area**

SPH has been detected in NAPIS-1 since 2017. The source of the SPH is suspected to be an unspecified release from the refinery.

2.4.2 Methyl Tert Butyl Ether

Methyl Tert Butyl Ether (MTBE) has not been used at the refinery since April 2006. Several monitoring wells were installed at various depths to monitor SPH and MTBE contaminant plumes from historical contamination. Historical analytical data for the observation wells (OW-14, 29 and 30) indicate the contaminant, MTBE has slowly been increasing over the years in these wells. Based on this information, New Mexico Environmental Department – Hazardous Waste Bureau (NMED-HWB) requested two Work Plans to further investigate the known MTBE plume at the Facility and investigate a suspected plume north of the tank farm (SWMU 6). Pursuant to NMED's February 23, 2016 Approval with Modifications of the *Investigation Work Plan OW-29 & OW-30 and North Drainage Ditch Areas*, wells OW-53, OW-54, OW-55, and OW-56 were installed. These observation wells (OW) are located downstream on the northeast section of the plant and are designated as follows.

<u>OBSERVATION WELLS</u>					
OW-13	OW-14	OW-29	OW-30	OW-50	OW-52
OW-53	OW-54	OW-55	OW-56		

Additionally, NMED has approved the *Work Plan 2015 Annual Groundwater Report Comments* on January 12, 2020, which includes installing multiple OWs to assess MTBE. A new well is proposed northeast of OW-30 to determine the hydraulic gradient on the east side of the refinery and the lateral extent of MTBE, which has been detected at elevated concentrations in groundwater samples collected from OW-30. An additional well will be installed near OW-13 to address concerns that OW-13 may be a migration pathway for contaminants to move vertically downward to the Sonsela aquifer. OW-13 will be retained at this time to allow for further evaluation. To

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

evaluate the potential migration of MTBE within the Sonsela aquifer, an additional well will be located approximately halfway between OW-12 and OW-13. The proposed locations are shown on Figure 4.2. To delineate the down-gradient extent of the plume detected at OW-1, a new Sonsela well will be installed approximately 500 feet down-gradient to the west of OW-1. The proposed location is shown on Figure 4.3.

2.4.3 NAPIS Unit

A unit at the southwest end of the facility that is used to recover and recycle oil back into the process has also – through leakage and spills – caused some MTBE and hydrocarbon contamination in shallow ground water. This unit is known as the NAPIS and was put into service in October 2004. The NAPIS has one up-gradient well NAPIS-1, located on the east side and three down-gradient shallow monitoring wells, NAPIS-2, NAPIS-3 and KA-3, which are located along the west side. The NAPIS unit is also equipped with three leak detection units on the east and west bays and also at the oil sump section on the east bay and are designated as follows:

NAPIS WELLS				LEAK DETECTION UNITS		
NAPIS-1	NAPIS-2	NAPIS-3	KA-3	EAST LDU	WEST LDU	OIL SUMP LDU

2.4.4 Aeration Basin

The Aeration Basin, which is designated as SWMU No. 1 in the facility's RCRA Post-Closure Care Permit includes three cells, known as AL-1, AL-2 (lagoons) and holding pond 1 which is currently referred to as EP-1, although it is not an evaporation pond and is not part of the area covered by SWMU No. 2 – Evaporation Ponds. All three of these cells are no longer in service since the startup of the Waste Water Treatment Plant in 2012. All refinery waste water flow was diverted to the WWTP bypassing the lagoons and pond 1. The Gallup Refinery has experienced intermittent discharges of oil and oily water into the lagoons and spills to ground surface while it was in operation. Most of these occurrences were the result of unit upsets and/or large storm events affecting the old API Separator.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Two ground water monitoring wells (GWM-1 and GWM-2) were installed immediately down gradient of the aeration lagoons in 2004 and 2005 in order to detect potential leakage from the aeration basin. GWM-3 was installed in 2005 on the northwest corner of pond 1 (EP-1).

Analysis of ground water samples collected at GWM-1 and GWM-2 have indicated several organic constituents at concentrations above the screening levels in ground water, which would indicate a potential for historical releases from the lagoons. In the third quarter of 2015, quarterly inspection of GWM-1 indicated the presence SPH during gauging activities. NMED was notified of this finding and the Gallup Refinery was instructed to collect a hydrocarbon sample for fingerprint analysis (DRO/GRO and MRO). Gallup was also instructed to purge and gauge the well on a weekly basis to check the recharge rate. The initial measurement was made without the use of an oil/interface probe and the thickness of the hydrocarbon layer in the well was not immediately known. Measured SPH thickness ranged from 0.35 to 0.45 feet in September, October and November 2015. On December 10, 2015, the Gallup Refinery sent a response to NMED–HWB concurring that the source of the hydrocarbons observed in GWM-1 is from the adjacent aeration lagoon.

Depth to water ranged from 20.83 feet to 22.07 feet during the quarterly monitoring in 2019. The measured thickness of SPH in 2019 ranged from 0.13 feet to 0.48 feet during the quarterly monitoring events.

GWM-2 and 3 upon installation in 2005 were found to be dry. Water was first detected in GWM-2 in the first quarter of 2008 and in GWM-3 in the third quarter of 2010. 24-hour notification of the finding was given to NMED and OCD respectively. Analyses of ground water samples collected from GWM-2 and GWM-3 have detected the presence of several constituents at concentration levels above applicable water quality standards such as fluoride, chloride, nitrates, and sulfates. MTBE is the only VOC to have been detected in GWM-2 or GWM-3, but at concentrations well below the screening level.

Quarterly inspections in 2011 and 2012 continued to indicate an increase in measurable water levels in GWM-2 and GWM-3, which was consistent with the increased levels in the lagoons and

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



pond 1. In the second half of 2012 through early 2013 the levels in the lagoons and pond 1 began to decrease with cessation of gravitational flow between lagoons to pond 1 due in part to the start-up of the WWTP. Continued quarterly inspections indicated no water present in GWM-2 and GWM-3 in 2013 through 2019.

Both GWM-2 and GWM-3 have been included in the Aeration Basin Corrective Action Work Plan which began investigative soil and water sampling near the aeration basin in the third quarter of 2012 to support selection of a remedy for SWMU NO. 1 and determine the source of water detected in GWM-2 and GWM-3.

In February of 2012, the Gallup Refinery submitted a "Revised Investigation Work Plan Solid Waste Management Unit (SWMU) No. 1 Aeration Basin" to include sampling of soils and ground water surrounding the Aeration Basin to determine if there has been a release to the environment and to delineate any such release. In addition, information was collected to help determine the source of ground water that had been observed in monitoring wells GWM-2 and GWM-3. The work plan also included SWMU No. 14 Old API Separator soil and ground water sampling. A new well OAPIS-1 (SWMU 14-2) was installed on the northwest corner where the benzene strippers were located on July 17, 2012 by Enviro-Drill Inc. OAPIS-1 (SWMU 14-2) was added to the 2014 Monitoring Schedule.

In February of 2013, the influent to the aeration lagoons was routed to the new Waste Water Treatment Plant (WWTP) and rerouting of the Travel Center sanitary effluent was completed in June of 2013. The aeration lagoons and pond 1 (EP-1), are no longer in service.

MPC submitted the *Solid Waste Management Unit 1 Investigation Report* on March 31, 2020, detailing a SWMU NO. 1 sampling event that took place the week of January 13, 2020. The sampling was conducted for the purposes of soil and sediment volume determination and chemical characterization for future SWMU No. 1 excavation, disposal, and closure. In the response titled, *Disapproval SWMU-1 Investigation Report*, dated August 31, 2020, NMED requested a revised report and an additional work plan to further delineate horizontal and vertical extents of

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

contamination in the area of SWMU No 1. The revised report and response to comments will be submitted by December 31, 2020. A due date from the additional work plan will be determined upon approval of the revised report.

WELLS AT THE AERATION BASIN

GWM-1

GWM-2

GWM-3

OAPIS-1

2.4.5 North Drainage Ditch

On April 22, 2015, the Gallup Refinery notified NMED-HWB of the discovery of hydrocarbons in a drainage ditch in the northern portion of the refinery property. Surface water samples were collected from the standing water in the drainage ditch and concentrations of benzene, toluene, ethylbenzene, and xylenes (BTEX) were detected as well as methyl tert-butyl ether (MTBE), gasoline range organics (GRO) and diesel range organics (DRO). An investigation work plan was submitted to NMED for review on August 13, 2015 and was subsequently implemented in May 2016 with installation of well OW-56.

2.4.6 OW-14 Source Area

In correspondence dated May 11, 2015, NMED requested submittal of a work plan to investigate the source of contaminants present in groundwater monitoring well OW-14. Subsequently, wells OW-57 and OW-58 were installed in 2016 pursuant to NMED's May 12, 2016 Approval with Modifications of the *Revised OW-14 Source Area Investigation Work Plan*. Well OW-58A was installed in 2019 adjacent to OW-58 in order to screen a higher interval than was screened in OW-58. A copy of the well log is included in Appendix D.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



3.0 Site Conditions

The Gallup Refinery is located within a rural and sparsely populated section of McKinley County. It is situated in the high desert plain on the western flank of the Continental Divide approximately 17 miles east of Gallup. The surrounding land is comprised primarily of public and private lands used for cattle and sheep grazing.

3.1 Current site topography and location of natural and manmade structures

Local topography consists of a gradually inclined down-slope from high ground in the southeast to a lowland fluvial plain in the northwest. The highest point on refinery property is located at the southeast corner boundary (elevation approximately 7,040 feet) and the lowest point is located at the northwest corner boundary (elevation approximately 6,860 feet). The refinery processing facility is located on a flat man-made terrace at an elevation of approximately 6,950 feet.

3.2 Drainages

Surface water in this region consists of the man-made evaporation ponds and aeration basins located within the refinery, a livestock watering pond (Jon Myer's Pond) located east of the refinery, two small unnamed spring fed ponds located south of the refinery, and the South Fork of the Puerco River and its tributary arroyos. The various ponds and basins typically contain water consistently throughout the year. The South Fork of the Puerco River and its tributaries are intermittent and generally contain water only during and immediately after the occurrence of precipitation.

There are several storm water conveyance ditches located throughout the refinery which are directed to discharge into contained basins where it is collected and recycled for use as process water; collected and allowed to evaporate; diverted around regulated industrial activity or into two designated outfalls located on the east and west section of the property, identified as Outfall 001 and Outfall 002 (Figure 7). Outfall 001 is located directly south of evaporation pond 8 on the western edge of the refinery's property boundary and equipped with four separate small diameter overflow pipelines, each with a manual flow valve for independent control. Outfall 002 is located north of the rail road loading rack on the eastern section of the facility. This outfall consists of a

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



concrete barrier with a valve to control discharges from a deep ditch that collects/ponds the runoff from the rail rack loading area.

Directly west of the crude tank area, there is also a concrete barrier with a valve to control discharges from a culvert that carries stormwater flow from the truck loading rack area. This concrete barrier is located downstream of the “hydrocarbon seep area.” The flow from this concrete barrier continues in a north-northwest direction alongside the southern bermed areas of evaporation ponds 3, 4, 5 and 6 and outward towards the Outfall 001 area. At the new waste water treatment plant, there are three storm drains located on the south, southwest and west side of the waste water treatment plant which is connected to an underground storm culvert that exits on the northwest section of STP-1 into a conveyance ditch along the northern edge of pond 2 into a holding pond equipped with manual flow valves, located north of evaporation pond 3. The discharge from this holding pond then flows north-northwest towards the Outfall 001 area.

3.3 Vegetation types

Surface vegetation consists of native xerophytic vegetation including grasses, shrubs, small junipers, and some prickly pear cacti. Average rainfall at the refinery is less than seven inches per year, although it can vary to slightly higher levels elsewhere in the county depending on elevation.

On alluvial fans on valley sides and drainage ways, the existing vegetation is usually alkali sacaton, western wheatgrass, Indian rice grass, blue grama, bottlebrush squirreltail, broom snakeweed, fourwing saltbush, threeawn, winterfat, mat muhly and spike muhly. On fan remnants on valley sides we usually find blue grama, western wheatgrass, Indian ricegrass, big sagebrush, galleta, bottlebrush squirreltail, fourwing saltbrush, needle and thread, one seed juniper, sand dropseed, spineless horsebrush, rabbitbrush, and two-needle pinyon. Cattails have been observed in isolated areas and are generally associated with wetlands.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

3.4 Erosion features

The impacts of historic overgrazing are visible at the north-side of the facility, in the form of arroyos that formed when surface run-off cut through the ground and washed away soils that were not able to hold water with their ground cover lost to overgrazing. Now that the facility is fenced and no livestock grazing occurs on the site, vegetation has recovered in these areas. With the facility helping to bring back vegetation in its undeveloped areas the formation and deepening of erosion features on its land has decreased.

3.5 Subsurface conditions**3.5.1 Soil types and associations**

Most of the soils found at the surface in the locations where wells are located consist of the Gish-Mentmore complex (USDA). These soils occur in alluvial fans on valley sides and fan remnants on valley sides. The parent material for these soils is slope and fan alluvium derived from sandstone and shale. These are well drained soils with moderately slow (0.2 in/hr) to slow permeability (0.06 in/hr). In this association, the Gish and similar soils make up about 45 percent, the Mentmore and similar soils 35 percent, and minor components 20 percent. These minor components are - Berryhill and similar soils 10 percent and Anodize and similar soils 10 percent. The typical profile for these soils is – 0 to 2 inches fine sandy loam, 2 to 72 inches of various kinds of clay loam.

Drill logs for various wells have been provided electronically to the NMED-HWB. From these well logs we can infer that the soils in the subsurface are generally composed of clays starting at the immediate subsurface, interbedded with narrow sand and silt layers. At about 100 to 150 feet, layers of mudstone, sandstone (from the Chinle Group, Petrified Forest Formation) and siltstone start to appear. Figure 3 shows a generalized relationship of soils in and around the Gallup Refinery.

3.5.2 Stratigraphy

The 810-acre refinery property site is located on a layered geologic formation. Surface soils generally consist of fluvial and alluvial deposits; primarily clay and silt with minor inter-bedded sand

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



layers. Below this surface layer is the Chinle Group, which consists of low permeability clay stones and siltstones. As such, the Chinle Group (Petrified Forest Formation) effectively serves as an aquiclude. Inter-bedded within the Chinle Group is the Sonsela Sandstone bed, which represents the uppermost potential aquifer in the region.

The Sonsela Sandstone bed lies within and parallels the dip of the Chinle Group. As such, its high point is located southeast of the refinery and it slopes downward to the northwest as it passes under the refinery. Due to the confinement of the Petrified Forest Formation aquitard, the Sonsela Sandstone bed acts as a water-bearing reservoir and is artesian at its lower extremis. Artesian conditions exist through much of the central and western portions of the refinery property.

3.5.3 Presence and flow direction of ground water

Ground water flow within the Petrified Forest Formation is extremely slow and typically averages less than 10^{-10} centimeters per second (less than 0.01 feet per year). Ground water flow within the surface soil layer above the Petrified Forest Formation is highly variable due to the presence of complex and irregular stratigraphy; including sand stringers, cobble beds, and dense clay layers. As such, hydraulic conductivity may range from less than 10^{-2} centimeters per second in the gravelly sands immediately overlying the Petrified Forest Formation down to 10^{-8} centimeters per second in the clay soil layers located near the surface.

Shallow ground water located under refinery property generally flows along the upper contact of the Petrified Forest Formation. The prevailing flow direction is from the southeast and toward the northwest.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.0 Investigation Methods

The purpose of this section is to describe the types of activities that will be conducted and the methods that will be used as part of this Plan. Appendix A, *Gallup Refinery Field Sampling Collection and Handling Standard Procedures*, provides the basis for the investigation methods section that follows.

4.1 Ground Water Sampling Methodology

All monitoring wells scheduled for sampling during a ground water sampling event will be sampled within 15 working days of the start of the monitoring and sampling event, weather permitting.

Appendix C-1 is a summary of the fluid level data collected in 2018 for the non-MKTF wells. Appendix C-1.1 is a summary of the fluid level data collected in 2018 for the MKTF wells. Appendices C-2 and C-2.1 include well information for the non-MKTF wells and MKTF wells, respectively. The well information consists of the survey data, screened intervals, and stratigraphic unit in which the wells are screened. Appendix C-3 includes well information for artesian wells also known as Process or Production wells (PW). Information provided for the artesian wells was gathered from well boring logs. These wells are encased and therefore measurement for depth to bottom was not field verified.

4.1.1 Well Gauging

At the beginning of each quarterly, semi-annual, or annual sampling event, all monitoring and recovery wells listed in Appendix B, Ground Water Monitoring Schedule, will be gauged to record the depth to SPH, if present, the DTW and the DTB of the well. The gauging will be performed using an oil/water interface probe attached to a measuring tape capable of recording measurements to the nearest 0.01 foot. Each monitoring well is field verified with the well number on the well casing or adjacent to the well to ensure that samples are collected at the correct well location. Wells also have a permanent marked reference point on the well casing from which ground water levels and well depths are measured. Figure 5 depicts the potentiometric surface

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



for the Sonsela aquifer and Figure 6 shows the potentiometric surface for the Alluvium/Chinle Group Interface zone.

Gauging measurements will be recorded on a field gauging form. Data obtained from the gauging will be reported in the annual ground water monitoring report. The data will be used to develop groundwater contour maps and SPH thickness isopleths which will also be included in the annual report.

4.1.2 Well Purging

Each monitoring well will be purged by removing ground water prior to sampling in order to ensure that formation water is being sampled. Generally, at least three well volumes (or a minimum of two if the well has low recharge rate) will be purged from each well prior to sampling. Field water quality parameters measured during purging are pH, electrical conductivity, temperature, dissolved oxygen (DO), and oxidation-reduction potential (ORP). One or more parameters must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples utilizing low-flow sampling techniques. When purging wells using a bailer, bailing will be considered complete when 3 well volumes have been removed from the wells. Field parameters will be measured and recorded while bailing, with the understanding that the process of hand-bailing may prevent stabilization of field parameters. Once the purging requirements are met, the well is ready for sample collection. The volume of ground water purged, the instruments used, and the readings obtained at each interval will be recorded on the field-monitoring log. Well purging and sampling will be performed using 1.5-inch x 3 foot and/or 3-inch x 3-foot disposable polyethylene bailers for ground water sampling and/or appropriately decontaminated portable sampling pumps.

If a well is pumped or bailed dry before two or three well volumes can be evacuated, it requires only that sufficient time elapse for an adequate volume of water to accumulate for the sampling event. The first sample will be tested for pH, temperature, specific conductivity, DO, and ORP. The well will be retested for pH, temperature, specific conductivity, DO, and ORP after sampling as a

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



measure of purging efficiency and as a check on the stability of the water samples over time. All well evacuation information will be recorded in a logbook.

Wells MW-1, MW-2, MW-4, MW-5, BW-1C, BW-2A, BW-2B, BW-3B, BW-4B, BW-5B, BW-5C, SMW-4, OW-1, OW-10, OW-13, OW-14, OW-29 and OW-30 are each equipped with a dedicated electrical pump. Wells SMW-2, OW-11, OW-12, OW-50, and OW-52 are purged and sampled using a portable Grundfos pump. The remaining wells are hand-bailed if the presence of water is detected.

If SPH is detected in any of these wells, no samples will be collected.

Purged well water is collected in 55-gallon drums, buckets, or totes and drained to the process sewer upstream of the NAPIS. The water is treated in the refinery's waste water treatment system.

4.2 Ground Water Sample Collection

Ground water samples will be obtained from each well within 24 hours of the completion of well purging. Sample collection methods will be documented in the field monitoring reports. The samples will be transferred to the appropriate, clean, laboratory-prepared containers provided by the analytical laboratory.

Ground water samples are collected and analyzed for both total and dissolved metals. Ground water samples obtained for dissolved metals analysis will be filtered through disposable filters with a 0.45 micrometers mesh size.

4.2.1 Sample Handling

All sample containers are supplied by the contracted analytical laboratory and shipped to the Gallup Refinery in sealed coolers. Chemical preservation is also provided by the laboratory through pre-preserved bottle ware. Collection of containerized ground water samples are in the order of

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

most volatile to least volatile, such as: VOCs, SVOCs, metals, phenols, cyanide, sulfate, chloride, nitrate and nitrite.

At a minimum, the following procedures will be used when collecting samples:

- Neoprene, nitrile, or other protective gloves will be worn when collecting samples. New disposable gloves will be used to collect each sample.
- All samples collected for chemical analysis will be transferred into clean sample containers supplied by the analytical laboratory. The sample container will be clearly marked. Sample container volumes and preservation methods will be in accordance with the most recent standard EPA and industry accepted practices for use by accredited analytical laboratories. Sufficient sample volume will be obtained for the laboratory to complete the method-specific quality control (QC) analyses on a laboratory-batch basis.
- Sample labels and documentation will be completed for each sample.

Immediately after the samples are collected, they will be stored in a cooler with ice or other appropriate storage method until they are delivered to the analytical laboratory. Standard chain-of-custody procedures, as described in Section 4.2.6 of this Plan, will be followed for all samples collected. All samples will be submitted to the laboratory to conduct the analyses within the method holding times.

4.2.2 General Well Sampling Procedures

To minimize cross contamination, rubber gloves or disposable nitrile gloves will be worn and changed between each activity.

A field notebook and sample log will be used to document weather conditions and sample date and time. Sample labels will be complete with location, date, time, analysis, preservative, and the name of the sampler. For low-flow sampling, converter speed will be adjusted prior to filling bottles. Sample labels will be affixed, and bottles will be filled according to lab instructions. Bottles with septa lids will be used for samples intended for VOC analysis. VOC bottles will be filled to

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

minimize headspace. Following collection, samples will be kept on ice to begin cooling prior to shipment.

Any reusable equipment that is not dedicated to a specific well will be decontaminated. Completed samples will be refrigerated until they are shipped to the lab. Appropriate shipping methods will be arranged to accommodate holding times. Sampling equipment and supplies will be checked, and proper inventory verified prior to sampling. Before departing, quality assurance (QA)/QC requirements will be checked to ensure there are additional equipment and supplies to fulfil the additional requirement.

4.2.3 Surface Water Sample Collection

At the evaporation ponds, samples will be collected as a grab sample at the pond edge near the inlets. This location will be noted in the field notebooks. The sampler will avoid disturbing sediment and gently allow the sample container to fill making sure that undue disturbance does not allow volatile contaminants to be lost. The sample bottle will be used for the sample collection in a shallow location near the bank. If a separate bottle and/or bailer are used to refill the sample container, this will be noted in the field log books. The decision to use a separate bottle/bailer will be made, if at all, by the sampler and the reasons will be noted in the field log book.

4.2.4 Decontamination Procedures

The objective of the decontamination procedures is to minimize the potential for cross-contamination. Most of field equipment used for ground water sampling will be disposable and, therefore, not require decontamination. To prevent cross-contamination, field equipment that comes into contact with water or soil will be decontaminated between each sampling location. The decontamination procedure will consist of washing the equipment with a non-phosphate detergent solution (e.g., Fantastik™, Liqui-Nox®), followed by two rinses of distilled water, and air dried.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Decontamination water and rinsate will be contained and disposed of the same way as purge water, as described in Section 4.1.2. Decontamination procedures and the cleaning agents used will be documented in the daily field log.

4.2.5 Documentation of Field Activities

Daily field activities, including observations and field procedures, will be recorded using indelible ink on field sampling forms. The original field forms will be maintained at the Gallup Refinery. Completed forms will be maintained in a bound and sequentially numbered field file for reference during field activities. The daily record of field activities will include the following information:

- Well identification (ID)/evaporation pond location/outfall
- Date
- Start and finish sampling time
- Field team members, including visitors
- Weather conditions
- Daily activities and times conducted
- Observations
- Record of samples collected with sample designations
- Photo log (if needed)
- Field monitoring data, including health and safety monitoring (if needed)
- Equipment used and calibration records, if appropriate
- List of additional data sheets and maps completed
- An inventory of the waste generated and the method of storage or disposal
- Signature of personnel completing the field record

4.2.6 Sample Custody

All samples collected for analysis will be recorded in the field report or data sheets. Chain-of-custody forms will be completed at the end of each sampling day, prior to the transfer of samples off site and will accompany the samples during shipment to the laboratory. A signed and dated custody seal will be affixed to the lid of the shipping container. Upon receipt of the samples at the laboratory, the custody seals will be broken, the chain-of-custody form will be signed as received by the laboratory, and the conditions of the samples will be recorded on the form. The original chain-of-custody form will remain with the laboratory; copies will be sent to the Gallup Refinery. The refinery will maintain copies of all chain-of-custody forms generated as part of sampling

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



activities. Copies of the chain-of-custody records will be included with all draft and final laboratory reports submitted to NMED and OCD.

4.2.7 Shipping Procedures

The following shipping procedures will be performed during each sampling event:

- Individual sample containers will be packed to prevent breakage and transported in a sealed cooler with ice or other suitable coolant or other EPA or industry-wide accepted method. The drainage hole at the bottom of the cooler will be sealed and secured in case of sample container leakage.
- Each cooler or other container will be delivered directly to the analytical laboratory.
- Glass bottles will be separated in the shipping container by cushioning material to prevent breakage.
- Plastic containers will be protected from possible puncture during shipping using cushioning material.
- The chain-of-custody (COC) form and sample request form will be shipped inside the sealed storage container to be delivered to the laboratory.
- Signed and dated chain-of-custody seals will be applied to each cooler prior to transport of samples from the site.

4.3 Analytical Methods

Ground water and surface water samples collected during the monitoring events will be analyzed using the specified analytical methods and for the constituents listed in Appendix B.

4.4 Quality Assurance Procedures

Contract analytical laboratories will maintain internal quality assurance programs in accordance with EPA and industry accepted practices and procedures. At a minimum, the laboratories will use a combination of standards, blanks, surrogates, duplicates, matrix spike/matrix spike duplicates (MS/MSD), blank spike/blank spike duplicates (BS/BSD), and laboratory control samples to demonstrate analytical Quality Assurance/Quality Control (QA/QC). The laboratories will establish control limits for individual chemicals or groups of chemicals based on the long-term performance of the test methods. In addition, the laboratories will establish internal QA/QC that meets EPA's laboratory certification requirements. The specific procedures to be completed are identified in the following sections.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.4.1 Equipment Calibration Procedures and Frequency

The laboratory's equipment calibration procedures, calibration frequency, and calibration standards will be in accordance with the EPA test methodology requirements and documented in the laboratory's quality assurance (QA) and Standard Operating Procedures (SOP) manuals. All instruments and equipment used by the laboratory will be operated, calibrated, and maintained according to the manufacturers' guidelines and recommendations. Operation, calibration, and maintenance will be performed by personnel who have been properly trained in these procedures. A routine schedule and record of instrument calibration and maintenance will be kept on file at the laboratory.

4.4.2 Field QA/QC Samples

Field duplicates, field blanks, equipment rinsate blanks, reagent blanks and trip blanks may be obtained for quality assurance during sampling activities. The samples will be handled as described in Section 4.4.3.

Field duplicates will consist of two samples either split from the same sample device or collected sequentially. Field duplicate ground water samples will be collected at a frequency of one per ten regular samples and will be analyzed for the full set of analyses used for the regular sample collected. At a minimum, one duplicate sample per sampling day must always be obtained.

Field blanks shall be obtained at a frequency of no less than one per day per site or unit. Field blanks shall be generated by filling sample containers in the field with deionized water and submitting the samples, along with the groundwater or surface water samples, to the analytical laboratory for the appropriate analyses.

Equipment blanks shall be obtained for chemical analysis at the rate of five percent but no fewer than one rinsate blank per sampling day. Equipment rinsate blanks shall be collected at a rate of one per sampling day if disposable sampling apparatus is used. Rinsate samples shall be generated by rinsing deionized water through unused or decontaminated sampling equipment. The rinsate

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



sample then shall be placed in the appropriate sample container and submitted with the groundwater or surface water samples to the analytical laboratory for the appropriate analyses.

Reagent blanks shall be obtained at a frequency of ten percent but no fewer than one per day per unit if chemical analyses requiring the use of chemical reagents are conducted in the field during water sampling activities.

Trip blanks will accompany laboratory sample bottles and shipping and storage containers intended for VOC analyses. Trip blanks will consist of a sample of analyte free deionized water placed in an appropriate sample container. Trip blanks will be analyzed at a frequency of one for each shipping container of samples.

4.4.3 Laboratory QA/QC Samples

Analytical procedures will be evaluated by analyzing reagent or method blanks, surrogates, MS/MSDs, BS/BSDs and/or laboratory duplicates, as appropriate for each method. The laboratory QA/QC samples and frequency of analysis to be completed will be documented in the cited EPA or other test methodologies. At a minimum, the laboratory will analyze laboratory blanks, MS/MSDs, BS/BSDs and laboratory duplicates at a frequency of one in twenty for all batch runs requiring EPA test methods and a frequency of one in ten for non-EPA test methods. Laboratory batch QA/QC samples will be project specific.

4.4.4 Laboratory Deliverables

The analytical data package will be prepared in accordance with EPA-established Level II analytical support protocol which will include:

- Transmittal letter, including information about the receipt of samples, the testing methodology performed, any deviations from the required procedures, any problems encountered in the analysis of the samples, any data quality exceptions, and any corrective actions taken by the laboratory relative to the quality of the data contained in the report;
- Sample analytical results, including sampling date; date of sample extraction or preparation; date of sample analysis; dilution factors and test method identification; water sample results in consistent units (milligrams per liter or micrograms per liter); and

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

detection limits for undetected analytes. Results will be reported for all field samples, including field duplicates and blanks, submitted for analysis;

- Method blank results, including reporting limits for undetected analytes;
- Surrogate recovery results and corresponding control limits for samples and method blanks (organic analyses only);
- Laboratory duplicate results for inorganic analyses, including relative percent differences and corresponding control limits;
- Sample COC documentation;
- Holding times and conditions;
- Conformance with required analytical protocol(s);
- Instrument calibration;
- Blanks;
- Detection/quantitative limits;
- Recoveries of surrogates and/or matrix spikes (MS/MSDs);
- Variability for duplicate analyses;
- Completeness; and,
- Data report formats.

Data deliverables provided by the laboratory that include analysis of organic compounds will also include the following:

- A cover letter referencing the procedure used and discussing any analytical problems, deviations, and modifications, including signature from authority representative certifying to the quality and authenticity of data as reported;
- A report of sample collection, extraction, and analysis dates, including sample holding conditions;
- Tabulated results for samples in units as specified, including data qualification in conformance with EPA protocol, and definition of data descriptor codes;
- Final extract volumes (and dilutions required), sample size, wet-to-dry weight ratios, and instrument practical detection/quantitative limit for each analyte;
- Analyte concentrations with reporting units identified, including data qualification and a description of the qualifiers;
- Quantification of analytes in all blank analyses, as well as identification of method blank associated with each sample; and,
- Recovery assessments and a replicate sample summary, including all surrogate spike recovery data with spike levels/concentrations for each sample and all MS/MSD results (recoveries and spike amounts).

4.4.5 Review of Field and Laboratory QA/QC Data

The sample data, field, and laboratory QA/QC results will be evaluated for acceptability with respect to the data quality objectives (DQOs). Each group of samples will be compared with the

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



DQOs and evaluated using data validation guidelines contained in EPA guidance documents: Guidance Document for the Assessment of RCRA Environmental Data Quality, National Functional Guidelines for Organic Data Review, and Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses, and the most recent version of SW-846, and industry-accepted QA/QC methods and procedures.

The laboratory will notify the Gallup Refinery Project Manager of data quality exceptions within one business day of identifying the data quality exception in order to allow for sample re-analysis, if possible. The Gallup Refinery Project Manager will contact NMED within one business day of receipt of laboratory notification of data quality exceptions in order to discuss the implementations and determine whether the data will still be considered acceptable, or if sample re-analysis or re-sampling is necessary.

4.4.6 Blanks, Field Duplicates, Reporting Limits and Holding Times**4.4.6.1 Blanks**

The analytical results of field blanks and field rinsate blanks will be reviewed to evaluate the adequacy of the equipment decontamination procedures and the possibility of cross-contamination caused by decontamination of sampling equipment. The analytical results of trip blanks will be reviewed to evaluate the possibility for contamination resulting from the laboratory-prepared sample containers or the sample transport containers. The analytical results of laboratory blanks will be reviewed to evaluate the possibility of contamination caused by the analytical procedures. If contaminants are detected in field or laboratory blanks, the sample data will be qualified or rejected, as appropriate. Methods and reasoning for the decision to qualify or reject sample data will be discussed in the Annual Groundwater Report. Furthermore, any impact to data quality and/or need to adjust methods will be addressed in the report.

4.4.6.2 Field Duplicates

Field duplicates will consist of two samples either split from the same sample device or collected sequentially. The analytical data quality objectives for precision shall be used for water duplicates.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.4.6.3 Method Reporting Limits

Method reporting limits for sample analyses will be established at the lowest level practicable for the method and analyte concentrations and will not exceed ground water or surface water cleanup standards and screening levels. Detection limits that exceed established standards or screening levels and are reported as “not detected” will be considered data quality exceptions and an explanation for its acceptability for use will be provided.

4.4.6.4 Holding Times

Per EPA protocol the sampling, extraction, and analysis dates will be reviewed to confirm that extraction and analyses were completed within the recommended holding times. Appropriate data qualifiers will be noted if holding times are exceeded.

4.4.7 Representativeness and Comparability

4.4.7.1 Representativeness

Representativeness is a qualitative parameter related to the degree to which the sample data represent the relevant specific characteristics of the media sampled. Procedures will be implemented to assure representative samples are collected and analyzed, such as repeated measurements of the same parameter at the same location over several distinct sampling events. Any procedures or variations that may affect the collection or analysis of representative samples will be noted and the data will be qualified.

4.4.7.2 Comparability

Comparability is a qualitative parameter related to whether similar sample data can be compared. To assure comparability, analytical results will be reported in appropriate units for comparison with other data (past studies, comparable sites, screening levels, and cleanup standards), and standard collection and analytical procedures will be implemented. Any procedure or variation that may affect comparability will be noted and the data will be qualified.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

4.4.8 Laboratory Reporting, Documentation, Data Reduction, and Corrective Action

Upon receipt of each laboratory data package, data will be evaluated against the criteria outlined in the previous sections. Any deviation from the established criteria will be noted and the data will be qualified. A full review and discussion of analytical data QA/QC and all data qualifiers will be submitted as appendices or attachments to the ground water monitoring reports. Data validation procedures for all samples will include checking the following, when appropriate:

- Holding times;
- Detection limits;
- Field equipment rinsate blanks;
- Field blanks;
- Field Duplicates;
- Trip blanks;
- Reagent blanks;
- Laboratory duplicates;
- Laboratory blanks;
- Laboratory matrix spikes;
- Laboratory matrix spike duplicates;
- Laboratory blank spikes;
- Laboratory blank spike duplicates; and
- Surrogate recoveries.

If significant quality assurance problems are encountered, appropriate corrective action will be implemented. All corrective action will be reported and the corrected data will be qualified.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



5.0 Monitoring and Sampling Program

The primary objective of ground water monitoring is to provide data which will be used to assess ground water quality at and near the facility. Ground water elevation data will also be collected to evaluate ground water flow conditions. The ground water monitoring program for the facility will consist of sample collection and analysis from a series of monitoring wells, recovery wells, outfalls, and evaporation pond locations.

The monitoring network is divided into six investigation areas (Groups A, B, C, D, E, and F). The sampling frequency, analyses and target analytes will vary for each investigation area and the combined data from these investigation areas will be used to assess ground water quality beneath and immediately down-gradient of the facility and evaluate local ground water flow conditions.

Samples will not be collected from monitoring wells that have measurable SPH. For wells that are purged dry, samples will be collected if recharge volume is sufficient for sample collection within 24 hours. Wells not sampled due to insufficient recharge will be documented in the field log.

If samples cannot be collected from a location due refinery activity or environmental concerns, such as elevated H₂S, arrangements will be made to collect samples from the affected location(s) during the next sampling or gauging event.

The following sections outline the monitoring program for each investigation area.

5.1 Group A Through Group F Sampling Locations

5.1.1 Sampling Locations

The location of the monitoring, recovery wells and leak detection units are shown in Figure 4. The following wells will be sampled (as described in Appendix B):

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

<u>GROUP A</u>	<u>GROUP B</u>	<u>GROUP C</u>	<u>GROUP D</u>	<u>GROUP E</u>
BW-1A, 1B, 1C	GWM-1, 2, 3	OW-13, 14, 29, 30	PW-2, 3, 4	MKTF-01 thru 50
BW-2A, 2B, 2C	NAPIS 1, 2, 3, KA-3	OW-50, 52, 53, 54	OW-1, 10	
	OW-62	OW-55, 56, 57, 58		
		OW-58A, 61, 63,		
		OW-64, 65		
BW-3A, 3B, 3C	OAPIS-1	RW-1, 2, 5, 6	OW-11, 12	
BW-4A, 4B	OW-59, 60			
BW-5A, 5B, 5C				
MW-1, 2, 4, 5	LDU (3)			
SMW-2, 4	STP1-NW, SW			

5.2 Evaporation Ponds, Outfalls**5.2.1 Sampling Locations**

The Group F outfalls and ponds will be sampled (as described in Appendix B, Table 1). (Note: these outfalls are from one section of the waste water treatment system to another – they do not discharge to any location outside the facility).

GROUP F OUTFALLS

STP-1 to EP-2

Boiler Water Inlet to EP-9

GROUP F EVAPORATION PONDS

Pond 1 – No longer in service

EP-5

EP-9

EP-2

EP-6

EP-11

EP-3

EP-7

EP-12A

EP-4

EP-8

EP-12B

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



6.0 Monitoring Program Revisions

Upon review of the analytical results from the monitoring events under this Plan, historic facility-wide monitoring data, available soil boring data, and other related information the Gallup Refinery will assess the monitoring program presented in this Plan. Revisions to the Plan, as necessary, will then be presented for agency review and approval on an annual basis. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target analytes listed in Appendix B, Table 1.

6.1 Requests for Modifications to Sampling Plan

New monitoring wells MKTF-46 through MKTF-50 have been added to the Sampling Plan. The proposed analytical suite for these five new wells includes the following:

- Volatile Organic Compounds;
- Semi-Volatile Organic Compounds;
- WQCC Metals – Total and Dissolved;
- GRO/DRO Extended;
- Major Cations/Anions; and
- 1,4-Dioxane by method 8270/8270 SIMMS for two consecutive events.

In addition, groundwater samples collected from MKTF-46 will be analyzed by method 8011 for 1,2-dibromoethane due to the detection of chlorinated solvents in samples collected from this well.

New monitoring well OW-58A has been added to the Sampling Plan. The proposed analytical suite includes the following:

- Volatile Organic Compounds (method 8260 & method 8011 for 1,2-dibromoethane);
- WQCC Metals – Total and Dissolved;
- GRO/DRO Extended; and
- Nitrite and nitrate.

Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

7.0 References

New Mexico Environment Department (NMED). 2012. Re: Investigation Work Plan, Solid Waste Management Unit (SWMU) No. 1 – Aeration Basin. February 24.

NMED. 2016. Approval with Modifications, Investigation Work Plan, OW-29 & OW-30 and North Drainage Ditch Areas. February 23.

NMED. 2016. Approval with Modifications, Revised OW-14 Source Area Investigation Work Plan, OW Series Wells and Contaminant Plume Migration. May 12.

NMED. 2019. Approval with Modifications, Response to Disapproval (Response to Approval with Modifications May 1, 2019), Interim Groundwater Recovery System Work Plan. August 6.

NMED. 2020. Approval, 2015 Annual Ground Water Work Plan. January 12.

NMED. 2020. Solid Waste Management Unit 1 Investigation Report. March 31.

United States Department of Agriculture (USDA). No date. Soil Survey of McKinley County Area, New Mexico, McKinley County and Parts of Cibola and San Juan Counties. Available from: https://www.nrcs.usda.gov/Internet/FSE_MANUSCRIPTS/new_mexico/NM692/0/McKinley.Area%20NM.pdf

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

FIGURES


M:\N\MARATHON\CADD\GALLUP\REPORTS\2020_GW_WORKPLAN_REVISION-RTC\697-GW-FRENCHDRAIN-2020



Image Cite: DigitalGlobe © CNES (2020) Distribution Airbus DS © Microsoft Corporation, BING Imagery

EXPLANATION

- OW-65 MONITORING WELL AND DESIGNATION (APPROXIMATE)
- FRENCH DRAIN




Trihydro
CORPORATION
1252 Commerce Drive
Laramie, Wyoming 82070
www.trihydro.com
(P) 307/745.7474 (F) 307/745.7729

Drawn By: REP	Checked By: BM	Scale: 1" = 200'	Date: 11/24/20	File: 697-GW-FRENCHDRAIN-2020
---------------	----------------	------------------	----------------	-------------------------------


FIGURE 4.1

FRENCH DRAIN LOCATION

**MARATHON PETROLEUM CORP.
GALLUP REFINING DIVISION
GALLUP, NEW MEXICO**



\\TRIHYRO.COM\CLIENTS\ITON\MARATHON\CADD\GALLUP\REPORTS\2020_GW_WORKPLAN_REVISION-RTC\697-GW-PROPMONLOCS2-2020



\\TRIHYRO.COM\CLIENTS\TOM MARATHON\CADD\GALLUP\REPORTS\2020_GW\WORKPLAN_REVISION-RTC\697-GW-WTRELEVMAP-2020

NOTES:

- 1. ORIGINAL CREATION DATE: MARCH 27, 2020 BY INTERTEK PSI.
- 2. GAUGING DATE: AUGUST 18, 2019.

Source: Intertek PSI, Modified by Trihydro Corporation November 24, 2020.

EXPLANATION

- WELL AND DESIGNATION (SHOWING GROUNDWATER ELEVATION)
- GROUNDWATER FLOW DIRECTION






1252 Commerce Drive
Laramie, Wyoming 82070
www.trihydro.com
(P) 307/745.7474 (F) 307/745.7729

Drawn By: REP	Checked By: BM	Scale: 1" = ~800'	Date: 11/23/20	File: 697-GW-WTRELEVMAP-2020
---------------	----------------	-------------------	----------------	------------------------------

FIGURE 5

SONSELA WATER ELEVATION MAP
2020

MARATHON PETROLEUM CORP.
GALLUP REFINING DIVISION
GALLUP, NEW MEXICO



Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX A

**Facility Wide Ground Water Monitoring Work Plan – 2019
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Appendix A

Gallup Refinery Field Sampling Collection and Handling Standard Procedures

Field Data Collection: Elevation and Purging

All facility monitoring wells and recovery wells are gauged as required throughout the year. Gallup does not have any recovery well pumps that need to be shut off and removed prior to water elevation measurements. There are groundwater recovery pumps installed in wells RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55, but they are inactive at this time. If MPC resumes recovery operations with these pumps, they must halt the pumping operation at least 48 hours prior to conducting depth measurements in these wells.

Each monitoring well is field verified with the well number on the well casing or adjacent to the well to ensure that samples are collected from the correct well location. Wells also have a permanent marked reference point on the well casing from which ground water levels and well depths are measured. The portable pump intake is lowered to the midpoint of the listed screened interval for each specific well using the markings identified on the pump hose which are set at one foot intervals. In wells with dedicated pumps, the pumps have been installed at the midpoint of the screened interval.

All water/product levels are measured to an accuracy of the nearest 0.01 foot using an oil/water interface meter. Water levels and well depths in the deeper wells are gauged with an electric water depth meter. After determining water levels, well volumes are calculated using the appropriate conversion factors for a given well based on its internal diameter. Volume is equal to the height of the liquid column times the internal cross-sectional area of the well.

Generally, at least three well volumes (or a minimum of two if the well has low recharge) are purged from each well prior to sampling. Field water quality parameters measured during purging are pH, electrical conductivity, temperature, dissolved oxygen (DO), and oxidation-reduction potential (ORP). One or more parameters must stabilize to within 10% for a minimum of three

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

consecutive measurements before collection of ground water samples utilizing low-flow sampling techniques. When purging wells using a bailer, bailing will be considered complete when 3 well volumes have been removed from the wells. Field parameters will be measured and recorded while bailing, with the understanding that the process of hand-bailing may prevent stabilization of field parameters. must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples from each well.

Before sample collection can begin, the water collected from each monitoring well must be fresh aquifer water. Well evacuation replaces stagnant well water with fresh aquifer water. The water level in the well, total depth of well and thickness of floating product (if any) will be measured using an oil/water interface meter. If any product is present, regardless of thickness, a ground water sample is not obtained.

If a well is pumped or bailed dry before two or three well volumes can be evacuated, it requires only that sufficient time elapse for an adequate volume of water to accumulate for the sampling event. The first sample will be tested for pH, temperature, specific conductivity and dissolved oxygen (mg/L). The well will be retested for pH, temperature, specific conductivity and dissolved oxygen (mg/L) after sampling as a measure of purging efficiency and as a check on the stability of the water samples over time. All well evacuation information will be recorded in a log book.

Wells MW-1, MW-2, MW-4, MW-5, BW-1C, BW-2A, BW-2B, BW-3B, BW-4B, BW-5B, BW-5C, SMW-4, OW-1, OW-10, OW-13, OW-14, OW-29 and OW-30 are each equipped with a dedicated electrical pump. Wells SMW-2, OW-11, OW-12, OW-50, and OW-52 are purged and sampled using a portable Grundfos pump. The remaining wells are hand-bailed if the presence of water is detected. If SPH is detected in any of these wells, no samples are collected.

Purged well water from wells is collected in 55-gallon drums, buckets, or totes and drained to the process sewer upstream of the NAPIS. The water is treated in the refinery's waste water treatment system.

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Sampling Equipment at Gallup Refinery

The following sampling equipment is maintained at the Gallup Refinery and used by the sampling personnel:

- Heron Instruments 100 ft. DipperT electric water depth tape complying with US GGG-T-106E, EEC Class II.
- Pall Corporation Acro 50A 0.45 micron disposable filter used with 60 ml disposable syringes for filtering water in the field.
- YSI pH/Conductivity meter Model 63, calibrated with a one-point, two-point, or three-point calibration procedure using pH standards of 7, 4 and 10. (Measures pH, temperature, conductivity, TDS, salinity, DO, and ORP)
- IQ Scientific Instruments (measures pH, temperature, conductivity, TDS, salinity, DO, and ORP), Model IQ1806LP.
- Grundfos 2-inch pumps with Grundfos 115-volt AC-to-DC converter.
- WaterMark Oil Water Interface Meter (100 ft), Model 101L/SMOIL, S/N 01-5509.

Calibration and maintenance procedures will be performed according to the manufacturer's specifications. In the event an instrument becomes inoperable, an instrument similar to the inoperable instrument will be used.

Order of Collection

Samples will be collected in the order listed below:

Parameter	Bottle Type
VOC	40 mL VOA vials (HCl)
TPH	40 mL VOA vials (HCl)
TPH	250 mL glass amber bottles
EDB AND EDC	40 mL VOA vials (Na ₂ S ₂ O ₃)
SVOC	1 liter glass amber bottle
Total Metals	250 mL plastic bottle (HNO ₃)
Dissolved Metals	125 mL plastic bottle (HNO ₃)
Major Cations/Anions	125 mL plastic bottle (HNO ₃)
Major Cations/Anions	125 mL plastic bottle (HNO ₃)
Major Cations/Anions	125 mL plastic bottle (HNO ₃)
BOD	1 liter plastic bottle
TDS	500 mL plastic bottle
COD	500 mL plastic bottle (H ₂ SO ₄)

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Parameter	Bottle Type
Cyanide	500 mL plastic bottle (NaOH)
Pesticides	1 liter glass amber bottle
E-Coli	100 mL plastic bottle

*Pre-filtration bottle for dissolved metals which is subsequently filtered in the field and transferred to a pint plastic bottle with HNO₃ preservative.

Filtration

Ground water samples are filtered prior to dissolve metals analysis. For dissolved metals, sample water is poured into a jar and then extracted with a syringe. The syringe is then used to force the sample water through a 0.45-micron pore filter into the proper sample bottle to collect dissolved metals samples. Filtration must be performed within two hours of sample collection. Pour the filtrate into a sample bottle containing HNO₃ preservative.

For samples destined for total metals analysis, do not filter the sample, and preserve with HNO₃ to pH <2 in the field.

Sampling personnel carry a cell phone when gathering ground water and other water samples. While sampling procedures are generally well known and the appropriate sample bottles are ordered to match each sampling event, occasional questions do arise from unforeseen circumstances which may develop during sampling. At such times, sampling personnel contact Hall Environmental Analytical Laboratory to verify that sampling is correctly performed. Examples would be if a well were to run dry short of filling the last sample bottle or to determine if there is enough water for sample analysis.

Sample Handling Procedures

At a minimum, the following procedures will be used when collecting samples:

- Neoprene, nitrile, or other protective gloves will be worn when collecting samples. New disposable gloves will be used to collect each sample.
- All samples collected for chemical analysis will be transferred into clean sample containers supplied by the analytical laboratory. The sample container will be clearly marked. Sample container volumes and preservation methods will be in accordance with the most recent

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

standard EPA and industry accepted practices for use by accredited analytical laboratories. Sufficient sample volume will be obtained for the laboratory to complete the method-specific QC analyses on a laboratory-batch basis.

- Sample labels and documentation will be completed for each sample.

Immediately after the samples are collected, they will be stored in a cooler with ice or other appropriate storage method until they are delivered to the analytical laboratory. Standard chain-of-custody procedures, as described in Section 4.2.1 of this Plan, will be followed for all samples collected. All samples will be submitted to the laboratory to allow the laboratory to conduct the analyses within the method holding times.

General Well Sampling Procedures

For safety, protection, and sampling purity, rubber gloves or disposable nitrile gloves will be worn and changed between each activity.

Sample bottle s and labels will be separated into plastic bags for each well to be sampled. The plastic bags holding the sample bottles, will be placed in an ice chest to take into the field. A field notebook and sample log will be used to document weather conditions and sample date and time. The label will be completed with location, date, time, analysis, preservative, and the name of the sampler. For low-flow sampling, converter speed will be adjusted prior to filling bottles. Sample labels will be affixed and bottle s will be filled according to lab instructions. Bottles with septa lids will be used for samples intended for VOC analysis. VOC bottles will be filled to the neck and a final amount of water will be added using the cap to form meniscus before screwing the lid onto the sample bottle. To ensure a proper sample has been collected, the bottles will be turned upside down and examined for bubbles, if bubbles are detected in the vial, the collection procedure will be repeated. If no bubbles are present, the lid will be secured and the bottles will be packed in bubble wrap and placed in the cooler until sampling is completed.

Any reusable equipment that is not dedicated to a specific well will be decontaminated. Completed samples will be refrigerated until they are shipped to the laboratory. Appropriate shipping methods will be arranged to accommodate holding times. Sampling equipment and supplies will

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

be checked, and proper inventory verified prior to sampling. Before departing, QA/QC requirements will be checked to ensure that there are equipment and supplies to fulfil the additional requirements.

Surface Water Sample Collection

At the evaporation ponds, samples will be collected as a grab sample at the pond edge near the inlets. This location will be noted in the field notebooks. The sampler will avoid disturbing sediment and gently allow the sample container to fill making sure that undue disturbance does not allow volatile contaminants to be lost. The sample bottle will be used for the sample collection in a shallow location near the bank. If a separate bottle and/or bailer are used to refill the sample container, this will be duly noted in the field log books. The decision to use a separate bottle/bailer will be made, if at all, by the sampler and the reasons for doing so will be noted in the field log book.

Upon arrival at the field site, the sampler will set out safety equipment such as traffic cones and signs (if required). The vehicle will be parked a sufficient distance away so as to prevent sample contamination from emissions. Appropriate sample containers and gloves must be used for the type of analyses to be performed.

Decontamination Procedures

The objective of the decontamination procedures is to minimize the potential for cross-contamination. The majority of field equipment used for ground water sampling will be disposable and, therefore, not require decontamination. In order to prevent cross-contamination, field equipment that comes into contact with water or soil will be decontaminated between each sampling location. The decontamination procedure will consist of washing the equipment with a non-phosphate detergent solution (examples include Fantastik™, Liqui-Nox®), followed by two rinses of distilled water and air dried.

**Facility Wide Ground Water Monitoring Work Plan – 2019
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Decontamination water and rinsate will be contained and disposed of the same way as purge water, as described in Section 4.2. Decontamination procedures and the cleaning agents used will be documented in the daily field log.

Field Equipment Calibration Procedures

Field equipment requiring calibration will be calibrated to known standards, in accordance with the manufacturers' recommended schedules and procedures. Calibration checks will be conducted daily and the instruments will be recalibrated if necessary. Calibration measurements will be recorded in the daily field logs.

If field equipment becomes inoperable, its use will be discontinued until the necessary repairs are made. A properly calibrated replacement instrument will be used in the interim. Instrumentation used during sampling events will be recorded in the daily field logs.

Collection and Management of Investigation Derived Waste

Investigation derived waste (IDW) generated during each groundwater sampling event may include purge water, decontamination water, excess sample material, and disposable sampling equipment. All water from all wells generated during sampling and decontamination activities will be temporarily stored in labeled 55-gallon drums until placed in the refinery wastewater treatment system upstream of the API separator. All other solid waste generated during sampling activities (including sampling gloves, tubing, etc.) will be disposed of with the Refinery's general municipal waste.

Documentation of Field Activities

Daily field activities, including observations and field procedures, will be recorded using indelible ink on field sampling forms. The original field forms will be maintained at the Gallup Refinery. Completed forms will be maintained in a bound and sequentially numbered field file for reference during field activities. The daily record of field activities will include the following information:

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

-
- Well ID/ Evaporation pond location/ Outfall
 - Date
 - Start and finish sampling time
 - Field team members, including visitors
 - Weather conditions
 - Daily activities and times conducted
 - Observations
 - Record of samples collected with sample designations
 - Photo log (if needed)
 - Field monitoring data, including health and safety monitoring (if needed)
 - Equipment used and calibration records, if appropriate
 - List of additional data sheets and maps completed
 - An inventory of the waste generated and the method of storage or disposal
 - Signature of personnel completing the field record

Sample Custody

All samples collected for analysis will be recorded in the field report or data sheets. Chain-of-custody forms will be completed at the end of each sampling day, prior to the transfer of samples off site, and will accompany the samples during shipment to the laboratory. A signed and dated custody seal will be affixed to the lid of the shipping container. Upon receipt of the samples at the laboratory, the custody seals will be broken, the chain-of-custody form will be signed as received by the laboratory, and the conditions of the samples will be recorded on the form. The original chain-of-custody form will remain with the laboratory. The Gallup Refinery will maintain copies of all chain-of-custody forms generated as part of sampling activities. Copies of the chain-of-custody records will be included with all draft and final laboratory reports submitted to NMED and OCD.

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX B

Appendix B - Table 1
Gallup Refinery - Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite
NAPI Secondary Containment (3 units)	Q	NA	NA	BTEX+MTBE, GRO/DRO extended, WQCC Metals or check for fluids
NAPI Inlet	Q	NA	NA	BTEX+MTBE, GRO/DRO extended, WQCC Metals
RW-1	Q	X	NA	Measure DTW, DTP (Hydrocarbon recovery). Sample for BTEX, MTBE, GRO/DRO extended if no SPH is detected, nitrite, nitrate
RW-2	Q	X	NA	Same as RW-1 with 1,4-dioxane by 8270/8270 SIMS for two consecutive events
RW-5	Q	X	NA	Same as RW-1
RW-6	Q	X	NA	Same as RW-1
OW-1	Q	X	pH, EC, DO, ORP, Temp, TDS	Visual check for artesian flow conditions: Sample for Major Cations/Anions, WQCC Metals, VOCS (Methods 8260 & 8011 for 1,2-dibromomethane), GRO/DRO extended, 1,4-dioxane by 8270/8270 SIMS for two consecutive events
OW-10	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-1
OW-13	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromomethane), WQCC Metals, GRO/DRO extended, 1,4-dioxane by 8270/8270 SIMS for two consecutive events, nitrite, nitrate
OW-14	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromomethane), WQCC Metals, GRO/DRO extended, 1,4-dioxane by 8270/8270 SIMS for two consecutive events, nitrite, nitrate
OW-29	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14
OW-30	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14
OW-53	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromomethane), WQCC Metals, GRO/DRO extended, nitrite, nitrate
OW-54	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14
OW-55	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14
OW-56	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14
OW-57	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-53
OW-58	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-53
OW-58A	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-53
OW-59	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, SVOCS, GRO/DRO extended, WQCC Metals
OW-60	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-59
OW-61	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions
OW-62	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions
OW-63	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions
OW-64	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions
OW-65	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions
GWM-1	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS (Methods 8260 & 8011 for 1,2-dibromomethane), GRO/DRO extended, WQCC Metals, 1,4-dioxane by 8270/8270 SIMS for two consecutive events
GWM-2	Q	X	NA	Check for Water - if water is detected report to OCD & NMED within 24 hours. Sample for GRO/DRO extended, Major Cations/Anions, VOCS
GWM-3	Q	X	NA	Check for Water - if water is detected report to OCD & NMED within 24 hours. Sample for VOCS, GRO/DRO extended, Major Cations/Anions

Appendix B - Table 1
Gallup Refinery - Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite
NAPIS-1 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, BTEX+MTBE, SVOCS, GRO/DRO extended, WQCC Metals
NAPIS-2 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1 with 1,4-dioxane by 8270/8270 SIMS for two consecutive events
NAPIS-3 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1 with Method 8011 for 1,2-dibromoethane, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
KA- 3 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1 with 1,4-dioxane by 8270/8270 SIMS for two consecutive events
OAPIS-1	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromoethane), SVOCS, GRO/DRO extended, WQCC Metals, Major Cations/Anions, Cyanide, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
STP1-NW	Q	X	NA	Major Cations/Anions, VOCS, SVOCS, GRO/DRO extended, WQCC Metals
STP1-SW	Q	X	NA	Major Cations/Anions, VOCS, SVOCS, GRO/DRO extended, WQCC Metals
STP-1 TO EP-2 (EP-2 Inlet)	Q	NA	NA	VOCS, GRO/DRO extended, BOD, COD, TDS, WQCC Metals, TSS
Boiler Water (Reverse Osmosis) inlet to EP-9	SA	NA	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions
Pond 1 ²				NO LONGER IN SERVICE
Evaporation Pond 2 ²	SA		pH, EC, DO, ORP, Temp, TDS	General Chemistry, VOCS, SVOCS, BOD, COD, E-Coli Bacteria, WQCC Metals
Evaporation Pond 3 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 4 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 5 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 6 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 7 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 8 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 9 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 11 ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 12A ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Evaporation Pond 12B ²	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
Any temporary Pond containing fluid	SA		pH, EC, DO, ORP, Temp, TDS	Same as EP-2
BW-1A	Annual (A)	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, WQCC METALS, GRO/DRO extended
BW-1B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-1C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-2A	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-2B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-2C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-3A	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-3B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-3C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-4A	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A

Appendix B - Table 1
Gallup Refinery - Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite
BW-4B	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-5A	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A
BW-5B	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS (Methods 8260 & 8011 for 1,2-dibromoethane), WQCC METALS, GRO/DRO extended, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
BW-5C	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-5B
MW-1	Annual and every 10 years beginning in 2009 per RCRA Post Closure Permit	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, GRO/DRO extended, WQCC Metals, Cyanide, SVOCS, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
MW-2	Annual and every 10 years beginning in 2009 per RCRA Post Closure Permit	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-1, excluding 1,4-dioxane
MW-4	Annual and every 10 years beginning in 2009 per RCRA Post Closure Permit	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-2
MW-5	Annual and every 10 years beginning in 2009 per RCRA Post Closure Permit	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-2
OW-11	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, WQCC Metals, GRO/DRO extended
OW-12	A	X	pH, EC, DO, ORP, Temp, TDS	VOCS, WQCC Metals, GRO/DRO extended, nitrite, nitrate
OW-50	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromoethane), GRO/DRO extended, WQCC Metals, General Chemistry, nitrite, nitrate
OW-52	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (methods 8260 & 8011 for 1,2-dibromoethane) , GRO/DRO extended, WQCC Metals, General Chemistry, nitrite, nitrate
SMW-2	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, GRO/DRO extended, WQCC Metals, Cyanide, SVOCS
SMW-4	Annual and every 10 years beginning in 2009 per RCRA Post Closure Permit	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, SVOCS, GRO/DRO extended, WQCC Metals, Cyanide, 1,4-dioxane by 8270/8270 SIMS for two consecutive events
PW-3	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite
PW-2	Every 3 years. Starting in 2008	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite, 1,4-dioxane by 8270/8270 SIMS for two consecutive events
PW-4	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite
MKTF-01	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS (Methods 8260 & 8011 for 1,2-dibromoethane), SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
MKTF-02	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-03	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions, and 1,4-dioxane by 8270/8270 SIMS for two consecutive events
MKTF-04	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-05	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-06	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-07	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-08	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03

Appendix B - Table 1
Gallup Refinery - Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite
MKTF-09	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-10	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-11	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-12	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-13	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-14	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-15	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-16	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-17	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-18	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-19	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-20	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-21	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-22	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-23	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-24	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-25	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-26	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-27	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-28	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-29	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-30	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-31	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-32	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-33	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-34	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-35	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-36	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-37	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-38	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-39	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-40	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-41	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-42	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-43	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03

Appendix B - Table 1
Gallup Refinery - Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite
MKTF-44	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-45	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-46	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01
MKTF-47	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-48	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-49	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03
MKTF-50	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03

DEFINITIONS:

DO- Dissolved Oxygen	DTW - Depth to Water	MW - Monitor Well	DRO - Diesel Range Organics	BTEX - Benzene, Toluene, Ethylbenzene, Xylenes, plus Methyl Tert-Butyl Ether (MTBE) - EPA Method 8021+MTBE
ORP - Oxygen Reduction Potential	DTP - Depth to Product	OW - Observation Well	MRO - Motor oil range organics	General Chemistry - pH, specific conductance, cations, Anions
Temp - Temperature	DTB - Depth to Bottom	RW - Recovery Well	GRO - Gasoline Range Organics	WQCC metals include the RCRA 8 metals, must be analyzed as totals and dissolved
EC - Electrical or Specific Conductivity	EP - Evaporation Pond	NA - Not Applicable	MKTF - Marketing Tank Farm Well	VOC - Volatile Organic Compounds - EPA Method 8260, must include MTBE
TDS - Total Dissolved Solids	BW - Boundary Well		PW - Raw Water Production Well	SVOC - Semi-Volatile Organic Compounds - EPA Method 8270, must include phenol

NOTES:

1. NAPIS-1, NAPIS-2, NAPIS-3, and KA-3: Detection of product during quarterly monitoring must comply with Section II.F.2 (24-hour reporting) of NMED Post-Closure Care Permit
2. Sample using the State of New Mexico approved analytical methods as required by 20.6.4.14 NMAC, as amended through February 16, 2006 (use methods 9221-E, until EPA approves 40 CFR 136 Methods (Colilert, Colilert-18, m-Colibblue24, membrane filter method)). Parameters are subject to change. Evaporation pond samples must be collected at the inlet where waste water flows into the evaporation ponds.
3. Where nitrite and/or major anions are specified Hach Field Test Kit NI-12 will be used for the field analysis of nitrite in addition to laboratory analysis for nitrate + nitrite.

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
NAPI Secondary Containment (3 units)	Q	NA	NA	BTEX+MTBE, GRO/DRO extended, WQCC Metals or check for fluids	None	
NAPI Inlet	Q	NA	NA	Same as above (SAA)	None	
RW-1	Q	X	NA	Measure DTW, DTP (Hydrocarbon recovery) Sample for BTEX + MTBE, GRO/DRO extended. Sample only if no SPH is detected.	None	
RW-2	Q	X	NA	Same as RW-1	None	
RW-5	Q	X	NA	Same as RW-1	None	
RW-6	Q	X	NA	Same as RW-1	None	
OW-1	Q	X	pH-, EC, DO, ORP, Temp, TDS	Visual check for artesian flow conditions: Sample for Major Cations/Anions, WQCC Metals, VOCs (Methods 8260 & 8011 for 1,2-dibromoethane), GRO/DRO extended	None	
OW-10	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-1	None	
OW-13	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs (Methods 8260 & 8011 for 1,2-dibromoethane), WQCC Metals, GRO/DRO extended	None	
OW-14	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs (Methods 8260 & 8011 for 1,2-dibromoethane), WQCC Metals, GRO/DRO extended	None	
OW-29	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-30	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-53	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-54	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-55	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-56	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-57	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-58	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	None	
OW-58A	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as OW-14	Add to Monitoring Schedule	New Well
OW-59	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCs, SVOCs, GRO/DRO extended, WQCC Metals	None	
OW-60	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-59	None	
OW-61	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs, SVOCs, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
OW-62	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	
OW-63	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	
OW-64	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	
OW-65	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCS, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	
GWM-1	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS (methods 8260 and 8011 for 1,2-dibromoethane), GRO/DRO extended, WQCC Metals	None	
GWM-2	Q	X	NA	Check for Water - if water is detected report to OCD & NMED within 24 hours. Sample for GRO/DRO extended, Major Cations/Anions, VOCS	None	
GWM-3	Q	X	NA	Same as GWM-2	None	
NAPIS-1 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, BTEX+MTBE, SVOCS, GRO/DRO extended, WQCC Metals	None	
NAPIS-2 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1	None	
NAPIS-3 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1 and Method 8011 for 1,2-dibromoethane	None	
KA-3 ¹	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as NAPIS-1	None	
OAPIS-1	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS (Methods 8260 and 8011), SVOCS, GRO/DRO extended, WQCC Metals, Cyanide	None	
STP1-NW	Q	X	NA	Major Cations/Anions, VOCS, SVOCS, GRO/DRO extended, WQCC Metals	None	
STP1-SW	Q	X	NA	Same as STP1-NW	None	
Boiler Water (Reverse Osmosis)inlet to EP-2	SA	NA	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions	None	
Pond 1 ²		NA		NO LONGER IN SERVICE	None	
Evaporation Ponds 2 - 9 ²	SA	NA	pH, EC, DO, ORP, Temp, TDS	General Chemistry, VOCS, SVOCS, BOD, COD, E-Coli Bacteria, WQCC Metals and Pesticides by method 8081A for EP-3)	None	
Evaporation Pond 11 ²	SA	NA	pH, EC, DO, ORP, Temp, TDS	Same as EP-2	None	

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
Evaporation Pond 12A ₂	SA	NA	pH, EC, DO, ORP, Temp, TDS	Same as EP-2, and Pesticides by method 8081A	None	
Evaporation Pond 12B ₂	SA	NA	pH , EC, DO, ORP, Temp, TDS	Same as EP-2, and Pesticides by method 8081A	None	
Any temporary Pond containing fluid	SA	NA	pH, EC, DO, ORP, Temp, TDS	Same as EP-2	None	
STP-1 TO EP-2 (EP-2 Inlet)	Q	NA	NA	VOCS, GRO/DRO extended, BOD, COD, TDS, WQCC Metals, TSS	None	
BW-1A	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS, WQCC METALS, GRO/DRO extended	None	
BW-1B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-1C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-2A	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-2B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-2C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-3A	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-3B	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-3C	A	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-4A	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-4B	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-5A	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-1A	None	
BW-5B	Q	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCS (8260 & 8011 for 1,2-dibromoethane) , WQCC METALS, GRO/DRO extended	None	
BW-5C	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as BW-5B	None	

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
MW-1	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCs, SVOCs, GRO/DRO extended, WQCC Metals, Cyanide	None	
MW-2	A	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-1	None	
MW-4	A	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-1	None	
MW-5	A	X	pH, EC, DO, ORP, Temp, TDS	Same as MW-1	None	
OW-11	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCs, WQCC Metals, GRO/DRO-extended	None	
OW-12	A	X	pH, EC, DO, ORP, Temp, TDS	VOCs, WQCC Metals, GRO/DRO extended	None	
OW-50	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs (Methods 8260 & 8011 for 1,2-dibromoethane) , GRO/DRO extended, WQCC Metals, GEN CHEM.	None	
OW-52	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as OW-50	None	
SMW-2	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCs, SVOCs, GRO/DRO extended, WQCC Metals, Cyanide	None	
SMW-4	A	X	pH, EC, DO, ORP, Temp, TDS	Major Cations/Anions, VOCs, SVOCs, GRO/DRO extended, WQCC Metals, Cyanide	None	
PW-3	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite	None	
PW-2	Every 3 years. Starting in 2008	X	pH, EC, DO, ORP, Temp, TDS	VOCs, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite	None	
PW-4	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs, SVOCS, WQCC Metals, Cyanide, Nitrate, Nitrite	None	
MKTF-01	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs (Methods 8260 & 8011 for 1,2-dibromoethane), SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions. Ground water samples will not be collected if SPH is present in any of the wells.	None	
MKTF-02	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-03	Q	X	pH, EC, DO, ORP, Temp, TDS	VOCs, SVOCS, WQCC Metals, GRO/DRO extended, Major Cations/Anions	None	
MKTF-04	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-05	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-06	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
MKTF-07	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-08	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-09	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-10	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-11	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-12	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-13	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-14	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-15	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-16	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-17	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-18	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-19	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-20	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-21	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-22	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-23	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-24	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-25	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-26	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-27	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-28	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	

Appendix B - Table 2
Gallup Refinery - Requested/Approved Changes to the Ground Water Monitoring Schedule

Sampling Location ID	Sampling Frequency (Q - Quarterly A - Annual SA - Semi-Annual)	Collect GW Elevation, DTW, DTP	Water Quality Parameters	Analytical Suite	2019 Requested Changes	Rationale for Requested Changes
MKTF-29	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-30	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-31	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-32	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-33	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-34	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-35	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-36	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-37	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-38	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-39	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-40	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-41	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-42	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	None	
MKTF-43	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-44	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-45	Q	X	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	None	
MKTF-46	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-01	Add to Monitoring Schedule	New well
MKTF-47	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	Add to Monitoring Schedule	New well
MKTF-48	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	Add to Monitoring Schedule	New well
MKTF-49	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	Add to Monitoring Schedule	New well
MKTF-50	Q	x	pH, EC, DO, ORP, Temp, TDS	Same as MKTF-03	Add to Monitoring Schedule	New well

DEFINITIONS:

STP-1 TO EP-2 - Sample collected at the inlet to Evaporation Pond 2 from STP-1
NAPIS 1 = (KA-1R); NAPIS-2 = (KA-2R), NAPIS-3 = KA-3R) - monitor wells positioned around NAPIS to detect leakage
DO- Dissolved Oxygen; ORP - Oxygen Reduction Potential; Temp - Temperature; EC - Electrical or Specific Conductivity
TDS - Total Dissolved Solids; VOC - Volatile Organic Compounds-EPA Method 8260, must include MTBE
SVOC - Semi-Volatile Organic Compounds - EPA Method 8270, must include phenol
DRO - Diesel Range Organics - EPA Method 8015B (or as modified); GRO - Gasoline Range Organics - EPA Method 8015B (or as modified)
BTEX - Benzene, Toluene, Ethylbenzene, Xylene, plus Methyl Tert-Butyl Ether (MTBE) - EPA Method 8021+MTBE
General Chemistry - pH, specific conductance, cations, Anions
DTW - Depth to Water; DTP - Depth to Product; EP - Evaporation Pond; BW - Boundary Wells
GWM wells - located around the aeration lagoons to detect leakage
MW - Monitor Well; OW - Observation Well; RW - Recovery Well; PW - Raw Water Production Well
WQCC metals include the RCRA 8 metals, must be analyzed as totals and dissolved
NA - Not Applicable

NOTES:

- 1) NAPIS 1, NAPIS 2, NAPIS 3, KA-3: Detection of product during quarterly monitoring must comply with Section II.F.2 (twenty-four hour reporting) of NMED Post-Closure Care Permit
- 2) Sample using the State of New Mexico approved analytical methods as required by 20.6.4.14 NMAC, as amended through February 16, 2006 (use methods 9221-E and 9221-F, until EPA approves 40 CFR 136 methods. (Colilert, Colilert - 18, m-Colibblue24, membrane filter method)). Parameters are subject to change. Evaporation Pond samples must be collected at the inlet where waste water flows into the evaporation ponds.

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX C

APPENDIX C-1. WELL DATA TABLES

Date of Installation	Well ID Number	Inspection or Sample Date	Casing Diameter (Inch)	Ground Level Elevation (ft)	Well Casing Rim Elevation (ft)	Stick-up length (ft)	Well Casing Bottom Elevation (ft)	Total Well Depth (ft)	Depth to SPH (ft)	SPH Column Thickness (ft)	Depth to Water (ft)	Ground water Elevation (ft)	Corrected Water Table ¹ Elevation (ft)	Screened Interval Depth Top to Bottom (ft)	Stratigraphic unit in which screen exists
03/29/95	RW-2	08/16/19	4.00	6,926.40	6,928.53	2.13	6,888.73	NM	NM	NA	NM	NA	NA	26.1 - 36.1	Chinle/Alluvial Interface
03/29/95	RW-2	11/01/19	4.00	6,926.40	6,928.53	2.13	6,888.73	NM	NM	NA	NM	NA	NA	26.1 - 36.1	Chinle/Alluvial Interface
08/27/97	RW-5	03/28/19	4.00	6,941.53	6,943.57	2.04	6,903.98	NM	NM	NA	NM	NA	NA	29.5 - 39.5	Chinle/Alluvial Interface
08/27/97	RW-5	05/08/19	4.00	6,941.53	6,943.57	2.04	6,903.98	NM	NM	NA	NM	NA	NA	29.5 - 39.5	Chinle/Alluvial Interface
08/27/97	RW-5	08/16/19	4.00	6,941.53	6,943.57	2.04	6,903.98	NM	NM	NA	NM	NA	NA	29.5 - 39.5	Chinle/Alluvial Interface
08/27/97	RW-5	11/01/19	4.00	6,941.53	6,943.57	2.04	6,903.98	NM	NM	NA	NM	NA	NA	29.5 - 39.5	Chinle/Alluvial Interface
08/27/97	RW-6	03/28/19	4.00	6,941.96	6,944.01	2.05	6,903.11	NM	NM	NA	NM	NA	NA	28.5 - 38.5	Chinle/Alluvial Interface
08/27/97	RW-6	05/08/19	4.00	6,941.96	6,944.01	2.05	6,903.11	NM	NM	NA	NM	NA	NA	28.5 - 38.5	Chinle/Alluvial Interface
08/27/97	RW-6	08/16/19	4.00	6,941.96	6,944.01	2.05	6,903.11	NM	NM	NA	NM	NA	NA	28.5 - 38.5	Chinle/Alluvial Interface
08/27/97	RW-6	11/01/19	4.00	6,941.96	6,944.01	2.05	6,903.11	NM	NM	NA	NM	NA	NA	28.5 - 38.5	Chinle/Alluvial Interface
09/26/85	SMW-2	08/19/19	2.00	6,881.63	6,883.97	2.34	6,831.17	52.80	ND	NA	25.30	6,858.67	NA	34.31 - 54.31	Chinle/Alluvial Interface and Upper Sand Well
09/25/85	SMW-4	08/13/19	2.00	6,877.63	6,879.52	1.89	6,809.84	69.68	ND	NA	29.10	6,850.42	NA	51.7 - 71.7	Chinle/Alluvial Interface
05/06/14	STP1-NW	02/13/19	2.00	6,904.50	6,904.47	-0.03	6,854.47	50.00	ND	NA	20.35	6,884.12	NA	20 - 50	Chinle/Alluvial Interface
05/06/14	STP1-NW	05/08/19	2.00	6,904.50	6,904.47	-0.03	6,854.47	50.00	ND	NA	19.54	6,884.93	NA	20 - 50	Chinle/Alluvial Interface
05/06/14	STP1-NW	08/21/19	2.00	6,904.50	6,904.47	-0.03	6,854.47	50.00	ND	NA	20.79	6,883.68	NA	20 - 50	Chinle/Alluvial Interface
05/06/14	STP1-NW	10/22/19	2.00	6,904.50	6,904.47	-0.03	6,854.47	50.00	ND	NA	20.76	6,883.71	NA	20 - 50	Chinle/Alluvial Interface
05/06/14	STP1-SW	02/13/19	2.00	6,912.40	6,912.38	-0.02	6,854.47	NM	NM	NA	NM	NA	NA	15 - 30	Chinle/Alluvial Interface
05/06/14	STP1-SW	05/08/19	2.00	6,912.40	6,912.38	-0.02	6,854.47	NM	NM	NA	NM	NA	NA	15 - 30	Chinle/Alluvial Interface
05/06/14	STP1-SW	08/21/19	2.00	6,912.40	6,912.38	-0.02	6,854.47	NM	NM	NA	NM	NA	NA	15 - 30	Chinle/Alluvial Interface
05/06/14	STP1-SW	10/22/19	2.00	6,912.40	6,912.38	-0.02	6,854.47	NM	NM	NA	NM	NA	NA	15 - 30	Chinle/Alluvial Interface

DEFINITIONS:

DTB - Depth to Bottom

DTW - Depth to Water

SPH = Separate Phase Hydrocarbons

* Wells also checked for Artesian flow conditions.

NA = Not Applicable

NS = Not Surveyed

NM = Not Measured

Negative number in Stick up Length column indicates well is flushmount and located at or below ground level.

Depth to Water Column - if 0.00 is indicated - means water is at top of casing (full) under artesian flow conditions.

Dry indicates no water was detected.

NOTES:

1. Corrected Water Table Elevation applies only if SPH thickness column measurement exists. (0.8 X SPH thickness + Groundwater Elevation)

12/06/18 - 10-Year Post Closure Sampling Event for the LTU (Land Treatment Unit)

02/09/18 - Was not able to gauge or sample wells around the NAPIS Unit due to elevated H₂S readings in the ambient air.

11/07/18 - Did not gauge or sample wells due to recovery apparatus installed on all the RW wells.

APPENDIX C-2
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT

Date of Installation	Well ID Number	Survey Measurement date	Verified Casing Diameter (Inch)	Survey Ground Level Elevation (feet)	Survey Well Casing Rim Elevation (feet)	Measuring Point Description	Survey Stick up Length (feet)	Survey Well Casing Bottom Elevation (feet)	Survey Total Well Depth (feet)	Screened Interval Depth Top to Bottom (feet)	Stratigraphic unit in which screen exists
10/11/03	BW-1A ²	09/15/14	2.00	6,883.17	6,885.12	North edge PVC casing	1.95	6,839.06	46.06	38 - 43	Upper Sand
10/28/03	BW-1B ²	09/15/14	2.00	6,883.17	6,885.78	North edge PVC casing	2.61	6,809.49	76.29	63.4 - 73.4	Chinle/Alluvium Interface
10/11/03	BW-1C ²	09/15/14	2.00	6,883.17	6,885.68	North edge PVC casing	2.51	6,740.39	145.29	133.9 - 143.9	Sonsela
10/11/03	BW-2A	07/06/11	2.00	6,871.88	6,874.69	North edge PVC casing	2.81	6,807.12	67.57	55 - 65	Upper Sand
10/28/03	BW-2B	07/06/11	2.00	6,871.66	6,874.50	North edge PVC casing	2.84	6,782.24	92.26	80 - 90	Chinle/Alluvium Interface
10/28/03	BW-2C	07/06/11	2.00	6,872.90	6,875.30	North edge PVC casing	2.40	6,722.46	152.84	139.5 - 149.5	Sonsela
06/15/04	BW-3A	07/06/11	2.00	6,875.94	6,878.39	North edge PVC casing	2.45	6,826.04	52.35	39.5 - 49.5	Upper Sand
10/15/03	BW-3B	07/06/11	2.00	6,876.16	6,878.59	North edge PVC casing	2.43	6,809.19	69.40	63 - 73	Chinle/Alluvium Interface
07/20/04	BW-3C	07/06/11	2.00	6,875.72	6,877.95	North edge PVC casing	2.23	6,723.40	154.55	144.5 - 154.5	Sonsela
06/14/17	BW-4A	03/16/18	2.00	6,870.67	6,873.18	North edge PVC casing	2.51	6,834.38	38.80	21 - 36	Upper Sand
06/16/17	BW-4B	03/16/18	2.00	6,870.62	6,873.23	North edge PVC casing	2.61	6,809.73	63.50	41 - 61	Chinle/Alluvium Interface
06/23/17	BW-5A	03/16/18	2.00	6,874.39	6,877.00	North edge PVC casing	2.61	6,854.00	23.00	10 - 20	Upper Sand
06/23/17	BW-5B	03/16/18	2.00	6,874.32	6,876.82	North edge PVC casing	2.5	6,815.37	61.45	48 - 58	Chinle/Alluvium Interface
06/21/17	BW-5C	03/16/18	2.00	6,874.22	6,876.85	North edge PVC casing	2.63	6,800.50	76.35	64.5 - 74.5	Sonsela
10/14/81	MW-1	6/7/2011	5.00	6,876.63	6,878.12	North edge PVC casing	1.49	6,747.29	130.83	117.72 - 127.72	Sonsela
10/15/81	MW-2	6/7/2011	5.00	6,878.39	6,880.30	North edge PVC casing	1.91	6,742.82	137.48	112 - 122	Sonsela
10/16/81	MW-4	6/7/2011	5.00	6,879.89	6,881.63	North edge PVC casing	1.74	6,759.91	121.72	101 - 121	Sonsela
07/21/86	MW-5	6/7/2011	4.00	6,880.20	6,882.83	North edge aluminum casing	2.63	6,752.00	130.83	115 - 125	Sonsela
09/26/85	SMW-2	6/7/2011	2.00	6,881.63	6,883.97	North edge aluminum casing	2.34	6,831.17	52.80	34.31 - 54.31	Chinle/Alluvium Interface and Upper Sand
09/25/85	SMW-4	6/7/2011	2.00	6,877.63	6,879.52	North edge aluminum casing	1.89	6,809.84	69.68	51.7 - 71.7	Chinle/Alluvium Interface
05/01/81	OW-1 ¹	6/7/2011	4.00	6,866.32	6,866.62	North edge PVC casing	0.30	6,772.07	94.55	89.3 - 99.3	Sonsela
11/25/80	OW-10	6/7/2011	4.00	6,873.67	6,874.91	North edge PVC casing	1.24	6,814.58	60.33	40 - 60	Sonsela
09/25/81	OW-11	6/7/2011	4.00	6,922.05	6,923.51	North edge PVC casing	1.46	6,857.72	65.79	43 - 65	Sonsela
12/15/80	OW-12	6/7/2011	4.00	6,939.57	6,940.69	North edge PVC casing	1.12	6,811.84	128.85	117.8 - 137.8	Sonsela
10/12/80	OW-13	6/7/2011	4.00	6,918.95	6,920.07	North edge PVC casing	1.12	6,820.92	99.15	78.2 - 98.2	Sonsela
12/17/80	OW-14	6/7/2011	4.00	6,924.55	6,926.65	North edge PVC casing	2.10	6,880.13	46.52	35 - 45	Chinle/Alluvium Interface

APPENDIX C-2
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT

Date of Installation	Well ID Number	Survey Measurement date	Verified Casing Diameter (Inch)	Survey Ground Level Elevation (feet)	Survey Well Casing Rim Elevation (feet)	Measuring Point Description	Survey Stick up Length (feet)	Survey Well Casing Bottom Elevation (feet)	Survey Total Well Depth (feet)	Screened Interval Depth Top to Bottom (feet)	Stratigraphic unit in which screen exists
08/23/96	OW-29	6/7/2011	4.00	6,913.89	6,917.00	North edge PVC casing	3.11	6,865.92	51.08	37.5 - 47.5	Chinle/Alluvium Interface
08/28/96	OW-30	6/7/2011	4.00	6,921.81	6,924.69	North edge PVC casing	2.88	6,874.79	49.90	37.9 - 47.9	Chinle/Alluvium Interface
05/10/09	OW-50	6/7/2011	2.00	6,912.63	6,914.21	North edge PVC casing	1.58	6,850.21	64.00	48 - 63	Chinle/Alluvium Interface
05/10/09	OW-52	6/7/2011	2.00	6,906.53	6,907.68	North edge PVC casing	1.15	6,829.94	77.74	64 - 79	Chinle/Alluvium Interface
05/26/16	OW-53	07/27/16	2.00	6,911.93	6,914.38	North edge PVC casing	2.45	6,880.48	33.90	16 - 31	Chinle/Alluvium Interface
05/25/16	OW-54	07/27/16	2.00	6,916.36	6,918.92	North edge PVC casing	2.56	6,887.88	31.04	13 - 28	Chinle/Alluvium Interface
05/24/16	OW-55	07/27/16	2.00	6,921.01	6,923.25	North edge PVC casing	2.24	6,892.55	30.70	13 - 28	Chinle/Alluvium Interface
05/24/16	OW-56	07/27/16	2.00	6,917.79	6,920.18	North edge PVC casing	2.39	6,901.59	18.59	6 - 16	Chinle/Alluvium Interface
09/21/16	OW-57	04/27/17	2.00	6,930.64	6,933.10	North edge PVC casing	2.46	6,904.75	28.35	15 - 25	Chinle/Alluvium Interface
09/22/16	OW-58	04/27/17	2.00	6,934.71	6,934.50	North edge PVC casing	-0.21	6,887.00	47.50	38 - 48	Chinle/Alluvium Interface
06/29/17	OW-59	03/16/18	2.00	6,887.63	6,889.73	North edge PVC casing	2.1	6,851.23	38.50	20 - 35	Chinle/Alluvium Interface
06/29/17	OW-60	03/16/18	2.00	6,891.06	6,893.51	North edge PVC casing	2.45	6,847.96	45.55	25 - 45	Chinle/Alluvium Interface
08/07/04	GWM-1	07/06/11	2.00	6,910.22	6,912.61	North edge PVC casing	2.39	6,886.41	26.20	17.5 - 23.5	Chinle/Alluvium Interface
09/25/05	GWM-2	07/06/11	2.00	6,910.32	6,913.09	North edge PVC casing	2.77	6,894.28	18.81	3.2 - 16.2	Chinle/Alluvium Interface
09/25/05	GWM-3	07/06/11	2.00	6,907.35	6,910.25	North edge PVC casing	2.90	6,892.45	17.80	3 - 15	Chinle/Alluvium Interface
03/14/08	NAPIS-1	07/06/11	2.00	6,913.62	6,913.86	North edge PVC casing	0.24	6,900.33	13.53	3.7 - 13.7	Chinle/Alluvium Interface
03/14/08	NAPIS-2 ⁴	10/17/16	2.00	6,918.29	6,917.87	North edge PVC casing	-0.42	6,903.54	14.33	4.2 - 14.2	Chinle/Alluvium Interface
03/14/08	NAPIS-3 ⁴	10/17/16	2.00	6,918.30	6,918.07	North edge PVC casing	-0.23	6,886.95	31.12	25.4 - 30.4	Chinle/Alluvium Interface
11/06/07	KA-3 ⁴	10/17/16	2.00	6,918.20	6,917.61	North edge PVC casing	-0.59	6,893.51	24.10	15 - 25	Chinle/Alluvium Interface
07/17/12	OAPIS-1	02/04/13	2.00	6,916.50	6,916.73	Northwest edge PVC casing	0.23	6,890.73	26.00	14 - 26	Chinle/Alluvium Interface
06/05/14	STP1-NW ³	09/15/14	2.00	6,904.50	6,904.47	North edge top of PVC	-0.03	6,854.47	50.00	20 - 50	Chinle/Alluvium Interface
06/05/14	STP1-SW ³	09/15/14	2.00	6,912.40	6,912.38	North edge top of PVC	-0.02	6,880.38	32.00	15 - 30	Chinle/Alluvium Interface
03/28/95	RW-1	07/06/11	4.00	6,942.86	6,946.06	North edge PVC casing	3.20	6,903.02	43.04	25 - 40	Chinle/Alluvium Interface
03/29/95	RW-2	07/06/11	4.00	6,926.40	6,928.53	North edge PVC casing	2.13	6,888.73	39.80	26.1 - 36.1	Chinle/Alluvium Interface
08/27/97	RW-5	07/06/11	4.00	6,941.53	6,943.57	West Edge PVC Casing (Existing Mark)	2.04	6,903.98	39.59	29.5 - 39.5	Chinle/Alluvium Interface
08/27/97	RW-6	07/06/11	4.00	6,941.96	6,944.01	North edge PVC casing	2.05	6,903.11	40.90	28.5 - 38.5	Chinle/Alluvium Interface

APPENDIX C-2
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT

Date of Installation	Well ID Number	Survey Measurement date	Verified Casing Diameter (Inch)	Survey Ground Level Elevation (feet)	Survey Well Casing Rim Elevation (feet)	Measuring Point Description	Survey Stick up Length (feet)	Survey Well Casing Bottom Elevation (feet)	Survey Total Well Depth (feet)	Screened Interval Depth Top to Bottom (feet)	Stratigraphic unit in which screen exists
2019 ADDITIONS TO THE FACILITY WIDE GROUNDWATER MONITORING PLAN											
3/14/18	OW-61	04/23/19	4.00	6,960.91	6,963.57	North edge PVC casing	2.66	6,924.77	38.80	8 - 28	Chinle/Alluvium Interface
3/15/18	OW-62	04/23/19	4.00	6,934.73	6,937.36	North edge PVC casing	2.63	6,873.86	63.50	8 - 28	Chinle/Alluvium Interface
3/14/18	OW-63	04/23/19	4.00	6,932.34	6,935.06	North edge PVC casing	2.72	6,912.06	23.00	9 - 29	Chinle/Alluvium Interface
3/16/18	OW-64	04/23/19	4.00	6,945.07	6,947.40	North edge PVC casing	2.33	6,885.95	61.45	4 - 24	Chinle/Alluvium Interface
3/12/18	OW-65	04/23/19	4.00	6,951.62	6,954.05	North edge PVC casing	2.43	6,877.70	76.35	17 - 37	Chinle/Alluvium Interface

DEFINITIONS:

NA = Not applicable

Survey of all wells conducted in June 2011, unless otherwise noted

Stick up length is determined by subtracting 2011 Survey Ground Level Elevation from 2011 Survey Well Casing Rim Elevation. Negative values indicate well is a flush mount. 2011 Survey Well Casing Bottom Elevation is determined by subtracting the 2011 Survey Well Casing Rim Elevation from the 2011 Survey Total Well Depth Measurement.

Total well depth was determined using a bottom sensing meter, Testwell Water level meter with bottom sensing indicator.

Screened interval for each well was verified to the well boring logs. Settlement may have occurred since installation of well which is why total well depth is higher or equal to the screened interval levels.

NOTES:

APPENDIX C-2.1
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT
MKTF-01 through MKTF-45

Date of Installation	Well ID Number	Survey Measurement Date ¹	Casing Diameter (Inch)	Ground Level Elevations (ft)	Well Casing Rim Elevations (ft)	Ground Elevation Inside Steel Sleeve (ft)	Measuring Point Description	Stick-up length (ft)	Well Casing Bottom Elevations (ft)	Total Well Depth ² (ft)	Screened Interval Depth Top to Bottom (ft)	Stratigraphic unit in which screen exists
11/14/13	MKTF-01	01/21/14	4.00	6,918.28	6,920.67	6,920.67	North edge PVC Casing	2.39	6,903.25	17.42	5 - 15	Chinle/Alluvium Interface
11/14/13	MKTF-02	01/21/14	4.00	6,915.00	6,917.45	6,917.18	North edge PVC Casing	2.45	6,896.97	20.48	7 - 17	Chinle/Alluvium Interface
11/07/13	MKTF-03	01/21/14	4.00	6,931.73	6,931.69	6,930.85	North edge PVC Casing	-0.04	6,913.24	18.45	3 - 18	Chinle/Alluvium Interface
11/12/13	MKTF-04	01/21/14	4.00	6,933.90	6,933.57	6,933.24	North edge PVC Casing	-0.33	6,911.42	22.15	10 - 22	Chinle/Alluvium Interface
11/20/13	MKTF-05	01/21/14	4.00	6,939.49	6,942.22	6,941.95	North edge PVC Casing	2.73	6,924.47	17.75	4 - 14	Chinle/Alluvium Interface
11/11/13	MKTF-06	01/21/14	4.00	6,944.24	6,946.81	6,946.63	North edge PVC Casing	2.57	6,923.04	23.77	8 - 20	Chinle/Alluvium Interface
11/11/13	MKTF-07	01/21/14	4.00	6,944.40	6,947.18	6,947.06	North edge PVC Casing	2.78	6,929.56	17.62	4 - 14	Chinle/Alluvium Interface
11/11/13	MKTF-08	01/21/14	4.00	6,944.02	6,947.09	6,942.67	North edge PVC Casing	3.07	6,925.11	21.98	8 - 18	Chinle/Alluvium Interface
11/11/13	MKTF-09	01/21/14	4.00	6,943.57	6,946.50	6,945.90	North edge PVC Casing	2.93	6,923.80	22.70	7 - 19	Chinle/Alluvium Interface
10/31/13	MKTF-10	01/21/14	4.00	6,937.51	6,937.16	6,936.63	North edge PVC Casing	-0.35	6,921.17	15.99	7 - 17	Chinle/Alluvium Interface
10/31/13	MKTF-11	01/21/14	4.00	6,931.61	6,931.34	6,930.86	South edge PVC Casing	-0.27	6,913.20	18.14	8 - 18	Chinle/Alluvium Interface
11/07/13	MKTF-12	01/21/14	4.00	6,939.70	6,942.11	6,941.88	North edge PVC Casing	2.41	6,916.51	25.60	12 - 22	Chinle/Alluvium Interface
11/12/13	MKTF-13	01/21/14	4.00	6,933.67	6,935.18	6,934.83	North edge PVC Casing	1.51	6,913.93	21.25	8 - 18	Chinle/Alluvium Interface
11/12/13	MKTF-14	01/21/14	4.00	6,925.65	6,928.02	6,927.80	North edge PVC Casing	2.37	6,910.56	17.46	4 - 14	Chinle/Alluvium Interface
10/29/13	MKTF-15	01/21/14	2.00	6,943.74	6,943.48	6,943.19	North edge PVC Casing	-0.26	6,924.00	19.48	9 - 19	Chinle/Alluvium Interface
11/07/13	MKTF-16	01/21/14	2.00	6,951.00	6,950.58	6,950.58	North edge PVC Casing	-0.42	6,936.48	14.10	4 - 14	Chinle/Alluvium Interface
11/14/13	MKTF-17	01/21/14	2.00	6,945.79	6,945.76	6,945.64	North edge PVC Casing	-0.03	6,921.65	24.11	14 - 24	Chinle/Alluvium Interface
11/15/13	MKTF-18	01/13/14	2.00	6,950.97	6,950.65	6,950.17	North edge PVC Casing	-0.32	6,925.27	25.38	17 - 27	Chinle/Alluvium Interface
11/05/13	MKTF-19	04/30/14	2.00	6,944.89	6,944.67	6,944.34	North edge PVC Casing	-0.22	6,927.20	17.47	10 - 20	Chinle/Alluvium Interface
02/10/14	MKTF-20	04/30/14	4.00	6,951.89	6,951.78	6,951.17	North edge PVC Casing	-0.11	6,941.89	9.89	2 - 10	Chinle/Alluvium Interface
02/10/14	MKTF-21	04/30/14	4.00	6,952.68	6,952.57	6,952.00	North edge PVC Casing	-0.11	6,942.68	9.89	2 - 10	Chinle/Alluvium Interface
04/30/14	MKTF-22	04/30/14	2.00	6,939.76	6,942.31	6,938.57	North edge PVC Casing	2.55	6,907.06	35.25	22 - 32	Chinle/Alluvium Interface
04/30/14	MKTF-23	04/30/14	2.00	6,927.23	6,929.98	6,925.79	North edge PVC Casing	2.75	6,909.62	20.36	7 - 17	Chinle/Alluvium Interface
04/30/14	MKTF-24	04/30/14	2.00	6,926.07	6,928.72	6,924.62	North edge PVC Casing	2.65	6,898.25	30.47	18 - 28	Chinle/Alluvium Interface
04/30/14	MKTF-25	04/30/14	2.00	6,913.35	6,916.19	6,911.79	North edge PVC Casing	2.84	6,896.76	19.43	6 - 16	Chinle/Alluvium Interface
04/30/14	MKTF-26	04/30/14	2.00	6,912.55	6,915.31	6,911.35	North edge PVC Casing	2.76	6,898.16	17.15	4 - 14	Chinle/Alluvium Interface
04/30/14	MKTF-27	04/30/14	2.00	6,915.36	6,917.90	6,914.18	North edge PVC Casing	2.54	6,903.18	14.72	2 - 12	Chinle/Alluvium Interface

APPENDIX C-2.1
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT
MKTF-01 through MKTF-45

Date of Installation	Well ID Number	Survey Measurement Date ¹	Casing Diameter (Inch)	Ground Level Elevations (ft)	Well Casing Rim Elevations (ft)	Ground Elevation Inside Steel Sleeve (ft)	Measuring Point Description	Stick-up length (ft)	Well Casing Bottom Elevations (ft)	Total Well Depth ² (ft)	Screened Interval Depth Top to Bottom (ft)	Stratigraphic unit in which screen exists
04/30/14	MKTF-28	04/30/14	2.00	6,918.67	6,921.52	6,917.51	North edge PVC Casing	2.85	6,905.36	16.16	3 - 13	Chinle/Alluvium Interface
04/30/14	MKTF-29	04/30/14	2.00	6,898.83	6,901.62	6,897.67	North edge PVC Casing	2.79	6,878.78	22.84	10 - 20	Chinle/Alluvium Interface
04/30/14	MKTF-30	04/30/14	2.00	6,898.10	6,900.80	6,896.68	North edge PVC Casing	2.70	6,877.60	23.20	10 - 20	Chinle/Alluvium Interface
04/30/14	MKTF-31	04/30/14	2.00	6,904.26	6,906.87	6,903.11	North edge PVC Casing	2.61	6,884.06	22.81	6 - 21	Chinle/Alluvium Interface
04/30/14	MKTF-32	04/30/14	2.00	6,908.44	6,911.11	6,907.16	North edge PVC Casing	2.67	6,883.36	27.75	9.5 - 24.5	Chinle/Alluvium Interface
04/30/14	MKTF-33	04/30/14	2.00	6,936.59	6,939.75	6,936.59	North edge PVC Casing	3.16	6,906.55	33.20	20 - 30	Chinle/Alluvium Interface
04/30/14	MKTF-34	04/30/14	2.00	6,942.42	6,945.35	6,943.52	North edge PVC Casing	2.93	6,917.67	27.68	9.5 - 24.5	Chinle/Alluvium Interface
11/19/14	MKTF-35	12/16/14	2.00	6,951.90	6,951.65	6,951.25	North edge PVC Casing	-0.25	6,935.20	16.45	6 - 16	Chinle/Alluvium Interface
11/19/14	MKTF-36	12/16/14	2.00	6,950.67	6,950.12	6,949.87	North edge PVC Casing	-0.55	6,934.67	15.45	5 - 15	Chinle/Alluvium Interface
11/18/14	MKTF-37	12/16/14	2.00	6,959.07	6,958.87	6,958.62	North edge PVC Casing	-0.20	6,934.27	24.60	4 - 24	Chinle/Alluvium Interface
11/20/14	MKTF-38	12/16/14	2.00	6,955.17	6,954.89	6,954.54	North edge PVC Casing	-0.28	6,934.60	20.29	5 - 20	Chinle/Alluvium Interface
11/14/14	MKTF-39	12/16/14	2.00	6,953.97	6,953.75	6,953.12	North edge PVC Casing	-0.22	6,938.55	15.20	5 - 15	Chinle/Alluvium Interface
11/13/14	MKTF-40	12/16/14	2.00	6,891.35	6,894.73	6,890.48	North edge PVC Casing	3.38	6,871.09	23.64	5 - 20	Chinle/Alluvium Interface
11/14/14	MKTF-41	12/16/14	2.00	6,891.11	6,893.64	6,889.80	North edge PVC Casing	2.53	6,853.54	40.10	22 - 37	Chinle/Alluvium Interface
11/12/14	MKTF-42	12/16/14	2.00	6,890.42	6,892.95	6,888.75	North edge PVC Casing	2.53	6,859.80	33.15	10 - 30	Chinle/Alluvium Interface
11/11/14	MKTF-43	12/16/14	2.00	6,874.12	6,876.90	6,873.22	North edge PVC Casing	2.78	6,861.47	15.43	2 - 12	Chinle/Alluvium Interface
11/11/14	MKTF-44	12/16/14	2.00	6,867.41	6,869.95	6,866.06	North edge PVC Casing	2.54	6,818.80	51.15	38 - 48	Chinle/Alluvium Interface
Unknown ³	MKTF-45	01/12/15	4.00	6,948.63	6,949.59	6,948.27	North edge PVC Casing	0.96	6,919.35	30.24	20 - 30	Chinle/Alluvium Interface

NOTES:

- 1) 1/21/14 AND 4/30/14 - Survey conducted by DePauli Engineering. 12/16/14 and 1/12/15 - Survey conducted by HEI - Hammon Enterprises, Inc. Professional licensed surveyors.
- 2) Depth to bottom field verified 2/4/2015 using a bottom sensing meter, Testwell Water Level Meter with bottom sensing indicator.
- 3) Pre-existing well - Well logs, survey data unavailable for well identification. Re-labeled as MKTF-45.

APPENDIX C-3
WELL INFORMATION - SURVEY DATA, SCREENED INTERVAL, STRATIGRAPHIC UNIT
ARTESIAN WATER WELLS

Date of Installation	Well ID Number	Submersible pump depth (feet)	Casing Diameter (Inch)	Well Head Elevation Mark* (North) (feet)	Well Head Elevation Mark* (West) (feet)	Well Head Elevation Mark* (Z) (feet)	Measuring Point Description	Total Well Depth (feet)	Well Casing Bottom Elevation ¹ (feet)	Stratigraphic unit	Aquifer
9/24/1956	PW-2	800	16.0	3,300.40	4,694.28	162.78	1st Discharge tee or elbow	1,075.00	2,225.40	Chinle	San Andreas/Yeso Aquifer
April 1979	PW-3	900	14.0	2,932.83	1,387.79	248.00	1st Discharge tee or elbow	1,030.00	1,902.83	Chinle	San Andreas/Yeso Aquifer
11/12/1999	PW-4	750	12.0 ²	1,895.73	2,979.78	178.51	1st Discharge tee or elbow	1,020.00 ³	819.73	Chinle	San Andreas/Yeso Aquifer

NOTES:

* Basis of survey Refinery Control Point at 1000W, 2575N, plant elevation = 254.87 feet and MSL elevation = 6959.41 feet.

1) Well casing bottom elevation using Well Head Elevation Mark (North) as reference point.

2) Actual well casing diameter is 12 inches. The 176 feet of 24 inch steel casing is the actual cemented support for development of the well.

3) The actual total well depth is 1020 feet with additional 56 feet x 7-7/8 inch diameter open exploratory hole which was accounted for as total well depth of 1076 feet.

At the time of the survey by DePauli Engineering the artesian wells were not included as these wells have never been listed on the summary table or had questionable elevations. These wells are sampled every three years and are not required to be gauged when sampling. A copy of an original survey dated February 13, 2003 conducted by DePauli Engineering is attached for reference.

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX D



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 18'
Saturation Depth : 6.5'
Start Date/Time : 10/11/19 - 10:00
Finish Date/Time : 10/11/19 - 13:30

WELL NO. MKTF-46

(Sheet 1 of 1)

Elev., TOC (ft. msl) : 6957.60
Elev., PAD (ft. msl) : 6955.02
Elev., GL (ft. msl) : 6954.73
N : 1633095.72
E : 2546068.60
Comments : Hand augered to five feet


Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation	Completion Results
							DESCRIPTION	
-3								
-2								
-1								
0								
1	0			CL	100			Steel Protective Casing
2	0			CL	100	⊗		Top of Casing 2.87' Above Ground Level
3				CL	100			Concrete Pad 4' x 4' x 4'
4	0			CL	100			Bentonite Pellets
5	0			CL	100			2" Sch 40 PVC w/Threaded Joints
6	105	▼		CL	70	⊗		
7	58.5			CL	70	⊗		
8				CH	100			10/20 Sieve Sand Filter Pack
9	0			CL	70			2" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints
10				CL	90			
11	0			SS	70			
12				SS	60	⊗		
13	0			SS	-			2" Flush Threaded Sch 40 PVC Cap
14				SS	-			
15				SS	-			
16				SS	-			
17				SS	-			
18				SS	-			
19				SS	-			

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190

02-28-2020 C:\Users\jreis\Desktop\AllWESTMarketing Tank Farm\MKTF 46 bor

							Geologist : Tracy Payne Drilling Company : Terracon Driller : Cothron Drilling Rig : CME 55 Track Rig Drilling Method : Hollow-Stem Augers 8" Sampling Method : 2' Split Spoon Total Depth : 14' Saturation Depth : 10' Start Date/Time : 10/14/19 - 09:40 Finish Date/Time : 10/14/19 - 12:25		WELL NO. MKTF-47 (Sheet 1 of 1)	
							Marathon Petroleum Company, LP Gallup Refinery - Up-Gradient MKTF Well Installations WEST19032-02		Elev., TOC (ft. msl) : 6959.09 Elev., PAD (ft. msl) : 6959.51 (flush w/ asphalt) Elev., GL (ft. msl) : 6956.51 N : 1633268.22 E : 2546444.16 Comments : Cored through asphalt. Hand augered to 5'	
Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation  Saturation		Completion Results Well No. MKTF-47	
							DESCRIPTION			
-3							ASPHALT			
-2							SANDY GRAVELLY CLAY - low, stiff, damp, light reddish brown, no odor, 10-20 mm gravel.			
-1										
0	-				-					
1	1.0			CL	100					
2	4.6									
3	4.2									
4	4.5									
5							GRAVELLY CLAY - Similar to above (STA).			
6	5.0			CL	70					
7										
8	14.4			CL	50		SILTY CLAY - low, firm, damp, brown, no odor, trace gravel.			
9							SILTY CLAY - STA, no odor.			
10	11.1			CL/GC	80		GRAVELLY CLAY/CLAYEY GRAVEL - low, firm, damp, brown clay with 5-30 mm gravel, chert and sandstone gravel.			
11	11.1			GC	90		CLAYEY GRAVEL - STA, very damp to very moist at base, no odor.			
12	10.0			SS	90		SILTSTONE - very fine, dense, damp, gray.			
13	9.0			SS	90		SILTSTONE - very fine, very dense, damp, brown with sandstone present, mudstone present at base, no odor.			
14										
15				SS	-		SILTSTONE - STA.			

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 18'
Saturation Depth : 4'
Start Date/Time : 10/14/19 - 13:30
Finish Date/Time : 10/14/19 - 16:50

WELL NO. MKTF-48

(Sheet 1 of 2)

Elev., TOC (ft. msl) : 6961.73
Elev., PAD (ft. msl) : 6959.41
Elev., GL (ft. msl) : 6959.24
N : 1633715.07
E : 2546508.76
Comments : Hand augered to 4.5'.
Refusal @ 4.5' in gravel.

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	DESCRIPTION	Completion Results
								Well No. MKTF-48
-3								Steel Protective Casing
-2								Top of Casing 2.49' Above Ground Level
-1								
0								Concrete Pad 4' x 4' x 4'
1	83.9			CL	100		SILTY CLAY - low, firm, damp, dark brown, odor.	Bentonite Pellets
2	181.6			CL	100		SILTY CLAY - Similar to above (STA), black, hydrocarbon odor.	2" Sch 40 PVC w/Threaded Joints
3	513			CL	100			
4	975			SW	100		GRAVELLY SAND - fine, loose, moist to very moist, SPH present, hydrocarbon odor, oily clayey at 4.5' with gravel.	
5	1414			CL	90		GRAVELLY SANDY CLAY - low, soft, damp, dark brown, moist to saturated in sand, small gravel lense from 5.25' to 5.5', SPH/oily.	
6				CL	90		GRAVELLY CLAY - low, firm, damp, hydrocarbon odor, brown.	10/20 Sieve Sand Filter Pack
7	760			CL	100		SILTY CLAY - low, firm, damp, brown, hydrocarbon odor, light tan silt present in pockets.	2" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints
8				CH	100		CLAY - high, stiff, damp, brown, hydrocarbon odor, light tan silt in pockets.	
9	160			CH	80		CLAY - STA.	
10				CL	80		SANDY CLAY - low, firm, damp to moist in clayey sand lenses, hydrocarbon odor, brown.	
11	392			CL	80			
12	511			CL			SILTY CLAY - low, firm, damp, brown grading to gray, trace gravel present, hydrocarbon odor.	
13								

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 18'
Saturation Depth : 4'
Start Date/Time : 10/14/19 - 13:30
Finish Date/Time : 10/14/19 - 16:15

WELL NO. MKTF-48


(Sheet 2 of 2)

Elev., TOC (ft. msl) : 6946.76
Elev., PAD (ft. msl) : 6959.41
Elev., GL (ft. msl) : 6959.24
N : 1633715.07
E : 2546508.76
Comments : Hand augered to 4.5'.
Refusal @ 4.5' in gravel.

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation SPH - Separate Phase Hydrocarbon
							DESCRIPTION
13	511		CL	90			
14			SM	90			SILTY SAND/SANDY SILT - very fine grain, compact, damp, gray, hydrocarbon odor.
15	398		SS	100			SILTSTONE - very fine, dense, gray, damp, trace sandstone present, crumbly in lenses, hydrocarbon odor.
16							
17	86		SS	100			SILTSTONE - STA, trace clay and sand, hydrocarbon odor.
18							
19							
20							
21							
22							
23							
24							
25							
26							
27							
28							
29							

Completion Results

Well No. MKTF-48



1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 28'
Saturation Depth : 16'
Start Date/Time : 10/15/19 - 10:30
Finish Date/Time : 10/15/19 - 15:00

WELL NO. MKTF-49

(Sheet 1 of 2)

Elev., TOC (ft. msl) : 6946.76
Elev., PAD (ft. msl) : 6944.25
Elev., GL (ft. msl) : 6944.00
N : 1634064.06
E : 2545788.35
Comments : Hand augered to 5'.

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation	Completion Results
							DESCRIPTION	
-3								Steel Protective Casing Top of Casing 2.76' Above Ground Level Concrete Pad 4' x 4' x 4' Bentonite Pellets 2" Sch 40 PVC w/Threaded Joints 2" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints 10/20 Sieve Sand Filter Pack
-2								
-1								
0							GRAVELLY SILTY CLAY - low, firm, damp, brown, odor.	
1	6.9							
2	9.1			CL	100	X		
3	6.6							
4							CLAY - high, firm, damp, brown, no odor.	
5	4.5			CH	100			
6	9.9			CL	70		GRAVELLY SANDY CLAY - low, soft, damp, brown, no odor.	
7	11.2			SM	70		GRAVELLY CLAYEY SAND - fine, crumbly, damp, brown, no odor.	
8				SM	70		GRAVELLY CLAYEY SAND - Similar to above (STA), no odor.	
9	11.3			CL	80		SANDY CLAY - low, firm, damp, brown, fine grain sand lenses throughout.	
10				CL	80		SANDY CLAY - STA.	
11	14			SM	80		SILTY SAND - fine, loose, damp, brown, no odor.	
12								

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 28'
Saturation Depth : 16'
Start Date/Time : 10/15/19 - 10:30
Finish Date/Time : 10/15/19 - 15:00

WELL NO. MKTF-49

(Sheet 2 of 2)

Elev., TOC (ft. msl) : 6947.06
Elev., PAD (ft. msl) : 6944.25
Elev., GL (ft. msl) : 6944.00
N : 1634064.06
E : 2545788.35
Comments : Hand augered to 5'.

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation	Completion Results Well No. MKTF-49
							DESCRIPTION	
12	9.7	1600		SC	70		CLAYEY SAND - fine, compact, damp, brown, no odor.	▼ 2" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints 10/20 Sieve Sand Filter Pack 2" Flush Threaded Sch 40 PVC Cap
13				CH	80		CLAY - high, firm, damp, dark brown, no odor.	
14				CL/SC	80		CLAYEY SAND/SANDY CLAY - low, soft, damp to moist, dark brown, hydrocarbon odor, very fine grain sand.	
15								
16				SC	80		CLAYEY SAND - STA, saturated, hydrocarbon odor.	
17	-							
18				SW	70		CLAYEY GRAVELLY SAND - fine, compact to loose, saturated, brown gravel lense at 19.5', hydrocarbon odor.	
19	-							
20				SW	70		GRAVELLY SAND - STA, trace clay, hydrocarbon odor, saturated.	
21	2245			SC/CL	-		CLAYEY SAND /SANDY CLAY - low, firm, very fine sand, moist to very moist, dark brown, hydrocarbon odor.	
22							SANDY CLAY - low, firm, damp, brown, hydrocarbon odor, sand in lenses.	
23	482			CL	50			
24							CLAY - high, stiff, damp, brown, odor.	
25	20.4			CH	70			
26	19.7			SC/CL			CLAYEY SAND/SANDY CLAY - low, firm, damp, brown, odor, sand in matrix.	
27								

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190

02-28-2020 C:\Users\jreis\Desktop\AllWEST\Marketing Tank Farm\MKTF 49 bor



Marathon Petroleum Company, LP
Gallup Refinery - Up-Gradient MKTF
Well Installations
WEST19032-02

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 8"
Sampling Method : 2' Split Spoon
Total Depth : 26'
Saturation Depth : 14'
Start Date/Time : 10/15/19 - 15:45
Finish Date/Time : 10/16/19 - 11:15

WELL NO. MKTF-50

(Sheet 1 of 2)

Elev., TOC (ft. msl) : 6942.82
Elev., PAD (ft. msl) : 6940.26
Elev., GL (ft. msl) : 6939.68
N : 1634294.68
E : 2545881.16
Comments : Hand augered to refusal at 3'.






Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation	Completion Results Well No. MKTF-50
							DESCRIPTION	
-3								
-2								
-1								
0								Concrete Pad 4' x 4' x 4'
1	3.2			CL	100			Bentonite Pellets
2	169			CL	100	✕		2" Sch 40 PVC w/Threaded Joints
3	70			CL	100			
4	158.6			CL	100			
5	148.9			SM	100			2" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints
6	494			CL	100			
7	889			CL	50	✕		10/20 Sieve Sand Filter Pack
8								
9	719			CL/SC	50			
10	1892			SC	80	✕		
11	15,000			CL	80			
12								

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190

02-28-2020 C:\Users\jreis\Desktop\AllWEST\Marketing Tank Farm\MKTF 50.bor

						Geologist : Tracy Payne Drilling Company : Terracon Driller : Cothron Drilling Rig : CME 55 Track Rig Drilling Method : Hollow-Stem Augers 8" Sampling Method : 2' Split Spoon Total Depth : 26' Saturation Depth : 14' Start Date/Time : 10/15/19 - 15:45 Finish Date/Time : 10/16/19 - 11:15		WELL NO. MKTF-50 (Sheet 2 of 2)			
						Marathon Petroleum Company, LP Gallup Refinery - Up-Gradient MKTF Well Installations WEST19032-02		Elev., TOC (ft. msl) : 6942.82 Elev., PAD (ft. msl) : 6940.26 Elev., GL (ft. msl) : 6939.68 N : 1634294.68 E : 2545881.16 Comments : Hand augered to refusal at 3'.			
Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation  Saturation		Completion Results Well No. MKTF-50		
							DESCRIPTION				
12	15,000			CL	80		CLAY - STA, oily, black, very soft, strong hydrocarbon odor.				
13							SC/SM	80		CLAYEY SILTY SAND - fine, very soft, saturated, black, strong hydrocarbon odor.	
14										CLAYEY SILTY SAND - STA, dark brown, saturated, hydrocarbon odor.	
15	-			SC/SM	80		CLAYEY SILTY SAND - STA, dark brown, saturated, hydrocarbon odor.				
16							CLAYEY SILTY SAND - STA, dark brown, saturated, hydrocarbon odor.				
17	149			SS	80		SANDSTONE/SILTSTONE/CLAYSTONE - fine grain grading to very fine, compact, dense, damp, odor, gray with traces of brown.				
18							SANDSTONE/SILTSTONE/CLAYSTONE - fine grain grading to very fine, compact, dense, damp, odor, gray with traces of brown.				
19	189			SS	90		SILTSTONE - very dense, damp, light gray, faint odor.				
20							SILTSTONE - very dense, damp, light gray, faint odor.				
21											
22											
23											
24											
25											
26											
27											

1001 Louisiana Street, Suite 3250
 Houston, Texas 77002
 713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
 Austin, Texas 78759
 512-693-4190

02-28-2020 C:\Users\jreis\Desktop\AllWEST\Marketing Tank Farm\MKTF 50.bor



Marathon Petroleum Company, LP
Gallup Refinery - OW-58A
WEST20004-Phase 01

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 10"
Sampling Method : 2' Split Spoon
Total Depth : 36'
Saturation Depth : 28'
Start Date/Time : 10/17/19 - 08:15
Finish Date/Time : 10/17/19 - 15:25

WELL NO. OW-58A

(Sheet 1 of 2)

Elev., TOC (ft. msl) : 6935.88
Elev., PAD (ft. msl) : 6933.39
Elev., GL (ft. msl) : 6932.98
N : 1634802.47
E : 2547429.22
Comments : Hand Augered to
five feet

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation SPH - Separate Phase Hydrocarbon	DESCRIPTION	Completion Results	
									Well OW-58A	
-3										Steel Protective Casing
-2										Top of Casing 2.9' Above Ground Level
-1										
0	3.0							GRAVELLY SILTY CLAY - moderate, firm to stiff, damp, brown, odor.		Concrete Pad 4' x 4' x 4'
1	6.8			CL	100					
2	9.5					X				
3	9.5							CLAY - high, firm, damp, reddish brown, odor, specks of black discoloration.		
4	4.2			CH	100					
5	7.4			CH	70			CLAY - Similar to above (STA), no odor.		
6								CLAY - STA, faint odor.		Bentonite Pellets
7	9.1			CH	50					
8								CLAY - STA, faint odor.		
9	12.7			CH	80					
10						X		CLAY - high, stiff, damp, reddish brown, odor, black discoloration.		
11	65			CH	90					
12								CLAY - STA, odor, trace very fine grain sand.		4" Sch 40 PVC w/Threaded Joints
13	121			CH	100					
14								SILTY SANDY CLAY - low, firm, crumbly, damp, brown, odor, fine grain sand, no discoloration.		10/20 Sieve Sand Filter Pack
15	340			CL	90					4" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints
16	757			CL				SILTY SANDY CLAY - STA, stiff, no discoloration, odor.		
17										

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190

02-28-2020 C:\Users\jreis\Desktop\AllWEST\Marketing Tank Farm\OW 58A.bor



Marathon Petroleum Company, LP
Gallup Refinery - OW-58A
WEST20004-Phase 01

Geologist : Tracy Payne
Drilling Company : Terracon
Driller : Cothron
Drilling Rig : CME 55 Track Rig
Drilling Method : Hollow-Stem Augers 10"
Sampling Method : 2' Split Spoon
Total Depth : 36'
Saturation Depth : 28'
Start Date/Time : 10/17/19 - 08:15
Finish Date/Time : 10/17/19 - 15:25

WELL NO. OW-58A

(Sheet 2 of 2)

Elev., TOC (ft. msl) : 6935.88
Elev., PAD (ft. msl) : 6933.39
Elev., GL (ft. msl) : 6932.98
N : 1634802.47
E : 2547429.22
Comments : Hand Augered to
five feet

Depth (ft.)	PID (ppm)	Saturation	Lithology	USCS	Recovery (%)	Sample	Saturation ▼ Saturation SPH - Separate Phase Hydrocarbon	DESCRIPTION	Completion Results Well OW-58A
17	757			CL	80				
18	326			CL	90			SANDY CLAY - low, stiff, damp, light brown, crumbly, fine grain sand, odor.	
19	1001			CL	90			CLAY - moderate, very stiff, damp, brown, odor.	
20								CLAY - STA, oily, sweet/chemical odor, glossy oil spots on core.	
21	1564			CL	90				
22								CLAY - STA, increase of SPH on core and weeping from clay.	
23	1350			CL	90				
24								SILTY CLAY - low, firm, damp, brown, hydrocarbon odor, oil on outside of core and weeping from core.	
25	1670			CL	100				
26								SILTY CLAY - moderate, stiff, damp, brown, hydrocarbon odor, silty sand seams at 27', black discoloration, SPH weeping from core.	
27	1848			CL	100				
28		▼						SILTY CLAY - STA, saturated silty sand seams approximately 2" thick @ 28', 28.75' & 29.25'.	▼
29	-			CL	100				
30				CL	100			SILTY CLAY - low, firm to soft, damp to very moist, brown, hydrocarbon odor.	
31				SM	100			SILTY SAND - fine, loose to compact, saturated, dark brown, hydrocarbon odor, clayey at base.	
32				SM	90			SILTY SAND - STA, saturated, hydrocarbon odor.	
33	1429			CH	90			CLAY/SILTY CLAY - moderate to high, soft, damp, brown, hydrocarbon odor.	
34								CLAY/SILTY CLAY - STA, hydrocarbon odor.	
35	575			CH	90				
36									
37									

4" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints

10/20 Sieve Sand Filter Pack

4" Flush Threaded Sch 40 PVC Cap

4" Sch 40 PVC Slotted 0.01" Screen w/Threaded Joints

10/20 Sieve Sand Filter Pack

4" Flush Threaded Sch 40 PVC Cap

02-28-2020 C:\Users\jreis\Desktop\AllWEST\Marketing Tank Farm\OW 58A.bor

1001 Louisiana Street, Suite 3250
Houston, Texas 77002
713-955-1230

DiSorbo Consulting, LLC

8501 N. MoPac Expy, Suite 300
Austin, Texas 78759
512-693-4190

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX E



Nitrate-Nitrite Test Kit

NI-12 (1408100)

DOC326.97.00083

Test preparation

CAUTION: ⚠ Review the Safety Data Sheets (MSDS/SDS) for the chemicals that are used. Use the recommended personal protective equipment.

- Put the color disc on the center pin in the color comparator box (numbers to the front).
- Use sunlight or a lamp as a light source to find the color match with the color comparator box.
- Rinse the tubes with sample before the test. Rinse the tubes with deionized water after the test.
- If the color match is between two segments, use the value that is in the middle of the two segments.
- If the color disc becomes wet internally, pull apart the flat plastic sides to open the color disc. Remove the thin inner disc. Dry all parts with a soft cloth. Assemble when fully dry.
- If the sample contains more than 40 mg/L nitrate-nitrogen or more than 0.4 mg/L nitrite-nitrogen, dilute the sample as follows. Use the dropper to add 1 mL of sample to each tube. Dilute the sample to the 5-mL mark with deionized water. Use the diluted sample in the test procedure and multiply the result by 5.


Nitrate

- The reagent contains a small quantity of cadmium metal that does not dissolve. Dispose of reacted solutions according to local, state and federal regulations.
- To verify the test accuracy, use a standard solution as the sample.
- To record the test result as mg/L NO_3^- , multiply the test result by 4.4.


Nitrite

- Undissolved reagent does not have an effect on test accuracy.
- Strong oxidizing and reducing substances interfere with the test. Cupric and ferrous ions cause low results. Ferric, mercurous, silver, bismuth, antimonous, lead, auric, chloroplatinate and metavanadate ions cause a precipitate to develop.
- To record the test result as mg/L NO_2^- , multiply the test result by 3.33.
- Nitrite-nitrogen develops during the biological decomposition of organic nitrogen compounds. Nitrite is also used as a corrosion inhibitor in industrial process water and as a food preservative in the food industry. Nitrites react with oxygen to form nitrates and are not usually found in surface waters.


Test procedure—Nitrate-nitrogen (0–40 mg/L NO_3^- -N)




1. Fill two tubes to the first line (5 mL) with sample.




2. Put one tube into the left opening of the color comparator box.




3. Add one NitraVer 5 Nitrate Reagent Powder Pillow to the second tube.




4. Put a cap on the tube. Shake vigorously for 1 minute.




5. Wait 1 minute. An amber color develops.



6. Put the second tube into the color comparator box.



7. Hold the color comparator box in front of a light source. Turn the color disc to find the color match.



8. Read the result in mg/L in the scale window.








Replacement items

Description	Unit	Item no.
NitraVer® 5 Nitrate Reagent Powder Pillows, 5 mL	100/pkg	1403599
NitriVer® 3 Nitrite Reagent Powder Pillows, 5 mL	100/pkg	1407899
Color disc, nitrate nitrogen, 0–40 mg/L	each	9261400
Color disc, nitrite nitrogen, 0–0.4 mg/L	each	9262300
Color comparator box	each	173200
Dropper, glass, 0.5- and 1.0-mL marks	5/pkg	1419705
Glass viewing tubes, 18 mm	6/pkg	173006
Stopper, rubber, size 2	12/pkg	211802

Optional items

Description	Unit	Item no.
Nitrate nitrogen standard solution, 10.0 mg/L NO_3^- -N	500 mL	30749
Plastic viewing tubes, 18 mm, with caps	4/pkg	4660004
Caps for plastic viewing tubes (4660004)	4/pkg	4660014
Water, deionized	500 mL	27249

Test procedure—Nitrite-nitrogen LR (0–0.4 mg/L NO₂⁻-N)



1. Fill two tubes to the first line (5 mL) with sample.

2. Put one tube into the left opening of the color comparator box.

3. Add one NitrVer 3 Nitrite Reagent Powder Pillow to the second tube.

4. Put a cap on the tube. Shake for 1 minute. A pink color develops.

5. Wait 10 minutes. Read the result within 15 minutes.

6. Put the second tube into the color comparator box.

7. Hold the color comparator box in front of a light source. Turn the color disc to find the color match.

8. Read the result in mg/L in the scale window.



Attachment B: Redline IWP Report



**Marathon
Petroleum Company LP**

Facility Wide Ground Water Monitoring Work Plan – Updates for 2020

**Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301
(505) 722-3833**

Submitted: April 8, 2020



Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision according to a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Robert S. Hanks
Refinery General Manager

Date

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

Executive Summary

Western Refining Southwest, Inc. conducts quarterly, semi-annual and annual ground water monitoring at its Gallup Refinery on a site wide basis. The Ground Water Monitoring Work Plan (Plan) documents any additions or revisions in ground water monitoring and also details the sampling procedures used.

This Plan divides the facility into six monitoring groups. Group A consists of the boundary wells situated along the northwest corner of the refinery property and monitoring wells around the land treatment area (LTU). Group B consists of a cluster of wells at the aeration basin and at the sanitary treatment pond 1 (STP-1) near the Waste Water Treatment Unit. Group C consists of the observation wells on the northeast section of the refinery including four product recovery wells. One new well (OW-58A) was installed in this area in 2019. Group D includes the process/production wells and the four observation wells located on the south-southwest section of the property. Group E includes 49 permanent monitoring wells installed to delineate the extent of a hydrocarbon plume associated with a seep discovered in 2013 directly west of the crude tanks (T-101, 102) and more recently any other potential releases within this area; included in this group is a pre-existing well located directly west of the truck loading terminal. Five new wells (MKTF-46, MKTF-47, MKTF-48, MKTF-49, and MKTF-50) were installed in this area in 2019. Group F includes the sampling requirements for the evaporation ponds and effluent from the sanitary treatment pond (STP-1).

The Gallup Refinery will periodically review facility-wide monitoring data and assess the monitoring program presented in this Plan. Revisions to the Plan, as necessary, will then be presented annually for agency review and approval. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target chemicals to be analyzed.

The Gallup Refinery follows the most current approved sampling/monitoring schedule from NMED: *Approval with Modifications Revised Facility-Wide Ground Water Monitoring Work Plan, Gallup Refinery – Updates for 2019*, HWB WRG 19-012, dated November 15, 2019.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

The Gallup Refinery has created a monitoring work plan with quality assurance practices and controls as well as standard procedures for sampling, and a schedule of activities to monitor ground water and surface water at select locations of the Gallup Refinery. The persons responsible for the implementation and oversight of this plan are:

Refinery General Manager

- Robert S. Hanks

Remediation Project Manager

- Brian K. Moore

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301

**Marathon
Petroleum Company LP**

TABLE OF CONTENTS

Executive Summary	iii
1.0 Introduction.....	1
1.1 Scope of Activities	1
1.2 Facility Ownership and Operation	2
2.0 Background Information	4
2.1 Historical and Current Site Use.....	4
2.2 Potential Receptors	8
2.3 Waste Contaminant Types, Characteristics, and Possible Sources	9
2.4 Summary of contaminant releases that could contribute to possible ground water contamination	12
2.4.1 Separate Phase Hydrocarbons.....	12
2.4.2 Methyl Tert Butyl Ether	15
2.4.3 NAPIS Unit	16
2.4.4 Aeration Basin	16
2.4.5 North Drainage Ditch.....	19
2.4.6 OW-14 Source Area	19
3.0 Site Conditions.....	21
3.1 Current site topography and location of natural and manmade structures	21
3.2 Drainages	21
3.3 Vegetation types	22
3.4 Erosion features	23
3.5 Subsurface conditions	23
3.5.1 Soil types and associations	23
3.5.2 Stratigraphy.....	24
3.5.3 Presence and flow direction of ground water	24
4.0 Investigation Methods.....	25
4.1 Ground Water Sampling Methodology.....	25
4.1.1 Well Gauging	25
4.1.2 Well Purging	26
4.2 Ground Water Sample Collection	27
4.2.1 Sample Handling.....	28
4.2.2 General Well Sampling Procedures	29
4.3 Analytical Methods.....	32
4.4 Quality Assurance Procedures.....	32
4.4.1 Equipment Calibration Procedures and Frequency	33
4.4.2 Field QA/QC Samples.....	33
4.4.3 Laboratory QA/QC Samples.....	34
4.4.4 Laboratory Deliverables.....	34

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

4.4.5 Review of Field and Laboratory QA/QC Data.....	36
4.4.6 Blanks, Field Duplicates, Reporting Limits and Holding Times.....	36
4.4.7 Representativeness and Comparability	37
4.4.8 Laboratory Reporting, Documentation, Data Reduction, and Corrective Action	38
5.0 Monitoring and Sampling Program	39
5.1 Group A Through Group F Sampling Locations.....	39
5.1.1 Sampling Locations.....	39
5.2 Evaporation Ponds, Outfalls	40
5.2.1 Sampling Locations.....	40
6.0 Monitoring Program Revisions	41
6.1 Requests for Modifications to Sampling Plan	41

List of Figures

Figure 1: Regional Map

Figure 2: Topographic Map

Figure 3: Generalized Relationship of Soils

Figure 4: Facilities and Well Groups — 2020

[Figure 4.1: French Drain Location](#)

[Figure 4.2: Proposed Monitoring Well Locations](#)

[Figure 4.3: Proposed Monitoring Well Location](#)

Figure 5: Sonsela Water Elevation Map - 2020

Figure 6: 2020 Alluvium/Chinle Gp Interface Water Elevation Map

Figure 7: Stormwater Pollution Prevention Plan – Site Plan

List of Appendices

Appendix A: Gallup Refinery Field Sampling Collection and Handling Standard Procedures

Appendix B: 2020 Ground Water Monitoring Schedule

Appendix C: Well Data Tables, C-1, C-2, C-3

Appendix D: Well Boring Logs

Appendix E: Field Methods for Nitrite Analysis

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

List of Acronyms

AL	Aeration Lagoon
API	American Petroleum Institute
BMP	Best Management Practices
BS	Blank Spike
BSD	Blank Spike Duplicate
BTEX	Benzene, Toluene, Ethylbenzene, Xylene
CFR	Code of Federal Regulations
DQO	Data Quality Objective
DRO	Diesel Range Organics
DTB	Depth to Bottom
DTW	Depth to Water
EP	Evaporation Pond
EPA	Environmental Protection Agency
FT.	Foot
FWGWMP	Facility Wide Ground Water Monitoring Plan
GPM	Gallons per minute
GRO	Gasoline Range Organics
HNO ₃	Nitric Acid
HWB	Hazardous Waste Bureau
IDW	Investigation Derived Waste
LDU	Leak Detection Unit
LTU	Land Treatment Unit
ML	Milliliter
MCL	Maximum Contaminant Level
MS	Matrix Spike
MSD	Matrix Spike Duplicate
MTBE	Methyl Tert Butyl Ether
NAICS	North American Industry Classification System

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

List of Acronyms – Continued

NAPIS	New American Petroleum Institute Separator
NMAC	New Mexico Administrative Code
NMED	New Mexico Environment Department
NOI	Notice of Intent
OAPIS	Old American Petroleum Institute Separator
OW	Observation Well
OCD	Oil Conservation Division
ORP	Oxidation-Reduction Potential
PPE	Personal Protective Equipment
PPM	Parts per million
PSTB	Petroleum Storage Tank Bureau
PVC	Polyvinyl Chloride
PW	Process Well
QA	Quality Assurance
QC	Quality Control
RW	Recovery Well
RCRA	Resource Conservation and Recovery Act
SIC	Standard Industrial Classification
SOP	Standard Operating Procedure
SPH	Separate Phase Hydrocarbon
STP	Sanitary Treatment Pond
SVOC	Semi-volatile Organic Compound
SWMU	Solid Waste Management Unit
SWPP	Storm Water Pollution Prevention Program
TOC	Total Organic Content
VOC	Volatile Organic Compound
WQCC	Water Quality Control Commission
WWTP	Waste water treatment plant

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates
 Gallup Refinery
 92 Giant Crossing Road
 Gallup, NM 87301



1.0 Introduction

This Facility-Wide Ground Water Monitoring Work Plan (Plan) has been prepared for the implementation of a ground water monitoring program at the Gallup Refinery owned by Marathon Petroleum Company (MPC) and operated by Western Refining Southwest, Inc. (“Gallup Refinery,” “Refinery,” or “Facility”).

1.1 Scope of Activities

This Plan has been prepared to collect data that will be used to characterize the nature and extent of potential impacts to ground water at the Gallup Refinery. The monitoring plan is designed to assist in evaluating any levels of contaminants that exceed compliance standards. This Plan divides the facility into six groups for periodic monitoring:

GROUP A	GROUP B	GROUP C	GROUP D	GROUP E	GROUP F
BW-1A, 1B, 1C	GWM-1, 2, 3	OW-13, 14, 29, OW-30	PW-2, 3, 4	MKTF-01 thru MKTF-50	EP-2, 3, 4, 5, 6, 7, 8, 9
BW-2A, 2B, 2C	NAPIS 1, 2, 3, KA-3, OW-62	OW-50, 52, 53, OW-54, 55, 56, OW-57, 58, OW-58A, 61, OW-63, 64, 65	OW-1, 10		EP-11, 12A, 12B
BW-3A, 3B, 3C	OAPIS-1	RW-1, 2, 5, 6	OW-11, 12		STP-1 to EP- 2, Boiler Water Inlet to EP-9
BW-4A, 4B	OW-59, 60				
BW-5A, 5B, 5C					
MW-1, 2, 4, 5	LDU (3)				
SMW-2, 4	STP1-NW, SW				

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Group A consists of the boundary wells situated along the northwest corner of the refinery property and the monitoring wells around the land treatment unit (LTU). Group B consists of a cluster of monitoring wells and leak detection units for the NAPIS at the aeration basin and at the sanitary treatment pond. Group C includes the observation wells located on the northeast section of the plant and includes recovery wells from which small quantities of free product has been continually removed. Group D includes the process/production wells and four observation wells located on the south, southwest section of the refinery property. Group E includes a total of 49 monitoring wells installed to delineate a hydrocarbon plume associated with a seep discovered west of the crude tank (Tank 101); included in this group is a pre-existing well located directly west of the truck loading terminal. Group F includes sampling requirements for the evaporation ponds and for the effluent from the sanitary treatment pond. Designated wells and sample points identified are monitored on a quarterly, semi-annual and annual basis following the procedures presented in this Plan.

The Gallup Refinery periodically reviews facility-wide monitoring data and evaluates the monitoring program presented in this Plan. Annual revisions to the Plan will be presented for agency review and approval. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target chemicals to be analyzed.

1.2 Facility Ownership and Operation

This Plan pertains to the Gallup Refinery located at Exit 39 on Interstate I-40. This refinery is located at Jamestown, New Mexico, approximately 17 miles east of Gallup. Figure 1 shows the regional location of the Gallup Refinery.

The owner is:

Marathon Petroleum Company (Parent Corporation)
539 South Main Street
Findlay, OH 45840

Operator: Western Refining Southwest Inc. (Postal Address)
Gallup Refinery
92 Giant Crossing Road
Gallup, New Mexico 87301

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Western Refining Southwest Inc. (physical address)
Gallup Refinery
I-40, Exit 39 (17 Miles East of Gallup, NM)
Jamestown, New Mexico 87347

The following regulatory identification and permit governs the Gallup Refinery:

- SIC code 2911 (petroleum refining) and NAICS code 32411 apply to the Gallup Refinery;
- U.S. EPA ID Number NMD000333211;
- New Mexico OCD Abatement Plan Number AP-111; and
- 2015 NPDES MSGP, ID #NMR053168.

The facility status is corrective action/compliance. Quarterly, semi-annual and annual ground water sampling is conducted at the facility to evaluate present contamination.

The refinery is situated on an 810-acre irregular shaped tract of land that is largely located within the lower one quarter of Section 28 and throughout Section 33 of Township 15 North, Range 15 West of the New Mexico Prime Meridian. A small component of the property lies within the northeastern one quarter of Section 4 of Township 14 North, Range 15 West. Figure 2 is a topographic map showing the general layout of the refinery in comparison to the local topography.

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



2.0 Background Information

2.1 Historical and Current Site Use

Built in the 1950's, the Gallup Refinery is located within a rural and sparsely populated section of McKinley County in Jamestown, New Mexico, 17 miles east of Gallup, New Mexico. The setting is a high desert plain on the western slope of the Continental Divide. The nearest population centers are the Pilot Flying J Travel Center (Travel Center) refueling plaza, the Interstate 40 highway corridor, and a small cluster of residential homes located on the south side of Interstate 40 approximately 2 miles southwest of the refinery (Jamestown). The surrounding land is comprised primarily of public lands and is used for cattle and sheep grazing.

The refinery is currently idled. When ~~The-the~~ refinery is operating, it primarily receives crude oil via two 6-inch diameter pipelines; ~~two pipelines~~ from the Four Corners Area, which enter the refinery property from the north. In addition, the refinery also ~~receives-received~~ natural gasoline feed stock via a 4-inch diameter pipeline that comes in from the west along the Interstate 40 corridor from the Western Refining Southwest, Inc. - Wingate Plant (formerly Conoco gas plant). Crude oil and other products also arrived d at the site via railroad cars. These feed stocks ~~are-were~~ then stored in tanks until refined into products.

The Gallup Refinery is a crude oil refining and petroleum products manufacturing facility. The Standard Industrial Classification (SIC) code is 2911 and the North American Industry Classification System Code (NAICS) is 32411. There are no organic chemicals, plastics, or synthetic fibers manufactured that contribute to our process flow of waste water. The Gallup Refinery does not manufacture lubricating oils.

The refinery incorporates various processing units that convert crude oil and natural gasoline into finished products. These units are briefly described as follows.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

- Crude Distillation Unit - separates crude oil into various fractions; including gas, naphtha, light oil, heavy oil, and residuum.
- Fluidized Catalytic Cracking Unit (FCCU) - dissociates long-chain hydrocarbon molecules into smaller molecules, and essentially converts heavier oils into naphtha and lighter oils.
- Alkylation Unit - combines specific types of hydrocarbon molecules into a high-octane gasoline blending component.
- Reforming Unit - breaks up and reforms low octane naphtha molecules to form high octane naphtha.
- Hydro-Treating Unit - removes undesirable sulfur and nitrogen compounds from intermediate feed stocks, and also saturates these feed stocks with hydrogen to make diesel fuel.
- Treater Unit - removes impurities from various intermediate and blending feed stocks to produce finished products that comply with sales specifications.
- Ammonium Thiosulfate Unit - accepts high H₂S and ammonia containing gas streams from the Amine and the Sour Water Stripper units, and converts these into a useful fertilizer product, ammonium thiosulfate.
- Sulfur Recovery Unit - converts and recovers various sulfur compounds from the gases and liquids produced in other processing units to create a solid elemental sulfur byproduct.
- Waste Water Treatment Plant - processes and treats refinery waste and storm water before releasing to treatment ponds.

As a result of these processing steps, the refinery produces a wide range of petroleum products including propane, butane, unleaded gasoline, diesel, and residual fuel. The refinery also produces commercial products of fertilizer and solid elemental sulfur. In addition to the afore-mentioned processing units, various other equipment and systems support the operation of the refinery and are briefly described as follows.

Storage tanks are used throughout the refinery to hold and store crude oil, natural gasoline, intermediate feed stocks, finished products, chemicals, and water, which are all located above ground. Capacity of these tanks range in size from 80,000 barrels to less than 1,000 barrels.

Pumps, valves, and piping systems are used throughout the refinery to transfer various liquids among storage tanks and processing units. A railroad spur track and a railcar loading rack are used to transfer feed stocks and products from refinery storage tanks into and out of railcars. Several tank truck loading racks are used at the refinery to load out finished products and also receive crude oil, other feed stocks, additives, and chemicals.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Gasoline and diesel are delivered to the Travel Center via tanker truck. An underground diesel pipeline exits between the refinery and the Travel Center. In 2013 the underground diesel line from Gallup Refinery to the Travel Center was replaced and put back in service on February 3, 2014, but was subsequently removed from service. The replaced line runs above ground from the marketing area of the refinery for approximately 150 feet and continues underground to the Travel Center.

A firefighting training facility is used to conduct employee firefighting training. Waste water from the facility, when training is conducted, is pumped into a tank which is then pumped out by a vacuum truck. The vacuum truck pumps the oily water into a process sewer upstream of the New API Separator (NAPIS).

The process waste water system is a network of curbing, paving, catch basins, and underground piping used to collect waste water from various processing areas within the refinery. The waste water effluent then flows into the equalization tanks and the NAPIS where the oil is separated from water based on the principle that, given a quiet surface, oil will float to the water surface where it can be skimmed off. The skimmed slop is passed to a collection chamber where it is pumped back into the refinery process. The clarified water is routed to a waste water treatment plant (WWTP) where benzene is removed via granular activated carbon (GAC) canisters that are placed at the effluent of the dissolved gas flotation (DGF) unit. WWTP operations alternate the configuration of these GAC canisters from a single setup to an in-series setup (i.e. primary and secondary canister). To help monitor the breakthrough of these GAC canisters, several waste water samples are taken at the effluent of the last GAC canister. Results from benzene analysis of the waste water samples are monitored to manage the breakthrough from the GAC canisters. When benzene values exceed 0.4 ppm, one or more of the following actions are taken: GAC canister configuration is modified to an in-series set-up; GAC canister is replaced with fresh carbon; GAC canister effluent is recirculated back through the WWTP. The treated water flows from the GAC canisters into pond STP-1. STP-1 consists of two bays, north and south and each bay is equipped with five aerators per bay. Effluent from STP-1 then flows into Evaporation Pond 2 and gravitated to the rest of the ponds.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

During episodes of unit upsets or major storm events, the waste water is held in one of the three equalization tanks, T-35, T-27 and T-28 which are used to handle large process and storm water flows allowing the flow to the NAPIS to be controlled. These tanks are also used to store waste water if problems are encountered with the downstream equipment, i.e., NAPIS and the WWTP.

The storm water system is a network of valves, gates, berms, embankments, culverts, trenches, ditches, natural arroyos, and retention ponds that collect, convey, control, and release storm water that falls within or passes through refinery property. Storm water that falls within the processing areas is considered equivalent to process waste water and is sent to tanks T-35, T-27 and T-28 when needed before it reaches the NAPIS, WWTP, STP-1 and into Evaporation Pond 2 where flow is gravitated to the rest of the ponds. Storm water discharge from the refinery is very infrequent due to the arid desert-like nature of the surrounding geographical areas.

At the evaporation ponds, waste water is converted into vapor via solar and mechanical wind-effect evaporation via two 80 gallons per minute electrically driven evaporation pond spraying snow machines located between ponds 4 and 5. Two additional 66 GPM (gallons per minute) evaporation pond sprayers were installed in October 2014 between ponds 3 and 4 for a total of four evaporators. No waste water is currently discharged from the refinery to surface waters of the state. Historically, reverse osmosis reject water from the Boiler House area was discharged to Evaporation Pond 9. In September 2015, Gallup Refinery submitted a Notice of Intent requesting continued coverage under the 2015 NPDES Multi-Sector General Permit which was approved on October 8, 2015 (NMR053168). The refinery maintains a Storm Water Pollution Prevention Plan (SWPPP) that includes Best Management Practices (BMPs) for effective storm water pollution prevention (updated September 2015). The refinery has constructed several new berms in various areas and improved outfalls (installed barrier dams equipped with gate valves) to minimize the possibility of potentially impacted runoff leaving the refinery property and also to minimize the stormwater run-on from the I-40 interchange and the Travel Center onto refinery property.

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



2.2 Potential Receptors

Potential receptors at the facility also include those that may arise from future land uses. Currently, these include on-site workers, nearby residents, wildlife, and livestock. There is extensive and regular 24-hour patrolling by facility security personnel; therefore, the refinery can discount the possibility of an inadvertent or deliberate intruder becoming exposed to contamination in groundwater that has reached the surface in some form.⁺ The major route to exposure of humans would be from contaminants reaching a drinking water well. Other routes could be from showering, cooking, etc. with contaminated ground water, raising crops and vegetables with contaminated ground water, or getting exposed to or fishing in surface water that has commingled with shallow ground water. Exposure can also occur through contact with soils and/or plants that have become contaminated through contact with contaminated ground water. However, drinking water wells remain the primary route of possible exposure.

At this time, the nearest drinking water wells are located on-site at the southwest areas of the facility, at depths of approximately 1000 feet which are identified as process or production (PW) wells. These wells are designated as PW-2, PW-3, and PW-4 (See Figure 4 for location). These wells are operated by the facility to provide the refinery's process water and drinking water to nearby refinery-owned houses, to the refinery itself, and to the Travel Center. Currently, PW-2 is sampled every three years and PW-3 and PW-4 are sampled on a quarterly ~~4 is sampled semi-annually and PW-3 is sampled on an annual basis.~~ The chemical analyses of these and all of the other water samples collected under this Work Plan are discussed in the Annual Facility-Wide Groundwater Monitoring Reports. Annual sampling results from 2009 through 2019 have indicated concentrations above screening levels of sulfate in samples collected at PW-3, a single detection of iron in a sample collected at PW-4, a single detection of Tetrachloroethene in a sample collected from PW-2, a single detection of phenol in a sample collected at PW-3, and two detections of bis(2-ethylhexyl phthalate) at PW-4. The chemical analyses of these and all of the other water samples

⁺ ~~Note: There is extensive and regular patrolling by security personnel of the facility which operates 24-hours—therefore, we can discount the possibility of an inadvertent or deliberate intruder becoming exposed to contamination in groundwater that has reached the surface in some form.~~

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

collected under this Work Plan are discussed in the Annual Facility-Wide Groundwater Monitoring Reports.

Other than the on-site wells, there is no known drinking water wells located within a 4-mile radius of the site. The nearest drinking water wells that could be used by off-site residents are located to the northwest of the site at a distance slightly greater than 4-miles located within the Navajo community of Iyanbito (shown on the USGS Topographical Map - Gallup Quadrangle (Revised 1980)). These wells are northwest of the South Fork of the Puerco River which, flows towards the southwest from immediately north of the facility. The Cibola National Forest lies in the south-east direction and there are no wells or residents in this protected area.

Artesian conditions at some locations of the site lead to the possibility of ground water emerging onto the surface and thus being able to affect wildlife. No surface water on the site is used for human consumption or primary contact, such as immersion, or secondary contact, such as recreation. The man-made ponds on the site are routinely monitored and are a part of this Plan. Therefore, if they are in contact with shallow ground water that has exhibited elevated levels of contaminants, the Plan will detect any commingling of ground water and surface waters.

Fluctuating ground water elevations can smear contaminants into subsurface soil and rocks, and there is a possibility that plant roots could reach such contaminated soils and bio-concentrate contaminants creating another route of exposure to potential receptors, such as birds and animals that eat the plants. No food crops are currently grown on the site.

2.3 Waste Contaminant Types, Characteristics, and Possible Sources ~~and characteristics of the waste and contaminants and any known and possible sources~~

The types of waste likely include —volatile and semi-volatile organic compounds, primarily hydrocarbons, but could include various other industrial chemicals such as solvents, acids, spent caustic solutions, and heavy metals present in spent chemicals and waste water. These wastes could be in the form of waste water, spent chemicals destined for off-site shipping and disposal packed in drums, sludge, and dry solids.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

Most of the wastes and contaminants that could possibly reach ground water have the characteristic that they would biodegrade and naturally attenuate. However, any heavy metals present in dirt and sludge could possibly leach into ground water and would not biodegrade. There is a possibility also that certain long-lived chemicals would not biodegrade, or, if they did, it would be at a very slow rate. Possible sources include leaks from buried pipes, tanks, surface spills, and historical dumping of wastes in remote areas of the site.

All above-ground large tanks have leak detection or equivalent systems, such as radar gauges. Pumps that could leak hydrocarbons are within containment areas, and all tanks are located inside earthen bermed areas to contain spills. The NAPIS has double walls and a leak detection system installed.

Similarly, surface impoundments can serve as a source of possible ground water contamination. In the past, waste water from the railroad loading rack flowed to a settling and separation lagoon north of the rack and flow exited at the north end where water leaving the lagoon was distributed across a flat open site known as the fan-out area. The free flow of liquids led to subsurface soil contamination. This area is identified as SWMU No. 8 and has been cleaned up for a corrective action complete with controls status. Disposal of waste water into open fields is not practiced at the Gallup Refinery.

There are fourteen Solid Waste Management Units (SWMU) identified at the Gallup Refinery, and one closed land treatment area. On December 31, 2013, the RCRA Post-Closure Care Permit ("Permit") became effective under §20.4.1.901A(10) NMAC and identified an additional 20 Areas of Concern (AOCs) requiring corrective action as listed below.

RCRA (Resource Conservation and Recovery Act) Regulated Units

- Land Treatment Unit (LTU)

SWMUs (Solid Waste Management Units)

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

-
- SWMU 1 – Aeration Basin
 - SWMU 2 – Evaporation Ponds
 - SWMU 3 – Empty Container Storage Area
 - SWMU 4 – Old Burn Pit
 - SWMU 5 – Landfill Areas
 - SWMU 6 – Tank Farm
 - SWMU 7 – Fire Training Area
 - SWMU 8 – Railroad Rack Lagoon
 - SWMU 9 – Drainage Ditch and the Inactive Land farm
 - SWMU 10 – Sludge Pits
 - SWMU 11 – Secondary Oil Skimmer
 - SWMU 12 – Contact Wastewater Collection System
 - SWMU 13 – Drainage Ditch between North and South Evaporation Ponds
 - SWMU 14 – API Separator

AOCs (Areas of Concern)

- AOC 15 – New API Separator
- AOC 16 – New API Separator Overflow Tanks
- AOC 17 – Railroad Loading/Unloading Facility
- AOC 18 – Asphalt Tank Farm (tanks 701-709, 713, 714)
- AOC 19 – East Fuel Oil Loading Rack
- AOC 20 – Crude Slop and Ethanol Unloading Facility
- AOC 21 – Main Loading Racks
- AOC 22 – Loading Rack Additive Tank Farm
- AOC 23 – Retail Fuel Tank Farm (tanks 1-7, 912, 913, 1001, 1002)
- AOC 24 – Crude Oil Tank Farm (tanks 101 and 102)
- AOC 25 – Tank 573 (Kerosene Tank)
- AOC 26 – Process Units
- AOC 27 – Boiler and Cooling Unit Area
- AOC 28 – Warehouse and Maintenance Shop Area
- AOC 29 – Equipment Yard and Drum Storage Area
- AOC 30 – Laboratory
- AOC 31 – Tanks 27 and 28
- AOC 32 – Flare and Ancillary Tanks (tanks Z85V2, Z85V3, Z84-T105)
- AOC 33 – Storm Water Collection System
- AOC 34 – Scrap Yard

Existing ground water monitoring wells effectively surround all of the above listed SWMUs and AOCs. The Permit was subsequently modified in September 2017, with SWMU 8 and AOCs 19 and 25 granted Corrective Action Complete status. AOC 32 was combined with SWMU 14 and AOC 33

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



was combined with SWMU 12. AOCs 20, 21, 22, and 23 are combined to make new AOC 35. The schedule in Appendix E, Table E-1 was amended to reflect prior submittals, revised due dates and deferral of other units. A new Consent Order was executed in January 2017 and this resulted in 11 AOCs (AOC 16, 17, 18, 24, 26, 27, 28, 29, 30, 31, and 34) being removed from the Permit and transferred to the Consent Order for further evaluation.

2.4 Summary of contaminant releases that could contribute to possible ground water contamination.

Spills and leaks are known to have occurred on the site in various locations. Although most hydrocarbons are immediately picked up for recovery and contaminated soil is removed, some of the liquids present in a spill may enter the subsurface. With precipitation, there is the possibility that some of the contaminants could leach and reach ground water.

2.4.1 Separate Phase Hydrocarbons

Separate phase hydrocarbons (SPH) have been found in multiple locations within the refinery. These locations include the Main Tank Farm, Hydrocarbon Seep Area, Aeration Basin, French Drain, Truck Loading Rack, and NAPIS Unit areas.

2.4.1.1 Main Tank Farm

Separate phase hydrocarbons (SPH) floating on shallow ground water was found in the mid-1990s at the northeast end of the facility in the main tank farm. A series of recovery wells were installed and SPH has been recovered since the initial discovery. Recovery through hand-bailing was conducted on a quarterly basis and in 2019 recovery pumps were installed. In March 2019, MPC proposed an interim recovery system using pumps in RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55. The interim system was proposed to recover SPH and dissolved-phase impacts within and down-gradient of the main tank farm. The *Interim Groundwater Recovery System Work Plan* was approved with modifications on August 6, 2019. ~~It is noted that observed SPH measurements may not accurately reflect site conditions.~~ Observed SPH measurements potentially overestimates SPH thicknesses in the soil. SPH will enter the well and depress the water table as the SPH tries to equilibrate with the SPH head in the soil column outside the monitoring

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

well. Therefore, if the SPH is not floating on the water table and is, instead, perched in a more permeable layer above the water table, the SPH in the monitoring well will appear to be thicker than the SPH in the surrounding soils. In other words, the SPH will flow into the well, and as long as there is sufficient SPH and pressure head, the SPH will rise within the well to the level of the perched SPH. It may also depress the water table within the monitoring well. The actual thickness of the SPH in the soil column may only be a few inches, but due to the mobility of the SPH, the thickness in the monitoring well may be several feet. Recovery wells in the main tank farm and the down-gradient area are listed as follows:

RECOVERY WELLS

RW-1	RW-2	RW-5	RW-6
OW-14	OW-58	OW-30	OW-55

2.4.1.2 Hydrocarbon Seep

In June of 2013 during a routine inspection, a hydrocarbon seep was discovered in an isolated area approximately 100 yards west of Tank 101/102. A series of excavations were completed in the area of the seep including installation of six temporary sumps for bi-weekly hydrocarbon recovery. Through 2019 a total of 1,727,574 gallons of liquid (hydrocarbon and ground water) have been recovered from these sumps. To date a total of 49 permanent monitoring wells have been installed with an addition of one pre-existing well, which has been labeled as MKTF-45, and is located in the vicinity of the site investigation. SPH has been measured in Marketing Tank Farm (MKTF) wells located west and northwest of the truck loading rack and marketing tank farm, extending northwest to the location of the hydrocarbon seep. The Gallup Refinery continues to further characterize potential source areas, recovery of liquids from the temporary sumps, and continued sampling of the monitoring wells for characterization and delineation purposes. All 50 wells are included in the Ground Water Monitoring Schedule (see Appendix B), which includes the addition of five new wells (MKTF-46 through MKTF-50) in 2019. The well logs are provided in Appendix D.

Additional soil staining was observed north, northwest of the sumps and these sites were excavated of approximately 38.26 tons of soil, which was sent to the Painted Desert Landfill for disposal.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

Temporary retention ditches were installed to recover liquids from this area. From April 1, 2016 through December 31, 2019, approximately 645,981 gallons of liquid (hydrocarbon and ground water) have been recovered from this area via vacuum truck.

RECOVERY WELLS

MKTF-01 THRU MKTF-50

2.4.1.3 Aeration Basin

A measurable level of SPH was identified in GWM-1 during the third quarter sampling event in 2015 through October 2019.

2.4.1.4 French Drain Release

On February 6, 2018 a mixture of hydrocarbon and water was discovered flowing out of a 4-inch diameter PVC pipe that discharges into a stormwater drainage ditch south of STP-1. Sample analysis indicated the hydrocarbon was naphtha. The flow from the pipe was estimated to be 1.7 gallons per minute. The drainage ditch ~~feeds-fed~~ into a small collection pond that ~~is-was~~ equipped with a drain valve. The valve was closed and no ~~additional~~ hydrocarbon was discharged from the pond. A catch basin was installed at the discharge point of the PVC pipe ~~and now feeds to a frac tank~~. ~~Site-Facility~~ personnel utilized a vacuum truck to transfer the discharge ~~from the frac tank~~ back into the Gallup Refinery. The location of the French drain and frac tank are shown on Figure 4.1.

A subsurface investigation was conducted during March 2018. Five monitor wells (OW-61 thru OW-65) were installed in effort to delineate the hydrocarbon plume that was discharging from the PVC pipe. During the 2019 quarterly gauging, SPH was detected in three of the monitor wells (OW-61, OW-62 and OW-65) during each event and only during the first event in OW-64. All of these wells are screened within the Chinle/Alluvium Interface and measured water levels are consistent with other nearby wells also screened within the Chinle/Alluvium Interface.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



2.4.1.5 Truck Loading Rack Underground Pipeline Gasoline Release

A release of gasoline was observed at the land surface on October 27, 2019 on the west side of the Truck Loading Rack. The source of the release was determined to be an underground transfer line on the north side of the Truck Loading Rack. Associated with this release, SPH was detected in MKTF-17, MKTF-19, and MKTF-36.

2.4.1.6 NAPIS Unit Area

SPH has been detected in NAPIS-1 since 2017. The source of the SPH is suspected to be an unspecified release from the refinery.

2.4.2 Methyl Tert Butyl Ether

Methyl Tert Butyl Ether (MTBE) has not been used at the refinery since April 2006. Several monitoring wells were installed at various depths to monitor SPH and MTBE contaminant plumes from historical contamination. Historical analytical data for the observation wells (OW-14, 29 and 30) indicate the contaminant, MTBE has slowly been increasing over the years in these wells. Based on this information, New Mexico Environmental Department – Hazardous Waste Bureau (NMED-HWB) requested two Work Plans to further investigate the known MTBE plume at the Facility and investigate a suspected plume north of the tank farm (SWMU 6). Pursuant to NMED's February 23, 2016 Approval with Modifications of the *Investigation Work Plan OW-29 & OW-30 and North Drainage Ditch Areas*, wells OW-53, OW-54, OW-55, and OW-56 were installed. These observation wells (OW) are located downstream on the northeast section of the plant and are designated as follows.

<u>OBSERVATION WELLS</u>					
OW-13	OW-14	OW-29	OW-30	OW-50	OW-52
OW-53	OW-54	OW-55	OW-56		

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates
 Gallup Refinery
 92 Giant Crossing Road
 Gallup, NM 87301



Additionally, NMED has approved the *Work Plan 2015 Annual Groundwater Report Comments* on January 12, 2020, which includes installing multiple OWs to assess MTBE. A new well is proposed northeast of OW-30 to determine the hydraulic gradient on the east side of the refinery and the lateral extent of MTBE, which has been detected at elevated concentrations in groundwater samples collected from OW-30. An additional well will be installed near OW-13 to address concerns that OW-13 may be a migration pathway for contaminants to move vertically downward to the Sonsela aquifer. OW-13 will be retained at this time to allow for further evaluation. To evaluate the potential migration of MTBE within the Sonsela aquifer, an additional well will be located approximately halfway between OW-12 and OW-13. The proposed locations are shown on Figure 4.2. To delineate the down-gradient extent of the plume detected at OW-1, a new Sonsela well will be installed approximately 500 feet down-gradient to the west of OW-1. The proposed location is shown on Figure 4.3.

2.4.3 NAPIS Unit

A unit at the southwest end of the facility that is used to recover and recycle oil back into the process has also – through leakage and spills – caused some MTBE and hydrocarbon contamination in shallow ground water. This unit is known as the NAPIS and was put into service in October 2004. The NAPIS has one up-gradient well NAPIS-1, located on the east side and three down-gradient shallow monitoring wells, NAPIS-2, NAPIS-3 and KA-3, which are located along the west side. The NAPIS unit is also equipped with three leak detection units on the east and west bays and also at the oil sump section on the east bay and are designated as follows:

NAPIS WELLS				LEAK DETECTION UNITS		
NAPIS-1	NAPIS-2	NAPIS-3	KA-3	EAST LDU	WEST LDU	OIL SUMP LDU

2.4.4 Aeration Basin

The Aeration Basin, which is designated as SWMU No. 1 in the facility's RCRA Post-Closure Care Permit includes three cells, known as AL-1, AL-2 (lagoons) and holding pond 1 which is currently referred to as EP-1, although it is not an evaporation pond and is not part of the area covered by SWMU No. 2 – Evaporation Ponds. All three of these cells are no longer in service since the startup

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

of the Waste Water Treatment Plant in 2012. All refinery waste water flow was diverted to the WWTP bypassing the lagoons and pond 1. The Gallup Refinery has experienced intermittent discharges of oil and oily water into the lagoons and spills to ground surface while it was in operation. Most of these occurrences were the result of unit upsets and/or large storm events affecting the old API Separator.

Two ground water monitoring wells (GWM-1 and GWM-2) were installed immediately down gradient of the aeration lagoons in 2004 and 2005 in order to detect potential leakage from the aeration basin. GWM-3 was installed in 2005 on the northwest corner of pond 1 (EP-1).

Analysis of ground water samples collected at GWM-1 and GWM-2 have indicated several organic constituents at concentrations above the screening levels in ground water, which would indicate a potential for historical releases from the lagoons. In the third quarter of 2015, quarterly inspection of GWM-1 indicated the presence SPH during gauging activities. NMED was notified of this finding and the Gallup Refinery was instructed to collect a hydrocarbon sample for fingerprint analysis (DRO/GRO and MRO). Gallup was also instructed to purge and gauge the well on a weekly basis to check the recharge rate. The initial measurement was made without the use of an oil/interface probe and the thickness of the hydrocarbon layer in the well was not immediately known. Measured SPH thickness ranged from 0.35 to 0.45 feet in September, October and November 2015. On December 10, 2015, the Gallup Refinery sent a response to NMED–HWB concurring that the source of the hydrocarbons observed in GWM-1 is from the adjacent aeration lagoon.

Depth to water ranged from 20.83 feet to 22.07 feet during the quarterly monitoring in 2019. The measured thickness of SPH in 2019 ranged from 0.13 feet to 0.48 feet during the quarterly monitoring events.

GWM-2 and 3 upon installation in 2005 were found to be dry. Water was first detected in GWM-2 in the first quarter of 2008 and in GWM-3 in the third quarter of 2010. 24-hour notification of the finding was given to NMED and OCD respectively. Analyses of ground water samples collected from GWM-2 and GWM-3 have detected the presence of several constituents at concentration

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



levels above applicable water quality standards such as fluoride, chloride, nitrates, and sulfates. MTBE is the only VOC to have been detected in GWM-2 or GWM-3, but at concentrations well below the screening level.

Quarterly inspections in 2011 and 2012 continued to indicate an increase in measurable water levels in GWM-2 and GWM-3, which was consistent with the increased levels in the lagoons and pond 1. In the second half of 2012 through early 2013 the levels in the lagoons and pond 1 began to decrease with cessation of gravitational flow between lagoons to pond 1 due in part to the start-up of the WWTP. Continued quarterly inspections indicated no water present in GWM-2 and GWM-3 in 2013 through 2019.

Both GWM-2 and GWM-3 have been included in the Aeration Basin Corrective Action Work Plan which began investigative soil and water sampling near the aeration basin in the third quarter of 2012 to support selection of a remedy for SWMU NO. 1 and determine the source of water detected in GWM-2 and GWM-3. ~~Figure 4 shows the location of all of the active monitoring wells on the facility.~~

In February of 2012, the Gallup Refinery submitted a "Revised Investigation Work Plan Solid Waste Management Unit (SWMU) No. 1 Aeration Basin" to include sampling of soils and ground water surrounding the Aeration Basin to determine if there has been a release to the environment and to delineate any such release. In addition, information was collected to help determine the source of ground water that had been observed in monitoring wells GWM-2 and GWM-3. The work plan also included SWMU No. 14 Old API Separator soil and ground water sampling. A new well OAPIS-1 (SWMU 14-2) was installed on the northwest corner where the benzene strippers were located on July 17, 2012 by Enviro-Drill Inc. OAPIS-1 (SWMU 14-2) was added to the 2014 Monitoring Schedule.

In February of 2013, the influent to the aeration lagoons was routed to the new Waste Water Treatment Plant (WWTP) and rerouting of the Travel Center sanitary effluent was completed in June of 2013. The aeration lagoons and pond 1 (EP-1), are no longer in service.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

MPC submitted the *Solid Waste Management Unit 1 Investigation Report* on March 31, 2020, detailing a SWMU NO. 1 sampling event that took place the week of January 13, 2020. The sampling was conducted for the purposes of soil and sediment volume determination and chemical characterization for future SWMU No. 1 excavation, disposal, and closure. In the response titled, *Disapproval SWMU-1 Investigation Report*, dated August 31, 2020, NMED requested a revised report and an additional work plan to further delineate horizontal and vertical extents of contamination in the area of SWMU No 1. The revised report and response to comments will be submitted by December 31, 2020. A due date from the additional work plan will be determined upon approval of the revised report.

WELLS AT THE AERATION BASIN

GWM-1

GWM-2

GWM-3

OAPIS-1

2.4.5 North Drainage Ditch

On April 22, 2015, the Gallup Refinery notified NMED-HWB of the discovery of hydrocarbons in a drainage ditch in the northern portion of the refinery property. Surface water samples were collected from the standing water in the drainage ditch and concentrations of benzene, toluene, ethylbenzene, and xylenes (BTEX) were detected as well as methyl tert-butyl ether (MTBE), gasoline range organics (GRO) and diesel range organics (DRO). An investigation work plan was submitted to NMED for review on August 13, 2015 and was subsequently implemented in May 2016 with installation of well OW-56.

2.4.6 OW-14 Source Area

In correspondence dated May 11, 2015, NMED requested submittal of a work plan to investigate the source of contaminants present in groundwater monitoring well OW-14. Subsequently, wells OW-57 and OW-58 were installed in 2016 pursuant to NMED's May 12, 2016 Approval with Modifications of the *Revised OW-14 Source Area Investigation Work Plan*. Well OW-58A was

Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

installed in 2019 adjacent to OW-58 in order to screen a higher interval than was screened in OW-58. A copy of the well log is included in Appendix D.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



3.0 Site Conditions

The Gallup Refinery is located within a rural and sparsely populated section of McKinley County. It is situated in the high desert plain on the western flank of the Continental Divide approximately 17 miles east of Gallup. The surrounding land is comprised primarily of public and private lands used for cattle and sheep grazing.²

3.1 Current site topography and location of natural and manmade structures

Local topography consists of a gradually inclined down-slope from high ground in the southeast to a lowland fluvial plain in the northwest. The highest point on refinery property is located at the southeast corner boundary (elevation approximately 7,040 feet) and the lowest point is located at the northwest corner boundary (elevation approximately 6,860 feet). The refinery processing facility is located on a flat man-made terrace at an elevation of approximately 6,950 feet.

3.2 Drainages

Surface water in this region consists of the man-made evaporation ponds and aeration basins located within the refinery, a livestock watering pond (Jon Myer's Pond) located east of the refinery, two small unnamed spring fed ponds located south of the refinery, and the South Fork of the Puerco River and its tributary arroyos. The various ponds and basins typically contain water consistently throughout the year. The South Fork of the Puerco River and its tributaries are intermittent and generally contain water only during, and immediately after, the occurrence of precipitation.

There are several storm water conveyance ditches located throughout the refinery which are directed to discharge into contained basins where it is collected and recycled for use as process water; collected and allowed to evaporate; diverted around regulated industrial activity or into two designated outfalls located on the east and west section of the property, identified as Outfall 001 and Outfall 002 (Figure 7). Outfall 001 is located directly south of evaporation pond 8 on the western edge of the refinery's property boundary and equipped with four separate small diameter

² See, for example, the web site of McKinley County at <http://www.co.mckinley.nm.us/>

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

overflow pipelines, each with a manual flow valve for independent control. Outfall 002 is located north of the rail road loading rack on the eastern section of the facility. This outfall consists of a concrete barrier with a valve to control discharges from a deep ditch that collects/ponds the runoff from the rail rack loading area.

Directly west of the crude tank area, there is also a concrete barrier with a valve to control discharges from a culvert that carries stormwater flow from the truck loading rack area. This concrete barrier is located downstream of the “hydrocarbon seep area.” The flow from this concrete barrier continues in a north-northwest direction alongside the southern bermed areas of evaporation ponds 3, 4, 5 and 6 and outward towards the Outfall 001 area. At the new waste water treatment plant, there are three storm drains located on the south, southwest and west side of the waste water treatment plant which is connected to an underground storm culvert that exits on the northwest section of STP-1 into a conveyance ditch along the northern edge of pond 2 into a holding pond equipped with manual flow valves, located north of evaporation pond 3. The discharge from this holding pond then flows north-northwest towards the Outfall 001 area.

3.3 Vegetation types

Surface vegetation consists of native xerophytic vegetation including grasses, shrubs, small junipers, and some prickly pear cacti. Average rainfall at the refinery is less than seven inches per year, although it can vary to slightly higher levels elsewhere in the county depending on elevation.

On alluvial fans on valley sides and drainage ways, the existing vegetation is usually alkali sacaton, western wheatgrass, Indian rice grass, blue grama, bottlebrush squirreltail, broom snakeweed, fourwing saltbush, threeawn, winterfat, mat muhly and spike muhly. On fan remnants on valley sides we usually find blue grama, western wheatgrass, Indian ricegrass, big sagebrush, galleta, bottlebrush squirreltail, fourwing saltbrush, needle and thread, one seed juniper, sand dropseed, spineless horsebrush, rabbitbrush, and two-needle pinyon. Cattails have been observed in isolated areas and are generally associated with wetlands.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301

**Marathon
Petroleum Company LP**

3.4 Erosion features

The impacts of historic overgrazing are visible at the north-side of the facility, in the form of arroyos that formed when surface run-off cut through the ground and washed away soils that were not able to hold water with their ground cover lost to overgrazing. Now that the facility is fenced and no livestock grazing occurs on the site, vegetation has recovered in these areas. With the facility helping to bring back vegetation in its undeveloped areas the formation and deepening of erosion features on its land has decreased.

3.5 Subsurface conditions**3.5.1 Soil types and associations**

Most of the soils found at the surface in the locations where wells are located consist of the Gish-Mentmore complex [\(USDA\)](#).³ These soils occur in alluvial fans on valley sides and fan remnants on valley sides. The parent material for these soils is slope and fan alluvium derived from sandstone and shale. These are well drained soils with moderately slow (0.2 in/hr) to slow permeability (0.06 in/hr). In this association, the Gish and similar soils make up about 45 percent, the Mentmore and similar soils 35 percent, and minor components 20 percent. These minor components are - Berryhill and similar soils 10 percent and Anodize and similar soils 10 percent. The typical profile for these soils is – 0 to 2 inches fine sandy loam, 2 to 72 inches of various kinds of clay loam.

Drill logs for various wells have been provided electronically to the NMED-HWB. From these well logs we can infer that the soils in the subsurface are generally composed of clays starting at the immediate subsurface, interbedded with narrow sand and silt layers. At about 100 to 150 feet, layers of mudstone, sandstone (from the Chinle Group, Petrified Forest Formation) and siltstone start to appear. Figure 3 shows a generalized relationship of soils in and around the Gallup Refinery.

³ ~~Soil Survey of McKinley County Area, New Mexico, McKinley County and Parts of Cibola and San Juan Counties, Natural Resources Conservation Service (NRCS), US Department of Agriculture, available at—
<http://soildatamart.nrcs.usda.gov/Manuscripts/NM692/0/McKinley.Area%20NM.pdf>~~

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



3.5.2 Stratigraphy

The 810-acre refinery property site is located on a layered geologic formation. Surface soils generally consist of fluvial and alluvial deposits; primarily clay and silt with minor inter-bedded sand layers. Below this surface layer is the Chinle Group, which consists of low permeability clay stones and siltstones. As such, the Chinle Group (Petrified Forest Formation) effectively serves as an aquiclude. Inter-bedded within the Chinle Group is the Sonsela Sandstone bed, which represents the uppermost potential aquifer in the region.

The Sonsela Sandstone bed lies within and parallels the dip of the Chinle Group. As such, its high point is located southeast of the refinery and it slopes downward to the northwest as it passes under the refinery. Due to the confinement of the Petrified Forest Formation aquitard, the Sonsela Sandstone bed acts as a water-bearing reservoir and is artesian at its lower extremis. Artesian conditions exist through much of the central and western portions of the refinery property.

3.5.3 Presence and flow direction of ground water

Ground water flow within the Petrified Forest Formation is extremely slow and typically averages less than 10^{-10} centimeters per second (less than 0.01 feet per year). Ground water flow within the surface soil layer above the Petrified Forest Formation is highly variable due to the presence of complex and irregular stratigraphy; including sand stringers, cobble beds, and dense clay layers. As such, hydraulic conductivity may range from less than 10^{-2} centimeters per second in the gravelly sands immediately overlying the Petrified Forest Formation down to 10^{-8} centimeters per second in the clay soil layers located near the surface.

Shallow ground water located under refinery property generally flows along the upper contact of the Petrified Forest Formation. The prevailing flow direction is from the southeast and toward the northwest.

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.0 Investigation Methods

The purpose of this section is to describe the types of activities that will be conducted and the methods that will be used as part of this Plan. Appendix A, Gallup Refinery Field Sampling Collection and Handling Standard Procedures, provides the basis for the investigation methods section that follows. ~~a thorough discussion on actual sampling methods that will be used.~~

4.1 Ground Water Sampling Methodology

All monitoring wells scheduled for sampling during a ground water sampling event will be sampled within 15 working days of the start of the monitoring and sampling event, weather permitting.

Appendix C-1 is a summary of the fluid level data collected in 2018 for the non-MKTF wells. Appendix C-1.1 is a summary of the fluid level data collected in 2018 for the MKTF wells. Appendices C-2 and C-2.1 include well information for the non-MKTF wells and MKTF wells, respectively. The well information consists of the survey data, screened intervals, and stratigraphic unit in which the wells are screened. Appendix C-3 includes well information for artesian wells also known as Process or Production wells (PW). Information provided for the artesian wells was gathered from well boring logs. These wells are encased and therefore measurement for depth to bottom was not field verified. ~~Table C-2.1 is revised to include new monitor wells installed in 2018.~~

4.1.1 Well Gauging

At the beginning of each quarterly, semi-annual, or annual sampling event, all monitoring and recovery wells listed in Appendix B, Ground Water Monitoring Schedule, will be gauged to record the depth to SPH, if present, the DTW and the DTB of the well. The gauging will be performed using an oil/water interface probe attached to a measuring tape capable of recording measurements to the nearest 0.01 foot. Each monitoring well is field verified with the well number on the well casing or adjacent to the well to ensure that samples are collected at the correct well location. Wells also have a permanent marked reference point on the well casing from which ground water levels and well depths are measured. Figure 5 depicts the potentiometric surface

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

for the Sonsela aquifer and Figure 6 shows the potentiometric surface for the Alluvium/Chinle Group Interface zone.

Gauging measurements will be recorded on a field gauging form. Data obtained from the gauging will be reported in the annual ground water monitoring report. The data will be used to develop groundwater contour maps and SPH thickness isopleths which will also be included in the annual report.

4.1.2 Well Purging

Each monitoring well will be purged by removing ground water prior to sampling in order to ensure that formation water is being sampled. Generally, at least three well volumes (or a minimum of two if the well has low recharge rate) will be purged from each well prior to sampling. Field water quality parameters measured during purging are pH, electrical conductivity, temperature, dissolved oxygen (DO), and oxidation-reduction potential (ORP). One or more parameters must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples utilizing low-flow sampling techniques. When purging wells using a bailer, bailing will be considered complete when 3 well volumes have been removed from the wells. Field parameters will be measured and recorded while bailing, with the understanding that the process of hand-bailing may prevent stabilization of field parameters.~~Field water quality measurements must stabilize for a minimum of three consecutive readings before purging will be discontinued. Field water quality measurements will include pH, electrical conductivity, temperature, dissolved oxygen (DO) mg/l, and oxidation-reduction potential (ORP). Field water quality measurement stability will be determined when field parameter readings stabilize to within ten percent between readings for three consecutive measurements. Once the purging requirements are met, readings are within ten percent, purging will stop and~~ the well is ready for sample collection. The volume of ground water purged, the instruments used, and the readings obtained at each interval will be recorded on the field-monitoring log. Well purging and sampling will be performed using 1.5-inch x 3 foot and/or 3-inch x 3-foot disposable polyethylene bailers for ground water sampling and/or appropriately decontaminated portable sampling pumps.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

If a well is pumped or bailed dry before two or three well volumes can be evacuated, it requires only that sufficient time elapse for an adequate volume of water to accumulate for the sampling event. The first sample will be tested for pH, temperature, specific conductivity, DO, and ORP. The well will be retested for pH, temperature, specific conductivity, DO, and ORP after sampling as a measure of purging efficiency and as a check on the stability of the water samples over time. All well evacuation information will be recorded in a logbook.

Wells MW-1, MW-2, MW-4, MW-5, BW-1C, BW-2A, BW-2B, BW-3B, BW-4B, BW-5B, BW-5C, SMW-4, OW-1, OW-10, OW-13, OW-14, OW-29 and OW-30 are each equipped with a dedicated electrical pump. Wells SMW-2, OW-11, OW-12, OW-50, and OW-52 are purged and sampled using a portable Grundfos pump. The remaining wells are hand-bailed if the presence of water is detected.

If SPH is detected in any of these wells, no samples will be collected.

Purged well water is collected in 55-gallon drums, buckets, or totes and drained to the process sewer upstream of the NAPIS. The water is treated in the refinery's waste water treatment system.

4.2 Ground ~~water~~ Water Sample Collection

Ground water samples will be obtained from each well within 24 hours of the completion of well purging. Sample collection methods will be documented in the field monitoring reports. The samples will be transferred to the appropriate, clean, laboratory-prepared containers provided by the analytical laboratory. ~~Sample handling and chain-of-custody (COC) procedures are described in more detail in Appendix A as well as decontamination procedures for reusable water sampling equipment.~~

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



~~All purged ground water and decontamination water from monitoring wells will be drained into the refinery waste water treatment system upstream of the NAPIS. The procedures for disposing materials are described in Appendix A.~~

Ground water samples are collected and analyzed for both total and dissolved metals. Ground water samples obtained for dissolved metals analysis will be filtered through disposable filters with a 0.45 micrometers mesh size.

4.2.1 Sample Handling

All sample containers are supplied by the contracted analytical laboratory and shipped to the Gallup Refinery in sealed coolers. Chemical preservation is also provided by the laboratory through pre-preserved bottle ware. Collection of containerized ground water samples are in the order of most volatile to least volatile, such as: VOCs, SVOCs, metals, phenols, cyanide, sulfate, chloride, nitrate and nitrite. ~~Immediately after the samples are collected, they will be stored in a cooler with ice or other appropriate storage method until they are delivered to the analytical laboratory. Standard COC procedures as detailed in Appendix A will be followed for all samples collected. All samples will be submitted to the laboratory as soon as possible to allow the laboratory to conduct the analyses within the specified method holding times.~~

At a minimum, the following procedures will be used when collecting samples:

- Neoprene, nitrile, or other protective gloves will be worn when collecting samples. New disposable gloves will be used to collect each sample.
- All samples collected for chemical analysis will be transferred into clean sample containers supplied by the analytical laboratory. The sample container will be clearly marked. Sample container volumes and preservation methods will be in accordance with the most recent standard EPA and industry accepted practices for use by accredited analytical laboratories. Sufficient sample volume will be obtained for the laboratory to complete the method-specific quality control (QC) analyses on a laboratory-batch basis.

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



- Sample labels and documentation will be completed for each sample.

Immediately after the samples are collected, they will be stored in a cooler with ice or other appropriate storage method until they are delivered to the analytical laboratory. Standard chain-of-custody procedures, as described in Section 4.2.6 of this Plan, will be followed for all samples collected. All samples will be submitted to the laboratory to conduct the analyses within the method holding times. Details of the general sample handling procedures are provided in Appendix A.

4.2.2 General Well Sampling Procedures

To minimize cross contamination, rubber gloves or disposable nitrile gloves will be worn and changed between each activity.

A field notebook and sample log will be used to document weather conditions and sample date and time. Sample labels will be complete with location, date, time, analysis, preservative, and the name of the sampler. For low-flow sampling, converter speed will be adjusted prior to filling bottles. Sample labels will be affixed, and bottles will be filled according to lab instructions. Bottles with septa lids will be used for samples intended for VOC analysis. VOC bottles will be filled to minimize headspace. Following collection, samples will be kept on ice to begin cooling prior to shipment.

Any reusable equipment that is not dedicated to a specific well will be decontaminated. Completed samples will be refrigerated until they are shipped to the lab. Appropriate shipping methods will be arranged to accommodate holding times. Sampling equipment and supplies will be checked, and proper inventory verified prior to sampling. Before departing, quality assurance (QA)/QC requirements will be checked to ensure there are additional equipment and supplies to fulfil the additional requirement.

4.2.3 Surface Water Sample Collection

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

At the evaporation ponds, samples will be collected as a grab sample at the pond edge near the inlets. This location will be noted in the field notebooks. The sampler will avoid disturbing sediment and gently allow the sample container to fill making sure that undue disturbance does not allow volatile contaminants to be lost. The sample bottle will be used for the sample collection in a shallow location near the bank. If a separate bottle and/or bailer are used to refill the sample container, this will be noted in the field log books. The decision to use a separate bottle/bailer will be made, if at all, by the sampler and the reasons will be noted in the field log book.

4.2.4 Decontamination Procedures

The objective of the decontamination procedures is to minimize the potential for cross-contamination. Most of field equipment used for ground water sampling will be disposable and, therefore, not require decontamination. To prevent cross-contamination, field equipment that comes into contact with water or soil will be decontaminated between each sampling location. The decontamination procedure will consist of washing the equipment with a non-phosphate detergent solution (e.g., Fantastik™, Liqui-Nox®), followed by two rinses of distilled water, and air dried.

Decontamination water and rinsate will be contained and disposed of the same way as purge water, as described in Section 4.1.2. Decontamination procedures and the cleaning agents used will be documented in the daily field log.

The following shipping procedures will be performed during each sampling event:

- Individual sample containers will be packed to prevent breakage and transported in a sealed cooler with ice or other suitable coolant or other EPA or industry wide accepted method. The drainage hole at the bottom of the cooler will be sealed and secured in case of sample container leakage.
- Each cooler or other container will be delivered directly to the analytical laboratory.
- Glass bottles will be separated in the shipping container by cushioning material to prevent breakage.

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

- ~~• Plastic containers will be protected from possible puncture during shipping using cushioning material.~~
- ~~• The COC form and sample request form will be shipped inside the sealed storage container to be delivered to the laboratory.~~
- ~~• Signed and dated COC seals will be applied to each cooler prior to transport of samples from the site.~~

4.2.5 Documentation of Field Activities

Daily field activities, including observations and field procedures, will be recorded using indelible ink on field sampling forms. The original field forms will be maintained at the Gallup Refinery. Completed forms will be maintained in a bound and sequentially numbered field file for reference during field activities. The daily record of field activities will include the following information:

- Well identification (ID)/evaporation pond location/outfall
- Date
- Start and finish sampling time
- Field team members, including visitors
- Weather conditions
- Daily activities and times conducted
- Observations
- Record of samples collected with sample designations
- Photo log (if needed)
- Field monitoring data, including health and safety monitoring (if needed)
- Equipment used and calibration records, if appropriate
- List of additional data sheets and maps completed
- An inventory of the waste generated and the method of storage or disposal
- Signature of personnel completing the field record

4.2.6 Sample Custody

All samples collected for analysis will be recorded in the field report or data sheets. Chain-of-custody forms will be completed at the end of each sampling day, prior to the transfer of samples off site and will accompany the samples during shipment to the laboratory. A signed and dated custody seal will be affixed to the lid of the shipping container. Upon receipt of the samples at the laboratory, the custody seals will be broken, the chain-of-custody form will be signed as received by the laboratory, and the conditions of the samples will be recorded on the form. The original chain-of-custody form will remain with the laboratory; copies will be sent to the Gallup Refinery.

Facility Wide Ground Water Monitoring Work Plan – 2020
Updates
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



The refinery will maintain copies of all chain-of-custody forms generated as part of sampling activities. Copies of the chain-of-custody records will be included with all draft and final laboratory reports submitted to NMED and OCD.

4.2.7 Shipping Procedures

The following shipping procedures will be performed during each sampling event:

- Individual sample containers will be packed to prevent breakage and transported in a sealed cooler with ice or other suitable coolant or other EPA or industry-wide accepted method. The drainage hole at the bottom of the cooler will be sealed and secured in case of sample container leakage.
- Each cooler or other container will be delivered directly to the analytical laboratory.
- Glass bottles will be separated in the shipping container by cushioning material to prevent breakage.
- Plastic containers will be protected from possible puncture during shipping using cushioning material.
- The chain-of-custody (COC) form and sample request form will be shipped inside the sealed storage container to be delivered to the laboratory.
- Signed and dated chain-of-custody seals will be applied to each cooler prior to transport of samples from the site.

4.3 Analytical Methods

Ground water and surface water samples collected during the monitoring events will be analyzed using the specified analytical methods and for the constituents listed in Appendix B.

4.4 Quality Assurance Procedures

Contract analytical laboratories will maintain internal quality assurance programs in accordance with EPA and industry accepted practices and procedures. At a minimum, the laboratories will use a combination of standards, blanks, surrogates, duplicates, matrix spike/matrix spike duplicates (MS/MSD), blank spike/blank spike duplicates (BS/BSD), and laboratory control samples to demonstrate analytical Quality Assurance/Quality Control (QA/QC). The laboratories will establish control limits for individual chemicals or groups of chemicals based on the long-term performance of the test methods. In addition, the laboratories will establish internal QA/QC that meets EPA's

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



laboratory certification requirements. The specific procedures to be completed are identified in the following sections.

4.4.1 Equipment Calibration Procedures and Frequency

The laboratory's equipment calibration procedures, calibration frequency, and calibration standards will be in accordance with the EPA test methodology requirements and documented in the laboratory's quality assurance (QA) and Standard Operating Procedures (SOP) manuals. All instruments and equipment used by the laboratory will be operated, calibrated, and maintained according to the manufacturers' guidelines and recommendations. Operation, calibration, and maintenance will be performed by personnel who have been properly trained in these procedures. A routine schedule and record of instrument calibration and maintenance will be kept on file at the laboratory.

4.4.2 Field QA/QC Samples

Field duplicates, field blanks, equipment rinsate blanks, reagent blanks and trip blanks may be obtained for quality assurance during sampling activities. The samples will be handled as described in Section 4.4.3.

Field duplicates will consist of two samples either split from the same sample device or collected sequentially. Field duplicate ground water samples will be collected at a frequency of one per ten regular samples and will be analyzed for the full set of analyses used for the regular sample collected. At a minimum, one duplicate sample per sampling day must always be obtained.

Field blanks shall be obtained at a frequency of no less than one per day per site or unit. Field blanks shall be generated by filling sample containers in the field with deionized water and submitting the samples, along with the groundwater or surface water samples, to the analytical laboratory for the appropriate analyses.

Equipment blanks shall be obtained for chemical analysis at the rate of five percent but no fewer than one rinsate blank per sampling day. Equipment rinsate blanks shall be collected at a rate of

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

one per sampling day if disposable sampling apparatus is used. Rinsate samples shall be generated by rinsing deionized water through unused or decontaminated sampling equipment. The rinsate sample then shall be placed in the appropriate sample container and submitted with the groundwater or surface water samples to the analytical laboratory for the appropriate analyses.

Reagent blanks shall be obtained at a frequency of ten percent but no fewer than one per day per unit if chemical analyses requiring the use of chemical reagents are conducted in the field during water sampling activities.

Trip blanks will accompany laboratory sample bottles and shipping and storage containers intended for VOC analyses. Trip blanks will consist of a sample of analyte free deionized water placed in an appropriate sample container. Trip blanks will be analyzed at a frequency of one for each shipping container of samples.

4.4.3 Laboratory QA/QC Samples

Analytical procedures will be evaluated by analyzing reagent or method blanks, surrogates, MS/MSDs, BS/BSDs and/or laboratory duplicates, as appropriate for each method. The laboratory QA/QC samples and frequency of analysis to be completed will be documented in the cited EPA or other test methodologies. At a minimum, the laboratory will analyze laboratory blanks, MS/MSDs, BS/BSDs and laboratory duplicates at a frequency of one in twenty for all batch runs requiring EPA test methods and a frequency of one in ten for non-EPA test methods. Laboratory batch QA/QC samples will be project specific.

4.4.4 Laboratory Deliverables

The analytical data package will be prepared in accordance with EPA-established Level II analytical support protocol which will include:

- Transmittal letter, including information about the receipt of samples, the testing methodology performed, any deviations from the required procedures, any problems encountered in the analysis of the samples, any data quality exceptions, and any corrective actions taken by the laboratory relative to the quality of the data contained in the report;

Facility Wide Ground Water Monitoring Work Plan – 2020 Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

-
- Sample analytical results, including sampling date; date of sample extraction or preparation; date of sample analysis; dilution factors and test method identification; water sample results in consistent units (milligrams per liter or micrograms per liter); and detection limits for undetected analytes. Results will be reported for all field samples, including field duplicates and blanks, submitted for analysis;
 - Method blank results, including reporting limits for undetected analytes;
 - Surrogate recovery results and corresponding control limits for samples and method blanks (organic analyses only);
 - Laboratory duplicate results for inorganic analyses, including relative percent differences and corresponding control limits;
 - Sample COC documentation;
 - Holding times and conditions;
 - Conformance with required analytical protocol(s);
 - Instrument calibration;
 - Blanks;
 - Detection/quantitative limits;
 - Recoveries of surrogates and/or matrix spikes (MS/MSDs);
 - Variability for duplicate analyses;
 - Completeness; and,
 - Data report formats.

Data deliverables provided by the laboratory that include analysis of organic compounds will also include the following:

- A cover letter referencing the procedure used and discussing any analytical problems, deviations, and modifications, including signature from authority representative certifying to the quality and authenticity of data as reported;
- A report of sample collection, extraction, and analysis dates, including sample holding conditions;
- Tabulated results for samples in units as specified, including data qualification in conformance with EPA protocol, and definition of data descriptor codes;
- Final extract volumes (and dilutions required), sample size, wet-to-dry weight ratios, and instrument practical detection/quantitative limit for each analyte;
- Analyte concentrations with reporting units identified, including data qualification and a description of the qualifiers;
- Quantification of analytes in all blank analyses, as well as identification of method blank associated with each sample; and,
- Recovery assessments and a replicate sample summary, including all surrogate spike recovery data with spike levels/concentrations for each sample and all MS/MSD results (recoveries and spike amounts).

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.4.5 Review of Field and Laboratory QA/QC Data

The sample data, field, and laboratory QA/QC results will be evaluated for acceptability with respect to the data quality objectives (DQOs). Each group of samples will be compared with the DQOs and evaluated using data validation guidelines contained in EPA guidance documents: Guidance Document for the Assessment of RCRA Environmental Data Quality, National Functional Guidelines for Organic Data Review, and Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses, and the most recent version of SW-846, and industry-accepted QA/QC methods and procedures.

The laboratory will notify the Gallup Refinery Project Manager of data quality exceptions within one business day of identifying the data quality exception in order to allow for sample re-analysis, if possible. The Gallup Refinery Project Manager will contact NMED within one business day of receipt of laboratory notification of data quality exceptions in order to discuss the implementations and determine whether the data will still be considered acceptable, or if sample re-analysis or re-sampling is necessary.

4.4.6 Blanks, Field Duplicates, Reporting Limits and Holding Times

4.4.6.1 Blanks

The analytical results of field blanks and field rinsate blanks will be reviewed to evaluate the adequacy of the equipment decontamination procedures and the possibility of cross-contamination caused by decontamination of sampling equipment. The analytical results of trip blanks will be reviewed to evaluate the possibility for contamination resulting from the laboratory-prepared sample containers or the sample transport containers. The analytical results of laboratory blanks will be reviewed to evaluate the possibility of contamination caused by the analytical procedures. If contaminants are detected in field or laboratory blanks, the sample data will be qualified or rejected, as appropriate. Methods and reasoning for the decision to qualify or reject sample data will be discussed in the Annual Groundwater Report. Furthermore, any impact to data quality and/or need to adjust methods will be addressed in the report.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



4.4.6.2 Field Duplicates

Field duplicates will consist of two samples either split from the same sample device or collected sequentially. The analytical data quality objectives for precision shall be used for water duplicates.

4.4.6.3 Method Reporting Limits

Method reporting limits for sample analyses will be established at the lowest level practicable for the method and analyte concentrations and will not exceed ground water or surface water cleanup standards and screening levels. Detection limits that exceed established standards or screening levels and are reported as “not detected” will be considered data quality exceptions and an explanation for its acceptability for use will be provided.

4.4.6.4 Holding Times

Per EPA protocol the sampling, extraction, and analysis dates will be reviewed to confirm that extraction and analyses were completed within the recommended holding times. Appropriate data qualifiers will be noted if holding times are exceeded.

4.4.7 Representativeness and Comparability

4.4.7.1 Representativeness

Representativeness is a qualitative parameter related to the degree to which the sample data represent the relevant specific characteristics of the media sampled. Procedures will be implemented to assure representative samples are collected and analyzed, such as repeated measurements of the same parameter at the same location over several distinct sampling events. Any procedures or variations that may affect the collection or analysis of representative samples will be noted and the data will be qualified.

4.4.7.2 Comparability

Comparability is a qualitative parameter related to whether similar sample data can be compared. To assure comparability, analytical results will be reported in appropriate units for comparison with other data (past studies, comparable sites, screening levels, and cleanup standards), and standard

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

collection and analytical procedures will be implemented. Any procedure or variation that may affect comparability will be noted and the data will be qualified.

4.4.8 Laboratory Reporting, Documentation, Data Reduction, and Corrective Action

Upon receipt of each laboratory data package, data will be evaluated against the criteria outlined in the previous sections. Any deviation from the established criteria will be noted and the data will be qualified. A full review and discussion of analytical data QA/QC and all data qualifiers will be submitted as appendices or attachments to the ground water monitoring reports. Data validation procedures for all samples will include checking the following, when appropriate:

- Holding times;
- Detection limits;
- Field equipment rinsate blanks;
- Field blanks;
- Field Duplicates;
- Trip blanks;
- Reagent blanks;
- Laboratory duplicates;
- Laboratory blanks;
- Laboratory matrix spikes;
- Laboratory matrix spike duplicates;
- Laboratory blank spikes;
- Laboratory blank spike duplicates; and
- Surrogate recoveries.

If significant quality assurance problems are encountered, appropriate corrective action will be implemented. All corrective action will be reported and the corrected data will be qualified.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



5.0 Monitoring and Sampling Program

The primary objective of ground water monitoring is to provide data which will be used to assess ground water quality at and near the facility. Ground water elevation data will also be collected to evaluate ground water flow conditions. The ground water monitoring program for the facility will consist of sample collection and analysis from a series of monitoring wells, recovery wells, outfalls, and evaporation pond locations.

The monitoring network is divided into six investigation areas (Groups A, B, C, D, E, and F). The sampling frequency, analyses and target analytes will vary for each investigation area and the combined data from these investigation areas will be used to assess ground water quality beneath and immediately down-gradient of the facility and evaluate local ground water flow conditions.

Samples will not be collected from monitoring wells that have measurable SPH. For wells that are purged dry, samples will be collected if recharge volume is sufficient for sample collection within 24 hours. Wells not sampled due to insufficient recharge will be documented in the field log.

If samples cannot be collected from a location due refinery activity or environmental concerns, such as elevated H₂S, arrangements will be made to collect samples from the affected location(s) during the next sampling or gauging event.

The following sections outline the monitoring program for each investigation area.

5.1 Group A Through Group F Sampling Locations

5.1.1 Sampling Locations

The location of the monitoring, recovery wells and leak detection units are shown in Figure 4. The following wells will be sampled (as described in Appendix B):

Facility Wide Ground Water Monitoring Work Plan – 2020**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

<u>GROUP A</u>	<u>GROUP B</u>	<u>GROUP C</u>	<u>GROUP D</u>	<u>GROUP E</u>
BW-1A, 1B, 1C	GWM-1, 2, 3	OW-13, 14, 29, 30	PW-2, 3, 4	MKTF-01 thru 50
BW-2A, 2B, 2C	NAPIS 1, 2, 3, KA-3	OW-50, 52, 53, 54	OW-1, 10	
	OW-62	OW-55, 56, 57, 58		
		OW-58A, 61, 63,		
		OW-64, 65		
BW-3A, 3B, 3C	OAPIS-1	RW-1, 2, 5, 6	OW-11, 12	
BW-4A, 4B	OW-59, 60			
BW-5A, 5B, 5C				
MW-1, 2, 4, 5	LDU (3)			
SMW-2, 4	STP1-NW, SW			

5.2 Evaporation Ponds, Outfalls**5.2.1 Sampling Locations**

The Group F outfalls and ponds will be sampled (as described in Appendix B, Table 1). (Note: these outfalls are from one section of the waste water treatment system to another – they do not discharge to any location outside the facility).

GROUP F OUTFALLS

STP-1 to EP-2

Boiler Water Inlet to EP-9

GROUP F EVAPORATION PONDS

Pond 1 – No longer in service

EP-5

EP-9

EP-2

EP-6

EP-11

EP-3

EP-7

EP-12A

EP-4

EP-8

EP-12B

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



6.0 Monitoring Program Revisions

Upon review of the analytical results from the monitoring events under this Plan, historic facility-wide monitoring data, available soil boring data, and other related information the Gallup Refinery will assess the monitoring program presented in this Plan. Revisions to the Plan, as necessary, will then be presented for agency review and approval on an annual basis. These revisions may include, but not be limited to, a reduction or change in monitoring locations, monitoring frequency, and/or target analytes listed in Appendix B, Table 1.

6.1 Requests for Modifications to Sampling Plan

New monitoring wells MKTF-46 through MKTF-50 have been added to the Sampling Plan. The proposed analytical suite for these five new wells includes the following:

- Volatile Organic Compounds;
- Semi-Volatile Organic Compounds;
- WQCC Metals – Total and Dissolved;
- GRO/DRO Extended;
- Major Cations/Anions; and
- 1,4-Dioxane by method 8270/8270 SIMMS for two consecutive events.

In addition, groundwater samples collected from MKTF-46 will be analyzed by method 8011 for 1,2-dibromoethane due to the detection of chlorinated solvents in samples collected from this well.

New monitoring well OW-58A has been added to the Sampling Plan. The proposed analytical suite includes the following:

- Volatile Organic Compounds (method 8260 & method 8011 for 1,2-dibromoethane);
- WQCC Metals – Total and Dissolved;
- GRO/DRO Extended; and
- Nitrite and nitrate.

**Facility Wide Ground Water Monitoring Work Plan – 2020
Updates**
Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



7.0 References

New Mexico Environment Department (NMED). 2012. Re: Investigation Work Plan, Solid Waste Management Unit (SWMU) No. 1 – Aeration Basin. February 24.

NMED. 2016. Approval with Modifications, Investigation Work Plan, OW-29 & OW-30 and North Drainage Ditch Areas. February 23.

NMED. 2016. Approval with Modifications, Revised OW-14 Source Area Investigation Work Plan, OW Series Wells and Contaminant Plume Migration. May 12.

NMED. 2019. Approval with Modifications, Response to Disapproval (Response to Approval with Modifications May 1, 2019), Interim Groundwater Recovery System Work Plan. August 6.

NMED. 2020. Approval, 2015 Annual Ground Water Work Plan. January 12.

NMED. 2020. Solid Waste Management Unit 1 Investigation Report. March 31.

United States Department of Agriculture (USDA). No date. Soil Survey of McKinley County Area, New Mexico, McKinley County and Parts of Cibola and San Juan Counties. Available from: https://www.nrcs.usda.gov/Internet/FSE_MANUSCRIPTS/new_mexico/NM692/0/McKinley.Area%20NM.pdf

Facility Wide Ground Water Monitoring Work Plan – 2020

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX A

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Appendix A

Gallup Refinery Field Sampling Collection and Handling Standard Procedures

Field Data Collection: Elevation and Purging

All facility monitoring wells and recovery wells are gauged as required throughout the year. Gallup does not have any recovery well pumps that need to be shut off and removed prior to water elevation measurements. There are groundwater recovery pumps installed in wells RW-1, RW-2, RW-5, RW-6, OW-14, OW-58, OW-30, and OW-55, but they are inactive at this time. If MPC resumes recovery operations with these pumps, they must halt the pumping operation at least 48 hours prior to conducting depth measurements in these wells.

Each monitoring well is field verified with the well number on the well casing or adjacent to the well to ensure that samples are collected from the correct well location. Wells also have a permanent marked reference point on the well casing from which ground water levels and well depths are measured. The portable pump intake is lowered to the midpoint of the listed screened interval for each specific well using the markings identified on the pump hose which are set at one foot interval~~every ten feet~~. In wells with dedicated pumps, the pumps have been installed at the midpoint of the screened interval.

All water/product levels are measured to an accuracy of the nearest 0.01 foot using an oil/water interface meter. Water levels and well depths in the deeper wells are gauged with an electric water depth meter. After determining water levels, well volumes are calculated using the appropriate conversion factors for a given well based on its internal diameter. Volume is equal to the height of the liquid column times the internal cross-sectional area of the well.

Generally, at least three well volumes (or a minimum of two if the well has low recharge) are purged from each well prior to sampling. Field water quality parameters measured during purging are ~~(pH, electrical conductivity, temperature, and dissolved oxygen (DO), and oxidation-reduction potential (ORP).~~ One or more parameters must stabilize to within 10% for a minimum of three

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



consecutive measurements before collection of ground water samples utilizing low-flow sampling techniques. When purging wells using a bailer, bailing will be considered complete when 3 well volumes have been removed from the wells. Field parameters will be measured and recorded while bailing, with the understanding that the process of hand-bailing may prevent stabilization of field parameters.}, must stabilize to within 10% for a minimum of three consecutive measurements before collection of ground water samples from each well.

Before sample collection can begin, the water collected from each monitoring well must be fresh aquifer water. Well evacuation replaces stagnant well water with fresh aquifer water. The water level in the well, total depth of well and thickness of floating product (if any) will be measured using an oil/water interface meter. If any product is present, regardless of thickness, a ground water sample is not obtained.

If a well is pumped or bailed dry before two or three well volumes can be evacuated, it requires only that sufficient time elapse for an adequate volume of water to accumulate for the sampling event. The first sample will be tested for pH, temperature, specific conductivity and dissolved oxygen (mg/L). The well will be retested for pH, temperature, specific conductivity and dissolved oxygen (mg/L) after sampling as a measure of purging efficiency and as a check on the stability of the water samples over time. All well evacuation information will be recorded in a log book.

Wells MW-1, MW-2, MW-4, MW-5, BW-1C, BW-2A, BW-2B, BW-3B, BW-4B, BW-5B, BW-5C, SMW-4, OW-1, OW-10, OW-13, OW-14, OW-29 and OW-30 are each equipped with a dedicated electrical pump. Wells SMW-2, OW-11, OW-12, OW-50, and OW-52 are purged and sampled using a portable Grundfos pump. The remaining wells are hand-bailed if the presence of water is detected. If SPH is detected in any of these wells, no samples are collected.

Purged well water from wells is collected in 55-gallon drums, buckets, or totes and drained to the process sewer upstream of the NAPIS. The water is treated in the refinery's waste water treatment system.

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

Sampling Equipment at Gallup Refinery

The following sampling equipment is maintained at the Gallup Refinery and used by the sampling personnel:

- Heron Instruments 100 ft. DipperT electric water depth tape complying with US GGG-T-106E, EEC Class II.
- Pall Corporation Acro 50A 0.45 micron disposable filter used with 60 ml disposable syringes for filtering water in the field.
- YSI pH/Conductivity meter Model 63, calibrated with a one-point, two-point, or three-point calibration procedure using pH standards of 7, 4 and 10. (Measures pH, temperature, conductivity, TDS, salinity, DO, and ORP)
- IQ Scientific Instruments (measures pH, temperature, conductivity, TDS, salinity, DO, and ORP), ~~pH/Temperature/Conductivity/ Dissolved Oxygen meter~~, Model IQ1806LP.
- Grundfos 2-inch pumps with Grundfos 115-volt AC-to-DC converter.
- WaterMark Oil Water Interface Meter (100 ft), Model 101L/SMOIL, S/N 01-5509.

Calibration and maintenance procedures will be performed according to the manufacturer's specifications. In the event an instrument becomes inoperable, an instrument similar to the inoperable instrument will be used.

Order of Collection

Samples will be collected in the order listed below:

<u>Parameter</u>	<u>Pesticides</u>
VOC	E-Coli
TPH	<u>Bottle Type</u>
TPH	40-ml VOA vials (HCl)
EDB and EDC	40-ml VOA vials (HCl)
SVOC	250-ml glass amber bottle
Total Metals	40-ml VOA vials (Na ₂ S ₂ O ₃)
Dissolved Metals	1-liter glass amber bottle
Major Cations/Anions	250-ml plastic bottle (HNO ₃)
Major Cations/Anions	125-ml plastic bottle (HNO ₃)
Major Cations/Anions	125-ml plastic bottle (HNO ₃)
BOD	125-ml plastic bottle (H ₂ SO ₄)
TDS	125-ml plastic bottle
COD	1-liter plastic bottle
Cyanide	500-ml plastic bottle

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



**Marathon
Petroleum Company LP**

500 ml plastic bottle (H₂SO₄)

1 liter glass amber bottle

500 ml plastic bottle (NaOH)

100 ml plastic

<u>Parameter</u>	<u>Bottle Type</u>
<u>VOC</u>	<u>40 mL VOA vials (HCl)</u>
<u>TPH</u>	<u>40 mL VOA vials (HCl)</u>
<u>TPH</u>	<u>250 mL glass amber bottles</u>
<u>EDB AND EDC</u>	<u>40 mL VOA vials (Na₂S₂O₃)</u>
<u>SVOC</u>	<u>1 liter glass amber bottle</u>
<u>Total Metals</u>	<u>250 mL plastic bottle (HNO₃)</u>
<u>Dissolved Metals</u>	<u>125 mL plastic bottle (HNO₃)</u>
<u>Major Cations/Anions</u>	<u>125 mL plastic bottle (HNO₃)</u>
<u>Major Cations/Anions</u>	<u>125 mL plastic bottle (HNO₃)</u>
<u>Major Cations/Anions</u>	<u>125 mL plastic bottle (HNO₃)</u>
<u>BOD</u>	<u>1 liter plastic bottle</u>
<u>TDS</u>	<u>500 mL plastic bottle</u>
<u>COD</u>	<u>500 mL plastic bottle (H₂SO₄)</u>
<u>Cyanide</u>	<u>500 mL plastic bottle (NaOH)</u>
<u>Pesticides</u>	<u>1 liter glass amber bottle</u>
<u>E-Coli</u>	<u>100 mL plastic bottle</u>

*Pre-filtration bottle for dissolved metals which is subsequently filtered in the field and transferred to a pint plastic bottle with HNO₃ preservative.

Filtration

Ground water samples are filtered prior to dissolved metals analysis. For dissolved metals, sample water is poured into a jar and then extracted with a syringe. The syringe is then used to force the sample water through a 0.45-micron pore filter into the proper sample bottle to collect dissolved metals samples. Filtration must be performed within two hours of sample collection. Pour the filtrate into a sample bottle containing HNO₃ preservative.

For samples destined for total metals analysis, do not filter the sample, and preserve with HNO₃ to pH <2 in the field.

Sampling personnel carry a cell phone when gathering ground water and other water samples. While sampling procedures are generally well known and the appropriate sample bottles are ordered to match each sampling event, occasional questions do arise from unforeseen

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



circumstances which may develop during sampling. At such times, sampling personnel contact Hall Environmental Analytical Laboratory to verify that sampling is correctly performed. Examples would be if a well were to run dry short of filling the last sample bottle or to determine if there is enough water for sample analysis.

Sample Handling Procedures

At a minimum, the following procedures will be used when collecting samples:

- Neoprene, nitrile, or other protective gloves will be worn when collecting samples. New disposable gloves will be used to collect each sample.
- All samples collected for chemical analysis will be transferred into clean sample containers supplied by the analytical laboratory. The sample container will be clearly marked. Sample container volumes and preservation methods will be in accordance with the most recent standard EPA and industry accepted practices for use by accredited analytical laboratories. Sufficient sample volume will be obtained for the laboratory to complete the method-specific QC analyses on a laboratory-batch basis.
- Sample labels and documentation will be completed for each sample.

Immediately after the samples are collected, they will be stored in a cooler with ice or other appropriate storage method until they are delivered to the analytical laboratory. Standard chain-of-custody procedures, as described in Section 4.2.1 of this Plan, will be followed for all samples collected. All samples will be submitted to the laboratory to allow the laboratory to conduct the analyses within the method holding times.

General Well Sampling Procedures

For safety, protection, and sampling purity, rubber gloves or disposable nitrile gloves ~~are~~ will be worn and changed between each activity.

~~Prepare for sampling event by making out s~~ Sample bottle s and labels ~~and have bottles~~ will be be separated into plastic bags for each well to be sampled. The plastic bags holding the sample bottles, will be ~~and~~ placed in an ice chest ~~ready~~ to take into the field. Bring along a field note book and sample log will be used ~~to~~ Document document weather conditions and sample date and time. ~~Fill in~~ The label will be completed with location, date, time, analysis, preservative, and ~~your the~~ name of the sampler. For low-flow sampling, converter speed will be adjusted prior to

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



~~filling bottles. Start sampling by adjusting converter speed for each well. Affix sample~~ Sample labels will be affixed ~~and fill bottle s will be filled~~ according to lab instructions. Bottles with septa lids will be used ~~For for~~ samples intended for VOC analysis. ~~use bottles with septa lids, fill VOC bottles will be filled bottle to the~~ neck and ~~add~~ final amount of water will be added using the ~~with~~ cap to form meniscus before screwing the lid onto the sample bottle. To ensure a proper sample has been collected, the ~~Turn~~ bottles will be turned upside down ~~to and~~ examined for bubbles, if bubbles are detected in the vial, repeat the collection procedure will be repeated. If no bubbles are present ~~show~~, the lid will be secured and ~~lids and the bottles will be~~ packed in bubble wrap and placed in the cooler until sampling is completed.

Any reusable equipment that is not dedicated to a specific well will be ~~Decontaminated~~ decontaminated. ~~equipment that is not dedicated for use in a particular well.~~ Completed samples will be ~~Refrigerate~~ refrigerated ~~completed samples until they are shipping~~ shipped to the laboratory. Appropriate shipping methods will be arranged to accommodate ~~Be~~ sure to check holding times ~~and arrange for appropriate shipping method.~~ Sampling equipment and supplies will be checked, and proper inventory verified prior to sampling. Before departing, ~~Be sure that the field effort is adequately staffed and equipped. Check~~ QA/QC requirements will be checked to ensure that there are ~~before departing~~ QA/QC samples require additional equipment and supplies to fulfil the additional requirements.

Surface Water Sample Collection

At the evaporation ponds, samples will be collected as a grab sample at the pond edge near the inlets. This location will be noted in the field notebooks. The sampler will avoid disturbing sediment and gently allow the sample container to fill making sure that undue disturbance does not allow volatile contaminants to be lost. The sample bottle will be used for the sample collection in a shallow location near the bank. If a separate bottle and/or bailer are used to refill the sample container, this will be duly noted in the field log books. The decision to use a separate bottle/bailer will be made, if at all, by the sampler and the reasons for doing so will be noted in the field log book.

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Upon arrival at the field site, the sampler will set out safety equipment such as traffic cones and signs (if required). The vehicle will be parked a sufficient distance away so as to prevent sample contamination from emissions. Appropriate sample containers and gloves must be used for the type of analyses to be performed.

Decontamination Procedures

The objective of the decontamination procedures is to minimize the potential for cross-contamination. The majority of field equipment used for ground water sampling will be disposable and, therefore, not require decontamination. In order to prevent cross-contamination, field equipment that comes into contact with water or soil will be decontaminated between each sampling location. The decontamination procedure will consist of washing the equipment with a non-phosphate detergent solution (examples include Fantastik™, Liqui-Nox®), followed by two rinses of distilled water and air dried.

Decontamination water and rinsate will be contained and disposed of the same way as purge water, as described in Section 4.2. Decontamination procedures and the cleaning agents used will be documented in the daily field log.

Field Equipment Calibration Procedures

Field equipment requiring calibration will be calibrated to known standards, in accordance with the manufacturers' recommended schedules and procedures. Calibration checks will be conducted daily and the instruments will be recalibrated if necessary. Calibration measurements will be recorded in the daily field logs.

If field equipment becomes inoperable, its use will be discontinued until the necessary repairs are made. A properly calibrated replacement instrument will be used in the interim. Instrumentation used during sampling events will be recorded in the daily field logs.

Collection and Management of Investigation Derived Waste

Facility Wide Ground Water Monitoring Work Plan – 2019**Updates**

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



Investigation derived waste (IDW) generated during each groundwater sampling event may include purge water, decontamination water, excess sample material, and disposable sampling equipment. All water from all wells generated during sampling and decontamination activities will be temporarily stored in labeled 55-gallon drums until placed in the refinery wastewater treatment system upstream of the API separator. All other solid waste generated during sampling activities (including sampling gloves, tubing, etc.) will be disposed of with the Refinery's general municipal waste.

Documentation of Field Activities

Daily field activities, including observations and field procedures, will be recorded using indelible ink on field sampling forms. The original field forms will be maintained at the Gallup Refinery. Completed forms will be maintained in a bound and sequentially numbered field file for reference during field activities. The daily record of field activities will include the following information:

- Well ID/ Evaporation pond location/ Outfall
- Date
- Start and finish sampling time
- Field team members, including visitors
- Weather conditions
- Daily activities and times conducted
- Observations
- Record of samples collected with sample designations
- Photo log (if needed)
- Field monitoring data, including health and safety monitoring (if needed)
- Equipment used and calibration records, if appropriate
- List of additional data sheets and maps completed
- An inventory of the waste generated and the method of storage or disposal
- Signature of personnel completing the field record

Sample Custody

All samples collected for analysis will be recorded in the field report or data sheets. Chain-of-custody forms will be completed at the end of each sampling day, prior to the transfer of samples off site, and will accompany the samples during shipment to the laboratory. A signed and dated custody seal will be affixed to the lid of the shipping container. Upon receipt of the samples at the

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery
92 Giant Crossing Road
Gallup, NM 87301



laboratory, the custody seals will be broken, the chain-of-custody form will be signed as received by the laboratory, and the conditions of the samples will be recorded on the form. The original chain-of-custody form will remain with the laboratory. The Gallup Refinery will maintain copies of all chain-of-custody forms generated as part of sampling activities. Copies of the chain-of-custody records will be included with all draft and final laboratory reports submitted to NMED and OCD.

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX B

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX C

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

APPENDIX D

Facility Wide Ground Water Monitoring Work Plan – 2019

Updates

Gallup Refinery

92 Giant Crossing Road

Gallup, NM 87301



**Marathon
Petroleum Company LP**

FIGURES

District I

1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

COMMENTS

Action 19502

COMMENTS

Operator:			OGRID:	Action Number:	Action Type:
WESTERN REFINING SOUTHWEST, IN	6700 Jefferson NE, Suite A-1	Albuquerque,	705791	19502	DISCHARGE
NM87109					PERMIT

Created By	Comment	Comment Date
cchavez	Permittee 2020 RTC FWGWMWP 1-8-2021.	03/02/2021

District I

1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 19502

CONDITIONS OF APPROVAL

Operator: WESTERN REFINING SOUTHWEST, IN NM87109	6700 Jefferson NE, Suite A-1 Albuquerque,	OGRID: 705791	Action Number: 19502	Action Type: DISCHARGE PERMIT
OCD Reviewer cchavez	Condition None			