

Form 3160-3  
(June 2015)FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. <b>NMNM112935</b> 6. If Indian, Allottee or Tribe Name  7. If Unit or CA Agreement, Name and No.  8. Lease Name and Well No. <b>ALMOST EDDY 30 FED COM</b> <b>[330825]</b> <b>506H</b> 9. API Well No. <b>30-025-49011</b>
2. Name of Operator <b>EOG RESOURCES INCORPORATED [7377]</b> 3a. Address <b>1111 BAGBY SKY LOBBY 2, HOUSTON, TX 77002</b> 3b. Phone No. (include area code) <b>(713) 651-7000</b>		10. Field and Pool, or Exploratory <b>BRADLEY; BONE SPRING [97903]</b> 11. Sec., T. R. M. or Blk. and Survey or Area <b>SEC 30/T25S/R32E/NMP</b>
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface <b>TR K / 2000 FSL / 2430 FWL / LAT 32.0995677 / LONG -103.7152084</b> At proposed prod. zone <b>TR O / 100 FSL / 2066 FEL / LAT 32.0798387 / LONG -103.7125482</b>		12. County or Parish <b>LEA</b> 13. State <b>NM</b>
14. Distance in miles and direction from nearest town or post office*  15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>100 feet</b> 16. No of acres in lease  17. Spacing Unit dedicated to this well <b>483.0</b>		18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>33 feet</b> 19. Proposed Depth <b>10430 feet / 18085 feet</b> 20. BLM/BIA Bond No. in file <b>FED:</b>
21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>3352 feet</b> 22. Approximate date work will start* <b>03/15/2021</b>		23. Estimated duration <b>25 days</b> 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |   |   |
|---|---|
| 1. Well plat certified by a registered surveyor.<br>2. A Drilling Plan.<br>3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).<br>5. Operator certification.<br>6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission)	Name (Printed/Typed) <b>STAR HARRELL / Ph: (713) 651-7000</b>	Date <b>09/14/2020</b>
Title <b>Regulatory Specialist</b>		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) <b>Cody Layton / Ph: (575) 234-5959</b>	Date <b>05/06/2021</b>
Title <b>Assistant Field Manager Lands &amp; Minerals</b> Office <b>Carlsbad Field Office</b>		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**GCP Rec 05/07/2021****SL**

(Continued on page 2)

**Approval Date: 05/06/2021**
**KZ**  
**06/11/2021**

\*(Instructions on page 2)

**District I**  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720

**District II**  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720

**District III**  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

**District IV**  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources  
Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

**FORM C-102**

Revised August 1, 2011

**Submit one copy to appropriate**

**District Office**

☐ **AMENDED REPORT**

# WELL LOCATION AND ACREAGE DEDICATION PLAT

<sup>1</sup> API Number <b>30-025- 49011</b>	<sup>2</sup> Pool Code <b>97903</b>	<sup>3</sup> Pool Name <b>WC-025 G-08 S253235G;LOWER BONE SPRING</b>
<sup>4</sup> Property Code <b>330825</b>	<sup>5</sup> Property Name <b>ALMOST EDDY 30 FED COM</b>	
<sup>7</sup> OGRID No. <b>7377</b>	<sup>8</sup> Operator Name <b>EOG RESOURCES, INC.</b>	<sup>6</sup> Well Number <b>506H</b>
		<sup>9</sup> Elevation <b>3352'</b>

<sup>10</sup>Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
K	30	25-S	32-E	—	2000'	SOUTH	2430'	WEST	LEA

<sup>11</sup>Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	31	25-S	32-E	-	100'	SOUTH	2066'	EAST	LEA

<sup>12</sup> Dedicated Acres <b>483.22</b>	<sup>13</sup> Joint or Infill	<sup>14</sup> Consolidation Code	<sup>15</sup> Order No.
--	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

**GAS CAPTURE PLAN**

**Lea County, NM**

Date: 5/7/2021

☒ Original

Operator & OGRID No.: EOG Resources, Inc. 7377

☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

**Well(s)/Production Facility – Name of facility**

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Almost Eddy 30 Fed Com 501H	30-025-*****	L-30-25S-32E	1936' FSL & 387' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 502H	30-025-*****	L-30-25S-32E	1903' FSL & 387' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 503H	30-025-*****	L-30-25S-32E	1870' FSL & 387' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 504H	30-025-*****	K-30-25S-32E	1948' FSL & 2390' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 505H	30-025-*****	K-30-25S-32E	1974' FSL & 2410' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 506H <b>30-025-49011</b>	30-025-*****	K-30-25S-32E	2000' FSL & 2430' FWL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 507H	30-025-*****	I-30-25S-32E	2182' FSL & 758' FEL	±3500	None Planned	APD Submission
Almost Eddy 30 Fed Com 508H	30-025-*****	I-30-25S-32E	2182' FSL & 725' FEL	±3500	None Planned	APD Submission

**Gathering System and Pipeline Notification**

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to **Enlink, MarkWest, Enterprise, Energy Transfer Company & Lucid** and will be connected to **EOG Resources** low/high pressure gathering system located in Lea County, New Mexico. **EOG Resources** provides (periodically) to **Enlink, MarkWest, Enterprise, Energy Transfer Company & Lucid** a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, **EOG Resources** and **Enlink, MarkWest, Enterprise, Energy Transfer Company & Lucid** have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at **Enlink, MarkWest, Enterprise, Energy Transfer Company & Lucid** Processing Plant located in Lea County, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

**Flowback Strategy**

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on **Enlink, MarkWest, Enterprise, Energy Transfer Company & Lucid** system at that time. Based on current information, it is **EOG Resources**' belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

**Alternatives to Reduce Flaring**

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

**1. GEOLOGIC NAME OF SURFACE FORMATION:**

Permian

**2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:**

Rustler	975'
Tamarisk Anhydrite	1,045'
Top of Salt	1,300'
Base of Salt	4,180'
Lamar	4,385'
Bell Canyon	4,410'
Cherry Canyon	5,360'
Brushy Canyon	6,865'
Bone Spring Lime	8,425'
Leonard A Shale	8,525'
Leonard B Shale	8,855'
1 <sup>st</sup> Bone Spring Sand	9,355'
2 <sup>nd</sup> Bone Spring Shale	9,665'
2 <sup>nd</sup> Bone Spring Sand	10,050'
TD	10,430'

**3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:**

Upper Permian Sands	0- 400'	Fresh Water
Cherry Canyon	5,360'	Oil
Brushy Canyon	6,865'	Oil
Leonard A Shale	8,525'	Oil
Leonard B Shale	8,855'	Oil
1 <sup>st</sup> Bone Spring Sand	9,355'	Oil
2 <sup>nd</sup> Bone Spring Shale	9,665'	Oil
2 <sup>nd</sup> Bone Spring Sand	10,050'	Oil

No other Formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 13.375" casing at 1,070' and circulating cement back to surface.

**EOG RESOURCES, INC.**  
**ALMOST EDDY 30 FED COM #506H**

**4. CASING PROGRAM - NEW**

Hole Size	Interval	Csg OD	Weight	Grade	Conn	DF <sub>min</sub> Collapse	DF <sub>min</sub> Burst	DF <sub>min</sub> Tension
17.5"	0' – 1,070'	13.375"	54.5#	J-55	STC	1.125	1.25	1.60
12.25"	0' – 4,000'	9.625"	40#	J-55	LTC	1.125	1.25	1.60
12.25"	4,000' – 4,280'	9.625"	40#	HCK-55	LTC	1.125	1.25	1.60
8.75"	0' – 10,798'	5.5"	17#	HCP-110	LTC	1.125	1.25	1.60
8.5"	10,798' – 18,085'	5.5"	17#	HCP-110	LTC	1.125	1.25	1.60

Variance is requested to waive the centralizer requirements for the 9-5/8" casing in the 12-1/4" hole size. An expansion additive will be utilized, in the cement slurry, for the entire length of the 12-1/4" hole interval to maximize cement bond and zonal isolation.

Variance is also requested to waive any centralizer requirements for the 5-1/2" casing in the 8-3/4" hole size. An expansion additive will be utilized, in the cement slurry, for the entire length of the 8-3/4" hole interval to maximize cement bond and zonal isolation.

**Cementing Program:**

Depth	No. Sacks	Wt. ppg	Yld Ft <sup>3</sup> /sk	Slurry Description
1,070'	470	13.5	1.73	Lead: Class C + 4.0% Bentonite + 0.5% CaCl <sub>2</sub> + 0.25 lb/sk Cello-Flake (TOC @ Surface)
	160	14.8	1.34	Tail: Class C + 0.6% FL-62 + 0.25 lb/sk Cello-Flake + 0.2% Sodium Metasilicate (TOC @ 870')
4,280'	630	12.7	2.22	Lead: Class C + 10% NaCl + 6% Bentonite Gel + 3% MagOx (TOC @ Surface)
	280	14.8	1.32	Tail: Class C + 10% NaCl + 3% MagOx (TOC @ 3,430')
18,085'	630	11.0	3.21	Lead: Class C + 3% CaCl <sub>2</sub> + 3% Microbond (TOC @ 3,780')
	1,950	14.4	1.2	Tail: Class H + 0.4% Halad-344 + 0.35% HR-601 + 3% Microbond (TOC @ 10,048')

**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

<b>Additive</b>	<b>Purpose</b>
Bentonite Gel	Lightweight/Lost circulation prevention
Calcium Chloride	Accelerator
Cello-flake	Lost circulation prevention
Sodium Metasilicate	Accelerator
MagOx	Expansive agent
Sodium Chloride	Accelerator
FL-62	Fluid loss control
Halad-344	Fluid loss control
Halad-9	Fluid loss control
HR-601	Retarder
Microbond	Expansive Agent

Cement integrity tests will be performed immediately following plug bump.

Note: Cement volumes based on bit size plus at least 25% excess in the open hole plus 10% excess in the cased-hole overlap section.

**5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

Variance is requested to use a co-flex line between the BOP and choke manifold (instead of using a 4" OD steel line).

The minimum blowout preventer equipment (BOPE) shown in Exhibit #1 will consist of a single ram, mud cross and double ram-type (10,000 psi WP) preventer and an annular preventer (5,000-psi WP). Both units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOPE will be tested in accordance with Onshore Oil & Gas order No. 2.

EOG will utilize wing unions on BOPE connections that can be isolated from wellbore pressure through means of a choke. All wing unions will be rated to a pressure that meets or exceeds the pressure rating of the BOPE system.

Variance is requested to use a 5,000 psi annular BOP with the 10,000 psi BOP stack.

Before drilling out of the surface casing, the ram-type BOP and accessory equipment will be tested to 10,000/ 250 psig and the annular preventer to 5,000/ 250 psig.

Pipe rams and blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

A hydraulically operated choke will be installed prior to drilling out of the intermediate casing shoe.



**EOG RESOURCES, INC.**  
**ALMOST EDDY 30 FED COM #506H**

**6. TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:**

During this procedure we plan to use a Closed-Loop System and haul contents to the required disposal.

The applicable depths and properties of the drilling fluid systems are as follows.

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 1,070'	Fresh - Gel	8.6-8.8	28-34	N/c
1,070' – 4,280'	Brine	8.6-8.8	28-34	N/c
4,280' – 18,085'	Oil Base	8.8-9.5	58-68	N/c - 6

An electronic pit volume totalizer (PVT) will be utilized on the circulating system, to monitor pit volume, flow rate, pump pressure and stroke rate.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

**7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:**

- (A) A kelly cock will be kept in the drill string at all times.
- (B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- (C) H<sub>2</sub>S monitoring and detection equipment will be utilized from surface casing point to TD.

**8. LOGGING, TESTING AND CORING PROGRAM:**

Open-hole logs are not planned for this well.

GR-CCL Will be run in cased hole during completions phase of operations.

**9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:**

The estimated bottom-hole temperature (BHT) at TD is 174 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 5,152 psig and a maximum anticipated surface pressure of 2,858 psig (based on 9.5 ppg MW). No hydrogen sulfide or other hazardous gases or fluids have been encountered, reported or are known to exist at this depth in this area. Severe loss circulation is expected from 6,865' to TD.



**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

**10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:**

The drilling operation should be finished in approximately one month. If the well is productive, an additional 60-90 days will be required for completion and testing before a decision is made to install permanent facilities.

(A) EOG Resources requests the option to contract a Surface Rig to drill, set surface casing, and cement on the subject well. After WOC 8 hours or 500 psi compressive strength (whichever is greater), the Surface Rig will move off so the wellhead can be installed. A welder will cut the casing to the proper height and weld on the wellhead (both "A" and "B" sections). The weld will be tested to 1000 psi. All valves will be closed and a wellhead cap will be installed (diagram attached). If the timing between rigs is such that EOG Resources would not be able to preset the surface, the Primary Rig will MIRU and drill the well in its entirety per the APD.

**11. WELLHEAD:**

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13-3/8" BOP/BOPE system with a minimum working pressure of 10,000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10,000 psi pressure test. This pressure test will be repeated at least every 30 days, as per Onshore Order No. 2

The minimum working pressure of the BOP and related BOPE required for drilling below the surface casing shoe shall be 10,000 psi.

The multi-bowl wellhead will be installed by vendor's representative(s). A copy of the installation instructions for the Cameron Multi-Bowl WH system has been sent to the NM BLM office in Carlsbad, NM.

The wellhead will be installed by a third party welder while being monitored by WH vendor's representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. EOG Resources reserves the option to conduct BOPE testing during wait on cement periods provided a test plug is utilized.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

Casing strings will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.


EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H

2000' FSL  
2430' FWL  
Section 30  
T-25-S, R-32-E

Proposed Wellbore

KB: 3,377'  
GL: 3,352'

API: 30-025-\*\*\*\*\*





## **EOG Resources - Midland**

**Lea County, NM (NAD 83 NME)**

**Almost Eddy 30 Fed Com**

**#506H**

**OH**

**Plan: Plan #0.1 RT**

## **Standard Planning Report**

**17 July, 2020**

## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

<b>Project</b>	Lea County, NM (NAD 83 NME)		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

<b>Site</b>	Almost Eddy 30 Fed Com		
<b>Site Position:</b>		<b>Northing:</b>	400,427.80 ft
<b>From:</b>	Map	<b>Easting:</b>	730,702.46 ft
<b>Position Uncertainty:</b>	0.000 ft	<b>Slot Radius:</b>	13.20 in
		<b>Latitude:</b>	32.099377
		<b>Longitude:</b>	-103.721805
		<b>Grid Convergence:</b>	0.325 °

Well	#506H					
Well Position	+N/-S	81.000 ft	Northing:	400,508.80 ft	Latitude:	32.099568
	+E/-W	2,042.004 ft	Easting:	732,744.46 ft	Longitude:	-103.715209
Position Uncertainty		0.000 ft	Wellhead Elevation:		Ground Level:	3,352.007 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b>	<b>Dip Angle</b>	<b>Field Strength</b>
			(°)	(°)	(nT)
	IGRF2020	7/16/2020	6.710	59.796	47,501.02436308

<b>Design</b>	Plan #0.1 RT			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.000
<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N/-S</b>	<b>+E/-W</b>	<b>Direction</b>
	(ft)	(ft)	(ft)	(°)
	0.000	0.000	0.000	173.123

<b>Plan Survey Tool Program</b>	<b>Date</b>	7/17/2020		
<b>Depth From</b>	<b>Depth To</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Remarks</b>
(ft)	(ft)			
1	0.000	18,084.896	Plan #0.1 RT (OH)	EOG MWD+IFR1
				MWD + IFR1

## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.000	0.00	0.000	0.000	0.000	0.000	0.00	0.00	0.00	0.000	
1,170.002	0.00	0.000	1,170.002	0.000	0.000	0.00	0.00	0.00	0.000	
1,728.927	11.18	54.305	1,725.388	31.712	44.140	2.00	2.00	0.00	54.305	
6,401.821	11.18	54.305	6,309.628	560.289	779.862	0.00	0.00	0.00	0.000	
6,960.745	0.00	0.000	6,865.013	592.001	824.002	2.00	-2.00	0.00	180.000	
10,048.252	0.00	0.000	9,952.519	592.001	824.002	0.00	0.00	0.00	0.000	KOP(Almost Eddy 30
10,268.703	26.46	180.000	10,165.220	542.001	824.002	12.00	12.00	81.65	180.000	FTP(Almost Eddy 30
10,798.230	90.00	179.690	10,429.964	114.545	825.601	12.00	12.00	-0.06	-0.346	
18,084.896	90.00	179.690	10,430.020	-7,172.014	865.002	0.00	0.00	0.00	0.000	PBHL(Almost Eddy 30

## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
0.000	0.00	0.000	0.000	0.000	0.000	0.000	0.00	0.00	0.00	
100.000	0.00	0.000	100.000	0.000	0.000	0.000	0.00	0.00	0.00	
200.000	0.00	0.000	200.000	0.000	0.000	0.000	0.00	0.00	0.00	
300.001	0.00	0.000	300.001	0.000	0.000	0.000	0.00	0.00	0.00	
400.001	0.00	0.000	400.001	0.000	0.000	0.000	0.00	0.00	0.00	
500.001	0.00	0.000	500.001	0.000	0.000	0.000	0.00	0.00	0.00	
600.001	0.00	0.000	600.001	0.000	0.000	0.000	0.00	0.00	0.00	
700.001	0.00	0.000	700.001	0.000	0.000	0.000	0.00	0.00	0.00	
800.002	0.00	0.000	800.002	0.000	0.000	0.000	0.00	0.00	0.00	
900.002	0.00	0.000	900.002	0.000	0.000	0.000	0.00	0.00	0.00	
1,000.002	0.00	0.000	1,000.002	0.000	0.000	0.000	0.00	0.00	0.00	
1,100.002	0.00	0.000	1,100.002	0.000	0.000	0.000	0.00	0.00	0.00	
1,170.002	0.00	0.000	1,170.002	0.000	0.000	0.000	0.00	0.00	0.00	
1,200.002	0.60	54.305	1,200.002	0.092	0.128	-0.076	2.00	2.00	0.00	
1,300.003	2.60	54.305	1,299.958	1.721	2.395	-1.422	2.00	2.00	0.00	
1,400.003	4.60	54.305	1,399.756	5.384	7.494	-4.448	2.00	2.00	0.00	
1,500.003	6.60	54.305	1,499.274	11.078	15.419	-9.152	2.00	2.00	0.00	
1,600.003	8.60	54.305	1,598.390	18.794	26.159	-15.527	2.00	2.00	0.00	
1,700.003	10.60	54.305	1,696.985	28.524	39.702	-23.565	2.00	2.00	0.00	
1,728.927	11.18	54.305	1,725.388	31.712	44.140	-26.199	2.00	2.00	0.00	
1,800.004	11.18	54.305	1,795.116	39.752	55.331	-32.841	0.00	0.00	0.00	
1,900.004	11.18	54.305	1,893.219	51.064	71.075	-42.186	0.00	0.00	0.00	
2,000.004	11.18	54.305	1,991.322	62.375	86.820	-51.531	0.00	0.00	0.00	
2,100.004	11.18	54.305	2,089.425	73.687	102.564	-60.876	0.00	0.00	0.00	
2,200.004	11.18	54.305	2,187.528	84.998	118.309	-70.221	0.00	0.00	0.00	
2,300.004	11.18	54.305	2,285.631	96.310	134.053	-79.565	0.00	0.00	0.00	
2,400.005	11.18	54.305	2,383.734	107.621	149.797	-88.910	0.00	0.00	0.00	
2,500.005	11.18	54.305	2,481.837	118.933	165.542	-98.255	0.00	0.00	0.00	
2,600.005	11.18	54.305	2,579.940	130.245	181.286	-107.600	0.00	0.00	0.00	
2,700.005	11.18	54.305	2,678.043	141.556	197.031	-116.945	0.00	0.00	0.00	
2,800.005	11.18	54.305	2,776.146	152.868	212.775	-126.290	0.00	0.00	0.00	
2,900.006	11.18	54.305	2,874.249	164.179	228.520	-135.635	0.00	0.00	0.00	
3,000.006	11.18	54.305	2,972.352	175.491	244.264	-144.980	0.00	0.00	0.00	
3,100.006	11.18	54.305	3,070.455	186.803	260.009	-154.325	0.00	0.00	0.00	
3,200.006	11.18	54.305	3,168.558	198.114	275.753	-163.670	0.00	0.00	0.00	
3,300.006	11.18	54.305	3,266.661	209.426	291.498	-173.015	0.00	0.00	0.00	
3,400.007	11.18	54.305	3,364.764	220.737	307.242	-182.360	0.00	0.00	0.00	
3,500.007	11.18	54.305	3,462.867	232.049	322.987	-191.705	0.00	0.00	0.00	
3,600.007	11.18	54.305	3,560.970	243.360	338.731	-201.050	0.00	0.00	0.00	
3,700.007	11.18	54.305	3,659.073	254.672	354.476	-210.395	0.00	0.00	0.00	
3,800.007	11.18	54.305	3,757.176	265.984	370.220	-219.740	0.00	0.00	0.00	
3,900.008	11.18	54.305	3,855.279	277.295	385.965	-229.085	0.00	0.00	0.00	
4,000.008	11.18	54.305	3,953.382	288.607	401.709	-238.429	0.00	0.00	0.00	
4,100.008	11.18	54.305	4,051.485	299.918	417.454	-247.774	0.00	0.00	0.00	
4,200.008	11.18	54.305	4,149.588	311.230	433.198	-257.119	0.00	0.00	0.00	
4,300.008	11.18	54.305	4,247.691	322.541	448.943	-266.464	0.00	0.00	0.00	
4,400.009	11.18	54.305	4,345.794	333.853	464.687	-275.809	0.00	0.00	0.00	
4,500.009	11.18	54.305	4,443.897	345.165	480.432	-285.154	0.00	0.00	0.00	
4,600.009	11.18	54.305	4,542.000	356.476	496.176	-294.499	0.00	0.00	0.00	
4,700.009	11.18	54.305	4,640.103	367.788	511.921	-303.844	0.00	0.00	0.00	
4,800.009	11.18	54.305	4,738.206	379.099	527.665	-313.189	0.00	0.00	0.00	
4,900.010	11.18	54.305	4,836.309	390.411	543.410	-322.534	0.00	0.00	0.00	
5,000.010	11.18	54.305	4,934.412	401.722	559.154	-331.879	0.00	0.00	0.00	

## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
5,100.010	11.18	54.305	5,032.515	413.034	574.899	-341.224	0.00	0.00	0.00	
5,200.010	11.18	54.305	5,130.618	424.346	590.643	-350.569	0.00	0.00	0.00	
5,300.010	11.18	54.305	5,228.721	435.657	606.388	-359.914	0.00	0.00	0.00	
5,400.011	11.18	54.305	5,326.824	446.969	622.132	-369.259	0.00	0.00	0.00	
5,500.011	11.18	54.305	5,424.927	458.280	637.877	-378.604	0.00	0.00	0.00	
5,600.011	11.18	54.305	5,523.030	469.592	653.621	-387.949	0.00	0.00	0.00	
5,700.011	11.18	54.305	5,621.133	480.903	669.366	-397.293	0.00	0.00	0.00	
5,800.011	11.18	54.305	5,719.236	492.215	685.110	-406.638	0.00	0.00	0.00	
5,900.012	11.18	54.305	5,817.339	503.527	700.855	-415.983	0.00	0.00	0.00	
6,000.012	11.18	54.305	5,915.442	514.838	716.599	-425.328	0.00	0.00	0.00	
6,100.012	11.18	54.305	6,013.545	526.150	732.344	-434.673	0.00	0.00	0.00	
6,200.012	11.18	54.305	6,111.648	537.461	748.088	-444.018	0.00	0.00	0.00	
6,300.012	11.18	54.305	6,209.751	548.773	763.832	-453.363	0.00	0.00	0.00	
6,401.821	11.18	54.305	6,309.628	560.289	779.862	-462.877	0.00	0.00	0.00	
6,500.013	9.21	54.305	6,406.264	570.431	793.978	-471.256	2.00	-2.00	0.00	
6,600.013	7.21	54.305	6,505.233	578.767	805.581	-478.143	2.00	-2.00	0.00	
6,700.013	5.21	54.305	6,604.641	585.083	814.372	-483.360	2.00	-2.00	0.00	
6,800.013	3.21	54.305	6,704.366	589.371	820.341	-486.903	2.00	-2.00	0.00	
6,900.013	1.21	54.305	6,804.286	591.626	823.479	-488.765	2.00	-2.00	0.00	
6,960.745	0.00	0.000	6,865.013	592.001	824.002	-489.076	2.00	-2.00	0.00	
7,000.014	0.00	0.000	6,904.282	592.001	824.002	-489.076	0.00	0.00	0.00	
7,100.014	0.00	0.000	7,004.282	592.001	824.002	-489.076	0.00	0.00	0.00	
7,200.014	0.00	0.000	7,104.282	592.001	824.002	-489.076	0.00	0.00	0.00	
7,300.014	0.00	0.000	7,204.282	592.001	824.002	-489.076	0.00	0.00	0.00	
7,400.014	0.00	0.000	7,304.282	592.001	824.002	-489.076	0.00	0.00	0.00	
7,500.015	0.00	0.000	7,404.283	592.001	824.002	-489.076	0.00	0.00	0.00	
7,600.015	0.00	0.000	7,504.283	592.001	824.002	-489.076	0.00	0.00	0.00	
7,700.015	0.00	0.000	7,604.283	592.001	824.002	-489.076	0.00	0.00	0.00	
7,800.015	0.00	0.000	7,704.283	592.001	824.002	-489.076	0.00	0.00	0.00	
7,900.015	0.00	0.000	7,804.283	592.001	824.002	-489.076	0.00	0.00	0.00	
8,000.016	0.00	0.000	7,904.284	592.001	824.002	-489.076	0.00	0.00	0.00	
8,100.016	0.00	0.000	8,004.284	592.001	824.002	-489.076	0.00	0.00	0.00	
8,200.016	0.00	0.000	8,104.284	592.001	824.002	-489.076	0.00	0.00	0.00	
8,300.016	0.00	0.000	8,204.284	592.001	824.002	-489.076	0.00	0.00	0.00	
8,400.016	0.00	0.000	8,304.284	592.001	824.002	-489.076	0.00	0.00	0.00	
8,500.017	0.00	0.000	8,404.285	592.001	824.002	-489.076	0.00	0.00	0.00	
8,600.017	0.00	0.000	8,504.285	592.001	824.002	-489.076	0.00	0.00	0.00	
8,700.017	0.00	0.000	8,604.285	592.001	824.002	-489.076	0.00	0.00	0.00	
8,800.017	0.00	0.000	8,704.285	592.001	824.002	-489.076	0.00	0.00	0.00	
8,900.017	0.00	0.000	8,804.285	592.001	824.002	-489.076	0.00	0.00	0.00	
9,000.018	0.00	0.000	8,904.285	592.001	824.002	-489.076	0.00	0.00	0.00	
9,100.018	0.00	0.000	9,004.286	592.001	824.002	-489.076	0.00	0.00	0.00	
9,200.018	0.00	0.000	9,104.286	592.001	824.002	-489.076	0.00	0.00	0.00	
9,300.018	0.00	0.000	9,204.286	592.001	824.002	-489.076	0.00	0.00	0.00	
9,400.018	0.00	0.000	9,304.286	592.001	824.002	-489.076	0.00	0.00	0.00	
9,500.019	0.00	0.000	9,404.286	592.001	824.002	-489.076	0.00	0.00	0.00	
9,600.019	0.00	0.000	9,504.287	592.001	824.002	-489.076	0.00	0.00	0.00	
9,700.019	0.00	0.000	9,604.287	592.001	824.002	-489.076	0.00	0.00	0.00	
9,800.019	0.00	0.000	9,704.287	592.001	824.002	-489.076	0.00	0.00	0.00	
9,900.019	0.00	0.000	9,804.287	592.001	824.002	-489.076	0.00	0.00	0.00	
10,000.020	0.00	0.000	9,904.287	592.001	824.002	-489.076	0.00	0.00	0.00	
10,048.252	0.00	0.000	9,952.519	592.001	824.002	-489.076	0.00	0.00	0.00	
10,050.020	0.21	180.000	9,954.288	591.998	824.002	-489.073	12.00	12.00	0.00	



## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
10,075.020	3.21	180.000	9,979.274	591.251	824.002	-488.331	12.00	12.00	0.00	
10,100.020	6.21	180.000	10,004.186	589.197	824.002	-486.292	12.00	12.00	0.00	
10,125.020	9.21	180.000	10,028.957	585.842	824.002	-482.961	12.00	12.00	0.00	
10,150.020	12.21	180.000	10,053.519	581.195	824.002	-478.348	12.00	12.00	0.00	
10,175.020	15.21	180.000	10,077.803	575.269	824.002	-472.464	12.00	12.00	0.00	
10,200.020	18.21	180.000	10,101.744	568.080	824.002	-465.327	12.00	12.00	0.00	
10,225.020	21.21	180.000	10,125.276	559.648	824.002	-456.955	12.00	12.00	0.00	
10,250.020	24.21	180.000	10,148.335	549.995	824.002	-447.372	12.00	12.00	0.00	
10,268.703	26.46	180.000	10,165.220	542.001	824.002	-439.435	12.00	12.00	0.00	
10,275.020	27.22	179.990	10,170.856	539.149	824.002	-436.604	12.00	12.00	-0.16	
10,300.020	30.21	179.955	10,192.779	527.139	824.008	-424.680	12.00	12.00	-0.14	
10,325.020	33.21	179.926	10,214.044	513.999	824.022	-411.632	12.00	12.00	-0.12	
10,350.020	36.21	179.901	10,234.592	499.763	824.043	-397.496	12.00	12.00	-0.10	
10,375.020	39.21	179.879	10,254.366	484.471	824.073	-382.311	12.00	12.00	-0.09	
10,400.020	42.21	179.860	10,273.313	468.166	824.110	-366.118	12.00	12.00	-0.08	
10,425.020	45.21	179.843	10,291.381	450.891	824.155	-348.962	12.00	12.00	-0.07	
10,450.020	48.21	179.828	10,308.519	432.694	824.207	-330.890	12.00	12.00	-0.06	
10,475.020	51.21	179.814	10,324.682	413.626	824.267	-311.952	12.00	12.00	-0.06	
10,500.021	54.21	179.801	10,339.825	393.737	824.333	-292.199	12.00	12.00	-0.05	
10,525.021	57.21	179.789	10,353.907	373.084	824.407	-271.685	12.00	12.00	-0.05	
10,550.022	60.21	179.778	10,366.888	351.721	824.488	-250.466	12.00	12.00	-0.04	
10,575.022	63.21	179.768	10,378.733	329.709	824.575	-228.602	12.00	12.00	-0.04	
10,600.022	66.21	179.758	10,389.410	307.107	824.668	-206.151	12.00	12.00	-0.04	
10,625.022	69.21	179.749	10,398.889	283.977	824.768	-183.176	12.00	12.00	-0.04	
10,650.022	72.21	179.740	10,407.145	260.383	824.873	-159.739	12.00	12.00	-0.04	
10,675.022	75.21	179.731	10,414.155	236.389	824.984	-135.904	12.00	12.00	-0.04	
10,700.022	78.21	179.722	10,419.899	212.061	825.100	-111.738	12.00	12.00	-0.03	
10,725.022	81.21	179.714	10,424.362	187.466	825.221	-87.305	12.00	12.00	-0.03	
10,750.022	84.21	179.706	10,427.532	162.671	825.347	-62.673	12.00	12.00	-0.03	
10,775.022	87.21	179.698	10,429.400	137.744	825.477	-37.910	12.00	12.00	-0.03	
10,798.230	90.00	179.690	10,429.964	114.545	825.601	-14.864	12.00	12.00	-0.03	
10,800.022	90.00	179.690	10,429.964	112.753	825.610	-13.083	0.00	0.00	0.00	
10,900.022	90.00	179.690	10,429.965	12.754	826.151	86.261	0.00	0.00	0.00	
11,000.022	90.00	179.690	10,429.966	-87.244	826.692	185.605	0.00	0.00	0.00	
11,100.023	90.00	179.690	10,429.967	-187.243	827.232	284.949	0.00	0.00	0.00	
11,200.023	90.00	179.690	10,429.967	-287.242	827.773	384.293	0.00	0.00	0.00	
11,300.023	90.00	179.690	10,429.968	-387.241	828.314	483.637	0.00	0.00	0.00	
11,400.023	90.00	179.690	10,429.969	-487.239	828.855	582.981	0.00	0.00	0.00	
11,500.023	90.00	179.690	10,429.970	-587.238	829.395	682.325	0.00	0.00	0.00	
11,600.024	90.00	179.690	10,429.970	-687.237	829.936	781.669	0.00	0.00	0.00	
11,700.024	90.00	179.690	10,429.971	-787.236	830.477	881.013	0.00	0.00	0.00	
11,800.024	90.00	179.690	10,429.972	-887.234	831.018	980.357	0.00	0.00	0.00	
11,900.024	90.00	179.690	10,429.973	-987.233	831.558	1,079.701	0.00	0.00	0.00	
12,000.024	90.00	179.690	10,429.973	-1,087.232	832.099	1,179.045	0.00	0.00	0.00	
12,100.025	90.00	179.690	10,429.974	-1,187.230	832.640	1,278.389	0.00	0.00	0.00	
12,200.025	90.00	179.690	10,429.975	-1,287.229	833.181	1,377.733	0.00	0.00	0.00	
12,300.025	90.00	179.690	10,429.976	-1,387.228	833.721	1,477.077	0.00	0.00	0.00	
12,400.025	90.00	179.690	10,429.977	-1,487.227	834.262	1,576.421	0.00	0.00	0.00	
12,500.025	90.00	179.690	10,429.977	-1,587.225	834.803	1,675.765	0.00	0.00	0.00	
12,600.026	90.00	179.690	10,429.978	-1,687.224	835.343	1,775.109	0.00	0.00	0.00	
12,700.026	90.00	179.690	10,429.979	-1,787.223	835.884	1,874.453	0.00	0.00	0.00	
12,800.026	90.00	179.690	10,429.980	-1,887.222	836.425	1,973.797	0.00	0.00	0.00	
12,900.026	90.00	179.690	10,429.980	-1,987.220	836.966	2,073.141	0.00	0.00	0.00	

## EOG Resources

## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
13,000.026	90.00	179.690	10,429.981	-2,087.219	837.506	2,172.485	0.00	0.00	0.00
13,100.027	90.00	179.690	10,429.982	-2,187.218	838.047	2,271.829	0.00	0.00	0.00
13,200.027	90.00	179.690	10,429.983	-2,287.217	838.588	2,371.173	0.00	0.00	0.00
13,300.027	90.00	179.690	10,429.983	-2,387.215	839.129	2,470.517	0.00	0.00	0.00
13,400.027	90.00	179.690	10,429.984	-2,487.214	839.669	2,569.861	0.00	0.00	0.00
13,500.027	90.00	179.690	10,429.985	-2,587.213	840.210	2,669.205	0.00	0.00	0.00
13,600.028	90.00	179.690	10,429.986	-2,687.211	840.751	2,768.549	0.00	0.00	0.00
13,700.028	90.00	179.690	10,429.987	-2,787.210	841.291	2,867.893	0.00	0.00	0.00
13,800.028	90.00	179.690	10,429.987	-2,887.209	841.832	2,967.237	0.00	0.00	0.00
13,900.028	90.00	179.690	10,429.988	-2,987.208	842.373	3,066.581	0.00	0.00	0.00
14,000.028	90.00	179.690	10,429.989	-3,087.206	842.914	3,165.925	0.00	0.00	0.00
14,100.029	90.00	179.690	10,429.990	-3,187.205	843.454	3,265.269	0.00	0.00	0.00
14,200.029	90.00	179.690	10,429.990	-3,287.204	843.995	3,364.613	0.00	0.00	0.00
14,300.029	90.00	179.690	10,429.991	-3,387.203	844.536	3,463.957	0.00	0.00	0.00
14,400.029	90.00	179.690	10,429.992	-3,487.201	845.077	3,563.301	0.00	0.00	0.00
14,500.029	90.00	179.690	10,429.993	-3,587.200	845.617	3,662.645	0.00	0.00	0.00
14,600.030	90.00	179.690	10,429.994	-3,687.199	846.158	3,761.989	0.00	0.00	0.00
14,700.030	90.00	179.690	10,429.994	-3,787.198	846.699	3,861.333	0.00	0.00	0.00
14,800.030	90.00	179.690	10,429.995	-3,887.196	847.239	3,960.677	0.00	0.00	0.00
14,900.030	90.00	179.690	10,429.996	-3,987.195	847.780	4,060.022	0.00	0.00	0.00
15,000.030	90.00	179.690	10,429.997	-4,087.194	848.321	4,159.366	0.00	0.00	0.00
15,100.030	90.00	179.690	10,429.997	-4,187.192	848.862	4,258.710	0.00	0.00	0.00
15,200.031	90.00	179.690	10,429.998	-4,287.191	849.402	4,358.054	0.00	0.00	0.00
15,300.031	90.00	179.690	10,429.999	-4,387.190	849.943	4,457.398	0.00	0.00	0.00
15,400.031	90.00	179.690	10,430.000	-4,487.189	850.484	4,556.742	0.00	0.00	0.00
15,500.031	90.00	179.690	10,430.000	-4,587.187	851.025	4,656.086	0.00	0.00	0.00
15,600.031	90.00	179.690	10,430.001	-4,687.186	851.565	4,755.430	0.00	0.00	0.00
15,700.032	90.00	179.690	10,430.002	-4,787.185	852.106	4,854.774	0.00	0.00	0.00
15,800.032	90.00	179.690	10,430.003	-4,887.184	852.647	4,954.118	0.00	0.00	0.00
15,900.032	90.00	179.690	10,430.004	-4,987.182	853.188	5,053.462	0.00	0.00	0.00
16,000.032	90.00	179.690	10,430.004	-5,087.181	853.728	5,152.806	0.00	0.00	0.00
16,100.032	90.00	179.690	10,430.005	-5,187.180	854.269	5,252.150	0.00	0.00	0.00
16,200.033	90.00	179.690	10,430.006	-5,287.179	854.810	5,351.494	0.00	0.00	0.00
16,300.033	90.00	179.690	10,430.007	-5,387.177	855.350	5,450.838	0.00	0.00	0.00
16,400.033	90.00	179.690	10,430.007	-5,487.176	855.891	5,550.182	0.00	0.00	0.00
16,500.033	90.00	179.690	10,430.008	-5,587.175	856.432	5,649.526	0.00	0.00	0.00
16,600.033	90.00	179.690	10,430.009	-5,687.173	856.973	5,748.870	0.00	0.00	0.00
16,700.034	90.00	179.690	10,430.010	-5,787.172	857.513	5,848.214	0.00	0.00	0.00
16,800.034	90.00	179.690	10,430.010	-5,887.171	858.054	5,947.558	0.00	0.00	0.00
16,900.034	90.00	179.690	10,430.011	-5,987.170	858.595	6,046.902	0.00	0.00	0.00
17,000.034	90.00	179.690	10,430.012	-6,087.168	859.136	6,146.246	0.00	0.00	0.00
17,100.034	90.00	179.690	10,430.013	-6,187.167	859.676	6,245.590	0.00	0.00	0.00
17,200.035	90.00	179.690	10,430.014	-6,287.166	860.217	6,344.934	0.00	0.00	0.00
17,300.035	90.00	179.690	10,430.014	-6,387.165	860.758	6,444.278	0.00	0.00	0.00
17,400.035	90.00	179.690	10,430.015	-6,487.163	861.298	6,543.622	0.00	0.00	0.00
17,500.035	90.00	179.690	10,430.016	-6,587.162	861.839	6,642.966	0.00	0.00	0.00
17,600.035	90.00	179.690	10,430.017	-6,687.161	862.380	6,742.310	0.00	0.00	0.00
17,700.036	90.00	179.690	10,430.017	-6,787.160	862.921	6,841.654	0.00	0.00	0.00
17,800.036	90.00	179.690	10,430.018	-6,887.158	863.461	6,940.998	0.00	0.00	0.00
17,900.036	90.00	179.690	10,430.019	-6,987.157	864.002	7,040.342	0.00	0.00	0.00
18,000.036	90.00	179.690	10,430.020	-7,087.156	864.543	7,139.686	0.00	0.00	0.00
18,084.896	90.00	179.690	10,430.020	-7,172.014	865.002	7,223.989	0.00	0.00	0.00

## EOG Resources


## Planning Report



<b>Database:</b>	EDM	<b>Local Co-ordinate Reference</b>	Well #506H
<b>Company:</b>	EOG Resources - Midland	<b>TVD Reference:</b>	kb = 25' @ 3377.007ft
<b>Project:</b>	Lea County, NM (NAD 83 NME)	<b>MD Reference:</b>	kb = 25' @ 3377.007ft
<b>Site:</b>	Almost Eddy 30 Fed Com	<b>North Reference:</b>	Grid
<b>Well:</b>	#506H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	OH		
<b>Design:</b>	Plan #0.1 RT		

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
KOP(Almost Eddy 30 Fe - plan hits target center - Point	0.00	0.000	9,952.519	592.001	824.002	401,100.80	733,568.46	32.101182	-103.712537
FTP(Almost Eddy 30 Fe - plan hits target center - Point	0.00	0.000	10,165.220	542.001	824.002	401,050.80	733,568.46	32.101045	-103.712538
PBHL(Almost Eddy 30 F - plan hits target center - Point	0.00	0.000	10,430.020	-7,172.014	865.002	393,336.79	733,609.46	32.079840	-103.712549







Azimuths to Grid North  
True North: -0.33°  
Magnetic North: 6.38°

Magnetic Field  
Strength: 47501.0nT  
Dip Angle: 59.80°  
Date: 7/16/2020  
Model: IGRF2020

To convert a Magnetic Direction to a Grid Direction, Add 6.38°  
To convert a Magnetic Direction to a True Direction, Add 6.71° East  
To convert a True Direction to a Grid Direction, Subtract 0.33°

Lea County, NM (NAD 83 NME)

Almost Eddy 30 Fed Com #505H

Plan #0.1 RT

PROJECT DETAILS: Lea County, NM (NAD 83 NME)

Geodetic System: US State Plane 1983  
Datum: North American Datum 1983  
Ellipsoid: GRS 1980  
Zone: New Mexico Eastern Zone  
System Datum: Mean Sea Level


WELL DETAILS: #505H			
		3352.0	
kb = 25' @ 3377.0usft			
Northing	Easting	Latitude	Longitude
400482.00	732723.00	32.0994965°N	103.7152739°W

SECTION DETAILS										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1170.0	0.00	0.00	1170.0	0.0	0.0	0.00	0.00	0.0	
3	1534.9	7.30	25.89	1533.9	20.9	10.1	2.00	25.89	-20.4	
4	6542.7	7.30	25.89	6501.1	593.1	287.9	0.00	0.00	-578.8	
5	6907.5	0.00	0.00	6865.0	614.0	298.0	2.00	180.00	-599.2	
6	9995.0	0.00	0.00	9952.5	614.0	298.0	0.00	0.00	-599.2	KOP(Almost Eddy 30 Fed Com #505H)
7	10215.5	26.46	180.00	10165.2	564.0	298.0	12.00	180.00	-549.3	FTP(Almost Eddy 30 Fed Com #505H)
8	10745.0	90.00	179.69	10429.9	136.5	299.6	12.00	-0.35	-122.2	
9	18032.7	90.00	179.69	10430.0	-7151.0	339.0	0.00	0.00	7159.0	PBHL(Almost Eddy 30 Fed Com #505H)

CASING DETAILS

No casing data is available

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)					
Name	TVD	+N/-S	+E/-W	Northing	Easting
KOP(Almost Eddy 30 Fed Com #505H)	9952.5	614.0	298.0	401096.00	733021.00
FTP(Almost Eddy 30 Fed Com #505H)	10165.2	564.0	298.0	401046.00	733021.00
PBHL(Almost Eddy 30 Fed Com #505H)	10430.0	-7151.0	339.0	393331.00	733062.00





## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>EOG RESOURCES</b>
<b>LEASE NO.:</b>	<b>NMNM112935</b>
<b>WELL NAME &amp; NO.:</b>	<b>ALMOST EDDY 30 FED COM 501H – 509H</b>
<b>LOCATION:</b>	<b>Section 30, T.25 S., R.32 E., NMPM</b>
<b>COUNTY:</b>	<b>Lea County, New Mexico</b>

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

### A. HYDROGEN SULFIDE

1. Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

### B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **1,070** feet (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**
3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification. **Excess cement calculates to 21%, additional cement may be required.**

### C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

**D. SPECIAL REQUIREMENT (S)****Communitization Agreement**

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

**JJP03152021****GENERAL REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig



- Notify the BLM when moving in and removing the Spudder Rig.
  - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
  - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
  3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

**B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.

- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
  - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall

have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

## **Hydrogen Sulfide Plan Summary**

- A. All personnel shall receive proper H<sub>2</sub>S training in accordance with Onshore Order III.C.3.a.
- B. Briefing Area: two perpendicular areas will be designated by signs and readily accessible.
- C. Required Emergency Equipment:

- Well control equipment
  - a. Flare line 150' from wellhead to be ignited by flare gun.
  - b. Choke manifold with a remotely operated choke.
  - c. Mud/gas separator

- Protective equipment for essential personnel.

Breathing apparatus:

- a. Rescue Packs (SCBA) — 1 unit shall be placed at each breathing area, 2 shall be stored in the safety trailer.
- b. Work/Escapes packs — 4 packs shall be stored on the rig floor with sufficient air hose not to restrict work activity.
- c. Emergency Escape Packs — 4 packs shall be stored in the doghouse for emergency evacuation.

Auxiliary Rescue Equipment:

- a. Stretcher
- b. Two OSHA full body harness
- c. 100 ft 5/8 inch OSHA approved rope
- d. 1-20# class ABC fire extinguisher

- H<sub>2</sub>S detection and monitoring equipment:

The stationary detector with three sensors will be placed in the upper dog house if equipped, set to visually alarm @ 10 ppm and audible @ 14 ppm. Calibrate a minimum of every 30 days or as needed. The sensors will be placed in the following places: Rig floor / Bell nipple / End of flow line or where well bore fluid is being discharged.

(Gas sample tubes will be stored in the safety trailer)

- Visual warning systems.
  - a. One color code condition sign will be placed at the entrance to the site reflecting the possible conditions at the site.
  - b. A colored condition flag will be on display, reflecting the current condition at the site at the time.
  - c. Two wind socks will be placed in strategic locations, visible from all angles.

**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

- **Mud program:**  
The mud program has been designed to minimize the volume of H<sub>2</sub>S circulated to surface. The operator will have the necessary mud products to minimize hazards while drilling in H<sub>2</sub>S bearing zones.
- **Metallurgy:**  
All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H<sub>2</sub>S service.
- **Communication:**  
Communication will be via cell phones and land lines where available.

**EOG RESOURCES, INC.  
ALMOST EDDY 30 FED COM #506H**

**Emergency Assistance Telephone List**

**PUBLIC SAFETY:** **911 or**

Lea County Sheriff's Department	(575) 396-3611
Rod Coffman	
Fire Department:	
Carlsbad	(575) 885-3125
Artesia	(575) 746-5050
Hospitals:	
Carlsbad	(575) 887-4121
Artesia	(575) 748-3333
Hobbs	(575) 392-1979
Dept. of Public Safety/Carlsbad	(575) 748-9718
Highway Department	(575) 885-3281
New Mexico Oil Conservation	(575) 476-3440
U.S. Dept. of Labor	(575) 887-1174

**EOG Resources, Inc.**

EOG / Midland	Office (432) 686-3600
---------------	-----------------------

**Company Drilling Consultants:**

Jett Dueitt	Cell (432) 230-4840
Blake Burney	

**Drilling Engineer**

Steve Munsell	Office (432) 686-3609
	Cell (432) 894-1256

**Drilling Manager**

Aj Dach	Office (432) 686-3751
	Cell (817) 480-1167

**Drilling Superintendent**

Jason Townsend	Office (432) 848-9209
	Cell (210) 776-5131

**H&P Drilling**

H&P Drilling	Office (432) 563-5757
H&P 415 Drilling Rig	Rig (432) 230-4840

**Tool Pusher:**

Johnathan Craig	Cell (817) 760-6374
Brad Garrett	

**Safety**

Brian Chandler (HSE Manager)	Office (432) 686-3695
	Cell (817) 239-0251



**District I**

1625 N. French Dr., Hobbs, NM 88240  
Phone:(575) 393-6161 Fax:(575) 393-0720

**District II**

811 S. First St., Artesia, NM 88210  
Phone:(575) 748-1283 Fax:(575) 748-9720

**District III**

1000 Rio Brazos Rd., Aztec, NM 87410  
Phone:(505) 334-6178 Fax:(505) 334-6170

**District IV**

1220 S. St Francis Dr., Santa Fe, NM 87505  
Phone:(505) 476-3470 Fax:(505) 476-3462

**State of New Mexico**  
**Energy, Minerals and Natural Resources**  
**Oil Conservation Division**  
**1220 S. St Francis Dr.**  
**Santa Fe, NM 87505**

CONDITIONS

Action 27367

**CONDITIONS**

Operator: EOG RESOURCES INC P.O. Box 2267 Midland, TX 79702	OGRID: 7377
	Action Number: 27367
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

**CONDITIONS**

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	6/11/2021
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	6/11/2021