U.S. Department of the Interior BUREAU OF LAND MANAGEMENT		Sundry Print Report 07/29/2021
Well Name: WTG FED COM	Well Location: T26S / R29E / SEC 27 / NENW /	County or Parish/State:
Well Number: 232H	Type of Well: CONVENTIONAL GAS WELL	Allottee or Tribe Name:
Lease Number: NMNM38636	Unit or CA Name:	Unit or CA Number:
US Well Number: 3001548296	Well Status: Approved Application for Permit to Drill	Operator: TAP ROCK OPERATING LLC

Notice of Intent

Type of Submission: Notice of Intent

Date Sundry Submitted: 07/07/2021

Type of Action Other Time Sundry Submitted: 04:41

Date proposed operation will begin: 07/07/2021

Procedure Description: Tap Rock would like to alter the casing plan for the WTG Fed Com 232H. Tap Rock is requesting permission to: Run one of the two options listed in the attached drill plan - A three or four string design. Alter the second intermediate string from 7.625 inch 29.7 lb P-110 W-513 to 7.625 inch 29.7 P-110 W-441 casing. Casing spec has been attached. Alter the production casing string from 5.5 inch 20 lb P-110 TXP by 5.0 inch 18 lb P-110 W-521 to 5.5 inch 20 lb P-110 TXP by 5.5 inch 20 lb P-110 W-441 casing. Casing spec has been attached. Tap Rock would also like to have the option of running a DV tool during cementing operations. If no DV tool is ran, we would like to cement the intermediate section in a single stage.

Surface Disturbance

Is any additional surface disturbance proposed?: No

NOI Attachments

Procedure Description

Tap_Rock_Operating___WTG_Fed_Com_232H___Plan_1_RPT_20210707162126.pdf

5.5_20_P110_TXP_20210707162112.pdf

5.5_20_P110_IC_W441_20210707162112.pdf

7.625_29.7_P110_IC_W441_20210707162112.pdf

WTG_Fed_Com_232H_APD_6.21.21_20210707162104.pdf

Received by OCD: 7/29/2021 3:43:46 PM Well Name: WTG FED COM	Well Location: T26S / R29E / SEC 27 / NENW /	County or Parish/State: Page 2	of 1
Well Number: 232H	Type of Well: CONVENTIONAL GAS WELL	Allottee or Tribe Name:	
Lease Number: NMNM38636	Unit or CA Name:	Unit or CA Number:	
US Well Number: 3001548296	Well Status: Approved Application for Permit to Drill	Operator: TAP ROCK OPERATING LLC	

Operator Certification

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a submission of Form 3160-5 or a Sundry Notice.

Operator Electronic Signature: BILL RAMSEY
Name: TAP ROCK OPERATING LLC
Title: Regulatory Analyst
Street Address: 523 PARK POINT DRIVE SUITE 200
City: GOLDEN State: CO
Phone: (720) 360-4028
Email address: BRAMSEY@TAPRK.COM

State:

Field Representative

Representative Name: Street Address: City: Phone: Email address:

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS BLM POC Phone: 5752342234 Disposition: Approved Signature: Chris Walls

BLM POC Title: Petroleum Engineer BLM POC Email Address: cwalls@blm.gov Disposition Date: 07/29/2021

Zip:

Signed on: JUL 07, 2021 04:41 PM

Received by OCD: 7/29/2021 3:43:46 PM

Tenaris





Coupling	Pipe Body
Grade: P110-IC	Grade: P110-IC
Body: White	1st Band: White
1st Band: -	2nd Band: Pale Green
2nd Band: -	3rd Band: -
3rd Band: -	4th Band: -
	5th Band: -
	6th Band: -

Outside Diameter	7.625 in.	Wall Thickness	0.375 in.	Grade	P110-IC
Min. Wall Thickness	90.00 %	Drift	API Standard	Туре	Casing
Connection OD Option	REGULAR				

Pipe Body Data

Geometry			
Nominal OD	7.625 in.	Wall Thickness	0.375 in.
Nominal Weight	29.70 lb/ft	Plain End Weight	29.06 lb/ft
Drift	6.750 in.	OD Tolerance	API
Nominal ID	6.875 in.		

Performance

Body Yield Strength	940 x1000 lb
Min. Internal Yield Pressure	9740 psi
SMYS	110,000 psi
Collapse Pressure	7360 psi

Connection Data

Geometry	
Connection OD	7.900 in.
Coupling Length	8.666 in.
Connection ID	6.875 in.
Make-up Loss	3.750 in.
Threads per inch	3.43
Connection OD Option	Regular

Performance	
Tension Efficiency	75 %
Joint Yield Strength	705 x1000 lb
Internal Pressure Capacity	9740 psi
Compression Efficiency	75 %
Compression Strength	705 x1000 lb
Max. Allowable Bending	49 °/100 ft
External Pressure Capacity	7360 psi

Make-Up Torques	
Minimum	22,000 ft-Ib
Optimum	23,000 ft-Ib
Maximum	27,000 ft-Ib
Operation Limit Torques	
Operating Torque	37,000 ft-Ib
Yield Torque	43,000 ft-lb
Buck-On	
Minimum	26,000 ft-Ib
Maximum	27,000 ft-Ib

Notes

For the lastest performance data, always visit our website: www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information –if any-provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information his document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com . ©Tenaris 2021.All rights reserved.

Data Sheet

TH DS-19.0478 23 October 2019

Rev 01

5.500" 20.00 lb/ft P110-IC TenarisHydril Wedge 441™

PIPE BODY DATA						
GEOMETRY						
Nominal OD	5.500 in.	Nominal Weight	20.00 lbs/ft	Standard Drift Diameter	4.653 in.	
Nominal ID	4.778 in.	Wall Thickness	0.361 in.	Special Drift Diameter	N/A	
Plain End Weight	19.83 lbs/ft					
PERFORMANCE						
Body Yield Strength	641 x 1000 lbs	Internal Yield	12640 psi	Collapse	12100 psi	

CONNECTION DATA							
GEOMETRY							
Connection OD	5.852 in.	Connection ID	4.778 in.	Make-up Loss	3.780 in.		
Coupling Length	8.214 in.	Threads per in.	Threads per in. 3.40				
		PERFORMA	NCE				
Tension Efficiency	81.5%	Joint Yield Strength	522 x 1000 lbs	Internal Yield	12640 psi		
Compression Efficiency	81.5%	Compression Strength	522 x 1000 lbs	Collapse	12100 psi		
Bending	75 °/100 ft						
		MAKE-UP TO	RQUES				
Minimum	14000 ft-lbs	Optimum	15000 ft-lbs	Maximum	18000 ft-lbs		
		BUCK-ON TO	RQUES				
Minimum	21600 ft-lbs			Maximum	23100 ft-lbs		
		OPERATIONAL LIM	IT TORQUES				
Operating Torque	Ie 25000 ft-lbs Yield Torque 29000 ft-lbs						

*If you need to use torque values that are higher than the maximum indicated, please contact a local Tenaris technical sales representative

.

5.5", 20#, P-110, TXP connection (modified buttress connection that provides a torque rating of nearly 24000ft-lbs)

TXP® BTC						SHARI				
Q Q	Outside 5,500 in Diameter		Outside 5.500 in. Mi Diameter Th		Min. Wall Thickness	87.5%	87.5%		Clear Filters	
	Wall 0 Thickness).361 in.	Drift Type	API Standard Casing		v	Request Info			
	Grade	<u>P110</u>	Connection OD Option	REGULAR		 	NFORMATION Blanking Dimensions Connection's Page Brochure			
						>	Datasheet Manual			
	GEOMETRY	JAIA								
	Nominal OD		5.500 in.	Nominal Weight	20 lbs/ft	Drift	4.653 in.			
	Nominal ID		4.778 in.	Wall Thickness	0.361 in.	Plain End Weight	19.83 lbs/ft			
	OD Tolerance		API							
	PERFORMAN	NCE								
	Body Yield Str	rength	641 x1000 lbs	Internal Yield	12640 psi	SMYS	110000 psi			
0	Collapse		11100 psi							
3	CONNECTIO	N DATA								
0	GEOMETRY									
	Connection O	D	6 .100 in.	Coupling Length	9.450 in.	Connection ID	4.766 in.			
	Make-up Loss	\$	4.204 in.	Threads per in	5	Connection OD Option	REGULAR			
	PERFORMAN	NCE								
	Tension Efficie	ency	100.0 %	Joint Yield Strength	641.000 ×1000 lbs	Internal Pressure Capacity ^[1]	12640.000 psi			
	Compression Efficiency		100 %	Compression Strength	641.000 ×1000 lbs	Max. Allowable Bending	92 °/100 ft			
	External Press Capacity	sure	11100.000 psi							
	MAKE-UP TO	RQUES								
	Minimum		11270 ft-Ibs	Optimum	12520 ft-Ibs	Maximum	13770 ft-lbs			
	OPERATION	LIMIT TO	RQUES							
	Operating Tor	que	21500 ft-lbs	Yield Torque	23900 ft-lbs					



Elevation above Sea Level: 2886'

DRILLING PROGRAM

1. Estimated Tops

Formation	TVD	MD	Lithologies	Bearing
Quaternary Deposits	0	0	Surface	None
Rustler Anhydrite	685	685		Salt
Salado	1180	1182	Salt	Salt
Base Salt	2730	2740		Salt
Lamar	2935	2946	Limestone	None
Bell Canyon	2970	2982	Sandstone	Hydrocarbons
Cherry Canyon	3870	3887	Sandstone	Hydrocarbons
Brushy Canyon	5085	5108	Sandstone	Hydrocarbons
Bone Spring	6695	6720	Limestone	Hydrocarbons
1st Bone Spring	7600	7625	Sandstone	Hydrocarbons
2nd Bone Spring	7875	7900	Sandstone	Hydrocarbons
3rd Bone Spring	8850	8875	Sandstone	Hydrocarbons
КОР	10332	10,356	Sandstone	Hydrocarbons
Wolfcamp	9800	9,825	Shale	Hydrocarbons
TD	10854	18071	Shale	Hydrocarbons

2. Notable Zones

Wolfcamp is the target formation.

3. Pressure Control

Pressure Control Equipment (See Schematics):

A 15,000', 5,000 psi BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram, and 1 annular preventer will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams. Also present will be an accumulator that meets the requirements of Onshore Order #2 for the pressure rating of the BOP stack. A rotating head will also be installed as needed. BOP will be inspected and operated as recommended in Onshore Order #2. A top drive check valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position. The wellhead will be a multi-bowl speed head.

BOP Test procedure will be as follows:

After surface casing is set and the BOP is nippled up, the BOP pressure tests will be made with a third party tester to 250 psi low, 5000 psi high, and the annular preventer will be tested to 2,500 psi. The BOP will be tested in this manner after nipple-up if any break of the stack occurs.

Variance Requests:

Tap Rock requests a variance to run a multi-bowl speed head for setting the Intermediate 1, Intermediate 2, and Production Strings. Tap Rock requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Tap Rock requests a variance to have the option of batch drilling this well with other wells on the same pad. In the event that this well is batch drilled, after drilling surface, 1st intermediate, and 2nd intermediate hole sections and cementing 2nd intermediate casing, a 10M dry hole cap with bleed off valve will be installed. The rig will then walk to another well on the pad. When the rig returns to this well and BOPs are installed, the operator will perform a full BOP test.

Tap Rock requests approval to possibly utilize a spudder rig to drill and set casing for the surface interval on this well. The spudder rig will be possibly utilized in order to reduce cost and save time. The wellhead will be installed and tested as soon as the surface casing is cut off per the existing COAs. A blind flange with the same pressure rating as the wellhead will be installed on the well. Once the spudder rig is removed, Tap Rock will secure the wellhead area by placing a guard rail around the cellar. Pressure will be monitored and a means for intervention will be maintained while the drilling rig is not over the well. Spudder rig operations are expected to take 2-3 days per well. Three wells on the pad will have surface casing set by the spudder rig as a part of this operation. The BLM will be notified 24 hours prior to commencing spudder rig operations. Within 90 days of the departure of the spudder rig, drilling operations will recommence on these wells. This rig will have a BOP stack equal or greater to the pressure rating required in the COAs. The BLM will be notified 24 hours before the larger rig moves on the pre-set wells. Tap Rock will have supervision on the spudder rig to ensure compliance with all BLM and NMOCD regulations.

If a DV tool is ran, the depth will be adjusted depending on current hole conditions. Cement volumes will be adjusted proportionally. The DV tool will be set a minimum of 50' below the previous casing shoe and a maximum of 200' above the current casing shoe. If cement is not circulated to surface on the 1st cement job, the 2nd stage will be pumped as planned. If cement does not return to surface on the 2nd stage the BLM will be notified immediately.

4. Casing & Cement

All Casing will be new.

Section	Hole Size	Casing Size	Standard	Tapered	Top MD	Bottom MD	Top TVD	BTM TVD	Grade	Weight	Thread	Collapse	Burst	Tension
Surface	17.5	13.375	API	No	0	760	0	760	J-55	54.5	BUTT	1.13	1.15	1.6
1st Intermediate	12.25	9.625	API	No	0	2996	0	2985	J-55	40	BUTT	1.13	1.15	1.6
2nd Intermediate	8.75	7.625	API	No	0	2696	0	2685	P-110	29.7	BUTT	1.13	1.15	1.6
2nd Intermediate	8.75	7.625	NON API	Yes	2696	10256	2685	10232	P-110	29.7	W441	1.13	1.15	1.6
Production	6.75	5.5	NON API	No	0	10056	0	10032	P-110	20	TXP	1.13	1.15	1.6
Production	6.75	5.5	NON API	No	10056	18071	10032	10854	P-110	20	W441	1.13	1.15	1.6

Faction	Dr	illed Interv	/al	Casing	Standard	Casing Set Depths					Casing Details					
Section	Hole Size	Тор	Btm	Size	Stanuaru	Tapereu	Top MD	Bottom MD	Top TVD	BTM TVD	Grade	Weight	Thread	Collapse	Burst	Tension
Surface	17.5	0	770	13.375	API	No	0	760	0	760	J-55	54.5	BUTT	1.13	1.15	1.6
Intermediate	9.875	770	4500	7.625	API	No	0	4200	0	4177	P-110	29.7	BUTT	1.13	1.15	1.6
Interneulate	8.75	4500	10266	7.625	NON API	Yes	4200	10256	4177	10232	P-110	29.7	W441	1.13	1.15	1.6
Production	6.75	10200	10071	5.5	NON API	No	0	10056	0	10032	P-110	20	TXP	1.13	1.15	1.6
Production	6.75	10200	100/1	5.5	NON API	No	10056	18071	10032	10854	P-110	20	W441	1.13	1.15	1.6

***OPTION TO RUN 3 STRING OR 4 STRING DESIGN**

Name	Туре	Top MD	Sacks	Yield	Cu. Ft	Weight	Excess	Cement	Additives
Surface	Lead	0	543	1.65	896	13.5	100%	С	5% NCI + LCM
Surrace	Tail	641	361	1.35	487	14.8	100%	С	5% NCI + LCM
1 at lator modiate	Lead	0	568	2.18	1239	12.7	65%	С	Bentonite + 1% CaCL2 + 8% NaCl + LCM
1st intermediate	Tail	2397	233	1.33	310	14.8	65%	С	5% NaCl + LCM
2nd Interne edicte	Lead	2696	310	2.87	890	11.5	35%	TXI	Fluid Loss + Dispersant + Retarder + LCM
	Tail	9256	87	1.56	136	13.2	35%	Н	Fluid Loss + Dispersant + Retarder + LCM
Production	Tail	9756	508	1.71	868	14.2	25%	Н	Fluid Loss + Dispersant + Retarder + LCM

Name	e	Туре	Top MD	Sacks	Yield	Cu. Ft	Weight	Excess	Cement	Additives
Surfa		Lead	0	543	1.65	896	13.5	100%	С	5% NCI + LCM
Surrac	le.	Tail	641	361	1.35	487	14.8	100%	С	5% NCI + LCM
	Stage 1	Lead	0	993	2.4	2383	11.5	65%	С	Fluid Loss + Dispersant + Retarder + LCM
Internetiste	Stage 1	Tail	9256	106	1.56	166	13.2	65%	С	Fluid Loss + Dispersant + Retarder + LCM
Intermediate	Stage 2	Primary	0	749	2.4	1799	11.5	65%	С	Bentonite + 1% CaCL2 + 8% NaCl + LCM
	DVT	50	85							
Product	tion	Primary	9756	508	1.71	868	14.2	25%	Н	Fluid Loss + Dispersant + Retarder + LCM
				KODTIO				NECEC		

OPTION TO RUN DV TOOL IF NECESSARY

5. Mud Program

Name	Тор	Bottom	Туре	Mud Weight	Visc	Fluid Loss
Surface	0	760	FW Spud Mud	8.30	28	NC
Intermediate	760	2996	Brine Water	10.00	30-32	NC
Intermediate 2	2996	10256	FW/Cut Brine	9.00	30-32	NC
Production	10256	18071	Oil Base Mud	11.50	50-70	<10

Name	Тор	Bottom	Туре	Mud Weight	Visc	Fluid Loss
Surface	0	760	FW Gel	8.30	28	NC
Intermediate	760	10266	DBE/Cut Brine	9.00	30-32	NC
Production	10266	18071	Oil Base Mud	11.50	55-75	<10

.



Electronic Pason mud monitor system complying with Onshore Order 1 will be used. All necessary mud products (e. g., barite, cedar bark) for weight addition and fluid loss control will always be on site. Mud program is subject to change due to hole conditions. A closed loop system will be used.

6. Cores, Tests, & Logs

- Electric Logging Program: No open-hole logs are planned at this time for the pilot hole.
- GR will be collected while drilling through the MWD tools from 9.625" casing shoe to TD.
- A 2-person mud logging program will be used from 9.625" casing shoe to TD.
- No DSTs or cores are planned at this time.
- CBL w/ CCL from as far as gravity will let it fall to TOC.

7. Down Hole Conditions

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is \approx 6,490 psi. Expected bottom hole temperature is \approx 170° F.

Tap Rock does not anticipate that there will be enough H2S from the surface to the Wolfcamp formations to meet the BLM's Onshore Order 6 requirements for the submission of an "H2S Drilling Operation Plan" or "Public Protection Plan" for drilling and completing this well. Tap Rock has an H2S safety package on all wells and an "H2S Drilling Operations Plan" is attached. Adequate flare lines will be installed off the mud/gas separator where gas may be safely flared. All personnel will be familiar with all aspects of safe operation of equipment being used.

8. <u>Other</u>

Road and location construction will begin after BLM approval of APD. Anticipated spud date as soon as approved. Drilling expected to take 30 days. If production casing is run an additional 60 days will be required to complete and construct surface facilities.



5,000 psi BOP Stack









Multi-bowl Wellhead





10M Choke Layout



District I 1625 N. French Dr., Hobbs, NM 88240 Phone:(575) 393-6161 Fax:(575) 393-0720 District II

811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone: (505) 476-3470 Fax: (505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

CONDITIONS

Operator:	OGRID:
TAP ROCK OPERATING, LLC	372043
523 Park Point Drive	Action Number:
Golden, CO 80401	38827
	Action Type:
	[C-103] NOI Change of Plans (C-103A)
	•

CONDITIONS

Created By	Condition	Condition Date
jagarcia	None	8/6/2021

CONDITIONS

Page 14 of 14

Action 38827