

Form 3160-3
(June 2015)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

5. Lease Serial No. NMNM16104	
6. If Indian, Allottee or Tribe Name	
7. If Unit or CA Agreement, Name and No.	
8. Lease Name and Well No. RIVERBEND 11-14 FEDERAL COM 16H	
9. API Well No. 30-015-49511	
10. Field and Pool, or Exploratory PURPLE SAGE/PURPLE SAGE WOLFC/	
11. Sec., T. R. M. or Blk. and Survey or Area SEC 11/T25S/R28E/NMP	
1a. Type of work: ☒ DRILL ☐ REENTER 1b. Type of Well: ☒ Oil Well ☒ Gas Well ☐ Other 1c. Type of Completion: ☐ Hydraulic Fracturing ☒ Single Zone ☐ Multiple Zone	
2. Name of Operator CIMAREX ENERGY COMPANY	
3a. Address 600 N MARIENFELD STREET ST SUITE 600, MIDLAND	3b. Phone No. (include area code) (432) 571-7800
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NENW / 390 FNL / 2029 FWL / LAT 32.150894 / LONG -104.060005 At proposed prod. zone SESW / 330 FSL / 2310 FWL / LAT 32.123736 / LONG -104.059024	
14. Distance in miles and direction from nearest town or post office* 5 miles	12. County or Parish EDDY
13. State	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 390 feet	16. No of acres in lease 640.0
17. Spacing Unit dedicated to this well	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 20 feet	19. Proposed Depth 9975 feet / 19698 feet
20. BLM/BIA Bond No. in file FED: NMB001188	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2967 feet	22. Approximate date work will start* 01/31/2021
23. Estimated duration 30 days	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission)	Name (Printed/Typed) AMITHY CRAWFORD / Ph: (432) 620-1936	Date 11/10/2020
Title Regulatory Analyst		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575) 234-5959	Date 04/13/2022
Title Assistant Field Manager Lands & Minerals		
Office Carlsbad Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

*(Instructions on page 2)

Approval Date: 04/13/2022

Additional Operator Remarks

Location of Well

O, SHL: NENW / 390 FNL / 2029 FWL / TWSP: 25S / RANGE: 28E / SECTION: 11 / LAT: 32.150894 / LONG: -104.060005 (TVD: 0 feet, MD: 0 feet)

PPP: NENW / 390 FNL / 2310 FWL / TWSP: 25S / RANGE: 28E / SECTION: 11 / LAT: 32.150907 / LONG: -104.059098 (TVD: 9690 feet, MD: 9712 feet)

PPP: SENW / 1320 FNL / 2310 FWL / TWSP: 25S / RANGE: 28E / SECTION: 11 / LAT: 32.148333 / LONG: -104.059094 (TVD: 9975 feet, MD: 10750 feet)

BHL: SESW / 330 FSL / 2310 FWL / TWSP: 25S / RANGE: 28E / SECTION: 14 / LAT: 32.123736 / LONG: -104.059024 (TVD: 9975 feet, MD: 19698 feet)

BLM Point of Contact

Name: JORDAN NAVARRETTE

Title: LIE

Phone: (575) 234-5972

Email: jnavarrette@blm.gov

CONFIDENTIAL

Approval Date: 04/13/2022

(Form 3160-3, page 3)

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

LAPI Number 30-0155-49511		Pool Code 98220	Pool Name Purple Sage, Wolfcamp (Gas)
Property Code 321641	Property Name RIVERBEND 11-14 FEDERAL COM		Well Number 16H
Location No. 215099	Operator Name CIMAREX ENERGY CO.		Elevation 2967.0'

"Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	11	25S	28E		390	NORTH	2029	WEST	EDDY

"Bottom Hole Location If Different From Surface


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	14	25S	28E		330	SOUTH	2310	WEST	EDDY

Dedicated Acres 6.40	Joint or Infill	Consolidation Code	Order No.
-------------------------	-----------------	--------------------	-----------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



- = SURFACE HOLE LOCATION
- ◆ = LANDING POINT/FIRST TAKE POINT
- = BOTTOM HOLE LOCATION/
LAST TAKE POINT
- ▲ = SECTION CORNER LOCATED



NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)

"OPERATOR
CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Amithy Crawford 11/09/2020
Signature Date

Amithy Crawford
Printed Name

acrawford@cimarex.com
E-mail Address

"SURVEYOR
CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

MARCH 03, 2017

Date of Survey
Signature and Seal of Professional Surveyor:



Certificate Number:

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: Cimarex Energy Company **OGRID:** 215099 **Date:** 5 / 3 / 2022

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Riverbend 11-14 Fed 16H		C, Sec 11 T25S, R28E	390 FNL/2029 FWL	1540	4700	7000

IV. Central Delivery Point Name: Riverbend 11-14 CDP Sales
[See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Riverbend 11-14 Fed 16H		1/1/2024	5/1/2024	11/1/2024	1/1/2025	1/1/2025

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan

EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices


1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	
Printed Name:	Sarah Jordan
Title:	Regulatory Analyst
E-mail Address:	sarah.jordan@coterra.com
Date:	5/3/2022
Phone:	432/620-1909
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)	
Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

From State of New Mexico, Natural Gas Management Plan

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

XEC Standard Response

Standard facility gas process flow begins at the inlet separator. These vessels are designed based off of forecasted rates and residence times in accordance with, and often greater than, API 12J. The separated gas is then routed to an additional separation vessel (ie sales scrubber) in order to extract liquids that may have carried over or developed due to the decrease in pressure. The sales scrubber is sized based on API 521. From the sales scrubber, the gas leaves the facility and enters the gas midstream gathering network.

Cimarex

VII. Operational Practices

Cimarex values the sustainable development of New Mexico's natural resources. Venting and flaring of natural gas is a source of waste in the industry, and Cimarex will ensure that its values are aligned with those of NMOCD. As such, Cimarex plans to take pointed steps to ensure compliance with Subsection A through F of 19.15.27.8 NMAC.

Specifically, below are the steps Cimarex will plan to follow under routine well commissioning and operations.

1. Capture or combust natural gas during drilling operations where technically feasible, using the best industry practices and control technologies.
 - a. All flares during these operations will be a minimum of 100ft away from the nearest surface-hole location.
2. All gas present during post-completion drill-out and flow back will be routed through separation equipment, and, if technically feasible, flare unsellable vapors rather than vent. Lastly, formal sales separator commissioning to process well-stream fluids and send gas to a gas flow line/collection system or use the gas for on-site fuel or beneficial usage, gas as soon as is safe and technically feasible.
3. Cimarex will ensure the flare or combustion equipment is properly sized to handle expected flow rates, ensure this equipment is equipped with an automatic or continuous ignition source, and ensure this equipment is designed for proper combustion efficiency.
4. If Cimarex must flare because gas is not meeting pipeline specifications, Cimarex will limit flaring to <60 days, analyze gas composition at least twice per week, and route gas into a gathering pipeline as soon as pipeline specifications are met.
5. Under routine production operations, Cimarex will not flare/vent unless:
 - a. Venting or flaring occurs due to an emergency or equipment malfunction.
 - b. Venting or flaring occurs as a result of unloading practices, and an operator is onsite (or within 30 minutes of drive time and posts contact information at the wellsite) until the end of unloading practice.
 - c. The venting or flaring occurs during automated plungerlift operations, in which case the Cimarex operator will work to optimize the plungerlift system to minimize venting/flaring.
 - d. The venting or flaring occurs during downhole well maintenance, in which case Cimarex will work to minimize venting or flaring operations to the extent that it does not pose a risk to safe operations.
 - e. The well is an exploratory well, the division has approved the well as an exploratory well, venting or flaring is limited to 12 months, as approved by the division, and venting/flaring does not cause Cimarex to breach its State-wide 98% gas capture requirement.
 - f. Venting or flaring occurs because the stock tanks or other low-pressure vessels are being gauged, sampled, or liquids are being loaded out.
 - g. The venting or flaring occurs because pressurized vessels are being maintained and are being blown-down or depressurized.
 - h. Venting or flaring occurs as a result of normal dehydration unit operations.

- i. Venting or flaring occurs as a result of bradenhead testing.
 - j. Venting or flaring occurs as a result of normal compressor operations, including general compressor operations, compressor engines and turbines.
 - k. Venting or flaring occurs as a result of a packer leakage test.
 - l. Venting or flaring occurs as a result of a production test lasting less than 24 hours unless otherwise approved by the division.
 - m. Venting or flaring occurs as a result of new equipment commissioning and is necessary to purge impurities from the pipeline or production equipment.
6. Cimarex will maintain its equipment in accordance with its Operations and Maintenance Program, to ensure venting or flaring events are minimized and that equipment is properly functioning.
7. Cimarex will install automatic tank gauging equipment on all production facilities constructed after May 25, 2021, to ensure minimal emissions from tank gauging practices.
8. By November 25, 2022, all Cimarex facilities equipped with flares or combustors will be equipped with continuous pilots or automatic igniters, and technology to ensure proper function, i.e. thermocouple, fire-eye, etc...
9. Cimarex will perform AVO (audio, visual, olfactory) facility inspections in accordance with NMOCD requirements. Specifically, Cimarex will:
 - a. Perform weekly inspections during the first year of production, and so long as production is greater than 60 MCFD.
 - b. If production is less than 60 MCFD, Cimarex will perform weekly AVO inspections when an operator is present on location, and inspections at least once per calendar month with at least 20 calendar days between inspections.
10. Cimarex will measure or estimate the volume of vented, flared or beneficially used natural gas, regardless of the reason or authorization for such venting or flaring.
11. On all facilities constructed after May 25, 2021, Cimarex will install metering where feasible and in accordance with available technology and best engineering practices, in an effort to measure how much gas could have been vented or flared.
 - a. In areas where metering is not technically feasible, such as low-pressure/low volume venting or flaring applications, engineering estimates will be used such that the methodology could be independently verified.
12. Cimarex will fulfill the division's requirements for reporting and filing of venting or flaring that exceeds 50 MCF in volume or last eight hours or more cumulatively within any 24-hour period.

VIII. Best Management Practices to minimize venting during active and planned maintenance

Cimarex strives to ensure minimal venting occurs during active and planned maintenance activities. Below is a description of common maintenance practices, and the steps Cimarex takes to limit venting exposure.

- **Workovers:**
 - Always strive to kill well when performing downhole maintenance.
 - If vapors or trapped pressure is present and must be relieved then:
 - Initial blowdown to production facility:
 - Route vapors to LP flare if possible/applicable
 - Blowdown to portable gas buster tank:
 - Vent to existing or portable flare if applicable.
- **Stock tank servicing:**
 - Minimize time spent with thief hatches open.
 - When cleaning or servicing via manway, suck tank bottoms to ensure minimal volatiles exposed to atmosphere.
 - Connect vacuum truck to low pressure flare while cleaning bottoms to limit venting.
 - Isolate the vent lines and overflows on the tank being serviced from other tanks.
- **Pressure vessel/compressor servicing and associated blowdowns:**
 - Route to flare where possible.
 - Blow vessel down to minimum available pressure via pipeline, prior to venting vessel.
 - Preemptively changing anodes to reduce failures and extended corrosion related servicing.
 - When cleaning or servicing via manway, suck vessel bottoms to ensure minimal volatiles exposed to atmosphere.
- **Flare/combustor maintenance:**
 - Minimize downtime by coordinating with vendor and Cimarex staff travel logistics.
 - Utilizing preventative and predictive maintenance programs to replace high wear components before failure.
 - Because the flare/combustor is the primary equipment used to limit venting practices, ensure flare/combustor is properly maintained and fully operational at all times via routine maintenance, temperature telemetry, onsite visual inspections.

The Cimarex expectation is to limit all venting exposure. Equipment that may not be listed on this document is still expected to be maintained and associated venting during such maintenance minimized.



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

04/25/2022

APD ID: 10400065021

Submission Date: 11/10/2020

Highlighted data
reflects the most
recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RIVERBEND 11-14 FEDERAL COM

Well Number: 16H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1138846	RUSTLER	2974	450	450	ANHYDRITE	USEABLE WATER	N
1138847	SALADO	1146	1828	1828	ANHYDRITE, SALT	NONE	N
1138848	CASTILE	610	2364	2368	ANHYDRITE, SALT	NONE	N
1138849	BELL CANYON	469	2505	2510	SANDSTONE	NONE	N
1138850	CHERRY CANYON	-501	3475	3487	SANDSTONE	NONE	N
1138851	BRUSHY CANYON	-2191	5165	5185	SANDSTONE	NATURAL GAS, OIL	N
1138852	BONE SPRING	-3175	6149	6169	LIMESTONE	NATURAL GAS, OIL	N
1138868	WOLFCAMP	-6426	9400	9413	SHALE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 2M

Rating Depth: 2450

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13-3/8" surface casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 2000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 2000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 2000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing strings utilizing steel

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RIVERBEND 11-14 FEDERAL COM**Well Number:** 16H

body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_Choke_Diagram_2M3M__20201109135049.pdf

BOP Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_BOP_2M__20201109135055.pdf

Pressure Rating (PSI): 5M**Rating Depth:** 10103

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13-3/8" surface casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi. Slips will be utilized after running and cementing the production casing. After installation of the slips and wellhead on the production casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_5M_Choke_20201109135623.pdf

BOP Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_5M_BOP_8.75_20201109135631.pdf

Pressure Rating (PSI): 5M**Rating Depth:** 19699

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RIVERBEND 11-14 FEDERAL COM**Well Number:** 16H

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13-3/8" surface casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi. Slips will be utilized after running and cementing the production casing. After installation of the slips and wellhead on the production casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_5M_Choke_20201109135659.pdf

BOP Diagram Attachment:

Riverbend_11_14_Fed_Com_16H_5M_BOP_6_20201109135704.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	NON API	N	0	450	0	450	2967	2517	450	OTH ER	48	ST&C	3.8	8.88	BUOY	14.91	BUOY	14.91
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2450	0	2450	2974	517	2450	J-55	36	LT&C	1.54	2.68	BUOY	5.14	BUOY	5.14
3	PRODUCTION	8.75	7.0	NEW	API	N	0	8475	0	8475	2974	-5508	8475	L-80	26	LT&C	1.36	1.83	BUOY	1.98	BUOY	1.98
4	PRODUCTION	8.75	7.0	NEW	API	N	8478	10103	8478	9926	-5511	-6959	1625	L-80	26	BUTT	1.16	1.56	BUOY	16.04	BUOY	16.04
5	COMPLETION SYSTEM	6	4.5	NEW	API	N	8478	19699	8478	9975	-5511	-7008	11221	P-110	11.6	BUTT	1.27	1.8	BUOY	21.13	BUOY	21.13

Casing Attachments

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RIVERBEND 11-14 FEDERAL COM**Well Number:** 16H**Casing Attachments**

Casing ID: 1 **String Type:** SURFACE**Inspection Document:****Spec Document:**

Riverbend_11_14_Fed_Com_16H_Casing_Spec_Sheet_20201109143931.pdf

Tapered String Spec:**Casing Design Assumptions and Worksheet(s):**Riverbend_11_14_Fed_Com_16H_Casing_Assumptions_20201109143942.pdf

Casing ID: 2 **String Type:** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**Riverbend_11_14_Fed_Com_16H_Casing_Assumptions_20201109144009.pdf

Casing ID: 3 **String Type:** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**Riverbend_11_14_Fed_Com_16H_Casing_Assumptions_20201109144200.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RIVERBEND 11-14 FEDERAL COM

Well Number: 16H

Casing Attachments

Casing ID: 4 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Riverbend_11_14_Fed_Com_16H_Casing_Assumptions_20201109144125.pdf

Casing ID: 5 String Type: COMPLETION SYSTEM

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Riverbend_11_14_Fed_Com_16H_Casing_Assumptions_20201109144400.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0	0	0	00

SURFACE	Lead		0	450	91	1.72	13.5	156	33	Class C	Bentonite
SURFACE	Tail		0	450	195	1.34	14.8	261	33	Class C	LCM
INTERMEDIATE	Lead		0	2450	468	1.88	12.9	1.88	49	35:65 (POZ C)	Salt Bentonite

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RIVERBEND 11-14 FEDERAL COM

Well Number: 16H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Tail		0	2450	141	1.36	14.8	191	49	Class C	Retarder
PRODUCTION	Lead		0	1010 3	445	3.64	10.3	1619	25	Tuned Light	LCM
PRODUCTION	Tail		0	1010 3	109	1.3	14.2	141	25	50:50 POZ H	Salt Bentonite Fluid Loss Dispersant SMS
COMPLETION SYSTEM	Lead		8478	1969 9	714	1.3	14.2	928	10	50:50)POZ H	Salt Bentonite Fluid Loss Dispersant SMS

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1010 3	1969 9	OIL-BASED MUD	11	11.5							
0	450	OTHER : Fresh Water	7.83	8.33							
450	2450	SALT SATURATED	9.8	10.3							
2450	1010	OTHER : Cut	8.5	9							

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RIVERBEND 11-14 FEDERAL COM**Well Number:** 16H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
		Based Mud									

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

No DST Planned

List of open and cased hole logs run in the well:

GAMMA RAY LOG,DIRECTIONAL SURVEY,COMPENSATED NEUTRON LOG,

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5965

Anticipated Surface Pressure: 3770

Anticipated Bottom Hole Temperature(F): 169

Anticipated abnormal pressures, temperatures, or potential geologic hazards? YES

Describe:

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

Contingency Plans geohazards description:

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Riverbend_11_14_Fed_Com_16H_H2S_Plan_20201109144949.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RIVERBEND 11-14 FEDERAL COM

Well Number: 16H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Riverbend_11_14_Fed_Com_16H_Directional_Survey_20201109145017.pdf

Riverbend_11_14_Fed_Com_16H_Directional_Survey_AC_Report_20201109145022.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Riverbend_11_14_Fed_Com_16H_Drilling_Plan__20201109145040.pdf

Riverbend_11_14_Fed_Com_16H_Gas_Capture_Plan_20201109145138.pdf

Other Variance attachment:

Riverbend_11_14_Fed_Com_16H_Flex_Hose_20201109145059.pdf

Riverbend_11_14_Federal_Com_16H_Multibowl_20201109145104.pdf

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H

1. Geological Formations

TVD of target 9,975

Pilot Hole TD N/A

MD at TD 19,699

Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	450	Useable Water	
Salado	1828	N/A	
Castille	2364	N/A	
Bell Canyon	2505	N/A	
Cherry Canyon	3475	N/A	
Brushy Canyon	5165	Hydrocarbons	
Bone Spring	6149	Hydrocarbons	
Wolfcamp	9400	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	450	450	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	3.80	8.88	14.91
12 1/4	0	2450	2450	9-5/8"	36.00	J-55	LT&C	1.54	2.68	5.14
8 3/4	0	8478	8478	7"	26.00	L-80	LT&C	1.36	1.83	1.98
8 3/4	8478	10103	9926	7"	26.00	L-80	BT&C	1.16	1.56	16.04
6	8478	19699	9975	4-1/2"	11.60	P-110	BT&C	1.27	1.80	21.13
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H

Question	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	Y

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H

3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	91	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	195	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	468	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	141	14.80	1.36	6.57	9.5	Tail: Class C + Retarder
Production	445	10.30	3.64	22.18		Lead: Tuned Light + LCM
	109	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS
Completion System	714	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

Casing String	TOC	% Excess
Surface	0	33
Intermediate	0	49
Production	2250	25
Completion System	9903	10

Cimarex request the ability to perform casing integrity tests after plug bump of cement job.

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H

4. Pressure Control Equipment

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
BOP Installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
12 1/4		2M	Annular	X	50% of working pressure
			Blind Ram		2M
			Pipe Ram		
			Double Ram	X	
			Other		
8 3/4	13 5/8	5M	Annular	X	50% of working pressure
			Blind Ram		5M
			Pipe Ram	X	
			Double Ram	X	
			Other		
6	13 5/8	5M	Annular	X	50% of working pressure
			Blind Ram		5M
			Pipe Ram	X	
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.				
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.				
	Y	Are anchors required by manufacturer?			

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H

5. Mud Program

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 450'	Fresh Water	7.83 - 8.33	28	N/C
450' to 2450'	Brine Water	9.80 - 10.30	30-32	N/C
2450' to 10103'	Cut Brine or OBM	8.50 - 9.00	27-70	N/C
10103' to 19699'	OBM	11.00 - 11.50	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
X	No logs are planned based on well control or offset log information.
	Drill stem test?
	Coring?

Additional Logs Planned	Interval
-------------------------	----------

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	5965 psi
Abnormal Temperature	No

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H ₂ S is present
	H ₂ S plan is attached

8. Other Facets of Operation**9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.


A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

A solid steel body pack-off will be utilized after running and cementing the production casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

All casing strings will be tested as per Onshore Order No.2 to atleast 0.22 psi/ft or 1,500 whichever is greater and not to exceed 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Cimarex Energy Co., Riverbend 11-14 Federal Com 16H



Schlumberger

Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20 Proposal

Geodetic Report

(Non-Def Plan)



Report Date: October 07, 2020 - 11:43 AM
Client: Cimarex Energy
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Riverbend 11-14 Federal Com #16H / New Slot
Well: Riverbend 11-14 Federal Com #16H
Borehole: Riverbend 11-14 Federal Com #16H
UWI / AP#: Unknown / Unknown
Survey Name: Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20
Survey Date: October 06, 2020
Tort / AHD / DDI / ERD Ratio: 100.935° / 10232.039 ft / 6.310 / 1.026
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 9' 3.21726", W 104° 3' 36.01680"
Location Grid N/E Y/X: N 418737.860 ftUS, E 625927.210 ftUS
CRS Grid Convergence Angle: 0.1455°
Grid Scale Factor: 0.99991729
Version / Patch: 2.10.821.3

Survey / DLS Computation:
Vertical Section Azimuth: Minimum Curvature / Lubinski
Vertical Section Origin: 179.717° (Grid North)
TVD Reference Datum: 0.000 ft, 0.000 ft
TVD Reference Elevation: RKB
Seabed / Ground Elevation: 2990.000 ft above MSL
Magnetic Declination: 2967.000 ft above MSL
Total Gravity Field Strength: 6.889°
Gravity Model: 998.4571 mgn (9.80665 Based)
Total Magnetic Field Strength: GARM
Magnetic Dip Angle: 47736.040 nT
Declination Date: 59.829°
Magnetic Declination Model: October 06, 2020
North Reference: HDGM 2020
Grid Convergence Used: Grid North
Total Corr Mag North->Grid: 0.1455°
Local Coord Referenced To: 6.7432°
Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [390' FNL, 2029' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	100.00	0.00	76.83	100.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	200.00	0.00	76.83	200.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	300.00	0.00	76.83	300.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	400.00	0.00	76.83	400.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	500.00	0.00	76.83	500.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	600.00	0.00	76.83	600.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	700.00	0.00	76.83	700.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	800.00	0.00	76.83	800.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	900.00	0.00	76.83	900.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1000.00	0.00	76.83	1000.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1100.00	0.00	76.83	1100.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1200.00	0.00	76.83	1200.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1300.00	0.00	76.83	1300.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1400.00	0.00	76.83	1400.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1500.00	0.00	76.83	1500.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1600.00	0.00	76.83	1600.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1700.00	0.00	76.83	1700.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1800.00	0.00	76.83	1800.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
Salado (Top Salt)	1828.00	0.00	76.83	1828.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
	1900.00	0.00	76.83	1900.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
Nudge 2"/100'	2000.00	0.00	76.83	2000.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32° 9' 3.22"	W 104° 3' 36.02"
DLS	2100.00	2.00	76.83	2099.98	-0.39	0.40	1.70	2.00	418738.26	625928.91	N 32° 9' 3.22"	W 104° 3' 36.02"
	2200.00	4.00	76.83	2199.84	-1.56	1.59	6.79	2.00	418739.45	625934.00	N 32° 9' 3.23"	W 104° 3' 36.94"
Hold Nudge	2273.38	5.47	76.83	2272.96	-2.91	2.97	12.69	2.00	418740.83	625939.90	N 32° 9' 3.25"	W 104° 3' 35.87"

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Castile (Base Salt)	2300.00	5.47	76.83	2299.46	-3.47	3.55	15.16	0.00	418741.41	625942.37	N 32 9 3.25	W 104 3 35.84
	2364.83	5.47	76.83	2364.00	-4.85	4.96	21.18	0.00	418742.81	625948.38	N 32 9 3.27	W 104 3 35.77
	2400.00	5.47	76.83	2399.01	-5.60	5.72	24.44	0.00	418743.58	625951.65	N 32 9 3.27	W 104 3 35.73
	2500.00	5.47	76.83	2498.55	-7.72	7.89	33.72	0.00	418745.75	625960.92	N 32 9 3.29	W 104 3 35.62
Bel Canyon (Top Delaware)	2506.48	5.47	76.83	2505.00	-7.86	8.03	34.32	0.00	418745.89	625961.52	N 32 9 3.30	W 104 3 35.62
	2600.00	5.47	76.83	2598.10	-9.85	10.06	42.99	0.00	418747.92	625970.20	N 32 9 3.32	W 104 3 35.52
	2700.00	5.47	76.83	2697.64	-11.97	12.23	52.27	0.00	418750.09	625979.48	N 32 9 3.34	W 104 3 35.41
	2800.00	5.47	76.83	2797.19	-14.10	14.40	61.55	0.00	418752.26	625988.75	N 32 9 3.36	W 104 3 35.30
	2900.00	5.47	76.83	2896.73	-16.22	16.57	70.83	0.00	418754.43	625998.03	N 32 9 3.38	W 104 3 35.19
	3000.00	5.47	76.83	2996.28	-18.35	18.74	80.10	0.00	418756.60	626007.31	N 32 9 3.40	W 104 3 35.08
	3100.00	5.47	76.83	3095.82	-20.47	20.91	89.38	0.00	418758.77	626016.58	N 32 9 3.42	W 104 3 34.98
	3200.00	5.47	76.83	3195.37	-22.60	23.09	98.66	0.00	418760.94	626025.86	N 32 9 3.44	W 104 3 34.87
	3300.00	5.47	76.83	3294.91	-24.72	25.26	107.94	0.00	418763.11	626035.14	N 32 9 3.46	W 104 3 34.76
	3400.00	5.47	76.83	3394.46	-26.85	27.43	117.21	0.00	418765.29	626044.41	N 32 9 3.49	W 104 3 34.65
Cherry Canyon	3480.91	5.47	76.83	3475.00	-28.97	29.78	124.72	0.00	418767.04	626051.92	N 32 9 3.50	W 104 3 34.57
	3500.00	5.47	76.83	3494.00	-28.97	29.60	126.49	0.00	418767.46	626053.69	N 32 9 3.51	W 104 3 34.54
	3600.00	5.47	76.83	3593.55	-31.10	31.77	135.77	0.00	418769.63	626062.97	N 32 9 3.53	W 104 3 34.44
	3700.00	5.47	76.83	3693.09	-33.22	33.94	145.05	0.00	418771.80	626072.24	N 32 9 3.55	W 104 3 34.33
	3800.00	5.47	76.83	3792.64	-35.35	36.11	154.32	0.00	418773.97	626081.52	N 32 9 3.57	W 104 3 34.22
	3900.00	5.47	76.83	3892.18	-37.47	38.28	163.60	0.00	418776.14	626090.80	N 32 9 3.59	W 104 3 34.11
	4000.00	5.47	76.83	3991.73	-39.60	40.45	172.88	0.00	418778.31	626100.07	N 32 9 3.61	W 104 3 34.00
	4100.00	5.47	76.83	4091.27	-41.72	42.62	182.16	0.00	418780.48	626109.35	N 32 9 3.63	W 104 3 33.90
	4200.00	5.47	76.83	4190.82	-43.85	44.79	191.43	0.00	418782.65	626118.63	N 32 9 3.66	W 104 3 33.79
	4300.00	5.47	76.83	4290.36	-45.97	46.97	200.71	0.00	418784.82	626127.90	N 32 9 3.68	W 104 3 33.68
	4400.00	5.47	76.83	4389.91	-48.10	49.14	209.99	0.00	418786.99	626137.18	N 32 9 3.70	W 104 3 33.57
	4500.00	5.47	76.83	4489.46	-50.22	51.31	219.27	0.00	418789.16	626146.46	N 32 9 3.72	W 104 3 33.46
	4600.00	5.47	76.83	4589.00	-52.35	53.48	228.54	0.00	418791.33	626155.73	N 32 9 3.74	W 104 3 33.36
	4700.00	5.47	76.83	4688.55	-54.47	55.65	237.82	0.00	418793.50	626165.01	N 32 9 3.76	W 104 3 33.25
	4800.00	5.47	76.83	4788.09	-56.60	57.82	247.10	0.00	418795.68	626174.29	N 32 9 3.78	W 104 3 33.14
	4900.00	5.47	76.83	4887.64	-58.72	59.99	256.38	0.00	418797.85	626183.56	N 32 9 3.80	W 104 3 33.03
	5000.00	5.47	76.83	4987.18	-60.85	62.16	265.65	0.00	418800.02	626192.84	N 32 9 3.83	W 104 3 32.93
Drop to Vertical 2°/100' DLS	5012.88	5.47	76.83	5000.00	-61.12	62.44	266.85	0.00	418800.30	626194.04	N 32 9 3.83	W 104 3 32.91
	5100.00	3.73	76.83	5086.84	-62.68	64.03	273.65	2.00	418801.89	626200.83	N 32 9 3.84	W 104 3 32.83
Brushy Canyon	5178.27	2.16	76.83	5165.00	-63.58	64.95	277.56	2.00	418802.80	626204.74	N 32 9 3.85	W 104 3 32.79
	5200.00	1.73	76.83	5186.72	-63.74	65.12	278.28	2.00	418802.97	626205.46	N 32 9 3.85	W 104 3 32.78
Hold Vertical	5286.25	0.00	76.83	5272.96	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5300.00	0.00	76.83	5286.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5400.00	0.00	76.83	5386.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5500.00	0.00	76.83	5486.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5600.00	0.00	76.83	5586.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5700.00	0.00	76.83	5686.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5800.00	0.00	76.83	5786.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	5900.00	0.00	76.83	5886.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6000.00	0.00	76.83	5986.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6100.00	0.00	76.83	6086.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
Top Bone Spring	6162.29	0.00	76.83	6149.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6200.00	0.00	76.83	6186.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6300.00	0.00	76.83	6286.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6400.00	0.00	76.83	6386.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6500.00	0.00	76.83	6486.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6600.00	0.00	76.83	6586.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6700.00	0.00	76.83	6686.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6800.00	0.00	76.83	6786.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
	6900.00	0.00	76.83	6886.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Top 1st BSPG SS	7000.00	0.00	76.83	6986.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7100.00	0.00	76.83	7086.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7146.29	0.00	76.83	7133.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7200.00	0.00	76.83	7186.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7300.00	0.00	76.83	7286.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7400.00	0.00	76.83	7386.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7500.00	0.00	76.83	7486.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7600.00	0.00	76.83	7586.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7700.00	0.00	76.83	7686.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7800.00	0.00	76.83	7786.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Top 2nd BSPG SS	7888.29	0.00	76.83	7875.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	7900.00	0.00	76.83	7886.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8000.00	0.00	76.83	7986.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8100.00	0.00	76.83	8086.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8200.00	0.00	76.83	8186.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Top 3rd BSPG Card	8273.29	0.00	76.83	8260.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8300.00	0.00	76.83	8286.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8400.00	0.00	76.83	8386.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8500.00	0.00	76.83	8486.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Top Harkey SS	8571.29	0.00	76.83	8556.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8600.00	0.00	76.83	8586.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8700.00	0.00	76.83	8686.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8800.00	0.00	76.83	8786.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	8900.00	0.00	76.83	8886.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9000.00	0.00	76.83	8986.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Top 3rd BSPG SS	9024.29	0.00	76.83	9011.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9100.00	0.00	76.83	9086.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9200.00	0.00	76.83	9186.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9300.00	0.00	76.83	9286.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9400.00	0.00	76.83	9386.71	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Top Wolfcamp KOP - Build 12°/100' DLS	9473.29	0.00	76.83	9400.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
	9478.29	0.00	76.83	9465.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86 W 104	3 32.76
Wolfcamp A1 Shale	9500.00	2.61	179.72	9486.70	-63.54	64.92	279.54	12.00	418802.77	626206.73	N 32 9 3.85 W 104	3 32.76
	9530.40	6.25	179.72	9517.00	-61.19	62.57	279.55	12.00	418800.43	626206.74	N 32 9 3.83 W 104	3 32.76
	9600.00	14.61	179.72	9585.39	-48.60	49.98	279.62	12.00	418787.84	626206.80	N 32 9 3.70 W 104	3 32.76
	9700.00	26.61	179.72	9678.82	-13.47	14.85	279.79	12.00	418752.71	626206.98	N 32 9 3.36 W 104	3 32.76
Wolfcamp A1' Target	9712.58	28.12	179.72	9690.00	-7.69	9.07	279.82	12.00	418746.93	626207.00	N 32 9 3.30 W 104	3 32.76
	9800.00	38.61	179.72	9762.91	40.31	-38.93	280.05	12.00	418698.93	626207.24	N 32 9 2.82 W 104	3 32.76
	9900.00	50.61	179.72	9833.98	110.41	-109.02	280.40	12.00	418628.85	626207.59	N 32 9 2.13 W 104	3 32.76
	10000.00	62.61	179.72	9888.92	193.74	-192.36	280.81	12.00	418545.52	626208.00	N 32 9 1.31 W 104	3 32.76
	10100.00	74.61	179.72	9925.33	286.68	-285.30	281.27	12.00	418452.59	626208.46	N 32 9 0.39 W 104	3 32.75
Build 4°/100' DLS	10103.29	75.00	179.72	9926.19	289.86	-288.47	281.29	12.00	418449.41	626208.47	N 32 9 0.36 W 104	3 32.75
	10200.00	78.87	179.72	9948.05	384.05	-382.66	281.75	4.00	418355.23	626208.94	N 32 8 59.42 W 104	3 32.75
Wolfcamp A2' Marker	10210.28	79.28	179.72	9950.00	394.14	-392.75	281.80	4.00	418345.14	626208.99	N 32 8 59.32 W 104	3 32.75
	10300.00	82.87	179.72	9963.92	482.76	-481.37	282.24	4.00	418256.53	626209.43	N 32 8 58.45 W 104	3 32.75
	10400.00	86.87	179.72	9972.86	582.34	-580.95	282.73	4.00	418156.96	626209.92	N 32 8 57.46 W 104	3 32.75
Landing Point	10478.29	90.00	179.72	9975.00	660.59	-659.20	283.12	4.00	418078.72	626210.30	N 32 8 56.69 W 104	3 32.74
	10500.00	90.00	179.72	9975.00	682.30	-680.91	283.23	0.00	418057.01	626210.41	N 32 8 56.47 W 104	3 32.74
	10600.00	90.00	179.72	9975.00	782.30	-780.91	283.72	0.00	417957.02	626210.91	N 32 8 55.48 W 104	3 32.74

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
NMNM016104 - NMNM013413 Crossing	10700.00	90.00	179.72	9975.00	882.30	-880.91	284.21	0.00	417857.03	626211.40	N 32 8 54.49 W 104 3 32.74	
	10750.20	90.00	179.72	9975.00	932.50	-931.11	284.46	0.00	417806.83	626211.65	N 32 8 54.00 W 104 3 32.74	
	10800.00	90.00	179.72	9975.00	982.30	-980.91	284.71	0.00	417757.04	626211.89	N 32 8 53.50 W 104 3 32.73	
	10900.00	90.00	179.72	9975.00	1082.30	-1080.90	285.20	0.00	417657.05	626212.39	N 32 8 52.51 W 104 3 32.73	
	11000.00	90.00	179.72	9975.00	1182.30	-1180.90	285.70	0.00	417557.06	626212.88	N 32 8 51.52 W 104 3 32.73	
	11100.00	90.00	179.72	9975.00	1282.30	-1280.90	286.19	0.00	417457.07	626213.37	N 32 8 50.54 W 104 3 32.73	
	11200.00	90.00	179.72	9975.00	1382.30	-1380.90	286.68	0.00	417357.08	626213.87	N 32 8 49.55 W 104 3 32.72	
	11300.00	90.00	179.72	9975.00	1482.30	-1480.90	287.18	0.00	417257.09	626214.36	N 32 8 48.56 W 104 3 32.72	
	11400.00	90.00	179.72	9975.00	1582.30	-1580.90	287.67	0.00	417157.10	626214.86	N 32 8 47.57 W 104 3 32.72	
	11500.00	90.00	179.72	9975.00	1682.30	-1680.90	288.16	0.00	417057.11	626215.35	N 32 8 46.58 W 104 3 32.71	
	11600.00	90.00	179.72	9975.00	1782.30	-1780.90	288.66	0.00	416957.12	626215.84	N 32 8 45.59 W 104 3 32.71	
	11700.00	90.00	179.72	9975.00	1882.30	-1880.89	289.15	0.00	416857.13	626216.34	N 32 8 44.60 W 104 3 32.71	
	11800.00	90.00	179.72	9975.00	1982.30	-1980.89	289.65	0.00	416757.14	626216.83	N 32 8 43.61 W 104 3 32.71	
	11900.00	90.00	179.72	9975.00	2082.30	-2080.89	290.14	0.00	416657.15	626217.33	N 32 8 42.62 W 104 3 32.70	
	12000.00	90.00	179.72	9975.00	2182.30	-2180.89	290.63	0.00	416557.16	626217.82	N 32 8 41.63 W 104 3 32.70	
	12100.00	90.00	179.72	9975.00	2282.30	-2280.89	291.13	0.00	416457.17	626218.31	N 32 8 40.64 W 104 3 32.70	
	12200.00	90.00	179.72	9975.00	2382.30	-2380.89	291.62	0.00	416357.18	626218.81	N 32 8 39.65 W 104 3 32.70	
	12300.00	90.00	179.72	9975.00	2482.30	-2480.89	292.12	0.00	416257.19	626219.30	N 32 8 38.66 W 104 3 32.69	
	12400.00	90.00	179.72	9975.00	2582.30	-2580.89	292.61	0.00	416157.20	626219.79	N 32 8 37.67 W 104 3 32.69	
	12500.00	90.00	179.72	9975.00	2682.30	-2680.88	293.10	0.00	416057.21	626220.29	N 32 8 36.68 W 104 3 32.68	
	12600.00	90.00	179.72	9975.00	2782.30	-2780.88	293.60	0.00	415957.22	626220.78	N 32 8 35.69 W 104 3 32.68	
	12700.00	90.00	179.72	9975.00	2882.30	-2880.88	294.09	0.00	415857.23	626221.28	N 32 8 34.70 W 104 3 32.68	
	12800.00	90.00	179.72	9975.00	2982.30	-2980.88	294.59	0.00	415757.24	626221.77	N 32 8 33.71 W 104 3 32.68	
	12900.00	90.00	179.72	9975.00	3082.30	-3080.88	295.08	0.00	415657.25	626222.26	N 32 8 32.72 W 104 3 32.68	
	13000.00	90.00	179.72	9975.00	3182.30	-3180.88	295.57	0.00	415557.26	626222.76	N 32 8 31.73 W 104 3 32.67	
	13100.00	90.00	179.72	9975.00	3282.30	-3280.88	296.07	0.00	415457.27	626223.25	N 32 8 30.74 W 104 3 32.67	
	13200.00	90.00	179.72	9975.00	3382.30	-3380.88	296.56	0.00	415357.28	626223.75	N 32 8 29.76 W 104 3 32.67	
	13300.00	90.00	179.72	9975.00	3482.30	-3480.87	297.05	0.00	415257.29	626224.24	N 32 8 28.77 W 104 3 32.66	
	13400.00	90.00	179.72	9975.00	3582.30	-3580.87	297.55	0.00	415157.30	626224.73	N 32 8 27.78 W 104 3 32.66	
	13500.00	90.00	179.72	9975.00	3682.30	-3680.87	298.04	0.00	415057.31	626225.23	N 32 8 26.79 W 104 3 32.66	
	13600.00	90.00	179.72	9975.00	3782.30	-3780.87	298.54	0.00	414957.32	626225.72	N 32 8 25.80 W 104 3 32.66	
	13700.00	90.00	179.72	9975.00	3882.30	-3880.87	299.03	0.00	414857.33	626226.22	N 32 8 24.81 W 104 3 32.65	
	13800.00	90.00	179.72	9975.00	3982.30	-3980.87	299.52	0.00	414757.34	626226.71	N 32 8 23.82 W 104 3 32.65	
	13900.00	90.00	179.72	9975.00	4082.30	-4080.87	300.02	0.00	414657.35	626227.20	N 32 8 22.83 W 104 3 32.65	
	14000.00	90.00	179.72	9975.00	4182.30	-4180.87	300.51	0.00	414557.36	626227.70	N 32 8 21.84 W 104 3 32.65	
	14100.00	90.00	179.72	9975.00	4282.30	-4280.87	301.01	0.00	414457.37	626228.19	N 32 8 20.85 W 104 3 32.64	
	14200.00	90.00	179.72	9975.00	4382.30	-4380.86	301.50	0.00	414357.38	626228.68	N 32 8 19.86 W 104 3 32.64	
	14300.00	90.00	179.72	9975.00	4482.30	-4480.86	301.99	0.00	414257.39	626229.18	N 32 8 18.87 W 104 3 32.64	
	14400.00	90.00	179.72	9975.00	4582.30	-4580.86	302.49	0.00	414157.40	626229.67	N 32 8 17.88 W 104 3 32.63	
	14500.00	90.00	179.72	9975.00	4682.30	-4680.86	302.98	0.00	414057.41	626230.17	N 32 8 16.89 W 104 3 32.63	
	14600.00	90.00	179.72	9975.00	4782.30	-4780.86	303.48	0.00	413957.42	626230.66	N 32 8 15.90 W 104 3 32.63	
	14700.00	90.00	179.72	9975.00	4882.30	-4880.86	303.97	0.00	413857.43	626231.15	N 32 8 14.91 W 104 3 32.63	
	14800.00	90.00	179.72	9975.00	4982.30	-4980.86	304.46	0.00	413757.44	626231.65	N 32 8 13.92 W 104 3 32.62	
	14900.00	90.00	179.72	9975.00	5082.30	-5080.86	304.96	0.00	413657.45	626232.14	N 32 8 12.93 W 104 3 32.62	
	15000.00	90.00	179.72	9975.00	5182.30	-5180.85	305.45	0.00	413557.46	626232.64	N 32 8 11.94 W 104 3 32.62	
	15100.00	90.00	179.72	9975.00	5282.30	-5280.85	305.95	0.00	413457.47	626233.13	N 32 8 10.95 W 104 3 32.61	
	15200.00	90.00	179.72	9975.00	5382.30	-5380.85	306.44	0.00	413357.48	626233.62	N 32 8 9.96 W 104 3 32.61	
	15300.00	90.00	179.72	9975.00	5482.30	-5480.85	306.93	0.00	413257.49	626234.12	N 32 8 8.98 W 104 3 32.61	
	15400.00	90.00	179.72	9975.00	5582.30	-5580.85	307.43	0.00	413157.50	626234.61	N 32 8 7.99 W 104 3 32.61	
	15500.00	90.00	179.72	9975.00	5682.30	-5680.85	307.92	0.00	413057.51	626235.10	N 32 8 7.00 W 104 3 32.60	
	15600.00	90.00	179.72	9975.00	5782.30	-5780.85	308.41	0.00	412957.52	626235.60	N 32 8 6.01 W 104 3 32.60	
	15700.00	90.00	179.72	9975.00	5882.30	-5880.85	308.91	0.00	412857.53	626236.09	N 32 8 5.02 W 104 3 32.60	
	15800.00	90.00	179.72	9975.00	5982.30	-5980.84	309.40	0.00	412757.54	626236.59	N 32 8 4.03 W 104 3 32.60	
	15900.00	90.00	179.72	9975.00	6082.30	-6080.84	309.90	0.00	412657.55	626237.08	N 32 8 3.04 W 104 3 32.59	
	16000.00	90.00	179.72	9975.00	6182.30	-6180.84	310.39	0.00	412557.56	626237.57	N 32 8 2.05 W 104 3 32.59	
	16100.00	90.00	179.72	9975.00	6282.30	-6280.84	310.88	0.00	412457.57	626238.07	N 32 8 1.06 W 104 3 32.59	

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
NMNM013413 - NMNM112920 Crossing	16200.00	90.00	179.72	9975.00	6382.30	-6380.84	311.38	0.00	412357.56	626238.56	N 32 8 0.07 W 104	3 32.56
	16300.00	90.00	179.72	9975.00	6482.30	-6480.84	311.87	0.00	412257.57	626239.06	N 32 7 59.08 W 104	3 32.58
	16400.00	90.00	179.72	9975.00	6582.30	-6580.84	312.37	0.00	412157.58	626239.55	N 32 7 58.09 W 104	3 32.58
	16500.00	90.00	179.72	9975.00	6682.30	-6680.84	312.86	0.00	412057.59	626240.04	N 32 7 57.10 W 104	3 32.58
	16600.00	90.00	179.72	9975.00	6782.30	-6780.83	313.35	0.00	411957.60	626240.54	N 32 7 56.11 W 104	3 32.57
	16700.00	90.00	179.72	9975.00	6882.30	-6880.83	313.85	0.00	411857.61	626241.03	N 32 7 55.12 W 104	3 32.57
	16800.00	90.00	179.72	9975.00	6982.30	-6980.83	314.34	0.00	411757.62	626241.52	N 32 7 54.13 W 104	3 32.57
	16900.00	90.00	179.72	9975.00	7082.30	-7080.83	314.84	0.00	411657.63	626242.02	N 32 7 53.14 W 104	3 32.56
	17000.00	90.00	179.72	9975.00	7182.30	-7180.83	315.33	0.00	411557.64	626242.51	N 32 7 52.15 W 104	3 32.56
	17100.00	90.00	179.72	9975.00	7282.30	-7280.83	315.82	0.00	411457.65	626243.01	N 32 7 51.16 W 104	3 32.56
	17200.00	90.00	179.72	9975.00	7382.30	-7380.83	316.32	0.00	411357.66	626243.50	N 32 7 50.17 W 104	3 32.56
	17300.00	90.00	179.72	9975.00	7482.30	-7480.83	316.81	0.00	411257.67	626243.99	N 32 7 49.18 W 104	3 32.55
	17382.30	90.00	179.72	9975.00	7564.60	-7563.13	317.22	0.00	411175.38	626244.40	N 32 7 48.37 W 104	3 32.55
	17400.00	90.00	179.72	9975.00	7582.30	-7580.82	317.30	0.00	411157.68	626244.49	N 32 7 48.20 W 104	3 32.55
	17500.00	90.00	179.72	9975.00	7682.30	-7680.82	317.80	0.00	411057.69	626244.98	N 32 7 47.21 W 104	3 32.55
	17600.00	90.00	179.72	9975.00	7782.30	-7780.82	318.29	0.00	410957.70	626245.48	N 32 7 46.22 W 104	3 32.55
	17700.00	90.00	179.72	9975.00	7882.30	-7880.82	318.79	0.00	410857.71	626245.97	N 32 7 45.23 W 104	3 32.54
	17800.00	90.00	179.72	9975.00	7982.30	-7980.82	319.28	0.00	410757.72	626246.46	N 32 7 44.24 W 104	3 32.54
	17900.00	90.00	179.72	9975.00	8082.30	-8080.82	319.77	0.00	410657.73	626246.96	N 32 7 43.25 W 104	3 32.54
	18000.00	90.00	179.72	9975.00	8182.30	-8180.82	320.27	0.00	410557.74	626247.45	N 32 7 42.26 W 104	3 32.53
	18100.00	90.00	179.72	9975.00	8282.30	-8280.82	320.76	0.00	410457.75	626247.95	N 32 7 41.27 W 104	3 32.53
	18200.00	90.00	179.72	9975.00	8382.30	-8380.82	321.26	0.00	410357.75	626248.44	N 32 7 40.28 W 104	3 32.53
	18300.00	90.00	179.72	9975.00	8482.30	-8480.81	321.75	0.00	410257.76	626248.93	N 32 7 39.29 W 104	3 32.53
	18400.00	90.00	179.72	9975.00	8582.30	-8580.81	322.24	0.00	410157.77	626249.42	N 32 7 38.30 W 104	3 32.52
	18500.00	90.00	179.72	9975.00	8682.30	-8680.81	322.74	0.00	410057.78	626249.92	N 32 7 37.31 W 104	3 32.52
	18600.00	90.00	179.72	9975.00	8782.30	-8780.81	323.23	0.00	409957.79	626250.41	N 32 7 36.32 W 104	3 32.52
	18700.00	90.00	179.72	9975.00	8882.30	-8880.81	323.73	0.00	409857.80	626250.91	N 32 7 35.33 W 104	3 32.51
	18800.00	90.00	179.72	9975.00	8982.30	-8980.81	324.22	0.00	409757.81	626251.40	N 32 7 34.34 W 104	3 32.51
	18900.00	90.00	179.72	9975.00	9082.30	-9080.81	324.71	0.00	409657.82	626251.90	N 32 7 33.35 W 104	3 32.51
	19000.00	90.00	179.72	9975.00	9182.30	-9180.81	325.21	0.00	409557.83	626252.39	N 32 7 32.36 W 104	3 32.51
	19100.00	90.00	179.72	9975.00	9282.30	-9280.80	325.70	0.00	409457.84	626252.88	N 32 7 31.37 W 104	3 32.50
	19200.00	90.00	179.72	9975.00	9382.30	-9380.80	326.20	0.00	409357.85	626253.38	N 32 7 30.38 W 104	3 32.50
	19300.00	90.00	179.72	9975.00	9482.30	-9480.80	326.69	0.00	409257.86	626253.87	N 32 7 29.39 W 104	3 32.50
	19400.00	90.00	179.72	9975.00	9582.30	-9580.80	327.18	0.00	409157.87	626254.37	N 32 7 28.40 W 104	3 32.50
	19500.00	90.00	179.72	9975.00	9682.30	-9680.80	327.68	0.00	409057.88	626254.86	N 32 7 27.42 W 104	3 32.49
	19600.00	90.00	179.72	9975.00	9782.30	-9780.80	328.17	0.00	408957.89	626255.35	N 32 7 26.43 W 104	3 32.49
Cimarex Riverbend 11-14 Federal Com #16H - PBHL[330]FSL.2 310[FWL]	19698.62	90.00	179.72	9975.00	9880.92	-9879.42	328.66	0.00	408859.28	626255.84	N 32 7 25.45 W 104	3 32.49
Survey Type:	Non-Def Plan											
Survey Error Model:	ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma											
Survey Program:												
Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey			

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ") Riverbend 11-14 Federal Com	Longitude (E/W ° ' ") Riverbend 11-14 Federal Com
		1	0.000	23.000	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS-Depth Only		#16H / Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM	
		1	23.000	19698.620	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS		Riverbend 11-14 Federal Com #16H / Cimarex Riverbend 11-14	

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')
Description	Part	MD From (ft)	MD To (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey		
	1	0.000	23.000	23.000	1/100.000	17.500	13.375		NAL_MWD_JFR1+MS-Depth Only		Riverbend 11-14 Federal Com #16H / Cimarex Riverbend 11-14	
	1	23.000	19698.620	19698.620	1/100.000	17.500	13.375		NAL_MWD_JFR1+MS		Federal Com #16H Rev0 RM Riverbend 11-14 Federal Com #16H / Cimarex Riverbend 11-14	

Schlumberger

Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20 Proposal

Geodetic Report

(Non-Def Plan)



Report Date: October 07, 2020 - 11:45 AM
Client: Cimarex Energy
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Riverbend 11-14 Federal Com #16H / New Slot
Well: Riverbend 11-14 Federal Com #16H
Borehole: Riverbend 11-14 Federal Com #16H
UWI / AP#: Unknown / Unknown
Survey Name: Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20
Survey Date: October 06, 2020
Tort / AHD / DDI / ERD Ratio: 100.935° / 10232.039 ft / 6.310 / 1.026
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 9' 3.21726", W 104° 3' 36.01880"
Location Grid N/E Y/X: N 418737.860 ftUS, E 625927.210 ftUS
CRS Grid Convergence Angle: 0.1455°
Grid Scale Factor: 0.99991729
Version / Patch: 2.10.821.3

Survey / DLS Computation:
Vertical Section Azimuth: Minimum Curvature / Lubinski
Vertical Section Origin: 179.717° (Grid North)
TVD Reference Datum: 0.000 ft, 0.000 ft
TVD Reference Elevation: RKB
Seabed / Ground Elevation: 2990.000 ft above MSL
Magnetic Declination: 2967.000 ft above MSL
Total Gravity Field Strength: 6.889°
Gravity Model: 998.4571mgm (9.80665 Based)
Total Magnetic Field Strength: GARM
Magnetic Dip Angle: 47736.040 nT
Declination Date: 59.829°
Magnetic Declination Model: October 06, 2020
North Reference: HDGM 2020
Grid Convergence Used: Grid North
Total Corr Mag North->Grid North: 0.1455°
Local Coord Referenced To: 6.7432°
Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [390' FNL, 2029' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	418737.86	625927.21	N 32 9 3.22	W 104 3 36.02
Nudge 2°/100'	2000.00	0.00	76.83	2000.00	0.00	0.00	0.00	0.00	418737.86	625927.21	N 32 9 3.22	W 104 3 36.02
Hold Nudge	2273.38	5.47	76.83	2272.96	-2.91	2.97	12.69	2.00	418740.83	625939.90	N 32 9 3.25	W 104 3 35.87
Drop to Vertical	5012.88	5.47	76.83	5000.00	-61.12	62.44	266.85	0.00	418800.30	626194.04	N 32 9 3.83	W 104 3 32.91
Hold Vertical	5286.25	0.00	76.83	5272.96	-64.03	65.41	279.54	2.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
KOP - Build	9478.29	0.00	76.83	9465.00	-64.03	65.41	279.54	0.00	418803.27	626206.73	N 32 9 3.86	W 104 3 32.76
Build 4°/100'	10103.29	75.00	179.72	9926.19	289.86	-288.47	281.29	12.00	418449.41	626208.47	N 32 9 0.36	W 104 3 32.75
DLS	10478.29	90.00	179.72	9975.00	660.59	-659.20	283.12	4.00	418078.72	626210.30	N 32 8 56.69	W 104 3 32.74
Landing Point												
Cimarex												
Riverbend 11-14												
Federal Com												
#16H -	19698.62	90.00	179.72	9975.00	9880.92	-9879.42	328.66	0.00	408859.28	626255.84	N 32 7 25.45	W 104 3 32.49
PBHL[330'FSL2 310'FWL]												

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma

Survey Program:

Drilling Office 2.10.821.3

...Riverbend 11-14 Federal Com #16H Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20

10/28/2020 2:23 PM Page 1 of 2

Schumberger



Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20 Anti-Collision Summary Report

Analysis Date-24hr Time: October 07, 2020 - 11:44
 Client: Cimarex Energy
 Field: NM Eddy County (NAD 83)
 Structure: Cimarex Riverbend 11-14 Federal Com #16H
 Slot: New Slot
 Well: Riverbend 11-14 Federal Com #16H
 Borehole: Riverbend 11-14 Federal Com #16H
 Scan MD Range: 0.00ft ~ 19698.62ft

Analysis Method: 3D Least Distance
 Reference Trajectory: Cimarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20 (Non-Def Plan)
 Depth Interval: Every 10.00 Measured Depth (ft)
 Rule Set: NAL Procedure: D&M Anti-Collision Standard S002
 Min Pts: All local minima indicated.
 Version / Patch: 2.10.821.3
 Database \ Project: US1153APP452.dfr.slb.com\drilling-NM Eddy County 2.10

ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For
 offset wells, error model version is specified with each well respectively.

Offset Trajectories Summary

Not performed!
 Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans
 Selection filters:
 - All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectory	Separation		Allow	Sep.	Controlling	Reference Trajectory		Alert	Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	Dev. (ft)	Fact.	Rule	MD (ft)	TVD (ft)		Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Mewbourne Hess 11 SWD #1
 (Offset) Blind SWD 0h-15650ft
 (Def Survey)

3050.30	32.81	3049.61	3018.09	N/A	MAS = 10.00 (m)	0.00	0.00					Surface
3050.66	32.81	3049.35	3017.85	102457.84	MAS = 10.00 (m)	23.00	23.00					MinP-O-SF
2874.90	895.44	2377.50	2079.46	4.99	OSF 1.50	2840.00	2836.55	OSF <= 5.00				Enter Alert
2766.96	2769.16	920.34	-2.19	1.50	OSF 1.50	8910.00	8896.71		OSF < 1.50			Enter Minor
2766.96	2947.30	801.24	-160.84	1.41	OSF 1.50	9478.29	9465.00					MinP-CICI
2766.46	3072.96	739.32	-284.50	1.36	OSF 1.50	9850.00	9863.63					MINPT-O-EQU
2793.40	3079.42	739.97	-286.01	1.36	OSF 1.50	9890.00	9894.22					MinP-O-SF
2796.13	3082.50	740.77	-286.17	1.36	OSF 1.50	10010.00	9993.43					MinP-O-ADP
3104.06	3107.80	1031.77	-3.74	1.50	OSF 1.50	11000.00	9975.00					Exit Minor
10352.31	3108.49	8279.55	7243.82	5.00	OSF 1.50	19560.00	9975.00	OSF > 5.00				Exit Alert
10485.97	3108.49	8413.21	7377.48	5.06	OSF 1.50	19698.62	9975.00					TD

Fail Minor

Cimarex Riverbend 11-14
 Federal Com #17H Rev0 RM
 06Oct20 (Non-Def Plan)

20.00	16.25	18.71	3.74	N/A	MAS = 4.95 (m)	0.00	0.00					Enter Alert
20.00	16.25	18.71	3.74	42102.76	MAS = 4.95 (m)	23.00	23.00					WRP
20.00	16.25	9.73	3.74	2.08	MAS = 4.95 (m)	1490.00	1490.00					MinPs
20.01	16.25	9.84	3.76	2.06	MAS = 4.95 (m)	1510.00	1510.00					MINPT-O-EQU
20.15	16.25	9.89	3.90	2.05	MAS = 4.95 (m)	1530.00	1530.00					MinP-O-SF
55.93	17.82	43.62	38.11	4.96	OSF 1.50	2010.00	2010.00	OSF > 5.00				Exit Alert
486.51	35.63	482.32	490.87	21.19	OSF 1.50	5000.00	5000.00					MinP-O-SF
499.49	70.50	452.06	428.99	10.80	OSF 1.50	9478.29	9465.00					MinPs

Warning Alert

Offset Trajectory	Separation		Allow	Sep.	Controlling Rule	Reference Trajectory		Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Dev. (ft)		MD (ft)	TVD (ft)	Alert	Minor	Major	
Cinarex Riverbend 11-14 Federal Com #15H Rev0 RM 05Oct20 (Non-Def Plan)	499.48	70.50	452.05	428.98	10.80	OSF1.50	9500.00	9486.70		MinPis	MinPis
	495.34	65.50	451.24	428.84	11.54	OSF1.50	10120.00	9930.42		MinPis	MinPis
	495.27	65.41	451.23	428.84	11.55	OSF1.50	10140.00	9935.24		MinPis	MinPis
	494.98	64.75	451.38	430.23	11.67	OSF1.50	10390.00	9972.28		MinPis	MinPis
	494.94	149.41	394.91	345.53	5.00	OSF1.50	14540.00	9975.00	OSF<5.00	Enter Alert	Enter Alert
	494.94	309.35	288.28	185.59	2.40	OSF1.50	19698.62	9975.00		MinPis	MinPis
	20.00	18.25	18.71	3.74	N/A	MAS = 4.95 (m)	0.00	0.00		Enter Alert	Warning Alert
	20.00	18.25	18.71	3.74	28068.80	MAS = 4.95 (m)	23.00	23.00		WRP	WRP
	20.01	18.25	9.84	3.76	2.06	MAS = 4.95 (m)	1490.00	1490.00		MinPis	MinPis
	56.27	20.15	16.25	9.69	3.90	MAS = 4.95 (m)	1530.00	1530.00		MinPis	MinPis
Cinarex Riverbend 14 Federal #2H XEN + MWD Off to 1245St (Def Survey)	58.38	35.80	34.09	22.59	2.48	OSF1.50	2000.00	2000.00	OSF>5.00	Enter Alert	Enter Alert
	58.41	35.89	34.08	22.53	2.48	OSF1.50	4010.00	4001.68	OSF<5.00	MinPis	MinPis
	58.45	35.93	34.07	22.52	2.48	OSF1.50	5010.00	4997.13		MinPis	MinPis
	58.55	36.00	34.12	22.55	2.47	OSF1.50	5030.00	5017.05		MinPis	MinPis
	59.91	58.82	20.27	1.09	1.53	OSF1.50	5040.00	5027.01		MinPis	MinPis
	160.82	50.12	126.98	110.70	4.90	OSF1.50	8240.00	8226.71		MinPis	MinPis
	1235.93	22.84	1220.10	1212.89	85.52	OSF1.50	8580.00	8566.71	OSF>5.00	Enter Alert	Enter Alert
	1275.30	305.29	1071.34	970.01	6.29	OSF1.50	10100.00	9925.33		MinPis	MinPis
	4978.12	32.81	4976.14	4945.31	N/A	MAS = 10.00 (m)	0.00	0.00		Surface	Surface
	4978.03	32.81	4976.04	4945.22	482688.40	MAS = 10.00 (m)	20.00	20.00		MinPis	MinPis
Cinarex Riverbend 11-14 Federal Com #16H Cinarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20	4978.02	32.81	4976.04	4945.22	545646.24	MAS = 10.00 (m)	23.00	23.00		WRP	WRP
	4978.01	32.81	4976.02	4945.21	315106.12	MAS = 10.00 (m)	30.00	30.00		MinPis	MinPis
	4978.05	32.81	4975.98	4945.24	59950.76	MAS = 10.00 (m)	60.00	60.00		MinPis	MinPis
	5011.81	32.81	5001.01	4979.00	567.75	MAS = 10.00 (m)	2030.00	2030.00		MinPis	MinPis
	5093.15	32.81	5072.93	5060.34	279.07	MAS = 10.00 (m)	5100.00	5086.84		MinPis	MinPis
	5115.58	34.56	5091.88	5081.02	235.41	OSF1.50	6480.00	6466.71		MinPis	MinPis
	5108.28	37.68	5082.51	5070.60	214.51	OSF1.50	7070.00	7056.71		MinPis	MinPis
	5103.29	42.15	5074.53	5061.14	190.50	OSF1.50	7610.00	7796.71		MinPis	MinPis
	5103.38	42.45	5074.42	5060.93	189.09	OSF1.50	7860.00	7846.71		MinPis	MinPis
	5103.84	42.97	5074.53	5060.86	186.69	OSF1.50	7960.00	7946.71		MinPis	MinPis
Cinarex Riverbend 11-14 Federal Com #16H Cinarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20	5104.96	45.17	5074.19	5059.80	177.24	OSF1.50	8360.00	8346.71		MinPis	MinPis
	5105.30	45.57	5074.26	5059.73	175.62	OSF1.50	8420.00	8406.71		MinPis	MinPis
	5137.22	52.02	5101.87	5085.19	153.92	OSF1.50	9478.29	9465.00		MinPis	MinPis
	352.18	109.76	277.44	242.42	4.96	OSF1.50	14750.00	9975.00	OSF<5.00	Enter Alert	Enter Alert
	315.97	115.30	238.36	200.58	4.16	OSF1.50	14900.00	9975.00		MinPis	MinPis
	315.84	115.21	238.38	200.63	4.16	OSF1.50	14910.00	9975.00		MinPis	MinPis
	347.07	105.61	276.00	241.46	5.00	OSF1.50	15050.00	9975.00	OSF>5.00	Enter Alert	Enter Alert
	866.84	137.77	774.33	728.07	9.55	OSF1.50	15720.00	9975.00		MinPis	MinPis
	869.76	142.62	774.02	727.14	9.26	OSF1.50	15810.00	9975.00		MinPis	MinPis
	873.65	149.70	773.19	723.95	8.85	OSF1.50	16180.00	9975.00		MinPis	MinPis
Cinarex Riverbend 11-14 Federal Com #16H Cinarex Riverbend 11-14 Federal Com #16H Rev0 RM 06Oct20	877.31	160.14	769.90	717.18	8.30	OSF1.50	16540.00	9975.00		MinPis	MinPis
	877.02	175.09	759.63	701.93	7.58	OSF1.50	16830.00	9975.00		MinPis	MinPis
	877.03	178.71	757.23	698.32	7.43	OSF1.50	16860.00	9975.00		MinPis	MinPis
	877.11	178.80	757.25	698.31	7.42	OSF1.50	16860.00	9975.00		MinPis	MinPis

Offset Trajectory	Separation		Allow	Sep.	Controlling Rule	Reference Trajectory		Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)			MD (ft)	TYD (ft)	Alert	Minor	Major	
Cimarex Riverbend 14 Federal #2H MWD 10734ft to 15325ft (Def Survey)	877.31	178.88	757.40	898.44	7.42	OSF1.50	16870.00	9975.00		MinPl-O-SF	TD
	2982.53	82.02	2927.19	2900.51	55.86	OSF1.50	19698.62	9975.00			
	4978.12	32.81	4976.14	4945.31	N/A	MAS = 10.00 (m)	0.00	0.00		Surface	
	4978.03	32.81	4976.04	4945.22	482688.40	MAS = 10.00 (m)	20.00	20.00		MinPl-O-SF	
	4978.02	32.81	4976.04	4945.22	545846.24	MAS = 10.00 (m)	23.00	23.00		WRP	
	4978.01	32.81	4976.02	4945.21	315106.12	MAS = 10.00 (m)	30.00	30.00		MinPls	
	4978.05	32.81	4975.98	4945.24	59950.76	MAS = 10.00 (m)	60.00	60.00		MINPT-O-EOU	
	5011.81	32.81	5001.07	4979.00	667.75	MAS = 10.00 (m)	2030.00	2030.00		MINPT-O-EOU	
	5093.15	32.81	5072.93	5060.34	279.07	MAS = 10.00 (m)	5100.00	5085.84		MinPl-O-SF	
	5115.58	34.56	5091.88	5081.02	235.41	OSF1.50	6480.00	6468.71		MinPl-O-SF	
	5103.29	37.69	5082.51	5070.60	214.51	OSF1.50	7070.00	7056.71		MinPl-CICt	
	5103.36	42.15	5074.53	5061.14	190.50	OSF1.50	7810.00	7796.71		MinPl-CICt	
	5103.84	42.45	5074.42	5060.93	189.09	OSF1.50	7860.00	7846.71		MINPT-O-EOU	
	5104.96	42.97	5074.53	5060.86	186.69	OSF1.50	7946.71	7946.71		MinPl-O-ADP	
	5105.30	45.17	5074.19	5059.80	177.24	OSF1.50	8360.00	8346.71		MINPT-O-EOU	
	5137.22	45.57	5074.26	5059.73	175.62	OSF1.50	8420.00	8406.71		MinPl-O-ADP	
	352.18	52.02	5101.87	5085.19	153.92	OSF1.50	9478.29	9465.00		MinPl-O-SF	
	315.87	109.76	277.44	242.42	4.95	OSF1.50	14750.00	9975.00	OSF<5.00	Enter Alert	
	315.84	115.30	238.35	200.58	4.16	OSF1.50	14900.00	9975.00		MinPls	
	347.07	105.61	276.00	241.46	5.00	OSF1.50	15050.00	9975.00	OSF>5.00	MinPl-CICt	
	900.59	138.12	807.85	762.47	9.90	OSF1.50	15750.00	9975.00		Exit Alert	
	914.90	147.44	815.94	767.46	9.41	OSF1.50	16040.00	9975.00		MinPls	
Melador Salt Draw 11 Federal Com #1 (Offset) Inc Only 0ft-13550ft (Def Survey)	915.20	148.99	816.21	767.21	9.33	OSF1.50	16100.00	9975.00		MINPT-O-EOU	Warning Alert
	921.99	162.26	813.15	759.73	8.61	OSF1.50	16530.00	9975.00		MinPl-O-ADP	
	877.20	195.55	746.17	681.65	6.78	OSF1.50	17710.00	9975.00		MinPl-CICt	
	969.43	213.12	725.69	655.31	6.16	OSF1.50	18280.00	9975.00		MinPl-CICt	
	855.97	244.68	682.20	611.30	5.28	OSF1.50	19220.00	9975.00		MinPl-CICt	
	849.32	255.98	677.02	592.37	5.00	OSF1.50	19560.00	9975.00	OSF<5.00	Enter Alert	
	844.90	262.79	668.95	582.01	4.85	OSF1.50	19698.62	9975.00		MinPls	
	1948.12	32.81	1946.83	1915.31	N/A	MAS = 10.00 (m)	0.00	0.00		MinPls	
	1948.12	32.81	1946.74	1915.32	20158.33	MAS = 10.00 (m)	23.00	23.00		WRP	
	1949.90	36.12	1925.09	1913.48	83.89	OSF1.50	810.00	810.00		MinPl-CICt	
	1949.11	73.60	1899.62	1875.51	40.40	OSF1.50	1540.00	1540.00		MinPl-CICt	
	1822.53	316.76	1610.88	1505.76	8.88	OSF1.50	6230.00	6216.71		MinPl-CICt	
	1822.89	420.74	1541.94	1402.16	6.52	OSF1.50	8230.00	8216.71		MinPl-CICt	
	1680.59	507.47	1341.80	1173.22	4.98	OSF1.50	9910.00	9840.24	OSF<5.00	Enter Alert	
	983.41	513.62	640.46	469.79	2.88	OSF1.50	11290.00	9975.00		MINPT-O-EOU	
Mawbourne Hess 2-11 W280 Fed Com 1H (Offset) MWD 0ft-20824ft (Def Survey)	983.40	513.61	640.47	469.79	2.88	OSF1.50	11300.00	9975.00		MinPls	Warning Alert
	1705.52	513.68	1382.65	1191.65	4.99	OSF1.50	12660.00	9975.00	OSF>5.00	Exit Alert	
	8458.99	509.92	8118.61	7949.06	24.94	OSF1.50	19698.62	9975.00		TD	
	5712.31	32.81	5709.41	5676.51	3535.51	MAS = 10.00 (m)	0.00	0.00		MinPl-O-SF	
	5710.30	32.81	5707.38	5677.46	3485.71	MAS = 10.00 (m)	23.00	23.00		MinPl-O-SF	

Offset Trajectory	Separation		Allow	Sep.	Controlling	Reference Trajectory		Risk Level		Alert	Status
	Cl-Ct (ft)	MAS (ft)	EOU (ft)			MD (ft)	TVD (ft)	Minor	Major		
	5879.46	32.81	5874.98	1778.85	MAS = 10.00 (m)	750.00	750.00			MinPis	
	5879.51	32.81	5874.88	1650.61	MAS = 10.00 (m)	810.00	810.00			MINPT-O-EQU	
	5880.59	32.81	5875.01	1324.13	MAS = 10.00 (m)	1010.00	1010.00			MINPT-O-EQU	
	5886.93	32.81	5877.01	659.40	MAS = 10.00 (m)	1990.00	1990.00			MinPis	
	5883.40	32.81	5863.74	305.45	MAS = 10.00 (m)	5100.00	5086.84			MinPis	
	5883.01	32.81	5863.49	307.79	MAS = 10.00 (m)	5140.00	5126.77			MINPT-O-EQU	
	5882.97	32.81	5863.52	308.98	MAS = 10.00 (m)	5160.00	5146.75			MinPis	
	1445.13	285.48	1267.74	1179.68	OSF1.50	9863.92	9863.92			MinPis	
	1445.86	287.07	1267.19	1178.59	OSF1.50	10340.00	9868.33			MINPT-O-EQU	
	1446.82	288.24	1267.37	1178.39	OSF1.50	10370.00	9970.91			MinPis	
	1455.35	305.59	1251.20	1149.76	OSF1.50	11030.00	9975.00			MINPT-O-EQU	
	1456.02	307.57	1250.55	1148.46	OSF1.50	11100.00	9975.00			MinPis	
	1456.72	308.39	1250.70	1148.33	OSF1.50	11130.00	9975.00			MINPT-O-EQU	
	1476.85	326.08	1259.03	1150.76	OSF1.50	11490.00	9975.00			MinPis	
	1480.74	327.42	1262.03	1153.32	OSF1.50	11570.00	9975.00			MINPT-O-EQU	
	1512.34	345.25	1281.74	1167.08	OSF1.50	12050.00	9975.00			MinPis	
	1522.51	349.94	1288.79	1172.57	OSF1.50	13220.00	9975.00			MINPT-O-EQU	
	1538.90	415.19	1281.68	1143.71	OSF1.50	13790.00	9975.00			MinPis	
	1540.93	442.45	1245.54	1068.48	OSF1.50	13900.00	9975.00			MINPT-O-EQU	
	1542.12	446.21	1244.22	1065.91	OSF1.50	14130.00	9975.00			MinPis	
	1533.23	480.93	1225.58	1072.36	OSF1.50	14240.00	9975.00			MINPT-O-EQU	
	1529.42	483.50	1219.99	1065.92	OSF1.50	14250.00	9975.00			MinPis	
	1529.43	483.55	1219.98	1065.87	OSF1.50	14380.00	9975.00			MINPT-O-EQU	
	1529.50	483.59	1220.01	1065.91	OSF1.50	14390.00	9975.00			MinPis	
	1536.37	482.27	1227.76	1074.09	OSF1.50	14698.62	9975.00			Exit Alert	
	5864.96	149.23	5864.83	5815.73	OSF1.50	19698.62	9975.00			TD	

Newbourne Hoss 2-11 B2B0
Fed Com 2H (Offset) MWID 0H-
18370H (Def Survey)

Offset Trajectory	Separation		Allow	Sep.	Controlling	Reference Trajectory		Risk Level		Alert	Status
	Cl-Ct (ft)	MAS (ft)	EOU (ft)			MD (ft)	TVD (ft)	Minor	Major		
	5734.21	32.81	5732.92	5701.40	N/A	0.00	0.00			Surface	
	5734.20	32.81	5732.91	5701.39	N/A	23.00	23.00			WRP	
	5732.37	32.81	5729.79	5899.56	MAS = 10.00 (m)	320.00	320.00			MinPis	
	5732.67	32.81	5729.51	5899.86	MAS = 10.00 (m)	470.00	470.00			MINPT-O-EQU	
	5732.72	32.81	5728.00	5899.91	MAS = 10.00 (m)	600.00	600.00			MinPis	
	4147.40	147.19	4048.84	4000.21	MAS = 10.00 (m)	4400.00	4389.91			MINPT-O-EQU	
	1285.28	283.62	1095.58	1001.46	OSF1.50	8320.00	8306.71			MinPis	
	1285.29	283.83	1095.59	1001.47	OSF1.50	8330.00	8316.71			MINPT-O-EQU	
	2087.33	222.48	1938.57	1864.84	OSF1.50	10490.00	9975.00			MinPis	
	2089.71	230.92	1935.34	1858.80	OSF1.50	10750.00	9975.00			MINPT-O-EQU	
	2090.93	243.82	1926.23	1845.39	OSF1.50	11090.00	9975.00			MinPis	
	2102.94	248.30	1924.97	1842.64	OSF1.50	11240.00	9975.00			MINPT-O-EQU	
	2103.41	257.72	1920.70	1845.22	OSF1.50	11500.00	9975.00			MinPis	
	2117.80	258.22	1930.83	1845.19	OSF1.50	11510.00	9975.00			MINPT-O-EQU	
	2110.32	280.29	1930.51	1837.51	OSF1.50	11940.00	9975.00			MinPis	
	2128.83	332.92	1898.14	1777.60	OSF1.50	13300.00	9975.00			MINPT-O-EQU	
	2128.83	362.51	1875.00	1754.59	OSF1.50	14060.00	9975.00			MinPis	
	2128.83	377.68	1876.61	1751.16	OSF1.50	14440.00	9975.00			MINPT-O-EQU	
	2129.16	377.99	1876.73	1751.16	OSF1.50	14450.00	9975.00			MinPis	
	5730.20	170.66	5616.00	5559.54	OSF1.50	19698.62	9975.00			TD	

Cimarex Riverbend 11-14
Federal Com #3H Rev0 RM
050-420 (Non-Def Plan)

Offset Trajectory	Separation		Allow	Sep.	Controlling	Reference Trajectory		Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Dev. (ft)	Rule	MD (ft)	TVD (ft)	Alert	Minor	Major	
Chisholm Salt Draw 11 Federal #1 (Offset) ST01 Gyro+HWYD 04-8850R (Def Survey)	1339.77	32.81	1338.48	1308.96	N/A	MAS = 10.00 (m)	0.00	0.00			Surface
	1339.77	32.81	1338.48	1308.96	78236.75	MAS = 10.00 (m)	23.00	23.00			WRP
	1339.77	32.81	1338.48	1308.96	148.70	MAS = 10.00 (m)	1490.00	1490.00			MinPis
	1339.81	32.81	1329.43	1307.00	147.25	MAS = 10.00 (m)	1510.00	1510.00			MINPT-O-EOU
	1841.26	35.33	1917.28	1905.93	85.48	OSF1.50	4760.00	4748.27			MinPis
	1975.81	36.15	1951.28	1939.66	84.95	OSF1.50	5100.00	5086.84			MinPis
	1981.77	67.45	1936.38	1914.32	44.90	OSF1.50	9478.29	9465.00			MinPis
	1980.10	62.79	1937.81	1917.31	48.28	OSF1.50	10110.00	9927.91			MINPT-O-EOU
	1979.86	62.14	1938.00	1917.72	48.77	OSF1.50	10350.00	9969.26			MINPT-O-EOU
	1979.79	62.42	1937.75	1917.37	48.55	OSF1.50	10570.00	9975.00			MinPis
	1979.78	310.11	1772.62	1669.68	9.61	OSF1.50	19698.62	19698.62			MinPis
	2791.97	32.81	2790.68	2758.16	N/A	MAS = 10.00 (m)	0.00	0.00			Surface
	2791.99	32.81	2790.25	2758.79	50465.60	MAS = 10.00 (m)	23.00	23.00			MinPis
	2791.39	32.81	2790.02	2758.58	33939.47	MAS = 10.00 (m)	60.00	60.00			MinPis
	2791.44	32.81	2788.81	2758.93	2081.05	MAS = 10.00 (m)	360.00	360.00			MinPis
Chisholm Salt Draw 11 Federal #1 (Offset) Gyro 04-5110R (Def Survey)	2791.59	32.81	2788.68	2758.78	1711.34	MAS = 10.00 (m)	420.00	420.00			MINPT-O-EOU
	2767.93	32.81	2758.63	2735.12	276.53	MAS = 10.00 (m)	2090.00	2089.99			MinPis
	2767.96	32.81	2756.62	2735.15	275.99	MAS = 10.00 (m)	2100.00	2099.98			MINPT-O-EOU
	1714.75	111.82	1639.73	1602.93	23.28	OSF1.50	4800.00	4788.09			MinPis
	1714.77	111.88	1639.70	1602.88	23.27	OSF1.50	4810.00	4798.04			MinPis
	1716.98	112.24	1641.68	1604.75	23.22	OSF1.50	4877.68	4877.68			MinPis
	5343.43	46.66	5311.89	5296.77	176.60	OSF1.50	10760.00	9975.00			MinPis
	5349.55	44.80	5319.25	5304.75	194.39	OSF1.50	11010.00	9975.00			MinPis
	5360.53	44.21	5330.73	5315.42	187.28	OSF1.50	11390.00	9975.00			MinPis
	5360.80	41.79	5332.51	5319.01	198.48	OSF1.50	11450.00	9975.00			MinPis
	5361.19	42.94	5332.13	5318.25	193.00	OSF1.50	11520.00	9975.00			MinPis
	5361.76	43.63	5332.24	5318.13	189.89	OSF1.50	11560.00	9975.00			MinPis
	6819.69	113.08	6743.98	6706.61	97.49	OSF1.50	19950.00	9975.00			MinPis
	9521.35	135.22	9430.77	9386.13	106.62	OSF1.50	19698.62	19698.62			TD
Chisholm Salt Draw 11 Federal #1 (Offset) Gyro 04-5110R (Def Survey)	2791.97	32.81	2790.68	2758.16	N/A	MAS = 10.00 (m)	0.00	0.00			Surface
	2791.99	32.81	2790.25	2758.79	50465.60	MAS = 10.00 (m)	23.00	23.00			MinPis
	2791.39	32.81	2790.02	2758.58	33939.47	MAS = 10.00 (m)	60.00	60.00			MinPis
	2791.44	32.81	2788.81	2758.93	2081.05	MAS = 10.00 (m)	360.00	360.00			MinPis
	2791.59	32.81	2788.68	2758.78	1711.34	MAS = 10.00 (m)	420.00	420.00			MINPT-O-EOU
	2767.93	32.81	2758.63	2735.12	276.53	MAS = 10.00 (m)	2090.00	2089.99			MinPis
	2767.96	32.81	2756.62	2735.15	275.99	MAS = 10.00 (m)	2100.00	2099.98			MINPT-O-EOU
	2965.56	32.81	2945.21	2932.85	154.58	MAS = 10.00 (m)	5012.68	5000.00			MinPis
	3289.53	34.77	3285.92	3254.76	147.39	OSF1.50	6580.00	6586.71			MinPis
	5179.56	58.62	5140.05	5120.94	135.47	OSF1.50	12020.00	9975.00			MinPis
	5178.86	58.67	5138.65	5120.19	133.06	OSF1.50	12080.00	9975.00			MINPT-O-EOU
	5180.44	60.37	5139.76	5120.07	131.49	OSF1.50	12120.00	9975.00			MinPis
	6209.78	110.33	6135.80	6099.45	85.41	OSF1.50	15450.00	9975.00			MinPis
	9258.44	131.12	9170.60	9127.32	106.95	OSF1.50	19698.62	19698.62			TD
	7475.94	32.81	7474.55	7443.03	N/A	MAS = 10.00 (m)	0.00	0.00			Surface

Chisholm Salt Draw 11 Federal
#1 (Offset) ST01 Gyro+HWYD
04-8850R (Def Survey)

Chisholm Salt Draw 11 Federal
#1 (Offset) Gyro 04-5110R (Def Survey)

Waller W Krug Mada Fed #1
(Offset) Dry Hole Blind 04-
3170R (Def Survey)

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Minor	Major		
7475.74	32.81	7474.44	7442.93	569474.58		MAS = 10.00 (m)	23.00	23.00				WRP
7460.30	982.28	6805.02	6478.03	11.41		OSF1.50	3270.00	3265.05				MinPLO-SF
7460.16	982.23	6804.90	6477.92	11.41		OSF1.50	3310.00	3304.87				MinPis
7460.15	982.22	6804.91	6477.94	11.41		OSF1.50	3320.00	3314.82				MinP-CICt
9551.22	695.07	9087.52	8855.26	20.05		OSF1.50	10490.00	9975.00				MinPLO-SF
7197.20	372.33	6948.55	6824.86	29.09		OSF1.50	16770.00	9975.00				MinP-CICt
7197.46	373.00	6948.38	6824.45	29.04		OSF1.50	16830.00	9975.00				MINPT-O-EOU
7197.90	373.54	6948.45	6824.37	29.00		OSF1.50	16870.00	9975.00				MinP-O-ADP
7770.54	528.02	7418.09	7242.51	22.12		OSF1.50	19698.82	9975.00				MinP-O-SF

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex
LEASE NO.:	NMNM16104
LOCATION:	Section 11, T.25 S., R.28 E., NMPM
COUNTY:	Lea County, New Mexico

WELL NAME & NO.:	Riverbend 11-14 Fed Com 16H
SURFACE HOLE FOOTAGE:	390'/N & 2029'/W
BOTTOM HOLE FOOTAGE:	330'/S & 2310'/W

COA

H2S	☐ Yes	☒ No	
Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☐ Low	☐ Medium	☒ High
Cave/Karst Potential	☐ Critical		
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☐ Conventional	☒ Multibowl	☐ Both
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP
Other	☐ Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	☒ COM	☐ Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately **450** feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8**

- hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
- Cement to surface. If cement does not circulate see B.1.a, c-d above.
- Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
- ❖ In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
3. The minimum required fill of cement behind the **7** inch production casing is:
- Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.
4. The minimum required fill of cement behind the **4-1/2** inch production liner is:
Cement should tie-back **100 feet** into the previous casing. Operator shall provide method of verification. **Excess calculates to 11%. Additional cement maybe required.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure

- rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
- b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.

- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall

have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS021522

Hydrogen Sulfide Drilling Operations Plan
Riverbend 11-14 Federal Com #16H
Cimarex Energy Co.
Eddy County, NM

- 1. All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:**
 - A. Characteristics of H₂S
 - B. Physical effects and hazards
 - C. Principal and operation of H₂S detectors, warning system and briefing areas.
 - D. Evacuation procedure, routes and first aid.
 - E. Proper use of safety equipment & life support systems
 - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.
- 2. H₂S Detection and Alarm Systems:**
 - A. H₂S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary.
 - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3. Windsock and/or wind streamers:**
 - A. Windsock at mudpit area should be high enough to be visible.
 - B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.
- 4. Condition Flags and Signs**
 - A. Warning sign on access road to location.
 - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only H₂S trained and certified personnel admitted to location.
- 5. Well control equipment:**
 - A. See exhibit "E-1"
- 6. Communication:**
 - A. While working under masks chalkboards will be used for communication.
 - B. Hand signals will be used where chalk board is inappropriate.
 - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7. Drillstem Testing:**

No DSTs or cores are planned at this time.
- 8. Tubular Goods & Other Equipment**

Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9. Mud System**

If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

H₂S Contingency Plan
Riverbend 11-14 Federal Com #16H
Cimarex Energy Co.
Eddy County, NM

10. Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the response.
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. Phone numbers attached.
- « Have received training in the:
 - Detection of H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

11. Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOC and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

12. Characteristics of H₂S and SO₂


Please see attached International Chemical Safety Cards.

13. Contacting Authorities

Cimarex Energy Co. personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).


H ₂ S Contingency Plan Emergency Contacts				
Riverbend 11-14 Federal Com #16H				
Cimarex Energy Co.				
Eddy County, NM				
Company Office				
Cimarex Energy Co. Midland Office			432-571-7800	
Cimarex Energy Co. After-Hours Contact			800-969-4789	
Key Personnel				
Name	Title	Office		Mobile
Larry Seigrist	Director of Drilling & Completions	915-560-7148		580-243-8485
Charlie Pritchard	Drilling Manager	432-620-1975		432-238-7084
Spencer Bryant	Drilling Manager	432-620-7885		580-768-9995
Stuart Wittenbach	Director of EHS	918-560-7257		918-404-1084
Artesia				
Ambulance		911		
State Police		575-746-2703		
City Police		575-746-2703		
Sheriff's Office		575-746-9888		
Fire Department		575-746-2701		
Local Emergency Planning Committee		575-746-2122		
New Mexico Oil Conservation Division		575-748-1283		
Carlsbad				
Ambulance		911		
State Police		575-885-3137		
City Police		575-885-2111		
Sheriff's Office		575-887-7551		
Fire Department		575-887-3798		
Local Emergency Planning Committee		575-887-6544		
US Bureau of Land Management		575-887-6544		
Santa Fe				
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600		
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126		
New Mexico State Emergency Operations Center		505-476-9635		
National				
National Emergency Response Center (Washington, D.C.)		800-424-8802		
Medical				
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911		
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923		
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433		
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949		
Other				
Boots & Coots IWC		800-256-9688	or	281-931-8884
Cudd Pressure Control		432-699-0139	or	432-563-3356
Halliburton		575-746-2757		
B.J. Services		575-746-3569		

Drilling 12-1/4" hole
below 13 3/8" Casing



2000# BOP
Riverbend 11-14 Federal Com 16H
Cimarex Energy Co.
Sec 11, 25S, 28E
Eddy County, NM

Drilling 8 3/4" hole
below 9 5/8" Casing



5000# BOP
Riverbend 11-14 Federal Com
16H Cimarex Energy Co.
1-25S-28E
Eddy, NM

Drilling 6" hole
below 7" Casing

Fill Line

Flowline

5000# (5M)
BOP

Annular Preventer

SRR & A

Pipe Rams

Blind Rams

2" Minimum Kill Line

Kill Line

Drilling
Spool

3" minimum choke line

Choke Line

2 Valves and a check valve

2 Valves Minimum
(HCR Required)

Wellhead
Assembly

11" 5000 psi x 7-1/16" 10,000 psi
Wellhead Assembly

Wellhead
Assembly

13-5/8" 3000 psi x 11" 5000 psi
Wellhead Assembly

13-5/8" 3000# psi x 13-3/8" SOW Casing Head

5000# BOP
Riverbend 11-14 Federal Com
16H Cimarex Energy Co.
1-25S-28E
Eddy, NM

District I

1625 N. French Dr., Hobbs, NM 88240
 Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
 Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
 Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 104133

CONDITIONS

Operator: CIMAREX ENERGY CO. 600 N. Marienfeld Street Midland, TX 79701	OGRID: 215099
	Action Number: 104133
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
kpickford	Surface casing must be set 25' below top of Rustler Anhydrite in order to seal off protectable water	5/6/2022
kpickford	Notify OCD 24 hours prior to casing & cement	5/6/2022
kpickford	Will require a File As Drilled C-102 and a Directional Survey with the C-104	5/6/2022
kpickford	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	5/6/2022
kpickford	Cement is required to circulate on both surface and intermediate1 strings of casing	5/6/2022
kpickford	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	5/6/2022