

| | | |
|--------------------------------------|--|--|
| Well Name: BELLOQ 11-2 FED STATE COM | Well Location: T23S / R31E / SEC 11 / SESW / 32.3121427 / -103.7506837 | County or Parish/State: EDDY / NM |
| Well Number: 702H | Type of Well: OIL WELL | Allottee or Tribe Name: |
| Lease Number: NMNM0404441 | Unit or CA Name: | Unit or CA Number: |
| US Well Number: 3001546763 | Well Status: Approved Application for Permit to Drill | Operator: DEVON ENERGY PRODUCTION COMPANY LP |

Notice of Intent

Sundry ID: 2668767

| | |
|--|------------------------------|
| Type of Submission: Notice of Intent | Type of Action: APD Change |
| Date Sundry Submitted: 04/26/2022 | Time Sundry Submitted: 03:55 |
| Date proposed operation will begin: 04/26/2022 | |

Procedure Description: BHL/NAME CHANGE Devon Energy Production Co., L.P. (Devon) respectfully requests to move the BHL and have a name change on the subject well. Please see attached revised C102, Drill plan, directional plan. Drilling changes include: Permitted BHL: LOT 3, 20 FNL, 2310 FWL, 02-23S-31E Proposed BHL: LOT 3, 20 FNL, 2250 FWL, 2-23S-31E Permitted Well name: BELLOQ 11 2 FED STATE COM 732H Proposed Well name: BELLOQ 11 2 FED STATE COM 702H

NOI Attachments

Procedure Description

- 5.5in_20lbf_P110EC_VAM_SPRINT_SF_20220426142403.pdf
- WA017899343_BELLOQ_11_2_FED_STATE_COM_702H_WL_R1_20220426142403.pdf
- 5.50_20_P110EC_DWC_C_IS_PLUS_VST_2__1__20220426142403.pdf
- 5.500in_20.00__0.361in_Wall__VST_P110EC_DWC_C_IS_CDS_AB_20220426142403.pdf
- 8.625_32_P110EC_SPRINT_FJ_VST_4__1__20220426142401.pdf
- Belloq_11_2_Fed_State_Com_702H_20220426142401.pdf
- MB_Wellhd_WC_4_STRING_13.375_10.75_8.625_5.5_20220426142401.pdf
- Belloq_11_2_Fed_State_Com_702H_Directional_Plan_20220426142401.pdf
- 1075_4550_J55_BTC_SC_BLP_Devon_20220426142401.pdf

Received by OCD: 5/6/2022 7:34:46 AM

Page 2 of 40

| | | |
|--------------------------------------|--|--|
| Well Name: BELLOQ 11-2 FED STATE COM | Well Location: T23S / R31E / SEC 11 / SESW / 32.3121427 / -103.7506837 | County or Parish/State: EDDY / NM |
| Well Number: 702H | Type of Well: OIL WELL | Allottee or Tribe Name: |
| Lease Number: NMNM0404441 | Unit or CA Name: | Unit or CA Number: |
| US Well Number: 3001546763 | Well Status: Approved Application for Permit to Drill | Operator: DEVON ENERGY PRODUCTION COMPANY LP |

Conditions of Approval

Additional

11_23_31_N_Sundry_ID_2668767_Belloq_11_2_Fed_State_Com_732H_Eddy_NM040444_13_22d_5_5_2022_LV_20220505130034.pdf
Belloq_11_2_Fed_State_Com_702H_Dr_COA_Sundry_ID_2668767_20220505130011.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: JENNY HARMS

Signed on: APR 26, 2022 03:55 PM

Name: DEVON ENERGY PRODUCTION COMPANY LP

Title: Regulatory Compliance Professional

Street Address: 333 West Sheridan Avenue

City: Oklahoma CityState: OK

Phone: (405) 552-6560

Email address: jennifer.harms@dvn.com

Field

Representative Name:

Street Address:

City:State:Zip:

Phone:

Email address:

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS

BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752342234

BLM POC Email Address: cwalls@blm.gov

Disposition: Approved

Disposition Date: 05/05/2022

Signature: Chris Walls

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

| | | |
|---|---|--|
| ¹ API Number 30-015-46763 | ² Pool Code 98123 | ³ Pool Name WC-015 G-08 S233102C; WOLFCAMP |
| ⁴ Property Code 322487 | ⁵ Property Name BELLOQ 11-2 FED STATE COM | |
| ⁷ OGRID No. 6137 | ⁸ Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P. | ⁶ Well Number 702H ⁹ Elevation 3455.5 |

¹⁰ Surface Location


| | | | | | | | | | |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| UL or lot no. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
| N | 11 | 23 S | 31 E | | 150 | SOUTH | 1990 | WEST | EDDY |

¹¹ Bottom Hole Location If Different From Surface

| UL or lot no. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| 3 | 2 | 23 S | 31 E | | 20 | NORTH | 2250 | WEST | EDDY |

| | | | |
|---|-------------------------------|----------------------------------|-------------------------|
| ¹² Dedicated Acres 619.13 | ¹³ Joint or Infill | ¹⁴ Consolidation Code | ¹⁵ Order No. |
|---|-------------------------------|----------------------------------|-------------------------|

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



Intent ☒ As Drilled ☐

| | | |
|--|---|---------------------|
| API # | | |
| Operator Name: DEVON ENERGY PRODUCTION COMPANY, L.P. | Property Name: BELLOQ 11-2 FED STATE COM | Well Number 702H |

Kick Off Point (KOP)

| UL | Section | Township | Range | Lot | Feet | From N/S | Feet | From E/W | County |
|-------------------------|---------|----------|-------|-----|----------------------------|----------|----------|----------|-----------|
| | 11 | 23S | 31E | | 44 FSL | | 2250 FWL | | EDDY |
| Latitude 32.31175583 | | | | | Longitude -103.74992461 | | | | NAD 83 |

First Take Point (FTP)

| UL | Section | Township | Range | Lot | Feet | From N/S | Feet | From E/W | County |
|------------------------|---------|----------|-------|-----|--------------------------|----------|------|----------|-----------|
| N | 11 | 23S | 31E | | 100 | SOUTH | 2250 | WEST | EDDY |
| Latitude 32.3120032 | | | | | Longitude 103.7498425 | | | | NAD 83 |

Last Take Point (LTP)

| UL | Section | Township | Range | Lot | Feet | From N/S | Feet | From E/W | County |
|------------------------|---------|----------|-------|-----|--------------------------|----------|------|----------|-----------|
| | 2 | 23S | 31E | 3 | 100 | NORTH | 2250 | WEST | EDDY |
| Latitude 32.3404563 | | | | | Longitude 103.7498761 | | | | NAD 83 |


Is this well the defining well for the Horizontal Spacing Unit? ☒Is this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

| | | |
|----------------|----------------|-------------|
| API # | | |
| Operator Name: | Property Name: | Well Number |

KZ 06/29/2018

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP



015 75 150 300

SCALE 1" = 150'

DIRECTIONS TO LOCATION

FROM STATE HWY. 128 AND CR. 798 (RED ROAD) GO NORTH ON RED ROAD 4.7 MILES, TURN LEFT ON CALICHE ROAD AND GO WEST 0.15 MILE, BEND RIGHT AND GO NORTHWEST 0.35 MILE, TURN LEFT AND GO SOUTHWEST 0.4 MILE, TURN LEFT AND GO SOUTH 0.25 MILE TO BARCLAY 11N FED 14 WELLPAD, AT EAST EDGE OF PAD FOLLOW FLAGS EAST 328' THEN SOUTH 185' THEN WEST 196' TO THE NORTHEAST CORNER OF THIS PAD.

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 702H
LOCATED 150 FT. FROM THE SOUTH LINE
AND 1990 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 16, 2021


SURVEY NO. 7494A

MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 INTERIM SITE RECLAMATION



 DENOTES RECLAMATION AREA

 DENOTES GRADING SITE RECLAMATION AREA

015 75 150 300
 SCALE 1" = 150'

3.459± ACRES INTERIM PAD RECLAMATION AREA
 3.369± ACRES GRADING SITE RECLAMATION AREA
 3.505± ACRES NON-RECLAIMED AREA
 10.333± ACRES BELLOQ 11 PAD 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 702H
 LOCATED 150 FT. FROM THE SOUTH LINE
 AND 1990 FT. FROM THE WEST LINE OF
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO


DECEMBER 16, 2021

SURVEY NO. 7494A

MADRON SURVEYING, INC. 301 SOUTH CANAL
 (575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 LOCATION VERIFICATION MAP



USGS QUAD MAP:
 LOS MEDANOS
 BOOTLEG RIDGE

NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 702H
 LOCATED 150 FT. FROM THE SOUTH LINE
 AND 1990 FT. FROM THE WEST LINE OF
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO


DECEMBER 16, 2021

MADRON SURVEYING, INC.

301 SOUTH CANAL
 (575) 234-3341

SURVEY NO. 7494A
 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM STATE HWY. 128 AND CR. 798 (RED ROAD) GO NORTH ON RED ROAD 4.7 MILES, TURN LEFT ON CALICHE ROAD AND GO WEST 0.15 MILE, BEND RIGHT AND GO NORTHWEST 0.35 MILE, TURN LEFT AND GO SOUTHWEST 0.4 MILE, TURN LEFT AND GO SOUTH 0.25 MILE TO BARCLAY 11N FED 14 WELLPAD, AT EAST EDGE OF PAD FOLLOW FLAGS EAST 328' THEN SOUTH 185' THEN WEST 196' TO THE NORTHEAST CORNER OF THIS PAD.

DEVON ENERGY PRODUCTION COMPANY, L.P.**BELLOQ 11-2 FED STATE COM 702H**

LOCATED 150 FT. FROM THE SOUTH LINE
 AND 1990 FT. FROM THE WEST LINE OF
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 16, 2021


SURVEY NO. 7494A

MADRON SURVEYING, INC. 301 SOUTH CANAL

(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 AERIAL PHOTO



NOT TO SCALE
 AERIAL PHOTO:
 GOOGLE EARTH
 NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 702H
 LOCATED 150 FT. FROM THE SOUTH LINE
 AND 1990 FT. FROM THE WEST LINE OF
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO


DECEMBER 16, 2021

MADRON SURVEYING, INC.

301 SOUTH CANAL
 (575) 234-3341

SURVEY NO. 7494A
 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 AERIAL ACCESS ROUTE MAP



NOT TO SCALE
 AERIAL PHOTO:
 GOOGLE EARTH
 NOV. 2017


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 702H
 LOCATED 150 FT. FROM THE SOUTH LINE
 AND 1990 FT. FROM THE WEST LINE OF
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 16, 2021

SURVEY NO. 7494A


MADRON SURVEYING, INC. 301 SOUTH CANAL
 (575) 234-3341

CARLSBAD, NEW MEXICO




CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



I, FILMON F. JARAMA, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFICATE NO. 12299, AM RESPONSIBLE FOR THIS SURVEY, THAT THE SURVEYING INSTRUMENTS AND EQUIPMENT USED IN THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR BELLO 11-2 FED STATE COM 702H

SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

| CUT | FILL | NET |
|---------------|---------------|---------------------|
| 35840 CU. YD. | 41628 CU. YD. | 5788 CU. YD. (FILL) |

EARTHWORK QUANTITIES ARE ESTIMATED

012 60 120 240
SCALE 1" = 120' - 1" = 20' VER


DECEMBER 16, 2021
301 SOUTH CANAL CARLSBAD, NEW MEXICO

SHEET 2-2
SURVEY NO. 7494A


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 522H, 702H,
512H, 701H, & 812H AND BELLOQ 11 FED 212H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 16, 2021



SEE NEXT SHEET (2-2) FOR DESCRIPTION

**GENERAL NOTES**

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 16th DAY OF DECEMBER 2021

FILMON F. JARAMILLO, PLS
12797
NEW MEXICO PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 7494A

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 522H, 702H,
512H, 701H, & 812H AND BELLOQ 11 FED 212H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 16, 2021

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S78°51'28"W, A DISTANCE OF 2280.60 FEET;
THENCE N89°51'22"E A DISTANCE OF 195.86 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°08'52"W A DISTANCE OF 15.05 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S24°38'45"E, A DISTANCE OF 494.62 FEET;

SAID STRIP OF LAND BEING 210.91 FEET OR 12.78 RODS IN LENGTH, CONTAINING 0.145 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4 210.91 L.F. 12.78 RODS 0.145 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 16TH DAY OF DECEMBER 2021

FILIMON F. JARAMILLO
12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SURVEY NO. 7494A

Belloq 11-2 Fed State Com 702H

1. Geologic Formations

| | | | |
|---------------|-------|------------------------------|-----|
| TVD of target | 11825 | Pilot hole depth | N/A |
| MD at TD: | 22093 | Deepest expected fresh water | |

Basin

| Formation | Depth (TVD) from KB | Water/Mineral Bearing/Target Zone? | Hazards* |
|----------------------|---------------------------|--|----------|
| Rustler | 700 | | |
| Salt | 1075 | | |
| Base of Salt | 4200 | | |
| Delaware | 4450 | | |
| Cherry Canyon | 5350 | | |
| Brushy Canyon | 6600 | | |
| 1st Bone Spring Lime | 8275 | | |
| Bone Spring 1st | 9350 | | |
| Bone Spring 2nd | 9900 | | |
| 3rd Bone Spring Lime | 10450 | | |
| Bone Spring 3rd | 11150 | | |
| Wolfcamp | 11600 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

*H₂S, water flows, loss of circulation, abnormal pressures, etc.

Belloq 11-2 Fed State Com 702H

2. Casing Program (Primary Design)

| Hole Size | Csg. Size | Wt (PPF) | Grade | Conn | Top (MD) | Bottom (MD) | Top (TVD) | Bottom (TVD) |
|-----------|-----------|----------|-------|-----------|----------|-------------|-----------|--------------|
| 17 1/2 | 13 3/8 | 48.0 | H40 | STC | 0.0 | 725.0 | 0 | 725 |
| 12 1/4 | 10 3/4 | 45.5 | J55 | BTC SC | 0.0 | 4450 | 0 | 4450 |
| 9 7/8 | 8 5/8 | 32 | P110 | SPRINT | 0 | 11175 | 0 | 11175 |
| 6 3/4 | 5 1/2 | 20.0 | P110 | DWC/C IS+ | 0 | 10675 | 0 | 10675 |
| 6 3/4 | 5 1/2 | 20.0 | P110 | SPRINT SF | 10675 | 12179 | 10675 | 11830 |
| 6 3/4 | 5 1/2 | 20.0 | P110 | DWC/C IS | 12179 | 22093 | 11830 | 11825 |

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.
- Assuming no returns are established while drilling, Devon requests to pump a two stage cement job on the 8-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brushy Canyon (6,600') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If necessary, a top out consisting of 477 sacks of Class C cement + 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. The final cement top will be verified by Echo-meter.
- Devon will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program.
Devon will report to the BLM the volume of fluid (limited to 1 bbls) used to flush intermediate casing valves following backside cementing procedures.
- Variance for radial clearance in production lateral has been approved

Belloq 11-2 Fed State Com 702H

3. Cementing Program (Primary Design)

| Casing | # Sks | TOC | Wt. (lb/gal) | Yld (ft ³ /sack) | Slurry Description |
|----------------------------------|--------------|---------------------|--------------|-----------------------------|--|
| Surface | 563 | Surf | 13.2 | 1.44 | Lead: Class C Cement + additives |
| Int | 297 | Surf | 9 | 3.27 | Lead: Class C Cement + additives |
| | 150 | 500' above shoe | 13.2 | 1.44 | Tail: Class H / C + additives |
| Int 1 | 331 | Surf | 9 | 3.27 | Lead: Class C Cement + additives |
| | 521 | 4000' above shoe | 13.2 | 1.44 | Tail: Class H / C + additives |
| Int 1 Intermediate Squeeze | As Needed | Surf | 9 | 1.44 | Squeeze Lead: Class C Cement + additives |
| | 280 | Surf | 9 | 3.27 | Lead: Class C Cement + additives |
| | 477 | 4000' above shoe | 13.2 | 1.44 | Tail: Class H / C + additives |
| Production | 654 | 0 | 9 | 3.27 | Lead: Class H / C + additives |
| | 690 | 11279 | 13.2 | 1.44 | Tail: Class H / C + additives |

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

| Casing String | % Excess |
|---------------------------------|----------|
| Surface | 50% |
| Intermediate and Intermediate 1 | 30% |
| Intermediate 1 (Two Stage) | 25% |
| Prod | 10% |

Belloq 11-2 Fed State Com 702H

4. Pressure Control Equipment (Four String Design)

| BOP installed and tested before drilling which hole? | | Size? | Min. Required WP | Type | ✓ | Tested to: |
|--|--|-------|------------------|------|---|--------------------------------|
| Int | 13-5/8" | 5M | Annular | | X | 50% of rated working pressure |
| | | | Blind Ram | | X | 5M |
| | | | Pipe Ram | | | |
| | | | Double Ram | | X | |
| | | | Other* | | | |
| Int 1 | 13-5/8" | 5M | Annular (5M) | | X | 100% of rated working pressure |
| | | | Blind Ram | | X | 5M |
| | | | Pipe Ram | | | |
| | | | Double Ram | | X | |
| | | | Other* | | | |
| Production | 13-5/8" | 5M | Annular (5M) | | X | 100% of rated working pressure |
| | | | Blind Ram | | X | 5M |
| | | | Pipe Ram | | | |
| | | | Double Ram | | X | |
| | | | Other* | | | |
| N | A variance is requested for the use of a diverter on the surface casing. See attached for schematic. | | | | | |
| N | A variance is requested to run a 5 M annular on a 10M system | | | | | |

Belloq 11-2 Fed State Com 702H

5. Mud Program (Four String Design)

| Section | Type | Weight (ppg) |
|----------------|-----------------|--------------|
| Surface | WBM | 8.5-9 |
| Intermediate | DBE / Cut Brine | 10-10.5 |
| Intermediate 1 | WBM | 8.5-9 |
| Production | OBM | 10-10.5 |

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

| | |
|---|-----------------------------|
| What will be used to monitor the loss or gain of fluid? | PVT/Pason/Visual Monitoring |
|---|-----------------------------|

6. Logging and Testing Procedures

| Logging, Coring and Testing | |
|-----------------------------|---|
| X | Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM. |
| | No logs are planned based on well control or offset log information. |
| | Drill stem test? If yes, explain. |
| | Coring? If yes, explain. |

| Additional logs planned | | Interval |
|-------------------------|-------------|-------------------------|
| | Resistivity | Int. shoe to KOP |
| | Density | Int. shoe to KOP |
| X | CBL | Production casing |
| X | Mud log | Intermediate shoe to TD |
| | PEX | |

7. Drilling Conditions

| Condition | Specify what type and where? |
|----------------------------|------------------------------|
| BH pressure at deepest TVD | 6456 |
| Abnormal temperature | No |

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

| | |
|---|---------------------------------|
| N | H ₂ S is present |
| Y | H ₂ S plan attached. |

Belloq 11-2 Fed State Com 702H

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan
 Other, describe

Section 2 - Blowout Preventer Testing Procedure

Variance Request

Devon Energy requests to only test BOP connection breaks after drilling out of surface casing and while skidding between wells which conforms to API Standard 53 and industry standards. This test will include the Top Pipe Rams, HCR, Kill Line Check Valve, QDC (quick disconnect to wellhead) and Shell of the 10M BOPE to 5M for 10 minutes. If a break to the flex hose that runs to the choke manifold is required due to repositioning from a skid, the HCR will remain open during the shell test to include that additional break. The variance only pertains to intermediate hole-sections and no deeper than the Bone Springs Formation where 5M BOP tests are required. The initial BOP test will follow OOGO2.III.A.2.i, and subsequent tests following a skid will only test connections that are broken. The annular preventer will be tested to 100% working pressure. This variance will meet or exceed OOGO2.III.A.2.i per the following: Devon Energy will perform a full BOP test per OOGO2.III.A.2.i before drilling out of the intermediate casing string(s) and starting the production hole, before starting any hole section that requires a 10M test, before the expiration of the allotted 14-days for 5M intermediate batch drilling or when the drilling rig is fully mobilized to a new well pad, whichever is sooner. We will utilize a 200' TVD tolerance between intermediate shoes as the cutoff for a full BOP test. The BLM will be contacted 4hrs prior to a BOPE test. The BLM will be notified if and when a well control event is encountered. Break test will be a 14 day interval and not a 30 day full BOPE test interval. If in the event break testing is not utilized, then a full BOPE test would be conducted.



1. Well Control Response:
 1. Primary barrier remains fluid
 2. In the event of an influx due to being underbalanced and after a realized gain or flow, the order of closing BOPE is as follows:
 - a) Annular first
 - b) If annular were to not hold, Upper pipe rams second (which were tested on the skid BOP test)
 - c) If the Upper Pipe Rams were to not hold, Lower Pipe Rams would be third

Cactus
Wellhead

2-9-17
E Bell

80.7 °F

15:49



50

Date 02-09-17

Tested By E.BELL

Transducer bay2

Transducer Serial 181504

Calibration Date 9/6/15

| | Job# | Part# | Serial# | Description | Test Pressure |
|---|-----------------|--------|-------------|---------------------------------------|---------------|
| 1 | TRJ0006341-0007 | 116966 | TRJ6341-7-1 | ADPT,DRLG,CW,MBU-3T,13-5/8 10M | 15000 |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | | | | TRANSDUCER CALIBRATION DUE 03/13/2017 | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |



Start



Stop



Zero



Config



Save



Print

EXIT


Belloq 11-2 Fed State Com 702H



Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD (ft) | INC (°) | AZI (°) | TVD (ft) | NS (ft) | EW (ft) | VS (ft) | DLS (°/100ft) | Comment |
|------------|------------|------------|-------------|------------|------------|------------|------------------|------------------|
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | SHL |
| 2000.00 | 0.00 | 112.00 | 2000.00 | 0.00 | 0.00 | 0.00 | 0.00 | Start Tangent |
| 2500.00 | 10.00 | 112.00 | 2497.47 | -16.30 | 40.35 | -15.55 | 2.00 | Hold Tangent |
| 3616.90 | 10.00 | 112.00 | 3597.40 | -88.96 | 220.18 | -84.85 | 0.00 | Drop to Vertical |
| 4116.90 | 0.00 | 112.00 | 4094.87 | -105.26 | 260.53 | -100.40 | 2.00 | Hold Vertical |
| 11279.08 | 0.00 | 359.63 | 11257.04 | -105.26 | 260.53 | -100.40 | 0.00 | KOP |
| 12179.37 | 90.03 | 359.63 | 11830.00 | 467.97 | 256.83 | 472.66 | 10.00 | Landing Point |
| 22093.28 | 90.03 | 359.63 | 11825.00 | 10381.68 | 192.81 | 10383.47 | 0.00 | BHL |



| Key Depths | MD (ft) | TVD (ft) |
|---------------------------------|------------|-------------|
| Rustler | 700.00 | 700.00 |
| Salt | 1075.00 | 1075.00 |
| Base of Salt | 4222.04 | 4200.00 |
| Delaware | 4472.04 | 4450.00 |
| Cherry Canyon | 5372.04 | 5350.00 |
| Brushy Canyon | 6622.04 | 6600.00 |
| 1st Bone Spring Lime | 8297.04 | 8275.00 |
| Bone Spring 1st | 9372.04 | 9350.00 |
| Bone Spring 2nd | 9922.04 | 9900.00 |
| 3rd Bone Spring Lime | 10472.04 | 10450.00 |
| Bone Spring 3rd | 11172.04 | 11150.00 |
| Wolfcamp / Point of Penetration | 11646.76 | 11600.00 |
| exit | 22013.28 | 11825.05 |

SHL
KOP
Point of Penetration
Exit
BHL

| MD (ft) | TVD (ft) | Lat (°) | Long (°) | Section Footages |
|------------|-------------|------------|-------------|---|
| 0.00 | 0.00 | 32.3120 | -103.7508 | 150' FSL, 1990' FWL of Sec 11 in T23S, R31E |
| 11279.08 | 11257.04 | 32.3118 | -103.7499 | 44' FSL, 2250' FWL of Sec 11 in T23S, R31E |
| 11646.76 | 11600.00 | 32.3120 | -103.7498 | 100' FSL, 2250' FWL of Sec 11 in T23S, R31E |
| 22013.28 | 11825.05 | 32.3405 | -103.7499 | 100' FNL, 2250' FWL of Sec 2 in T23S, R31E |
| 22093.28 | 11825.00 | 32.3406 | -103.7500 | 20' FNL, 2250' FWL of Sec 2 in T23S, R31E |

Belloq 11-2 Fed State Com 702H



Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD (ft) | INC (°) | AZI (°) | TVD (ft) | NS (ft) | EW (ft) | VS (ft) | DLS (°/100ft) | Comment |
|------------|------------|------------|-------------|------------|------------|------------|------------------|------------------|
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | SHL |
| 100.00 | 0.00 | 112.00 | 100.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 200.00 | 0.00 | 112.00 | 200.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 300.00 | 0.00 | 112.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 400.00 | 0.00 | 112.00 | 400.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 500.00 | 0.00 | 112.00 | 500.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 600.00 | 0.00 | 112.00 | 600.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 700.00 | 0.00 | 112.00 | 700.00 | 0.00 | 0.00 | 0.00 | 0.00 | Rustler, |
| 800.00 | 0.00 | 112.00 | 800.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 900.00 | 0.00 | 112.00 | 900.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1000.00 | 0.00 | 112.00 | 1000.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1075.00 | 0.00 | 112.00 | 1075.00 | 0.00 | 0.00 | 0.00 | 0.00 | Salt |
| 1100.00 | 0.00 | 112.00 | 1100.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1200.00 | 0.00 | 112.00 | 1200.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1300.00 | 0.00 | 112.00 | 1300.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1400.00 | 0.00 | 112.00 | 1400.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1500.00 | 0.00 | 112.00 | 1500.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1600.00 | 0.00 | 112.00 | 1600.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1700.00 | 0.00 | 112.00 | 1700.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1800.00 | 0.00 | 112.00 | 1800.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1900.00 | 0.00 | 112.00 | 1900.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 2000.00 | 0.00 | 112.00 | 2000.00 | 0.00 | 0.00 | 0.00 | 0.00 | Start Tangent |
| 2100.00 | 2.00 | 112.00 | 2099.98 | -0.65 | 1.62 | -0.62 | 2.00 | |
| 2200.00 | 4.00 | 112.00 | 2199.84 | -2.61 | 6.47 | -2.49 | 2.00 | |
| 2300.00 | 6.00 | 112.00 | 2299.45 | -5.88 | 14.55 | -5.61 | 2.00 | |
| 2400.00 | 8.00 | 112.00 | 2398.70 | -10.44 | 25.85 | -9.96 | 2.00 | |
| 2500.00 | 10.00 | 112.00 | 2497.47 | -16.30 | 40.35 | -15.55 | 2.00 | Hold Tangent |
| 2600.00 | 10.00 | 112.00 | 2595.95 | -22.81 | 56.45 | -21.76 | 0.00 | |
| 2700.00 | 10.00 | 112.00 | 2694.43 | -29.31 | 72.55 | -27.96 | 0.00 | |
| 2800.00 | 10.00 | 112.00 | 2792.91 | -35.82 | 88.65 | -34.17 | 0.00 | |
| 2900.00 | 10.00 | 112.00 | 2891.39 | -42.32 | 104.75 | -40.37 | 0.00 | |
| 3000.00 | 10.00 | 112.00 | 2989.87 | -48.83 | 120.86 | -46.58 | 0.00 | |
| 3100.00 | 10.00 | 112.00 | 3088.35 | -55.33 | 136.96 | -52.78 | 0.00 | |
| 3200.00 | 10.00 | 112.00 | 3186.83 | -61.84 | 153.06 | -58.99 | 0.00 | |
| 3300.00 | 10.00 | 112.00 | 3285.31 | -68.34 | 169.16 | -65.19 | 0.00 | |
| 3400.00 | 10.00 | 112.00 | 3383.79 | -74.85 | 185.26 | -71.40 | 0.00 | |
| 3500.00 | 10.00 | 112.00 | 3482.27 | -81.35 | 201.36 | -77.60 | 0.00 | |
| 3600.00 | 10.00 | 112.00 | 3580.75 | -87.86 | 217.46 | -83.80 | 0.00 | |
| 3616.90 | 10.00 | 112.00 | 3597.40 | -88.96 | 220.18 | -84.85 | 0.00 | Drop to Vertical |
| 3700.00 | 8.34 | 112.00 | 3679.43 | -93.92 | 232.46 | -89.59 | 2.00 | |
| 3800.00 | 6.34 | 112.00 | 3778.61 | -98.70 | 244.30 | -94.15 | 2.00 | |
| 3900.00 | 4.34 | 112.00 | 3878.17 | -102.19 | 252.92 | -97.47 | 2.00 | |
| 4000.00 | 2.34 | 112.00 | 3977.99 | -104.37 | 258.32 | -99.55 | 2.00 | |
| 4100.00 | 0.34 | 112.00 | 4077.96 | -105.24 | 260.49 | -100.39 | 2.00 | |
| 4116.90 | 0.00 | 112.00 | 4094.87 | -105.26 | 260.53 | -100.40 | 2.00 | Hold Vertical |
| 4200.00 | 0.00 | 359.63 | 4177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4222.04 | 0.00 | 359.63 | 4200.00 | -105.26 | 260.53 | -100.41 | 0.00 | Base of Salt |
| 4300.00 | 0.00 | 359.63 | 4277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4400.00 | 0.00 | 359.63 | 4377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4472.04 | 0.00 | 359.63 | 4450.00 | -105.26 | 260.53 | -100.41 | 0.00 | Delaware |
| 4500.00 | 0.00 | 359.63 | 4477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4600.00 | 0.00 | 359.63 | 4577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4700.00 | 0.00 | 359.63 | 4677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4800.00 | 0.00 | 359.63 | 4777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 4900.00 | 0.00 | 359.63 | 4877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5000.00 | 0.00 | 359.63 | 4977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5100.00 | 0.00 | 359.63 | 5077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5200.00 | 0.00 | 359.63 | 5177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5300.00 | 0.00 | 359.63 | 5277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5372.04 | 0.00 | 359.63 | 5350.00 | -105.26 | 260.53 | -100.41 | 0.00 | Cherry Canyon |
| 5400.00 | 0.00 | 359.63 | 5377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5500.00 | 0.00 | 359.63 | 5477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5600.00 | 0.00 | 359.63 | 5577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5700.00 | 0.00 | 359.63 | 5677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5800.00 | 0.00 | 359.63 | 5777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 5900.00 | 0.00 | 359.63 | 5877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6000.00 | 0.00 | 359.63 | 5977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6100.00 | 0.00 | 359.63 | 6077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6200.00 | 0.00 | 359.63 | 6177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6300.00 | 0.00 | 359.63 | 6277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |

Belloq 11-2 Fed State Com 702H



Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD (ft) | INC (") | AZI (") | TVD (ft) | NS (ft) | EW (ft) | VS (ft) | DLS (°/100ft) | Comment |
|------------|------------|------------|-------------|------------|------------|------------|------------------|---------------------------------|
| 6400.00 | 0.00 | 359.63 | 6377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6500.00 | 0.00 | 359.63 | 6477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6600.00 | 0.00 | 359.63 | 6577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6622.04 | 0.00 | 359.63 | 6600.00 | -105.26 | 260.53 | -100.41 | 0.00 | Brushy Canyon |
| 6700.00 | 0.00 | 359.63 | 6677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6800.00 | 0.00 | 359.63 | 6777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 6900.00 | 0.00 | 359.63 | 6877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7000.00 | 0.00 | 359.63 | 6977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7100.00 | 0.00 | 359.63 | 7077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7200.00 | 0.00 | 359.63 | 7177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7300.00 | 0.00 | 359.63 | 7277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7400.00 | 0.00 | 359.63 | 7377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7500.00 | 0.00 | 359.63 | 7477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7600.00 | 0.00 | 359.63 | 7577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7700.00 | 0.00 | 359.63 | 7677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7800.00 | 0.00 | 359.63 | 7777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 7900.00 | 0.00 | 359.63 | 7877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8000.00 | 0.00 | 359.63 | 7977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8100.00 | 0.00 | 359.63 | 8077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8200.00 | 0.00 | 359.63 | 8177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8297.04 | 0.00 | 359.63 | 8275.00 | -105.26 | 260.53 | -100.41 | 0.00 | 1st Bone Spring Lime |
| 8300.00 | 0.00 | 359.63 | 8277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8400.00 | 0.00 | 359.63 | 8377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8500.00 | 0.00 | 359.63 | 8477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8600.00 | 0.00 | 359.63 | 8577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8700.00 | 0.00 | 359.63 | 8677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8800.00 | 0.00 | 359.63 | 8777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 8900.00 | 0.00 | 359.63 | 8877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9000.00 | 0.00 | 359.63 | 8977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9100.00 | 0.00 | 359.63 | 9077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9200.00 | 0.00 | 359.63 | 9177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9300.00 | 0.00 | 359.63 | 9277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9372.04 | 0.00 | 359.63 | 9350.00 | -105.26 | 260.53 | -100.41 | 0.00 | Bone Spring 1st |
| 9400.00 | 0.00 | 359.63 | 9377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9500.00 | 0.00 | 359.63 | 9477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9600.00 | 0.00 | 359.63 | 9577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9700.00 | 0.00 | 359.63 | 9677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9800.00 | 0.00 | 359.63 | 9777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9900.00 | 0.00 | 359.63 | 9877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 9922.04 | 0.00 | 359.63 | 9900.00 | -105.26 | 260.53 | -100.41 | 0.00 | Bone Spring 2nd |
| 10000.00 | 0.00 | 359.63 | 9977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10100.00 | 0.00 | 359.63 | 10077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10200.00 | 0.00 | 359.63 | 10177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10300.00 | 0.00 | 359.63 | 10277.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10400.00 | 0.00 | 359.63 | 10377.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10472.04 | 0.00 | 359.63 | 10450.00 | -105.26 | 260.53 | -100.41 | 0.00 | 3rd Bone Spring Lime |
| 10500.00 | 0.00 | 359.63 | 10477.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10600.00 | 0.00 | 359.63 | 10577.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10700.00 | 0.00 | 359.63 | 10677.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10800.00 | 0.00 | 359.63 | 10777.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 10900.00 | 0.00 | 359.63 | 10877.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 11000.00 | 0.00 | 359.63 | 10977.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 11100.00 | 0.00 | 359.63 | 11077.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 11172.04 | 0.00 | 359.63 | 11150.00 | -105.26 | 260.53 | -100.41 | 0.00 | Bone Spring 3rd |
| 11200.00 | 0.00 | 359.63 | 11177.96 | -105.26 | 260.53 | -100.41 | 0.00 | |
| 11279.08 | 0.00 | 359.63 | 11257.04 | -105.26 | 260.53 | -100.40 | 0.00 | KOP |
| 11300.00 | 2.09 | 359.63 | 11277.96 | -104.88 | 260.53 | -100.02 | 10.00 | |
| 11400.00 | 12.09 | 359.63 | 11377.07 | -92.55 | 260.45 | -87.70 | 10.00 | |
| 11500.00 | 22.09 | 359.63 | 11472.53 | -63.20 | 260.26 | -58.35 | 10.00 | |
| 11600.00 | 32.09 | 359.63 | 11561.44 | -17.71 | 259.97 | -12.88 | 10.00 | |
| 11646.76 | 36.77 | 359.63 | 11600.00 | 8.72 | 259.80 | 13.54 | 10.00 | Wolfcamp / Point of Penetration |
| 11700.00 | 42.09 | 359.63 | 11641.11 | 42.52 | 259.58 | 47.33 | 10.00 | |
| 11800.00 | 52.09 | 359.63 | 11709.11 | 115.67 | 259.10 | 120.46 | 10.00 | |
| 11900.00 | 62.09 | 359.63 | 11763.37 | 199.51 | 258.56 | 204.28 | 10.00 | |
| 12000.00 | 72.09 | 359.63 | 11802.24 | 291.51 | 257.97 | 296.25 | 10.00 | |
| 12100.00 | 82.09 | 359.63 | 11824.55 | 388.86 | 257.34 | 393.57 | 10.00 | |
| 12179.37 | 90.03 | 359.63 | 11830.00 | 467.97 | 256.83 | 472.66 | 10.00 | Landing Point |
| 12200.00 | 90.03 | 359.63 | 11829.99 | 488.60 | 256.70 | 493.29 | 0.00 | |
| 12300.00 | 90.03 | 359.63 | 11829.94 | 588.60 | 256.05 | 593.26 | 0.00 | |
| 12400.00 | 90.03 | 359.63 | 11829.89 | 688.60 | 255.40 | 693.22 | 0.00 | |

Belloq 11-2 Fed State Com 702H



Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD (ft) | INC (") | AZI (") | TVD (ft) | NS (ft) | EW (ft) | VS (ft) | DLS (°/100ft) | Comment |
|------------|------------|------------|-------------|------------|------------|------------|------------------|---------|
| 12500.00 | 90.03 | 359.63 | 11829.84 | 788.60 | 254.76 | 793.19 | 0.00 | |
| 12600.00 | 90.03 | 359.63 | 11829.79 | 888.60 | 254.11 | 893.16 | 0.00 | |
| 12700.00 | 90.03 | 359.63 | 11829.74 | 988.59 | 253.47 | 993.13 | 0.00 | |
| 12800.00 | 90.03 | 359.63 | 11829.69 | 1088.59 | 252.82 | 1093.10 | 0.00 | |
| 12900.00 | 90.03 | 359.63 | 11829.64 | 1188.59 | 252.17 | 1193.07 | 0.00 | |
| 13000.00 | 90.03 | 359.63 | 11829.59 | 1288.59 | 251.53 | 1293.04 | 0.00 | |
| 13100.00 | 90.03 | 359.63 | 11829.54 | 1388.59 | 250.88 | 1393.00 | 0.00 | |
| 13200.00 | 90.03 | 359.63 | 11829.49 | 1488.58 | 250.23 | 1492.97 | 0.00 | |
| 13300.00 | 90.03 | 359.63 | 11829.44 | 1588.58 | 249.59 | 1592.94 | 0.00 | |
| 13400.00 | 90.03 | 359.63 | 11829.39 | 1688.58 | 248.94 | 1692.91 | 0.00 | |
| 13500.00 | 90.03 | 359.63 | 11829.34 | 1788.58 | 248.30 | 1792.88 | 0.00 | |
| 13600.00 | 90.03 | 359.63 | 11829.29 | 1888.57 | 247.65 | 1892.85 | 0.00 | |
| 13700.00 | 90.03 | 359.63 | 11829.24 | 1988.57 | 247.00 | 1992.82 | 0.00 | |
| 13800.00 | 90.03 | 359.63 | 11829.18 | 2088.57 | 246.36 | 2092.79 | 0.00 | |
| 13900.00 | 90.03 | 359.63 | 11829.13 | 2188.57 | 245.71 | 2192.75 | 0.00 | |
| 14000.00 | 90.03 | 359.63 | 11829.08 | 2288.57 | 245.06 | 2292.72 | 0.00 | |
| 14100.00 | 90.03 | 359.63 | 11829.03 | 2388.56 | 244.42 | 2392.69 | 0.00 | |
| 14200.00 | 90.03 | 359.63 | 11828.98 | 2488.56 | 243.77 | 2492.66 | 0.00 | |
| 14300.00 | 90.03 | 359.63 | 11828.93 | 2588.56 | 243.13 | 2592.63 | 0.00 | |
| 14400.00 | 90.03 | 359.63 | 11828.88 | 2688.56 | 242.48 | 2692.60 | 0.00 | |
| 14500.00 | 90.03 | 359.63 | 11828.83 | 2788.56 | 241.83 | 2792.57 | 0.00 | |
| 14600.00 | 90.03 | 359.63 | 11828.78 | 2888.55 | 241.19 | 2892.53 | 0.00 | |
| 14700.00 | 90.03 | 359.63 | 11828.73 | 2988.55 | 240.54 | 2992.50 | 0.00 | |
| 14800.00 | 90.03 | 359.63 | 11828.68 | 3088.55 | 239.89 | 3092.47 | 0.00 | |
| 14900.00 | 90.03 | 359.63 | 11828.63 | 3188.55 | 239.25 | 3192.44 | 0.00 | |
| 15000.00 | 90.03 | 359.63 | 11828.58 | 3288.55 | 238.60 | 3292.41 | 0.00 | |
| 15100.00 | 90.03 | 359.63 | 11828.53 | 3388.54 | 237.95 | 3392.38 | 0.00 | |
| 15200.00 | 90.03 | 359.63 | 11828.48 | 3488.54 | 237.31 | 3492.35 | 0.00 | |
| 15300.00 | 90.03 | 359.63 | 11828.43 | 3588.54 | 236.66 | 3592.31 | 0.00 | |
| 15400.00 | 90.03 | 359.63 | 11828.38 | 3688.54 | 236.02 | 3692.28 | 0.00 | |
| 15500.00 | 90.03 | 359.63 | 11828.33 | 3788.53 | 235.37 | 3792.25 | 0.00 | |
| 15600.00 | 90.03 | 359.63 | 11828.28 | 3888.53 | 234.72 | 3892.22 | 0.00 | |
| 15700.00 | 90.03 | 359.63 | 11828.23 | 3988.53 | 234.08 | 3992.19 | 0.00 | |
| 15800.00 | 90.03 | 359.63 | 11828.18 | 4088.53 | 233.43 | 4092.16 | 0.00 | |
| 15900.00 | 90.03 | 359.63 | 11828.13 | 4188.53 | 232.78 | 4192.13 | 0.00 | |
| 16000.00 | 90.03 | 359.63 | 11828.08 | 4288.52 | 232.14 | 4292.10 | 0.00 | |
| 16100.00 | 90.03 | 359.63 | 11828.03 | 4388.52 | 231.49 | 4392.06 | 0.00 | |
| 16200.00 | 90.03 | 359.63 | 11827.98 | 4488.52 | 230.85 | 4492.03 | 0.00 | |
| 16300.00 | 90.03 | 359.63 | 11827.93 | 4588.52 | 230.20 | 4592.00 | 0.00 | |
| 16400.00 | 90.03 | 359.63 | 11827.88 | 4688.52 | 229.55 | 4691.97 | 0.00 | |
| 16500.00 | 90.03 | 359.63 | 11827.83 | 4788.51 | 228.91 | 4791.94 | 0.00 | |
| 16600.00 | 90.03 | 359.63 | 11827.78 | 4888.51 | 228.26 | 4891.91 | 0.00 | |
| 16700.00 | 90.03 | 359.63 | 11827.73 | 4988.51 | 227.61 | 4991.88 | 0.00 | |
| 16800.00 | 90.03 | 359.63 | 11827.68 | 5088.51 | 226.97 | 5091.84 | 0.00 | |
| 16900.00 | 90.03 | 359.63 | 11827.63 | 5188.51 | 226.32 | 5191.81 | 0.00 | |
| 17000.00 | 90.03 | 359.63 | 11827.58 | 5288.50 | 225.68 | 5291.78 | 0.00 | |
| 17100.00 | 90.03 | 359.63 | 11827.52 | 5388.50 | 225.03 | 5391.75 | 0.00 | |
| 17200.00 | 90.03 | 359.63 | 11827.47 | 5488.50 | 224.38 | 5491.72 | 0.00 | |
| 17300.00 | 90.03 | 359.63 | 11827.42 | 5588.50 | 223.74 | 5591.69 | 0.00 | |
| 17400.00 | 90.03 | 359.63 | 11827.37 | 5688.49 | 223.09 | 5691.66 | 0.00 | |
| 17500.00 | 90.03 | 359.63 | 11827.32 | 5788.49 | 222.44 | 5791.63 | 0.00 | |
| 17600.00 | 90.03 | 359.63 | 11827.27 | 5888.49 | 221.80 | 5891.59 | 0.00 | |
| 17700.00 | 90.03 | 359.63 | 11827.22 | 5988.49 | 221.15 | 5991.56 | 0.00 | |
| 17800.00 | 90.03 | 359.63 | 11827.17 | 6088.49 | 220.50 | 6091.53 | 0.00 | |
| 17900.00 | 90.03 | 359.63 | 11827.12 | 6188.48 | 219.86 | 6191.50 | 0.00 | |
| 18000.00 | 90.03 | 359.63 | 11827.07 | 6288.48 | 219.21 | 6291.47 | 0.00 | |
| 18100.00 | 90.03 | 359.63 | 11827.02 | 6388.48 | 218.57 | 6391.44 | 0.00 | |
| 18200.00 | 90.03 | 359.63 | 11826.97 | 6488.48 | 217.92 | 6491.41 | 0.00 | |
| 18300.00 | 90.03 | 359.63 | 11826.92 | 6588.48 | 217.27 | 6591.37 | 0.00 | |
| 18400.00 | 90.03 | 359.63 | 11826.87 | 6688.47 | 216.63 | 6691.34 | 0.00 | |
| 18500.00 | 90.03 | 359.63 | 11826.82 | 6788.47 | 215.98 | 6791.31 | 0.00 | |
| 18600.00 | 90.03 | 359.63 | 11826.77 | 6888.47 | 215.33 | 6891.28 | 0.00 | |
| 18700.00 | 90.03 | 359.63 | 11826.72 | 6988.47 | 214.69 | 6991.25 | 0.00 | |
| 18800.00 | 90.03 | 359.63 | 11826.67 | 7088.47 | 214.04 | 7091.22 | 0.00 | |
| 18900.00 | 90.03 | 359.63 | 11826.62 | 7188.46 | 213.40 | 7191.19 | 0.00 | |
| 19000.00 | 90.03 | 359.63 | 11826.57 | 7288.46 | 212.75 | 7291.16 | 0.00 | |
| 19100.00 | 90.03 | 359.63 | 11826.52 | 7388.46 | 212.10 | 7391.12 | 0.00 | |
| 19200.00 | 90.03 | 359.63 | 11826.47 | 7488.46 | 211.46 | 7491.09 | 0.00 | |
| 19300.00 | 90.03 | 359.63 | 11826.42 | 7588.45 | 210.81 | 7591.06 | 0.00 | |
| 19400.00 | 90.03 | 359.63 | 11826.37 | 7688.45 | 210.16 | 7691.03 | 0.00 | |

Belloq 11-2 Fed State Com 702H



Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD (ft) | INC (°) | AZI (°) | TVD (ft) | NS (ft) | EW (ft) | VS (ft) | DLS (°/100ft) | Comment |
|------------|------------|------------|-------------|------------|------------|------------|------------------|---------|
| 19500.00 | 90.03 | 359.63 | 11826.32 | 7788.45 | 209.52 | 7791.00 | 0.00 | |
| 19600.00 | 90.03 | 359.63 | 11826.27 | 7888.45 | 208.87 | 7890.97 | 0.00 | |
| 19700.00 | 90.03 | 359.63 | 11826.22 | 7988.45 | 208.23 | 7990.94 | 0.00 | |
| 19800.00 | 90.03 | 359.63 | 11826.17 | 8088.44 | 207.58 | 8090.90 | 0.00 | |
| 19900.00 | 90.03 | 359.63 | 11826.12 | 8188.44 | 206.93 | 8190.87 | 0.00 | |
| 20000.00 | 90.03 | 359.63 | 11826.07 | 8288.44 | 206.29 | 8290.84 | 0.00 | |
| 20100.00 | 90.03 | 359.63 | 11826.02 | 8388.44 | 205.64 | 8390.81 | 0.00 | |
| 20200.00 | 90.03 | 359.63 | 11825.97 | 8488.44 | 204.99 | 8490.78 | 0.00 | |
| 20300.00 | 90.03 | 359.63 | 11825.92 | 8588.43 | 204.35 | 8590.75 | 0.00 | |
| 20400.00 | 90.03 | 359.63 | 11825.86 | 8688.43 | 203.70 | 8690.72 | 0.00 | |
| 20500.00 | 90.03 | 359.63 | 11825.81 | 8788.43 | 203.05 | 8790.68 | 0.00 | |
| 20600.00 | 90.03 | 359.63 | 11825.76 | 8888.43 | 202.41 | 8890.65 | 0.00 | |
| 20700.00 | 90.03 | 359.63 | 11825.71 | 8988.43 | 201.76 | 8990.62 | 0.00 | |
| 20800.00 | 90.03 | 359.63 | 11825.66 | 9088.42 | 201.12 | 9090.59 | 0.00 | |
| 20900.00 | 90.03 | 359.63 | 11825.61 | 9188.42 | 200.47 | 9190.56 | 0.00 | |
| 21000.00 | 90.03 | 359.63 | 11825.56 | 9288.42 | 199.82 | 9290.53 | 0.00 | |
| 21100.00 | 90.03 | 359.63 | 11825.51 | 9388.42 | 199.18 | 9390.50 | 0.00 | |
| 21200.00 | 90.03 | 359.63 | 11825.46 | 9488.41 | 198.53 | 9490.47 | 0.00 | |
| 21300.00 | 90.03 | 359.63 | 11825.41 | 9588.41 | 197.88 | 9590.43 | 0.00 | |
| 21400.00 | 90.03 | 359.63 | 11825.36 | 9688.41 | 197.24 | 9690.40 | 0.00 | |
| 21500.00 | 90.03 | 359.63 | 11825.31 | 9788.41 | 196.59 | 9790.37 | 0.00 | |
| 21600.00 | 90.03 | 359.63 | 11825.26 | 9888.41 | 195.95 | 9890.34 | 0.00 | |
| 21700.00 | 90.03 | 359.63 | 11825.21 | 9988.40 | 195.30 | 9990.31 | 0.00 | |
| 21800.00 | 90.03 | 359.63 | 11825.16 | 10088.40 | 194.65 | 10090.28 | 0.00 | |
| 21900.00 | 90.03 | 359.63 | 11825.11 | 10188.40 | 194.01 | 10190.25 | 0.00 | |
| 22000.00 | 90.03 | 359.63 | 11825.06 | 10288.40 | 193.36 | 10290.21 | 0.00 | |
| 22013.28 | 90.03 | 359.63 | 11825.05 | 10301.68 | 193.27 | 10303.49 | 0.00 | exit |
| 22093.28 | 90.03 | 359.63 | 11825.00 | 10381.68 | 192.81 | 10383.47 | 0.00 | BHL |

Belloq 11-2 Fed State Com 702H

Well: Belloq 11-2 Fed State Com 702H
County: Eddy
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

| MD | INC | AZI | TVD | NS | EW | VS | DLS | Comment |
|------|-----|-----|------|------|------|------|-----------|---------|
| (ft) | (°) | (°) | (ft) | (ft) | (ft) | (ft) | (°/100ft) | |

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

| | |
|-------------------------|---|
| OPERATOR'S NAME: | Devon Energy Production Company LP |
| LEASE NO.: | NMNM0404441 |
| LOCATION: | Section 11, T.23 S., R.31 E., NMPM |
| COUNTY: | Eddy County, New Mexico |
| Sundry ID: | 2668767 |

| | |
|------------------------------|---------------------------------------|
| WELL NAME & NO.: | Belloq 11-2 Fed State Com 702H |
| SURFACE HOLE FOOTAGE: | 150'S & 1990'W |
| BOTTOM HOLE FOOTAGE: | 20'N & 2250'W |

COA

| | | | |
|-------------------------------|--|---|---|
| H2S | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No | |
| Potash | <input type="checkbox"/> None | <input type="checkbox"/> Secretary | <input checked="" type="checkbox"/> R-111-P |
| Cave/Karst Potential | <input checked="" type="checkbox"/> Low | <input type="checkbox"/> Medium | <input type="checkbox"/> High |
| Cave/Karst Potential | <input type="checkbox"/> Critical | | |
| Variance | <input type="checkbox"/> None | <input checked="" type="checkbox"/> Flex Hose | <input type="checkbox"/> Other |
| Wellhead | <input type="checkbox"/> Conventional | <input type="checkbox"/> Multibowl | <input checked="" type="checkbox"/> Both |
| Wellhead Variance | <input type="checkbox"/> Diverter | | |
| Other | <input checked="" type="checkbox"/> 4 String | <input type="checkbox"/> Capitan Reef | <input type="checkbox"/> WIPP |
| Other | <input checked="" type="checkbox"/> Fluid Filled | <input type="checkbox"/> Pilot Hole | <input type="checkbox"/> Open Annulus |
| Cementing | <input checked="" type="checkbox"/> Cement Squeeze | <input checked="" type="checkbox"/> EchoMeter | |
| Special Requirements | <input type="checkbox"/> Water Disposal | <input checked="" type="checkbox"/> COM | <input type="checkbox"/> Unit |
| Special Requirements Variance | <input checked="" type="checkbox"/> Break Testing | <input type="checkbox"/> Offline Cementing | |

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **750 feet** (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall

be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **10-3/4** inch intermediate casing shall be set at approximately **4450 feet** is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
Cement excess is less than 25%, more cement might be required.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

3. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
Cement excess is less than 25%, more cement might be required.

Option 2:

Operator has proposed to cement in two stages by conventionally cementing the first stage and performing a bradenhead squeeze on the second stage, contingent upon no returns to surface.

- a. First stage: Operator will cement with intent to reach the top of the Brushy Canyon.

b. Second stage:

- Operator will perform bradenhead squeeze and top-out. Cement to surface. If cement does not reach surface, the appropriate BLM office shall be notified.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

- ❖ In R111 Potash Areas if cement does not circulate to surface on the first two salt protection casing strings, the cement on the 3rd casing salt string must come to surface.

Operator has proposed to pump down 10-3/4" X 8-5/8" annulus after primary cementing stage. Operator must run Echo-meter to verify Cement Slurry/Fluid top in the annulus Or operator shall run a CBL from TD of the 8-5/8" casing to surface after the second stage BH to verify TOC.

Submit results to the BLM. No displacement fluid/wash out shall be utilized at the top of the cement slurry between second stage BH and top out. Operator must run one CBL per Well Pad.

If cement does not reach surface, the next casing string must come to surface.

Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

4. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- Cement should tie-back at least **500 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2.

Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi. Annular which shall be tested to 2100 (70% Working Pressure) psi.**

- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **10-3/4** inch intermediate casing shoe shall be **5000 (5M) psi. Annular which shall be tested to 3500 (70% Working Pressure) psi.**
- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **8-5/8** inch intermediate casing shoe shall be **5000 (5M) psi.**

Option 2:

- a. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the **13-3/8** inch surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi.**
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

BOPE Break Testing Variance

- BOPE Break Testing is ONLY permitted for 5M BOPE or less. **(Annular preventer must be tested to a minimum of 70% of BOPE working pressure and shall be higher than the MASP)**
- BOPE Break Testing is NOT permitted to drilling the production hole section.
- Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation.
- While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Any well control event while drilling require notification to the BLM Petroleum Engineer **(575-706-2779)** prior to the commencement of any BOPE Break Testing operations.
- A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable).
- The BLM is to be contacted **(575-361-2822 Eddy County)** 4 hours prior to BOPE tests.
- As a minimum, a full BOPE test shall be performed at 14-day intervals.
- In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per Onshore Oil and Gas Order No. 2.
- If in the event break testing is not utilized, then a full BOPE test would be conducted.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.


C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.



INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.

ALL DIMENSIONS APPROXIMATE

CACTUS WELLHEAD LLC

MATADOR RESOURCES
WOLFCAMP A WELLS (TEXAS)

20" x 13-3/8" x 10-3/4" x 8-5/8" x 5-1/2" MBU-4T-SOW Wellhead
With 13-5/8" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head,
10-3/4" & 8-5/8" Mandrel Hangers And 5-1/2" Slip Casing Hanger

| | | |
|-------------|-----|------------|
| DRAWN | DLE | 09AUG19 |
| APPRV | | |
| DRAWING NO. | | HBE0000156 |

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 104817

CONDITIONS

| | |
|---|--|
| Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102 | OGRID: 6137 |
| | Action Number: 104817 |
| | Action Type: [C-103] NOI Change of Plans (C-103A) |

CONDITIONS

| Created By | Condition | Condition Date |
|------------|---|----------------|
| kpickford | Adhere to previous NMOCD Conditions of Approval | 5/9/2022 |