Form 3160-3 FORM APPROVED OMB No. 1004-0137 (June 2015) Expires: January 31, 2018 **UNITED STATES** DEPARTMENT OF THE INTERIOR 5. Lease Serial No. BUREAU OF LAND MANAGEMENT APPLICATION FOR PERMIT TO DRILL OR REENTER 6. If Indian, Allotee or Tribe Name 7. If Unit or CA Agreement, Name and No. DRILL REENTER 1a. Type of work: 1b. Type of Well: Oil Well Gas Well Other 8. Lease Name and Well No. 1c. Type of Completion: Hydraulic Fracturing Single Zone Multiple Zone 2. Name of Operator 9. API Well No. 3a. Address 3b. Phone No. (include area code) 10. Field and Pool, or Exploratory 4. Location of Well (Report location clearly and in accordance with any State requirements.*) 11. Sec., T. R. M. or Blk. and Survey or Area At surface At proposed prod. zone 14. Distance in miles and direction from nearest town or post office* 12. County or Parish 13. State 15. Distance from proposed* 16. No of acres in lease 17. Spacing Unit dedicated to this well location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 18. Distance from proposed location* 19. Proposed Depth 20. BLM/BIA Bond No. in file to nearest well, drilling, completed, applied for, on this lease, ft. 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 22. Approximate date work will start* 23. Estimated duration 24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable) 1. Well plat certified by a registered surveyor. 4. Bond to cover the operations unless covered by an existing bond on file (see 2. A Drilling Plan. Item 20 above). 3. A Surface Use Plan (if the location is on National Forest System Lands, the 5. Operator certification. SUPO must be filed with the appropriate Forest Service Office). 6. Such other site specific information and/or plans as may be requested by the 25. Signature Name (Printed/Typed) Date Title Approved by (Signature) Name (Printed/Typed) Date Title Office Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction



*(Instructions on page 2)

District I

1625 N. French Dr., Hobbs, NM 88240 Phone: (575) 393-6161 Fax: (575) 393-0720 District II

811 S. First St., Artesia, NM 88210 Phone: (575) 748-1283 Fax: (575) 748-9720

160

<u>District III</u> 1000 Rio Brazos Road, Aztec, NM 87410 Phone: (505) 334-6178 Fax: (505) 334-6170 District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505 Phone: (505) 476-3460 Fax: (505) 476-3462 State of New Mexico

Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr.

Santa Fe, NM 87505

Form C-102
Revised August 1,
2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT


WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number		² Pool Code ³ Pool Name		
30-015-49915		51120		
⁴ Property Code		⁵ Pr	operty Name	⁶ Well Number
333223		MALCO B	6 FEDERAL COM	4 H
⁷ OGRID No.		8 O _I	perator Name	⁹ Elevation
330211		REDWOOD	OPERATING LLC	3450.3

Surface Location


Surface Location										
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County	
4	5	18 S	27 E		330	NORTH	978	WEST	EDDY	
¹¹ Bottom Hole Location If Different From Surface										
UL or lot no.	Section	n Township Range Lot I		Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County	
4	6	18 S	27 E		330	NORTH	1	WEST	EDDY	
12 Dedicated Acres	s ¹³ Joint	or Infill 14	Consolidation	n Code	e ¹⁵ Order No.					

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the




Operator Name: REDWOOD OPERATING LLC MALCO B 6 FEDERAL COM 4H MALCO B 6 FEDERAL COM 4H MALCO B 6 FEDERAL COM AND AND AND AND AND AND AND AN	ntent	(X)	X As Drill	ed										
REDWOOD OPERATING LLC MALCO B 6 FEDERAL COM 4H MALCO B 6 FEDERAL COM MALCO B 6 FROM N/S METAL COM MALCO B 6 FEDERAL COM MALCO B 6 FROM N/S METAL COM MALCO B 6 FROM N/S ME	API#													
Gick Off Point (KOP) UL Section Township Range 32.7830733 Longitude 104.3061021 From N/S NORTH 978 WEST EDDY NAD 83 First Take Point (FTP) UL Section Township Range 1 Lot 188 27E 1 330 NORTH 100 EAST EDDY Latitude 32.7831486 Longitude 104.3096110 Longitude 104.3096110 Longitude 104.3096110 Longitude 104.3096110 NAD 83 Latitude 32.7833914 Longitude 104.3096110 NAD 83 Latitude 32.7833914 Longitude 104.3261795 NAD 83 Section Township Range Lot 4 330 NORTH 100 WEST EDDY Latitude 32.7833914 Longitude 104.3261795 NAD 83	Ope	rator Nan	ne:				Property Na	ame:					Well Number	
UL Section 18S 27E 4 330 NORTH 978 WEST County EDDY Latitude 32.7830733	RED	WOOD	OPERATIN	NG LLC			MA	LCO E	6 FEDER	RAL CO	MC		4H	
UL Section 18S 27E 4 330 NORTH 978 WEST County EDDY Latitude 32.7830733	(ick C	off Point (KOP)											
32.7830733 104.3061021 83 104.3061021 83 104.3061021 83 104.3061021 83 104.3061021 84 105 105 105 105 105 105 105 10		Section	Township	Range 27E					Feet 978	From WE	n E/W ST	County EDDY		
UL Section 18S 27E 1 1 330 NORTH 100 EAST EDDY Latitude 32.7831486 Longitude 104.3096110 Longitude 104.3096110 Sast Take Point (LTP) UL Section 18S 27E 4 330 NORTH 100 From E/W EDDY Latitude 32.7833914 Longitude 104.3096110 Sast Take Point (LTP) UL Section 18S 27E 4 330 NORTH 100 WEST EDDY Latitude 32.7833914 Longitude 104.3261795 Sast Take Point (LTP) Longitude Sast Take Point (LTP) Longitude 104.3261795 Sast Take Point (LTP) Longitude 104.3261795 Sast Take Point (LTP) Sast Take Point (LTP) Longitude 104.3261795 Sast Take Point (LTP) Sast Take Point (LTP) Longitude 104.3261795 Sast Take Point (LTP) Sast	Latitu		30733		1	Longitu		102	l.	<u> </u>				
Section Township Range 27E 1 330 NORTH 100 EAST EDDY	irst 1	ake Poin	t (FTP)											
ast Take Point (LTP) UL Section 188	UL		Township 18S	Range 27E			From N NORT	/s 「 H	Feet 100	From	n E/W S T	County EDDY		
UL Section 18S 27E 4 330 NORTH 100 Feet DDY Latitude 32.7833914 Lot 4 330 NORTH 100 WEST EDDY Longitude 104.3261795 83 So this well the defining well for the Horizontal Spacing Unit? If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit. API#	Latitu		1486	I		Longitu		5110						
32.7833914 104.3261795 83 s this well the defining well for the Horizontal Spacing Unit? s this well an infill well? f infill is yes please provide API if available, Operator Name and well number for Defining well for Horizonta Spacing Unit. API#		Section	Township	Range 27E		Feet 330	From N/S NORTH	Feet 100	Fron WE	m E/W E ST	Count EDD	Y		
s this well an infill well? f infill is yes please provide API if available, Operator Name and well number for Defining well for Horizonta spacing Unit. API#	Latitu		833914	l		Longitu								
API#	s this	well an i	nfill well?					e and	well num	ber fo	r Defi	ning well	for Horizontal	
Operator Name: Property Name: Well Numbe		ng Unit.		1										
				1										

KZ 06/29/2018



SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO LOCATION VERIFICATION MAP



REDWOOD OPERATING LLC

MALCO B 6 FEDERAL COM 4H

LOCATED 330 FT. FROM THE NORTH LINE

AND 978 FT. FROM THE WEST LINE OF

SECTION 5, TOWNSHIP 18 SOUTH,


RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEY NO. 8546

SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF CR. 201 (CHALK BLUFF) & CR. 227 (LITTLE DIAMOND) GO NORTHWEST ON CR. 201 FOR APPROX. 0.4 OF A MILE, GO SOUTHWEST ON 20' CALICHE LEASE ROAD FOR APPROX. 0.3 OF A MILE, GO NORTH ON 20' CALICHE LEASE ROAD FOR APPROX. 0.4 OF A MILE, GO WEST ON 15' CALICHE LEASE ROAD FOR APPROX. 300' TO SOUTHWEST PAD CORNER OF AN EXISTING PAD & BEGIN ROAD SURVEY, FOLLOW ROAD SURVEY WEST FOR APPROX. 482' TO THE SOUTHEAST PAD CORNER FOR THIS LOCATION.

REDWOOD OPERATING LLC

MALCO B 6 FEDERAL COM 4H

LOCATED 330 FT. FROM THE NORTH LINE

AND 978 FT. FROM THE WEST LINE OF

SECTION 5, TOWNSHIP 18 SOUTH,

RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEY NO. 8546

SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO AERIAL PHOTO



NOT TO SCALE AERIAL PHOTO: GOOGLE EARTH DECEMBER 2019

REDWOOD OPERATING LLC

MALCO B 6 FEDERAL COM 4H

LOCATED 330 FT. FROM THE NORTH LINE

AND 978 FT. FROM THE WEST LINE OF

SECTION 5, TOWNSHIP 18 SOUTH,


RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEY NO. 8546

SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
ACCESS AERIAL ROUTE MAP



NOT TO SCALE AERIAL PHOTO: GOOGLE EARTH DECEMBER 2019

REDWOOD OPERATING LLC

MALCO B 6 FEDERAL COM 4H

LOCATED 330 FT. FROM THE NORTH LINE

AND 978 FT. FROM THE WEST LINE OF


SECTION 5, TOWNSHIP 18 SOUTH,

RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEY NO. 8546




Received by OCD: 8/22/2022 2:27:57 PM


I, FILIMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTLY AND MESSION RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE

BEST OF MY KNOWLED MEET THE MINIMUM S

FILIMON F.

CROSS-SECTIONS





REDWOOD OPERATING LLC GRADING PLAN AND CROSS SECTIONS FOR MALCO B 6 FEDERAL COM 4H SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

6789 CU. YD | 8022 CU. YD | 1233 CU. YD (FILL) EARTHWORK QUANTITIES ARE ESTIMATED

120

SCALE 1" = 120' - 1" = 20' VER

60

SHEET 2-3 SURVEY NO. 8546


Received by OCD: 8/22/2022 2:27:57 PM

I, FILIMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTLY AND MESSION RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE

BEST OF MY KNOWLEDO

FILIMON F. JARAMI

CROSS-SECTIONS



REDWOOD OPERATING LLC GRADING PLAN AND CROSS SECTIONS FOR MALCO B 6 FEDERAL COM 4H SECTION 5, TOWNSHIP 18 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 30, 2020

SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

CUT	FILL	NET
6789 CU. YD	8022 CU. YD	1233 CU. YD (FILL)
EARTHW	ORK QUANTITIES	ARE ESTIMATED

120

SCALE 1" = 120' - 1" = 20' VER

SHEET 3-3 SURVEY NO. 8546

012 60

I. Operator: Redwood Operating LLC

State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Date: 12 / 21 / 2021

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

OGRID:

330211

Amendmen	t due to □ 19.15.27	7.9.D(6)(a) NMA(C □ 19.15.27.9.D((6)(b) NMAC □ (Other.
		()(u) 1 (i) 1	= 1,,110,2,1,5,12 ((0)(0)11111110	O VII. 01.
				wells proposed to	be drilled or proposed to
API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
	Sec. 5 T18S R27E	330 FNL 978 FWL	100	100	1,000
			al delivery point. Completion	Initial I	Flow First Production
	8/1/2022	8/21/2022	9/21/2022	9/21/202	2 9/21/2022
ces: ☑ Atta f 19.15.27.8 Practices:	ach a complete desc B NMAC.	cription of the act	ions Operator wil	l take to comply	with the requirements of
	API API API API API API API API	following information for each agle well pad or connected to a API ULSTR Sec. 5 T18S R27E Int Name: DCP Midstream Liname: Provide the following informated from a single well pad or consect form a complete description of the	following information for each new or recompleted well pad or connected to a central delivery particle. API ULSTR Footages Sec. 5 T18S R27E 330 FNL 978 FWL Int Name: DCP Midstream Linam Ranch Processing Provide the following information for each newed from a single well pad or connected to a central pate. API Spud Date TD Reached Date 8/1/2022 8/21/2022 Practices: X Attach a complete description of the act of 19.15.27.8 NMAC. Practices: X Attach a complete description of the act of 19.15.27.8 NMAC.	following information for each new or recompleted well or set of rigle well pad or connected to a central delivery point. API ULSTR Footages Anticipated Oil BBL/D Sec. 5 T18S R27E 330 FNL 978 FWL 100 Int Name: DCP Midstream Linam Ranch Processing Plant/ Durango Mids Provide the following information for each new or recompleted well from a single well pad or connected to a central delivery point. API Spud Date TD Reached Completion Commencement B/1/2022 B/21/2022 9/21/2022 Part: XAttach a complete description of how Operator will size septoms: Attach a complete description of the actions Operator will f 19.15.27.8 NMAC. Practices: X Attach a complete description of Operator's best in	following information for each new or recompleted well or set of wells proposed to a gle well pad or connected to a central delivery point. API ULSTR Footages Anticipated Gas MCF/D Sec. 5 T18S R27E 330 FNL 978 FWL 100 100 Int Name: DCP Midstream Linam Ranch Processing Plant/ Durango Midstream [See It Provide the following information for each new or recompleted well or set of wells and from a single well pad or connected to a central delivery point. API Spud Date TD Reached Completion Commencement Date Back It Back It 8/1/2022 8/21/2022 9/21/2022 9/21/2022 9/21/2022 9/21/2022

Section 2 – Enhanced Plan EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

🔀 Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering	Available Maximum Daily Capacity
			Start Date	of System Segment Tie-in

XI. Map. \square Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the
production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of
the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII.	Line Capaci	ty. The natural	gas gathering	system \square	will □ will	not have	capacity to	gather	100% of th	ne anticipated	natural ga	ıs
prod	uction volum	e from the well	prior to the da	te of first p	production.							

XIII. Line Pressure. Operator \square does \square does not anticipate that its existing well(s) connected to the same segment, or portion, of	f the
natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well	(s).

_									
1 1	Attach (Onaratar	'a nlan	to monogo	nroduction	in recnance	to the inc	creased line p	raccure

XIV. Confidentiality: \Box Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided	d in
Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information	tion
for which confidentiality is asserted and the basis for such assertion.	

(i)

Section 3 - Certifications Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal: 🛮 Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or ☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. If Operator checks this box, Operator will select one of the following: Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or Venting and Flaring Plan.

Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including: power generation on lease; (a) **(b)** power generation for grid; compression on lease; (c) (d) liquids removal on lease; reinjection for underground storage; (e) **(f)** reinjection for temporary storage; **(g)** reinjection for enhanced oil recovery; fuel cell production; and (h)

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

other alternative beneficial uses approved by the division.

- (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: Delilah Flores
Printed Name: Delilah Flores
Title: Regulatory Technician I
E-mail Address: regulatory@redwoodoperating.com
Date: 12/21/2021
Phone:
575-748-1288
OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)
Approved By:
Title:
Approval Date:
Conditions of Approval:

VI. Separation Equipment:

Redwood Operating LLC production facilities include separation equipment designed to efficiently separate gas from liquid phases to optimize gas capture based on projected and estimated volumes from the targeted pool of our completion project. Redwood Operating LLC will utilize flowback separation equipment and production separation equipment designed and built to industry specifications after the completion to optimize gas capture and send gas to sales or flare based on analytical composition. Redwood Operating LLC operates facilities that are typically multi-well facilities. Production separation equipment is upgraded prior to new wells being completed, if determined to be undersized or inadequate. This equipment is already on-site and tied into our sales gas lines prior to the new drill operations.

VII. Operational Practices:

- 1. Subsection (A) Venting and Flaring of Natural Gas. Redwood Operating LLC understands the requirements of NMAC 19.15.27.8 which outlines that the venting and flaring of natural gas during drilling, completion or production operations that constitutes waste as defined in 19.15.2 are prohibited.
- 2. Subsection (B) Venting and Flaring during drilling operations. This gas capture plan isn't for a well being drilled.
- 3. Subsection (C) Venting and flaring during completion or recompletion. Flowlines will be routed for flowback fluids into a completion or storage tank and if feasible under well conditions, flare rather than vent and commence operation of a separator as soon as it is technically feasible for a separator to function.
 - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
- 4. Subsection (D) Venting and flaring during production operations o At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
 - Monitor manual liquid unloading for wells on-site or in close proximity (<30 minutes' drive time), take reasonable actions to achieve a stabilized rate and pressure at the earliest practical time, and take reasonable actions to minimize venting to the maximum extent practicable.
 - Redwood Operating LLC will not vent or flare except during the approved activities listed in NMAC 19.15.27.8 (D) 14.
- 5. Subsection (E) Performance standards o All tanks and separation equipment are designed for maximum throughput and pressure to minimize waste.
 - If a flare is utilized during production operations it will have a continuous pilot and is located more than 100 feet from any known well or storage tanks.
 - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.

- 6. Subsection (F) Measurement or estimation of vented and flared natural gas o Measurement equipment is installed to measure the volume of natural gas flared from process piping.
 - When measurement isn't practicable, estimation of vented and flared natural gas will be completed as noted in 19.15.27.8 (F) 5-6.

VIII. Best Management Practices:

- 1. Redwood Operating LLC has adequate storage and takeaway capacity for wells it chooses to complete as the flowlines at the sites are already in place and tied into a gathering system.
- 2. Redwood Operating LLC will flare rather than vent vessel blowdown gas when technically feasible during active and/or planned maintenance to equipment on-site.
- 3. Redwood Operating LLC combusts natural gas that would otherwise be vented or flared, when technically feasible.
- 4. Redwood Operating LLC will shut in wells in the event of a takeaway disruption, emergency situation, or other operations where venting or flaring may occur due to equipment failures.

Well Name: MALCO B 6 FEDERAL COM



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

08/22/2022

APD ID: 10400074762

Submission Date: 06/07/2021

Highlighted data reflects the most recent changes

Operator Name: REDWOOD OPERATING LLC

Well Number: 4H

Well Type: OIL WELL

Well Work Type: Drill

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
4116394	QUATERNARY	3450	0	0	ALLUVIUM	NONE	N
4116395	QUEEN	2785	665	665	SILTSTONE	NATURAL GAS, OIL	N
4116396	GRAYBURG	2369	1081	1081	DOLOMITE, SILTSTONE	NATURAL GAS, OIL	N
4116397	SAN ANDRES	2116	1334	1334	DOLOMITE	NATURAL GAS, OIL	N
4116398	GLORIETA	785	2665	2665	SILTSTONE	NATURAL GAS, OIL	Y
4116399	YESO	713	2737	2737	DOLOMITE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M Rating Depth: 8778

Equipment: Rotating Head, Mud Gas Separator

Requesting Variance? NO

Variance request:

Testing Procedure: The BOP/BOPE test shall include a low pressure test from 250 to 300spi. The test will be held for a minimum of 10 minutes if test plug and 30 minutes without a test plug. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1367 psig (0.052*2858' TVD * 9.2ppg) less than 2900 bottom hole pressure. Will test to 2000psi for 30 minutes.

Choke Diagram Attachment:

choke_manifold_diagram_20210517121729.pdf

choke_manifold_20210517121736.pdf

BOP Diagram Attachment:

bop_diagram_20210517121742.pdf

Well Name: MALCO B 6 FEDERAL COM Well Number: 4H

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	375	0	375	3450	3075	375	J-55	48	ST&C	3.95 3	4.66 7	BUOY	28.1 97	BUOY	4.74
2	INTERMED IATE	12.2 5	9.625	NEW	API	N	0	1230	0	1230	3450	2220	1230	J-55	36	ST&C	3.15 8	7.04	BUOY	10.5 05	BUOY	7.04
3	PRODUCTI ON	8.75	7.0	NEW	API	N	0	1950	0	1950	3450	1500	1950	L-80	26	LT&C		2.43 8	BUOY	4.81 5	BUOY	2.41 3
4	PRODUCTI ON	8.75	7.0	NEW	API	N	1950	3050	1950	3050	1500	400	1100	L-80		OTHER - BTC	3.16 6	2.45 2	BUOY	4.81 5	BUOY	2.43 8
5	PRODUCTI ON	8.75	5.5	NEW	API	N	3050	8778	3050	8778	400	-5328	5728	L-80		OTHER - BTC	4.07 8	2.70 3	BUOY	4.12	BUOY	2.62 2

Casing Attachments

Casing ID: 1 String SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Surface_Csg_20210517123423.pdf

Operator Name: REDWOOD OPERATING LLC
Well Name: MALCO B 6 FEDERAL COM Well Number: 4H

sing Attachments
Casing ID: 2 String INTERMEDIATE
Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Intermediate_Csg_20210517123740.pdf
Casing ID: 3 String PRODUCTION
Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Production_Csg_20210517123942.pdf
Casing ID: 4 String PRODUCTION
Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Production_Csg_20210517124146.pdf

Well Name: MALCO B 6 FEDERAL COM Well Number: 4H

Casing Attachments

Casing ID: 5

String

PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

 $Production_Csg_20210517124333.pdf$

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Тор МD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0		0	0

PRODUCTION	Lead	0	0	0	0	0	0	0	0	0	

SURFACE	Lead	0	375	420	1.34	14.8	261	100	Class C + 1%	20bbls Gel Spacer 50sx
									PF1	of 11# Scavenger
										Cement

INTERMEDIATE	Lead	0	1230	250	1.72	13.5	385.2	100	Class C+ 4%PF20+1% PF1+.0125#/skP F29 + .4%PF45	20bbls Gel Spacer 50sx of 11# Scavenger Cement
INTERMEDIATE	Tail	0	1230	200	1.34	14.8	385.2 3	100	Class C+ .1%PF1	20bbls Gel Spacer 50sx of 11# Scavenger Cement
PRODUCTION	Lead	0	8778	475	1.82	12.9	2217. 33	35	35/65 Perlite/C 5% PF44 +6% PF20+.2%PF13+ 3pps PF42+.	20bbls Gel Spacer 50sx of 11# Scavenger Cement

Well Name: MALCO B 6 FEDERAL COM

Well Number: 4H

String Type	Lead/Tail	Stage Tool Depth	Тор МD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
										4ppsPF45+.125p psPF29	
PRODUCTION	Tail		0	8778	1450	1.48	13	2217. 33	35		20bbls Gel Spacer 50sx of 11# Scavenger Cement

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: BOPE Brine Water

Describe the mud monitoring system utilized: Pason PVT with pit volume recorder

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	НА	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	375	SPUD MUD	8.5	10	74.8	0.1	11		12000	15	
375	1230	LSND/GEL	8.3	10	74.8	0.1	11		12000	15	
1230	8778	LSND/GEL	8.3	9.2	74.8	0.1	11		12000	15	The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1367 psig (0.052*2858' TVD*9.2ppg) less than 2900 bottom hole pressure

Well Name: MALCO B 6 FEDERAL COM Well Number: 4H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

None

List of open and cased hole logs run in the well:

CNL/FDC, GAMMA RAY LOG, FORMATION DENSITY COMPENSATED LOG,

Coring operation description for the well:

Will evaluate after logging to determine the necessity for sidewall coring

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 1367 Anticipated Surface Pressure: 733

Anticipated Bottom Hole Temperature(F): 95

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? NO

Hydrogen sulfide drilling operations

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Malco_B_6_Federal_Com_4H_Preliminary_Plan_1_20210518124040.pdf

Horizontal_Spacing_Unit_20210518124047.pdf

GasCapturePlanFormFinal_000_20210518124054.pdf

escape_Route_20210518124102.pdf

H2S Plan 20210520094825.pdf

Drilling_Plan_20210520094838.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Other Variance attachment:

Cactus_Wellhead_installation_Procedure_20210518124128.pdf


Variance_request_20210518124136.pdf



Received by OCD: 8/22/2022 2:27:57 PM


Released to Imaging: 8/29/2022 9:26:06 AM

Mack Energy Corporation MANIFOLD SCHEMATIC Exhibit #12



Mack Energy Corporation Exhibit #11

Exhibit #11
MIMIMUM CHOKE MANIFOLD
3,000, 5,000, and 10,000 PSI Working Pressure
3M will be used
3 MWP - 5 MWP - 10 MWP



Mud Pit

Reserve Pit

* Location of separator optional

Released to Imaging: 8/29/2022 9:26:06 AM

Below Substructure

Mimimum requirements

		3.0	00 MWP	Mimimun		.000 MWP		10	0,000 MWP	
No.		LD.	Nominal	Rating	I.D.	Nominal	Rating	I.D.	Nominal	Rating
1	Line from drilling Spool		3"	3,000		3"	5,000		3"	10,000
2	Cross 3" x 3" x 3" x 2"			3,000			5,000			
2	Cross 3" x 3" x 3" x 2"									10,000
3	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
4	Valve Gate Plug	1 13/16		3,000	1 13/16		5,000	1 13/16		10,000
4a	Valves (1)	2 1/16		3,000	2 1/16		5,000	2 1/16		10,000
5	Pressure Gauge			3,000			5,000			10,000
6	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
7	Adjustable Choke (3)	2"		3,000	2"		5,000	2"		10,000
8	Adjustable Choke	1"		3,000	1"		5,000	2"		10,000
9	Line		3"	3,000		3"	5,000		3"	10,000
10	Line		2"	3,000		2"	5,000		2"	10,000
11	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
12	Line		3"	1,000		3"	1,000		3"	2,000
13	Line		3"	1,000		3"	1,000		3"	2,000
14	Remote reading compound Standpipe pressure quage			3,000			5,000			10,000
15	Gas Separator		2' x5'			2' x5'			2' x5'	
16	Line		4"	1,000		4"	1,000		4"	2,000
17	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000

- (1) Only one required in Class 3M
- (2) Gate valves only shall be used for Class 10 M
- (3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling.

EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTION

- . All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX. Use only BX for 10 MWP.
- All lines shall be securely anchored.
- 4. Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge.
- Line from drilling spool to choke manifold should bee as straight as possible. Lines downstream from chokes shall make turns by large bends or 90 degree bends using bull plugged tees


Mack Energy Corporation

Minimum Blowout Preventer Requirements

5000 psi Working Pressure 13 5/8 inch- 5 MWP 11 Inch - 5 MWP

Stack Requirements

	Stack Requireme	IIIS	
NO.	Items	Min. I.D.	Min. Nominal
1	Flowline		2"
2	Fill up line		2"
3	Drilling nipple		
4	Annular preventer		
5	Two single or one dual hydraulically operated rams		
6a	Drilling spool with 2" min. kill line and 3" min choke line outlets		2" Choke
6b	2" min. kill line and 3" min. choke line outlets in ram. (Alternate to 6a above)		
7	Valve Gate Plug	3 1/8	
8	Gate valve-power operated	3 1/8	
9	Line to choke manifold		3"
10	Valve Gate Plug	2 1/16	
- 11	Check valve	2 1/16	
12	Casing head		
13	Valve Gate Plug	1 13/16	
14	Pressure gauge with needle valve		
15	Kill line to rig mud pump manifold		2"



OPTIONAL

	OI IIO.		
16	Flanged Valve	1 13/16	

CONTRACTOR'S OPTION TO

CONTRACTOR'S OPTION TO FURNISH:

- All equipment and connections above bradenhead or casinghead. Working pressure of preventers to be 2000 psi minimum.
- Automatic accumulator (80 gallons, minimum) capable of closing BOP in 30 seconds or less and, holding them closed against full rated working pressure.
- BOP controls, to be located near drillers' position.
- Kelly equipped with Kelly cock.
- Inside blowout preventer or its equivalent on derrick floor at all times with proper threads to fit pipe being used.
- Kelly saver-sub equipped with rubber casing protector at all times.
- Plug type blowout preventer tester.
- Extra set pipe rams to fit drill pipe in use on location at all times.
- Type RX ring gaskets in place of Type R.

MEC TO FURNISH:

- Bradenhead or casing head and side valves.
- 2. Wear bushing. If required.

GENERAL NOTES:

- Deviations from this drawing may be made only with the express permission of MEC's Drilling Manager.
- All connections, valves, fittings, piping, etc., subject to well or pump pressure must be flanged (suitable clamp connections acceptable) and have minimum working pressure equal to rated working pressure of preventers up through choke valves must be full opening and suitable for high pressure mud service.
- Controls to be of standard design and each marked, showing opening and closing position
- Chokes will be positioned so as not to hamper or delay changing of choke beans.

- Replaceable parts for adjustable choke, or bean sizes, retainers, and choke wrenches to be conveniently located for immediate use.
- All valves to be equipped with hand-wheels or handles ready for immediate use.
- Choke lines must be suitably anchored.
- Handwheels and extensions to be connected and ready for
- Valves adjacent to drilling spool to be kept open. Use outside valves except for emergency.
- All seamless steel control piping (2000 psi working pressure) to have flexible joints to avoid stress. Hoses will be permitted.
- Casinghead connections shall not be used except in case of emergency.

Released to Imaging: 8/29/2022 9:26:06 AM

 Does not use kill line for routine fill up operations.

OperatorRedwood Operating LLCUnitsfeet, °/100ft17:11 Friday, December 11, 2020 Page 1 of 4FieldRed LakeCountyEddyVertical Section Azimuth 270.99

Well Name Malco B 6 Federal Com #4H State New Mexico Survey Calculation Method Minimum Curvature
Plan 1 Country USA Database Access

Location SL: 330 FNL & 978 FWL Section 5-T18S-R27E BHL: Map Zone UTM Lat Long Ref

330 FNL & 1 FWL Secition 6-T18S-27E

Site Surface X 1853853 Surface Long
Slot Name UWI Surface Y 11900342.3 Surface Lat
Well Number 4H API Surface Z 3468.3 Global Z Ref KB
Project MD/TVD Ref KB Ground Level 3450.3 Local North Ref Grid

DIRECTIONAL WELL PLAN

MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN* S	SysTVD*
*** TIE (at MD	= 1963 00)	hah	ft	ft	ft	°/1∩∩ f t	ft	ft	ft	ft
1963.00	0.00	0.0	1963.00	0.00	0.00		0.00	1853853.00	11900342.30	1505.30
2000.00	0.00	0.0	2000.00	0.00	0.00	0.00	0.00	1853853.00	11900342.30	1468.30
2050.00	0.00	0.0	2050.00	0.00	0.00	0.00	0.00	1853853.00	11900342.30	1418.30
*** KOP 9 DEG				0.00	0.00	0.00	0.00	1000000.00	11000012.00	1110.00
2063.00	0.00	0.0	2063.00	0.00	0.00	0.00	0.00	1853853.00	11900342.30	1405.30
2100.00	2.96	271.0	2099.98	0.02	-0.96	8.00	0.96	1853852.04	11900342.32	1368.32
2100.00	2.00	27 1.0	2000.00	0.02	-0.50	0.00	0.50	1000002.04	110000-12.02	1000.02
2150.00	6.96	271.0	2149.79	0.09	-5.28	8.00	5.28	1853847.72	11900342.39	1318.51
2200.00	10.96	271.0	2199.17	0.23	-13.06	8.00	13.06	1853839.94	11900342.53	1269.13
2250.00	14.96	271.0	2247.88	0.42	-24.27	8.00	24.27	1853828.73	11900342.72	1220.42
2300.00	18.96	271.0	2295.70	0.67	-38.85	8.00	38.86	1853814.15	11900342.97	1172.60
2350.00	22.96	271.0	2342.38	0.98	-56.73	8.00	56.74	1853796.27	11900343.28	1125.92
2400.00	26.96	271.0	2387.70	1.34	-77.82	8.00	77.83	1853775.18	11900343.64	1080.60
2450.00	30.96	271.0	2431.44	1.76	-102.02	8.00	102.04	1853750.98	11900344.06	1036.86
2500.00	34.96	271.0	2473.38	2.23	-129.22	8.00	129.24	1853723.78	11900344.53	994.92
2550.00	38.96	271.0	2513.33	2.75	-159.27	8.00	159.29	1853693.73	11900345.05	954.97
2600.00	42.96	271.0	2551.08	3.32	-192.03	8.00	192.06	1853660.97	11900345.62	917.22
2650.00	46.96	271.0	2586.45	3.93	-227.35	8.00	227.39	1853625.65	11900346.23	881.85
2700.00	50.96	271.0	2619.28	4.58	-265.05	8.00	265.09	1853587.95	11900346.88	849.03
2750.00	54.96	271.0	2649.39	5.27	-304.95	8.00	304.99	1853548.05	11900347.57	818.91
*** 55 DEGREE	E TANGEN	Γ (at MD =	2750.50)							
2750.50	55.00	271.0	2649.67	5.28	-305.36	8.00	305.40	1853547.64	11900347.58	818.63
2800.00	55.00	271.0	2678.07	5.98	-345.90	0.00	345.95	1853507.10	11900348.28	790.23
2850.00	55.00	271.0	2706.75	6.69	-386.85	0.00	386.91	1853466.15	11900348.99	761.55
2900.00	55.00	271.0	2735.42	7.39	-427.80	0.00	427.87	1853425.20	11900349.69	732.88
2950.00	55.00	271.0	2764.10	8.10	-468.75	0.00	468.82	1853384.25	11900350.40	704.20
3000.00	55.00	271.0	2792.78	8.81	-509.71	0.00	509.78	1853343.29	11900351.11	675.52
*** 12 DEGREE										
3000.50	55.00	271.0	2793.07	8.82	-510.12	0.00	510.19	1853342.88	11900351.12	675.23
3050.00	60.94	271.0	2819.31	9.54	-552.05	12.00	552.14	1853300.95	11900351.84	648.99
3100.00	66.94	271.0	2841.27	10.32	-596.94	12.00	597.03	1853256.06	11900352.62	627.03
3150.00	72.94	271.0	2858.41	11.13	-643.88	12.00	643.98	1853209.12	11900353.43	609.89
3200.00	78.94	271.0	2870.55	11.96	-692.36	12.00	692.46	1853160.64	11900354.26	597.75
3250.00	84.94	271.0	2877.56	12.82	-741.83	12.00	741.94	1853111.17	11900355.12	590.74
*** LANDING F	POINT (at M	MD = 3294	00)							
3294.00	90.22	271.0	2879.41	13.58	-785.77	12.00	785.89	1853067.23	11900355.88	588.89
3300.00	90.22	271.0	2879.39	13.68	-791.77	0.00	791.89	1853061.23	11900355.98	588.91
3350.00	90.22	271.0	2879.20	14.55	-841.76	0.00	841.89	1853011.24	11900356.85	589.10
3400.00	90.22	271.0	2879.01	15.41	-891.75	0.00	891.89	1852961.25	11900357.71	589.29
Page 1 of 4	30.22	21 1.0	2013.01	10.71	SES v5		031.03	1002001.20		makinhole.com

OperatorRedwood Operating LLCUnitsfeet, °/100ft17:11 Friday, December 11, 2020 Page 2 of 4FieldRed LakeCountyEddyVertical Section Azimuth 270.99

Well Name Malco B 6 Federal Com #4H State New Mexico Survey Calculation Method Minimum Curvature
Plan 1 Country USA Database Access

Location SL: 330 FNL & 978 FWL Section 5-T18S-R27E BHL: Map Zone UTM Lat Long Ref

330 FNL & 1 FWL Secition 6-T18S-27E

Site Surface X 1853853 Surface Long
Slot Name UWI Surface Y 11900342.3 Surface Lat
Well Number 4H API Surface Z 3468.3 Global Z Ref KB
Project MD/TVD Ref KB Ground Level 3450.3 Local North Ref Grid

DIRECTIONAL WELL PLAN

MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN* S	sysTVD*
3450.00	90.22	271.0	2878.81	16.27	-941.75	0.00	941.89	1852911.25	11900358.57	589.49
3500.00	90.22	271.0	2878.62	17.14	-991.74	0.00	991.89	1852861.26	11900359.44	589.68
3550.00	90.22	271.0	2878.43	18.00	-1041.73	0.00	1041.89	1852811.27	11900360.30	589.87
3600.00	90.22	271.0	2878.24	18.87	-1091.72	0.00	1091.89	1852761.28	11900361.17	590.06
3650.00	90.22	271.0	2878.05	19.73	-1141.71	0.00	1141.88	1852711.29	11900362.03	590.25
3700.00	90.22	271.0	2877.85	20.59	-1191.71	0.00	1191.88	1852661.29	11900362.89	590.45
3750.00	90.22	271.0	2877.66	21.46	-1241.70	0.00	1241.88	1852611.30	11900363.76	590.64
3800.00	90.22	271.0	2877.47	22.32	-1291.69	0.00	1291.88	1852561.31	11900364.62	590.83
3850.00	90.22	271.0	2877.28	23.18	-1341.68	0.00	1341.88	1852511.32	11900365.48	591.02
3900.00	90.22	271.0	2877.09	24.05	-1391.68	0.00	1391.88	1852461.32	11900366.35	591.21
3950.00	90.22	271.0	2876.89	24.91	-1441.67	0.00	1441.88	1852411.33	11900367.21	591.41
4000.00	90.22	271.0	2876.70	25.78	-1491.66	0.00	1491.88	1852361.34	11900368.08	591.60
4050.00	90.22	271.0	2876.51	26.64	-1541.65	0.00	1541.88	1852311.35	11900368.94	591.79
4100.00	90.22	271.0	2876.32	27.50	-1591.64	0.00	1591.88	1852261.36	11900369.80	591.98
4150.00	90.22	271.0	2876.13	28.37	-1641.64	0.00	1641.88	1852211.36	11900370.67	592.17
4200.00	90.22	271.0	2875.93	29.23	-1691.63	0.00	1691.88	1852161.37	11900371.53	592.37
4250.00	90.22	271.0	2875.74	30.10	-1741.62	0.00	1741.88	1852111.38	11900372.40	592.56
4300.00	90.22	271.0	2875.55	30.96	-1791.61	0.00	1791.88	1852061.39	11900373.26	592.75
4350.00	90.22	271.0	2875.36	31.82	-1841.60	0.00	1841.88	1852011.40	11900374.12	592.94
4400.00	90.22	271.0	2875.17	32.69	-1891.60	0.00	1891.88	1851961.40	11900374.99	593.13
4450.00	90.22	271.0	2874.97	33.55	-1941.59	0.00	1941.88	1851911.41	11900375.85	593.33
4500.00	90.22	271.0	2874.78	34.42	-1991.58	0.00	1991.88	1851861.42	11900376.72	593.52
4550.00	90.22	271.0	2874.59	35.28	-2041.57	0.00	2041.88	1851811.43	11900377.58	593.71
4600.00	90.22	271.0	2874.40	36.14	-2091.57	0.00	2091.88	1851761.43	11900378.44	593.90
4650.00	90.22	271.0	2874.21	37.01	-2141.56	0.00	2141.88	1851711.44	11900379.31	594.09
4700.00	90.22	271.0	2874.01	37.87	-2191.55	0.00	2191.88	1851661.45	11900380.17	594.29
4750.00	90.22	271.0	2873.82	38.73	-2241.54	0.00	2241.88	1851611.46	11900381.03	594.48
4800.00	90.22	271.0	2873.63	39.60	-2291.53	0.00	2291.88	1851561.47	11900381.90	594.67
4850.00	90.22	271.0	2873.44	40.46	-2341.53	0.00	2341.88	1851511.47	11900382.76	594.86
4900.00	90.22	271.0	2873.25	41.33	-2391.52	0.00	2391.88	1851461.48	11900383.63	595.05
4950.00	90.22	271.0	2873.06	42.19	-2441.51	0.00	2441.88	1851411.49	11900384.49	595.25
5000.00	90.22	271.0	2872.86	43.05	-2491.50	0.00	2491.87	1851361.50	11900385.35	595.44
5050.00	90.22	271.0	2872.67	43.92	-2541.49	0.00	2541.87	1851311.51	11900386.22	595.63
5100.00	90.22	271.0	2872.48	44.78	-2591.49	0.00	2591.87	1851261.51	11900387.08	595.82
5150.00	90.22	271.0	2872.29	45.65	-2641.48	0.00	2641.87	1851211.52	11900387.95	596.01
5200.00	90.22	271.0	2872.10	46.51	-2691.47	0.00	2691.87	1851161.53	11900388.81	596.20
5250.00	90.22	271.0	2871.90	47.37	-2741.46	0.00	2741.87	1851111.54	11900389.67	596.40
ge 2 of 4					SES v5	.76			1.WWW	makinhole.con

OperatorRedwood Operating LLCUnitsfeet, °/100ft17:11 Friday, December 11, 2020 Page 3 of 4FieldRed LakeCountyEddyVertical Section Azimuth 270.99

Well Name Malco B 6 Federal Com #4H State New Mexico Survey Calculation Method Minimum Curvature
Plan 1 Country USA Database Access

Location SL: 330 FNL & 978 FWL Section 5-T18S-R27E BHL: Map Zone UTM Lat Long Ref

330 FNL & 1 FWL Secition 6-T18S-27E

Site Surface X 1853853 Surface Long
Slot Name UWI Surface Y 11900342.3 Surface Lat
Well Number 4H API Surface Z 3468.3 Global Z Ref KB
Project MD/TVD Ref KB Ground Level 3450.3 Local North Ref Grid

DIRECTIONAL WELL PLAN

MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN*	SysTVD*
5300.00	90.22	271.0	2871.71	48.24	-2791.46	0.00	2791.87	1851061.54	11900390.54	596.59
5350.00	90.22	271.0	2871.52	49.10	-2841.45	0.00	2841.87	1851011.55	11900391.40	596.78
5400.00	90.22	271.0	2871.33	49.97	-2891.44	0.00	2891.87	1850961.56	11900392.27	596.97
5450.00	90.22	271.0	2871.14	50.83	-2941.43	0.00	2941.87	1850911.57	11900393.13	597.16
5500.00	90.22	271.0	2870.94	51.69	-2991.42	0.00	2991.87	1850861.58	11900393.99	597.36
5550.00	90.22	271.0	2870.75	52.56	-3041.42	0.00	3041.87	1850811.58	11900394.86	597.55
5600.00	90.22	271.0	2870.56	53.42	-3091.41	0.00	3091.87	1850761.59	11900395.72	597.74
5650.00	90.22	271.0	2870.37	54.28	-3141.40	0.00	3141.87	1850711.60	11900396.58	597.93
5700.00	90.22	271.0	2870.18	55.15	-3191.39	0.00	3191.87	1850661.61	11900397.45	598.12
5750.00	90.22	271.0	2869.98	56.01	-3241.39	0.00	3241.87	1850611.61	11900398.31	598.32
5800.00	90.22	271.0	2869.79	56.88	-3291.38	0.00	3291.87	1850561.62	11900399.18	598.51
5850.00	90.22	271.0	2869.60	57.74	-3341.37	0.00	3341.87	1850511.63	11900400.04	598.70
5900.00	90.22	271.0	2869.41	58.60	-3391.36	0.00	3391.87	1850461.64	11900400.90	598.89
5950.00	90.22	271.0	2869.22	59.47	-3441.35	0.00	3441.87	1850411.65	11900401.77	599.08
6000.00	90.22	271.0	2869.02	60.33	-3491.35	0.00	3491.87	1850361.65	11900402.63	599.28
6050.00	90.22	271.0	2868.83	61.20	-3541.34	0.00	3541.87	1850311.66	11900403.50	599.47
6100.00	90.22	271.0	2868.64	62.06	-3591.33	0.00	3591.87	1850261.67	11900404.36	599.66
6150.00	90.22	271.0	2868.45	62.92	-3641.32	0.00	3641.87	1850211.68	11900405.22	599.85
6200.00	90.22	271.0	2868.26	63.79	-3691.31	0.00	3691.87	1850161.69	11900406.09	600.04
6250.00	90.22	271.0	2868.06	64.65	-3741.31	0.00	3741.87	1850111.69	11900406.95	600.24
6300.00	90.22	271.0	2867.87	65.52	-3791.30	0.00	3791.87	1850061.70	11900407.82	600.43
6350.00	90.22	271.0	2867.68	66.38	-3841.29	0.00	3841.86	1850011.71	11900408.68	600.62
6400.00	90.22	271.0	2867.49	67.24	-3891.28	0.00	3891.86	1849961.72	11900409.54	600.81
6450.00	90.22	271.0	2867.30	68.11	-3941.28	0.00	3941.86	1849911.72	11900410.41	601.00
6500.00	90.22	271.0	2867.10	68.97	-3991.27	0.00	3991.86	1849861.73	11900411.27	601.20
6550.00	90.22	271.0	2866.91	69.83	-4041.26	0.00	4041.86	1849811.74	11900412.13	601.39
6600.00	90.22	271.0	2866.72	70.70	-4091.25	0.00	4091.86	1849761.75	11900413.00	601.58
6650.00	90.22	271.0	2866.53	71.56	-4141.24	0.00	4141.86	1849711.76	11900413.86	601.77
6700.00	90.22	271.0	2866.34	72.43	-4191.24	0.00	4191.86	1849661.76	11900414.73	601.96
6750.00	90.22	271.0	2866.14	73.29	-4241.23	0.00	4241.86	1849611.77	11900415.59	602.16
6800.00	90.22	271.0	2865.95	74.15	-4291.22	0.00	4291.86	1849561.78	11900416.45	602.35
6850.00	90.22	271.0	2865.76	75.02	-4341.21	0.00	4341.86	1849511.79	11900417.32	602.54
6900.00	90.22	271.0	2865.57	75.88	-4391.21	0.00	4391.86	1849461.79	11900418.18	602.73
6950.00	90.22	271.0	2865.38	76.75	-4441.20	0.00	4441.86	1849411.80	11900419.05	602.92
7000.00	90.22	271.0	2865.18	77.61	-4491.19	0.00	4491.86	1849361.81	11900419.91	603.12
7050.00	90.22	271.0	2864.99	78.47	-4541.18	0.00	4541.86	1849311.82	11900420.77	603.31
7100.00	90.22	271.0	2864.80	79.34	-4591.17	0.00	4591.86	1849261.83	11900421.64	603.50
7150.00	90.22	271.0	2864.61	80.20	-4641.17	0.00	4641.86	1849211.83	11900422.50	603.69
age 3 of 4					SES v5	.76			www.	.makinhole.cor

OperatorRedwood Operating LLCUnitsfeet, °/100ft17:11 Friday, December 11, 2020 Page 4 of 4FieldRed LakeCountyEddyVertical Section Azimuth 270.99

Well Name Malco B 6 Federal Com #4H State New Mexico Survey Calculation Method Minimum Curvature
Plan 1 Country USA Database Access

Location SL: 330 FNL & 978 FWL Section 5-T18S-R27E BHL: Map Zone UTM Lat Long Ref

330 FNL & 1 FWL Secition 6-T18S-27E

 Site
 Surface X
 1853853
 Surface Long

 Slot Name
 UWI
 Surface Y
 11900342.3
 Surface Lat

 Well Number 4H
 API
 Surface Z
 3468.3
 Global Z Ref KB

 Project
 MD/TVD Ref KB
 Ground Level 3450.3
 Local North Ref Grid

DIRECTIONAL WELL PLAN

MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN* S	sysTVD*
7200.00	90.22	271.0	2864.42	81.07	-4691.16	0.00	4691.86	1849161.84	11900423.37	603.88
7250.00	90.22	271.0	2864.22	81.93	-4741.15	0.00	4741.86	1849111.85	11900424.23	604.08
7300.00	90.22	271.0	2864.03	82.79	-4791.14	0.00	4791.86	1849061.86	11900425.09	604.27
7350.00	90.22	271.0	2863.84	83.66	-4841.13	0.00	4841.86	1849011.87	11900425.96	604.46
7400.00	90.22	271.0	2863.65	84.52	-4891.13	0.00	4891.86	1848961.87	11900426.82	604.65
7450.00	90.22	271.0	2863.46	85.38	-4941.12	0.00	4941.86	1848911.88	11900427.68	604.84
7500.00	90.22	271.0	2863.26	86.25	-4991.11	0.00	4991.86	1848861.89	11900428.55	605.04
7550.00	90.22	271.0	2863.07	87.11	-5041.10	0.00	5041.86	1848811.90	11900429.41	605.23
7600.00	90.22	271.0	2862.88	87.98	-5091.10	0.00	5091.86	1848761.90	11900430.28	605.42
7650.00	90.22	271.0	2862.69	88.84	-5141.09	0.00	5141.86	1848711.91	11900431.14	605.61
7700.00	90.22	271.0	2862.50	89.70	-5191.08	0.00	5191.85	1848661.92	11900432.00	605.80
7750.00	90.22	271.0	2862.30	90.57	-5241.07	0.00	5241.85	1848611.93	11900432.87	606.00
7800.00	90.22	271.0	2862.11	91.43	-5291.06	0.00	5291.85	1848561.94	11900433.73	606.19
7850.00	90.22	271.0	2861.92	92.30	-5341.06	0.00	5341.85	1848511.94	11900434.60	606.38
7900.00	90.22	271.0	2861.73	93.16	-5391.05	0.00	5391.85	1848461.95	11900435.46	606.57
7950.00	90.22	271.0	2861.54	94.02	-5441.04	0.00	5441.85	1848411.96	11900436.32	606.76
8000.00	90.22	271.0	2861.34	94.89	-5491.03	0.00	5491.85	1848361.97	11900437.19	606.96
8050.00	90.22	271.0	2861.15	95.75	-5541.03	0.00	5541.85	1848311.98	11900438.05	607.15
8100.00	90.22	271.0	2860.96	96.62	-5591.02	0.00	5591.85	1848261.98	11900438.92	607.34
8150.00	90.22	271.0	2860.77	97.48	-5641.01	0.00	5641.85	1848211.99	11900439.78	607.53
8200.00	90.22	271.0	2860.58	98.34	-5691.00	0.00	5691.85	1848162.00	11900440.64	607.72
8250.00	90.22	271.0	2860.38	99.21	-5740.99	0.00	5741.85	1848112.01	11900441.51	607.92
8300.00	90.22	271.0	2860.19	100.07	-5790.99	0.00	5791.85	1848062.01	11900442.37	608.11
8350.00	90.22	271.0	2860.00	100.93	-5840.98	0.00	5841.85	1848012.02	11900443.23	608.30
8400.00	90.22	271.0	2859.81	101.80	-5890.97	0.00	5891.85	1847962.03	11900444.10	608.49
8450.00	90.22	271.0	2859.62	102.66	-5940.96	0.00	5941.85	1847912.04	11900444.96	608.68
8500.00	90.22	271.0	2859.42	103.53	-5990.95	0.00	5991.85	1847862.05	11900445.83	608.88
8550.00	90.22	271.0	2859.23	104.39	-6040.95	0.00	6041.85	1847812.05	11900446.69	609.07
8600.00	90.22	271.0	2859.04	105.25	-6090.94	0.00	6091.85	1847762.06	11900447.55	609.26
8650.00	90.22	271.0	2858.85	106.12	-6140.93	0.00	6141.85	1847712.07	11900448.42	609.45
8700.00	90.22	271.0	2858.66	106.98	-6190.92	0.00	6191.85	1847662.08	11900449.28	609.64
8750.00	90.22	271.0	2858.46	107.85	-6240.92	0.00	6241.85	1847612.08	11900450.15	609.84
*** TD (at MD		074.0	0050.00	400.00	0000.64	0.00	0000.05	4047504.00	11000150 00	000.04
8778.00	90.22	271.0	2858.36	108.33	-6268.91	0.00	6269.85	1847584.09	11900450.63	609.94

Page 4 of 4 SES v5.76 www.makinhole.co

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME: | REDWOOD OPERATING LLC

LEASE NO.: | NMLC0026874F

WELL NAME & NO.: | MALCO B 6 FEDERAL COM 4H

SURFACE HOLE FOOTAGE: 330'/N & 978'/W **BOTTOM HOLE FOOTAGE** 3300'/N & 1'/W

LOCATION: | Section 05, T.18 S., R.27 E., NMPM

COUNTY: Eddy County, New Mexico

COA

H2S	Yes	O No	
Potash	None	Secretary	© R-111-P
Cave/Karst Potential	O Low	Medium	• High
Cave/Karst Potential	O Critical		
Variance	None	C Flex Hose	Other
Wellhead	Conventional	• Multibowl	O Both
Other	□4 String Area	□Capitan Reef	□WIPP
Other	□Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	✓ COM	□ Unit

A. <u>HYDROGEN SULFIDE</u>

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

- 1. The 13-3/8 inch surface casing shall be set at approximately 375 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8

- **hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The 9-5/8 inch intermediate casing shall be set at 1375 feet. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
- ❖ In <u>High Cave/Karst Areas</u> if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- 3. The minimum required fill of cement behind the 7 inch production casing is:

Option 1 (Single Stage):

• Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

A. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2. **BOP REQUIREMENTS**

Option 1:

a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.

b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **2000 (2M)** psi.

Option 2:

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000** (**5M**) psi.

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

B. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)
 - Eddy County
 Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822
 - Lea County
 Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
 393-3612
- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. <u>CASING</u>

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- 2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
- 5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- 6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including

- lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. <u>DRILLING MUD</u>

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. <u>WASTE MATERIAL AND FLUIDS</u>

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

RI01312022

Redwood Operating LLC

Malco B 6 Federal Com 4H NMLC-0049648A NMNM-007711 NMLC-0069274

SHL: 330 FNL & 978 FWL, Lot 4, Sec. 5 T18S R27E BHL: 330 FNL & 1 FWL, Lot 4, Sec. 6 T18S R27E

Eddy County, NM

Mack Energy Corporation Onshore Order #6 Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- 1. The hazards an characteristics of hydrogen sulfide (H2S)
- 2. The proper use and maintenance of personal protective equipment and life support systems.
- 3. The proper use of H2S detectors alarms warning systems, briefing areas, evacuation procedures, and prevailing winds.
- 4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- 1. The effects of H2S on metal components. If high tensile tubular are to be used, personnel well be trained in their special maintenance requirements.
- 2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- 3. The contents and requirements of the H2S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H2S zone (within 3 days or 500 feet) and weekly H2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H2S Drilling Operations Plan and the Public Protection Plan. The concentrations of H2S of wells in this area from surface to TD are low enough that a contingency plan is not required.

II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold.
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- D. Auxiliary equipment may include if applicable: annular preventer & rotating head.

Redwood Operating LLC

Malco B 6 Federal Com 4H NMLC-0049648A NMNM-007711 NMLC-0069274

SHL: 330 FNL & 978 FWL, Lot 4, Sec. 5 T18S R27E BHL: 330 FNL & 1 FWL, Lot 4, Sec. 6 T18S R27E

Eddy County, NM

2. Protective equipment for essential personnel:

A. Mark II Survive air 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

3. H2S detection and monitoring equipment:

A. 1 portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram (Exhibit #8).
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

5. Mud program:

A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.

6. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- B. All elastomers used for packing and seals shall be H2S trim.

7. Communication:

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

8. Well testing:

A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H2S environment will use the closed chamber method of testing.

Redwood Operating LLC

Malco B 6 Federal Com 4H NMLC-0049648A NMNM-007711 NMLC-0069274

SHL: 330 FNL & 978 FWL, Lot 4, Sec. 5 T18S R27E BHL: 330 FNL & 1 FWL, Lot 4, Sec. 6 T18S R27E

Eddy County, NM

B. There will be no drill stem testing.

EXHIBIT #7

WARNING

YOU ARE ENTERING AN H2S


AUTHORIZED PERSONNEL ONLY

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED
- 2. HARD HATS REQUIRED
- 3. SMOKING IN DESIGNATED AREAS ONLY
- 4. BE WIND CONSCIOUS AT ALL TIMES
- 5. CHECK WITH Redwood Operating FOREMAN AT OFFICE

Redwood Operating LLC

1-575-748-1288


Warning sign @ access road entrance



Access Road Escape Route

- H2S Monitors with alarms at the bell nipple
- Wind Direction Indicators
- Safe Briefing areas with caution signs and breathing equipment min 1:0 feet from wellhead

DRILLING LOCATION H2S SAFTY EQUIPMENT Exhibit # 8



Location Layout

Mack Energy Corporation Call List, Eddy County

Artesia (575)	Cellular	Office	
Jim Krogman	432-934-1596	748-1288	
Emilio Martinez	432-934-7586	748-1288	

Agency Call List (575)

		•
А	rte	SIA

State Police	746-2703
City Police	746-2703
Sheriff's Office.	746-9888
Ambulance	911
Fire Department	746-2701
LEPC (Local Emergency Planning Committee	
NMOCD	

Carlsbad

vau	
State Police	885-3137
City Police	885-2111
Sheriff's Office	887-7551
Ambulance	911
Fire Department	885-2111
LEPC (Local Emergency Planning Committee	887-3798
Bureau of Land Management	887-6544
New Mexico Emergency Response Commission	(505)476-9690
24 Hour	(505)827-9126
Natonal Emergency Response Center (Washington).	(800)424-8802

Emergency Services

Boots & Coots IWC	1-800-256-9688 or (281)931-8884
	(915)699-0139 or (915)563-3356
Halliburton	
Par Five	748-9539
Flight For Life-Lubbock, TX	(806)743-9911
Aerocare-Lubbock, TX	(806)747-8923

Med Flight Air Amb-Albuquerque, NM.....(505)842-4433 Lifeguard Air Med Svc. Albuquerque, NM.....(505)272-3115

Drilling Program Page 11

ntent	: X	As Drill	ed										
API#													
Ope	rator Nan	ne:	l .			Property	Name:					Well Number	
REDWOOD OPERATING LLC						N	IALCO	B 6 FI	EDERAL	СОМ		4H	
(ick O	off Point (KOD)											
UL	Section 5	Township 18S	Range 27E	Lot 4	Feet 330	Fron NO	n N/S RTH	Feet 978	F	rom E/W	County EDDY		
Latitu		30733		1	Longitu	104.30	06102	21			NAD 83	}	
irst T	ake Poin	t (FTP)											
UL	Section 6	Township 18S	Range 27E	Lot 1	Feet 330	Fron NO	n N/S RTH	Feet 100		rom E/W	County EDDY		
Latitu	de 32.783	1486		1	Longitu	104.30	96110)			NAD 83	 3	
ast T	ake Point Section 6	Township 18S	Range 27E	Lot 4	Feet 330	From N/S NORTH	Feet		From E/\	N Coun	ity		
Latitu	de	183 833914	2/6	4	Longitu				WEST	NAD	83		
		defining wo	ell for the	Horiz	ontal Spa	icing Unit?]				
f infil	I is yes p ng Unit.		ide API if	avail	l able, Op	erator Naı	me and	well	number	for Def	ining well	for Horizonta	
Ope	rator Nan	ne:	<u> </u>			Property	Name:					Well Numbe	

KZ 06/29/2018

Well Name: MALCO B 6 FEDERAL COM



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

08/22/2022

APD ID: 10400074762

Submission Date: 06/07/2021

Highlighted data reflects the most recent changes

Operator Name: REDWOOD OPERATING LLC

Well Number: 4H

Well Type: OIL WELL

Well Work Type: Drill

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
4116394	QUATERNARY	3450	0	Ö	ALLUVIUM	NONE	N
4116395	QUEEN	2785	665	665	SILTSTONE	NATURAL GAS, OIL	N
4116396	GRAYBURG	2369	1081	1081	DOLOMITE, SILTSTONE	NATURAL GAS, OIL	N
4116397	SAN ANDRES	2116	1334	1334	DOLOMITE	NATURAL GAS, OIL	N
4116398	GLORIETA	785	2665	2665	SILTSTONE	NATURAL GAS, OIL	Y
4116399	YESO	713	2737	2737	DOLOMITE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M Rating Depth: 8778

Equipment: Rotating Head, Mud Gas Separator

Requesting Variance? NO

Variance request:

Testing Procedure: The BOP/BOPE test shall include a low pressure test from 250 to 300spi. The test will be held for a minimum of 10 minutes if test plug and 30 minutes without a test plug. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1367 psig (0.052*2858' TVD * 9.2ppg) less than 2900 bottom hole pressure. Will test to 2000psi for 30 minutes.

Choke Diagram Attachment:

choke_manifold_diagram_20210517121729.pdf


choke_manifold_20210517121736.pdf

BOP Diagram Attachment:

bop_diagram_20210517121742.pdf


Released to Imaging: 8/29/2022 9:26:06 AM

Mack Energy Corporation MANIFOLD SCHEMATIC Exhibit #12



Mack Energy Corporation Exhibit #11

Exhibit #11
MIMIMUM CHOKE MANIFOLD
3,000, 5,000, and 10,000 PSI Working Pressure
3M will be used
3 MWP - 5 MWP - 10 MWP



Mud Pit

Reserve Pit

* Location of separator optional

Below Substructure

Mimimum requirements

		3,0	000 MWP		5.	,000 MWP		10	0,000 MWP	
No.		I.D.	Nominal	Rating	I.D.	Nominal	Rating	I.D.	Nominal	Rating
1	Line from drilling Spool		3"	3,000		3"	5,000		3"	10,000
2	Cross 3" x 3" x 3" x 2"			3,000			5,000			
2	Cross 3" x 3" x 3" x 2"									10,000
3	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
4	Valve Gate Plug	1 13/16		3,000	1 13/16		5,000	1 13/16		10,000
4a	Valves (1)	2 1/16		3,000	2 1/16		5,000	2 1/16		10,000
5	Pressure Gauge			3,000			5,000			10,000
6	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
7	Adjustable Choke (3)	2"		3,000	2"		5,000	2"		10,000
8	Adjustable Choke	1"		3,000	1"		5,000	2"		10,000
9	Line		3"	3,000		3"	5,000		3"	10,000
10	Line		2"	3,000		2"	5,000		2"	10,000
11	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
12	Line		3"	1,000		3"	1,000		3"	2,000
13	Line		3"	1,000		3"	1,000		3"	2,000
14	Remote reading compound Standpipe pressure quage			3,000			5,000			10,000
15	Gas Separator		2' x5'			2' x5'			2' x5'	
16	Line		4"	1,000		4"	1,000		4"	2,000
17	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000

- (1) Only one required in Class 3M
- (2) Gate valves only shall be used for Class 10 M
- (3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling.

EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTION

- . All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX. Use only BX for 10 MWP.
- All lines shall be securely anchored.
- Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge.
- Line from drilling spool to choke manifold should bee as straight as possible. Lines downstream from chokes shall make turns by large bends or 90 degree bends using bull plugged tees


Mack Energy Corporation

Minimum Blowout Preventer Requirements

5000 psi Working Pressure 13 5/8 inch- 5 MWP 11 Inch - 5 MWP

Stack Requirements

NO.	Items	Min.	Min.
NO.	items	I.D.	Nominal
1	Flowline		2"
2	Fill up line		2"
3	Drilling nipple		
4	Annular preventer		
5	Two single or one dual hydraulically operated rams		
6a	Drilling spool with 2" min. kill line and 3" min choke line outlets		2" Choke
6b	2" min. kill line and 3" min. choke line outlets in ram. (Alternate to 6a above)		
7	Valve Gate Plug	3 1/8	
8	Gate valve-power operated	3 1/8	
9	Line to choke manifold		3"
10	Valve Gate Plug	2 1/16	
11	Check valve	2 1/16	
12	Casing head		
13	Valve Gate Plug	1 13/16	
14	Pressure gauge with needle valve		
15	Kill line to rig mud pump manifold		2"



OPTIONAL

	OI IIO.		
16	Flanged Valve	1 13/16	

CONTRACTOR'S OPTION TO

CONTRACTOR'S OPTION TO FURNISH:

- All equipment and connections above bradenhead or casinghead. Working pressure of preventers to be 2000 psi minimum.
- Automatic accumulator (80 gallons, minimum) capable of closing BOP in 30 seconds or less and, holding them closed against full rated working pressure.
- BOP controls, to be located near drillers' position.
- Kelly equipped with Kelly cock.
- Inside blowout preventer or its equivalent on derrick floor at all times with proper threads to fit pipe being used.
- Kelly saver-sub equipped with rubber casing protector at all times.
- Plug type blowout preventer tester.
- Extra set pipe rams to fit drill pipe in use on location at all times.
- Type RX ring gaskets in place of Type R.

MEC TO FURNISH:

- Bradenhead or casing head and side valves
- 2. Wear bushing. If required.

GENERAL NOTES:

- Deviations from this drawing may be made only with the express permission of MEC's Drilling Manager.
- All connections, valves, fittings, piping, etc., subject to well or pump pressure must be flanged (suitable clamp connections acceptable) and have minimum working pressure equal to rated working pressure of preventers up through choke valves must be full opening and suitable for high pressure mud service.
- Controls to be of standard design and each marked, showing opening and closing position
- Chokes will be positioned so as not to hamper or delay changing of choke beans.

- Replaceable parts for adjustable choke, or bean sizes, retainers, and choke wrenches to be conveniently located for immediate use.
- All valves to be equipped with hand-wheels or handles ready for immediate use.
- Choke lines must be suitably anchored.
- Handwheels and extensions to be connected and ready for use
- Valves adjacent to drilling spool to be kept open. Use outside valves except for emergency.
- All seamless steel control piping (2000 psi working pressure) to have flexible joints to avoid stress. Hoses will be permitted.
- Casinghead connections shall not be used except in case of emergency.

Released to Imaging: 8/29/2022 9:26:06 AM

 Does not use kill line for routine fill up operations.

District I 1625 N. French Dr., Hobbs, NM 88240 Phone: (575) 393-6161 Fax: (575) 393-0720

District II 811 S. First St., Artesia, NM 88210 Phone: (575) 748-1283 Fax: (575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

CONDITIONS

Action 136515

CONDITIONS

Operator:	OGRID:
Redwood Operating LLC	330211
PO Box 1370	Action Number:
Artesia, NM 88210	136515
	Action Type:
	[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
kpickford	Notify OCD 24 hours prior to casing & cement	8/29/2022
kpickford	Will require a File As Drilled C-102 and a Directional Survey with the C-104	8/29/2022
kpickford	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	8/29/2022
kpickford	Cement is required to circulate on both surface and intermediate1 strings of casing	8/29/2022
kpickford	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	8/29/2022