<u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720 District III 1000 Rio Brazos Rd., Aztec, NM 87410

Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

Form C-101 August 1, 2011

Permit 333308

| APPLICATION FOR PERMIT TO DRIL | ., RE-ENTER, DEEPEN | I, PLUGBACK | , OR ADD A ZONE |
|--------------------------------|---------------------|-------------|-----------------|
|--------------------------------|---------------------|-------------|-----------------|

| | <u> </u> | | | |
|---------------------------|----------------------|-----------------|--|--|
| Operator Name and Address | | 2. OGRID Number | | |
| TAP ROCK OPERATING, LLC | 372043 | | | |
| 523 Park Point Drive | 523 Park Point Drive | | | |
| Golden, CO 80401 | | 30-015-53351 | | |
| 4. Property Code | 5. Property Name | 6. Well No. | | |
| 329796 | Schlitz Fed Com | 141H | | |

7. Surface Location

| UL - Lot | Section | Township | Range | Lot Idn | Feet From | N/S Line | Feet From | E/W Line | County |
|----------|---------|----------|-------|---------|-----------|----------|-----------|----------|--------|
| M | 16 | 25S | 26E | | 648 | S | 921 | W | Eddy |

8. Proposed Bottom Hole Location

| UL - Lot | Section | Township | Range | Lot Idn | Feet From | N/S Line | Feet From | E/W Line | County |
|----------|---------|----------|-------|---------|-----------|----------|-----------|----------|--------|
| D | 9 | 25S | 26E | D | 5 | N | 331 | W | Eddv |

9. Pool Information

| COTTONWOOD DRAW; BONE SPRING (O) | 97494 |
|----------------------------------|-------|

Additional Well Information

| 11. Work Type New Well 12. Well Type OIL | | 13. Cable/Rotary | 14. Lease Type State | 15. Ground Level Elevation 3427 |
|--|-----------------------------|---|-------------------------|-----------------------------------|
| 16. Multiple | 17. Proposed Depth 16985 | 18. Formation 2nd Bone Spring Carbonate | 19. Contractor | 20. Spud Date 3/1/2023 |
| Depth to Ground water | | Distance from nearest fresh water well | | Distance to nearest surface water |

☑ We will be using a closed-loop system in lieu of lined pits

21. Proposed Casing and Cement Program

| 2111 Toposta ettinig tila esiminit Tegitim | | | | | | | | | |
|--|-------|-------|--|-------|------|---------------|-----------------|---------------|--|
| Туре | | | Hole Size Casing Size Casing Weight/ft | | | Setting Depth | Sacks of Cement | Estimated TOC | |
| Surf | | | 54.5 | 335 | 455 | 0 | | | |
| Int1 | 12.25 | 9.625 | 40 | 1946 | 623 | 0 | | | |
| Prod | 7.875 | 5.5 | 20 | 16985 | 2047 | 6117 | | | |
| Prod | 8.75 | 5.5 | 20 | 6117 | 319 | 1746 | | | |

Casing/Cement Program: Additional Comments

22. Proposed Blowout Prevention Program

| Туре | | Working Pressure | Test Pressure | Manufacturer |
|------|------------|------------------|---------------|--------------|
| | Double Ram | 10000 | 5000 | |
| | Pipe | 10000 | 5000 | |
| | Annular | 5000 | 2500 | |

| 23. I hereby certify that the information given above is true and complete to the best of my knowledge and belief. I further certify I have complied with 19.15.14.9 (A) NMAC ☒ and/or 19.15.14.9 (B) NMAC ☒, if applicable. | | | | OIL CONSERVATION | ON DIVISION | |
|---|-------------------------------------|------|----------------|--------------------------------------|-------------|--|
| Signature: | | | | | | |
| Printed Name: | Electronically filed by Christian C | ombs | Approved By: | Katherine Pickford | | |
| Title: | e: Regulatory Manager | | | Geoscientist | | |
| Email Address: ccombs@taprk.com | | | Approved Date: | 1/30/2023 Expiration Date: 1/30/2025 | | |
| Date: | 1/30/2023 Phone: 720-360-4028 | | | Conditions of Approval Attached | | |

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

FORM C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

| AMENDED | REPORT |
|---------|--------|
|---------|--------|


WELL LOCATION AND ACREAGE DEDICATION PLAT

| ¹ API Number | | ² Pool Code | | | | |
|----------------------------|-------|--------------------------------------|--------------|--------------------------|--|--|
| 30-015- | 53351 | 53351 97494 COTTONWOOD DRAW; BONE SE | | | | |
| ⁴ Property Code | | ⁵ Pr | operty Name | ⁶ Well Number | | |
| 329796 | | 141H | | | | |
| ⁷ OGRID No. | | ⁸ O _I | perator Name | ⁹ Elevation | | |
| 372043 | | 3427' | | | | |


¹⁰Surface Location

| M | 16 | 25-S | 26-E | Lot Idn | 648' | SOUTH | 921' | WEST | EDDY | | | |
|-------------------|--|-------------|-----------------|----------------------|---------------|------------------|---------------|----------------|--------|--|--|--|
| | ¹¹ Bottom Hole Location If Different From Surface | | | | | | | | | | | |
| UL or lot no. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County | | | |
| D | 9 | 25-S | 26-E | _ | 5' | NORTH | 331' | WEST | EDDY | | | |
| 12Dedicated Acres | ¹³ Joint or l | infill 14Co | onsolidation Co | de ¹⁵ Ord | er No. | | | | | | | |
| 640 | | | | | | | | | | | | |

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



LOCATION & ELEVATION VERIFICATION MAP






LEASE NAME & WELL NO.: SCHLITZ FED COM 141H

 SECTION
 16
 TWP
 25-S
 RGE
 26-E
 SURVEY
 N.M.P.M.

 COUNTY
 EDDY
 STATE
 NM
 ELEVATION
 3427'

 DESCRIPTION
 648' FSL & 921' FWL


LATITUDE N 32.1246113 LONGITUDE W 104.3033660



THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.







LEASE NAME & WELL NO.:

SCHLITZ FED COM 141H

 SECTION
 16
 TWP
 25-S
 RGE
 26-E
 SURVEY
 N.M.P.M.

 COUNTY
 EDDY
 STATE
 NM

 DESCRIPTION
 648' FSL & 921' FWL

DISTANCE & DIRECTION

FROM INT. OF BLACK RIVER VILLAGE RD., & US-180 W/US-62 W, GO SOUTHWEST ON US-180 W/US-62 W ±1.5 MILES, THENCE SOUTHEAST (LEFT) ON MEANS RD. ±1.9 MILES, THENCE EAST (LEFT) ON CREOSOTE RD. ±194 FEET, THENCE SOUTH (RIGHT) ON MEANS RD. ±4.8 MILES, THENCE EAST (LEFT) ON A LEASE RD. ±1.1 MILES, THENCE NORTH (RIGHT) ON A PROPOSED RD. ±3044 FEET TO A POINT ±219 FEET SOUTHWEST OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.





1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140

TELEPHONE: (817) 744-7512 • FAX (817) 744-7554


2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705

TELEPHONE: (432) 682-1630 OR (800) 767-1653 • FAX (432) 682-1743

WWW.TOPOGRAPHIC.COM



SECTION 16, TOWNSHIP 25-S, RANGE 26-E, N.M.P.M.



DISTANCE & DIRECTION

SCALE: 1"

COUNTY.

DESCRIPTION

1000'

FROM INT. OF BLACK RIVER VILLAGE RD., & US-180 W/US-62 W, GO SOUTHWEST ON US-180 W/US-62 W ±1.5 MILES, THENCE SOUTHEAST (LEFT) ON MEANS RD. ±1.9 MILES, THENCE EAST (LEFT) ON CREOSOTE RD. ±194 FEET, THENCE SOUTH (RIGHT) ON MEANS RD. ±4.8 MILES, THENCE EAST (LEFT) ON A LEASE RD. ±1.1 MILES, THENCE NORTH (RIGHT) ON A PROPOSED RD. ±3044 FEET TO A POINT ±219 FEET SOUTHWEST OF THE LOCATION.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

Ramon A Dominguez, P.S. No. 24508 January 12, 2023




1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705 HONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743 WWW.TOPOGRAPHIC.COM SECTION LINE

PROPOSED ROAD



SECTION 16. TOWNSHIP 25-S. RANGE 26-E. N.M.P.M. EDDY COUNTY, NEW MEXICO

DETAIL VIEW SCALE: 1" = 100'



Ramon A Dominguez, P.S. No. 24508

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. ELEVATIONS USED ARE NAVD88, OBTAINED THROUGH AN OPUS SOLUTION.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER THIS PROPUSED PAD SHE EVOLATION SHOWN REREDUCT HAS BEEN SURVEYED UNTITLE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. ONLY THE DATA SHOWN ABOVE IS BEING CERTIFIED TO, ALL OTHER INFORMATION WAS INTENTIONALLY OMITTED. THIS PLAT IS ONLY INTENDED TO BE USED FOR A PERMIT AND IS NOT A BOUNDARY SURVEY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743 WWW.TOPOGRAPHIC.COM

<u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 Phone:(575) 393-6161 Fax:(575) 393-0720

District II 811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410

Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

Form APD Comments

Permit 333308

PERMIT COMMENTS

| Operator Name and Address: | API Number: |
|----------------------------------|-----------------------|
| TAP ROCK OPERATING, LLC [372043] | 30-015-53351 |
| 523 Park Point Drive | Well: |
| Golden, CO 80401 | Schlitz Fed Com #141H |

| Created By | Comment | Comment Date |
|------------|--|--------------|
| kpickford | Defining well 3001549942 SCHLITZ FEDERAL COM #152H | 1/30/2023 |

Form APD Conditions

Permit 333308

<u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 Phone:(575) 393-6161 Fax:(575) 393-0720 District II

811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410

Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

PERMIT CONDITIONS OF APPROVAL

| Operator I | lame and Address: | API Number: |
|------------|----------------------------------|-----------------------|
| | TAP ROCK OPERATING, LLC [372043] | 30-015-53351 |
| | 523 Park Point Drive | Well: |
| | Golden, CO 80401 | Schlitz Fed Com #141H |
| | | |
| 000 | O-mail: | |

| OCD | Condition |
|-----------|--|
| Reviewer | |
| kpickford | Notify OCD 24 hours prior to casing & cement |
| kpickford | Will require a File As Drilled C-102 and a Directional Survey with the C-104 |
| kpickford | The Operator is to notify NMOCD by sundry (Form C-103) within ten (10) days of the well being spud |
| | Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string |
| kpickford | Cement is required to circulate on both surface and intermediate1 strings of casing |
| | Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system |

State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

| Tills Natural Gas Maliag | emem i ian i | Section | 11- | · Plan D | escription | io Dilli (A | .I D) 10. | a new or | 1600 | impleted well. |
|--|---------------|-------------------------|---------|----------------------------|-------------------|------------------------------|-----------|-----------------------------|--------|----------------------------------|
| I. Operator: Ta | p Rock Oper | | | <u>ve May 25</u> OGRID: | | 1 | Da | ate: _1/24/ | 23 | |
| II. Type: ⊠ Original □ | _ | | | | | | | _ | | |
| If Other, please describes | : | | | | | | | | | |
| III. Well(s): Provide the be recompleted from a si | | | | | | of wells p | roposed | l to be dril | lled o | or proposed to |
| Well Name | API | ULSTR | | F | ootages | Antici Oil BI | | Anticipa Gas MCF/I | | Anticipated Produced Water |
| Schiltz Fed Com 141H | | Sec 16 T25S R261 | E | 648 FSL, 921 FWL | | 1999 | 4124 | | | 5836 |
| V. Anticipated Schedulproposed to be recomple | e: Provide th | e following information | ation f | for each nev | w or recomplete | d well or s | | ells propo | sed to | o be drilled or |
| Well Name | API | Spud Date | TD | Reached Date | | Completion Commencement Date | | Initial Flow Find Back Date | | st Production Date |
| Schlitz Fed Com 141H | | 3/23/23 | 4/5 | /23 | 8/30/23 | | 9/9/23 | 3 | 9/9/ | /23 |
| VI. Separation Equipm | ent: 🗵 Atta | ch a complete descr | ription | of how Op | perator will size | separation | equipr | nent to op | timiz | e gas capture. |
| VII. Operational Pract Subsection A through F | | | criptic | on of the ac | etions Operator | will take t | o comp | oly with th | ne re | quirements of |
| VIII. Best Managemen during active and planne | | | ete de | escription o | f Operator's be | st manage | ment p | ractices to | min | imize venting |

Section 2 – Enhanced Plan <u>EFFECTIVE APRIL 1, 2022</u>

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

🗵 Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

| Well | API | Anticipated Average Natural Gas Rate MCF/D | Anticipated Volume of Natural Gas for the First Year MCF |
|------|-----|---|--|
| | | | |
| | | | |

X. Natural Gas Gathering System (NGGS):

| Operator | System | ULSTR of Tie-in | Anticipated Gathering Start Date | Available Maximum Daily Capacity of System Segment Tie-in |
|----------|--------|-----------------|----------------------------------|---|
| | | | | |
| | | | | |

| XI. Map. Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the |
|---|
| production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of |
| the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected. |

| XII. Line Capacity. The natural gas gathering system \square will \square will not have capacity to gather 100% of the a | anticipated natural gas |
|---|-------------------------|
| production volume from the well prior to the date of first production. | |

| XIII. Line Pressure. Operator \square does \square does not anticipate that its existing well(s) connected to the same segment, or portion | n, of the |
|--|-----------|
| natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new | |

| XIV. Confidentiality: Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided |
|--|
| Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific informati |
| for which confidentiality is asserted and the basis for such assertion. |

(i)

Section 3 - Certifications Effective May 25, 2021

| | <u>Effective May 25, 2021</u> | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|
| Operator certifies that, a | Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal: | | | | | | | | |
| one hundred percent of | Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, aking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or | | | | | | | | |
| hundred percent of the a into account the current | able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. box, Operator will select one of the following: | | | | | | | | |
| Well Shut-In. ☐ Opera D of 19.15.27.9 NMAC | tor will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection ; or | | | | | | | | |
| alternative beneficial us | Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential ses for the natural gas until a natural gas gathering system is available, including: | | | | | | | | |
| (a) | power generation on lease; | | | | | | | | |
| (b) | power generation for grid; compression on lease; | | | | | | | | |
| (c) (d) | liquids removal on lease; | | | | | | | | |
| (e) | | | | | | | | | |
| (f) | reinjection for temporary storage; | | | | | | | | |
| (g) | reinjection for enhanced oil recovery; | | | | | | | | |
| (h) | | | | | | | | | |

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

other alternative beneficial uses approved by the division.

- (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

| Signature: |
|---|
| Printed Name: Jeff Trlica |
| Title: Regulatory Analyst |
| E-mail Address: jtrlica@taprk.com |
| Date: 1/30/2023 |
| Phone: 720-772-5910 |
| OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form) |
| Approved By: |
| Title: |
| Approval Date: |
| Conditions of Approval: |
| |
| |
| |
| |

VI. **Separation Equipment:** Attach a complete description of how Operator will size separation equipment to optimize gas capture:

Each surface facility design includes the following process equipment: 3-phase separators (1 separator per well), a sales gas scrubber, one or two 3-phase heater treaters, a vapor recovery tower (VRT), a VRU compressor, multiple water and oil tanks, as well as flare knockouts (HP & LP), and flares (HP & LP). All process vessels will be sized to separate oil, water, gas based upon typical/historical & predicted well performance. Each process vessel will be fitted with an appropriately sized PSV as per ASME code requirements to mitigate vessel rupture and loss of containment. Additionally, the process vessels will be fitted with pressure transmitters tied to the facility control system which will allow operations to monitor pressures and when necessary, shut-in the facility to avoid vessel over-pressure and the potential vent of natural gas. Natural gas will preferentially be sold to pipeline, and only during upset/emergency conditions will gas be directed to the HP flare system. Flash gas from both the 3-phase heater treater and the VRT will be recompressed using a VRU compressor and this gas will also preferentially be directed to the gas sales pipeline. Oil tanks & water tanks will be fitted with 16 oz thief hatches as well as PVRVs to protect the tanks from rupture/collapse. Additionally, the tank vapor outlets and tank vapor capture system will be sized to keep tank pressures below 12 oz. The tank vapor capture system will include a tank vapor blower & knockout as well as a lowpressure flare and knockout. Tank vapors will preferentially be directed to the VRU and the sales gas pipeline. Only during process upsets/emergency conditions will tank vapors be directed to the LP flare system.

VII. **Operational Practices:** Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC. ← See attached reg for requirements.

- During drilling operations- Gas meters will be installed at the shakers and Volume
 Totalizers will be installed on the pits. In the event that elevated gas levels, or a pit
 gain are observed, returns will be diverted to a gas buster. Gas coming off the gas
 buster will be combusted at the flare stack. A 10' or taller flare will be located at
 least 100' from the SHL.
- During completions operations, including stimulation and frac plug drill out operations, hydrocarbon production to surface is minimized. When gas production does occur, gas will be combusted at a flare stack. A 10' or taller flare will be located at least 100' from the SHL.
- During production operations, all process vessels (separators, heater treaters, VRTs, Tanks) will recompress (where necessary) and route gas outlets into the natural gas gathering pipeline. Gas will preferentially be routed to natural gas gathering pipeline and the flare system will be used only during emergency, malfunction, or if the gas does not meet pipeline specifications. In the event of flaring off-specification gas, operations will pull gas samples twice a week and will also route gas back to pipeline as soon as the gas meets specification. Exceptions to this will include only those qualified exceptions per the regulation 19.15.27.8 Subsection D.

• To comply with state performance standards, separation and storage equipment will be designed to handle the maximum anticipated throughput and pressure to minimize waste and reduce the likelihood of venting gas to atmosphere. Additionally, each storage atmospheric tank (Oil & Water) will be fitted with a level transmitter to facilitate gauging of the tank without opening of the thief hatch. Any gas collected through the tank vent system is expected to be recompressed and routed to sales. However, in the event of an emergency, the tank vapor capture system will be designed to combust the gas using a flare stack fitted with a continuous or automatic ignitor. The flare stack will be properly anchored and will be located a minimum of 100 feet from the well and storage tanks. Operators will conduct weekly AVO inspections. These AVO inspection records will be stored for the required 5-year period and will be made available upon Division request.

VIII. **Best Management Practices:** Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

• When performing routine or preventive maintenance on a vessel or tank, initially all inlet valves are closed, and the vessel or tank is allowed to depressurize through the normal outlet connections to gas sales and/or liquid tanks. Once the vessel or tank is depressurized to lowest acceptable sales outlet pressure, usually around 20 psig, a temporary low-pressure flowline is connected from the vessel or tank to the Vapor Recovery Unit (VRU) for further pressure reduction. Once depressurized to less than 1-2 psig, the remaining natural gas in the vessel or tank is vented to atmosphere through a controlled pressure relief valve. Once the vessel or tank is depressurized to atmospheric pressure, the vessel or tank can be safely opened, and maintenance performed.



Tap Rock Resources, LLC

Eddy County, NM (NAD 83 NME) (Schlitz Fed Com) Sec-16_T-25-S_R-26-E Schlitz Fed Com #141H

OWB

Plan: Plan #1

Standard Planning Report

26 January, 2023





Intrepid Planning Report



Database: Company: Project:

EDM 5000.15 Single User Db Tap Rock Resources, LLC Eddy County, NM (NAD 83 NME)

(Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Well:

Site:

Schlitz Fed Com #141H

Wellbore: **OWB** Design: Plan #1 Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

Minimum Curvature

Project Eddy County, NM (NAD 83 NME)

Map System: Geo Datum:

Map Zone:

US State Plane 1983 North American Datum 1983 New Mexico Eastern Zone

System Datum:

Mean Sea Level

Site (Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Site Position: From:

Мар

Northing: Easting: Slot Radius: 409,046.00 usft 550,854.00 usft 13-3/16 "

Latitude: Longitude: **Grid Convergence:**

32° 7' 28.354 N 104° 18' 9.332 W

0.02°

Well Schlitz Fed Com #141H

+E/-W

Well Position +N/-S

Position Uncertainty:

25.0 usft -240.0 usft

0.0 usft

Northing: Easting:

409.071.00 usft 550,614.00 usft

Latitude: Longitude:

32° 7' 28.602 N 104° 18' 12.123 W

Position Uncertainty 0.0 usft Wellhead Elevation: Ground Level: 3,427.0 usft

OWB Wellbore

Declination **Field Strength** Magnetics **Model Name** Sample Date **Dip Angle** (°) (°) (nT) 47.228.31944308 **IGRF2015** 01/25/23 6.68 59.79

Design Plan #1

Audit Notes:

Version:

Phase:

PLAN

Tie On Depth:

0.0

Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (usft)

0.0

(usft) 0.0

(usft) 0.0

(°) 359.64

Date 01/26/23 **Plan Survey Tool Program**

Depth From Depth To (usft)

(usft)

Survey (Wellbore)

Tool Name

Remarks

0.0 MWD 16,984.5 Plan #1 (OWB)

OWSG MWD - Standard

Plan Sections Vertical Build Measured Dogleg Turn Depth Inclination **Azimuth** Depth +N/-S +E/-W Rate Rate Rate **TFO** (usft) (usft) (°/100usft) (°/100usft) (°/100usft) (usft) (usft) (°) (°) (°) Target 0.00 0.00 0.0 0.00 0.00 0.0 0.0 0.0 0.00 0.00 600.0 0.00 0.00 600.0 0.0 0.0 0.00 0.00 0.00 0.00 1.857.4 12.57 226.59 1,847.3 -94.4 -99.8 1.00 1.00 0.00 226.59 4.736.8 12.57 226.59 4.657.7 -525.2 -555.2 0.00 0.00 0.00 0.00 0.00 0.00 5,905.0 -619.7 -655.0 1.00 -1.00 0.00 180.00 5,994.2 0.00 0.00 6,117.2 0.00 0.00 6,028.0 -619.7-655.0 0.00 0.00 11.00 6,526.3 45 00 14.00 6,396.3 -471.6-618.111.00 0.00 14.00 6,952.3 90.10 359.64 6,555.5 -91.1 -580.9 11.00 10.59 -3.37-19.87-644.0 16,984.5 90.10 359.64 6,538.6 9,941.0 0.00 0.00 0.00 0.00 PBHL (Schlitz Fed (



Site:

IntrepidPlanning Report



Database: EDM 5000.15 Single User Db Tap Rock Resources, LLC Project: Eddy County, NM (NAD 83 NM

Eddy County, NM (NAD 83 NME) (Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Well: Schlitz Fed Com #141H

Wellbore: OWB
Design: Plan #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

| ned Surv | vey | | | | | | | | | |
|-----------------------|----------------|-----------------|------------------|-----------------------------|-------------------------------|------------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| Measu Dept (usf | th | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| | 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1 | 100.0 | 0.00 | 0.00 | 100.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 2 | 200.0 | 0.00 | 0.00 | 200.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 3 | 300.0 | 0.00 | 0.00 | 300.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 4 | 100.0 | 0.00 | 0.00 | 400.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| _ | -00 0 | 0.00 | 0.00 | 500.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| | 500.0 500.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| | | | 0.00 | 000.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| | | uild 1.00 | 220 50 | 700.0 | 0.0 | 0.0 | 0.0 | 4.00 | 4.00 | 0.00 |
| | 700.0 | 1.00 | 226.59 | 700.0 | -0.6 | -0.6 | -0.6 | 1.00 | 1.00 | 0.00 |
| | 300.0 | 2.00 | 226.59 | 800.0 | -2.4 | -2.5 | -2.4 | 1.00 | 1.00 | 0.00 |
| ٤ | 0.00 | 3.00 | 226.59 | 899.9 | -5.4 | -5.7 | -5.4 | 1.00 | 1.00 | 0.00 |
| 1,0 | 0.00 | 4.00 | 226.59 | 999.7 | -9.6 | -10.1 | -9.5 | 1.00 | 1.00 | 0.00 |
| 1,1 | 100.0 | 5.00 | 226.59 | 1,099.4 | -15.0 | -15.8 | -14.9 | 1.00 | 1.00 | 0.00 |
| 1,2 | 200.0 | 6.00 | 226.59 | 1,198.9 | -21.6 | -22.8 | -21.4 | 1.00 | 1.00 | 0.00 |
| | 300.0 | 7.00 | 226.59 | 1,298.3 | -29.4 | -31.0 | -29.2 | 1.00 | 1.00 | 0.00 |
| 1,4 | 100.0 | 8.00 | 226.59 | 1,397.4 | -38.3 | -40.5 | -38.1 | 1.00 | 1.00 | 0.00 |
| 1.5 | 500.0 | 9.00 | 226.59 | 1.496.3 | -48.5 | -51.2 | -48.2 | 1.00 | 1.00 | 0.00 |
| | 0.00 | 10.00 | 226.59 | 1,594.9 | - 4 6.5 -59.8 | -63.2 | -46.2 -59.4 | 1.00 | 1.00 | 0.00 |
| | 700.0 | 11.00 | 226.59 | 1,693.3 | -59.6 -72.3 | -03.2 -76.5 | -39.4 -71.9 | 1.00 | 1.00 | 0.00 |
| | 300.0 | 12.00 | 226.59 | 1,791.2 | -72.3 -86.0 | -70.5 -91.0 | -7 1.9 -85.5 | | 1.00 | 0.00 |
| | 357.4 | 12.00 | 226.59 | 1,791.2 | -00.0 -94.4 | -91.0 -99.8 | -05.5 -93.8 | 1.00 1.00 | 1.00 | 0.00 |
| | | | | 1,047.3 | -34.4 | -99.0 | -93.0 | 1.00 | 1.00 | 0.00 |
| HULI | D - 201 | 9.5 at 1857.4 | MD | | | | | | | |
| 1,9 | 0.00 | 12.57 | 226.59 | 1,888.9 | -100.8 | -106.6 | -100.1 | 0.00 | 0.00 | 0.00 |
| 2,0 | 0.00 | 12.57 | 226.59 | 1,986.5 | -115.8 | -122.4 | -115.0 | 0.00 | 0.00 | 0.00 |
| 2,1 | 100.0 | 12.57 | 226.59 | 2,084.1 | -130.7 | -138.2 | -129.9 | 0.00 | 0.00 | 0.00 |
| | 200.0 | 12.57 | 226.59 | 2,181.7 | -145.7 | -154.0 | -144.7 | 0.00 | 0.00 | 0.00 |
| 2,3 | 300.0 | 12.57 | 226.59 | 2,279.3 | -160.7 | -169.8 | -159.6 | 0.00 | 0.00 | 0.00 |
| 2 4 | 100.0 | 12.57 | 226.59 | 2,376.9 | -175.6 | -185.6 | -174.4 | 0.00 | 0.00 | 0.00 |
| | 500.0 | 12.57 | 226.59 | 2,474.5 | -190.6 | -201.4 | -189.3 | 0.00 | 0.00 | 0.00 |
| | 0.00 | 12.57 | 226.59 | 2,572.1 | -205.5 | -217.3 | -204.2 | 0.00 | 0.00 | 0.00 |
| | 700.0 | 12.57 | 226.59 | 2,669.7 | -220.5 | -233.1 | -219.0 | 0.00 | 0.00 | 0.00 |
| | 300.0 | 12.57 | 226.59 | 2,767.3 | -235.5 | -248.9 | -233.9 | 0.00 | 0.00 | 0.00 |
| - | | | | • | | | | | | |
| | 0.00 | 12.57 | 226.59 | 2,864.9 2.962.5 | -250.4 | -264.7 | -248.8 | 0.00 | 0.00 | 0.00 |
| | 0.000 | 12.57 | 226.59 226.59 | , | -265.4 | -280.5 | -263.6 -278.5 | 0.00 | 0.00 | 0.00 |
| | 100.0 200.0 | 12.57 12.57 | 226.59 226.59 | 3,060.1 3,157.7 | -280.3 -295.3 | -296.3 -312.1 | -278.5 -293.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| | 300.0 | 12.57 | 226.59 | 3,157.7 | -295.3 -310.3 | -312.1 | -293.3 -308.2 | 0.00 | 0.00 | 0.00 |
| | | | | • | | | | | | |
| | 100.0 | 12.57 | 226.59 | 3,352.9 | -325.2 | -343.8 | -323.1 | 0.00 | 0.00 | 0.00 |
| | 500.0 | 12.57 | 226.59 | 3,450.5 | -340.2 | -359.6 | -337.9 | 0.00 | 0.00 | 0.00 |
| | 0.00 | 12.57 | 226.59 | 3,548.1 | -355.1 | -375.4 | -352.8 | 0.00 | 0.00 | 0.00 |
| | 700.0 | 12.57 | 226.59 | 3,645.7 | -370.1 | -391.2 | -367.6 | 0.00 | 0.00 | 0.00 |
| 3,8 | 300.0 | 12.57 | 226.59 | 3,743.3 | -385.1 | -407.0 | -382.5 | 0.00 | 0.00 | 0.00 |
| 3.9 | 0.00 | 12.57 | 226.59 | 3,840.9 | -400.0 | -422.8 | -397.4 | 0.00 | 0.00 | 0.00 |
| 4,0 | 0.00 | 12.57 | 226.59 | 3,938.5 | -415.0 | -438.7 | -412.2 | 0.00 | 0.00 | 0.00 |
| | 100.0 | 12.57 | 226.59 | 4,036.1 | -429.9 | -454.5 | -427.1 | 0.00 | 0.00 | 0.00 |
| | 200.0 | 12.57 | 226.59 | 4,133.7 | -444.9 | -470.3 | -441.9 | 0.00 | 0.00 | 0.00 |
| | 300.0 | 12.57 | 226.59 | 4,231.4 | -459.9 | -486.1 | -456.8 | 0.00 | 0.00 | 0.00 |
| 1 1 | 100.0 | 12.57 | 226.59 | 4.329.0 | -474.8 | -501.9 | -471.7 | 0.00 | 0.00 | 0.00 |
| | 500.0 | 12.57 | 226.59 | 4,329.0 4,426.6 | -474.6 -489.8 | -501.9 -517.7 | -471.7 -486.5 | 0.00 | 0.00 | 0.00 |
| | 0.008 | 12.57 | 226.59 | 4,524.2 | - 4 69.6 -504.8 | -517.7 -533.5 | -460.5 -501.4 | 0.00 | 0.00 | 0.00 |
| | 700.0 | 12.57 | 226.59 | 4,621.8 | -504.6 -519.7 | -535.5 -549.4 | -501.4 -516.2 | 0.00 | 0.00 | 0.00 |
| | 736.8 | 12.57 | 226.59 | 4,657.7 | -519.7 -525.2 | -549.4 -555.2 | -510.2 -521.7 | 0.00 | 0.00 | 0.00 |
| ⊿ 7 | | | | 7.001.1 | | | | | | |



Site:

IntrepidPlanning Report



Database: EDM 5000.15 Single User Db Company: Tap Rock Resources, LLC Project: Eddy County, NM (NAD 83 NM

Eddy County, NM (NAD 83 NME) (Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Well: Schlitz Fed Com #141H

Wellbore: OWB
Design: Plan #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

| Planned S | urvey | | | | | | | | | |
|-----------|-------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| D | asured epth usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| | 4.800.0 | 11.94 | 226.59 | 4,719.4 | -534.4 | -564.9 | -530.9 | 1.00 | -1.00 | 0.00 |
| | 4,900.0 | 10.94 | 226.59 | 4,817.4 | -548.1 | -579.3 | -544.4 | 1.00 | -1.00 | 0.00 |
| | 5,000.0 | 9.94 | 226.59 | 4,915.8 | -560.5 | -592.5 | -556.8 | 1.00 | -1.00 | 0.00 |
| | 5,100.0 | 8.94 | 226.59 | 5,014.4 | -571.8 | -604.4 | -568.0 | 1.00 | -1.00 | 0.00 |
| | 5,200.0 | 7.94 | 226.59 | 5,113.3 | -581.9 | -615.1 | -578.0 | 1.00 | -1.00 | 0.00 |
| | 3,200.0 | | | | | | | 1.00 | | |
| | 5,300.0 | 6.94 | 226.59 | 5,212.5 | -590.8 | -624.5 | -586.9 | 1.00 | -1.00 | 0.00 |
| | 5,400.0 | 5.94 | 226.59 | 5,311.9 | -598.5 | -632.6 | -594.5 | 1.00 | -1.00 | 0.00 |
| | 5,500.0 | 4.94 | 226.59 | 5,411.4 | -605.0 | -639.5 | -601.0 | 1.00 | -1.00 | 0.00 |
| | 5,600.0 | 3.94 | 226.59 | 5,511.1 | -610.3 | -645.2 | -606.3 | 1.00 | -1.00 | 0.00 |
| | 5,700.0 | 2.94 | 226.59 | 5,610.9 | -614.5 | -649.5 | -610.4 | 1.00 | -1.00 | 0.00 |
| | • | | | • | | | | | | |
| | 5,800.0 | 1.94 | 226.59 | 5,710.8 | -617.4 | -652.6 | -613.3 | 1.00 | -1.00 | 0.00 |
| | 5,900.0 | 0.94 | 226.59 | 5,810.8 | -619.1 | -654.4 | -615.0 | 1.00 | -1.00 | 0.00 |
| | 5,994.2 | 0.00 | 0.00 | 5,905.0 | -619.7 | -655.0 | -615.5 | 1.00 | -1.00 | 0.00 |
| H | OLD - 12 | 3.0 at 5994.2 N | 1D | | | | | | | |
| | 6,000.0 | 0.00 | 0.00 | 5,910.8 | -619.7 | -655.0 | -615.5 | 0.00 | 0.00 | 0.00 |
| | 6,100.0 | 0.00 | 0.00 | 6,010.8 | -619.7 | -655.0 | -615.5 | 0.00 | 0.00 | 0.00 |
| | | | | • | | | | | | |
| | 6,117.2 | 0.00 | 0.00 | 6,028.0 | -619.7 | -655.0 | -615.5 | 0.00 | 0.00 | 0.00 |
| | OP - Buil | | | | | | | | | |
| | 6,150.0 | 3.61 | 14.00 | 6,060.8 | -618.7 | -654.8 | -614.5 | 11.00 | 11.00 | 0.00 |
| | 6,200.0 | 9.11 | 14.00 | 6,110.5 | -613.3 | -653.4 | -609.2 | 11.00 | 11.00 | 0.00 |
| | 6,250.0 | 14.61 | 14.00 | 6,159.4 | -603.3 | -650.9 | -599.2 | 11.00 | 11.00 | 0.00 |
| | 6,300.0 | 20.11 | 14.00 | 6,207.1 | -588.8 | -647.3 | -584.8 | 11.00 | 11.00 | 0.00 |
| | 0.050.0 | | 14.00 | | F70.0 | | | 44.00 | 44.00 | |
| | 6,350.0 | 25.61 | 14.00 | 6,253.1 | -570.0 | -642.6 | -566.0 | 11.00 | 11.00 | 0.00 |
| | 6,400.0 | 31.11 | 14.00 | 6,297.1 | -547.0 | -636.9 | -543.0 | 11.00 | 11.00 | 0.00 |
| | 6,450.0 | 36.61 | 14.00 | 6,338.6 | -520.0 | -630.1 | -516.0 | 11.00 | 11.00 | 0.00 |
| | 6,463.5 | 38.09 | 14.00 | 6,349.4 | -512.0 | -628.2 | -508.1 | 11.00 | 11.00 | 0.00 |
| | | corridor at 64 | 63.5'MD, 38.1° | | | | | | | |
| | 6,500.0 | 42.11 | 14.00 | 6,377.3 | -489.2 | -622.5 | -485.3 | 11.00 | 11.00 | 0.00 |
| | 6,526.3 | 45.00 | 14.00 | 6,396.3 | -471.6 | -618.1 | -467.7 | 11.00 | 11.00 | 0.00 |
| | | DLS 11.00 TF | | 0,000.0 | -471.0 | -010.1 | -407.7 | 11.00 | 11.00 | 0.00 |
| | | | | 0.440.7 | 455.0 | 0444 | 454.4 | 44.00 | 40.07 | F 07 |
| | 6,550.0 | 47.46 | 12.80 | 6,412.7 | -455.0 | -614.1 | -451.1 | 11.00 | 10.37 | -5.07 |
| | 6,600.0 | 52.68 | 10.54 | 6,444.8 | -417.4 | -606.4 | -413.6 | 11.00 | 10.44 | -4.51 |
| | 6,650.0 | 57.94 | 8.58 | 6,473.2 | -376.9 | -599.6 | -373.1 | 11.00 | 10.52 | -3.92 |
| | 6,700.0 | 63.23 | 6.84 | 6,497.8 | -333.8 | -593.8 | -330.0 | 11.00 | 10.57 | -3.49 |
| | 6,750.0 | 68.53 | 5.25 | 6,518.2 | -288.4 | -589.0 | -284.7 | 11.00 | 10.61 | -3.18 |
| | 6,800.0 | 73.85 | 3.77 | 6,534.3 | -241.2 | -585.3 | -237.5 | 11.00 | 10.64 | -2.95 |
| | 6,850.0 | 79.18 | 2.38 | 6,546.0 | -192.7 | -582.7 | -189.0 | 11.00 | 10.66 | -2.80 |
| | 6,900.0 | 84.52 | 1.03 | 6.553.1 | -143.2 | -581.2 | -139.6 | 11.00 | 10.67 | -2.70 |
| | 6,952.3 | 90.10 | 359.64 | 6,555.5 | -91.1 | -580.9 | -87.4 | 11.00 | 10.68 | -2.65 |
| | - | 32.3 hold at 69 | | 5,555.5 | 01.1 | 300.0 | O1.1 | 11.00 | 10.00 | 2.00 |
| | | | | | | | | | | |
| | 7,000.0 | 90.10 | 359.64 | 6,555.5 | -43.3 | -581.2 | -39.7 | 0.00 | 0.00 | 0.00 |
| | 7,100.0 | 90.10 | 359.64 | 6,555.3 | 56.7 | -581.8 | 60.3 | 0.00 | 0.00 | 0.00 |
| | 7,200.0 | 90.10 | 359.64 | 6,555.1 | 156.7 | -582.5 | 160.3 | 0.00 | 0.00 | 0.00 |
| | 7,300.0 | 90.10 | 359.64 | 6,554.9 | 256.7 | -583.1 | 260.3 | 0.00 | 0.00 | 0.00 |
| | 7,400.0 | 90.10 | 359.64 | 6,554.8 | 356.7 | -583.7 | 360.3 | 0.00 | 0.00 | 0.00 |
| | 7,500.0 | 90.10 | 359.64 | 6,554.6 | 456.7 | -584.3 | 460.3 | 0.00 | 0.00 | 0.00 |
| | | | | | | | | | | |
| | 7,600.0 | 90.10 | 359.64 | 6,554.4 | 556.7 | -585.0 | 560.3 | 0.00 | 0.00 | 0.00 |
| | 7,700.0 | 90.10 | 359.64 | 6,554.3 | 656.7 | -585.6 | 660.3 | 0.00 | 0.00 | 0.00 |
| | 7,800.0 | 90.10 | 359.64 | 6,554.1 | 756.7 | -586.2 | 760.3 | 0.00 | 0.00 | 0.00 |
| | 7,900.0 | 90.10 | 359.64 | 6,553.9 | 856.7 | -586.9 | 860.3 | 0.00 | 0.00 | 0.00 |
| | 8,000.0 | 90.10 | 359.64 | 6,553.8 | 956.7 | -587.5 | 960.3 | 0.00 | 0.00 | 0.00 |
| | 8,100.0 | 90.10 | 359.64 | 6,553.6 | 1,056.7 | -588.1 | 1,060.3 | 0.00 | 0.00 | 0.00 |
| | 8,200.0 | 90.10 | 359.64 | 6,553.4 | 1,156.7 | -588.7 | 1,160.3 | 0.00 | 0.00 | 0.00 |
| | 8,300.0 | 90.10 | 359.64 | 6,553.3 | 1,256.6 | -589.4 | 1,260.3 | 0.00 | 0.00 | 0.00 |
| | 0,500.0 | 90.10 | JJ9.04 | 0,000.0 | 1,200.0 | -309.4 | 1,200.3 | 0.00 | 0.00 | 0.00 |



Well:

IntrepidPlanning Report



Database: EDM 50 Company: Tap Ropert: Eddy Company: Eddy C

EDM 5000.15 Single User Db Tap Rock Resources, LLC Eddy County, NM (NAD 83 NME) (Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Schlitz Fed Com #141H

Wellbore: OWB
Design: Plan #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

| Planned Survey | | | | | | | | | |
|-----------------------------|-----------------|------------------|-----------------------------|--------------------|------------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 8,400.0 | 90.10 | 359.64 | 6,553.1 | 1,356.6 | -590.0 | 1,360.3 | 0.00 | 0.00 | 0.00 |
| 8,500.0 8,600.0 | 90.10 90.10 | 359.64 359.64 | 6,552.9 6,552.8 | 1,456.6 1,556.6 | -590.6 -591.3 | 1,460.3 1,560.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 8,700.0 8,800.0 | 90.10 90.10 | 359.64 359.64 | 6,552.6 6,552.4 | 1,656.6 1,756.6 | -591.9 -592.5 | 1,660.3 1,760.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 8,900.0 | 90.10 | 359.64 | 6,552.3 | 1,856.6 | -593.2 | 1,860.3 | 0.00 | 0.00 | 0.00 |
| 9,000.0 9,100.0 | 90.10 90.10 | 359.64 359.64 | 6,552.1 6,551.9 | 1,956.6 2,056.6 | -593.8 -594.4 | 1,960.3 2,060.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 9,200.0 | 90.10 | 359.64 | 6,551.7 | 2,156.6 | -595.0 | 2,160.3 | 0.00 | 0.00 | 0.00 |
| 9,300.0 | 90.10 | 359.64 | 6,551.6 | 2,256.6 | -595.7 | 2,260.3 | 0.00 | 0.00 | 0.00 |
| 9,400.0 | 90.10 | 359.64 | 6,551.4 | 2,356.6 | -596.3 | 2,360.3 | 0.00 | 0.00 | 0.00 |
| 9,500.0 9,600.0 | 90.10 90.10 | 359.64 359.64 | 6,551.2 6,551.1 | 2,456.6 2,556.6 | -596.9 -597.6 | 2,460.3 2,560.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 9,700.0 | 90.10 | 359.64 | 6,550.9 | 2,656.6 | -598.2 | 2,660.3 | 0.00 | 0.00 | 0.00 |
| 9,800.0 | 90.10 | 359.64 | 6,550.7 | 2,756.6 | -598.8 | 2,760.3 | 0.00 | 0.00 | 0.00 |
| 9,900.0 | 90.10 | 359.64 | 6,550.6 | 2,856.6 | -599.4 | 2,860.3 | 0.00 | 0.00 | 0.00 |
| 10,000.0 10,100.0 | 90.10 90.10 | 359.64 359.64 | 6,550.4 6,550.2 | 2,956.6 3,056.6 | -600.1 -600.7 | 2,960.3 3,060.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 10,100.0 | 90.10 | 359.64 | 6,550.1 | 3,156.6 | -601.3 | 3,160.3 | 0.00 | 0.00 | 0.00 |
| 10,300.0 | 90.10 | 359.64 | 6,549.9 | 3,256.6 | -602.0 | 3,260.3 | 0.00 | 0.00 | 0.00 |
| 10,400.0 | 90.10 | 359.64 | 6,549.7 | 3,356.6 | -602.6 | 3,360.3 | 0.00 | 0.00 | 0.00 |
| 10,500.0 10,600.0 | 90.10 90.10 | 359.64 359.64 | 6,549.6 6.549.4 | 3,456.6 3.556.6 | -603.2 -603.8 | 3,460.3 3,560.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 10,700.0 | 90.10 | 359.64 | 6,549.2 | 3,656.6 | -604.5 | 3,660.3 | 0.00 | 0.00 | 0.00 |
| 10,800.0 | 90.10 | 359.64 | 6,549.1 | 3,756.6 | -605.1 | 3,760.3 | 0.00 | 0.00 | 0.00 |
| 10,900.0 | 90.10 | 359.64 | 6,548.9 | 3,856.6 | -605.7 | 3,860.3 | 0.00 | 0.00 | 0.00 |
| 11,000.0 11,100.0 | 90.10 90.10 | 359.64 359.64 | 6,548.7 6,548.5 | 3,956.6 4,056.6 | -606.4 -607.0 | 3,960.3 4,060.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 11,200.0 | 90.10 | 359.64 | 6,548.4 | 4,156.6 | -607.6 | 4,160.3 | 0.00 | 0.00 | 0.00 |
| 11,300.0 | 90.10 | 359.64 | 6,548.2 | 4,256.6 | -608.2 | 4,260.3 | 0.00 | 0.00 | 0.00 |
| 11,400.0 11,500.0 | 90.10 90.10 | 359.64 359.64 | 6,548.0 6,547.9 | 4,356.6 4,456.6 | -608.9 -609.5 | 4,360.3 4,460.3 | 0.00 | 0.00 | 0.00 0.00 |
| 11,600.0 | 90.10 | 359.64 | 6,547.7 | 4,556.6 | -610.1 | 4,560.3 | 0.00 | 0.00 | 0.00 |
| 11,700.0 | 90.10 | 359.64 | 6,547.5 | 4,656.6 | -610.8 | 4,660.3 | 0.00 | 0.00 | 0.00 |
| 11,800.0 11,900.0 | 90.10 90.10 | 359.64 359.64 | 6,547.4 6,547.2 | 4,756.6 4,856.6 | -611.4 -612.0 | 4,760.3 4,860.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 12.000.0 | 90.10 | 359.64 | 6,547.0 | 4,956.6 | -612.6 | 4,960.3 | 0.00 | 0.00 | 0.00 |
| 12,100.0 | 90.10 | 359.64 | 6,546.9 | 5,056.6 | -613.3 | 5,060.3 | 0.00 | 0.00 | 0.00 |
| 12,200.0 | 90.10 | 359.64 | 6,546.7 6,546.5 | 5,156.6 | -613.9 | 5,160.3 | 0.00 | 0.00 | 0.00 |
| 12,300.0 12,400.0 | 90.10 90.10 | 359.64 359.64 | 6,546.5 6,546.4 | 5,256.6 5,356.6 | -614.5 -615.2 | 5,260.3 5,360.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 12,500.0 | 90.10 | 359.64 | 6,546.2 | 5,456.6 | -615.8 | 5,460.3 | 0.00 | 0.00 | 0.00 |
| 12,600.0 | 90.10 | 359.64 | 6,546.0 | 5,556.6 | -616.4 | 5,560.3 | 0.00 | 0.00 | 0.00 |
| 12,700.0 12,800.0 | 90.10 90.10 | 359.64 359.64 | 6,545.9 6,545.7 | 5,656.6 5,756.6 | -617.1 -617.7 | 5,660.3 5,760.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 12,900.0 | 90.10 | 359.64 | 6,545.5 | 5,856.6 | -618.3 | 5,860.3 | 0.00 | 0.00 | 0.00 |
| 13,000.0 | 90.10 | 359.64 | 6,545.4 | 5,956.5 | -618.9 | 5,960.3 | 0.00 | 0.00 | 0.00 |
| 13,100.0 | 90.10 | 359.64 | 6,545.2 | 6,056.5 | -619.6 | 6,060.3 | 0.00 | 0.00 | 0.00 |
| 13,200.0 13,300.0 | 90.10 90.10 | 359.64 359.64 | 6,545.0 6,544.8 | 6,156.5 6,256.5 | -620.2 -620.8 | 6,160.3 6,260.3 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 13,400.0 | 90.10 | 359.64 | 6,544.7 | 6,356.5 | -621.5 | 6,360.3 | 0.00 | 0.00 | 0.00 |
| 13,500.0 | 90.10 | 359.64 | 6,544.5 | 6,456.5 | -622.1 | 6,460.3 | 0.00 | 0.00 | 0.00 |
| 13,600.0 | 90.10 | 359.64 | 6,544.3 | 6,556.5 | -622.7 | 6,560.3 | 0.00 | 0.00 | 0.00 |
| 13,700.0 | 90.10 | 359.64 | 6,544.2 | 6,656.5 | -623.3 | 6,660.3 | 0.00 | 0.00 | 0.00 |



IntrepidPlanning Report



Database: Company: Project: Site:

Well:

EDM 5000.15 Single User Db Tap Rock Resources, LLC Eddy County, NM (NAD 83 NME)

(Schlitz Fed Com) Sec-16_T-25-S_R-26-E Schlitz Fed Com #141H

Wellbore: OWB
Design: Plan #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

| | esigii. | 1 Idii # 1 | | | | | | | | |
|--|----------------------------------|-------------------------|--------------------------------------|--|-------------------------------|--------------------------------------|-------------------------------|----------------------|------------------------------|----------------------|
| Depth (usft) | lanned Survey | | | | | | | | | |
| 13,900.0 90.10 359.64 6,543.8 6,856.5 -624.6 6,860.3 0.00 0.00 0.00 14,000.0 90.10 359.64 6,543.7 6,956.5 -625.2 6,960.3 0.00 0.00 0.00 0.00 14,200.0 90.10 359.64 6,543.5 7,056.5 -625.9 7,060.3 0.00 0.00 0.00 0.00 14,200.0 90.10 359.64 6,543.3 7,156.5 -625.9 7,160.3 0.00 0.00 0.00 0.00 14,200.0 90.10 359.64 6,543.2 7,256.5 -627.1 7,260.3 0.00 0.00 0.00 0.00 14,400.0 90.10 359.64 6,543.2 7,256.5 -627.7 7,360.3 0.00 0.00 0.00 0.00 14,400.0 90.10 359.64 6,543.2 7,256.5 -627.7 7,360.3 0.00 0.00 0.00 0.00 14,600.0 90.10 359.64 6,542.7 7,556.5 -628.4 7,460.3 0.00 0.00 0.00 0.00 14,600.0 90.10 359.64 6,542.7 7,556.5 -629.0 7,560.3 0.00 0.00 0.00 0.00 14,800.0 90.10 359.64 6,542.3 7,565.5 -629.6 7,560.3 0.00 0.00 0.00 0.00 14,800.0 90.10 359.64 6,542.3 7,565.5 -630.3 7,760.3 0.00 0.00 0.00 0.00 14,900.0 90.10 359.64 6,542.2 7,856.5 -630.9 7,860.3 0.00 0.00 0.00 0.00 15,100.0 90.10 359.64 6,542.2 7,856.5 -630.9 7,860.3 0.00 0.00 0.00 0.00 15,100.0 90.10 359.64 6,541.8 8,056.5 -632.1 8,060.3 0.00 0.00 0.00 0.00 15,200.0 90.10 359.64 6,541.8 8,056.5 -632.1 8,060.3 0.00 0.00 0.00 0.00 15,300.0 90.10 359.64 6,541.8 8,056.5 -632.8 8,160.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.8 8,056.5 -632.8 8,160.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.3 8,356.5 -632.8 8,160.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.3 8,356.5 -633.4 8,260.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.3 8,356.5 -634.0 8,360.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.8 8,656.5 -635.3 8,560.3 0.00 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.8 8,656.5 -632.8 8,660.3 0.00 0.00 0.00 0.00 15,600.0 90.10 359.64 6,541.8 8,565.5 -636.8 8,660.3 0.00 0.00 0.00 0.00 15,600.0 90.10 359.64 6,541.8 8,565.5 -636.8 8,660.3 0.00 0.00 0.00 0.00 15,600.0 90.10 359.64 6,541.8 8,565.5 -636.8 8,660.3 0.00 0.00 0.00 0.00 15,600.0 90.10 359.64 6,540.8 8,565.5 -636.8 8,960.3 0.00 0.00 0.00 0.00 16,600.0 90.10 359.64 6,540.8 8,565.5 -636.8 8,960.3 0.00 0.00 0.00 0.00 16,000.0 90.10 359.64 6,540.8 8,565.5 -636.8 8,960.3 0.00 0.00 0.00 0.00 16,600. | Depth | | | Depth | | | Section | Rate | Rate | Rate |
| 14,100.0 90.10 359.64 6,543.5 7,056.5 -625.9 7,060.3 0.00 0.00 0.00 14,200.0 90.10 359.64 6,543.3 7,156.5 -626.5 7,160.3 0.00 0.00 0.00 0.00 14,300.0 90.10 359.64 6,543.2 7,256.5 -627.7 7,360.3 0.00 0.00 0.00 0.00 14,400.0 90.10 359.64 6,543.0 7,356.5 -627.7 7,360.3 0.00 0.00 0.00 0.00 14,500.0 90.10 359.64 6,542.8 7,456.5 -628.4 7,460.3 0.00 0.00 0.00 0.00 14,500.0 90.10 359.64 6,542.8 7,456.5 -629.6 7,560.3 0.00 0.00 0.00 0.00 14,500.0 90.10 359.64 6,542.5 7,656.5 -629.6 7,560.3 0.00 0.00 0.00 0.00 14,700.0 90.10 359.64 6,542.5 7,656.5 -629.6 7,660.3 0.00 0.00 0.00 0.00 14,900.0 90.10 359.64 6,542.2 7,856.5 -630.9 7,860.3 0.00 0.00 0.00 0.00 14,900.0 90.10 359.64 6,542.2 7,856.5 -630.9 7,860.3 0.00 0.00 0.00 0.00 15,000.0 90.10 359.64 6,542.2 7,856.5 -630.9 7,860.3 0.00 0.00 0.00 0.00 15,000.0 90.10 359.64 6,542.2 7,856.5 -631.5 7,960.3 0.00 0.00 0.00 0.00 15,000.0 90.10 359.64 6,541.8 8,056.5 -632.1 8,060.3 0.00 0.00 0.00 0.00 15,000.0 90.10 359.64 6,541.8 8,056.5 -632.1 8,060.3 0.00 0.00 0.00 0.00 15,000 90.10 359.64 6,541.8 8,056.5 -632.8 8,160.3 0.00 0.00 0.00 0.00 15,000.0 90.10 359.64 6,541.5 8,256.5 -633.4 8,260.3 0.00 0.00 0.00 0.00 15,000 90.10 359.64 6,541.5 8,256.5 -633.4 8,260.3 0.00 0.00 0.00 0.00 15,000 90.10 359.64 6,541.8 8,356.5 -634.7 8,460.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,541.8 8,356.5 -634.7 8,460.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,541.0 8,556.5 -635.3 8,560.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,541.0 8,556.5 -635.3 8,560.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.6 8,756.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.6 8,756.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.6 8,756.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.6 8,756.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.6 8,756.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 15,500.0 90.10 359.64 6,540.5 8,856.5 -635.8 8,660.3 0.00 0.00 0.00 0.00 16,000 90.10 359.64 6,540.5 9,565.5 -636.5 8,760.3 0.00 0.00 0.00 0.00 16,000 90.10 35 | | | | | | | -, | | | |
| 14,500.0 90.10 359.64 6,542.8 7,456.5 -628.4 7,460.3 0.00 0.00 0.00 14,600.0 90.10 359.64 6,542.7 7,556.5 -629.0 7,560.3 0.00 0.00 0.00 14,700.0 90.10 359.64 6,542.3 7,756.5 -630.3 7,760.3 0.00 0.00 0.00 14,800.0 90.10 359.64 6,542.2 7,756.5 -630.9 7,860.3 0.00 0.00 0.00 15,000.0 90.10 359.64 6,542.2 7,756.5 -630.9 7,860.3 0.00 0.00 0.00 15,100.0 90.10 359.64 6,541.8 8,056.5 -631.5 7,960.3 0.00 0.00 0.00 15,200.0 90.10 359.64 6,541.6 8,156.5 -632.8 8,160.3 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.5 8,256.5 -633.4 8,260.3 0.00 0.00 0.00 15,500.0 90.10 359.64 6,541.3 8,356.5 -634.7 | 14,100.0 14,200.0 14,300.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 | 6,543.5 6,543.3 6,543.2 | 7,056.5 7,156.5 7,256.5 | -625.9 -626.5 -627.1 | 7,060.3 7,160.3 7,260.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| 15,100.0 90.10 359.64 6,541.8 8,056.5 -632.1 8,060.3 0.00 0.00 0.00 15,200.0 90.10 359.64 6,541.6 8,156.5 -632.8 8,160.3 0.00 0.00 0.00 15,300.0 90.10 359.64 6,541.5 8,256.5 -633.4 8,260.3 0.00 0.00 0.00 15,400.0 90.10 359.64 6,541.1 8,356.5 -634.0 8,360.3 0.00 0.00 0.00 15,500.0 90.10 359.64 6,541.1 8,456.5 -634.7 8,460.3 0.00 0.00 0.00 15,600.0 90.10 359.64 6,541.0 8,556.5 -635.3 8,560.3 0.00 0.00 0.00 15,700.0 90.10 359.64 6,540.8 8,656.5 -635.9 8,660.3 0.00 0.00 0.00 15,800.0 90.10 359.64 6,540.5 8,856.5 -637.2 8,860.3 0.00 0.00 0.00 <th>14,600.0 14,700.0 14,800.0</th> <td>90.10 90.10 90.10</td> <td>359.64 359.64 359.64 359.64</td> <td>6,542.8 6,542.7 6,542.5 6,542.3</td> <td>7,556.5 7,656.5 7,756.5</td> <td>-628.4 -629.0 -629.6 -630.3</td> <td>7,560.3 7,660.3 7,760.3</td> <td>0.00 0.00 0.00</td> <td>0.00 0.00 0.00 0.00</td> <td>0.00 0.00 0.00</td> | 14,600.0 14,700.0 14,800.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 359.64 | 6,542.8 6,542.7 6,542.5 6,542.3 | 7,556.5 7,656.5 7,756.5 | -628.4 -629.0 -629.6 -630.3 | 7,560.3 7,660.3 7,760.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| 15,600.0 90.10 359.64 6,541.0 8,556.5 -635.3 8,560.3 0.00 0.00 0.00 15,700.0 90.10 359.64 6,540.8 8,656.5 -635.9 8,660.3 0.00 0.00 0.00 15,800.0 90.10 359.64 6,540.6 8,756.5 -636.5 8,760.3 0.00 0.00 0.00 15,900.0 90.10 359.64 6,540.5 8,856.5 -637.2 8,860.3 0.00 0.00 0.00 16,000.0 90.10 359.64 6,540.1 9,060.5 -637.8 8,960.3 0.00 0.00 0.00 16,200.0 90.10 359.64 6,540.1 9,056.5 -637.8 8,960.3 0.00 0.00 0.00 16,200.0 90.10 359.64 6,540.1 9,056.5 -638.4 9,060.3 0.00 0.00 0.00 16,300.0 90.10 359.64 6,539.8 9,256.5 -639.7 9,260.3 0.00 0.00 0.00 16,500.0 90.10 359.64 6,539.5 9,456.5 -641.0 | 15,100.0 15,200.0 15,300.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 | 6,541.8 6,541.6 6,541.5 | 8,056.5 8,156.5 8,256.5 | -632.1 -632.8 -633.4 | 8,060.3 8,160.3 8,260.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| 16,100.0 90.10 359.64 6,540.1 9,056.5 -638.4 9,060.3 0.00 0.00 0.00 16,200.0 90.10 359.64 6,540.0 9,156.5 -639.1 9,160.3 0.00 0.00 0.00 16,300.0 90.10 359.64 6,539.8 9,256.5 -639.7 9,260.3 0.00 0.00 0.00 16,400.0 90.10 359.64 6,539.6 9,356.5 -640.3 9,360.3 0.00 0.00 0.00 16,500.0 90.10 359.64 6,539.5 9,456.5 -641.0 9,460.3 0.00 0.00 0.00 16,600.0 90.10 359.64 6,539.3 9,556.5 -641.6 9,560.3 0.00 0.00 0.00 16,700.0 90.10 359.64 6,539.1 9,656.5 -642.2 9,660.3 0.00 0.00 0.00 16,800.0 90.10 359.64 6,539.0 9,756.5 -642.2 9,660.3 0.00 0.00 0.00 16,900.0 90.10 359.64 6,538.8 9,856.5 -643.5 | 15,600.0 15,700.0 15,800.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 | 6,541.0 6,540.8 6,540.6 | 8,556.5 8,656.5 8,756.5 | -635.3 -635.9 -636.5 | 8,560.3 8,660.3 8,760.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| 16,600.0 90.10 359.64 6,539.3 9,556.5 -641.6 9,560.3 0.00 0.00 0.00 16,700.0 90.10 359.64 6,539.1 9,656.5 -642.2 9,660.3 0.00 0.00 0.00 16,800.0 90.10 359.64 6,539.0 9,756.5 -642.8 9,760.3 0.00 0.00 0.00 16,900.0 90.10 359.64 6,538.8 9,856.5 -643.5 9,860.3 0.00 0.00 0.00 16,984.5 90.10 359.64 6,538.6 9,941.0 -644.0 9,944.8 0.00 0.00 0.00 | 16,100.0 16,200.0 16,300.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 | 6,540.1 6,540.0 6,539.8 | 9,056.5 9,156.5 9,256.5 | -638.4 -639.1 -639.7 | 9,060.3 9,160.3 9,260.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| | 16,600.0 16,700.0 16,800.0 | 90.10 90.10 90.10 | 359.64 359.64 359.64 | 6,539.3 6,539.1 6,539.0 | 9,556.5 9,656.5 9,756.5 | -641.6 -642.2 -642.8 | 9,560.3 9,660.3 9,760.3 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| | 16,984.5 TD at 1698 | | 359.64 | 6,538.6 | 9,941.0 | -644.0 | 9,944.8 | 0.00 | 0.00 | 0.00 |

| Design Targets | | | | | | | | | |
|--|------------------|-----------------|------------------------|------------------------|-------------------------|------------------------------|-------------------|-----------------|-------------------|
| Target Name - hit/miss target - Shape | Dip Angle (°) | Dip Dir. (°) | TVD (usft) | +N/-S (usft) | +E/-W (usft) | Northing (usft) | Easting (usft) | Latitude | Longitude |
| PBHL (Schlitz Fed C - plan hits target - Rectangle (side | center | | 6,538.6 0.0) | 9,941.0 | -644.0 | 419,012.00 | 549,970.00 | 32° 9' 6.982 N | 104° 18' 19.582 W |
| LTP (Schlitz Fed Con - plan misses tar - Point | | | 6,538.6 6889.5usft | 9,846.0 MD (6538.8 | -644.0 TVD, 9846.0 | 418,917.00 N, -643.4 E) | 549,970.00 | 32° 9' 6.042 N | 104° 18' 19.582 W |
| FTP (Schlitz Fed Co - plan misses tar - Point | | | 6,556.0 t 6561.0usf | -570.0 t MD (6420.1 | -579.0 1 TVD, -447.0 | 408,501.00 0 N, -612.4 E) | 550,035.00 | 32° 7' 22.963 N | 104° 18' 18.858 W |



IntrepidPlanning Report



Database: Company: Project: Site:

EDM 5000.15 Single User Db Tap Rock Resources, LLC Eddy County, NM (NAD 83 NME)

(Schlitz Fed Com) Sec-16_T-25-S_R-26-E

Well: Schlitz Fed Com #141H
Wellbore: OWB
Design: Plan #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Schlitz Fed Com #141H

KB @ 3453.0usft KB @ 3453.0usft

Grid

| Formations | | | | | | |
|------------|-----------------------------|-----------------------------|--------------------|-----------|------------|-------------------------|
| | Measured Depth (usft) | Vertical Depth (usft) | Name | Lithology | Dip (°) | Dip Direction (°) |
| | 85.0 | 85.0 | RUSTLER | | | |
| | 435.0 | 435.0 | SALT [T] | | | |
| | 1,676.3 | 1,670.0 | SALT [B] | | | |
| | 1,896.0 | 1,885.0 | DELAWARE/LAMAR | | | |
| | 1,926.7 | 1,915.0 | BELL | | | |
| | 2,930.8 | 2,895.0 | CHERRY | | | |
| | 3,847.8 | 3,790.0 | BRUSHY | | | |
| | 5,503.6 | * | BONE SPRING | | | |
| | 5,674.0 | 5,585.0 | AVALON UPPER | | | |
| | 5,934.2 | * | AVALON MIDDLE | | | |
| | 6,225.0 | * | AVALON LOWER | | | |
| | 6,415.2 | • | 1ST BONE SPRING | | | |
| | 6,728.6 | 6,510.0 | 2ND BONE SPRING FS | | | |

| Plan Annotations | | | | |
|-----------------------------|-----------------------------|-------------------------------|-----------------------------|--|
| Measured Depth (usft) | Vertical Depth (usft) | Local Cool +N/-S (usft) | rdinates +E/-W (usft) | Comment |
| 600.0 | 600.0 | 0.0 | 0.0 | NUDGE - Build 1.00 |
| 1,857.4 | 1,847.3 | -94.4 | -99.8 | HOLD - 2879.5 at 1857.4 MD |
| 4,736.8 | 4,657.7 | -525.2 | -555.2 | DROP1.00 |
| 5,994.2 | 5,905.0 | -619.7 | -655.0 | HOLD - 123.0 at 5994.2 MD |
| 6,117.2 | 6,028.0 | -619.7 | -655.0 | KOP - Build 11.00 |
| 6,463.5 | 6,349.4 | -512.0 | -628.2 | Enter 100' corridor at 6463.5'MD, 38.1°inc |
| 6,526.3 | 6,396.3 | -471.6 | -618.1 | BLD/TRN - DLS 11.00 TFO -19.87 |
| 6,952.3 | 6,555.5 | -91.1 | -580.9 | EOC - 10032.3 hold at 6952.3 MD |
| 16,984.5 | 6,538.6 | 9,941.0 | -644.0 | TD at 16984.5 |