

Well Name: SNEAKY SNAKE 24-12 FED COM	Well Location: T23S / R32E / SEC 24 / SESW / 32.283609 / -103.631862	County or Parish/State: LEA / NM
Well Number: 4H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM86154	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002547467	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Notice of Intent

Sundry ID: 2739439

Type of Submission: Notice of Intent	Type of Action: APD Change
Date Sundry Submitted: 07/06/2023	Time Sundry Submitted: 08:12
Date proposed operation will begin: 07/05/2023	

Procedure Description: Devon Energy Production Company, L.P. respectfully requests a NAME & BHL move: Name change from SNEAKY SNAKE 24-12 FED COM 4H to SNEAKY SNAKE 24 FED COM 4H. BHL move from 20 FNL & 2310 FWL, 12-23S-32E to 20 FNL to 2300 FWL, 13-23S-32E. New leases have been added since approved APD and notification has been given. TVD/MD change from 12570'/17572' to 12,570'/22,881'. Spacing acreage change from 480acs to 320acs. Pool Name/Code remains [17645] DIAMONDTAIL;WOLFCAMP. Casing program change from Hole Size Csg. Size Wt (PPF) Grade Conn From (MD) To (MD) From (TVD) To (TVD 17 1/2 13 3/8 48 H40 STC 0 1255 0 1255 9 7/8 8 5/8 32 P110 TLW 0 11122 0 11122 7 7/8 5 1/2 17 P110 BTC 0 28166 0 12570 To Hole Size Csg. Size Wt (PPF) Grade Conn From (MD) To (MD) From (TVD) To (TVD 14 3/4 10 3/4 45.5 J-55 BTC 0 1255 0 1255 9 7/8 8 5/8 32 P110 Sprint FJ 0 11622 0 11622 7 7/8 5 1/2 20 P110EC DWC/C-IS+ 0 22881 0 12570 Cement volume changes to accommodate casing changes. Please see revised C-102, Drilling and Directional plans

NOI Attachments

Procedure Description

- SNEAKY_SNAKE_24_FED_COM_4H_C_102_BHL_NOI_20230706081151.pdf
- SNEAKY_SNAKE_24_FED_COM_4H_Directional_Plan_06_30_23_20230705145425.pdf
- SNEAKY_SNAKE_24_FED_COM_4H_20230705145425.pdf

Received by OCD: 9/15/2023 10:15:43 AM

Page 2 of 27

Well Name: SNEAKY SNAKE 24-12 FED COM	Well Location: T23S / R32E / SEC 24 / SESW / 32.283609 / -103.631862	County or Parish/State: LEA / NM
Well Number: 4H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM86154	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002547467	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Conditions of Approval

Additional

Sneaky_Snake_24_Fed_Com_4H_Dr_COA_20230726074056.pdf
24_23_32_N_Sundry_ID_2739439_Sneaky_Snake_20230726074056.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: REBECCA DEAL
Signed on: JUL 05, 2023 02:52 PM
Name: DEVON ENERGY PRODUCTION COMPANY LP
Title: Regulatory Analyst
Street Address: 333 W SHERIDAN AVE
City: OKLAHOMA CITY State: OK
Phone: (303) 299-1406
Email address: REBECCA.DEAL@DVN.COM

Field

Representative Name:
Street Address:
City: State: Zip:
Phone:
Email address:

BLM Point of Contact

BLM POC Name: CODY LAYTON
BLM POC Title: Assistant Field Manager Lands & Minerals
BLM POC Phone: 5752345959
BLM POC Email Address: clayton@blm.gov
Disposition: Approved
Disposition Date: 09/13/2023
Signature: Cody R. Layton

Form 3160-5
(June 2019)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2021**SUNDRY NOTICES AND REPORTS ON WELLS**
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well

☐ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

3a. Address

3b. Phone No. (include area code)

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

9. API Well No.

10. Field and Pool or Exploratory Area

11. Country or Parish, State

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon		
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal		

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

Title

Signature

Date

THE SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Additional Remarks

9 7/8 8 5/8 32 P110 Sprint FJ 0 11622 0 11622

7 7/8 5 1/2 20 P110EC DWC/C-IS+ 0 22881 0 12570

Cement volume changes to accommodate casing changes. Please see revised C-102, Drilling and Directional plans

Location of Well

0. SHL: SESW / 230 FSL / 1553 FWL / TWSP: 23S / RANGE: 32E / SECTION: 24 / LAT: 32.283609 / LONG: -103.631862 (TVD: 0 feet, MD: 0 feet)

PPP: SESW / 100 FSL / 2255 FWL / TWSP: 23S / RANGE: 32E / SECTION: 24 / LAT: 32.283258 / LONG: -103.62959 (TVD: 12231 feet, MD: 12268 feet)

BHL: NENW / 20 FNL / 2310 FWL / TWSP: 23S / RANGE: 32E / SECTION: 12 / LAT: 32.297445 / LONG: -103.6296 (TVD: 12570 feet, MD: 28166 feet)

CONFIDENTIAL

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company LP
LEASE NO.:	NMNM086154
LOCATION:	Section 24, T.23 S., R.32 E., NMPM
COUNTY:	Lea County, New Mexico

WELL NAME & NO.:	Sneaky Snake 24 Fed Com 4H
SURFACE HOLE FOOTAGE:	230'/S & 1553'/W
BOTTOM HOLE FOOTAGE:	20'/N & 2300'/W

COA

H2S	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	
Potash	<input checked="" type="checkbox"/> None	<input type="checkbox"/> Secretary	<input type="checkbox"/> R-111-P
Cave/Karst Potential	<input checked="" type="checkbox"/> Low	<input type="checkbox"/> Medium	<input type="checkbox"/> High
Cave/Karst Potential	<input type="checkbox"/> Critical		
Variance	<input type="checkbox"/> None	<input checked="" type="checkbox"/> Flex Hose	<input type="checkbox"/> Other
Wellhead	<input type="checkbox"/> Conventional	<input checked="" type="checkbox"/> Multibowl	<input type="checkbox"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input checked="" type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Bone Springs and Brushy Canyon** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **10-3/4** inch surface casing shall be set at approximately **1320 feet** (a minimum of **25 feet (Lea County)**) into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.

Operator has proposed to pump down 10-3/4" X 8-5/8" annulus. Operator must run a CBL from TD of the 8-5/8" casing to surface. Submit results to BLM.

Production casing must be kept fluid filled to meet BLM minimum collapse requirement.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.
Cement excess is less than 25%, more cement might be required.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2.

Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **8-5/8** inch intermediate casing shoe shall be **10,000 (10M) psi**. **Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**

Option 2:

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the **10-3/4** inch surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M)** psi. **Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)**Communitization Agreement**

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

24-23-32-N Sundry ID 2739439 Sneaky Snake 24 Fed Com 4H Lea NM086154 Devon Energy Production Company LP
13-22b 4-7-2020 LV.xlsm

Sneaky Snake 24 Fed Com 4H

10 3/4	surface csg in a	14 3/4	inch hole.	Design Factors					Surface			
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	B@s	a-B	a-C	Weight	
"A"	45.50	j 55	btc	11.91	3.39	0.56	1,320	6	0.95	6.40	60,060	
"B"			btc				0				0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 1,500				Tail Cmt	does not	circ to sfc.	Totals:	1,320			60,060	
Comparison of Proposed to Minimum Required Cement Volumes												
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd			Min Dist	
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE			Hole-Cplg	
14 3/4	0.5563	751	1081	734	47	9.00	3782	5M			1.50	
Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.												
Site plat (pipe racks 5 or 6) as per O.O.I.III.D.4.I: not found.												

8 5/8	casing inside the	10 3/4		Design Factors					Int 1			
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight	
"A"	32.00	p 110	vam sprint fj	2.00	0.63	1.04	11,622	1	1.75	1.06	371,904	
"B"							0				0	
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	11,622			371,904	
The cement volume(s) are intended to achieve a top of				0		ft from surface or a	1320				overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd			Min Dist	
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE			Hole-Cplg	
9 7/8	0.1261	836	1883	1477	28	10.50	4091	5M			0.61	
Class 'H' tail cmt yld > 1.20												

5 1/2	casing inside the	8 5/8		Design Factors					Prod 1			
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight	
"A"	20.00	p 110	dwc/c is+	2.90	1.76	2.09	22,881	2	3.51	2.96	457,620	
"B"							0				0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,765							Totals:	22,881			457,620	
The cement volume(s) are intended to achieve a top of				11422		ft from surface or a	200				overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd			Min Dist	
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE			Hole-Cplg	
7 7/8	0.1733	1551	2451	1986	23	10.50					1.19	
Class 'C' tail cmt yld > 1.35												

0		5 1/2		Design Factors					<Choose Casing>			
Segment	#/ft	Grade	Coupling	#N/A	Collapse	Burst	Length	B@s	a-B	a-C	Weight	
"A"			0.00				0				0	
"B"			0.00				0				0	
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	0			0	
Cmt vol calc below includes this csg, TOC intended				#N/A		ft from surface or a	#N/A				overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd			Min Dist	
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE			Hole-Cplg	
0		#N/A	#N/A	0	#N/A							
#N/A Capitan Reef est top XXXX.												

DISTRICT I
1625 N. FRENCH DR., HOBBS, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II
811 S. FIRST ST., ARTESIA, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III
1000 RIO BRAZOS RD., AZTEC, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

Form C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☒ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-025-47467		Pool Code 98177	Pool Name WC-025 G-09 S223332A;UPR WOLFCAMP
Property Code 328900	Property Name SNEAKY SNAKE 24 FED COM		Well Number 4H
OGRID No. 6137	Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.		Elevation 3717.5'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	24	23-S	32-E		230	SOUTH	1553	WEST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	13	23-S	32-E		20	NORTH	2300	WEST	LEA

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
320			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

SNEAKY SNAKE 24 FED COM 4H

EL: 3717.5'
GEODEIC COORDINATES NAD 83
NMSP EAST SURFACE LOCATION
N:467618.48
E:758115.72
LAT:32.283609
LON:103.631862
KICK OFF POINT
CALLS: 50' ESL 2298' FWL
N: 758862.2513
E: 467446.1322
LAT: 32.2830
LON: -103.6295

FIRST TAKE POINT (PPP 1)
100' FSL 2300' FWL SEC. 24
N:467495.75
E:758863.66
LAT:32.283258
LON:103.629444

LAST TAKE POINT
100' FNL 2300' FWL SEC. 13
N:477858.43
E:758789.75
LAT:32.311743
LON:103.629463


BOTTOM OF HOLE
N:477938.42
E:758789.19
LAT:32.311963
LON:103.629463

(PPP 2)
2642' FSL 2301' FWL SEC. 24
N:470037.88
E:758845.53
LAT:32.290246
LON:103.629449

(PPP 3)
0' FSL 2300' FWL SEC. 13
N:472677.06
E:758826.70
LAT:32.297500
LON:103.629454

(PPP 4)
1319' FNL 2300' FWL SEC. 13
N:476639.35
E:758798.45
LAT:32.308392
LON:103.629461

A	=	N:477938.40	E:756489.13
B	=	N:477961.43	E:759134.44
C	=	N:477986.21	E:761782.42
D	=	N:475296.77	E:756507.78
E	=	N:475350.88	E:761800.41
F	=	N:472655.16	E:756526.45
G	=	N:472680.34	E:759171.22
H	=	N:472706.24	E:761818.45
I	=	N:470014.05	E:756544.88
J	=	N:470068.85	E:761836.05
K	=	N:467373.38	E:756564.50
L	=	N:467399.10	E:759208.52
M	=	N:467425.40	E:761852.95



OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization with over a working interest or undivided mineral interest in the land including the proposed bottom hole location or has the right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Rebecca Deal 7/5/2023
Signature Date

Rebecca Deal, Regulatory Analyst
Printed Name

rebecca.deal@dvn.com
E-mail Address


SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

06/24/2021

Date of Survey

Signature & Seal of Professional Surveyor



06/19/23

Certificate No. 22404	B.L. LAMAN
	DRAWN BY: CM

Intent ☒ As Drilled ☐

API # 30-025-47467		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, LP.	Property Name: SNEAKY SNAKE 24 FED COM	Well Number 4H

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
	24	23S	32E		50	FSL	2298	FWL	LEA
Latitude 32.2830					Longitude -103.6295				NAD 83

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
N	24	23-S	32-E		100	SOUTH	2300	WEST	LEA
Latitude 32.283258					Longitude 103.629444				NAD 83

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
C	13	23-S	32-E		100	NORTH	2300	WEST	LEA
Latitude 32.311743					Longitude 103.629463				NAD 83

Is this well the defining well for the Horizontal Spacing Unit? ☐ NIs this well an infill well? ☐ Y

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, LP.	Property Name: SNEAKY SNAKE 24 FED COM	Well Number 3H


KZ 06/29/2018



Well: SNEAKY SNAKE 24 FED COM 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
2000.00	0.00	103.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2500.00	10.00	103.00	2497.47	-9.79	42.41	-7.01	2.00	Hold Tangent
6410.90	10.00	103.00	6348.95	-162.56	704.12	-116.37	0.00	Drop to Vertical
6910.90	0.00	103.00	6846.41	-172.35	746.53	-123.38	2.00	Hold Vertical
12061.53	0.00	359.60	11997.04	-172.35	746.53	-123.38	0.00	KOP
12961.53	90.00	359.60	12570.00	400.59	742.53	448.08	10.00	Landing Point
22881.11	90.00	359.60	12570.00	10319.94	673.28	10341.88	0.00	BHL



Key Depths	MD	TVD
	(ft)	(ft)
Rustler	1230.00	1230.00
Salt	1765.00	1765.00
Base of Salt	5030.99	4990.00
Delaware	5030.99	4990.00
Bone Spring 1st	8904.48	8840.00
Bone Spring 2nd	10339.48	10275.00
Bone Spring 3rd	11186.48	11122.00
Wolfcamp / Point of Penetration	12323.52	12250.00
Exit	22801.11	12570.01

SHL
KOP
Point of Penetration
Exit
BHL

MD	TVD	Lat	Long	Section Footages
(ft)	(ft)	(°)	(°)	
0.00	0.00	32.2835	-103.6319	230' FSL, 1553' FWL of Sec 24 in T23S, R32E
12061.53	11997.04	32.2830	-103.6295	50' FSL, 2298' FWL of Sec 24 in T23S, R32E
12323.52	12250.00	32.2833	-103.6294	100' FSL, 2300' FWL of Sec 24 in T23S, R32E
22801.11	12570.01	32.3117	-103.6295	100' FNL, 2300' FWL of Sec 13 in T23S, R32E
22881.11	12570.00	32.3119	-103.6295	20' FNL, 2300' FWL of Sec 13 in T23S, R32E

SNEAKY SNAKE 24 FED COM 4H



Well: SNEAKY SNAKE 24 FED COM 4H
 County: Lea
 Wellbore: Permit Plan
 Design: Permit Plan #1

Geodetic System: US State Plane 1983
 Datum: North American Datum 1927
 Ellipsoid: Clarke 1866
 Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
100.00	0.00	103.00	100.00	0.00	0.00	0.00	0.00	
200.00	0.00	103.00	200.00	0.00	0.00	0.00	0.00	
300.00	0.00	103.00	300.00	0.00	0.00	0.00	0.00	
400.00	0.00	103.00	400.00	0.00	0.00	0.00	0.00	
500.00	0.00	103.00	500.00	0.00	0.00	0.00	0.00	
600.00	0.00	103.00	600.00	0.00	0.00	0.00	0.00	
700.00	0.00	103.00	700.00	0.00	0.00	0.00	0.00	
800.00	0.00	103.00	800.00	0.00	0.00	0.00	0.00	
900.00	0.00	103.00	900.00	0.00	0.00	0.00	0.00	
1000.00	0.00	103.00	1000.00	0.00	0.00	0.00	0.00	
1100.00	0.00	103.00	1100.00	0.00	0.00	0.00	0.00	
1200.00	0.00	103.00	1200.00	0.00	0.00	0.00	0.00	
1230.00	0.00	103.00	1230.00	0.00	0.00	0.00	0.00	Rustler
1300.00	0.00	103.00	1300.00	0.00	0.00	0.00	0.00	
1400.00	0.00	103.00	1400.00	0.00	0.00	0.00	0.00	
1500.00	0.00	103.00	1500.00	0.00	0.00	0.00	0.00	
1600.00	0.00	103.00	1600.00	0.00	0.00	0.00	0.00	
1700.00	0.00	103.00	1700.00	0.00	0.00	0.00	0.00	
1765.00	0.00	103.00	1765.00	0.00	0.00	0.00	0.00	Salt
1800.00	0.00	103.00	1800.00	0.00	0.00	0.00	0.00	
1900.00	0.00	103.00	1900.00	0.00	0.00	0.00	0.00	
2000.00	0.00	103.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2100.00	2.00	103.00	2099.98	-0.39	1.70	-0.28	2.00	
2200.00	4.00	103.00	2199.84	-1.57	6.80	-1.12	2.00	
2300.00	6.00	103.00	2299.45	-3.53	15.29	-2.53	2.00	
2400.00	8.00	103.00	2398.70	-6.27	27.17	-4.49	2.00	
2500.00	10.00	103.00	2497.47	-9.79	42.41	-7.01	2.00	Hold Tangent
2600.00	10.00	103.00	2595.95	-13.70	59.33	-9.81	0.00	
2700.00	10.00	103.00	2694.43	-17.60	76.25	-12.60	0.00	
2800.00	10.00	103.00	2792.91	-21.51	93.17	-15.40	0.00	
2900.00	10.00	103.00	2891.39	-25.42	110.09	-18.19	0.00	
3000.00	10.00	103.00	2989.87	-29.32	127.01	-20.99	0.00	
3100.00	10.00	103.00	3088.35	-33.23	143.93	-23.79	0.00	
3200.00	10.00	103.00	3186.83	-37.13	160.85	-26.58	0.00	
3300.00	10.00	103.00	3285.31	-41.04	177.77	-29.38	0.00	
3400.00	10.00	103.00	3383.79	-44.95	194.68	-32.18	0.00	
3500.00	10.00	103.00	3482.27	-48.85	211.60	-34.97	0.00	
3600.00	10.00	103.00	3580.75	-52.76	228.52	-37.77	0.00	
3700.00	10.00	103.00	3679.23	-56.66	245.44	-40.57	0.00	
3800.00	10.00	103.00	3777.72	-60.57	262.36	-43.36	0.00	
3900.00	10.00	103.00	3876.20	-64.48	279.28	-46.16	0.00	
4000.00	10.00	103.00	3974.68	-68.38	296.20	-48.95	0.00	
4100.00	10.00	103.00	4073.16	-72.29	313.12	-51.75	0.00	
4200.00	10.00	103.00	4171.64	-76.20	330.04	-54.55	0.00	
4300.00	10.00	103.00	4270.12	-80.10	346.96	-57.34	0.00	
4400.00	10.00	103.00	4368.60	-84.01	363.88	-60.14	0.00	
4500.00	10.00	103.00	4467.08	-87.91	380.80	-62.94	0.00	
4600.00	10.00	103.00	4565.56	-91.82	397.72	-65.73	0.00	
4700.00	10.00	103.00	4664.04	-95.73	414.64	-68.53	0.00	
4800.00	10.00	103.00	4762.52	-99.63	431.56	-71.33	0.00	
4900.00	10.00	103.00	4861.00	-103.54	448.48	-74.12	0.00	
5000.00	10.00	103.00	4959.48	-107.45	465.40	-76.92	0.00	
5030.99	10.00	103.00	4990.00	-108.66	470.64	-77.78	0.00	Base of Salt, Delaware
5100.00	10.00	103.00	5057.97	-111.35	482.32	-79.71	0.00	
5200.00	10.00	103.00	5156.45	-115.26	499.24	-82.51	0.00	
5300.00	10.00	103.00	5254.93	-119.16	516.16	-85.31	0.00	
5400.00	10.00	103.00	5353.41	-123.07	533.08	-88.10	0.00	
5500.00	10.00	103.00	5451.89	-126.98	550.00	-90.90	0.00	
5600.00	10.00	103.00	5550.37	-130.88	566.92	-93.70	0.00	
5700.00	10.00	103.00	5648.85	-134.79	583.84	-96.49	0.00	
5800.00	10.00	103.00	5747.33	-138.70	600.76	-99.29	0.00	
5900.00	10.00	103.00	5845.81	-142.60	617.68	-102.09	0.00	
6000.00	10.00	103.00	5944.29	-146.51	634.60	-104.88	0.00	
6100.00	10.00	103.00	6042.77	-150.41	651.52	-107.68	0.00	
6200.00	10.00	103.00	6141.25	-154.32	668.44	-110.48	0.00	
6300.00	10.00	103.00	6239.73	-158.23	685.36	-113.27	0.00	
6400.00	10.00	103.00	6338.22	-162.13	702.28	-116.07	0.00	
6410.90	10.00	103.00	6348.95	-162.56	704.12	-116.37	0.00	Drop to Vertical
6500.00	8.22	103.00	6436.92	-165.73	717.87	-118.65	2.00	

SNEAKY SNAKE 24 FED COM 4H



Well: SNEAKY SNAKE 24 FED COM 4H
 County: Lea
 Wellbore: Permit Plan
 Design: Permit Plan #1

Geodetic System: US State Plane 1983
 Datum: North American Datum 1927
 Ellipsoid: Clarke 1866
 Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
6600.00	6.22	103.00	6536.13	-168.56	730.11	-120.67	2.00	
6700.00	4.22	103.00	6635.71	-170.60	738.97	-122.13	2.00	
6800.00	2.22	103.00	6735.54	-171.87	744.44	-123.04	2.00	
6900.00	0.22	103.00	6835.52	-172.34	746.51	-123.38	2.00	
6910.90	0.00	103.00	6846.41	-172.35	746.53	-123.38	2.00	Hold Vertical
7000.00	0.00	359.60	6935.52	-172.35	746.53	-123.38	0.00	
7100.00	0.00	359.60	7035.52	-172.35	746.53	-123.38	0.00	
7200.00	0.00	359.60	7135.52	-172.35	746.53	-123.38	0.00	
7300.00	0.00	359.60	7235.52	-172.35	746.53	-123.38	0.00	
7400.00	0.00	359.60	7335.52	-172.35	746.53	-123.38	0.00	
7500.00	0.00	359.60	7435.52	-172.35	746.53	-123.38	0.00	
7600.00	0.00	359.60	7535.52	-172.35	746.53	-123.38	0.00	
7700.00	0.00	359.60	7635.52	-172.35	746.53	-123.38	0.00	
7800.00	0.00	359.60	7735.52	-172.35	746.53	-123.38	0.00	
7900.00	0.00	359.60	7835.52	-172.35	746.53	-123.38	0.00	
8000.00	0.00	359.60	7935.52	-172.35	746.53	-123.38	0.00	
8100.00	0.00	359.60	8035.52	-172.35	746.53	-123.38	0.00	
8200.00	0.00	359.60	8135.52	-172.35	746.53	-123.38	0.00	
8300.00	0.00	359.60	8235.52	-172.35	746.53	-123.38	0.00	
8400.00	0.00	359.60	8335.52	-172.35	746.53	-123.38	0.00	
8500.00	0.00	359.60	8435.52	-172.35	746.53	-123.38	0.00	
8600.00	0.00	359.60	8535.52	-172.35	746.53	-123.38	0.00	
8700.00	0.00	359.60	8635.52	-172.35	746.53	-123.38	0.00	
8800.00	0.00	359.60	8735.52	-172.35	746.53	-123.38	0.00	
8900.00	0.00	359.60	8835.52	-172.35	746.53	-123.38	0.00	
8904.48	0.00	359.60	8840.00	-172.35	746.53	-123.38	0.00	Bone Spring 1st
9000.00	0.00	359.60	8935.52	-172.35	746.53	-123.38	0.00	
9100.00	0.00	359.60	9035.52	-172.35	746.53	-123.38	0.00	
9200.00	0.00	359.60	9135.52	-172.35	746.53	-123.38	0.00	
9300.00	0.00	359.60	9235.52	-172.35	746.53	-123.38	0.00	
9400.00	0.00	359.60	9335.52	-172.35	746.53	-123.38	0.00	
9500.00	0.00	359.60	9435.52	-172.35	746.53	-123.38	0.00	
9600.00	0.00	359.60	9535.52	-172.35	746.53	-123.38	0.00	
9700.00	0.00	359.60	9635.52	-172.35	746.53	-123.38	0.00	
9800.00	0.00	359.60	9735.52	-172.35	746.53	-123.38	0.00	
9900.00	0.00	359.60	9835.52	-172.35	746.53	-123.38	0.00	
10000.00	0.00	359.60	9935.52	-172.35	746.53	-123.38	0.00	
10100.00	0.00	359.60	10035.52	-172.35	746.53	-123.38	0.00	
10200.00	0.00	359.60	10135.52	-172.35	746.53	-123.38	0.00	
10300.00	0.00	359.60	10235.52	-172.35	746.53	-123.38	0.00	
10339.48	0.00	359.60	10275.00	-172.35	746.53	-123.38	0.00	Bone Spring 2nd
10400.00	0.00	359.60	10335.52	-172.35	746.53	-123.38	0.00	
10500.00	0.00	359.60	10435.52	-172.35	746.53	-123.38	0.00	
10600.00	0.00	359.60	10535.52	-172.35	746.53	-123.38	0.00	
10700.00	0.00	359.60	10635.52	-172.35	746.53	-123.38	0.00	
10800.00	0.00	359.60	10735.52	-172.35	746.53	-123.38	0.00	
10900.00	0.00	359.60	10835.52	-172.35	746.53	-123.38	0.00	
11000.00	0.00	359.60	10935.52	-172.35	746.53	-123.38	0.00	
11100.00	0.00	359.60	11035.52	-172.35	746.53	-123.38	0.00	
11186.48	0.00	359.60	11122.00	-172.35	746.53	-123.38	0.00	Bone Spring 3rd
11200.00	0.00	359.60	11135.52	-172.35	746.53	-123.38	0.00	
11300.00	0.00	359.60	11235.52	-172.35	746.53	-123.38	0.00	
11400.00	0.00	359.60	11335.52	-172.35	746.53	-123.38	0.00	
11500.00	0.00	359.60	11435.52	-172.35	746.53	-123.38	0.00	
11600.00	0.00	359.60	11535.52	-172.35	746.53	-123.38	0.00	
11700.00	0.00	359.60	11635.52	-172.35	746.53	-123.38	0.00	
11800.00	0.00	359.60	11735.52	-172.35	746.53	-123.38	0.00	
11900.00	0.00	359.60	11835.52	-172.35	746.53	-123.38	0.00	
12000.00	0.00	359.60	11935.52	-172.35	746.53	-123.38	0.00	
12061.53	0.00	359.60	11997.04	-172.35	746.53	-123.38	0.00	KOP
12100.00	3.85	359.60	12035.49	-171.06	746.52	-122.09	10.00	
12200.00	13.85	359.60	12134.17	-155.70	746.41	-106.77	10.00	
12300.00	23.85	359.60	12228.69	-123.44	746.19	-74.59	10.00	
12323.52	26.20	359.60	12250.00	-113.49	746.12	-64.67	10.00	Wolfcamp / Point of Penetration
12400.00	33.85	359.60	12316.17	-75.25	745.85	-26.53	10.00	
12500.00	43.85	359.60	12393.95	-12.61	745.41	35.95	10.00	
12600.00	53.85	359.60	12459.68	62.59	744.89	110.95	10.00	
12700.00	63.85	359.60	12511.34	148.06	744.29	196.20	10.00	
12800.00	73.85	359.60	12547.38	241.20	743.64	289.10	10.00	
12900.00	83.85	359.60	12566.70	339.19	742.95	386.84	10.00	

SNEAKY SNAKE 24 FED COM 4H



Well: SNEAKY SNAKE 24 FED COM 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
12961.53	90.00	359.60	12570.00	400.59	742.53	448.08	10.00	Landing Point
13000.00	90.00	359.60	12570.00	439.07	742.26	486.46	0.00	
13100.00	90.00	359.60	12570.00	539.06	741.56	586.20	0.00	
13200.00	90.00	359.60	12570.00	639.06	740.86	685.94	0.00	
13300.00	90.00	359.60	12570.00	739.06	740.16	785.68	0.00	
13400.00	90.00	359.60	12570.00	839.06	739.46	885.42	0.00	
13500.00	90.00	359.60	12570.00	939.05	738.77	985.16	0.00	
13600.00	90.00	359.60	12570.00	1039.05	738.07	1084.90	0.00	
13700.00	90.00	359.60	12570.00	1139.05	737.37	1184.64	0.00	
13800.00	90.00	359.60	12570.00	1239.05	736.67	1284.38	0.00	
13900.00	90.00	359.60	12570.00	1339.04	735.97	1384.12	0.00	
14000.00	90.00	359.60	12570.00	1439.04	735.27	1483.86	0.00	
14100.00	90.00	359.60	12570.00	1539.04	734.57	1583.60	0.00	
14200.00	90.00	359.60	12570.00	1639.04	733.88	1683.34	0.00	
14300.00	90.00	359.60	12570.00	1739.04	733.18	1783.08	0.00	
14400.00	90.00	359.60	12570.00	1839.03	732.48	1882.82	0.00	
14500.00	90.00	359.60	12570.00	1939.03	731.78	1982.56	0.00	
14600.00	90.00	359.60	12570.00	2039.03	731.08	2082.30	0.00	
14700.00	90.00	359.60	12570.00	2139.03	730.38	2182.04	0.00	
14800.00	90.00	359.60	12570.00	2239.02	729.68	2281.78	0.00	
14900.00	90.00	359.60	12570.00	2339.02	728.99	2381.52	0.00	
15000.00	90.00	359.60	12570.00	2439.02	728.29	2481.26	0.00	
15100.00	90.00	359.60	12570.00	2539.02	727.59	2581.00	0.00	
15200.00	90.00	359.60	12570.00	2639.01	726.89	2680.74	0.00	
15300.00	90.00	359.60	12570.00	2739.01	726.19	2780.48	0.00	
15400.00	90.00	359.60	12570.00	2839.01	725.49	2880.22	0.00	
15500.00	90.00	359.60	12570.00	2939.01	724.79	2979.96	0.00	
15600.00	90.00	359.60	12570.00	3039.00	724.09	3079.70	0.00	
15700.00	90.00	359.60	12570.00	3139.00	723.40	3179.44	0.00	
15800.00	90.00	359.60	12570.00	3239.00	722.70	3279.18	0.00	
15900.00	90.00	359.60	12570.00	3339.00	722.00	3378.92	0.00	
16000.00	90.00	359.60	12570.00	3438.99	721.30	3478.66	0.00	
16100.00	90.00	359.60	12570.00	3538.99	720.60	3578.40	0.00	
16200.00	90.00	359.60	12570.00	3638.99	719.90	3678.14	0.00	
16300.00	90.00	359.60	12570.00	3738.99	719.20	3777.88	0.00	
16400.00	90.00	359.60	12570.00	3838.98	718.51	3877.62	0.00	
16500.00	90.00	359.60	12570.00	3938.98	717.81	3977.36	0.00	
16600.00	90.00	359.60	12570.00	4038.98	717.11	4077.10	0.00	
16700.00	90.00	359.60	12570.00	4138.98	716.41	4176.84	0.00	
16800.00	90.00	359.60	12570.01	4238.97	715.71	4276.58	0.00	
16900.00	90.00	359.60	12570.01	4338.97	715.01	4376.32	0.00	
17000.00	90.00	359.60	12570.01	4438.97	714.31	4476.06	0.00	
17100.00	90.00	359.60	12570.01	4538.97	713.61	4575.80	0.00	
17200.00	90.00	359.60	12570.01	4638.96	712.92	4675.54	0.00	
17300.00	90.00	359.60	12570.01	4738.96	712.22	4775.28	0.00	
17400.00	90.00	359.60	12570.01	4838.96	711.52	4875.02	0.00	
17500.00	90.00	359.60	12570.01	4938.96	710.82	4974.76	0.00	
17600.00	90.00	359.60	12570.01	5038.95	710.12	5074.50	0.00	
17700.00	90.00	359.60	12570.01	5138.95	709.42	5174.24	0.00	
17800.00	90.00	359.60	12570.01	5238.95	708.72	5273.98	0.00	
17900.00	90.00	359.60	12570.01	5338.95	708.03	5373.72	0.00	
18000.00	90.00	359.60	12570.01	5438.94	707.33	5473.46	0.00	
18100.00	90.00	359.60	12570.01	5538.94	706.63	5573.20	0.00	
18200.00	90.00	359.60	12570.01	5638.94	705.93	5672.94	0.00	
18300.00	90.00	359.60	12570.01	5738.94	705.23	5772.68	0.00	
18400.00	90.00	359.60	12570.01	5838.94	704.53	5872.42	0.00	
18500.00	90.00	359.60	12570.01	5938.93	703.83	5972.16	0.00	
18600.00	90.00	359.60	12570.01	6038.93	703.13	6071.90	0.00	
18700.00	90.00	359.60	12570.01	6138.93	702.44	6171.64	0.00	
18800.00	90.00	359.60	12570.01	6238.93	701.74	6271.38	0.00	
18900.00	90.00	359.60	12570.01	6338.92	701.04	6371.12	0.00	
19000.00	90.00	359.60	12570.01	6438.92	700.34	6470.85	0.00	
19100.00	90.00	359.60	12570.01	6538.92	699.64	6570.59	0.00	
19200.00	90.00	359.60	12570.01	6638.92	698.94	6670.33	0.00	
19300.00	90.00	359.60	12570.01	6738.91	698.24	6770.07	0.00	
19400.00	90.00	359.60	12570.01	6838.91	697.55	6869.81	0.00	
19500.00	90.00	359.60	12570.01	6938.91	696.85	6969.55	0.00	
19600.00	90.00	359.60	12570.01	7038.91	696.15	7069.29	0.00	
19700.00	90.00	359.60	12570.01	7138.90	695.45	7169.03	0.00	
19800.00	90.00	359.60	12570.01	7238.90	694.75	7268.77	0.00	

SNEAKY SNAKE 24 FED COM 4H



Well: SNEAKY SNAKE 24 FED COM 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
19900.00	90.00	359.60	12570.01	7338.90	694.05	7368.51	0.00	
20000.00	90.00	359.60	12570.01	7438.90	693.35	7468.25	0.00	
20100.00	90.00	359.60	12570.01	7538.89	692.66	7567.99	0.00	
20200.00	90.00	359.60	12570.01	7638.89	691.96	7667.73	0.00	
20300.00	90.00	359.60	12570.01	7738.89	691.26	7767.47	0.00	
20400.00	90.00	359.60	12570.01	7838.89	690.56	7867.21	0.00	
20500.00	90.00	359.60	12570.01	7938.88	689.86	7966.95	0.00	
20600.00	90.00	359.60	12570.01	8038.88	689.16	8066.69	0.00	
20700.00	90.00	359.60	12570.01	8138.88	688.46	8166.43	0.00	
20800.00	90.00	359.60	12570.01	8238.88	687.76	8266.17	0.00	
20900.00	90.00	359.60	12570.01	8338.87	687.07	8365.91	0.00	
21000.00	90.00	359.60	12570.01	8438.87	686.37	8465.65	0.00	
21100.00	90.00	359.60	12570.01	8538.87	685.67	8565.39	0.00	
21200.00	90.00	359.60	12570.01	8638.87	684.97	8665.13	0.00	
21300.00	90.00	359.60	12570.01	8738.86	684.27	8764.87	0.00	
21400.00	90.00	359.60	12570.01	8838.86	683.57	8864.61	0.00	
21500.00	90.00	359.60	12570.01	8938.86	682.87	8964.35	0.00	
21600.00	90.00	359.60	12570.01	9038.86	682.18	9064.09	0.00	
21700.00	90.00	359.60	12570.01	9138.85	681.48	9163.83	0.00	
21800.00	90.00	359.60	12570.01	9238.85	680.78	9263.57	0.00	
21900.00	90.00	359.60	12570.01	9338.85	680.08	9363.31	0.00	
22000.00	90.00	359.60	12570.01	9438.85	679.38	9463.05	0.00	
22100.00	90.00	359.60	12570.01	9538.84	678.68	9562.79	0.00	
22200.00	90.00	359.60	12570.01	9638.84	677.98	9662.53	0.00	
22300.00	90.00	359.60	12570.01	9738.84	677.28	9762.27	0.00	
22400.00	90.00	359.60	12570.01	9838.84	676.59	9862.01	0.00	
22500.00	90.00	359.60	12570.01	9938.84	675.89	9961.75	0.00	
22600.00	90.00	359.60	12570.01	10038.83	675.19	10061.49	0.00	
22700.00	90.00	359.60	12570.01	10138.83	674.49	10161.23	0.00	
22800.00	90.00	359.60	12570.01	10238.83	673.79	10260.97	0.00	
22801.11	90.00	359.60	12570.01	10239.94	673.78	10262.08	0.00	Exit
22881.11	90.00	359.60	12570.00	10319.94	673.28	10341.88	0.00	BHL

SNEAKY SNAKE 24 FED COM 4H

1. Geologic Formations

TVD of target	12570	Pilot hole depth	N/A
MD at TD:	22881	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	1230		
Salt	1765		
Base of Salt	4990		
Delaware	4990		
Bone Spring 1st	8840		
Bone Spring 2nd	10275		
Bone Spring 3rd	11122		
Wolfcamp	12250		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

SNEAKY SNAKE 24 FED COM 4H

2. Casing Program (Primary Design)

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
14 3/4	10 3/4	45 1/2	J-55	BTC	0	1255	0	1255
9 7/8	8 5/8	32	P110	Sprint FJ	0	11622	0	11622
7 7/8	5 1/2	20	P110EC	DWC/C-IS+	0	22881	0	12570

• All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.

3. Cementing Program (Primary Design)

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	751	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	371	Surf	9	3.27	Lead: Class C Cement + additives
	465	7622	13.2	1.44	Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.44	Squeeze Lead: Class C Cement + additives
	371	Surf	9	3.27	Lead: Class C Cement + additives
	465	7622	13.2	1.44	Tail: Class H / C + additives
Production	119	10062	9	3.27	Lead: Class H / C + additives
	1432	12062	13.2	1.44	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

SNEAKY SNAKE 24 FED COM 4H

4. Pressure Control Equipment (Three String Design)

BOP installed and tested before drilling which hole?		Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular		X	50% of rated working pressure
			Blind Ram		X	5M
			Pipe Ram			
			Double Ram		X	
			Other*			
Production	13-5/8"	10M	Annular (5M)		X	100% of rated working pressure
			Blind Ram		X	10M
			Pipe Ram			
			Double Ram		X	
			Other*			
			Annular (5M)			
			Blind Ram			
			Pipe Ram			
			Double Ram			
			Other*			
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
Y	A variance is requested to run a 5 M annular on a 10M system					

SNEAKY SNAKE 24 FED COM 4H

5. Mud Program (Three String Design)

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	10-10.5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH pressure at deepest TVD	6863
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S plan attached.

SNEAKY SNAKE 24 FED COM 4H

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan
 Other, describe

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 265713

CONDITIONS

Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102	OGRID: 6137
	Action Number: 265713
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
pkautz	None	10/26/2023