



U.S. Department of the Interior
Bureau of Land Management

Application for Permit to Drill

APD Package Report

Date Printed: 01/29/2024 03:38 PM

APD ID: 10400085975

Well Status: AAPD

APD Received Date: 06/09/2022 08:05 AM

Well Name: KOALA 9 FED COM

Operator: COLGATE OPERATING LLC

Well Number: 121H

APD Package Report Contents

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
 - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 1 file(s)
 - Blowout Prevention BOP Diagram Attachment: 1 file(s)
 - Casing Spec Documents: 2 file(s)
 - Casing Design Assumptions and Worksheet(s): 4 file(s)
 - Hydrogen sulfide drilling operations plan: 1 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
 - Other Facets: 1 file(s)
 - Other Variances: 2 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - New Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Production Facilities map: 1 file(s)
 - Water source and transportation map: 1 file(s)
 - Construction Materials source location attachment: 1 file(s)
 - Well Site Layout Diagram: 1 file(s)
 - Recontouring attachment: 1 file(s)
 - Other SUPO Attachment: 2 file(s)
- PWD Report
- PWD Attachments

-- None

- Bond Report

- Bond Attachments

-- None

Form 3160-3
(June 2015)FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. NMNM137444 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. KOALA 9 FED COM 121H 9. API Well No. 30-015-54728
2. Name of Operator COLGATE OPERATING LLC 3a. Address 300 N MARIENFELD STREET SUITE 1000, MIDLAND, TX 3b. Phone No. (include area code) (432) 695-4272		10. Field and Pool, or Exploratory OLD MILLMAN RANCH/BS (ASSOC) 11. Sec., T. R. M. or Blk. and Survey or Area SEC 8/T20S/R28E/NMP
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NENE / 795 FNL / 422 FEL / LAT 32.5930661 / LONG -104.1918628 At proposed prod. zone NENE / 990 FNL / 10 FEL / LAT 32.5928193 / LONG -104.1564892		12. County or Parish EDDY 13. State NM
14. Distance in miles and direction from nearest town or post office* 12 miles		15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 422 feet 16. No of acres in lease 17. Spacing Unit dedicated to this well 320.0
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1528 feet 19. Proposed Depth 7289 feet / 18159 feet 20. BLM/BIA Bond No. in file FED: NMB001382		21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3288 feet 22. Approximate date work will start* 09/30/2022 23. Estimated duration 90 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission) Title Regulatory Manager	Name (Printed/Typed) MIKAH THOMAS / Ph: (432) 695-4224	Date 06/09/2022
Approved by (Signature) (Electronic Submission) Title Assistant Field Manager Lands & Minerals	Name (Printed/Typed) CODY LAYTON / Ph: (575) 234-5959 Office Carlsbad Field Office	Date 11/03/2023

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)



INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

0. SHL: NENE / 795 FNL / 422 FEL / TWSP: 20S / RANGE: 28E / SECTION: 8 / LAT: 32.5930661 / LONG: -104.1918628 (TVD: 0 feet, MD: 0 feet)

PPP: NWNW / 990 FNL / 0 FEL / TWSP: 20S / RANGE: 28E / SECTION: 10 / LAT: 32.5927358 / LONG: -104.1737073 (TVD: 7289 feet, MD: 12856 feet)

PPP: NWNE / 990 FNL / 0 FEL / TWSP: 20S / RANGE: 28E / SECTION: 9 / LAT: 32.592693 / LONG: -104.1823589 (TVD: 7289 feet, MD: 10192 feet)

PPP: NWNW / 990 FNL / 100 FWL / TWSP: 20S / RANGE: 28E / SECTION: 9 / LAT: 32.5926539 / LONG: -104.1906855 (TVD: 7289 feet, MD: 7627 feet)

BHL: NENE / 990 FNL / 10 FEL / TWSP: 20S / RANGE: 28E / SECTION: 10 / LAT: 32.5928193 / LONG: -104.1564892 (TVD: 7289 feet, MD: 18159 feet)

BLM Point of Contact

Name: GAVIN MICKWEE

Title: Land Law Examiner

Phone: (575) 234-5972

Email: gmickwee@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Centennial
LEASE NO.:	NMNM137444
LOCATION:	Section 8, T.20 S, R.28E., NMPM
COUNTY:	Eddy County, New Mexico
WELL NAME & NO.:	Koala 9 Fed Com 121H
SURFACE HOLE FOOTAGE:	795'/N & 422'/E
BOTTOM HOLE FOOTAGE:	990'/N & 10'/E

COA

H₂S	<input checked="" type="radio"/> Yes	<input type="radio"/> No		
Potash / WIPP	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P	<input type="checkbox"/> WIPP
Cave / Karst	<input type="radio"/> Low	<input type="radio"/> Medium	<input checked="" type="radio"/> High	<input type="radio"/> Critical
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both	<input type="radio"/> Diverter
Cementing	<input type="checkbox"/> Primary Squeeze	<input type="checkbox"/> Cont. Squeeze	<input type="checkbox"/> EchoMeter	<input type="checkbox"/> DV Tool
Special Req	<input type="checkbox"/> Break Testing	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit
Variance	<input checked="" type="checkbox"/> Flex Hose	<input type="checkbox"/> Casing Clearance	<input type="checkbox"/> Pilot Hole	<input checked="" type="checkbox"/> Capitan Reef
Variance	<input checked="" type="checkbox"/> Four-String	<input checked="" type="checkbox"/> Offline Cementing	<input type="checkbox"/> Fluid-Filled	<input type="checkbox"/> Open Annulus
<input type="checkbox"/> Batch APD / Sundry				

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. As a result, the Hydrogen Sulfide area must meet all requirements from **43 CFR 3176**, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

- The **13-3/8** inch surface casing shall be set at approximately **340** feet (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface. **Excess calculates to 19%.**
Additional cement maybe required.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
1. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, and Capitan Reef.

 - ❖ In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
 - ❖ In Capitan Reef Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
 - ❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:

(Use this for 3 string wells in the Capitan Reef, if 4 string well ensure FW based mud used across the Capitan interval)

 - Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
 - Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.
2. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into the previous casing, whichever is greater. If cement does not circulate see B.1.a, c-d above. **Excess calculates to 4%. Additional cement maybe required.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the casing shoe shall be **5000 (5M)** psi. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - a. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - b. Manufacturer representative shall install the test plug for the initial BOP test.
 - c. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - d. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in 43 CFR 3171 and 3172.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Offline Cementing

Operator is not approved for any offline cementing procedure.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Email **or** call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, BLM_NM_CFO_DrillingNotifications@BLM.GOV
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,
(575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **43 CFR part 3170 Subpart 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR part 3170 Subpart 3172** and **API STD 53 Sec. 5.3**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in **43 CFR part 3170 Subpart 3172** must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin

after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR part 3170 Subpart 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR part 3170 Subpart 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS 10/4/2023



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

01/29/2024

Operator

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME:

Signed on: 07/17/2023

Title:

Street Address:

City:

State:

Zip:

Phone:

Email address:

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data

01/29/2024

APD ID: 10400085975

Submission Date: 06/09/2022

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Section 1 - General

APD ID: 10400085975

Tie to previous NOS?

Submission Date: 06/09/2022

BLM Office: Carlsbad

User: MIKAH X THOMAS

Title: Regulatory Manager

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM137444

Lease Acres:

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? Y

Permitting Agent? NO

APD Operator: COLGATE OPERATING LLC

Operator letter of

Operator Info

Operator Organization Name: COLGATE OPERATING LLC

Operator Address: 300 N MARIENFELD STREET SUITE 1000

Zip: 79701

Operator PO Box:

Operator City: MIDLAND

State: TX

Operator Phone: (432)695-4272

Operator Internet Address: MTHOMAS@COLGATEENERGY.COM

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: KOALA 9 FED COM

Well Number: 121H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: OLD MILLMAN
RANCH

Pool Name: BS (ASSOC)

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Is the proposed well in a Helium production area? N

Use Existing Well Pad? N

New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:
KOALA 9 FED COM NORTH

Number: 2

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 12 Miles

Distance to nearest well: 1528 FT

Distance to lease line: 422 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: KOALA_9_FED_COM_121H_C102_SIGNED_20230807084853.pdf

Well work start Date: 09/30/2022

Duration: 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 12177

Reference Datum: KELLY BUSHING

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	795	FNL	422	FEL	20S	28E	8	Aliquot NENE	32.5930661	- 104.1918628	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 83584	3288	0	0	N
KOP Leg #1	975	FNL	362	FEL	20S	28E	8	Aliquot NENE	32.5926795	- 104.1923388	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 83584	- 2353	5646	5641	N
PPP Leg #1-1	990	FNL	100	FW L	20S	28E	9	Aliquot NWN W	32.5926539	- 104.1906855	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 137444	- 4001	7627	7289	Y

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-2	990	FNL	0	FEL	20S	28E	9	Aliquot NWNE	32.592693	- 104.1823589	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 13232	- 4001	10192	7289	Y
PPP Leg #1-3	990	FNL	0	FEL	20S	28E	10	Aliquot NWN W	32.5927358	- 104.1737073	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 15003	- 4001	12856	7289	Y
EXIT Leg #1	990	FNL	100	FEL	20S	28E	10	Aliquot NENE	32.5928179	- 104.1567815	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 15003	- 4001	18069	7289	Y
BHL Leg #1	990	FNL	10	FEL	20S	28E	10	Aliquot NENE	32.5928193	- 104.1564892	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 15003	- 4001	18159	7289	Y

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number 30-015-54728	2 Pool Code [48035]	3 Pool Name OLD MILLMAN RANCH;BS (ASSOC)
4 Property Code 334680	5 Property Name KOALA 9 FED COM	6 Well Number 121H
7 OGRID No. 371449	8 Operator Name COLGATE ENERGY LLC	9 Elevation 3288'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	8	20-S	28-E		795'	NORTH	422'	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	10	20-S	28-E		990'	NORTH	10'	EAST	EDDY

12 Dedicated Acres 320.00	13 Joint or Infill	14 Consolidation Code	15 Order No.
------------------------------	--------------------	-----------------------	--------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>16</p> <p>CORNER DATA NEW MEXICO EAST - NAD 83 A. FOUND IRON PIPE W/ BRASS CAP N:580356.62' E:585185.65' B. FOUND 1" IRON PIPE N:580373.68' E:587849.16' C. FOUND 1" IRON PIPE N:580391.30' E:590513.47' D. FOUND 1" IRON PIPE N:580412.62' E:593168.80' E. FOUND 1" IRON PIPE N:580433.88' E:595824.69' F. FOUND IRON PIPE W/ BRASS CAP N:577783.78' E:595789.28' G. FOUND IRON PIPE W/ BRASS CAP N:575134.28' E:595753.43' H. FOUND IRON PIPE W/ BRASS CAP N:575115.45' E:593094.38' I. FOUND 2" IRON PIPE N:575097.10' E:590435.59' J. FOUND 1 1/4" IRON PIPE N:575080.69' E:587767.05' K. FOUND IRON PIPE W/ BRASS CAP N:575063.99' E:585099.23' L. FOUND IRON PIPE W/ BRASS CAP N:577711.68' E:585143.38' M. FOUND 1" IRON PIPE N:577744.14' E:590473.87'</p>	<p>17 OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Ashley Brown</i> 08/07/2023 Signature Date Ashley Brown Printed Name ashley.brown@permianres.com E-mail Address</p>
<p>SURFACE HOLE LOCATION (SHL) NEW MEXICO EAST - NAD 83 X=584750.65 LAT.= 32.59318332° N Y=579559.58 LONG.= 104.19237051° W NEW MEXICO EAST - NAD 27 X=543570.51 LAT.= 32.59306616° N Y=579498.10 LONG.= 104.19186281° W 795' FNL, 422' FEL - SECTION 8</p> <p>FIRST TAKE POINT (FTP) NEW MEXICO EAST - NAD 83 X=585269.85 LAT.= 32.59265245° N Y=579367.14 LONG.= 104.19068550° W NEW MEXICO EAST - NAD 27 X=544089.71 LAT.= 32.59253528° N Y=579305.66 LONG.= 104.19017786° W 990' FNL, 100' FWL - SECTION 9</p> <p>LAST TAKE POINT (LTP) NEW MEXICO EAST - NAD 83 X=595711.44 LAT.= 32.59281774° N Y=579442.94 LONG.= 104.15678150° W NEW MEXICO EAST - NAD 27 X=554531.27 LAT.= 32.59270020° N Y=579381.38 LONG.= 104.15627472° W 990' FNL, 100' FEL - SECTION 10</p> <p>BOTTOM HOLE LOCATION (BHL) NEW MEXICO EAST - NAD 83 X=595801.46 LAT.= 32.59281931° N Y=579443.67 LONG.= 104.15648921° W NEW MEXICO EAST - NAD 27 X=554621.29 LAT.= 32.59270177° N Y=579382.10 LONG.= 104.15598244° W 990' FNL, 10' FEL - SECTION 10</p>	<p>18 SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>MARK J. MURRAY NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR 12177 Date of Survey Signature and Seal of Professional Surveyor 5/5/2022 Certificate Number</p>



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

01/29/2024

APD ID: 10400085975

Submission Date: 06/09/2022

Highlighted data
reflects the most
recent changes

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
12409611	RUSTLER	3288	241	241	ANHYDRITE, LIMESTONE, SALT	NONE	N
12409612	TOP SALT	2906	382	382	ANHYDRITE, SALT	NONE	N
12409613	TANSILL	2520	768	768	ANHYDRITE, DOLOMITE	NONE	N
12409617	YATES	2445	843	843	DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409614	SEVEN RIVERS	2070	1218	1218	ANHYDRITE, DOLOMITE, SANDSTONE, SHALE	NONE	N
12409616	QUEEN	1479	1809	1809	ANHYDRITE, DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409618	GRAYBURG	1270	2018	2018	ANHYDRITE, DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409620	SAN ANDRES	870	2418	2418	ANHYDRITE, DOLOMITE	NATURAL GAS, OIL	N
12409622	CHERRY CANYON	295	2993	2993	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409607	BRUSHY CANYON	70	3218	3218	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409623	BONE SPRING LIME	-1280	4568	4568	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409625	BONE SPRING 1ST	-2830	6118	6118	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409610	BONE SPRING 2ND	-3855	7143	7143	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y
12409608	BONE SPRING 3RD	-4980	8268	8268	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12409609	WOLFCAMP	-5405	8693	8693	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N

Section 2 - Blowout Prevention

Operator Name: COLGATE OPERATING LLC**Well Name:** KOALA 9 FED COM**Well Number:** 121H**Pressure Rating (PSI):** 5M**Rating Depth:** 7389

Equipment: BOPE with working pressure ratings in excess of anticipated maximum surface pressure will be utilized for well control from drill out of surface casing to TMD. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. All BOPE connections shall be flanged, welded or clamped. All choke lines shall be straight unless targeted with running tees or tee blocks are used, and choke lines shall be anchored to prevent whip and reduce vibrations. All valves in the choke line & the choke manifold shall be full opening as to not cause restrictions and to allow for straight fluid paths to minimize potential erosion. All gauges utilized in the well control system shall be of a type designed for drilling fluid service. A top drive inside BOP valve will be utilized at all times. Subs equipped with full opening valves sized to fit the drill pipe and collars will be available on the rig floor in the open position. The key to operate said valve equipped subs will be on the rig floor at all times. The accumulator system will have sufficient capacity to open the HCR and close all three sets of rams plus the annular preventer while retaining at least 300 psi above precharge on the closing manifold (accumulator system shall be capable of doing so without using the closing unit pumps). The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity, and the fluid level will be maintained at the manufacturer's recommended level. Prior to connecting the closing unit to the BOP stack, an accumulator precharge pressure test shall be performed to ensure the precharge pressure is within 100 psi of the desired precharge pressure (only nitrogen gas will be used to precharge). Two independent power sources will be made available at all times to power the closing unit pumps so that the pumps can automatically start when the closing valve manifold pressure has decreased to the preset level. Closing unit pumps will be sized to allow opening of HCR and closing of annular preventer on 5" drill pipe achieving at least 200 psi above precharge pressure with the accumulator system isolated from service in less than two minutes. A valve shall be installed in the closing line as close to the annular preventer as possible to act as a locking device; the valve shall be maintained in the open position and shall be closed only when the power source for the accumulator system is inoperative. Remote controls capable of opening and closing all preventers & the HCR shall be readily accessible to the driller; master controls with the same capability will be operable at the accumulator. The wellhead will be a multibowl speed head allowing for hangoff of intermediate casing & isolation of the 133/8 x 95/8 annulus without breaking the connection between the BOP & wellhead to install an additional casing head. A wear bushing will be installed & inspected frequently to guard against internal wear to wellhead. VBRs (variablebore rams) will be run in upper rambody of BOP stack to provide redundancy to annular preventer while RIH w/ production casing;

Requesting Variance? YES**Variance request:** Flex hose and offline cement variances, see attachments in section 8.

Testing Procedure: The BOP test shall be performed before drilling out of the surface casing shoe and will occur at a minimum: a. when initially installed b. whenever any seal subject to test pressure is broken c. following related repairs d. at 30-day intervals e. checked daily as to mechanical operating conditions. The ram type preventer(s) will be tested using a test plug to 250 psi (low) and 5,000 psi (high) (casinghead WP) with a test plug upon its installation onto the 13 surface casing. If a test plug is not used, the ram type preventer(s) shall be tested to 70% of the minimum internal yield pressure of the casing. The annular type preventer(s) shall be tested to 3500 psi. Pressure will be maintained for at least 10 minutes or until provisions of the test are met, whichever is longer. A Sundry Notice (Form 3160 5), along with a copy of the BOP test report, shall be submitted to the local BLM office within 5 working days following the test. If the bleed line is connected into the buffer tank (header), all BOP equipment including the buffer tank and associated valves will be rated at the required BOP pressure. The BLM office will be provided with a minimum of four (4) hours notice of BOP testing to allow witnessing. The BOP Configuration, choke manifold layout, and accumulator system, will be in compliance with Onshore Order 2 for a 5,000 psi system. A remote accumulator and a multi-bowl system will be used, please see attachment in section 8 for multi-bowl procedure. Pressures, capacities, and specific placement and use of the manual and/or hydraulic controls, accumulator controls, bleed lines, etc., will be identified at the time of the BLM 'witnessed OP test. Any remote controls will be capable of both opening and closing all preventers and shall be readily accessible.

Choke Diagram Attachment:

Choke_Diagram_Attachment_20230717114707.pdf

BOP Diagram Attachment:

BOP_Diagram_Attachment_20230717114711.pdf

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COMWell Number: 121H

Choke_Diagram_Attachment_20230717114707.pdf

BOP_Diagram_Attachment_20230717114711.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	266	0	266	3288	3022	266	J-55	54.5	OTHER - BTC	8.6	3.42	DRY	7.94	DRY	7.45
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2943	0	2943	3274	345	2943	J-55	36	OTHER - BTC	3.13	1.72	DRY	3.1	DRY	2.74
3	PRODUCTION	8.75	5.5	NEW	NON API	N	0	7620	0	7289	3274	-4001	7620	P-110	17	OTHER - GEOCONN	1.97	2.06	DRY	2.44	DRY	2.44
4	PRODUCTION	7.875	5.5	NEW	NON API	N	7620	18159	7289	7289	-4001	-4001	10539	P-110	17	OTHER - GEOCONN	1.97	2.06	DRY	2.44	DRY	2.44

Casing Attachments

Casing ID: 1StringSURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Assumptions_Worksheet_20230717114755.pdf

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Casing Attachments

Casing ID: 2	String	INTERMEDIATE
Inspection Document:		
Spec Document:		
Tapered String Spec:		
Casing Design Assumptions and Worksheet(s):		
Casing_Assumptions_Worksheet_20230717114828.pdf		
Casing ID: 3	String	PRODUCTION
Inspection Document:		
Spec Document:		
Connection_Data_Sheet_P110RY_GeoConn_SC_20230717114900.pdf		
Tapered String Spec:		
Casing Design Assumptions and Worksheet(s):		
Casing_Assumptions_Worksheet_20230717114923.pdf		
Casing ID: 4	String	PRODUCTION
Inspection Document:		
Spec Document:		
Connection_Data_Sheet_P110RY_GeoConn_SC_20230717115005.pdf		
Tapered String Spec:		
Casing Design Assumptions and Worksheet(s):		
Casing_Assumptions_Worksheet_20230717115020.pdf		

Section 4 - Cement

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	0	0	0	0	0		0	0
SURFACE	Tail		0	266	210	1.34	14.8	280	50	Class C	Accelerator
INTERMEDIATE	Lead		0	2350	520	2.08	12.7	1080	50	Class C	Salt, Extender & LCM Additives
INTERMEDIATE	Tail		2350	2943	210	1.34	14.8	280	50	Class C	Accelerator
PRODUCTION	Lead		2443	6720	620	2.41	11.5	1480	40	Class H	POZ, Extender, Fluid Loss, Dispersant & Retarder
PRODUCTION	Tail		6720	18159	1490	1.73	12.5	2570	25	Class H	POZ, Extender, Fluid Loss, Dispersant & Retarder
PRODUCTION	Lead		2443	6720	620	2.41	11.5	1480	40	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder
PRODUCTION	Tail		6720	18159	1490	1.73	12.5	2570	25	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient quantities of mud materials will be on the well site at all times for the purpose of assuring well control and maintaining wellbore integrity. Surface interval will employ fresh water mud. The intermediate hole will utilize a saturated brine fluid to inhibit salt washout. The production hole will employ brine based and oil base fluid to inhibit formation reactivity and of the appropriate density to maintain well control.

Describe the mud monitoring system utilized: Centrifuge separation system. Open tank monitoring with EDR will be used for drilling fluids and return volumes. Open tank monitoring will be used for cement and cuttings return volumes. Mud properties will be monitored at least every 24 hours using industry accepted mud check practices.

Circulating Medium Table

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COMWell Number: 121H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	266	WATER-BASED MUD	8.6	9.5							
266	2943	SALT SATURATED	10	10							
2943	7620	OTHER : Brine	9	10							
7620	1815 9	OIL-BASED MUD	9	10							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will utilize MWD/LWD (Gamma Ray logging) from intermediate hole to TD of the well.

List of open and cased hole logs run in the well:

GAMMA RAY LOG,DIRECTIONAL SURVEY,

Coring operation description for the well:

N/A.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 3800

Anticipated Surface Pressure: 2196

Anticipated Bottom Hole Temperature(F): 131

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Colgate_H2S_Contingency_Plan_20220602142028.pdf

Operator Name: COLGATE OPERATING LLC**Well Name:** KOALA 9 FED COM**Well Number:** 121H**Section 8 - Other Information****Proposed horizontal/directional/multi-lateral plan submission:**[_A05__Koala_9_Fed_Com_121H_APD_Rev00_20220609062524.pdf](#)[_A05__Koala_9_Fed_Com_121H_APD_Rev00_AC_20230717115526.pdf](#)**Other proposed operations facets description:**

Please see attached Drilling Plan, including multi-bowl diagram and procedure, proposed WBD, and casing connection data sheet. We also plan to batch drill this well along with offline cementing, see details under variance request below. Permian Resources Operating, LLC requests to use a flex hose on H&P choke manifold for this well. The Flex Hose specifications are attached below.

Other proposed operations facets attachment:[Koala_9_Fed_Com_121H_drilling_packet_20230717115553.pdf](#)**Other Variance attachment:**[Multi_well_Pad_Batch_Drilling___Offline_Cement_Procedure_20230717115609.pdf](#)[Flex_Hose_Data_Sheet_20230717115606.pdf](#)

The diagram illustrates a wellbore flow system. At the top, the 'OUTLET FROM BOP' leads into a vertical line. This line contains a 'Choke Line Valve' and a 'Remotely Operated HCR'. A red arrow points to these components with the text 'Sequence Optional'. The line then turns horizontal, passing through a '4" NOMINAL CHOKE LINE' and a '5M PRESSURE GAUGE'. It then turns vertical again, passing through another 'Remotely Operated HCR' and 'Choke Line Valve'. The system then splits into two horizontal branches. The left branch leads to a 'Remotely Operated Choke' and a '2" Nominal' line. The right branch leads to a 'MANUAL CHOKE' and a '2" Nominal' line. Both branches then lead to 'Choke Isolation Valve' and '2" Nominal' lines. These lines then lead to a 'BUFFER TANK'. Below the buffer tank is a 'MUD GAS SEPARATOR (MGS)'. The 'MGS AND/OR PIT' is connected to the bottom of the MGS. A 'CLOSED LOOP MUD SYSTEM' is shown at the bottom right, connected to the MGS. A 'MGS Gas Vent Line' is shown at the bottom center. A vertical dimension line on the left indicates a height of '150' to Flare Pit'.



ContiTech

CONTITECH RUBBER Industrial Kft.	No:QC-DB- 210/ 2014
	Page: 9 / 113

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE		CERT. N°: 504	
PURCHASER: ContiTech Oil & Marine Corp.		P.O. N°: 4500408659	
CONTITECH RUBBER order N°: 538236	HOSE TYPE: 3" ID	Choke and Kill Hose	
HOSE SERIAL N°: 67255	NOMINAL / ACTUAL LENGTH: 10,67 m / 10,77 m		
W.P. 68,9 MPa 10000 psi	T.P. 103,4 MPa 15000 psi	Duration: 60 min.	
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>			
↑ 10 mm = 10 Min. → 10 mm = 20 MPa			
COUPLINGS Type	Serial N°	Quality	Heat N°
3" coupling with	9251 9254	AISI 4130	A0579N
4 1/16" 10K API b.w. Flange-end		AISI 4130	035608
Not Designed For Well Testing		API Spec 16 C	
All metal parts are flawless		Temperature rate:"B"	
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.			
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated, inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.			
COUNTRY OF ORIGIN HUNGARY/EU			
Date:	Inspector	Quality Control	
20. March 2014.		ContiTech Rubber Industrial Kft. Quality Control Unit  	


ContiTech Rubber Industrial Kft. : Budapest 110, H-1128 Szigetud H 4/OT P.O.Box 322 Szigetud, Hungary
 Phone: +36 82 584 720 / Fax: +36 82 584 728 / e-mail: info@busd.contitech.hu / info@contitech.hu / www.contitech.hu
 The Court of Company Law of Hungary (Registry Court No: Cg/95-09-00250 / EU VAT No: HU11537208
 BATAIUM-Gesellschaft Zrt., Budapest : 14220105-2083000


No. 501, 504, 505

Page: 1/1




5,000 psi BOP Schematic



Metal One Corp. 	GEOCONN-SC Pipe: SeAH P110RY 95%PBW (SMYS110ksi) *1 Coupling: P110RY (SMYS110ksi) Connection Data Sheet	Page Date Rev.	MAI GC 5.5 17 SeAH P110RY 95%RBW+SC-Cplg6.050 P110RY 3-Feb-21 0
---	--	----------------------	--

GEOCONN-SC



Geometry		Imperial		S.I.	
Pipe Body					
Grade *1	P110RY	-	P110RY	-	
SMYS	110	ksi	110	ksi	
Pipe OD (D)	5.500	in	139.70	mm	
Weight	17.00	lb/ft	25.33	kg/m	
Wall Thickness (t)	0.304	in	7.72	mm	
Pipe ID (d)	4.892	in	124.26	mm	
Drift Dia.	4.767	in	121.08	mm	
Connection					
Coupling SMYS	110	ksi	110	ksi	
SC-Coupling OD (Wsc1)	6.050	in	153.67	mm	
Coupling Length (NL)	8.350	in	212.09	mm	
Make up Loss	4.125	in	104.78	mm	
Pipe Critical Area	4.96	in ²	3,202	mm ²	
Box Critical Area	6.10	in ²	3,937	mm ²	
Thread Taper	1 / 16 (3/4" per ft)				
Number of Threads	5 TPI				

Performance		Imperial		S.I.	
Performance Properties for Pipe Body					
S.M.Y.S. *1	546	ksi	2,428	MPa	
M.I.Y.P. *1	11,550	psi	79.66	MPa	
Collapse Strength *1	7,480	psi	51.59	MPa	
Note S.M.Y.S.= Specified Minimum YIELD Strength of Pipe body M.I.Y.P. = Minimum Internal Yield Pressure of Pipe body *1: SeAH P110RY 95%RBW: SMYS110ksi, MIYP11,550psi					
Performance Properties for Connection					
Min. Connection Joint Strength	100%		of S.M.Y.S.		
Min. Compression Yield	100%		of S.M.Y.S.		
Internal Pressure	100%		of M.I.Y.P.		
External Pressure	100%		of Collapse Strength		
Max. DLS (deg. /100ft)			>90		

Recommended Torque				
Min.	10,800	ft-lb	14,600	N-m
Opti.	12,000	ft-lb	16,200	N-m
Max.	13,200	ft-lb	17,800	N-m
Operational Max.	15,600	ft-lb	21,100	N-m


Note : Operational Max. torque can be applied for high torque application

Legal Notice


The use of this information is at the reader/user's risk and no warranty is implied or expressed by Metal One Corporation or its parents, subsidiaries or affiliates (herein collectively referred to as "Metal One") with respect to the use of information contained herein. The information provided on this Connection Data Sheet is for informational purposes only, and was prepared by reference to engineering information that is specific to the subject products, without regard to safety-related factors, all of which are the sole responsibility of the operators and users of the subject connectors. Metal One assumes no responsibility for any errors with respect to this information.

Statements regarding the suitability of products for certain types of applications are based on Metal One's knowledge of typical requirements that are often placed on Metal One products in standard well configurations. Such statements are not binding statements about the suitability of products for a particular application. It is the customer's responsibility to validate that a particular product with the properties described in the product specification is suitable for use in a particular application.

The products described in this Connection Data Sheet are not recommended for use in deep water offshore applications. For more information, please refer to http://www.mto.co.jp/mto-con/ Images/top/WebsiteTerms_Active_20333287_1.pdf the contents of which are incorporated by reference into this Connection Data Sheet.

Metal One Corp. 	GEOCONN-SC Pipe: SeAH P110RY 95%PBW (SMYS110ksi) *1 Coupling: P110RY (SMYS110ksi) Connection Data Sheet	Page Date Rev.	MAI GC 5.5 17 SeAH P110RY 95%RBW+SC-Cplg6.050 P110RY 3-Feb-21 0
---	--	----------------------	--

GEOCONN-SC



Geometry		Imperial		S.I.	
Pipe Body					
Grade *1	P110RY	-	P110RY	-	
SMYS	110	ksi	110	ksi	
Pipe OD (D)	5.500	in	139.70	mm	
Weight	17.00	lb/ft	25.33	kg/m	
Wall Thickness (t)	0.304	in	7.72	mm	
Pipe ID (d)	4.892	in	124.26	mm	
Drift Dia.	4.767	in	121.08	mm	
Connection					
Coupling SMYS	110	ksi	110	ksi	
SC-Coupling OD (Wsc1)	6.050	in	153.67	mm	
Coupling Length (NL)	8.350	in	212.09	mm	
Make up Loss	4.125	in	104.78	mm	
Pipe Critical Area	4.96	in ²	3,202	mm ²	
Box Critical Area	6.10	in ²	3,937	mm ²	
Thread Taper	1 / 16 (3/4" per ft)				
Number of Threads	5 TPI				

Performance		Imperial		S.I.	
Performance Properties for Pipe Body					
S.M.Y.S. *1	546	ksi	2,428	MPa	
M.I.Y.P. *1	11,550	psi	79.66	MPa	
Collapse Strength *1	7,480	psi	51.59	MPa	
Note S.M.Y.S.= Specified Minimum YIELD Strength of Pipe body M.I.Y.P. = Minimum Internal Yield Pressure of Pipe body *1: SeAH P110RY 95%RBW: SMYS110ksi, MIYP11,550psi					
Performance Properties for Connection					
Min. Connection Joint Strength	100%		of S.M.Y.S.		
Min. Compression Yield	100%		of S.M.Y.S.		
Internal Pressure	100%		of M.I.Y.P.		
External Pressure	100%		of Collapse Strength		
Max. DLS (deg. /100ft)	>90				

Recommended Torque				
Min.	10,800	ft-lb	14,600	N-m
Opti.	12,000	ft-lb	16,200	N-m
Max.	13,200	ft-lb	17,800	N-m
Operational Max.	15,600	ft-lb	21,100	N-m

Note : Operational Max. torque can be applied for high torque application

Legal Notice

The use of this information is at the reader/user's risk and no warranty is implied or expressed by Metal One Corporation or its parents, subsidiaries or affiliates (herein collectively referred to as "Metal One") with respect to the use of information contained herein. The information provided on this Connection Data Sheet is for informational purposes only, and was prepared by reference to engineering information that is specific to the subject products, without regard to safety-related factors, all of which are the sole responsibility of the operators and users of the subject connectors. Metal One assumes no responsibility for any errors with respect to this information.

Statements regarding the suitability of products for certain types of applications are based on Metal One's knowledge of typical requirements that are often placed on Metal One products in standard well configurations. Such statements are not binding statements about the suitability of products for a particular application. It is the customer's responsibility to validate that a particular product with the properties described in the product specification is suitable for use in a particular application.

The products described in this Connection Data Sheet are not recommended for use in deep water offshore applications. For more information, please refer to http://www.mto.co.jp/mto-con/ Images/top/WebsiteTerms_Active_20333287_1.pdf the contents of which are incorporated by reference into this Connection Data Sheet.

Permian Resources Casing Design Criteria

A sundry will be requested if any lesser grade or different size casing is substituted. All casing will be centralized as specified in On Shore Order II. Casing will be tested as specified in On Shore Order II.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Permian Resources Casing Design Criteria

A sundry will be requested if any lesser grade or different size casing is substituted. All casing will be centralized as specified in On Shore Order II. Casing will be tested as specified in On Shore Order II.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Permian Resources Casing Design Criteria

A sundry will be requested if any lesser grade or different size casing is substituted. All casing will be centralized as specified in On Shore Order II. Casing will be tested as specified in On Shore Order II.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Permian Resources Casing Design Criteria

A sundry will be requested if any lesser grade or different size casing is substituted. All casing will be centralized as specified in On Shore Order II. Casing will be tested as specified in On Shore Order II.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.



H₂S Contingency Plan



Table of Contents

I. EMERGENCY ASSISTANCE TELEPHONE LIST3

II. H₂S CONTINGENCY PLAN SECTION5

III. OPERATING PROCEDURES7

IV. OPERATING CONDITIONS 10

V. EMERGENCY PROCEDURES 11

VI. POST EMERGENCY ACTIONS..... 14

VII. IGNITION PROCEDURES..... 15

VIII. TRAINING PROGRAM..... 16

IX. EMERGENCY EQUIPMENT 16

X. CHECKLISTS..... 20

XI. BRIEFING PROCEDURES..... 22

XII. EVACUATION PLAN..... 23

XIII. APPENDICES AND GENERAL INFORMATION 24

I. EMERGENCY ASSISTANCE TELEPHONE LIST**PUBLIC SAFETY****911 or****Sheriff's Department:**

Eddy County Sherriff's Office (575) 887-7551

Fire Department:

Carlsbad Fire Department (575) 885-3125

Artesia Fire Department (575) 746-5051

Ambulance:

Elite Medical Transport (Carlsbad) (915) 542-1144

Trans Aero MedEvac (Artesia) (970) 657-7449

Hospitals:

Carlsbad Medical Center (575) 887-4100

Artesia General Hospital (575) 748-3333

New Mexico Dept. of Transportation:

Highway & Transportation Department (505) 795- 1401

New Mexico Railroad Commission:

Main Line (505) 476-3441

OSHA 24 Hr. Reporting

(800) 321-6742

(8 hrs. after death or 24 hrs. after in-patient, amputation, loss of an eye)

Office Contacts**911 or****Colgate Energy LLC.****(432) 695-4222****Vice President of Operations:**

Casey McCain

(432) 664-6140

Drilling Engineering Supervisor

Rafael Madrid

(432) 556-6387

Drilling Engineering Technical Adviser

Steven Segrest

(405) 550-0277

Operations Superintendent

Rick Lawson

(432) 530- 3188

Drilling Superintendent

Daniel Cameron

(405) 933-0435

Onsite Supervision (H&P 481 Rig Managers)

Juan Gutierrez

(970)394-4768

Jonathan Jackson

(970)394-4768

Onsite Supervision (H&P 481 Company Men)

Pierre Dupuis

(432)438-0114

Eric Rutherford

(432)438-0114

Rolando Torres

(432)438-0114

Trevor Hein

(432)438-0114

Emergency Accommodations

Safety Solutions Office

(432) 563-0400

Safety Solutions Dispatch

(432) 556-2002

Craig Strasner

(432) 894-0341 (Cell)

II. H₂S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H₂S).

Objective:

Prevent any and all accidents and prevent the uncontrolled release of H₂S into the atmosphere.
Provide proper evacuation procedures to cope with emergencies.
Provide immediate and adequate medical attention should an injury occur.

Purpose, Distribution and Updating of Contingency Plan:

The Purpose of this contingency plan is to protect the general public from the harmful effects of H₂S accidentally escaping from the subject producing well. This plan is designed to accomplish its purpose by assuring the preparedness necessary to:

1. Minimize the possibility of releasing H₂S into the atmosphere during related operations.
2. Provide for the logical, efficient, and safe emergency actions required to protect the general public in the event of an accidental release of a potentially hazardous quantity of H₂S.

Supplemental information is included with this plan and is intended as reference material for anyone needing a more detailed understanding of the many factors pertinent to H₂S drilling operations safety. The release of a potentially hazardous quantity of H₂S is highly unlikely. If such a release should occur however, obviously the exact time, rate, duration, and other pertinent facts will be known in advance thus, this contingency plan must necessarily be somewhat general. The plan does review in detail, as is reasonably possible, the type of accidental release that could possibly endanger the general public, the probable extent of such danger, and the emergency actions generally appropriate. In the event of such an accidental release, the specific actions to be taken will have to be determined at the time of release by the responsible personnel at the drilling location. Complete familiarity with this plan will help such personnel make the proper decisions rapidly. Familiarity with this plan is so required all operators, operator representatives, and drilling contractor supervisory personnel who could possibly be on duty at the drilling location at the time of an H₂S emergency.

IT IS THE RESPONSIBILITY OF THE OPERATOR TO ASSURE SUCH FAMILIARITY BEFORE DRILLING WITHIN 1000' OR THREE DAYS PRIOR TO PENETRATION OF THE SHALLOWEST FORMATION KNOWN OR SUSPECTED TO CONTAIN H₂S IN POTENTIALLY HAZARDOUS QUANTITIES, AND ALSO TO ASSURE THE TIMELY ACCOMPLISHMENT OF ALL THE OTHER ACTION SPECIFIED HERE IN.

As this contingency plan was prepared considerably in advance of the anticipated H₂S operation, the plan must be kept current if it is to effectively serve its purpose. The operators will be responsible for seeing that all copies are updated. Updating the plan is required when any changes to the personnel Call List (Section) including telephone numbers occur or when any pertinent data or plans for the well are altered. The plan must also be updated when any changes in the general public likely to be within the exposure area in the event of an

accidental release from the well bore of a potentially hazardous quantity of H₂S. Two copies of this plan shall be retained at the office of Colgate Energy. Two copies shall be retained at the drilling location.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 1000' before drilling into the first sour zone.

Emergency Response Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 1000' before drilling into the first sour zone.

Emergency call list: Included are the telephone numbers of all persons that would need to be contacted, should an H₂S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

Check Lists: Status check lists and procedural check lists have been included to ensure adherence to the plan.

General Information: A general information section has been included to supply support information.

III. OPERATING PROCEDURES

A. Blowout Preventer Drills

Due to the special piping and Mani folding necessary to handle poisonous gas, particular care will be taken to ensure that all rig personnel are completely familiar with their jobs during the drills. The Drilling Consultant and Tool Pusher (Rig Superintendent) are thoroughly familiar with the additional controls and piping necessary.

B. H₂S Alarm Drills

The Company Man and/ or designee will conduct frequent H₂S alarm drills for each crew by injecting a trace of H₂S where the detector will give an alarm. Under these conditions all personnel on location will put on air equipment and remain masked until all clear is announced.

C. Surface Annular Preventer/ Diverter System Testing

After installation of the surface annular preventer, Hydraulic Control Valve and diverter system, both are to be function tested. They also should be function tested frequently while drilling surface hole.

D. Blowout Preventer

After installation of the Blowout Preventer Stack, the stack will be pressure tested. The Choke manifold is also to be pressure tested at this time. This procedure will be repeated as required by the NMOCD, the BLM, or if any of the stack is nipped down. Also, at this time, the Blind and Pipe Rams are checked for correct operation.

E. Well Control Practice Drills and Safety Meeting for Crew Members

Pit drills are for the purpose of acquainting each member of the drilling crew with his duties in the event of an emergency. Drills will be held with each crew as frequently as required to thoroughly familiarize each man with his duties. Drills are to be held at least weekly from that time forward.

1. BOP Drill while on Bottom Drilling:

A. Signal will be three or more long blast given by driller on the horn.

B. Procedure will be as follows:

1. Tool Pusher: Supervises entire operation.

2. Driller

a. Gives signal.

b. Picks up Kelly.

c. Stops pumps.

d. Observes flow.

e. Signal to close (pipe rams if necessary).

f. Check that Choke Manifold is closed.

g. Record drill pipe pressure, casing pressure and determine mud volume gain.

3. Motorman

a. Go to closing unit and standby for signal to close BOP.

b. Close BOP in signal.

c. Check on BOP closing.

d. Go to floor to assist driller. (NOTE: During test drills the BOP

need not be completely closed at the discretion of the supervisor. Supervisor should make it very clear that it is a test drill only!)

4. Derrickman
 - a. Check pumps.
 - b. Go to floor for directions from the driller.
 5. Floorman
 - a. Go to manifold.
 - b. Observe and record pressure.
 - c. Check manifold and BOP for leaks.
 - d. Check with driller for additional instructions.
2. BOP Drill While Making Trip:
- A. During trip driller will fill hole every five (5) stands and check the pits to be sure hole is taking mud.
 - B. Drill Procedure is as follows:
 1. Driller
 - a. Order Safety valve installed.
 - b. Alert those not on the floor.
 - c. Go to stations as described in above drill.
3. Safety Meetings
- A. Every person involved in the operating will be informed of the characteristics of H₂S, its danger and safety procedures to be used when it is encountered, and recommended first-aid procedure for regular rig personnel. This will be done through a series of talks made before spud.
 - B. The Safety Advisor or Drilling Supervisor will conduct these training sessions and will repeat them as deemed necessary by him or as instructed by Colgate Energy. Talks may include the following subjects:
 1. Dangers of Hydrogen Sulfide (H₂S).
 2. Use and limitations of air equipment.
 3. Use of resuscitator.
 4. Organize Buddy System.
 5. First Aid procedures.
 6. Use of H₂S detection devices.
 7. Designate responsible people.
 8. Explain rig layout and policy to visitors.
 - a. Designate smoking and safety or Muster area.
 - b. Emphasize the importance of wind directions.
 9. Describe and explain operation of BOP stack, manifold, separator, and pit piping. Include maximum allowable pressure for casing procedure.
 10. Explain functions of Safety Supervisor.
 11. Explain organize H₂S Drills.
 12. Explain the overall emergency plan with emphasis given to the evacuation phase of the plans.

- Note: The above talks will be attended by every person involved in the operation. When drilling has reached a depth where H₂S is anticipated, temporary service personnel and visitors will be directed to the Drilling Consultant, who will designate the air equipment to be used by them in case of emergency, acquaint them with the dangers involved and be sure of their safety while they are in the area. He will point out the Briefing Areas, Windsocks, and Smoking Areas. He may refuse entrance to anyone, who in his opinion should not be admitted because of lack of safety equipment, special operations in progress or for other reasons involving personnel safety.

F. Outside Service Personnel

All service people such as cementing crews, logging crews, specialist, mechanics, and welders will furnish their own safety equipment. The Company Man/ or designee will be sure that the number of people on location does not exceed the number of masks on location, and they have been briefed regarding safety procedures. He will also be sure each of these people know about smoking and "Briefing Areas" and know what to do in case of an emergency alert or drill. Visitors will be restricted, except with special permission from the Drilling Consultant, when H₂S might be encountered. They will be briefed as to what to do in case of an alert or drill.

G. Onsite/ off shift workers

All workers that are staying on site must be identified as to where they are staying while off tour. If a drill/ or emergency takes place related to an H₂S release, each crew must have a designated person(s) that will wake them up and ensure that they are cleared to the appropriate muster area immediately.

H. Simultaneous Operations (SIMOPS)

If work is going on adjacent to the location is the responsibility of the Drilling Consultant or designee to communicate any applicable risks that may affect personnel working on that adjacent location. In the case of an H₂S drill or event, there should be a designated crew member that is responsible for contacting personnel on adjacent locations. This could include just communication on potential events or in case of an event, notification to evacuate location. Drilling Consultant or designee are the Point of Contact and oversee all activities at such point of an H₂S event occurrence.

I. Area Residences/ Occupied Locations/ Public Roads

Any occupied residences/ businesses that are within a reasonable perimeter of the location (attached map will identify a 3000' radius around location) should be identified as part of this contingency and a reasonable effort will be made to gain contact information for them. As part of the briefing of the contingency plan, the team reviewing should identify where these potential receptors are and plan on who will contact them in case of a release that may impact that area.

J. Drilling Fluids

Drilling Fluid Monitoring – On Any Hazardous H₂S gas well, the earlier the warning of danger the better chance to control operations. Mud Company will be in daily contact with Colgate Energy Consultant. The Mud Engineer will take samples of the mud, analyze these samples, and make necessary recommendations to prevent H₂S gas from the formation, the pH will be increased as necessary for corrosion control.

pH Control – For normal drilling, pH of 10.5 – 11.5. Would be enough for corrosion protection. If there is an influx of H₂S gas from the formation, the pH will be increased as necessary for corrosion control.

H₂S Scavengers – If necessary H₂S scavengers will be added to the drilling mud.

IV. OPERATING CONDITIONS

A. Posting Well Condition Flags

Post the green, yellow or red well condition flag, as appropriate, on the well condition sign at the location entrance, and take necessary precautions as indicated below:

1. **Green Flag:** Potential Danger- When Drilling in known H₂S zones or when H₂S has been detected in the drilling fluid atmosphere. Protective breathing equipment shall be inspected, and all personnel on duty shall be alerted to be ready to use this equipment.
2. **Yellow Flag:** Potential Danger- When the threshold limit value of H₂S (10 PPM) or of SO₂ (5 PPM) is reached. If the concentration of H₂S or SO₂ reaches 10 PPM, protective breathing equipment shall be worn by all working personnel, and non-working personnel shall go to the upwind Safe Briefing Area.
3. **Red Flag:** Extreme danger*- When the ambient concentration of H₂S or SO₂ is reasonably believed or determined to have exceeded the potentially hazardous level. All non-essential personnel shall leave the drilling location taking the route most likely to exposure to escaping gas.

B. Requiring Air Masks Conditions

1. Whenever air masks are used, the person must be clean shaven as shown in the APC Guidelines
2. When breaking out any line where H₂S can reasonably be expected.
3. When sampling air in areas to determine if toxic concentrations of H₂S exist.
4. When working in areas where 10 PPM or more of H₂S has been detected.
5. At any time, there is doubt as to the H₂S level in the area to be entered.

C. Kick Procedure

1. It is very important that the driller be continuously alert, especially when approaching a gas formation.
2. Should gas come into the well bore, it is very important to be aware of a kick at the earliest time.
3. If a kick is identified, follow appropriate diverter or shut in procedures according to the situation that is presented utilizing appropriate kick procedures.

V. EMERGENCY PROCEDURES

- I. In the event of any evidence of H₂S level above 10ppm, take the following steps immediately:
 - a. Secure breathing apparatus.
 - b. Order non-essential personnel out of the danger zone.
 - c. Take steps to determine if the H₂S level can be corrected or suppressed, and if so, proceed with normal operations.
- II. If uncontrollable conditions occur, proceed with the following:
 - a. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel.
 - b. Remove all personnel to the Safe Briefing Area.
 - c. Notify public safety personnel for help with maintaining roadblocks, thus limiting traffic and implementing evacuation.
 - d. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.
- III. Responsibility
 - a. The Company Approved Supervisor shall be responsible for the total implementation of the plan.
 - b. The Company Approved Supervisor shall be in complete command during any emergency.
 - c. The Company Approved Supervisor shall designate a backup Supervisor if he/she is not available.
- IV. Actions to be taken
 - a. Assign specific tasks to drilling location personnel
 - b. Evacuate the general public from the exposure area
 - c. Cordon off the exposure area to prevent entry by unauthorized persons
 - d. Request assistance if and as needed and initiate emergency notifications
 - e. Stop the dispersion of H₂S
 - f. Complete emergency notifications as required
 - g. Return the situation to normal

EMERGENCY PROCEDURE IMPLEMENTATION**I. Drilling or Tripping****a. All Personnel**

- i. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
- ii. Check status of other personnel (buddy system).
- iii. Secure breathing apparatus.
- iv. Wait for orders from supervisor.

b. Drilling Consultant

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

c. Tool Pusher

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Drilling Consultant or the Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

d. Driller

- i. Check the status of other personnel (in a rescue attempt, always use the buddy system).
- ii. Assign the least essential person to notify the Drilling Consultant and Tool Pusher, in the event of their absence.
- iii. Assume the responsibility of the Drilling Consultant and the Tool Pusher until they arrive, in the event of their absence.

e. Derrick Man and Floor Hands

- i. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

f. Mud Engineer

- i. Report to the upwind Safe Briefing Area.
- ii. When instructed, begin check of mud for pH level and H₂S level.

g. Safety Personnel

- i. Don Breathing Apparatus.
- ii. Check status of personnel.
- iii. Wait for instructions from Drilling Consultant or Tool Pusher.

II. Taking a Kick

- a.* All Personnel report to the upwind Safe Briefing Area.
- b.* Follow standard BOP/ diverter procedures.

III. Open Hole Logging

- a.* All unnecessary personnel should leave the rig floor.
- b.* Drilling Consultant and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

- a.* Follow "Drilling or Tripping" procedures.
- b.* Assure that all personnel have access to protective equipment.

VI. POST EMERGENCY ACTIONS

In the event this plan is activated, the following post emergency actions shall be taken in an effort to reduce the possibility of a reoccurrence of the type of problem that required its activation, and/or assure that any future activation of a similar plan will be as effective as possible.

- A. Review the factors that caused or permitted the emergency occur, and if the need is indicated, modify operating, maintenance and/or surveillance procedures.
- B. If the need is indicated, retrain employees in blowout prevention, H₂S emergency procedures and etc.
- C. Clean up, recharge, restock, repair, and/ or replace H₂S emergency equipment as necessary, and return it to its proper place. (For whatever rental equipment is used, this will be the responsibility of Rental Company).
- D. See that future H₂S drilling contingency plans are modified accordingly, if the need is indicated.

VII. IGNITION PROCEDURES

Responsibilities:

The decision to ignite the well is the responsibility of the DRILLING CONSULTANT in concurrence with the STATE POLICE. In the event the Drilling Consultant is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Consultant is responsible for igniting the well.
2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.
3. Ignite from upwind and do not approach any closer than is warranted.
4. Select the ignition site best suited for protection and which offers an easy escape route.
5. Before igniting, check for the presence of combustible gases.
6. After igniting, continue emergency actions and procedures as before.
7. All unassigned personnel will limit their actions to those directed by the Drilling Consultant.

Note: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide, which is also highly toxic. Also, both are heavier than air. Do not assume the area is safe even after the well is ignited.

VIII. TRAINING PROGRAM

When working in an area where Hydrogen Sulfide (H₂S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel, at the well site, have had adequate training in the following:

1. Hazards and characteristics of Hydrogen Sulfide (H₂S).
2. Physicals effects of Hydrogen Sulfide on the human body.
3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
4. H₂S detection, Emergency alarm and sensor location.
5. Don and Doff of SCBA and be clean shaven.
6. Emergency rescue.
7. Resuscitators.
8. First aid and artificial resuscitation.
9. The effects of Hydrogen Sulfide on metals.
10. Location safety.

Service company personnel and visiting personnel must be notified if the zone contains H₂S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

IX. EMERGENCY EQUIPMENT

Lease Entrance Sign:

Should be located at the lease entrance with the following information:

CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the safe briefing areas and should include the following:
- Two SCBA's at each briefing area.
- Enough airline units to operate safely, anytime the H₂S concentration reaches the IDLH level (100 ppm).

- Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Windssocks or Wind Streamers:

- A minimum of two 10" windssocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should always be placed at various locations on the well site to ensure wind consciousness. (Corners of location).

Hydrogen Sulfide Detector and Alarms:

- 1 - Four channel H₂S monitor with alarms.
- Three (3) sensors located as follows: #1 – Rig Floor, #2 – Shale Shaker, #3 – Cellar.
- Gastec or Draeger pump with tubes.
- Sensor test gas.

Well Condition Sign and Flags:

The Well Condition Sign w/flags should be placed a minimum of 150' before you enter the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions
YELLOW – Potential Danger
RED – Danger, H₂S Gas Present

Auxiliary Rescue Equipment:

- Stretcher
- 2 – 100' Rescue lines.
- First Aid kit properly stocked.

Mud Inspection Equipment:

Garret Gas Train or Hach Tester for inspection of Hydrogen Sulfide in the drilling mud system.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Blowout Preventer:

- The well shall have hydraulic BOP equipment for the anticipated bottom hole pressure (BHP).
- The BOP should be tested upon installation.
- BOP, Choke Line and Kill Line will be tested as specified by Operator.

Confined Space Monitor:

There should be a portable multi-gas monitor with at least 3 sensors (O₂, LEL H₂S), preferably 4 (O₂, LEL, H₂S, CO). This instrument should be used to test the atmosphere of any confined space before entering. It should also be used for atmospheric testing for LEL gas before beginning any type of Hot Work. Proper calibration documentation will need to be provided.

Communication Equipment:

- Proper communication equipment such as cell phones or 2-way radios should be available at the rig.
- Radio communication shall be available for communication between the company man's trailer, rig floor and the tool pusher's trailer.
- Communication equipment shall be available on the vehicles.

Special Control Equipment:

- Hydraulic BOP equipment with remote control on the ground.
- Rotating head at the surface casing point.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:***Parking and Visitor area:***

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- Designated smoking area.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds, or they are at a 180-degree angle if wind directions tend to shift in the area.
- Personal protective equipment should be stored at both briefing areas and if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

Note:

- Additional equipment will be available at the H₂S Provider Safety office.
- Additional personal H₂S monitors are available for all employees on location.
- Automatic Flare Igniters are recommended for installation on the rig.

X. CHECKLISTS**Rig-up & Equipment Status Check List**

Note: Initial & Date each item as they are implemented. Multiple wells require additional Columns to be Dated/ Initialed

	Date & Initial 1 st Well	Date & Initial 2 nd Well	Date & Initial 3 rd Well	Date & Initial 4 th Well
Sign at location entrance.				
Two (2) windsocks (in required locations).				
Wind Streamers (if required).				
SCBA's on location (Minimum of 2 @ each Muster Area)				
Air packs (working packs and escape packs), inspected and ready for use.				
Spare bottles for each air pack (if required).				
Cascade system and hose line hook up.				
Choke manifold hooked-up and tested. (before drilling out surface casing.)				
Remote Hydraulic BOP control tested (before drilling out surface casing).				
BOP tested (before drilling out surface casing).				
Safe Briefing Areas set-up				
Well Condition sign and flags on location and ready.				
Hydrogen Sulfide detection/ alarm system hooked-up & tested.				
Stretcher on location				
2 – 100' Lifelines on location.				
1 – 20# Fire Extinguisher in safety trailer.				
Confined Space monitor on location and tested.				
All rig crews and supervisor trained (as required).				
All rig crews and supervision medically qualified and fit tested on proper respirators				
Access restricted for unauthorized personnel.				
Pre-spud meeting held reviewing Contingencies				
Drills on H ₂ S and well control procedures.				
All outside service contractors advised of potential H ₂ S on the well.				
25mm Flare Gun on location w/flares.				

Procedural Check List

Perform the following on each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that they have not been tampered with.
3. Check pressure on the supply air bottles to make sure they are capable of recharging.
4. Make sure all the Hydrogen Sulfide detection systems are operative.
5. Ensure that all BOP/ Surface Annular/ Diverter systems are functioning and operational.

Perform the following each week:

1. Check each piece of breathing equipment to make sure that they are fully charged and operational. This requires that the air cylinder be opened, and the mask assembly be put on and tested to make sure that the regulators and masks are properly working. Negative and Positive pressure should be conducted on all masks.
2. BOP skills.
3. Check supply pressure on BOP accumulator stand-by source.
4. Check all breathing air mask assemblies to see that straps are loosened and turned back, ready for use.
5. Check pressure on cascade air cylinders to make sure they are fully charged and ready to use for refill purposes if necessary.
6. Check all cascade system regulators to make sure they work properly.
7. Perform breathing drills with on-site personnel.
8. Check the following supplies for availability (may be with H₂S Techs On-call):
 - Stretcher
 - Safety Belts and Ropes
 - Spare air Bottles
 - Spare Oxygen Bottles (if resuscitator required)
 - Gas Detector Pump and Tubes
 - Emergency telephone lists
 - Test the Confined Space Monitor to verify the batteries are good.

XI. BRIEFING PROCEDURES

The following scheduled briefings will be held to ensure the effective drilling and operation of this project:

Pre-Spud Meeting

Date: Prior to spudding the well.

Attendance: Drilling Supervisor
 Drilling Engineer
 Drilling Consultant
 Rig Tool Pushers
 Rig Drillers
 Mud Engineer
 All Safety Personnel
 Key Service Company Personnel

Purpose: Review and discuss the well program, step-by-step, to insure complete understanding of assignments and responsibilities.

XII. EVACUATION PLAN

General Plan

The direct lines of action prepared by Colgate Energy to protect the public from hazardous gas situations are as follows:

1. When the company approved supervisor (Drilling Consultant, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the area map.
2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists, and evacuation needs to be implemented.
3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.
4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining roadblocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, "Company" personnel will determine when the area is safe for re-entry.
6. If a major release is secured, all exposed housing, vehicles, rig buildings, and low-lying areas and other structures downwind must be tested and clear with SCBAs donned to ensure that all residual H₂S is cleared. Fans, or opening of doors is recommended to ensure that areas are cleared out as part of this process.

XIII. APPENDICES AND GENERAL INFORMATION

Radius of Exposure Affected Notification List

(within a 65' radius of exposure @100ppm)

The geologic zones that will be encountered during drilling are known to contain hazardous quantities of H₂S. The accompanying map illustrates the affected areas of the community. The residents within this radius will be notified via a hand delivered written notice describing the activities, potential hazards, conditions of evacuation, evacuation drill siren alarms and other precautionary measures.

Evacuee Description: Residents:

Notification Process:

A continuous siren audible to all residence will be activated, signaling evacuation of previously notified and informed residents.

Evacuation Plan:

All evacuees will migrate lateral to the wind direction.

The Operating Company will identify all home bound or highly susceptible individuals and make special evacuation preparations, interfacing with the local and emergency medical service as necessary.

Toxic Effects of H₂S Poisoning

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity – 1.192) and is colorless and transparent. Hydrogen Sulfide is almost as toxic as Hydrogen Cyanide and is 5-6 times more toxic than Carbon Monoxide. Occupational exposure limits for Hydrogen Sulfide and other gases are compared below in Table 1. Toxicity table for H₂S and physical effects are shown in Table 2.

Table 1
Permissible Exposure Limits of Various Gases

<u>Common Name</u>	<u>Symbol</u>	<u>Sp. Gravity</u>	<u>TLV</u>	<u>STEL</u>	<u>IDLH</u>
Hydrogen Cyanide	HCN	.94	4.7 ppm	4.7 ppm	50 ppm
Hydrogen Sulfide	H ₂ S	1.192	10 ppm	15 ppm	100 ppm
Sulfide Dioxide	SO ₂	2.21	2 ppm	5 ppm	100 ppm
Chlorine	CL	2.45	.5 ppm	1 ppm	10 ppm
Carbon Monoxide	CO	.97	25 ppm	200 ppm	1200 ppm
Carbon Dioxide	CO ₂	1.52	5000 ppm	30,000 ppm	40,000 ppm
Methane	CH ₄	.55	5% LEL	15% UEL	

Definitions

- A. TLV – Threshold Limit Value is the concentration employees may be exposed based on a TWA (time weighted average) for eight (8) hours in one day for 40 hours in one (1) week. This is set by ACGIH (American Conference of Governmental Hygienists) and regulated by OSHA.
- B. STEL – Short Term Exposure Limit is the 15-minute average concentration an employee may be exposed to providing that the highest exposure never exceeds the OEL (Occupational Exposure Limit). The OEL for H₂S is 20 PPM.
- C. IDLH – Immediately Dangerous to Life and Health is the concentration that has been determined by the ACGIH to cause serious health problems or death if exposed to this level. The IDLH for H₂S is 100 PPM.
- D. TWA – Time Weighted Average is the average concentration of any chemical or gas for an eight (8) hour period. This is the concentration that any employee may be exposed based on a TWA.

Toxicity Table of H₂S

<u>Percent %</u>	<u>PPM</u>	<u>Physical Effects</u>
.0001	1	Can smell less than 1 ppm.
.001	10	TLV for 8 hours of exposure.
.0015	15	STEL for 15 minutes of exposure.
.01	100	Immediately Dangerous to Life & Health. Kills sense of smell in 3 to 5 minutes.
.02	200	Kills sense of smell quickly, may burn eyes and throat.
.05	500	Dizziness, cessation of breathing begins in a few minutes .
.07	700	Unconscious quickly, death will result if not rescued promptly.
.10	1000	Death will result unless rescued promptly. Artificial resuscitation may be necessary.

PHYSICAL PROPERTIES OF H₂S

The properties of all gases are usually described in the context of seven major categories:

- COLOR
- ODOR
- VAPOR DENSITY
- EXPLOSIVE LIMITS
- FLAMMABILITY
- SOLUBILITY (IN WATER)
- BOILING POINT

Hydrogen Sulfide is no exception. Information from these categories should be considered in order to provide a complete picture of the properties of the gas.

COLOR – TRANSPARENT

Hydrogen Sulfide is colorless, so it is invisible. This fact simply means that you can't rely on your eyes to detect its presence. In fact, that makes this gas extremely dangerous to be around.

ODOR – ROTTEN EGGS

Hydrogen Sulfide has a distinctive offensive smell, like "rotten eggs". For this reason, it earned its common name "sour gas". However, H₂S, even in low concentrations, is so toxic that it attacks and quickly impairs a victim's sense of smell, so it could be fatal to rely on your nose as a detection device.

VAPOR DENSITY – SPECIFIC GRAVITY OF 1.192

Hydrogen Sulfide is heavier than air, so it tends to settle in low-lying areas like pits, cellars or tanks. If you find yourself in a location where H₂S is known to exist, protect yourself. Whenever possible, work in an area upwind and keep to higher ground.

EXPLOSIVE LIMITS – 4.0% TO 44%

Mixed with the right proportion of air or oxygen, H₂S will ignite and burn or explode, producing another alarming element of danger besides poisoning.

FLAMMABILITY

Hydrogen Sulfide will burn readily with a distinctive clear blue flame, producing Sulfur Dioxide (SO₂), another hazardous gas that irritates the eyes and lungs.

SOLUBILITY – 4 TO 1 RATIO WITH WATER

Hydrogen Sulfide can be dissolved in liquids, which means that it can be present in any container or vessel used to carry or hold well fluids including oil, water, emulsion and sludge. The solubility of H₂S is dependent on temperature and pressure, but if conditions are right, simply agitating a fluid containing H₂S may release the gas into the air.

BOILING POINT – (-77° Fahrenheit)

Liquefied Hydrogen Sulfide boils at a very low temperature, so it is usually found as a gas.

RESPIRATOR USE

The Occupational Safety and Health Administration (OSHA) regulate the use of respiratory protection to protect the health of employees. OSHA's requirements are written in the Code of Federal Regulations, Title 29, Part 1910, Section 134, Respiratory Protection. This regulation requires that all employees who might be required to wear respirators, shall complete an OSHA mandated medical evaluation questionnaire. The employee then should be fit tested prior to wearing any respirator while being exposed to hazardous gases.

Written procedures shall be prepared covering safe use of respirators in dangerous atmospheric situations, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available respirators.

Respirators shall be inspected prior to and after each use to make sure that the respirator has been properly cleaned, disinfected and that the respirator works properly. The unit should be fully charged prior to being used.

Anyone who may use respirators shall be properly trained in how to properly seal the face piece. They shall wear respirators in normal air and then in a test atmosphere. (Note: Such items as facial hair (beard or sideburns) and eyeglass temple pieces will not allow a proper seal.) Anyone who may be expected to wear respirators should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses. Contact lenses should not be allowed.

Respirators shall be worn during the following conditions:

- A. Any employee who works near the top or on the top of any tank unless tests reveal less than 20 ppm of H₂S.
- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas where H₂S may be present.
- D. When working in areas where the concentration of H₂S exceeds the Threshold Limit Value for H₂S (10 ppm).
- E. At any time where there is a doubt as to the H₂S level in the area to be entered.

EMERGENCY RESCUE PROCEDURES


DO NOT PANIC!!!

Remain Calm – Think

1. Before attempting any rescue, you must first get out of the hazardous area yourself. Go to a safe briefing area.
2. Sound alarm and activate the 911 system.
3. Put on breathing apparatus. At least two persons should do this, when available use the buddy system.
4. Rescue the victim and return them to a safe briefing area.
5. Perform an initial assessment and begin proper First Aid/CPR procedures.
6. Keep victim lying down with a blanket or coat, etc., under the shoulders to keep airway open. Conserve body heat and do not leave unattended.
7. If the eyes are affected by H₂S, wash them thoroughly with potable water. For slight irritation, cold compresses are helpful.
8. In case a person has only minor exposure and does not lose consciousness totally, it's best if he doesn't return to work until the following day.
9. Any personnel overcome by H₂S should always be examined by medical personnel. They should always be transported to a hospital or doctor.

Facial Hair – Clean Shaven Examples

Purpose: To define clean shaven expectations in the field for: 1) Respirator Use, if applicable and 2) First Aid Administration, if situation occurs related to H₂S exposure, having no facial hair can greatly benefit response time and treatment ability.





Colgate Energy

(Permit) Eddy County, NM (83-NME)

(Permit) Koala 9 Fed Com

(A05) Koala 9 Fed Com 121H

Permit

Plan: APD-Rev00

Standard Planning Report

12 May, 2022



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Project	(Permit) Eddy County, NM (83-NME)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		(Permit) Koala 9 Fed Com			
Site Position:		Northing:	579,560.58 usft	Latitude:	32.59318638
From:	Map	Easting:	584,661.65 usft	Longitude:	-104.19265949
Position Uncertainty:		0.00 usft	Slot Radius:	13-3/16 "	

Well	(A05) Koala 9 Fed Com 121H					
Well Position	+N/-S	-1.00 usft	Northing:	579,559.58 usft	Latitude:	32.59318331
	+E/-W	89.00 usft	Easting:	584,750.65 usft	Longitude:	-104.19237051
Position Uncertainty		0.00 usft	Wellhead Elevation:	usft	Ground Level:	3,288.00 usft
Grid Convergence:		0.08 °				

Wellbore	Permit				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	5/6/2022	6.76	60.11	47,555.80061296

Design	APD-Rev00				
Audit Notes:					
Version:		Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.00	-1.00	89.00	89.58	

Plan Survey Tool Program	Date	5/12/2022			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.00	18,159.20	APD-Rev00 (Permit)	MWD+IFR1+SAG+FDIR (SQC OWSG MWD + IFR1 + Sag + F	



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	-1.00	89.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	-1.00	89.00	0.00	0.00	0.00	0.00	
1,400.96	3.01	198.46	1,400.86	-6.01	87.33	1.50	1.50	0.00	198.46	
4,803.94	3.01	198.46	4,799.14	-175.76	30.67	0.00	0.00	0.00	0.00	
5,004.89	0.00	0.01	5,000.00	-180.77	29.00	1.50	-1.50	0.00	180.00	
6,720.93	0.00	0.01	6,716.04	-180.77	29.00	0.00	0.00	0.00	0.01	
7,620.93	90.00	91.20	7,289.00	-192.77	601.83	10.00	10.00	0.00	91.20	
7,701.87	90.00	89.58	7,289.00	-193.32	682.76	2.00	0.00	-2.00	-90.00	
18,159.20	90.00	89.58	7,289.00	-116.91	11,139.81	0.00	0.00	0.00	0.00	PBHL(K9- 121H)



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	-1.00	89.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	-1.00	89.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	-1.00	89.00	0.00	0.00	0.00	0.00
241.00	0.00	0.00	241.00	-1.00	89.00	0.00	0.00	0.00	0.00
Rustler									
300.00	0.00	0.00	300.00	-1.00	89.00	0.00	0.00	0.00	0.00
382.00	0.00	0.00	382.00	-1.00	89.00	0.00	0.00	0.00	0.00
T/Salt									
400.00	0.00	0.00	400.00	-1.00	89.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	-1.00	89.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	-1.00	89.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	-1.00	89.00	0.00	0.00	0.00	0.00
768.00	0.00	0.00	768.00	-1.00	89.00	0.00	0.00	0.00	0.00
Tansill									
800.00	0.00	0.00	800.00	-1.00	89.00	0.00	0.00	0.00	0.00
843.00	0.00	0.00	843.00	-1.00	89.00	0.00	0.00	0.00	0.00
Yates									
900.00	0.00	0.00	900.00	-1.00	89.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	-1.00	89.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	-1.00	89.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	-1.00	89.00	0.00	0.00	0.00	0.00
1,218.00	0.27	198.46	1,218.00	-1.04	88.99	-0.01	1.50	1.50	0.00
Seven Rivers									
1,300.00	1.50	198.46	1,299.99	-2.24	88.59	-0.42	1.50	1.50	0.00
1,400.96	3.01	198.46	1,400.86	-6.01	87.33	-1.71	1.50	1.50	0.00
1,500.00	3.01	198.46	1,499.77	-10.95	85.68	-3.39	0.00	0.00	0.00
1,600.00	3.01	198.46	1,599.63	-15.94	84.01	-5.10	0.00	0.00	0.00
1,700.00	3.01	198.46	1,699.49	-20.93	82.35	-6.80	0.00	0.00	0.00
1,800.00	3.01	198.46	1,799.36	-25.92	80.68	-8.50	0.00	0.00	0.00
1,809.66	3.01	198.46	1,809.00	-26.40	80.52	-8.66	0.00	0.00	0.00
Queen									
1,900.00	3.01	198.46	1,899.22	-30.91	79.02	-10.20	0.00	0.00	0.00
2,000.00	3.01	198.46	1,999.08	-35.89	77.35	-11.90	0.00	0.00	0.00
2,018.95	3.01	198.46	2,018.00	-36.84	77.04	-12.22	0.00	0.00	0.00
Grayburg									
2,100.00	3.01	198.46	2,098.94	-40.88	75.69	-13.60	0.00	0.00	0.00
2,200.00	3.01	198.46	2,198.80	-45.87	74.02	-15.30	0.00	0.00	0.00
2,300.00	3.01	198.46	2,298.66	-50.86	72.36	-17.01	0.00	0.00	0.00
2,400.00	3.01	198.46	2,398.53	-55.85	70.69	-18.71	0.00	0.00	0.00
2,419.50	3.01	198.46	2,418.00	-56.82	70.37	-19.04	0.00	0.00	0.00
San Andres									
2,500.00	3.01	198.46	2,498.39	-60.83	69.03	-20.41	0.00	0.00	0.00
2,600.00	3.01	198.46	2,598.25	-65.82	67.36	-22.11	0.00	0.00	0.00
2,700.00	3.01	198.46	2,698.11	-70.81	65.70	-23.81	0.00	0.00	0.00
2,800.00	3.01	198.46	2,797.97	-75.80	64.04	-25.51	0.00	0.00	0.00
2,900.00	3.01	198.46	2,897.83	-80.79	62.37	-27.21	0.00	0.00	0.00
2,995.30	3.01	198.46	2,993.00	-85.54	60.78	-28.84	0.00	0.00	0.00
CYCN									
3,000.00	3.01	198.46	2,997.69	-85.77	60.71	-28.92	0.00	0.00	0.00
3,100.00	3.01	198.46	3,097.56	-90.76	59.04	-30.62	0.00	0.00	0.00
3,200.00	3.01	198.46	3,197.42	-95.75	57.38	-32.32	0.00	0.00	0.00
3,300.00	3.01	198.46	3,297.28	-100.74	55.71	-34.02	0.00	0.00	0.00
3,400.00	3.01	198.46	3,397.14	-105.73	54.05	-35.72	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
3,500.00	3.01	198.46	3,497.00	-110.72	52.38	-37.42	0.00	0.00	0.00
3,600.00	3.01	198.46	3,596.86	-115.70	50.72	-39.12	0.00	0.00	0.00
3,700.00	3.01	198.46	3,696.73	-120.69	49.05	-40.82	0.00	0.00	0.00
3,800.00	3.01	198.46	3,796.59	-125.68	47.39	-42.53	0.00	0.00	0.00
3,900.00	3.01	198.46	3,896.45	-130.67	45.72	-44.23	0.00	0.00	0.00
4,000.00	3.01	198.46	3,996.31	-135.66	44.06	-45.93	0.00	0.00	0.00
4,100.00	3.01	198.46	4,096.17	-140.64	42.39	-47.63	0.00	0.00	0.00
4,200.00	3.01	198.46	4,196.03	-145.63	40.73	-49.33	0.00	0.00	0.00
4,300.00	3.01	198.46	4,295.90	-150.62	39.06	-51.03	0.00	0.00	0.00
4,400.00	3.01	198.46	4,395.76	-155.61	37.40	-52.73	0.00	0.00	0.00
4,500.00	3.01	198.46	4,495.62	-160.60	35.73	-54.44	0.00	0.00	0.00
4,572.48	3.01	198.46	4,568.00	-164.21	34.53	-55.67	0.00	0.00	0.00
BSGL									
4,600.00	3.01	198.46	4,595.48	-165.58	34.07	-56.14	0.00	0.00	0.00
4,700.00	3.01	198.46	4,695.34	-170.57	32.40	-57.84	0.00	0.00	0.00
4,803.94	3.01	198.46	4,799.14	-175.76	30.67	-59.61	0.00	0.00	0.00
4,900.00	1.57	198.46	4,895.12	-179.40	29.46	-60.85	1.50	-1.50	0.00
5,004.89	0.00	0.01	5,000.00	-180.77	29.00	-61.32	1.50	-1.50	0.00
5,100.00	0.00	0.00	5,095.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,200.00	0.00	0.00	5,195.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,300.00	0.00	0.00	5,295.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,400.00	0.00	0.00	5,395.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,500.00	0.00	0.00	5,495.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,600.00	0.00	0.00	5,595.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,700.00	0.00	0.00	5,695.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,800.00	0.00	0.00	5,795.11	-180.77	29.00	-61.32	0.00	0.00	0.00
5,900.00	0.00	0.00	5,895.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,000.00	0.00	0.00	5,995.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,100.00	0.00	0.00	6,095.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,122.89	0.00	0.00	6,118.00	-180.77	29.00	-61.32	0.00	0.00	0.00
FBSG									
6,200.00	0.00	0.00	6,195.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,300.00	0.00	0.00	6,295.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,400.00	0.00	0.00	6,395.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,500.00	0.00	0.00	6,495.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,600.00	0.00	0.00	6,595.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,700.00	0.00	0.00	6,695.11	-180.77	29.00	-61.32	0.00	0.00	0.00
6,720.93	0.00	0.00	6,716.04	-180.77	29.00	-61.32	0.00	0.00	0.00
KOP: 6720.93' MD, -61.32' VS, 6716.04' TVD									
6,750.00	2.91	91.20	6,745.09	-180.79	29.74	-60.58	10.00	10.00	0.00
6,800.00	7.91	91.20	6,794.86	-180.88	34.45	-55.87	10.00	10.00	0.00
6,850.00	12.91	91.20	6,844.02	-181.07	43.47	-46.85	10.00	10.00	0.00
6,900.00	17.91	91.20	6,892.21	-181.35	56.75	-33.57	10.00	10.00	0.00
6,950.00	22.91	91.20	6,939.05	-181.72	74.17	-16.15	10.00	10.00	0.00
7,000.00	27.91	91.20	6,984.20	-182.17	95.61	5.29	10.00	10.00	0.00
7,050.00	32.91	91.20	7,027.31	-182.70	120.91	30.57	10.00	10.00	0.00
7,100.00	37.91	91.20	7,068.05	-183.30	149.86	59.52	10.00	10.00	0.00
7,150.00	42.91	91.20	7,106.11	-183.98	182.25	91.91	10.00	10.00	0.00
7,200.00	47.91	91.20	7,141.21	-184.73	217.84	127.49	10.00	10.00	0.00
7,202.68	48.18	91.20	7,143.00	-184.77	219.84	129.48	10.00	10.00	0.00
SBSG									
7,250.00	52.91	91.20	7,173.06	-185.53	256.35	165.99	10.00	10.00	0.00
7,300.00	57.91	91.20	7,201.44	-186.39	297.49	207.12	10.00	10.00	0.00



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
7,350.00	62.91	91.20	7,226.12	-187.30	340.94	250.57	10.00	10.00	0.00
7,400.00	67.91	91.20	7,246.93	-188.26	386.38	296.00	10.00	10.00	0.00
7,450.00	72.91	91.20	7,263.69	-189.24	433.46	343.07	10.00	10.00	0.00
7,500.00	77.91	91.20	7,276.28	-190.26	481.82	391.42	10.00	10.00	0.00
7,550.00	82.91	91.20	7,284.61	-191.29	531.09	440.69	10.00	10.00	0.00
7,564.86	84.39	91.20	7,286.26	-191.60	545.86	455.45	10.00	10.00	0.00
20" Casing									
7,600.00	87.91	91.20	7,288.62	-192.33	580.91	490.49	10.00	10.00	0.00
7,620.93	90.00	91.20	7,289.00	-192.77	601.83	511.41	10.00	10.00	0.00
EOC: 7620.93' MD, 511.41' VS, 7289.00' TVD									
7,627.31	90.00	91.07	7,289.00	-192.90	608.21	517.79	2.00	0.01	-2.00
FTP(K9- 121H)									
7,627.32	90.00	91.07	7,289.00	-192.90	608.22	517.80	2.00	0.01	-2.00
100'FWL									
7,701.87	90.00	89.58	7,289.00	-193.32	682.76	592.33	2.00	0.00	-2.00
7,800.00	90.00	89.58	7,289.00	-192.60	780.89	690.47	0.00	0.00	0.00
7,900.00	90.00	89.58	7,289.00	-191.87	880.89	790.47	0.00	0.00	0.00
8,000.00	90.00	89.58	7,289.00	-191.14	980.89	890.47	0.00	0.00	0.00
8,100.00	90.00	89.58	7,289.00	-190.41	1,080.88	990.47	0.00	0.00	0.00
8,200.00	90.00	89.58	7,289.00	-189.68	1,180.88	1,090.47	0.00	0.00	0.00
8,300.00	90.00	89.58	7,289.00	-188.95	1,280.88	1,190.47	0.00	0.00	0.00
8,400.00	90.00	89.58	7,289.00	-188.22	1,380.88	1,290.47	0.00	0.00	0.00
8,500.00	90.00	89.58	7,289.00	-187.49	1,480.87	1,390.47	0.00	0.00	0.00
8,600.00	90.00	89.58	7,289.00	-186.76	1,580.87	1,490.47	0.00	0.00	0.00
8,700.00	90.00	89.58	7,289.00	-186.03	1,680.87	1,590.47	0.00	0.00	0.00
8,800.00	90.00	89.58	7,289.00	-185.30	1,780.86	1,690.47	0.00	0.00	0.00
8,900.00	90.00	89.58	7,289.00	-184.57	1,880.86	1,790.47	0.00	0.00	0.00
9,000.00	90.00	89.58	7,289.00	-183.84	1,980.86	1,890.47	0.00	0.00	0.00
9,100.00	90.00	89.58	7,289.00	-183.10	2,080.86	1,990.47	0.00	0.00	0.00
9,200.00	90.00	89.58	7,289.00	-182.37	2,180.85	2,090.47	0.00	0.00	0.00
9,300.00	90.00	89.58	7,289.00	-181.64	2,280.85	2,190.47	0.00	0.00	0.00
9,400.00	90.00	89.58	7,289.00	-180.91	2,380.85	2,290.47	0.00	0.00	0.00
9,500.00	90.00	89.58	7,289.00	-180.18	2,480.85	2,390.47	0.00	0.00	0.00
9,600.00	90.00	89.58	7,289.00	-179.45	2,580.84	2,490.47	0.00	0.00	0.00
9,700.00	90.00	89.58	7,289.00	-178.72	2,680.84	2,590.47	0.00	0.00	0.00
9,800.00	90.00	89.58	7,289.00	-177.99	2,780.84	2,690.47	0.00	0.00	0.00
9,900.00	90.00	89.58	7,289.00	-177.26	2,880.84	2,790.47	0.00	0.00	0.00
10,000.00	90.00	89.58	7,289.00	-176.53	2,980.83	2,890.47	0.00	0.00	0.00
10,100.00	90.00	89.58	7,289.00	-175.80	3,080.83	2,990.47	0.00	0.00	0.00
10,191.74	90.00	89.58	7,289.00	-175.13	3,172.57	3,082.21	0.00	0.00	0.00
Exit NM 137444 - Enter NM 013232									
10,200.00	90.00	89.58	7,289.00	-175.07	3,180.83	3,090.47	0.00	0.00	0.00
10,300.00	90.00	89.58	7,289.00	-174.34	3,280.82	3,190.47	0.00	0.00	0.00
10,400.00	90.00	89.58	7,289.00	-173.61	3,380.82	3,290.47	0.00	0.00	0.00
10,500.00	90.00	89.58	7,289.00	-172.88	3,480.82	3,390.47	0.00	0.00	0.00
10,600.00	90.00	89.58	7,289.00	-172.14	3,580.82	3,490.47	0.00	0.00	0.00
10,700.00	90.00	89.58	7,289.00	-171.41	3,680.81	3,590.47	0.00	0.00	0.00
10,800.00	90.00	89.58	7,289.00	-170.68	3,780.81	3,690.47	0.00	0.00	0.00
10,900.00	90.00	89.58	7,289.00	-169.95	3,880.81	3,790.47	0.00	0.00	0.00
11,000.00	90.00	89.58	7,289.00	-169.22	3,980.81	3,890.47	0.00	0.00	0.00
11,100.00	90.00	89.58	7,289.00	-168.49	4,080.80	3,990.47	0.00	0.00	0.00
11,200.00	90.00	89.58	7,289.00	-167.76	4,180.80	4,090.47	0.00	0.00	0.00
11,300.00	90.00	89.58	7,289.00	-167.03	4,280.80	4,190.47	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,400.00	90.00	89.58	7,289.00	-166.30	4,380.80	4,290.47	0.00	0.00	0.00
11,500.00	90.00	89.58	7,289.00	-165.57	4,480.79	4,390.47	0.00	0.00	0.00
11,600.00	90.00	89.58	7,289.00	-164.84	4,580.79	4,490.47	0.00	0.00	0.00
11,700.00	90.00	89.58	7,289.00	-164.11	4,680.79	4,590.47	0.00	0.00	0.00
11,800.00	90.00	89.58	7,289.00	-163.38	4,780.78	4,690.47	0.00	0.00	0.00
11,900.00	90.00	89.58	7,289.00	-162.65	4,880.78	4,790.47	0.00	0.00	0.00
12,000.00	90.00	89.58	7,289.00	-161.91	4,980.78	4,890.47	0.00	0.00	0.00
12,100.00	90.00	89.58	7,289.00	-161.18	5,080.78	4,990.47	0.00	0.00	0.00
12,200.00	90.00	89.58	7,289.00	-160.45	5,180.77	5,090.47	0.00	0.00	0.00
12,300.00	90.00	89.58	7,289.00	-159.72	5,280.77	5,190.47	0.00	0.00	0.00
12,400.00	90.00	89.58	7,289.00	-158.99	5,380.77	5,290.47	0.00	0.00	0.00
12,500.00	90.00	89.58	7,289.00	-158.26	5,480.77	5,390.47	0.00	0.00	0.00
12,600.00	90.00	89.58	7,289.00	-157.53	5,580.76	5,490.47	0.00	0.00	0.00
12,700.00	90.00	89.58	7,289.00	-156.80	5,680.76	5,590.47	0.00	0.00	0.00
12,800.00	90.00	89.58	7,289.00	-156.07	5,780.76	5,690.47	0.00	0.00	0.00
12,856.31	90.00	89.58	7,289.00	-155.66	5,837.07	5,746.78	0.00	0.00	0.00
Exit NM 013232 - Enter NM 015003									
12,900.00	90.00	89.58	7,289.00	-155.34	5,880.76	5,790.47	0.00	0.00	0.00
13,000.00	90.00	89.58	7,289.00	-154.61	5,980.75	5,890.47	0.00	0.00	0.00
13,100.00	90.00	89.58	7,289.00	-153.88	6,080.75	5,990.47	0.00	0.00	0.00
13,200.00	90.00	89.58	7,289.00	-153.15	6,180.75	6,090.47	0.00	0.00	0.00
13,300.00	90.00	89.58	7,289.00	-152.42	6,280.74	6,190.47	0.00	0.00	0.00
13,400.00	90.00	89.58	7,289.00	-151.69	6,380.74	6,290.47	0.00	0.00	0.00
13,500.00	90.00	89.58	7,289.00	-150.95	6,480.74	6,390.47	0.00	0.00	0.00
13,600.00	90.00	89.58	7,289.00	-150.22	6,580.74	6,490.47	0.00	0.00	0.00
13,700.00	90.00	89.58	7,289.00	-149.49	6,680.73	6,590.47	0.00	0.00	0.00
13,800.00	90.00	89.58	7,289.00	-148.76	6,780.73	6,690.47	0.00	0.00	0.00
13,900.00	90.00	89.58	7,289.00	-148.03	6,880.73	6,790.47	0.00	0.00	0.00
14,000.00	90.00	89.58	7,289.00	-147.30	6,980.73	6,890.47	0.00	0.00	0.00
14,100.00	90.00	89.58	7,289.00	-146.57	7,080.72	6,990.47	0.00	0.00	0.00
14,200.00	90.00	89.58	7,289.00	-145.84	7,180.72	7,090.47	0.00	0.00	0.00
14,300.00	90.00	89.58	7,289.00	-145.11	7,280.72	7,190.47	0.00	0.00	0.00
14,400.00	90.00	89.58	7,289.00	-144.38	7,380.72	7,290.47	0.00	0.00	0.00
14,500.00	90.00	89.58	7,289.00	-143.65	7,480.71	7,390.47	0.00	0.00	0.00
14,600.00	90.00	89.58	7,289.00	-142.92	7,580.71	7,490.47	0.00	0.00	0.00
14,700.00	90.00	89.58	7,289.00	-142.19	7,680.71	7,590.47	0.00	0.00	0.00
14,800.00	90.00	89.58	7,289.00	-141.46	7,780.70	7,690.47	0.00	0.00	0.00
14,900.00	90.00	89.58	7,289.00	-140.72	7,880.70	7,790.47	0.00	0.00	0.00
15,000.00	90.00	89.58	7,289.00	-139.99	7,980.70	7,890.47	0.00	0.00	0.00
15,100.00	90.00	89.58	7,289.00	-139.26	8,080.70	7,990.47	0.00	0.00	0.00
15,200.00	90.00	89.58	7,289.00	-138.53	8,180.69	8,090.47	0.00	0.00	0.00
15,300.00	90.00	89.58	7,289.00	-137.80	8,280.69	8,190.47	0.00	0.00	0.00
15,400.00	90.00	89.58	7,289.00	-137.07	8,380.69	8,290.47	0.00	0.00	0.00
15,500.00	90.00	89.58	7,289.00	-136.34	8,480.69	8,390.47	0.00	0.00	0.00
15,600.00	90.00	89.58	7,289.00	-135.61	8,580.68	8,490.47	0.00	0.00	0.00
15,700.00	90.00	89.58	7,289.00	-134.88	8,680.68	8,590.47	0.00	0.00	0.00
15,800.00	90.00	89.58	7,289.00	-134.15	8,780.68	8,690.47	0.00	0.00	0.00
15,900.00	90.00	89.58	7,289.00	-133.42	8,880.68	8,790.47	0.00	0.00	0.00
16,000.00	90.00	89.58	7,289.00	-132.69	8,980.67	8,890.47	0.00	0.00	0.00
16,100.00	90.00	89.58	7,289.00	-131.96	9,080.67	8,990.47	0.00	0.00	0.00
16,200.00	90.00	89.58	7,289.00	-131.23	9,180.67	9,090.47	0.00	0.00	0.00
16,300.00	90.00	89.58	7,289.00	-130.50	9,280.66	9,190.47	0.00	0.00	0.00
16,400.00	90.00	89.58	7,289.00	-129.76	9,380.66	9,290.47	0.00	0.00	0.00
16,500.00	90.00	89.58	7,289.00	-129.03	9,480.66	9,390.47	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
16,600.00	90.00	89.58	7,289.00	-128.30	9,580.66	9,490.47	0.00	0.00	0.00	
16,700.00	90.00	89.58	7,289.00	-127.57	9,680.65	9,590.47	0.00	0.00	0.00	
16,800.00	90.00	89.58	7,289.00	-126.84	9,780.65	9,690.47	0.00	0.00	0.00	
16,900.00	90.00	89.58	7,289.00	-126.11	9,880.65	9,790.47	0.00	0.00	0.00	
17,000.00	90.00	89.58	7,289.00	-125.38	9,980.65	9,890.47	0.00	0.00	0.00	
17,100.00	90.00	89.58	7,289.00	-124.65	10,080.64	9,990.47	0.00	0.00	0.00	
17,200.00	90.00	89.58	7,289.00	-123.92	10,180.64	10,090.47	0.00	0.00	0.00	
17,300.00	90.00	89.58	7,289.00	-123.19	10,280.64	10,190.47	0.00	0.00	0.00	
17,400.00	90.00	89.58	7,289.00	-122.46	10,380.64	10,290.47	0.00	0.00	0.00	
17,500.00	90.00	89.58	7,289.00	-121.73	10,480.63	10,390.47	0.00	0.00	0.00	
17,600.00	90.00	89.58	7,289.00	-121.00	10,580.63	10,490.47	0.00	0.00	0.00	
17,700.00	90.00	89.58	7,289.00	-120.27	10,680.63	10,590.47	0.00	0.00	0.00	
17,800.00	90.00	89.58	7,289.00	-119.53	10,780.62	10,690.47	0.00	0.00	0.00	
17,900.00	90.00	89.58	7,289.00	-118.80	10,880.62	10,790.47	0.00	0.00	0.00	
18,000.00	90.00	89.58	7,289.00	-118.07	10,980.62	10,890.47	0.00	0.00	0.00	
18,069.17	90.00	89.58	7,289.00	-117.57	11,049.79	10,959.64	0.00	0.00	0.00	
100'FEL - LTP(K9- 121H)										
18,100.00	90.00	89.58	7,289.00	-117.34	11,080.62	10,990.47	0.00	0.00	0.00	
18,159.20	90.00	89.58	7,289.00	-116.91	11,139.81	11,049.66	0.00	0.00	0.00	
TD: 18159.20' MD, 11049.67' VS,7289.00' TVD - PBHL(K9- 121H)										

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
PBHL(K9- 121H)	0.00	0.00	7,289.00	-116.91	11,139.81	579,443.67	595,801.46	32.59281932	-104.15648921
- plan hits target center									
- Point									
LTP(K9- 121H)	0.00	0.01	7,289.00	-117.64	11,049.79	579,442.94	595,711.44	32.59281773	-104.15678150
- plan misses target center by 0.07usft at 18069.17usft MD (7289.00 TVD, -117.57 N, 11049.79 E)									
- Point									
FTP(K9- 121H)	0.00	0.00	7,289.00	-193.44	608.20	579,367.14	585,269.85	32.59265244	-104.19068551
- plan misses target center by 0.54usft at 7627.31usft MD (7289.00 TVD, -192.90 N, 608.21 E)									
- Point									

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name		Casing Diameter (")	Hole Diameter (")
7,564.86	7,286.26	20" Casing		20	24



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Site (Permit) Koala 9 Fed Com
Company:	Colgate Energy	TVD Reference:	3288+30 @ 3318.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3288+30 @ 3318.00usft
Site:	(Permit) Koala 9 Fed Com	North Reference:	Grid
Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev00		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
241.00	241.00	Rustler				
382.00	382.00	T/Salt				
768.00	768.00	Tansill				
843.00	843.00	Yates				
1,218.00	1,218.00	Seven Rivers				
1,809.66	1,809.00	Queen				
2,018.95	2,018.00	Grayburg				
2,419.50	2,418.00	San Andres				
2,995.30	2,993.00	CYCN				
4,572.48	4,568.00	BSGL				
6,122.89	6,118.00	FBSG				
7,202.68	7,143.00	SBSG				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
6,720.93	6,716.04	-180.77	29.00	KOP: 6720.93' MD, -61.32' VS,6716.04' TVD	
7,620.93	7,289.00	-192.77	601.83	EOC: 7620.93' MD, 511.41' VS,7289.00' TVD	
7,627.32	7,289.00	-192.90	608.22	100'FWL	
10,191.74	7,289.00	-175.13	3,172.57	Exit NM 137444	
10,191.74	7,289.00	-175.13	3,172.57	Enter NM 013232	
12,856.31	7,289.00	-155.66	5,837.07	Exit NM 013232	
12,856.31	7,289.00	-155.66	5,837.07	Enter NM 015003	
18,069.17	7,289.00	-117.57	11,049.79	100'FEL	
18,159.20	7,289.00	-116.91	11,139.81	TD: 18159.20' MD, 11049.67' VS,7289.00' TVD	



Colgate Energy

(Permit) Eddy County, NM (83-NME)

(Permit) Koala 9 Fed Com

(A05) Koala 9 Fed Com 121H

Permit

APD-Rev00

Anticollision Report

13 May, 2022



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Reference	APD-Rev00		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	Stations	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum separation factor of 25	Error Surface:	Pedal Curve
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program	Date	5/12/2022		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.00	18,159.20	APD-Rev00 (Permit)	MWD+IFR1+SAG+FDIR	(SQ OWSG MWD + IFR1 + Sag + FDIR Correction)

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
(Permit) Koala 9 Fed Com						
(A01) Koala 9 Fed Com 201H - Permit - APD-Rev00	1,527.91	1,528.51	116.85	106.45	11.235	CC, ES
(A01) Koala 9 Fed Com 201H - Permit - APD-Rev00	1,800.00	1,795.79	125.91	113.65	10.268	SF
(A02) Koala 9 Fed Com 202H - Permit - APD-Rev00	1,809.99	1,810.37	82.56	70.33	6.754	CC
(A02) Koala 9 Fed Com 202H - Permit - APD-Rev00	1,900.00	1,900.06	82.91	70.07	6.457	ES
(A02) Koala 9 Fed Com 202H - Permit - APD-Rev00	2,400.00	2,398.28	96.40	80.12	5.920	SF
(A03) Koala 9 Fed Com 131H - Permit - APD-Rev00	1,643.59	1,643.16	57.22	46.01	5.106	CC
(A03) Koala 9 Fed Com 131H - Permit - APD-Rev00	3,818.13	3,819.39	61.35	35.05	2.333	ES
(A03) Koala 9 Fed Com 131H - Permit - APD-Rev00	3,900.00	3,900.00	62.24	35.37	2.316	SF
(A04) Koala 9 Fed Com 132H - Permit - APD-Rev00	800.00	800.00	30.00	24.73	5.694	CC
(A04) Koala 9 Fed Com 132H - Permit - APD-Rev00	1,000.00	999.79	30.54	23.88	4.589	ES
(A04) Koala 9 Fed Com 132H - Permit - APD-Rev00	1,100.00	1,099.35	32.40	25.06	4.412	SF
(A06) Koala 9 Fed Com 122H - Permit - APD-Rev00	861.82	861.82	30.00	24.30	5.262	CC
(A06) Koala 9 Fed Com 122H - Permit - APD-Rev00	1,000.00	999.84	30.37	23.72	4.564	ES
(A06) Koala 9 Fed Com 122H - Permit - APD-Rev00	1,100.00	1,099.42	32.04	24.70	4.363	SF
(A07) Koala 9 Fed Com 111H - Permit - APD-Rev00	1,200.00	1,200.00	60.00	51.86	7.373	CC
(A07) Koala 9 Fed Com 111H - Permit - APD-Rev00	5,607.38	5,607.36	70.08	31.13	1.799	ES, SF
(A08) Koala 9 Fed Com 112H - Permit - APD-Rev00	863.12	863.12	90.00	84.29	15.760	CC
(A08) Koala 9 Fed Com 112H - Permit - APD-Rev00	1,100.00	1,099.43	90.70	83.35	12.348	ES
(A08) Koala 9 Fed Com 112H - Permit - APD-Rev00	18,159.20	17,163.72	1,702.60	1,496.72	8.270	SF
(B01) Koala 9 Fed Com 203H - Permit - APD-Rev00	11,900.00	13,491.32	2,543.49	2,441.20	24.866	CC
(B01) Koala 9 Fed Com 203H - Permit - APD-Rev00	18,159.20	19,710.50	2,547.16	2,335.72	12.047	ES, SF
(B02) Koala 9 Fed Com 204H - Permit - APD-Rev00	13,900.00	15,390.12	3,672.42	3,523.80	24.711	CC
(B02) Koala 9 Fed Com 204H - Permit - APD-Rev00	18,100.00	19,583.50	3,675.00	3,442.88	15.832	ES
(B02) Koala 9 Fed Com 204H - Permit - APD-Rev00	18,159.20	19,583.50	3,675.62	3,442.92	15.795	SF
(B03) Koala 9 Fed Com 133H - Permit - APD-Rev00	12,300.00	13,203.77	2,933.81	2,815.28	24.752	CC
(B03) Koala 9 Fed Com 133H - Permit - APD-Rev00	18,159.20	19,009.61	2,937.83	2,704.52	12.592	ES, SF
(B04) Koala 9 Fed Com 134H - Permit - APD-Rev00	14,600.00	15,756.63	4,167.81	3,999.74	24.798	CC
(B04) Koala 9 Fed Com 134H - Permit - APD-Rev00	18,100.00	19,235.87	4,170.12	3,929.13	17.304	ES
(B04) Koala 9 Fed Com 134H - Permit - APD-Rev00	18,159.20	19,235.87	4,170.87	3,929.25	17.262	SF
(B05) Koala 9 Fed Com 123H - Permit - APD-Rev00	11,400.00	11,057.25	2,655.02	2,548.02	24.814	CC
(B05) Koala 9 Fed Com 123H - Permit - APD-Rev00	18,159.20	17,763.11	2,660.11	2,409.99	10.635	ES, SF
(B06) Koala 9 Fed Com 124H - Permit - APD-Rev00	14,000.00	13,913.90	3,976.51	3,816.30	24.821	CC
(B06) Koala 9 Fed Com 124H - Permit - APD-Rev00	18,100.00	17,993.15	3,979.34	3,730.38	15.984	ES
(B06) Koala 9 Fed Com 124H - Permit - APD-Rev00	18,159.20	17,993.15	3,980.13	3,730.51	15.945	SF
(B07) Koala 9 Fed Com 113H - Permit - APD-Rev00	12,200.00	11,015.92	2,827.42	2,713.08	24.727	CC
(B07) Koala 9 Fed Com 113H - Permit - APD-Rev00	18,159.20	16,922.61	2,831.62	2,596.21	12.029	ES, SF
(B08) Koala 9 Fed Com 114H - Permit - APD-Rev00	14,500.00	13,310.75	4,093.53	3,928.15	24.753	CC

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Summary

Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
(Permit) Koala 9 Fed Com						
(B08) Koala 9 Fed Com 114H - Permit - APD-Rev00	18,100.00	16,890.04	4,095.99	3,854.33	16.949	ES
(B08) Koala 9 Fed Com 114H - Permit - APD-Rev00	18,159.20	16,890.04	4,096.76	3,854.44	16.906	SF
Koala 9 Fed Com Offsets						
W01_PRE-ONGARD WELL #001_1520917 - Depth Only						Out of range
W02_GOVERNMENT AO COM #001_1524032 - Inc Only	6,569.74	6,537.77	4,693.83	4,496.94	23.840	CC
W02_GOVERNMENT AO COM #001_1524032 - Inc Only	6,750.00	6,719.13	4,695.15	4,485.47	22.392	ES
W02_GOVERNMENT AO COM #001_1524032 - Inc Only	7,250.00	7,148.46	4,836.36	4,604.29	20.840	SF
W03_PRE-ONGARD WELL #001_1525793 - Inc Only - In						Out of range
W04_FEDERAL V #001_1526451 - Inc Only - Inc Only	5,194.12	5,164.40	2,016.48	1,878.89	14.656	CC
W04_FEDERAL V #001_1526451 - Inc Only - Inc Only	6,750.00	6,718.38	2,017.83	1,836.93	11.155	ES
W04_FEDERAL V #001_1526451 - Inc Only - Inc Only	6,950.00	6,914.92	2,056.46	1,870.28	11.046	SF
W05_FEDERAL V #002_1526702 - Inc Only - Inc Only	6,303.35	6,274.42	1,761.90	1,606.15	11.312	CC
W05_FEDERAL V #002_1526702 - Inc Only - Inc Only	6,400.00	6,330.00	1,762.38	1,605.06	11.202	ES, SF
W06_FEDERAL V #003_1526867 - Depth Only - Depth O	6,300.00	6,272.11	4,324.27	3,906.26	10.345	CC
W06_FEDERAL V #003_1526867 - Depth Only - Depth O	6,400.00	6,300.00	4,325.01	3,904.96	10.296	ES, SF
W07_PRE-ONGARD WELL #001_1527282 - Depth Only	6,720.93	6,669.04	3,944.98	3,500.49	8.875	CC
W07_PRE-ONGARD WELL #001_1527282 - Depth Only	6,850.00	6,797.02	3,950.11	3,497.10	8.720	ES
W07_PRE-ONGARD WELL #001_1527282 - Depth Only	7,250.00	7,126.06	4,030.81	3,555.82	8.486	SF
W08_FEDERAL V COM #004_1535127 - Inc Only - Inc O	6,593.99	6,543.85	3,993.78	3,813.92	22.205	CC
W08_FEDERAL V COM #004_1535127 - Inc Only - Inc O	6,750.00	6,696.08	3,994.58	3,810.51	21.701	ES
W08_FEDERAL V COM #004_1535127 - Inc Only - Inc O	7,050.00	6,982.32	4,084.51	3,892.02	21.220	SF
W09_GOVERNMENT AB #002_1521480 - Inc Only - Inc	17,446.59	7,238.03	2,330.32	2,043.15	8.115	CC, ES
W09_GOVERNMENT AB #002_1521480 - Inc Only - Inc	17,600.00	7,238.03	2,335.37	2,046.70	8.090	SF
W10_GOVERNMENT AB #003_1521774 - Inc Only - Inc	14,774.78	7,246.43	2,328.97	2,101.90	10.256	CC
W10_GOVERNMENT AB #003_1521774 - Inc Only - Inc	14,800.00	7,246.43	2,329.11	2,101.76	10.244	ES
W10_GOVERNMENT AB #003_1521774 - Inc Only - Inc	15,000.00	7,246.43	2,339.84	2,110.65	10.209	SF
W11_GOVERNMENT AB #006_1527846 - Inc Only - Inc	13,511.81	6,554.00	770.71	654.95	6.658	CC, ES
W11_GOVERNMENT AB #006_1527846 - Inc Only - Inc	14,000.00	6,554.00	912.32	762.60	6.094	SF
W12_GOVERNMENT AB #007_1527847 - Inc Only - Inc	14,832.34	6,590.00	734.04	600.05	5.478	CC, ES
W12_GOVERNMENT AB #007_1527847 - Inc Only - Inc	15,200.00	6,590.00	820.97	662.04	5.166	SF
W13_GOVERNMENT AB #008_1527863 - Inc Only - Inc	16,177.89	6,630.00	641.57	543.54	6.545	CC
W13_GOVERNMENT AB #008_1527863 - Inc Only - Inc	16,200.00	6,630.00	641.95	543.51	6.521	ES
W13_GOVERNMENT AB #008_1527863 - Inc Only - Inc	16,600.00	6,630.00	767.98	626.77	5.439	SF
W14_GOVERNMENT AB #009_1527964 - MWD/Inc - M	17,504.04	6,678.00	672.52	601.37	9.452	CC, ES, SF
W15_GOVERNMENT AB FEDERAL #011_1540853 - MW	14,588.45	6,684.00	1,234.34	1,137.34	12.725	CC
W15_GOVERNMENT AB FEDERAL #011_1540853 - MW	14,600.00	6,684.00	1,234.39	1,137.28	12.711	ES
W15_GOVERNMENT AB FEDERAL #011_1540853 - MW	14,700.00	6,684.00	1,239.37	1,141.52	12.666	SF
W16_GOVERNMENT AB FEDERAL #014_1540854 - MW	13,568.02	6,555.00	1,175.67	1,096.46	14.842	CC, ES
W16_GOVERNMENT AB FEDERAL #014_1540854 - MW	13,700.00	6,555.00	1,183.06	1,102.67	14.717	SF
W17_GOVERNMENT AB FEDERAL #013_1540920 - MW	17,426.97	6,652.00	1,131.24	1,007.07	9.110	CC, ES
W17_GOVERNMENT AB FEDERAL #013_1540920 - MW	17,500.00	6,652.00	1,133.59	1,008.94	9.094	SF
W18_GOVERNMENT AB FEDERAL #012_1541049 - MW	16,351.03	6,784.00	1,073.31	959.18	9.405	CC, ES
W18_GOVERNMENT AB FEDERAL #012_1541049 - MW	16,400.00	6,784.00	1,074.42	959.72	9.367	SF

Offset Design: (Permit) Koala 9 Fed Com - (A01) Koala 9 Fed Com 201H - Permit - APD-Rev00													Offset Site Error:	0.00 usft
Survey Program:		0-MWD+IFR1+SAG+FDIR (SQC2)										Offset Well Error:	0.00 usft	
Reference		Offset		Semi Major Axis		Offset Wellbore Centre			Rule Assigned:					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A01) Koala 9 Fed Com 201H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
800.00	800.00	801.00	801.00	2.63	2.64	-89.05	2.00	-119.98	120.00	114.72	5.27	22.756			
900.00	900.00	901.00	901.00	2.99	3.00	-89.05	2.00	-119.98	120.00	114.01	5.99	20.033			
1,000.00	1,000.00	1,001.00	1,001.00	3.35	3.36	-89.05	2.00	-119.98	120.00	113.29	6.71	17.891			
1,100.00	1,100.00	1,101.00	1,101.00	3.71	3.71	-89.05	2.00	-119.98	120.00	112.57	7.42	16.163			
1,200.00	1,200.00	1,201.01	1,201.01	4.07	4.07	-89.04	2.00	-119.98	120.00	111.86	8.14	14.740			
1,300.00	1,299.99	1,301.46	1,301.44	4.41	4.43	73.75	3.33	-119.74	119.41	110.57	8.84	13.506			
1,400.96	1,400.86	1,402.44	1,402.35	4.74	4.79	77.55	7.27	-119.01	117.98	108.45	9.53	12.378			
1,500.00	1,499.77	1,500.89	1,500.58	5.07	5.15	83.19	13.65	-117.83	116.92	106.71	10.21	11.452			
1,527.91	1,527.64	1,528.51	1,528.11	5.16	5.25	85.01	15.88	-117.42	116.85	106.45	10.40	11.235 CC, ES			
1,600.00	1,599.63	1,599.61	1,598.88	5.40	5.50	90.12	22.54	-116.20	117.37	106.47	10.90	10.773			
1,700.00	1,699.49	1,697.52	1,696.12	5.74	5.85	98.00	33.82	-114.12	120.24	108.66	11.58	10.385			
1,800.00	1,799.36	1,795.79	1,793.53	6.08	6.20	105.98	46.51	-111.78	125.91	113.65	12.26	10.268 SF			
1,900.00	1,899.22	1,894.10	1,891.00	6.43	6.55	113.18	59.20	-109.44	133.86	120.91	12.95	10.338			
2,000.00	1,999.08	1,992.42	1,988.46	6.77	6.90	119.50	71.90	-107.11	143.71	130.07	13.64	10.539			
2,100.00	2,098.94	2,090.73	2,085.92	7.12	7.25	124.98	84.59	-104.77	155.10	140.77	14.32	10.827			
2,200.00	2,198.80	2,189.04	2,183.38	7.47	7.60	129.68	97.29	-102.43	167.71	152.70	15.01	11.170			
2,300.00	2,298.66	2,287.36	2,280.84	7.81	7.95	133.71	109.98	-100.09	181.30	165.59	15.71	11.543			
2,400.00	2,398.53	2,385.67	2,378.31	8.17	8.31	137.17	122.68	-97.75	195.65	179.25	16.40	11.931			
2,500.00	2,498.39	2,483.98	2,475.77	8.52	8.66	140.16	135.38	-95.42	210.61	193.52	17.09	12.322			
2,600.00	2,598.25	2,582.30	2,573.23	8.87	9.02	142.74	148.07	-93.08	226.06	208.28	17.79	12.710			
2,700.00	2,698.11	2,680.61	2,670.69	9.22	9.37	145.00	160.77	-90.74	241.91	223.43	18.48	13.088			
2,800.00	2,797.97	2,778.92	2,768.15	9.58	9.73	146.98	173.46	-88.40	258.08	238.90	19.18	13.456			
2,900.00	2,897.83	2,877.24	2,865.62	9.93	10.08	148.72	186.16	-86.06	274.52	254.64	19.88	13.810			
3,000.00	2,997.69	2,975.55	2,963.08	10.29	10.44	150.27	198.85	-83.72	291.18	270.60	20.58	14.151			
3,100.00	3,097.56	3,073.86	3,060.54	10.64	10.80	151.65	211.55	-81.39	308.03	286.75	21.28	14.478			
3,200.00	3,197.42	3,172.18	3,158.00	11.00	11.15	152.88	224.25	-79.05	325.03	303.05	21.98	14.790			
3,300.00	3,297.28	3,270.49	3,255.46	11.35	11.51	154.00	236.94	-76.71	342.16	319.48	22.68	15.089			
3,400.00	3,397.14	3,368.80	3,352.93	11.71	11.87	155.00	249.64	-74.37	359.41	336.03	23.38	15.374			
3,500.00	3,497.00	3,467.12	3,450.39	12.07	12.22	155.92	262.33	-72.03	376.75	352.67	24.08	15.646			
3,600.00	3,596.86	3,565.43	3,547.85	12.42	12.58	156.75	275.03	-69.70	394.18	369.40	24.78	15.906			
3,700.00	3,696.73	3,663.74	3,645.31	12.78	12.94	157.52	287.72	-67.36	411.69	386.20	25.48	16.155			
3,800.00	3,796.59	3,762.06	3,742.78	13.14	13.29	158.22	300.42	-65.02	429.26	403.07	26.19	16.392			
3,900.00	3,896.45	3,860.37	3,840.24	13.50	13.65	158.87	313.12	-62.68	446.89	420.00	26.89	16.619			
4,000.00	3,996.31	3,958.68	3,937.70	13.86	14.01	159.46	325.81	-60.34	464.56	436.97	27.59	16.836			
4,100.00	4,096.17	4,057.00	4,035.16	14.21	14.37	160.02	338.51	-58.00	482.29	453.99	28.30	17.044			
4,200.00	4,196.03	4,155.31	4,132.62	14.57	14.72	160.53	351.20	-55.67	500.05	471.05	29.00	17.243			
4,300.00	4,295.90	4,253.62	4,230.09	14.93	15.08	161.01	363.90	-53.33	517.86	488.15	29.71	17.433			
4,400.00	4,395.76	4,351.94	4,327.55	15.29	15.44	161.46	376.59	-50.99	535.69	505.28	30.41	17.616			
4,500.00	4,495.62	4,450.25	4,425.01	15.65	15.80	161.88	389.29	-48.65	553.56	522.44	31.11	17.791			
4,600.00	4,595.48	4,552.76	4,526.64	16.01	16.17	162.29	402.42	-46.23	571.36	539.50	31.85	17.937			
4,700.00	4,695.34	4,668.83	4,642.02	16.37	16.59	162.68	414.85	-43.94	587.07	554.38	32.69	17.959			
4,803.94	4,799.14	4,790.58	4,763.40	16.74	17.03	163.01	424.17	-42.23	600.27	566.73	33.54	17.898			
4,900.00	4,895.12	4,904.02	4,876.71	17.09	17.43	163.25	429.42	-41.26	608.41	574.11	34.30	17.737			
5,004.89	5,000.00	5,028.52	5,001.19	17.45	17.87	1.79	431.38	-40.90	611.45	576.35	35.10	17.421			
5,036.27	5,031.37	5,059.70	5,032.37	17.55	17.98	1.79	431.38	-40.90	611.45	576.13	35.32	17.314			
5,100.00	5,095.11	5,123.44	5,096.11	17.77	18.21	1.79	431.38	-40.90	611.45	575.69	35.76	17.100			
5,200.00	5,195.11	5,223.44	5,196.11	18.10	18.56	1.79	431.38	-40.90	611.45	575.00	36.45	16.774			
5,300.00	5,295.11	5,323.44	5,296.11	18.44	18.91	1.79	431.38	-40.90	611.45	574.30	37.15	16.460			
5,400.00	5,395.11	5,423.44	5,396.11	18.78	19.27	1.79	431.38	-40.90	611.45	573.61	37.84	16.158			
5,500.00	5,495.11	5,523.44	5,496.11	19.12	19.62	1.79	431.38	-40.90	611.45	572.91	38.54	15.866			
5,600.00	5,595.11	5,623.44	5,596.11	19.46	19.97	1.79	431.38	-40.90	611.45	572.21	39.24	15.584			
5,700.00	5,695.11	5,723.44	5,696.11	19.80	20.33	1.79	431.38	-40.90	611.45	571.51	39.93	15.311			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A01) Koala 9 Fed Com 201H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
5,800.00	5,795.11	5,823.44	5,796.11	20.14	20.68	1.79	431.38	-40.90	611.45	570.81	40.63	15.048	
5,900.00	5,895.11	5,923.44	5,896.11	20.48	21.03	1.79	431.38	-40.90	611.45	570.12	41.33	14.793	
6,000.00	5,995.11	6,023.44	5,996.11	20.82	21.39	1.79	431.38	-40.90	611.45	569.42	42.03	14.547	
6,100.00	6,095.11	6,123.44	6,096.11	21.16	21.74	1.79	431.38	-40.90	611.45	568.71	42.73	14.308	
6,200.00	6,195.11	6,223.44	6,196.11	21.51	22.09	1.79	431.38	-40.90	611.45	568.01	43.43	14.077	
6,300.00	6,295.11	6,323.44	6,296.11	21.85	22.45	1.79	431.38	-40.90	611.45	567.31	44.14	13.854	
6,400.00	6,395.11	6,423.44	6,396.11	22.19	22.80	1.79	431.38	-40.90	611.45	566.61	44.84	13.637	
6,500.00	6,495.11	6,523.44	6,496.11	22.54	23.16	1.79	431.38	-40.90	611.45	565.91	45.54	13.426	
6,600.00	6,595.11	6,623.44	6,596.11	22.88	23.51	1.79	431.38	-40.90	611.45	565.20	46.24	13.222	
6,700.00	6,695.11	6,723.44	6,696.11	23.23	23.87	1.79	431.38	-40.90	611.45	564.50	46.95	13.024	
6,720.93	6,716.04	6,744.37	6,717.04	23.30	23.94	1.79	431.38	-40.90	611.45	564.35	47.09	12.983	
6,750.00	6,745.09	6,773.43	6,746.09	23.40	24.04	-89.48	431.38	-40.90	611.44	564.14	47.30	12.927	
6,800.00	6,794.86	6,823.19	6,795.86	23.57	24.22	-89.92	431.38	-40.90	611.42	563.77	47.65	12.832	
6,805.94	6,800.73	6,829.06	6,801.73	23.59	24.24	-90.00	431.38	-40.90	611.42	563.73	47.69	12.821	
6,850.00	6,844.02	6,872.35	6,845.02	23.74	24.40	-90.75	431.38	-40.90	611.47	563.48	47.99	12.741	
6,900.00	6,892.21	6,920.54	6,893.21	23.90	24.57	-91.91	431.38	-40.90	611.79	563.46	48.33	12.658	
6,950.00	6,939.05	6,967.39	6,940.05	24.06	24.73	-93.35	431.38	-40.90	612.65	563.99	48.66	12.589	
7,000.00	6,984.20	7,012.54	6,985.20	24.21	24.89	-94.98	431.38	-40.90	614.39	565.40	48.99	12.542	
7,050.00	7,027.31	7,055.64	7,028.31	24.35	25.05	-96.71	431.38	-40.90	617.38	568.09	49.29	12.524	
7,100.00	7,068.05	7,096.38	7,069.05	24.48	25.19	-98.41	431.38	-40.90	622.06	572.47	49.59	12.544	
7,150.00	7,106.11	7,134.45	7,107.11	24.62	25.33	-99.99	431.38	-40.90	628.84	578.96	49.87	12.609	
7,200.00	7,141.21	7,169.54	7,142.21	24.76	25.45	-101.32	431.38	-40.90	638.10	587.96	50.14	12.727	
7,250.00	7,173.06	7,201.39	7,174.06	24.90	25.56	-102.30	431.38	-40.90	650.17	599.78	50.38	12.905	
7,300.00	7,201.44	7,229.77	7,202.44	25.03	25.67	-102.84	431.38	-40.90	665.28	614.68	50.60	13.147	
7,350.00	7,226.12	7,254.46	7,227.12	25.17	25.75	-102.83	431.38	-40.90	683.59	632.78	50.80	13.456	
7,400.00	7,246.93	7,275.26	7,247.93	25.30	25.83	-102.19	431.38	-40.90	705.08	654.11	50.97	13.832	
7,450.00	7,263.69	7,292.02	7,264.69	25.43	25.89	-100.84	431.38	-40.90	729.68	678.57	51.12	14.275	
7,500.00	7,276.28	7,304.62	7,277.28	25.56	25.93	-98.70	431.38	-40.90	757.17	705.94	51.23	14.781	
7,550.00	7,284.61	7,312.95	7,285.61	25.68	25.96	-95.72	431.38	-40.90	787.24	735.94	51.31	15.344	
7,600.00	7,288.62	7,316.95	7,289.62	25.80	25.98	-91.87	431.38	-40.90	819.54	768.19	51.36	15.958	
7,620.93	7,289.00	7,317.33	7,290.00	25.85	25.98	-90.00	431.38	-40.90	833.63	782.26	51.37	16.228	
7,701.87	7,289.00	7,317.33	7,290.00	26.06	25.98	-90.00	431.38	-40.90	889.83	838.42	51.41	17.309	
7,800.00	7,289.00	7,317.33	7,290.00	26.35	25.98	-90.00	431.38	-40.90	961.82	910.36	51.45	18.693	
7,900.00	7,289.00	7,317.33	7,290.00	26.69	25.98	-90.00	431.38	-40.90	1,039.58	988.09	51.50	20.188	
8,000.00	7,289.00	7,317.33	7,290.00	27.08	25.98	-90.00	431.38	-40.90	1,120.88	1,069.35	51.53	21.750	
8,100.00	7,289.00	7,317.33	7,290.00	27.50	25.98	-90.00	431.38	-40.90	1,205.00	1,153.43	51.57	23.367	
12,100.00	7,289.00	13,649.33	8,839.00	61.19	64.31	-156.93	499.51	4,986.92	1,683.63	1,615.79	67.85	24.815	
12,200.00	7,289.00	13,749.33	8,839.00	62.22	65.29	-156.93	500.24	5,086.92	1,683.63	1,614.74	68.90	24.436	
12,300.00	7,289.00	13,849.33	8,839.00	63.24	66.27	-156.93	500.98	5,186.92	1,683.64	1,613.68	69.95	24.068	
12,400.00	7,289.00	13,949.33	8,839.00	64.27	67.26	-156.93	501.72	5,286.92	1,683.64	1,612.62	71.01	23.708	
12,500.00	7,289.00	14,049.33	8,839.00	65.31	68.25	-156.93	502.45	5,386.91	1,683.64	1,611.56	72.08	23.358	
12,600.00	7,289.00	14,149.33	8,839.00	66.34	69.25	-156.93	503.19	5,486.91	1,683.64	1,610.49	73.15	23.017	
12,700.00	7,289.00	14,249.33	8,839.00	67.38	70.25	-156.93	503.92	5,586.91	1,683.64	1,609.42	74.22	22.684	
12,800.00	7,289.00	14,349.33	8,839.00	68.42	71.26	-156.93	504.66	5,686.90	1,683.65	1,608.35	75.30	22.360	
12,900.00	7,289.00	14,449.33	8,839.00	69.47	72.26	-156.93	505.39	5,786.90	1,683.65	1,607.27	76.38	22.043	
13,000.00	7,289.00	14,549.33	8,839.00	70.51	73.28	-156.93	506.13	5,886.90	1,683.65	1,606.19	77.46	21.735	
13,100.00	7,289.00	14,649.33	8,839.00	71.56	74.29	-156.93	506.86	5,986.90	1,683.65	1,605.10	78.55	21.434	
13,200.00	7,289.00	14,749.33	8,839.00	72.61	75.31	-156.93	507.60	6,086.89	1,683.65	1,604.01	79.64	21.141	
13,300.00	7,289.00	14,849.33	8,839.00	73.67	76.33	-156.93	508.34	6,186.89	1,683.66	1,602.92	80.73	20.854	
13,400.00	7,289.00	14,949.33	8,839.00	74.72	77.35	-156.93	509.07	6,286.89	1,683.66	1,601.83	81.83	20.575	
13,500.00	7,289.00	15,049.33	8,839.00	75.78	78.38	-156.93	509.81	6,386.89	1,683.66	1,600.73	82.93	20.302	
13,600.00	7,289.00	15,149.33	8,839.00	76.84	79.41	-156.93	510.54	6,486.88	1,683.66	1,599.63	84.03	20.036	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A01) Koala 9 Fed Com 201H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
13,700.00	7,289.00	15,249.33	8,839.00	77.90	80.44	-156.93	511.28	6,586.88	1,683.66	1,598.53	85.14	19.776			
13,800.00	7,289.00	15,349.33	8,839.00	78.96	81.47	-156.93	512.01	6,686.88	1,683.67	1,597.42	86.24	19.522			
13,900.00	7,289.00	15,449.33	8,839.00	80.02	82.51	-156.93	512.75	6,786.87	1,683.67	1,596.31	87.35	19.274			
14,000.00	7,289.00	15,549.33	8,839.00	81.09	83.54	-156.93	513.48	6,886.87	1,683.67	1,595.20	88.47	19.032			
14,100.00	7,289.00	15,649.33	8,839.00	82.15	84.58	-156.93	514.22	6,986.87	1,683.67	1,594.09	89.58	18.795			
14,200.00	7,289.00	15,749.33	8,839.00	83.22	85.63	-156.93	514.96	7,086.87	1,683.67	1,592.98	90.70	18.564			
14,300.00	7,289.00	15,849.33	8,839.00	84.29	86.67	-156.93	515.69	7,186.86	1,683.67	1,591.86	91.82	18.337			
14,400.00	7,289.00	15,949.33	8,839.00	85.36	87.72	-156.93	516.43	7,286.86	1,683.68	1,590.74	92.94	18.116			
14,500.00	7,289.00	16,049.33	8,839.00	86.44	88.76	-156.93	517.16	7,386.86	1,683.68	1,589.62	94.06	17.900			
14,600.00	7,289.00	16,149.33	8,839.00	87.51	89.81	-156.93	517.90	7,486.86	1,683.68	1,588.50	95.18	17.689			
14,700.00	7,289.00	16,249.33	8,839.00	88.58	90.86	-156.93	518.63	7,586.85	1,683.68	1,587.37	96.31	17.482			
14,800.00	7,289.00	16,349.33	8,839.00	89.66	91.92	-156.93	519.37	7,686.85	1,683.68	1,586.25	97.44	17.279			
14,900.00	7,289.00	16,449.33	8,839.00	90.74	92.97	-156.93	520.11	7,786.85	1,683.69	1,585.12	98.57	17.081			
15,000.00	7,289.00	16,549.33	8,839.00	91.82	94.03	-156.93	520.84	7,886.84	1,683.69	1,583.99	99.70	16.887			
15,100.00	7,289.00	16,649.33	8,839.00	92.90	95.09	-156.93	521.58	7,986.84	1,683.69	1,582.86	100.83	16.698			
15,200.00	7,289.00	16,749.33	8,839.00	93.98	96.15	-156.93	522.31	8,086.84	1,683.69	1,581.72	101.97	16.512			
15,300.00	7,289.00	16,849.33	8,839.00	95.06	97.21	-156.93	523.05	8,186.84	1,683.69	1,580.59	103.10	16.330			
15,400.00	7,289.00	16,949.33	8,839.00	96.14	98.27	-156.93	523.78	8,286.83	1,683.70	1,579.45	104.24	16.152			
15,500.00	7,289.00	17,049.33	8,839.00	97.22	99.33	-156.93	524.52	8,386.83	1,683.70	1,578.32	105.38	15.977			
15,600.00	7,289.00	17,149.33	8,839.00	98.31	100.40	-156.93	525.25	8,486.83	1,683.70	1,577.18	106.52	15.806			
15,700.00	7,289.00	17,249.33	8,839.00	99.39	101.46	-156.93	525.99	8,586.83	1,683.70	1,576.04	107.66	15.639			
15,800.00	7,289.00	17,349.33	8,839.00	100.48	102.53	-156.93	526.73	8,686.82	1,683.70	1,574.90	108.81	15.474			
15,900.00	7,289.00	17,449.33	8,839.00	101.56	103.60	-156.93	527.46	8,786.82	1,683.71	1,573.76	109.95	15.313			
16,000.00	7,289.00	17,549.33	8,839.00	102.65	104.67	-156.93	528.20	8,886.82	1,683.71	1,572.61	111.09	15.156			
16,100.00	7,289.00	17,649.33	8,839.00	103.74	105.74	-156.92	528.93	8,986.82	1,683.71	1,571.47	112.24	15.001			
16,200.00	7,289.00	17,749.33	8,839.00	104.83	106.81	-156.92	529.67	9,086.81	1,683.71	1,570.32	113.39	14.849			
16,300.00	7,289.00	17,849.33	8,839.00	105.92	107.88	-156.92	530.40	9,186.81	1,683.71	1,569.18	114.54	14.700			
16,400.00	7,289.00	17,949.33	8,839.00	107.01	108.96	-156.92	531.14	9,286.81	1,683.72	1,568.03	115.69	14.554			
16,500.00	7,289.00	18,049.33	8,839.00	108.10	110.03	-156.92	531.87	9,386.80	1,683.72	1,566.88	116.84	14.411			
16,600.00	7,289.00	18,149.33	8,839.00	109.19	111.11	-156.92	532.61	9,486.80	1,683.72	1,565.73	117.99	14.270			
16,700.00	7,289.00	18,249.33	8,839.00	110.28	112.18	-156.92	533.35	9,586.80	1,683.72	1,564.58	119.14	14.132			
16,800.00	7,289.00	18,349.33	8,839.00	111.37	113.26	-156.92	534.08	9,686.80	1,683.72	1,563.43	120.30	13.997			
16,900.00	7,289.00	18,449.33	8,839.00	112.46	114.34	-156.92	534.82	9,786.79	1,683.72	1,562.27	121.45	13.863			
17,000.00	7,289.00	18,549.33	8,839.00	113.56	115.42	-156.92	535.55	9,886.79	1,683.73	1,561.12	122.61	13.733			
17,100.00	7,289.00	18,649.33	8,839.00	114.65	116.50	-156.92	536.29	9,986.79	1,683.73	1,559.97	123.76	13.605			
17,200.00	7,289.00	18,749.33	8,839.00	115.75	117.58	-156.92	537.02	10,086.79	1,683.73	1,558.81	124.92	13.479			
17,300.00	7,289.00	18,849.33	8,839.00	116.84	118.66	-156.92	537.76	10,186.78	1,683.73	1,557.66	126.08	13.355			
17,400.00	7,289.00	18,949.33	8,839.00	117.94	119.74	-156.92	538.49	10,286.78	1,683.73	1,556.50	127.24	13.233			
17,500.00	7,289.00	19,049.33	8,839.00	119.03	120.82	-156.92	539.23	10,386.78	1,683.74	1,555.34	128.40	13.114			
17,600.00	7,289.00	19,149.33	8,839.00	120.13	121.91	-156.92	539.97	10,486.77	1,683.74	1,554.18	129.56	12.996			
17,700.00	7,289.00	19,249.33	8,839.00	121.23	122.99	-156.92	540.70	10,586.77	1,683.74	1,553.02	130.72	12.881			
17,800.00	7,289.00	19,349.33	8,839.00	122.33	124.08	-156.92	541.44	10,686.77	1,683.74	1,551.86	131.88	12.767			
17,900.00	7,289.00	19,449.33	8,839.00	123.42	125.16	-156.92	542.17	10,786.77	1,683.74	1,550.70	133.04	12.656			
18,000.00	7,289.00	19,549.33	8,839.00	124.52	126.25	-156.92	542.91	10,886.76	1,683.75	1,549.54	134.20	12.546			
18,100.00	7,289.00	19,649.33	8,839.00	125.62	127.33	-156.92	543.64	10,986.76	1,683.75	1,548.38	135.37	12.438			
18,159.20	7,289.00	19,708.53	8,839.00	126.27	127.98	-156.92	544.08	11,045.95	1,683.75	1,547.69	136.06	12.375			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A02) Koala 9 Fed Com 202H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
600.00	600.00	601.00	601.00	1.92	1.92	-89.05	1.50	-89.99	90.00	86.16	3.84	23.443			
700.00	700.00	701.00	701.00	2.28	2.28	-89.05	1.50	-89.99	90.00	85.45	4.56	19.754			
800.00	800.00	801.00	801.00	2.63	2.64	-89.05	1.50	-89.99	90.00	84.73	5.27	17.068			
900.00	900.00	901.00	901.00	2.99	3.00	-89.05	1.50	-89.99	90.00	84.01	5.99	15.025			
1,000.00	1,000.00	1,001.00	1,001.00	3.35	3.36	-89.05	1.50	-89.99	90.00	83.30	6.71	13.419			
1,100.00	1,100.00	1,101.00	1,101.00	3.71	3.71	-89.05	1.50	-89.99	90.00	82.58	7.42	12.123			
1,200.00	1,200.00	1,201.00	1,201.00	4.07	4.07	-89.05	1.50	-89.99	90.00	81.86	8.14	11.056			
1,300.00	1,299.99	1,301.11	1,301.10	4.41	4.41	72.45	0.16	-89.95	89.54	80.72	8.82	10.150			
1,400.96	1,400.86	1,402.17	1,402.07	4.74	4.74	72.33	-3.85	-89.82	88.15	78.67	9.48	9.298			
1,500.00	1,499.77	1,501.27	1,500.95	5.07	5.07	71.30	-10.37	-89.61	86.29	76.16	10.14	8.514			
1,600.00	1,599.63	1,601.17	1,600.43	5.40	5.41	68.44	-19.54	-89.32	84.46	73.65	10.80	7.818			
1,700.00	1,699.49	1,700.78	1,699.35	5.74	5.74	63.70	-31.26	-88.95	83.08	71.60	11.48	7.239			
1,800.00	1,799.36	1,800.42	1,798.12	6.08	6.08	57.89	-44.35	-88.53	82.56	70.41	12.16	6.792			
1,809.99	1,809.34	1,810.37	1,807.99	6.12	6.11	57.31	-45.66	-88.49	82.56	70.33	12.22	6,754 CC			
1,900.00	1,899.22	1,900.06	1,896.90	6.43	6.42	52.07	-57.44	-88.11	82.91	70.07	12.84	6,457 ES			
2,000.00	1,999.08	1,999.70	1,995.68	6.77	6.77	46.36	-70.53	-87.70	84.10	70.58	13.52	6.218			
2,100.00	2,098.94	2,099.35	2,094.46	7.12	7.12	40.86	-83.62	-87.28	86.11	71.89	14.21	6,059			
2,200.00	2,198.80	2,198.99	2,193.24	7.47	7.47	35.65	-96.71	-86.86	88.87	73.97	14.90	5,964			
2,300.00	2,298.66	2,298.63	2,292.01	7.81	7.83	30.79	-109.80	-86.44	92.33	76.74	15.59	5,921			
2,400.00	2,398.53	2,398.28	2,390.79	8.17	8.18	26.32	-122.89	-86.03	96.40	80.12	16.28	5,920 SF			
2,500.00	2,498.39	2,497.92	2,489.57	8.52	8.54	22.22	-135.98	-85.61	101.01	84.04	16.98	5,950			
2,600.00	2,598.25	2,597.56	2,588.35	8.87	8.90	18.50	-149.07	-85.19	106.10	88.43	17.67	6,004			
2,700.00	2,698.11	2,697.21	2,687.13	9.22	9.26	15.13	-162.16	-84.78	111.59	93.22	18.37	6,076			
2,800.00	2,797.97	2,796.85	2,785.91	9.58	9.62	12.08	-175.25	-84.36	117.43	98.37	19.06	6,160			
2,900.00	2,897.83	2,896.50	2,884.69	9.93	9.98	9.33	-188.34	-83.94	123.57	103.81	19.76	6,253			
3,000.00	2,997.69	2,996.14	2,983.47	10.29	10.34	6.84	-201.44	-83.53	129.97	109.51	20.46	6,352			
3,100.00	3,097.56	3,095.78	3,082.25	10.64	10.71	4.59	-214.53	-83.11	136.59	115.43	21.16	6,455			
3,200.00	3,197.42	3,195.43	3,181.03	11.00	11.07	2.55	-227.62	-82.69	143.40	121.54	21.86	6,559			
3,300.00	3,297.28	3,295.07	3,279.81	11.35	11.43	0.70	-240.71	-82.27	150.37	127.81	22.57	6,664			
3,400.00	3,397.14	3,394.71	3,378.58	11.71	11.80	-0.99	-253.80	-81.86	157.49	134.22	23.27	6,768			
3,500.00	3,497.00	3,494.36	3,477.36	12.07	12.17	-2.53	-266.89	-81.44	164.74	140.76	23.97	6,871			
3,600.00	3,596.86	3,594.00	3,576.14	12.42	12.53	-3.94	-279.98	-81.02	172.09	147.41	24.68	6,973			
3,700.00	3,696.73	3,693.64	3,674.92	12.78	12.90	-5.23	-293.07	-80.61	179.53	154.15	25.39	7,072			
3,800.00	3,796.59	3,793.29	3,773.70	13.14	13.26	-6.42	-306.16	-80.19	187.06	160.97	26.09	7,169			
3,900.00	3,896.45	3,892.93	3,872.48	13.50	13.63	-7.52	-319.25	-79.77	194.67	167.87	26.80	7,263			
4,000.00	3,996.31	3,992.58	3,971.26	13.86	14.00	-8.54	-332.34	-79.36	202.34	174.83	27.51	7,355			
4,100.00	4,096.17	4,092.22	4,070.04	14.21	14.37	-9.48	-345.43	-78.94	210.07	181.85	28.22	7,444			
4,200.00	4,196.03	4,191.86	4,168.82	14.57	14.74	-10.35	-358.52	-78.52	217.85	188.92	28.93	7,531			
4,300.00	4,295.90	4,291.51	4,267.60	14.93	15.10	-11.16	-371.61	-78.10	225.68	196.04	29.64	7,614			
4,400.00	4,395.76	4,391.15	4,366.38	15.29	15.47	-11.92	-384.70	-77.69	233.55	203.20	30.35	7,696			
4,500.00	4,495.62	4,490.79	4,465.16	15.65	15.84	-12.63	-397.79	-77.27	241.46	210.40	31.06	7,774			
4,600.00	4,595.48	4,590.44	4,563.93	16.01	16.21	-13.30	-410.88	-76.85	249.40	217.63	31.77	7,850			
4,700.00	4,695.34	4,690.08	4,662.71	16.37	16.58	-13.92	-423.97	-76.44	257.38	224.89	32.48	7,924			
4,803.94	4,799.14	4,793.65	4,765.38	16.74	16.96	-14.53	-437.58	-76.00	265.70	232.47	33.22	7,998			
4,900.00	4,895.12	4,889.27	4,860.18	17.09	17.32	-15.03	-450.14	-75.60	274.57	240.66	33.91	8,098			
5,004.89	5,000.00	4,993.42	4,963.42	17.45	17.71	-176.94	-463.82	-75.17	286.93	252.28	34.64	8,283			
5,100.00	5,095.11	5,087.70	5,056.88	17.77	18.06	-177.15	-476.21	-74.77	299.38	264.09	35.30	8,482			
5,200.00	5,195.11	5,186.83	5,155.16	18.10	18.42	-177.34	-489.23	-74.36	312.49	276.50	35.99	8,683			
5,300.00	5,295.11	5,285.97	5,253.43	18.44	18.79	-177.52	-502.25	-73.94	325.59	288.91	36.68	8,876			
5,400.00	5,395.11	5,385.10	5,351.70	18.78	19.16	-177.69	-515.28	-73.53	338.70	301.33	37.37	9,062			
5,500.00	5,495.11	5,484.23	5,449.97	19.12	19.53	-177.85	-528.30	-73.11	351.81	313.74	38.07	9,242			
5,600.00	5,595.11	5,583.36	5,548.25	19.46	19.90	-177.99	-541.32	-72.70	364.93	326.16	38.76	9,414			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A02) Koala 9 Fed Com 202H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
5,700.00	5,695.11	5,682.50	5,646.52	19.80	20.27	-178.12	-554.34	-72.28	378.04	338.58	39.46	9.581			
5,800.00	5,795.11	5,781.63	5,744.79	20.14	20.63	-178.25	-567.37	-71.87	391.16	351.01	40.15	9.741			
5,900.00	5,895.11	5,880.76	5,843.06	20.48	21.00	-178.36	-580.39	-71.45	404.28	363.43	40.85	9.896			
6,000.00	5,995.11	5,979.89	5,941.34	20.82	21.37	-178.47	-593.41	-71.04	417.40	375.85	41.55	10.046			
6,100.00	6,095.11	6,079.03	6,039.61	21.16	21.74	-178.57	-606.44	-70.62	430.52	388.28	42.25	10.191			
6,200.00	6,195.11	6,178.16	6,137.88	21.51	22.11	-178.67	-619.46	-70.21	443.65	400.70	42.94	10.331			
6,300.00	6,295.11	6,277.29	6,236.15	21.85	22.48	-178.76	-632.48	-69.79	456.77	413.13	43.64	10.466			
6,400.00	6,395.11	6,376.42	6,334.43	22.19	22.85	-178.85	-645.51	-69.38	469.90	425.55	44.34	10.597			
6,500.00	6,495.11	6,475.56	6,432.70	22.54	23.22	-178.93	-658.53	-68.96	483.02	437.98	45.04	10.724			
6,600.00	6,595.11	6,574.69	6,530.97	22.88	23.59	-179.00	-671.55	-68.55	496.15	450.41	45.74	10.847			
6,700.00	6,695.11	6,673.82	6,629.24	23.23	23.96	-179.08	-684.58	-68.13	509.28	462.84	46.44	10.966			
6,720.93	6,716.04	6,694.57	6,649.82	23.30	24.04	-179.09	-687.30	-68.05	512.03	465.44	46.59	10.990			
6,750.00	6,745.09	6,723.38	6,678.37	23.40	24.14	89.39	-691.09	-67.93	515.84	469.05	46.79	11.024			
6,800.00	6,794.86	6,772.74	6,727.31	23.57	24.33	89.21	-697.57	-67.72	522.37	475.23	47.14	11.081			
6,850.00	6,844.02	6,821.54	6,775.68	23.74	24.51	89.48	-703.98	-67.52	528.93	481.45	47.48	11.139			
6,900.00	6,892.21	6,869.40	6,823.13	23.90	24.69	90.14	-710.27	-67.32	535.68	487.86	47.82	11.201			
6,950.00	6,939.05	6,915.96	6,869.29	24.06	24.86	91.10	-716.39	-67.12	542.85	494.69	48.16	11.273			
7,000.00	6,984.20	6,960.87	6,913.80	24.21	25.03	92.27	-722.29	-66.93	550.74	502.26	48.48	11.360			
7,050.00	7,027.31	7,003.78	6,956.34	24.35	25.19	93.56	-727.92	-66.75	559.71	510.92	48.80	11.470			
7,100.00	7,068.05	7,044.37	6,996.58	24.48	25.34	94.84	-733.25	-66.58	570.13	521.02	49.10	11.611			
7,150.00	7,106.11	7,082.32	7,034.20	24.62	25.48	96.01	-738.24	-66.42	582.35	532.95	49.40	11.788			
7,200.00	7,141.21	7,117.36	7,068.93	24.76	25.61	96.94	-742.84	-66.28	596.70	547.01	49.69	12.009			
7,250.00	7,173.06	7,149.21	7,100.51	24.90	25.73	97.53	-747.03	-66.15	613.46	563.50	49.96	12.279			
7,300.00	7,201.44	7,177.62	7,128.68	25.03	25.84	97.68	-750.76	-66.03	632.80	582.59	50.21	12.602			
7,350.00	7,226.12	7,202.40	7,153.23	25.17	25.93	97.30	-754.02	-65.92	654.82	604.37	50.45	12.980			
7,400.00	7,246.93	7,223.33	7,173.99	25.30	26.01	96.29	-756.77	-65.83	679.51	628.85	50.66	13.413			
7,450.00	7,263.69	7,240.28	7,190.78	25.43	26.07	94.58	-758.99	-65.76	706.75	655.91	50.85	13.900			
7,500.00	7,276.28	7,253.10	7,203.49	25.56	26.12	92.11	-760.68	-65.71	736.35	685.35	51.00	14.437			
7,550.00	7,284.61	7,261.70	7,212.02	25.68	26.15	88.84	-761.81	-65.67	768.04	716.91	51.13	15.021			
7,600.00	7,288.62	7,266.01	7,216.29	25.80	26.17	84.77	-762.37	-65.66	801.46	750.24	51.23	15.645			
7,620.93	7,289.00	7,266.53	7,216.81	25.85	26.17	82.84	-762.44	-65.65	815.89	764.63	51.26	15.917			
7,701.87	7,289.00	7,266.94	7,217.22	26.06	26.17	82.66	-762.49	-65.65	874.77	823.40	51.37	17.030			
7,800.00	7,289.00	7,267.26	7,217.54	26.35	26.17	82.70	-762.54	-65.65	951.36	899.88	51.48	18.480			
7,900.00	7,289.00	7,267.58	7,217.86	26.69	26.17	82.73	-762.58	-65.65	1,033.16	981.58	51.58	20.030			
8,000.00	7,289.00	7,267.91	7,218.18	27.08	26.17	82.76	-762.62	-65.65	1,117.93	1,066.26	51.67	21.638			
8,100.00	7,289.00	7,268.23	7,218.49	27.50	26.17	82.79	-762.66	-65.65	1,205.03	1,153.29	51.74	23.290			
8,200.00	7,289.00	7,268.55	7,218.81	27.96	26.18	82.83	-762.71	-65.65	1,294.00	1,242.20	51.80	24.978			
12,100.00	7,289.00	13,707.30	8,839.00	61.19	64.13	156.93	-819.93	4,996.57	1,683.65	1,615.83	67.82	24.826			
12,200.00	7,289.00	13,807.30	8,839.00	62.22	65.11	156.93	-819.20	5,096.57	1,683.65	1,614.75	68.91	24.434			
12,300.00	7,289.00	13,907.30	8,839.00	63.24	66.10	156.93	-818.47	5,196.56	1,683.66	1,613.66	70.00	24.053			
12,400.00	7,289.00	14,007.30	8,839.00	64.27	67.09	156.93	-817.75	5,296.56	1,683.66	1,612.56	71.09	23.682			
12,500.00	7,289.00	14,107.30	8,839.00	65.31	68.09	156.93	-817.02	5,396.56	1,683.66	1,611.47	72.19	23.321			
12,600.00	7,289.00	14,207.30	8,839.00	66.34	69.09	156.93	-816.30	5,496.56	1,683.66	1,610.36	73.30	22.970			
12,700.00	7,289.00	14,307.30	8,839.00	67.38	70.09	156.93	-815.57	5,596.55	1,683.66	1,609.26	74.41	22.628			
12,800.00	7,289.00	14,407.30	8,839.00	68.42	71.10	156.93	-814.84	5,696.55	1,683.66	1,608.15	75.52	22.295			
12,900.00	7,289.00	14,507.30	8,839.00	69.47	72.11	156.93	-814.12	5,796.55	1,683.67	1,607.03	76.63	21.970			
13,000.00	7,289.00	14,607.30	8,839.00	70.51	73.12	156.93	-813.39	5,896.55	1,683.67	1,605.92	77.75	21.654			
13,100.00	7,289.00	14,707.30	8,839.00	71.56	74.13	156.93	-812.66	5,996.54	1,683.67	1,604.80	78.87	21.346			
13,200.00	7,289.00	14,807.30	8,839.00	72.61	75.15	156.93	-811.94	6,096.54	1,683.67	1,603.67	80.00	21.046			
13,300.00	7,289.00	14,907.30	8,839.00	73.67	76.18	156.93	-811.21	6,196.54	1,683.67	1,602.55	81.13	20.754			
13,400.00	7,289.00	15,007.30	8,839.00	74.72	77.20	156.93	-810.48	6,296.53	1,683.67	1,601.42	82.26	20.468			
13,500.00	7,289.00	15,107.30	8,839.00	75.78	78.23	156.93	-809.76	6,396.53	1,683.68	1,600.28	83.39	20.190			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A02) Koala 9 Fed Com 202H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
13,600.00	7,289.00	15,207.30	8,839.00	76.84	79.26	156.93	-809.03	6,496.53	1,683.68	1,599.15	84.53	19.919			
13,700.00	7,289.00	15,307.30	8,839.00	77.90	80.29	156.93	-808.30	6,596.53	1,683.68	1,598.01	85.67	19.654			
13,800.00	7,289.00	15,407.30	8,839.00	78.96	81.33	156.93	-807.58	6,696.52	1,683.68	1,596.87	86.81	19.396			
13,900.00	7,289.00	15,507.30	8,839.00	80.02	82.36	156.93	-806.85	6,796.52	1,683.68	1,595.73	87.95	19.144			
14,000.00	7,289.00	15,607.30	8,839.00	81.09	83.40	156.93	-806.12	6,896.52	1,683.68	1,594.59	89.10	18.897			
14,100.00	7,289.00	15,707.30	8,839.00	82.15	84.45	156.93	-805.40	6,996.52	1,683.69	1,593.44	90.24	18.657			
14,200.00	7,289.00	15,807.30	8,839.00	83.22	85.49	156.93	-804.67	7,096.51	1,683.69	1,592.29	91.39	18.422			
14,300.00	7,289.00	15,907.30	8,839.00	84.29	86.54	156.93	-803.95	7,196.51	1,683.69	1,591.14	92.55	18.193			
14,400.00	7,289.00	16,007.30	8,839.00	85.36	87.58	156.93	-803.22	7,296.51	1,683.69	1,589.99	93.70	17.969			
14,500.00	7,289.00	16,107.30	8,839.00	86.44	88.63	156.93	-802.49	7,396.51	1,683.69	1,588.84	94.85	17.750			
14,600.00	7,289.00	16,207.30	8,839.00	87.51	89.68	156.93	-801.77	7,496.50	1,683.69	1,587.68	96.01	17.536			
14,700.00	7,289.00	16,307.30	8,839.00	88.58	90.74	156.93	-801.04	7,596.50	1,683.70	1,586.52	97.17	17.327			
14,800.00	7,289.00	16,407.30	8,839.00	89.66	91.79	156.93	-800.31	7,696.50	1,683.70	1,585.37	98.33	17.123			
14,900.00	7,289.00	16,507.30	8,839.00	90.74	92.85	156.93	-799.59	7,796.50	1,683.70	1,584.20	99.49	16.923			
15,000.00	7,289.00	16,607.30	8,839.00	91.82	93.90	156.93	-798.86	7,896.49	1,683.70	1,583.04	100.66	16.727			
15,100.00	7,289.00	16,707.30	8,839.00	92.90	94.96	156.93	-798.13	7,996.49	1,683.70	1,581.88	101.82	16.535			
15,200.00	7,289.00	16,807.30	8,839.00	93.98	96.02	156.93	-797.41	8,096.49	1,683.70	1,580.71	102.99	16.348			
15,300.00	7,289.00	16,907.30	8,839.00	95.06	97.09	156.93	-796.68	8,196.48	1,683.71	1,579.55	104.16	16.165			
15,400.00	7,289.00	17,007.30	8,839.00	96.14	98.15	156.93	-795.95	8,296.48	1,683.71	1,578.38	105.33	15.985			
15,500.00	7,289.00	17,107.30	8,839.00	97.22	99.21	156.93	-795.23	8,396.48	1,683.71	1,577.21	106.50	15.810			
15,600.00	7,289.00	17,207.30	8,839.00	98.31	100.28	156.92	-794.50	8,496.48	1,683.71	1,576.04	107.67	15.638			
15,700.00	7,289.00	17,307.30	8,839.00	99.39	101.35	156.92	-793.78	8,596.47	1,683.71	1,574.87	108.84	15.469			
15,800.00	7,289.00	17,407.30	8,839.00	100.48	102.41	156.92	-793.05	8,696.47	1,683.71	1,573.69	110.02	15.304			
15,900.00	7,289.00	17,507.30	8,839.00	101.56	103.48	156.92	-792.32	8,796.47	1,683.72	1,572.52	111.19	15.142			
16,000.00	7,289.00	17,607.30	8,839.00	102.65	104.55	156.92	-791.60	8,896.47	1,683.72	1,571.35	112.37	14.983			
16,100.00	7,289.00	17,707.30	8,839.00	103.74	105.63	156.92	-790.87	8,996.46	1,683.72	1,570.17	113.55	14.828			
16,200.00	7,289.00	17,807.30	8,839.00	104.83	106.70	156.92	-790.14	9,096.46	1,683.72	1,568.99	114.73	14.676			
16,300.00	7,289.00	17,907.30	8,839.00	105.92	107.77	156.92	-789.42	9,196.46	1,683.72	1,567.81	115.91	14.526			
16,400.00	7,289.00	18,007.30	8,839.00	107.01	108.85	156.92	-788.69	9,296.46	1,683.72	1,566.63	117.09	14.380			
16,500.00	7,289.00	18,107.30	8,839.00	108.10	109.92	156.92	-787.96	9,396.45	1,683.73	1,565.45	118.27	14.236			
16,600.00	7,289.00	18,207.30	8,839.00	109.19	111.00	156.92	-787.24	9,496.45	1,683.73	1,564.27	119.45	14.095			
16,700.00	7,289.00	18,307.30	8,839.00	110.28	112.08	156.92	-786.51	9,596.45	1,683.73	1,563.09	120.64	13.957			
16,800.00	7,289.00	18,407.30	8,839.00	111.37	113.15	156.92	-785.78	9,696.44	1,683.73	1,561.91	121.82	13.821			
16,900.00	7,289.00	18,507.30	8,839.00	112.46	114.23	156.92	-785.06	9,796.44	1,683.73	1,560.72	123.01	13.688			
17,000.00	7,289.00	18,607.30	8,839.00	113.56	115.31	156.92	-784.33	9,896.44	1,683.73	1,559.54	124.19	13.557			
17,100.00	7,289.00	18,707.30	8,839.00	114.65	116.39	156.92	-783.61	9,996.44	1,683.74	1,558.36	125.38	13.429			
17,200.00	7,289.00	18,807.30	8,839.00	115.75	117.48	156.92	-782.88	10,096.43	1,683.74	1,557.17	126.57	13.303			
17,300.00	7,289.00	18,907.30	8,839.00	116.84	118.56	156.92	-782.15	10,196.43	1,683.74	1,555.98	127.76	13.179			
17,400.00	7,289.00	19,007.30	8,839.00	117.94	119.64	156.92	-781.43	10,296.43	1,683.74	1,554.79	128.95	13.058			
17,500.00	7,289.00	19,107.30	8,839.00	119.03	120.72	156.92	-780.70	10,396.43	1,683.74	1,553.61	130.14	12.938			
17,600.00	7,289.00	19,207.30	8,839.00	120.13	121.81	156.92	-779.97	10,496.42	1,683.74	1,552.42	131.33	12.821			
17,700.00	7,289.00	19,307.30	8,839.00	121.23	122.89	156.92	-779.25	10,596.42	1,683.75	1,551.23	132.52	12.706			
17,800.00	7,289.00	19,407.30	8,839.00	122.33	123.98	156.92	-778.52	10,696.42	1,683.75	1,550.04	133.71	12.592			
17,900.00	7,289.00	19,507.30	8,839.00	123.42	125.07	156.92	-777.79	10,796.42	1,683.75	1,548.85	134.90	12.481			
18,000.00	7,289.00	19,607.30	8,839.00	124.52	126.15	156.92	-777.07	10,896.41	1,683.75	1,547.65	136.10	12.372			
18,100.00	7,289.00	19,707.30	8,839.00	125.62	127.24	156.92	-776.34	10,996.41	1,683.75	1,546.46	137.29	12.264			
18,100.62	7,289.00	19,707.93	8,839.00	125.63	127.25	156.92	-776.34	10,997.03	1,683.75	1,546.45	137.30	12.264			
18,159.20	7,289.00	19,752.88	8,839.00	126.27	127.74	156.92	-776.01	11,041.99	1,683.81	1,545.91	137.90	12.210			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A03) Koala 9 Fed Com 131H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
400.00	400.00	400.00	400.00	1.20	1.20	-89.05	1.00	-59.99	60.00	57.60	2.40	24.981			
500.00	500.00	500.00	500.00	1.56	1.56	-89.05	1.00	-59.99	60.00	56.88	3.12	19.238			
600.00	600.00	600.00	600.00	1.92	1.92	-89.05	1.00	-59.99	60.00	56.16	3.84	15.642			
700.00	700.00	700.00	700.00	2.28	2.28	-89.05	1.00	-59.99	60.00	55.45	4.55	13.179			
800.00	800.00	800.00	800.00	2.63	2.63	-89.05	1.00	-59.99	60.00	54.73	5.27	11.386			
900.00	900.00	900.00	900.00	2.99	2.99	-89.05	1.00	-59.99	60.00	54.01	5.99	10.022			
1,000.00	1,000.00	1,000.00	1,000.00	3.35	3.35	-89.05	1.00	-59.99	60.00	53.29	6.70	8.950			
1,100.00	1,100.00	1,100.00	1,100.00	3.71	3.71	-89.05	1.00	-59.99	60.00	52.58	7.42	8.086			
1,200.00	1,200.00	1,200.00	1,200.00	4.07	4.07	-89.05	1.00	-59.99	60.00	51.86	8.14	7.373			
1,300.00	1,299.99	1,299.99	1,299.99	4.41	4.43	73.70	1.00	-59.99	59.62	50.78	8.84	6.747			
1,400.96	1,400.86	1,400.86	1,400.86	4.74	4.79	77.45	1.00	-59.99	58.63	49.10	9.53	6.153			
1,500.00	1,499.77	1,499.77	1,499.77	5.07	5.14	82.49	1.00	-59.99	57.72	47.51	10.21	5.653			
1,600.00	1,599.63	1,599.63	1,599.63	5.40	5.50	87.71	1.00	-59.99	57.27	46.36	10.90	5.252			
1,643.59	1,643.16	1,643.16	1,643.16	5.55	5.66	90.00	1.00	-59.99	57.22	46.01	11.21	5,106 CC			
1,700.00	1,699.49	1,699.49	1,699.49	5.74	5.86	92.96	1.00	-59.99	57.30	45.70	11.60	4.940			
1,800.00	1,799.36	1,799.36	1,799.36	6.08	6.22	98.17	1.00	-59.99	57.81	45.51	12.30	4.700			
1,900.00	1,899.22	1,899.22	1,899.22	6.43	6.58	103.24	1.00	-59.99	58.79	45.79	13.00	4.522			
2,000.00	1,999.08	1,999.08	1,999.08	6.77	6.93	108.11	1.00	-59.99	60.21	46.51	13.70	4.394			
2,100.00	2,098.94	2,098.94	2,098.94	7.12	7.29	112.73	1.00	-59.99	62.05	47.64	14.41	4.307			
2,200.00	2,198.80	2,198.80	2,198.80	7.47	7.65	117.05	1.00	-59.99	64.27	49.15	15.11	4.252			
2,300.00	2,298.66	2,298.66	2,298.66	7.81	8.01	121.07	1.00	-59.99	66.83	51.01	15.82	4.224			
2,400.00	2,398.53	2,398.53	2,398.53	8.17	8.37	124.77	1.00	-59.99	69.69	53.16	16.53	4.216			
2,500.00	2,498.39	2,498.39	2,498.39	8.52	8.72	128.17	1.00	-59.99	72.82	55.58	17.24	4.225			
2,600.00	2,598.25	2,600.09	2,600.08	8.87	9.07	130.98	-0.29	-59.77	74.98	57.05	17.93	4.182			
2,700.00	2,698.11	2,701.94	2,701.85	9.22	9.40	132.97	-4.26	-59.10	74.78	56.18	18.60	4.020			
2,800.00	2,797.97	2,802.06	2,801.81	9.58	9.73	134.59	-9.68	-58.18	73.20	53.93	19.28	3.797			
2,900.00	2,897.83	2,902.02	2,901.63	9.93	10.05	136.27	-15.09	-57.27	71.68	51.72	19.96	3.591			
3,000.00	2,997.69	3,001.99	3,001.44	10.29	10.38	138.03	-20.51	-56.35	70.22	49.58	20.64	3.402			
3,100.00	3,097.56	3,101.95	3,101.25	10.64	10.72	139.85	-25.93	-55.44	68.83	47.50	21.33	3.227			
3,200.00	3,197.42	3,201.92	3,201.07	11.00	11.05	141.75	-31.34	-54.52	67.51	45.50	22.01	3.067			
3,300.00	3,297.28	3,301.88	3,300.88	11.35	11.39	143.72	-36.76	-53.60	66.27	43.57	22.70	2.919			
3,400.00	3,397.14	3,401.85	3,400.70	11.71	11.72	145.77	-42.18	-52.69	65.11	41.72	23.39	2.783			
3,500.00	3,497.00	3,501.82	3,500.51	12.07	12.06	147.89	-47.59	-51.77	64.04	39.95	24.09	2.659			
3,600.00	3,596.86	3,601.78	3,600.33	12.42	12.40	150.07	-53.01	-50.85	63.06	38.28	24.78	2.545			
3,700.00	3,696.73	3,701.75	3,700.14	12.78	12.74	152.33	-58.43	-49.94	62.17	36.69	25.47	2.441			
3,800.00	3,796.59	3,801.56	3,799.80	13.14	13.08	154.64	-63.82	-49.03	61.39	35.22	26.17	2.346			
3,818.13	3,814.69	3,819.39	3,817.62	13.20	13.14	155.05	-64.70	-48.88	61.35	35.05	26.30	2,333 ES			
3,900.00	3,896.45	3,900.00	3,898.17	13.50	13.42	156.85	-67.66	-48.38	62.24	35.37	26.87	2,316 SF			
4,000.00	3,996.31	3,998.22	3,996.37	13.86	13.76	158.72	-69.00	-48.15	65.74	38.18	27.56	2.385			
4,100.00	4,096.17	4,098.02	4,096.17	14.21	14.12	160.27	-69.00	-48.15	70.66	42.39	28.27	2.500			
4,200.00	4,196.03	4,197.88	4,196.03	14.57	14.47	161.61	-69.00	-48.15	75.63	46.66	28.97	2.610			
4,300.00	4,295.90	4,297.74	4,295.90	14.93	14.82	162.79	-69.00	-48.15	80.64	50.96	29.68	2.717			
4,400.00	4,395.76	4,397.60	4,395.76	15.29	15.18	163.83	-69.00	-48.15	85.68	55.28	30.39	2.819			
4,500.00	4,495.62	4,497.47	4,495.62	15.65	15.53	164.76	-69.00	-48.15	90.74	59.64	31.10	2.917			
4,600.00	4,595.48	4,597.33	4,595.48	16.01	15.88	165.58	-69.00	-48.15	95.82	64.01	31.81	3.012			
4,700.00	4,695.34	4,697.19	4,695.34	16.37	16.24	166.33	-69.00	-48.15	100.93	68.40	32.52	3.103			
4,803.94	4,799.14	4,800.98	4,799.14	16.74	16.61	167.02	-69.00	-48.15	106.25	72.98	33.26	3.194			
4,900.00	4,895.12	4,896.97	4,895.12	17.09	16.95	167.48	-69.00	-48.15	110.00	76.05	33.94	3.241			
5,004.89	5,000.00	5,001.85	5,000.00	17.45	17.32	6.11	-69.00	-48.15	111.40	76.72	34.68	3.212			
5,100.00	5,095.11	5,096.95	5,095.11	17.77	17.66	6.11	-69.00	-48.15	111.40	76.06	35.34	3.152			
5,200.00	5,195.11	5,196.95	5,195.11	18.10	18.01	6.11	-69.00	-48.15	111.40	75.37	36.03	3.092			
5,300.00	5,295.11	5,296.95	5,295.11	18.44	18.37	6.11	-69.00	-48.15	111.40	74.67	36.73	3.033			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A03) Koala 9 Fed Com 131H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
5,400.00	5,395.11	5,396.95	5,395.11	18.78	18.72	6.11	-69.00	-48.15	111.40	73.98	37.42	2.977			
5,500.00	5,495.11	5,496.95	5,495.11	19.12	19.08	6.11	-69.00	-48.15	111.40	73.28	38.12	2.922			
5,600.00	5,595.11	5,596.95	5,595.11	19.46	19.44	6.11	-69.00	-48.15	111.40	72.58	38.82	2.870			
5,700.00	5,695.11	5,696.95	5,695.11	19.80	19.79	6.11	-69.00	-48.15	111.40	71.89	39.52	2.819			
5,800.00	5,795.11	5,796.95	5,795.11	20.14	20.15	6.11	-69.00	-48.15	111.40	71.19	40.22	2.770			
5,900.00	5,895.11	5,896.95	5,895.11	20.48	20.50	6.11	-69.00	-48.15	111.40	70.49	40.91	2.723			
6,000.00	5,995.11	5,996.95	5,995.11	20.82	20.86	6.11	-69.00	-48.15	111.40	69.79	41.61	2.677			
6,100.00	6,095.11	6,096.95	6,095.11	21.16	21.22	6.11	-69.00	-48.15	111.40	69.09	42.31	2.633			
6,200.00	6,195.11	6,196.95	6,195.11	21.51	21.57	6.11	-69.00	-48.15	111.40	68.39	43.02	2.590			
6,300.00	6,295.11	6,296.95	6,295.11	21.85	21.93	6.11	-69.00	-48.15	111.40	67.68	43.72	2.548			
6,400.00	6,395.11	6,396.95	6,395.11	22.19	22.29	6.11	-69.00	-48.15	111.40	66.98	44.42	2.508			
6,500.00	6,495.11	6,496.95	6,495.11	22.54	22.64	6.11	-69.00	-48.15	111.40	66.28	45.12	2.469			
6,600.00	6,595.11	6,596.95	6,595.11	22.88	23.00	6.11	-69.00	-48.15	111.40	65.58	45.83	2.431			
6,700.00	6,695.11	6,696.95	6,695.11	23.23	23.36	6.11	-69.00	-48.15	111.40	64.87	46.53	2.394			
6,720.93	6,716.04	6,717.89	6,716.04	23.30	23.43	6.11	-69.00	-48.15	111.40	64.73	46.68	2.387			
6,750.00	6,745.09	6,746.94	6,745.09	23.40	23.53	-85.48	-69.00	-48.15	111.34	64.46	46.88	2.375			
6,800.00	6,794.86	6,796.70	6,794.86	23.57	23.71	-87.91	-69.00	-48.15	111.07	63.84	47.23	2.352			
6,825.55	6,820.08	6,821.92	6,820.08	23.66	23.80	-90.00	-69.00	-48.15	110.99	63.59	47.41	2.341			
6,850.00	6,844.02	6,845.86	6,844.02	23.74	23.89	-92.49	-69.00	-48.15	111.10	63.53	47.58	2.335			
6,900.00	6,892.21	6,894.05	6,892.21	23.90	24.06	-98.88	-69.00	-48.15	112.48	64.56	47.92	2.347			
6,950.00	6,939.05	6,940.90	6,939.05	24.06	24.23	-106.48	-69.00	-48.15	116.58	68.33	48.25	2.416			
7,000.00	6,984.20	6,986.05	6,984.20	24.21	24.39	-114.45	-69.00	-48.15	124.82	76.25	48.57	2.570			
7,050.00	7,027.31	7,029.16	7,027.31	24.35	24.54	-121.93	-69.00	-48.15	138.24	89.36	48.88	2.828			
7,100.00	7,068.05	7,069.90	7,068.05	24.48	24.69	-128.37	-69.00	-48.15	157.23	108.07	49.16	3.198			
7,150.00	7,106.11	7,107.96	7,106.11	24.62	24.82	-133.49	-69.00	-48.15	181.62	132.21	49.41	3.676			
7,200.00	7,141.21	7,143.05	7,141.21	24.76	24.95	-137.29	-69.00	-48.15	210.92	161.28	49.64	4.249			
7,250.00	7,173.06	7,174.91	7,173.06	24.90	25.06	-139.81	-69.00	-48.15	244.51	194.67	49.84	4.906			
7,300.00	7,201.44	7,203.29	7,201.44	25.03	25.16	-141.11	-69.00	-48.15	281.80	231.79	50.01	5.635			
7,350.00	7,226.12	7,227.97	7,226.12	25.17	25.25	-141.14	-69.00	-48.15	322.20	272.05	50.15	6.424			
7,400.00	7,246.93	7,248.77	7,246.93	25.30	25.33	-139.70	-69.00	-48.15	365.21	314.94	50.27	7.265			
7,450.00	7,263.69	7,265.54	7,263.69	25.43	25.39	-136.29	-69.00	-48.15	410.32	359.96	50.36	8.148			
7,500.00	7,276.28	7,278.13	7,276.28	25.56	25.43	-129.93	-69.00	-48.15	457.07	406.65	50.42	9.065			
7,550.00	7,284.61	7,286.46	7,284.61	25.68	25.46	-118.73	-69.00	-48.15	505.03	454.56	50.46	10.008			
7,600.00	7,288.62	7,290.46	7,288.62	25.80	25.47	-100.12	-69.00	-48.15	553.74	503.26	50.48	10.969			
7,620.93	7,289.00	7,290.84	7,289.00	25.85	25.48	-90.00	-69.00	-48.15	574.26	523.77	50.49	11.375			
7,701.87	7,289.00	7,290.84	7,289.00	26.06	25.48	-90.00	-69.00	-48.15	653.65	603.16	50.49	12.947			
7,800.00	7,289.00	7,290.84	7,289.00	26.35	25.48	-90.00	-69.00	-48.15	750.13	699.64	50.49	14.856			
7,900.00	7,289.00	7,290.84	7,289.00	26.69	25.48	-90.00	-69.00	-48.15	848.83	798.33	50.50	16.809			
8,000.00	7,289.00	7,290.84	7,289.00	27.08	25.48	-90.00	-69.00	-48.15	947.81	897.30	50.51	18.766			
8,100.00	7,289.00	7,290.84	7,289.00	27.50	25.48	-90.00	-69.00	-48.15	1,046.98	996.46	50.52	20.725			
8,200.00	7,289.00	7,290.84	7,289.00	27.96	25.48	-90.00	-69.00	-48.15	1,146.30	1,095.77	50.53	22.686			
11,700.00	7,289.00	12,896.76	8,494.00	57.13	59.37	179.99	-163.33	4,591.79	1,205.00	1,156.21	48.79	24.700			
11,800.00	7,289.00	12,996.76	8,494.00	58.14	60.34	179.99	-162.60	4,691.79	1,205.00	1,155.44	49.56	24.315			
11,900.00	7,289.00	13,096.76	8,494.00	59.16	61.32	179.99	-161.86	4,791.78	1,205.00	1,154.67	50.33	23.940			
12,000.00	7,289.00	13,196.76	8,494.00	60.17	62.30	179.99	-161.13	4,891.78	1,205.00	1,153.89	51.11	23.575			
12,100.00	7,289.00	13,296.76	8,494.00	61.19	63.29	179.99	-160.40	4,991.78	1,205.00	1,153.10	51.90	23.219			
12,200.00	7,289.00	13,396.76	8,494.00	62.22	64.28	179.99	-159.66	5,091.77	1,205.00	1,152.31	52.69	22.871			
12,300.00	7,289.00	13,496.76	8,494.00	63.24	65.27	179.99	-158.93	5,191.77	1,205.00	1,151.52	53.48	22.532			
12,400.00	7,289.00	13,596.76	8,494.00	64.27	66.27	179.99	-158.19	5,291.77	1,205.00	1,150.72	54.27	22.202			
12,500.00	7,289.00	13,696.76	8,494.00	65.31	67.28	179.99	-157.46	5,391.77	1,205.00	1,149.93	55.07	21.880			
12,600.00	7,289.00	13,796.76	8,494.00	66.34	68.28	179.99	-156.73	5,491.76	1,205.00	1,149.12	55.88	21.566			
12,700.00	7,289.00	13,896.76	8,494.00	67.38	69.30	179.99	-155.99	5,591.76	1,205.00	1,148.32	56.68	21.259			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A03) Koala 9 Fed Com 131H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
12,800.00	7,289.00	13,996.76	8,494.00	68.42	70.31	179.99	-155.26	5,691.76	1,205.00	1,147.51	57.49	20.960	
12,900.00	7,289.00	14,096.76	8,494.00	69.47	71.33	179.99	-154.52	5,791.76	1,205.00	1,146.70	58.30	20.668	
13,000.00	7,289.00	14,196.76	8,494.00	70.51	72.35	179.99	-153.79	5,891.75	1,205.00	1,145.88	59.12	20.383	
13,100.00	7,289.00	14,296.76	8,494.00	71.56	73.37	179.99	-153.05	5,991.75	1,205.00	1,145.07	59.93	20.105	
13,200.00	7,289.00	14,396.76	8,494.00	72.61	74.40	179.99	-152.32	6,091.75	1,205.00	1,144.25	60.75	19.834	
13,300.00	7,289.00	14,496.76	8,494.00	73.67	75.43	179.99	-151.59	6,191.75	1,205.00	1,143.42	61.58	19.569	
13,400.00	7,289.00	14,596.76	8,494.00	74.72	76.46	179.99	-150.85	6,291.74	1,205.00	1,142.60	62.40	19.311	
13,500.00	7,289.00	14,696.76	8,494.00	75.78	77.49	179.99	-150.12	6,391.74	1,205.00	1,141.77	63.23	19.058	
13,600.00	7,289.00	14,796.76	8,494.00	76.84	78.53	179.99	-149.38	6,491.74	1,205.00	1,140.94	64.06	18.811	
13,700.00	7,289.00	14,896.76	8,494.00	77.90	79.57	179.99	-148.65	6,591.73	1,205.00	1,140.11	64.89	18.570	
13,800.00	7,289.00	14,996.76	8,494.00	78.96	80.61	179.99	-147.92	6,691.73	1,205.00	1,139.28	65.72	18.335	
13,900.00	7,289.00	15,096.76	8,494.00	80.02	81.65	179.99	-147.18	6,791.73	1,205.00	1,138.44	66.56	18.105	
14,000.00	7,289.00	15,196.76	8,494.00	81.09	82.70	179.99	-146.45	6,891.73	1,205.00	1,137.61	67.39	17.880	
14,100.00	7,289.00	15,296.76	8,494.00	82.15	83.75	179.99	-145.71	6,991.72	1,205.00	1,136.77	68.23	17.660	
14,200.00	7,289.00	15,396.76	8,494.00	83.22	84.80	179.99	-144.98	7,091.72	1,205.00	1,135.93	69.07	17.445	
14,300.00	7,289.00	15,496.76	8,494.00	84.29	85.85	179.99	-144.24	7,191.72	1,205.00	1,135.08	69.92	17.235	
14,400.00	7,289.00	15,596.76	8,494.00	85.36	86.90	179.99	-143.51	7,291.72	1,205.00	1,134.24	70.76	17.029	
14,500.00	7,289.00	15,696.76	8,494.00	86.44	87.96	179.99	-142.78	7,391.71	1,205.00	1,133.39	71.61	16.828	
14,600.00	7,289.00	15,796.76	8,494.00	87.51	89.01	179.99	-142.04	7,491.71	1,205.00	1,132.55	72.45	16.631	
14,700.00	7,289.00	15,896.76	8,494.00	88.58	90.07	179.99	-141.31	7,591.71	1,205.00	1,131.70	73.30	16.439	
14,800.00	7,289.00	15,996.76	8,494.00	89.66	91.13	179.99	-140.57	7,691.70	1,205.00	1,130.85	74.15	16.250	
14,900.00	7,289.00	16,096.76	8,494.00	90.74	92.19	179.99	-139.84	7,791.70	1,205.00	1,130.00	75.00	16.066	
15,000.00	7,289.00	16,196.76	8,494.00	91.82	93.25	179.99	-139.10	7,891.70	1,205.00	1,129.14	75.86	15.885	
15,100.00	7,289.00	16,296.76	8,494.00	92.90	94.32	179.99	-138.37	7,991.70	1,205.00	1,128.29	76.71	15.708	
15,200.00	7,289.00	16,396.76	8,494.00	93.98	95.38	180.00	-137.64	8,091.69	1,205.00	1,127.43	77.57	15.535	
15,300.00	7,289.00	16,496.76	8,494.00	95.06	96.45	180.00	-136.90	8,191.69	1,205.00	1,126.58	78.42	15.366	
15,400.00	7,289.00	16,596.76	8,494.00	96.14	97.52	180.00	-136.17	8,291.69	1,205.00	1,125.72	79.28	15.199	
15,500.00	7,289.00	16,696.76	8,494.00	97.22	98.58	180.00	-135.43	8,391.69	1,205.00	1,124.86	80.14	15.036	
15,600.00	7,289.00	16,796.76	8,494.00	98.31	99.65	180.00	-134.70	8,491.68	1,205.00	1,124.00	81.00	14.877	
15,700.00	7,289.00	16,896.76	8,494.00	99.39	100.73	180.00	-133.97	8,591.68	1,205.00	1,123.14	81.86	14.720	
15,800.00	7,289.00	16,996.76	8,494.00	100.48	101.80	180.00	-133.23	8,691.68	1,205.00	1,122.28	82.72	14.567	
15,900.00	7,289.00	17,096.76	8,494.00	101.56	102.87	180.00	-132.50	8,791.68	1,205.00	1,121.42	83.58	14.417	
16,000.00	7,289.00	17,196.76	8,494.00	102.65	103.95	180.00	-131.76	8,891.67	1,205.00	1,120.55	84.45	14.269	
16,100.00	7,289.00	17,296.76	8,494.00	103.74	105.02	180.00	-131.03	8,991.67	1,205.00	1,119.69	85.31	14.124	
16,200.00	7,289.00	17,396.76	8,494.00	104.83	106.10	180.00	-130.29	9,091.67	1,205.00	1,118.82	86.18	13.983	
16,300.00	7,289.00	17,496.76	8,494.00	105.92	107.17	180.00	-129.56	9,191.66	1,205.00	1,117.95	87.05	13.843	
16,400.00	7,289.00	17,596.76	8,494.00	107.01	108.25	180.00	-128.83	9,291.66	1,205.00	1,117.09	87.91	13.707	
16,500.00	7,289.00	17,696.76	8,494.00	108.10	109.33	180.00	-128.09	9,391.66	1,205.00	1,116.22	88.78	13.573	
16,600.00	7,289.00	17,796.76	8,494.00	109.19	110.41	180.00	-127.36	9,491.66	1,205.00	1,115.35	89.65	13.441	
16,700.00	7,289.00	17,896.76	8,494.00	110.28	111.49	180.00	-126.62	9,591.65	1,205.00	1,114.48	90.52	13.312	
16,800.00	7,289.00	17,996.76	8,494.00	111.37	112.57	180.00	-125.89	9,691.65	1,205.00	1,113.61	91.39	13.185	
16,900.00	7,289.00	18,096.76	8,494.00	112.46	113.66	180.00	-125.15	9,791.65	1,205.00	1,112.74	92.26	13.061	
17,000.00	7,289.00	18,196.76	8,494.00	113.56	114.74	180.00	-124.42	9,891.65	1,205.00	1,111.87	93.13	12.938	
17,100.00	7,289.00	18,296.76	8,494.00	114.65	115.82	180.00	-123.69	9,991.64	1,205.00	1,110.99	94.01	12.818	
17,200.00	7,289.00	18,396.76	8,494.00	115.75	116.91	180.00	-122.95	10,091.64	1,205.00	1,110.12	94.88	12.700	
17,300.00	7,289.00	18,496.76	8,494.00	116.84	117.99	180.00	-122.22	10,191.64	1,205.00	1,109.25	95.75	12.584	
17,400.00	7,289.00	18,596.76	8,494.00	117.94	119.08	180.00	-121.48	10,291.63	1,205.00	1,108.37	96.63	12.470	
17,500.00	7,289.00	18,696.76	8,494.00	119.03	120.17	180.00	-120.75	10,391.63	1,205.00	1,107.50	97.50	12.358	
17,600.00	7,289.00	18,796.76	8,494.00	120.13	121.25	180.00	-120.02	10,491.63	1,205.00	1,106.62	98.38	12.248	
17,700.00	7,289.00	18,896.76	8,494.00	121.23	122.34	180.00	-119.28	10,591.63	1,205.00	1,105.74	99.26	12.140	
17,800.00	7,289.00	18,996.76	8,494.00	122.33	123.43	180.00	-118.55	10,691.62	1,205.00	1,104.87	100.13	12.034	
17,900.00	7,289.00	19,096.76	8,494.00	123.42	124.52	180.00	-117.81	10,791.62	1,205.00	1,103.99	101.01	11.929	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A03) Koala 9 Fed Com 131H - Permit - APD-Rev00													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
18,000.00	7,289.00	19,196.76	8,494.00	124.52	125.61	180.00	-117.08	10,891.62	1,205.00	1,103.11	101.89	11.826		
18,100.00	7,289.00	19,296.76	8,494.00	125.62	126.70	180.00	-116.34	10,991.62	1,205.00	1,102.23	102.77	11.725		
18,159.20	7,289.00	19,355.95	8,494.00	126.27	127.34	-180.00	-115.91	11,050.81	1,205.00	1,101.71	103.29	11.666		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A04) Koala 9 Fed Com 132H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
300.00	300.00	300.00	300.00	0.84	0.84	-89.05	0.50	-30.00	30.00	28.32	1.68	17.809	
400.00	400.00	400.00	400.00	1.20	1.20	-89.05	0.50	-30.00	30.00	27.60	2.40	12.493	
500.00	500.00	500.00	500.00	1.56	1.56	-89.05	0.50	-30.00	30.00	26.89	3.12	9.621	
600.00	600.00	600.00	600.00	1.92	1.92	-89.05	0.50	-30.00	30.00	26.17	3.84	7.822	
700.00	700.00	700.00	700.00	2.28	2.28	-89.05	0.50	-30.00	30.00	25.45	4.55	6.591	
800.00	800.00	800.00	800.00	2.63	2.63	-89.05	0.50	-30.00	30.00	24.73	5.27	5.694	CC
803.24	803.24	803.24	803.24	2.65	2.65	-89.05	0.50	-30.00	30.00	24.71	5.29	5.670	
900.00	900.00	899.96	899.95	2.99	2.98	-91.54	-0.81	-30.04	30.05	24.09	5.97	5.035	
1,000.00	1,000.00	999.79	999.70	3.35	3.31	-98.89	-4.72	-30.17	30.54	23.88	6.65	4.589	ES
1,100.00	1,100.00	1,099.35	1,099.04	3.71	3.64	-110.26	-11.22	-30.38	32.40	25.06	7.34	4.412	SF
1,200.00	1,200.00	1,198.50	1,197.78	4.07	3.98	-123.44	-20.26	-30.68	36.83	28.80	8.03	4.586	
1,300.00	1,299.99	1,297.26	1,295.86	4.41	4.31	26.56	-31.80	-31.05	43.47	34.78	8.69	5.000	
1,400.96	1,400.86	1,396.68	1,394.26	4.74	4.66	17.52	-45.99	-31.52	51.12	41.78	9.34	5.473	
1,500.00	1,499.77	1,493.80	1,489.99	5.07	5.00	10.23	-62.30	-32.05	60.51	50.54	9.97	6.070	
1,600.00	1,599.63	1,591.34	1,585.69	5.40	5.35	4.20	-81.13	-32.66	73.08	62.48	10.60	6.892	
1,700.00	1,699.49	1,690.13	1,682.42	5.74	5.71	-0.29	-101.23	-33.32	87.25	75.97	11.27	7.739	
1,800.00	1,799.36	1,788.93	1,779.15	6.08	6.07	-3.52	-121.33	-33.98	101.79	89.84	11.95	8.517	
1,900.00	1,899.22	1,887.73	1,875.87	6.43	6.44	-5.94	-141.43	-34.63	116.58	103.94	12.63	9.227	
2,000.00	1,999.08	1,986.52	1,972.60	6.77	6.81	-7.81	-161.53	-35.29	131.52	118.20	13.32	9.873	
2,100.00	2,098.94	2,085.32	2,069.33	7.12	7.18	-9.30	-181.63	-35.94	146.57	132.56	14.01	10.461	
2,200.00	2,198.80	2,184.12	2,166.06	7.47	7.55	-10.51	-201.74	-36.60	161.70	147.00	14.70	10.998	
2,300.00	2,298.66	2,282.91	2,262.78	7.81	7.93	-11.51	-221.84	-37.26	176.89	161.49	15.40	11.488	
2,400.00	2,398.53	2,381.71	2,359.51	8.17	8.30	-12.36	-241.94	-37.91	192.12	176.03	16.09	11.937	
2,500.00	2,498.39	2,480.50	2,456.24	8.52	8.68	-13.08	-262.04	-38.57	207.39	190.60	16.79	12.350	
2,600.00	2,598.25	2,579.30	2,552.97	8.87	9.06	-13.70	-282.14	-39.22	222.68	205.19	17.49	12.731	
2,700.00	2,698.11	2,678.10	2,649.69	9.22	9.43	-14.24	-302.24	-39.88	238.00	219.81	18.19	13.082	
2,800.00	2,797.97	2,776.89	2,746.42	9.58	9.81	-14.72	-322.35	-40.54	253.34	234.44	18.89	13.408	
2,900.00	2,897.83	2,875.69	2,843.15	9.93	10.19	-15.14	-342.45	-41.19	268.69	249.09	19.60	13.710	
3,000.00	2,997.69	2,974.49	2,939.88	10.29	10.58	-15.52	-362.55	-41.85	284.05	263.75	20.30	13.992	
3,100.00	3,097.56	3,073.28	3,036.60	10.64	10.96	-15.85	-382.65	-42.50	299.43	278.42	21.01	14.254	
3,200.00	3,197.42	3,172.08	3,133.33	11.00	11.34	-16.16	-402.75	-43.16	314.81	293.10	21.71	14.500	
3,300.00	3,297.28	3,270.88	3,230.06	11.35	11.72	-16.44	-422.86	-43.81	330.20	307.78	22.42	14.730	
3,400.00	3,397.14	3,369.67	3,326.79	11.71	12.10	-16.69	-442.96	-44.47	345.60	322.48	23.12	14.946	
3,500.00	3,497.00	3,468.47	3,423.51	12.07	12.49	-16.92	-463.06	-45.13	361.00	337.17	23.83	15.149	
3,600.00	3,596.86	3,567.27	3,520.24	12.42	12.87	-17.13	-483.16	-45.78	376.41	351.88	24.54	15.340	
3,700.00	3,696.73	3,666.06	3,616.97	12.78	13.26	-17.32	-503.26	-46.44	391.83	366.58	25.25	15.520	
3,800.00	3,796.59	3,764.86	3,713.70	13.14	13.64	-17.50	-523.36	-47.09	407.25	381.29	25.96	15.690	
3,900.00	3,896.45	3,863.66	3,810.43	13.50	14.02	-17.67	-543.47	-47.75	422.67	396.00	26.66	15.852	
4,000.00	3,996.31	3,962.45	3,907.15	13.86	14.41	-17.83	-563.57	-48.41	438.09	410.72	27.37	16.004	
4,100.00	4,096.17	4,061.25	4,003.88	14.21	14.79	-17.97	-583.67	-49.06	453.52	425.44	28.08	16.149	
4,200.00	4,196.03	4,160.04	4,100.61	14.57	15.18	-18.11	-603.77	-49.72	468.95	440.16	28.79	16.287	
4,300.00	4,295.90	4,258.84	4,197.34	14.93	15.57	-18.23	-623.87	-50.37	484.39	454.88	29.50	16.418	
4,400.00	4,395.76	4,357.64	4,294.06	15.29	15.95	-18.35	-643.97	-51.03	499.82	469.61	30.21	16.543	
4,500.00	4,495.62	4,456.43	4,390.79	15.65	16.34	-18.46	-664.08	-51.69	515.26	484.33	30.92	16.662	
4,600.00	4,595.48	4,555.23	4,487.52	16.01	16.72	-18.57	-684.18	-52.34	530.70	499.06	31.64	16.775	
4,700.00	4,695.34	4,654.03	4,584.25	16.37	17.11	-18.67	-704.28	-53.00	546.14	513.79	32.35	16.884	
4,803.94	4,799.14	4,756.71	4,684.78	16.74	17.51	-18.76	-725.17	-53.68	562.19	529.10	33.09	16.992	
4,900.00	4,895.12	4,851.44	4,777.52	17.09	17.88	-18.89	-744.44	-54.31	578.15	544.38	33.77	17.121	
5,004.89	5,000.00	4,954.40	4,878.33	17.45	18.28	179.51	-765.39	-54.99	598.15	563.65	34.50	17.337	
5,100.00	5,095.11	5,047.52	4,969.50	17.77	18.65	179.58	-784.34	-55.61	617.50	582.34	35.16	17.565	
5,200.00	5,195.11	5,145.42	5,065.35	18.10	19.03	179.66	-804.26	-56.26	637.84	602.00	35.84	17.795	
5,300.00	5,295.11	5,243.33	5,161.21	18.44	19.42	179.73	-824.18	-56.91	658.18	621.65	36.53	18.017	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A04) Koala 9 Fed Com 132H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
5,400.00	5,395.11	5,341.23	5,257.06	18.78	19.80	179.79	-844.10	-57.56	678.53	641.31	37.22	18.230			
5,500.00	5,495.11	5,439.14	5,352.92	19.12	20.18	179.85	-864.02	-58.21	698.87	660.96	37.91	18.434			
5,600.00	5,595.11	5,537.05	5,448.77	19.46	20.57	179.91	-883.94	-58.86	719.22	680.62	38.60	18.632			
5,700.00	5,695.11	5,634.95	5,544.63	19.80	20.95	179.96	-903.86	-59.51	739.56	700.27	39.29	18.821			
5,800.00	5,795.11	5,732.86	5,640.49	20.14	21.33	-179.99	-923.78	-60.16	759.91	719.92	39.99	19.004			
5,900.00	5,895.11	5,830.76	5,736.34	20.48	21.72	-179.94	-943.70	-60.81	780.26	739.58	40.68	19.181			
6,000.00	5,995.11	5,928.67	5,832.20	20.82	22.10	-179.89	-963.63	-61.46	800.61	759.23	41.37	19.351			
6,100.00	6,095.11	6,026.58	5,928.05	21.16	22.48	-179.85	-983.55	-62.11	820.95	778.89	42.07	19.516			
6,200.00	6,195.11	6,124.48	6,023.91	21.51	22.87	-179.81	-1,003.47	-62.76	841.30	798.54	42.76	19.675			
6,300.00	6,295.11	6,222.39	6,119.76	21.85	23.25	-179.77	-1,023.39	-63.41	861.65	818.20	43.46	19.828			
6,400.00	6,395.11	6,320.29	6,215.62	22.19	23.64	-179.73	-1,043.31	-64.06	882.00	837.85	44.15	19.977			
6,500.00	6,495.11	6,418.20	6,311.48	22.54	24.02	-179.69	-1,063.23	-64.71	902.35	857.50	44.85	20.120			
6,600.00	6,595.11	6,516.11	6,407.33	22.88	24.41	-179.66	-1,083.15	-65.36	922.70	877.16	45.54	20.260			
6,700.00	6,695.11	6,614.01	6,503.19	23.23	24.79	-179.63	-1,103.07	-66.01	943.05	896.81	46.24	20.394			
6,720.93	6,716.04	6,634.51	6,523.25	23.30	24.87	-179.62	-1,107.24	-66.15	947.31	900.93	46.39	20.422			
6,750.00	6,745.09	6,662.95	6,551.10	23.40	24.98	88.63	-1,113.03	-66.34	953.22	906.63	46.59	20.460			
6,800.00	6,794.86	6,711.66	6,598.79	23.57	25.17	87.90	-1,122.94	-66.66	963.29	916.36	46.93	20.524			
6,850.00	6,844.02	6,759.77	6,645.89	23.74	25.36	87.43	-1,132.73	-66.98	973.27	926.00	47.27	20.588			
6,900.00	6,892.21	6,806.92	6,692.05	23.90	25.55	87.18	-1,142.32	-67.29	983.19	935.59	47.61	20.652			
6,950.00	6,939.05	6,852.74	6,736.92	24.06	25.73	87.12	-1,151.64	-67.60	993.15	945.21	47.93	20.719			
7,000.00	6,984.20	6,896.90	6,780.15	24.21	25.90	87.21	-1,160.63	-67.89	1,003.26	955.01	48.25	20.793			
7,050.00	7,027.31	6,939.04	6,821.41	24.35	26.07	87.38	-1,169.20	-68.17	1,013.70	965.14	48.56	20.876			
7,100.00	7,068.05	6,978.86	6,860.40	24.48	26.22	87.59	-1,177.30	-68.43	1,024.63	975.77	48.86	20.973			
7,150.00	7,106.11	7,016.05	6,896.80	24.62	26.37	87.76	-1,184.87	-68.68	1,036.25	987.11	49.14	21.087			
7,200.00	7,141.21	7,050.32	6,930.36	24.76	26.50	87.85	-1,191.84	-68.91	1,048.74	999.32	49.42	21.221			
7,250.00	7,173.06	7,081.42	6,960.81	24.90	26.63	87.78	-1,198.17	-69.11	1,062.27	1,012.59	49.69	21.380			
7,300.00	7,201.44	7,109.10	6,987.91	25.03	26.73	87.50	-1,203.80	-69.30	1,076.99	1,027.05	49.94	21.565			
7,350.00	7,226.12	7,133.17	7,011.47	25.17	26.83	86.97	-1,208.70	-69.46	1,093.01	1,042.82	50.18	21.780			
7,400.00	7,246.93	7,153.43	7,031.31	25.30	26.91	86.13	-1,212.82	-69.59	1,110.38	1,059.97	50.41	22.026			
7,450.00	7,263.69	7,169.73	7,047.27	25.43	26.97	84.96	-1,216.14	-69.70	1,129.13	1,078.51	50.62	22.304			
7,500.00	7,276.28	7,181.94	7,059.22	25.56	27.02	83.42	-1,218.62	-69.78	1,149.22	1,098.40	50.82	22.614			
7,550.00	7,284.61	7,189.98	7,067.09	25.68	27.05	81.51	-1,220.26	-69.84	1,170.57	1,119.57	50.99	22.956			
7,600.00	7,288.62	7,193.78	7,070.82	25.80	27.07	79.24	-1,221.03	-69.86	1,193.02	1,141.88	51.14	23.326			
7,620.93	7,289.00	7,194.11	7,071.13	25.85	27.07	78.18	-1,221.10	-69.86	1,202.71	1,151.51	51.20	23.490			
7,701.87	7,289.00	7,193.68	7,070.72	26.06	27.07	77.96	-1,221.01	-69.86	1,243.48	1,192.06	51.42	24.184			
10,500.00	7,289.00	11,877.81	8,494.00	45.45	48.90	132.40	-1,491.52	3,401.40	1,787.06	1,715.17	71.89	24.859			
10,600.00	7,289.00	11,977.81	8,494.00	46.39	49.77	132.40	-1,490.79	3,501.40	1,787.06	1,713.72	73.34	24.366			
10,700.00	7,289.00	12,077.81	8,494.00	47.33	50.66	132.40	-1,490.07	3,601.40	1,787.07	1,712.26	74.81	23.888			
10,800.00	7,289.00	12,177.81	8,494.00	48.28	51.55	132.40	-1,489.34	3,701.39	1,787.07	1,710.78	76.29	23.425			
10,900.00	7,289.00	12,277.81	8,494.00	49.24	52.45	132.40	-1,488.61	3,801.39	1,787.07	1,709.29	77.78	22.975			
11,000.00	7,289.00	12,377.81	8,494.00	50.21	53.36	132.40	-1,487.89	3,901.39	1,787.08	1,707.79	79.29	22.539			
11,100.00	7,289.00	12,477.81	8,494.00	51.18	54.28	132.40	-1,487.16	4,001.39	1,787.08	1,706.27	80.81	22.116			
11,200.00	7,289.00	12,577.81	8,494.00	52.16	55.21	132.40	-1,486.43	4,101.38	1,787.08	1,704.75	82.33	21.706			
11,300.00	7,289.00	12,677.81	8,494.00	53.15	56.14	132.40	-1,485.71	4,201.38	1,787.09	1,703.22	83.87	21.308			
11,400.00	7,289.00	12,777.81	8,494.00	54.14	57.08	132.40	-1,484.98	4,301.38	1,787.09	1,701.67	85.42	20.922			
11,500.00	7,289.00	12,877.81	8,494.00	55.13	58.03	132.40	-1,484.26	4,401.38	1,787.09	1,700.12	86.97	20.548			
11,600.00	7,289.00	12,977.81	8,494.00	56.13	58.98	132.40	-1,483.53	4,501.37	1,787.10	1,698.56	88.54	20.185			
11,700.00	7,289.00	13,077.81	8,494.00	57.13	59.94	132.40	-1,482.80	4,601.37	1,787.10	1,696.99	90.11	19.833			
11,800.00	7,289.00	13,177.81	8,494.00	58.14	60.90	132.40	-1,482.08	4,701.37	1,787.10	1,695.41	91.69	19.491			
11,900.00	7,289.00	13,277.81	8,494.00	59.16	61.87	132.40	-1,481.35	4,801.36	1,787.11	1,693.83	93.27	19.160			
12,000.00	7,289.00	13,377.81	8,494.00	60.17	62.85	132.40	-1,480.63	4,901.36	1,787.11	1,692.24	94.87	18.838			
12,100.00	7,289.00	13,477.81	8,494.00	61.19	63.83	132.40	-1,479.90	5,001.36	1,787.11	1,690.64	96.47	18.526			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A04) Koala 9 Fed Com 132H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance		Rule Assigned:		Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
12,200.00	7,289.00	13,577.81	8,494.00	62.22	64.81	132.40	-1,479.17	5,101.36	1,787.12	1,689.04	98.07	18.222	
12,300.00	7,289.00	13,677.81	8,494.00	63.24	65.80	132.40	-1,478.45	5,201.35	1,787.12	1,687.43	99.69	17.928	
12,400.00	7,289.00	13,777.81	8,494.00	64.27	66.79	132.40	-1,477.72	5,301.35	1,787.12	1,685.82	101.30	17.641	
12,500.00	7,289.00	13,877.81	8,494.00	65.31	67.79	132.40	-1,477.00	5,401.35	1,787.13	1,684.20	102.93	17.363	
12,600.00	7,289.00	13,977.81	8,494.00	66.34	68.79	132.40	-1,476.27	5,501.35	1,787.13	1,682.57	104.55	17.093	
12,700.00	7,289.00	14,077.81	8,494.00	67.38	69.80	132.40	-1,475.54	5,601.34	1,787.13	1,680.94	106.19	16.830	
12,800.00	7,289.00	14,177.81	8,494.00	68.42	70.80	132.40	-1,474.82	5,701.34	1,787.14	1,679.31	107.83	16.574	
12,900.00	7,289.00	14,277.81	8,494.00	69.47	71.82	132.40	-1,474.09	5,801.34	1,787.14	1,677.67	109.47	16.326	
13,000.00	7,289.00	14,377.81	8,494.00	70.51	72.83	132.40	-1,473.36	5,901.34	1,787.14	1,676.03	111.11	16.084	
13,100.00	7,289.00	14,477.81	8,494.00	71.56	73.85	132.40	-1,472.64	6,001.33	1,787.15	1,674.38	112.76	15.848	
13,200.00	7,289.00	14,577.81	8,494.00	72.61	74.87	132.40	-1,471.91	6,101.33	1,787.15	1,672.73	114.42	15.619	
13,300.00	7,289.00	14,677.81	8,494.00	73.67	75.89	132.40	-1,471.19	6,201.33	1,787.15	1,671.07	116.08	15.396	
13,400.00	7,289.00	14,777.81	8,494.00	74.72	76.92	132.40	-1,470.46	6,301.33	1,787.16	1,669.42	117.74	15.179	
13,500.00	7,289.00	14,877.81	8,494.00	75.78	77.95	132.40	-1,469.73	6,401.32	1,787.16	1,667.75	119.40	14.967	
13,600.00	7,289.00	14,977.81	8,494.00	76.84	78.98	132.40	-1,468.99	6,501.32	1,787.16	1,666.09	121.07	14.761	
13,700.00	7,289.00	15,077.81	8,494.00	77.90	80.02	132.40	-1,468.28	6,601.32	1,787.17	1,664.42	122.74	14.560	
13,800.00	7,289.00	15,177.81	8,494.00	78.96	81.05	132.40	-1,467.56	6,701.31	1,787.17	1,662.75	124.42	14.364	
13,900.00	7,289.00	15,277.81	8,494.00	80.02	82.09	132.40	-1,466.83	6,801.31	1,787.17	1,661.08	126.10	14.173	
14,000.00	7,289.00	15,377.81	8,494.00	81.09	83.13	132.40	-1,466.10	6,901.31	1,787.18	1,659.40	127.78	13.987	
14,100.00	7,289.00	15,477.81	8,494.00	82.15	84.18	132.40	-1,465.38	7,001.31	1,787.18	1,657.72	129.46	13.805	
14,200.00	7,289.00	15,577.81	8,494.00	83.22	85.22	132.40	-1,464.65	7,101.30	1,787.18	1,656.04	131.14	13.628	
14,300.00	7,289.00	15,677.81	8,494.00	84.29	86.27	132.40	-1,463.92	7,201.30	1,787.19	1,654.35	132.83	13.454	
14,400.00	7,289.00	15,777.81	8,494.00	85.36	87.32	132.40	-1,463.20	7,301.30	1,787.19	1,652.67	134.52	13.285	
14,500.00	7,289.00	15,877.81	8,494.00	86.44	88.37	132.40	-1,462.47	7,401.30	1,787.19	1,650.98	136.22	13.120	
14,600.00	7,289.00	15,977.81	8,494.00	87.51	89.42	132.40	-1,461.75	7,501.29	1,787.20	1,649.29	137.91	12.959	
14,700.00	7,289.00	16,077.81	8,494.00	88.58	90.47	132.40	-1,461.02	7,601.29	1,787.20	1,647.59	139.61	12.802	
14,800.00	7,289.00	16,177.81	8,494.00	89.66	91.53	132.40	-1,460.29	7,701.29	1,787.20	1,645.90	141.31	12.648	
14,900.00	7,289.00	16,277.81	8,494.00	90.74	92.59	132.39	-1,459.57	7,801.29	1,787.21	1,644.20	143.01	12.497	
15,000.00	7,289.00	16,377.81	8,494.00	91.82	93.64	132.39	-1,458.84	7,901.28	1,787.21	1,642.50	144.71	12.350	
15,100.00	7,289.00	16,477.81	8,494.00	92.90	94.71	132.39	-1,458.12	8,001.28	1,787.21	1,640.80	146.41	12.207	
15,200.00	7,289.00	16,577.81	8,494.00	93.98	95.77	132.39	-1,457.39	8,101.28	1,787.22	1,639.10	148.12	12.066	
15,300.00	7,289.00	16,677.81	8,494.00	95.06	96.83	132.39	-1,456.66	8,201.28	1,787.22	1,637.39	149.83	11.928	
15,400.00	7,289.00	16,777.81	8,494.00	96.14	97.89	132.39	-1,455.94	8,301.27	1,787.22	1,635.68	151.54	11.794	
15,500.00	7,289.00	16,877.81	8,494.00	97.22	98.96	132.39	-1,455.21	8,401.27	1,787.23	1,633.98	153.25	11.662	
15,600.00	7,289.00	16,977.81	8,494.00	98.31	100.03	132.39	-1,454.49	8,501.27	1,787.23	1,632.27	154.96	11.533	
15,700.00	7,289.00	17,077.81	8,494.00	99.39	101.09	132.39	-1,453.76	8,601.26	1,787.23	1,630.56	156.68	11.407	
15,800.00	7,289.00	17,177.81	8,494.00	100.48	102.16	132.39	-1,453.03	8,701.26	1,787.24	1,628.84	158.39	11.284	
15,900.00	7,289.00	17,277.81	8,494.00	101.56	103.23	132.39	-1,452.31	8,801.26	1,787.24	1,627.13	160.11	11.163	
16,000.00	7,289.00	17,377.81	8,494.00	102.65	104.31	132.39	-1,451.58	8,901.26	1,787.24	1,625.41	161.83	11.044	
16,100.00	7,289.00	17,477.81	8,494.00	103.74	105.38	132.39	-1,450.85	9,001.25	1,787.25	1,623.70	163.55	10.928	
16,200.00	7,289.00	17,577.81	8,494.00	104.83	106.45	132.39	-1,450.13	9,101.25	1,787.25	1,621.98	165.27	10.814	
16,300.00	7,289.00	17,677.81	8,494.00	105.92	107.53	132.39	-1,449.40	9,201.25	1,787.25	1,620.26	166.99	10.703	
16,400.00	7,289.00	17,777.81	8,494.00	107.01	108.60	132.39	-1,448.68	9,301.25	1,787.26	1,618.54	168.72	10.593	
16,500.00	7,289.00	17,877.81	8,494.00	108.10	109.68	132.39	-1,447.95	9,401.24	1,787.26	1,616.82	170.44	10.486	
16,600.00	7,289.00	17,977.81	8,494.00	109.19	110.76	132.39	-1,447.22	9,501.24	1,787.26	1,615.09	172.17	10.381	
16,700.00	7,289.00	18,077.81	8,494.00	110.28	111.83	132.39	-1,446.50	9,601.24	1,787.27	1,613.37	173.90	10.278	
16,800.00	7,289.00	18,177.81	8,494.00	111.37	112.91	132.39	-1,445.77	9,701.24	1,787.27	1,611.65	175.62	10.177	
16,900.00	7,289.00	18,277.81	8,494.00	112.46	113.99	132.39	-1,445.05	9,801.23	1,787.27	1,609.92	177.35	10.078	
17,000.00	7,289.00	18,377.81	8,494.00	113.56	115.07	132.39	-1,444.32	9,901.23	1,787.28	1,608.19	179.08	9.980	
17,100.00	7,289.00	18,477.81	8,494.00	114.65	116.15	132.39	-1,443.59	10,001.23	1,787.28	1,606.47	180.81	9.885	
17,200.00	7,289.00	18,577.81	8,494.00	115.75	117.24	132.39	-1,442.87	10,101.23	1,787.28	1,604.74	182.55	9.791	
17,300.00	7,289.00	18,677.81	8,494.00	116.84	118.32	132.39	-1,442.14	10,201.22	1,787.29	1,603.01	184.28	9.699	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A04) Koala 9 Fed Com 132H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Rule Assigned:		Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
17,400.00	7,289.00	18,777.81	8,494.00	117.94	119.40	132.39	-1,441.42	10,301.22	1,787.29	1,601.28	186.01	9.608			
17,500.00	7,289.00	18,877.81	8,494.00	119.03	120.49	132.39	-1,440.69	10,401.22	1,787.29	1,599.55	187.75	9.520			
17,600.00	7,289.00	18,977.81	8,494.00	120.13	121.57	132.39	-1,439.96	10,501.21	1,787.30	1,597.81	189.48	9.432			
17,700.00	7,289.00	19,077.81	8,494.00	121.23	122.66	132.39	-1,439.24	10,601.21	1,787.30	1,596.08	191.22	9.347			
17,800.00	7,289.00	19,177.81	8,494.00	122.33	123.74	132.39	-1,438.51	10,701.21	1,787.30	1,594.35	192.96	9.263			
17,900.00	7,289.00	19,277.81	8,494.00	123.42	124.83	132.39	-1,437.78	10,801.21	1,787.31	1,592.61	194.70	9.180			
18,000.00	7,289.00	19,377.81	8,494.00	124.52	125.92	132.39	-1,437.06	10,901.20	1,787.31	1,590.88	196.43	9.099			
18,100.00	7,289.00	19,477.81	8,494.00	125.62	127.01	132.39	-1,436.33	11,001.20	1,787.31	1,589.14	198.17	9.019			
18,101.43	7,289.00	19,479.24	8,494.00	125.64	127.02	132.39	-1,436.32	11,002.63	1,787.31	1,589.11	198.20	9.018			
18,159.20	7,289.00	19,509.78	8,494.00	126.27	127.36	132.39	-1,436.10	11,033.17	1,787.52	1,588.52	199.00	8.982			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A06) Koala 9 Fed Com 122H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
300.00	300.00	300.00	300.00	0.84	0.84	90.95	-0.50	30.00	30.00	28.32	1.68	17.809	
400.00	400.00	400.00	400.00	1.20	1.20	90.95	-0.50	30.00	30.00	27.60	2.40	12.493	
500.00	500.00	500.00	500.00	1.56	1.56	90.95	-0.50	30.00	30.00	26.89	3.12	9.621	
600.00	600.00	600.00	600.00	1.92	1.92	90.95	-0.50	30.00	30.00	26.17	3.84	7.822	
700.00	700.00	700.00	700.00	2.28	2.28	90.95	-0.50	30.00	30.00	25.45	4.55	6.591	
800.00	800.00	800.00	800.00	2.63	2.63	90.95	-0.50	30.00	30.00	24.73	5.27	5.694	
861.82	861.82	861.82	861.82	2.86	2.85	91.91	-1.00	29.98	30.00	24.30	5.70	5.262 CC	
900.00	900.00	900.00	899.99	2.99	2.98	93.45	-1.81	29.96	30.01	24.04	5.97	5.028	
1,000.00	1,000.00	999.84	999.75	3.35	3.31	100.86	-5.72	29.83	30.37	23.72	6.65	4.564 ES	
1,100.00	1,100.00	1,099.42	1,099.12	3.71	3.64	112.43	-12.22	29.61	32.04	24.70	7.34	4.363 SF	
1,200.00	1,200.00	1,198.60	1,197.88	4.07	3.98	125.97	-21.27	29.31	36.27	28.24	8.03	4.516	
1,300.00	1,299.99	1,297.39	1,295.98	4.41	4.31	-61.24	-32.82	28.92	43.29	34.59	8.70	4.978	
1,400.96	1,400.86	1,396.83	1,394.41	4.74	4.66	-53.84	-47.01	28.45	52.08	42.74	9.35	5.573	
1,500.00	1,499.77	1,493.97	1,490.16	5.07	5.00	-48.47	-63.33	27.90	62.58	52.60	9.98	6.271	
1,600.00	1,599.63	1,591.39	1,585.74	5.40	5.35	-43.75	-82.14	27.28	75.83	65.21	10.62	7.143	
1,700.00	1,699.49	1,688.03	1,680.05	5.74	5.70	-39.83	-103.21	26.57	91.74	80.50	11.24	8.159	
1,800.00	1,799.36	1,784.87	1,774.05	6.08	6.06	-36.64	-126.48	25.80	110.09	98.20	11.89	9.262	
1,900.00	1,899.22	1,882.93	1,869.13	6.43	6.43	-34.27	-150.44	25.00	129.07	116.50	12.56	10.275	
2,000.00	1,999.08	1,980.99	1,964.22	6.77	6.80	-32.51	-174.41	24.20	148.20	134.96	13.24	11.193	
2,100.00	2,098.94	2,079.06	2,059.31	7.12	7.17	-31.15	-198.37	23.40	167.44	153.52	13.92	12.025	
2,200.00	2,198.80	2,177.12	2,154.39	7.47	7.55	-30.08	-222.33	22.60	186.76	172.14	14.61	12.782	
2,300.00	2,298.66	2,275.18	2,249.48	7.81	7.93	-29.20	-246.30	21.80	206.12	190.82	15.30	13.471	
2,400.00	2,398.53	2,373.25	2,344.57	8.17	8.31	-28.48	-270.26	21.00	225.52	209.53	15.99	14.102	
2,500.00	2,498.39	2,471.31	2,439.65	8.52	8.70	-27.87	-294.23	20.20	244.95	228.27	16.69	14.680	
2,600.00	2,598.25	2,569.37	2,534.74	8.87	9.08	-27.35	-318.19	19.40	264.41	247.03	17.38	15.212	
2,700.00	2,698.11	2,667.44	2,629.83	9.22	9.47	-26.90	-342.15	18.61	283.88	265.80	18.08	15.703	
2,800.00	2,797.97	2,765.50	2,724.91	9.58	9.85	-26.51	-366.12	17.81	303.37	284.59	18.78	16.158	
2,900.00	2,897.83	2,863.56	2,820.00	9.93	10.24	-26.16	-390.08	17.01	322.87	303.39	19.47	16.579	
3,000.00	2,997.69	2,961.62	2,915.09	10.29	10.63	-25.86	-414.04	16.21	342.38	322.20	20.17	16.971	
3,100.00	3,097.56	3,059.69	3,010.17	10.64	11.02	-25.59	-438.01	15.41	361.90	341.02	20.88	17.336	
3,200.00	3,197.42	3,157.75	3,105.26	11.00	11.41	-25.34	-461.97	14.61	381.42	359.84	21.58	17.677	
3,300.00	3,297.28	3,255.81	3,200.35	11.35	11.80	-25.12	-485.94	13.81	400.95	378.67	22.28	17.996	
3,400.00	3,397.14	3,353.88	3,295.43	11.71	12.19	-24.92	-509.90	13.01	420.49	397.51	22.98	18.296	
3,500.00	3,497.00	3,451.94	3,390.52	12.07	12.58	-24.74	-533.86	12.21	440.03	416.34	23.69	18.577	
3,600.00	3,596.86	3,550.00	3,485.61	12.42	12.98	-24.57	-557.83	11.41	459.57	435.18	24.39	18.842	
3,700.00	3,696.73	3,648.07	3,580.69	12.78	13.37	-24.42	-581.79	10.61	479.12	454.02	25.10	19.092	
3,800.00	3,796.59	3,746.13	3,675.78	13.14	13.76	-24.28	-605.76	9.81	498.67	472.87	25.80	19.327	
3,900.00	3,896.45	3,844.19	3,770.87	13.50	14.16	-24.15	-629.72	9.01	518.22	491.72	26.51	19.550	
4,000.00	3,996.31	3,942.26	3,865.95	13.86	14.55	-24.03	-653.68	8.21	537.78	510.57	27.21	19.762	
4,100.00	4,096.17	4,040.32	3,961.04	14.21	14.95	-23.92	-677.65	7.42	557.34	529.42	27.92	19.962	
4,200.00	4,196.03	4,138.38	4,056.13	14.57	15.34	-23.81	-701.61	6.62	576.90	548.27	28.63	20.153	
4,300.00	4,295.90	4,236.44	4,151.21	14.93	15.74	-23.71	-725.57	5.82	596.46	567.13	29.33	20.334	
4,400.00	4,395.76	4,334.51	4,246.30	15.29	16.13	-23.62	-749.54	5.02	616.02	585.98	30.04	20.506	
4,500.00	4,495.62	4,432.57	4,341.39	15.65	16.53	-23.53	-773.50	4.22	635.59	604.84	30.75	20.670	
4,600.00	4,595.48	4,530.63	4,436.47	16.01	16.92	-23.45	-797.47	3.42	655.15	623.70	31.46	20.827	
4,700.00	4,695.34	4,628.70	4,531.56	16.37	17.32	-23.38	-821.43	2.62	674.72	642.56	32.17	20.976	
4,803.94	4,799.14	4,730.62	4,630.39	16.74	17.73	-23.30	-846.34	1.79	695.06	662.16	32.90	21.125	
4,900.00	4,895.12	4,824.59	4,721.51	17.09	18.11	-23.32	-869.30	1.02	714.95	681.36	33.58	21.290	
5,004.89	5,000.00	4,926.63	4,820.45	17.45	18.52	175.18	-894.23	0.19	739.14	704.83	34.31	21.543	
5,100.00	5,095.11	5,018.85	4,909.87	17.77	18.90	175.39	-916.77	-0.56	762.24	727.28	34.96	21.803	
5,200.00	5,195.11	5,115.81	5,003.89	18.10	19.29	175.59	-940.47	-1.35	786.55	750.91	35.64	22.067	
5,300.00	5,295.11	5,212.78	5,097.91	18.44	19.68	175.78	-964.16	-2.14	810.87	774.54	36.33	22.321	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A06) Koala 9 Fed Com 122H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance		Rule Assigned:		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
5,400.00	5,395.11	5,309.74	5,191.93	18.78	20.07	175.96	-987.86	-2.93	835.19	798.18	37.01	22.566			
5,500.00	5,495.11	5,406.71	5,285.95	19.12	20.47	176.13	-1,011.55	-3.72	859.52	821.82	37.70	22.800			
5,600.00	5,595.11	5,503.67	5,379.97	19.46	20.86	176.29	-1,035.25	-4.51	883.86	845.47	38.38	23.027			
5,700.00	5,695.11	5,600.63	5,474.00	19.80	21.25	176.44	-1,058.94	-5.30	908.20	869.13	39.07	23.245			
5,800.00	5,795.11	5,697.60	5,568.02	20.14	21.65	176.58	-1,082.64	-6.09	932.55	892.79	39.76	23.455			
5,900.00	5,895.11	5,794.56	5,662.04	20.48	22.04	176.72	-1,106.33	-6.88	956.90	916.45	40.45	23.658			
6,000.00	5,995.11	5,891.53	5,756.06	20.82	22.43	176.85	-1,130.03	-7.67	981.26	940.12	41.14	23.854			
6,100.00	6,095.11	5,988.49	5,850.08	21.16	22.83	176.97	-1,153.72	-8.46	1,005.62	963.80	41.83	24.043			
6,200.00	6,195.11	6,085.46	5,944.10	21.51	23.22	177.09	-1,177.42	-9.25	1,029.99	987.47	42.52	24.225			
6,300.00	6,295.11	6,182.42	6,038.13	21.85	23.61	177.20	-1,201.12	-10.04	1,054.36	1,011.15	43.21	24.402			
6,400.00	6,395.11	6,279.39	6,132.15	22.19	24.01	177.31	-1,224.81	-10.83	1,078.74	1,034.84	43.90	24.573			
6,500.00	6,495.11	6,376.35	6,226.17	22.54	24.40	177.41	-1,248.51	-11.62	1,103.12	1,058.52	44.59	24.738			
6,600.00	6,595.11	6,473.32	6,320.19	22.88	24.79	177.51	-1,272.20	-12.41	1,127.50	1,082.21	45.28	24.898			
7,800.00	7,289.00	7,942.84	7,289.00	26.35	28.81	90.00	-1,511.12	701.47	1,319.55	1,266.32	53.23	24.789			
7,900.00	7,289.00	8,042.84	7,289.00	26.69	28.96	90.00	-1,510.39	801.47	1,319.55	1,265.67	53.88	24.489			
8,000.00	7,289.00	8,142.84	7,289.00	27.08	29.15	90.00	-1,509.67	901.47	1,319.56	1,264.94	54.62	24.158			
8,100.00	7,289.00	8,242.84	7,289.00	27.50	29.39	90.00	-1,508.94	1,001.46	1,319.56	1,264.12	55.44	23.802			
8,200.00	7,289.00	8,342.84	7,289.00	27.96	29.68	90.00	-1,508.21	1,101.46	1,319.57	1,263.23	56.34	23.423			
8,300.00	7,289.00	8,442.84	7,289.00	28.46	30.03	90.00	-1,507.49	1,201.46	1,319.57	1,262.27	57.31	23.027			
8,400.00	7,289.00	8,542.84	7,289.00	28.99	30.43	90.00	-1,506.76	1,301.46	1,319.58	1,261.23	58.35	22.617			
8,500.00	7,289.00	8,642.84	7,289.00	29.56	30.89	90.00	-1,506.04	1,401.45	1,319.58	1,260.13	59.45	22.196			
8,600.00	7,289.00	8,742.84	7,289.00	30.16	31.39	90.00	-1,505.31	1,501.45	1,319.59	1,258.97	60.62	21.768			
8,700.00	7,289.00	8,842.84	7,289.00	30.79	31.93	90.00	-1,504.58	1,601.45	1,319.59	1,257.74	61.85	21.335			
8,800.00	7,289.00	8,942.84	7,289.00	31.44	32.51	90.00	-1,503.86	1,701.45	1,319.60	1,256.46	63.13	20.901			
8,900.00	7,289.00	9,042.84	7,289.00	32.12	33.12	90.00	-1,503.13	1,801.44	1,319.60	1,255.13	64.47	20.468			
9,000.00	7,289.00	9,142.84	7,289.00	32.82	33.77	90.00	-1,502.41	1,901.44	1,319.61	1,253.75	65.86	20.037			
9,100.00	7,289.00	9,242.84	7,289.00	33.55	34.44	90.00	-1,501.68	2,001.44	1,319.61	1,252.32	67.29	19.611			
9,200.00	7,289.00	9,342.84	7,289.00	34.30	35.14	90.00	-1,500.95	2,101.44	1,319.61	1,250.85	68.77	19.190			
9,300.00	7,289.00	9,442.84	7,289.00	35.07	35.86	90.00	-1,500.23	2,201.43	1,319.62	1,249.34	70.28	18.776			
9,400.00	7,289.00	9,542.84	7,289.00	35.86	36.60	90.00	-1,499.50	2,301.43	1,319.62	1,247.78	71.84	18.369			
9,500.00	7,289.00	9,642.84	7,289.00	36.66	37.37	90.00	-1,498.78	2,401.43	1,319.63	1,246.20	73.43	17.971			
9,600.00	7,289.00	9,742.84	7,289.00	37.48	38.15	90.00	-1,498.05	2,501.42	1,319.63	1,244.58	75.05	17.583			
9,700.00	7,289.00	9,842.84	7,289.00	38.32	38.95	90.00	-1,497.32	2,601.42	1,319.64	1,242.93	76.71	17.203			
9,800.00	7,289.00	9,942.84	7,289.00	39.17	39.77	90.00	-1,496.60	2,701.42	1,319.64	1,241.25	78.39	16.834			
9,900.00	7,289.00	10,042.84	7,289.00	40.03	40.60	90.00	-1,495.87	2,801.42	1,319.65	1,239.54	80.11	16.474			
10,000.00	7,289.00	10,142.84	7,289.00	40.91	41.44	90.00	-1,495.15	2,901.41	1,319.65	1,237.81	81.84	16.124			
10,100.00	7,289.00	10,242.84	7,289.00	41.80	42.30	90.00	-1,494.42	3,001.41	1,319.66	1,236.05	83.60	15.784			
10,200.00	7,289.00	10,342.84	7,289.00	42.69	43.18	90.00	-1,493.69	3,101.41	1,319.66	1,234.27	85.39	15.455			
10,300.00	7,289.00	10,442.84	7,289.00	43.60	44.06	90.00	-1,492.97	3,201.41	1,319.67	1,232.47	87.19	15.135			
10,400.00	7,289.00	10,542.84	7,289.00	44.52	44.95	90.00	-1,492.24	3,301.40	1,319.67	1,230.65	89.02	14.824			
10,500.00	7,289.00	10,642.84	7,289.00	45.45	45.86	90.00	-1,491.51	3,401.40	1,319.67	1,228.81	90.86	14.523			
10,600.00	7,289.00	10,742.84	7,289.00	46.39	46.77	90.00	-1,490.79	3,501.40	1,319.68	1,226.95	92.73	14.232			
10,700.00	7,289.00	10,842.84	7,289.00	47.33	47.70	90.00	-1,490.06	3,601.40	1,319.68	1,225.08	94.61	13.949			
10,800.00	7,289.00	10,942.84	7,289.00	48.28	48.63	90.00	-1,489.34	3,701.39	1,319.69	1,223.19	96.50	13.676			
10,900.00	7,289.00	11,042.84	7,289.00	49.24	49.57	90.00	-1,488.61	3,801.39	1,319.69	1,221.28	98.41	13.410			
11,000.00	7,289.00	11,142.84	7,289.00	50.21	50.51	90.00	-1,487.88	3,901.39	1,319.70	1,219.37	100.33	13.153			
11,100.00	7,289.00	11,242.84	7,289.00	51.18	51.47	90.00	-1,487.16	4,001.39	1,319.70	1,217.43	102.27	12.904			
11,200.00	7,289.00	11,342.84	7,289.00	52.16	52.43	90.00	-1,486.43	4,101.38	1,319.71	1,215.49	104.22	12.663			
11,300.00	7,289.00	11,442.84	7,289.00	53.15	53.40	90.00	-1,485.71	4,201.38	1,319.71	1,213.54	106.18	12.430			
11,400.00	7,289.00	11,542.84	7,289.00	54.14	54.37	90.00	-1,484.98	4,301.38	1,319.72	1,211.57	108.15	12.203			
11,500.00	7,289.00	11,642.84	7,289.00	55.13	55.35	90.00	-1,484.25	4,401.37	1,319.72	1,209.59	110.13	11.983			
11,600.00	7,289.00	11,742.84	7,289.00	56.13	56.34	90.00	-1,483.53	4,501.37	1,319.72	1,207.61	112.12	11.771			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A06) Koala 9 Fed Com 122H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
11,700.00	7,289.00	11,842.84	7,289.00	57.13	57.33	90.00	-1,482.80	4,601.37	1,319.73	1,205.61	114.12	11.564	
11,800.00	7,289.00	11,942.84	7,289.00	58.14	58.32	90.00	-1,482.08	4,701.37	1,319.73	1,203.60	116.13	11.364	
11,900.00	7,289.00	12,042.84	7,289.00	59.16	59.32	90.00	-1,481.35	4,801.36	1,319.74	1,201.59	118.15	11.170	
12,000.00	7,289.00	12,142.84	7,289.00	60.17	60.32	90.00	-1,480.62	4,901.36	1,319.74	1,199.57	120.17	10.982	
12,100.00	7,289.00	12,242.84	7,289.00	61.19	61.33	90.00	-1,479.90	5,001.36	1,319.75	1,197.54	122.21	10.799	
12,200.00	7,289.00	12,342.84	7,289.00	62.22	62.34	90.00	-1,479.17	5,101.36	1,319.75	1,195.50	124.25	10.622	
12,300.00	7,289.00	12,442.84	7,289.00	63.24	63.36	90.00	-1,478.45	5,201.35	1,319.76	1,193.46	126.30	10.450	
12,400.00	7,289.00	12,542.84	7,289.00	64.27	64.38	90.00	-1,477.72	5,301.35	1,319.76	1,191.41	128.35	10.282	
12,500.00	7,289.00	12,642.84	7,289.00	65.31	65.40	90.00	-1,476.99	5,401.35	1,319.77	1,189.35	130.41	10.120	
12,600.00	7,289.00	12,742.84	7,289.00	66.34	66.43	90.00	-1,476.27	5,501.35	1,319.77	1,187.29	132.48	9.962	
12,700.00	7,289.00	12,842.84	7,289.00	67.38	67.45	90.00	-1,475.54	5,601.34	1,319.78	1,185.22	134.55	9.809	
12,800.00	7,289.00	12,942.84	7,289.00	68.42	68.49	90.00	-1,474.81	5,701.34	1,319.78	1,183.15	136.63	9.660	
12,900.00	7,289.00	13,042.84	7,289.00	69.47	69.52	90.00	-1,474.09	5,801.34	1,319.78	1,181.07	138.71	9.515	
13,000.00	7,289.00	13,142.84	7,289.00	70.51	70.56	90.00	-1,473.36	5,901.34	1,319.79	1,178.99	140.80	9.374	
13,100.00	7,289.00	13,242.84	7,289.00	71.56	71.60	90.00	-1,472.64	6,001.33	1,319.79	1,176.90	142.89	9.236	
13,200.00	7,289.00	13,342.84	7,289.00	72.61	72.64	90.00	-1,471.91	6,101.33	1,319.80	1,174.81	144.99	9.103	
13,300.00	7,289.00	13,442.84	7,289.00	73.67	73.68	90.00	-1,471.18	6,201.33	1,319.80	1,172.71	147.09	8.973	
13,400.00	7,289.00	13,542.84	7,289.00	74.72	74.73	90.00	-1,470.46	6,301.32	1,319.81	1,170.61	149.20	8.846	
13,500.00	7,289.00	13,642.84	7,289.00	75.78	75.78	90.00	-1,469.73	6,401.32	1,319.81	1,168.51	151.31	8.723	
13,600.00	7,289.00	13,742.84	7,289.00	76.84	76.83	90.00	-1,469.01	6,501.32	1,319.82	1,166.40	153.42	8.603	
13,700.00	7,289.00	13,842.84	7,289.00	77.90	77.88	90.00	-1,468.28	6,601.32	1,319.82	1,164.28	155.54	8.486	
13,800.00	7,289.00	13,942.84	7,289.00	78.96	78.94	90.00	-1,467.55	6,701.31	1,319.83	1,162.17	157.66	8.371	
13,900.00	7,289.00	14,042.84	7,289.00	80.02	80.00	90.00	-1,466.83	6,801.31	1,319.83	1,160.05	159.78	8.260	
14,000.00	7,289.00	14,142.84	7,289.00	81.09	81.05	90.00	-1,466.10	6,901.31	1,319.84	1,157.93	161.91	8.152	
14,100.00	7,289.00	14,242.84	7,289.00	82.15	82.11	90.00	-1,465.38	7,001.31	1,319.84	1,155.80	164.04	8.046	
14,200.00	7,289.00	14,342.84	7,289.00	83.22	83.18	90.00	-1,464.65	7,101.30	1,319.84	1,153.67	166.17	7.943	
14,300.00	7,289.00	14,442.84	7,289.00	84.29	84.24	90.00	-1,463.92	7,201.30	1,319.85	1,151.54	168.31	7.842	
14,400.00	7,289.00	14,542.84	7,289.00	85.36	85.30	90.00	-1,463.20	7,301.30	1,319.85	1,149.41	170.45	7.743	
14,500.00	7,289.00	14,642.84	7,289.00	86.44	86.37	90.00	-1,462.47	7,401.30	1,319.86	1,147.27	172.59	7.647	
14,600.00	7,289.00	14,742.84	7,289.00	87.51	87.44	90.00	-1,461.75	7,501.29	1,319.86	1,145.13	174.73	7.554	
14,700.00	7,289.00	14,842.84	7,289.00	88.58	88.51	90.00	-1,461.02	7,601.29	1,319.87	1,142.99	176.88	7.462	
14,800.00	7,289.00	14,942.84	7,289.00	89.66	89.58	90.00	-1,460.29	7,701.29	1,319.87	1,140.84	179.03	7.372	
14,900.00	7,289.00	15,042.84	7,289.00	90.74	90.65	90.00	-1,459.57	7,801.29	1,319.88	1,138.70	181.18	7.285	
15,000.00	7,289.00	15,142.84	7,289.00	91.82	91.72	90.00	-1,458.84	7,901.28	1,319.88	1,136.55	183.33	7.199	
15,100.00	7,289.00	15,242.84	7,289.00	92.90	92.80	90.00	-1,458.11	8,001.28	1,319.89	1,134.40	185.49	7.116	
15,200.00	7,289.00	15,342.84	7,289.00	93.98	93.87	90.00	-1,457.39	8,101.28	1,319.89	1,132.24	187.65	7.034	
15,300.00	7,289.00	15,442.84	7,289.00	95.06	94.95	90.00	-1,456.66	8,201.27	1,319.90	1,130.09	189.81	6.954	
15,400.00	7,289.00	15,542.84	7,289.00	96.14	96.03	90.00	-1,455.94	8,301.27	1,319.90	1,127.93	191.97	6.876	
15,500.00	7,289.00	15,642.84	7,289.00	97.22	97.10	90.00	-1,455.21	8,401.27	1,319.90	1,125.77	194.13	6.799	
15,600.00	7,289.00	15,742.84	7,289.00	98.31	98.18	90.00	-1,454.48	8,501.27	1,319.91	1,123.61	196.30	6.724	
15,700.00	7,289.00	15,842.84	7,289.00	99.39	99.26	90.00	-1,453.76	8,601.26	1,319.91	1,121.45	198.47	6.651	
15,800.00	7,289.00	15,942.84	7,289.00	100.48	100.35	90.00	-1,453.03	8,701.26	1,319.92	1,119.28	200.64	6.579	
15,900.00	7,289.00	16,042.84	7,289.00	101.56	101.43	90.00	-1,452.31	8,801.26	1,319.92	1,117.12	202.81	6.508	
16,000.00	7,289.00	16,142.84	7,289.00	102.65	102.51	90.00	-1,451.58	8,901.26	1,319.93	1,114.95	204.98	6.439	
16,100.00	7,289.00	16,242.84	7,289.00	103.74	103.59	90.00	-1,450.85	9,001.25	1,319.93	1,112.78	207.15	6.372	
16,200.00	7,289.00	16,342.84	7,289.00	104.83	104.68	90.00	-1,450.13	9,101.25	1,319.94	1,110.61	209.33	6.306	
16,300.00	7,289.00	16,442.84	7,289.00	105.92	105.76	90.00	-1,449.40	9,201.25	1,319.94	1,108.44	211.50	6.241	
16,400.00	7,289.00	16,542.84	7,289.00	107.01	106.85	90.00	-1,448.68	9,301.25	1,319.95	1,106.26	213.68	6.177	
16,500.00	7,289.00	16,642.84	7,289.00	108.10	107.94	90.00	-1,447.95	9,401.24	1,319.95	1,104.09	215.86	6.115	
16,600.00	7,289.00	16,742.84	7,289.00	109.19	109.03	90.00	-1,447.22	9,501.24	1,319.96	1,101.91	218.04	6.054	
16,700.00	7,289.00	16,842.84	7,289.00	110.28	110.11	90.00	-1,446.50	9,601.24	1,319.96	1,099.74	220.22	5.994	
16,800.00	7,289.00	16,942.84	7,289.00	111.37	111.20	90.00	-1,445.77	9,701.24	1,319.96	1,097.56	222.41	5.935	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A06) Koala 9 Fed Com 122H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
16,900.00	7,289.00	17,042.84	7,289.00	112.46	112.29	90.00	-1,445.05	9,801.23	1,319.97	1,095.38	224.59	5.877	
17,000.00	7,289.00	17,142.84	7,289.00	113.56	113.38	90.00	-1,444.32	9,901.23	1,319.97	1,093.20	226.78	5.821	
17,100.00	7,289.00	17,242.84	7,289.00	114.65	114.47	90.00	-1,443.59	10,001.23	1,319.98	1,091.02	228.96	5.765	
17,200.00	7,289.00	17,342.84	7,289.00	115.75	115.56	90.00	-1,442.87	10,101.22	1,319.98	1,088.83	231.15	5.710	
17,300.00	7,289.00	17,442.84	7,289.00	116.84	116.66	90.00	-1,442.14	10,201.22	1,319.99	1,086.65	233.34	5.657	
17,400.00	7,289.00	17,542.84	7,289.00	117.94	117.75	90.00	-1,441.41	10,301.22	1,319.99	1,084.46	235.53	5.604	
17,500.00	7,289.00	17,642.84	7,289.00	119.03	118.84	90.00	-1,440.69	10,401.22	1,320.00	1,082.28	237.72	5.553	
17,600.00	7,289.00	17,742.84	7,289.00	120.13	119.94	90.00	-1,439.96	10,501.21	1,320.00	1,080.09	239.91	5.502	
17,700.00	7,289.00	17,842.84	7,289.00	121.23	121.03	90.00	-1,439.24	10,601.21	1,320.01	1,077.90	242.11	5.452	
17,800.00	7,289.00	17,942.84	7,289.00	122.33	122.13	90.00	-1,438.51	10,701.21	1,320.01	1,075.71	244.30	5.403	
17,900.00	7,289.00	18,042.84	7,289.00	123.42	123.22	90.00	-1,437.78	10,801.21	1,320.02	1,073.52	246.49	5.355	
18,000.00	7,289.00	18,142.84	7,289.00	124.52	124.32	90.00	-1,437.06	10,901.20	1,320.02	1,071.33	248.69	5.308	
18,100.00	7,289.00	18,242.84	7,289.00	125.62	125.41	90.00	-1,436.33	11,001.20	1,320.02	1,069.14	250.89	5.261	
18,101.43	7,289.00	18,244.27	7,289.00	125.64	125.43	90.00	-1,436.32	11,002.63	1,320.02	1,069.11	250.92	5.261	
18,159.20	7,289.00	18,274.81	7,289.00	126.27	125.76	90.00	-1,436.10	11,033.17	1,320.31	1,068.33	251.97	5.240	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A07) Koala 9 Fed Com 111H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
400.00	400.00	400.00	400.00	1.20	1.20	90.96	-1.00	59.99	60.00	57.60	2.40	24.981			
500.00	500.00	500.00	500.00	1.56	1.56	90.96	-1.00	59.99	60.00	56.88	3.12	19.238			
600.00	600.00	600.00	600.00	1.92	1.92	90.96	-1.00	59.99	60.00	56.16	3.84	15.642			
700.00	700.00	700.00	700.00	2.28	2.28	90.96	-1.00	59.99	60.00	55.45	4.55	13.179			
800.00	800.00	800.00	800.00	2.63	2.63	90.96	-1.00	59.99	60.00	54.73	5.27	11.386			
900.00	900.00	900.00	900.00	2.99	2.99	90.96	-1.00	59.99	60.00	54.01	5.99	10.022			
1,000.00	1,000.00	1,000.00	1,000.00	3.35	3.35	90.96	-1.00	59.99	60.00	53.29	6.70	8.950			
1,100.00	1,100.00	1,100.00	1,100.00	3.71	3.71	90.96	-1.00	59.99	60.00	52.58	7.42	8.086			
1,200.00	1,200.00	1,200.00	1,200.00	4.07	4.07	90.96	-1.00	59.99	60.00	51.86	8.14	7.373 CC			
1,300.00	1,299.99	1,300.39	1,300.38	4.41	4.41	-107.48	-2.27	59.64	60.07	51.25	8.82	6.810			
1,400.96	1,400.86	1,401.74	1,401.64	4.74	4.74	-107.40	-6.14	58.58	60.27	50.79	9.48	6.358			
1,500.00	1,499.77	1,500.78	1,500.55	5.07	5.07	-107.34	-11.14	57.21	60.55	50.41	10.13	5.974			
1,600.00	1,599.63	1,600.78	1,600.41	5.40	5.41	-107.29	-16.20	55.82	60.82	50.02	10.80	5.630			
1,700.00	1,699.49	1,700.78	1,700.27	5.74	5.74	-107.23	-21.26	54.43	61.10	49.62	11.48	5.322			
1,800.00	1,799.36	1,800.78	1,800.14	6.08	6.08	-107.17	-26.31	53.05	61.38	49.22	12.16	5.047			
1,900.00	1,899.22	1,900.78	1,900.00	6.43	6.43	-107.11	-31.37	51.66	61.66	48.81	12.85	4.799			
2,000.00	1,999.08	2,000.78	1,999.86	6.77	6.77	-107.05	-36.43	50.27	61.94	48.40	13.54	4.575			
2,100.00	2,098.94	2,100.78	2,099.72	7.12	7.12	-107.00	-41.48	48.88	62.22	47.99	14.23	4.372			
2,200.00	2,198.80	2,200.78	2,199.59	7.47	7.47	-106.94	-46.54	47.50	62.50	47.57	14.93	4.187			
2,300.00	2,298.66	2,300.78	2,299.45	7.81	7.82	-106.89	-51.60	46.11	62.78	47.15	15.63	4.017			
2,400.00	2,398.53	2,400.78	2,399.31	8.17	8.17	-106.83	-56.65	44.72	63.06	46.73	16.33	3.862			
2,500.00	2,498.39	2,500.78	2,499.17	8.52	8.52	-106.78	-61.71	43.34	63.34	46.31	17.03	3.719			
2,600.00	2,598.25	2,600.78	2,599.03	8.87	8.87	-106.72	-66.76	41.95	63.62	45.88	17.74	3.587			
2,700.00	2,698.11	2,700.78	2,698.90	9.22	9.22	-106.67	-71.82	40.56	63.90	45.46	18.44	3.465			
2,800.00	2,797.97	2,800.78	2,798.76	9.58	9.58	-106.61	-76.88	39.17	64.18	45.03	19.15	3.351			
2,900.00	2,897.83	2,900.78	2,898.62	9.93	9.93	-106.56	-81.93	37.79	64.46	44.60	19.86	3.246			
3,000.00	2,997.69	3,000.77	2,998.48	10.29	10.29	-106.51	-86.99	36.40	64.74	44.17	20.57	3.148			
3,100.00	3,097.56	3,100.77	3,098.34	10.64	10.64	-106.46	-92.05	35.01	65.02	43.74	21.28	3.056			
3,200.00	3,197.42	3,200.77	3,198.21	11.00	11.00	-106.41	-97.10	33.63	65.30	43.31	21.99	2.969			
3,300.00	3,297.28	3,300.77	3,298.07	11.35	11.35	-106.36	-102.16	32.24	65.58	42.88	22.70	2.889			
3,400.00	3,397.14	3,400.77	3,397.93	11.71	11.71	-106.30	-107.22	30.85	65.86	42.44	23.42	2.813			
3,500.00	3,497.00	3,500.77	3,497.79	12.07	12.07	-106.25	-112.27	29.46	66.14	42.01	24.13	2.741			
3,600.00	3,596.86	3,600.77	3,597.65	12.42	12.42	-106.21	-117.33	28.08	66.42	41.57	24.84	2.673			
3,700.00	3,696.73	3,700.77	3,697.52	12.78	12.78	-106.16	-122.38	26.69	66.70	41.14	25.56	2.610			
3,800.00	3,796.59	3,800.77	3,797.38	13.14	13.14	-106.11	-127.44	25.30	66.98	40.70	26.27	2.549			
3,900.00	3,896.45	3,900.77	3,897.24	13.50	13.50	-106.06	-132.50	23.92	67.26	40.27	26.99	2.492			
4,000.00	3,996.31	4,000.77	3,997.10	13.86	13.86	-106.01	-137.55	22.53	67.54	39.83	27.70	2.438			
4,100.00	4,096.17	4,100.77	4,096.96	14.21	14.21	-105.96	-142.61	21.14	67.82	39.40	28.42	2.386			
4,200.00	4,196.03	4,200.77	4,196.83	14.57	14.57	-105.92	-147.67	19.75	68.10	38.96	29.14	2.337			
4,300.00	4,295.90	4,300.77	4,296.69	14.93	14.93	-105.87	-152.72	18.37	68.38	38.52	29.86	2.290			
4,400.00	4,395.76	4,400.77	4,396.55	15.29	15.29	-105.82	-157.78	16.98	68.66	38.09	30.57	2.246			
4,500.00	4,495.62	4,500.77	4,496.41	15.65	15.65	-105.78	-162.84	15.59	68.94	37.65	31.29	2.203			
4,600.00	4,595.48	4,600.77	4,596.27	16.01	16.01	-105.73	-167.89	14.21	69.22	37.21	32.01	2.163			
4,700.00	4,695.34	4,700.77	4,696.14	16.37	16.37	-105.69	-172.95	12.82	69.50	36.77	32.73	2.124			
4,803.94	4,799.14	4,804.70	4,799.93	16.74	16.74	-105.64	-178.20	11.38	69.79	36.32	33.47	2.085			
4,900.00	4,895.12	4,900.39	4,895.53	17.09	17.08	-105.61	-181.88	10.37	70.00	35.84	34.16	2.049			
5,004.89	5,000.00	5,004.87	5,000.00	17.45	17.45	92.85	-183.26	9.99	70.08	35.19	34.89	2.009			
5,100.00	5,095.11	5,099.97	5,095.11	17.77	17.76	92.85	-183.26	9.99	70.08	34.55	35.52	1.973			
5,200.00	5,195.11	5,199.97	5,195.11	18.10	18.10	92.85	-183.26	9.99	70.08	33.88	36.20	1.936			
5,300.00	5,295.11	5,299.97	5,295.11	18.44	18.44	92.85	-183.26	9.99	70.08	33.21	36.87	1.901			
5,400.00	5,395.11	5,399.97	5,395.11	18.78	18.78	92.85	-183.26	9.99	70.08	32.53	37.54	1.867			
5,500.00	5,495.11	5,499.97	5,495.11	19.12	19.11	92.85	-183.26	9.99	70.08	31.86	38.22	1.833			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A07) Koala 9 Fed Com 111H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Rule Assigned:		Distance		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
5,600.00	5,595.11	5,599.97	5,595.11	19.46	19.45	92.85	-183.26	9.99	70.08	31.18	38.90	1.801	
5,607.38	5,602.49	5,607.36	5,602.49	19.48	19.48	92.85	-183.26	9.99	70.08	31.13	38.95	1.799 ES, SF	
5,700.00	5,695.11	5,693.97	5,689.05	19.80	19.77	92.80	-183.29	12.00	72.34	32.92	39.42	1.835	
5,800.00	5,795.11	5,780.65	5,774.55	20.14	20.07	92.50	-183.51	25.76	88.27	49.04	39.23	2.250	
5,900.00	5,895.11	5,861.51	5,851.59	20.48	20.33	92.14	-183.89	50.07	118.44	80.05	38.39	3.085	
6,000.00	5,995.11	5,934.30	5,917.41	20.82	20.54	91.87	-184.38	81.04	161.09	123.97	37.13	4.339	
6,100.00	6,095.11	6,000.00	5,973.02	21.16	20.72	91.68	-184.92	115.96	214.22	178.40	35.83	5.980	
6,200.00	6,195.11	6,050.00	6,012.46	21.51	20.84	91.56	-185.41	146.66	275.87	241.97	33.90	8.138	
6,300.00	6,295.11	6,100.00	6,049.07	21.85	20.97	91.47	-185.94	180.69	344.25	311.54	32.70	10.527	
6,400.00	6,395.11	6,150.00	6,082.57	22.19	21.12	91.39	-186.52	217.78	418.19	386.21	31.98	13.075	
6,500.00	6,495.11	6,176.16	6,098.78	22.54	21.19	91.36	-186.85	238.31	496.10	465.75	30.35	16.345	
6,600.00	6,595.11	6,200.00	6,112.72	22.88	21.26	91.33	-187.15	257.64	577.63	548.51	29.11	19.840	
6,700.00	6,695.11	6,232.07	6,130.17	23.23	21.35	91.30	-187.57	284.54	661.75	633.18	28.57	23.163	
6,720.93	6,716.04	6,250.00	6,139.27	23.30	21.40	91.28	-187.82	299.99	679.94	651.03	28.91	23.517	
6,750.00	6,745.09	6,250.00	6,139.27	23.40	21.40	0.07	-187.82	299.99	704.38	675.96	28.42	24.786	
11,400.00	7,289.00	10,254.93	6,214.00	54.14	51.82	0.02	-165.70	4,291.80	1,075.00	1,031.55	43.45	24.740	
11,500.00	7,289.00	10,354.93	6,214.00	55.13	52.84	0.02	-164.96	4,391.80	1,075.00	1,030.75	44.25	24.292	
11,600.00	7,289.00	10,454.93	6,214.00	56.13	53.86	0.02	-164.23	4,491.79	1,075.00	1,029.94	45.06	23.858	
11,700.00	7,289.00	10,554.93	6,214.00	57.13	54.89	0.02	-163.49	4,591.79	1,075.00	1,029.13	45.87	23.437	
11,800.00	7,289.00	10,654.93	6,214.00	58.14	55.93	0.02	-162.75	4,691.79	1,075.00	1,028.32	46.68	23.028	
11,900.00	7,289.00	10,754.93	6,214.00	59.16	56.97	0.02	-162.02	4,791.78	1,075.00	1,027.50	47.50	22.632	
12,000.00	7,289.00	10,854.93	6,214.00	60.17	58.01	0.02	-161.28	4,891.78	1,075.00	1,026.68	48.32	22.248	
12,100.00	7,289.00	10,954.93	6,214.00	61.19	59.05	0.02	-160.54	4,991.78	1,075.00	1,025.86	49.14	21.876	
12,200.00	7,289.00	11,054.93	6,214.00	62.22	60.09	0.02	-159.81	5,091.78	1,075.00	1,025.03	49.97	21.514	
12,300.00	7,289.00	11,154.93	6,214.00	63.24	61.14	0.02	-159.07	5,191.77	1,075.00	1,024.20	50.80	21.163	
12,400.00	7,289.00	11,254.93	6,214.00	64.27	62.19	0.02	-158.33	5,291.77	1,075.00	1,023.37	51.63	20.822	
12,500.00	7,289.00	11,354.93	6,214.00	65.31	63.25	0.02	-157.60	5,391.77	1,075.00	1,022.54	52.46	20.491	
12,600.00	7,289.00	11,454.93	6,214.00	66.34	64.30	0.02	-156.86	5,491.77	1,075.00	1,021.70	53.30	20.170	
12,700.00	7,289.00	11,554.93	6,214.00	67.38	65.36	0.02	-156.12	5,591.76	1,075.00	1,020.86	54.14	19.857	
12,800.00	7,289.00	11,654.93	6,214.00	68.42	66.42	0.02	-155.39	5,691.76	1,075.00	1,020.02	54.98	19.553	
12,900.00	7,289.00	11,754.93	6,214.00	69.47	67.49	0.02	-154.65	5,791.76	1,075.00	1,019.18	55.82	19.258	
13,000.00	7,289.00	11,854.93	6,214.00	70.51	68.55	0.02	-153.91	5,891.75	1,075.00	1,018.33	56.67	18.971	
13,100.00	7,289.00	11,954.93	6,214.00	71.56	69.62	0.02	-153.18	5,991.75	1,075.00	1,017.49	57.51	18.691	
13,200.00	7,289.00	12,054.93	6,214.00	72.61	70.68	0.02	-152.44	6,091.75	1,075.00	1,016.64	58.36	18.419	
13,300.00	7,289.00	12,154.93	6,214.00	73.67	71.75	0.02	-151.70	6,191.75	1,075.00	1,015.79	59.21	18.155	
13,400.00	7,289.00	12,254.93	6,214.00	74.72	72.82	0.02	-150.97	6,291.74	1,075.00	1,014.93	60.07	17.897	
13,500.00	7,289.00	12,354.93	6,214.00	75.78	73.90	0.01	-150.23	6,391.74	1,075.00	1,014.08	60.92	17.646	
13,600.00	7,289.00	12,454.93	6,214.00	76.84	74.97	0.01	-149.49	6,491.74	1,075.00	1,013.22	61.78	17.402	
13,700.00	7,289.00	12,554.93	6,214.00	77.90	76.05	0.01	-148.76	6,591.74	1,075.00	1,012.37	62.63	17.164	
13,800.00	7,289.00	12,654.93	6,214.00	78.96	77.12	0.01	-148.02	6,691.73	1,075.00	1,011.51	63.49	16.932	
13,900.00	7,289.00	12,754.93	6,214.00	80.02	78.20	0.01	-147.28	6,791.73	1,075.00	1,010.65	64.35	16.705	
14,000.00	7,289.00	12,854.93	6,214.00	81.09	79.28	0.01	-146.55	6,891.73	1,075.00	1,009.79	65.21	16.485	
14,100.00	7,289.00	12,954.93	6,214.00	82.15	80.36	0.01	-145.81	6,991.73	1,075.00	1,008.93	66.07	16.269	
14,200.00	7,289.00	13,054.93	6,214.00	83.22	81.44	0.01	-145.07	7,091.72	1,075.00	1,008.06	66.94	16.060	
14,300.00	7,289.00	13,154.93	6,214.00	84.29	82.52	0.01	-144.34	7,191.72	1,075.00	1,007.20	67.80	15.855	
14,400.00	7,289.00	13,254.93	6,214.00	85.36	83.61	0.01	-143.60	7,291.72	1,075.00	1,006.33	68.67	15.655	
14,500.00	7,289.00	13,354.93	6,214.00	86.44	84.69	0.01	-142.86	7,391.71	1,075.00	1,005.46	69.54	15.460	
14,600.00	7,289.00	13,454.93	6,214.00	87.51	85.78	0.01	-142.13	7,491.71	1,075.00	1,004.60	70.40	15.269	
14,700.00	7,289.00	13,554.93	6,214.00	88.58	86.87	0.01	-141.39	7,591.71	1,075.00	1,003.73	71.27	15.083	
14,800.00	7,289.00	13,654.93	6,214.00	89.66	87.95	0.01	-140.65	7,691.71	1,075.00	1,002.86	72.14	14.901	
14,900.00	7,289.00	13,754.93	6,214.00	90.74	89.04	0.01	-139.92	7,791.70	1,075.00	1,001.99	73.01	14.723	
15,000.00	7,289.00	13,854.93	6,214.00	91.82	90.13	0.01	-139.18	7,891.70	1,075.00	1,001.11	73.89	14.549	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A07) Koala 9 Fed Com 111H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance		Rule Assigned:		Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
15,100.00	7,289.00	13,954.93	6,214.00	92.90	91.22	0.01	-138.45	7,991.70	1,075.00	1,000.24	74.76	14.379	
15,200.00	7,289.00	14,054.93	6,214.00	93.98	92.31	0.01	-137.71	8,091.70	1,075.00	999.37	75.63	14.213	
15,300.00	7,289.00	14,154.93	6,214.00	95.06	93.40	0.01	-136.97	8,191.69	1,075.00	998.49	76.51	14.051	
15,400.00	7,289.00	14,254.93	6,214.00	96.14	94.49	0.01	-136.24	8,291.69	1,075.00	997.62	77.38	13.892	
15,500.00	7,289.00	14,354.93	6,214.00	97.22	95.59	0.01	-135.50	8,391.69	1,075.00	996.74	78.26	13.736	
15,600.00	7,289.00	14,454.93	6,214.00	98.31	96.68	0.01	-134.76	8,491.68	1,075.00	995.86	79.14	13.584	
15,700.00	7,289.00	14,554.93	6,214.00	99.39	97.77	0.01	-134.03	8,591.68	1,075.00	994.99	80.01	13.435	
15,800.00	7,289.00	14,654.93	6,214.00	100.48	98.87	0.01	-133.29	8,691.68	1,075.00	994.11	80.89	13.289	
15,900.00	7,289.00	14,754.93	6,214.00	101.56	99.96	0.01	-132.55	8,791.68	1,075.00	993.23	81.77	13.147	
16,000.00	7,289.00	14,854.93	6,214.00	102.65	101.06	0.01	-131.82	8,891.67	1,075.00	992.35	82.65	13.007	
16,100.00	7,289.00	14,954.93	6,214.00	103.74	102.16	0.01	-131.08	8,991.67	1,075.00	991.47	83.53	12.870	
16,200.00	7,289.00	15,054.93	6,214.00	104.83	103.25	0.01	-130.34	9,091.67	1,075.00	990.59	84.41	12.735	
16,300.00	7,289.00	15,154.93	6,214.00	105.92	104.35	0.01	-129.61	9,191.67	1,075.00	989.71	85.29	12.604	
16,400.00	7,289.00	15,254.93	6,214.00	107.01	105.45	0.01	-128.87	9,291.66	1,075.00	988.83	86.17	12.475	
16,500.00	7,289.00	15,354.93	6,214.00	108.10	106.55	0.01	-128.13	9,391.66	1,075.00	987.94	87.06	12.348	
16,600.00	7,289.00	15,454.93	6,214.00	109.19	107.65	0.00	-127.40	9,491.66	1,075.00	987.06	87.94	12.224	
16,700.00	7,289.00	15,554.93	6,214.00	110.28	108.75	0.00	-126.66	9,591.65	1,075.00	986.18	88.82	12.103	
16,800.00	7,289.00	15,654.93	6,214.00	111.37	109.85	0.00	-125.92	9,691.65	1,075.00	985.29	89.71	11.983	
16,900.00	7,289.00	15,754.93	6,214.00	112.46	110.95	0.00	-125.19	9,791.65	1,075.00	984.41	90.59	11.866	
17,000.00	7,289.00	15,854.93	6,214.00	113.56	112.05	0.00	-124.45	9,891.65	1,075.00	983.52	91.48	11.752	
17,100.00	7,289.00	15,954.93	6,214.00	114.65	113.15	0.00	-123.71	9,991.64	1,075.00	982.64	92.36	11.639	
17,200.00	7,289.00	16,054.93	6,214.00	115.75	114.25	0.00	-122.98	10,091.64	1,075.00	981.75	93.25	11.528	
17,300.00	7,289.00	16,154.93	6,214.00	116.84	115.35	0.00	-122.24	10,191.64	1,075.00	980.87	94.13	11.420	
17,400.00	7,289.00	16,254.93	6,214.00	117.94	116.46	0.00	-121.50	10,291.64	1,075.00	979.98	95.02	11.313	
17,500.00	7,289.00	16,354.93	6,214.00	119.03	117.56	0.00	-120.77	10,391.63	1,075.00	979.09	95.91	11.209	
17,600.00	7,289.00	16,454.93	6,214.00	120.13	118.66	0.00	-120.03	10,491.63	1,075.00	978.20	96.80	11.106	
17,700.00	7,289.00	16,554.93	6,214.00	121.23	119.77	0.00	-119.29	10,591.63	1,075.00	977.32	97.68	11.005	
17,800.00	7,289.00	16,654.93	6,214.00	122.33	120.87	0.00	-118.56	10,691.62	1,075.00	976.43	98.57	10.906	
17,900.00	7,289.00	16,754.93	6,214.00	123.42	121.97	0.00	-117.82	10,791.62	1,075.00	975.54	99.46	10.808	
18,000.00	7,289.00	16,854.93	6,214.00	124.52	123.08	0.00	-117.08	10,891.62	1,075.00	974.65	100.35	10.712	
18,100.00	7,289.00	16,954.93	6,214.00	125.62	124.18	0.00	-116.35	10,991.62	1,075.00	973.76	101.24	10.618	
18,139.65	7,289.00	16,994.58	6,214.00	126.06	124.62	0.00	-116.05	11,031.26	1,075.00	973.41	101.59	10.581	
18,159.20	7,289.00	17,014.12	6,214.00	126.27	124.84	0.00	-115.91	11,050.81	1,075.00	973.23	101.77	10.563	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A08) Koala 9 Fed Com 112H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
600.00	600.00	600.00	600.00	1.92	1.92	90.95	-1.50	89.99	90.00	86.17	3.84	23.465	
700.00	700.00	700.00	700.00	2.28	2.28	90.95	-1.50	89.99	90.00	85.45	4.55	19.770	
800.00	800.00	800.00	800.00	2.63	2.63	90.95	-1.50	89.99	90.00	84.73	5.27	17.080	
863.12	863.12	863.12	863.12	2.86	2.85	91.29	-2.02	89.98	90.00	84.29	5.71	15.760 CC	
900.00	900.00	900.00	899.99	2.99	2.98	91.79	-2.81	89.96	90.00	84.04	5.97	15.080	
1,000.00	1,000.00	999.84	999.75	3.35	3.31	94.28	-6.73	89.87	90.12	83.47	6.65	13.543	
1,100.00	1,100.00	1,099.43	1,099.12	3.71	3.64	98.39	-13.23	89.73	90.70	83.35	7.35	12.348 ES	
1,200.00	1,200.00	1,198.60	1,197.88	4.07	3.98	103.97	-22.27	89.52	92.28	84.24	8.04	11.478	
1,300.00	1,299.99	1,297.39	1,295.99	4.41	4.31	-88.42	-33.83	89.26	95.50	86.78	8.72	10.957	
1,400.96	1,400.86	1,396.84	1,394.41	4.74	4.66	-82.88	-48.02	88.94	100.51	91.13	9.38	10.711	
1,500.00	1,499.77	1,493.97	1,490.16	5.07	5.00	-77.59	-64.35	88.58	107.22	97.19	10.04	10.681	
1,600.00	1,599.63	1,591.38	1,585.73	5.40	5.35	-71.91	-83.17	88.16	116.29	105.59	10.70	10.873	
1,700.00	1,699.49	1,688.02	1,680.04	5.74	5.70	-66.27	-104.23	87.68	128.00	116.66	11.34	11.286	
1,800.00	1,799.36	1,783.76	1,772.92	6.08	6.06	-60.95	-127.45	87.16	142.58	130.60	11.97	11.907	
1,900.00	1,899.22	1,878.50	1,864.23	6.43	6.42	-56.11	-152.71	86.59	160.10	147.51	12.59	12.713	
2,000.00	1,999.08	1,972.55	1,954.23	6.77	6.78	-51.82	-180.00	85.98	180.55	167.35	13.20	13.676	
2,100.00	2,098.94	2,069.33	2,046.57	7.12	7.15	-48.15	-208.98	85.33	202.65	188.79	13.86	14.620	
2,200.00	2,198.80	2,166.12	2,138.91	7.47	7.53	-45.20	-237.96	84.68	225.39	210.87	14.53	15.515	
2,300.00	2,298.66	2,262.90	2,231.25	7.81	7.92	-42.80	-266.94	84.03	248.60	233.41	15.20	16.357	
2,400.00	2,398.53	2,359.68	2,323.58	8.17	8.31	-40.80	-295.92	83.38	272.16	256.29	15.87	17.146	
2,500.00	2,498.39	2,456.46	2,415.92	8.52	8.70	-39.12	-324.90	82.73	295.98	279.43	16.55	17.882	
2,600.00	2,598.25	2,553.24	2,508.26	8.87	9.09	-37.69	-353.88	82.07	320.01	302.78	17.23	18.569	
2,700.00	2,698.11	2,650.03	2,600.60	9.22	9.48	-36.46	-382.86	81.42	344.20	326.28	17.92	19.210	
2,800.00	2,797.97	2,746.81	2,692.94	9.58	9.88	-35.39	-411.84	80.77	368.52	349.91	18.60	19.808	
2,900.00	2,897.83	2,843.59	2,785.28	9.93	10.28	-34.46	-440.82	80.12	392.94	373.65	19.29	20.368	
3,000.00	2,997.69	2,940.37	2,877.62	10.29	10.68	-33.63	-469.80	79.47	417.46	397.48	19.98	20.891	
3,100.00	3,097.56	3,037.16	2,969.96	10.64	11.08	-32.89	-498.77	78.82	442.04	421.37	20.67	21.382	
3,200.00	3,197.42	3,133.94	3,062.30	11.00	11.48	-32.23	-527.75	78.17	466.69	445.33	21.37	21.843	
3,300.00	3,297.28	3,230.72	3,154.64	11.35	11.88	-31.64	-556.73	77.52	491.39	469.33	22.06	22.276	
3,400.00	3,397.14	3,327.50	3,246.98	11.71	12.29	-31.11	-585.71	76.87	516.14	493.38	22.75	22.683	
3,500.00	3,497.00	3,424.29	3,339.32	12.07	12.69	-30.62	-614.69	76.22	540.92	517.47	23.45	23.067	
3,600.00	3,596.86	3,521.07	3,431.66	12.42	13.10	-30.18	-643.67	75.56	565.74	541.59	24.15	23.430	
3,700.00	3,696.73	3,617.85	3,524.00	12.78	13.50	-29.77	-672.65	74.91	590.59	565.74	24.84	23.772	
3,800.00	3,796.59	3,714.63	3,616.34	13.14	13.91	-29.39	-701.63	74.26	615.46	589.92	25.54	24.097	
3,900.00	3,896.45	3,811.41	3,708.68	13.50	14.32	-29.05	-730.61	73.61	640.35	614.11	26.24	24.404	
4,000.00	3,996.31	3,908.20	3,801.02	13.86	14.72	-28.73	-759.59	72.96	665.27	638.33	26.94	24.696	
4,100.00	4,096.17	4,004.98	3,893.36	14.21	15.13	-28.43	-788.57	72.31	690.20	662.56	27.64	24.973	
10,100.00	7,289.00	9,131.87	6,214.00	41.80	39.49	50.85	-1,495.19	3,001.54	1,702.69	1,633.49	69.20	24.604	
10,200.00	7,289.00	9,231.87	6,214.00	42.69	40.40	50.85	-1,494.46	3,101.54	1,702.69	1,632.03	70.66	24.097	
10,300.00	7,289.00	9,331.87	6,214.00	43.60	41.32	50.85	-1,493.72	3,201.54	1,702.68	1,630.55	72.13	23.605	
10,400.00	7,289.00	9,431.87	6,214.00	44.52	42.25	50.85	-1,492.98	3,301.54	1,702.68	1,629.06	73.62	23.127	
10,500.00	7,289.00	9,531.87	6,214.00	45.45	43.19	50.85	-1,492.25	3,401.53	1,702.67	1,627.55	75.12	22.665	
10,600.00	7,289.00	9,631.87	6,214.00	46.39	44.14	50.85	-1,491.51	3,501.53	1,702.67	1,626.03	76.64	22.216	
10,700.00	7,289.00	9,731.87	6,214.00	47.33	45.10	50.85	-1,490.78	3,601.53	1,702.67	1,624.50	78.17	21.781	
10,800.00	7,289.00	9,831.87	6,214.00	48.28	46.06	50.85	-1,490.04	3,701.53	1,702.66	1,622.95	79.71	21.360	
10,900.00	7,289.00	9,931.87	6,214.00	49.24	47.04	50.85	-1,489.31	3,801.52	1,702.66	1,621.39	81.27	20.952	
11,000.00	7,289.00	10,031.87	6,214.00	50.21	48.01	50.85	-1,488.57	3,901.52	1,702.66	1,619.83	82.83	20.556	
11,100.00	7,289.00	10,131.87	6,214.00	51.18	49.00	50.85	-1,487.83	4,001.52	1,702.65	1,618.25	84.40	20.173	
11,200.00	7,289.00	10,231.87	6,214.00	52.16	49.99	50.85	-1,487.10	4,101.51	1,702.65	1,616.66	85.99	19.801	
11,300.00	7,289.00	10,331.87	6,214.00	53.15	50.99	50.85	-1,486.36	4,201.51	1,702.64	1,615.06	87.58	19.441	
11,400.00	7,289.00	10,431.87	6,214.00	54.14	51.99	50.85	-1,485.63	4,301.51	1,702.64	1,613.46	89.18	19.092	
11,500.00	7,289.00	10,531.87	6,214.00	55.13	52.99	50.85	-1,484.89	4,401.51	1,702.64	1,611.84	90.79	18.753	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A08) Koala 9 Fed Com 112H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
11,600.00	7,289.00	10,631.87	6,214.00	56.13	54.01	50.85	-1,484.16	4,501.50	1,702.63	1,610.22	92.41	18.425	
11,700.00	7,289.00	10,731.87	6,214.00	57.13	55.02	50.85	-1,483.42	4,601.50	1,702.63	1,608.59	94.04	18.106	
11,800.00	7,289.00	10,831.87	6,214.00	58.14	56.04	50.85	-1,482.68	4,701.50	1,702.62	1,606.96	95.67	17.797	
11,900.00	7,289.00	10,931.87	6,214.00	59.16	57.06	50.85	-1,481.95	4,801.50	1,702.62	1,605.31	97.31	17.497	
12,000.00	7,289.00	11,031.87	6,214.00	60.17	58.09	50.85	-1,481.21	4,901.49	1,702.62	1,603.66	98.95	17.206	
12,100.00	7,289.00	11,131.87	6,214.00	61.19	59.12	50.85	-1,480.48	5,001.49	1,702.61	1,602.01	100.60	16.924	
12,200.00	7,289.00	11,231.87	6,214.00	62.22	60.16	50.85	-1,479.74	5,101.49	1,702.61	1,600.35	102.26	16.650	
12,300.00	7,289.00	11,331.87	6,214.00	63.24	61.19	50.85	-1,479.01	5,201.48	1,702.61	1,598.68	103.92	16.383	
12,400.00	7,289.00	11,431.87	6,214.00	64.27	62.23	50.85	-1,478.27	5,301.48	1,702.60	1,597.01	105.59	16.124	
12,500.00	7,289.00	11,531.87	6,214.00	65.31	63.28	50.85	-1,477.53	5,401.48	1,702.60	1,595.33	107.26	15.873	
12,600.00	7,289.00	11,631.87	6,214.00	66.34	64.32	50.85	-1,476.80	5,501.48	1,702.59	1,593.65	108.94	15.629	
12,700.00	7,289.00	11,731.87	6,214.00	67.38	65.37	50.85	-1,476.06	5,601.47	1,702.59	1,591.97	110.62	15.391	
12,800.00	7,289.00	11,831.87	6,214.00	68.42	66.42	50.85	-1,475.33	5,701.47	1,702.59	1,590.28	112.31	15.160	
12,900.00	7,289.00	11,931.87	6,214.00	69.47	67.47	50.85	-1,474.59	5,801.47	1,702.58	1,588.58	114.00	14.935	
13,000.00	7,289.00	12,031.87	6,214.00	70.51	68.53	50.85	-1,473.86	5,901.47	1,702.58	1,586.88	115.69	14.716	
13,100.00	7,289.00	12,131.87	6,214.00	71.56	69.59	50.85	-1,473.12	6,001.46	1,702.57	1,585.18	117.39	14.503	
13,200.00	7,289.00	12,231.87	6,214.00	72.61	70.65	50.85	-1,472.38	6,101.46	1,702.57	1,583.48	119.09	14.296	
13,300.00	7,289.00	12,331.87	6,214.00	73.67	71.71	50.85	-1,471.65	6,201.46	1,702.57	1,581.77	120.80	14.094	
13,400.00	7,289.00	12,431.87	6,214.00	74.72	72.77	50.85	-1,470.91	6,301.46	1,702.56	1,580.06	122.51	13.898	
13,500.00	7,289.00	12,531.87	6,214.00	75.78	73.84	50.85	-1,470.18	6,401.45	1,702.56	1,578.34	124.22	13.706	
13,600.00	7,289.00	12,631.87	6,214.00	76.84	74.90	50.85	-1,469.44	6,501.45	1,702.55	1,576.62	125.93	13.520	
13,700.00	7,289.00	12,731.87	6,214.00	77.90	75.97	50.85	-1,468.71	6,601.45	1,702.55	1,574.90	127.65	13.338	
13,800.00	7,289.00	12,831.87	6,214.00	78.96	77.04	50.85	-1,467.97	6,701.44	1,702.55	1,573.18	129.37	13.160	
13,900.00	7,289.00	12,931.87	6,214.00	80.02	78.11	50.85	-1,467.23	6,801.44	1,702.54	1,571.45	131.09	12.987	
14,000.00	7,289.00	13,031.87	6,214.00	81.09	79.18	50.85	-1,466.50	6,901.44	1,702.54	1,569.72	132.82	12.819	
14,100.00	7,289.00	13,131.87	6,214.00	82.15	80.26	50.85	-1,465.76	7,001.44	1,702.54	1,567.99	134.55	12.654	
14,200.00	7,289.00	13,231.87	6,214.00	83.22	81.33	50.85	-1,465.03	7,101.43	1,702.53	1,566.25	136.28	12.493	
14,300.00	7,289.00	13,331.87	6,214.00	84.29	82.41	50.85	-1,464.29	7,201.43	1,702.53	1,564.52	138.01	12.336	
14,400.00	7,289.00	13,431.87	6,214.00	85.36	83.49	50.85	-1,463.56	7,301.43	1,702.52	1,562.78	139.74	12.183	
14,500.00	7,289.00	13,531.87	6,214.00	86.44	84.57	50.85	-1,462.82	7,401.43	1,702.52	1,561.04	141.48	12.034	
14,600.00	7,289.00	13,631.87	6,214.00	87.51	85.65	50.85	-1,462.08	7,501.42	1,702.52	1,559.30	143.22	11.887	
14,700.00	7,289.00	13,731.87	6,214.00	88.58	86.73	50.85	-1,461.35	7,601.42	1,702.51	1,557.55	144.96	11.745	
14,800.00	7,289.00	13,831.87	6,214.00	89.66	87.81	50.84	-1,460.61	7,701.42	1,702.51	1,555.80	146.70	11.605	
14,900.00	7,289.00	13,931.87	6,214.00	90.74	88.89	50.84	-1,459.88	7,801.41	1,702.50	1,554.06	148.45	11.469	
15,000.00	7,289.00	14,031.87	6,214.00	91.82	89.98	50.84	-1,459.14	7,901.41	1,702.50	1,552.30	150.20	11.335	
15,100.00	7,289.00	14,131.87	6,214.00	92.90	91.06	50.84	-1,458.41	8,001.41	1,702.50	1,550.55	151.94	11.205	
15,200.00	7,289.00	14,231.87	6,214.00	93.98	92.15	50.84	-1,457.67	8,101.41	1,702.49	1,548.80	153.69	11.077	
15,300.00	7,289.00	14,331.87	6,214.00	95.06	93.23	50.84	-1,456.93	8,201.40	1,702.49	1,547.04	155.45	10.952	
15,400.00	7,289.00	14,431.87	6,214.00	96.14	94.32	50.84	-1,456.20	8,301.40	1,702.48	1,545.29	157.20	10.830	
15,500.00	7,289.00	14,531.87	6,214.00	97.22	95.41	50.84	-1,455.46	8,401.40	1,702.48	1,543.53	158.95	10.711	
15,600.00	7,289.00	14,631.87	6,214.00	98.31	96.50	50.84	-1,454.73	8,501.40	1,702.48	1,541.77	160.71	10.594	
15,700.00	7,289.00	14,731.87	6,214.00	99.39	97.59	50.84	-1,453.99	8,601.39	1,702.47	1,540.01	162.47	10.479	
15,800.00	7,289.00	14,831.87	6,214.00	100.48	98.68	50.84	-1,453.26	8,701.39	1,702.47	1,538.24	164.23	10.367	
15,900.00	7,289.00	14,931.87	6,214.00	101.56	99.77	50.84	-1,452.52	8,801.39	1,702.47	1,536.48	165.99	10.257	
16,000.00	7,289.00	15,031.87	6,214.00	102.65	100.86	50.84	-1,451.78	8,901.38	1,702.46	1,534.71	167.75	10.149	
16,100.00	7,289.00	15,131.87	6,214.00	103.74	101.96	50.84	-1,451.05	9,001.38	1,702.46	1,532.95	169.51	10.043	
16,200.00	7,289.00	15,231.87	6,214.00	104.83	103.05	50.84	-1,450.31	9,101.38	1,702.45	1,531.18	171.27	9.940	
16,300.00	7,289.00	15,331.87	6,214.00	105.92	104.14	50.84	-1,449.58	9,201.38	1,702.45	1,529.41	173.04	9.839	
16,400.00	7,289.00	15,431.87	6,214.00	107.01	105.24	50.84	-1,448.84	9,301.37	1,702.45	1,527.64	174.80	9.739	
16,500.00	7,289.00	15,531.87	6,214.00	108.10	106.33	50.84	-1,448.11	9,401.37	1,702.44	1,525.87	176.57	9.642	
16,600.00	7,289.00	15,631.87	6,214.00	109.19	107.43	50.84	-1,447.37	9,501.37	1,702.44	1,524.10	178.34	9.546	
16,700.00	7,289.00	15,731.87	6,214.00	110.28	108.52	50.84	-1,446.63	9,601.37	1,702.43	1,522.33	180.11	9.452	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (A08) Koala 9 Fed Com 112H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
16,800.00	7,289.00	15,831.87	6,214.00	111.37	109.62	50.84	-1,445.90	9,701.36	1,702.43	1,520.55	181.88	9.360	
16,900.00	7,289.00	15,931.87	6,214.00	112.46	110.72	50.84	-1,445.16	9,801.36	1,702.43	1,518.78	183.65	9.270	
17,000.00	7,289.00	16,031.87	6,214.00	113.56	111.82	50.84	-1,444.43	9,901.36	1,702.42	1,517.00	185.42	9.181	
17,100.00	7,289.00	16,131.87	6,214.00	114.65	112.91	50.84	-1,443.69	10,001.36	1,702.42	1,515.22	187.20	9.094	
17,200.00	7,289.00	16,231.87	6,214.00	115.75	114.01	50.84	-1,442.96	10,101.35	1,702.41	1,513.45	188.97	9.009	
17,300.00	7,289.00	16,331.87	6,214.00	116.84	115.11	50.84	-1,442.22	10,201.35	1,702.41	1,511.67	190.74	8.925	
17,400.00	7,289.00	16,431.87	6,214.00	117.94	116.21	50.84	-1,441.48	10,301.35	1,702.41	1,509.89	192.52	8.843	
17,500.00	7,289.00	16,531.87	6,214.00	119.03	117.31	50.84	-1,440.75	10,401.34	1,702.40	1,508.11	194.30	8.762	
17,600.00	7,289.00	16,631.87	6,214.00	120.13	118.41	50.84	-1,440.01	10,501.34	1,702.40	1,506.33	196.07	8.682	
17,700.00	7,289.00	16,731.87	6,214.00	121.23	119.51	50.84	-1,439.28	10,601.34	1,702.40	1,504.54	197.85	8.604	
17,800.00	7,289.00	16,831.87	6,214.00	122.33	120.61	50.84	-1,438.54	10,701.34	1,702.39	1,502.76	199.63	8.528	
17,900.00	7,289.00	16,931.87	6,214.00	123.42	121.72	50.84	-1,437.81	10,801.33	1,702.39	1,500.98	201.41	8.452	
18,000.00	7,289.00	17,031.87	6,214.00	124.52	122.82	50.84	-1,437.07	10,901.33	1,702.38	1,499.19	203.19	8.378	
18,100.00	7,289.00	17,131.87	6,214.00	125.62	123.92	50.84	-1,436.33	11,001.33	1,702.38	1,497.41	204.97	8.305	
18,131.62	7,289.00	17,163.50	6,214.00	125.97	124.27	50.84	-1,436.10	11,032.95	1,702.38	1,496.84	205.53	8.283	
18,159.20	7,289.00	17,163.72	6,214.00	126.27	124.27	50.84	-1,436.10	11,033.17	1,702.60	1,496.72	205.88	8.270 SF	



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B01) Koala 9 Fed Com 203H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
11,900.00	7,289.00	13,491.32	8,853.00	59.16	61.90	128.35	-2,156.41	4,804.99	2,543.49	2,441.20	102.29	24.866	CC		
12,000.00	7,289.00	13,591.32	8,853.00	60.17	62.86	128.34	-2,155.74	4,904.99	2,543.54	2,439.62	103.92	24.476			
12,100.00	7,289.00	13,691.32	8,853.00	61.19	63.83	128.34	-2,155.08	5,004.99	2,543.60	2,438.03	105.56	24.096			
12,200.00	7,289.00	13,791.32	8,853.00	62.22	64.80	128.34	-2,154.42	5,104.99	2,543.65	2,436.44	107.21	23.726			
12,300.00	7,289.00	13,891.32	8,853.00	63.24	65.78	128.34	-2,153.76	5,204.98	2,543.70	2,434.84	108.86	23.366			
12,400.00	7,289.00	13,991.32	8,853.00	64.27	66.76	128.34	-2,153.10	5,304.98	2,543.76	2,433.23	110.52	23.015			
12,500.00	7,289.00	14,091.32	8,853.00	65.31	67.75	128.34	-2,152.43	5,404.98	2,543.81	2,431.62	112.19	22.674			
12,600.00	7,289.00	14,191.32	8,853.00	66.34	68.74	128.34	-2,151.77	5,504.98	2,543.86	2,430.00	113.87	22.341			
12,700.00	7,289.00	14,291.32	8,853.00	67.38	69.74	128.34	-2,151.11	5,604.97	2,543.92	2,428.37	115.54	22.017			
12,800.00	7,289.00	14,391.32	8,853.00	68.42	70.74	128.34	-2,150.45	5,704.97	2,543.97	2,426.74	117.23	21.701			
12,900.00	7,289.00	14,491.32	8,853.00	69.47	71.74	128.34	-2,149.78	5,804.97	2,544.02	2,425.11	118.92	21.393			
13,000.00	7,289.00	14,591.32	8,853.00	70.51	72.75	128.34	-2,149.12	5,904.97	2,544.08	2,423.47	120.61	21.093			
13,100.00	7,289.00	14,691.32	8,853.00	71.56	73.76	128.33	-2,148.46	6,004.97	2,544.13	2,421.82	122.31	20.800			
13,200.00	7,289.00	14,791.32	8,853.00	72.61	74.77	128.33	-2,147.80	6,104.96	2,544.19	2,420.17	124.02	20.515			
13,300.00	7,289.00	14,891.32	8,853.00	73.67	75.78	128.33	-2,147.14	6,204.96	2,544.24	2,418.51	125.73	20.236			
13,400.00	7,289.00	14,991.32	8,853.00	74.72	76.80	128.33	-2,146.47	6,304.96	2,544.29	2,416.85	127.44	19.965			
13,500.00	7,289.00	15,091.32	8,853.00	75.78	77.82	128.33	-2,145.81	6,404.96	2,544.35	2,415.19	129.16	19.700			
13,600.00	7,289.00	15,191.32	8,853.00	76.84	78.85	128.33	-2,145.15	6,504.95	2,544.40	2,413.52	130.88	19.441			
13,700.00	7,289.00	15,291.32	8,853.00	77.90	79.88	128.33	-2,144.49	6,604.95	2,544.45	2,411.85	132.60	19.189			
13,800.00	7,289.00	15,391.32	8,853.00	78.96	80.90	128.33	-2,143.82	6,704.95	2,544.51	2,410.18	134.33	18.942			
13,900.00	7,289.00	15,491.32	8,853.00	80.02	81.94	128.33	-2,143.16	6,804.95	2,544.56	2,408.50	136.06	18.702			
14,000.00	7,289.00	15,591.32	8,853.00	81.09	82.97	128.33	-2,142.50	6,904.95	2,544.62	2,406.82	137.80	18.466			
14,100.00	7,289.00	15,691.32	8,853.00	82.15	84.01	128.32	-2,141.84	7,004.94	2,544.67	2,405.13	139.54	18.237			
14,200.00	7,289.00	15,791.32	8,853.00	83.22	85.05	128.32	-2,141.17	7,104.94	2,544.72	2,403.45	141.28	18.012			
14,300.00	7,289.00	15,891.32	8,853.00	84.29	86.09	128.32	-2,140.51	7,204.94	2,544.78	2,401.75	143.02	17.793			
14,400.00	7,289.00	15,991.32	8,853.00	85.36	87.13	128.32	-2,139.85	7,304.94	2,544.83	2,400.06	144.77	17.578			
14,500.00	7,289.00	16,091.32	8,853.00	86.44	88.17	128.32	-2,139.19	7,404.93	2,544.88	2,398.36	146.52	17.369			
14,600.00	7,289.00	16,191.32	8,853.00	87.51	89.22	128.32	-2,138.53	7,504.93	2,544.94	2,396.66	148.27	17.164			
14,700.00	7,289.00	16,291.32	8,853.00	88.58	90.27	128.32	-2,137.86	7,604.93	2,544.99	2,394.96	150.03	16.963			
14,800.00	7,289.00	16,391.32	8,853.00	89.66	91.32	128.32	-2,137.20	7,704.93	2,545.04	2,393.26	151.79	16.767			
14,900.00	7,289.00	16,491.32	8,853.00	90.74	92.37	128.32	-2,136.54	7,804.93	2,545.10	2,391.55	153.55	16.575			
15,000.00	7,289.00	16,591.32	8,853.00	91.82	93.42	128.32	-2,135.88	7,904.92	2,545.15	2,389.84	155.31	16.387			
15,100.00	7,289.00	16,691.32	8,853.00	92.90	94.48	128.32	-2,135.21	8,004.92	2,545.21	2,388.13	157.08	16.204			
15,200.00	7,289.00	16,791.32	8,853.00	93.98	95.54	128.31	-2,134.55	8,104.92	2,545.26	2,386.41	158.85	16.024			
15,300.00	7,289.00	16,891.32	8,853.00	95.06	96.59	128.31	-2,133.89	8,204.92	2,545.31	2,384.70	160.62	15.847			
15,400.00	7,289.00	16,991.32	8,853.00	96.14	97.65	128.31	-2,133.23	8,304.91	2,545.37	2,382.98	162.39	15.675			
15,500.00	7,289.00	17,091.32	8,853.00	97.22	98.71	128.31	-2,132.57	8,404.91	2,545.42	2,381.26	164.16	15.506			
15,600.00	7,289.00	17,191.32	8,853.00	98.31	99.78	128.31	-2,131.90	8,504.91	2,545.47	2,379.54	165.94	15.340			
15,700.00	7,289.00	17,291.32	8,853.00	99.39	100.84	128.31	-2,131.24	8,604.91	2,545.53	2,377.81	167.72	15.178			
15,800.00	7,289.00	17,391.32	8,853.00	100.48	101.90	128.31	-2,130.58	8,704.91	2,545.58	2,376.09	169.49	15.019			
15,900.00	7,289.00	17,491.32	8,853.00	101.56	102.97	128.31	-2,129.92	8,804.90	2,545.64	2,374.36	171.28	14.863			
16,000.00	7,289.00	17,591.32	8,853.00	102.65	104.04	128.31	-2,129.25	8,904.90	2,545.69	2,372.63	173.06	14.710			
16,100.00	7,289.00	17,691.32	8,853.00	103.74	105.11	128.31	-2,128.59	9,004.90	2,545.74	2,370.90	174.84	14.560			
16,200.00	7,289.00	17,791.32	8,853.00	104.83	106.17	128.30	-2,127.93	9,104.90	2,545.80	2,369.17	176.63	14.413			
16,300.00	7,289.00	17,891.32	8,853.00	105.92	107.24	128.30	-2,127.27	9,204.89	2,545.85	2,367.43	178.42	14.269			
16,400.00	7,289.00	17,991.32	8,853.00	107.01	108.32	128.30	-2,126.61	9,304.89	2,545.90	2,365.70	180.21	14.128			
16,500.00	7,289.00	18,091.32	8,853.00	108.10	109.39	128.30	-2,125.94	9,404.89	2,545.96	2,363.96	182.00	13.989			
16,600.00	7,289.00	18,191.32	8,853.00	109.19	110.46	128.30	-2,125.28	9,504.89	2,546.01	2,362.22	183.79	13.853			
16,700.00	7,289.00	18,291.32	8,853.00	110.28	111.54	128.30	-2,124.62	9,604.89	2,546.07	2,360.48	185.59	13.719			
16,800.00	7,289.00	18,391.32	8,853.00	111.37	112.61	128.30	-2,123.96	9,704.88	2,546.12	2,358.74	187.38	13.588			
16,900.00	7,289.00	18,491.32	8,853.00	112.46	113.69	128.30	-2,123.29	9,804.88	2,546.17	2,356.99	189.18	13.459			
17,000.00	7,289.00	18,591.32	8,853.00	113.56	114.77	128.30	-2,122.63	9,904.88	2,546.23	2,355.25	190.98	13.333			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B01) Koala 9 Fed Com 203H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Offset Wellbore Centre		Rule Assigned:				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
17,100.00	7,289.00	18,691.32	8,853.00	114.65	115.84	128.30	-2,121.97	10,004.88	2,546.28	2,353.50	192.78	13.209	
17,200.00	7,289.00	18,791.32	8,853.00	115.75	116.92	128.30	-2,121.31	10,104.87	2,546.33	2,351.76	194.58	13.087	
17,300.00	7,289.00	18,891.32	8,853.00	116.84	118.00	128.29	-2,120.65	10,204.87	2,546.39	2,350.01	196.38	12.967	
17,400.00	7,289.00	18,991.32	8,853.00	117.94	119.08	128.29	-2,119.98	10,304.87	2,546.44	2,348.26	198.18	12.849	
17,500.00	7,289.00	19,091.32	8,853.00	119.03	120.16	128.29	-2,119.32	10,404.87	2,546.50	2,346.51	199.98	12.733	
17,600.00	7,289.00	19,191.32	8,853.00	120.13	121.25	128.29	-2,118.66	10,504.87	2,546.55	2,344.76	201.79	12.620	
17,700.00	7,289.00	19,291.32	8,853.00	121.23	122.33	128.29	-2,118.00	10,604.86	2,546.60	2,343.01	203.60	12.508	
17,800.00	7,289.00	19,391.32	8,853.00	122.33	123.41	128.29	-2,117.33	10,704.86	2,546.66	2,341.25	205.40	12.398	
17,900.00	7,289.00	19,491.32	8,853.00	123.42	124.50	128.29	-2,116.67	10,804.86	2,546.71	2,339.50	207.21	12.290	
18,000.00	7,289.00	19,591.32	8,853.00	124.52	125.58	128.29	-2,116.01	10,904.86	2,546.76	2,337.74	209.02	12.184	
18,100.00	7,289.00	19,691.32	8,853.00	125.62	126.67	128.29	-2,115.35	11,004.85	2,546.82	2,335.99	210.83	12.080	
18,159.20	7,289.00	19,710.50	8,853.00	126.27	126.87	128.29	-2,115.22	11,024.04	2,547.16	2,335.72	211.44	12.047 ES, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B02) Koala 9 Fed Com 204H - Permit - APD-Revv00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
13,900.00	7,289.00	15,390.12	8,853.00	80.02	81.31	115.45	-3,463.07	6,813.71	3,672.42	3,523.80	148.62	24.711	CC		
14,000.00	7,289.00	15,490.12	8,853.00	81.09	82.34	115.45	-3,462.40	6,913.70	3,672.48	3,521.92	150.56	24.392			
14,100.00	7,289.00	15,590.12	8,853.00	82.15	83.38	115.45	-3,461.74	7,013.70	3,672.54	3,520.03	152.51	24.081			
14,200.00	7,289.00	15,690.12	8,853.00	83.22	84.43	115.45	-3,461.08	7,113.70	3,672.60	3,518.14	154.46	23.777			
14,300.00	7,289.00	15,790.12	8,853.00	84.29	85.47	115.45	-3,460.41	7,213.70	3,672.66	3,516.25	156.41	23.481			
14,400.00	7,289.00	15,890.12	8,853.00	85.36	86.52	115.45	-3,459.75	7,313.69	3,672.72	3,514.35	158.37	23.191			
14,500.00	7,289.00	15,990.12	8,853.00	86.44	87.57	115.45	-3,459.09	7,413.69	3,672.79	3,512.46	160.33	22.908			
14,600.00	7,289.00	16,090.12	8,853.00	87.51	88.62	115.44	-3,458.43	7,513.69	3,672.85	3,510.56	162.29	22.631			
14,700.00	7,289.00	16,190.12	8,853.00	88.58	89.67	115.44	-3,457.76	7,613.69	3,672.91	3,508.65	164.26	22.361			
14,800.00	7,289.00	16,290.12	8,853.00	89.66	90.72	115.44	-3,457.10	7,713.69	3,672.97	3,506.75	166.22	22.096			
14,900.00	7,289.00	16,390.12	8,853.00	90.74	91.78	115.44	-3,456.44	7,813.68	3,673.03	3,504.84	168.19	21.838			
15,000.00	7,289.00	16,490.12	8,853.00	91.82	92.84	115.44	-3,455.78	7,913.68	3,673.09	3,502.92	170.17	21.585			
15,100.00	7,289.00	16,590.12	8,853.00	92.90	93.89	115.44	-3,455.11	8,013.68	3,673.15	3,501.01	172.14	21.338			
15,200.00	7,289.00	16,690.12	8,853.00	93.98	94.95	115.44	-3,454.45	8,113.68	3,673.22	3,499.10	174.12	21.096			
15,300.00	7,289.00	16,790.12	8,853.00	95.06	96.02	115.44	-3,453.79	8,213.67	3,673.28	3,497.18	176.10	20.859			
15,400.00	7,289.00	16,890.12	8,853.00	96.14	97.08	115.44	-3,453.12	8,313.67	3,673.34	3,495.26	178.08	20.627			
15,500.00	7,289.00	16,990.12	8,853.00	97.22	98.14	115.44	-3,452.46	8,413.67	3,673.40	3,493.33	180.07	20.400			
15,600.00	7,289.00	17,090.12	8,853.00	98.31	99.21	115.44	-3,451.80	8,513.67	3,673.46	3,491.41	182.05	20.178			
15,700.00	7,289.00	17,190.12	8,853.00	99.39	100.27	115.44	-3,451.14	8,613.67	3,673.52	3,489.48	184.04	19.961			
15,800.00	7,289.00	17,290.12	8,853.00	100.48	101.34	115.44	-3,450.47	8,713.66	3,673.58	3,487.56	186.03	19.747			
15,900.00	7,289.00	17,390.12	8,853.00	101.56	102.41	115.44	-3,449.81	8,813.66	3,673.64	3,485.62	188.02	19.539			
16,000.00	7,289.00	17,490.12	8,853.00	102.65	103.48	115.44	-3,449.15	8,913.66	3,673.71	3,483.69	190.01	19.334			
16,100.00	7,289.00	17,590.12	8,853.00	103.74	104.55	115.44	-3,448.49	9,013.66	3,673.77	3,481.76	192.01	19.133			
16,200.00	7,289.00	17,690.12	8,853.00	104.83	105.62	115.44	-3,447.82	9,113.65	3,673.83	3,479.82	194.00	18.937			
16,300.00	7,289.00	17,790.12	8,853.00	105.92	106.70	115.44	-3,447.16	9,213.65	3,673.89	3,477.89	196.00	18.744			
16,400.00	7,289.00	17,890.12	8,853.00	107.01	107.77	115.44	-3,446.50	9,313.65	3,673.95	3,475.95	198.00	18.555			
16,500.00	7,289.00	17,990.12	8,853.00	108.10	108.85	115.44	-3,445.83	9,413.65	3,674.01	3,474.01	200.00	18.370			
16,600.00	7,289.00	18,090.12	8,853.00	109.19	109.92	115.44	-3,445.17	9,513.65	3,674.07	3,472.07	202.01	18.188			
16,700.00	7,289.00	18,190.12	8,853.00	110.28	111.00	115.44	-3,444.51	9,613.64	3,674.14	3,470.13	204.01	18.010			
16,800.00	7,289.00	18,290.12	8,853.00	111.37	112.08	115.43	-3,443.85	9,713.64	3,674.20	3,468.18	206.02	17.835			
16,900.00	7,289.00	18,390.12	8,853.00	112.46	113.16	115.43	-3,443.18	9,813.64	3,674.26	3,466.24	208.02	17.663			
17,000.00	7,289.00	18,490.12	8,853.00	113.56	114.24	115.43	-3,442.52	9,913.64	3,674.32	3,464.29	210.03	17.494			
17,100.00	7,289.00	18,590.12	8,853.00	114.65	115.32	115.43	-3,441.86	10,013.63	3,674.38	3,462.34	212.04	17.329			
17,200.00	7,289.00	18,690.12	8,853.00	115.75	116.40	115.43	-3,441.20	10,113.63	3,674.44	3,460.39	214.05	17.166			
17,300.00	7,289.00	18,790.12	8,853.00	116.84	117.48	115.43	-3,440.53	10,213.63	3,674.50	3,458.44	216.06	17.007			
17,400.00	7,289.00	18,890.12	8,853.00	117.94	118.56	115.43	-3,439.87	10,313.63	3,674.57	3,456.49	218.07	16.850			
17,500.00	7,289.00	18,990.12	8,853.00	119.03	119.65	115.43	-3,439.21	10,413.63	3,674.63	3,454.54	220.09	16.696			
17,600.00	7,289.00	19,090.12	8,853.00	120.13	120.73	115.43	-3,438.54	10,513.62	3,674.69	3,452.58	222.10	16.545			
17,700.00	7,289.00	19,190.12	8,853.00	121.23	121.81	115.43	-3,437.88	10,613.62	3,674.75	3,450.63	224.12	16.396			
17,800.00	7,289.00	19,290.12	8,853.00	122.33	122.90	115.43	-3,437.22	10,713.62	3,674.81	3,448.67	226.14	16.250			
17,900.00	7,289.00	19,390.12	8,853.00	123.42	123.99	115.43	-3,436.56	10,813.62	3,674.87	3,446.72	228.15	16.107			
18,000.00	7,289.00	19,490.12	8,853.00	124.52	125.07	115.43	-3,435.89	10,913.61	3,674.93	3,444.76	230.17	15.966			
18,100.00	7,289.00	19,583.50	8,853.00	125.62	126.08	115.43	-3,435.27	11,007.00	3,675.00	3,442.88	232.13	15.832	ES		
18,159.20	7,289.00	19,583.50	8,853.00	126.27	126.08	115.43	-3,435.27	11,007.00	3,675.62	3,442.92	232.70	15.795	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B03) Koala 9 Fed Com 133H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance		Rule Assigned:		Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
12,300.00	7,289.00	13,203.77	8,523.00	63.24	64.34	115.18	-2,813.80	5,209.40	2,933.81	2,815.28	118.53	24.752	CC
12,400.00	7,289.00	13,303.77	8,523.00	64.27	65.33	115.17	-2,813.13	5,309.40	2,933.87	2,813.48	120.39	24.369	
12,500.00	7,289.00	13,403.77	8,523.00	65.31	66.32	115.17	-2,812.47	5,409.39	2,933.93	2,811.67	122.26	23.997	
12,600.00	7,289.00	13,503.77	8,523.00	66.34	67.32	115.17	-2,811.80	5,509.39	2,933.99	2,809.85	124.14	23.634	
12,700.00	7,289.00	13,603.77	8,523.00	67.38	68.32	115.17	-2,811.14	5,609.39	2,934.05	2,808.02	126.03	23.281	
12,800.00	7,289.00	13,703.77	8,523.00	68.42	69.33	115.17	-2,810.48	5,709.39	2,934.11	2,806.19	127.92	22.937	
12,900.00	7,289.00	13,803.77	8,523.00	69.47	70.34	115.17	-2,809.81	5,809.39	2,934.17	2,804.36	129.81	22.603	
13,000.00	7,289.00	13,903.77	8,523.00	70.51	71.35	115.17	-2,809.15	5,909.38	2,934.23	2,802.52	131.72	22.277	
13,100.00	7,289.00	14,003.77	8,523.00	71.56	72.36	115.17	-2,808.48	6,009.38	2,934.29	2,800.67	133.62	21.959	
13,200.00	7,289.00	14,103.77	8,523.00	72.61	73.38	115.17	-2,807.82	6,109.38	2,934.35	2,798.82	135.53	21.650	
13,300.00	7,289.00	14,203.77	8,523.00	73.67	74.40	115.17	-2,807.16	6,209.38	2,934.41	2,796.96	137.45	21.349	
13,400.00	7,289.00	14,303.77	8,523.00	74.72	75.43	115.17	-2,806.49	6,309.37	2,934.47	2,795.10	139.37	21.055	
13,500.00	7,289.00	14,403.77	8,523.00	75.78	76.45	115.17	-2,805.83	6,409.37	2,934.53	2,793.24	141.30	20.768	
13,600.00	7,289.00	14,503.77	8,523.00	76.84	77.48	115.17	-2,805.16	6,509.37	2,934.59	2,791.37	143.23	20.489	
13,700.00	7,289.00	14,603.77	8,523.00	77.90	78.51	115.17	-2,804.50	6,609.37	2,934.65	2,789.49	145.16	20.216	
13,800.00	7,289.00	14,703.77	8,523.00	78.96	79.55	115.17	-2,803.84	6,709.37	2,934.71	2,787.61	147.10	19.950	
13,900.00	7,289.00	14,803.77	8,523.00	80.02	80.58	115.17	-2,803.17	6,809.36	2,934.78	2,785.73	149.04	19.691	
14,000.00	7,289.00	14,903.77	8,523.00	81.09	81.62	115.17	-2,802.51	6,909.36	2,934.84	2,783.85	150.99	19.438	
14,100.00	7,289.00	15,003.77	8,523.00	82.15	82.66	115.17	-2,801.85	7,009.36	2,934.90	2,781.96	152.94	19.190	
14,200.00	7,289.00	15,103.77	8,523.00	83.22	83.71	115.16	-2,801.18	7,109.36	2,934.96	2,780.07	154.89	18.949	
14,300.00	7,289.00	15,203.77	8,523.00	84.29	84.75	115.16	-2,800.52	7,209.35	2,935.02	2,778.17	156.84	18.713	
14,400.00	7,289.00	15,303.77	8,523.00	85.36	85.80	115.16	-2,799.85	7,309.35	2,935.08	2,776.28	158.80	18.483	
14,500.00	7,289.00	15,403.77	8,523.00	86.44	86.85	115.16	-2,799.19	7,409.35	2,935.14	2,774.38	160.76	18.258	
14,600.00	7,289.00	15,503.77	8,523.00	87.51	87.90	115.16	-2,798.53	7,509.35	2,935.20	2,772.47	162.73	18.038	
14,700.00	7,289.00	15,603.77	8,523.00	88.58	88.95	115.16	-2,797.86	7,609.35	2,935.26	2,770.57	164.69	17.823	
14,800.00	7,289.00	15,703.77	8,523.00	89.66	90.01	115.16	-2,797.20	7,709.34	2,935.32	2,768.66	166.66	17.612	
14,900.00	7,289.00	15,803.77	8,523.00	90.74	91.06	115.16	-2,796.53	7,809.34	2,935.38	2,766.75	168.63	17.407	
15,000.00	7,289.00	15,903.77	8,523.00	91.82	92.12	115.16	-2,795.87	7,909.34	2,935.44	2,764.83	170.61	17.206	
15,100.00	7,289.00	16,003.77	8,523.00	92.90	93.18	115.16	-2,795.21	8,009.34	2,935.50	2,762.92	172.59	17.009	
15,200.00	7,289.00	16,103.77	8,523.00	93.98	94.24	115.16	-2,794.54	8,109.33	2,935.56	2,761.00	174.56	16.816	
15,300.00	7,289.00	16,203.77	8,523.00	95.06	95.30	115.16	-2,793.88	8,209.33	2,935.62	2,759.08	176.55	16.628	
15,400.00	7,289.00	16,303.77	8,523.00	96.14	96.36	115.16	-2,793.21	8,309.33	2,935.68	2,757.15	178.53	16.444	
15,500.00	7,289.00	16,403.77	8,523.00	97.22	97.43	115.16	-2,792.55	8,409.33	2,935.74	2,755.23	180.52	16.263	
15,600.00	7,289.00	16,503.77	8,523.00	98.31	98.49	115.16	-2,791.89	8,509.33	2,935.80	2,753.30	182.50	16.086	
15,700.00	7,289.00	16,603.77	8,523.00	99.39	99.56	115.16	-2,791.22	8,609.32	2,935.86	2,751.37	184.49	15.913	
15,800.00	7,289.00	16,703.77	8,523.00	100.48	100.63	115.16	-2,790.56	8,709.32	2,935.92	2,749.44	186.49	15.743	
15,900.00	7,289.00	16,803.77	8,523.00	101.56	101.70	115.16	-2,789.89	8,809.32	2,935.98	2,747.51	188.48	15.577	
16,000.00	7,289.00	16,903.77	8,523.00	102.65	102.77	115.15	-2,789.23	8,909.32	2,936.04	2,745.57	190.47	15.414	
16,100.00	7,289.00	17,003.77	8,523.00	103.74	103.84	115.15	-2,788.57	9,009.31	2,936.10	2,743.63	192.47	15.255	
16,200.00	7,289.00	17,103.77	8,523.00	104.83	104.91	115.15	-2,787.90	9,109.31	2,936.17	2,741.70	194.47	15.098	
16,300.00	7,289.00	17,203.77	8,523.00	105.92	105.99	115.15	-2,787.24	9,209.31	2,936.23	2,739.76	196.47	14.945	
16,400.00	7,289.00	17,303.77	8,523.00	107.01	107.06	115.15	-2,786.58	9,309.31	2,936.29	2,737.81	198.47	14.794	
16,500.00	7,289.00	17,403.77	8,523.00	108.10	108.14	115.15	-2,785.91	9,409.31	2,936.35	2,735.87	200.48	14.647	
16,600.00	7,289.00	17,503.77	8,523.00	109.19	109.21	115.15	-2,785.25	9,509.30	2,936.41	2,733.93	202.48	14.502	
16,700.00	7,289.00	17,603.77	8,523.00	110.28	110.29	115.15	-2,784.58	9,609.30	2,936.47	2,731.98	204.49	14.360	
16,800.00	7,289.00	17,703.77	8,523.00	111.37	111.37	115.15	-2,783.92	9,709.30	2,936.53	2,730.03	206.49	14.221	
16,900.00	7,289.00	17,803.77	8,523.00	112.46	112.45	115.15	-2,783.26	9,809.30	2,936.59	2,728.08	208.50	14.084	
17,000.00	7,289.00	17,903.77	8,523.00	113.56	113.53	115.15	-2,782.59	9,909.29	2,936.65	2,726.13	210.51	13.950	
17,100.00	7,289.00	18,003.77	8,523.00	114.65	114.61	115.15	-2,781.93	10,009.29	2,936.71	2,724.18	212.53	13.818	
17,200.00	7,289.00	18,103.77	8,523.00	115.75	115.69	115.15	-2,781.26	10,109.29	2,936.77	2,722.23	214.54	13.689	
17,300.00	7,289.00	18,203.77	8,523.00	116.84	116.77	115.15	-2,780.60	10,209.29	2,936.83	2,720.28	216.55	13.562	
17,400.00	7,289.00	18,303.77	8,523.00	117.94	117.86	115.15	-2,779.94	10,309.29	2,936.89	2,718.32	218.57	13.437	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B03) Koala 9 Fed Com 133H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Rule Assigned:		Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
17,500.00	7,289.00	18,403.77	8,523.00	119.03	118.94	115.15	-2,779.27	10,409.28	2,936.95	2,716.36	220.59	13.314			
17,600.00	7,289.00	18,503.77	8,523.00	120.13	120.03	115.15	-2,778.61	10,509.28	2,937.01	2,714.41	222.60	13.194			
17,700.00	7,289.00	18,603.77	8,523.00	121.23	121.11	115.15	-2,777.94	10,609.28	2,937.07	2,712.45	224.62	13.076			
17,800.00	7,289.00	18,703.77	8,523.00	122.33	122.20	115.14	-2,777.28	10,709.28	2,937.13	2,710.49	226.64	12.959			
17,900.00	7,289.00	18,803.77	8,523.00	123.42	123.28	115.14	-2,776.62	10,809.27	2,937.19	2,708.53	228.66	12.845			
18,000.00	7,289.00	18,903.77	8,523.00	124.52	124.37	115.14	-2,775.95	10,909.27	2,937.25	2,706.57	230.69	12.733			
18,100.00	7,289.00	19,003.77	8,523.00	125.62	125.46	115.14	-2,775.29	11,009.27	2,937.31	2,704.60	232.71	12.622			
18,159.20	7,289.00	19,009.61	8,523.00	126.27	125.52	115.14	-2,775.25	11,015.11	2,937.83	2,704.52	233.31	12.592 ES, SF			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B04) Koala 9 Fed Com 134H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
14,600.00	7,289.00	15,756.63	8,523.00	87.51	87.59	107.42	-4,118.40	7,518.08	4,167.81	3,999.74	168.07	24.798	CC		
14,700.00	7,289.00	15,856.63	8,523.00	88.58	88.65	107.42	-4,117.74	7,618.08	4,167.87	3,997.75	170.13	24.499			
14,800.00	7,289.00	15,956.63	8,523.00	89.66	89.70	107.42	-4,117.08	7,718.07	4,167.94	3,995.75	172.19	24.206			
14,900.00	7,289.00	16,056.63	8,523.00	90.74	90.76	107.42	-4,116.41	7,818.07	4,168.00	3,993.75	174.25	23.920			
15,000.00	7,289.00	16,156.63	8,523.00	91.82	91.82	107.42	-4,115.75	7,918.07	4,168.07	3,991.75	176.31	23.640			
15,100.00	7,289.00	16,256.63	8,523.00	92.90	92.88	107.42	-4,115.09	8,018.07	4,168.13	3,989.75	178.38	23.366			
15,200.00	7,289.00	16,356.63	8,523.00	93.98	93.95	107.42	-4,114.42	8,118.07	4,168.20	3,987.75	180.45	23.099			
15,300.00	7,289.00	16,456.63	8,523.00	95.06	95.01	107.42	-4,113.76	8,218.06	4,168.26	3,985.74	182.52	22.837			
15,400.00	7,289.00	16,556.63	8,523.00	96.14	96.08	107.42	-4,113.10	8,318.06	4,168.32	3,983.73	184.60	22.581			
15,500.00	7,289.00	16,656.63	8,523.00	97.22	97.14	107.42	-4,112.43	8,418.06	4,168.39	3,981.72	186.67	22.330			
15,600.00	7,289.00	16,756.63	8,523.00	98.31	98.21	107.42	-4,111.77	8,518.06	4,168.45	3,979.70	188.75	22.084			
15,700.00	7,289.00	16,856.63	8,523.00	99.39	99.28	107.42	-4,111.11	8,618.05	4,168.52	3,977.69	190.83	21.844			
15,800.00	7,289.00	16,956.63	8,523.00	100.48	100.35	107.42	-4,110.44	8,718.05	4,168.58	3,975.67	192.91	21.609			
15,900.00	7,289.00	17,056.63	8,523.00	101.56	101.42	107.42	-4,109.78	8,818.05	4,168.65	3,973.65	195.00	21.378			
16,000.00	7,289.00	17,156.63	8,523.00	102.65	102.49	107.42	-4,109.12	8,918.05	4,168.71	3,971.63	197.08	21.152			
16,100.00	7,289.00	17,256.63	8,523.00	103.74	103.57	107.42	-4,108.45	9,018.05	4,168.78	3,969.61	199.17	20.931			
16,200.00	7,289.00	17,356.63	8,523.00	104.83	104.64	107.42	-4,107.79	9,118.04	4,168.84	3,967.58	201.26	20.714			
16,300.00	7,289.00	17,456.63	8,523.00	105.92	105.72	107.42	-4,107.13	9,218.04	4,168.90	3,965.56	203.35	20.501			
16,400.00	7,289.00	17,556.63	8,523.00	107.01	106.79	107.42	-4,106.47	9,318.04	4,168.97	3,963.53	205.44	20.293			
16,500.00	7,289.00	17,656.63	8,523.00	108.10	107.87	107.42	-4,105.80	9,418.04	4,169.03	3,961.50	207.53	20.089			
16,600.00	7,289.00	17,756.63	8,523.00	109.19	108.95	107.42	-4,105.14	9,518.03	4,169.10	3,959.47	209.63	19.888			
16,700.00	7,289.00	17,856.63	8,523.00	110.28	110.03	107.42	-4,104.48	9,618.03	4,169.16	3,957.44	211.72	19.691			
16,800.00	7,289.00	17,956.63	8,523.00	111.37	111.11	107.42	-4,103.81	9,718.03	4,169.23	3,955.41	213.82	19.499			
16,900.00	7,289.00	18,056.63	8,523.00	112.46	112.19	107.42	-4,103.15	9,818.03	4,169.29	3,953.37	215.92	19.309			
17,000.00	7,289.00	18,156.63	8,523.00	113.56	113.27	107.42	-4,102.49	9,918.03	4,169.36	3,951.34	218.02	19.124			
17,100.00	7,289.00	18,256.63	8,523.00	114.65	114.35	107.42	-4,101.82	10,018.02	4,169.42	3,949.30	220.12	18.941			
17,200.00	7,289.00	18,356.63	8,523.00	115.75	115.43	107.42	-4,101.16	10,118.02	4,169.49	3,947.26	222.23	18.762			
17,300.00	7,289.00	18,456.63	8,523.00	116.84	116.52	107.42	-4,100.50	10,218.02	4,169.55	3,945.22	224.33	18.587			
17,400.00	7,289.00	18,556.63	8,523.00	117.94	117.60	107.42	-4,099.83	10,318.02	4,169.61	3,943.18	226.43	18.414			
17,500.00	7,289.00	18,656.63	8,523.00	119.03	118.69	107.42	-4,099.17	10,418.01	4,169.68	3,941.14	228.54	18.245			
17,600.00	7,289.00	18,756.63	8,523.00	120.13	119.77	107.42	-4,098.51	10,518.01	4,169.74	3,939.10	230.65	18.078			
17,700.00	7,289.00	18,856.63	8,523.00	121.23	120.86	107.42	-4,097.84	10,618.01	4,169.81	3,937.05	232.76	17.915			
17,800.00	7,289.00	18,956.63	8,523.00	122.33	121.95	107.41	-4,097.18	10,718.01	4,169.87	3,935.01	234.87	17.754			
17,900.00	7,289.00	19,056.63	8,523.00	123.42	123.03	107.41	-4,096.52	10,818.01	4,169.94	3,932.96	236.98	17.596			
18,000.00	7,289.00	19,156.63	8,523.00	124.52	124.12	107.41	-4,095.86	10,918.00	4,170.00	3,930.91	239.09	17.441			
18,000.57	7,289.00	19,157.20	8,523.00	124.53	124.13	107.41	-4,095.85	10,918.57	4,170.00	3,930.90	239.10	17.440			
18,100.00	7,289.00	19,235.87	8,523.00	125.62	124.99	107.41	-4,095.33	10,997.24	4,170.12	3,929.13	240.99	17.304	ES		
18,159.20	7,289.00	19,235.87	8,523.00	126.27	124.99	107.41	-4,095.33	10,997.24	4,170.87	3,929.25	241.62	17.262	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B05) Koala 9 Fed Com 123H - Permit - APD-Rev00													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
11,400.00	7,289.00	11,057.25	7,328.00		54.14	52.84	91.14	-2,819.73	4,309.40	2,655.02	2,548.02	107.00	24.814	CC
11,500.00	7,289.00	11,157.25	7,328.00		55.13	53.82	91.14	-2,819.07	4,409.40	2,655.09	2,546.12	108.97	24.366	
11,600.00	7,289.00	11,257.25	7,328.00		56.13	54.80	91.14	-2,818.40	4,509.40	2,655.15	2,544.21	110.95	23.931	
11,700.00	7,289.00	11,357.25	7,328.00		57.13	55.79	91.14	-2,817.74	4,609.40	2,655.22	2,542.28	112.94	23.510	
11,800.00	7,289.00	11,457.25	7,328.00		58.14	56.78	91.14	-2,817.08	4,709.39	2,655.29	2,540.35	114.94	23.102	
11,900.00	7,289.00	11,557.25	7,328.00		59.16	57.77	91.14	-2,816.41	4,809.39	2,655.36	2,538.41	116.95	22.706	
12,000.00	7,289.00	11,657.25	7,328.00		60.17	58.77	91.14	-2,815.75	4,909.39	2,655.42	2,536.46	118.96	22.321	
12,100.00	7,289.00	11,757.25	7,328.00		61.19	59.78	91.14	-2,815.09	5,009.39	2,655.49	2,534.50	120.99	21.948	
12,200.00	7,289.00	11,857.25	7,328.00		62.22	60.79	91.14	-2,814.42	5,109.39	2,655.56	2,532.54	123.02	21.586	
12,300.00	7,289.00	11,957.25	7,328.00		63.24	61.80	91.14	-2,813.76	5,209.38	2,655.63	2,530.56	125.06	21.234	
12,400.00	7,289.00	12,057.25	7,328.00		64.27	62.82	91.14	-2,813.10	5,309.38	2,655.69	2,528.58	127.11	20.893	
12,500.00	7,289.00	12,157.25	7,328.00		65.31	63.84	91.14	-2,812.43	5,409.38	2,655.76	2,526.60	129.16	20.561	
12,600.00	7,289.00	12,257.25	7,328.00		66.34	64.86	91.14	-2,811.77	5,509.38	2,655.83	2,524.61	131.22	20.239	
12,700.00	7,289.00	12,357.25	7,328.00		67.38	65.89	91.14	-2,811.11	5,609.37	2,655.90	2,522.61	133.29	19.926	
12,800.00	7,289.00	12,457.25	7,328.00		68.42	66.92	91.14	-2,810.45	5,709.37	2,655.96	2,520.60	135.36	19.622	
12,900.00	7,289.00	12,557.25	7,328.00		69.47	67.95	91.14	-2,809.78	5,809.37	2,656.03	2,518.60	137.44	19.326	
13,000.00	7,289.00	12,657.25	7,328.00		70.51	68.99	91.14	-2,809.12	5,909.37	2,656.10	2,516.58	139.52	19.038	
13,100.00	7,289.00	12,757.25	7,328.00		71.56	70.02	91.14	-2,808.46	6,009.37	2,656.17	2,514.56	141.60	18.758	
13,200.00	7,289.00	12,857.25	7,328.00		72.61	71.07	91.14	-2,807.79	6,109.36	2,656.23	2,512.54	143.70	18.485	
13,300.00	7,289.00	12,957.25	7,328.00		73.67	72.11	91.14	-2,807.13	6,209.36	2,656.30	2,510.51	145.79	18.220	
13,400.00	7,289.00	13,057.25	7,328.00		74.72	73.15	91.14	-2,806.47	6,309.36	2,656.37	2,508.48	147.89	17.962	
13,500.00	7,289.00	13,157.25	7,328.00		75.78	74.20	91.14	-2,805.80	6,409.36	2,656.43	2,506.44	150.00	17.710	
13,600.00	7,289.00	13,257.25	7,328.00		76.84	75.25	91.14	-2,805.14	6,509.35	2,656.50	2,504.40	152.10	17.465	
13,700.00	7,289.00	13,357.25	7,328.00		77.90	76.30	91.14	-2,804.48	6,609.35	2,656.57	2,502.35	154.22	17.226	
13,800.00	7,289.00	13,457.25	7,328.00		78.96	77.36	91.14	-2,803.81	6,709.35	2,656.64	2,500.30	156.33	16.993	
13,900.00	7,289.00	13,557.25	7,328.00		80.02	78.41	91.14	-2,803.15	6,809.35	2,656.70	2,498.25	158.45	16.767	
14,000.00	7,289.00	13,657.25	7,328.00		81.09	79.47	91.14	-2,802.49	6,909.35	2,656.77	2,496.20	160.58	16.545	
14,100.00	7,289.00	13,757.25	7,328.00		82.15	80.53	91.14	-2,801.82	7,009.34	2,656.84	2,494.14	162.70	16.329	
14,200.00	7,289.00	13,857.25	7,328.00		83.22	81.59	91.14	-2,801.16	7,109.34	2,656.91	2,492.07	164.83	16.119	
14,300.00	7,289.00	13,957.25	7,328.00		84.29	82.65	91.14	-2,800.50	7,209.34	2,656.97	2,490.01	166.96	15.913	
14,400.00	7,289.00	14,057.25	7,328.00		85.36	83.72	91.14	-2,799.83	7,309.34	2,657.04	2,487.94	169.10	15.713	
14,500.00	7,289.00	14,157.25	7,328.00		86.44	84.78	91.14	-2,799.17	7,409.33	2,657.11	2,485.87	171.24	15.517	
14,600.00	7,289.00	14,257.25	7,328.00		87.51	85.85	91.14	-2,798.51	7,509.33	2,657.18	2,483.80	173.38	15.326	
14,700.00	7,289.00	14,357.25	7,328.00		88.58	86.92	91.14	-2,797.84	7,609.33	2,657.24	2,481.72	175.52	15.139	
14,800.00	7,289.00	14,457.25	7,328.00		89.66	87.99	91.14	-2,797.18	7,709.33	2,657.31	2,479.64	177.67	14.957	
14,900.00	7,289.00	14,557.25	7,328.00		90.74	89.06	91.14	-2,796.52	7,809.33	2,657.38	2,477.56	179.82	14.778	
15,000.00	7,289.00	14,657.25	7,328.00		91.82	90.13	91.14	-2,795.85	7,909.32	2,657.44	2,475.48	181.97	14.604	
15,100.00	7,289.00	14,757.25	7,328.00		92.90	91.21	91.14	-2,795.19	8,009.32	2,657.51	2,473.39	184.12	14.434	
15,200.00	7,289.00	14,857.25	7,328.00		93.98	92.28	91.14	-2,794.53	8,109.32	2,657.58	2,471.31	186.27	14.267	
15,300.00	7,289.00	14,957.25	7,328.00		95.06	93.36	91.14	-2,793.86	8,209.32	2,657.65	2,469.22	188.43	14.104	
15,400.00	7,289.00	15,057.25	7,328.00		96.14	94.43	91.14	-2,793.20	8,309.31	2,657.71	2,467.12	190.59	13.945	
15,500.00	7,289.00	15,157.25	7,328.00		97.22	95.51	91.14	-2,792.54	8,409.31	2,657.78	2,465.03	192.75	13.789	
15,600.00	7,289.00	15,257.25	7,328.00		98.31	96.59	91.14	-2,791.87	8,509.31	2,657.85	2,462.94	194.91	13.636	
15,700.00	7,289.00	15,357.25	7,328.00		99.39	97.67	91.14	-2,791.21	8,609.31	2,657.92	2,460.84	197.08	13.487	
15,800.00	7,289.00	15,457.25	7,328.00		100.48	98.75	91.14	-2,790.55	8,709.31	2,657.98	2,458.74	199.24	13.340	
15,900.00	7,289.00	15,557.25	7,328.00		101.56	99.83	91.14	-2,789.88	8,809.30	2,658.05	2,456.64	201.41	13.197	
16,000.00	7,289.00	15,657.25	7,328.00		102.65	100.91	91.14	-2,789.22	8,909.30	2,658.12	2,454.54	203.58	13.057	
16,100.00	7,289.00	15,757.25	7,328.00		103.74	102.00	91.14	-2,788.56	9,009.30	2,658.19	2,452.43	205.75	12.919	
16,200.00	7,289.00	15,857.25	7,328.00		104.83	103.08	91.14	-2,787.89	9,109.30	2,658.25	2,450.33	207.93	12.785	
16,300.00	7,289.00	15,957.25	7,328.00		105.92	104.17	91.14	-2,787.23	9,209.29	2,658.32	2,448.22	210.10	12.653	
16,400.00	7,289.00	16,057.25	7,328.00		107.01	105.25	91.14	-2,786.57	9,309.29	2,658.39	2,446.11	212.28	12.523	
16,500.00	7,289.00	16,157.25	7,328.00		108.10	106.34	91.14	-2,785.90	9,409.29	2,658.46	2,444.00	214.45	12.396	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B05) Koala 9 Fed Com 123H - Permit - APD-Rev00													Offset Site Error: 0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
16,600.00	7,289.00	16,257.25	7,328.00	109.19	107.43	91.14	-2,785.24	9,509.29	2,658.52	2,441.89	216.63	12.272	
16,700.00	7,289.00	16,357.25	7,328.00	110.28	108.51	91.14	-2,784.58	9,609.29	2,658.59	2,439.78	218.81	12.150	
16,800.00	7,289.00	16,457.25	7,328.00	111.37	109.60	91.14	-2,783.91	9,709.28	2,658.66	2,437.66	220.99	12.030	
16,900.00	7,289.00	16,557.25	7,328.00	112.46	110.69	91.14	-2,783.25	9,809.28	2,658.72	2,435.55	223.18	11.913	
17,000.00	7,289.00	16,657.25	7,328.00	113.56	111.78	91.14	-2,782.59	9,909.28	2,658.79	2,433.43	225.36	11.798	
17,100.00	7,289.00	16,757.25	7,328.00	114.65	112.87	91.14	-2,781.92	10,009.28	2,658.86	2,431.31	227.55	11.685	
17,200.00	7,289.00	16,857.25	7,328.00	115.75	113.96	91.14	-2,781.26	10,109.27	2,658.93	2,429.20	229.73	11.574	
17,300.00	7,289.00	16,957.25	7,328.00	116.84	115.06	91.14	-2,780.60	10,209.27	2,658.99	2,427.08	231.92	11.465	
17,400.00	7,289.00	17,057.25	7,328.00	117.94	116.15	91.14	-2,779.93	10,309.27	2,659.06	2,424.96	234.11	11.358	
17,500.00	7,289.00	17,157.25	7,328.00	119.03	117.24	91.14	-2,779.27	10,409.27	2,659.13	2,422.83	236.30	11.253	
17,600.00	7,289.00	17,257.25	7,328.00	120.13	118.34	91.14	-2,778.61	10,509.27	2,659.20	2,420.71	238.49	11.150	
17,700.00	7,289.00	17,357.25	7,328.00	121.23	119.43	91.14	-2,777.94	10,609.26	2,659.26	2,418.59	240.68	11.049	
17,800.00	7,289.00	17,457.25	7,328.00	122.33	120.52	91.14	-2,777.28	10,709.26	2,659.33	2,416.46	242.87	10.950	
17,900.00	7,289.00	17,557.25	7,328.00	123.42	121.62	91.14	-2,776.62	10,809.26	2,659.40	2,414.34	245.06	10.852	
18,000.00	7,289.00	17,657.25	7,328.00	124.52	122.71	91.14	-2,775.95	10,909.26	2,659.47	2,412.21	247.26	10.756	
18,100.00	7,289.00	17,757.25	7,328.00	125.62	123.81	91.14	-2,775.29	11,009.25	2,659.53	2,410.08	249.45	10.662	
18,159.20	7,289.00	17,763.11	7,328.00	126.27	123.87	91.14	-2,775.25	11,015.11	2,660.11	2,409.99	250.12	10.635 ES, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B06) Koala 9 Fed Com 124H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
14,000.00	7,289.00	13,913.90	7,328.00	81.09	79.20	90.76	-4,122.37	6,918.08	3,976.51	3,816.30	160.21	24.821	CC		
14,100.00	7,289.00	14,013.90	7,328.00	82.15	80.26	90.76	-4,121.71	7,018.08	3,976.58	3,814.24	162.33	24.496			
14,200.00	7,289.00	14,113.90	7,328.00	83.22	81.33	90.76	-4,121.04	7,118.08	3,976.64	3,812.18	164.47	24.179			
14,300.00	7,289.00	14,213.90	7,328.00	84.29	82.39	90.76	-4,120.38	7,218.07	3,976.71	3,810.11	166.60	23.869			
14,400.00	7,289.00	14,313.90	7,328.00	85.36	83.46	90.76	-4,119.72	7,318.07	3,976.78	3,808.04	168.74	23.567			
14,500.00	7,289.00	14,413.90	7,328.00	86.44	84.53	90.76	-4,119.05	7,418.07	3,976.85	3,805.96	170.88	23.272			
14,600.00	7,289.00	14,513.90	7,328.00	87.51	85.60	90.76	-4,118.39	7,518.07	3,976.91	3,803.89	173.03	22.984			
14,700.00	7,289.00	14,613.90	7,328.00	88.58	86.67	90.76	-4,117.73	7,618.06	3,976.98	3,801.81	175.17	22.703			
14,800.00	7,289.00	14,713.90	7,328.00	89.66	87.74	90.76	-4,117.07	7,718.06	3,977.05	3,799.73	177.32	22.428			
14,900.00	7,289.00	14,813.90	7,328.00	90.74	88.81	90.76	-4,116.40	7,818.06	3,977.12	3,797.65	179.47	22.160			
15,000.00	7,289.00	14,913.90	7,328.00	91.82	89.89	90.76	-4,115.74	7,918.06	3,977.19	3,795.56	181.63	21.898			
15,100.00	7,289.00	15,013.90	7,328.00	92.90	90.96	90.76	-4,115.08	8,018.06	3,977.25	3,793.47	183.78	21.641			
15,200.00	7,289.00	15,113.90	7,328.00	93.98	92.04	90.76	-4,114.41	8,118.05	3,977.32	3,791.38	185.94	21.390			
15,300.00	7,289.00	15,213.90	7,328.00	95.06	93.12	90.76	-4,113.75	8,218.05	3,977.39	3,789.29	188.10	21.145			
15,400.00	7,289.00	15,313.90	7,328.00	96.14	94.19	90.76	-4,113.09	8,318.05	3,977.46	3,787.20	190.26	20.905			
15,500.00	7,289.00	15,413.90	7,328.00	97.22	95.27	90.76	-4,112.43	8,418.05	3,977.53	3,785.10	192.42	20.671			
15,600.00	7,289.00	15,513.90	7,328.00	98.31	96.35	90.76	-4,111.76	8,518.05	3,977.59	3,783.00	194.59	20.441			
15,700.00	7,289.00	15,613.90	7,328.00	99.39	97.44	90.76	-4,111.10	8,618.04	3,977.66	3,780.91	196.76	20.216			
15,800.00	7,289.00	15,713.90	7,328.00	100.48	98.52	90.76	-4,110.44	8,718.04	3,977.73	3,778.80	198.92	19.996			
15,900.00	7,289.00	15,813.90	7,328.00	101.56	99.60	90.76	-4,109.77	8,818.04	3,977.80	3,776.70	201.10	19.781			
16,000.00	7,289.00	15,913.90	7,328.00	102.65	100.69	90.76	-4,109.11	8,918.04	3,977.87	3,774.60	203.27	19.570			
16,100.00	7,289.00	16,013.90	7,328.00	103.74	101.77	90.76	-4,108.45	9,018.03	3,977.93	3,772.49	205.44	19.363			
16,200.00	7,289.00	16,113.90	7,328.00	104.83	102.86	90.76	-4,107.79	9,118.03	3,978.00	3,770.39	207.62	19.160			
16,300.00	7,289.00	16,213.90	7,328.00	105.92	103.94	90.76	-4,107.12	9,218.03	3,978.07	3,768.28	209.79	18.962			
16,400.00	7,289.00	16,313.90	7,328.00	107.01	105.03	90.76	-4,106.46	9,318.03	3,978.14	3,766.17	211.97	18.767			
16,500.00	7,289.00	16,413.90	7,328.00	108.10	106.12	90.76	-4,105.80	9,418.03	3,978.20	3,764.05	214.15	18.577			
16,600.00	7,289.00	16,513.90	7,328.00	109.19	107.21	90.76	-4,105.13	9,518.02	3,978.27	3,761.94	216.33	18.390			
16,700.00	7,289.00	16,613.90	7,328.00	110.28	108.30	90.76	-4,104.47	9,618.02	3,978.34	3,759.83	218.51	18.207			
16,800.00	7,289.00	16,713.90	7,328.00	111.37	109.39	90.76	-4,103.81	9,718.02	3,978.41	3,757.71	220.70	18.027			
16,900.00	7,289.00	16,813.90	7,328.00	112.46	110.48	90.76	-4,103.15	9,818.02	3,978.48	3,755.60	222.88	17.850			
17,000.00	7,289.00	16,913.90	7,328.00	113.56	111.57	90.76	-4,102.48	9,918.01	3,978.54	3,753.48	225.07	17.677			
17,100.00	7,289.00	17,013.90	7,328.00	114.65	112.66	90.76	-4,101.82	10,018.01	3,978.61	3,751.36	227.25	17.507			
17,200.00	7,289.00	17,113.90	7,328.00	115.75	113.75	90.76	-4,101.16	10,118.01	3,978.68	3,749.24	229.44	17.341			
17,300.00	7,289.00	17,213.90	7,328.00	116.84	114.85	90.76	-4,100.50	10,218.01	3,978.75	3,747.12	231.63	17.177			
17,400.00	7,289.00	17,313.90	7,328.00	117.94	115.94	90.76	-4,099.83	10,318.01	3,978.82	3,745.00	233.82	17.017			
17,500.00	7,289.00	17,413.90	7,328.00	119.03	117.03	90.76	-4,099.17	10,418.00	3,978.88	3,742.87	236.01	16.859			
17,600.00	7,289.00	17,513.90	7,328.00	120.13	118.13	90.76	-4,098.51	10,518.00	3,978.95	3,740.75	238.20	16.704			
17,700.00	7,289.00	17,613.90	7,328.00	121.23	119.22	90.76	-4,097.84	10,618.00	3,979.02	3,738.62	240.39	16.552			
17,800.00	7,289.00	17,713.90	7,328.00	122.33	120.32	90.76	-4,097.18	10,718.00	3,979.09	3,736.50	242.59	16.403			
17,900.00	7,289.00	17,813.90	7,328.00	123.42	121.42	90.76	-4,096.52	10,817.99	3,979.15	3,734.37	244.78	16.256			
18,000.00	7,289.00	17,913.90	7,328.00	124.52	122.51	90.76	-4,095.86	10,917.99	3,979.22	3,732.24	246.98	16.112			
18,000.50	7,289.00	17,914.40	7,328.00	124.53	122.52	90.76	-4,095.85	10,918.49	3,979.22	3,732.23	246.99	16.111			
18,100.00	7,289.00	17,993.15	7,328.00	125.62	123.38	90.76	-4,095.33	10,997.24	3,979.34	3,730.38	248.96	15.984	ES		
18,159.20	7,289.00	17,993.15	7,328.00	126.27	123.38	90.76	-4,095.33	10,997.24	3,980.13	3,730.51	249.62	15.945	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B07) Koala 9 Fed Com 113H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program:		0-MWD+IFR1+SAG+FDIR (SQC2)					Rule Assigned:			Offset Well Error:	0.00 usft				
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance			Warning						
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
12,200.00	7,289.00	11,015.92	6,303.00	62.22	58.89	69.89	-2,814.49	5,109.42	2,827.42	2,713.08	114.35	24.727	CC		
12,300.00	7,289.00	11,115.92	6,303.00	63.24	59.93	69.89	-2,813.83	5,209.41	2,827.49	2,711.19	116.30	24.312			
12,400.00	7,289.00	11,215.92	6,303.00	64.27	60.97	69.89	-2,813.16	5,309.41	2,827.55	2,709.29	118.26	23.909			
12,500.00	7,289.00	11,315.92	6,303.00	65.31	62.02	69.89	-2,812.50	5,409.41	2,827.61	2,707.38	120.23	23.519			
12,600.00	7,289.00	11,415.92	6,303.00	66.34	63.07	69.89	-2,811.83	5,509.41	2,827.67	2,705.47	122.20	23.140			
12,700.00	7,289.00	11,515.92	6,303.00	67.38	64.11	69.90	-2,811.17	5,609.41	2,827.74	2,703.56	124.18	22.772			
12,800.00	7,289.00	11,615.92	6,303.00	68.42	65.17	69.90	-2,810.51	5,709.40	2,827.80	2,701.64	126.16	22.414			
12,900.00	7,289.00	11,715.92	6,303.00	69.47	66.22	69.90	-2,809.84	5,809.40	2,827.86	2,699.71	128.15	22.068			
13,000.00	7,289.00	11,815.92	6,303.00	70.51	67.28	69.90	-2,809.18	5,909.40	2,827.92	2,697.79	130.14	21.730			
13,100.00	7,289.00	11,915.92	6,303.00	71.56	68.34	69.90	-2,808.51	6,009.40	2,827.98	2,695.85	132.13	21.403			
13,200.00	7,289.00	12,015.92	6,303.00	72.61	69.40	69.90	-2,807.85	6,109.39	2,828.05	2,693.92	134.13	21.084			
13,300.00	7,289.00	12,115.92	6,303.00	73.67	70.46	69.90	-2,807.18	6,209.39	2,828.11	2,691.98	136.13	20.775			
13,400.00	7,289.00	12,215.92	6,303.00	74.72	71.52	69.90	-2,806.52	6,309.39	2,828.17	2,690.03	138.14	20.473			
13,500.00	7,289.00	12,315.92	6,303.00	75.78	72.59	69.90	-2,805.85	6,409.39	2,828.23	2,688.08	140.15	20.180			
13,600.00	7,289.00	12,415.92	6,303.00	76.84	73.66	69.90	-2,805.19	6,509.39	2,828.30	2,686.13	142.16	19.895			
13,700.00	7,289.00	12,515.92	6,303.00	77.90	74.72	69.90	-2,804.53	6,609.38	2,828.36	2,684.18	144.18	19.617			
13,800.00	7,289.00	12,615.92	6,303.00	78.96	75.80	69.90	-2,803.86	6,709.38	2,828.42	2,682.22	146.20	19.347			
13,900.00	7,289.00	12,715.92	6,303.00	80.02	76.87	69.90	-2,803.20	6,809.38	2,828.48	2,680.26	148.22	19.083			
14,000.00	7,289.00	12,815.91	6,303.00	81.09	77.94	69.90	-2,802.53	6,909.38	2,828.54	2,678.30	150.24	18.826			
14,100.00	7,289.00	12,915.91	6,303.00	82.15	79.02	69.90	-2,801.87	7,009.37	2,828.61	2,676.34	152.27	18.576			
14,200.00	7,289.00	13,015.91	6,303.00	83.22	80.09	69.90	-2,801.20	7,109.37	2,828.67	2,674.37	154.30	18.332			
14,300.00	7,289.00	13,115.91	6,303.00	84.29	81.17	69.90	-2,800.54	7,209.37	2,828.73	2,672.40	156.33	18.094			
14,400.00	7,289.00	13,215.91	6,303.00	85.36	82.25	69.90	-2,799.87	7,309.37	2,828.79	2,670.42	158.37	17.862			
14,500.00	7,289.00	13,315.91	6,303.00	86.44	83.33	69.90	-2,799.21	7,409.37	2,828.85	2,668.45	160.41	17.636			
14,600.00	7,289.00	13,415.91	6,303.00	87.51	84.41	69.90	-2,798.55	7,509.36	2,828.92	2,666.47	162.45	17.415			
14,700.00	7,289.00	13,515.91	6,303.00	88.58	85.49	69.90	-2,797.88	7,609.36	2,828.98	2,664.49	164.49	17.199			
14,800.00	7,289.00	13,615.91	6,303.00	89.66	86.57	69.90	-2,797.22	7,709.36	2,829.04	2,662.51	166.53	16.988			
14,900.00	7,289.00	13,715.91	6,303.00	90.74	87.66	69.91	-2,796.55	7,809.36	2,829.10	2,660.53	168.58	16.782			
15,000.00	7,289.00	13,815.91	6,303.00	91.82	88.74	69.91	-2,795.89	7,909.35	2,829.17	2,658.54	170.62	16.581			
15,100.00	7,289.00	13,915.91	6,303.00	92.90	89.83	69.91	-2,795.22	8,009.35	2,829.23	2,656.55	172.67	16.385			
15,200.00	7,289.00	14,015.91	6,303.00	93.98	90.92	69.91	-2,794.56	8,109.35	2,829.29	2,654.56	174.73	16.193			
15,300.00	7,289.00	14,115.91	6,303.00	95.06	92.00	69.91	-2,793.89	8,209.35	2,829.35	2,652.57	176.78	16.005			
15,400.00	7,289.00	14,215.91	6,303.00	96.14	93.09	69.91	-2,793.23	8,309.35	2,829.41	2,650.58	178.83	15.822			
15,500.00	7,289.00	14,315.91	6,303.00	97.22	94.18	69.91	-2,792.57	8,409.34	2,829.48	2,648.59	180.89	15.642			
15,600.00	7,289.00	14,415.91	6,303.00	98.31	95.27	69.91	-2,791.90	8,509.34	2,829.54	2,646.59	182.95	15.466			
15,700.00	7,289.00	14,515.91	6,303.00	99.39	96.36	69.91	-2,791.24	8,609.34	2,829.60	2,644.59	185.01	15.295			
15,800.00	7,289.00	14,615.91	6,303.00	100.48	97.45	69.91	-2,790.57	8,709.34	2,829.66	2,642.60	187.07	15.126			
15,900.00	7,289.00	14,715.91	6,303.00	101.56	98.54	69.91	-2,789.91	8,809.33	2,829.73	2,640.60	189.13	14.962			
16,000.00	7,289.00	14,815.91	6,303.00	102.65	99.64	69.91	-2,789.24	8,909.33	2,829.79	2,638.59	191.19	14.801			
16,100.00	7,289.00	14,915.91	6,303.00	103.74	100.73	69.91	-2,788.58	9,009.33	2,829.85	2,636.59	193.26	14.643			
16,200.00	7,289.00	15,015.91	6,303.00	104.83	101.82	69.91	-2,787.91	9,109.33	2,829.91	2,634.59	195.32	14.488			
16,300.00	7,289.00	15,115.91	6,303.00	105.92	102.92	69.91	-2,787.25	9,209.33	2,829.97	2,632.58	197.39	14.337			
16,400.00	7,289.00	15,215.91	6,303.00	107.01	104.01	69.91	-2,786.58	9,309.32	2,830.04	2,630.58	199.46	14.188			
16,500.00	7,289.00	15,315.91	6,303.00	108.10	105.11	69.91	-2,785.92	9,409.32	2,830.10	2,628.57	201.53	14.043			
16,600.00	7,289.00	15,415.91	6,303.00	109.19	106.21	69.91	-2,785.26	9,509.32	2,830.16	2,626.56	203.60	13.901			
16,700.00	7,289.00	15,515.91	6,303.00	110.28	107.30	69.91	-2,784.59	9,609.32	2,830.22	2,624.55	205.67	13.761			
16,800.00	7,289.00	15,615.91	6,303.00	111.37	108.40	69.91	-2,783.93	9,709.31	2,830.29	2,622.54	207.75	13.624			
16,900.00	7,289.00	15,715.91	6,303.00	112.46	109.50	69.91	-2,783.26	9,809.31	2,830.35	2,620.53	209.82	13.489			
17,000.00	7,289.00	15,815.91	6,303.00	113.56	110.60	69.92	-2,782.60	9,909.31	2,830.41	2,618.51	211.90	13.358			
17,100.00	7,289.00	15,915.91	6,303.00	114.65	111.69	69.92	-2,781.93	10,009.31	2,830.47	2,616.50	213.97	13.228			
17,200.00	7,289.00	16,015.91	6,303.00	115.75	112.79	69.92	-2,781.27	10,109.31	2,830.53	2,614.49	216.05	13.101			
17,300.00	7,289.00	16,115.91	6,303.00	116.84	113.89	69.92	-2,780.60	10,209.30	2,830.60	2,612.47	218.13	12.977			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B07) Koala 9 Fed Com 113H - Permit - APD-Rev00													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)							Rule Assigned:						Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
17,400.00	7,289.00	16,215.91	6,303.00	117.94	114.99	69.92	-2,779.94	10,309.30	2,830.66	2,610.45	220.20	12.855		
17,500.00	7,289.00	16,315.91	6,303.00	119.03	116.09	69.92	-2,779.28	10,409.30	2,830.72	2,608.44	222.28	12.735		
17,600.00	7,289.00	16,415.91	6,303.00	120.13	117.19	69.92	-2,778.61	10,509.30	2,830.78	2,606.42	224.37	12.617		
17,700.00	7,289.00	16,515.91	6,303.00	121.23	118.30	69.92	-2,777.95	10,609.29	2,830.84	2,604.40	226.45	12.501		
17,800.00	7,289.00	16,615.91	6,303.00	122.33	119.40	69.92	-2,777.28	10,709.29	2,830.91	2,602.38	228.53	12.388		
17,900.00	7,289.00	16,715.91	6,303.00	123.42	120.50	69.92	-2,776.62	10,809.29	2,830.97	2,600.36	230.61	12.276		
18,000.00	7,289.00	16,815.91	6,303.00	124.52	121.60	69.92	-2,775.95	10,909.29	2,831.03	2,598.34	232.70	12.166		
18,100.00	7,289.00	16,915.91	6,303.00	125.62	122.70	69.92	-2,775.29	11,009.28	2,831.09	2,596.31	234.78	12.059		
18,159.20	7,289.00	16,922.61	6,303.00	126.27	122.78	69.92	-2,775.24	11,015.98	2,831.62	2,596.21	235.41	12.029 ES, SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: (Permit) Koala 9 Fed Com - (B08) Koala 9 Fed Com 114H - Permit - APD-Rev00														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+IFR1+SAG+FDIR (SQC2)														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
14,500.00	7,289.00	13,310.75	6,303.00	86.44	82.79	76.26	-4,119.02	7,418.03	4,093.53	3,928.15	165.38	24.753	CC		
14,600.00	7,289.00	13,410.75	6,303.00	87.51	83.87	76.26	-4,118.35	7,518.02	4,093.60	3,926.12	167.48	24.443			
14,700.00	7,289.00	13,510.75	6,303.00	88.58	84.95	76.26	-4,117.69	7,618.02	4,093.66	3,924.09	169.57	24.141			
14,800.00	7,289.00	13,610.75	6,303.00	89.66	86.03	76.26	-4,117.03	7,718.02	4,093.73	3,922.05	171.68	23.846			
14,900.00	7,289.00	13,710.75	6,303.00	90.74	87.12	76.26	-4,116.37	7,818.02	4,093.80	3,920.02	173.78	23.557			
15,000.00	7,289.00	13,810.75	6,303.00	91.82	88.20	76.27	-4,115.71	7,918.02	4,093.86	3,917.98	175.89	23.276			
15,100.00	7,289.00	13,910.75	6,303.00	92.90	89.29	76.27	-4,115.05	8,018.01	4,093.93	3,915.94	177.99	23.001			
15,200.00	7,289.00	14,010.75	6,303.00	93.98	90.37	76.27	-4,114.38	8,118.01	4,094.00	3,913.90	180.10	22.732			
15,300.00	7,289.00	14,110.75	6,303.00	95.06	91.46	76.27	-4,113.72	8,218.01	4,094.07	3,911.85	182.21	22.469			
15,400.00	7,289.00	14,210.75	6,303.00	96.14	92.55	76.27	-4,113.06	8,318.01	4,094.13	3,909.81	184.33	22.211			
15,500.00	7,289.00	14,310.75	6,303.00	97.22	93.64	76.27	-4,112.40	8,418.00	4,094.20	3,907.76	186.44	21.960			
15,600.00	7,289.00	14,410.75	6,303.00	98.31	94.73	76.27	-4,111.74	8,518.00	4,094.27	3,905.71	188.56	21.714			
15,700.00	7,289.00	14,510.75	6,303.00	99.39	95.82	76.27	-4,111.08	8,618.00	4,094.33	3,903.66	190.68	21.473			
15,800.00	7,289.00	14,610.75	6,303.00	100.48	96.91	76.27	-4,110.41	8,718.00	4,094.40	3,901.61	192.79	21.237			
15,900.00	7,289.00	14,710.75	6,303.00	101.56	98.00	76.27	-4,109.75	8,818.00	4,094.47	3,899.55	194.92	21.006			
16,000.00	7,289.00	14,810.75	6,303.00	102.65	99.09	76.27	-4,109.09	8,917.99	4,094.53	3,897.50	197.04	20.780			
16,100.00	7,289.00	14,910.75	6,303.00	103.74	100.19	76.27	-4,108.43	9,017.99	4,094.60	3,895.44	199.16	20.559			
16,200.00	7,289.00	15,010.75	6,303.00	104.83	101.28	76.27	-4,107.77	9,117.99	4,094.67	3,893.38	201.29	20.343			
16,300.00	7,289.00	15,110.75	6,303.00	105.92	102.38	76.27	-4,107.10	9,217.99	4,094.74	3,891.32	203.41	20.130			
16,400.00	7,289.00	15,210.75	6,303.00	107.01	103.47	76.27	-4,106.44	9,317.98	4,094.80	3,889.26	205.54	19.922			
16,500.00	7,289.00	15,310.75	6,303.00	108.10	104.57	76.27	-4,105.78	9,417.98	4,094.87	3,887.20	207.67	19.718			
16,600.00	7,289.00	15,410.75	6,303.00	109.19	105.66	76.27	-4,105.12	9,517.98	4,094.94	3,885.14	209.80	19.518			
16,700.00	7,289.00	15,510.75	6,303.00	110.28	106.76	76.27	-4,104.46	9,617.98	4,095.00	3,883.07	211.93	19.322			
16,800.00	7,289.00	15,610.75	6,303.00	111.37	107.86	76.27	-4,103.80	9,717.98	4,095.07	3,881.01	214.06	19.130			
16,900.00	7,289.00	15,710.75	6,303.00	112.46	108.96	76.27	-4,103.13	9,817.97	4,095.14	3,878.94	216.19	18.942			
17,000.00	7,289.00	15,810.75	6,303.00	113.56	110.05	76.27	-4,102.47	9,917.97	4,095.20	3,876.87	218.33	18.757			
17,100.00	7,289.00	15,910.75	6,303.00	114.65	111.15	76.27	-4,101.81	10,017.97	4,095.27	3,874.81	220.46	18.576			
17,200.00	7,289.00	16,010.75	6,303.00	115.75	112.25	76.27	-4,101.15	10,117.97	4,095.34	3,872.74	222.60	18.398			
17,300.00	7,289.00	16,110.75	6,303.00	116.84	113.35	76.27	-4,100.49	10,217.97	4,095.40	3,870.67	224.74	18.223			
17,400.00	7,289.00	16,210.75	6,303.00	117.94	114.45	76.27	-4,099.83	10,317.96	4,095.47	3,868.60	226.88	18.052			
17,500.00	7,289.00	16,310.75	6,303.00	119.03	115.55	76.27	-4,099.16	10,417.96	4,095.54	3,866.52	229.02	17.883			
17,600.00	7,289.00	16,410.75	6,303.00	120.13	116.65	76.27	-4,098.50	10,517.96	4,095.61	3,864.45	231.16	17.718			
17,700.00	7,289.00	16,510.75	6,303.00	121.23	117.75	76.27	-4,097.84	10,617.96	4,095.67	3,862.38	233.30	17.556			
17,800.00	7,289.00	16,610.75	6,303.00	122.33	118.86	76.27	-4,097.18	10,717.95	4,095.74	3,860.30	235.44	17.396			
17,900.00	7,289.00	16,710.75	6,303.00	123.42	119.96	76.27	-4,096.52	10,817.95	4,095.81	3,858.23	237.58	17.240			
18,000.00	7,289.00	16,810.75	6,303.00	124.52	121.06	76.27	-4,095.85	10,917.95	4,095.87	3,856.15	239.72	17.086			
18,000.25	7,289.00	16,811.00	6,303.00	124.53	121.06	76.27	-4,095.85	10,918.20	4,095.87	3,856.15	239.73	17.085			
18,100.00	7,289.00	16,890.04	6,303.00	125.62	121.94	76.27	-4,095.33	10,997.24	4,095.99	3,854.33	241.66	16.949	ES		
18,159.20	7,289.00	16,890.04	6,303.00	126.27	121.94	76.27	-4,095.33	10,997.24	4,096.76	3,854.44	242.32	16.906	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W02_GOVERNMENT AO COM #001_1524032 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 121-INC-NONLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
6,500.00	6,495.11	6,467.88	6,462.11	22.54	169.06	-141.34	-3,845.88	-2,992.54	4,694.70	4,503.15	191.54	24.510	
6,569.74	6,564.85	6,537.77	6,531.62	22.78	174.17	-141.34	-3,844.77	-2,992.54	4,693.83	4,496.94	196.89	23.840	CC
6,600.00	6,595.11	6,542.30	6,536.14	22.88	174.49	-141.34	-3,844.79	-2,992.54	4,693.92	4,496.60	197.32	23.788	
6,700.00	6,695.11	6,669.14	6,662.11	23.23	183.24	-141.34	-3,845.88	-2,992.54	4,694.70	4,488.28	206.42	22.744	
6,720.93	6,716.04	6,690.07	6,683.04	23.30	184.54	-141.34	-3,845.88	-2,992.54	4,694.70	4,486.91	207.78	22.594	
6,750.00	6,745.09	6,719.13	6,712.09	23.40	186.33	127.43	-3,845.88	-2,992.54	4,695.15	4,485.47	209.68	22.392	ES
6,800.00	6,794.86	6,736.27	6,729.12	23.57	187.39	127.22	-3,844.01	-2,992.54	4,696.67	4,485.76	210.91	22.269	
6,850.00	6,844.02	6,818.71	6,811.02	23.74	192.30	126.89	-3,845.88	-2,992.54	4,703.52	4,487.53	215.99	21.777	
6,900.00	6,892.21	6,860.39	6,852.65	23.90	194.49	126.35	-3,844.65	-2,992.54	4,710.67	4,492.32	218.35	21.574	
6,950.00	6,939.05	6,873.67	6,865.92	24.06	195.19	125.49	-3,844.73	-2,992.54	4,721.59	4,502.38	219.21	21.539	
7,000.00	6,984.20	6,959.24	6,951.20	24.21	199.36	124.72	-3,845.88	-2,992.54	4,735.51	4,511.98	223.53	21.185	
7,050.00	7,027.31	6,987.22	6,979.14	24.35	200.61	123.50	-3,844.82	-2,992.54	4,750.37	4,525.44	224.93	21.120	
7,100.00	7,068.05	7,043.32	7,035.05	24.48	203.09	122.21	-3,845.88	-2,992.54	4,769.18	4,541.63	227.55	20.958	
7,150.00	7,106.11	7,081.38	7,073.11	24.62	204.60	120.60	-3,845.88	-2,992.54	4,789.47	4,560.27	229.20	20.897	
7,200.00	7,141.21	7,098.00	7,089.71	24.76	205.26	118.54	-3,845.29	-2,992.54	4,811.49	4,581.51	229.98	20.921	
7,250.00	7,173.06	7,148.46	7,140.06	24.90	207.23	116.51	-3,845.88	-2,992.54	4,836.36	4,604.29	232.07	20.840	SF
7,300.00	7,201.44	7,176.84	7,168.44	25.03	208.29	114.00	-3,845.88	-2,992.54	4,862.69	4,629.45	233.24	20.848	
7,350.00	7,226.12	7,201.53	7,193.12	25.17	209.21	111.16	-3,845.88	-2,992.54	4,890.73	4,656.46	234.27	20.877	
7,400.00	7,246.93	7,222.33	7,213.93	25.30	209.98	107.96	-3,845.88	-2,992.54	4,920.28	4,685.14	235.14	20.925	
7,450.00	7,263.69	7,239.09	7,230.69	25.43	210.61	104.42	-3,845.88	-2,992.54	4,951.15	4,715.30	235.86	20.992	
7,500.00	7,276.28	7,251.68	7,243.28	25.56	211.08	100.53	-3,845.88	-2,992.54	4,983.13	4,746.72	236.41	21.078	
7,550.00	7,284.61	7,260.01	7,251.61	25.68	211.39	96.35	-3,845.88	-2,992.54	5,015.99	4,779.19	236.80	21.183	
7,600.00	7,288.62	7,262.43	7,253.98	25.80	211.48	91.89	-3,844.26	-2,992.54	5,048.29	4,811.33	236.96	21.304	
7,620.93	7,289.00	7,262.64	7,254.20	25.85	211.49	89.97	-3,844.26	-2,992.54	5,062.44	4,825.45	237.00	21.361	
7,701.87	7,289.00	7,262.64	7,254.20	26.06	211.49	89.97	-3,844.26	-2,992.54	5,118.42	4,881.31	237.11	21.586	
7,800.00	7,289.00	7,262.64	7,254.20	26.35	211.49	89.97	-3,844.26	-2,992.54	5,188.15	4,950.89	237.27	21.866	
7,900.00	7,289.00	7,262.64	7,254.20	26.69	211.49	89.97	-3,844.26	-2,992.54	5,260.15	5,022.71	237.44	22.154	
8,000.00	7,289.00	7,262.64	7,254.20	27.08	211.49	89.97	-3,844.26	-2,992.54	5,333.04	5,095.42	237.62	22.444	
8,100.00	7,289.00	7,262.64	7,254.20	27.50	211.49	89.97	-3,844.26	-2,992.54	5,406.81	5,168.99	237.81	22.735	
8,200.00	7,289.00	7,262.64	7,254.20	27.96	211.49	89.97	-3,844.26	-2,992.54	5,481.40	5,243.38	238.02	23.029	
8,300.00	7,289.00	7,262.64	7,254.20	28.46	211.49	89.97	-3,844.26	-2,992.54	5,556.79	5,318.56	238.23	23.325	
8,400.00	7,289.00	7,262.64	7,254.20	28.99	211.49	89.97	-3,844.26	-2,992.54	5,632.95	5,394.50	238.45	23.623	
8,500.00	7,289.00	7,262.64	7,254.20	29.56	211.49	89.97	-3,844.26	-2,992.54	5,709.85	5,471.17	238.68	23.923	
8,600.00	7,289.00	7,262.64	7,254.20	30.16	211.49	89.97	-3,844.26	-2,992.54	5,787.45	5,548.54	238.91	24.224	
8,700.00	7,289.00	7,262.64	7,254.20	30.79	211.49	89.97	-3,844.26	-2,992.54	5,865.73	5,626.58	239.15	24.527	
8,800.00	7,289.00	7,262.64	7,254.20	31.44	211.49	89.97	-3,844.26	-2,992.54	5,944.66	5,705.27	239.39	24.833	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W04_FEDERAL V #001_1526451 - Inc Only - Inc Only													Offset Site Error:	0.00 usft	
Survey Program:		456-INC-ONLY					Rule Assigned:							Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance			Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)				
3,400.00	3,397.14	3,367.44	3,366.88	11.71	73.64	40.14	-1,187.75	-1,806.83	2,076.66	1,991.33	85.33	24.338			
3,500.00	3,497.00	3,461.26	3,460.69	12.07	75.72	40.22	-1,188.38	-1,806.83	2,072.99	1,985.23	87.76	23.621			
3,600.00	3,596.86	3,571.49	3,570.86	12.42	78.15	40.29	-1,189.55	-1,806.83	2,069.56	1,979.01	90.55	22.856			
3,700.00	3,696.73	3,671.35	3,670.73	12.78	80.28	40.39	-1,189.55	-1,806.83	2,065.54	1,972.52	93.03	22.204			
3,800.00	3,796.59	3,771.22	3,770.59	13.14	82.40	40.48	-1,189.55	-1,806.83	2,061.54	1,966.03	95.51	21.585			
3,900.00	3,896.45	3,869.44	3,868.81	13.50	84.49	40.59	-1,189.11	-1,806.83	2,057.31	1,959.36	97.95	21.003			
4,000.00	3,996.31	3,967.37	3,966.74	13.86	86.57	40.67	-1,189.35	-1,806.83	2,053.45	1,953.05	100.39	20.454			
4,100.00	4,096.17	4,070.88	4,070.17	14.21	88.96	40.77	-1,189.55	-1,806.83	2,049.56	1,946.42	103.14	19.871			
4,200.00	4,196.03	4,170.74	4,170.03	14.57	91.46	40.86	-1,189.55	-1,806.83	2,045.58	1,939.58	105.99	19.299			
4,300.00	4,295.90	4,270.36	4,269.63	14.93	93.95	41.00	-1,187.93	-1,806.83	2,040.78	1,931.94	108.84	18.751			
4,400.00	4,395.76	4,365.07	4,364.33	15.29	96.31	41.08	-1,188.19	-1,806.83	2,036.95	1,925.39	111.56	18.259			
4,500.00	4,495.62	4,459.84	4,459.09	15.65	98.68	41.16	-1,188.93	-1,806.83	2,033.38	1,919.10	114.28	17.793			
4,600.00	4,595.48	4,570.36	4,569.48	16.01	101.66	41.25	-1,189.55	-1,806.83	2,029.71	1,912.09	117.62	17.257			
4,700.00	4,695.34	4,661.12	4,660.23	16.37	104.27	41.35	-1,189.24	-1,806.83	2,025.62	1,905.03	120.59	16.797			
4,803.94	4,799.14	4,774.12	4,773.14	16.74	107.79	41.45	-1,189.55	-1,806.83	2,021.65	1,897.17	124.48	16.241			
4,900.00	4,895.12	4,859.27	4,858.24	17.09	110.50	41.51	-1,188.61	-1,806.83	2,018.33	1,890.79	127.54	15.825			
5,004.89	5,000.00	4,975.18	4,974.00	17.45	114.04	-120.03	-1,189.55	-1,806.83	2,017.69	1,886.26	131.44	15.351			
5,100.00	5,095.11	5,070.29	5,069.11	17.77	116.81	-120.03	-1,189.55	-1,806.83	2,017.69	1,883.16	134.53	14.998			
5,194.12	5,189.23	5,164.40	5,163.18	18.08	119.55	-119.97	-1,187.12	-1,806.83	2,016.48	1,878.89	137.59	14.656	CC		
5,200.00	5,195.11	5,169.85	5,168.62	18.10	119.71	-119.97	-1,187.12	-1,806.83	2,016.48	1,878.71	137.77	14.637			
5,300.00	5,295.11	5,262.52	5,261.27	18.44	122.41	-119.98	-1,187.50	-1,806.83	2,016.68	1,875.87	140.81	14.322			
5,400.00	5,395.11	5,355.23	5,353.95	18.78	125.12	-120.01	-1,188.56	-1,806.83	2,017.26	1,873.41	143.85	14.023			
5,500.00	5,495.11	5,470.59	5,469.11	19.12	128.25	-120.03	-1,189.55	-1,806.83	2,017.69	1,870.37	147.32	13.696			
5,600.00	5,595.11	5,570.59	5,569.11	19.46	130.77	-120.03	-1,189.55	-1,806.83	2,017.69	1,867.51	150.18	13.435			
5,693.92	5,689.02	5,664.27	5,662.76	19.78	133.13	-119.98	-1,187.65	-1,806.83	2,016.74	1,863.88	152.86	13.193			
5,700.00	5,695.11	5,670.00	5,668.49	19.80	133.27	-119.98	-1,187.65	-1,806.83	2,016.74	1,863.72	153.03	13.179			
5,800.00	5,795.11	5,764.21	5,762.69	20.14	135.65	-119.99	-1,187.98	-1,806.83	2,016.92	1,861.18	155.74	12.950			
5,900.00	5,895.11	5,858.45	5,856.90	20.48	138.02	-120.01	-1,188.86	-1,806.83	2,017.38	1,858.92	158.46	12.731			
6,000.00	5,995.11	5,970.76	5,969.11	20.82	140.66	-120.03	-1,189.55	-1,806.83	2,017.69	1,856.25	161.44	12.498			
6,100.00	6,095.11	6,070.76	6,069.11	21.16	142.87	-120.03	-1,189.55	-1,806.83	2,017.69	1,853.69	164.00	12.303			
6,185.70	6,180.81	6,156.46	6,154.79	21.46	144.77	-120.00	-1,188.20	-1,806.83	2,017.02	1,850.83	166.19	12.137			
6,200.00	6,195.11	6,170.15	6,168.48	21.51	145.07	-120.00	-1,188.20	-1,806.83	2,017.02	1,850.48	166.54	12.111			
6,300.00	6,295.11	6,265.92	6,264.25	21.85	147.19	-120.00	-1,188.46	-1,806.83	2,017.15	1,848.15	169.01	11.935			
6,400.00	6,395.11	6,361.70	6,360.02	22.19	149.31	-120.02	-1,189.13	-1,806.83	2,017.50	1,846.03	171.47	11.766			
6,500.00	6,495.11	6,470.86	6,469.11	22.54	151.80	-120.03	-1,189.55	-1,806.83	2,017.69	1,843.39	174.30	11.576			
6,600.00	6,595.11	6,570.86	6,569.11	22.88	154.11	-120.03	-1,189.55	-1,806.83	2,017.69	1,840.73	176.96	11.402			
6,678.63	6,673.73	6,649.48	6,647.72	23.15	155.94	-120.00	-1,188.48	-1,806.83	2,017.16	1,838.10	179.05	11.266			
6,700.00	6,695.11	6,670.12	6,668.36	23.23	156.41	-120.00	-1,188.48	-1,806.83	2,017.16	1,837.55	179.61	11.231			
6,720.93	6,716.04	6,690.33	6,688.57	23.30	156.88	-120.00	-1,188.51	-1,806.83	2,017.17	1,837.02	180.15	11.197			
6,750.00	6,745.09	6,718.38	6,716.62	23.40	157.53	148.77	-1,188.56	-1,806.83	2,017.83	1,836.93	180.90	11.155	ES		
6,800.00	6,794.86	6,766.43	6,764.67	23.57	158.64	148.62	-1,188.72	-1,806.83	2,021.94	1,839.76	182.18	11.099			
6,850.00	6,844.02	6,813.90	6,812.13	23.74	159.74	148.32	-1,188.96	-1,806.83	2,029.80	1,846.35	183.45	11.065			
6,900.00	6,892.21	6,860.44	6,858.67	23.90	160.82	147.88	-1,189.27	-1,806.83	2,041.35	1,856.66	184.69	11.053			
6,950.00	6,939.05	6,914.92	6,913.05	24.06	162.14	147.32	-1,189.55	-1,806.83	2,056.46	1,870.28	186.18	11.046	SF		
7,000.00	6,984.20	6,960.07	6,958.20	24.21	163.33	146.55	-1,189.55	-1,806.83	2,074.95	1,887.44	187.51	11.066			
7,050.00	7,027.31	7,003.18	7,001.31	24.35	164.46	145.56	-1,189.55	-1,806.83	2,096.84	1,908.05	188.79	11.107			
7,100.00	7,068.05	7,043.92	7,042.05	24.48	165.53	144.32	-1,189.55	-1,806.83	2,121.99	1,932.00	189.99	11.169			
7,150.00	7,106.11	7,081.98	7,080.11	24.62	166.52	142.76	-1,189.55	-1,806.83	2,150.23	1,959.13	191.11	11.252			
7,200.00	7,141.21	7,117.07	7,115.21	24.76	167.44	140.81	-1,189.55	-1,806.83	2,181.40	1,989.26	192.14	11.353			
7,250.00	7,173.06	7,148.60	7,146.71	24.90	168.27	138.42	-1,187.93	-1,806.83	2,214.54	2,021.48	193.06	11.471			
7,300.00	7,201.44	7,175.56	7,173.67	25.03	168.98	135.36	-1,187.96	-1,806.83	2,250.92	2,057.07	193.85	11.611			
7,350.00	7,226.12	7,199.01	7,197.12	25.17	169.59	131.53	-1,188.01	-1,806.83	2,289.54	2,094.99	194.54	11.769			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W04_FEDERAL V #001_1526451 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 456-INC-ONLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
7,400.00	7,246.93	7,218.78	7,216.88	25.30	170.11	126.73	-1,188.08	-1,806.83	2,330.10	2,134.98	195.12	11.942	
7,450.00	7,263.69	7,234.71	7,232.81	25.43	170.53	120.74	-1,188.15	-1,806.83	2,372.32	2,176.73	195.59	12.129	
7,500.00	7,276.28	7,246.68	7,244.78	25.56	170.84	113.35	-1,188.22	-1,806.83	2,415.87	2,219.92	195.95	12.329	
7,550.00	7,284.61	7,254.60	7,252.70	25.68	171.05	104.45	-1,188.26	-1,806.83	2,460.42	2,264.23	196.19	12.541	
7,600.00	7,288.62	7,258.41	7,256.51	25.80	171.15	94.22	-1,188.28	-1,806.83	2,505.63	2,309.30	196.32	12.763	
7,620.93	7,289.00	7,258.78	7,256.88	25.85	171.16	89.66	-1,188.29	-1,806.83	2,524.66	2,328.32	196.34	12.858	
7,701.87	7,289.00	7,258.78	7,256.88	26.06	171.16	89.64	-1,188.29	-1,806.83	2,599.01	2,402.63	196.38	13.234	
7,800.00	7,289.00	7,258.78	7,256.88	26.35	171.16	89.64	-1,188.29	-1,806.83	2,690.17	2,493.75	196.43	13.695	
7,900.00	7,289.00	7,258.77	7,256.87	26.69	171.16	89.64	-1,188.29	-1,806.83	2,783.56	2,587.08	196.48	14.167	
8,000.00	7,289.00	7,258.77	7,256.87	27.08	171.16	89.64	-1,188.29	-1,806.83	2,877.40	2,680.87	196.53	14.641	
8,100.00	7,289.00	7,258.76	7,256.86	27.50	171.16	89.64	-1,188.29	-1,806.83	2,971.63	2,775.05	196.58	15.117	
8,200.00	7,289.00	7,258.76	7,256.86	27.96	171.16	89.64	-1,188.29	-1,806.83	3,066.23	2,869.60	196.63	15.594	
8,300.00	7,289.00	7,258.76	7,256.85	28.46	171.16	89.64	-1,188.29	-1,806.83	3,161.17	2,964.48	196.69	16.072	
8,400.00	7,289.00	7,258.75	7,256.85	28.99	171.16	89.64	-1,188.29	-1,806.83	3,256.40	3,059.66	196.74	16.552	
8,500.00	7,289.00	7,258.75	7,256.85	29.56	171.16	89.64	-1,188.29	-1,806.83	3,351.92	3,155.12	196.80	17.032	
8,600.00	7,289.00	7,258.74	7,256.84	30.16	171.16	89.64	-1,188.29	-1,806.83	3,447.69	3,250.84	196.85	17.514	
8,700.00	7,289.00	7,258.74	7,256.84	30.79	171.16	89.64	-1,188.29	-1,806.83	3,543.69	3,346.78	196.90	17.997	
8,800.00	7,289.00	7,258.74	7,256.83	31.44	171.16	89.64	-1,188.29	-1,806.83	3,639.91	3,442.95	196.96	18.481	
8,900.00	7,289.00	7,258.73	7,256.83	32.12	171.16	89.64	-1,188.29	-1,806.83	3,736.32	3,539.31	197.01	18.965	
9,000.00	7,289.00	7,258.73	7,256.82	32.82	171.16	89.64	-1,188.29	-1,806.83	3,832.92	3,635.85	197.07	19.450	
9,100.00	7,289.00	7,258.72	7,256.82	33.55	171.16	89.64	-1,188.29	-1,806.83	3,929.69	3,732.57	197.12	19.935	
9,200.00	7,289.00	7,258.72	7,256.82	34.30	171.16	89.64	-1,188.29	-1,806.83	4,026.62	3,829.44	197.18	20.421	
9,300.00	7,289.00	7,258.71	7,256.81	35.07	171.16	89.64	-1,188.29	-1,806.83	4,123.69	3,926.47	197.23	20.908	
9,400.00	7,289.00	7,258.71	7,256.81	35.86	171.16	89.64	-1,188.29	-1,806.83	4,220.91	4,023.62	197.28	21.395	
9,500.00	7,289.00	7,258.71	7,256.80	36.66	171.16	89.64	-1,188.29	-1,806.83	4,318.24	4,120.91	197.34	21.883	
9,600.00	7,289.00	7,258.70	7,256.80	37.48	171.16	89.64	-1,188.29	-1,806.83	4,415.70	4,218.31	197.39	22.370	
9,700.00	7,289.00	7,258.70	7,256.79	38.32	171.16	89.64	-1,188.29	-1,806.83	4,513.27	4,315.82	197.45	22.858	
9,800.00	7,289.00	7,258.69	7,256.79	39.17	171.16	89.64	-1,188.29	-1,806.83	4,610.94	4,413.44	197.50	23.347	
9,900.00	7,289.00	7,258.69	7,256.79	40.03	171.16	89.64	-1,188.29	-1,806.83	4,708.71	4,511.16	197.55	23.835	
10,000.00	7,289.00	7,258.68	7,256.78	40.91	171.16	89.64	-1,188.29	-1,806.83	4,806.58	4,608.97	197.61	24.324	
10,100.00	7,289.00	7,258.68	7,256.78	41.80	171.16	89.64	-1,188.29	-1,806.83	4,904.52	4,706.86	197.66	24.813	



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W05_FEDERAL V #002_1526702 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 400-INC-ONLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
2,900.00	2,897.83	2,875.87	2,875.47	9.93	61.86	78.35	130.50	-1,794.40	1,780.24	1,708.45	71.79	24.799	
3,000.00	2,997.69	2,973.22	2,972.69	10.29	64.06	78.50	130.27	-1,794.40	1,779.15	1,704.81	74.35	23.931	
3,100.00	3,097.56	3,073.08	3,072.56	10.64	66.28	78.67	130.27	-1,794.40	1,778.11	1,701.20	76.92	23.118	
3,200.00	3,197.42	3,173.33	3,172.79	11.00	68.50	78.88	131.87	-1,794.40	1,777.29	1,697.79	79.49	22.357	
3,300.00	3,297.28	3,274.48	3,273.93	11.35	70.74	79.04	131.42	-1,794.40	1,776.22	1,694.13	82.09	21.637	
3,400.00	3,397.14	3,375.71	3,375.13	11.71	72.99	79.18	130.44	-1,794.40	1,775.10	1,690.41	84.69	20.959	
3,500.00	3,497.00	3,472.62	3,472.00	12.07	74.91	79.33	130.27	-1,794.40	1,774.09	1,687.12	86.98	20.397	
3,600.00	3,596.86	3,572.49	3,571.86	12.42	76.86	79.50	130.27	-1,794.40	1,773.13	1,683.84	89.28	19.860	
3,700.00	3,696.73	3,672.74	3,672.12	12.78	78.81	79.69	130.98	-1,794.40	1,772.27	1,680.68	91.60	19.349	
3,800.00	3,796.59	3,773.36	3,772.73	13.14	80.78	79.85	130.68	-1,794.40	1,771.29	1,677.38	93.92	18.861	
3,900.00	3,896.45	3,872.11	3,871.45	13.50	82.70	80.00	130.27	-1,794.40	1,770.31	1,674.11	96.20	18.402	
4,000.00	3,996.31	3,971.97	3,971.31	13.86	84.66	80.17	130.27	-1,794.40	1,769.41	1,670.90	98.51	17.962	
4,100.00	4,096.17	4,071.83	4,071.17	14.21	86.61	80.34	130.27	-1,794.40	1,768.52	1,667.70	100.82	17.541	
4,200.00	4,196.03	4,172.15	4,171.49	14.57	88.57	80.53	131.07	-1,794.40	1,767.76	1,664.62	103.14	17.139	
4,300.00	4,295.90	4,272.75	4,272.07	14.93	90.53	80.69	130.78	-1,794.40	1,766.86	1,661.39	105.46	16.753	
4,400.00	4,395.76	4,371.46	4,370.76	15.29	92.47	80.84	130.27	-1,794.40	1,765.93	1,658.17	107.76	16.388	
4,500.00	4,495.62	4,471.32	4,470.62	15.65	94.60	81.01	130.27	-1,794.40	1,765.10	1,654.86	110.25	16.011	
4,600.00	4,595.48	4,571.19	4,570.48	16.01	96.72	81.18	130.27	-1,794.40	1,764.29	1,651.56	112.73	15.651	
4,700.00	4,695.34	4,671.53	4,670.82	16.37	98.86	81.37	131.03	-1,794.40	1,763.61	1,648.39	115.22	15.306	
4,803.94	4,799.14	4,776.20	4,775.49	16.74	101.09	81.54	130.71	-1,794.40	1,762.75	1,644.92	117.83	14.961	
4,900.00	4,895.12	4,870.90	4,870.12	17.09	103.11	81.64	130.27	-1,794.40	1,762.11	1,641.91	120.20	14.660	
5,004.89	5,000.00	4,975.78	4,975.00	17.45	105.44	-79.86	130.27	-1,794.40	1,761.90	1,639.01	122.88	14.338	
5,100.00	5,095.11	5,070.89	5,070.11	17.77	107.54	-79.86	130.27	-1,794.40	1,761.90	1,636.59	125.31	14.060	
5,200.00	5,195.11	5,172.51	5,171.71	18.10	109.79	-79.84	131.18	-1,794.40	1,762.06	1,634.16	127.90	13.777	
5,300.00	5,295.11	5,274.16	5,273.35	18.44	112.04	-79.86	130.40	-1,794.40	1,761.92	1,631.44	130.48	13.503	
5,323.30	5,318.41	5,294.27	5,293.41	18.52	112.48	-79.86	130.27	-1,794.40	1,761.90	1,630.90	131.00	13.450	
5,400.00	5,395.11	5,371.06	5,370.19	18.78	114.12	-79.85	130.63	-1,794.40	1,761.96	1,629.07	132.89	13.258	
5,500.00	5,495.11	5,471.00	5,470.11	19.12	116.24	-79.86	130.27	-1,794.40	1,761.90	1,626.54	135.36	13.016	
5,600.00	5,595.11	5,571.00	5,570.11	19.46	118.37	-79.86	130.27	-1,794.40	1,761.90	1,624.07	137.83	12.783	
5,700.00	5,695.11	5,671.00	5,670.11	19.80	120.50	-79.86	130.27	-1,794.40	1,761.90	1,621.60	140.30	12.558	
5,800.00	5,795.11	5,771.71	5,770.80	20.14	122.64	-79.83	131.31	-1,794.40	1,762.08	1,619.30	142.78	12.341	
5,900.00	5,895.11	5,872.80	5,871.90	20.48	124.80	-79.84	130.91	-1,794.40	1,762.01	1,616.74	145.27	12.129	
6,000.00	5,995.11	5,971.07	5,970.11	20.82	126.90	-79.86	130.27	-1,794.40	1,761.90	1,614.17	147.72	11.927	
6,100.00	6,095.11	6,071.07	6,070.11	21.16	129.21	-79.86	130.27	-1,794.40	1,761.90	1,611.53	150.37	11.717	
6,200.00	6,195.11	6,171.07	6,170.11	21.51	131.51	-79.86	130.27	-1,794.40	1,761.90	1,608.88	153.01	11.515	
6,300.00	6,295.11	6,271.07	6,270.11	21.85	133.81	-79.86	130.27	-1,794.40	1,761.90	1,606.24	155.66	11.319	
6,303.35	6,298.45	6,274.42	6,273.45	21.86	133.89	-79.86	130.27	-1,794.40	1,761.90	1,606.15	155.75	11.312 CC	
6,400.00	6,395.11	6,330.00	6,328.94	22.19	135.17	-79.86	130.27	-1,794.40	1,762.38	1,605.06	157.32	11.202 ES, SF	
6,500.00	6,495.11	6,330.00	6,328.94	22.54	135.17	-79.86	130.27	-1,794.40	1,767.54	1,610.31	157.23	11.242	
6,600.00	6,595.11	6,330.00	6,328.94	22.88	135.17	-79.86	130.27	-1,794.40	1,778.33	1,621.65	156.67	11.351	
6,700.00	6,695.11	6,330.00	6,328.94	23.23	135.17	-79.86	130.27	-1,794.40	1,794.62	1,638.96	155.66	11.529	
6,720.93	6,716.04	6,330.00	6,328.94	23.30	135.17	-79.86	130.27	-1,794.40	1,798.72	1,643.32	155.40	11.575	
6,750.00	6,745.09	6,330.00	6,328.94	23.40	135.17	-170.96	130.27	-1,794.40	1,805.50	1,650.50	155.01	11.648	
6,800.00	6,794.86	6,330.00	6,328.94	23.57	135.17	-170.69	130.27	-1,794.40	1,821.45	1,667.17	154.27	11.807	
6,850.00	6,844.02	6,330.00	6,328.94	23.74	135.17	-170.30	130.27	-1,794.40	1,842.57	1,689.07	153.49	12.004	
6,900.00	6,892.21	6,330.00	6,328.94	23.90	135.17	-169.78	130.27	-1,794.40	1,868.53	1,715.84	152.69	12.237	
6,950.00	6,939.05	6,330.00	6,328.94	24.06	135.17	-169.07	130.27	-1,794.40	1,898.94	1,747.04	151.89	12.502	
7,000.00	6,984.20	6,330.00	6,328.94	24.21	135.17	-168.13	130.27	-1,794.40	1,933.36	1,782.24	151.12	12.793	
7,050.00	7,027.31	6,330.00	6,328.94	24.35	135.17	-166.86	130.27	-1,794.40	1,971.33	1,820.93	150.41	13.107	
7,100.00	7,068.05	6,330.00	6,328.94	24.48	135.17	-165.12	130.27	-1,794.40	2,012.38	1,862.61	149.77	13.437	
7,150.00	7,106.11	6,330.00	6,328.94	24.62	135.17	-162.63	130.27	-1,794.40	2,056.00	1,906.79	149.21	13.779	
7,200.00	7,141.21	6,330.00	6,328.94	24.76	135.17	-158.90	130.27	-1,794.40	2,101.72	1,952.97	148.76	14.129	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W05_FEDERAL V #002_1526702 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 400-INC-ONLY													Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
		Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
7,250.00	7,173.06	6,330.00	6,328.94	24.90	135.17	-152.85	130.27	-1,794.40	2,149.08	2,000.67	148.41	14.481	
7,300.00	7,201.44	6,330.00	6,328.94	25.03	135.17	-141.93	130.27	-1,794.40	2,197.60	2,049.43	148.17	14.831	
7,350.00	7,226.12	6,330.00	6,328.94	25.17	135.17	-120.05	130.27	-1,794.40	2,246.87	2,098.83	148.05	15.177	
7,400.00	7,246.93	6,330.00	6,328.94	25.30	135.17	-82.03	130.27	-1,794.40	2,296.48	2,148.45	148.03	15.514	
7,450.00	7,263.69	6,330.00	6,328.94	25.43	135.17	-48.86	130.27	-1,794.40	2,346.02	2,197.91	148.11	15.840	
7,500.00	7,276.28	6,330.00	6,328.94	25.56	135.17	-31.74	130.27	-1,794.40	2,395.15	2,246.86	148.30	16.151	
7,550.00	7,284.61	6,330.00	6,328.94	25.68	135.17	-22.94	130.27	-1,794.40	2,443.53	2,294.96	148.57	16.447	
7,600.00	7,288.62	6,330.00	6,328.94	25.80	135.17	-17.84	130.27	-1,794.40	2,490.84	2,341.91	148.93	16.725	
7,620.93	7,289.00	6,330.00	6,328.94	25.85	135.17	-16.31	130.27	-1,794.40	2,510.25	2,361.15	149.10	16.836	
7,701.87	7,289.00	6,330.00	6,328.94	26.06	135.17	-19.98	130.27	-1,794.40	2,584.90	2,435.13	149.77	17.259	
7,800.00	7,289.00	6,330.00	6,328.94	26.35	135.17	-19.98	130.27	-1,794.40	2,675.74	2,525.23	150.51	17.778	
7,900.00	7,289.00	6,330.00	6,328.94	26.69	135.17	-19.98	130.27	-1,794.40	2,768.82	2,617.62	151.20	18.312	
8,000.00	7,289.00	6,330.00	6,328.94	27.08	135.17	-19.98	130.27	-1,794.40	2,862.37	2,710.54	151.83	18.853	
8,100.00	7,289.00	6,330.00	6,328.94	27.50	135.17	-19.98	130.27	-1,794.40	2,956.34	2,803.94	152.40	19.399	
8,200.00	7,289.00	6,330.00	6,328.94	27.96	135.17	-19.98	130.27	-1,794.40	3,050.69	2,897.77	152.92	19.950	
8,300.00	7,289.00	6,330.00	6,328.94	28.46	135.17	-19.98	130.27	-1,794.40	3,145.39	2,991.99	153.40	20.505	
8,400.00	7,289.00	6,330.00	6,328.94	28.99	135.17	-19.98	130.27	-1,794.40	3,240.41	3,086.57	153.84	21.063	
8,500.00	7,289.00	6,330.00	6,328.94	29.56	135.17	-19.98	130.27	-1,794.40	3,335.72	3,181.47	154.25	21.626	
8,600.00	7,289.00	6,330.00	6,328.94	30.16	135.17	-19.98	130.27	-1,794.40	3,431.30	3,276.67	154.63	22.191	
8,700.00	7,289.00	6,330.00	6,328.94	30.79	135.17	-19.98	130.27	-1,794.40	3,527.12	3,372.14	154.98	22.759	
8,800.00	7,289.00	6,330.00	6,328.94	31.44	135.17	-19.98	130.27	-1,794.40	3,623.17	3,467.87	155.30	23.330	
8,900.00	7,289.00	6,330.00	6,328.94	32.12	135.17	-19.98	130.27	-1,794.40	3,719.43	3,563.82	155.61	23.903	
9,000.00	7,289.00	6,330.00	6,328.94	32.82	135.17	-19.98	130.27	-1,794.40	3,815.87	3,659.98	155.89	24.478	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W06_FEDERAL V #003_1526867 - Depth Only - Depth Only													Offset Site Error: 0.00 usft
Survey Program: 6300-INC-ONLY													Offset Well Error: 0.00 usft
Reference	Offset	Rule Assigned:											
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
							+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
2,700.00	2,698.11	2,675.11	2,675.11	9.22	168.97	56.66	-1,199.49	-4,262.31	4,386.96	4,208.77	178.19	24.620	
2,800.00	2,797.97	2,774.97	2,774.97	9.58	175.28	56.71	-1,199.49	-4,262.31	4,384.07	4,199.22	184.85	23.717	
2,900.00	2,897.83	2,874.83	2,874.83	9.93	181.59	56.77	-1,199.49	-4,262.31	4,381.18	4,189.67	191.51	22.877	
3,000.00	2,997.69	2,974.69	2,974.69	10.29	187.90	56.83	-1,199.49	-4,262.31	4,378.30	4,180.13	198.17	22.093	
3,100.00	3,097.56	3,074.56	3,074.56	10.64	194.20	56.89	-1,199.49	-4,262.31	4,375.42	4,170.59	204.84	21.361	
3,200.00	3,197.42	3,174.42	3,174.42	11.00	200.51	56.94	-1,199.49	-4,262.31	4,372.55	4,161.05	211.50	20.674	
3,300.00	3,297.28	3,274.28	3,274.28	11.35	206.82	57.00	-1,199.49	-4,262.31	4,369.68	4,151.52	218.16	20.030	
3,400.00	3,397.14	3,374.14	3,374.14	11.71	213.13	57.06	-1,199.49	-4,262.31	4,366.82	4,141.99	224.82	19.423	
3,500.00	3,497.00	3,474.00	3,474.00	12.07	219.44	57.12	-1,199.49	-4,262.31	4,363.96	4,132.47	231.49	18.852	
3,600.00	3,596.86	3,573.86	3,573.86	12.42	225.74	57.18	-1,199.49	-4,262.31	4,361.10	4,122.95	238.15	18.312	
3,700.00	3,696.73	3,673.73	3,673.73	12.78	232.05	57.23	-1,199.49	-4,262.31	4,358.25	4,113.43	244.82	17.802	
3,800.00	3,796.59	3,773.59	3,773.59	13.14	238.36	57.29	-1,199.49	-4,262.31	4,355.40	4,103.92	251.48	17.319	
3,900.00	3,896.45	3,873.45	3,873.45	13.50	244.67	57.35	-1,199.49	-4,262.31	4,352.56	4,094.41	258.15	16.861	
4,000.00	3,996.31	3,973.31	3,973.31	13.86	250.97	57.41	-1,199.49	-4,262.31	4,349.72	4,084.91	264.81	16.426	
4,100.00	4,096.17	4,073.17	4,073.17	14.21	257.28	57.47	-1,199.49	-4,262.31	4,346.89	4,075.41	271.48	16.012	
4,200.00	4,196.03	4,173.03	4,173.03	14.57	263.59	57.53	-1,199.49	-4,262.31	4,344.06	4,065.92	278.14	15.618	
4,300.00	4,295.90	4,272.90	4,272.90	14.93	269.90	57.58	-1,199.49	-4,262.31	4,341.24	4,056.43	284.81	15.243	
4,400.00	4,395.76	4,372.76	4,372.76	15.29	276.21	57.64	-1,199.49	-4,262.31	4,338.42	4,046.94	291.48	14.884	
4,500.00	4,495.62	4,472.62	4,472.62	15.65	282.51	57.70	-1,199.49	-4,262.31	4,335.60	4,037.46	298.14	14.542	
4,600.00	4,595.48	4,572.48	4,572.48	16.01	288.82	57.76	-1,199.49	-4,262.31	4,332.79	4,027.99	304.81	14.215	
4,700.00	4,695.34	4,672.34	4,672.34	16.37	295.13	57.82	-1,199.49	-4,262.31	4,329.99	4,018.51	311.47	13.902	
4,803.94	4,799.14	4,776.14	4,776.14	16.74	301.68	57.88	-1,199.49	-4,262.31	4,327.08	4,008.67	318.40	13.590	
4,900.00	4,895.12	4,872.12	4,872.12	17.09	307.75	57.90	-1,199.49	-4,262.31	4,325.03	4,000.22	324.81	13.316	
5,004.89	5,000.00	4,977.00	4,977.00	17.45	314.37	-103.64	-1,199.49	-4,262.31	4,324.27	3,992.47	331.80	13.033	
5,100.00	5,095.11	5,072.11	5,072.11	17.77	320.38	-103.64	-1,199.49	-4,262.31	4,324.27	3,986.14	338.12	12.789	
5,200.00	5,195.11	5,172.11	5,172.11	18.10	326.70	-103.64	-1,199.49	-4,262.31	4,324.27	3,979.49	344.78	12.542	
5,300.00	5,295.11	5,272.11	5,272.11	18.44	333.01	-103.64	-1,199.49	-4,262.31	4,324.27	3,972.83	351.43	12.305	
5,400.00	5,395.11	5,372.11	5,372.11	18.78	339.33	-103.64	-1,199.49	-4,262.31	4,324.27	3,966.18	358.09	12.076	
5,500.00	5,495.11	5,472.11	5,472.11	19.12	345.65	-103.64	-1,199.49	-4,262.31	4,324.27	3,959.52	364.74	11.856	
5,600.00	5,595.11	5,572.11	5,572.11	19.46	351.96	-103.64	-1,199.49	-4,262.31	4,324.27	3,952.87	371.40	11.643	
5,700.00	5,695.11	5,672.11	5,672.11	19.80	358.28	-103.64	-1,199.49	-4,262.31	4,324.27	3,946.21	378.05	11.438	
5,800.00	5,795.11	5,772.11	5,772.11	20.14	364.59	-103.64	-1,199.49	-4,262.31	4,324.27	3,939.55	384.71	11.240	
5,900.00	5,895.11	5,872.11	5,872.11	20.48	370.91	-103.64	-1,199.49	-4,262.31	4,324.27	3,932.90	391.37	11.049	
6,000.00	5,995.11	5,972.11	5,972.11	20.82	377.23	-103.64	-1,199.49	-4,262.31	4,324.27	3,926.24	398.03	10.864	
6,100.00	6,095.11	6,072.11	6,072.11	21.16	383.54	-103.64	-1,199.49	-4,262.31	4,324.27	3,919.58	404.69	10.685	
6,200.00	6,195.11	6,172.11	6,172.11	21.51	389.86	-103.64	-1,199.49	-4,262.31	4,324.27	3,912.92	411.35	10.512	
6,300.00	6,295.11	6,272.11	6,272.11	21.85	396.18	-103.64	-1,199.49	-4,262.31	4,324.27	3,906.26	418.01	10.345 CC	
6,400.00	6,395.11	6,300.00	6,292.04	22.19	397.94	-103.64	-1,199.49	-4,262.31	4,325.01	3,904.96	420.05	10.296 ES, SF	
6,500.00	6,495.11	6,300.00	6,292.04	22.54	397.94	-103.64	-1,199.49	-4,262.31	4,328.01	3,907.90	420.11	10.302	
6,600.00	6,595.11	6,300.00	6,292.04	22.88	397.94	-103.64	-1,199.49	-4,262.31	4,333.33	3,913.37	419.95	10.319	
6,700.00	6,695.11	6,300.00	6,292.04	23.23	397.94	-103.64	-1,199.49	-4,262.31	4,340.94	3,921.36	419.58	10.346	
6,720.93	6,716.04	6,300.00	6,292.04	23.30	397.94	-103.64	-1,199.49	-4,262.31	4,342.82	3,923.35	419.47	10.353	
6,750.00	6,745.09	6,300.00	6,292.04	23.40	397.94	165.07	-1,199.49	-4,262.31	4,346.31	3,927.00	419.31	10.365	
6,800.00	6,794.86	6,300.00	6,292.04	23.57	397.94	164.81	-1,199.49	-4,262.31	4,356.04	3,937.04	419.00	10.396	
6,850.00	6,844.02	6,300.00	6,292.04	23.74	397.94	164.41	-1,199.49	-4,262.31	4,370.39	3,951.75	418.64	10.439	
6,900.00	6,892.21	6,300.00	6,292.04	23.90	397.94	163.86	-1,199.49	-4,262.31	4,389.21	3,970.96	418.25	10.494	
6,950.00	6,939.05	6,300.00	6,292.04	24.06	397.94	163.12	-1,199.49	-4,262.31	4,412.31	3,994.47	417.84	10.560	
7,000.00	6,984.20	6,300.00	6,292.04	24.21	397.94	162.15	-1,199.49	-4,262.31	4,439.43	4,022.01	417.41	10.636	
7,050.00	7,027.31	6,300.00	6,292.04	24.35	397.94	160.91	-1,199.49	-4,262.31	4,470.30	4,053.31	416.99	10.721	
7,100.00	7,068.05	6,300.00	6,292.04	24.48	397.94	159.30	-1,199.49	-4,262.31	4,504.61	4,088.05	416.57	10.814	
7,150.00	7,106.11	6,300.00	6,292.04	24.62	397.94	157.21	-1,199.49	-4,262.31	4,542.03	4,125.86	416.17	10.914	
7,200.00	7,141.21	6,300.00	6,292.04	24.76	397.94	154.44	-1,199.49	-4,262.31	4,582.20	4,166.40	415.80	11.020	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W06_FEDERAL V #003_1526867 - Depth Only - Depth Only												Offset Site Error:	0.00 usft
Survey Program: 6300-INC-ONLY				Rule Assigned:								Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance			Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)		
7,250.00	7,173.06	6,300.00	6,292.04	24.90	397.94	150.70	-1,199.49	-4,262.31	4,624.74	4,209.27	415.47	11.131	
7,300.00	7,201.44	6,300.00	6,292.04	25.03	397.94	145.52	-1,199.49	-4,262.31	4,669.28	4,254.08	415.19	11.246	
7,350.00	7,226.12	6,300.00	6,292.04	25.17	397.94	138.11	-1,199.49	-4,262.31	4,715.41	4,300.44	414.97	11.363	
7,400.00	7,246.93	6,300.00	6,292.04	25.30	397.94	127.28	-1,199.49	-4,262.31	4,762.76	4,347.95	414.81	11.482	
7,450.00	7,263.69	6,300.00	6,292.04	25.43	397.94	111.70	-1,199.49	-4,262.31	4,810.92	4,396.20	414.71	11.601	
7,500.00	7,276.28	6,300.00	6,292.04	25.56	397.94	91.59	-1,199.49	-4,262.31	4,859.51	4,444.83	414.68	11.719	
7,550.00	7,284.61	6,300.00	6,292.04	25.68	397.94	70.88	-1,199.49	-4,262.31	4,908.16	4,493.43	414.72	11.835	
7,600.00	7,288.62	6,300.00	6,292.04	25.80	397.94	54.16	-1,199.49	-4,262.31	4,956.50	4,541.66	414.83	11.948	
7,620.93	7,289.00	6,300.00	6,292.04	25.85	397.94	48.67	-1,199.49	-4,262.31	4,976.56	4,561.66	414.90	11.995	
7,701.87	7,289.00	6,300.00	6,292.04	26.06	397.94	44.93	-1,199.49	-4,262.31	5,054.15	4,638.98	415.17	12.174	
7,800.00	7,289.00	6,300.00	6,292.04	26.35	397.94	44.93	-1,199.49	-4,262.31	5,148.65	4,733.15	415.50	12.392	
7,900.00	7,289.00	6,300.00	6,292.04	26.69	397.94	44.93	-1,199.49	-4,262.31	5,245.08	4,829.27	415.81	12.614	
8,000.00	7,289.00	6,300.00	6,292.04	27.08	397.94	44.93	-1,199.49	-4,262.31	5,341.64	4,925.53	416.11	12.837	
8,100.00	7,289.00	6,300.00	6,292.04	27.50	397.94	44.93	-1,199.49	-4,262.31	5,438.33	5,021.93	416.40	13.060	
8,200.00	7,289.00	6,300.00	6,292.04	27.96	397.94	44.93	-1,199.49	-4,262.31	5,535.14	5,118.46	416.67	13.284	
8,300.00	7,289.00	6,300.00	6,292.04	28.46	397.94	44.93	-1,199.49	-4,262.31	5,632.05	5,215.12	416.94	13.508	
8,400.00	7,289.00	6,300.00	6,292.04	28.99	397.94	44.93	-1,199.49	-4,262.31	5,729.08	5,311.88	417.19	13.732	
8,500.00	7,289.00	6,300.00	6,292.04	29.56	397.94	44.93	-1,199.49	-4,262.31	5,826.20	5,408.76	417.44	13.957	
8,600.00	7,289.00	6,300.00	6,292.04	30.16	397.94	44.93	-1,199.49	-4,262.31	5,923.42	5,505.74	417.67	14.182	
8,700.00	7,289.00	6,300.00	6,292.04	30.79	397.94	44.93	-1,199.49	-4,262.31	6,020.73	5,602.83	417.90	14.407	
8,800.00	7,289.00	6,300.00	6,292.04	31.44	397.94	44.93	-1,199.49	-4,262.31	6,118.13	5,700.00	418.12	14.632	
8,900.00	7,289.00	6,300.00	6,292.04	32.12	397.94	44.93	-1,199.49	-4,262.31	6,215.60	5,797.27	418.34	14.858	
9,000.00	7,289.00	6,300.00	6,292.04	32.82	397.94	44.93	-1,199.49	-4,262.31	6,313.16	5,894.62	418.54	15.084	
9,100.00	7,289.00	6,300.00	6,292.04	33.55	397.94	44.93	-1,199.49	-4,262.31	6,410.80	5,992.06	418.74	15.310	
9,200.00	7,289.00	6,300.00	6,292.04	34.30	397.94	44.93	-1,199.49	-4,262.31	6,508.50	6,089.57	418.93	15.536	
9,300.00	7,289.00	6,300.00	6,292.04	35.07	397.94	44.93	-1,199.49	-4,262.31	6,606.28	6,187.15	419.12	15.762	
9,400.00	7,289.00	6,300.00	6,292.04	35.86	397.94	44.93	-1,199.49	-4,262.31	6,704.12	6,284.81	419.30	15.989	
9,500.00	7,289.00	6,300.00	6,292.04	36.66	397.94	44.93	-1,199.49	-4,262.31	6,802.02	6,382.54	419.48	16.215	
9,600.00	7,289.00	6,300.00	6,292.04	37.48	397.94	44.93	-1,199.49	-4,262.31	6,899.98	6,480.33	419.66	16.442	
9,700.00	7,289.00	6,300.00	6,292.04	38.32	397.94	44.93	-1,199.49	-4,262.31	6,998.00	6,578.18	419.82	16.669	
9,800.00	7,289.00	6,300.00	6,292.04	39.17	397.94	44.93	-1,199.49	-4,262.31	7,096.08	6,676.09	419.99	16.896	
9,900.00	7,289.00	6,300.00	6,292.04	40.03	397.94	44.93	-1,199.49	-4,262.31	7,194.21	6,774.06	420.15	17.123	
10,000.00	7,289.00	6,300.00	6,292.04	40.91	397.94	44.93	-1,199.49	-4,262.31	7,292.39	6,872.08	420.30	17.350	
10,100.00	7,289.00	6,300.00	6,292.04	41.80	397.94	44.93	-1,199.49	-4,262.31	7,390.62	6,970.16	420.46	17.578	
10,200.00	7,289.00	6,300.00	6,292.04	42.69	397.94	44.93	-1,199.49	-4,262.31	7,488.89	7,068.28	420.61	17.805	
10,300.00	7,289.00	6,300.00	6,292.04	43.60	397.94	44.93	-1,199.49	-4,262.31	7,587.21	7,166.46	420.75	18.032	
10,400.00	7,289.00	6,300.00	6,292.04	44.52	397.94	44.93	-1,199.49	-4,262.31	7,685.57	7,264.68	420.90	18.260	
10,500.00	7,289.00	6,300.00	6,292.04	45.45	397.94	44.93	-1,199.49	-4,262.31	7,783.98	7,362.94	421.04	18.488	
10,600.00	7,289.00	6,300.00	6,292.04	46.39	397.94	44.93	-1,199.49	-4,262.31	7,882.43	7,461.25	421.17	18.715	
10,700.00	7,289.00	6,300.00	6,292.04	47.33	397.94	44.93	-1,199.49	-4,262.31	7,980.91	7,559.60	421.31	18.943	
10,800.00	7,289.00	6,300.00	6,292.04	48.28	397.94	44.93	-1,199.49	-4,262.31	8,079.43	7,657.99	421.44	19.171	
10,900.00	7,289.00	6,300.00	6,292.04	49.24	397.94	44.93	-1,199.49	-4,262.31	8,177.99	7,756.41	421.57	19.399	
11,000.00	7,289.00	6,300.00	6,292.04	50.21	397.94	44.93	-1,199.49	-4,262.31	8,276.58	7,854.88	421.70	19.627	
11,100.00	7,289.00	6,300.00	6,292.04	51.18	397.94	44.93	-1,199.49	-4,262.31	8,375.21	7,953.38	421.83	19.854	
11,200.00	7,289.00	6,300.00	6,292.04	52.16	397.94	44.93	-1,199.49	-4,262.31	8,473.86	8,051.91	421.96	20.082	
11,300.00	7,289.00	6,300.00	6,292.04	53.15	397.94	44.93	-1,199.49	-4,262.31	8,572.55	8,150.47	422.08	20.310	
11,400.00	7,289.00	6,300.00	6,292.04	54.14	397.94	44.93	-1,199.49	-4,262.31	8,671.27	8,249.07	422.20	20.538	
11,500.00	7,289.00	6,300.00	6,292.04	55.13	397.94	44.93	-1,199.49	-4,262.31	8,770.02	8,347.70	422.32	20.766	
11,600.00	7,289.00	6,300.00	6,292.04	56.13	397.94	44.93	-1,199.49	-4,262.31	8,868.79	8,446.35	422.44	20.994	
11,700.00	7,289.00	6,300.00	6,292.04	57.13	397.94	44.93	-1,199.49	-4,262.31	8,967.60	8,545.04	422.56	21.222	
11,800.00	7,289.00	6,300.00	6,292.04	58.14	397.94	44.93	-1,199.49	-4,262.31	9,066.43	8,643.75	422.67	21.450	
11,900.00	7,289.00	6,300.00	6,292.04	59.16	397.94	44.93	-1,199.49	-4,262.31	9,165.28	8,742.49	422.79	21.678	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W06_FEDERAL V #003_1526867 - Depth Only - Depth Only													Offset Site Error: 0.00 usft
Survey Program: 6300-INC-ONLY													Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
		Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
12,000.00	7,289.00	6,300.00	6,292.04	60.17	397.94	44.93	-1,199.49	-4,262.31	9,264.16	8,841.26	422.90	21.906	
12,100.00	7,289.00	6,300.00	6,292.04	61.19	397.94	44.93	-1,199.49	-4,262.31	9,363.06	8,940.05	423.01	22.134	
12,200.00	7,289.00	6,300.00	6,292.04	62.22	397.94	44.93	-1,199.49	-4,262.31	9,461.99	9,038.86	423.13	22.362	
12,300.00	7,289.00	6,300.00	6,292.04	63.24	397.94	44.93	-1,199.49	-4,262.31	9,560.94	9,137.70	423.24	22.590	
12,400.00	7,289.00	6,300.00	6,292.04	64.27	397.94	44.93	-1,199.49	-4,262.31	9,659.91	9,236.56	423.35	22.818	
12,500.00	7,289.00	6,300.00	6,292.04	65.31	397.94	44.93	-1,199.49	-4,262.31	9,758.90	9,335.44	423.46	23.046	
12,600.00	7,289.00	6,300.00	6,292.04	66.34	397.94	44.93	-1,199.49	-4,262.31	9,857.91	9,434.35	423.56	23.274	
12,700.00	7,289.00	6,300.00	6,292.04	67.38	397.94	44.93	-1,199.49	-4,262.31	9,956.94	9,533.27	423.67	23.502	
12,800.00	7,289.00	6,300.00	6,292.04	68.42	397.94	44.93	-1,199.49	-4,262.31	10,055.99	9,632.21	423.78	23.729	
12,900.00	7,289.00	6,300.00	6,292.04	69.47	397.94	44.93	-1,199.49	-4,262.31	10,155.06	9,731.18	423.88	23.957	
13,000.00	7,289.00	6,300.00	6,292.04	70.51	397.94	44.93	-1,199.49	-4,262.31	10,254.15	9,830.16	423.99	24.185	
13,100.00	7,289.00	6,300.00	6,292.04	71.56	397.94	44.93	-1,199.49	-4,262.31	10,353.25	9,929.16	424.10	24.413	
13,200.00	7,289.00	6,300.00	6,292.04	72.61	397.94	44.93	-1,199.49	-4,262.31	10,452.37	10,028.17	424.20	24.640	
13,300.00	7,289.00	6,300.00	6,292.04	73.67	397.94	44.93	-1,199.49	-4,262.31	10,551.51	10,127.21	424.30	24.868	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W07_PRE-ONGARD WELL #001_1527282 - Depth Only - Depth Only													Offset Site Error: 0.00 usft
Survey Program: 7450-INC-ONLY													Offset Well Error: 0.00 usft
Reference	Offset	Rule Assigned:											
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
							+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
2,500.00	2,498.39	2,451.39	2,451.39	8.52	154.84	3.30	-3,841.24	-1,528.50	4,071.21	3,907.86	163.34	24.924	
2,600.00	2,598.25	2,551.25	2,551.25	8.87	161.15	3.30	-3,841.24	-1,528.50	4,065.96	3,895.96	170.00	23.917	
2,700.00	2,698.11	2,651.11	2,651.11	9.22	167.46	3.30	-3,841.24	-1,528.50	4,060.71	3,884.05	176.66	22.986	
2,800.00	2,797.97	2,750.97	2,750.97	9.58	173.77	3.31	-3,841.24	-1,528.50	4,055.46	3,872.14	183.32	22.123	
2,900.00	2,897.83	2,850.83	2,850.83	9.93	180.07	3.31	-3,841.24	-1,528.50	4,050.21	3,860.23	189.98	21.319	
3,000.00	2,997.69	2,950.69	2,950.69	10.29	186.38	3.32	-3,841.24	-1,528.50	4,044.96	3,848.32	196.64	20.571	
3,100.00	3,097.56	3,050.56	3,050.56	10.64	192.69	3.32	-3,841.24	-1,528.50	4,039.71	3,836.41	203.30	19.871	
3,200.00	3,197.42	3,150.42	3,150.42	11.00	199.00	3.33	-3,841.24	-1,528.50	4,034.46	3,824.50	209.96	19.216	
3,300.00	3,297.28	3,250.28	3,250.28	11.35	205.30	3.33	-3,841.24	-1,528.50	4,029.21	3,812.59	216.62	18.600	
3,400.00	3,397.14	3,350.14	3,350.14	11.71	211.61	3.34	-3,841.24	-1,528.50	4,023.96	3,800.68	223.28	18.022	
3,500.00	3,497.00	3,450.00	3,450.00	12.07	217.92	3.34	-3,841.24	-1,528.50	4,018.71	3,788.77	229.94	17.477	
3,600.00	3,596.86	3,549.86	3,549.86	12.42	224.23	3.34	-3,841.24	-1,528.50	4,013.46	3,776.86	236.60	16.963	
3,700.00	3,696.73	3,649.73	3,649.73	12.78	230.53	3.35	-3,841.24	-1,528.50	4,008.21	3,764.94	243.27	16.477	
3,800.00	3,796.59	3,749.59	3,749.59	13.14	236.84	3.35	-3,841.24	-1,528.50	4,002.96	3,753.03	249.93	16.016	
3,900.00	3,896.45	3,849.45	3,849.45	13.50	243.15	3.36	-3,841.24	-1,528.50	3,997.71	3,741.12	256.59	15.580	
4,000.00	3,996.31	3,949.31	3,949.31	13.86	249.46	3.36	-3,841.24	-1,528.50	3,992.46	3,729.21	263.25	15.166	
4,100.00	4,096.17	4,049.17	4,049.17	14.21	255.77	3.37	-3,841.24	-1,528.50	3,987.21	3,717.30	269.92	14.772	
4,200.00	4,196.03	4,149.03	4,149.03	14.57	262.07	3.37	-3,841.24	-1,528.50	3,981.96	3,705.38	276.58	14.397	
4,300.00	4,295.90	4,248.90	4,248.90	14.93	268.38	3.37	-3,841.24	-1,528.50	3,976.71	3,693.47	283.24	14.040	
4,400.00	4,395.76	4,348.76	4,348.76	15.29	274.69	3.38	-3,841.24	-1,528.50	3,971.46	3,681.56	289.91	13.699	
4,500.00	4,495.62	4,448.62	4,448.62	15.65	281.00	3.38	-3,841.24	-1,528.50	3,966.21	3,669.64	296.57	13.374	
4,600.00	4,595.48	4,548.48	4,548.48	16.01	287.30	3.39	-3,841.24	-1,528.50	3,960.96	3,657.73	303.23	13.062	
4,700.00	4,695.34	4,648.34	4,648.34	16.37	293.61	3.39	-3,841.24	-1,528.50	3,955.71	3,645.82	309.90	12.765	
4,803.94	4,799.14	4,752.14	4,752.14	16.74	300.17	3.40	-3,841.24	-1,528.50	3,950.26	3,633.44	316.82	12.468	
4,900.00	4,895.12	4,848.12	4,848.12	17.09	306.23	3.40	-3,841.24	-1,528.50	3,946.42	3,623.19	323.23	12.209	
5,004.89	5,000.00	4,953.00	4,953.00	17.45	312.86	-158.15	-3,841.24	-1,528.50	3,944.98	3,614.77	330.22	11.947	
5,100.00	5,095.11	5,048.11	5,048.11	17.77	318.86	-158.15	-3,841.24	-1,528.50	3,944.98	3,608.44	336.55	11.722	
5,200.00	5,195.11	5,148.11	5,148.11	18.10	325.18	-158.15	-3,841.24	-1,528.50	3,944.98	3,601.78	343.20	11.495	
5,300.00	5,295.11	5,248.11	5,248.11	18.44	331.50	-158.15	-3,841.24	-1,528.50	3,944.98	3,595.13	349.86	11.276	
5,400.00	5,395.11	5,348.11	5,348.11	18.78	337.81	-158.15	-3,841.24	-1,528.50	3,944.98	3,588.47	356.51	11.065	
5,500.00	5,495.11	5,448.11	5,448.11	19.12	344.13	-158.15	-3,841.24	-1,528.50	3,944.98	3,581.81	363.17	10.863	
5,600.00	5,595.11	5,548.11	5,548.11	19.46	350.45	-158.15	-3,841.24	-1,528.50	3,944.98	3,575.16	369.83	10.667	
5,700.00	5,695.11	5,648.11	5,648.11	19.80	356.76	-158.15	-3,841.24	-1,528.50	3,944.98	3,568.50	376.49	10.478	
5,800.00	5,795.11	5,748.11	5,748.11	20.14	363.08	-158.15	-3,841.24	-1,528.50	3,944.98	3,561.84	383.14	10.296	
5,900.00	5,895.11	5,848.11	5,848.11	20.48	369.40	-158.15	-3,841.24	-1,528.50	3,944.98	3,555.18	389.80	10.120	
6,000.00	5,995.11	5,948.11	5,948.11	20.82	375.71	-158.15	-3,841.24	-1,528.50	3,944.98	3,548.52	396.46	9.950	
6,100.00	6,095.11	6,048.11	6,048.11	21.16	382.03	-158.15	-3,841.24	-1,528.50	3,944.98	3,541.86	403.12	9.786	
6,200.00	6,195.11	6,148.11	6,148.11	21.51	388.35	-158.15	-3,841.24	-1,528.50	3,944.98	3,535.20	409.79	9.627	
6,300.00	6,295.11	6,248.11	6,248.11	21.85	394.66	-158.15	-3,841.24	-1,528.50	3,944.98	3,528.54	416.45	9.473	
6,400.00	6,395.11	6,348.11	6,348.11	22.19	400.98	-158.15	-3,841.24	-1,528.50	3,944.98	3,521.87	423.11	9.324	
6,500.00	6,495.11	6,448.11	6,448.11	22.54	407.29	-158.15	-3,841.24	-1,528.50	3,944.98	3,515.21	429.77	9.179	
6,600.00	6,595.11	6,548.11	6,548.11	22.88	413.61	-158.15	-3,841.24	-1,528.50	3,944.98	3,508.55	436.43	9.039	
6,700.00	6,695.11	6,648.11	6,648.11	23.23	419.93	-158.15	-3,841.24	-1,528.50	3,944.98	3,501.89	443.10	8.903	
6,720.93	6,716.04	6,669.04	6,669.04	23.30	421.25	-158.15	-3,841.24	-1,528.50	3,944.98	3,500.49	444.49	8.875 CC	
6,750.00	6,745.09	6,698.09	6,698.09	23.40	423.08	110.64	-3,841.24	-1,528.50	3,945.24	3,498.82	446.43	8.837	
6,800.00	6,794.86	6,747.86	6,747.86	23.57	426.23	110.55	-3,841.24	-1,528.50	3,946.91	3,497.17	449.74	8.776	
6,850.00	6,844.02	6,797.02	6,797.02	23.74	429.33	110.37	-3,841.24	-1,528.50	3,950.11	3,497.10	453.02	8.720 ES	
6,900.00	6,892.21	6,845.21	6,845.21	23.90	432.38	110.10	-3,841.24	-1,528.50	3,954.86	3,498.63	456.23	8.669	
6,950.00	6,939.05	6,892.05	6,892.05	24.06	435.34	109.72	-3,841.24	-1,528.50	3,961.15	3,501.80	459.35	8.623	
7,000.00	6,984.20	6,937.20	6,937.20	24.21	438.19	109.24	-3,841.24	-1,528.50	3,968.97	3,506.62	462.36	8.584	
7,050.00	7,027.31	6,980.31	6,980.31	24.35	440.91	108.64	-3,841.24	-1,528.50	3,978.34	3,513.11	465.23	8.551	
7,100.00	7,068.05	7,021.05	7,021.05	24.48	443.48	107.91	-3,841.24	-1,528.50	3,989.23	3,521.28	467.95	8.525	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W07_PRE-ONGARD WELL #001_1527282 - Depth Only - Depth Only													Offset Site Error: 0.00 usft
Survey Program: 7450-INC-ONLY							Rule Assigned:						Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
7,150.00	7,106.11	7,059.11	7,059.11	24.62	445.89	107.04	-3,841.24	-1,528.50	4,001.62	3,531.13	470.50	8.505	
7,200.00	7,141.21	7,094.21	7,094.21	24.76	448.11	106.01	-3,841.24	-1,528.50	4,015.50	3,542.65	472.85	8.492	
7,250.00	7,173.06	7,126.06	7,126.06	24.90	450.12	104.82	-3,841.24	-1,528.50	4,030.81	3,555.82	474.99	8.486 SF	
7,300.00	7,201.44	7,154.44	7,154.44	25.03	451.91	103.44	-3,841.24	-1,528.50	4,047.51	3,570.60	476.91	8.487	
7,350.00	7,226.12	7,179.12	7,179.12	25.17	453.47	101.87	-3,841.24	-1,528.50	4,065.53	3,586.94	478.59	8.495	
7,400.00	7,246.93	7,199.93	7,199.93	25.30	454.78	100.10	-3,841.24	-1,528.50	4,084.79	3,604.76	480.02	8.510	
7,450.00	7,263.69	7,216.69	7,216.69	25.43	455.84	98.14	-3,841.24	-1,528.50	4,105.17	3,623.97	481.20	8.531	
7,500.00	7,276.28	7,229.28	7,229.28	25.56	456.64	95.98	-3,841.24	-1,528.50	4,126.56	3,644.46	482.10	8.560	
7,550.00	7,284.61	7,237.61	7,237.61	25.68	457.16	93.62	-3,841.24	-1,528.50	4,148.82	3,666.09	482.73	8.594	
7,600.00	7,288.62	7,241.62	7,241.62	25.80	457.42	91.10	-3,841.24	-1,528.50	4,171.80	3,688.72	483.08	8.636	
7,620.93	7,289.00	7,242.00	7,242.00	25.85	457.44	90.00	-3,841.24	-1,528.50	4,181.59	3,698.45	483.14	8.655	
7,701.87	7,289.00	7,242.00	7,242.00	26.06	457.44	90.00	-3,841.24	-1,528.50	4,221.21	3,737.91	483.30	8.734	
7,800.00	7,289.00	7,242.00	7,242.00	26.35	457.44	90.00	-3,841.24	-1,528.50	4,272.00	3,788.49	483.52	8.835	
7,900.00	7,289.00	7,242.00	7,242.00	26.69	457.44	90.00	-3,841.24	-1,528.50	4,325.44	3,841.68	483.76	8.941	
8,000.00	7,289.00	7,242.00	7,242.00	27.08	457.44	90.00	-3,841.24	-1,528.50	4,380.50	3,896.49	484.02	9.050	
8,100.00	7,289.00	7,242.00	7,242.00	27.50	457.44	90.00	-3,841.24	-1,528.50	4,437.14	3,952.85	484.29	9.162	
8,200.00	7,289.00	7,242.00	7,242.00	27.96	457.44	90.00	-3,841.24	-1,528.50	4,495.29	4,010.71	484.58	9.277	
8,300.00	7,289.00	7,242.00	7,242.00	28.46	457.44	90.00	-3,841.24	-1,528.50	4,554.89	4,070.01	484.88	9.394	
8,400.00	7,289.00	7,242.00	7,242.00	28.99	457.44	90.00	-3,841.24	-1,528.50	4,615.89	4,130.69	485.20	9.513	
8,500.00	7,289.00	7,242.00	7,242.00	29.56	457.44	90.00	-3,841.24	-1,528.50	4,678.23	4,192.72	485.51	9.636	
8,600.00	7,289.00	7,242.00	7,242.00	30.16	457.44	90.00	-3,841.24	-1,528.50	4,741.86	4,256.02	485.84	9.760	
8,700.00	7,289.00	7,242.00	7,242.00	30.79	457.44	90.00	-3,841.24	-1,528.50	4,806.73	4,320.56	486.17	9.887	
8,800.00	7,289.00	7,242.00	7,242.00	31.44	457.44	90.00	-3,841.24	-1,528.50	4,872.78	4,386.29	486.50	10.016	
8,900.00	7,289.00	7,242.00	7,242.00	32.12	457.44	90.00	-3,841.24	-1,528.50	4,939.98	4,453.15	486.83	10.147	
9,000.00	7,289.00	7,242.00	7,242.00	32.82	457.44	90.00	-3,841.24	-1,528.50	5,008.28	4,521.11	487.16	10.281	
9,100.00	7,289.00	7,242.00	7,242.00	33.55	457.44	90.00	-3,841.24	-1,528.50	5,077.62	4,590.13	487.49	10.416	
9,200.00	7,289.00	7,242.00	7,242.00	34.30	457.44	90.00	-3,841.24	-1,528.50	5,147.97	4,660.15	487.82	10.553	
9,300.00	7,289.00	7,242.00	7,242.00	35.07	457.44	90.00	-3,841.24	-1,528.50	5,219.29	4,731.14	488.15	10.692	
9,400.00	7,289.00	7,242.00	7,242.00	35.86	457.44	90.00	-3,841.24	-1,528.50	5,291.54	4,803.07	488.47	10.833	
9,500.00	7,289.00	7,242.00	7,242.00	36.66	457.44	90.00	-3,841.24	-1,528.50	5,364.68	4,875.89	488.80	10.975	
9,600.00	7,289.00	7,242.00	7,242.00	37.48	457.44	90.00	-3,841.24	-1,528.50	5,438.68	4,949.57	489.11	11.119	
9,700.00	7,289.00	7,242.00	7,242.00	38.32	457.44	90.00	-3,841.24	-1,528.50	5,513.50	5,024.07	489.43	11.265	
9,800.00	7,289.00	7,242.00	7,242.00	39.17	457.44	90.00	-3,841.24	-1,528.50	5,589.10	5,099.36	489.73	11.413	
9,900.00	7,289.00	7,242.00	7,242.00	40.03	457.44	90.00	-3,841.24	-1,528.50	5,665.46	5,175.42	490.04	11.561	
10,000.00	7,289.00	7,242.00	7,242.00	40.91	457.44	90.00	-3,841.24	-1,528.50	5,742.55	5,252.21	490.34	11.711	
10,100.00	7,289.00	7,242.00	7,242.00	41.80	457.44	90.00	-3,841.24	-1,528.50	5,820.33	5,329.70	490.63	11.863	
10,200.00	7,289.00	7,242.00	7,242.00	42.69	457.44	90.00	-3,841.24	-1,528.50	5,898.78	5,407.86	490.92	12.016	
10,300.00	7,289.00	7,242.00	7,242.00	43.60	457.44	90.00	-3,841.24	-1,528.50	5,977.88	5,486.68	491.20	12.170	
10,400.00	7,289.00	7,242.00	7,242.00	44.52	457.44	90.00	-3,841.24	-1,528.50	6,057.59	5,566.11	491.48	12.325	
10,500.00	7,289.00	7,242.00	7,242.00	45.45	457.44	90.00	-3,841.24	-1,528.50	6,137.90	5,646.15	491.75	12.482	
10,600.00	7,289.00	7,242.00	7,242.00	46.39	457.44	90.00	-3,841.24	-1,528.50	6,218.78	5,726.76	492.02	12.639	
10,700.00	7,289.00	7,242.00	7,242.00	47.33	457.44	90.00	-3,841.24	-1,528.50	6,300.21	5,807.92	492.28	12.798	
10,800.00	7,289.00	7,242.00	7,242.00	48.28	457.44	90.00	-3,841.24	-1,528.50	6,382.17	5,889.62	492.54	12.958	
10,900.00	7,289.00	7,242.00	7,242.00	49.24	457.44	90.00	-3,841.24	-1,528.50	6,464.63	5,971.84	492.79	13.118	
11,000.00	7,289.00	7,242.00	7,242.00	50.21	457.44	90.00	-3,841.24	-1,528.50	6,547.58	6,054.54	493.04	13.280	
11,100.00	7,289.00	7,242.00	7,242.00	51.18	457.44	90.00	-3,841.24	-1,528.50	6,631.01	6,137.72	493.28	13.443	
11,200.00	7,289.00	7,242.00	7,242.00	52.16	457.44	90.00	-3,841.24	-1,528.50	6,714.88	6,221.36	493.52	13.606	
11,300.00	7,289.00	7,242.00	7,242.00	53.15	457.44	90.00	-3,841.24	-1,528.50	6,799.19	6,305.44	493.76	13.770	
11,400.00	7,289.00	7,242.00	7,242.00	54.14	457.44	90.00	-3,841.24	-1,528.50	6,883.93	6,389.94	493.98	13.936	
11,500.00	7,289.00	7,242.00	7,242.00	55.13	457.44	90.00	-3,841.24	-1,528.50	6,969.06	6,474.85	494.21	14.101	
11,600.00	7,289.00	7,242.00	7,242.00	56.13	457.44	90.00	-3,841.24	-1,528.50	7,054.59	6,560.16	494.43	14.268	
11,700.00	7,289.00	7,242.00	7,242.00	57.13	457.44	90.00	-3,841.24	-1,528.50	7,140.49	6,645.85	494.64	14.436	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W07_PRE-ONGARD WELL #001_1527282 - Depth Only - Depth Only												Offset Site Error:	0.00 usft
Survey Program: 7450-INC-ONLY												Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
11,800.00	7,289.00	7,242.00	7,242.00	58.14	457.44	90.00	-3,841.24	-1,528.50	7,226.76	6,731.90	494.86	14.604	
11,900.00	7,289.00	7,242.00	7,242.00	59.16	457.44	90.00	-3,841.24	-1,528.50	7,313.37	6,818.31	495.06	14.773	
12,000.00	7,289.00	7,242.00	7,242.00	60.17	457.44	90.00	-3,841.24	-1,528.50	7,400.33	6,905.06	495.27	14.942	
12,100.00	7,289.00	7,242.00	7,242.00	61.19	457.44	90.00	-3,841.24	-1,528.50	7,487.61	6,992.14	495.47	15.112	
12,200.00	7,289.00	7,242.00	7,242.00	62.22	457.44	90.00	-3,841.24	-1,528.50	7,575.20	7,079.54	495.66	15.283	
12,300.00	7,289.00	7,242.00	7,242.00	63.24	457.44	90.00	-3,841.24	-1,528.50	7,663.10	7,167.24	495.86	15.454	
12,400.00	7,289.00	7,242.00	7,242.00	64.27	457.44	90.00	-3,841.24	-1,528.50	7,751.29	7,255.24	496.05	15.626	
12,500.00	7,289.00	7,242.00	7,242.00	65.31	457.44	90.00	-3,841.24	-1,528.50	7,839.76	7,343.53	496.23	15.799	
12,600.00	7,289.00	7,242.00	7,242.00	66.34	457.44	90.00	-3,841.24	-1,528.50	7,928.51	7,432.09	496.41	15.972	
12,700.00	7,289.00	7,242.00	7,242.00	67.38	457.44	90.00	-3,841.24	-1,528.50	8,017.52	7,520.93	496.59	16.145	
12,800.00	7,289.00	7,242.00	7,242.00	68.42	457.44	90.00	-3,841.24	-1,528.50	8,106.79	7,610.02	496.77	16.319	
12,900.00	7,289.00	7,242.00	7,242.00	69.47	457.44	90.00	-3,841.24	-1,528.50	8,196.31	7,699.36	496.94	16.493	
13,000.00	7,289.00	7,242.00	7,242.00	70.51	457.44	90.00	-3,841.24	-1,528.50	8,286.06	7,788.95	497.11	16.668	
13,100.00	7,289.00	7,242.00	7,242.00	71.56	457.44	90.00	-3,841.24	-1,528.50	8,376.05	7,878.77	497.28	16.844	
13,200.00	7,289.00	7,242.00	7,242.00	72.61	457.44	90.00	-3,841.24	-1,528.50	8,466.27	7,968.82	497.45	17.019	
13,300.00	7,289.00	7,242.00	7,242.00	73.67	457.44	90.00	-3,841.24	-1,528.50	8,556.70	8,059.09	497.61	17.196	
13,400.00	7,289.00	7,242.00	7,242.00	74.72	457.44	90.00	-3,841.24	-1,528.50	8,647.34	8,149.57	497.77	17.372	
13,500.00	7,289.00	7,242.00	7,242.00	75.78	457.44	90.00	-3,841.24	-1,528.50	8,738.18	8,240.25	497.93	17.549	
13,600.00	7,289.00	7,242.00	7,242.00	76.84	457.44	90.00	-3,841.24	-1,528.50	8,829.23	8,331.14	498.08	17.726	
13,700.00	7,289.00	7,242.00	7,242.00	77.90	457.44	90.00	-3,841.24	-1,528.50	8,920.46	8,422.22	498.24	17.904	
13,800.00	7,289.00	7,242.00	7,242.00	78.96	457.44	90.00	-3,841.24	-1,528.50	9,011.88	8,513.49	498.39	18.082	
13,900.00	7,289.00	7,242.00	7,242.00	80.02	457.44	90.00	-3,841.24	-1,528.50	9,103.49	8,604.95	498.54	18.260	
14,000.00	7,289.00	7,242.00	7,242.00	81.09	457.44	90.00	-3,841.24	-1,528.50	9,195.26	8,696.58	498.69	18.439	
14,100.00	7,289.00	7,242.00	7,242.00	82.15	457.44	90.00	-3,841.24	-1,528.50	9,287.21	8,788.38	498.83	18.618	
14,200.00	7,289.00	7,242.00	7,242.00	83.22	457.44	90.00	-3,841.24	-1,528.50	9,379.32	8,880.35	498.97	18.797	
14,300.00	7,289.00	7,242.00	7,242.00	84.29	457.44	90.00	-3,841.24	-1,528.50	9,471.59	8,972.48	499.12	18.977	
14,400.00	7,289.00	7,242.00	7,242.00	85.36	457.44	90.00	-3,841.24	-1,528.50	9,564.02	9,064.76	499.26	19.157	
14,500.00	7,289.00	7,242.00	7,242.00	86.44	457.44	90.00	-3,841.24	-1,528.50	9,656.60	9,157.20	499.39	19.337	
14,600.00	7,289.00	7,242.00	7,242.00	87.51	457.44	90.00	-3,841.24	-1,528.50	9,749.32	9,249.79	499.53	19.517	
14,700.00	7,289.00	7,242.00	7,242.00	88.58	457.44	90.00	-3,841.24	-1,528.50	9,842.19	9,342.52	499.67	19.698	
14,800.00	7,289.00	7,242.00	7,242.00	89.66	457.44	90.00	-3,841.24	-1,528.50	9,935.19	9,435.39	499.80	19.878	
14,900.00	7,289.00	7,242.00	7,242.00	90.74	457.44	90.00	-3,841.24	-1,528.50	10,028.33	9,528.40	499.93	20.059	
15,000.00	7,289.00	7,242.00	7,242.00	91.82	457.44	90.00	-3,841.24	-1,528.50	10,121.60	9,621.54	500.06	20.241	
15,100.00	7,289.00	7,242.00	7,242.00	92.90	457.44	90.00	-3,841.24	-1,528.50	10,215.00	9,714.81	500.19	20.422	
15,200.00	7,289.00	7,242.00	7,242.00	93.98	457.44	90.00	-3,841.24	-1,528.50	10,308.52	9,808.20	500.32	20.604	
15,300.00	7,289.00	7,242.00	7,242.00	95.06	457.44	90.00	-3,841.24	-1,528.50	10,402.17	9,901.72	500.45	20.786	
15,400.00	7,289.00	7,242.00	7,242.00	96.14	457.44	90.00	-3,841.24	-1,528.50	10,495.93	9,995.36	500.57	20.968	
15,500.00	7,289.00	7,242.00	7,242.00	97.22	457.44	90.00	-3,841.24	-1,528.50	10,589.80	10,089.10	500.69	21.150	
15,600.00	7,289.00	7,242.00	7,242.00	98.31	457.44	90.00	-3,841.24	-1,528.50	10,683.78	10,182.97	500.82	21.333	
15,700.00	7,289.00	7,242.00	7,242.00	99.39	457.44	90.00	-3,841.24	-1,528.50	10,777.88	10,276.94	500.94	21.515	
15,800.00	7,289.00	7,242.00	7,242.00	100.48	457.44	90.00	-3,841.24	-1,528.50	10,872.08	10,371.02	501.06	21.698	
15,900.00	7,289.00	7,242.00	7,242.00	101.56	457.44	90.00	-3,841.24	-1,528.50	10,966.38	10,465.20	501.18	21.881	
16,000.00	7,289.00	7,242.00	7,242.00	102.65	457.44	90.00	-3,841.24	-1,528.50	11,060.78	10,559.48	501.30	22.064	
16,100.00	7,289.00	7,242.00	7,242.00	103.74	457.44	90.00	-3,841.24	-1,528.50	11,155.28	10,653.86	501.42	22.247	
16,200.00	7,289.00	7,242.00	7,242.00	104.83	457.44	90.00	-3,841.24	-1,528.50	11,249.87	10,748.34	501.54	22.431	
16,300.00	7,289.00	7,242.00	7,242.00	105.92	457.44	90.00	-3,841.24	-1,528.50	11,344.56	10,842.91	501.65	22.614	
16,400.00	7,289.00	7,242.00	7,242.00	107.01	457.44	90.00	-3,841.24	-1,528.50	11,439.34	10,937.57	501.77	22.798	
16,500.00	7,289.00	7,242.00	7,242.00	108.10	457.44	90.00	-3,841.24	-1,528.50	11,534.20	11,032.32	501.88	22.982	
16,600.00	7,289.00	7,242.00	7,242.00	109.19	457.44	90.00	-3,841.24	-1,528.50	11,629.16	11,127.16	502.00	23.166	
16,700.00	7,289.00	7,242.00	7,242.00	110.28	457.44	90.00	-3,841.24	-1,528.50	11,724.19	11,222.08	502.11	23.350	
16,800.00	7,289.00	7,242.00	7,242.00	111.37	457.44	90.00	-3,841.24	-1,528.50	11,819.31	11,317.09	502.22	23.534	
16,900.00	7,289.00	7,242.00	7,242.00	112.46	457.44	90.00	-3,841.24	-1,528.50	11,914.51	11,412.17	502.33	23.718	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W07_PRE-ONGARD WELL #001_1527282 - Depth Only - Depth Only													Offset Site Error:	0.00 usft
Survey Program: 7450-INC-ONLY													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Rule Assigned:		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
17,000.00	7,289.00	7,242.00	7,242.00	113.56	457.44	90.00	-3,841.24	-1,528.50	12,009.78	11,507.34	502.44	23.903		
17,100.00	7,289.00	7,242.00	7,242.00	114.65	457.44	90.00	-3,841.24	-1,528.50	12,105.13	11,602.58	502.55	24.087		
17,200.00	7,289.00	7,242.00	7,242.00	115.75	457.44	90.00	-3,841.24	-1,528.50	12,200.56	11,697.90	502.66	24.272		
17,300.00	7,289.00	7,242.00	7,242.00	116.84	457.44	90.00	-3,841.24	-1,528.50	12,296.06	11,793.29	502.77	24.456		
17,400.00	7,289.00	7,242.00	7,242.00	117.94	457.44	90.00	-3,841.24	-1,528.50	12,391.63	11,888.75	502.88	24.641		
17,500.00	7,289.00	7,242.00	7,242.00	119.03	457.44	90.00	-3,841.24	-1,528.50	12,487.27	11,984.28	502.99	24.826		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W08_FEDERAL V COM #004_1535127 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 262-INC-NOLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
5,900.00	5,895.11	5,849.84	5,848.11	20.48	140.42	-99.05	-807.83	-4,004.32	3,994.01	3,833.13	160.88	24.825	
6,000.00	5,995.11	5,949.84	5,948.11	20.82	142.84	-99.05	-807.83	-4,004.32	3,994.01	3,830.37	163.64	24.407	
6,025.11	6,020.21	5,973.49	5,971.74	20.91	143.41	-99.04	-807.04	-4,004.32	3,993.89	3,829.59	164.30	24.308	
6,100.00	6,095.11	6,043.83	6,042.07	21.16	145.11	-99.04	-807.46	-4,004.32	3,993.96	3,827.70	166.26	24.022	
6,200.00	6,195.11	6,149.91	6,148.11	21.51	147.60	-99.05	-807.83	-4,004.32	3,994.01	3,824.92	169.09	23.620	
6,222.07	6,217.18	6,171.98	6,170.17	21.58	148.11	-99.04	-807.32	-4,004.32	3,993.93	3,824.25	169.68	23.538	
6,300.00	6,295.11	6,244.69	6,242.88	21.85	149.80	-99.04	-807.62	-4,004.32	3,993.98	3,822.35	171.63	23.271	
6,400.00	6,395.11	6,349.96	6,348.11	22.19	152.32	-99.05	-807.83	-4,004.32	3,994.01	3,819.52	174.50	22.889	
6,500.00	6,495.11	6,449.96	6,448.11	22.54	154.74	-99.05	-807.83	-4,004.32	3,994.01	3,816.75	177.26	22.532	
6,593.99	6,589.10	6,543.85	6,541.98	22.86	157.01	-99.03	-806.35	-4,004.32	3,993.78	3,813.92	179.86	22.205 CC	
6,600.00	6,595.11	6,549.71	6,547.85	22.88	157.15	-99.03	-806.35	-4,004.32	3,993.78	3,813.76	180.02	22.185	
6,700.00	6,695.11	6,647.30	6,645.42	23.23	159.51	-99.03	-806.58	-4,004.32	3,993.82	3,811.09	182.72	21.857	
6,720.93	6,716.04	6,667.72	6,665.85	23.30	160.01	-99.03	-806.67	-4,004.32	3,993.83	3,810.54	183.29	21.790	
6,750.00	6,745.09	6,696.08	6,694.20	23.40	160.69	169.76	-806.83	-4,004.32	3,994.58	3,810.51	184.08	21.701 ES	
6,800.00	6,794.86	6,744.64	6,742.76	23.57	161.87	169.68	-807.18	-4,004.32	3,999.27	3,813.85	185.42	21.568	
6,850.00	6,844.02	6,792.63	6,790.74	23.74	163.03	169.53	-807.62	-4,004.32	4,008.23	3,821.48	186.75	21.463	
6,900.00	6,892.21	6,847.21	6,845.21	23.90	164.45	169.32	-807.83	-4,004.32	4,021.33	3,832.98	188.35	21.351	
6,950.00	6,939.05	6,894.06	6,892.05	24.06	165.74	169.02	-807.83	-4,004.32	4,038.48	3,848.70	189.78	21.279	
7,000.00	6,984.20	6,939.21	6,937.20	24.21	166.97	168.63	-807.83	-4,004.32	4,059.60	3,868.43	191.17	21.236	
7,050.00	7,027.31	6,982.32	6,980.31	24.35	168.15	168.12	-807.83	-4,004.32	4,084.51	3,892.02	192.48	21.220 SF	
7,100.00	7,068.05	7,021.31	7,019.29	24.48	169.21	167.48	-806.76	-4,004.32	4,112.87	3,919.19	193.68	21.236	
7,150.00	7,106.11	7,057.66	7,055.63	24.62	170.21	166.64	-806.92	-4,004.32	4,144.81	3,950.02	194.78	21.279	
7,200.00	7,141.21	7,091.18	7,089.15	24.76	171.12	165.56	-807.15	-4,004.32	4,179.92	3,984.12	195.80	21.348	
7,250.00	7,173.06	7,121.62	7,119.58	24.90	171.96	164.16	-807.43	-4,004.32	4,217.92	4,021.21	196.72	21.441	
7,300.00	7,201.44	7,156.61	7,154.44	25.03	172.91	162.33	-807.83	-4,004.32	4,258.54	4,060.79	197.75	21.535	
7,350.00	7,226.12	7,181.29	7,179.12	25.17	173.61	159.81	-807.83	-4,004.32	4,301.40	4,102.90	198.51	21.669	
7,400.00	7,246.93	7,202.10	7,199.93	25.30	174.20	156.22	-807.83	-4,004.32	4,346.24	4,147.09	199.15	21.824	
7,450.00	7,263.69	7,218.86	7,216.69	25.43	174.68	150.85	-807.83	-4,004.32	4,392.70	4,193.04	199.66	22.001	
7,500.00	7,276.28	7,231.45	7,229.28	25.56	175.04	142.27	-807.83	-4,004.32	4,440.44	4,240.40	200.04	22.198	
7,550.00	7,284.61	7,239.78	7,237.61	25.68	175.28	127.61	-807.83	-4,004.32	4,489.10	4,288.80	200.30	22.412	
7,600.00	7,288.62	7,243.78	7,241.62	25.80	175.39	102.98	-807.83	-4,004.32	4,538.30	4,337.88	200.42	22.644	
7,620.93	7,289.00	7,244.17	7,242.00	25.85	175.40	90.00	-807.83	-4,004.32	4,558.97	4,358.53	200.44	22.745	
7,701.87	7,289.00	7,244.17	7,242.00	26.06	175.40	90.00	-807.83	-4,004.32	4,639.10	4,438.65	200.45	23.143	
7,800.00	7,289.00	7,244.17	7,242.00	26.35	175.40	90.00	-807.83	-4,004.32	4,736.47	4,536.01	200.47	23.627	
7,900.00	7,289.00	7,244.17	7,242.00	26.69	175.40	90.00	-807.83	-4,004.32	4,835.73	4,635.25	200.48	24.120	
8,000.00	7,289.00	7,244.17	7,242.00	27.08	175.40	90.00	-807.83	-4,004.32	4,935.02	4,734.52	200.50	24.614	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W09_GOVERNMENT AB #002_1521480 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 300-INC-ONLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
12,900.00	7,289.00	7,238.03	7,236.00	69.47	168.73	90.00	-2,451.38	10,355.26	5,109.01	4,901.21	207.79	24.587	
13,000.00	7,289.00	7,238.03	7,236.00	70.51	168.73	90.00	-2,451.38	10,355.26	5,020.22	4,811.63	208.59	24.067	
13,100.00	7,289.00	7,238.03	7,236.00	71.56	168.73	90.00	-2,451.38	10,355.26	4,931.87	4,722.44	209.43	23.549	
13,200.00	7,289.00	7,238.03	7,236.00	72.61	168.73	90.00	-2,451.38	10,355.26	4,843.96	4,633.66	210.31	23.033	
13,300.00	7,289.00	7,238.03	7,236.00	73.67	168.73	90.00	-2,451.38	10,355.26	4,756.54	4,545.32	211.22	22.519	
13,400.00	7,289.00	7,238.03	7,236.00	74.72	168.73	90.00	-2,451.38	10,355.26	4,669.62	4,457.44	212.18	22.008	
13,500.00	7,289.00	7,238.03	7,236.00	75.78	168.73	90.00	-2,451.38	10,355.26	4,583.23	4,370.05	213.19	21.499	
13,600.00	7,289.00	7,238.03	7,236.00	76.84	168.73	90.00	-2,451.38	10,355.26	4,497.41	4,283.18	214.23	20.993	
13,700.00	7,289.00	7,238.03	7,236.00	77.90	168.73	90.00	-2,451.38	10,355.26	4,412.19	4,196.86	215.33	20.490	
13,800.00	7,289.00	7,238.03	7,236.00	78.96	168.73	90.00	-2,451.38	10,355.26	4,327.59	4,111.12	216.47	19.991	
13,900.00	7,289.00	7,238.03	7,236.00	80.02	168.73	90.00	-2,451.38	10,355.26	4,243.67	4,026.00	217.67	19.496	
14,000.00	7,289.00	7,238.03	7,236.00	81.09	168.73	90.00	-2,451.38	10,355.26	4,160.46	3,941.54	218.92	19.005	
14,100.00	7,289.00	7,238.03	7,236.00	82.15	168.73	90.00	-2,451.38	10,355.26	4,078.00	3,857.78	220.22	18.518	
14,200.00	7,289.00	7,238.03	7,236.00	83.22	168.73	90.00	-2,451.38	10,355.26	3,996.35	3,774.77	221.58	18.036	
14,300.00	7,289.00	7,238.03	7,236.00	84.29	168.73	90.00	-2,451.38	10,355.26	3,915.54	3,692.55	223.00	17.559	
14,400.00	7,289.00	7,238.03	7,236.00	85.36	168.73	90.00	-2,451.38	10,355.26	3,835.64	3,611.17	224.48	17.087	
14,500.00	7,289.00	7,238.03	7,236.00	86.44	168.73	90.00	-2,451.38	10,355.26	3,756.71	3,530.69	226.02	16.621	
14,600.00	7,289.00	7,238.03	7,236.00	87.51	168.73	90.00	-2,451.38	10,355.26	3,678.79	3,451.17	227.62	16.162	
14,700.00	7,289.00	7,238.03	7,236.00	88.58	168.73	90.00	-2,451.38	10,355.26	3,601.97	3,372.68	229.29	15.709	
14,800.00	7,289.00	7,238.03	7,236.00	89.66	168.73	90.00	-2,451.38	10,355.26	3,526.31	3,295.29	231.02	15.264	
14,900.00	7,289.00	7,238.03	7,236.00	90.74	168.73	90.00	-2,451.38	10,355.26	3,451.89	3,219.07	232.82	14.826	
15,000.00	7,289.00	7,238.03	7,236.00	91.82	168.73	90.00	-2,451.38	10,355.26	3,378.79	3,144.10	234.69	14.397	
15,100.00	7,289.00	7,238.03	7,236.00	92.90	168.73	90.00	-2,451.38	10,355.26	3,307.10	3,070.47	236.63	13.976	
15,200.00	7,289.00	7,238.03	7,236.00	93.98	168.73	90.00	-2,451.38	10,355.26	3,236.91	2,998.28	238.64	13.564	
15,300.00	7,289.00	7,238.03	7,236.00	95.06	168.73	90.00	-2,451.38	10,355.26	3,168.32	2,927.62	240.71	13.162	
15,400.00	7,289.00	7,238.03	7,236.00	96.14	168.73	90.00	-2,451.38	10,355.26	3,101.45	2,858.60	242.85	12.771	
15,500.00	7,289.00	7,238.03	7,236.00	97.22	168.73	90.00	-2,451.38	10,355.26	3,036.39	2,791.34	245.05	12.391	
15,600.00	7,289.00	7,238.03	7,236.00	98.31	168.73	90.00	-2,451.38	10,355.26	2,973.27	2,725.96	247.31	12.022	
15,700.00	7,289.00	7,238.03	7,236.00	99.39	168.73	90.00	-2,451.38	10,355.26	2,912.22	2,662.59	249.63	11.666	
15,800.00	7,289.00	7,238.03	7,236.00	100.48	168.73	90.00	-2,451.38	10,355.26	2,853.36	2,601.37	251.99	11.323	
15,900.00	7,289.00	7,238.03	7,236.00	101.56	168.73	90.00	-2,451.38	10,355.26	2,796.85	2,542.45	254.40	10.994	
16,000.00	7,289.00	7,238.03	7,236.00	102.65	168.73	90.00	-2,451.38	10,355.26	2,742.82	2,485.97	256.85	10.679	
16,100.00	7,289.00	7,238.03	7,236.00	103.74	168.73	90.00	-2,451.38	10,355.26	2,691.42	2,432.10	259.32	10.379	
16,200.00	7,289.00	7,238.03	7,236.00	104.83	168.73	90.00	-2,451.38	10,355.26	2,642.80	2,381.01	261.80	10.095	
16,300.00	7,289.00	7,238.03	7,236.00	105.92	168.73	90.00	-2,451.38	10,355.26	2,597.13	2,332.85	264.28	9.827	
16,400.00	7,289.00	7,238.03	7,236.00	107.01	168.73	90.00	-2,451.38	10,355.26	2,554.56	2,287.81	266.75	9.577	
16,500.00	7,289.00	7,238.03	7,236.00	108.10	168.73	90.00	-2,451.38	10,355.26	2,515.24	2,246.06	269.18	9.344	
16,600.00	7,289.00	7,238.03	7,236.00	109.19	168.73	90.00	-2,451.38	10,355.26	2,479.34	2,207.77	271.57	9.130	
16,700.00	7,289.00	7,238.03	7,236.00	110.28	168.73	90.00	-2,451.38	10,355.26	2,447.00	2,173.11	273.89	8.934	
16,800.00	7,289.00	7,238.03	7,236.00	111.37	168.73	90.00	-2,451.38	10,355.26	2,418.37	2,142.24	276.12	8.758	
16,900.00	7,289.00	7,238.03	7,236.00	112.46	168.73	90.00	-2,451.38	10,355.26	2,393.57	2,115.32	278.25	8.602	
17,000.00	7,289.00	7,238.03	7,236.00	113.56	168.73	90.00	-2,451.38	10,355.26	2,372.73	2,092.49	280.25	8.467	
17,100.00	7,289.00	7,238.03	7,236.00	114.65	168.73	90.00	-2,451.38	10,355.26	2,355.96	2,073.86	282.10	8.351	
17,200.00	7,289.00	7,238.03	7,236.00	115.75	168.73	90.00	-2,451.38	10,355.26	2,343.34	2,059.54	283.79	8.257	
17,300.00	7,289.00	7,238.03	7,236.00	116.84	168.73	90.00	-2,451.38	10,355.26	2,334.93	2,049.63	285.30	8.184	
17,400.00	7,289.00	7,238.03	7,236.00	117.94	168.73	90.00	-2,451.38	10,355.26	2,330.79	2,044.16	286.63	8.132	
17,446.59	7,289.00	7,238.03	7,236.00	118.45	168.73	90.00	-2,451.38	10,355.26	2,330.32	2,043.15	287.17	8.115 CC, ES	
17,500.00	7,289.00	7,238.03	7,236.00	119.03	168.73	90.00	-2,451.38	10,355.26	2,330.94	2,043.19	287.75	8.101	
17,600.00	7,289.00	7,238.03	7,236.00	120.13	168.73	90.00	-2,451.38	10,355.26	2,335.37	2,046.70	288.66	8.090 SF	
17,700.00	7,289.00	7,238.03	7,236.00	121.23	168.73	90.00	-2,451.38	10,355.26	2,344.06	2,054.69	289.37	8.101	
17,800.00	7,289.00	7,238.03	7,236.00	122.33	168.73	90.00	-2,451.38	10,355.26	2,356.97	2,067.10	289.87	8.131	
17,900.00	7,289.00	7,238.03	7,236.00	123.42	168.73	90.00	-2,451.38	10,355.26	2,374.02	2,083.86	290.16	8.182	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design:	Koala 9 Fed Com Offsets - W09_GOVERNMENT AB #002_1521480 - Inc Only - Inc Only											Offset Site Error:	0.00 usft
Survey Program:	300-INC-ONLY											Offset Well Error:	0.00 usft
Reference	Offset	Rule Assigned:										Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (")	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
18,000.00	7,289.00	7,238.03	7,236.00	124.52	168.73	90.00	-2,451.38	10,355.26	2,395.13	2,104.87	290.26	8.252	
18,100.00	7,289.00	7,238.03	7,236.00	125.62	168.73	90.00	-2,451.38	10,355.26	2,420.20	2,130.03	290.17	8.341	
18,159.20	7,289.00	7,238.03	7,236.00	126.27	168.73	90.00	-2,451.38	10,355.26	2,436.84	2,146.81	290.03	8.402	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W10_GOVERNMENT AB #003_1521774 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 350-INC-ONLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
11,200.00	7,289.00	7,246.43	7,246.00	52.16	137.69	90.00	-2,469.55	7,683.51	4,266.52	4,093.51	173.01	24.660	
11,300.00	7,289.00	7,246.43	7,246.00	53.15	137.69	90.00	-2,469.55	7,683.51	4,183.09	4,009.28	173.81	24.067	
11,400.00	7,289.00	7,246.43	7,246.00	54.14	137.69	90.00	-2,469.55	7,683.51	4,100.40	3,925.75	174.65	23.477	
11,500.00	7,289.00	7,246.43	7,246.00	55.13	137.69	90.00	-2,469.55	7,683.51	4,018.50	3,842.95	175.55	22.891	
11,600.00	7,289.00	7,246.43	7,246.00	56.13	137.69	90.00	-2,469.55	7,683.51	3,937.43	3,760.94	176.49	22.310	
11,700.00	7,289.00	7,246.43	7,246.00	57.13	137.69	90.00	-2,469.55	7,683.51	3,857.25	3,679.77	177.48	21.733	
11,800.00	7,289.00	7,246.43	7,246.00	58.14	137.69	90.00	-2,469.55	7,683.51	3,778.02	3,599.49	178.53	21.162	
11,900.00	7,289.00	7,246.43	7,246.00	59.16	137.69	90.00	-2,469.55	7,683.51	3,699.80	3,520.17	179.63	20.597	
12,000.00	7,289.00	7,246.43	7,246.00	60.17	137.69	90.00	-2,469.55	7,683.51	3,622.64	3,441.86	180.79	20.038	
12,100.00	7,289.00	7,246.43	7,246.00	61.19	137.69	90.00	-2,469.55	7,683.51	3,546.63	3,364.63	182.00	19.487	
12,200.00	7,289.00	7,246.43	7,246.00	62.22	137.69	90.00	-2,469.55	7,683.51	3,471.83	3,288.56	183.28	18.943	
12,300.00	7,289.00	7,246.43	7,246.00	63.24	137.69	90.00	-2,469.55	7,683.51	3,398.33	3,213.72	184.61	18.408	
12,400.00	7,289.00	7,246.43	7,246.00	64.27	137.69	90.00	-2,469.55	7,683.51	3,326.22	3,140.21	186.01	17.882	
12,500.00	7,289.00	7,246.43	7,246.00	65.31	137.69	90.00	-2,469.55	7,683.51	3,255.57	3,068.11	187.46	17.367	
12,600.00	7,289.00	7,246.43	7,246.00	66.34	137.69	90.00	-2,469.55	7,683.51	3,186.50	2,997.52	188.98	16.862	
12,700.00	7,289.00	7,246.43	7,246.00	67.38	137.69	90.00	-2,469.55	7,683.51	3,119.11	2,928.55	190.56	16.369	
12,800.00	7,289.00	7,246.43	7,246.00	68.42	137.69	90.00	-2,469.55	7,683.51	3,053.50	2,861.31	192.19	15.888	
12,900.00	7,289.00	7,246.43	7,246.00	69.47	137.69	90.00	-2,469.55	7,683.51	2,989.80	2,795.92	193.89	15.420	
13,000.00	7,289.00	7,246.43	7,246.00	70.51	137.69	90.00	-2,469.55	7,683.51	2,928.13	2,732.50	195.64	14.967	
13,100.00	7,289.00	7,246.43	7,246.00	71.56	137.69	90.00	-2,469.55	7,683.51	2,868.63	2,671.19	197.44	14.529	
13,200.00	7,289.00	7,246.43	7,246.00	72.61	137.69	90.00	-2,469.55	7,683.51	2,811.42	2,612.13	199.29	14.107	
13,300.00	7,289.00	7,246.43	7,246.00	73.67	137.69	90.00	-2,469.55	7,683.51	2,756.65	2,555.47	201.18	13.702	
13,400.00	7,289.00	7,246.43	7,246.00	74.72	137.69	90.00	-2,469.55	7,683.51	2,704.47	2,501.36	203.11	13.315	
13,500.00	7,289.00	7,246.43	7,246.00	75.78	137.69	90.00	-2,469.55	7,683.51	2,655.03	2,449.97	205.06	12.947	
13,600.00	7,289.00	7,246.43	7,246.00	76.84	137.69	90.00	-2,469.55	7,683.51	2,608.49	2,401.46	207.04	12.599	
13,700.00	7,289.00	7,246.43	7,246.00	77.90	137.69	90.00	-2,469.55	7,683.51	2,565.01	2,355.99	209.02	12.272	
13,800.00	7,289.00	7,246.43	7,246.00	78.96	137.69	90.00	-2,469.55	7,683.51	2,524.74	2,313.75	210.99	11.966	
13,900.00	7,289.00	7,246.43	7,246.00	80.02	137.69	90.00	-2,469.55	7,683.51	2,487.84	2,274.89	212.95	11.683	
14,000.00	7,289.00	7,246.43	7,246.00	81.09	137.69	90.00	-2,469.55	7,683.51	2,454.47	2,239.59	214.88	11.423	
14,100.00	7,289.00	7,246.43	7,246.00	82.15	137.69	90.00	-2,469.55	7,683.51	2,424.76	2,208.00	216.76	11.187	
14,200.00	7,289.00	7,246.43	7,246.00	83.22	137.69	90.00	-2,469.55	7,683.51	2,398.85	2,180.28	218.58	10.975	
14,300.00	7,289.00	7,246.43	7,246.00	84.29	137.69	90.00	-2,469.55	7,683.51	2,376.88	2,156.56	220.32	10.789	
14,400.00	7,289.00	7,246.43	7,246.00	85.36	137.69	90.00	-2,469.55	7,683.51	2,358.94	2,136.97	221.96	10.628	
14,500.00	7,289.00	7,246.43	7,246.00	86.44	137.69	90.00	-2,469.55	7,683.51	2,345.13	2,121.63	223.50	10.493	
14,600.00	7,289.00	7,246.43	7,246.00	87.51	137.69	90.00	-2,469.55	7,683.51	2,335.52	2,110.60	224.92	10.384	
14,700.00	7,289.00	7,246.43	7,246.00	88.58	137.69	90.00	-2,469.55	7,683.51	2,330.17	2,103.97	226.21	10.301	
14,774.78	7,289.00	7,246.43	7,246.00	89.39	137.69	90.00	-2,469.55	7,683.51	2,328.97	2,101.90	227.08	10.256 CC	
14,800.00	7,289.00	7,246.43	7,246.00	89.66	137.69	90.00	-2,469.55	7,683.51	2,329.11	2,101.76	227.35	10.244 ES	
14,900.00	7,289.00	7,246.43	7,246.00	90.74	137.69	90.00	-2,469.55	7,683.51	2,332.34	2,103.99	228.35	10.214	
15,000.00	7,289.00	7,246.43	7,246.00	91.82	137.69	90.00	-2,469.55	7,683.51	2,339.84	2,110.65	229.19	10.209 SF	
15,100.00	7,289.00	7,246.43	7,246.00	92.90	137.69	90.00	-2,469.55	7,683.51	2,351.57	2,121.69	229.88	10.230	
15,200.00	7,289.00	7,246.43	7,246.00	93.98	137.69	90.00	-2,469.55	7,683.51	2,367.47	2,137.06	230.41	10.275	
15,300.00	7,289.00	7,246.43	7,246.00	95.06	137.69	90.00	-2,469.55	7,683.51	2,387.46	2,156.67	230.79	10.345	
15,400.00	7,289.00	7,246.43	7,246.00	96.14	137.69	90.00	-2,469.55	7,683.51	2,411.43	2,180.41	231.03	10.438	
15,500.00	7,289.00	7,246.43	7,246.00	97.22	137.69	90.00	-2,469.55	7,683.51	2,439.27	2,208.15	231.12	10.554	
15,600.00	7,289.00	7,246.43	7,246.00	98.31	137.69	90.00	-2,469.55	7,683.51	2,470.85	2,239.76	231.09	10.692	
15,700.00	7,289.00	7,246.43	7,246.00	99.39	137.69	90.00	-2,469.55	7,683.51	2,506.02	2,275.09	230.94	10.852	
15,800.00	7,289.00	7,246.43	7,246.00	100.48	137.69	90.00	-2,469.55	7,683.51	2,544.64	2,313.96	230.68	11.031	
15,900.00	7,289.00	7,246.43	7,246.00	101.56	137.69	90.00	-2,469.55	7,683.51	2,586.55	2,356.23	230.32	11.230	
16,000.00	7,289.00	7,246.43	7,246.00	102.65	137.69	90.00	-2,469.55	7,683.51	2,631.59	2,401.72	229.87	11.448	
16,100.00	7,289.00	7,246.43	7,246.00	103.74	137.69	90.00	-2,469.55	7,683.51	2,679.61	2,450.26	229.35	11.684	
16,200.00	7,289.00	7,246.43	7,246.00	104.83	137.69	90.00	-2,469.55	7,683.51	2,730.45	2,501.69	228.76	11.936	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W10_GOVERNMENT AB #003_1521774 - Inc Only - Inc Only												Offset Site Error:	0.00 usft
Survey Program: 350-INC-ONLY												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
16,300.00	7,289.00	7,246.43	7,246.00	105.92	137.69	90.00	-2,469.55	7,683.51	2,783.96	2,555.83	228.12	12.204	
16,400.00	7,289.00	7,246.43	7,246.00	107.01	137.69	90.00	-2,469.55	7,683.51	2,839.97	2,612.54	227.44	12.487	
16,500.00	7,289.00	7,246.43	7,246.00	108.10	137.69	90.00	-2,469.55	7,683.51	2,898.36	2,671.65	226.72	12.784	
16,600.00	7,289.00	7,246.43	7,246.00	109.19	137.69	90.00	-2,469.55	7,683.51	2,958.98	2,733.01	225.97	13.095	
16,700.00	7,289.00	7,246.43	7,246.00	110.28	137.69	90.00	-2,469.55	7,683.51	3,021.69	2,796.49	225.20	13.418	
16,800.00	7,289.00	7,246.43	7,246.00	111.37	137.69	90.00	-2,469.55	7,683.51	3,086.36	2,861.95	224.41	13.753	
16,900.00	7,289.00	7,246.43	7,246.00	112.46	137.69	90.00	-2,469.55	7,683.51	3,152.88	2,929.27	223.62	14.100	
17,000.00	7,289.00	7,246.43	7,246.00	113.56	137.69	90.00	-2,469.55	7,683.51	3,221.14	2,998.32	222.82	14.456	
17,100.00	7,289.00	7,246.43	7,246.00	114.65	137.69	90.00	-2,469.55	7,683.51	3,291.01	3,068.99	222.02	14.823	
17,200.00	7,289.00	7,246.43	7,246.00	115.75	137.69	90.00	-2,469.55	7,683.51	3,362.41	3,141.19	221.22	15.199	
17,300.00	7,289.00	7,246.43	7,246.00	116.84	137.69	90.00	-2,469.55	7,683.51	3,435.24	3,214.80	220.43	15.584	
17,400.00	7,289.00	7,246.43	7,246.00	117.94	137.69	90.00	-2,469.55	7,683.51	3,509.40	3,289.75	219.65	15.977	
17,500.00	7,289.00	7,246.43	7,246.00	119.03	137.69	90.00	-2,469.55	7,683.51	3,584.82	3,365.94	218.88	16.378	
17,600.00	7,289.00	7,246.43	7,246.00	120.13	137.69	90.00	-2,469.55	7,683.51	3,661.42	3,443.29	218.12	16.786	
17,700.00	7,289.00	7,246.43	7,246.00	121.23	137.69	90.00	-2,469.55	7,683.51	3,739.12	3,521.74	217.38	17.201	
17,800.00	7,289.00	7,246.43	7,246.00	122.33	137.69	90.00	-2,469.55	7,683.51	3,817.86	3,601.21	216.65	17.622	
17,900.00	7,289.00	7,246.43	7,246.00	123.42	137.69	90.00	-2,469.55	7,683.51	3,897.58	3,681.63	215.94	18.049	
18,000.00	7,289.00	7,246.43	7,246.00	124.52	137.69	90.00	-2,469.55	7,683.51	3,978.21	3,762.96	215.25	18.482	
18,100.00	7,289.00	7,246.43	7,246.00	125.62	137.69	90.00	-2,469.55	7,683.51	4,059.70	3,845.13	214.57	18.920	
18,159.20	7,289.00	7,246.43	7,246.00	126.27	137.69	90.00	-2,469.55	7,683.51	4,108.33	3,894.15	214.18	19.182	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W11_GOVERNMENT AB #006_1527846 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 156-INC-NOLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
8,900.00	7,289.00	6,554.00	6,551.42	32.12	165.57	-25.16	177.80	6,401.16	4,675.77	4,487.01	188.75	24.772	
9,000.00	7,289.00	6,554.00	6,551.42	32.82	165.57	-25.16	177.80	6,401.16	4,577.16	4,388.47	188.69	24.258	
9,100.00	7,289.00	6,554.00	6,551.42	33.55	165.57	-25.16	177.80	6,401.16	4,478.62	4,290.00	188.62	23.744	
9,200.00	7,289.00	6,554.00	6,551.42	34.30	165.57	-25.16	177.80	6,401.16	4,380.15	4,191.60	188.55	23.231	
9,300.00	7,289.00	6,554.00	6,551.42	35.07	165.57	-25.16	177.80	6,401.16	4,281.74	4,093.28	188.47	22.719	
9,400.00	7,289.00	6,554.00	6,551.42	35.86	165.57	-25.16	177.80	6,401.16	4,183.42	3,995.03	188.38	22.207	
9,500.00	7,289.00	6,554.00	6,551.42	36.66	165.57	-25.16	177.80	6,401.16	4,085.17	3,896.88	188.29	21.696	
9,600.00	7,289.00	6,554.00	6,551.42	37.48	165.57	-25.16	177.80	6,401.16	3,987.01	3,798.81	188.20	21.185	
9,700.00	7,289.00	6,554.00	6,551.42	38.32	165.57	-25.16	177.80	6,401.16	3,888.94	3,700.85	188.10	20.675	
9,800.00	7,289.00	6,554.00	6,551.42	39.17	165.57	-25.16	177.80	6,401.16	3,790.98	3,602.99	187.99	20.166	
9,900.00	7,289.00	6,554.00	6,551.42	40.03	165.57	-25.16	177.80	6,401.16	3,693.12	3,505.26	187.87	19.658	
10,000.00	7,289.00	6,554.00	6,551.42	40.91	165.57	-25.16	177.80	6,401.16	3,595.39	3,407.65	187.74	19.151	
10,100.00	7,289.00	6,554.00	6,551.42	41.80	165.57	-25.16	177.80	6,401.16	3,497.78	3,310.18	187.60	18.645	
10,200.00	7,289.00	6,554.00	6,551.42	42.69	165.57	-25.16	177.80	6,401.16	3,400.31	3,212.86	187.44	18.141	
10,300.00	7,289.00	6,554.00	6,551.42	43.60	165.57	-25.16	177.80	6,401.16	3,302.99	3,115.71	187.28	17.637	
10,400.00	7,289.00	6,554.00	6,551.42	44.52	165.57	-25.16	177.80	6,401.16	3,205.83	3,018.74	187.09	17.135	
10,500.00	7,289.00	6,554.00	6,551.42	45.45	165.57	-25.16	177.80	6,401.16	3,108.86	2,921.96	186.89	16.634	
10,600.00	7,289.00	6,554.00	6,551.42	46.39	165.57	-25.16	177.80	6,401.16	3,012.08	2,825.40	186.68	16.135	
10,700.00	7,289.00	6,554.00	6,551.42	47.33	165.57	-25.16	177.80	6,401.16	2,915.52	2,729.09	186.44	15.638	
10,800.00	7,289.00	6,554.00	6,551.42	48.28	165.57	-25.16	177.80	6,401.16	2,819.20	2,633.03	186.17	15.143	
10,900.00	7,289.00	6,554.00	6,551.42	49.24	165.57	-25.16	177.80	6,401.16	2,723.15	2,537.27	185.88	14.650	
11,000.00	7,289.00	6,554.00	6,551.42	50.21	165.57	-25.16	177.80	6,401.16	2,627.39	2,441.84	185.55	14.160	
11,100.00	7,289.00	6,554.00	6,551.42	51.18	165.57	-25.16	177.80	6,401.16	2,531.96	2,346.78	185.18	13.673	
11,200.00	7,289.00	6,554.00	6,551.42	52.16	165.57	-25.16	177.80	6,401.16	2,436.90	2,252.12	184.78	13.188	
11,300.00	7,289.00	6,554.00	6,551.42	53.15	165.57	-25.16	177.80	6,401.16	2,342.24	2,157.92	184.32	12.707	
11,400.00	7,289.00	6,554.00	6,551.42	54.14	165.57	-25.16	177.80	6,401.16	2,248.05	2,064.24	183.81	12.230	
11,500.00	7,289.00	6,554.00	6,551.42	55.13	165.57	-25.16	177.80	6,401.16	2,154.38	1,971.16	183.23	11.758	
11,600.00	7,289.00	6,554.00	6,551.42	56.13	165.57	-25.16	177.80	6,401.16	2,061.31	1,878.75	182.57	11.291	
11,700.00	7,289.00	6,554.00	6,551.42	57.13	165.57	-25.16	177.80	6,401.16	1,968.92	1,787.11	181.81	10.829	
11,800.00	7,289.00	6,554.00	6,551.42	58.14	165.57	-25.16	177.80	6,401.16	1,877.31	1,696.36	180.95	10.375	
11,900.00	7,289.00	6,554.00	6,551.42	59.16	165.57	-25.16	177.80	6,401.16	1,786.60	1,606.64	179.95	9.928	
12,000.00	7,289.00	6,554.00	6,551.42	60.17	165.57	-25.16	177.80	6,401.16	1,696.93	1,518.13	178.80	9.491	
12,100.00	7,289.00	6,554.00	6,551.42	61.19	165.57	-25.16	177.80	6,401.16	1,608.48	1,431.03	177.45	9.064	
12,200.00	7,289.00	6,554.00	6,551.42	62.22	165.57	-25.16	177.80	6,401.16	1,521.46	1,345.59	175.87	8.651	
12,300.00	7,289.00	6,554.00	6,551.42	63.24	165.57	-25.16	177.80	6,401.16	1,436.13	1,262.13	174.00	8.253	
12,400.00	7,289.00	6,554.00	6,551.42	64.27	165.57	-25.16	177.80	6,401.16	1,352.82	1,181.03	171.79	7.875	
12,500.00	7,289.00	6,554.00	6,551.42	65.31	165.57	-25.16	177.80	6,401.16	1,271.91	1,102.76	169.15	7.519	
12,600.00	7,289.00	6,554.00	6,551.42	66.34	165.57	-25.16	177.80	6,401.16	1,193.90	1,027.92	165.98	7.193	
12,700.00	7,289.00	6,554.00	6,551.42	67.38	165.57	-25.16	177.80	6,401.16	1,119.39	957.21	162.17	6.902	
12,800.00	7,289.00	6,554.00	6,551.42	68.42	165.57	-25.16	177.80	6,401.16	1,049.13	891.52	157.61	6.657	
12,900.00	7,289.00	6,554.00	6,551.42	69.47	165.57	-25.16	177.80	6,401.16	984.02	831.86	152.16	6.467	
13,000.00	7,289.00	6,554.00	6,551.42	70.51	165.57	-25.16	177.80	6,401.16	925.17	779.39	145.78	6.346	
13,100.00	7,289.00	6,554.00	6,551.42	71.56	165.57	-25.16	177.80	6,401.16	873.83	735.30	138.53	6.308	
13,200.00	7,289.00	6,554.00	6,551.42	72.61	165.57	-25.16	177.80	6,401.16	831.39	700.62	130.78	6.357	
13,300.00	7,289.00	6,554.00	6,551.42	73.67	165.57	-25.16	177.80	6,401.16	799.28	675.92	123.37	6.479	
13,400.00	7,289.00	6,554.00	6,551.42	74.72	165.57	-25.16	177.80	6,401.16	778.78	661.02	117.76	6.613	
13,500.00	7,289.00	6,554.00	6,551.42	75.78	165.57	-25.16	177.80	6,401.16	770.80	655.10	115.70	6.662	
13,511.81	7,289.00	6,554.00	6,551.42	75.90	165.57	-25.16	177.80	6,401.16	770.71	654.95	115.75	6.658 CC, ES	
13,600.00	7,289.00	6,554.00	6,551.42	76.84	165.57	-25.16	177.80	6,401.16	775.74	657.59	118.15	6.566	
13,700.00	7,289.00	6,554.00	6,551.42	77.90	165.57	-25.16	177.80	6,401.16	793.35	668.95	124.40	6.377	
13,800.00	7,289.00	6,554.00	6,551.42	78.96	165.57	-25.16	177.80	6,401.16	822.83	690.10	132.73	6.199	
13,900.00	7,289.00	6,554.00	6,551.42	80.02	165.57	-25.16	177.80	6,401.16	862.95	721.45	141.50	6.098	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W11_GOVERNMENT AB #006_1527846 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 156-INC-NOLY													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
14,000.00	7,289.00	6,554.00	6,551.42	81.09	165.57	-25.16	177.80	6,401.16	912.32	762.60	149.72	6,094 SF	
14,100.00	7,289.00	6,554.00	6,551.42	82.15	165.57	-25.16	177.80	6,401.16	969.51	812.58	156.94	6,178	
14,200.00	7,289.00	6,554.00	6,551.42	83.22	165.57	-25.16	177.80	6,401.16	1,033.25	870.19	163.05	6,337	
14,300.00	7,289.00	6,554.00	6,551.42	84.29	165.57	-25.16	177.80	6,401.16	1,102.38	934.24	168.13	6,557	
14,400.00	7,289.00	6,554.00	6,551.42	85.36	165.57	-25.16	177.80	6,401.16	1,175.96	1,003.64	172.32	6,824	
14,500.00	7,289.00	6,554.00	6,551.42	86.44	165.57	-25.16	177.80	6,401.16	1,253.20	1,077.44	175.76	7,130	
14,600.00	7,289.00	6,554.00	6,551.42	87.51	165.57	-25.16	177.80	6,401.16	1,333.47	1,154.88	178.59	7,467	
14,700.00	7,289.00	6,554.00	6,551.42	88.58	165.57	-25.16	177.80	6,401.16	1,416.26	1,235.33	180.93	7,828	
14,800.00	7,289.00	6,554.00	6,551.42	89.66	165.57	-25.16	177.80	6,401.16	1,501.14	1,318.27	182.87	8,209	
14,900.00	7,289.00	6,554.00	6,551.42	90.74	165.57	-25.16	177.80	6,401.16	1,587.78	1,403.29	184.49	8,606	
15,000.00	7,289.00	6,554.00	6,551.42	91.82	165.57	-25.16	177.80	6,401.16	1,675.92	1,490.06	185.86	9,017	
15,100.00	7,289.00	6,554.00	6,551.42	92.90	165.57	-25.16	177.80	6,401.16	1,765.31	1,578.30	187.02	9,439	
15,200.00	7,289.00	6,554.00	6,551.42	93.98	165.57	-25.16	177.80	6,401.16	1,855.79	1,667.79	188.01	9,871	
15,300.00	7,289.00	6,554.00	6,551.42	95.06	165.57	-25.16	177.80	6,401.16	1,947.21	1,758.35	188.86	10,310	
15,400.00	7,289.00	6,554.00	6,551.42	96.14	165.57	-25.16	177.80	6,401.16	2,039.42	1,849.83	189.60	10,757	
15,500.00	7,289.00	6,554.00	6,551.42	97.22	165.57	-25.16	177.80	6,401.16	2,132.34	1,942.10	190.24	11,208	
15,600.00	7,289.00	6,554.00	6,551.42	98.31	165.57	-25.16	177.80	6,401.16	2,225.88	2,035.07	190.81	11,665	
15,700.00	7,289.00	6,554.00	6,551.42	99.39	165.57	-25.16	177.80	6,401.16	2,319.95	2,128.64	191.31	12,126	
15,800.00	7,289.00	6,554.00	6,551.42	100.48	165.57	-25.16	177.80	6,401.16	2,414.50	2,222.74	191.76	12,591	
15,900.00	7,289.00	6,554.00	6,551.42	101.56	165.57	-25.16	177.80	6,401.16	2,509.47	2,317.31	192.16	13,059	
16,000.00	7,289.00	6,554.00	6,551.42	102.65	165.57	-25.16	177.80	6,401.16	2,604.82	2,412.29	192.52	13,530	
16,100.00	7,289.00	6,554.00	6,551.42	103.74	165.57	-25.16	177.80	6,401.16	2,700.50	2,507.65	192.85	14,003	
16,200.00	7,289.00	6,554.00	6,551.42	104.83	165.57	-25.16	177.80	6,401.16	2,796.49	2,603.34	193.15	14,478	
16,300.00	7,289.00	6,554.00	6,551.42	105.92	165.57	-25.16	177.80	6,401.16	2,892.75	2,699.32	193.43	14,955	
16,400.00	7,289.00	6,554.00	6,551.42	107.01	165.57	-25.16	177.80	6,401.16	2,989.25	2,795.57	193.68	15,434	
16,500.00	7,289.00	6,554.00	6,551.42	108.10	165.57	-25.16	177.80	6,401.16	3,085.98	2,892.06	193.92	15,914	
16,600.00	7,289.00	6,554.00	6,551.42	109.19	165.57	-25.16	177.80	6,401.16	3,182.91	2,988.77	194.14	16,395	
16,700.00	7,289.00	6,554.00	6,551.42	110.28	165.57	-25.16	177.80	6,401.16	3,280.02	3,085.68	194.35	16,877	
16,800.00	7,289.00	6,554.00	6,551.42	111.37	165.57	-25.16	177.80	6,401.16	3,377.30	3,182.76	194.54	17,360	
16,900.00	7,289.00	6,554.00	6,551.42	112.46	165.57	-25.16	177.80	6,401.16	3,474.74	3,280.02	194.72	17,844	
17,000.00	7,289.00	6,554.00	6,551.42	113.56	165.57	-25.16	177.80	6,401.16	3,572.32	3,377.42	194.90	18,329	
17,100.00	7,289.00	6,554.00	6,551.42	114.65	165.57	-25.16	177.80	6,401.16	3,670.03	3,474.96	195.07	18,814	
17,200.00	7,289.00	6,554.00	6,551.42	115.75	165.57	-25.16	177.80	6,401.16	3,767.86	3,572.63	195.22	19,300	
17,300.00	7,289.00	6,554.00	6,551.42	116.84	165.57	-25.16	177.80	6,401.16	3,865.80	3,670.42	195.38	19,786	
17,400.00	7,289.00	6,554.00	6,551.42	117.94	165.57	-25.16	177.80	6,401.16	3,963.84	3,768.31	195.52	20,273	
17,500.00	7,289.00	6,554.00	6,551.42	119.03	165.57	-25.16	177.80	6,401.16	4,061.98	3,866.31	195.67	20,760	
17,600.00	7,289.00	6,554.00	6,551.42	120.13	165.57	-25.16	177.80	6,401.16	4,160.20	3,964.40	195.81	21,247	
17,700.00	7,289.00	6,554.00	6,551.42	121.23	165.57	-25.16	177.80	6,401.16	4,258.51	4,062.57	195.94	21,734	
17,800.00	7,289.00	6,554.00	6,551.42	122.33	165.57	-25.16	177.80	6,401.16	4,356.90	4,160.83	196.07	22,221	
17,900.00	7,289.00	6,554.00	6,551.42	123.42	165.57	-25.16	177.80	6,401.16	4,455.36	4,259.16	196.20	22,709	
18,000.00	7,289.00	6,554.00	6,551.42	124.52	165.57	-25.16	177.80	6,401.16	4,553.88	4,357.56	196.32	23,196	
18,100.00	7,289.00	6,554.00	6,551.42	125.62	165.57	-25.16	177.80	6,401.16	4,652.47	4,456.03	196.44	23,683	
18,159.20	7,289.00	6,554.00	6,551.42	126.27	165.57	-25.16	177.80	6,401.16	4,710.86	4,514.34	196.52	23,972	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W12_GOVERNMENT AB #007_1527847 - Inc Only - Inc Only													Offset Site Error:	0.00 usft	
Survey Program:		155-INC-NOLY				Rule Assigned:								Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance			Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)				
9,900.00	7,289.00	6,590.00	6,586.51	40.03	178.10	-26.58	188.17	7,721.65	4,986.66	4,784.77	201.89	24.700			
10,000.00	7,289.00	6,590.00	6,586.51	40.91	178.10	-26.58	188.17	7,721.65	4,887.77	4,685.91	201.86	24.213			
10,100.00	7,289.00	6,590.00	6,586.51	41.80	178.10	-26.58	188.17	7,721.65	4,788.93	4,587.10	201.83	23.728			
10,200.00	7,289.00	6,590.00	6,586.51	42.69	178.10	-26.58	188.17	7,721.65	4,690.14	4,488.35	201.79	23.242			
10,300.00	7,289.00	6,590.00	6,586.51	43.60	178.10	-26.58	188.17	7,721.65	4,591.40	4,389.64	201.75	22.757			
10,400.00	7,289.00	6,590.00	6,586.51	44.52	178.10	-26.58	188.17	7,721.65	4,492.71	4,291.00	201.71	22.273			
10,500.00	7,289.00	6,590.00	6,586.51	45.45	178.10	-26.58	188.17	7,721.65	4,394.09	4,192.42	201.67	21.789			
10,600.00	7,289.00	6,590.00	6,586.51	46.39	178.10	-26.58	188.17	7,721.65	4,295.52	4,093.90	201.62	21.305			
10,700.00	7,289.00	6,590.00	6,586.51	47.33	178.10	-26.58	188.17	7,721.65	4,197.03	3,995.46	201.57	20.822			
10,800.00	7,289.00	6,590.00	6,586.51	48.28	178.10	-26.58	188.17	7,721.65	4,098.61	3,897.10	201.51	20.339			
10,900.00	7,289.00	6,590.00	6,586.51	49.24	178.10	-26.58	188.17	7,721.65	4,000.27	3,798.81	201.45	19.857			
11,000.00	7,289.00	6,590.00	6,586.51	50.21	178.10	-26.58	188.17	7,721.65	3,902.01	3,700.62	201.39	19.376			
11,100.00	7,289.00	6,590.00	6,586.51	51.18	178.10	-26.58	188.17	7,721.65	3,803.84	3,602.53	201.31	18.895			
11,200.00	7,289.00	6,590.00	6,586.51	52.16	178.10	-26.58	188.17	7,721.65	3,705.77	3,504.53	201.23	18.415			
11,300.00	7,289.00	6,590.00	6,586.51	53.15	178.10	-26.58	188.17	7,721.65	3,607.80	3,406.66	201.15	17.936			
11,400.00	7,289.00	6,590.00	6,586.51	54.14	178.10	-26.58	188.17	7,721.65	3,509.96	3,308.90	201.05	17.458			
11,500.00	7,289.00	6,590.00	6,586.51	55.13	178.10	-26.58	188.17	7,721.65	3,412.23	3,211.28	200.95	16.981			
11,600.00	7,289.00	6,590.00	6,586.51	56.13	178.10	-26.58	188.17	7,721.65	3,314.64	3,113.81	200.83	16.504			
11,700.00	7,289.00	6,590.00	6,586.51	57.13	178.10	-26.58	188.17	7,721.65	3,217.20	3,016.49	200.71	16.029			
11,800.00	7,289.00	6,590.00	6,586.51	58.14	178.10	-26.58	188.17	7,721.65	3,119.92	2,919.35	200.57	15.555			
11,900.00	7,289.00	6,590.00	6,586.51	59.16	178.10	-26.58	188.17	7,721.65	3,022.82	2,822.41	200.41	15.083			
12,000.00	7,289.00	6,590.00	6,586.51	60.17	178.10	-26.58	188.17	7,721.65	2,925.91	2,725.67	200.24	14.612			
12,100.00	7,289.00	6,590.00	6,586.51	61.19	178.10	-26.58	188.17	7,721.65	2,829.22	2,629.17	200.05	14.142			
12,200.00	7,289.00	6,590.00	6,586.51	62.22	178.10	-26.58	188.17	7,721.65	2,732.77	2,532.93	199.84	13.675			
12,300.00	7,289.00	6,590.00	6,586.51	63.24	178.10	-26.58	188.17	7,721.65	2,636.58	2,436.98	199.60	13.209			
12,400.00	7,289.00	6,590.00	6,586.51	64.27	178.10	-26.58	188.17	7,721.65	2,540.69	2,341.35	199.34	12.746			
12,500.00	7,289.00	6,590.00	6,586.51	65.31	178.10	-26.58	188.17	7,721.65	2,445.12	2,246.09	199.04	12.285			
12,600.00	7,289.00	6,590.00	6,586.51	66.34	178.10	-26.58	188.17	7,721.65	2,349.93	2,151.23	198.70	11.826			
12,700.00	7,289.00	6,590.00	6,586.51	67.38	178.10	-26.58	188.17	7,721.65	2,255.15	2,056.83	198.32	11.371			
12,800.00	7,289.00	6,590.00	6,586.51	68.42	178.10	-26.58	188.17	7,721.65	2,160.84	1,962.96	197.88	10.920			
12,900.00	7,289.00	6,590.00	6,586.51	69.47	178.10	-26.58	188.17	7,721.65	2,067.07	1,869.68	197.39	10.472			
13,000.00	7,289.00	6,590.00	6,586.51	70.51	178.10	-26.58	188.17	7,721.65	1,973.90	1,777.09	196.82	10.029			
13,100.00	7,289.00	6,590.00	6,586.51	71.56	178.10	-26.58	188.17	7,721.65	1,881.44	1,685.29	196.16	9.592			
13,200.00	7,289.00	6,590.00	6,586.51	72.61	178.10	-26.58	188.17	7,721.65	1,789.79	1,594.40	195.39	9.160			
13,300.00	7,289.00	6,590.00	6,586.51	73.67	178.10	-26.58	188.17	7,721.65	1,699.09	1,504.59	194.49	8.736			
13,400.00	7,289.00	6,590.00	6,586.51	74.72	178.10	-26.58	188.17	7,721.65	1,609.48	1,416.04	193.44	8.320			
13,500.00	7,289.00	6,590.00	6,586.51	75.78	178.10	-26.58	188.17	7,721.65	1,521.17	1,328.98	192.19	7.915			
13,600.00	7,289.00	6,590.00	6,586.51	76.84	178.10	-26.58	188.17	7,721.65	1,434.39	1,243.70	190.70	7.522			
13,700.00	7,289.00	6,590.00	6,586.51	77.90	178.10	-26.58	188.17	7,721.65	1,349.45	1,160.55	188.90	7.144			
13,800.00	7,289.00	6,590.00	6,586.51	78.96	178.10	-26.58	188.17	7,721.65	1,266.71	1,079.98	186.72	6.784			
13,900.00	7,289.00	6,590.00	6,586.51	80.02	178.10	-26.58	188.17	7,721.65	1,186.63	1,002.56	184.07	6.447			
14,000.00	7,289.00	6,590.00	6,586.51	81.09	178.10	-26.58	188.17	7,721.65	1,109.78	928.97	180.81	6.138			
14,100.00	7,289.00	6,590.00	6,586.51	82.15	178.10	-26.58	188.17	7,721.65	1,036.89	860.08	176.81	5.864			
14,200.00	7,289.00	6,590.00	6,586.51	83.22	178.10	-26.58	188.17	7,721.65	968.85	796.93	171.92	5.635			
14,300.00	7,289.00	6,590.00	6,586.51	84.29	178.10	-26.58	188.17	7,721.65	906.76	740.74	166.01	5.462			
14,400.00	7,289.00	6,590.00	6,586.51	85.36	178.10	-26.58	188.17	7,721.65	851.90	692.83	159.07	5.356			
14,500.00	7,289.00	6,590.00	6,586.51	86.44	178.10	-26.58	188.17	7,721.65	805.77	654.44	151.33	5.324			
14,600.00	7,289.00	6,590.00	6,586.51	87.51	178.10	-26.58	188.17	7,721.65	769.94	626.40	143.54	5.364			
14,700.00	7,289.00	6,590.00	6,586.51	88.58	178.10	-26.58	188.17	7,721.65	745.88	608.76	137.11	5.440			
14,800.00	7,289.00	6,590.00	6,586.51	89.66	178.10	-26.58	188.17	7,721.65	734.76	600.74	134.01	5.483			
14,832.34	7,289.00	6,590.00	6,586.51	90.01	178.10	-26.58	188.17	7,721.65	734.04	600.05	134.00	5.478 CC, ES			
14,900.00	7,289.00	6,590.00	6,586.51	90.74	178.10	-26.58	188.17	7,721.65	737.16	601.54	135.62	5.435			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W12_GOVERNMENT AB #007_1527847 - Inc Only - Inc Only														Offset Site Error: 0.00 usft
Survey Program: 155-INC-ONLY														Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Offset Wellbore Centre		Rule Assigned:				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
15,000.00	7,289.00	6,590.00	6,586.51	91.82	178.10	-26.58	188.17	7,721.65	752.95	611.41	141.54	5.320		
15,100.00	7,289.00	6,590.00	6,586.51	92.90	178.10	-26.58	188.17	7,721.65	781.32	631.38	149.94	5.211		
15,200.00	7,289.00	6,590.00	6,586.51	93.98	178.10	-26.58	188.17	7,721.65	820.97	662.04	158.93	5.166 SF		
15,300.00	7,289.00	6,590.00	6,586.51	95.06	178.10	-26.58	188.17	7,721.65	870.36	703.03	167.33	5.202		
15,400.00	7,289.00	6,590.00	6,586.51	96.14	178.10	-26.58	188.17	7,721.65	927.93	753.33	174.61	5.314		
15,500.00	7,289.00	6,590.00	6,586.51	97.22	178.10	-26.58	188.17	7,721.65	992.26	811.60	180.67	5.492		
15,600.00	7,289.00	6,590.00	6,586.51	98.31	178.10	-26.58	188.17	7,721.65	1,062.13	876.52	185.61	5.722		
15,700.00	7,289.00	6,590.00	6,586.51	99.39	178.10	-26.58	188.17	7,721.65	1,136.51	946.91	189.60	5.994		
15,800.00	7,289.00	6,590.00	6,586.51	100.48	178.10	-26.58	188.17	7,721.65	1,214.57	1,021.76	192.81	6.299		
15,900.00	7,289.00	6,590.00	6,586.51	101.56	178.10	-26.58	188.17	7,721.65	1,295.65	1,100.24	195.41	6.630		
16,000.00	7,289.00	6,590.00	6,586.51	102.65	178.10	-26.58	188.17	7,721.65	1,379.22	1,181.71	197.51	6.983		
16,100.00	7,289.00	6,590.00	6,586.51	103.74	178.10	-26.58	188.17	7,721.65	1,464.85	1,265.61	199.23	7.352		
16,200.00	7,289.00	6,590.00	6,586.51	104.83	178.10	-26.58	188.17	7,721.65	1,552.20	1,351.55	200.65	7.736		
16,300.00	7,289.00	6,590.00	6,586.51	105.92	178.10	-26.58	188.17	7,721.65	1,640.99	1,439.16	201.83	8.131		
16,400.00	7,289.00	6,590.00	6,586.51	107.01	178.10	-26.58	188.17	7,721.65	1,731.00	1,528.19	202.81	8.535		
16,500.00	7,289.00	6,590.00	6,586.51	108.10	178.10	-26.58	188.17	7,721.65	1,822.06	1,618.42	203.64	8.947		
16,600.00	7,289.00	6,590.00	6,586.51	109.19	178.10	-26.58	188.17	7,721.65	1,914.01	1,709.66	204.35	9.366		
16,700.00	7,289.00	6,590.00	6,586.51	110.28	178.10	-26.58	188.17	7,721.65	2,006.73	1,801.78	204.96	9.791		
16,800.00	7,289.00	6,590.00	6,586.51	111.37	178.10	-26.58	188.17	7,721.65	2,100.12	1,894.64	205.48	10.220		
16,900.00	7,289.00	6,590.00	6,586.51	112.46	178.10	-26.58	188.17	7,721.65	2,194.09	1,988.15	205.94	10.654		
17,000.00	7,289.00	6,590.00	6,586.51	113.56	178.10	-26.58	188.17	7,721.65	2,288.57	2,082.22	206.35	11.091		
17,100.00	7,289.00	6,590.00	6,586.51	114.65	178.10	-26.58	188.17	7,721.65	2,383.51	2,176.80	206.71	11.531		
17,200.00	7,289.00	6,590.00	6,586.51	115.75	178.10	-26.58	188.17	7,721.65	2,478.84	2,271.81	207.03	11.973		
17,300.00	7,289.00	6,590.00	6,586.51	116.84	178.10	-26.58	188.17	7,721.65	2,574.52	2,367.20	207.32	12.418		
17,400.00	7,289.00	6,590.00	6,586.51	117.94	178.10	-26.58	188.17	7,721.65	2,670.52	2,462.94	207.58	12.865		
17,500.00	7,289.00	6,590.00	6,586.51	119.03	178.10	-26.58	188.17	7,721.65	2,766.81	2,558.98	207.82	13.313		
17,600.00	7,289.00	6,590.00	6,586.51	120.13	178.10	-26.58	188.17	7,721.65	2,863.35	2,655.30	208.05	13.763		
17,700.00	7,289.00	6,590.00	6,586.51	121.23	178.10	-26.58	188.17	7,721.65	2,960.12	2,751.86	208.25	14.214		
17,800.00	7,289.00	6,590.00	6,586.51	122.33	178.10	-26.58	188.17	7,721.65	3,057.09	2,848.65	208.44	14.666		
17,900.00	7,289.00	6,590.00	6,586.51	123.42	178.10	-26.58	188.17	7,721.65	3,154.26	2,945.64	208.62	15.119		
18,000.00	7,289.00	6,590.00	6,586.51	124.52	178.10	-26.58	188.17	7,721.65	3,251.60	3,042.80	208.79	15.573		
18,100.00	7,289.00	6,590.00	6,586.51	125.62	178.10	-26.58	188.17	7,721.65	3,349.09	3,140.14	208.95	16.028		
18,159.20	7,289.00	6,590.00	6,586.51	126.27	178.10	-26.58	188.17	7,721.65	3,406.87	3,197.83	209.04	16.297		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W13_GOVERNMENT AB #008_1527863 - Inc Only - Inc Only														Offset Site Error:	0.00 usft
Survey Program:		150-INC-ONLY						Rule Assigned:						Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Distance				Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
11,800.00	7,289.00	6,630.00	6,627.95	58.14	154.10	-16.21	48.74	9,068.24	4,424.65	4,246.04	178.61	24.773			
11,900.00	7,289.00	6,630.00	6,627.95	59.16	154.10	-16.21	48.74	9,068.24	4,325.73	4,147.14	178.59	24.222			
12,000.00	7,289.00	6,630.00	6,627.95	60.17	154.10	-16.21	48.74	9,068.24	4,226.86	4,048.29	178.57	23.671			
12,100.00	7,289.00	6,630.00	6,627.95	61.19	154.10	-16.21	48.74	9,068.24	4,128.05	3,949.50	178.54	23.121			
12,200.00	7,289.00	6,630.00	6,627.95	62.22	154.10	-16.21	48.74	9,068.24	4,029.29	3,850.78	178.51	22.571			
12,300.00	7,289.00	6,630.00	6,627.95	63.24	154.10	-16.21	48.74	9,068.24	3,930.60	3,752.12	178.48	22.023			
12,400.00	7,289.00	6,630.00	6,627.95	64.27	154.10	-16.21	48.74	9,068.24	3,831.97	3,653.53	178.44	21.475			
12,500.00	7,289.00	6,630.00	6,627.95	65.31	154.10	-16.21	48.74	9,068.24	3,733.42	3,555.03	178.40	20.928			
12,600.00	7,289.00	6,630.00	6,627.95	66.34	154.10	-16.21	48.74	9,068.24	3,634.95	3,456.60	178.35	20.381			
12,700.00	7,289.00	6,630.00	6,627.95	67.38	154.10	-16.21	48.74	9,068.24	3,536.57	3,358.27	178.29	19.836			
12,800.00	7,289.00	6,630.00	6,627.95	68.42	154.10	-16.21	48.74	9,068.24	3,438.27	3,260.04	178.23	19.291			
12,900.00	7,289.00	6,630.00	6,627.95	69.47	154.10	-16.21	48.74	9,068.24	3,340.08	3,161.92	178.16	18.748			
13,000.00	7,289.00	6,630.00	6,627.95	70.51	154.10	-16.21	48.74	9,068.24	3,242.00	3,063.92	178.08	18.206			
13,100.00	7,289.00	6,630.00	6,627.95	71.56	154.10	-16.21	48.74	9,068.24	3,144.04	2,966.06	177.98	17.665			
13,200.00	7,289.00	6,630.00	6,627.95	72.61	154.10	-16.21	48.74	9,068.24	3,046.21	2,868.33	177.88	17.125			
13,300.00	7,289.00	6,630.00	6,627.95	73.67	154.10	-16.21	48.74	9,068.24	2,948.53	2,770.77	177.76	16.587			
13,400.00	7,289.00	6,630.00	6,627.95	74.72	154.10	-16.21	48.74	9,068.24	2,851.01	2,673.38	177.63	16.050			
13,500.00	7,289.00	6,630.00	6,627.95	75.78	154.10	-16.21	48.74	9,068.24	2,753.67	2,576.19	177.48	15.515			
13,600.00	7,289.00	6,630.00	6,627.95	76.84	154.10	-16.21	48.74	9,068.24	2,656.52	2,479.21	177.31	14.982			
13,700.00	7,289.00	6,630.00	6,627.95	77.90	154.10	-16.21	48.74	9,068.24	2,559.60	2,382.48	177.12	14.452			
13,800.00	7,289.00	6,630.00	6,627.95	78.96	154.10	-16.21	48.74	9,068.24	2,462.91	2,286.02	176.89	13.923			
13,900.00	7,289.00	6,630.00	6,627.95	80.02	154.10	-16.21	48.74	9,068.24	2,366.51	2,189.87	176.64	13.397			
14,000.00	7,289.00	6,630.00	6,627.95	81.09	154.10	-16.21	48.74	9,068.24	2,270.42	2,094.06	176.35	12.874			
14,100.00	7,289.00	6,630.00	6,627.95	82.15	154.10	-16.21	48.74	9,068.24	2,174.68	1,998.66	176.02	12.355			
14,200.00	7,289.00	6,630.00	6,627.95	83.22	154.10	-16.21	48.74	9,068.24	2,079.34	1,903.70	175.64	11.839			
14,300.00	7,289.00	6,630.00	6,627.95	84.29	154.10	-16.21	48.74	9,068.24	1,984.46	1,809.26	175.20	11.327			
14,400.00	7,289.00	6,630.00	6,627.95	85.36	154.10	-16.21	48.74	9,068.24	1,890.10	1,715.42	174.68	10.820			
14,500.00	7,289.00	6,630.00	6,627.95	86.44	154.10	-16.21	48.74	9,068.24	1,796.36	1,622.28	174.08	10.319			
14,600.00	7,289.00	6,630.00	6,627.95	87.51	154.10	-16.21	48.74	9,068.24	1,703.33	1,529.96	173.37	9.825			
14,700.00	7,289.00	6,630.00	6,627.95	88.58	154.10	-16.21	48.74	9,068.24	1,611.13	1,438.61	172.52	9.339			
14,800.00	7,289.00	6,630.00	6,627.95	89.66	154.10	-16.21	48.74	9,068.24	1,519.93	1,348.41	171.52	8.862			
14,900.00	7,289.00	6,630.00	6,627.95	90.74	154.10	-16.21	48.74	9,068.24	1,429.90	1,259.59	170.31	8.396			
15,000.00	7,289.00	6,630.00	6,627.95	91.82	154.10	-16.21	48.74	9,068.24	1,341.28	1,172.44	168.83	7.944			
15,100.00	7,289.00	6,630.00	6,627.95	92.90	154.10	-16.21	48.74	9,068.24	1,254.37	1,087.34	167.03	7.510			
15,200.00	7,289.00	6,630.00	6,627.95	93.98	154.10	-16.21	48.74	9,068.24	1,169.56	1,004.77	164.79	7.097			
15,300.00	7,289.00	6,630.00	6,627.95	95.06	154.10	-16.21	48.74	9,068.24	1,087.33	925.35	161.98	6.713			
15,400.00	7,289.00	6,630.00	6,627.95	96.14	154.10	-16.21	48.74	9,068.24	1,008.32	849.88	158.44	6.364			
15,500.00	7,289.00	6,630.00	6,627.95	97.22	154.10	-16.21	48.74	9,068.24	933.35	779.41	153.93	6.063			
15,600.00	7,289.00	6,630.00	6,627.95	98.31	154.10	-16.21	48.74	9,068.24	863.46	715.28	148.18	5.827			
15,700.00	7,289.00	6,630.00	6,627.95	99.39	154.10	-16.21	48.74	9,068.24	799.99	659.12	140.87	5.679			
15,800.00	7,289.00	6,630.00	6,627.95	100.48	154.10	-16.21	48.74	9,068.24	744.58	612.80	131.78	5.650			
15,900.00	7,289.00	6,630.00	6,627.95	101.56	154.10	-16.21	48.74	9,068.24	699.16	578.16	121.00	5.778			
16,000.00	7,289.00	6,630.00	6,627.95	102.65	154.10	-16.21	48.74	9,068.24	665.77	556.23	109.55	6.078			
16,100.00	7,289.00	6,630.00	6,627.95	103.74	154.10	-16.21	48.74	9,068.24	646.28	545.92	100.36	6.440			
16,177.89	7,289.00	6,630.00	6,627.95	104.59	154.10	-16.21	48.74	9,068.24	641.57	543.54	98.02	6.545 CC			
16,200.00	7,289.00	6,630.00	6,627.95	104.83	154.10	-16.21	48.74	9,068.24	641.95	543.51	98.44	6.521 ES			
16,300.00	7,289.00	6,630.00	6,627.95	105.92	154.10	-16.21	48.74	9,068.24	653.09	547.41	105.67	6.180			
16,400.00	7,289.00	6,630.00	6,627.95	107.01	154.10	-16.21	48.74	9,068.24	678.93	561.19	117.74	5.766			
16,500.00	7,289.00	6,630.00	6,627.95	108.10	154.10	-16.21	48.74	9,068.24	717.89	587.65	130.24	5.512			
16,600.00	7,289.00	6,630.00	6,627.95	109.19	154.10	-16.21	48.74	9,068.24	767.98	626.77	141.20	5.439 SF			
16,700.00	7,289.00	6,630.00	6,627.95	110.28	154.10	-16.21	48.74	9,068.24	827.17	677.02	150.15	5.509			
16,800.00	7,289.00	6,630.00	6,627.95	111.37	154.10	-16.21	48.74	9,068.24	893.66	736.46	157.20	5.685			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W13_GOVERNMENT AB #008_1527863 - Inc Only - Inc Only													Offset Site Error: 0.00 usft
Survey Program: 150-INC-ONLY													Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance			Separation Factor	Warning
		Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)		
16,900.00	7,289.00	6,630.00	6,627.95	112.46	154.10	-16.21	48.74	9,068.24	965.95	803.26	162.69	5.937	
17,000.00	7,289.00	6,630.00	6,627.95	113.56	154.10	-16.21	48.74	9,068.24	1,042.82	875.87	166.95	6.246	
17,100.00	7,289.00	6,630.00	6,627.95	114.65	154.10	-16.21	48.74	9,068.24	1,123.34	953.07	170.27	6.597	
17,200.00	7,289.00	6,630.00	6,627.95	115.75	154.10	-16.21	48.74	9,068.24	1,206.78	1,033.90	172.89	6.980	
17,300.00	7,289.00	6,630.00	6,627.95	116.84	154.10	-16.21	48.74	9,068.24	1,292.57	1,117.61	174.96	7.388	
17,400.00	7,289.00	6,630.00	6,627.95	117.94	154.10	-16.21	48.74	9,068.24	1,380.28	1,203.65	176.63	7.815	
17,500.00	7,289.00	6,630.00	6,627.95	119.03	154.10	-16.21	48.74	9,068.24	1,469.56	1,291.57	177.98	8.257	
17,600.00	7,289.00	6,630.00	6,627.95	120.13	154.10	-16.21	48.74	9,068.24	1,560.13	1,381.04	179.10	8.711	
17,700.00	7,289.00	6,630.00	6,627.95	121.23	154.10	-16.21	48.74	9,068.24	1,651.80	1,471.78	180.02	9.176	
17,800.00	7,289.00	6,630.00	6,627.95	122.33	154.10	-16.21	48.74	9,068.24	1,744.38	1,563.58	180.80	9.648	
17,900.00	7,289.00	6,630.00	6,627.95	123.42	154.10	-16.21	48.74	9,068.24	1,837.74	1,656.28	181.46	10.127	
18,000.00	7,289.00	6,630.00	6,627.95	124.52	154.10	-16.21	48.74	9,068.24	1,931.76	1,749.73	182.03	10.612	
18,100.00	7,289.00	6,630.00	6,627.95	125.62	154.10	-16.21	48.74	9,068.24	2,026.36	1,843.84	182.52	11.102	
18,159.20	7,289.00	6,630.00	6,627.95	126.27	154.10	-16.21	48.74	9,068.24	2,082.59	1,899.81	182.78	11.394	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W14_ GOVERNMENT AB #009_1527964 - MWD/Inc - MWD/Inc													Offset Site Error: 0.00 usft
Survey Program: 100-OWSG MWD Rev 5													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
16,500.00	7,289.00	6,678.00	6,603.96	108.10	15.72	-19.22	100.68	10,394.06	1,208.47	1,157.39	51.08	23.660	
16,600.00	7,289.00	6,678.00	6,603.96	109.19	15.72	-19.22	100.68	10,394.06	1,126.76	1,074.32	52.44	21.485	
16,700.00	7,289.00	6,678.00	6,603.96	110.28	15.72	-19.22	100.68	10,394.06	1,048.23	994.19	54.03	19.400	
16,800.00	7,289.00	6,678.00	6,603.96	111.37	15.72	-19.22	100.68	10,394.06	973.64	917.77	55.86	17.429	
16,900.00	7,289.00	6,678.00	6,603.96	112.46	15.72	-19.22	100.68	10,394.06	903.97	846.02	57.95	15.600	
17,000.00	7,289.00	6,678.00	6,603.96	113.56	15.72	-19.22	100.68	10,394.06	840.45	780.19	60.26	13.947	
17,100.00	7,289.00	6,678.00	6,603.96	114.65	15.72	-19.22	100.68	10,394.06	784.56	721.82	62.75	12.504	
17,200.00	7,289.00	6,678.00	6,603.96	115.75	15.72	-19.22	100.68	10,394.06	738.06	672.78	65.28	11.306	
17,300.00	7,289.00	6,678.00	6,603.96	116.84	15.72	-19.22	100.68	10,394.06	702.80	635.12	67.68	10.384	
17,400.00	7,289.00	6,678.00	6,603.96	117.94	15.72	-19.22	100.68	10,394.06	680.53	610.82	69.70	9.763	
17,500.00	7,289.00	6,678.00	6,603.96	119.03	15.72	-19.22	100.68	10,394.06	672.54	601.43	71.11	9.458	
17,504.04	7,289.00	6,678.00	6,603.96	119.08	15.72	-19.22	100.68	10,394.06	672.52	601.37	71.15	9.452 CC, ES, SF	
17,600.00	7,289.00	6,678.00	6,603.96	120.13	15.72	-19.22	100.68	10,394.06	679.34	607.60	71.73	9.470	
17,700.00	7,289.00	6,678.00	6,603.96	121.23	15.72	-19.22	100.68	10,394.06	700.49	628.95	71.54	9.791	
17,800.00	7,289.00	6,678.00	6,603.96	122.33	15.72	-19.22	100.68	10,394.06	734.76	664.10	70.66	10.398	
17,900.00	7,289.00	6,678.00	6,603.96	123.42	15.72	-19.22	100.68	10,394.06	780.43	711.13	69.30	11.261	
18,000.00	7,289.00	6,678.00	6,603.96	124.52	15.72	-19.22	100.68	10,394.06	835.62	767.94	67.68	12.346	
18,100.00	7,289.00	6,678.00	6,603.96	125.62	15.72	-19.22	100.68	10,394.06	898.58	832.61	65.98	13.620	
18,159.20	7,289.00	6,678.00	6,603.96	126.27	15.72	-19.22	100.68	10,394.06	938.89	873.91	64.98	14.449	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W15_GOVERNMENT AB FEDERAL #011_1540853 - MWD - MWD													Offset Site Error: 0.00 usft
Survey Program: 359-OWSG MWD Rev 5													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
13,400.00	7,289.00	6,684.00	6,681.41	74.72	20.00	61.94	-1,231.24	7,488.12	1,713.47	1,643.46	70.02	24.472	
13,500.00	7,289.00	6,684.00	6,681.41	75.78	20.00	61.94	-1,231.24	7,488.12	1,645.69	1,573.41	72.28	22.768	
13,600.00	7,289.00	6,684.00	6,681.41	76.84	20.00	61.94	-1,231.24	7,488.12	1,581.33	1,506.66	74.68	21.176	
13,700.00	7,289.00	6,684.00	6,681.41	77.90	20.00	61.94	-1,231.24	7,488.12	1,520.83	1,443.65	77.18	19.704	
13,800.00	7,289.00	6,684.00	6,681.41	78.96	20.00	61.94	-1,231.24	7,488.12	1,464.66	1,384.88	79.78	18.359	
13,900.00	7,289.00	6,684.00	6,681.41	80.02	20.00	61.94	-1,231.24	7,488.12	1,413.35	1,330.92	82.43	17.146	
14,000.00	7,289.00	6,684.00	6,681.41	81.09	20.00	61.94	-1,231.24	7,488.12	1,367.43	1,282.35	85.08	16.072	
14,100.00	7,289.00	6,684.00	6,681.41	82.15	20.00	61.94	-1,231.24	7,488.12	1,327.47	1,239.80	87.67	15.141	
14,200.00	7,289.00	6,684.00	6,681.41	83.22	20.00	61.94	-1,231.24	7,488.12	1,294.02	1,203.89	90.13	14.357	
14,300.00	7,289.00	6,684.00	6,681.41	84.29	20.00	61.94	-1,231.24	7,488.12	1,267.59	1,175.21	92.38	13.722	
14,400.00	7,289.00	6,684.00	6,681.41	85.36	20.00	61.94	-1,231.24	7,488.12	1,248.64	1,154.30	94.33	13.236	
14,500.00	7,289.00	6,684.00	6,681.41	86.44	20.00	61.94	-1,231.24	7,488.12	1,237.50	1,141.57	95.93	12.900	
14,588.45	7,289.00	6,684.00	6,681.41	87.39	20.00	61.94	-1,231.24	7,488.12	1,234.34	1,137.34	97.00	12.725 CC	
14,600.00	7,289.00	6,684.00	6,681.41	87.51	20.00	61.94	-1,231.24	7,488.12	1,234.39	1,137.28	97.11	12.711 ES	
14,700.00	7,289.00	6,684.00	6,681.41	88.58	20.00	61.94	-1,231.24	7,488.12	1,239.37	1,141.52	97.85	12.666 SF	
14,800.00	7,289.00	6,684.00	6,681.41	89.66	20.00	61.94	-1,231.24	7,488.12	1,252.33	1,154.19	98.14	12.761	
14,900.00	7,289.00	6,684.00	6,681.41	90.74	20.00	61.94	-1,231.24	7,488.12	1,273.05	1,175.05	98.00	12.990	
15,000.00	7,289.00	6,684.00	6,681.41	91.82	20.00	61.94	-1,231.24	7,488.12	1,301.14	1,203.66	97.48	13.348	
15,100.00	7,289.00	6,684.00	6,681.41	92.90	20.00	61.94	-1,231.24	7,488.12	1,336.14	1,239.51	96.63	13.827	
15,200.00	7,289.00	6,684.00	6,681.41	93.98	20.00	61.94	-1,231.24	7,488.12	1,377.53	1,282.00	95.53	14.420	
15,300.00	7,289.00	6,684.00	6,681.41	95.06	20.00	61.94	-1,231.24	7,488.12	1,424.74	1,330.51	94.23	15.120	
15,400.00	7,289.00	6,684.00	6,681.41	96.14	20.00	61.94	-1,231.24	7,488.12	1,477.23	1,384.43	92.80	15.919	
15,500.00	7,289.00	6,684.00	6,681.41	97.22	20.00	61.94	-1,231.24	7,488.12	1,534.44	1,443.16	91.28	16.810	
15,600.00	7,289.00	6,684.00	6,681.41	98.31	20.00	61.94	-1,231.24	7,488.12	1,595.88	1,506.15	89.73	17.785	
15,700.00	7,289.00	6,684.00	6,681.41	99.39	20.00	61.94	-1,231.24	7,488.12	1,661.06	1,572.89	88.17	18.839	
15,800.00	7,289.00	6,684.00	6,681.41	100.48	20.00	61.94	-1,231.24	7,488.12	1,729.58	1,642.94	86.64	19.964	
15,900.00	7,289.00	6,684.00	6,681.41	101.56	20.00	61.94	-1,231.24	7,488.12	1,801.04	1,715.90	85.14	21.154	
16,000.00	7,289.00	6,684.00	6,681.41	102.65	20.00	61.94	-1,231.24	7,488.12	1,875.12	1,791.42	83.70	22.403	
16,100.00	7,289.00	6,684.00	6,681.41	103.74	20.00	61.94	-1,231.24	7,488.12	1,951.51	1,869.19	82.32	23.707	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W16_GOVERNMENT AB FEDERAL #014_1540854 - MWD - MWD												Offset Site Error:	0.00 usft
Survey Program: 155-OWSG MWD Rev 5												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
12,600.00	7,289.00	6,555.00	6,552.38	66.34	19.42	52.75	-1,085.27	6,466.59	1,522.91	1,461.46	61.46	24.781	
12,700.00	7,289.00	6,555.00	6,552.38	67.38	19.42	52.75	-1,085.27	6,466.59	1,461.39	1,398.11	63.28	23.093	
12,800.00	7,289.00	6,555.00	6,552.38	68.42	19.42	52.75	-1,085.27	6,466.59	1,404.30	1,339.09	65.21	21.534	
12,900.00	7,289.00	6,555.00	6,552.38	69.47	19.42	52.75	-1,085.27	6,466.59	1,352.20	1,284.98	67.22	20.116	
13,000.00	7,289.00	6,555.00	6,552.38	70.51	19.42	52.75	-1,085.27	6,466.59	1,305.70	1,236.42	69.28	18.848	
13,100.00	7,289.00	6,555.00	6,552.38	71.56	19.42	52.75	-1,085.27	6,466.59	1,265.40	1,194.07	71.33	17.740	
13,200.00	7,289.00	6,555.00	6,552.38	72.61	19.42	52.75	-1,085.27	6,466.59	1,231.93	1,158.59	73.33	16.799	
13,300.00	7,289.00	6,555.00	6,552.38	73.67	19.42	52.75	-1,085.27	6,466.59	1,205.84	1,130.62	75.22	16.031	
13,400.00	7,289.00	6,555.00	6,552.38	74.72	19.42	52.75	-1,085.27	6,466.59	1,187.62	1,110.70	76.92	15.439	
13,500.00	7,289.00	6,555.00	6,552.38	75.78	19.42	52.75	-1,085.27	6,466.59	1,177.64	1,099.26	78.38	15.024	
13,568.02	7,289.00	6,555.00	6,552.38	76.50	19.42	52.75	-1,085.27	6,466.59	1,175.67	1,096.46	79.21	14.842	CC, ES
13,600.00	7,289.00	6,555.00	6,552.38	76.84	19.42	52.75	-1,085.27	6,466.59	1,176.11	1,096.56	79.55	14.785	
13,700.00	7,289.00	6,555.00	6,552.38	77.90	19.42	52.75	-1,085.27	6,466.59	1,183.06	1,102.67	80.39	14.717	SF
13,800.00	7,289.00	6,555.00	6,552.38	78.96	19.42	52.75	-1,085.27	6,466.59	1,198.34	1,117.46	80.88	14.816	
13,900.00	7,289.00	6,555.00	6,552.38	80.02	19.42	52.75	-1,085.27	6,466.59	1,221.65	1,140.60	81.05	15.074	
14,000.00	7,289.00	6,555.00	6,552.38	81.09	19.42	52.75	-1,085.27	6,466.59	1,252.52	1,171.62	80.91	15.481	
14,100.00	7,289.00	6,555.00	6,552.38	82.15	19.42	52.75	-1,085.27	6,466.59	1,290.43	1,209.93	80.50	16.029	
14,200.00	7,289.00	6,555.00	6,552.38	83.22	19.42	52.75	-1,085.27	6,466.59	1,334.77	1,254.88	79.89	16.707	
14,300.00	7,289.00	6,555.00	6,552.38	84.29	19.42	52.75	-1,085.27	6,466.59	1,384.92	1,305.81	79.12	17.505	
14,400.00	7,289.00	6,555.00	6,552.38	85.36	19.42	52.75	-1,085.27	6,466.59	1,440.28	1,362.06	78.22	18.412	
14,500.00	7,289.00	6,555.00	6,552.38	86.44	19.42	52.75	-1,085.27	6,466.59	1,500.27	1,423.01	77.26	19.419	
14,600.00	7,289.00	6,555.00	6,552.38	87.51	19.42	52.75	-1,085.27	6,466.59	1,564.35	1,488.10	76.25	20.515	
14,700.00	7,289.00	6,555.00	6,552.38	88.58	19.42	52.75	-1,085.27	6,466.59	1,632.05	1,556.82	75.23	21.693	
14,800.00	7,289.00	6,555.00	6,552.38	89.66	19.42	52.75	-1,085.27	6,466.59	1,702.94	1,628.72	74.22	22.944	
14,900.00	7,289.00	6,555.00	6,552.38	90.74	19.42	52.75	-1,085.27	6,466.59	1,776.62	1,703.39	73.23	24.261	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W17_GOVERNMENT AB FEDERAL #013_1540920 - MWD - MWD												Offset Site Error:	0.00 usft
Survey Program: 267-OWSG MWD Rev 5												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
15,900.00	7,289.00	6,652.00	6,649.47	101.56	25.17	57.58	-1,076.13	10,325.59	1,900.36	1,821.25	79.11	24.022	
16,000.00	7,289.00	6,652.00	6,649.47	102.65	25.17	57.58	-1,076.13	10,325.59	1,820.98	1,739.41	81.56	22.326	
16,100.00	7,289.00	6,652.00	6,649.47	103.74	25.17	57.58	-1,076.13	10,325.59	1,743.72	1,659.51	84.21	20.707	
16,200.00	7,289.00	6,652.00	6,649.47	104.83	25.17	57.58	-1,076.13	10,325.59	1,668.88	1,581.83	87.05	19.172	
16,300.00	7,289.00	6,652.00	6,649.47	105.92	25.17	57.58	-1,076.13	10,325.59	1,596.80	1,506.72	90.08	17.726	
16,400.00	7,289.00	6,652.00	6,649.47	107.01	25.17	57.58	-1,076.13	10,325.59	1,527.87	1,434.56	93.31	16.374	
16,500.00	7,289.00	6,652.00	6,649.47	108.10	25.17	57.58	-1,076.13	10,325.59	1,462.53	1,365.82	96.70	15.124	
16,600.00	7,289.00	6,652.00	6,649.47	109.19	25.17	57.58	-1,076.13	10,325.59	1,401.28	1,301.04	100.24	13.979	
16,700.00	7,289.00	6,652.00	6,649.47	110.28	25.17	57.58	-1,076.13	10,325.59	1,344.69	1,240.82	103.87	12.946	
16,800.00	7,289.00	6,652.00	6,649.47	111.37	25.17	57.58	-1,076.13	10,325.59	1,293.37	1,185.85	107.52	12.029	
16,900.00	7,289.00	6,652.00	6,649.47	112.46	25.17	57.58	-1,076.13	10,325.59	1,247.96	1,136.85	111.11	11.232	
17,000.00	7,289.00	6,652.00	6,649.47	113.56	25.17	57.58	-1,076.13	10,325.59	1,209.13	1,094.61	114.52	10.558	
17,100.00	7,289.00	6,652.00	6,649.47	114.65	25.17	57.58	-1,076.13	10,325.59	1,177.54	1,059.91	117.63	10.010	
17,200.00	7,289.00	6,652.00	6,649.47	115.75	25.17	57.58	-1,076.13	10,325.59	1,153.78	1,033.47	120.31	9.590	
17,300.00	7,289.00	6,652.00	6,649.47	116.84	25.17	57.58	-1,076.13	10,325.59	1,138.34	1,015.91	122.43	9.298	
17,400.00	7,289.00	6,652.00	6,649.47	117.94	25.17	57.58	-1,076.13	10,325.59	1,131.56	1,007.66	123.90	9.133	
17,426.97	7,289.00	6,652.00	6,649.47	118.23	25.17	57.58	-1,076.13	10,325.59	1,131.24	1,007.07	124.17	9.110 CC, ES	
17,500.00	7,289.00	6,652.00	6,649.47	119.03	25.17	57.58	-1,076.13	10,325.59	1,133.59	1,008.94	124.65	9.094 SF	
17,600.00	7,289.00	6,652.00	6,649.47	120.13	25.17	57.58	-1,076.13	10,325.59	1,144.39	1,019.71	124.69	9.178	
17,700.00	7,289.00	6,652.00	6,649.47	121.23	25.17	57.58	-1,076.13	10,325.59	1,163.72	1,039.67	124.04	9.381	
17,800.00	7,289.00	6,652.00	6,649.47	122.33	25.17	57.58	-1,076.13	10,325.59	1,191.15	1,068.34	122.81	9.699	
17,900.00	7,289.00	6,652.00	6,649.47	123.42	25.17	57.58	-1,076.13	10,325.59	1,226.15	1,105.06	121.09	10.126	
18,000.00	7,289.00	6,652.00	6,649.47	124.52	25.17	57.58	-1,076.13	10,325.59	1,268.09	1,149.09	119.00	10.656	
18,100.00	7,289.00	6,652.00	6,649.47	125.62	25.17	57.58	-1,076.13	10,325.59	1,316.31	1,199.64	116.66	11.283	
18,159.20	7,289.00	6,652.00	6,649.47	126.27	25.17	57.58	-1,076.13	10,325.59	1,347.53	1,232.33	115.20	11.697	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Offset Design: Koala 9 Fed Com Offsets - W18_GOVERNMENT AB FEDERAL #012_1541049 - MWD - MWD													Offset Site Error: 0.00 usft
Survey Program: 144-OWSG MWD Rev 5													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
15,000.00	7,289.00	6,784.00	6,661.38	91.82	24.55	55.97	-1,018.62	9,249.19	1,725.48	1,653.79	71.69	24.069	
15,100.00	7,289.00	6,784.00	6,661.38	92.90	24.55	55.97	-1,018.62	9,249.19	1,648.35	1,574.12	74.23	22.206	
15,200.00	7,289.00	6,784.00	6,661.38	93.98	24.55	55.97	-1,018.62	9,249.19	1,573.81	1,496.80	77.00	20.439	
15,300.00	7,289.00	6,784.00	6,661.38	95.06	24.55	55.97	-1,018.62	9,249.19	1,502.22	1,422.21	80.00	18.777	
15,400.00	7,289.00	6,784.00	6,661.38	96.14	24.55	55.97	-1,018.62	9,249.19	1,434.03	1,350.80	83.23	17.229	
15,500.00	7,289.00	6,784.00	6,661.38	97.22	24.55	55.97	-1,018.62	9,249.19	1,369.76	1,283.08	86.68	15.802	
15,600.00	7,289.00	6,784.00	6,661.38	98.31	24.55	55.97	-1,018.62	9,249.19	1,309.98	1,219.66	90.31	14.505	
15,700.00	7,289.00	6,784.00	6,661.38	99.39	24.55	55.97	-1,018.62	9,249.19	1,255.32	1,161.24	94.08	13.344	
15,800.00	7,289.00	6,784.00	6,661.38	100.48	24.55	55.97	-1,018.62	9,249.19	1,206.49	1,108.60	97.90	12.324	
15,900.00	7,289.00	6,784.00	6,661.38	101.56	24.55	55.97	-1,018.62	9,249.19	1,164.22	1,062.56	101.66	11.452	
16,000.00	7,289.00	6,784.00	6,661.38	102.65	24.55	55.97	-1,018.62	9,249.19	1,129.25	1,024.01	105.24	10.730	
16,100.00	7,289.00	6,784.00	6,661.38	103.74	24.55	55.97	-1,018.62	9,249.19	1,102.27	993.79	108.48	10.161	
16,200.00	7,289.00	6,784.00	6,661.38	104.83	24.55	55.97	-1,018.62	9,249.19	1,083.88	972.66	111.22	9.745	
16,300.00	7,289.00	6,784.00	6,661.38	105.92	24.55	55.97	-1,018.62	9,249.19	1,074.52	961.19	113.33	9.481	
16,351.03	7,289.00	6,784.00	6,661.38	106.47	24.55	55.97	-1,018.62	9,249.19	1,073.31	959.18	114.13	9.405 CC, ES	
16,400.00	7,289.00	6,784.00	6,661.38	107.01	24.55	55.97	-1,018.62	9,249.19	1,074.42	959.72	114.70	9.367 SF	
16,500.00	7,289.00	6,784.00	6,661.38	108.10	24.55	55.97	-1,018.62	9,249.19	1,083.60	968.30	115.29	9.399	
16,600.00	7,289.00	6,784.00	6,661.38	109.19	24.55	55.97	-1,018.62	9,249.19	1,101.81	986.68	115.13	9.571	
16,700.00	7,289.00	6,784.00	6,661.38	110.28	24.55	55.97	-1,018.62	9,249.19	1,128.61	1,014.34	114.27	9.876	
16,800.00	7,289.00	6,784.00	6,661.38	111.37	24.55	55.97	-1,018.62	9,249.19	1,163.43	1,050.57	112.85	10.309	
16,900.00	7,289.00	6,784.00	6,661.38	112.46	24.55	55.97	-1,018.62	9,249.19	1,205.55	1,094.56	110.99	10.861	
17,000.00	7,289.00	6,784.00	6,661.38	113.56	24.55	55.97	-1,018.62	9,249.19	1,254.25	1,145.43	108.83	11.525	
17,100.00	7,289.00	6,784.00	6,661.38	114.65	24.55	55.97	-1,018.62	9,249.19	1,308.80	1,202.33	106.47	12.293	
17,200.00	7,289.00	6,784.00	6,661.38	115.75	24.55	55.97	-1,018.62	9,249.19	1,368.48	1,264.47	104.01	13.157	
17,300.00	7,289.00	6,784.00	6,661.38	116.84	24.55	55.97	-1,018.62	9,249.19	1,432.67	1,331.12	101.54	14.109	
17,400.00	7,289.00	6,784.00	6,661.38	117.94	24.55	55.97	-1,018.62	9,249.19	1,500.78	1,401.67	99.11	15.143	
17,500.00	7,289.00	6,784.00	6,661.38	119.03	24.55	55.97	-1,018.62	9,249.19	1,572.30	1,475.54	96.76	16.250	
17,600.00	7,289.00	6,784.00	6,661.38	120.13	24.55	55.97	-1,018.62	9,249.19	1,646.79	1,552.28	94.51	17.425	
17,700.00	7,289.00	6,784.00	6,661.38	121.23	24.55	55.97	-1,018.62	9,249.19	1,723.86	1,631.49	92.37	18.662	
17,800.00	7,289.00	6,784.00	6,661.38	122.33	24.55	55.97	-1,018.62	9,249.19	1,803.19	1,712.83	90.36	19.955	
17,900.00	7,289.00	6,784.00	6,661.38	123.42	24.55	55.97	-1,018.62	9,249.19	1,884.49	1,796.01	88.48	21.298	
18,000.00	7,289.00	6,784.00	6,661.38	124.52	24.55	55.97	-1,018.62	9,249.19	1,967.51	1,880.78	86.72	22.687	
18,100.00	7,289.00	6,784.00	6,661.38	125.62	24.55	55.97	-1,018.62	9,249.19	2,052.04	1,966.96	85.09	24.117	
18,159.20	7,289.00	6,784.00	6,661.38	126.27	24.55	55.97	-1,018.62	9,249.19	2,102.72	2,018.55	84.17	24.982	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation




Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Reference Depths are relative to 3288+30 @ 3318.00usft
 Offset Depths are relative to Offset Datum
 Central Meridian is -104.33333334

Coordinates are relative to: (A05) Koala 9 Fed Com 121H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.08°



CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation




Anticollision Report

Company:	Colgate Energy	Local Co-ordinate Reference:	Well (A05) Koala 9 Fed Com 121H
Project:	(Permit) Eddy County, NM (83-NME)	TVD Reference:	3288+30 @ 3318.00usft
Reference Site:	(Permit) Koala 9 Fed Com	MD Reference:	3288+30 @ 3318.00usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	(A05) Koala 9 Fed Com 121H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Permit	Database:	EDM 5000.14 Single User Db
Reference Design:	APD-Rev00	Offset TVD Reference:	Offset Datum

Reference Depths are relative to 3288+30 @ 3318.00usft
 Offset Depths are relative to Offset Datum
 Central Meridian is -104.33333334

Coordinates are relative to: (A05) Koala 9 Fed Com 121H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.08°

Separation Factor Plot



LEGEND

(A04) Koala 9 Fed Com 132H, Permit, APD-Rev00 V0	(B02) Koala 9 Fed Com 204H, Permit, APD-Rev00 V0	W05_FEDERAL V#002_1526702, Inc Only, Inc Only V0
(A02) Koala 9 Fed Com 203H, Permit, APD-Rev00 V0	(A03) Koala 9 Fed Com 133H, Permit, APD-Rev00 V0	W17_GOVERNMENT AB FEDERAL #013_1540920, MWD, MWD V0
(B03) Koala 9 Fed Com 133H, Permit, APD-Rev00 V0	(B04) Koala 9 Fed Com 134H, Permit, APD-Rev00 V0	W15_GOVERNMENT AB FEDERAL #011_1540853, MWD, MWD V0
(A01) Koala 9 Fed Com 201H, Permit, APD-Rev00 V0	(B07) Koala 9 Fed Com 113H, Permit, APD-Rev00 V0	W13_GOVERNMENT AB #008_1527863, Inc Only, Inc Only V0
(B08) Koala 9 Fed Com 114H, Permit, APD-Rev00 V0	W02_GOVERNMENT AB COM #001_1524032, Inc Only, Inc Only V0	W16_GOVERNMENT AB FEDERAL #014_1540854, MWD, MWD V0
(A06) Koala 9 Fed Com 123H, Permit, APD-Rev00 V0	W08_FEDERAL VCOM #004_1535127, Inc Only, Inc Only V0	W18_GOVERNMENT AB FEDERAL #012_1541049, MWD, MWD V0
(B01) Koala 9 Fed Com 203H, Permit, APD-Rev00 V0	W04_FEDERAL V#001_1526451, Inc Only, Inc Only V0	W10_GOVERNMENT AB #003_1521774, Inc Only, Inc Only V0
(A08) Koala 9 Fed Com 112H, Permit, APD-Rev00 V0	W11_GOVERNMENT AB #006_1527846, Inc Only, Inc Only V0	W09_GOVERNMENT AB #002_1521480, Inc Only, Inc Only V0
(B05) Koala 9 Fed Com 123H, Permit, APD-Rev00 V0	W06_FEDERAL V#003_1526987, Depth Only, Depth Only V0	W07_PRE-ONGARD WELL #001_1527282, Depth Only, Depth Only V0
(B06) Koala 9 Fed Com 124H, Permit, APD-Rev00 V0	W12_GOVERNMENT AB #007_1527847, Inc Only, Inc Only V0	
(A07) Koala 9 Fed Com 111H, Permit, APD-Rev00 V0	W14_GOVERNMENT AB #009_1527964, MWD, Inc, MWD, Inc V0	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Permian Resources - Koala 9 Fed Com 121H

1. Geologic Formations

Formation	Elevation	TVD	Target
Rustler	-3077	241	No
Top of Salt	-2936	382	No
Capitan	NP	NP	No
Tansill	-2550	768	No
Yates	-2475	843	No
Seven Rivers	-2100	1218	No
Queen	-1509	1809	No
Grayburg	-1300	2018	No
San Andres	-900	2418	No
Delaware Mountain Group	-325	2993	No
Bone Spring Lime	1250	4568	No
1st Bone Spring Sand	2800	6118	No
2nd Bone Spring Sand	3825	7143	Yes
3rd Bone Spring Sand	NP	NP	No

2. Blowout Prevention

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	x	Tested to:
12.25	13-5/8"	5M	Annular	x	2500 psi
			Blind Ram	x	5000 psi
			Pipe Ram	x	
			Double Ram		
			Other*		
8.75	13-5/8"	5M	Annular	x	2500 psi
			Blind Ram	x	5000 psi
			Pipe Ram	x	
			Double Ram		
			Other*		

Equipment: BOPE with working pressure ratings in excess of anticipated maximum surface pressure will be utilized for well control from drill out of surface casing to TMD. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. All BOPE connections shall be flanged, welded or clamped. All choke lines shall be straight unless targeted with running tees or tee blocks are used, and choke lines shall be anchored to prevent whip and reduce vibrations. All valves in the choke line & the choke manifold shall be full opening as to not cause restrictions and to allow for straight fluid paths to minimize potential erosion. All gauges utilized in the well control system shall be of a type designed for drilling fluid service. A top drive inside BOP valve will be utilized at all times. Subs equipped with full opening valves sized to fit the drill pipe and collars will be available on the rig floor in the open position. The key to operate said valve equipped subs will be on the rig floor at all times. The accumulator system will have sufficient capacity to open the HCR and close all three sets of rams plus the annular preventer while retaining at least 300 psi above precharge on the closing manifold (accumulator system shall be capable of doing so without using the closing unit pumps). The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity, and the fluid level will be maintained at the manufacturer's recommended level. Prior to connecting the closing unit to the BOP stack, an accumulator precharge pressure test shall be performed to ensure the precharge pressure is within 100 psi of the desired precharge pressure (only nitrogen gas will be used to precharge). Two independent power sources will be made available at all times to power the closing unit pumps so that the pumps can automatically start when the closing valve manifold pressure has decreased to the preset level. Closing unit pumps will be sized to allow opening of HCR and closing of annular preventer on 5" drill pipe achieving at least 200 psi above precharge pressure with the accumulator system isolated from service in less than two minutes. A valve shall be installed in the closing line as close to the annular preventer as possible to act as a locking device; the valve shall be maintained in the open position and shall be closed only when the power source for the accumulator system is inoperative. Remote controls capable of opening and closing all preventers & the HCR shall be readily accessible to the driller; master controls with the same capability will be operable at the accumulator. The wellhead will be a multibowl speed head allowing for hangoff of intermediate casing & isolation of the 133/8 x 95/8 annulus without breaking the connection between the BOP & wellhead to install an additional casing head. A wear bushing will be installed & inspected frequently to guard against internal wear to wellhead. VBRs (variablebore rams) will be run in upper rambody of BOP stack to provide redundancy to annular preventer while RIH w/ production casing;

Requesting Variance? YES

Variance request: Flex hose and offline cement variances, see attachments in section 8.

Testing Procedure: The BOP test shall be performed before drilling out of the surface casing shoe and will occur at a minimum: a. when initially installed b. whenever any seal subject to test pressure is broken c. following related repairs d. at 30 day intervals e. checked daily as to mechanical operating conditions. The ram type preventer(s) will be tested using a test plug to 250 psi (low) and 5,000 psi (high) (casinghead WP) with a test plug upon its installation onto the 13 surface casing. If a test plug is not used, the ram type preventer(s) shall be tested to 70% of the minimum internal yield pressure of the casing. The annular type preventer(s) shall be tested to 3500 psi. Pressure will be maintained for at least 10 minutes or until provisions of the test are met, whichever is longer. A Sundry Notice (Form 3160 5), along with a copy of the BOP test report, shall be submitted to the local BLM office within 5 working days following the test. If the bleed line is connected into the buffer tank (header), all BOP equipment including the buffer tank and associated valves will be rated at the required BOP pressure. The BLM office will be provided with a minimum of four (4) hours notice of BOP testing to allow witnessing. The BOP Configuration, choke manifold layout, and accumulator system, will be in compliance with Onshore Order 2 for a 5,000 psi system. A remote accumulator and a multi-bowl system will be used, please see attachment in section 8 for multi-bowl procedure. Pressures, capacities, and specific placement and use of the manual and/or hydraulic controls, accumulator controls, bleed lines, etc., will be identified at the time of the BLM 'witnessed BOP test. Any remote controls will be capable of both opening and closing all preventers and shall be readily accessible.

Choke Diagram Attachemnt: 5 M Choe Manifold

BOP Diagram Attachment: BOP Schematic

3. Casing

String	Hole Size	Casing Size	Top	Bottom	Top TVD	Bottom TVD	Length	Grade	Weight	Connection	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
Surface	17.5	13.375	0	266	0	266	266	J55	54.5	BTC	8.60	3.42	Dry	7.94	Dry	7.45
Intermediate	12.25	9.625	0	2943	0	2943	2943	J55	36	BTC	3.13	1.72	Dry	3.10	Dry	2.74
Production	8.75	5.5	0	7620	0	7289	7620	P110RY	17	GeoConn	1.97	2.06	Dry	2.44	Dry	2.44
Production	7.875	5.5	7620	18159	7289	7289	10539	P110RY	17	GeoConn	1.97	2.06	Dry	2.44	Dry	2.44
BLM Min Safety Factor											1.125	1		1.6		1.6

Non API casing spec sheets and casing design assumptions attached.

4. Cement

String	Lead/Tail	Top MD	Bottom MD	Quantity (sx)	Yield	Density	Cu Ft	Excess %	Cement Type	Additives
Surface	Tail	0	266	210	1.34	14.8	280	50%	Class C	Accelerator
Intermediate	Lead	0	2350	520	2.08	12.7	1080	50%	Class C	Salt, Extender, and LCM
Intermediate	Tail	2350	2943	210	1.34	14.8	280	50%	Class C	Accelerator
Production	Lead	2443	6720	620	2.41	11.5	1480	40%	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder
Production	Tail	6720	18159	1490	1.73	12.5	2570	25%	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder

5. Circulating Medium

Mud System Type: Closed

Will an air or gas system be used: No

Describe what will be on location to control well or mitigate other conditions: Sufficient quantities of mud materials will be on the well site at all times for the purpose of assuring well control and maintaining wellbore integrity. Surface interval will employ fresh water mud. The intermediate hole will utilize a saturated brine fluid to inhibit salt washout. The production hole will employ brine based and oil base fluid to inhibit formation reactivity and of the appropriate density to maintain well control.

Describe the mud monitoring system utilized: Centrifuge separation system. Open tank monitoring with EDR will be used for drilling fluids and return volumes. Open tank monitoring will be used for cement and cuttings return volumes. Mud properties will be monitored at least every 24 hours using industry accepted mud check practices.

Cuttings Volume: 8160 Cu Ft

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight	Max Weight
0	266	Water Based Mud	8.6	9.5
266	2943	Salt Saturated	10	10
2943	7620	Brine	9	10
7620	18159	OBM	9	10

6. Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will utilize MWD/LWD (Gamma Ray logging) from intermediate hole to TD of the well.

List of open and cased hole logs run in the well:

DIRECTIONAL SURVEY, GAMMA RAY LOG,

Coring operation description for the well:

N/A

7. Pressure

Anticipated Bottom Hole Pressure	3800	psi
Anticipated Surface Pressure	2186.7	psi
Anticipated Bottom Hole Temperature	131	°F
Anticipated Abnormal pressure, temp, or geo hazards	No	

8. Other Information


Well Plan and AC Report: attached

Batching Drilling Procedure: attached


WBD: attached


Flex Hose Specs: attached

Offline Cementing Procedure Attached:



5,000 psi BOP Schematic



5M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



ContiTech

CONTITECH RUBBER Industrial Kft.	No:QC-DB- 210/ 2014
	Page: 9 / 113

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE		CERT. N°: 504	
PURCHASER: ContiTech Oil & Marine Corp.		P.O. N°: 4500408659	
CONTITECH RUBBER order N°: 538236	HOSE TYPE: 3" ID	Choke and Kill Hose	
HOSE SERIAL N°: 67255	NOMINAL / ACTUAL LENGTH: 10,67 m / 10,77 m		
W.P. 68,9 MPa 10000 psi	T.P. 103,4 MPa 15000 psi	Duration: 60 min.	
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>			
↑ 10 mm = 10 Min. → 10 mm = 20 MPa			
COUPLINGS Type	Serial N°	Quality	Heat N°
3" coupling with	9251 9254	AISI 4130	A0579N
4 1/16" 10K API b.w. Flange-end		AISI 4130	035608
Not Designed For Well Testing		API Spec 16 C	
All metal parts are flawless		Temperature rate:"B"	
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.			
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated, inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.			
COUNTRY OF ORIGIN HUNGARY/EU			
Date:	Inspector	Quality Control	
20. March 2014.		ContiTech Rubber Industrial Kft. Quality Control Unit  	

ContiTech Rubber Industrial Kft. : Budapest 110, H-1128 Szigetud H 4/OT P.O.Box 322 Szigetud, Hungary
 Phone: +36 82 584 720 / Fax: +36 82 584 726 / e-mail: info@busd.cocontech.hu / sales@busd.cocontech.hu / www.cocontech.hu
 The Court of Company Law of Hungary (Registry Court No: Cg/95-09-002503 / EU VAT No: HU11537208
 BATA Kft. Gyomaiút 21., Budapest 1142/0105-2083000)

No. 501, 504, 505

Page: 111





CONTITECH RUBBER
Industrial Kft.

No:QC-DB- 210/ 2014


Page: 15 / 113

ContiTech

Hose Data Sheet

CRI Order No.	538236
Customer	ContiTech Oil & Marine Corp.
Customer Order No.	4500409659
Item No.	1
Hose Type	Flexible Hose
Standard	API SPEC 16 C
Inside dia in inches	3
Length	35 ft
Type of coupling one end	FLANGE 4.1/16" 10K API SPEC 6A TYPE 6BX FLANGE C/W BX155 R.GR.SOUR
Type of coupling other end	FLANGE 4.1/16" 10K API SPEC 6A TYPE 6BX FLANGE C/W BX155 R.GR.SOUR
H2S service NACE MR0175	Yes
Working Pressure	10 000 psi
Design Pressure	10 000 psi
Test Pressure	15 000 psi
Safety Factor	2,25
Marking	USUAL PHOENIX
Cover	NOT FIRE RESISTANT
Outside protection	St. steel outer wrap
Internal stripwound tube	No
Lining	OIL + GAS RESISTANT SOUR
Safety clamp	No
Lifting collar	No
Element C	No
Safety chain	No
Safety wire rope	No
Max. design temperature [°C]	100
Min. design temperature [°C]	-20
Min. Bend Radius operating [m]	0,90
Min. Bend Radius storage [m]	0,90
Electrical continuity	The Hose is electrically continuous
Type of packing	WOODEN CRATE ISPM-15

Printed: TIRETECH2\CSantosG - 2014.03.10 15:22:17



INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.

ALL DIMENSIONS APPROXIMATE

CACTUS WELLHEAD LLC		CENTENNIAL RESOURCE DEVELOPMENT LEE CO, NM	
20" x 13-3/8" x 9-5/8" x 5-1/2" 10M MBU-3T-CFL-R-DBLO System With 13-5/8" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head, 20" Landing Ring & Pin Down Mandrel Casing Hangers	DRAWN	DLE	10JUN20
	APPRV		
DRAWING NO.		HBE0000338	

Permian Resources Casing Design Criteria

A sundry will be requested if any lesser grade or different size casing is substituted. All casing will be centralized as specified in On Shore Order II. Casing will be tested as specified in On Shore Order II.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Permian Resources

Multi-Well Pad Batch Drilling Procedure

Surface Casing - PR intends to Batch set all 13-3/8" casing to a depth approved in the APD. 17-1/2" Surface Holes will be batch drilled by a rig. Appropriate notifications will be made prior to spudding the well, running and cementing casing and prior to skidding to the rig to the next well on pad.

1. Drill 17-1/2" Surface hole to Approved Depth with Rig and perform wellbore cleanup cycles. Trip out and rack back drilling BHA.
2. Run and land 13-3/8" 54.5# J55 BTC casing see Illustration 1-1 Below to depth approved in APD.
3. Set packoff and test to 5k psi
4. Offline Cement
5. Install wellhead with pressure gauge and nightcap. Nightcap is shown on final wellhead Stack up Illustration #2-2.
6. Skid Rig to adjacent well to drill Surface hole.
7. Surface casing test will be performed by the rig in order to allow ample time for Cement to develop 500psi compressive strength. Casing test to 0.22 psi/ft or 1500 psi whichever is




Illustration 1-1

Intermediate Casing – PR intends to Batch set all intermediate casing strings to a depth approved in the APD, typically set into Lamar. 12-1/4" Intermediate Holes will be batch drilled by the rig. Appropriate notifications will be made prior Testing BOPE, and prior to running/cementing all casing strings.

1. Rig will remove the nightcap and install and test BOPE.
2. Test Surface casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) - not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
3. Install wear bushing then drill out 13-3/8" shoe-track plus 20' and conduct FIT to minimum of the MW equivalent anticipated to control the formation pressure to the next casing point.
4. Drill Intermediate hole to approved casing point. Trip out of hole with BHA to run Casing.
5. Remove wear bushing then run and land Intermediate Casing with mandrel hanger in wellhead.
6. Cement casing to surface with floats holding.
7. Washout stack then run wash tool in wellhead and wash hanger and pack-off setting area.
8. Install pack-off and test void to 5,000 psi for 15 minutes. Nightcap shown on final wellhead stack up illustration 2-2 on page 3.
9. Test casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) - not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
10. Install nightcap – skid rig to adjacent well to drill Intermediate hole.





Illustration 2-2

Production Casing – PR intends to Batch set all Production casings with Rig. Appropriate notifications will be made prior Testing BOPE, and prior to running/cementing all casing strings.


1. Big Rig will remove the nightcap and install and test BOPE.
2. Install wear bushing then drill Intermediate shoe-track plus 20' and conduct FIT to minimum MW equivalent to control the formation pressure to TD of well.
3. Drill Vertical hole to KOP – Trip out for Curve BHA.
4. Drill Curve, landing in production interval – Trip for Lateral BHA.
5. Drill Lateral / Production hole to Permitted BHL, perform cleanup cycles and trip out to run 5 1/2" Production Casing.
6. Remove wear bushing then run 5-1/2" production casing to TD landing casing mandrel in wellhead.
7. Cement 5-1/2" Production string with floats holding.
8. Run in with wash tool and wash wellhead area – install pack-off and test void to 5,000psi for 15 minutes.
9. Install BPV in 5-1/2" mandrel hanger – Nipple down BOPE and install nightcap.
10. Test nightcap void to 5,000psi for 30 minutes per illustration 2-2
11. Skid rig to adjacent well on pad to drill production hole.

Permian Resources Offline Cementing Procedure 13-3/8" & 9-5/8" Casing


1. Drill hole to Total Depth with Rig and perform wellbore cleanup cycles.
2. Run and casing to Depth.
3. Land casing with mandrel.
4. Circulate 1.5 csg capacity.
5. Flow test – Confirm well is static and floats are holding.
6. Set Annular packoff and pressure test. Test to 5k.
7. Nipple down BOP and install cap flange.
8. Skid rig to next well on pad
9. Remove cap flange (confirm well is static before removal)
 - a) If well is not static use the casing outlet valves to kill well
 - b) Drillers method will be used in well control event
 - c) High pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - d) Kill mud will be circulated once influx is circulated out of hole
 - e) Confirm well is static and remove cap flange to start offline cement operations
10. Install offline cement tool.
11. Rig up cementers.
12. Circulate bottoms up with cement truck
13. Commence planned cement job, take returns through the annulus wellhead valve
14. After plug is bumped confirm floats hold and well is static
15. Rig down cementers and equipment
16. Install night cap with pressure gauge to monitor.




9 5/8" Intermediate




Run 9-5/8" Casing
Land Casing on 9-5/8" Mandrel Hanger
Cement 9-5/8" Casing
Retrieve Running Tool




Run 13-5/8" Packoff
Test Upper and Lower Seals
Engage Lockring
Retrieve Running Tool



Metal One Corp. 	GEOCONN-SC Pipe: SeAH P110RY 95%PBW (SMYS110ksi) *1 Coupling: P110RY (SMYS110ksi) Connection Data Sheet	Page Date Rev.	MAI GC 5.5 17 SeAH P110RY 95%RBW+SC-Cplg6.050 P110RY 3-Feb-21 0
---	--	----------------------	--

GEOCONN-SC



Geometry		Imperial		S.I.	
Pipe Body					
Grade *1	P110RY	-	P110RY	-	
SMYS	110	ksi	110	ksi	
Pipe OD (D)	5.500	in	139.70	mm	
Weight	17.00	lb/ft	25.33	kg/m	
Wall Thickness (t)	0.304	in	7.72	mm	
Pipe ID (d)	4.892	in	124.26	mm	
Drift Dia.	4.767	in	121.08	mm	
Connection					
Coupling SMYS	110	ksi	110	ksi	
SC-Coupling OD (Wsc1)	6.050	in	153.67	mm	
Coupling Length (NL)	8.350	in	212.09	mm	
Make up Loss	4.125	in	104.78	mm	
Pipe Critical Area	4.96	in ²	3,202	mm ²	
Box Critical Area	6.10	in ²	3,937	mm ²	
Thread Taper	1 / 16 (3/4" per ft)				
Number of Threads	5 TPI				

Performance		Imperial		S.I.	
Performance Properties for Pipe Body					
S.M.Y.S. *1	546	ksi	2,428	MPa	
M.I.Y.P. *1	11,550	psi	79.66	MPa	
Collapse Strength *1	7,480	psi	51.59	MPa	
Note S.M.Y.S.= Specified Minimum YIELD Strength of Pipe body M.I.Y.P. = Minimum Internal Yield Pressure of Pipe body *1: SeAH P110RY 95%RBW: SMYS110ksi, MIYP11,550psi					
Performance Properties for Connection					
Min. Connection Joint Strength	100%		of S.M.Y.S.		
Min. Compression Yield	100%		of S.M.Y.S.		
Internal Pressure	100%		of M.I.Y.P.		
External Pressure	100%		of Collapse Strength		
Max. DLS (deg. /100ft)			>90		

Recommended Torque				
Min.	10,800	ft-lb	14,600	N-m
Opti.	12,000	ft-lb	16,200	N-m
Max.	13,200	ft-lb	17,800	N-m
Operational Max.	15,600	ft-lb	21,100	N-m

Note : Operational Max. torque can be applied for high torque application

Legal Notice

The use of this information is at the reader/user's risk and no warranty is implied or expressed by Metal One Corporation or its parents, subsidiaries or affiliates (herein collectively referred to as "Metal One") with respect to the use of information contained herein. The information provided on this Connection Data Sheet is for informational purposes only, and was prepared by reference to engineering information that is specific to the subject products, without regard to safety-related factors, all of which are the sole responsibility of the operators and users of the subject connectors. Metal One assumes no responsibility for any errors with respect to this information.

Statements regarding the suitability of products for certain types of applications are based on Metal One's knowledge of typical requirements that are often placed on Metal One products in standard well configurations. Such statements are not binding statements about the suitability of products for a particular application. It is the customer's responsibility to validate that a particular product with the properties described in the product specification is suitable for use in a particular application.

The products described in this Connection Data Sheet are not recommended for use in deep water offshore applications. For more information, please refer to http://www.mto.co.jp/mo-con/Images/top/WebsiteTerms_Active_20333287_1.pdf the contents of which are incorporated by reference into this Connection Data Sheet.

Permian Resources

Multi-Well Pad Batch Drilling Procedure

Surface Casing - PR intends to Batch set all 13-3/8" casing to a depth approved in the APD. 17-1/2" Surface Holes will be batch drilled by a rig. Appropriate notifications will be made prior to spudding the well, running and cementing casing and prior to skidding to the rig to the next well on pad.

1. Drill 17-1/2" Surface hole to Approved Depth with Rig and perform wellbore cleanup cycles. Trip out and rack back drilling BHA.
2. Run and land 13-3/8" 54.5# J55 BTC casing see Illustration 1-1 Below to depth approved in APD.
3. Set packoff and test to 5k psi
4. Offline Cement
5. Install wellhead with pressure gauge and nightcap. Nightcap is shown on final wellhead Stack up Illustration #2-2.
6. Skid Rig to adjacent well to drill Surface hole.
7. Surface casing test will be performed by the rig in order to allow ample time for Cement to develop 500psi compressive strength. Casing test to 0.22 psi/ft or 1500 psi whichever is




Illustration 1-1

Intermediate Casing – PR intends to Batch set all intermediate casing strings to a depth approved in the APD, typically set into Lamar. 12-1/4" Intermediate Holes will be batch drilled by the rig. Appropriate notifications will be made prior Testing BOPE, and prior to running/cementing all casing strings.

1. Rig will remove the nightcap and install and test BOPE.
2. Test Surface casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) - not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
3. Install wear bushing then drill out 13-3/8" shoe-track plus 20' and conduct FIT to minimum of the MW equivalent anticipated to control the formation pressure to the next casing point.
4. Drill Intermediate hole to approved casing point. Trip out of hole with BHA to run Casing.
5. Remove wear bushing then run and land Intermediate Casing with mandrel hanger in wellhead.
6. Cement casing to surface with floats holding.
7. Washout stack then run wash tool in wellhead and wash hanger and pack-off setting area.
8. Install pack-off and test void to 5,000 psi for 15 minutes. Nightcap shown on final wellhead stack up illustration 2-2 on page 3.
9. Test casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) - not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
10. Install nightcap – skid rig to adjacent well to drill Intermediate hole.





Illustration 2-2

Production Casing – PR intends to Batch set all Production casings with Rig. Appropriate notifications will be made prior Testing BOPE, and prior to running/cementing all casing strings.


1. Big Rig will remove the nightcap and install and test BOPE.
2. Install wear bushing then drill Intermediate shoe-track plus 20' and conduct FIT to minimum MW equivalent to control the formation pressure to TD of well.
3. Drill Vertical hole to KOP – Trip out for Curve BHA.
4. Drill Curve, landing in production interval – Trip for Lateral BHA.
5. Drill Lateral / Production hole to Permitted BHL, perform cleanup cycles and trip out to run 5 1/2" Production Casing.
6. Remove wear bushing then run 5-1/2" production casing to TD landing casing mandrel in wellhead.
7. Cement 5-1/2" Production string with floats holding.
8. Run in with wash tool and wash wellhead area – install pack-off and test void to 5,000psi for 15 minutes.
9. Install BPV in 5-1/2" mandrel hanger – Nipple down BOPE and install nightcap.
10. Test nightcap void to 5,000psi for 30 minutes per illustration 2-2
11. Skid rig to adjacent well on pad to drill production hole.

Permian Resources Offline Cementing Procedure 13-3/8" & 9-5/8" Casing


1. Drill hole to Total Depth with Rig and perform wellbore cleanup cycles.
2. Run and casing to Depth.
3. Land casing with mandrel.
4. Circulate 1.5 csg capacity.
5. Flow test – Confirm well is static and floats are holding.
6. Set Annular packoff and pressure test. Test to 5k.
7. Nipple down BOP and install cap flange.
8. Skid rig to next well on pad
9. Remove cap flange (confirm well is static before removal)
 - a) If well is not static use the casing outlet valves to kill well
 - b) Drillers method will be used in well control event
 - c) High pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - d) Kill mud will be circulated once influx is circulated out of hole
 - e) Confirm well is static and remove cap flange to start offline cement operations
10. Install offline cement tool.
11. Rig up cementers.
12. Circulate bottoms up with cement truck
13. Commence planned cement job, take returns through the annulus wellhead valve
14. After plug is bumped confirm floats hold and well is static
15. Rig down cementers and equipment
16. Install night cap with pressure gauge to monitor.




9 5/8" Intermediate



Run 9-5/8" Casing
Land Casing on 9-5/8" Mandrel Hanger
Cement 9-5/8" Casing
Retrieve Running Tool



Run 13-5/8" Packoff
Test Upper and Lower Seals
Engage Lockring
Retrieve Running Tool





CONTITECH RUBBER
Industrial Kft.

No:QC-DB- 210/ 2014


Page: 15 / 113


ContiTech

Hose Data Sheet

CRI Order No.	538236
Customer	ContiTech Oil & Marine Corp.
Customer Order No.	4500409659
Item No.	1
Hose Type	Flexible Hose
Standard	API SPEC 16 C
Inside dia in inches	3
Length	35 ft
Type of coupling one end	FLANGE 4.1/16" 10K API SPEC 6A TYPE 6BX FLANGE C/W BX155 R.GR.SOUR
Type of coupling other end	FLANGE 4.1/16" 10K API SPEC 6A TYPE 6BX FLANGE C/W BX155 R.GR.SOUR
H2S service NACE MR0175	Yes
Working Pressure	10 000 psi
Design Pressure	10 000 psi
Test Pressure	15 000 psi
Safety Factor	2,25
Marking	USUAL PHOENIX
Cover	NOT FIRE RESISTANT
Outside protection	St. steel outer wrap
Internal stripwound tube	No
Lining	OIL + GAS RESISTANT SOUR
Safety clamp	No
Lifting collar	No
Element C	No
Safety chain	No
Safety wire rope	No
Max. design temperature [°C]	100
Min. design temperature [°C]	-20
Min. Bend Radius operating [m]	0,90
Min. Bend Radius storage [m]	0,90
Electrical continuity	The Hose is electrically continuous
Type of packing	WOODEN CRATE ISPM-15

Printed: TIRETECH2\CsontosG - 2014.03.10 15:22:17






KOALA 9 FED COM
EDDY COUNTY, NEW MEXICO


Legend


- SHL
- Well Bore
- Access Road
- Proposed Flowline
- CTB
- Pad

Date: 5/11/2022
GIS Tech: VKV



1:6,000
1" = 500'







U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

01/29/2024

APD ID: 10400085975

Submission Date: 06/09/2022

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: COLGATE OPERATING LLC**Well Name:** KOALA 9 FED COM**Well Number:** 121H**Is the reclamation bond a rider under the BLM bond?****Unlined pit bond number:****Unlined pit bond amount:****Additional bond information****Section 4 -****Would you like to utilize Injection PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Injection PWD discharge volume (bbl/day):****Injection well mineral owner:****Injection well type:****Injection well number:****Injection well name:****Assigned injection well API number?****Injection well API number:****Injection well new surface disturbance (acres):****Minerals protection information:****Mineral protection****Underground Injection Control (UIC) Permit?****UIC Permit****Section 5 - Surface****Would you like to utilize Surface Discharge PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Surface discharge PWD discharge volume (bbl/day):****Surface Discharge NPDES Permit?****Surface Discharge NPDES Permit attachment:****Surface Discharge site facilities information:****Surface discharge site facilities map:****Section 6 -****Would you like to utilize Other PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Other PWD discharge volume (bbl/day):**

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data

01/29/2024

APD ID: 10400085975

Submission Date: 06/09/2022

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Operator Name: COLGATE OPERATING LLC

Well Name: KOALA 9 FED COM

Well Number: 121H

Well Type: OIL WELL

Well Work Type: Drill

Bond

Federal/Indian APD: FED

BLM Bond number: NMB001382

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information

State of New Mexico
Energy, Minerals and Natural Resources Department

Oil Conservation Division
1220 South St. Francis Dr
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

I. Operator: Permian Resources Operating, LLC **OGRID:** 372165 **Date:** 7/25/2023

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____.

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil	Anticipated Gas	Anticipated Prod Water
Koala 9 Fed Com 111H		A-8-T20S-R28E	796' FNL - 362' FEL	560 BOPD	3083 MCFD	3923 BWPD
Koala 9 Fed Com 112H		A-8-T20S-R28E	797' FNL - 332' FEL	560 BOPD	3083 MCFD	3923 BWPD
Koala 9 Fed Com 113H		P-8-T20S-R28E	1144' FSL - 135' FEL	560 BOPD	3083 MCFD	3923 BWPD
Koala 9 Fed Com 114H		P-8-T20S-R28E	1144' FSL - 105' FEL	560 BOPD	3083 MCFD	3923 BWPD
Koala 9 Fed Com 121H		A-8-T20S-R28E	795' FNL - 422' FEL	1098 BOPD	2166 MCFD	2843 BWPD
Koala 9 Fed Com 122H		A-8-T20S-R28E	796' FNL - 392' FEL	1359 BOPD	2681 MCFD	3518 BWPD
Koala 9 Fed Com 123H		P-8-T20S-R28E	1144' FSL - 195' FEL	1236 BOPD	2437 MCFD	3199 BWPD
Koala 9 Fed Com 124H		P-8-T20S-R28E	1144' FSL - 165' FEL	1236 BOPD	2437 MCFD	3199 BWPD
Koala 9 Fed Com 131H		A-8-T20S-R28E	794' FNL - 482' FEL	1046 BOPD	2417 MCFD	3347 BWPD
Koala 9 Fed Com 132H		A-8-T20S-R28E	795' FNL - 452' FEL	1095 BOPD	2530 MCFD	3503 BWPD
Koala 9 Fed Com 133H		P-8-T20S-R28E	1144' FSL - 255' FEL	1046 BOPD	2417 MCFD	3347 BWPD
Koala 9 Fed Com 134H		P-8-T20S-R28E	1144' FSL - 225' FEL	1046 BOPD	2417 MCFD	3347 BWPD
Koala 9 Fed Com 201H		A-8-T20S-R28E	793' FNL - 512' FEL	939 BOPD	1465 MCFD	1428 BWPD
Koala 9 Fed Com 202H		A-8-T20S-R28E	793' FNL - 542' FEL	939 BOPD	1465 MCFD	1428 BWPD
Koala 9 Fed Com 203H		P-8-T20S-R28E	1144' FSL - 285' FEL	1461 BOPD	2356 MCFD	2223 BWPD
Koala 9 Fed Com 204H		P-8-T20S-R28E	1144' FSL - 315' FEL	1198 BOPD	1798 MCFD	2995 BWPD

IV. Central Delivery Point Name: Dundee-Koala CDP [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Koala 9 Fed Com 111H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 112H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 113H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 114H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 121H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 122H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 123H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 124H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 131H		TBD	TBD	TBD	TBD	TBD
Koala 9 Fed Com 132H		12/12/2023	12/27/2023	12/31/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 133H		11/16/2023	12/1/2023	12/28/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 134H		12/1/2023	12/17/2023	12/28/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 201H		11/9/2023	11/25/2023	12/31/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 202H		11/25/2023	12/12/2023	12/31/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 203H		10/14/2023	10/30/2023	12/28/2023	1/27/2024	1/27/2024
Koala 9 Fed Com 204H		10/30/2023	11/16/2023	12/28/2023	1/27/2024	1/27/2024

VI. Separation Equipment: ☒ Attach a complete description of how Operator will seize separation equipment to optimize gas capture.

VII. Operations Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan
Effective April 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☐ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well Name	API	Anticipated Average Natural Gas Rate	Anticipated Volume of Natural Gas for the First Year

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Volume of Natural Gas for the First Year

XI. Map. ☒ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas system(s) to which the well(s) will be connected.

XII. Line Capacity. Operator ☒ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☒ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☒ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attached a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 – Certifications **Effective May 25, 2021**

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) Power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 – Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
 - (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
 - (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, not later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file and update for each Natural Gas Management Plan until the Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
 - (c) OCD may deny or conditionally approve and APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:



Printed Name:

Jackson Taylor

Title:

Director of Midstream & Marketing

E-mail Address:

jackson.taylor@permianres.com

Date:

Phone:

(432) 400-1048

OIL CONSERVATION DIVISION**(Only applicable when submitted as a standalone form)**

Approved By:

Title:

Approval Date:

Conditions of Approval:

Natural Gas Management Plan Descriptions**VI. Separation Equipment:**

Permian Resources Operating, LLC (Permian) utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations. Our goal is to maintain 5 minutes of retention time in the test vessel and 20 minutes in the heater treater at peak production rates. The gas produced is routed from the separator to the gas sales line.

VII. Operational Practices:*Drilling*

During Permian's drilling operations it is uncommon for venting or flaring to occur. If flaring is needed due to safety concerns, gas will be routed to a flare and volumes will be estimated.

Flowback

During completion/recompletion flowback operations, after separation flowback begins and as soon as it is technically feasible, Permian routes gas through a permanent separator and the controlled facility where the gas is either sold or flared through a high-pressure flare if needed.

Production

Per 19.15.27.8.D, Permian's facilities are designed to minimize waste. Our produced gas will only be vented or flared in an emergency or malfunction situation, except as allowed for normal operations noted in 19.15.27.8.D(2) & (4). All gas that is flared is metered. All gas that may be vented will be estimated.

Performance Standards

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations.

All of Permian's permanent storage tanks associated with production operations which are routed to a flare or control device are equipped with an automatic gauging system.

All of Permian's flare stacks, both currently installed and for future installation, are:

- 1) Appropriately sized and designed to ensure proper combustion efficiency.
- 2) Equipped with an automatic ignitor or continuous pilot.
- 3) Anchored and located at least 100 feet from the well and storage tanks.

Permian's field operations and HSE teams have implemented an AVO inspection schedule that adheres to the requirements of 19.15.27.8.E(5).

All of our operations and facilities are designed to minimize waste. We routinely employ the following methods and practices:

- Closed-loop systems
- Enclosed and properly sized tanks

Permian Resources Operating, LLC (372165)

- Vapor recovery units to maximize recovery of low-pressure gas streams and potential unauthorized emissions
- Low-emitting or electric engines whenever practical
- Combustors and flare stacks in the event of a malfunction or emergency
- Routine facility inspections to identify leaking components, functioning control devices, such as flares and combustors, and repair / replacement of malfunctioning components where applicable

Measurement or estimation

Permian measures or estimates the volumes of natural gas vented, flared and/or beneficially used for all of our drilling, completing and producing wells. We utilize accepted industry standards and methodology which can be independently verified. Annual GOR testing is completed on our wells and will be submitted as required by the OCD. None of our equipment is designed to allow diversion around metering elements except during inspection, maintenance and repair operations.

VIII. Best Management Practices:


Permian Resources utilizes the following BMPs to minimize venting during active and planned maintenance activities:


- Use a closed-loop process wherever possible during planned maintenance activities, such as blowdowns, liquid removal, and work over operations.
- Employ low-emitting or electric engines for equipment, such as compressors
- Adhere to a strict preventative maintenance program which includes routine facility inspections, identification of component malfunctions, and repairing or replacing components such as hatches, seals, valves, etc. where applicable
- Utilize vapor recovery units (VRU's) to maximize recovery of volumes of low-pressure gas streams and potential unauthorized emissions
- Route low pressure gas and emissions streams to a combustion device to prevent venting where necessary

Enhanced Natural Gas Management Plan

Operator's Plan to Manage Production in Response to Increased Line Pressure

Permian Resources Operating, LLC (Permian) anticipates that its existing wells connected to the same portion of the natural gas gathering system will continue to meet anticipated increases in line pressure caused by the new wells. Permian will actively monitor line pressure throughout the field and will make necessary adjustments to existing production separators' pressures to send gas to sales. Permian also plans to implement automated alarms on all flare meters to alert of flaring events as they occur. The alarms will send notifications to field operations and engineering staff via text message and email at every occurrence of flaring. In addition, Permian plans to implement automated alarms on all flare meters to alert of any continuous flaring event that has continued for at least 4 hours. The alarms will send notifications to field operations and engineering management. Permian personnel will promptly respond to these alarms, communicate with midstream partners, and take the appropriate action to reduce flaring caused by high line pressure from new well production.





District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 309252

CONDITIONS

Operator: COLGATE OPERATING, LLC 300 North Marienfeld Street Midland, TX 79701	OGRID:
	371449
	Action Number:
	309252
Action Type:	
[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)	

CONDITIONS

Created By	Condition	Condition Date
ward.rikala	Notify OCD 24 hours prior to casing & cement	2/9/2024
ward.rikala	Will require a File As Drilled C-102 and a Directional Survey with the C-104	2/9/2024
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	2/9/2024
ward.rikala	Cement is required to circulate on both surface and intermediate1 strings of casing	2/9/2024
ward.rikala	If cement does not circulate on any string, a CBL is required for that string of casing	2/9/2024
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	2/9/2024