

Form 3160-3
(June 2015)

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. NMNM13276
2. Name of Operator COLGATE OPERATING LLC		6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. ROBIN FED 127H
3a. Address 300 N MARIENFELD STREET SUITE 1000, MIDLAND, TX	3b. Phone No. (include area code) (432) 695-4272	9. API Well No. 30-025-52625
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SESE / 330 FSL / 1295 FEL / LAT 32.5522307 / LONG -103.5780535 At proposed prod. zone NENE / 10 FNL / 660 FEL / LAT 32.580395 / LONG -103.5760115		10. Field and Pool, or Exploratory Lea/Bone Spring, South 11. Sec., T. R. M. or Blk. and Survey or Area SEC 20/T20S/R34E/NMP
14. Distance in miles and direction from nearest town or post office* 27 miles		12. County or Parish LEA
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 330 feet		13. State NM
16. No of acres in lease		17. Spacing Unit dedicated to this well 320.0
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1223 feet		20. BLM/BIA Bond No. in file FED:
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3670 feet	22. Approximate date work will start* 08/31/2022	23. Estimated duration 90 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission)	Name (Printed/Typed) MIKAH THOMAS / Ph: (432) 695-4224	Date 05/21/2022
Title Regulatory Manager		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) CODY LAYTON / Ph: (575) 234-5959	Date 02/16/2024
Title Assistant Field Manager Lands & Minerals Office Carlsbad Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

*(Instructions on page 2)

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number 30-025-52625		2 Pool Code 58960		3 Pool Name TEAS;BONE SPRING	
4 Property Code 335483		5 Property Name ROBIN FED			6 Well Number 127H
7 OGRID No. 371449		8 Operator Name COLGATE ENERGY LLC			9 Elevation 3669.70'

10 Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	20	20-S	34-E		330'	SOUTH	1295'	EAST	LEA

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	17	20-S	34-E		10'	NORTH	660'	EAST	LEA

12 Dedicated Acres 320	13 Joint or Infill	14 Consolidation Code	15 Order No.
----------------------------------	---------------------------	------------------------------	---------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

17 OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *Mikah Thomas* Date: 05.16.2022
Printed Name: Mikah Thomas
E-mail Address: mthomas@colgateenergy.com

18 SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Date of Survey: [Blank]
Signature and Seal of Professional Surveyor: *Mark J. Murray*
Certificate Number: 12177
3/28/2022

CORNER DATA
NEW MEXICO EAST - NAD 83

A - CALCULATED CORNER N:575683.60° E:770024.14'	E - FOUND 1" IRON PIPE N:570444.44° E:775311.14'	I - FOUND 2" IRON PIPE N:565124.75° E:770055.49'	L - FOUND 1/2" IRON ROD N:573038.97° E:769997.80'
B - FOUND 2" IRON ROD N:575698.69° E:772576.32'	F - FOUND BENT 1" IRON PIPE N:567799.07° E:775330.83'	J - FOUND 1/2" IRON ROD N:567764.31° E:770035.95'	M - FOUND 3/8" IRON ROD N:570422.45° E:772663.28'
C - FOUND 1" IRON ROD N:575725.09° E:775270.15'	G - FOUND BENT 1" T-RAIL N:565162.69° E:775351.32'	K - CALCULATED CORNER N:570396.23° E:770013.74'	
D - FOUND 1/2" IRON ROD N:573083.40° E:775289.90'	H - FOUND 4" IRON PIPE N:565090.87° E:772709.30'		

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Colgate
LEASE NO.:	NMNM13276
LOCATION:	Section 20, T.20 S, R.34 E., NMPM
COUNTY:	Lea County, New Mexico
WELL NAME & NO.:	Robin Fed 127H
SURFACE HOLE FOOTAGE:	330'/S & 1295'/E
BOTTOM HOLE FOOTAGE:	10'/N & 660'/E

COA

H₂S	<input type="radio"/> Yes	<input checked="" type="radio"/> No		
Potash / WIPP	<input type="radio"/> None	<input type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P	<input type="checkbox"/> WIPP
Cave / Karst	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High	<input type="radio"/> Critical
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both	<input type="radio"/> Diverter
Cementing	<input type="checkbox"/> Primary Squeeze	<input type="checkbox"/> Cont. Squeeze	<input type="checkbox"/> EchoMeter	<input type="checkbox"/> DV Tool
Special Req	<input type="checkbox"/> Break Testing	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input type="checkbox"/> Unit
Variance	<input checked="" type="checkbox"/> Flex Hose	<input type="checkbox"/> Casing Clearance	<input type="checkbox"/> Pilot Hole	<input checked="" type="checkbox"/> Capitan Reef
Variance	<input type="checkbox"/> Four-String	<input type="checkbox"/> Offline Cementing	<input type="checkbox"/> Fluid-Filled	<input type="checkbox"/> Open Annulus
<input type="checkbox"/> Batch APD / Sundry				

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area must meet all requirements from **43 CFR 3176**, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **1600** feet (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever

- is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing shall be set at **3256ft**:
 - Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.
 - a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job. **Excess calculates to 12%. Additional cement maybe required.**
 - b. Second stage above DV tool:
 - c. Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Excess calculates to 19%. Additional cement maybe required.**

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, Capitan Reef, and potash.

- ❖ In R111 Potash Areas if cement does not circulate to surface on the first two salt protection casing strings, the cement on the 3rd casing salt string must come to surface.
- ❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:
(Use this for 3 string wells in the Capitan Reef, if 4 string well ensure FW based mud used across the capitan interval)
 - Switch to freshwater mud to protect the Capitan Reef and use freshwater mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
 - Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval.

If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.

Operator will sundry this APD for a four-string Casing Plan

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office. Operator shall provide method of verification.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, Capitan Reef, and potash.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the casing shoe shall be **5000 (5M)** psi.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Email **or** call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, BLM_NM_CFO_DrillingNotifications@BLM.GOV
(575) 361-2822

Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,
(575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **43 CFR part 3170 Subpart 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive

strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR part 3170 Subpart 3172 and API STD 53 Sec. 5.3**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal

or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in **43 CFR part 3170 Subpart 3172** must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)

- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR part 3170 Subpart 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR part 3170 Subpart 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS 2/5/2024



Operator Certification Data Report

02/29/2024

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME:

Signed on: 05/18/2022

Title:

Street Address:

City:

State:

Zip:

Phone:

Email address:

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data

02/29/2024

APD ID: 10400085479

Submission Date: 05/21/2022

Highlighted data reflects the most recent changes
[Show Final Text](#)

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400085479

Tie to previous NOS? N

Submission Date: 05/21/2022

BLM Office: Carlsbad

User: MIKAH X THOMAS

Title: Regulatory Manager

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM13276

Lease Acres:

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? N

Permitting Agent? NO

APD Operator: COLGATE OPERATING LLC

Operator letter of

Operator Info

Operator Organization Name: COLGATE OPERATING LLC

Operator Address: 300 N MARIENFELD STREET SUITE 1000

Zip: 79701

Operator PO Box:

Operator City: MIDLAND

State: TX

Operator Phone: (432)695-4272

Operator Internet Address: MTHOMAS@COLGATEENERGY.COM

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: ROBIN FED

Well Number: 127H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: Lea

Pool Name: Bone Spring, South

Operator Name: COLGATE OPERATING LLC
Well Name: ROBIN FED **Well Number:** 127H

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Is the proposed well in a Helium production area? N Use Existing Well Pad? N New surface disturbance?

Type of Well Pad: MULTIPLE WELL **Multiple Well Pad Name:** Robin **Number:** 2
Well Class: HORIZONTAL **Pad East**
Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 27 Miles **Distance to nearest well:** 1223 FT **Distance to lease line:** 330 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: Robin_Fed_127H_Plat_C_102_Signed_20220518120923.pdf

Well work start Date: 08/31/2022 **Duration:** 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 12177

Reference Datum: KELLY BUSHING

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	330	FSL	1295	FEL	20S	34E	20	Aliquot SESE	32.5522307	-103.5780535	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 13276	3670	0	0	Y
KOP Leg #1	87	FSL	743	FEL	20S	34E	20	Aliquot SESE	32.5515526	-103.5762669	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 13276	-6310	10001	9980	Y
PPP Leg #1-1	100	FSL	660	FEL	20S	34E	20	Aliquot SESE	32.5516334	-103.5759921	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 13276	-6734	10478	10404	Y

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
EXIT Leg #1	100	FNL	660	FEL	20S	34E	17	Aliquot NENE	32.5801477	-103.5760114	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 13276	-6888	20740	10558	Y
BHL Leg #1	10	FNL	660	FEL	20S	34E	17	Aliquot NENE	32.580395	-103.5760115	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 13276	-6888	20830	10558	Y



Drilling Plan Data Report

02/29/2024

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

APD ID: 10400085479

Submission Date: 05/21/2022

Highlighted data reflects the most recent changes

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
12946671	QUATERNARY	3669	30	30	ALLUVIUM	NONE	N
12946681	RUSTLER	2114	1555	1555	ANHYDRITE, LIMESTONE, SALT	NONE	N
12946672	SALADO	2004	1665	1666	ANHYDRITE, SALT	NONE	N
12946673	TANSILL	419	3250	3255	ANHYDRITE, DOLOMITE	NONE	N
12946674	YATES	244	3425	3430	DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946675	SEVEN RIVERS	19	3650	3656	ANHYDRITE, DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946676	CAPITAN REEF	-281	3950	3957	LIMESTONE	NONE	N
12946677	QUEEN	-481	4150	4157	ANHYDRITE, DOLOMITE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946678	CHERRY CANYON	-1911	5580	5580	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946670	BRUSHY CANYON	-3121	6790	6790	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946679	BONE SPRING	-4806	8475	8493	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946680	BONE SPRING 1ST	-5881	9550	9571	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	N
12946705	BONE SPRING 2ND	-6456	10125	10148	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Operator Name: COLGATE OPERATING LLC**Well Name:** ROBIN FED**Well Number:** 127H**Pressure Rating (PSI):** 10M**Rating Depth:** 15000

Equipment: BOPE with working pressure ratings in excess of anticipated maximum surface pressure will be utilized for well control from drill out of surface casing to TMD. A rotating head will also be installed and utilized as needed. All BOPE connections shall be flanged, welded or clamped. All choke lines shall be straight unless targeted with running tees or tee blocks are used, and choke lines shall be anchored to prevent whip and reduce vibrations. All valves in the choke line & the choke manifold shall be full opening as to not cause restrictions and to allow for straight fluid paths to minimize potential erosion. All gauges utilized in the well control system shall be of a type designed for drilling fluid service. A top drive inside BOP valve will be utilized at all times. Subs equipped with full opening valves sized to fit the drill pipe and collars will be available on the rig floor in the open position. The key to operate said valve equipped subs will be on the rig floor at all times. The accumulator system will have sufficient capacity to open the HCR and close all three sets of rams plus the annular preventer while retaining at least 300 psi above precharge on the closing manifold (accumulator system shall be capable of doing so without using the closing unit pumps). The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity, and the fluid level will be maintained at the manufacturer's recommended level. Prior to connecting the closing unit to the BOP stack, an accumulator precharge pressure test shall be performed to ensure the precharge pressure is within 100 psi of the desired precharge pressure (only nitrogen gas will be used to precharge). Two independent power sources will be made available at all times to power the closing unit pumps so that the pumps can automatically start when the closing valve manifold pressure has decreased to the preset level. Closing unit pumps will be sized to allow opening of HCR and closing of annular preventer on 5" drill pipe achieving at least 200 psi above precharge pressure with the accumulator system isolated from service in less than two minutes. A valve shall be installed in the closing line as close to the annular preventer as possible to act as a locking device; the valve shall be maintained in the open position and shall be closed only when the power source for the accumulator system is inoperative. Remote controls capable of opening and closing all preventers & the HCR shall be readily accessible to the driller; master controls with the same capability will be operable at the accumulator. The wellhead will be a multibowl speed head allowing for hangoff of intermediate casing & isolation of the 133/8 x 95/8 annulus without breaking the connection between the BOP & wellhead to install an additional casing head. A wear bushing will be installed & inspected frequently to guard against internal wear to wellhead. VBRs (variablebore rams) will be run in upper rambody of BOP stack to provide redundancy to annular preventer while RIH w/ production casing;

Requesting Variance? YES

Variance request: 1. Colgate Energy requests a variance to drill this well using a coflex line between the BOP and choke manifold. Certification for proposed coflex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

Testing Procedure: After surface casing is set and the BOPE installed, pressure tests of BOPE will be performed by a third party tester utilizing water and a test plug to 250 psi low and 5,000 psi high. To deem a pressure test successful, pressure must be maintained for ten minutes without any bleedoff. A valve on the wellhead below seat of test plug will be open at all time during BOPE tests to guard against damage to casing. The BOPE will be retested in this manner after any connection breaks or passage of allotted time (25 days). Any BOPE which fails to pass pressure tests after initial install will be replaced prior to drilling out of surface casing shoe. If at any time a BOPE component cannot function to secure the hole, the hole shall be secured utilizing a retrievable packer, and the nonfunctioning BOPE component shall be repair or replaced. After repair or replacement, a pressure test of the repaired or replaced component and any connections broken to repair or replace the nonfunctioning component will be tested in the same manner as described for initial install of BOPE. The annular preventer will be faction tested at least weekly, and the ramtype preventers will be function tested on each trip. BOPE pit level drills will be conducted weekly with each drilling crews. All pressure tests performed on BOPE and BOPE pit level drills will be logged in the drilling log. Isolation of 133/8" x 95/8" casing annulus shall be confirmed by pressure testing of wellhead sealing component after said sealing component is installed.

Choke Diagram Attachment:

Robin__10M_Choke_Layout_20220517173729.pdf

BOP Diagram Attachment:

Robin__BOP_Stack_20220517173735.pdf

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Robin__10M_Choke_Layout_20220517173729.pdf

Robin__BOP_Stack_20220517173735.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	5.5	NEW	API	N	0	1620	0	1620	3670	2050	1620	J-55	54.5	BUTT	1.125	1.2	DRY	1.6	DRY	1.6
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	5520	0	5489	0	-1819	5520	J-55	40	BUTT	1.125	1.2	DRY	1.6	DRY	1.6
3	PRODUCTION	8.7	5.5	NEW	API	N	0	20830	0	10558	0	-6888	20830	OTHER	17	OTHER - CDC HTQ	1.125	1.1	DRY	1.6	DRY	1.6

Casing Attachments

Casing ID: 1 **String** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Robin_Fed_127H__Casing_Design_Summary_20220518122150.pdf

Casing_Design_Assumptions_20220518122156.pdf

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Casing Attachments

Casing ID: 2 **String** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Assumptions_20220518105442.pdf

Robin_Fed_127H___Casing_Design_Summary_20220518122136.pdf

Casing ID: 3 **String** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Assumptions_20220518102758.pdf

Robin_Fed_127H___Casing_Design_Summary_20220518122042.pdf

Proprietary_Connections_Performance_Data_5.5000_17.0000_0.3040__P110_HP_20230223165034.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1290	1050	1.68	13.7	1764	100	ExtendaCem-CZ	None
SURFACE	Tail		1290	1620	340	1.35	14.8	459	100	HalCem-C	Accelerator
INTERMEDIATE	Lead	3730	0	2620	564	1.88	12.9	1060.32	50	EconoCem-HLC	5% salt + 5 lb/sk Kol-Seal

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Tail		2620	3730	325	1.33	14.8	432.25	25	HalCem-C	None
INTERMEDIATE	Lead		3730	4416	171	1.88	12.9	321.48	50	EconCem-HLC	5% Salt + 5 lb/sk Kol-Seal
INTERMEDIATE	Tail		4416	5520	325	1.33	14.8	432.25	25	HalCem-C	None
PRODUCTION	Lead		0	9760	1155	2.41	11.5	2617.26	25	Class H	POZ + extender + fluid loss + dispersant + retarder
PRODUCTION	Tail		9760	20830	2025	1.73	12.5	3075.94	25	Class H	POZ + extender + fluid loss + dispersant + retarder

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary mud products for weight addition and fluid loss control will be on location at all times.

Describe the mud monitoring system utilized: Mud program is subject to change due to hole conditions. The mud monitoring system is an electronic Pason system satisfying requirements of Onshore Order #1. Both visual and electronic mud monitoring equipment will be utilized to detect volume changes indicating loss or gain of circulating system fluid volume. Slow pump rates will be taken & recorded tourly in the drilling log. Mud engineer will perform tests and provide written report at least every 12 hours while circulating. A trip tank will be utilized and trip sheet will be recorded to ensure wellbore is taking proper fill or displacing proper fluid volume during all tripping operations. Gas detecting equipment will be utilized to monitor for hydrocarbon gas at the shakers while drilling and/or circulating. H2S monitoring equipment with both visual & auditory alarms will be installed and operational at the shakers, rig floor and cellar while drilling and/or circulating. A flare system with an effective method for ignition & discharge more than 100 feet from the wellbore will be utilized to gather and burn all gas; lines will be straight unless targeted with running tees. A mud gas separator will be installed and operable at least 500 feet before first anticipated hydrocarbon zone.

Circulating Medium Table

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1620	SPUD MUD	8.6	9							
1620	5520	SALT SATURATED	10	10.2							
5520	20830	OIL-BASED MUD	9	10							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Directional surveys will be collected at no greater than 200' intervals while drilling through the MWD tools. A GR log will be collected while drilling through the MWD tools from intermediate casing to TD. No DSTs or cores are planned at this time. No temperature logs planned at this time.

CBL will be run to confirm TOC on production casing after rig is removed from location. A formation integrity test (FIT) will be performed on 95/8" casing string after

BOPE is installed to at least 1 ppge over planned section mud weight after drilling ten feet of new hole.

List of open and cased hole logs run in the well:

DIRECTIONAL SURVEY, GAMMA RAY LOG,

Coring operation description for the well:

No openhole logs are planned at this time.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4162

Anticipated Surface Pressure: 1839

Anticipated Bottom Hole Temperature(F): 120

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Colgate_H2S_Contingency_Plan_20220510162250.pdf

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

_C04__Robin_Fed_127H_APD_Rev01_20220518122523.pdf

Other proposed operations facets description:

After surface casing is set and the BOPE installed, pressure tests of BOPE will be performed by a third party tester utilizing water and a test plug to 250 psi low and 5,000 psi high. To deem a pressure test successful, pressure must be maintained for ten minutes without any bleedoff. A valve on the wellhead below seat of test plug will be open at all time during BOPE tests to guard against damage to casing. The BOPE will be retested in this manner after any connection breaks or passage of allotted time (25 days). Any BOPE which fails to pass pressure tests after initial install will be replaced prior to drilling out of surface casing shoe. If at any time a BOPE component cannot function to secure the hole, the hole shall be secured utilizing a retrievable packer, and the nonfunctioning BOPE component shall be repair or replaced. After repair or replacement, a pressure test of the repaired or replaced component and any connections broken to repair or replace the nonfunctioning component will be tested in the same manner as described for initial install of BOPE. The annular preventer will be faction tested at least weekly, and the ramtype preventers will be function tested on each trip. BOPE pit level drills will be conducted weekly with each drilling crews. All pressure tests performed on BOPE and BOPE pit level drills will be logged in the drilling log. Isolation of 133/8" x 95/8" casing annulus shall be confirmed by pressure testing of wellhead sealing component after said sealing component is installed.

Casing will be tested by pressuring up to 1,500 psi and holding pressure for thirty minutes. A casing test will be deemed successful if test pressure does not decline more than 10% over the thirty minute period. Cement will be allowed to sit undisturbed for twentyfour hours and reach a minimum of 500 psi compressive strength across the "zone of interest" prior to testing casing and drilling out. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Cement will be placed on all casing strings utilizing the pump and plug method. A float will be installed in the casing shoe and float collar on all casing strings to hold cement in place once pumping is completed. A top plug will be utilized on all casing strings to prevent contamination of the cement by the displacement fluid. A preflush fluid will be pumped prior to cement to aid in removal of drilling mud from the wellbore, eliminate drilling mud contamination of the cement slurry and prepare the surface of both the wellbore and casing for cement.

No abnormal pressures or temperatures are expected. In accordance with Onshore Order No. 6, Colgate Energy does not anticipate that there will be enough H2S from the surface to the Wolfcamp formations to meet the BLMs minimum requirements for the submission of an H2S Drilling Operation Plan or Public Protection Plan for the drilling and completion of this well. Since we have an H2S safety package on all wells, attached is an H2S Drilling Operations Plan. Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Other proposed operations facets attachment:

Choke_Hose_SN_53621_20220511064656.pdf

Colgate_13_MBS_RP_20220511064642.PDF

Robin__Overview_Map_20220517174412.pdf

Robin_Fed_127H_APD_Procedure_Update_4.24.23_20230425093944.pdf


Other Variance attachment:

Operator Name: COLGATE OPERATING LLC


Well Name: ROBIN FED

Well Number: 127H

Multi-bowl Wellhead



10M Choke Layout




10,000 psi BOP Stack:


Mud Cross Valves:

- 5. 10M Check Valve
- 6. Outside 10M Kill Line Valve
- 7. Inside 10M Kill Line Valve
- 8. Outside 10M Kill Line Valve
- 9. 10M HCR Valve

*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side



Closed Loop System Layout:



Colgate's Minimum Design Criteria

Burst, collapse and tension SF are calculated using Landmark's StressCheck (casing design) software. A sundry will be requested if any lesser grade or different size casing is substituted.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

File: APD-Rev00

Date: April 29, 2022 Page: 1

WELL SUMMARY

	String	OD/Weight/Grade	Connection	MD Interval (usft)	Drift Dia. (")	Minimum Safety Factor (Abs)				Design Cost (\$)
						Burst	Collapse	Axial	Triaxial	
1	Surface Casing	13 3/8", 54.500 ppf, J-55	BTC, J-55	30-1620	12.459	1.61	1.20	1.68	1.46	38,421
2										Total = 38,421
3										
4	Intermediate Casing	9 5/8", 40.000 ppf, J-55	BTC, J-55	30-5520	8.750 A	1.39	1.68	1.84	1.37	93,624
5										Total = 93,624
6										
7	Production Casing	5 1/2", 17.000 ppf, HP P-110	CDC-HTQ, BTC	30-20830	4.767	1.15	1.45	1.65	1.19	292,584
8										Total = 292,584
9										
10										Total = 424,629



U. S. Steel Tubular Products

3/5/2020 8:48:46 PM

5.500" 17.00lbs/ft (0.304" Wall) P110 HP USS-CDC HTQ®

MECHANICAL PROPERTIES	Pipe	USS-CDC HTQ®	
Minimum Yield Strength	125,000	--	psi
Maximum Yield Strength	140,000	--	psi
Minimum Tensile Strength	130,000	--	psi
DIMENSIONS	Pipe	USS-CDC HTQ®	
Outside Diameter	5,500	6,300	in.
Wall Thickness	0,304	--	in.
Inside Diameter	4,892	4,892	in.
Standard Drift	4,767	4,767	in.
Alternate Drift	--	--	in.
Coupling Length	--	9,250	in.
Nominal Linear Weight, T&C	17.00	--	lbs/ft
Plain End Weight	16.89	--	lbs/ft
SECTION AREA	Pipe	USS-CDC HTQ®	
Critical Area	4,962	4,962	sq. in.
Joint Efficiency	--	97.1	%
PERFORMANCE	Pipe	USS-CDC HTQ®	
Minimum Collapse Pressure	9,440	9,440	psi
External Pressure Leak Resistance	--	7,550	psi
Minimum Internal Yield Pressure	12,090	12,090	psi
Minimum Pipe Body Yield Strength	620,000	--	lbs
Joint Strength	--	602,000	lbs
Compression Rating	--	361,000	lbs
Reference Length	--	23,608	ft
Maximum Uniaxial Bend Rating	--	60.7	deg/100 ft
MAKE-UP DATA	Pipe	USS-CDC HTQ®	
Make-Up Loss	--	4,63	in.
Minimum Make-Up Torque	--	11,000	ft-lbs
Maximum Make-Up Torque	--	15,500	ft-lbs
Connection Yield Torque	--	19,200	ft-lbs

1. Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness and Specified Minimum Yield Strength (SMYS).
2. Uniaxial bending rating shown is structural only, and equal to compression efficiency.
3. Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
4. Reference length is calculated by joint strength divided by nominal threaded and coupled weight with 1.5 safety factor.
5. Connection external pressure leak resistance has been verified to 80% API pipe body collapse pressure following the guidelines of API 5C5 Cal II.

Legal Notice

USS - CDC HTQ® (High Torque Casing Drilling Connection) is a trademark of U. S. Steel Corporation. This product is a modified API Buttress threaded and coupled connection designed for drilling with casing applications. All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com

Colgate's Minimum Design Criteria

Burst, collapse and tension SF are calculated using Landmark's StressCheck (casing design) software. A sundry will be requested if any lesser grade or different size casing is substituted.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

File: APD-Rev00

Date: April 29, 2022 Page: 1

WELL SUMMARY

	String	OD/Weight/Grade	Connection	MD Interval (usft)	Drift Dia. (")	Minimum Safety Factor (Abs)				Design Cost (\$)
						Burst	Collapse	Axial	Triaxial	
1	Surface Casing	13 3/8", 54.500 ppf, J-55	BTC, J-55	30-1620	12.459	1.61	1.20	1.68	1.46	38,421
2										Total = 38,421
3										
4	Intermediate Casing	9 5/8", 40.000 ppf, J-55	BTC, J-55	30-5520	8.750 A	1.39	1.68	1.84	1.37	93,624
5										Total = 93,624
6										
7	Production Casing	5 1/2", 17.000 ppf, HP P-110	CDC-HTQ, BTC	30-20830	4.767	1.15	1.45	1.65	1.19	292,584
8										Total = 292,584
9										
10										Total = 424,629

File: APD-Rev00

Date: April 29, 2022 Page: 1

WELL SUMMARY

	String	OD/Weight/Grade	Connection	MD Interval (usft)	Drift Dia. (")	Minimum Safety Factor (Abs)				Design Cost (\$)
						Burst	Collapse	Axial	Triaxial	
1	Surface Casing	13 3/8", 54.500 ppf, J-55	BTC, J-55	30-1620	12.459	1.61	1.20	1.68	1.46	38,421
2										Total = 38,421
3										
4	Intermediate Casing	9 5/8", 40.000 ppf, J-55	BTC, J-55	30-5520	8.750 A	1.39	1.68	1.84	1.37	93,624
5										Total = 93,624
6										
7	Production Casing	5 1/2", 17.000 ppf, HP P-110	CDC-HTQ, BTC	30-20830	4.767	1.15	1.45	1.65	1.19	292,584
8										Total = 292,584
9										
10										Total = 424,629

Colgate's Minimum Design Criteria

Burst, collapse and tension SF are calculated using Landmark's StressCheck (casing design) software. A sundry will be requested if any lesser grade or different size casing is substituted.

Casing Design Assumptions:

Surface

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate I

- 1) Burst Design Loads
 - a) Displacement to Gas
 - (1) Internal: Assumes a full column of gas in the casing with a gas gradient of 0.7 psi/ft in the absence of better information. It is limited to the controlling pressure based on the maximum expected pore pressure within the next drilling interval.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.

- (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the TD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Intermediate or Intermediate II

- 1) Burst Design Loads
 - a) Gas Kick Profile
 - (1) Internal: Load profile based on influx encountered in lateral portion of wellbore with a maximum influx volume of 150 bbl and a kick intensity of 1.5 ppg using maximum anticipated MW of 9.9 ppg.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight from TOC to surface and cement slurry weight from TOC to shoe.
 - b) Lost Returns with Mud Drop
 - (1) Internal: Lost circulation at the deepest TVD of the next hole section and the fluid level falls to a depth where the hydrostatic pressure of the mud column equals pore pressure at the depth of the lost circulation zone.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 - 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 - 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.

Production

- 1) Burst Design Loads
 - a) Injection Down Casing
 - (1) Internal: Surface pressure plus injection fluid gradient.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - b) Casing Pressure Test (Drilling)
 - (1) Internal: Displacement fluid plus surface pressure required to comply with regulatory casing test pressure requirements of Onshore Oil and Gas Order No. 2 and NM NMAC 19.15.16 of NMOCD regulations.
 - (2) External: Mud weight to TOC and cement mix water gradient (8.4 ppg) below TOC.
 - c) Casing Pressure Test (Production)
 - (1) Internal: The design pressure test should be the greater of the planned test pressure prior to simulation down the casing, the regulatory test pressure, and the expected gas lift system pressure. The design test fluid should be the fluid associated with the pressure test having the greatest pressure.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
 - d) Tubing Leak
 - (1) Internal: SITP plus a packer fluid gradient to the top of packer.
 - (2) External: Mud base-fluid density to top of cement and cement mix water gradient (8.4 ppg) below TOC.
- 2) Collapse Loads
 - a) Cementing
 - (1) Internal: Displacement fluid density.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
 - b) Full Evacuation
 - (1) Internal: Full void pipe.
 - (2) External: Mud weight to TOC and cement slurry(s) density below TOC.
- 3) Tension Loads
 - a) Overpull Force
 1. Axial: Buoyant weight of the string plus planned 100,000 lbs applied in stuck pipe situation.
 - b) Green Cement Casing Test
 1. Axial: Buoyant weight of the string plus cement plug bump pressure load.



H₂S Contingency Plan



Table of Contents

I. EMERGENCY ASSISTANCE TELEPHONE LIST	3
II. H ₂ S CONTINGENCY PLAN SECTION.....	5
III. OPERATING PROCEDURES.....	7
IV. OPERATING CONDITIONS.....	10
V. EMERGENCY PROCEDURES	11
VI. POST EMERGENCY ACTIONS.....	14
VII. IGNITION PROCEDURES.....	15
VIII. TRAINING PROGRAM.....	16
IX. EMERGENCY EQUIPMENT	16
X. CHECKLISTS.....	20
XI. BRIEFING PROCEDURES.....	22
XII. EVACUATION PLAN.....	23
XIII. APPENDICES AND GENERAL INFORMATION	24

I. EMERGENCY ASSISTANCE TELEPHONE LIST

PUBLIC SAFETY **911 or**

Sheriff's Department:

Eddy County Sherriff's Office (575) 887-7551

Fire Department:

Carlsbad Fire Department (575) 885-3125

Artesia Fire Department (575) 746-5051

Ambulance:

Elite Medical Transport (Carlsbad) (915) 542-1144

Trans Aero MedEvac (Artesia) (970) 657-7449

Hospitals:

Carlsbad Medical Center (575) 887-4100

Artesia General Hospital (575) 748-3333

New Mexico Dept. of Transportation:

Highway & Transportation Department (505) 795- 1401

New Mexico Railroad Commission:

Main Line (505) 476-3441

OSHA 24 Hr. Reporting (800) 321-6742

(8 hrs. after death or 24 hrs. after in-patient, amputation, loss of an eye)

Office Contacts

911 or

Colgate Energy LLC. (432) 695-4222

Vice President of Operations:

Casey McCain (432) 664-6140

Drilling Engineering Supervisor

Rafael Madrid (432) 556-6387

Drilling Engineering Technical Adviser

Steven Segrest (405) 550-0277

Operations Superintendent

Rick Lawson (432) 530- 3188

Drilling Superintendent

Daniel Cameron (405) 933-0435

Onsite Supervision (H&P 481 Rig Managers)

Juan Gutierrez (970)394-4768

Jonathan Jackson (970)394-4768

Onsite Supervision (H&P 481 Company Men)

Pierre Dupuis (432)438-0114

Eric Rutherford (432)438-0114

Rolando Torres (432)438-0114

Trevor Hein (432)438-0114

Emergency Accommodations

Safety Solutions Office (432) 563-0400

Safety Solutions Dispatch (432) 556-2002

Craig Strasner (432) 894-0341 (Cell)

II. H₂S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H₂S).

Objective:

Prevent any and all accidents and prevent the uncontrolled release of H₂S into the atmosphere.
Provide proper evacuation procedures to cope with emergencies.
Provide immediate and adequate medical attention should an injury occur.

Purpose, Distribution and Updating of Contingency Plan:

The Purpose of this contingency plan is to protect the general public from the harmful effects of H₂S accidentally escaping from the subject producing well. This plan is designed to accomplish its purpose by assuring the preparedness necessary to:

1. Minimize the possibility of releasing H₂S into the atmosphere during related operations.
2. Provide for the logical, efficient, and safe emergency actions required to protect the general public in the event of an accidental release of a potentially hazardous quantity of H₂S.

Supplemental information is included with this plan and is intended as reference material for anyone needing a more detailed understanding of the many factors pertinent to H₂S drilling operations safety. The release of a potentially hazardous quantity of H₂S is highly unlikely. If such a release should occur however, obviously the exact time, rate, duration, and other pertinent facts will be known in advance thus, this contingency plan must necessarily be somewhat general. The plan does review in detail, as is reasonably possible, the type of accidental release that could possibly endanger the general public, the probable extent of such danger, and the emergency actions generally appropriate. In the event of such an accidental release, the specific actions to be taken will have to be determined at the time of release by the responsible personnel at the drilling location. Complete familiarity with this plan will help such personnel make the proper decisions rapidly. Familiarity with this plan is so required all operators, operator representatives, and drilling contractor supervisory personnel who could possibly be on duty at the drilling location at the time of an H₂S emergency.

IT IS THE RESPONSIBILITY OF THE OPERATOR TO ASSURE SUCH FAMILIARITY BEFORE DRILLING WITHIN 1000' OR THREE DAYS PRIOR TO PENETRATION OF THE SHALLOWEST FORMATION KNOWN OR SUSPECTED TO CONTAIN H₂S IN POTENTIALLY HAZARDOUS QUANTITIES, AND ALSO TO ASSURE THE TIMELY ACCOMPLISHMENT OF ALL THE OTHER ACTION SPECIFIED HERE IN.

As this contingency plan was prepared considerably in advance of the anticipated H₂S operation, the plan must be kept current if it is to effectively serve its purpose. The operators will be responsible for seeing that all copies are updated. Updating the plan is required when any changes to the personnel Call List (Section) including telephone numbers occur or when any pertinent data or plans for the well are altered. The plan must also be updated when any changes in the general public likely to be within the exposure area in the event of an

accidental release from the well bore of a potentially hazardous quantity of H₂S. Two copies of this plan shall be retained at the office of Colgate Energy. Two copies shall be retained at the drilling location.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 1000' before drilling into the first sour zone.

Emergency Response Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 1000' before drilling into the first sour zone.

Emergency call list: Included are the telephone numbers of all persons that would need to be contacted, should an H₂S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

Check Lists: Status check lists and procedural check lists have been included to ensure adherence to the plan.

General Information: A general information section has been included to supply support information.

III. OPERATING PROCEDURES

A. Blowout Preventer Drills

Due to the special piping and Mani folding necessary to handle poisonous gas, particular care will be taken to ensure that all rig personnel are completely familiar with their jobs during the drills. The Drilling Consultant and Tool Pusher (Rig Superintendent) are thoroughly familiar with the additional controls and piping necessary.

B. H₂S Alarm Drills

The Company Man and/ or designee will conduct frequent H₂S alarm drills for each crew by injecting a trace of H₂S where the detector will give an alarm. Under these conditions all personnel on location will put on air equipment and remain masked until all clear is announced.

C. Surface Annular Preventer/ Diverter System Testing

After installation of the surface annular preventer, Hydraulic Control Valve and diverter system, both are to be function tested. They also should be function tested frequently while drilling surface hole.

D. Blowout Preventer

After installation of the Blowout Preventer Stack, the stack will be pressure tested. The Choke manifold is also to be pressure tested at this time. This procedure will be repeated as required by the NMOCD, the BLM, or if any of the stack is nipped down. Also, at this time, the Blind and Pipe Rams are checked for correct operation.

E. Well Control Practice Drills and Safety Meeting for Crew Members

Pit drills are for the purpose of acquainting each member of the drilling crew with his duties in the event of an emergency. Drills will be held with each crew as frequently as required to thoroughly familiarize each man with his duties. Drills are to be held at least weekly from that time forward.

1. BOP Drill while on Bottom Drilling:

A. Signal will be three or more long blast given by driller on the horn.

B. Procedure will be as follows:

1. Tool Pusher: Supervises entire operation.

2. Driller

a. Gives signal.

b. Picks up Kelly.

c. Stops pumps.

d. Observes flow.

e. Signal to close (pipe rams if necessary).

f. Check that Choke Manifold is closed.

g. Record drill pipe pressure, casing pressure and determine mud volume gain.

3. Motorman

a. Go to closing unit and standby for signal to close BOP.

b. Close BOP in signal.

c. Check on BOP closing.

d. Go to floor to assist driller. (NOTE: During test drills the BOP

need not be completely closed at the discretion of the supervisor. Supervisor should make it very clear that it is a test drill only!)

4. Derrickman
 - a. Check pumps.
 - b. Go to floor for directions from the driller.
 5. Floorman
 - a. Go to manifold.
 - b. Observe and record pressure.
 - c. Check manifold and BOP for leaks.
 - d. Check with driller for additional instructions.
2. BOP Drill While Making Trip:
- A. During trip driller will fill hole every five (5) stands and check the pits to be sure hole is taking mud.
 - B. Drill Procedure is as follows:
 1. Driller
 - a. Order Safety valve installed.
 - b. Alert those not on the floor.
 - c. Go to stations as described in above drill.
3. Safety Meetings
- A. Every person involved in the operating will be informed of the characteristics of H₂S, its danger and safety procedures to be used when it is encountered, and recommended first-aid procedure for regular rig personnel. This will be done through a series of talks made before spud.
 - B. The Safety Advisor or Drilling Supervisor will conduct these training sessions and will repeat them as deemed necessary by him or as instructed by Colgate Energy. Talks may include the following subjects:
 1. Dangers of Hydrogen Sulfide (H₂S).
 2. Use and limitations of air equipment.
 3. Use of resuscitator.
 4. Organize Buddy System.
 5. First Aid procedures.
 6. Use of H₂S detection devices.
 7. Designate responsible people.
 8. Explain rig layout and policy to visitors.
 - a. Designate smoking and safety or Muster area.
 - b. Emphasize the importance of wind directions.
 9. Describe and explain operation of BOP stack, manifold, separator, and pit piping. Include maximum allowable pressure for casing procedure.
 10. Explain functions of Safety Supervisor.
 11. Explain organize H₂S Drills.
 12. Explain the overall emergency plan with emphasis given to the evacuation phase of the plans.

- Note: The above talks will be attended by every person involved in the operation. When drilling has reached a depth where H₂S is anticipated, temporary service personnel and visitors will be directed to the Drilling Consultant, who will designate the air equipment to be used by them in case of emergency, acquaint them with the dangers involved and be sure of their safety while they are in the area. He will point out the Briefing Areas, Windsocks, and Smoking Areas. He may refuse entrance to anyone, who in his opinion should not be admitted because of lack of safety equipment, special operations in progress or for other reasons involving personnel safety.

F. Outside Service Personnel

All service people such as cementing crews, logging crews, specialist, mechanics, and welders will furnish their own safety equipment. The Company Man/ or designee will be sure that the number of people on location does not exceed the number of masks on location, and they have been briefed regarding safety procedures. He will also be sure each of these people know about smoking and "Briefing Areas" and know what to do in case of an emergency alert or drill. Visitors will be restricted, except with special permission from the Drilling Consultant, when H₂S might be encountered. They will be briefed as to what to do in case of an alert or drill.

G. Onsite/ off shift workers

All workers that are staying on site must be identified as to where they are staying while off tour. If a drill/ or emergency takes place related to an H₂S release, each crew must have a designated person(s) that will wake them up and ensure that they are cleared to the appropriate muster area immediately.

H. Simultaneous Operations (SIMOPS)

If work is going on adjacent to the location is the responsibility of the Drilling Consultant or designee to communicate any applicable risks that may affect personnel working on that adjacent location. In the case of an H₂S drill or event, there should be a designated crew member that is responsible for contacting personnel on adjacent locations. This could include just communication on potential events or in case of an event, notification to evacuate location. Drilling Consultant or designee are the Point of Contact and oversee all activities at such point of an H₂S event occurrence.

I. Area Residences/ Occupied Locations/ Public Roads

Any occupied residences/ businesses that are within a reasonable perimeter of the location (attached map will identify a 3000' radius around location) should be identified as part of this contingency and a reasonable effort will be made to gain contact information for them. As part of the briefing of the contingency plan, the team reviewing should identify where these potential receptors are and plan on who will contact them in case of a release that may impact that area.

J. Drilling Fluids

Drilling Fluid Monitoring – On Any Hazardous H₂S gas well, the earlier the warning of danger the better chance to control operations. Mud Company will be in daily contact with Colgate Energy Consultant. The Mud Engineer will take samples of the mud, analyze these samples, and make necessary recommendations to prevent H₂S gas from the formation, the pH will be increased as necessary for corrosion control.

pH Control – For normal drilling, pH of 10.5 – 11.5. Would be enough for corrosion protection. If there is an influx of H₂S gas from the formation, the pH will be increased as necessary for corrosion control.

H₂S Scavengers – If necessary H₂S scavengers will be added to the drilling mud.

IV. OPERATING CONDITIONS

A. Posting Well Condition Flags

Post the green, yellow or red well condition flag, as appropriate, on the well condition sign at the location entrance, and take necessary precautions as indicated below:

1. **Green Flag:** Potential Danger- When Drilling in known H₂S zones or when H₂S has been detected in the drilling fluid atmosphere. Protective breathing equipment shall be inspected, and all personnel on duty shall be alerted to be ready to use this equipment.
2. **Yellow Flag:** Potential Danger- When the threshold limit value of H₂S (10 PPM) or of SO₂ (5 PPM) is reached. If the concentration of H₂S or SO₂ reaches 10 PPM, protective breathing equipment shall be worn by all working personnel, and non-working personnel shall go to the upwind Safe Briefing Area.
3. **Red Flag:** Extreme danger*- When the ambient concentration of H₂S or SO₂ is reasonably believed or determined to have exceeded the potentially hazardous level. All non-essential personnel shall leave the drilling location taking the route most likely to exposure to escaping gas.

B. Requiring Air Masks Conditions

1. Whenever air masks are used, the person must be clean shaven as shown in the APC Guidelines
2. When breaking out any line where H₂S can reasonably be expected.
3. When sampling air in areas to determine if toxic concentrations of H₂S exist.
4. When working in areas where 10 PPM or more of H₂S has been detected.
5. At any time, there is doubt as to the H₂S level in the area to be entered.

C. Kick Procedure

1. It is very important that the driller be continuously alert, especially when approaching a gas formation.
2. Should gas come into the well bore, it is very important to be aware of a kick at the earliest time.
3. If a kick is identified, follow appropriate diverter or shut in procedures according to the situation that is presented utilizing appropriate kick procedures.

V. EMERGENCY PROCEDURES

- I. In the event of any evidence of H₂S level above 10ppm, take the following steps immediately:
 - a. Secure breathing apparatus.
 - b. Order non-essential personnel out of the danger zone.
 - c. Take steps to determine if the H₂S level can be corrected or suppressed, and if so, proceed with normal operations.

- II. If uncontrollable conditions occur, proceed with the following:
 - a. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel.
 - b. Remove all personnel to the Safe Briefing Area.
 - c. Notify public safety personnel for help with maintaining roadblocks, thus limiting traffic and implementing evacuation.
 - d. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.

- III. Responsibility
 - a. The Company Approved Supervisor shall be responsible for the total implementation of the plan.
 - b. The Company Approved Supervisor shall be in complete command during any emergency.
 - c. The Company Approved Supervisor shall designate a backup Supervisor if he/she is not available.

- IV. Actions to be taken
 - a. Assign specific tasks to drilling location personnel
 - b. Evacuate the general public from the exposure area
 - c. Cordon off the exposure area to prevent entry by unauthorized persons
 - d. Request assistance if and as needed and initiate emergency notifications
 - e. Stop the dispersion of H₂S
 - f. Complete emergency notifications as required
 - g. Return the situation to normal

EMERGENCY PROCEDURE IMPLEMENTATION**I. Drilling or Tripping****a. All Personnel**

- i. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
- ii. Check status of other personnel (buddy system).
- iii. Secure breathing apparatus.
- iv. Wait for orders from supervisor.

b. Drilling Consultant

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

c. Tool Pusher

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Drilling Consultant or the Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

d. Driller

- i. Check the status of other personnel (in a rescue attempt, always use the buddy system).
- ii. Assign the least essential person to notify the Drilling Consultant and Tool Pusher, in the event of their absence.
- iii. Assume the responsibility of the Drilling Consultant and the Tool Pusher until they arrive, in the event of their absence.

e. Derrick Man and Floor Hands

- i. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

f. Mud Engineer

- i. Report to the upwind Safe Briefing Area.
- ii. When instructed, begin check of mud for pH level and H₂S level.

g. Safety Personnel

- i. Don Breathing Apparatus.
- ii. Check status of personnel.
- iii. Wait for instructions from Drilling Consultant or Tool Pusher.

II. Taking a Kick

- a. All Personnel report to the upwind Safe Briefing Area.
- b. Follow standard BOP/ diverter procedures.

III. Open Hole Logging

- a. All unnecessary personnel should leave the rig floor.
- b. Drilling Consultant and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

- a. Follow "Drilling or Tripping" procedures.
- b. Assure that all personnel have access to protective equipment.

VI. POST EMERGENCY ACTIONS

In the event this plan is activated, the following post emergency actions shall be taken in an effort to reduce the possibility of a reoccurrence of the type of problem that required its activation, and/or assure that any future activation of a similar plan will be as effective as possible.

- A. Review the factors that caused or permitted the emergency occur, and if the need is indicated, modify operating, maintenance and/or surveillance procedures.
- B. If the need is indicated, retrain employees in blowout prevention, H₂S emergency procedures and etc.
- C. Clean up, recharge, restock, repair, and/ or replace H₂S emergency equipment as necessary, and return it to its proper place. (For whatever rental equipment is used, this will be the responsibility of Rental Company).
- D. See that future H₂S drilling contingency plans are modified accordingly, if the need is indicated.

VII. IGNITION PROCEDURES

Responsibilities:

The decision to ignite the well is the responsibility of the DRILLING CONSULTANT in concurrence with the STATE POLICE. In the event the Drilling Consultant is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Consultant is responsible for igniting the well.
2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.
3. Ignite from upwind and do not approach any closer than is warranted.
4. Select the ignition site best suited for protection and which offers an easy escape route.
5. Before igniting, check for the presence of combustible gases.
6. After igniting, continue emergency actions and procedures as before.
7. All unassigned personnel will limit their actions to those directed by the Drilling Consultant.

Note: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide, which is also highly toxic. Also, both are heavier than air. Do not assume the area is safe even after the well is ignited.

VIII. TRAINING PROGRAM

When working in an area where Hydrogen Sulfide (H₂S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel, at the well site, have had adequate training in the following:

1. Hazards and characteristics of Hydrogen Sulfide (H₂S).
2. Physical effects of Hydrogen Sulfide on the human body.
3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
4. H₂S detection, Emergency alarm and sensor location.
5. Don and Doff of SCBA and be clean shaven.
6. Emergency rescue.
7. Resuscitators.
8. First aid and artificial resuscitation.
9. The effects of Hydrogen Sulfide on metals.
10. Location safety.

Service company personnel and visiting personnel must be notified if the zone contains H₂S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

IX. EMERGENCY EQUIPMENT

Lease Entrance Sign:

Should be located at the lease entrance with the following information:

CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the safe briefing areas and should include the following:
- Two SCBA's at each briefing area.
- Enough airline units to operate safely, anytime the H₂S concentration reaches the IDLH level (100 ppm).

- Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Windssocks or Wind Streamers:

- A minimum of two 10" windssocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should always be placed at various locations on the well site to ensure wind consciousness. (Corners of location).

Hydrogen Sulfide Detector and Alarms:

- 1 - Four channel H₂S monitor with alarms.
- Three (3) sensors located as follows: #1 – Rig Floor, #2 – Shale Shaker, #3 – Cellar.
- Gastec or Draeger pump with tubes.
- Sensor test gas.

Well Condition Sign and Flags:

The Well Condition Sign w/flags should be placed a minimum of 150' before you enter the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions
YELLOW – Potential Danger
RED – Danger, H₂S Gas Present

Auxiliary Rescue Equipment:

- Stretcher
- 2 – 100' Rescue lines.
- First Aid kit properly stocked.

Mud Inspection Equipment:

Garret Gas Train or Hach Tester for inspection of Hydrogen Sulfide in the drilling mud system.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Blowout Preventer:

- The well shall have hydraulic BOP equipment for the anticipated bottom hole pressure (BHP).
- The BOP should be tested upon installation.
- BOP, Choke Line and Kill Line will be tested as specified by Operator.

Confined Space Monitor:

There should be a portable multi-gas monitor with at least 3 sensors (O₂, LEL H₂S), preferably 4 (O₂, LEL, H₂S, CO). This instrument should be used to test the atmosphere of any confined space before entering. It should also be used for atmospheric testing for LEL gas before beginning any type of Hot Work. Proper calibration documentation will need to be provided.

Communication Equipment:

- Proper communication equipment such as cell phones or 2-way radios should be available at the rig.
- Radio communication shall be available for communication between the company man's trailer, rig floor and the tool pusher's trailer.
- Communication equipment shall be available on the vehicles.

Special Control Equipment:

- Hydraulic BOP equipment with remote control on the ground.
- Rotating head at the surface casing point.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:***Parking and Visitor area:***

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- Designated smoking area.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds, or they are at a 180-degree angle if wind directions tend to shift in the area.
- Personal protective equipment should be stored at both briefing areas and if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

Note:

- Additional equipment will be available at the H₂S Provider Safety office.
- Additional personal H₂S monitors are available for all employees on location.
- Automatic Flare Igniters are recommended for installation on the rig.

X. CHECKLISTS

Rig-up & Equipment Status Check List

Note: Initial & Date each item as they are implemented. Multiple wells require additional Columns to be Dated/ Initialed

	Date & Initial 1 st Well	Date & Initial 2 nd Well	Date & Initial 3 rd Well	Date & Initial 4 th Well
Sign at location entrance.				
Two (2) windsocks (in required locations).				
Wind Streamers (if required).				
SCBA's on location (Minimum of 2 @ each Muster Area)				
Air packs (working packs and escape packs), inspected and ready for use.				
Spare bottles for each air pack (if required).				
Cascade system and hose line hook up.				
Choke manifold hooked-up and tested. (before drilling out surface casing.)				
Remote Hydraulic BOP control tested (before drilling out surface casing).				
BOP tested (before drilling out surface casing).				
Safe Briefing Areas set-up				
Well Condition sign and flags on location and ready.				
Hydrogen Sulfide detection/ alarm system hooked-up & tested.				
Stretcher on location				
2 – 100' Lifelines on location.				
1 – 20# Fire Extinguisher in safety trailer.				
Confined Space monitor on location and tested.				
All rig crews and supervisor trained (as required).				
All rig crews and supervision medically qualified and fit tested on proper respirators				
Access restricted for unauthorized personnel.				
Pre-spud meeting held reviewing Contingencies				
Drills on H ₂ S and well control procedures.				
All outside service contractors advised of potential H ₂ S on the well.				
25mm Flare Gun on location w/flares.				

Procedural Check List

Perform the following on each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that they have not been tampered with.
3. Check pressure on the supply air bottles to make sure they are capable of recharging.
4. Make sure all the Hydrogen Sulfide detection systems are operative.
5. Ensure that all BOP/ Surface Annular/ Diverter systems are functioning and operational.

Perform the following each week:

1. Check each piece of breathing equipment to make sure that they are fully charged and operational. This requires that the air cylinder be opened, and the mask assembly be put on and tested to make sure that the regulators and masks are properly working. Negative and Positive pressure should be conducted on all masks.
2. BOP skills.
3. Check supply pressure on BOP accumulator stand-by source.
4. Check all breathing air mask assemblies to see that straps are loosened and turned back, ready for use.
5. Check pressure on cascade air cylinders to make sure they are fully charged and ready to use for refill purposes if necessary.
6. Check all cascade system regulators to make sure they work properly.
7. Perform breathing drills with on-site personnel.
8. Check the following supplies for availability (may be with H₂S Techs On-call):
 - Stretcher
 - Safety Belts and Ropes
 - Spare air Bottles
 - Spare Oxygen Bottles (if resuscitator required)
 - Gas Detector Pump and Tubes
 - Emergency telephone lists
 - Test the Confined Space Monitor to verify the batteries are good.

XI. BRIEFING PROCEDURES

The following scheduled briefings will be held to ensure the effective drilling and operation of this project:

Pre-Spud Meeting

Date: Prior to spudding the well.

Attendance: Drilling Supervisor
 Drilling Engineer
 Drilling Consultant
 Rig Tool Pushers
 Rig Drillers
 Mud Engineer
 All Safety Personnel
 Key Service Company Personnel

Purpose: Review and discuss the well program, step-by-step, to insure complete understanding of assignments and responsibilities.

XII. EVACUATION PLAN

General Plan

The direct lines of action prepared by Colgate Energy to protect the public from hazardous gas situations are as follows:

1. When the company approved supervisor (Drilling Consultant, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the area map.
2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists, and evacuation needs to be implemented.
3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.
4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining roadblocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, "Company" personnel will determine when the area is safe for re-entry.
6. If a major release is secured, all exposed housing, vehicles, rig buildings, and low-lying areas and other structures downwind must be tested and clear with SCBAs donned to ensure that all residual H₂S is cleared. Fans, or opening of doors is recommended to ensure that areas are cleared out as part of this process.

XIII. APPENDICES AND GENERAL INFORMATION

Radius of Exposure Affected Notification List

(within a 65' radius of exposure @100ppm)

The geologic zones that will be encountered during drilling are known to contain hazardous quantities of H₂S. The accompanying map illustrates the affected areas of the community. The residents within this radius will be notified via a hand delivered written notice describing the activities, potential hazards, conditions of evacuation, evacuation drill siren alarms and other precautionary measures.

Evacuee Description: Residents:

Notification Process:

A continuous siren audible to all residence will be activated, signaling evacuation of previously notified and informed residents.

Evacuation Plan:

All evacuees will migrate lateral to the wind direction.

The Operating Company will identify all home bound or highly susceptible individuals and make special evacuation preparations, interfacing with the local and emergency medical service as necessary.

Toxic Effects of H₂S Poisoning

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity – 1.192) and is colorless and transparent. Hydrogen Sulfide is almost as toxic as Hydrogen Cyanide and is 5-6 times more toxic than Carbon Monoxide. Occupational exposure limits for Hydrogen Sulfide and other gases are compared below in Table 1. Toxicity table for H₂S and physical effects are shown in Table 2.

Table 1
Permissible Exposure Limits of Various Gases

<u>Common Name</u>	<u>Symbol</u>	<u>Sp. Gravity</u>	<u>TLV</u>	<u>STEL</u>	<u>IDLH</u>
Hydrogen Cyanide	HCN	.94	4.7 ppm	4.7 ppm	50 ppm
Hydrogen Sulfide	H ₂ S	1.192	10 ppm	15 ppm	100 ppm
Sulfide Dioxide	SO ₂	2.21	2 ppm	5 ppm	100 ppm
Chlorine	CL	2.45	.5 ppm	1 ppm	10 ppm
Carbon Monoxide	CO	.97	25 ppm	200 ppm	1200 ppm
Carbon Dioxide	CO ₂	1.52	5000 ppm	30,000 ppm	40,000 ppm
Methane	CH ₄	.55	5% LEL	15% UEL	

Definitions

- A. TLV – Threshold Limit Value is the concentration employees may be exposed based on a TWA (time weighted average) for eight (8) hours in one day for 40 hours in one (1) week. This is set by ACGIH (American Conference of Governmental Hygienists) and regulated by OSHA.
- B. STEL – Short Term Exposure Limit is the 15-minute average concentration an employee may be exposed to providing that the highest exposure never exceeds the OEL (Occupational Exposure Limit). The OEL for H₂S is 20 PPM.
- C. IDLH – Immediately Dangerous to Life and Health is the concentration that has been determined by the ACGIH to cause serious health problems or death if exposed to this level. The IDLH for H₂S is 100 PPM.
- D. TWA – Time Weighted Average is the average concentration of any chemical or gas for an eight (8) hour period. This is the concentration that any employee may be exposed based on a TWA.

Toxicity Table of H₂S

<u>Percent %</u>	<u>PPM</u>	<u>Physical Effects</u>
.0001	1	Can smell less than 1 ppm.
.001	10	TLV for 8 hours of exposure.
.0015	15	STEL for 15 minutes of exposure.
.01	100	Immediately Dangerous to Life & Health. Kills sense of smell in 3 to 5 minutes.
.02	200	Kills sense of smell quickly, may burn eyes and throat.
.05	500	Dizziness, cessation of breathing begins in a few minutes .
.07	700	Unconscious quickly, death will result if not rescued promptly.
.10	1000	Death will result unless rescued promptly. Artificial resuscitation may be necessary.

PHYSICAL PROPERTIES OF H₂S

The properties of all gases are usually described in the context of seven major categories:

- COLOR
- ODOR
- VAPOR DENSITY
- EXPLOSIVE LIMITS
- FLAMMABILITY
- SOLUBILITY (IN WATER)
- BOILING POINT

Hydrogen Sulfide is no exception. Information from these categories should be considered in order to provide a complete picture of the properties of the gas.

COLOR – TRANSPARENT

Hydrogen Sulfide is colorless, so it is invisible. This fact simply means that you can't rely on your eyes to detect its presence. In fact, that makes this gas extremely dangerous to be around.

ODOR – ROTTEN EGGS

Hydrogen Sulfide has a distinctive offensive smell, like "rotten eggs". For this reason, it earned its common name "sour gas". However, H₂S, even in low concentrations, is so toxic that it attacks and quickly impairs a victim's sense of smell, so it could be fatal to rely on your nose as a detection device.

VAPOR DENSITY – SPECIFIC GRAVITY OF 1.192

Hydrogen Sulfide is heavier than air, so it tends to settle in low-lying areas like pits, cellars or tanks. If you find yourself in a location where H₂S is known to exist, protect yourself. Whenever possible, work in an area upwind and keep to higher ground.

EXPLOSIVE LIMITS – 4.0% TO 44%

Mixed with the right proportion of air or oxygen, H₂S will ignite and burn or explode, producing another alarming element of danger besides poisoning.

FLAMMABILITY

Hydrogen Sulfide will burn readily with a distinctive clear blue flame, producing Sulfur Dioxide (SO₂), another hazardous gas that irritates the eyes and lungs.

SOLUBILITY – 4 TO 1 RATIO WITH WATER

Hydrogen Sulfide can be dissolved in liquids, which means that it can be present in any container or vessel used to carry or hold well fluids including oil, water, emulsion and sludge. The solubility of H₂S is dependent on temperature and pressure, but if conditions are right, simply agitating a fluid containing H₂S may release the gas into the air.

BOILING POINT – (-77° Fahrenheit)

Liquefied Hydrogen Sulfide boils at a very low temperature, so it is usually found as a gas.

RESPIRATOR USE

The Occupational Safety and Health Administration (OSHA) regulate the use of respiratory protection to protect the health of employees. OSHA's requirements are written in the Code of Federal Regulations, Title 29, Part 1910, Section 134, Respiratory Protection. This regulation requires that all employees who might be required to wear respirators, shall complete an OSHA mandated medical evaluation questionnaire. The employee then should be fit tested prior to wearing any respirator while being exposed to hazardous gases.

Written procedures shall be prepared covering safe use of respirators in dangerous atmospheric situations, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available respirators.

Respirators shall be inspected prior to and after each use to make sure that the respirator has been properly cleaned, disinfected and that the respirator works properly. The unit should be fully charged prior to being used.

Anyone who may use respirators shall be properly trained in how to properly seal the face piece. They shall wear respirators in normal air and then in a test atmosphere. (Note: Such items as facial hair (beard or sideburns) and eyeglass temple pieces will not allow a proper seal.) Anyone who may be expected to wear respirators should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses. Contact lenses should not be allowed.

Respirators shall be worn during the following conditions:

- A. Any employee who works near the top or on the top of any tank unless tests reveal less than 20 ppm of H₂S.
- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas where H₂S may be present.
- D. When working in areas where the concentration of H₂S exceeds the Threshold Limit Value for H₂S (10 ppm).
- E. At any time where there is a doubt as to the H₂S level in the area to be entered.

EMERGENCY RESCUE PROCEDURES


DO NOT PANIC!!!

Remain Calm – Think

1. Before attempting any rescue, you must first get out of the hazardous area yourself. Go to a safe briefing area.
2. Sound alarm and activate the 911 system.
3. Put on breathing apparatus. At least two persons should do this, when available use the buddy system.
4. Rescue the victim and return them to a safe briefing area.
5. Perform an initial assessment and begin proper First Aid/CPR procedures.
6. Keep victim lying down with a blanket or coat, etc., under the shoulders to keep airway open. Conserve body heat and do not leave unattended.
7. If the eyes are affected by H₂S, wash them thoroughly with potable water. For slight irritation, cold compresses are helpful.
8. In case a person has only minor exposure and does not lose consciousness totally, it's best if he doesn't return to work until the following day.
9. Any personnel overcome by H₂S should always be examined by medical personnel. They should always be transported to a hospital or doctor.

Facial Hair – Clean Shaven Examples

Purpose: To define clean shaven expectations in the field for: 1) Respirator Use, if applicable and 2) First Aid Administration, if situation occurs related to H₂S exposure, having no facial hair can greatly benefit response time and treatment ability.





Colgate Energy

(Permit) Eddy County, NM (83-NME)

(Permit) Robin Fed DSU

(C04) Robin Fed 127H - Slot (C04)

Permit

Plan: APD-Rev01

Standard Planning Report

29 April, 2022



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Project	(Permit) Eddy County, NM (83-NME)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	(Permit) Robin Fed DSU				
Site Position:		Northing:	566,789.01 usft	Latitude:	32.55594366
From:	Map	Easting:	771,298.22 usft	Longitude:	-103.58696631
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "		

Well	(C04) Robin Fed 127H - Slot (C04)					
Well Position	+N-S	0.00 usft	Northing:	565,457.56 usft	Latitude:	32.55223072
	+E-W	0.00 usft	Easting:	774,053.97 usft	Longitude:	-103.57805349
Position Uncertainty		0.00 usft	Wellhead Elevation:	usft	Ground Level:	3,670.00 usft
Grid Convergence:	0.41 °					

Wellbore	Permit				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	3/15/2022	6.49	60.17	47,607.17723439

Design	APD-Rev01			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	359.56

Plan Survey Tool Program	Date	4/28/2022		
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	20,830.22 APD-Rev01 (Permit)	MWD+IFR1+SAG+FDIR (SQC OWSG MWD + IFR1 + Sag + F	



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,473.48	4.10	113.73	1,473.25	-3.94	8.96	1.50	1.50	0.00	113.73	
9,632.89	4.10	113.73	9,611.75	-238.84	543.29	0.00	0.00	0.00	0.00	
9,906.37	0.00	0.00	9,885.00	-242.78	552.25	1.50	-1.50	0.00	180.00	
10,001.25	0.00	0.00	9,979.88	-242.78	552.25	0.00	0.00	0.00	0.00	
10,601.25	60.00	11.00	10,476.08	38.44	606.91	10.00	10.00	0.00	11.00	
10,920.42	90.00	359.56	10,558.00	341.56	632.72	10.00	9.40	-3.58	-22.04	
20,830.22	90.00	359.56	10,558.00	10,251.06	556.28	0.00	0.00	0.00	0.00	03-PBHL(R-L127H)



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	1.50	113.73	1,299.99	-0.53	1.20	-0.54	1.50	1.50	0.00	0.00
1,400.00	3.00	113.73	1,399.91	-2.11	4.79	-2.14	1.50	1.50	0.00	0.00
1,473.48	4.10	113.73	1,473.25	-3.94	8.96	-4.01	1.50	1.50	0.00	0.00
1,500.00	4.10	113.73	1,499.70	-4.70	10.70	-4.78	0.00	0.00	0.00	0.00
1,555.44	4.10	113.73	1,555.00	-6.30	14.33	-6.41	0.00	0.00	0.00	0.00
Rustler										
1,600.00	4.10	113.73	1,599.44	-7.58	17.24	-7.71	0.00	0.00	0.00	0.00
1,665.73	4.10	113.73	1,665.00	-9.47	21.55	-9.64	0.00	0.00	0.00	0.00
Salado										
1,700.00	4.10	113.73	1,699.19	-10.46	23.79	-10.64	0.00	0.00	0.00	0.00
1,800.00	4.10	113.73	1,798.93	-13.34	30.34	-13.57	0.00	0.00	0.00	0.00
1,900.00	4.10	113.73	1,898.67	-16.22	36.89	-16.50	0.00	0.00	0.00	0.00
2,000.00	4.10	113.73	1,998.42	-19.10	43.44	-19.43	0.00	0.00	0.00	0.00
2,100.00	4.10	113.73	2,098.16	-21.98	49.99	-22.36	0.00	0.00	0.00	0.00
2,200.00	4.10	113.73	2,197.91	-24.85	56.54	-25.29	0.00	0.00	0.00	0.00
2,300.00	4.10	113.73	2,297.65	-27.73	63.08	-28.22	0.00	0.00	0.00	0.00
2,400.00	4.10	113.73	2,397.39	-30.61	69.63	-31.15	0.00	0.00	0.00	0.00
2,500.00	4.10	113.73	2,497.14	-33.49	76.18	-34.08	0.00	0.00	0.00	0.00
2,600.00	4.10	113.73	2,596.88	-36.37	82.73	-37.00	0.00	0.00	0.00	0.00
2,700.00	4.10	113.73	2,696.62	-39.25	89.28	-39.93	0.00	0.00	0.00	0.00
2,800.00	4.10	113.73	2,796.37	-42.13	95.83	-42.86	0.00	0.00	0.00	0.00
2,900.00	4.10	113.73	2,896.11	-45.01	102.38	-45.79	0.00	0.00	0.00	0.00
3,000.00	4.10	113.73	2,995.86	-47.89	108.93	-48.72	0.00	0.00	0.00	0.00
3,100.00	4.10	113.73	3,095.60	-50.76	115.47	-51.65	0.00	0.00	0.00	0.00
3,200.00	4.10	113.73	3,195.34	-53.64	122.02	-54.58	0.00	0.00	0.00	0.00
3,254.80	4.10	113.73	3,250.00	-55.22	125.61	-56.18	0.00	0.00	0.00	0.00
Tansill										
3,300.00	4.10	113.73	3,295.09	-56.52	128.57	-57.51	0.00	0.00	0.00	0.00
3,400.00	4.10	113.73	3,394.83	-59.40	135.12	-60.44	0.00	0.00	0.00	0.00
3,430.25	4.10	113.73	3,425.00	-60.27	137.10	-61.32	0.00	0.00	0.00	0.00
Yates										
3,500.00	4.10	113.73	3,494.57	-62.28	141.67	-63.37	0.00	0.00	0.00	0.00
3,600.00	4.10	113.73	3,594.32	-65.16	148.22	-66.30	0.00	0.00	0.00	0.00
3,655.82	4.10	113.73	3,650.00	-66.77	151.87	-67.93	0.00	0.00	0.00	0.00
Seven Rivers										
3,700.00	4.10	113.73	3,694.06	-68.04	154.77	-69.22	0.00	0.00	0.00	0.00
3,800.00	4.10	113.73	3,793.81	-70.92	161.31	-72.15	0.00	0.00	0.00	0.00
3,900.00	4.10	113.73	3,893.55	-73.80	167.86	-75.08	0.00	0.00	0.00	0.00
3,956.60	4.10	113.73	3,950.00	-75.43	171.57	-76.74	0.00	0.00	0.00	0.00
Capitan										



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
4,000.00	4.10	113.73	3,993.29	-76.67	174.41	-78.01	0.00	0.00	0.00	
4,100.00	4.10	113.73	4,093.04	-79.55	180.96	-80.94	0.00	0.00	0.00	
4,157.11	4.10	113.73	4,150.00	-81.20	184.70	-82.61	0.00	0.00	0.00	
Queen										
4,200.00	4.10	113.73	4,192.78	-82.43	187.51	-83.87	0.00	0.00	0.00	
4,300.00	4.10	113.73	4,292.53	-85.31	194.06	-86.80	0.00	0.00	0.00	
4,400.00	4.10	113.73	4,392.27	-88.19	200.61	-89.73	0.00	0.00	0.00	
4,500.00	4.10	113.73	4,492.01	-91.07	207.16	-92.66	0.00	0.00	0.00	
4,600.00	4.10	113.73	4,591.76	-93.95	213.70	-95.59	0.00	0.00	0.00	
4,700.00	4.10	113.73	4,691.50	-96.83	220.25	-98.52	0.00	0.00	0.00	
4,800.00	4.10	113.73	4,791.24	-99.71	226.80	-101.45	0.00	0.00	0.00	
4,900.00	4.10	113.73	4,890.99	-102.59	233.35	-104.37	0.00	0.00	0.00	
5,000.00	4.10	113.73	4,990.73	-105.46	239.90	-107.30	0.00	0.00	0.00	
5,100.00	4.10	113.73	5,090.48	-108.34	246.45	-110.23	0.00	0.00	0.00	
5,200.00	4.10	113.73	5,190.22	-111.22	253.00	-113.16	0.00	0.00	0.00	
5,300.00	4.10	113.73	5,289.96	-114.10	259.54	-116.09	0.00	0.00	0.00	
5,400.00	4.10	113.73	5,389.71	-116.98	266.09	-119.02	0.00	0.00	0.00	
5,500.00	4.10	113.73	5,489.45	-119.86	272.64	-121.95	0.00	0.00	0.00	
5,590.78	4.10	113.73	5,580.00	-122.47	278.59	-124.61	0.00	0.00	0.00	
Delaware Sands										
5,600.00	4.10	113.73	5,589.19	-122.74	279.19	-124.88	0.00	0.00	0.00	
5,700.00	4.10	113.73	5,688.94	-125.62	285.74	-127.81	0.00	0.00	0.00	
5,800.00	4.10	113.73	5,788.68	-128.50	292.29	-130.74	0.00	0.00	0.00	
5,900.00	4.10	113.73	5,888.43	-131.37	298.84	-133.67	0.00	0.00	0.00	
6,000.00	4.10	113.73	5,988.17	-134.25	305.39	-136.59	0.00	0.00	0.00	
6,100.00	4.10	113.73	6,087.91	-137.13	311.93	-139.52	0.00	0.00	0.00	
6,200.00	4.10	113.73	6,187.66	-140.01	318.48	-142.45	0.00	0.00	0.00	
6,300.00	4.10	113.73	6,287.40	-142.89	325.03	-145.38	0.00	0.00	0.00	
6,400.00	4.10	113.73	6,387.15	-145.77	331.58	-148.31	0.00	0.00	0.00	
6,500.00	4.10	113.73	6,486.89	-148.65	338.13	-151.24	0.00	0.00	0.00	
6,600.00	4.10	113.73	6,586.63	-151.53	344.68	-154.17	0.00	0.00	0.00	
6,700.00	4.10	113.73	6,686.38	-154.41	351.23	-157.10	0.00	0.00	0.00	
6,800.00	4.10	113.73	6,786.12	-157.28	357.77	-160.03	0.00	0.00	0.00	
6,900.00	4.10	113.73	6,885.86	-160.16	364.32	-162.96	0.00	0.00	0.00	
7,000.00	4.10	113.73	6,985.61	-163.04	370.87	-165.89	0.00	0.00	0.00	
7,100.00	4.10	113.73	7,085.35	-165.92	377.42	-168.82	0.00	0.00	0.00	
7,200.00	4.10	113.73	7,185.10	-168.80	383.97	-171.74	0.00	0.00	0.00	
7,300.00	4.10	113.73	7,284.84	-171.68	390.52	-174.67	0.00	0.00	0.00	
7,400.00	4.10	113.73	7,384.58	-174.56	397.07	-177.60	0.00	0.00	0.00	
7,500.00	4.10	113.73	7,484.33	-177.44	403.62	-180.53	0.00	0.00	0.00	
7,600.00	4.10	113.73	7,584.07	-180.32	410.16	-183.46	0.00	0.00	0.00	
7,700.00	4.10	113.73	7,683.81	-183.20	416.71	-186.39	0.00	0.00	0.00	
7,800.00	4.10	113.73	7,783.56	-186.07	423.26	-189.32	0.00	0.00	0.00	
7,900.00	4.10	113.73	7,883.30	-188.95	429.81	-192.25	0.00	0.00	0.00	
8,000.00	4.10	113.73	7,983.05	-191.83	436.36	-195.18	0.00	0.00	0.00	
8,100.00	4.10	113.73	8,082.79	-194.71	442.91	-198.11	0.00	0.00	0.00	
8,200.00	4.10	113.73	8,182.53	-197.59	449.46	-201.04	0.00	0.00	0.00	
8,300.00	4.10	113.73	8,282.28	-200.47	456.00	-203.96	0.00	0.00	0.00	
8,400.00	4.10	113.73	8,382.02	-203.35	462.55	-206.89	0.00	0.00	0.00	
8,493.22	4.10	113.73	8,475.00	-206.03	468.66	-209.62	0.00	0.00	0.00	
Bone Spring										
8,500.00	4.10	113.73	8,481.77	-206.23	469.10	-209.82	0.00	0.00	0.00	
8,600.00	4.10	113.73	8,581.51	-209.11	475.65	-212.75	0.00	0.00	0.00	



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,700.00	4.10	113.73	8,681.25	-211.98	482.20	-215.68	0.00	0.00	0.00	
8,800.00	4.10	113.73	8,781.00	-214.86	488.75	-218.61	0.00	0.00	0.00	
8,900.00	4.10	113.73	8,880.74	-217.74	495.30	-221.54	0.00	0.00	0.00	
9,000.00	4.10	113.73	8,980.48	-220.62	501.85	-224.47	0.00	0.00	0.00	
9,100.00	4.10	113.73	9,080.23	-223.50	508.39	-227.40	0.00	0.00	0.00	
9,200.00	4.10	113.73	9,179.97	-226.38	514.94	-230.33	0.00	0.00	0.00	
9,300.00	4.10	113.73	9,279.72	-229.26	521.49	-233.26	0.00	0.00	0.00	
9,400.00	4.10	113.73	9,379.46	-232.14	528.04	-236.19	0.00	0.00	0.00	
9,500.00	4.10	113.73	9,479.20	-235.02	534.59	-239.11	0.00	0.00	0.00	
9,570.98	4.10	113.73	9,550.00	-237.06	539.24	-241.19	0.00	0.00	0.00	
FBSG										
9,600.00	4.10	113.73	9,578.95	-237.89	541.14	-242.04	0.00	0.00	0.00	
9,632.89	4.10	113.73	9,611.75	-238.84	543.29	-243.01	0.00	0.00	0.00	
9,700.00	3.10	113.73	9,678.73	-240.54	547.15	-244.73	1.50	-1.50	0.00	
9,800.00	1.60	113.73	9,778.64	-242.18	550.89	-246.41	1.50	-1.50	0.00	
9,906.37	0.00	0.00	9,885.00	-242.78	552.25	-247.01	1.50	-1.50	0.00	
10,001.25	0.00	0.00	9,979.88	-242.78	552.25	-247.01	0.00	0.00	0.00	
KOP: 10001.25' MD, -247.01' VS,9979.88' TVD										
10,022.05	2.08	11.00	10,000.67	-242.41	552.32	-246.64	10.00	10.00	0.00	
00-EON(R-L127H)										
10,050.00	4.87	11.00	10,028.57	-240.75	552.65	-244.98	10.00	10.00	0.00	
10,100.00	9.87	11.00	10,078.14	-234.45	553.87	-238.69	10.00	10.00	0.00	
10,147.97	14.67	11.00	10,125.00	-224.44	555.81	-228.70	10.00	10.00	0.00	
SBSG										
10,150.00	14.87	11.00	10,126.96	-223.93	555.91	-228.19	10.00	10.00	0.00	
10,182.28	18.10	11.00	10,157.91	-214.94	557.66	-219.22	10.00	10.00	0.00	
100FSL										
10,200.00	19.87	11.00	10,174.67	-209.28	558.76	-213.56	10.00	10.00	0.00	
10,250.00	24.87	11.00	10,220.89	-190.60	562.39	-194.92	10.00	10.00	0.00	
10,300.00	29.87	11.00	10,265.27	-168.04	566.78	-172.39	10.00	10.00	0.00	
10,350.00	34.87	11.00	10,307.49	-141.77	571.88	-146.16	10.00	10.00	0.00	
10,400.00	39.87	11.00	10,347.21	-111.98	577.67	-116.42	10.00	10.00	0.00	
10,450.00	44.87	11.00	10,384.14	-78.92	584.10	-83.40	10.00	10.00	0.00	
10,478.44	47.72	11.00	10,403.78	-58.74	588.02	-63.25	10.00	10.00	0.00	
01-FTP(R-L127H)										
10,500.00	49.87	11.00	10,417.99	-42.81	591.12	-47.35	10.00	10.00	0.00	
10,550.00	54.87	11.00	10,448.50	-3.95	598.67	-8.55	10.00	10.00	0.00	
10,601.25	60.00	11.00	10,476.08	38.44	606.91	33.77	10.00	10.00	0.00	
10,650.00	64.53	8.98	10,498.76	80.92	614.38	76.20	10.00	9.30	-4.15	
10,700.00	69.21	7.05	10,518.39	126.44	620.77	121.67	10.00	9.35	-3.85	
10,750.00	73.91	5.25	10,534.20	173.58	625.84	168.77	10.00	9.39	-3.61	
10,800.00	78.62	3.52	10,546.07	222.00	629.55	217.15	10.00	9.42	-3.45	
10,850.00	83.34	1.86	10,553.91	271.31	631.86	266.45	10.00	9.44	-3.33	
10,900.00	88.07	0.22	10,557.65	321.14	632.76	316.27	10.00	9.45	-3.27	
10,920.42	90.00	359.56	10,558.00	341.56	632.72	336.69	10.00	9.46	-3.25	
EOC: 10920.42' MD, 336.69' VS,10558.00' TVD										
11,000.00	90.00	359.56	10,558.00	421.14	632.11	416.27	0.00	0.00	0.00	
11,100.00	90.00	359.56	10,558.00	521.13	631.34	516.27	0.00	0.00	0.00	
11,200.00	90.00	359.56	10,558.00	621.13	630.57	616.27	0.00	0.00	0.00	
11,300.00	90.00	359.56	10,558.00	721.13	629.80	716.27	0.00	0.00	0.00	
11,400.00	90.00	359.56	10,558.00	821.13	629.02	816.27	0.00	0.00	0.00	
11,500.00	90.00	359.56	10,558.00	921.12	628.25	916.27	0.00	0.00	0.00	
11,600.00	90.00	359.56	10,558.00	1,021.12	627.48	1,016.27	0.00	0.00	0.00	



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
11,700.00	90.00	359.56	10,558.00	1,121.12	626.71	1,116.27	0.00	0.00	0.00	
11,800.00	90.00	359.56	10,558.00	1,221.11	625.94	1,216.27	0.00	0.00	0.00	
11,900.00	90.00	359.56	10,558.00	1,321.11	625.17	1,316.27	0.00	0.00	0.00	
12,000.00	90.00	359.56	10,558.00	1,421.11	624.40	1,416.27	0.00	0.00	0.00	
12,100.00	90.00	359.56	10,558.00	1,521.10	623.62	1,516.27	0.00	0.00	0.00	
12,200.00	90.00	359.56	10,558.00	1,621.10	622.85	1,616.27	0.00	0.00	0.00	
12,300.00	90.00	359.56	10,558.00	1,721.10	622.08	1,716.27	0.00	0.00	0.00	
12,400.00	90.00	359.56	10,558.00	1,821.10	621.31	1,816.27	0.00	0.00	0.00	
12,500.00	90.00	359.56	10,558.00	1,921.09	620.54	1,916.27	0.00	0.00	0.00	
12,600.00	90.00	359.56	10,558.00	2,021.09	619.77	2,016.27	0.00	0.00	0.00	
12,700.00	90.00	359.56	10,558.00	2,121.09	619.00	2,116.27	0.00	0.00	0.00	
12,800.00	90.00	359.56	10,558.00	2,221.08	618.22	2,216.27	0.00	0.00	0.00	
12,900.00	90.00	359.56	10,558.00	2,321.08	617.45	2,316.27	0.00	0.00	0.00	
13,000.00	90.00	359.56	10,558.00	2,421.08	616.68	2,416.27	0.00	0.00	0.00	
13,100.00	90.00	359.56	10,558.00	2,521.07	615.91	2,516.27	0.00	0.00	0.00	
13,200.00	90.00	359.56	10,558.00	2,621.07	615.14	2,616.27	0.00	0.00	0.00	
13,300.00	90.00	359.56	10,558.00	2,721.07	614.37	2,716.27	0.00	0.00	0.00	
13,400.00	90.00	359.56	10,558.00	2,821.07	613.60	2,816.27	0.00	0.00	0.00	
13,500.00	90.00	359.56	10,558.00	2,921.06	612.82	2,916.27	0.00	0.00	0.00	
13,600.00	90.00	359.56	10,558.00	3,021.06	612.05	3,016.27	0.00	0.00	0.00	
13,700.00	90.00	359.56	10,558.00	3,121.06	611.28	3,116.27	0.00	0.00	0.00	
13,800.00	90.00	359.56	10,558.00	3,221.05	610.51	3,216.27	0.00	0.00	0.00	
13,900.00	90.00	359.56	10,558.00	3,321.05	609.74	3,316.27	0.00	0.00	0.00	
14,000.00	90.00	359.56	10,558.00	3,421.05	608.97	3,416.27	0.00	0.00	0.00	
14,100.00	90.00	359.56	10,558.00	3,521.04	608.20	3,516.27	0.00	0.00	0.00	
14,200.00	90.00	359.56	10,558.00	3,621.04	607.42	3,616.27	0.00	0.00	0.00	
14,300.00	90.00	359.56	10,558.00	3,721.04	606.65	3,716.27	0.00	0.00	0.00	
14,400.00	90.00	359.56	10,558.00	3,821.04	605.88	3,816.27	0.00	0.00	0.00	
14,500.00	90.00	359.56	10,558.00	3,921.03	605.11	3,916.27	0.00	0.00	0.00	
14,600.00	90.00	359.56	10,558.00	4,021.03	604.34	4,016.27	0.00	0.00	0.00	
14,700.00	90.00	359.56	10,558.00	4,121.03	603.57	4,116.27	0.00	0.00	0.00	
14,800.00	90.00	359.56	10,558.00	4,221.02	602.80	4,216.27	0.00	0.00	0.00	
14,900.00	90.00	359.56	10,558.00	4,321.02	602.03	4,316.27	0.00	0.00	0.00	
15,000.00	90.00	359.56	10,558.00	4,421.02	601.25	4,416.27	0.00	0.00	0.00	
15,100.00	90.00	359.56	10,558.00	4,521.02	600.48	4,516.27	0.00	0.00	0.00	
15,200.00	90.00	359.56	10,558.00	4,621.01	599.71	4,616.27	0.00	0.00	0.00	
15,300.00	90.00	359.56	10,558.00	4,721.01	598.94	4,716.27	0.00	0.00	0.00	
15,400.00	90.00	359.56	10,558.00	4,821.01	598.17	4,816.27	0.00	0.00	0.00	
15,500.00	90.00	359.56	10,558.00	4,921.00	597.40	4,916.27	0.00	0.00	0.00	
15,600.00	90.00	359.56	10,558.00	5,021.00	596.63	5,016.27	0.00	0.00	0.00	
15,700.00	90.00	359.56	10,558.00	5,121.00	595.85	5,116.27	0.00	0.00	0.00	
15,800.00	90.00	359.56	10,558.00	5,220.99	595.08	5,216.27	0.00	0.00	0.00	
15,900.00	90.00	359.56	10,558.00	5,320.99	594.31	5,316.27	0.00	0.00	0.00	
16,000.00	90.00	359.56	10,558.00	5,420.99	593.54	5,416.27	0.00	0.00	0.00	
16,100.00	90.00	359.56	10,558.00	5,520.99	592.77	5,516.27	0.00	0.00	0.00	
16,200.00	90.00	359.56	10,558.00	5,620.98	592.00	5,616.27	0.00	0.00	0.00	
16,300.00	90.00	359.56	10,558.00	5,720.98	591.23	5,716.27	0.00	0.00	0.00	
16,400.00	90.00	359.56	10,558.00	5,820.98	590.45	5,816.27	0.00	0.00	0.00	
16,500.00	90.00	359.56	10,558.00	5,920.97	589.68	5,916.27	0.00	0.00	0.00	
16,600.00	90.00	359.56	10,558.00	6,020.97	588.91	6,016.27	0.00	0.00	0.00	
16,700.00	90.00	359.56	10,558.00	6,120.97	588.14	6,116.27	0.00	0.00	0.00	
16,800.00	90.00	359.56	10,558.00	6,220.96	587.37	6,216.27	0.00	0.00	0.00	
16,900.00	90.00	359.56	10,558.00	6,320.96	586.60	6,316.27	0.00	0.00	0.00	
17,000.00	90.00	359.56	10,558.00	6,420.96	585.83	6,416.27	0.00	0.00	0.00	



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
17,100.00	90.00	359.56	10,558.00	6,520.96	585.05	6,516.27	0.00	0.00	0.00	
17,200.00	90.00	359.56	10,558.00	6,620.95	584.28	6,616.27	0.00	0.00	0.00	
17,300.00	90.00	359.56	10,558.00	6,720.95	583.51	6,716.27	0.00	0.00	0.00	
17,400.00	90.00	359.56	10,558.00	6,820.95	582.74	6,816.27	0.00	0.00	0.00	
17,500.00	90.00	359.56	10,558.00	6,920.94	581.97	6,916.27	0.00	0.00	0.00	
17,600.00	90.00	359.56	10,558.00	7,020.94	581.20	7,016.27	0.00	0.00	0.00	
17,700.00	90.00	359.56	10,558.00	7,120.94	580.43	7,116.27	0.00	0.00	0.00	
17,800.00	90.00	359.56	10,558.00	7,220.93	579.65	7,216.27	0.00	0.00	0.00	
17,900.00	90.00	359.56	10,558.00	7,320.93	578.88	7,316.27	0.00	0.00	0.00	
18,000.00	90.00	359.56	10,558.00	7,420.93	578.11	7,416.27	0.00	0.00	0.00	
18,100.00	90.00	359.56	10,558.00	7,520.93	577.34	7,516.27	0.00	0.00	0.00	
18,200.00	90.00	359.56	10,558.00	7,620.92	576.57	7,616.27	0.00	0.00	0.00	
18,300.00	90.00	359.56	10,558.00	7,720.92	575.80	7,716.27	0.00	0.00	0.00	
18,400.00	90.00	359.56	10,558.00	7,820.92	575.03	7,816.27	0.00	0.00	0.00	
18,500.00	90.00	359.56	10,558.00	7,920.91	574.26	7,916.27	0.00	0.00	0.00	
18,600.00	90.00	359.56	10,558.00	8,020.91	573.48	8,016.27	0.00	0.00	0.00	
18,700.00	90.00	359.56	10,558.00	8,120.91	572.71	8,116.27	0.00	0.00	0.00	
18,800.00	90.00	359.56	10,558.00	8,220.91	571.94	8,216.27	0.00	0.00	0.00	
18,900.00	90.00	359.56	10,558.00	8,320.90	571.17	8,316.27	0.00	0.00	0.00	
19,000.00	90.00	359.56	10,558.00	8,420.90	570.40	8,416.27	0.00	0.00	0.00	
19,100.00	90.00	359.56	10,558.00	8,520.90	569.63	8,516.27	0.00	0.00	0.00	
19,200.00	90.00	359.56	10,558.00	8,620.89	568.86	8,616.27	0.00	0.00	0.00	
19,300.00	90.00	359.56	10,558.00	8,720.89	568.08	8,716.27	0.00	0.00	0.00	
19,400.00	90.00	359.56	10,558.00	8,820.89	567.31	8,816.27	0.00	0.00	0.00	
19,500.00	90.00	359.56	10,558.00	8,920.88	566.54	8,916.27	0.00	0.00	0.00	
19,600.00	90.00	359.56	10,558.00	9,020.88	565.77	9,016.27	0.00	0.00	0.00	
19,700.00	90.00	359.56	10,558.00	9,120.88	565.00	9,116.27	0.00	0.00	0.00	
19,800.00	90.00	359.56	10,558.00	9,220.88	564.23	9,216.27	0.00	0.00	0.00	
19,900.00	90.00	359.56	10,558.00	9,320.87	563.46	9,316.27	0.00	0.00	0.00	
20,000.00	90.00	359.56	10,558.00	9,420.87	562.68	9,416.27	0.00	0.00	0.00	
20,100.00	90.00	359.56	10,558.00	9,520.87	561.91	9,516.27	0.00	0.00	0.00	
20,200.00	90.00	359.56	10,558.00	9,620.86	561.14	9,616.27	0.00	0.00	0.00	
20,300.00	90.00	359.56	10,558.00	9,720.86	560.37	9,716.27	0.00	0.00	0.00	
20,400.00	90.00	359.56	10,558.00	9,820.86	559.60	9,816.27	0.00	0.00	0.00	
20,500.00	90.00	359.56	10,558.00	9,920.85	558.83	9,916.27	0.00	0.00	0.00	
20,600.00	90.00	359.56	10,558.00	10,020.85	558.06	10,016.27	0.00	0.00	0.00	
20,700.00	90.00	359.56	10,558.00	10,120.85	557.28	10,116.27	0.00	0.00	0.00	
20,740.19	90.00	359.56	10,558.00	10,161.04	556.97	10,156.46	0.00	0.00	0.00	
100FNL										
20,740.21	90.00	359.56	10,558.00	10,161.06	556.97	10,156.48	0.00	0.00	0.00	
02-LTP(R-L127H)										
20,800.00	90.00	359.56	10,558.00	10,220.85	556.51	10,216.27	0.00	0.00	0.00	
20,830.22	90.00	359.56	10,558.00	10,251.06	556.28	10,246.49	0.00	0.00	0.00	
TD: 20830.22' MD, 10246.49' VS, 10558.00' TVD - 03-PBHL(R-L127H)										



Planning Report

Database:	EDM 5000.14 Single User Db	Local Co-ordinate Reference:	Well (C04) Robin Fed 127H - Slot (C04)
Company:	Colgate Energy	TVD Reference:	3670+30 @ 3700.00usft
Project:	(Permit) Eddy County, NM (83-NME)	MD Reference:	3670+30 @ 3700.00usft
Site:	(Permit) Robin Fed DSU	North Reference:	Grid
Well:	(C04) Robin Fed 127H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Permit		
Design:	APD-Rev01		

Design Targets									
Target Name	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- hit/miss target	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)		
- Shape									
00-EON(R-L127H)	0.00	0.00	10,000.00	-242.78	636.86	565,214.78	774,690.83	32.55155100	-103.57599232
- plan misses target center by 84.54usft at 10021.66usft MD (10000.29 TVD, -242.42 N, 552.32 E)									
- Point									
01-FTP(R-L127H)	0.00	0.00	10,558.00	-212.79	636.69	565,244.77	774,690.66	32.55163343	-103.57599218
- plan misses target center by 223.35usft at 10478.44usft MD (10403.78 TVD, -58.74 N, 588.02 E)									
- Point									
02-LTP(R-L127H)	0.00	0.00	10,558.00	10,161.06	556.95	575,618.62	774,610.92	32.58014769	-103.57601142
- plan misses target center by 0.02usft at 20740.21usft MD (10558.00 TVD, 10161.06 N, 556.97 E)									
- Point									
03-PBHL(R-L127H)	0.00	0.00	10,558.00	10,251.06	556.28	575,708.62	774,610.25	32.58039507	-103.57601152
- plan hits target center									
- Point									

Casing Points				
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
20,832.94		20" Casing	20	24

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
1,555.44	1,555.00	Rustler				
1,665.73	1,665.00	Salado				
3,254.80	3,250.00	Tansill				
3,430.25	3,425.00	Yates				
3,655.82	3,650.00	Seven Rivers				
3,956.60	3,950.00	Capitan				
4,157.11	4,150.00	Queen				
5,590.78	5,580.00	Delaware Sands				
8,493.22	8,475.00	Bone Spring				
9,570.98	9,550.00	FBSG				
10,147.97	10,125.00	SBSG				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment	
		+N/-S (usft)	+E/-W (usft)		
10,001.25	9,979.88	-242.78	552.25	KOP: 10001.25' MD, -247.01' VS,9979.88' TVD	
10,182.28	10,157.91	-214.94	557.66	100FSL	
10,920.42	10,558.00	341.56	632.72	EOC: 10920.42' MD, 336.69' VS,10558.00' TVD	
20,740.19	10,558.00	10,161.04	556.97	100FNL	
20,830.22	10,558.00	10,251.06	556.28	TD: 20830.22' MD, 10246.49' VS,10558.00' TVD	



Certificate of Conformity

ContiTech

Certificate Number 1036465	COM Order Reference 1036465	Customer Name & Address HELMERICH & PAYNE DRILLING CO 1434 SOUTH BOULDER AVE TULSA, OK 74119 USA	
Customer Purchase Order No: 740122520			
Project:			
Test Center Address	Accepted by COM Inspection		Accepted by Client Inspection
ContiTech Oil & Marine Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA	Signed: Gerson Mejia-Lazo 		
	Date: 11/29/17		

We certify that the items detailed below meet the requirements of the customer's Purchase Order referenced above, and are in conformance with the specifications given below.

Item	Part No.	Description	Qty	Serial Number	Specifications
60		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	64526	ContiTech Standard
90		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	53621	ContiTech Standard



Hydrostatic Test Certificate

ContiTech

Certificate Number 1036465	COM Order Reference 1036465	Customer Name & Address HELMERICH & PAYNE DRILLING CO 1434 SOUTH BOULDER AVE TULSA, OK 74119 USA	
Customer Purchase Order No: 740122520	Project:		
Test Center Address ContiTech Oil & Marine Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA	Accepted by COM Inspection Signed: Gerson Mejia-Lazo Date: 2/27/18	Accepted by Client Inspection	

We certify that the goods detailed hereon have been inspected as described below by our Quality Management System, and to the best of our knowledge are found to conform the requirements of the above referenced purchase order as issued to ContiTech Oil & Marine Corporation.

Item	Part No.	Description	Qty	Serial Number	Work. Press.	Test Press.	Test Time (minutes)
60		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	64526	10,000 psi	15,000 psi	60
90		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	53621	10,000 psi	15,000 psi	60

Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	COM Reference #	COM Inspector	Date of Inspection
H&P Drilling	740122520	1036465	A. Jaimes	02/22/2018

Hose Manufacturer	Contitech Rubber Industrial
--------------------------	-----------------------------

Hose Serial #	53621	Date of Manufacture	08/2008
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'

Conclusion: Hose #53621 passed the external inspection with no notable damage to the armor. Internal video inspection showed no damage to the hose liner. Hose #53621 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #53621 is suitable for continued service.

Recommendations: In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:


- Visual inspection: Every 3 to 6 months (or during installation/removal)
- Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)
- Initial 5 years service: Major inspection
- 2nd Major inspection: Following subsequent 3 year life cycle
- (Detailed description of test regime available upon request, QCP 206-1)

****NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

Issued By: Alejandro Jaimes
Date: 2/27/2018


Checked By: Roger Suarez
Date: 2/27/2018

Page 1 of 1
QF97





MULTI-BOWL WELLHEAD SYSTEM RUNNING PROCEDURE



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 1 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

Table of Contents

1.0 DIAGRAM OF STACK-UP3

2.0 CASING HEAD SECTION4

3.0 TEST PLUG SECTION.....6

4.0 WEAR BUSHING SECTION7

5.0 LOWER CASING HANGER SECTION.....8

6.0 PACKOFF SUPPORT BUSHING SECTION.....10


7.0 TEST PLUG FOR PACKOFF SECTION13

8.0 C-22 HANGER SECTION14

9.0 TUBING HEAD SECTION.....16


10.0 EMERGENCY CASING HANGER C-21 SECTION19

**APPENDIX A: RECOMMENDED PROCEDURE FOR FIELD WELDING PIPE TO WELLHEAD PARTS
FOR LOW PRESSURE SEAL21**

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 2 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

1.0 DIAGRAM OF STACK-UP

1.1 DIMENSIONS FOR CONFIGURATION



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 3 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

2.0 CASING HEAD SECTION

2.1 PREPARATION

- 2.1.1 Check and record Multi-bowl Assembly part numbers and serial numbers.
- 2.1.2 Inspect assembly's upper and lower bowl. Ensure seal areas are in good condition and free from damage.
- 2.1.3 Inspect ring groove for burrs, damage and any defects. If burrs exist, redress using emery cloth.
- 2.1.4 Ensure SOW O-Ring is in good condition. Replace if damaged.

2.2 LANDING


- 2.2.1 Determine 13-3/8" casing cutoff height. Cut and bevel accordingly.
- 2.2.2 Clean scale off casing OD.
- 2.2.3 Lift Multi-bowl Assembly with certified wire rope harness or landing & flange and lower carefully over casing stub.
- 2.2.4 Ensure Multi-bowl Assembly is level and outlet orientation will match flow lines. Remove 1/2" NPT pipe plug from bottom of casing head.
- 2.2.5 Tack weld Multi-bowl SOW to casing at four points. Recheck level.

NOTE: DO NOT USE HOT HEADS OR SIMILAR METHODS OF PREHEATING, AS IT MAY DAMAGE SEALS AND PACKING

- 2.2.6 Preheat casing and Multi-bowl to specifications, 3" on either side of weld areas. Use heat sensitive crayons to monitor temperature limits.
- 2.2.7 Complete external weld. Perform post weld heat treatment.

NOTE: STEPS 2.2.4 TO 2.2.6 ARE TO BE COMPLETED BY OPERATOR'S AUTHORIZED WELDER ONLY. SEE SECTION 3.0 FOR FIELD WELDING PROCEDURE.

- 2.2.8 When weld is cool, test weld to 80% of casing collapse for minimum of 15 minutes. Use only water as test fluid, do not use oil.
- 2.2.9 Bleed off pressure after successful test. Replace pipe plug.
- 2.2.10 Install outlet accessories as required.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 4 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		




FIGURE 1 – LANDING MULTI-BOWL



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 5 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

3.0 TEST PLUG SECTION

3.1 PREPARATION

- 3.1.1 Check and record BOP Test Plug Assembly part & serial numbers.
- 3.1.2 Inspect test plug's LP threads and Tool Joint threads for damage. Ensure O-rings & lift lugs are in good condition.

3.2 RUNNING – TEST PLUG


- 3.2.1 Make up a joint of drill pipe to test plug. Ensure O-rings are in down position.

NOTE: IF PUMPING THROUGH DRILL PIPE, MAKE SURE 1/2" LP PIPE PLUGS ARE REMOVED. IF PRESSURIZING THROUGH CHOKE OR KILL LINE, 1/2" LP PIPE PLUGS MUST BE INSTALLED AND DRILL PIPE MUST BE PROPERLY TORQUED TO TEST PLUG.

- 3.2.2 Open casing head outlet valve to check for leakage during BOP test.
- 3.2.3 Lightly oil test plug's O-rings.
- 3.2.4 Lower test plug through BOP and riser stack, land on casing head load shoulder.
- 3.2.5 Test BOP stack per operator's requirements. Never exceed connection's max working pressure. Monitor any leakage through open outlet valve.

3.3 RETRIEVING – TEST PLUG

- 3.3.1 After a successful test, release pressure and open BOP rams.
- 3.3.2 Drain fluid from BOP stack.
- 3.3.3 Pull and retrieve test plug slowly to avoid damage to seals.
- 3.3.4 Close casing head outlet valve.
- 3.3.5 Inspect test plug for damage. Replace O-rings if necessary. Clean, grease, store.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 6 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

4.0 WEAR BUSHING SECTION

4.1 PREPARATION

- 4.1.1 Check and record wear bushing and running tool part and serial numbers.
- 4.1.2 Inspect wear bushing for damage, ensuring bore, slots are clean and the bore is the correct ID.
- 4.1.3 Inspect running tool for damage, ensure threads and slots are clean.

4.2 RUNNING


- 4.2.1 Make up drill pipe to running tool. Ensure lift lugs are in the down position.
- 4.2.2 Lower running tool into wear bushing. Rotate 1/4 turn clockwise to lock position.
- 4.2.3 Slowly lower wear bushing through BOP stack and riser, land on casing head load shoulder.
- 4.2.4 Run in two Lockscrews, 180° apart, for retention.
- 4.2.5 Remove Running Tool from Wear Bushing by rotating drill pipe counter-clockwise 1/4 turn and slowly lifting it straight up.

4.2.5.1 NOTE: WHILE RETRIEVING THE TOOL, MONITOR THE WEIGHT INDICATOR TO ENSURE THE TOOL IS PROPERLY DISENGAGED.

- 4.2.6 Inspect the Running Tool for any visible damage.
- 4.2.7 Proceed with drilling for next casing size.

4.3 RETRIEVING – WEAR BUSHING

- 4.3.1 Make up drill pipe to Running Tool. Ensure lift lugs are in the down position.
- 4.3.2 Slowly lower Running Tool through BOP stack until it lands on Wear Bushing.
- 4.3.3 Slowly Rotate tool until it drop. This indicates the lift lugs have aligned with j-slots of the Wear Bushing.
- 4.3.4 Slack off all weight to make sure tool is down.
- 4.3.5 Rotate tool 1/4 turn clockwise to fully engage in Wear Bushing.
- 4.3.6 Retract the two engaged Lockscrews, 180° apart.
- 4.3.7 Inspect Running Tool and Wear Bushing for any damage. Clean, grease, & store.
- 4.3.8 Proceed to running next casing.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 7 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

5.0 LOWER CASING HANGER SECTION

5.1 PREPARATION

- 5.1.1 Inspect Mandrel Casing Hanger's casing thread and ACME running threads for damage. Ensure neck seal area is clean and in good condition.
- 5.1.2 Inspect the Running Tool's casing thread and running thread for any damage. Ensure bore and O-ring is clean and in good condition.
- 5.1.3 Verify Running Tool's .50" width OD groove is painted with fluorescent yellow.

5.2 INSTALLATION


- 5.2.1 Make up the Running Tool to the Hanger by rotating counter-clockwise 8 to 9 turns until it bottoms out on the Hanger.

NOTE: DO NOT TORQUE TO HANGER.

- 5.2.2 Pressure test the Running Tool's seal through the 1/8 LP test port for at least 15 minutes. Do not exceed 5,000psi test pressure.
- 5.2.3 After a successful test, release pressure.
- 5.2.4 Lower the Hanger onto the last joint of casing run. Make up the connection to the API threads recommended optimum torque.
- 5.2.5 Verify all lock-screws are fully retracted.
- 5.2.6 Slowly and carefully lower the Hanger through the BOP and land it in the Multi-bowl.
- 5.2.7 Slack off all weight on the casing.
- 5.2.8 Visually verify the yellow paint marking on the Running Tool is in the center of the upper-most outlet of the Multi-bowl indicating that the Hanger is properly landed.

NOTE: ENSURE THAT THE WELL IS SAFE AND THERE IS NO PRESSURE BEFORE OPENING THE UPPERMOST OUTLET VALVE. CLOSE THE OUTLET AFTER VISUAL INSPECTION.

- 5.2.9 Cement as required.
- 5.2.10 Back off Running Tool by rotating clockwise until thread jump can be felt.
- 5.2.11 Retrieve the landing joint and running tool to the rig floor.
- 5.2.12 Inspect the running tool for any damage. Clean, grease, and store.
- 5.2.13 Proceed to next operation.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 8 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		




FIGURE 2 –CASING HANGER MANDREL



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 9 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

6.0 PACKOFF SUPPORT BUSHING SECTION

6.1 PREPARATION

- 6.1.1 Check and record Pack-off Support Bushing and Running Tool part and serial numbers.
- 6.1.2 Inspect the Pack-offs elastomeric seals, bore, and OD for any damage. Ensure that all are clean and in good condition.
- 6.1.3 Inspect the Running Tool's IF thread for any damage. Ensure all are clean and in good condition.
- 6.1.4 Wash out Multi-bowl and top of casing hanger landing flutes and open lower valves in lower head.


NOTE: WASHING CAN BE DONE MANUALLY USING PRESSURIZED HOSE OR WITH A WASH TOOL.

6.2 INSTALLATION

- 6.2.1 Make up a landing joint to the Running Tool. Ensure to power tight the landing joint to the Running tool per API thread's specification.
- 6.2.2 Lightly oil the Pack-offs elastomeric seals and running threads.
- 6.2.3 Lower Running Tool into Pack-off and rotate 1/4 turn clockwise to lock position.
- 6.2.4 Verify all Lock-screws are fully retracted.
- 6.2.5 Slowly and carefully lower the Pack-off through the BOP and land it on the Hanger inside the Multi-bowl.

NOTE: HEAVY DRILL PIPE OR DRILL COLLAR MIGHT BE REQUIRED AS ADDITIONAL WEIGHT TO PULL DOWN THE PACK-OFF INTO ITS LANDING POSITION.

- 6.2.6 Verify that the Pack-off has landed properly by making measurement on its setting depth.
- 6.2.7 Run Lock-screws in pairs, 180 degrees apart, at the lower Multi-bowl. Tighten gland nuts to 350 ft.-lbs and Lock-screws to 450 ft.-lbs.
- 6.2.8 Pull the Running Tool to 2,000 lbs to confirm that the Pack-off has been successfully locked down.
- 6.2.9 Slack off tension.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 10 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		


- 6.2.10 Locate the two Flange Test Ports on the upper Multi-bowl and remove the test cap from each of the fittings.
- 6.2.11 Attach a bleeder tool to one of the fittings and open the tool.
- 6.2.12 Attach a hydraulic test pump to the other fitting and pump hydraulic fluid until a continuous stream flows from the bleeder tool. Close the bleeder tool.
- 6.2.13 Perform pressure test to 5,000 psi for at least 15 minutes.

NOTE: IN CASE OF TESTING AGAINST A CASING, DO NOT EXCEED 80% OF CASING COLLAPSE.

- 6.2.14 After a successful test, release pressure. Replace test caps.
- 6.2.15 Remove the Running Tool from Pack-off by rotating the drill pipe counter-clockwise 1/4 turn and slowly lifting it straight up.

NOTE: WHILE RETRIEVING THE TOOL, MONITOR THE WEIGHT INDICATOR TO ENSURE THE TOOL IS PROPERLY DISENGAGED.

- 6.2.16 Retrieve the Running Tool to the rig floor.
- 6.2.17 Inspect the Running Tool for any damage. Clean, grease, and store.
- 6.2.18 Proceed to next operation.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 11 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		




FIGURE 3 – PACKOFF SUPPORT BUSHING



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 12 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

7.0 TEST PLUG FOR PACKOFF SECTION

7.1 PREPARATION

- 7.1.1 Check and record the BOP Test plug Assembly part number and serial number.
- 7.1.2 Inspect test plug's LP & tool joints threads for damage. Ensure O-ring & lift lugs are in good condition.

7.2 RUNNING


- 7.2.1 Make up a joint of drill pipe to test plug. Ensure O-ring is down and lift lugs are up.

NOTE: IF IT IS INTENDED TO TEST BY PUMPING THROUGH DRILL PIPE, MAKE SURE THAT THE FOUR 1/2" LP PIPE PLUGS ARE REMOVED. HOWEVER, IF TEST IS TO BE DONE BY PRESSURIZING THROUGH THE CHOKE OR KILL LINE, THE FOUR 1/2" LP PIPE PLUGS SHOULD BE INSTALLED AND DRILL PIPE MUST BE PROPERLY TORQUED TO THE TEST PLUG.

- 7.2.2 Verify lock-screws in the top flange are fully retracted.
- 7.2.3 Open Multi-bowl upper valve to check for leakage past test plug during BOP test.
- 7.2.4 Lightly oil test plug's O-ring.
- 7.2.5 Lower test plug through BOP stack until it lands on Pack-off Support Bushing.
- 7.2.6 Test BOP stack per operator's requirements. Never exceed connection's maximum working pressure. Monitor any leakage through open lower valve.

7.3 RETRIEVING

- 7.3.1 After a successful test, release pressure and open BOP rams.
- 7.3.2 Drain the fluid from BOP stack.
- 7.3.3 Pull and retrieve the test plug slowly to avoid damage.
- 7.3.4 Close the Multi-bowl upper outlet valve.
- 7.3.5 Inspect test plug for damage. Replace O-ring if necessary. Clean, grease, & store.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 13 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

8.0 C-22 HANGER SECTION

8.1 PREPARATION

- 8.1.1 Check and record Slip Casing Hanger Assembly Part serial numbers.
- 8.1.2 Inspect Slip Casing Hanger, Ensure all screws are in place & seals are in good condition.

8.2 INSTALLATION

- 8.2.1 Cement casing as required.
- 8.2.2 Drain multi-bowl
- 8.2.3 Separate Upper Multi-bowl from BOP.


NOTE: ENSURE WELL IS SAFE AND THERE IS NO PRESSURE BEFORE BREAKING CONNECTION.

- 8.2.4 Lift BOP and suspend above Upper Multi-bowl high enough to install Hanger.
- 8.2.5 Washout as necessary.
- 8.2.6 Place two boards on Upper Multi-bowl top flange against casing.
- 8.2.7 Wrap Hanger around casing using boards as support.
- 8.2.8 Replace latch screw
- 8.2.9 Grease Hanger body and remove slip retaining screws.
- 8.2.10 Remove boards and lower Hanger into Multi-bowl.

NOTE: ENSURE TO CENTER CASING AS MUCH AS POSSIBLE USING CAT-LINE.

- 8.2.11 Ensure Hanger is properly seated by tapping down on slip bowl.
- 8.2.12 Engage slip segments evenly by hammering down on top of segments.
- 8.2.13 Pull tension on casing to desired weight then slack off tension to set load to energize packing.
- 8.2.14 Rough cut casing approximately 18” above casing spool top flange.
- 8.2.15 Clean ring groove and install ring gasket into top flange.
- 8.2.16 Final cut casing at 5-3/4” +/-1/8” above top flange and bevel cut stub to specifications.

NOTE: ENSURE STUB IS PROPERLY BEVELED WITHOUT ANY ROUGH EDGES THAT COULD DAMAGE THE PACK-OFF SEALS, PICK-UP LANDING JOINT WITH PRE-INSTALLED MANDREL CASING HANGER RUNNING TOOL.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 14 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		




FIGURE 4 – HANGER INSTALLED



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 15 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		

9.0 TUBING HEAD SECTION


9.1 PREPARATION

- 9.1.1 Check & record tubing head assembly part & serial numbers.
- 9.1.2 Inspect tubing head's bowl & ring groove for burrs, damage and/or any defects. Ensure seal areas are in good condition and free from damage. If burrs exist, redress using emery cloth.
- 9.1.3 Ensure bore and FS seals are clean and in good condition.


9.2 INSTALLATION

- 9.2.1 Place ring gasket into casing spool ring groove.
- 9.2.2 Slowly and carefully lift and orient tubing head assembly over casing spool and casing hanger neck. Line up casing spool to bolt holes on casing head.
- 9.2.3 Lower tubing head and install onto casing spool. Nipple up tubing head to API recommended specifications.
- 9.2.4 Locate 1/2 LP flange test port on Tubing Head bottom flange remove fitting test cap.
- 9.2.5 Torque lock-screw glands to 350 ft.-lbs on the upper multi-bowl flange.


See reference 1



REFERENCE – 1

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 16 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		


- 9.2.6 Attach hydraulic test pump to fitting and pressure test flange to 5,000 psi or 80% of collapse of casing whichever is less, Perform test for at least 15 minutes.
- 9.2.7 After successful test, release pressure, detach test pump and reinstall cap.
- 9.2.8 Torque lock-screws glands to 350 ft.-lbs before nipple up of BOP's on 7-1/16" flange.
See reference 2



REFERENCE - 2

- 9.2.9 Nipple up BOP to casing spool assembly.
- 9.2.10 Proceed to drilling and running next casing size.

NOTE: SECONDARY SEAL WILL BE INSTALLED AND LANDED WITH TUBING HEAD.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 17 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		




FIGURE 5 – TUBING HEAD SECTION



Prepared By:	Reviewed By:	Rev:	EQ #:	Page 18 of 23
LAP			4070	
Date: 4/22/21	Date:	Date:		


10.0 EMERGENCY CASING HANGER C-21 SECTION

10.1 PREPARATION

- 10.1.1 If casing becomes stuck, follow the steps outlined below.
- 10.1.2 With casing suspended break flange connection between casing spool & casing head, lift & secure the casing spool & BOP at a safe working distance above casing head.
- 10.1.3 Examine the C-21 casing hanger for damage.

10.2 INSTALLATION

- 10.2.1 Place two boards on casing to support the casing hanger.
- 10.2.2 Remove the latch screw to open the hanger.
- 10.2.3 Wrap hanger around the casing & replace the latch screw, remove slip retainer screws.
- 10.2.4 Prepare to lower the hanger.
- 10.2.5 Remove the boards & carefully lower the hanger. If necessary, use a cat line or tugger to centralize the casing.
- 10.2.6 When the hanger is landed on load shoulder pull tension on the casing to desired hanging weight & then slack off.
- 10.2.7 Nipple up casing spool & BOP to casing head.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 19 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		





FIGURE 6 – EMERGENCY CASING HANGER

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 20 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		


APPENDIX A: RECOMMENDED PROCEDURE FOR FIELD WELDING PIPE TO WELLHEAD PARTS FOR LOW PRESSURE SEAL

The following procedure is a direct extraction (except for the numeric, footnote designators) from the 20th Edition of the API 6A. Editorial footnotes have been added to provide additional information that may be of benefit when developing procedures for specific field welding applications. The recommended procedure and footnotes are for general information purposes and it should be mentioned that Encore is not responsible for determining or administering any field welding practices. The organization performing the welding should qualify their welding procedure(s) and welder(s) in accordance with applicable codes and standards. The success of any field weld should be verified by subsequent hydrostatic test at the direction of the customer.

1. **Introduction and Scope** - The following recommended procedure has been prepared with particular regard to attaining pressure-tight welds when attaching casing heads, flanges, etc., to casing. Although most of the high strength casing used (such as P-110) is not normally considered field weldable, some success may be obtained by using the following or similar procedures.

CAUTION: IN SOME WELLHEADS, THE SEAL WELD IS ALSO A STRUCTURAL WELD AND CAN BE SUBJECTED TO HIGH TENSILE STRESSES. CONSIDERATION MUST THEREFORE BE GIVEN BY COMPETENT AUTHORITY TO THE MECHANICAL PROPERTIES OF THE WELD AND ITS HEAT AFFECTED ZONE.

2. The steels used in wellhead parts and in casing are high strength steels that are susceptible to cracking when welded. It is imperative that the finished weld and adjacent metal be free from cracks. The heat from welding also affects the mechanical properties. This is especially serious if the weld is subjected to service tension stresses.
3. This procedure is offered only as a recommendation. The responsibility for welding lies with the user and results are largely governed by the welder's skill. Weld-ability of these several makes and grades of casing varies widely, thus placing added responsibility on the welder. Transporting a qualified welder to the job, rather than using a less-skilled man who may be at hand, will, in most cases, prove economically. The responsible operating representative should ascertain the welder's qualifications and if necessary, assure himself by instruction or demonstration, that the welder is able to perform the work satisfactorily.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 21 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

4. **Welding Conditions** - Unfavorable welding conditions must be avoided or minimized in every way possible, as even the most skilled welder cannot successfully weld steels that are susceptible to cracking under adverse working conditions, or when the work is rushed. Work above the welder on the drilling floor should be avoided. The weld should be protected from dripping mud, water, and oil and from wind, rain, or other adverse weather conditions. The drilling mud, water, or other fluids must be lowered in the casing and kept at a low level until the weld has properly cooled. It is the responsibility of the user to provide supervision that will assure favorable working conditions, adequate time, and the necessary cooperation of the rig personnel.


5. **Welding** - The welding should be done by the shielded metal-arc or other approved process.

6. **Filler Metal** - After the root pass, low hydrogen electrodes or filler wires of a yield strength equal to the casing yield strength should be used. The low hydrogen electrodes include classes EXX15, EXX16, EX18, and EXX28 of AWS A5.1 (latest edition): *Mild Steel Covered Arc-Welding Electrodes** and AWS A5.5 (latest edition): *Low Alloy Steel Covered Arc-Welding Electrodes**. Low hydrogen electrodes should not be exposed to the atmosphere until ready for use. Electrodes exposed to atmosphere should be dried 1 to 2 hours at 500 to 600°F (260 to 316°C) just before use.
 *Available from the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.


7. **Preparation of Base Metal** - The area to be welded should be dry and free of any paint, grease, scale, rust, or dirt.


8. **Preheating** - Both the casing and the wellhead member should be preheated to 250-400°F (121 to 204°C) for a distance of at least 3 inches (76.2mm) on either side of the weld location, using a suitable preheating torch. Before applying preheat, the fluid should be bailed out of the casing to a point several inches (mm) below the weld location. The preheat temperature should be checked by the use of heat sensitive crayons. Special attention must be given to preheating the thick sections of wellhead parts to be welded, to insure uniform heating and expansion with respect to the relatively thin casing.

NOTE: PREHEATING MAY HAVE TO BE MODIFIED BECAUSE OF THE EFFECT OF TEMPERATURE ON ADJACENT PACKING ELEMENTS WHICH MAY BE DAMAGED BY EXPOSURE TO TEMPERATURES 200°F (93°C) AND HIGHER. TEMPERATURE LIMITATIONS OF THE PACKING MATERIALS SHOULD BE DETERMINED BEFORE THE APPLICATION OF PREHEAT.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 22 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		

9. **Welding Technique** - Use a 1/8" or 5/32" (3.2 or 4.0mm) E6010 electrodes and step weld the first beat (root pass); that is, weld approximately 2 to 4 inches (50 to 100mm) and then move diametrically opposite this point and weld 2 to 4 inches (50 to 100mm). Then weld 2 to 4 inches (50 to 100mm) halfway between the first two welds, more diametrically opposite this weld, and so on until the first pass is completed. The second pass should be make with 5/32" (4.0mm) low hydrogen electrode of the proper strength and may be continuous. The balance of the welding groove may then be filled with continuous passes without back stepping or lacing, using a 3/16" (4.8mm) low hydrogen electrode. All beads should be stringer beads with good penetration, and each bead after the root pass should be thoroughly peened before applying the next bead. There should be no undercutting and welds shall be workmanlike in appearance.
 - a. Test ports should be open when welding is performed to prevent pressure build-up within the test cavity.
 - b. During welding temperature of base metal on either side of weld should be maintained at 250°F (121°C) minimum.
 - c. Care should be taken to insure that the welding cable is properly grounded to the casing, but ground wire should not be welded to the casing or the wellhead. Ground wire should be firmly clamped to the casing, the wellhead, or fixed in position between pipe slips. Bad contact may cause sparking, with resultant hard spots beneath which incipient cracks may develop; the welding cable should not be grounded to the steel derrick, nor to the rotary-table base.
10. **Cleaning** - All slag or flux remaining on any welding bead should be removed before laying the next bead. This also applies to the completed weld.
11. **Defects** - Any cracks or blow holes that appear on any bead should be removed to sound metal by chipping or grinding before depositing the next bead.
12. **Post heating** - For the removal of all brittle areas on high strength steel casing, a post heat temperature of 1050-1100°F (566 to 593°C) is desirable. It is recognized, however, that this temperature is difficult or impossible to obtain in the field, and that the mechanical properties of the wellhead parts and the pipe may be considerably reduced by these temperatures. As a practical matter, the temperature range of 500-900°F (260-482°C) has been used with satisfactory results.
13. **Cooling** - Rapid cooling must be avoided. To assure slow cooling, welds should be protected from extreme weather conditions (cold, rain, high winds, etc.). By the use of a blanket made from suitable insulating material. Particular attention should be given to maintaining uniform cooling of the thick sections of the wellhead parts and the relatively thin casing will pull away from the head or hanger if allowed to cool more rapidly. The welds should cool in air to 250°F (121°C) (measured with a heat sensitive crayon) prior to permitting the mud to rise in the casing.

	Prepared By:	Reviewed By:	Rev:	EQ #:	Page 23 of 23
	LAP			4070	
	Date: 4/22/21	Date:	Date:		



ROBIN FED COM
LEA COUNTY, NEW MEXICO

Date: 3/1/2022

GIS Tech: VKV

Legend	
Proposed Pipeline	Pad
Access Road	Federal
CTB	State

1:2,400 0 0.05 0.1 0.2 Miles

1" = 200' 0 250 500 1,000 Feet

CONFIDENTIAL FOR INTERNAL USE ONLY

BERRY DANIEL C II
Sec: 28

Drilling Program
Colgate Energy
 Robin Fed 127H
 330' FSL & 1,295' FEL (SHL)
 Sec 20-T20S-R34E
 Lea County, New Mexico

The estimated tops of geologic formations are as follows:

Formation:	TVD	Subsea
Rustler	1555	2145
Salado	1665	2035
Tansill	3250	450
Yates	3425	275
Seven Rivers	3650	50
Capitan	3950	-250
Queen	4150	-450
Cherry Canyon	5580	-1880
Brushy Canyon	6790	-3120
Bone Spring Lime	8475	-4775
1st Bone Spring Sand*	9550	-5850
2nd Bone Spring Sand*	10125	-6425

Formations anticipated to contain fresh water, oil or gas are as follows:

- Water: Fresh water is anticipated at 65' and will be protected by setting a water string at 1620' and cementing to surface.
- Water: The Capitan Reef is anticipated to contain usable water and will be protected by setting an intermediate casing string at 5520' and cementing to surface using a stage tool.
- Hydrocarbons: Oil and gas are anticipated in the above (*) formations. These zones will be protected by casing as necessary.

Proposed casing program is as follows:

Name	Hole Size	Casing Size	Weight & Grade	Thread Collar	Top Csg	Setting Depth	Collapse	Burst	Tension
Surface	17 1/2	13 3/8	54.5# J-55 (new)	BTC	0	1,620'	1.125	1.2	1.6
Intermediate	12 1/4	9 5/8	40# J-55 (new)	BTC	0	5,520'	1.125	1.2	1.6
Production	8 3/4	5 1/2	17# HPP-110 (new)	CDC HTQ	0	20,830'	1.125	1.1	1.6

SF Values will meet or exceed

Proposed cementing program is as follows:

Name	Slurry	Sacks	Yield	Weight	Excess	Top Cement	Blend
Surface	Lead	1050	1.68	13.7	100%	0'	ExtendaCem-CZ
	Tail	340	1.35	14.8	100%	1,290'	HalCem-C + accelerator
Intermediate	Lead	171	1.88	12.9	50%	3,730'	EconoCem-HLC + 5 % salt + 5 lb/sk Kol-Seal
	Tail	230	1.33	14.8	25%	4,416'	HalCem-C
2nd Stage	Lead	564	1.88	12.9	50%	0'	EconoCem-HLC + 5 % salt + 5 lb/sk Kol-Seal
	Tail	325	1.33	14.8	25%	2,626'	HalCem-C
Production	Lead	1086	2.41	11.5	10%	0'	Class H + POZ + extender + fluid loss + dispersant + retarder
	Tail	1778	1.73	12.5	10%	9,760'	Class H + POZ + extender + fluid loss + dispersant + retarder

Proposed casing and cementing accessories are as follows: (Casing will be centralized per Onshore Order 2.III.B.1.f)

- Surface: 1 centralizer 5' above shoe held in place with stop ring; 1 centralizer per joint for following 2 joints then every other joint to surface
- Intermediate: 2 centralizers on 1st joint, 1 centralizer on 2nd joint, 1 centralizer every 4th joint to surface
 Stage tool will be placed at approximately 3730' to ensure intermediate casing string is adequately cemented.
- Production: 2 centralizers on bottom joint, 1 centralizer on 2nd joint, 1 centralizer every 3rd joint to 5020'

Proposed pressure control equipment is as follows (see schematics below):

BOPE with working pressure ratings in excess of anticipated maximum surface pressure will be utilized for well control from drill out of surface casing to TMD. A rotating head will also be installed and utilized as needed. All BOPE connections shall be flanged, welded or clamped. All choke lines shall be straight unless targeted with running tees or tee blocks are used, and choke lines shall be anchored to prevent whip and reduce vibrations. All valves in the choke line & the choke manifold shall be full opening as to not cause restrictions and to allow for straight fluid paths to minimize potential erosion. All gauges utilized in the well control system shall be of a type designed for drilling fluid service. A top drive inside BOP valve will be utilized at all times. Subs equipped with full opening valves sized to fit the drill pipe and collars will be available on the rig floor in the open position. The key to operate said valve equipped subs will be on the rig floor at all times. The accumulator system will have sufficient capacity to open the HCR and close all three sets of rams plus the annular preventer while retaining at least 300 psi above precharge on the closing manifold (accumulator system shall be capable of doing so without using the closing unit pumps). The fluid reservoir capacity will be double the usable fluid volume of the accumulator system capacity, and the fluid level will be maintained at the manufacturer's recommended level. Prior to connecting the closing unit to the BOP stack, an accumulator precharge pressure test shall be performed to ensure the precharge pressure is within 100 psi of the desired precharge pressure (only nitrogen gas will be used to precharge). Two independent power sources will be made available at all times to power the closing unit pumps so that the pumps can automatically start when the closing valve manifold pressure has decreased to the pre-set level. Closing unit pumps will be sized to allow opening of HCR and closing of annular preventer on 5" drill pipe achieving at least 200 psi above precharge pressure with the accumulator system isolated from service in less than two minutes. A valve shall be installed in the closing line as close to the annular preventer as possible to act as a locking device; the valve shall be maintained in the open position and shall be closed only when the power source for the accumulator system is inoperative. Remote controls capable of opening and closing all preventers & the HCR shall be readily accessible to the driller; master controls with the same capability will be operable at the accumulator. The wellhead will be a multi-bowl speed head allowing for hang-off of intermediate casing & isolation of the 13-3/8" x 9-5/8" annulus without breaking the connection between the BOP & wellhead to install an additional casing head. A wear bushing will be installed & inspected frequently to guard against internal wear to wellhead. VBRs (variable-bore rams) will be run in upper ram-body of BOP stack to provide redundancy to annular preventer while RIH w/ production casing;

A request for variance of pressure control equipment as follows:

1. Colgate Energy requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

BOPE will be tested per the following procedure:

After surface casing is set and the BOPE installed, pressure tests of BOPE will be performed by a third party tester utilizing water and a test plug to 250 psi low and 5,000 psi high. To deem a pressure test successful, pressure must be maintained for ten minutes without any bleed-off. A valve on the wellhead below seat of test plug will be open at all time during BOPE tests to guard against damage to casing. The BOPE will be re-tested in this manner after any connection breaks or passage of allotted time (25 days). Any BOPE which fails to pass pressure tests after initial install will be replaced prior to drilling out of surface casing shoe. If at any time a BOPE component cannot function to secure the hole, the hole shall be secured utilizing a retrievable packer, and the non-functioning BOPE component shall be repair or replaced. After repair or replacement, a pressure test of the repaired or replaced component and any connections broken to repair or replace the non-functioning component will be tested in the same manner as described for initial install of BOPE. The annular preventer will be faction tested at least weekly, and the ram-type preventers will be function tested on each trip. BOPE pit level drills will be conducted weekly with each drilling crews. All pressure tests performed on BOPE and BOPE pit level drills will be logged in the drilling log. Isolation of 13-3/8" x 9-5/8" casing annulus shall be confirmed by pressure testing of wellhead sealing component after said sealing component is installed.

Each casing string will be tested once installed in the wellbore per the following procedure:

Casing will be tested by pressuring up to 1,500 psi and holding pressure for thirty minutes. A casing test will be deemed successful if test pressure does not decline more than 10% over the thirty minute period. Cement will be allowed to sit undisturbed for twenty-four hours and reach a minimum of 500 psi compressive strength across the "zone of interest" prior to testing casing and drilling out. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Each casing string will be cemented per the following cementing procedure:

Cement will be placed on all casing strings utilizing the pump and plug method. A float will be installed in the casing shoe and float collar on all casing strings to hold cement in place once pumping is completed. A top plug will be utilized on all casing strings to prevent contamination of the cement by the displacement fluid. A preflush fluid will be pumped prior to cement to aid in removal of drilling mud from the wellbore, eliminate drilling mud contamination of the cement slurry and prepare the surface of both the wellbore and casing for cement.

Proposed mud system is as follows:

<u>Name</u>	<u>Hole Size</u>	<u>Mud Weight</u>	<u>Viscosity</u>	<u>Fluid Loss</u>	<u>Type Mud</u>
Surface	17-1/2"	8.6 - 9.0	28 - 34	NC	FW Spud Mud
Intermediate*	12-1/4"	10.0 - 10.2	30 - 32	NC	Brine Water
Production	8-3/4"	9.0 - 10.0	32 - 35	-	OBM

All necessary mud products for weight addition and fluid loss control will be on location at all times. Mud program is subject to change due to hole conditions. The mud monitoring system is an electronic Pason system satisfying requirements of Onshore Order #1. Both visual and electronic mud monitoring equipment will be utilized to detect volume changes indicating loss or gain of circulating system fluid volume. Slow pump rates will be taken & recorded hourly in the drilling log. Mud engineer will perform tests and provide written report at least every 12 hours while circulating. A trip tank will be utilized and trip sheet will be recorded to ensure wellbore is taking proper fill or displacing proper fluid volume during all tripping operations. Gas detecting equipment will be utilized to monitor for hydrocarbon gas at the shakers while drilling and/or circulating. H2S monitoring equipment with both visual & auditory alarms will be installed and operational at the shakers, rig floor and cellar while drilling and/or circulating. A flare system with an effective method for ignition & discharge more than 100 feet from the wellbore will be utilized to gather and burn all gas; lines will be straight unless targeted with running tees. A mud gas separator will be installed and operable at least 500 feet before first anticipated hydrocarbon zone.

*If loss circulation is encountered in Capitan Reef, only fresh water will be pumped down drill string for remainder of hole section.

Proposed testing, surveying, logging and coring program is as follows:

No open-hole logs are planned at this time. Directional surveys will be collected at no greater than 200' intervals while drilling through the MWD tools. A GR log will be collected while drilling through the MWD tools from intermediate casing to TD. No DSTs or cores are planned at this time. No temperature logs planned at this time. CBL will be run to confirm TOC on production casing after rig is removed from location. A formation integrity test (FIT) will be performed on 9-5/8" casing string after BOPE is installed to at least 1 ppg over planned section mud weight after drilling ten feet of new hole.

Anticipated potential hazards are as follows:

No abnormal pressures or temperatures are expected. In accordance with Onshore Order No. 6, Colgate Energy does not anticipate that there will be enough H₂S from the surface to the Wolfcamp formations to meet the BLM's minimum requirements for the submission of an "H₂S Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. Since we have an H₂S safety package on all wells, attached is an "H₂S Drilling Operations Plan". Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Estimated BHP: 8.3 lbs/gal gradient or less
 Estimated BHT: 120° F

Planned commencement of operations is as follows:


Road and location construction will begin after BLM approval of APD. Anticipated spud date as soon as approved. Drilling expected to take 30 days. If production casing is run an additional 60 days will be required to complete and construct surface facilities.

10,000 psi BOP Stack:


Mud Cross Valves:

- 5. 10M Check Valve
- 6. Outside 10M Kill Line Valve
- 7. Inside 10M Kill Line Valve
- 8. Outside 10M Kill Line Valve
- 9. 10M HCR Valve


*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side




Closed Loop System Layout:



Multi-bowl Wellhead



10M Choke Layout





U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

02/29/2024

APD ID: 10400085479

Submission Date: 05/21/2022

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data reflects the most recent changes
[Show Final Text](#)

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Robin_Fed_East_SUPO_Section_1_20220518083144.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Robin_Federal_Road_20231129050342.pdf

New road type: LOCAL

Length: 5755.39 Feet

Width (ft.): 30

Max slope (%): 1

Max grade (%): 1

Army Corp of Engineers (ACOE) permit required? N

ACOE Permit Number(s):

New road travel width: 20

New road access erosion control: None

New road access plan or profile prepared? N

New road access plan

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Access road engineering design? N

Access road engineering design

Turnout? N

Access surfacing type: GRAVEL

Access topsoil source: ONSITE

Access surfacing type description:

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Grader

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: No drainage crossed

Road Drainage Control Structures (DCS) description: None

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Robin_Fed_East_SUPO_Section_3_20220518083404.pdf

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: Production Facilities. One pad was staked with the BLM for construction and use as Central Tank Battery (CTB). The Central Tank Battery is the Robin Federal tank battery. The Robin Federal tank battery is 300ftx450ft (3.09 Acres) located in the NESE Section 20-T20S-R31E NMPM, Lea County, New Mexico (Centerpoint: 815FSL & 1183FEL). Plat of the proposed facility is attached. A 3160-5 sundry notification will be submitted after construction with a site-security diagram and layout of the facility with associated equipment. Buried & Surface Flowlines. In the event the Robin Federal wells are found productive, twenty-four (24) 22in. or less buried composite flexpipe or steel flowlines with a maximum safety pressure rating of 1400psi (operating pressure: 750 psi) for transport of oil, gas, frac water, gas lift, fuel gas, and produced water are requested to the Robin Federal Central Tank Battery. If Colgate Operating, LLC

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

decides to run surface lines, twenty-four (24) 4in. or less composite flexpipe or steel flowlines with a max. safety psi rating of 750 (op. psi: 125psi) for transport of oil, gas and produced water will be required to the Robin Federal Central Tank Battery. Total Flowline Length: 3237.35ft long by 30ft wide or 2.22 acres. Midstream Tie-In. A midstream tie-in is not requested with this project. In the event that a midstream tie-in is necessary, Colgate Operating, LLC will file application with the appropriate authorities to construct via right-of-way. Disposal Facilities. Produced water will be hauled from location to a commercial disposal facility as needed. Once wells are drilled and completed, a 3160-5 sundry notification will be submitted to BLM in compliance with Onshore Order 7. Flare. A flare is not requested with this project. The flare will be located on the proposed CTB and submitted on the subsequent facility diagram. Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as shale green that reduce the visual impacts of the built environment. Containment Berms. Containment berms will be constructed completely around any production facilities designed to hold fluids. The containment berms will be constructed of compacted subsoil, be sufficiently impervious, hold 1.5 times the capacity of the largest tank and away from cut or fill areas. Electrical. Electrical is not proposed with this project as a power tie-in has not been identified. Once identified, Colgate Operating, LLC will file an application with the appropriate authorities to construct planned lines via right-of-way.

Production Facilities map:

Robin_Federal_FL_20231003052853.pdf

Robin_Federal_CTB_20231003052854.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: OTHER

Describe type: Berry's existing water station on state land in N2NE4 2-21 s-33e

Water source use type: SURFACE CASING

Source latitude:

Source longitude:

Source datum:

Water source permit type: OTHER

Water source transport method: TRUCKING

Source land ownership: STATE

Source transportation land ownership: STATE

Water source volume (barrels): 17000

Source volume (acre-feet): 2.19118264

Source volume (gal): 714000

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Water source type: OTHER

Describe type: Water will be trucked from Legacy's existing pond on private land in NWNW 1 8-20s-34e

Water source use type: SURFACE CASING

Source latitude:

Source longitude:

Source datum:

Water source permit type: OTHER

Water source transport method: TRUCKING

Source land ownership: PRIVATE

Source transportation land ownership: PRIVATE

Water source volume (barrels): 17000

Source volume (acre-feet): 2.19118264

Source volume (gal): 714000

Water source and transportation

Robin_Fed_East_SUPO_Section_5_20220518083539.pdf

Water source comments:

New water well? N

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: NM One Call (811), Legacy, Targa, DCP, and Solaris will be notified before construction starts. Top 6" of soil and brush will be stockpiled south and west of the well pad and south and west of the CTB. CTB topsoil pile will be no higher than 3 6" and will be seeded in place. V-door will face east. Closed loop mud system will be used. Caliche will be hauled from an existing caliche pit on private land in SENE 28-20s-34e.

Construction Materials source location

Robin_Fed_East_SUPO_Section_6_20220518083627.pdf

Section 7 - Methods for Handling

Waste type: DRILLING

Waste content description: Drill cuttings, mud, salts, and other chemicals

Amount of waste: 550 barrels

Waste disposal frequency : Daily

Safe containment description: Steel mud tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to R360's state approved (NM-01-0006) disposal site at Halfway.

Waste type: SEWAGE

Waste content description: Black and Grey Water

Amount of waste: 5 barrels

Waste disposal frequency : Daily

Safe containment description: Plastic holding tanks and chemical toilets

Safe containmant attachment:

Waste disposal type: OTHER **Disposal location ownership:** OTHER

Disposal type description: Public

Disposal location description: Human waste will be disposed of in chemical toilets and hauled to the Carlsbad wastewater treatment plant.

Operator Name: COLGATE OPERATING LLC	
Well Name: ROBIN FED	Well Number: 127H

Waste type: GARBAGE

Waste content description: Trash

Amount of waste: 10 barrels

Waste disposal frequency : Daily

Safe containment description: Portable trash cage

Safe containmant attachment:

Waste disposal type: OTHER

Disposal location ownership: OTHER

Disposal type description: Public

Disposal location description: All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? Y

Description of cuttings location Steel tanks

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

Section 9 - Well Site

Well Site Layout Diagram:

Robin_Fed_East_SUPO_Section_9_20220518083806.pdf

Comments: Also see Rig Layout diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: Robin Pad East

Multiple Well Pad Number: 2

Recontouring

Robin_Fed_East_SUPO_Section_10_20220518083818.pdf

Drainage/Erosion control construction: Crowned and ditched

Drainage/Erosion control reclamation: Harrowed on the contour

Well pad proposed disturbance (acres): 19.55	Well pad interim reclamation (acres): 4.46	Well pad long term disturbance (acres): 15.09
Road proposed disturbance (acres): 3.96	Road interim reclamation (acres): 0	Road long term disturbance (acres): 3.96
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 2.22	Pipeline interim reclamation (acres): 2.22	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 3.09	Other interim reclamation (acres): 0	Other long term disturbance (acres): 3.09
Total proposed disturbance: 28.82	Total interim reclamation: 6.68	Total long term disturbance: 22.14

Disturbance Comments:

Reconstruction method: All of the west driveway, south 80' of the east driveway, south and west 80' of the well pad will be interim reclaimed. After the last well is plugged, then the remainder of the pad will be reclaimed within 6 months of plugging. Disturbed areas will be contoured to match pre-construction grades.

Topsoil redistribution: Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with surface owner requirements. Noxious weeds will be controlled. CTB will be similarly reclaimed once its last well is plugged.

Soil treatment: None

Existing Vegetation at the well pad: Mesquite and/or Creosote bush

Operator Name: COLGATE OPERATING LLC	Well Number: 127H
Well Name: ROBIN FED	

Existing Vegetation at the well pad

Existing Vegetation Community at the road: Mesquite and/or Creosote bush

Existing Vegetation Community at the road

Existing Vegetation Community at the pipeline: Mesquite and/or Creosote bush

Existing Vegetation Community at the pipeline

Existing Vegetation Community at other disturbances: Mesquite and/or Creosote bush

Existing Vegetation Community at other disturbances

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Seed

Seed Table

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation

Operator Contact/Responsible Official

First Name:

Last Name:

Phone:

Email:

Seedbed prep:

Seed BMP:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Seed method:

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment

Weed treatment plan description: To BLM Standards

Weed treatment plan

Monitoring plan description: To BLM Standards

Monitoring plan

Success standards: To BLM Standards

Pit closure description: No Pit

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: AGREEMENT

Surface Access Agreement Need description: There is not currently an SUA from the private land owner.

Surface Access Bond BLM or Forest Service:

BLM Surface Access Bond number:

USFS Surface access bond number:

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: AGREEMENT

Surface Access Agreement Need description: There is not currently an SUA from the private land owner.

Surface Access Bond BLM or Forest Service:

BLM Surface Access Bond number:

USFS Surface access bond number:

Disturbance type: OTHER

Describe: Tank Battery

Surface Owner: BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: AGREEMENT

Surface Access Agreement Need description: There is not currently an SUA from the private land owner.

Surface Access Bond BLM or Forest Service:

BLM Surface Access Bond number:

USFS Surface access bond number:

Section 12 - Other

Right of Way needed? Y

Use APD as ROW? Y

ROW Type(s): 281001 ROW - ROADS,285003 ROW – POWER TRANS,288100 ROW – O&G Pipeline,288101 ROW – O&G Facility Sites,289001 ROW- O&G Well Pad,FLPMA (Powerline)

ROW

SUPO Additional Information: Lone Mountain Archaeological conducted a block inspection filed report NMCRIS-149522 on January 17, 2022. On-site inspection was conducted on February 1, 2022, with Jeff Robertson and Jim Rutley (both BLM).

Use a previously conducted onsite? N


Previous Onsite information:

Other SUPO


Robin_Federal_Well_List_20231003053025.pdf

Robin_Federal_SUPO_20231129050355.pdf

TOPO! map printed on 04/25/22 from "Untitled.tpo"






Map created with TOPO! © 2010 National Geographic




04/25/22

TOPO! map printed on 04/25/22 from "Untitled.tpo"



TOPO! map printed on 04/25/22 from "Untitled.tpo"





MAP 3


Robin Fed east pad



01, 32.55191° N, 103.57823° W

Map created with T@2010 National Geographic, ©2005-Tele Atlas, Rel. 8/2005





proposed road


CTB

Robin Fed east pad

MAP 4



700 ft





CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1" BENT IRON PIPE FOUND FOR THE EAST QUARTER CORNER OF SAID SECTION 20 BEARS N 24°26'18" E, A DISTANCE OF 1385.21 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566537.96, E:774757.76 FEET FOR REFERENCE:

THENCE S 40°40'23" W, A DISTANCE OF 575.09 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 58°52'01" W, A DISTANCE OF 1955.26 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566101.79, E:774382.95 FEET FOR REFERENCE.

SAID CENTERLINE CONTAINING A TOTAL OF 575.09 FEET OR 34.85 RODS IN SAID SECTION 20.

NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.


#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

ROBIN FED COM CTB BUREAU OF LAND MANAGEMENT PROPOSED ACCESS ROAD			
SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM	REV. 0
CHECKED BY: MJM	DATE: 04/13/22	CTB AR (20-20S-34E)	
SCALE: 1"=1000'	PAGE 2 OF 2		



MAP 5c

SECTION 20
TOWNSHIP 20 SOUTH, RANGE 34 EAST
NEW MEXICO PRINCIPAL MERIDIAN
LEA COUNTY, NEW MEXICO


ACCESS ROAD CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
SW-SE	BLM	940.34	56.99	27,760	0.637
TOTAL		940.34	56.99	27,760	0.637

ACCESS ROAD CENTERLINE
TOTAL LENGTH = 940.34 FEET
(56.99 RODS)

ACCESS ROAD BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 00°26'42" E	940.34'



- LEGEND**
- SECTION LINE
 - OHE
 - OVERHEAD ELECTRIC
 - ACCESS ROAD CENTERLINE
 - EDGE OF ROAD
 - EXISTING PIPELINE
 - X FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



I, MARK J. MURRAY, A NEW MEXICO REGISTERED PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

MARK J. MURRAY NEW MEXICO #12177 DATE 4/14/2022

NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910

TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM EAST WELL PAD
 BUREAU OF LAND MANAGEMENT
 PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		



CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1" BENT IRON PIPE FOUND FOR THE EAST QUARTER CORNER OF SAID SECTION 20 BEARS N 43°29'02" E, A DISTANCE OF 2399.95 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566057.74, E:773679.31 FEET FOR REFERENCE;

THENCE S 00°26'42" E, A DISTANCE OF 940.34 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN THE SOUTH BOUNDARY LINE OF SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 88°26'34" W, A DISTANCE OF 977.68 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565117.44, E:773686.62 FEET FOR REFERENCE.

SAID CENTERLINE CONTAINING A TOTAL OF 940.34 FEET OR 56.99 RODS IN SAID SECTION 20.

NOTES

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.


#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181


ROBIN FED COM EAST WELL PAD BUREAU OF LAND MANAGEMENT PROPOSED ACCESS ROAD			
SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22	PAGE 2 OF 2	
SCALE: 1"=1000'			



MAP 5e

ACCESS ROAD CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
NW-NE	BLM	626.90	37.99	18,807	0.432
TOTAL		626.90	37.99	18,807	0.432

ACCESS ROAD BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 00°26'42" E	626.90'



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

MARK J. MURRAY NEW MEXICO PS #12177 4/14/2022 DATE

NOTES

- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
- LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
- THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910

TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM EAST WELL PAD
 BUREAU OF LAND MANAGEMENT
 PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 29
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (29-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		



CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 29, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN THE NORTH BOUNDARY LINE OF SAID SECTION 29, FROM WHICH A 4" IRON PIPE FOUND FOR THE NORTH QUARTER CORNER OF SAID SECTION 29 BEARS S 88°26'34" W, A DISTANCE OF 977.68 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565117.44, E:773686.62 FEET FOR REFERENCE;

THENCE S 00°26'42" E, A DISTANCE OF 626.90 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 29, FROM WHICH A BENT T-RAIL FOUND FOR THE NORTHEAST CORNER OF SAID SECTION 29 BEARS N 67°57'18" E, A DISTANCE OF 1790.75 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:564490.56, E:773691.49 FEET FOR REFERENCE.

SAID CENTERLINE CONTAINING A TOTAL OF 626.90 FEET OR 37.99 RODS IN SAID SECTION 29.

NOTES

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910





TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181




ROBIN FED COM EAST WELL PAD
 BUREAU OF LAND MANAGEMENT
 PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 29
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (29-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 2 OF 2		



- LEGEND**
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - ACCESS ROAD CENTERLINE
 - EDGE OF ROAD
 - EXISTING PIPELINE
 - FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



MARK J. MURRAY
 NEW MEXICO
 12177
 REGISTERED PROFESSIONAL SURVEYOR

I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

- NOTES:**
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				

ROBIN FED COM WEST WELL PAD
BUREAU OF LAND MANAGEMENT
PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM WEST AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		

CENTERLINE DESCRIPTION

EASEMENT DETAIL "A"

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1/2" BENT IRON PIPE FOUND FOR THE WEST QUARTER CORNER OF SAID SECTION 20 BEARS N 36°53'41" W, A DISTANCE OF 1690.75 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566412.15, E:771050.98 FEET FOR REFERENCE;

THENCE S 00°30'59" E, A DISTANCE OF 372.43 FEET TO A POINT;
 THENCE N 89°36'05" E, A DISTANCE OF 569.70 FEET TO A POINT;

THENCE N 89°36'30" E, A DISTANCE OF 2309.74 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A BENT T-RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS S 57°40'55" E, A DISTANCE OF 1677.45 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566059.48, E:773933.71 FEET FOR REFERENCE.

SAID CENTERLINE CONTAINING A TOTAL OF 3251.87 FEET OR 197.08 RODS IN SAID SECTION 20.

EASEMENT DETAIL "B"

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1/2" BENT IRON PIPE FOUND FOR THE WEST QUARTER CORNER OF SAID SECTION 20 BEARS N 49°06'38" W, A DISTANCE OF 2076.93 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566404.75, E:771606.06 FEET FOR REFERENCE;

THENCE S 00°28'27" E, A DISTANCE OF 361.19 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 49°06'40" E, A DISTANCE OF 1455.40 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566043.57, E:771609.05 FEET FOR REFERENCE.

SAID CENTERLINE CONTAINING A TOTAL OF 361.19 FEET OR 21.89 RODS IN SAID SECTION 20.

NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910


TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM WEST WELL PAD
BUREAU OF LAND MANAGEMENT
 PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO


DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM WEST AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 2 OF 2		





ACCESS ROAD CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
				ACCESS ROAD EASEMENT	
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
NE-SE	BLM	81.02	4.91	2,431	0.056
SE-SE	BLM	494.07	29.94	15,048	0.345
TOTAL		575.09	34.85	17,479	0.401

**ACCESS ROAD CENTERLINE
TOTAL LENGTH = 575.09 FEET
(34.85 RODS)**

ACCESS ROAD BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 40°40'23" W	575.09'



- LEGEND**
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - ACCESS ROAD CENTERLINE
 - EDGE OF ROAD
 - EXISTING PIPELINE
 - FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

- NOTES:**
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				



ROBIN FED COM CTB
BUREAU OF LAND MANAGEMENT
PROPOSED ACCESS ROAD

SITUATED IN
SECTION 20
TOWNSHIP 20 SOUTH, RANGE 34 EAST
NEW MEXICO PRINCIPAL MERIDIAN
LEA COUNTY, NEW MEXICO

TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM CTB AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		

CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1" BENT IRON PIPE FOUND FOR THE EAST QUARTER CORNER OF SAID SECTION 20 BEARS N 24°26'18" E, A DISTANCE OF 1385.21 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566537.96, E:774757.76 FEET FOR REFERENCE;

THENCE S 40°40'23" W, A DISTANCE OF 575.09 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 58°52'01" W, A DISTANCE OF 1955.26 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566101.79, E:774382.95 FEET FOR REFERENCE.


SAID CENTERLINE CONTAINING A TOTAL OF 575.09 FEET OR 34.85 RODS IN SAID SECTION 20.

NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.


#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910




TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

			
<p>ROBIN FED COM CTB BUREAU OF LAND MANAGEMENT PROPOSED ACCESS ROAD</p>			
<p>SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO</p>			
DRAWN BY: CAS	DATE: 04/13/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 04/13/22	8910 ROBIN FED COM	0
SCALE: 1"=1000'	PAGE 2 OF 2	CTB AR (20-20S-34E)	



ACCESS ROAD CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
				ACCESS ROAD EASEMENT	
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
SW-SE	BLM	940.34	56.99	27,760	0.637
TOTAL		940.34	56.99	27,760	0.637

**ACCESS ROAD CENTERLINE
TOTAL LENGTH = 940.34 FEET
(56.99 RODS)**



ACCESS ROAD BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 00°26'42" E	940.34'

- LEGEND**
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - ACCESS ROAD CENTERLINE
 - EDGE OF ROAD
 - EXISTING PIPELINE
 - FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

- NOTES:**
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				

ROBIN FED COM EAST WELL PAD
BUREAU OF LAND MANAGEMENT
PROPOSED ACCESS ROAD

SITUATED IN
SECTION 20
TOWNSHIP 20 SOUTH, RANGE 34 EAST
NEW MEXICO PRINCIPAL MERIDIAN
LEA COUNTY, NEW MEXICO

TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		

CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1" BENT IRON PIPE FOUND FOR THE EAST QUARTER CORNER OF SAID SECTION 20 BEARS N 43°29'02" E, A DISTANCE OF 2399.95 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566057.74, E:773679.31 FEET FOR REFERENCE;

THENCE S 00°26'42" E, A DISTANCE OF 940.34 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN THE SOUTH BOUNDARY LINE OF SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 88°26'34" W, A DISTANCE OF 977.68 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565117.44, E:773686.62 FEET FOR REFERENCE.


SAID CENTERLINE CONTAINING A TOTAL OF 940.34 FEET OR 56.99 RODS IN SAID SECTION 20.


NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910


TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

			
ROBIN FED COM EAST WELL PAD BUREAU OF LAND MANAGEMENT PROPOSED ACCESS ROAD			
SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: CAS	DATE: 04/13/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 04/13/22	8910 ROBIN FED COM	0
SCALE: 1"=1000'	PAGE 2 OF 2	EAST AR (20-20S-34E)	




ACCESS ROAD CENTERLINE BREAKDOWN BY SECTION 1/4 1/4


1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
NW-NE	BLM	626.90	37.99	18,807	0.432
TOTAL		626.90	37.99	18,807	0.432

ACCESS ROAD BEARING & DISTANCE TABLE

LINE #	BEARING	DISTANCE
L1	S 00°26'42" E	626.90'



- LEGEND**
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - ACCESS ROAD CENTERLINE
 - EDGE OF ROAD
 - EXISTING PIPELINE
 - FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



MARK J. MURRAY
 NEW MEXICO
 12177
 REGISTERED PROFESSIONAL SURVEYOR

I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

- NOTES:**
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				

COLGATE ENERGY

ROBIN FED COM EAST WELL PAD
 BUREAU OF LAND MANAGEMENT
 PROPOSED ACCESS ROAD

SITUATED IN
 SECTION 29
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM EAST AR (29-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		

CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED ACCESS ROAD, SITUATED IN SECTION 29, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN THE NORTH BOUNDARY LINE OF SAID SECTION 29, FROM WHICH A 4" IRON PIPE FOUND FOR THE NORTH QUARTER CORNER OF SAID SECTION 29 BEARS S 88°26'34" W, A DISTANCE OF 977.68 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565117.44, E:773686.62 FEET FOR REFERENCE;

THENCE S 00°26'42" E, A DISTANCE OF 626.90 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 29, FROM WHICH A BENT T-RAIL FOUND FOR THE NORTHEAST CORNER OF SAID SECTION 29 BEARS N 67°57'18" E, A DISTANCE OF 1790.75 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:564490.56, E:773691.49 FEET FOR REFERENCE.


SAID CENTERLINE CONTAINING A TOTAL OF 626.90 FEET OR 37.99 RODS IN SAID SECTION 29.


NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910

	TBPELS FIRM# 10193740 / 19148
	2129 S Great Southwest Parkway Suite 313
	Grand Prairie, TX 75051 (817) 529-1180 ~ Fax (817) 529-1181


			
ROBIN FED COM EAST WELL PAD BUREAU OF LAND MANAGEMENT PROPOSED ACCESS ROAD			
SITUATED IN SECTION 29 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: CAS CHECKED BY: MJM SCALE: 1"=1000'	DATE: 04/13/22 DATE: 04/13/22 PAGE 2 OF 2	DWG. NO. 8910 ROBIN FED COM EAST AR (29-20S-34E)	REV. 0




EASEMENT CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
SW-SE	BLM	369.61	22.40	10,638	0.244
TOTAL		369.61	22.40	10,638	0.244

**EASEMENT CENTERLINE
TOTAL LENGTH = 369.61 FEET
(22.40 RODS)**

EASEMENT CENTERLINE BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 00°26'11" E	369.61'



- LEGEND**
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - EASEMENT CENTERLINE
 - PERMANENT EASEMENT
 - EXISTING PIPELINE
 - X- FENCE LINE
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

- NOTES:**
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				

ROBIN FED COM EAST WELL PAD
BUREAU OF LAND MANAGEMENT
PROPOSED PIPELINE EASEMENT CENTERLINE

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM FLOWLINE EAST (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		

CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED PIPELINE EASEMENT, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1" BENT IRON PIPE FOUND FOR THE EAST QUARTER CORNER OF SAID SECTION 20 BEARS N 43°27'47" E, A DISTANCE OF 2357.51 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566087.94, E:773709.13 FEET FOR REFERENCE;

THENCE S 00°26'11" E, A DISTANCE OF 369.61 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A BENT T-RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS S 71°16'34" W, A DISTANCE OF 1730.98 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565718.35, E:773711.95 FEET FOR REFERENCE.


SAID CENTERLINE CONTAINING A TOTAL OF 369.61 FEET OR 22.40 RODS IN SAID SECTION 20.

NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910




TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM EAST WELL PAD
BUREAU OF LAND MANAGEMENT
 PROPOSED PIPELINE EASEMENT CENTERLINE

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 04/13/22	8910 ROBIN FED COM	0
SCALE: 1"=1000'	PAGE 2 OF 2	FLOWLINE EAST	
		(20-20S-34E)	



EASEMENT CENTERLINE BREAKDOWN BY SECTION 1/4 1/4					
1/4 1/4	OWNERSHIP	CL LENGTH	CL RODS	SQ. FEET	ACRES
SE-SW	BLM	1,391.64	84.34	41,749	0.958
SW-SE	BLM	1,325.73	80.35	39,772	0.913
SE-SE	BLM	150.37	9.11	4,511	0.104
TOTAL		2,867.74	173.80	86,032	1.975

EASEMENT CENTERLINE BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	S 00°28'27" E	331.23'
L2	N 89°36'28" E	2214.52'
L3	N 71°25'04" E	48.05'
L4	N 89°36'48" E	33.98'
L5	N 88°25'54" E	224.96'
L6	S 01°34'06" E	15.00'



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE

NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8910				

ROBIN FED COM WEST WELL PAD
BUREAU OF LAND MANAGEMENT
PROPOSED PIPELINE EASEMENT CENTERLINE

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: CAS	DATE: 04/13/22	DWG. NO. 8910 ROBIN FED COM FLOWLINE WEST (20-20S-34E)	REV. 0
CHECKED BY: MJM	DATE: 04/13/22		
SCALE: 1"=1000'	PAGE 1 OF 2		



TRANSGLOBAL SERVICES LLC

TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

CENTERLINE DESCRIPTION

BEING THE CENTERLINE OF A PROPOSED PIPELINE EASEMENT, SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID CENTERLINE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 1/2" BENT IRON PIPE FOUND FOR THE WEST QUARTER CORNER OF SAID SECTION 20 BEARS N 49°39'06" W, A DISTANCE OF 2099.54 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566404.99, E:771636.06 FEET FOR REFERENCE;

THENCE S 00°28'27" E, A DISTANCE OF 331.23 FEET TO A POINT;
 THENCE N 89°36'28" E, A DISTANCE OF 2214.52 FEET TO A POINT;
 THENCE N 71°25'04" E, A DISTANCE OF 48.05 FEET TO A POINT;
 THENCE N 89°36'48" E, A DISTANCE OF 33.98 FEET TO A POINT;
 THENCE N 88°25'54" E, A DISTANCE OF 224.96 FEET TO A POINT;

THENCE S 01°34'06" E, A DISTANCE OF 15.00 FEET TO THE POINT OF TERMINATION OF SAID CENTERLINE IN SAID SECTION 20, FROM WHICH A BENT T-RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS S 51°58'47" W, A DISTANCE OF 1514.66 FEET (TIE). SAID POINT OF TERMINATION HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:566095.63, E:774158.08 FEET FOR REFERENCE.


SAID CENTERLINE CONTAINING A TOTAL OF 2867.74 FEET OR 173.80 RODS IN SAID SECTION 20.


NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS EFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8910


TRANSGLOBAL SERVICES LLC
 TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181


			
ROBIN FED COM WEST WELL PAD BUREAU OF LAND MANAGEMENT PROPOSED PIPELINE EASEMENT CENTERLINE			
SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: CAS CHECKED BY: MJM SCALE: 1"=1000'	DATE: 04/13/22 DATE: 04/13/22 PAGE 2 OF 2	DWG. NO. 8910 ROBIN FED COM FLOWLINE WEST (20-20S-34E)	REV. 0



SURFACE SITE BEARING & DISTANCE TABLE		
LINE #	BEARING	DISTANCE
L1	N 01°33'10" W	300.03'
L2	N 88°25'54" E	449.91'
L3	S 01°33'42" E	300.07'
L4	S 88°26'13" W	449.96'

SURFACE SITE BREAKDOWN BY SECTION 1/4 1/4			
		AREA	
1/4 1/4	OWNERSHIP	SQ. FEET	ACRES
SW-SE	BLM	25,938	0.595
SE-SE	BLM	109,064	2.504
TOTAL		135,002	3.099

- LEGEND**
- SECTION LINE
 - OHE — OVERHEAD ELECTRIC
 - - - PROPOSED SURFACE SITE
 - EXISTING PIPELINE
 - FENCE LINE
 - X
 - POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



NOTES:

- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
- LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
- THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK
PROJECT NO. 8908				



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL LAND SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE



**ROBIN FED COM CTB PAD
 BUREAU OF LAND MANAGEMENT
 PROPOSED WELL PAD**

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: RRG	DATE: 03/15/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 03/15/22	8908 ROBIN FED COM CTB PAD (20-20S-34E) SURFACE SITE	0
SCALE: 1"=100'	PAGE 1 OF 2		

EXHIBIT "A"

METES AND BOUNDS DESCRIPTION

BEING A PROPOSED SURFACE SITE SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID SURFACE SITE BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 60°26'32" W, A DISTANCE OF 1416.36 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565789.56, E:773941.34 FEET FOR REFERENCE;

THENCE N 01°33'10" W, A DISTANCE OF 300.03 FEET TO A POINT;
 THENCE N 88°25'54" E, A DISTANCE OF 449.91 FEET TO A POINT;
 THENCE S 01°33'42" E, A DISTANCE OF 300.07 FEET TO A POINT, FROM WHICH A BENT T RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS S 56°21'02" E, A DISTANCE OF 1153.46 FEET (TIE);

THENCE S 88°26'13" W, A DISTANCE OF 449.96 FEET TO THE POINT OF BEGINNING.

SAID SURFACE SITE CONTAINING A TOTAL OF 135,002 SQUARE FEET OR 3.099 ACRES IN SAID SECTION 20.

NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8908

TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181




ROBIN FED COM CTB PAD
BUREAU OF LAND MANAGEMENT
 PROPOSED WELL PAD

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: RRG	DATE: 03/15/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 03/15/22	8908 ROBIN FED COM CTB PAD (20-20S-34E) SURFACE SITE	0
SCALE: 1"=100'	PAGE 2 OF 2		

PLAN VIEW




SECTION 20
T-20-S
R-34-E

ROBIN FED COM
CTB PAD CENTER POINT
NEW MEXICO EAST - NAD 83
LAT. = 32.55357018° N
LONG. = -103.57769117° W
815' FSL, 1183' FEL - SECTION 20
CUT: 0.30

LIMITS OF EARTHWORK
3:1 SLOPE (TYP.)




4/14/2022



ROBIN FED COM
EAST WELL PAD

TOTAL ACRES: 3.10



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM CTB PAD PAD GRADING AND CROSS SECTIONS




SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO

CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 1-2
------------------	-----------------	-----------


CROSS-SECTIONS



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181




ROBIN FED COM CTB PAD
PAD GRADING AND CROSS SECTIONS
 SITUATED IN
 SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
 N.M.P.M.
 LEA COUNTY, NEW MEXICO



CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 2-2
------------------	-----------------	-----------




Robin east pad

32.553, -103.57728
32.553, -103.57923
32.55087, -103.57923
32.55087, -103.57728
32.5496, -103.57927

T Over V pond
NWNE 28-20s-34e

Berry water station
N2NE4 2-21s-33e

MAP 8
4000 ft



SECTION 20
T-20-S
R-34-E

SECTION 29
T-20-S
R-34-E

LIMITS OF
EARTHWORK
3:1 SLOPE (TYP.)

PROPOSED
FLOWLINE

PROPOSED
ROAD



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM EAST WELL PAD PAD GRADING AND CROSS SECTIONS


SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO



4/14/2022

MAP 9a




TOTAL ACRES: 10.61



CUT	FILL	NET
16,436.41 CU. YD	16,436.40 CU. YD	0.01 CU. YD (CUT)
EARTHWORK QUANTITIES ARE ESTIMATED		

PROJECT NO. 8910	DATE: 04/13/2022	SHEET 1-2
------------------	------------------	-----------

CROSS-SECTIONS




ROBIN FED COM EAST WELL PAD PAD GRADING AND CROSS SECTIONS

SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181


MAP 9b



CUT	FILL	NET
16,436.41 CU. YD	16,436.40 CU. YD	0.01 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8910	DATE: 04/13/2022	SHEET 2-2
------------------	------------------	-----------



MAP 9d

METES AND BOUNDS DESCRIPTION

BEING A PROPOSED SURFACE SITE SITUATED IN SECTION 20 & SECTION 29, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID SURFACE SITE BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 29, FROM WHICH AN 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS N 81°48'27" W, A DISTANCE OF 1003.88 FEET (TIE), SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:564947.82, E:773702.93 FEET FOR REFERENCE;

THENCE N 00°26'42" W, A DISTANCE OF 770.15 FEET TO A POINT;
 THENCE N 88°26'34" E, A DISTANCE OF 600.11 FEET TO A POINT;
 THENCE S 00°26'42" E, A DISTANCE OF 770.15 FEET TO A POINT, FROM WHICH A BENT T RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS N 79°16'34" E, A DISTANCE OF 1067.13 FEET (TIE);

THENCE S 88°26'34" W, A DISTANCE OF 600.11 FEET TO THE POINT OF BEGINNING.

SAID SURFACE SITE CONTAINING A TOTAL OF 462,087 SQUARE FEET OR 10.608 ACRES IN SAID SECTION 20 & SECTION 29.


NOTES:

1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.


#	DATE	BY	DESCRIPTION	CHK

PROJECT NO. 8910


TRANSGLOBAL SERVICES LLC
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

 COLGATE ENERGY	
ROBIN FED COM EAST WELL PAD BUREAU OF LAND MANAGEMENT PROPOSED WELL PAD	
SITUATED IN SECTION 20 & SECTION 29 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO	
DRAWN BY: CAS	DATE: 04/13/22
CHECKED BY: MJM	DATE: 04/13/22
SCALE: 1"=100'	PAGE 2 OF 2
DWG. NO. 8910 ROBIN FED COM EAST WELL PAD (20-20S-34E) SURFACE SITE	REV. 0

PLAN VIEW



SECTION 20
T-20-S
R-34-E

ROBIN FED COM
EAST WELL PAD



MAP 9e

TOTAL ACRES: 3.10



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



ROBIN FED COM CTB PAD PAD GRADING AND CROSS SECTIONS




SITUATED IN
 SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
 N.M.P.M.
 LEA COUNTY, NEW MEXICO

CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)


EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 1-2
------------------	-----------------	-----------

CROSS-SECTIONS



MAP 9f



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181




ROBIN FED COM CTB PAD
PAD GRADING AND CROSS SECTIONS
SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO

CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 2-2
------------------	-----------------	-----------




SURFACE SITE BEARING & DISTANCE TABLE

LINE #	BEARING	DISTANCE
L1	N 01°33'10\" W	300.03'
L2	N 88°25'54\" E	449.91'
L3	S 01°33'42\" E	300.07'
L4	S 88°26'13\" W	449.96'

SURFACE SITE BREAKDOWN BY SECTION 1/4 1/4

1/4 1/4	OWNERSHIP	AREA	
		SQ. FEET	ACRES
SW-SE	BLM	25,938	0.595
SE-SE	BLM	109,064	2.504
TOTAL		135,002	3.099

- LEGEND
- SECTION LINE
 - OHE OVERHEAD ELECTRIC
 - - - PROPOSED SURFACE SITE
 - EXISTING PIPELINE
 - FENCE LINE
 - X POWER POLE
 - FOUND MONUMENT
 - CALCULATED CORNER
 - BEARING CHANGE



- NOTES:
- BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
 - LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
 - THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.

#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8908

TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181



I, MARK J. MURRAY, A NEW MEXICO PROFESSIONAL SURVEYOR, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

4/14/2022

MARK J. MURRAY NEW MEXICO PS #12177 DATE



ROBIN FED COM CTB PAD
BUREAU OF LAND MANAGEMENT
PROPOSED WELL PAD

SITUATED IN
 SECTION 20
 TOWNSHIP 20 SOUTH, RANGE 34 EAST
 NEW MEXICO PRINCIPAL MERIDIAN
 LEA COUNTY, NEW MEXICO

DRAWN BY: RRG	DATE: 03/15/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 03/15/22	8908 ROBIN FED COM CTB PAD (20-20S-34E) SURFACE SITE	0
SCALE: 1"=100'	PAGE 1 OF 2		

MAP 9h

METES AND BOUNDS DESCRIPTION

BEING A PROPOSED SURFACE SITE SITUATED IN SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST, NEW MEXICO PRINCIPAL MERIDIAN, LEA COUNTY, NEW MEXICO. SAID SURFACE SITE BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT, IN SAID SECTION 20, FROM WHICH A 4" IRON PIPE FOUND FOR THE SOUTH QUARTER CORNER OF SAID SECTION 20 BEARS S 60°26'32" W, A DISTANCE OF 1416.36 FEET (TIE). SAID POINT OF BEGINNING HAVING A NEW MEXICO STATE PLANE COORDINATES OF 1983, EAST ZONE, VALUE OF N:565789.56, E:773941.34 FEET FOR REFERENCE;

THENCE N 01°33'10" W, A DISTANCE OF 300.03 FEET TO A POINT;
 THENCE N 88°25'54" E, A DISTANCE OF 449.91 FEET TO A POINT;
 THENCE S 01°33'42" E, A DISTANCE OF 300.07 FEET TO A POINT, FROM WHICH A BENT T RAIL FOUND FOR THE SOUTHEAST CORNER OF SAID SECTION 20 BEARS S 56°21'02" E, A DISTANCE OF 1153.46 FEET (TIE);

THENCE S 88°26'13" W, A DISTANCE OF 449.96 FEET TO THE POINT OF BEGINNING.

SAID SURFACE SITE CONTAINING A TOTAL OF 135,002 SQUARE FEET OR 3.099 ACRES IN SAID SECTION 20.

NOTES:


1. BEARINGS, DISTANCES, AREA AND COORDINATES SHOWN HEREON ARE CORRELATED TO THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, AS DETERMINED BY GPS OPUS OBSERVATIONS. ALL BEARINGS AND DISTANCES SHOWN ARE GRID.
2. LATITUDE & LONGITUDE ARE NAD 83 DECIMAL GEOGRAPHIC.
3. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT AND THE REVIEW OF THE ABSTRACT OF TITLE. THERE MAY BE EASEMENTS AND/OR COVENANTS AFFECTING THIS PROPERTY NOT SHOWN HEREON. LOCATION OF ALL IMPROVEMENTS WAS BEYOND COMMISSIONED SCOPE OF THIS PROJECT AND HAS BEEN SPECIFICALLY OMITTED. VESTING DOCUMENTS NOT FURNISHED FOR THIS SURVEY.


#	DATE	BY:	DESCRIPTION	CHK

PROJECT NO. 8908



TBPELS FIRM# 10193740 / 19148
 2129 S Great Southwest Parkway Suite 313
 Grand Prairie, TX 75051
 (817) 529-1180 ~ Fax (817) 529-1181

 ROBIN FED COM CTB PAD BUREAU OF LAND MANAGEMENT PROPOSED WELL PAD			
SITUATED IN SECTION 20 TOWNSHIP 20 SOUTH, RANGE 34 EAST NEW MEXICO PRINCIPAL MERIDIAN LEA COUNTY, NEW MEXICO			
DRAWN BY: RRG	DATE: 03/15/22	DWG. NO.	REV.
CHECKED BY: MJM	DATE: 03/15/22	8908 ROBIN FED COM CTB PAD (20-20S-34E) SURFACE SITE	0
SCALE: 1"=100'	PAGE 2 OF 2		




Robin east pad

T Over V caliche pit
SENE 28-20s-34e

MAP 10

3000 ft



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181



**ROBIN FED COM EAST WELL PAD
PAD GRADING AND CROSS SECTIONS**


SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO



4/14/2022

MAP 9a


TOTAL ACRES: 10.61



CUT	FILL	NET
16,436.41 CU. YD	16,436.40 CU. YD	0.01 CU. YD (CUT)
EARTHWORK QUANTITIES ARE ESTIMATED		


PROJECT NO. 8910 DATE: 04/13/2022 SHEET 1-2

PLAN VIEW



MAP 11a

TOTAL ACRES: 10.61



ROBIN FED COM EAST WELL PAD
PAD GRADING AND CROSS SECTIONS
SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO

CUT	FILL	NET
16,436.41 CU. YD	16,436.40 CU. YD	0.01 CU. YD (CUT)
EARTHWORK QUANTITIES ARE ESTIMATED		
PROJECT NO. 8910	DATE: 04/13/2022	SHEET 1-2




TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181




4/14/2022

CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'




MAP 11b



ROBIN FED COM EAST WELL PAD PAD GRADING AND CROSS SECTIONS

SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO



CUT	FILL	NET
16,436.41 CU. YD	16,436.40 CU. YD	0.01 CU. YD (CUT)


EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8910	DATE: 04/13/2022	SHEET 2-2
------------------	------------------	-----------



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181

PLAN VIEW



SECTION 20
T-20-S
R-34-E

ROBIN FED COM
CTB PAD CENTER POINT
NEW MEXICO EAST - NAD 83
LAT. = 32.55357018° N
LONG. = -103.57769117° W
815' FSL, 1183' FEL - SECTION 20
CUT: 0.30

LIMITS OF EARTHWORK
3:1 SLOPE (TYP.)




4/14/2022

ROBIN FED COM
EAST WELL PAD

MAP 11c

TOTAL ACRES: 3.10



ROBIN FED COM CTB PAD PAD GRADING AND CROSS SECTIONS

SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO

CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)




EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 1-2
------------------	-----------------	-----------



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181

CROSS-SECTIONS




MAP 11d



**ROBIN FED COM CTB PAD
PAD GRADING AND CROSS SECTIONS**

SITUATED IN
SECTION 20, TOWNSHIP 20 SOUTH, RANGE 34 EAST
N.M.P.M.
LEA COUNTY, NEW MEXICO



CUT	FILL	NET
2,065.66 CU. YD	2,065.67 CU. YD	0.01 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

PROJECT NO. 8908	DATE: 3/07/2022	SHEET 2-2
------------------	-----------------	-----------



TBPELS FIRM# 10193740 / 19148
2129 S Great Southwest Parkway Suite 313
Grand Prairie, TX 75051
(817) 529-1180 ~ Fax (817) 529-1181

Robin Federal Project Well List

Colgate Operating, LLC

08/17/2023

Robin Fed Com Wells

West Pad

Robin Fed Com 111H

Surface Hole Location: 1680' FSL & 1255' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 112H

Surface Hole Location: 1680' FSL & 1375' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 121H

Surface Hole Location: 1680' FSL & 1285' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 122H

Surface Hole Location: 1680' FSL & 1315' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 990' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 123H

Surface Hole Location: 1680' FSL & 1345' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 124H

Surface Hole Location: 1680' FSL & 1405' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 131H

Surface Hole Location: 1480' FSL & 1285' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 132H

Surface Hole Location: 1480' FSL & 1345' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 201H

Surface Hole Location: 1480' FSL & 1315' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 990' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 202H

Surface Hole Location: 1480' FSL & 1375' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 171H

Surface Hole Location: 1480' FSL & 1255' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 990' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Com 172H

Surface Hole Location: 1480' FSL & 1405' FWL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FWL, Section 17, T. 20 S., R. 34. E.

Robin Fed Wells

East Pad

Robin Fed 113H

Surface Hole Location: 330' FSL & 1385' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 114H

Surface Hole Location: 330' FSL & 1265' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 125H

Surface Hole Location: 330' FSL & 1355' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 126H

Surface Hole Location: 330' FSL & 1325' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 127H

Surface Hole Location: 330' FSL & 1295' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 660' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 128H

Surface Hole Location: 330' FSL & 1235' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 133H

Surface Hole Location: 10' FSL & 1355' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 2310' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 134H

Surface Hole Location: 10' FSL & 1295' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 990' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 173H

Surface Hole Location: 10' FSL & 1385' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 174H

Surface Hole Location: 10' FSL & 1235' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 203H

Surface Hole Location: 10' FSL & 1325' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 1650' FEL, Section 17, T. 20 S., R. 34. E.

Robin Fed 204H

Surface Hole Location: 10' FSL & 1265' FEL, Section 20, T. 20 S., R. 34. E.

Bottom Hole Location: 10' FNL & 330' FEL, Section 17, T. 20 S., R. 34. E.

Well Site Locations

The results of the Robin Federal Development Program will develop economic quantities of oil and gas in the 'Parkway' area with multiple primary formations targeted. Well locations are determined based on cross-section variations and details. Locations will be selected to minimize the likelihood of encountering faults and/or drilling hazards while still targeting suitably productive zones.

If drilling results in an unproductive well, the well will be plugged and abandoned as soon as practical after the conclusion of production testing. Productive wells may be shut-in temporarily for BLM authorization for production activities and facilities.


Surface Use Plan

1. Existing Roads

- A. From the Junction of NM 18 and US 62/180 in South Hobbs go West 28.5 miles on US 62/180 to the equivalent of Mile Post 76.6. Turn left and go South by Southeast 3.75 miles on caliche County Road 27 (aka – Sheen Road). Turn right and go Southwest 575.09ft cross-county to the Northeast corner of the CTB. Transportation maps identifying existing roads that will be used to access the project area are included from TransGlobal marked as, 'Robin Federal Existing Access Map'.
- B. Transportation Plan identifying existing roads that will be used to access the project area is included from Permits West marked as, 'Robin Federal Existing Access Map.' All equipment and vehicles will be confined to the routes shown on the 'Robin Federal Existing Access Map' as provided by Permits West. Maintenance of the access roads will continue until abandonment and reclamation of the well pads is completed.

2. New or Upgraded Access Roads

- A. **New Roads.** There are a total of 5,755.39ft or 1.09 miles (3.96 acres) of proposed and staked access roads in the Robin Federal lease area.
- B. **Well Pads.** The well pads selected for development will determine which existing roads will be upgraded and which new roads will be built. The lease flow diagram shows the location of proposed roads that will need to be constructed to access the well pads.
- C. **Anticipated Traffic.** After well completion, travel to each well site will include one lease operator truck and two oil trucks per day until the Central Tank Battery are completed. Upon completion of the Central Tank Battery, one lease operator truck will continue to travel to each well site to monitor the working order of the wells and to check well equipment for proper operation. Two oil trucks will continue to travel to the Central Tank Battery only for oil hauling. Additional traffic will include one maintenance truck periodically throughout the year for pad upkeep and weed removal. Well service trips will include only the traffic necessary to work on the wells or provide chemical treatments periodically and as needed throughout the year.
- D. **Routing.** All equipment and vehicles will be confined to the travel routes laid out in the Robin Federal Existing Access Map and proposed new roads provided by Uintah Engineering & Land Surveying and Permits West unless otherwise approved by the BLM and applied for by Colgate Operating, LLC.
- E. **Road Dimensions.** The maximum width of the driving surface of new roads will be 14 feet. The roads will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1 foot deep with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.



Level Ground Section

- F. **Surface Material.** Surface material will be native caliche. The average grade of all roads will be approximately 3%.
- G. **Fence Cuts:** No.
- H. **Fences:** No.
- I. **Cattle Guards:** No.
- J. **Turnouts:** No.
- K. **Culverts:** No.
- L. **Cuts and Fills:** Not significant.
- M. **Topsoil.** Approximately 6 inches of topsoil (root zone) will be stripped from the proposed access road prior to any further construction activity. The topsoil that was stripped will be spread along the edge of the road and within the ditch. The topsoil will be seeded with the proper seed mix designated by the BLM.
- N. **Maintenance.** The access road will be constructed and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts installed as necessary to provide for proper drainage along with access road route.
- O. **Drainage.** The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, The Gold Book, Fourth Edition and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction.

3. Location of Existing Wells

- A. See attached Existing Wells map.

4. Ancillary Facilities

- A. **Ancillary Facilities.** No off-pad ancillary facilities are planned during the exploration phase including, but not limited to: campsites, airstrips or staging areas.

5. Location of Proposed Production Facilities

- A. **Production Facilities.** One pad was staked with the BLM for construction and use as Central Tank Battery (CTB). The Central Tank Battery is the Robin Federal tank battery. The Robin Federal tank battery is 300ftx450ft (3.09 Acres) located in the NESE Section 20-T20S-R31E NMPM, Lea County, New Mexico (Centerpoint: 815'FSL & 1183'FEL). Plat of the proposed facility is attached. A 3160-5 sundry notification will be submitted after construction with a site-security diagram and layout of the facility with associated equipment.
- B. **Buried & Surface Flowlines.** In the event the Robin Federal wells are found productive, twenty-four (24) 22in. or less buried composite flexpipe or steel flowlines with a maximum safety pressure rating of 1400psi (operating pressure: 750 psi) for transport of oil, gas, frac water, gas lift, fuel gas, and produced water are requested to the Robin Federal Central Tank Battery. If Colgate Operating, LLC decides to run surface lines, twenty-four (24) 4in. or less composite flexpipe or steel flowlines with a max. safety psi rating of 750 (op. psi: 125psi) for transport of oil, gas and produced water will be

- required to the Robin Federal Central Tank Battery. Total Flowline Length: 3237.35ft long by 30ft wide or 2.22 acres.
- C. **Midstream Tie-In.** A midstream tie-in is not requested with this project. In the event that a midstream tie-in is necessary, Colgate Operating, LLC will file application with the appropriate authorities to construct via right-of-way.
 - D. **Disposal Facilities.** Produced water will be hauled from location to a commercial disposal facility as needed. Once wells are drilled and completed, a 3160-5 sundry notification will be submitted to BLM in compliance with Onshore Order 7.
 - E. **Flare.** A flare is not requested with this project. The flare will be located on the proposed CTB and submitted on the subsequent facility diagram.
 - F. **Aboveground Structures.** All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as 'shale green' that reduce the visual impacts of the built environment.
 - G. **Containment Berms.** Containment berms will be constructed completely around any production facilities designed to hold fluids. The containment berms will be constructed of compacted subsoil, be sufficiently impervious, hold 1.5 times the capacity of the largest tank and away from cut or fill areas.
 - H. **Electrical.** Electrical is not proposed with this project as a power tie-in has not been identified. Once identified, Colgate Operating, LLC will file an application with the appropriate authorities to construct planned lines via right-of-way.

Production Facilities. One pad was staked with the BLM for construction and use as Central Tank Battery (CTB). The Central Tank Battery is the Robin Federal tank battery. The Robin Federal tank battery is 300ftx450ft (3.09 Acres) located in the NESE Section 20-T20S-R31E NMPM, Lea County, New Mexico (Centerpoint: 815'FSL & 1183'FEL). Plat of the proposed facility is attached. A 3160-5 sundry notification will be submitted after construction with a site-security diagram and layout of the facility with associated equipment. **Buried & Surface Flowlines.** In the event the Robin Federal wells are found productive, twenty-four (24) 22in. or less buried composite flexpipe or steel flowlines with a maximum safety pressure rating of 1400psi (operating pressure: 750 psi) for transport of oil, gas, frac water, gas lift, fuel gas, and produced water are requested to the Robin Federal Central Tank Battery. If Colgate Operating, LLC decides to run surface lines, twenty-four (24) 4in. or less composite flexpipe or steel flowlines with a max. safety psi rating of 750 (op. psi: 125psi) for transport of oil, gas and produced water will be required to the Robin Federal Central Tank Battery. Total Flowline Length: 3237.35ft long by 30ft wide or 2.22 acres. **Midstream Tie-In.** A midstream tie-in is not requested with this project. In the event that a midstream tie-in is necessary, Colgate Operating, LLC will file application with the appropriate authorities to construct via right-of-way. **Disposal Facilities.** Produced water will be hauled from location to a commercial disposal facility as needed. Once wells are drilled and completed, a 3160-5 sundry notification will be submitted to BLM in compliance with Onshore Order 7. **Flare.** A flare is not requested with this project. The flare will be located on the proposed CTB and submitted on the subsequent facility diagram. **Aboveground Structures.** All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as 'shale green' that reduce the visual impacts of the built environment. **Containment Berms.** Containment berms will be constructed completely around any production facilities designed to hold fluids. The containment berms will be constructed of compacted subsoil, be sufficiently impervious, hold 1.5 times the capacity of the largest tank and away from cut or fill areas. **Electrical.** Electrical is not proposed with this project as a power tie-in has not been identified. Once identified, Colgate Operating, LLC will file an application with the appropriate authorities to construct planned lines via right-of-way.

6. Location and Types of Water Supply

The well will be drilled using a combination of water mud systems as outlined in the drilling program. The water will be obtained from a 3rd party vendor and hauled to the proposed location by transport truck using the existing and proposed roads depicted in the attached exhibits. No water well will be drilled on the location.

Water for drilling, completion and dust control will be purchased from the following company:
Twin Wells Ranch (private source)

Water for drilling, completion and dust control will be supplied by private supplier T Over V's to Colgate Operating, LLC from the NWNE Section 28-T20S-R34E, Lea County, NM. If T Over V's is unable to provide water for drilling, completion, and dust control, Permian Rescours will utilize Berry's existing water station on State Land in the N2NE4 Section 2-T21S-R33E.

Anticipated water usage for drilling includes an estimated 50,000 barrels (bbls) of water to drill a horizontal well in a combination of fresh water and brine as detailed in the mud program in the drilling plans. These volumes are calculated for ~1.5 bbls per foot of hole drilled with excess to accommodate any lost circulation or wash out that may occur. Actual water volumes used during operations will depend on the depth of the well, length of horizontal sections, and the losses that may occur during the operation.

Temporary water flowlines will be permitted via ROW approval letter and proper grants as-needed based on drilling and completion schedules. Well completion is expected to require approximately 1,950,000 bbls of water per horizontal well. Actual water volumes used during operations will depend on the depth of the well and length of horizontal sections.

7. Construction Activities

- A. Construction, reclamation, and/or routine maintenance will not be conducted during periods when the soil conditions for construction could lead to impacts to the surrounding environment, or when watershed damage is likely to occur as a result of these activities.
- B. Any construction material that may be required for surfacing of the drill pad and access road will be from a contractor having a permitted source of materials within the general area. No construction materials will be removed from federal lands without prior approval from the appropriate surface management agency. All roads and well pads will be constructed of 6" rolled and compacted caliche.
- C. Anticipated Caliche Location:
 - a. Private Caliche Pit, SENE Section 28-T20S-R34E

8. Methods for Handling Waste

- **Cuttings.** The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.
- **Drilling Fluids.** These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility.
- **Produced Fluids.** Water produced from the well during completion will be held temporarily in steel tanks and then taken to a NMOCD approved commercial disposal facility. Oil produced during operations will be stored in tanks until sold.
- **Sewage.** Portable, self-contained toilets will be provided for human waste disposal. Upon completion of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- **Garbage and Other Waste Materials.** All garbage, junk and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed

and deposited in an approved sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location.

- **Debris.** Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned and removed from the well location. No potential adverse materials or substances will be left on location.
- **Hazardous Materials.**
 - i. All drilling wastes identified as hazardous substances by the Comprehensive Environmental Response Compensation Liability Act (CERCLA) removed from the location, and not reused at another drilling location, will be disposed of at a hazardous waste facility approved by the U.S. Environmental Protection Agency (EPA).
 - ii. Colgate Operating, LLC and its contractors will comply with all applicable Federal, State and local laws and regulations, existing or hereafter enacted/promulgated, with regard to any hazardous material, as defined in this paragraph, that will be used, produced, transported or stored on the oil and gas lease. "Hazardous material" means any substance, pollutant or contaminant that is listed as hazardous under the CERCLA of 1980, as amended, 42 U.S.C 9601 et seq., and its regulation. The definition of hazardous substances under CERCLA includes any "hazardous waste" as defined in the RCRA of 1976, as amended, 42 U.S.C. 6901 et seq., and its regulations. The term hazardous material also includes any nuclear or nuclear by-product material as defined by the Atomic Energy Act of 1954, as amended, 42 U.C.S. 2011 et seq. The term does not include petroleum, including crude oil or any fraction thereof that is not otherwise specifically listed or designated as a hazardous substance under CERCLA Section 101 (14) U.S.C. 9601 (14) nor does the term include natural gas.
 - iii. No hazardous substances or wastes will be stored on the location after completion of the well.
 - iv. Chemicals brought to location will be on the Toxic Substance Control Act (TSCA) approved inventory list.
 - v. All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in Notice to Lessees (NTL) 3A will be reported to the BLM Carlsbad Field Office. Major events will be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days.

9. Well Site Layout

- A. **Rig Plat Diagrams:** There are two (2) multi-well pads requested for the Robin Federal anticipated project. This will allow enough space for cuts and fills, topsoil storage, and storm water control. Interim reclamation of these pads is anticipated after the drilling and completion of all wells on the pad. The well site layout for all pads is attached.:
 1. West Pad: 650ftx600ft (8.95 Acres)
 2. East Pad: 600ftx770ft (10.60 Acres)
- B. **Closed-Loop System:** There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17.
- C. **V-Door Orientation:** The pad was staked with an East v-door orientation in accordance to the staked section and as agreed upon with Jeff Robertson, BLM Natural Resource Specialist, present at on-site inspection.
- D. All equipment and vehicles will be confined to the approved disturbed areas of this APD (i.e., access road, well pad and topsoil storage areas).

10. Plans for Surface Reclamation:

Colgate Operating, LLC requests a variance from interim reclamation until all drilling and completion activities have been finished on the pads as these are multi-well pads where drilling and completion will be consecutive with the other wells on the pad. Once activities are completed, Colgate Operating, LLC. will coordinate interim reclamation with the appropriate BLM personnel or use the following plan:

Non-Commercial Well (Not Productive), Interim & Final Reclamation:

Definition: Reclamation includes disturbed areas where the original landform and a natural vegetative community will be restored and it is anticipated the site will not be disturbed for future development.

Reclamation Standards:

The portions of the pad not essential to production facilities or space required for workover operations will be reclaimed and seeded as per BLM requirements for interim reclamation. (See Interim Reclamation plats attached).

All equipment and trash will be removed, and the surfacing material will be removed from the well pad and road and transported to the original caliche pit or used to maintain other roads. The location will then be ripped and seeded.

The original stock piled topsoil will be spread over the areas being reclaimed and the original landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors as close as possible to the original topography. The location will then be ripped and seeded.

A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gulying, headcutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

The site will be free of State or County listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native noxious weeds will be controlled.

Seeding:

- Seedbed Preparation: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left rough enough to trap seed and snow, control erosion, and increase water infiltration.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.
- Seed Application. Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.
- If the site is harrowed or dragged, seed will be covered by no more than 0.25 inch of soil.

11. Surface Ownership

- A. 100% of the Robin Federal project area is under the administrative jurisdiction of the Bureau of Land Management.
- B. The surface is multiple-use with the primary uses of the region for grazing and for the production of oil and gas.

12. Other Information

- **Cultural Resources – Archaeology:** A Class III Cultural Resources Examination has been by Lone Mountain Archaeological Services and the results will be forwarded to the BLM Office.
- **Dwellings and Structures.** There are no dwellings or structures within 2 miles of this location.

Surveying

- **Well Sites.** Well pad locations have been staked. Surveys of the proposed access roads and well pad locations have been completed by Uintah Engineering & Land Surveying, a registered professional land surveyor. Center stake surveys with access roads have been completed on Federal lands with Jeff Robertson, Bureau of Land Management Natural Resource Specialist, in attendance.

Soils and Vegetation

- **Environmental Setting.** Soils are classified as Reeves soils. These soils are associated with the loamy ecological site which typically supports black and blue grama and tobosa grasslands with an even distribution of yucca, mesquite, American tarbush, cholla, and creosote.
- **Traffic.** No truck traffic will be operated during periods or in areas of saturated ground when surface rutting could occur. The access road will be constructed and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts installed as necessary to provide for proper drainage along the access road route.
- **Water.** There is no permanent or live water in the immediate or within the project area.

13. Bond Coverage

Bond Number: NMB001841

Onsite: February 1, 2022 with Jeff Robertson (BLM Natural Resource Specialist) and James Rutley (BLM Geologist).



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

02/29/2024

APD ID: 10400085479

Submission Date: 05/21/2022

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information

Section 4 -

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection

Underground Injection Control (UIC) Permit?

UIC Permit

Section 5 - Surface

Would you like to utilize Surface Discharge PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 -

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data

02/29/2024

APD ID: 10400085479

Submission Date: 05/21/2022

Operator Name: COLGATE OPERATING LLC

Well Name: ROBIN FED

Well Number: 127H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data reflects the most recent changes
[Show Final Text](#)

Bond

Federal/Indian APD: FED

BLM Bond number:

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information

State of New Mexico
Energy, Minerals and Natural Resources Department

Oil Conservation Division
1220 South St. Francis Dr
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

I. Operator: Permian Resources Operating, LLC **OGRID:** 372165 **Date:** 8/29/2023

II. Type: Original Amendment due to 19.15.27.9.D(6)(a) NMAC 19.15.27.9.D(6)(b) NMAC Other.
If Other, please describe: _____.

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil	Anticipated Gas	Anticipated Prod Water
Robin Fed Com 111H		L-20-T20S-R34E	1680' FSL – 1255' FWL	730 BOPD	1062 MCFD	1729 BWPD
Robin Fed Com 112H		K-20-T20S-R34E	1680' FSL – 1375' FWL	730 BOPD	1062 MCFD	1729 BWPD
Robin Fed 113H		O-20-T20S-R34E	330' FSL – 1385' FEL	730 BOPD	1062 MCFD	1729 BWPD
Robin Fed 114H		P-20-T20S-R34E	330' FSL – 1265' FEL	730 BOPD	1062 MCFD	1729 BWPD
Robin Fed Com 121H		L-20-T20S-R34E	1680' FSL – 1285' FWL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed Com 122H		L-20-T20S-R34E	1680' FSL – 1315' FWL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed Com 123H		K-20-T20S-R34E	1680' FSL – 1345' FWL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed Com 124H		K-20-T20S-R34E	1680' FSL – 1405' FWL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed 125H		O-20-T20S-R34E	330' FSL – 1355' FEL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed 126H		O-20-T20S-R34E	330' FSL – 1325' FEL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed 127H		P-20-T20S-R34E	330' FSL – 1295' FEL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed 128H		P-20-T20S-R34E	330' FSL – 1235' FEL	869 BOPD	685 MCFD	3740 BWPD
Robin Fed Com 131H		L-20-T20S-R34E	1480' FSL – 1285' FWL	949 BOPD	1059 MCFD	4116 BWPD
Robin Fed Com 132H		K-20-T20S-R34E	1480' FSL – 1345' FWL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed 133H		O-20-T20S-R34E	10' FSL – 1355' FEL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed 134H		P-20-T20S-R34E	10' FSL – 1295' FEL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed Com 171H		L-20-T20S-R34E	1480' FSL – 1255' FWL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed Com 172H		K-20-T20S-R34E	1480' FSL – 1405' FWL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed 173H		O-20-T20S-R34E	10' FSL – 1385' FEL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed 174H		P-20-T20S-R34E	10' FSL – 1235' FEL	1054 BOPD	1177 MCFD	4573 BWPD
Robin Fed Com 201H		L-20-T20S-R34E	1480' FSL – 1315' FWL	2100 BOPD	2100 MCFD	5000 BWPD
Robin Fed Com 202H		K-20-T20S-R34E	1480' FSL – 1375' FWL	2100 BOPD	2100 MCFD	5000 BWPD
Robin Fed 203H		O-20-T20S-R34E	10' FSL – 1325' FEL	2100 BOPD	2100 MCFD	5000 BWPD
Robin Fed 204H		P-20-T20S-R34E	10' FSL – 1265' FEL	2100 BOPD	2100 MCFD	5000 BWPD

IV. Central Delivery Point Name: Batman CTB [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Robin Fed Com 111H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 112H		TBD	TBD	TBD	TBD	TBD
Robin Fed 113H		TBD	TBD	TBD	TBD	TBD
Robin Fed 114H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 121H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 122H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 123H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 124H		TBD	TBD	TBD	TBD	TBD
Robin Fed 125H		TBD	TBD	TBD	TBD	TBD
Robin Fed 126H		TBD	TBD	TBD	TBD	TBD
Robin Fed 127H		TBD	TBD	TBD	TBD	TBD
Robin Fed 128H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 131H		2/26/2024	3/13/2024	5/30/2024	6/23/2024	6/23/2024
Robin Fed Com 132H		4/1/2024	4/17/2024	5/30/2024	6/23/2024	6/23/2024
Robin Fed 133H		3/17/2024	4/2/2024	5/26/2024	6/23/2024	6/23/2024
Robin Fed 134H		4/21/2024	5/7/2024	5/26/2024	6/23/2024	6/23/2024
Robin Fed Com 171H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 172H		TBD	TBD	TBD	TBD	TBD
Robin Fed 173H		TBD	TBD	TBD	TBD	TBD
Robin Fed 174H		TBD	TBD	TBD	TBD	TBD
Robin Fed Com 201H		3/13/2024	4/1/2024	5/30/2024	6/23/2024	6/23/2024
Robin Fed Com 202H		4/2/2024	4/21/2024	5/26/2024	6/23/2024	6/23/2024
Robin Fed 203H		TBD	TBD	TBD	TBD	TBD
Robin Fed 204H		TBD	TBD	TBD	TBD	TBD

VI. Separation Equipment: Attach a complete description of how Operator will seize separation equipment to optimize gas capture.

VII. Operations Practices: Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 3 – Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or


Venting and Flaring Plan. Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) Power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 – Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
 - (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
 - (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, not later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file and update for each Natural Gas Management Plan until the Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
 - (c) OCD may deny or conditionally approve and APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: 
Printed Name: Tinlee Via
Title: Contract Drilling Engineer
E-mail Address: tinlee.via@permianres.com
Date: 9/29/2023
Phone: 512-755-6018

OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)

Approved By:
Title:
Approval Date:
Conditions of Approval:

Permian Resources Operating, LLC (372165)

Natural Gas Management Plan Descriptions**VI. Separation Equipment:**

Permian Resources Operating, LLC (Permian) utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations. Our goal is to maintain 5 minutes of retention time in the test vessel and 20 minutes in the heater treater at peak production rates. The gas produced is routed from the separator to the gas sales line.

VII. Operational Practices:*Drilling*

During Permian's drilling operations it is uncommon for venting or flaring to occur. If flaring is needed due to safety concerns, gas will be routed to a flare and volumes will be estimated.

Flowback

During completion/recompletion flowback operations, after separation flowback begins and as soon as it is technically feasible, Permian routes gas through a permanent separator and the controlled facility where the gas is either sold or flared through a high-pressure flare if needed.

Production

Per 19.15.27.8.D, Permian's facilities are designed to minimize waste. Our produced gas will only be vented or flared in an emergency or malfunction situation, except as allowed for normal operations noted in 19.15.27.8.D(2) & (4). All gas that is flared is metered. All gas that may be vented will be estimated.

Performance Standards

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations.

All of Permian's permanent storage tanks associated with production operations which are routed to a flare or control device are equipped with an automatic gauging system.

All of Permian's flare stacks, both currently installed and for future installation, are:

- 1) Appropriately sized and designed to ensure proper combustion efficiency.
- 2) Equipped with an automatic ignitor or continuous pilot.
- 3) Anchored and located at least 100 feet from the well and storage tanks.

Permian's field operations and HSE teams have implemented an AVO inspection schedule that adheres to the requirements of 19.15.27.8.E(5).

All of our operations and facilities are designed to minimize waste. We routinely employ the following methods and practices:

- Closed-loop systems
- Enclosed and properly sized tanks

Permian Resources Operating, LLC (372165)

- Vapor recovery units to maximize recovery of low-pressure gas streams and potential unauthorized emissions
- Low-emitting or electric engines whenever practical
- Combustors and flare stacks in the event of a malfunction or emergency
- Routine facility inspections to identify leaking components, functioning control devices, such as flares and combustors, and repair / replacement of malfunctioning components where applicable

Measurement or estimation

Permian measures or estimates the volumes of natural gas vented, flared and/or beneficially used for all of our drilling, completing and producing wells. We utilize accepted industry standards and methodology which can be independently verified. Annual GOR testing is completed on our wells and will be submitted as required by the OCD. None of our equipment is designed to allow diversion around metering elements except during inspection, maintenance and repair operations.

VIII. Best Management Practices:

Permian Resources utilizes the following BMPs to minimize venting during active and planned maintenance activities:

- Use a closed-loop process wherever possible during planned maintenance activities, such as blowdowns, liquid removal, and work over operations.
- Employ low-emitting or electric engines for equipment, such as compressors
- Adhere to a strict preventative maintenance program which includes routine facility inspections, identification of component malfunctions, and repairing or replacing components such as hatches, seals, valves, etc. where applicable
- Utilize vapor recovery units (VRU's) to maximize recovery of volumes of low-pressure gas streams and potential unauthorized emissions
- Route low pressure gas and emissions streams to a combustion device to prevent venting where necessary

Enhanced Natural Gas Management Plan

Operator's Plan to Manage Production in Response to Increased Line Pressure

Permian Resources Operating, LLC (Permian) anticipates that its existing wells connected to the same portion of the natural gas gathering system will continue to meet anticipated increases in line pressure caused by the new wells. Permian will actively monitor line pressure throughout the field and will make necessary adjustments to existing production separators' pressures to send gas to sales. Permian also plans to implement automated alarms on all flare meters to alert of flaring events as they occur. The alarms will send notifications to field operations and engineering staff via text message and email at every occurrence of flaring. In addition, Permian plans to implement automated alarms on all flare meters to alert of any continuous flaring event that has continued for at least 4 hours. The alarms will send notifications to field operations and engineering management. Permian personnel will promptly respond to these alarms, communicate with midstream partners, and take the appropriate action to reduce flaring caused by high line pressure from new well production.

District I
 1625 N. French Dr., Hobbs, NM 88240
 Phone:(575) 393-6161 Fax:(575) 393-0720
District II
 811 S. First St., Artesia, NM 88210
 Phone:(575) 748-1283 Fax:(575) 748-9720
District III
 1000 Rio Brazos Rd., Aztec, NM 87410
 Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
 1220 S. St Francis Dr., Santa Fe, NM 87505
 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 319299

CONDITIONS

Operator: Permian Resources Operating, LLC 300 N. Marienfeld St Ste 1000 Midland, TX 79701	OGRID: 372165
	Action Number: 319299
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	3/8/2024
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	3/8/2024
pkautz	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	3/8/2024
pkautz	Cement is required to circulate on both surface and intermediate1 strings of casing	3/8/2024
pkautz	If cement does not circulate on any string, a CBL is required for that string of casing	3/8/2024