NAME: MELISSA GUIDRY

**Email address:** 

# Operator Certification Data Report

Signed on: 02/18/2025

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

### **Operator**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Title: Advisor Regulatory Sr.		
Street Address: 5 GREENWAY PLA	AZA SUITE 110	
City: HOUSTON	State: TX	<b>Zip</b> : 77026
Phone: (713)497-2481		
Email address: MELISSA_GUIDRY	@OXY.COM	
Field		
Representative Name:		
Street Address:		
City: St	ate:	Zip:
Phone:		

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT Application Data

**APD ID**: 10400097805

Submission Date: 04/02/2024

Highlighted data reflects the most recent changes

**Operator Name: OXY USA INCORPORATED** 

Well Number: 15H

Show Final Text

Well Name: STACK CATS 25\_36 FED COM

Well Type: OIL WELL

Well Work Type: Drill

### **Section 1 - General**

APD ID: 10400097805 Tie to previous NOS? N Submission Date: 04/02/2024

**BLM Office:** Carlsbad **User:** MELISSA GUIDRY Title: Advisor Regulatory Sr.

Federal/Indian APD: FED Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM2379 Lease Acres:

Allotted? Reservation: Surface access agreement in place?

Federal or Indian agreement: FEDERAL Agreement in place? YES

Agreement number: NMNM106353894

Agreement name:

Keep application confidential? N

**Permitting Agent? NO** APD Operator: OXY USA INCORPORATED

Operator letter of

### **Operator Info**

**Operator Organization Name: OXY USA INCORPORATED** 

Operator Address: P.O. BOX 1002 **Zip:** 93276-1002

**Operator PO Box:** 

Operator City: TUPMAN State: CA

**Operator Phone:** (661)763-6046

**Operator Internet Address:** 

#### Section 2 - Well Information

Well in Master Development Plan? NO **Master Development Plan name:** 

Well in Master SUPO? NO **Master SUPO name:** 

Well in Master Drilling Plan? NO Master Drilling Plan name:

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H Well API Number:

Field Name: RED TANK Pool Name: BONE SPRING Field/Pool or Exploratory? Field and Pool

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

Is the proposed well in a Helium production area? N Use Existing Well Pad? N New surface disturbance?

Type of Well Pad: MULTIPLE WELL Multiple Well Pad Name: Number: 2504

REDTNK\_T22SR32E

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill
Well Type: OIL WELL
Describe Well Type:
Well sub-Type: INFILL

Describe sub-type:

Distance to town: Distance to nearest well: 30 FT Distance to lease line: 210 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: StackCats25\_36FedCom15H\_SitePlan\_20240402125957.pdf

StackCats25\_36FedCom15H\_C102\_20250218081321.pdf

### **Section 3 - Well Location Table**

Survey Type: RECTANGULAR

**Describe Survey Type:** 

Datum: NAD83 Vertical Datum: NAVD88

Survey number: Reference Datum: GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	210	FNL	168 9	FEL	22S	32E	25	Aliquot NWNE	32.36949 98	- 103.6252 656	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 2379	375 1	0	0	N
KOP Leg #1	300	FSL	131 0	FEL	22S	32E	24	Aliquot SESE	32.37090 59	- 103.6240 377	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 81633	- 516 6	896 5	891 7	N

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-1	100	FNL	131 0	FEL	22S	32E	25	Aliquot NENE	32.36980 64	103.6240 369	LEA	MEXI CO	NEW MEXI CO	F	NMNM 2379	- 581 8	994 7	956 9	Y
PPP Leg #1-2	0	FSL	131 0	FEL	22S	32E	25	Aliquot SESE	32.35556 5	- 103.6240 274	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 2379	- 581 8	149 05	956 9	Y
EXIT Leg #1	100	FSL	131 0	FEL	22S	32E	36	Aliquot SWSE	32.34132 93	- 103.6240 161	LEA	NEW MEXI CO	NEW MEXI CO	S	STATE	- 581 8	200 84	956 9	Y
BHL Leg #1	20	FSL	131 0	FEL	228	32E	36	Aliquot SWSE	32.34110 94	- 103.6240 159	LEA	NEW MEXI CO	NEW MEXI CO	S	STATE	- 581 8	201 64	956 9	N



### U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

**APD ID**: 10400097805 **Submission Date**: 04/02/2024

**Operator Name: OXY USA INCORPORATED** 

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Well Type: OIL WELL Well Work Type: Drill

Highlighted data reflects the most recent changes

**Show Final Text** 

### **Section 1 - Geologic Formations**

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
15300328	RUSTLER	3751	1020	1020	ANHYDRITE, DOLOMITE, SHALE	USEABLE WATER	N
15300329	SALADO	2041	1710	1710	ANHYDRITE, DOLOMITE, HALITE, SHALE	OTHER: SALT	N
15300330	CASTILE	416	3335	3335	ANHYDRITE	OTHER: SALT	N
15300331	DELAWARE	-1223	4974	4974	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : BRINE	Y
15300332	BELL CANYON	-1267	5018	5018	SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : BRINE	Y
15300333	CHERRY CANYON	-2060	5811	5811	SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : BRINE	Y
15300334	BRUSHY CANYON	-3390	7141	7161	SANDSTONE, SILTSTONE	OTHER: LOSSES	N
15300335	BONE SPRING	-5014	8765	8810	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y

### **Section 2 - Blowout Prevention**

Pressure Rating (PSI): 5M Rating Depth: 9569

Equipment: 13-5/8" 5M Annular, 5M Blind Ram, 5M Double Ram

Requesting Variance? YES

Variance request: Request for the use of a flexible choke line from the BOP to Choke Manifold.

**Testing Procedure:** BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per 43 CFR part 3170 Subpart 3172 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. OXY requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019. See the attached BOP Break Testing variance.

#### **Choke Diagram Attachment:**

StackCats25 36FedCom15H ChkManifolds 20240402140111.pdf

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

StackCats25\_36FedCom15H\_ChkManifolds\_20240402140111.pdf

### **BOP Diagram Attachment:**

StackCats25\_36FedCom15H\_BOP\_20240402140116.pdf

StackCats25\_36FedCom15H\_13inADAPT\_4S\_10x15\_20240402140124.pdf

StackCats25\_36FedCom15H\_FlexHoseCert\_20240402140129.pdf

### **Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1080	0	1080	3751	2671	1080	J-55	54.5	BUTT	1	1.1	BUOY	1.4	BUOY	1.4
2	INTERMED IATE	9.87 5	7.625	NEW	API	N	0	8865	0	8817	3698	-5066	8865	HCL -80	26.4	BUTT	1	1.1	BUOY	1.4	BUOY	1.4
3	PRODUCTI ON	6.75	5.5	NEW	API	N	0	20164	0	9569	3698	-5818	20164	P- 110		OTHER - WEDGE 461	1	1.1	BUOY	1.4	BUOY	1.4

#### **Casing Attachments**

Casing ID: 1 String SURFACE

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Casing Design Assumptions and Worksheet(s):

StackCats25\_36FedCom15H\_CsgCriteria\_20240402140348.pdf

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

### **Casing Attachments**

Casing ID: 2

String

**INTERMEDIATE** 

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Casing Design Assumptions and Worksheet(s):

StackCats25\_36FedCom15H\_CsgCriteria\_20240402140407.pdf

Casing ID: 3

String

**PRODUCTION** 

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Casing Design Assumptions and Worksheet(s):

StackCats25\_36FedCom15H\_CsgCriteria\_20240402140427.pdf

StackCats25\_36FedCom15H\_TNSWedge461\_5.500in\_20.00ppf\_P110CY\_20240402140436.pdf

### **Section 4 - Cement**

	String Type	Lead/Tail	Stage Tool Depth	Тор МD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
S	SURFACE	Lead	1	0	1080	1128	1.33	14.8	1500	100	Class C	Accelerator

INTERMEDIATE	Lead	2	0	7411	1342	1.71	13.3	2295	25	Class C	Accelerator

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Lead	1	7411	8865	199	1.65	13.2	328	5		Accelerator, Dispersant, Salt

PRODUCTION	Lead	1	8365	2016	668	1.84	13.3	1229	25	Class C	Retarder
				4							

### **Section 5 - Circulating Medium**

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

Describe the mud monitoring system utilized: PVT/MD Totco/Visual Monitoring

### **Circulating Medium Table**

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	РН	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1080	WATER-BASED MUD	8.6	8.8							
1080	8865	OTHER: SATURATED BRINE-BASED OR OIL-BASED MUD	8	10							
8865	2016 4	OTHER : WATER-BASED MUD OR OIL-	8	9.6							Page 4 of 6

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Top Depth
Bottom Depth
Min Weight (lbs/gal)
Max Weight (lbs/gal)
Max Weight (lbs/cu ft)
Gel Strength (lbs/100 sqft)
Yiscosity (CP)
Salinity (ppm)
Filtration (cc)
Additional Characteristics

### **Section 6 - Test, Logging, Coring**

List of production tests including testing procedures, equipment and safety measures:

GR from TD to surface (horizontal well vertical portion of hole)

Mud Log from Bone Spring - TD

CBL (production string) - to be ran by completions.

List of open and cased hole logs run in the well:

GAMMA RAY LOG, CEMENT BOND LOG, DIRECTIONAL SURVEY, MUD LOG/GEOLOGICAL LITHOLOGY LOG,

#### Coring operation description for the well:

No coring is planned at this time.

#### **Section 7 - Pressure**

Anticipated Bottom Hole Pressure: 4777 Anticipated Surface Pressure: 2671

Anticipated Bottom Hole Temperature(F): 157

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

StackCats25\_36FedCom15H\_H2S1\_20240402140946.pdf StackCats25\_36FedCom15H\_H2S2\_20240402140950.pdf

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

### **Section 8 - Other Information**

#### Proposed horizontal/directional/multi-lateral plan submission:

StackCats25\_36FedCom15H\_DirectPlan\_20240402141008.pdf

#### Other proposed operations facets description:

#### Other proposed operations facets attachment:

 $Stack Cats 25\_36 Fed Com 15 H\_API\_BTC\_SC\_10.750 in\_45.50 ppf\_L80 IC\_20240402141034.pdf$ 

 $Stack Cats 25\_36 Fed Com 15 H\_Drill Plan\_3S\_20240402141020.pdf$ 

 $Stack Cats 25\_36 Fed Com 15 H\_Spud Rig Data\_20240402141025.pdf$ 

StackCats25\_36FedCom15H\_DrillPlan\_4S\_20240402141030.pdf

#### Other Variance attachment:

StackCats25\_36FedCom15H\_BOPBreakTestingVariance\_20240402141041.pdf

StackCats25\_36FedCom15H\_BradenheadCBLVariance\_20240402141048.pdf

StackCats25\_36FedCom15H\_OfflineCementVariance\_20240402141053.pdf

 $Stack Cats 25\_36 Fed Com 15 H\_Prod Csg Ann Clearance Variance\_20240402141058.pdf$ 



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT SUPO Data Report

APD ID: 10400097805

Submission Date: 04/02/2024

Highlighted data reflects the most recent changes

**Show Final Text** 

**Operator Name: OXY USA INCORPORATED** 

Well Number: 15H

Well Name: STACK CATS 25\_36 FED COM

Well Type: OIL WELL

Well Work Type: Drill

### **Section 1 - Existing Roads**

Will existing roads be used? YES

**Existing Road Map:** 

StackCats25 36FedCom15H ExistRoads 20240402141136.pdf

Existing Road Purpose: ACCESS, FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

**Existing Road Improvement Description:** 

**Existing Road Improvement Attachment:** 

### **Section 2 - New or Reconstructed Access Roads**

Will new roads be needed? YES

**New Road Map:** 

StackCats25\_36FedCom15H\_NewRoads\_20241112143658.pdf

New road type: LOCAL

Length: 7293 Feet Width (ft.): 30

Max grade (%): 0 Max slope (%): 0

Army Corp of Engineers (ACOE) permit required? N

ACOE Permit Number(s):

New road travel width: 20

New road access erosion control: Watershed diversion every 200', if needed.

New road access plan or profile prepared? N

New road access plan

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Access road engineering design? N

Access road engineering design

Turnout? N

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: CALICHE

Access onsite topsoil source depth: 0

Offsite topsoil source description:

Onsite topsoil removal process: If available

Access other construction information:

Access miscellaneous information:

Number of access turnouts: Access turnout map:

### **Drainage Control**

New road drainage crossing: CULVERT

Drainage Control comments: Watershed diversion every 200', if needed.

Road Drainage Control Structures (DCS) description: Watershed diversion every 200', if needed.

Road Drainage Control Structures (DCS) attachment:

#### **Access Additional Attachments**

### **Section 3 - Location of Existing Wells**

**Existing Wells Map?** YES

Attach Well map:

StackCats25 36FedCom15H ExistWells 20240402141218.pdf

### Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

**Production Facilities description:** 

**Production Facilities map:** 

StackCats25\_36FedCom15H\_LeaseFacility\_20241203070418.pdf

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

### **Section 5 - Location and Types of Water Supply**

#### **Water Source Table**

Water source type: GW WELL

Water source use type: SURFACE CASING

OTHER Describe use type: DRILLING

INTERMEDIATE/PRODUCTION

**CASING** 

Source latitude: Source longitude:

Source datum:

Water source permit type: WATER WELL

Water source transport method: TRUCKING

**PIPELINE** 

Source land ownership: COMMERCIAL

Source transportation land ownership: COMMERCIAL

Water source volume (barrels): 2000 Source volume (acre-feet): 0.25778619

Source volume (gal): 84000

#### Water source and transportation

StackCats25\_36FedCom15H\_GRRWtrSrc\_20240402141247.pdf

StackCats25\_36FedCom15H\_MesqWtrSrc\_20240402141252.pdf

 $Stack Cats 25\_36 Fed Com 15 H\_Water Caliche Source Map\_20241112143750.pdf$ 

**Water source comments:** This well will be drilled using a combination of water mud systems. It will be obtained from commercial water stations (Gregory Rockhouse, Mesquite) in the area and will be hauled to location by transport truck using existing and proposed roads.

New water well? N

### **New Water Well Info**

Well latitude: Well Longitude: Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft): Est thickness of aquifer:

**Aquifer comments:** 

Aguifer documentation:

Well depth (ft): Well casing type:

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Well casing outside diameter (in.): Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method: Drill material:

Grout material: Grout depth:

Casing length (ft.): Casing top depth (ft.):

Well Production type: Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

#### **Section 6 - Construction Materials**

Using any construction materials: YES

Construction Materials description: Primary All caliche utilized for the drilling pad and proposed access road will be obtained from an existing BLM/State/Fee approved pit or from prevailing deposits found on the location. Will use BLM recommended extra caliche from other locations close by for roads, if available. Secondary The secondary way of obtaining caliche to build locations and roads will be by turning over the location. This means, caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cubic yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel: a. The top 6 of topsoil is pushed off and stockpiled along the side of the location. b. An approximate 120 X 120 area is used within the proposed well site to remove caliche. c. Subsoil is removed and piled alongside the 120 X 120 within the pad site. d. When caliche is found, material will be stockpiled within the pad site to build the location and road. e. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road. f. Once the well is drilled the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the site plan included with this APD.

#### **Construction Materials source location**

StackCats25 36FedCom15H WaterCalicheSourceMap 20241112143801.pdf

### **Section 7 - Methods for Handling**

Waste type: DRILLING

Waste content description: Water-Based Cuttings, Water-Based Mud, Oil-Based Cuttings, Oil-Based Mud, Produced Water

Amount of waste: 1559 barrels

Waste disposal frequency : Daily

Safe containment description: Haul-Off Bins

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: COMMERCIAL

FACILITY

Disposal type description:

**Disposal location description:** An approved facility that can process drill cuttings, drill fluids, flowback water, produced water, contaminated soils, and other non-hazardous wastes. Methods of Handling Waste Material: a. A closed loop system will be utilized consisting of above ground steel tanks and haul-off bins.

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Disposal of liquids, drilling fluids and cuttings will be disposed of at an approved facility. Solids-CRI, Liquids-Laguna b. All trash, junk and other waste material will be contained in trash cages or bins to prevent scattering. When the job is completed, all contents will be removed and disposed of in an approved sanitary landfill. c. The supplier, including broken sacks, will pickup slats remaining after completion of well. d. A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete. e. Disposal of fluids to be transported will be by the following companies. TFH Ltd, Laguna SWD Facility

#### **Reserve Pit**

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) Reserve pit width (ft.)

Reserve pit depth (ft.) Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

### **Cuttings Area**

Cuttings Area being used? NO

Are you storing cuttings on location? Y

**Description of cuttings location** A closed loop system will be utilized consisting of above ground steel tanks and haul-off bins. Disposal of liquids, drilling fluids and cuttings will be disposed of at an approved facility.

Cuttings area width (ft.)

Cuttings area length (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

**WCuttings** area liner

Cuttings area liner specifications and installation description

### **Section 8 - Ancillary**

Are you requesting any Ancillary Facilities?: N

**Ancillary Facilities** 

Comments:

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

#### Section 9 - Well Site

#### Well Site Layout Diagram:

StackCats25 36FedCom15H ClosedLoop 20241112143902.pdf

Comments:

#### Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance Multiple Well Pad Name: REDTNK\_T22SR32E

Multiple Well Pad Number: 2504

#### Recontouring

StackCats25\_36FedCom15H\_CutFill\_20240402141742.pdf StackCats25\_36FedCom15H\_SitePlan\_20241112143909.pdf

**Drainage/Erosion control construction:** Reclamation to be wind rowed as needed to control erosion.

Drainage/Erosion control reclamation: Reclamation to be wind rowed as needed to control erosion.

Well pad proposed disturbance Well pad interim reclamation (acres): 1 Well pad long term disturbance

(acres): 6 (acres): 5

Road proposed disturbance (acres): 5 Road interim reclamation (acres): 2 Road long term disturbance (acres): 3

Powerline proposed disturbance Powerline interim reclamation (acres): Powerline long term disturbance

(acres): 6 (acres): 0

Pipeline proposed disturbance Pipeline interim reclamation (acres): Pipeline long term disturbance

(acres): 24 16 (acres): 8

Other proposed disturbance (acres): 1 Other interim reclamation (acres): 0 Other long term disturbance (acres): 1

Total proposed disturbance: 42 Total interim reclamation: 25 Total long term disturbance: 17

#### **Disturbance Comments:**

Reconstruction method: If the well is deemed commercially productive, caliche from the areas of the pad site not required for operations will be reclaimed. The original topsoil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography, and the are will be seeded with an approved BLM mixture to re-establish vegetation. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. the original topsoil will again be returned to the pad and contoured, as close as possible, to the original topography and the area will be seeded with an approved BLM mixture to re-establish vegetation.

**Topsoil redistribution:** The original topsoil will be returned to the area of the drill pad not necessary to operate the well.

Soil treatment: To be determined by BLM.

Existing Vegetation at the well pad: To be determined by BLM at onsite.

Existing Vegetation at the well pad

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Existing Vegetation Community at the road: To be determined by BLM at onsite.

**Existing Vegetation Community at the road** 

Existing Vegetation Community at the pipeline: To be determined by BLM at onsite.

**Existing Vegetation Community at the pipeline** 

Existing Vegetation Community at other disturbances: To be determined by BLM at onsite.

**Existing Vegetation Community at other disturbances** 

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Seed

**Seed Table** 

Seed Summary

Total pounds/Acre:

Seed Type

Pounds/Acre

Seed reclamation

## Operator Contact/Responsible Official

First Name: Mike Last Name: Wilson

Phone: (575)631-6618 Email: michael\_wilson@oxy.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? N

Existing invasive species treatment description:

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

**Existing invasive species treatment** 

Weed treatment plan description: To be determined by BLM.

Weed treatment plan

Monitoring plan description: To be determined by BLM.

Monitoring plan

Success standards: To be determined by BLM.

Pit closure description: NA

Pit closure attachment:

### **Section 11 - Surface Ownership**

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

NPS Local Office:

State Local Office:

Military Local Office:

**USFWS Local Office:** 

Other Local Office:

**USFS Region:** 

USFS Forest/Grassland: USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

**BIA Local Office:** 

Operator Name: OXY USA INCORPORATED	
Well Name: STACK CATS 25_36 FED COM	Well Number: 15H
BOR Local Office:	
COE Local Office:	
DOD Local Office:	
NPS Local Office:	
State Local Office:	
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:
Disturbance type: PIPELINE	
Describe:	
Surface Owner: BUREAU OF LAND MANAGEMENT	
Other surface owner description:	
BIA Local Office:	
BOR Local Office:	
COE Local Office:	
DOD Local Office:	
NPS Local Office:	
State Local Office:	
Military Local Office:	

**USFS Ranger District:** 

USFWS Local Office:
Other Local Office:

**USFS Forest/Grassland:** 

**USFS Region:** 

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Disturbance type: OTHER

Describe: ELECTRIC LINES

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

**NPS Local Office:** 

State Local Office:

Military Local Office:

**USFWS Local Office:** 

Other Local Office:

**USFS Region:** 

**USFS** Forest/Grassland:

**USFS Ranger District:** 

### Section 12 - Other

Right of Way needed? Y

Use APD as ROW? Y

**ROW Type(s):** 281001 ROW - ROADS,285003 ROW - POWER TRANS,288100 ROW - O&G Pipeline,288101 ROW - O&G Facility Sites,289001 ROW- O&G Well Pad

**ROW** 

**SUPO Additional Information:** Permian Basin MOA: To be submitted after APD acceptance. GIS shapefiles available for BLM.

Use a previously conducted onsite? N

**Previous Onsite information:** 

**Other SUPO** 

StackCats25\_36FedCom15H\_NGMP\_20240402141934.pdf StackCats25\_36FedCom15H\_StakingSheet\_20240402141927.pdf

#### U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

PWD Data Report

PWD disturbance (acres):

**APD ID**: 10400097805 **Submission Date**: 04/02/2024

**Operator Name: OXY USA INCORPORATED** 

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Well Type: OIL WELL Well Work Type: Drill

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### **Section 2 - Lined**

Would you like to utilize Lined Pit PWD options? N

**Produced Water Disposal (PWD) Location:** 

PWD surface owner:
Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Released to Imaging: 4/30/2025 11:44:29 AM

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Lined pit Monitor description:

**Lined pit Monitor** 

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

### **Section 3 - Unlined**

Would you like to utilize Unlined Pit PWD options? N

**Produced Water Disposal (PWD) Location:** 

PWD disturbance (acres): PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

**Unlined** pit

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

**Unlined pit Monitor description:** 

**Unlined pit Monitor** 

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

State

**Unlined Produced Water Pit Estimated** 

Unlined pit: do you have a reclamation bond for the pit?

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information

Section 4 -

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner: PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number: Injection well name:

Assigned injection well API number? Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection

**Underground Injection Control (UIC) Permit?** 

**UIC Permit** 

**Section 5 - Surface** 

Would you like to utilize Surface Discharge PWD options? N

**Produced Water Disposal (PWD) Location:** 

PWD surface owner: PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

**Surface Discharge NPDES Permit attachment:** 

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 -

Would you like to utilize Other PWD options? N

**Produced Water Disposal (PWD) Location:** 

PWD surface owner: PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Well Name: STACK CATS 25\_36 FED COM Well Number: 15H

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements

#### U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

**Bond Info Data** 03/27/2025

APD ID: 10400097805

Submission Date: 04/02/2024

Highlighted data reflects the most recent changes

**Operator Name: OXY USA INCORPORATED** 

Well Number: 15H

Show Final Text

Well Name: STACK CATS 25\_36 FED COM

Well Work Type: Drill

Well Type: OIL WELL

#### **Bond**

Federal/Indian APD: FED

**BLM Bond number:** ESB000226

**BIA Bond number:** 

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

**BLM** reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond

Reclamation bond number:

**Reclamation bond amount:** 

**Reclamation bond rider amount:** 

Additional reclamation bond information

Form 3160-3 FORM APPROVED OMB No. 1004-0137 (June 2015) Expires: January 31, 2018 **UNITED STATES** DEPARTMENT OF THE INTERIOR 5. Lease Serial No. NMNM2379 **BUREAU OF LAND MANAGEMENT** APPLICATION FOR PERMIT TO DRILL OR REENTER 6. If Indian, Allotee or Tribe Name 7. If Unit or CA Agreement, Name and No. **✓** DRILL REENTER 1a. Type of work: NMNM106353894 Oil Well 1b. Type of Well: Gas Well Other 8. Lease Name and Well No. 1c. Type of Completion: Hydraulic Fracturing Single Zone ✓ Multiple Zone STACK CATS 25 36 FED COM 15H 2. Name of Operator 9. API Well No. **OXY USA INCORPORATED** 30-025-54618 3a. Address 3b. Phone No. (include area code) 10. Field and Pool, or Exploratory P.O. BOX 1002, TUPMAN, CA 93276-1002 (661) 763-6046 RED TANK/BONE SPRING 4. Location of Well (Report location clearly and in accordance with any State requirements.\*) 11. Sec., T. R. M. or Blk. and Survey or Area SEC 25/T22S/R32E/NMP At surface NWNE / 210 FNL / 1689 FEL / LAT 32.3694998 / LONG -103.6252656 At proposed prod. zone SWSE / 20 FSL / 1310 FEL / LAT 32.3411094 / LONG -103.6240159 14. Distance in miles and direction from nearest town or post office\* 12. County or Parish 13. State NM LEA 15. Distance from proposed\* 16. No of acres in lease 17. Spacing Unit dedicated to this well 210 feet location to nearest property or lease line, ft. 640.0 (Also to nearest drig. unit line, if any) 18. Distance from proposed location\* 19. Proposed Depth 20. BLM/BIA Bond No. in file to nearest well, drilling, completed, 30 feet 9569 feet / 20164 feet FED: ESB000226 applied for, on this lease, ft. 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 22. Approximate date work will start\* 23. Estimated duration 3751 feet 02/28/2025 45 days 24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable) 1. Well plat certified by a registered surveyor. 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the 5. Operator certification. SUPO must be filed with the appropriate Forest Service Office). 6. Such other site specific information and/or plans as may be requested by the 25. Signature Name (Printed/Typed) Date MELISSA GUIDRY / Ph: (713) 366-5716 04/02/2024 (Electronic Submission) Title Advisor Regulatory Sr. Approved by (Signature) Date Name (Printed/Typed) (Electronic Submission) CHRISTOPHER WALLS / Ph: (575) 234-2234 03/27/2025 Title Office Petroleum Engineer Carlsbad Field Office Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



Conditions of approval, if any, are attached.

#### **INSTRUCTIONS**

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

#### NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

### **Additional Operator Remarks**

#### **Location of Well**

0. SHL: NWNE / 210 FNL / 1689 FEL / TWSP: 22S / RANGE: 32E / SECTION: 25 / LAT: 32.3694998 / LONG: -103.6252656 ( TVD: 0 feet, MD: 0 feet )
PPP: NENE / 100 FNL / 1310 FEL / TWSP: 22S / RANGE: 32E / SECTION: 25 / LAT: 32.3698064 / LONG: -103.6240369 ( TVD: 9569 feet, MD: 9947 feet )
PPP: SESE / 0 FSL / 1310 FEL / TWSP: 22S / RANGE: 32E / SECTION: 25 / LAT: 32.355565 / LONG: -103.6240274 ( TVD: 9569 feet, MD: 14905 feet )
BHL: SWSE / 20 FSL / 1310 FEL / TWSP: 22S / RANGE: 32E / SECTION: 36 / LAT: 32.3411094 / LONG: -103.6240159 ( TVD: 9569 feet, MD: 20164 feet )

#### **BLM Point of Contact**

Name: TENILLE C MOLINA Title: Land Law Examiner Phone: (575) 234-2224

Email: TCMOLINA@BLM.GOV

### **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

	•	/28/2025 7:0	03:50 AM		G: 0==				1		Page 30
<u>C-1</u>	<u>02</u>		En	erov M	State of No		Mexico Resources Departm	ent		1	Revised July 9, 202
Suhmi	it Electronica	llv	Lil				ON DIVISION	CIII			
	CD Permitting	,							Submittal	☑ Initial Su	bmittal
									Type:	☐ Amended	d Report
										☐ As Drille	ed .
					WELL LOCA	ATIO	N INFORMATION				
30-02	Number 25-54618		Pool Code 51683				l Name RED T			E SPF	RING
Prope	rty Code 33	3676	Property N	ame ST	TACK C	ΑT	S 25_36 I	FED (	COM	Well Number	er
OGRI <b>1669</b> (	D No. 6		Operator N		XY USA	١N	1C.			Ground Level 3751'	el Elevation
Surfac	ce Owner: 🗆	State □ Fee □	Tribal 🗹 Fee	deral			Mineral Owner:   S	State   Fee	🗆 Tribal 🗹 I	Federal	
					Sui	rface	Location				
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude	L	ongitude	County
В	25	22S	32E		210' FN	۱L	1689' FEL	32.3694	19985 -10	03.62526566	LEA
					Botto	m Ho	ole Location		<b>I</b>		<u> </u>
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude	L	ongitude	County
O	36	22S	32E		20' FS	L	1310' FEL	32.3411	10939 -10	03.62401594	LEA
			·					I			
	ated Acres	Infill or Def	ining Well	Definin	ng Well API		Overlapping Spacing	Unit (Y/N)	Consolidati	on Code	
<u>640</u>	0.00	INFILL					N				
Order	Numbers.						Well setbacks are und	ler Common (	Ownership: [	□Yes □No	
					Kick	Off P	Point (KOP)				
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude	L	ongitude	County
0	24	22S	32E		300' FS	SL	1310' FEL	32.3709	0592 -10	03.62403772	LEA
		1	1		First	Take	Point (FTP)				<u>  — — -                                  </u>
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude	L	ongitude	County
Α	25	22S	32E		100' FN	۱L	1310' FEL	32.3698	30643 -10	03.62403697	LEA
					Last T	Take 1	Point (LTP)	<u> </u>			
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude	L	ongitude	County
O	36	22S	32E		100' FS	SL	1310' FEL	32.3413	32929 -10	03.62401612	LEA
								<u> </u>			
Unitiz	zed Area or A	rea of Uniform	Interest	Spacing	g Unit Type 🛭 Hor	rizont	al   Vertical	Groun 3751	nd Floor Elev	vation:	
OPER	RATOR CER	TIFICATIONS				SI	URVEYOR CERTIFIC	CATIONS			
my kno organi includi locatio interes	owledge and be zation either ov ing the propose on pursuant to a	lief, and, if the we wns a working into d bottom hole loca a contract with an tary pooling agree	ll is a vertical or crest or unleasea ation or has a ri owner of a work	directional mineral int ght to drill t ing interest	terest in the land	su my	hereby certify that the we urveys made by me or unde y belief.		on, and that the		d correct to the best o
					on has received the cased mineral interest	t				f Survey: MARCH 27,2024 re and Seal of Professional Surveyor	

in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

#### Melissa Guidry 03/28/25

Signature Melissa Guidry

Signature and Seal of Professional Surveyor

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

Printed Name


melissa\_guidry@oxy.com

Email Address

Certificate Number Date of Survey March 27, 2024

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.



Distances/areas relative to NAD 83 grid measurements. Combined Scale Factor: 0.99975697 and a Convergence Angle: 0.070667000

### State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

### NATURAL GAS MANAGEMENT PLAN

	11	AT UKAL G	AD MANA	GENIENT I					
This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.									
			1 – Plan D ffective May 25.						
I. Operator: OXY US	A INC.		OGRID: _16	6696	Γ	Date: 0 4/	0 2/2 4		
II. Type: 🗹 Original	☐ Amendment	due to □ 19.15.27.	.9.D(6)(a) NMA	C □ 19.15.27.9.D(	(6)(b) NMA	C □ Other.			
If Other, please describe	»:								
III. Well(s): Provide the be recompleted from a s					wells propos	sed to be dr	illed or proposed to		
Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipa Gas MCI		Anticipated Produced Water BBL/D		
SEE ATTACHED									
IV. Central Delivery P V. Anticipated Schedul proposed to be recomple	le: Provide the	e following informa	tion for each nev			•	27.9(D)(1) NMAC] osed to be drilled or		
Well Name	API	Spud Date	TD Reached Date	Completion Commencement		itial Flow ack Date	First Production Date		
SEE ATTACHED									
VI. Separation Equipment: ✓ Attach a complete description of how Operator will size separation equipment to optimize gas capture.  VII. Operational Practices: ✓ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.  VIII. Best Management Practices: ✓ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.									

### Section 2 – Enhanced Plan EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

✓ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

### IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

### X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering	Available Maximum Daily Capacity
_	-		Start Date	of System Segment Tie-in

XI. Map. $\square$ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the
production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of
the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system $\square$ will $\square$ will not have capacity to gather 100% of the anticipated natural	ral gas
production volume from the well prior to the date of first production.	

XIII. L	ine Pressure.	Operator	does 🗆 does	not anticipate	e that its exis	ting well(s)	connected to	the same se	gment,	or portion	, of the
natural	gas gathering	system(s) des	scribed above	will continue	e to meet ant	icipated inc	reases in line	pressure cau	used by	the new w	ell(s).

		· •	1 .		1	•	1		1.
1 1	Affach (	Inerator's	s nlan ta	manage	nroduction	in resnonce	to the	increased	line pressure

XIV.	nfidentiality:  Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in
Section	as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information
for wh	confidentiality is asserted and the basis for such assertion.

Released to Imaging: 4/30/2025 11:44:29 AM

## Section 3 - Certifications Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☑ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

**Well Shut-In.** □ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. □ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

(a) power generation on lease;

If Operator checks this box, Operator will select one of the following:

- **(b)** power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- **(g)** reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

### **Section 4 - Notices**

- 1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
- (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: Melíssa Guídry
Printed Name: Melissa Guidry
Title: Advisor Regulatory Sr.
E-mail Address: melissa_guidry@oxy.com
Date: 04/02/24
Phone: 713-497-2481
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)
Approved By:
Title:
Approval Date:
Conditions of Approval:

### III. Well(s)

Well Name	API	WELL LOCATION (ULSTR)	Footages	ANTICIPATED OIL BBL/D	ANTICIPATED GAS MCF/D	ANTICIPATED PROD WATER BBL/D
STACK CATS 25-36 FED COM 1H	Pending	S-24-22S-32E	275 FSL 1215 FWL	1000	4000	3500
STACK CATS 25-36 FED COM 2H	Pending	S-24-22S-32E	275 FSL 1275 FWL	1000	4000	3500
STACK CATS 25-36 FED COM 3H	Pending	N-25-22S-32E	210 FNL 1719 FEL	1000	4000	3500
STACK CATS 25-36 FED COM 4H	Pending	N-25-22S-32E	210 FNL 1659 FEL	1000	4000	3500
STACK CATS 25-36 FED COM 11H	Pending	S-24-22S-32E	275 FSL 1185 FWL	1500	6000	5000
STACK CATS 25-36 FED COM 12H	Pending	S-24-22S-32E	275 FSL 1245 FWL	1500	6000	5000
STACK CATS 25-36 FED COM 13H	Pending	S-24-22S-32E	275 FSL 1305 FWL	1500	6000	5000
STACK CATS 25-36 FED COM 14H	Pending	S-25-22S-32E	210 FNL 1749 FEL	1500	6000	5000
STACK CATS 25-36 FED COM 15H	Pending	S-25-22S-32E	210 FNL 1689 FEL	1500	6000	5000
STACK CATS 25-36 FED COM 16H	Pending	S-25-22S-32E	210 FNL 1629 FEL	1500	6000	5000

#### V. Anticipated Schedule

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
STACK CATS 25-36 FED COM 1H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 2H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 3H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 4H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 11H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 12H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 13H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 14H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 15H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026
STACK CATS 25-36 FED COM 16H	Pending	Jan-2026	Feb-2026	Mar-2026	Apr-2026	Apr-2026

Central Delivery Point Name: Red Tank 26 CPF

#### Part VI. Separation Equipment

Operator will size the flowback separator to handle 11,000 Bbls of fluid and 6-10MMscfd which is more than the expected peak rates for these wells. Each separator is rated to 1440psig, and pressure control valves and automated communication will cause the wells to shut in in the event of an upset at the facility, therefore no gas will be flared on pad during an upset. Current Oxy practices avoid use of flare or venting on pad, therefore if there is an upset or emergency condition at the facility, the wells will immediately shut down, and reassume production once the condition has cleared.

#### **VII. Operational Practices**

#### **Gathering System and Pipeline Notification**

Well(s) will be connected to a production facility after flowback operations are complete, where a gas transporter system is in place. The gas produced from production facility is dedicated to MPLX GP LLC ("MPLX") and is connected to MPLX's high pressure gathering system located in Eddy County, New Mexico. OXY USA INC. ("OXY") provides (periodically) to MPLX a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, OXY and MPLX have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at MPLX's Processing Plants located in New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

#### Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on MPLX's system at that time. Based on current information, it is OXY's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

#### **VIII. Best Management Practices**

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

Power Generation – On lease

Only a portion of gas is consumed operating the generator, remainder of gas will be flared


Compressed Natural Gas - On lease

Gas flared would be minimal, but might be uneconomical to operate when gas volume declines


NGL Removal - On lease

Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

	TANKS BONESPRING					
	Oil (bbl/d)	Gas (mcf/d)				
Jan-2024	1,006	1,259				
Feb-2024	1,133	1,807				
Mar-2024	938	1,919				
Apr-2024	790	1,931				
May-2024	681	1,965				
Jun-2024	596	1,922				
Jul-2024	530	1,827				
Aug-2024	477	1,744				
Sep-2024	432	1,671				
Oct-2024	395	1,604				
Nov-2024	363	1,543				
Dec-2024	337	1,490				
Jan-2025	314	1,441				
Feb-2025	293	1,393				
Mar-2025	274	1,350				
Apr-2025	258	1,309				
May-2025	243	1,271				
Jun-2025	229	1,234				
Jul-2025	218	1,200				
Aug-2025	207	1,169				
Sep-2025	197	1,139				
Oct-2025	188	1,110				
Nov-2025	179	1,083				
Dec-2025	172	1,058				
Jan-2026	165	1,034				
Feb-2026	159	1,011				
Mar-2026	152	988				
Apr-2026	147	967				
May-2026	141	947				
Jun-2026	136	927				
Jul-2026	132	908				
Aug-2026	127	890				
Sep-2026	123	873				
Oct-2026	120	856				
Nov-2026	116	840				
Dec-2026	112	825				



	TANKS WOLFCAMP					
	Oil (bbl/d) Gas (mcf/d					
Jan-2024	2,008	3,461				
Feb-2024	1,671	2,856				
Mar-2024	1,182	2,118				
Apr-2024	921	1,733				
May-2024	758	1,490				
Jun-2024	644	1,317				
Jul-2024	562	1,190				
Aug-2024	500	1,091				
Sep-2024	450	1,011				
Oct-2024	410	944				
Nov-2024	376	887				
Dec-2024	349	841				
Jan-2025	325	800				
Feb-2025	304	763				
Mar-2025	286	730				
Apr-2025	270	700				
May-2025	256	674				
Jun-2025	243	649				
Jul-2025	231	627				
Aug-2025	221	607				
Sep-2025	211	589				
Oct-2025	203	571				
Nov-2025	194	555				
Dec-2025	187	541				
Jan-2026	181	528				
Feb-2026	175	515				
Mar-2026	169	502				
Apr-2026	163	491				
May-2026	158	480				
Jun-2026	153	470				
Jul-2026	149	460				
Aug-2026	145	451				
Sep-2026	141	442				
Oct-2026	137	434				
Nov-2026	133	426				
Dec-2026	130	419				



## Oxy USA Inc. - Stack Cats 25\_36 Fed Com 15H Drill Plan

#### 1. Geologic Formations

TVD of Target (ft):	9569	Pilot Hole Depth (ft):	
Total Measured Depth (ft):	20164	Deepest Expected Fresh Water (ft):	1020

#### **Delaware Basin**

Formation	MD-RKB (ft)	TVD-RKB (ft)	<b>Expected Fluids</b>
Rustler	1020	1020	
Salado	1710	1710	Salt
Castile	3335	3335	Salt
Delaware	4974	4974	Oil/Gas/Brine
Bell Canyon	5018	5018	Oil/Gas/Brine
Cherry Canyon	5811	5811	Oil/Gas/Brine
Brushy Canyon	7161	7141	Losses
Bone Spring	8810	8765	Oil/Gas
Bone Spring 1st			Oil/Gas
Bone Spring 2nd			Oil/Gas
Bone Spring 3rd			Oil/Gas
Wolfcamp			Oil/Gas
Penn			Oil/Gas
Strawn			Oil/Gas

<sup>\*</sup>H2S, water flows, loss of circulation, abnormal pressures, etc.

#### 2. Casing Program

		N	ID	TVD					
	Hole	From	То	From	То	Csg.	Csg Wt.		
Section	Size (in)	(ft)	(ft)	(ft)	(ft)	OD (in)	(ppf)	Grade	Conn.
Surface	17.5	0	1080	0	1080	13.375	54.5	J-55	втс
Intermediate	9.875	0	8865	0	8817	7.625	26.4	L-80 HC	втс
Production	6.75	0	20164	0	9569	5.5	20	P-110	Wedge 461

All casing strings will be tested in accordance with 43 CFR part 3170 Subpart 3172

\*Oxy requests the option to run the 10.75" Intermediate I as a contingency string to be run only if severe hole conditions dictate an additional casing string necessary. This would make the planned 7.625" / 7.827" Casing the Intermediate II.

\*\*If 4S Contingency is not required, Oxy requests permission to transition from 12.25" to 9.875" Intermediate I at 1st trip point below Brushy top (estimated top in formation table above). Cement volumes will be updated on C103 submission.

Occidental - Permian New Mexico

All Casing SF Values will meet or exceed							
those below							
SF	SF	Body SF	Joint SF				
Collapse	Burst	Tension	Tension				

#### **Annular Clearance Variance Request**

As per the agreement reached in the Oxy/BLM face-to-face meeting on Feb 22, 2018, Oxy requests permission to allow deviation from the 0.422" annular clearance requirement. Please see Annular Clearance Variance attachment for further details.

	Y or N
Is casing new? If used, attach certification as required in 43 CFR 3160	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards?	Y
If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching	Y
the collapse pressure rating of the casing?	1
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back	
500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Created On: 3/13/2024 at 12:24 PM

Occidental - Permian New Mexico Stack Cats 25\_36 Fed Com 15H

3. Cementing Program

Section	Stage	Slurry:	Sacks	Yield (ft^3/ft)	Density (lb/gal)	Excess:	тос	Placement	Description
Surface	1	Surface - Tail	1128	1.33	14.8	100%	-	Circulate	Class C+Accel.
Int.	1	Intermediate 1S - Tail	199	1.65	13.2	5%	7,411	Circulate	Class H+Accel., Disper., Salt
Int.	2	Intermediate 2S - Tail BH	1342	1.71	13.3	25%	-	Bradenhead	Class C+Accel.
Prod.	1	Production - Tail	668	1.84	13.3	25%	8,365	Circulate	Class C+Ret.

#### **Offline Cementing Request**

Oxy requests a variance to cement the 9.625" and/or 7.625" intermediate casing strings offline in accordance to the approved variance, EC Tran 461365. Please see Offline Cementing Variance attachment for further details.

#### **Bradenhead CBL Request**

Oxy requests permission to adjust the CBL requirement after bradenhead cement jobs, on 7-5/8" intermediate casings, as per the agreement reached in the OXY/BLM meeting on September 5, 2019. Please see Bradenhead CBL Variance attachment for further details.

Created On: 3/13/2024 at 12:24 PM

Occidental - Permian New Mexico

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP		Туре	<b>✓</b>	Tested to:	Deepest TVD Depth (ft) per Section:	
		5M		Annu <b>l</b> ar	✓	70% of working pressure		
				Blind Ram	✓			
9.875" Hole	13-5/8"	5M	Pipe Ram			250 psi / 5000 psi	8817	
			Double Ram		<	230 psi / 3000 psi		
			Other*					
		5M		Annular	<b>✓</b>	70% of working pressure		
				Blind Ram	<b>✓</b>			
6.75" Hole	13-5/8"	5M		Pipe Ram		250 psi / 5000 psi	9569	
		SIVI		Double Ram		230 psi / 3000 psi		
			Other*					

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per 43 CFR part 3170 Subpart 3172 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold.

<sup>\*</sup>Specify if additional ram is utilized

Created On: 3/13/2024 at 12:24 PM

Occidental - Permian New Mexico

Formation integrity test will be performed per 43 CFR part 3170 Subpart 3172.

On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with 43 CFR part 3170 Subpart 3172.

A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.

Are anchors required by manufacturer?

A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per 43 CFR part 3170 Subpart 3172 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015.

See attached schematics.

#### **BOP Break Testing Request**

Oxy requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019. Please see BOP Break Testing Variance attachment for further details.

Oxy will use Cameron ADAPT wellhead system that uses an OEC top flange connection. This connection has been fully vetted and verified by API to Spec 6A and carries an API monogram.

Occidental - Permian New Mexico

5. Mud Program

Section	Depth - MD		Depth - TVD		Tyma	Weight	Viscosity	Water
Section	From (ft)	To (ft)	From (ft)	To (ft)	Туре	(ppg)	Viscosity	Loss
Surface	0	1080	0	1080	Water-Based Mud	8.6 - 8.8	40-60	N/C
Intermediate	1080	8865	1080	8817	Saturated Brine-Based or Oil-Based Mud	8.0 - 10.0	35-45	N/C
Production	8865	20164	8817	9569	Water-Based or Oil- Based Mud	8.0 - 9.6	38-50	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

What will be used to monitor the	PVT/MD Totco/Visual Monitoring	
loss or gain of fluid?	FV1/IVID TOLCO/VISUAL MONITORING	l

**6. Logging and Testing Procedures** 

Loggi	Logging, Coring and Testing.						
Yes Will run GR from TD to surface (horizontal well – vertical portion of hole).							
res	Stated logs run will be in the Completion Report and submitted to the BLM.						
No	Logs are planned based on well control or offset log information.						
No	Drill stem test? If yes, explain						
No	Coring? If yes, explain						

Addit	ional logs planned	Interval
No	Resistivity	
No	Density	
Yes	CBL	Production string
Yes	Mud log	Bone Spring – TD
No	PEX	

Stack Cats 25\_36 Fed Com 15H

Created On: 3/13/2024 at 12:24 PM

Occidental - Permian New Mexico

#### 7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4777 psi
Abnormal Temperature	No
BH Temperature at deepest TVD	157°F

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of 43 CFR part 3170 Subpart 3172. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

LITE L	CIVI.
N	H2S is present
Υ	H2S Plan attached

#### 8. Other facets of operation

·	Yes/No
Will the well be drilled with a walking/skidding operation? If yes, describe.	
We plan to drill the 6 well pad in batch by section: all surface sections, intermediate	Yes
sections and production sections. The wellhead will be secured with a night cap whenever	1 68
the rig is not over the well.	
Will more than one drilling rig be used for drilling operations? If yes, describe.	
Oxy requests the option to contract a Surface Rig to drill, set surface casing, and cement for	
this well. If the timing between rigs is such that Oxy would not be able to preset surface,	Yes
the Primary Rig will MIRU and drill the well in its entirety per the APD. Please see the	
attached document for information on the spudder rig.	

Total Estimated Cuttings Volume: 1559 bbls

## Oxy USA Inc. - Stack Cats 25\_36 Fed Com 15H Drill Plan

#### 1. Geologic Formations

TVD of Target (ft):	9569	Pilot Hole Depth (ft):	
Total Measured Depth (ft):	20164	Deepest Expected Fresh Water (ft):	1020

#### **Delaware Basin**

Formation	MD-RKB (ft)	TVD-RKB (ft)	<b>Expected Fluids</b>
Rustler	1020	1020	
Salado	1710	1710	Salt
Castile	3335	3335	Salt
Delaware	4974	4974	Oil/Gas/Brine
Bell Canyon	5018	5018	Oil/Gas/Brine
Cherry Canyon	5811	5811	Oil/Gas/Brine
Brushy Canyon	7161	7141	Losses
Bone Spring	8810	8765	Oil/Gas
Bone Spring 1st			Oil/Gas
Bone Spring 2nd			Oil/Gas
Bone Spring 3rd			Oil/Gas
Wolfcamp			Oil/Gas
Penn			Oil/Gas
Strawn			Oil/Gas

<sup>\*</sup>H2S, water flows, loss of circulation, abnormal pressures, etc.

#### 2. Casing Program

	N	ID	Τ\	/D					
	Hole	From	То	From	То	Csg.	Csg Wt.		
Section	Size (in)	(ft)	(ft)	(ft)	(ft)	OD (in)	(ppf)	Grade	Conn.
Surface	17.5	0	1080	0	1080	13.375	54.5	J-55	втс
Salt	12.25	0	5074	0	5074	10.75	45.5	L-80 HC	BTC-SC
Intermediate	9.875	0	8865	0	8817	7.625	26.4	L-80 HC	втс
Production	6.75	0	20164	0	9569	5.5	20	P-110	Wedge 461

All casing strings will be tested in accordance with 43 CFR part 3170 Subpart 3172  $\,$ 

All Casing SF Values will meet or exceed								
those below								
SF SF Body SF Joint SF								
<u> </u>	٠.	Douy S.	301116 31					
Collapse	Burst	-	Tension					

#### **Annular Clearance Variance Request**

As per the agreement reached in the Oxy/BLM face-to-face meeting on Feb 22, 2018, Oxy requests permission to allow deviation from the 0.422" annular clearance requirement. Please see Annular Clearance Variance attachment for further details.

	Y or N
Is casing new? If used, attach certification as required in 43 CFR 3160	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards?	
If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching	37
the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back	
500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Stack Cats 25\_36 Fed Com 15H

Occidental - Permian New Mexico

3. Cementing Program

Section	Stage	Slurry:	Sacks	Yield (ft^3/ft)	Density (lb/gal)	Excess:	тос	Placement	Description
Surface	1	Surface - Tail	1128	1.33	14.8	100%	1	Circulate	Class C+Accel.
Int.1	1	Intermediate - Tail	85	1.33	14.8	20%	4,574	Circulate	Class C+Accel.
Int.1	1	Intermediate - Lead	718	1.73	12.9	50%	-	Circulate	Class Pozz+Ret.
Int. 2	1	Intermediate 1S - Tail	93	1.65	13.2	5%	7,411	Circulate	Class H+Accel., Disper., Salt
Int. 2	2	Intermediate 2S - Tail BH	833	1.71	13.3	25%	-	Bradenhead	Class C+Accel.
Prod.	1	Production - Tail	668	1.84	13.3	25%	8,365	Circulate	Class C+Ret.

#### **Offline Cementing Request**

Oxy requests a variance to cement the 9.625" and/or 7.625" intermediate casing strings offline in accordance to the approved variance, EC Tran 461365. Please see Offline Cementing Variance attachment for further details.

#### **Bradenhead CBL Request**

Oxy requests permission to adjust the CBL requirement after bradenhead cement jobs, on 7-5/8" intermediate casings, as per the agreement reached in the OXY/BLM meeting on September 5, 2019. Please see Bradenhead CBL Variance attachment for further details.

Stack Cats 25\_36 Fed Com 15H

Created On: 3/13/2024 at 12:25 PM

Occidental - Permian New Mexico

4. Pressure Control Equipment

BOP installed and		Min.					TVD Depth
tested before drilling	Size?	Required		Туре	✓	Tested to:	(ft) per
which hole?		WP					Section:
		5M		Annular	✓	70% of working pressure	
				Blind Ram	✓		5074
12.25" Hole	13-5/8"	5M		Pipe Ram		250 psi / 5000 psi	
		DIVI		Double Ram	✓	250 psi / 5000 psi	
			Other*				
	13-5/8"	5M		Annular	✓	70% of working pressure	
		3" 5M		Blind Ram	✓		
9.875" Hole			Pipe Ram			250 psi / 5000 psi	8817
				Double Ram	✓	250 psi / 5000 psi	
			Other*				
		5M		Annular	✓	70% of working pressure	
		5/8" 5M		Blind Ram			9569
6.75" Hole	13-5/8"		Pipe Ram			250 psi / 5000 psi	
				Double Ram	✓ ✓	250 psi / 5000 psi	
			Other*				

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per 43 CFR part 3170 Subpart 3172 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold.

<sup>\*</sup>Specify if additional ram is utilized

Created On: 3/13/2024 at 12:25 PM

Occidental - Permian New Mexico Stack Cats 25\_36 Fed Com 15H

Formation integrity test will be performed per 43 CFR part 3170 Subpart 3172.

On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with 43 CFR part 3170 Subpart 3172.

A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.

Are anchors required by manufacturer?

A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per 43 CFR part 3170 Subpart 3172 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015.

See attached schematics.

#### **BOP Break Testing Request**

Oxy requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019. Please see BOP Break Testing Variance attachment for further details.

Oxy will use Cameron ADAPT wellhead system that uses an OEC top flange connection. This connection has been fully vetted and verified by API to Spec 6A and carries an API monogram.

Stack Cats 25\_36 Fed Com 15H

Occidental - Permian New Mexico

5. Mud Program

Section	Depth		Depth - TVD Weight Viscosity		pth - TVD Weight		Vissositu	Water
Section	From (ft)	To (ft)	From (ft)	To (ft)	Туре	(ppg)	Viscosity	Loss
Surface	0	1080	0	1080	Water-Based Mud	8.6 - 8.8	40-60	N/C
Intermediate 1	1080	5074	1080	5074	Saturated Brine-Based or Oil-Based Mud	8.0 - 10.0	35-45	N/C
Intermediate 2	5074	8865	5074	8817	Water-Based or Oil- Based Mud	8.0 - 10.0	38-50	N/C
Production	8865	20164	8817	9569	Water-Based or Oil- Based Mud	8.0 - 9.6	38-50	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

What will be used to monitor the	2) (7/142 7 )	ĺ
loss or gain of fluid?	PVT/MD Totco/Visual Monitoring	ı

**6. Logging and Testing Procedures** 

Loggi	ng, Coring and Testing.
Yes	Will run GR from TD to surface (horizontal well – vertical portion of hole).
1 68	Stated logs run will be in the Completion Report and submitted to the BLM.
No	Logs are planned based on well control or offset log information.
No	Drill stem test? If yes, explain
No	Coring? If yes, explain

Addit	ional logs planned	Interval
No	Resistivity	
No	Density	
Yes	CBL	Production string
Yes	Mud log	Bone Spring – TD
No	PEX	

Stack Cats 25\_36 Fed Com 15H

Created On: 3/13/2024 at 12:25 PM

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4777 psi
Abnormal Temperature	No
BH Temperature at deepest TVD	157°F

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of 43 CFR part 3170 Subpart 3172. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H2S is present
Υ	H2S Plan attached

#### 8. Other facets of operation

·	Yes/No
Will the well be drilled with a walking/skidding operation? If yes, describe.	
We plan to drill the 6 well pad in batch by section: all surface sections, intermediate	Yes
sections and production sections. The wellhead will be secured with a night cap whenever	
the rig is not over the well.	
Will more than one drilling rig be used for drilling operations? If yes, describe.	
Oxy requests the option to contract a Surface Rig to drill, set surface casing, and cement for	
this well. If the timing between rigs is such that Oxy would not be able to preset surface,	Yes
the Primary Rig will MIRU and drill the well in its entirety per the APD. Please see the	
attached document for information on the spudder rig.	

Total Estimated Cuttings Volume: 1763 bbls

PRD NM DIRECTIONAL PLANS (NAD 1983) Stack Cats 25\_36 Stack Cats 25\_36 Fed Com 15H

Wellbore #1

Plan: Permitting Plan

## **Standard Planning Report**

21 December, 2023

## **OXY**Planning Report

Company: ENGINEERING DESIGNS

Project: PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Database:

Well: Stack Cats 25\_36 Fed Com 15H

HOPSPP

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft RKB = 25' @ 3776.00ft

Grid

Minimum Curvature

Project PRD NM DIRECTIONAL PLANS (NAD 1983)

Map System: US State Plane 1983 Geo Datum: North American Datum 1983

Map Zone: New Mexico Eastern Zone

System Datum: Mean Sea Level

Using geodetic scale factor

Site Stack Cats 25\_36

 Site Position:
 Northing:
 499,452.71 usft
 Latitude:
 32.371120

 From:
 Map
 Easting:
 757,564.76 usft
 Longitude:
 -103.632971

Position Uncertainty: 0.89 ft Slot Radius: 13.200 in

Well Stack Cats 25\_36 Fed Com 15H

 Well Position
 +N/-S
 0.00 ft
 Northing:
 498,878.92 usf
 Latitude:
 32.369500

 +E/-W
 0.00 ft
 Easting:
 759,947.62 usf
 Longitude:
 -103.625266

Position Uncertainty 2.00 ft Wellhead Elevation: ft Ground Level: 3,751.00 ft

Grid Convergence: 0.38 °

Wellbore #1 Wellbore **Model Name** Declination Field Strength Magnetics Sample Date Dip Angle (°) (°) (nT) HDGM\_FILE 12/21/2023 6.23 59.95 47,563.30000000

Design Permitting Plan Audit Notes: Version: Phase: **PROTOTYPE** Tie On Depth: 0.00 Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 177.48

Plan Survey Tool Program

Date 12/21/2023

Depth From (ft) (ft) Survey (Wellbore)

Tool Name Remarks

1 0.00 20,164.36 Permitting Plan (Wellbore #1) B005Mc\_MWD+HRGM+SA

ISCWSA MWD + HRGM +

ISOWOA MIWU I TIKOMI

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,530.00	0.00	0.00	5,530.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,030.14	10.00	34.19	6,027.61	36.02	24.47	2.00	2.00	0.00	34.19	
8,964.53	10.00	34.19	8,917.39	457.64	310.87	0.00	0.00	0.00	0.00	
9,946.73	90.00	179.58	9,569.00	-108.94	380.25	10.00	8.14	14.80	144.99	
20,164.36	90.00	179.58	9,569.00	-10,326.30	454.30	0.00	0.00	0.00	0.00	PBHL (Stack Cats

#### Planning Report

Database: Company: HOPSPP

**ENGINEERING DESIGNS** 

**Project:** PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Well: Stack Cats 25\_36 Fed Com 15H

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft

RKB = 25' @ 3776.00ft

lanned Survey									
aoa oarvoy									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
•			•						
1,500.00 1,600.00	0.00 0.00	0.00 0.00	1,500.00 1,600.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
*			· ·						
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500,00	0.00	0.00	3,500,00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00
5,000.00 5,100.00	0.00 0.00	0.00 0.00	5,000 <b>.</b> 00 5,100 <b>.</b> 00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00
5,200.00			5,100.00						
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00
5,400.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
5.400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00

#### Planning Report

Database: Company: HOPSPP

**ENGINEERING DESIGNS** 

**Project:** PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Well: Stack Cats 25\_36 Fed Com 15H

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

North Reference:

Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft

RKB = 25' @ 3776.00ft

esign:	Permitting Pla	an							
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00
5,530.00	0.00	0.00	5,530.00	0.00	0.00	0.00	0.00	0.00	0.00
5,600.00	1.40	34.19	5,599.99	0.71	0.48	-0.69	2.00	2.00	0.00
5,700.00	3.40	34.19	5,699.90	4.17	2.83	-4.04	2.00	2.00	0.00
5,800.00	5.40	34.19	5,799.60	10.52	7.14	-10.19	2.00	2.00	0.00
5,900.00	7.40	34.19	5,898.97	19.74	13.41	-19.13	2.00	2.00	0.00
6,000.00	9.40	34.19	5,997.89	31.82	21.62	-30.84	2.00	2.00	0.00
6,030.14	10.00	34.19	6,027.61	36.02	24.47	-34.91	2.00	2.00	0.00
6,100.00	10.00	34.19	6,096.40	46.06	31.29	-44.64	0.00	0.00	0.00
6,200.00	10.00	34.19	6,194.88	60.43	41.05	-58 <b>.</b> 57	0.00	0.00	0.00
6,300.00	10.00	34.19	6,293.36	74.80	50.81	-72.49	0.00	0.00	0.00
6,400.00	10.00	34.19	6,391.84	89.16	60.57	-86.42	0.00	0.00	0.00
6,500.00	10.00	34.19	6,490.32	103.53	70.33	-100.34	0.00	0.00	0.00
6,600.00	10.00	34.19	6,588.80	117.90	80.09	-114.27	0.00	0.00	0.00
6,700.00	10.00	34.19	6,687.28	132.27	89.85	-128.19	0.00	0.00	0.00
6,800.00	10.00	34.19	6,785.76	146.64	99.61	-142.12	0.00	0.00	0.00
6.900.00	10.00	34.19	6,884.24	161.01	109.37	-156.04	0.00	0.00	0.00
7,000.00	10.00	34.19	6,982.72	175.37	119.13	-169.97	0.00	0.00	0.00
7,100.00	10.00	34.19	7,081.20	189.74	128.89	-183.89	0.00	0.00	0.00
7,200.00	10.00	34.19	7,179.68	204.11	138.65	-197.82	0.00	0.00	0.00
7,300.00	10.00	34.19	7.278.16	218.48	148.41	-211.74	0.00	0.00	0.00
7,300.00 7,400.00	10.00	34.19 34.19	7,278.16	232.85	158.17	-211.74 -225.67	0.00	0.00	0.00
7,500.00	10.00	34.19 34.19	7,376.64	232.03 247.21	167.93	-223.67	0.00	0.00	0.00
7,600.00	10.00	34.19	7,573.60	261.58	177.69	-253.52	0.00	0.00	0.00
7,700.00	10.00	34.19	7,672.08	275.95	187.45	-267.45	0.00	0.00	0.00
7,800.00	10.00	34.19	7,770.56	290.32	197.21	-281.37	0.00	0.00	0.00
7,900.00	10.00	34.19	7,869.04	304.69	206.97	-295.30	0.00	0.00	0.00
8,000 <u>.</u> 00	10.00 10.00	34.19	7,967.52 8,066.00	319.06	216.73	-309.22 -323.15	0.00 0.00	0.00 0.00	0.00
8,100 <b>.</b> 00 8,200 <b>.</b> 00	10.00	34.19 34.19	8,164.48	333.42 347.79	226.49 236.25	-323.15 -337.07	0.00	0.00	0.00 0.00
			•						
8,300.00	10.00	34.19	8,262.96	362.16	246.01	-351.00	0.00	0.00	0.00
8,400.00	10.00	34.19	8,361.44	376.53	255.77	-364.92	0.00	0.00	0.00
8,500.00	10.00	34.19	8,459.92	390.90	265.54	-378.85	0.00	0.00	0.00
8,600.00	10.00	34.19	8,558.40	405.27	275.30	-392.77	0.00	0.00	0.00
8,700.00	10.00	34.19	8,656.88	419.63	285.06	-406.70	0.00	0.00	0.00
8,800.00	10.00	34.19	8,755.36	434.00	294.82	-420.62	0.00	0.00	0.00
8,900.00	10.00	34.19	8,853.84	448.37	304.58	-434.55	0.00	0.00	0.00
8,964.53	10.00	34.19	8,917.39	457.64	310.87	-443.54	0.00	0.00	0.00
9,000.00	7.38	50.23	8,952.45	461.65	314.36	-447.39	10.00	-7.39	45.22
9,100.00	7.81	132.68	9,051.83	461.15	324.32	-446.45	10.00	0.43	82.45
9,200.00	16.34	159.60	9,149.59	443.32	334.24	-428.20	10.00	8.53	26.92
9,300.00	25.92	167.69	9,242.78	408.69	343.82	-393.18	10.00	9.59	8.09
9,400.00	35.73	171.58	9,328.56	358.33	352.78	-342.47	10.00	9.80	3.89
9,500.00	45.61	173.96	9,404.32	293.75	360.84	-277.61	10.00	9.88	2.38
9,600.00	55.52	175.64	9,467.76	216.92	367.75	-200.55	10.00	9.92	1.68
9,700.00	65.46	176.96	9,516.95	130.19	373.30	-113.65	10.00	9.93	1.32
9,800.00	75.40	178.09	9,550.41	36.17	377.34	-19.55	10.00	9.94	1.13
9,900.00	85.35	179.12	9,567.11	-62.27	379.72	78.90	10.00	9.95	1.03
9,946.73	90.00	179.58	9,569.00	-108.94	380.25	125.55	10.00	9.95	1.00
10,000.00	90.00	179.58	9,569.00	-162.21	380.64	178.79	0.00	0.00	0.00
10,100.00	90.00	179.58	9,569.00	-262.21	381.36	278.72	0.00	0.00	0.00
10,200.00	90.00	179.58	9,569.00	-362.21	382.09	378.65	0.00	0.00	0.00
10,300.00	90.00	179.58	9,569.00	-462.21	382.81	478.58	0.00	0.00	0.00
10,400.00	90.00	179.58	9,569.00	-562.20	383.54	578.52	0.00	0.00	0.00

#### Planning Report

Database: Company: HOPSPP

**ENGINEERING DESIGNS** 

**Project:** PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Well: Stack Cats 25\_36 Fed Com 15H

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft RKB = 25' @ 3776.00ft

Grid

esign:	Permitting Pia	all							
lanned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
10,600.00	90.00	179.58	9,569.00	-762.20	384.98	778.38	0.00	0.00	0.00
10,700.00	90.00	179.58	9,569.00	-862.20	385.71	878.32	0.00	0.00	0.00
10,800.00	90.00	179.58	9,569.00	-962.19	386.43	978.25	0.00	0.00	0.00
10,900.00	90.00	179.58	9,569.00	-1,062.19	387.16	1,078.18	0.00	0.00	0.00
11,000.00	90.00	179.58	9,569.00	-1,162.19	387.88	1,178.11	0.00	0.00	0.00
11,100.00	90.00	179.58	9,569.00	-1,262.19	388.61	1,278.05	0.00	0.00	0.00
11,200.00	90.00	179.58	9,569.00	-1,362.18	389.33	1,377.98	0.00	0.00	0.00
11,300.00	90.00	179.58	9,569.00	-1,362.18 -1,462.18	390.06	1,377.90	0.00	0.00	
	90.00	179.58		-1,462.18 -1,562.18	390.00				0.00
11,400.00			9,569.00			1,577.84	0.00	0.00	0.00
11,500.00	90.00	179.58	9,569.00	-1,662.17	391.51	1,677.78	0.00	0.00	0.00
11,600.00	90.00	179.58	9,569.00	-1,762.17	392.23	1,777.71	0.00	0.00	0.00
11,700.00	90.00	179.58	9,569.00	-1,862.17	392.96	1,877.64	0.00	0.00	0.00
11,800.00	90.00	179.58	9,569.00	-1,962.17	393.68	1,977.57	0.00	0.00	0.00
11,900.00	90.00	179.58	9,569.00	-2,062.16	394.41	2,077.51	0.00	0.00	0.00
12,000.00	90.00	179.58	9,569.00	-2,162.16	395.13	2,177.44	0.00	0.00	0.00
						,			
12,100.00	90.00	179.58	9,569.00	-2,262.16	395.86	2,277.37	0.00	0.00	0.00
12,200.00	90.00	179.58	9,569.00	-2,362.16	396.58	2,377.30	0.00	0.00	0.00
12,300.00	90.00	179.58	9,569.00	-2,462.15	397.30	2,477.24	0.00	0.00	0.00
12,400.00	90.00	179.58	9,569.00	-2,562.15	398.03	2,577.17	0.00	0.00	0.00
12,500.00	90.00	179.58	9,569.00	-2,662.15	398.75	2,677.10	0.00	0.00	0.00
12,600.00	90.00	179.58	9,569.00	-2,762.15	399.48	2,777.03	0.00	0.00	0.00
12,700.00	90.00	179.58	9,569.00	-2,862.14	400.20	2,876.97	0.00	0.00	0.00
12,800.00	90.00	179.58	9,569.00	-2,962.14	400.93	2,976.90	0.00	0.00	0.00
12,900.00	90.00	179.58	9,569.00	-3,062.14	401.65	3,076.83	0.00	0.00	0.00
13,000.00	90.00	179.58	9,569.00	-3,162.14	402.38	3,176.77	0.00	0.00	0.00
•			•	•		•			
13,100.00	90.00	179.58	9,569.00	-3,262.13	403.10	3,276.70	0.00	0.00	0.00
13,200.00	90.00	179.58	9,569.00	-3,362.13	403.83	3,376.63	0.00	0.00	0.00
13,300.00	90.00	179.58	9,569.00	-3,462.13	404.55	3,476.56	0.00	0.00	0.00
13,400.00	90.00	179.58	9,569.00	-3,562.13	405.28	3,576.50	0.00	0.00	0.00
13,500.00	90.00	179.58	9,569.00	-3,662.12	406.00	3,676.43	0.00	0.00	0.00
13,600.00	90.00	179.58	9,569.00	-3,762.12	406.73	3,776.36	0.00	0.00	0.00
13,700.00	90.00	179.58	9,569.00	-3,762.12 -3,862.12	400.73	3,876.29	0.00	0.00	0.00
13,800.00			9,569.00	-3,962.12 -3,962.11					
,	90.00	179.58			408.18	3,976.23	0.00	0.00	0.00
13,900.00	90.00	179.58	9,569.00	-4,062.11	408.90	4,076.16	0.00	0.00	0.00
14,000.00	90.00	179.58	9,569.00	-4,162.11	409.62	4,176.09	0.00	0.00	0.00
14,100.00	90.00	179.58	9,569.00	-4,262.11	410.35	4,276.02	0.00	0.00	0.00
14,200.00	90.00	179.58	9,569.00	-4,362.10	411.07	4,375.96	0.00	0.00	0.00
14,300.00	90.00	179.58	9,569.00	4,462.10	411.80	4,475.89	0.00	0.00	0.00
14,400.00	90.00	179.58	9,569.00	4,562.10	412.52	4,575.82	0.00	0.00	0.00
14,500.00	90.00	179.58	9,569.00	-4,662.10	413.25	4,675.75	0.00	0.00	0.00
14,600.00	90.00	179.58	9,569.00	-4,762.09	413.97	4,775.69	0.00	0.00	0.00
14,700.00	90.00	179.58	9,569.00	-4,862.09	414.70	4,875.62	0.00	0.00	0.00
14,800.00	90.00	179.58	9,569.00	-4,962.09	415.42	4,975.55	0.00	0.00	0.00
14,900.00	90.00	179.58	9,569.00	-5,062.09	416.15	5,075.48	0.00	0.00	0.00
15,000.00	90.00	179.58	9,569.00	-5,162.08	416.87	5,175 <b>.</b> 42	0.00	0.00	0.00
15,100.00	90.00	179.58	9,569.00	-5,262.08	417.60	5,275.35	0.00	0.00	0.00
15,200.00	90.00	179.58	9,569.00	-5,362.08	418.32	5,375.28	0.00	0.00	0.00
15,300.00	90.00	179.58	9,569.00	-5,462.08	419.05	5,475.21	0.00	0.00	0.00
15,400.00	90.00	179.58	9,569.00	-5,562.07	419.77	5,575.15	0.00	0.00	0.00
15,500.00	90.00	179.58	9,569.00	-5,662.07	420.49	5,675.08	0.00	0.00	0.00
15,600.00	90.00	179.58	9,569.00	-5,762.07	421.22	5,775.01	0.00	0.00	0.00
15,700.00	90.00	179.58	9,569.00	-5,862.06	421.94	5,874.95	0.00	0.00	0.00
15,800.00	90.00	179.58	9,569.00	-5,962.06	422.67	5,974.88	0.00	0.00	0.00
15,900.00	90.00	179.58	9,569.00	-6,062.06	423.39	6,074.81	0.00	0.00	0.00
	90.00	179.58	9,569.00	-6,162.06	424.12	6,174.74	0.00	0.00	0.00

#### Planning Report

Database: Company: HOPSPP

**ENGINEERING DESIGNS** 

**Project:** PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Well: Stack Cats 25\_36 Fed Com 15H

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference: Survey Calculation Method: Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft RKB = 25' @ 3776.00ft

Grid

sign:	Permitting Pla	all							
anned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
16,100.00	90.00	179.58	9,569.00	-6,262.05	424.84	6,274.68	0.00	0.00	0.00
16,200.00	90.00	179.58	9,569.00	-6,362.05	425.57	6,374.61	0.00	0.00	0.00
16,300.00	90.00	179.58	9,569.00	-6,462.05	426.29	6,474.54	0.00	0.00	0.00
16,400.00	90.00	179.58	9,569.00	-6,562.05	427.02	6,574.47	0.00	0.00	0.00
16,500.00	90.00	179.58	9,569.00	-6,662.04	427.74	6,674.41	0.00	0.00	0.00
16,600.00	90.00	179.58	9,569.00	-6,762.04	428.47	6,774.34	0.00	0.00	0.00
16,700.00	90.00	179.58	9,569.00	-6,862.04	429.19	6,874.27	0.00	0.00	0.00
16,800.00	90.00	179.58	9,569.00	-6,962.04	429.92	6,974.20	0.00	0.00	0.00
16,900.00	90.00	179.58	9,569.00	-7,062.03	430.64	7,074.14	0.00	0.00	0.00
17,000.00	90.00	179.58	9,569.00	-7,162.03	431.37	7,174.07	0.00	0.00	0.00
17,100.00	90.00	179.58	9,569.00	-7,262.03	432.09	7,274.00	0.00	0.00	0.00
17,200.00	90.00	179.58	9,569.00	-7,362.03	432.81	7,373.93	0.00	0.00	0.00
17,300.00	90.00	179.58	9,569.00	-7,462.02	433.54	7,473.87	0.00	0.00	0.00
17,400.00	90.00	179.58	9,569.00	-7,562.02	434.26	7,573.80	0.00	0.00	0.00
17,500.00	90.00	179.58	9,569.00	-7,662.02	434.99	7,673.73	0.00	0.00	0.00
17,600.00	90.00	179.58	9,569.00	-7,762.01	435.71	7,773.66	0.00	0.00	0.00
17,700.00	90.00	179.58	9,569.00	-7,862.01	436.44	7,873.60	0.00	0.00	0.00
17,800.00	90.00	179.58	9,569.00	-7,962.01	437.16	7,973.53	0.00	0.00	0.00
17,900.00	90.00	179.58	9,569.00	-8,062.01	437.89	8,073.46	0.00	0.00	0.00
18,000.00	90.00	179.58	9,569.00	-8,162.00	438.61	8,173.39	0.00	0.00	0.00
18,100.00	90.00	179.58	9,569.00	-8,262.00	439.34	8,273.33	0.00	0.00	0.00
18,200.00	90.00	179.58	9,569.00	-8,362.00	440.06	8,373.26	0.00	0.00	0.00
18,300.00	90.00	179.58	9,569.00	-8,462.00	440.79	8,473.19	0.00	0.00	0.00
18,400.00	90.00	179.58	9,569.00	-8,561.99	441.51	8,573.13	0.00	0.00	0.00
18,500.00	90.00	179.58	9,569.00	-8,661.99	442.24	8,673.06	0.00	0.00	0.00
18,600.00	90.00	179.58	9,569.00	-8,761.99	442.96	8,772.99	0.00	0.00	0.00
18,700.00	90.00	179.58	9,569.00	-8,861.99	443.69	8,872.92	0.00	0.00	0.00
18,800.00	90.00	179.58	9,569.00	-8,961.98	444.41	8,972.86	0.00	0.00	0.00
18,900.00	90.00	179.58	9,569.00	-9,061 <u>.</u> 98	445.13	9,072.79	0.00	0.00	0.00
19,000.00	90.00	179.58	9,569.00	-9,161.98	445.86	9,172.72	0.00	0.00	0.00
19,100.00	90.00	179.58	9,569.00	-9,261.98	446.58	9,272.65	0.00	0.00	0.00
19,200.00	90.00	179.58	9,569.00	-9,361.97	447.31	9,372.59	0.00	0.00	0.00
19,300.00	90.00	179.58	9,569.00	-9,461 <u>.</u> 97	448.03	9,472.52	0.00	0.00	0.00
19,400.00	90.00	179.58	9,569.00	-9,561 <u>.</u> 97	448.76	9,572.45	0.00 0.00	0.00	0.00
19,500.00	90.00	179.58	9,569.00	-9,661.97	449.48	9,672.38		0.00	0.00
19,600.00	90.00	179.58	9,569.00	-9,761.96	450.21	9,772.32	0.00	0.00	0.00
19,700.00	90.00	179.58	9,569.00	-9,861.96	450.93	9,872.25	0.00	0.00	0.00
19,800.00	90.00	179.58	9,569.00	-9,961 <u>.</u> 96	451.66	9,972.18	0.00	0.00	0.00
19,900.00 20,000.00	90.00 90.00	179.58 179.58	9,569.00 9,569.00	-10,061.95 -10,161.95	452.38 453.11	10,072.11	0.00 0.00	0.00 0.00	0.00 0.00
•			•	•		10,172.05			
20,100.00	90.00	179.58	9,569.00	-10,261.95	453.83	10,271.98	0.00	0.00	0.00
20,164.36	90.00	179.58	9,569.00	-10,326.30	454.30	10,336.29	0.00	0.00	0.00



#### **Planning Report**

Database: HOPSPP

Company: ENGINEERING DESIGNS

**Project:** PRD NM DIRECTIONAL PLANS (NAD 1983)

Site: Stack Cats 25\_36

Well: Stack Cats 25\_36 Fed Com 15H

Wellbore: Wellbore #1

Design: Permitting Plan

Local Co-ordinate Reference:

TVD Reference:
MD Reference:

North Reference: Survey Calculation Method: Well Stack Cats 25\_36 Fed Com 15H

RKB = 25' @ 3776.00ft

RKB = 25' @ 3776.00ft

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
KOP (Stack Cats - plan misses targe - Point	0.00 t center by 63	0.00 36.74ft at 0.0	0.00 Ooft MD (0.0	514.06 00 TVD, 0.00 I	375.74 N, 0.00 E)	499,392.96	760,323.35	32.370906	-103.624038
FTP (Stack Cats - plan misses targe - Point	0.00 t center by 41	0.00 1.89ft at 973	9,569.00 2.88ft MD (	114.05 9529.75 TVD,	378.63 99.94 N, 374	498,992.97 81 E)	760,326.24	32.369807	-103.624037
PBHL (Stack Cats - plan hits target ce - Point	0.00 enter	0.00	9,569.00	-10,326.30	454.30	488,553.01	760,401.90	32.341109	-103.624016

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,020.00	1,020.00	RUSTLER				
	1,710.00	1,710.00	SALADO				
	3,335.00	3,335.00	CASTILE				
	4,974.00	4,974.00	DELAWARE				
	5,018.00	5,018.00	BELL CANYON				
	5,811 <b>.</b> 45	5,811.00	CHERRY CANYON				
	7,160.72	7,141.00	BRUSHY CANYON				
	8,809.79	8,765.00	BONE SPRING				

Plan Annota	Plan Annotations							
	Measured	Vertical	Local Coordinates					
	Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment			
	5.530.00	5,530.00	0.00	0.00	Build 2°/100'			
	6,030.14	6,027.61	36.02	24.47	Hold 10° Tangent			
	8,964.53	8,917.39	457.64	310.87	KOP, Build 10°/100'			
	9,946.73	9,569.00	-108.94	380.25	Landing Point			
	20,164.36	9,569.00	-10,326.30	454.30	TD at 20164.36' MD			

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME: OXY USA INCORPORATED
WELL NAME & NO.: STACK CATS 25 36 FED COM 15H
LOCATION: Section 25, T.22 S., R.32 E.
COUNTY: Lea County, New Mexico

COA

H2S	• Yes	O No		
Potash	None	O Secretary	O R-111-P	
Cave/Karst Potential	• Low	O Medium	O High	
Cave/Karst Potential	O Critical			
Variance	O None	• Flex Hose	O Other	
Wellhead	Conventional	<ul><li>Multibowl</li></ul>	O Both	
Wellhead Variance	O Diverter			
Other	□4 String	☐ Capitan Reef	□WIPP	
Other	☐ Fluid Filled	☐ Pilot Hole	☐ Open Annulus	
Cementing	☐ Contingency	☐ EchoMeter	✓ Primary Cement	
	Cement Squeeze		Squeeze	
Special Requirements	☐ Water Disposal	<b>☑</b> COM	□ Unit	
Special Requirements	☐ Batch Sundry			
Special Requirements	☑ Break Testing	☑ Offline	☐ Casing	
Variance		Cementing	Clearance	

#### A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated AT SPUD. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

#### B. CASING

NOTE: ONLY PRIMARY DESIGN REVIEWED AND APPROVED. PLEASE SUBMIT SUNDRY IF CONTINGENCY DESIGN IS NEEDED

#### **Primary Design:**

- 1. The 13-3/8 inch surface casing shall be set at approximately 1080 feet TVD (a minimum of 25 feet (Lea County) into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall

be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of 24 hours in the Potash Area or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that
- 2. The 7-5/8 inch intermediate casing shall be set at approximately 8865 feet. KEEP CASING 1/2 FULL FOR COLLAPSE SF. PRESSURE TEST NEEDS EXTERNAL PRESSURE REVIEW AS WELL. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:

#### **Option 1 (Single Stage):**

• Cement to surface. If cement does not circulate see B.1.a, c-d above.

#### **Option 2 (Bradenhead):**

Operator has proposed to cement in two stages by conventionally cementing the first stage and performing a bradenhead squeeze on the second stage, contingent upon no returns to surface.

- a. First stage: Operator will cement with intent to reach the top of the **Brushy** Canyon
- b. Second stage:
  - Operator will perform bradenhead squeeze and top-out. Cement to surface. If cement does not reach surface, the appropriate BLM office shall be notified
- 3. The 5-1/2 inch production casing shall be set at approximately 20,164 feet. The minimum required fill of cement behind the 5-1/2 inch production casing is:

#### **Option 1 (Single Stage):**

• Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

#### C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi and for drilling below the intermediate casing is 5000 (5M) psi. Variance is approved to use a 5000 (5M) Annular which shall be tested to 3500 (70% Working Pressure) psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

#### D. SPECIAL REQUIREMENT (S)

#### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in Onshore Order 1 and 2.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

(Note: For a minimum 5M BOPE or less (Utilizing a 10M BOPE system)

#### **BOPE Break Testing Variance**

- BOPE Break Testing is ONLY permitted for 5M BOPE or less. (Annular preventer must be tested to a minimum of 70% of BOPE working pressure and shall be higher than the MASP)
- BOPE Break Testing is NOT permitted to drilling the production hole section.
- Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation.
- While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Any well control event while drilling require notification to the BLM Petroleum Engineer (575-706-2779) prior to the commencement of any BOPE Break Testing operations.
- A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable).
- The BLM is to be contacted (575-361-2822 Eddy County) 4 hours prior to BOPE tests.
- As a minimum, a full BOPE test shall be performed at 21-day intervals.
- In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per Onshore Oil and Gas Order No. 2.
- If in the event break testing is not utilized, then a full BOPE test would be conducted.

#### **Offline Cementing**

Offline cementing OK for surface and intermediate intervals. Notify the BLM prior to the commencement of any offline cementing procedure.

### **GENERAL REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

#### **Contact Eddy County Petroleum Engineering Inspection Staff:**

Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220; BLM NM CFO DrillingNotifications@BLM.GOV; (575) 361-2822

#### **Contact Lea County Petroleum Engineering Inspection Staff:**

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after

installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).

- b. When the operator proposes to set surface casing with Spudder Rig
  - i. Notify the BLM when moving in and removing the Spudder
  - ii. Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
  - iii.BOP/BOPE test to be conducted per 43 CFR 3172 as soon as 2<sup>nd</sup> Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

#### A. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
- 5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe

- shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

#### **B. PRESSURE CONTROL**

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in 43 CFR 3172.
- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - ii.If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - iii.Manufacturer representative shall install the test plug for the initial BOP
  - iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
  - v.If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - i.In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation

- has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to 43 CFR 3172 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- iv. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- v.The results of the test shall be reported to the appropriate BLM office.
- vi.All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- vii. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- viii.BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per 43 CFR 3172.

#### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**KPI** 3/19/2025




# Permian Drilling Hydrogen Sulfide Drilling Operations Plan

Open drill site. No homes or buildings are near the proposed location.

#### 1. Escape

Personnel shall escape upwind of wellbore in the event of an emergency gas release. Escape can take place through the lease road on the Southeast side of the location. Personnel need to move to a safe distance and block the entrance to location. If the primary route is not an option due to the wind direction, then a secondary egress route should be taken.





### Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

### **Scope**

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H2S) gas.

While drilling this well, it is possible to encounter H2S bearing formations. At all times, the first barrier to control H2S emissions will be the drilling fluid, which will have a density high enough to control influx.

### **Objective**

- 1. Provide an immediate and predetermined response plan to any condition when H2S is detected. All H2S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
- 2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
- 3. Provide proper evacuation procedures to cope with emergencies.
- 4. Provide immediate and adequate medical attention should an injury occur.

### **Discussion**

Implementation: This plan with all details is to be fully implemented

before drilling to commence.

Emergency response

Procedure:

This section outlines the conditions and denotes steps

to be taken in the event of an emergency.

Emergency equipment

Procedure:

This section outlines the safety and emergency

equipment that will be required for the drilling of this

well.

Training provisions: This section outlines the training provisions that

must be adhered to prior to drilling.

Drilling emergency call lists: Included are the telephone numbers of all persons to

be contacted should an emergency exist.

Briefing: This section deals with the briefing of all people

involved in the drilling operation.

Public safety: Public safety personnel will be made aware of any

potential evacuation and any additional support

needed.

Check lists: Status check lists and procedural check lists have been

included to insure adherence to the plan.

General information: A general information section has been included to

supply support information.

### **Hydrogen Sulfide Training**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

- 1. The hazards and characteristics of H2S.
- 2. Proper use and maintenance of personal protective equipment and life support systems.
- 3. H2S detection.
- 4. Proper use of H2S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
- 5. Proper techniques for first aid and rescue procedures.
- 6. Physical effects of hydrogen sulfide on the human body.
- 7. Toxicity of hydrogen sulfide and sulfur dioxide.
- 8. Use of SCBA and supplied air equipment.
- 9. First aid and artificial respiration.
- 10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

- 1. The effects of H2S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
- 2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
- 3. The contents and requirements of the H2S Drilling Operations Plan.

H2S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H2S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H2S training has been taken.

### Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H2S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site

### **Emergency Equipment Requirements**

### 1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as 43 CFR part 3170 Subpart 3172.

### Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground. Remotely operated choke.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

### 2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
  - Rig floor and trailers.
  - Vehicle.

### 3. Hydrogen sulfide sensors and alarms

- A. H2S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H2S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

### 4. Visual Warning Systems

A. One sign located at each location entrance with the following language:

Caution – potential poison gas Hydrogen sulfide No admittance without authorization

### *Wind sock – wind streamers:*

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

### Condition flags

A. One each condition flag to be displayed to denote conditions.

```
green – normal conditions
yellow – potential danger
red – danger, H2S present
```

B. Condition flag shall be posted at each location sign entrance.

### 5. Mud Program

The mud program is designed to minimize the risk of having H2S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H2S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

*Mud inspection devices:* 

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

### 6. <u>Metallurgy</u>

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H2S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H2S service.

### 7. Well Testing

No drill stem test will be performed on this well.

### 8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

### 9. <u>Designated area</u>

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

### **Emergency procedures**

- A. In the event of any evidence of H2S level above 10 ppm, take the following steps:
  - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
  - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
  - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
  - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
  - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
  - 6. Take steps to determine if the H2S level can be corrected or suppressed and, if so, proceed as required.

### B. If uncontrollable conditions occur:

1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

- 2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
- 3. Notify public safety personnel of safe briefing / muster area.
- 4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
- 5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

### C. Responsibility:

- 1. Designated personnel.
  - a. Shall be responsible for the total implementation of this plan.
  - b. Shall be in complete command during any emergency.
  - c. Shall designate a back-up.

All personnel:

- 1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw
- 2. Check status of personnel (buddy system).
- 3. Secure breathing equipment.
- 4. Await orders from supervisor.

Drill site manager:

- 1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area.
- 2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system).
- 3. Determine H2S concentrations.
- 4. Assess situation and take control measures.

Tool pusher:

- 1. Don escape unit Report to up nearest upwind designated safe briefing / muster area.
- 2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system).
- 3. Determine H2S concentration.
- 4. Assess situation and take control measures.

Driller:

1. Don escape unit, shut down pumps, continue

rotating DP.

- 2. Check monitor for point of release.
- 3. Report to nearest upwind designated safe briefing / muster area.
- 4. Check status of personnel (in an attempt to rescue, use the buddy system).
- 5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
- 6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.

Derrick man Floor man #1 Floor man #2 1. Will remain in briefing / muster area until instructed by supervisor.

Mud engineer:

- 1. Report to nearest upwind designated safe briefing / muster area.
- 2. When instructed, begin check of mud for ph and H2S level. (Garett gas train.)

Safety personnel:

1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

### Taking a kick

When taking a kick during an H2S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

### **Open-hole logging**

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

### Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

### **Ignition procedures**

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

- 1. Human life and property are endangered.
- 2. There is no hope controlling the blowout under the prevailing conditions at the well.

### <u>Instructions for igniting the well</u>

- 1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
- 2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
- 3. Ignite upwind and do not approach any closer than is warranted.
- 4. Select the ignition site best for protection, and which offers an easy escape route.
- 5. Before firing, check for presence of combustible gas.
- 6. After lighting, continue emergency action and procedure as before.
- 7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

<u>Remember</u>: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. <u>Do not assume the area is safe after the well is ignited.</u>

### Status check list

Note: All items on this list must be completed before drilling to production casing point.

- 1. H2S sign at location entrance.
- 2. Two (2) wind socks located as required.
- 3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
- 4. Air packs inspected and ready for use.
- 5. Cascade system and hose line hook-up as needed.
- 6. Cascade system for refilling air bottles as needed.
- 7. Condition flag on location and ready for use.
- 8. H2S detection system hooked up and tested.
- 9. H2S alarm system hooked up and tested.
- 10. Hand operated H2S detector with tubes on location.
- 11. 1 100' length of nylon rope on location.
- 12. All rig crew and supervisors trained as required.
- 13. All outside service contractors advised of potential H2S hazard on well.
- 14. No smoking sign posted and a designated smoking area identified.
- 15. Calibration of all H2S equipment shall be noted on the IADC report.

Checked by:	Date

### **Procedural check list during H2S events**

### Perform each tour:

- 1. Check fire extinguishers to see that they have the proper charge.
- 2. Check breathing equipment to ensure that it in proper working order.
- 3. Make sure all the H2S detection system is operative.

### Perform each week:

- 1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
- 2. BOP skills (well control drills).
- 3. Check supply pressure on BOP accumulator stand by source.
- 4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
- 5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
- 6. Confirm pressure on all supply air bottles.
- 7. Perform breathing equipment drills with on-site personnel.
- 8. Check the following supplies for availability.
  - A. Emergency telephone list.
  - B. Hand operated H2S detectors and tubes.

### **General evacuation plan**

- 1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H2S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
- 2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
- 3. Company or contractor safety personnel that have been trained in the use of H2S detection equipment and self-contained breathing equipment will monitor H2S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
- 4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
- 5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

<u>Important:</u> Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

### **Emergency actions**

### Well blowout – if emergency

- 1. Evacuate all personnel to "Safe Briefing / Muster Areas" or off location if needed.
- 2. If sour gas evacuate rig personnel.
- 3. If sour gas evacuate public within 3000 ft radius of exposure.
- 4. Don SCBA and shut well in if possible using the buddy system.
- 5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
- 6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
- 6. Give first aid as needed.

### Person down location/facility

- 1. If immediately possible, contact 911. Give location and wait for confirmation.
- 2. Don SCBA and perform rescue operation using buddy system.

### Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hen	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H2S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So2	2.21	5 ppm	-	1000 ppm
Chlorine	C12	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co2	1.52	5000 ppm	5%	10%
Methane	Ch4	0.55	90,000 ppm	Combustib	le above 5% in air

- 1) threshold limit concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit concentration that will cause death with short-term exposure.
- 3) lethal concentration concentration that will cause death with short-term exposure.

### Toxic effects of hydrogen sulfide

Table ii Physical effects of hydrogen sulfide

		Concentration	Physical effects
Percent (%)	Ppm	Grains	
	_	100 std. Ft3*	
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in $3 - 15$ minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

<sup>\*</sup>at 15.00 psia and 60'f.

### **Use of self-contained breathing equipment (SCBA)**

- 1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
- 2 SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
- 3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
- 4. Maintenance and care of SCBA's:
  - a. A program for maintenance and care of SCBA's shall include the following:
    - 1. Inspection for defects, including leak checks.
    - 2. Cleaning and disinfecting.
    - 3. Repair.
    - 4. Storage.
  - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
    - 1. Fully charged cylinders.
    - 2. Regulator and warning device operation.
    - 3. Condition of face piece and connections.
    - 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
  - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
- 5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
- 6. SCBA's should be worn when:
  - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H2S.

- B. When breaking out any line where H2S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H2S exists.
- D. When working in areas where over 10 ppm H2S has been detected.
- E. At any time there is a doubt as to the H2S level in the area to be entered.

### Rescue First aid for H2S poisoning


### Do not panic!

Remain calm – think!

- 1. Don SCBA breathing equipment.
- 2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
- 3. Briefly apply chest pressure arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
- 4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
- 5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H2S gas poisoning no matter how remote the possibility is.
- 6. Notify emergency room personnel that the victim(s) has been exposed to H2S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012



REVISION BLOCK

DATE

ġ

Released to Imaging: 4/30/2025 11:44:29 AM




### SITE PLAN

REDTNK\_T22SR32E\_2504 SEC. 25 TWP. 22-S RGE. 32-E SURVEY: N.M.P.M.

COUNTY: LEA


TANK BATTERY
RECLAMATION
30' TOP SOIL
20' DISTURBANCE AREA



OPERATOR: OXY USA, INC.


U.S.G.S. TOPOGRAPHIC MAP: BOOTLEG RIDGE, N.M. FAA PERMIT NEEDED: NO


100' 0' 100' 200' SCALE: 1" = 200'



### BASIS OF BEARING

ALL BEARINGS AND COORDINATES REFER TO NAD 83, NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET. (ALL BEARINGS, DISTANCES, COORDINATES AND AREAS ARE GRID MEASUREMENTS UTILIZING A COMBINED SCALE FACTOR OF 0.99975697 CONVERGENCE ANGLE OF 0.07066669°.)





SHEET 1 OF 2
PREPARED BY:
R-SQUARED GLOBAL, LLC
510 TRENTON ST. UNIT B
WEST MONROE, LA 71291
318-323-6900 OFFICE
JOB No. R4195\_003



### SITE PLAN

REDTNK\_T22SR32E\_2504 SEC. 25 TWP. 22-S RGE. 32-E

SURVEY: N.M.P.M.
COUNTY: LEA

OPERATOR: OXY USA, INC.

U.S.G.S. TOPOGRAPHIC MAP: BOOTLEG RIDGE, N.M.

FAA PERMIT NEEDED: NO

### WELL 1 STACK CATS 25\_36 FED COM 14H OXY USA, INC.

210' FNL 1749' FEL, SECTION 25

NAD 83, SPCS NM EAST X:759887.63' / Y:498878.27' LAT:32.36949916N / LON:103.62545998W

ND 27, SPCS NM EAST X:718704.94' / Y:498817.96' LAT:32.36937594N / LON:103.62497480W ELEVATION = 3752'

### WELL 2 STACK CATS 25\_36 FED COM 3H CXY USA, INC.

210' FNL 1719' FEL, SECTION 25 NAD 83, SPCS NM EAST

X:759917.62' / Y:498878.59' LAT:32.36949951N / LON:103.62536282W NVD 27, SPCS NM EAST

X:718734.93' / Y:498818.29' LAT:32.36937629N / LON:103.62487764W ELEVATION = 3751'

### WELL 3 STACK CATS 25\_36 FED COM 15H CAY USA, INC.

O' FNL 1689' FEL, SECTION 25 NAD 83, SPCS NM EAST

X:759947.62' / Y:498878.92' LAT:32.36949985N / LON:103.62526566W

NVD 27, SPCS NM EXST X:718764.93' / Y:498818.61' LAT:32.36937663N / LON:103.62478048W ELEVATION = 3751'

### WELL 4 STACK CATS 25\_36 FED COM 4H OXY USA, INC.

210' FNL 1659' FEL, SECTION 25 NAD 83, SPCS NM EAST

X:759977.62' / Y:498879.24' LAT:32.36950019N / LON:103.62516849W NAD 27, SPCS NM EAST

X:718794.93' / Y:498818.93' LAT:32.36937697N / LON:103.62468332W ELEVATION = 3751'

### WELL 5 STACK CATS 25\_36 FED COM 16H OXY USA, INC.

210' FNL 1629' FEL, SECTION 25

NVD 83, SPCS NM EAST X:760007.62' / Y:498879.56' LAT:32.36950053N / LON:103.62507133W NVD 27, SPCS NM EAST

X:718824.93' / Y:498819.25' LAT:32.36937731N / LON:103.62458616W ELEVATION = 3751'

### WELL 6 TUNA NUT 24\_13 FED COM 24H OXY USA, INC.

210' FNL 1569' FEL, SECTION 25

NAD 83, SPCS NM EAST

X:760067.61' / Y:498880.21 LAT:32.36950122N / LON:103.62487700W

NO 27, SPOS NA EAST X:718884.92' / Y:498819.90' LAT:32.36937800N / LON:103.62439183W ELEVATION = 3751'

### WELL 7 Tuna nut 24\_13 FeD com 25H Oxy USA, Inc.

210' FNL 1539' FEL, SECTION 25 NVD 83, SPCS NM EAST

X:760097.61' / Y:498880.53' LAT:32.36950156N / LON:103.62477984W NAD 27, SPCS NM EAST

X:718914.92' / Y:498820.22'
LAT:32.36937834N / LON:103.62429467W
ELEVATION = 3751'

### WELL 8 TUNA NUT 24\_13 FED COM 26H ORY USA, INC.

210' FNL 1509' FEL, SECTION 25

NAD 83, SPCS NM EAST

X:760127.61' / Y:498880.86' LAT:32.36950190N / LON:103.62468268W


NPD 27, SPCS NM EAST X:718944.92' / Y:498820.55' LAT:32.36937868N / LON:103.62419751W ELEVATION = 3751'


10/18/2021	10/26/2021
DATE SURVEYED	DATE DRAWN

REV. DATE BY


### BASIS OF BEARING


ALL BEARINGS AND COORDINATES REFER TO NAD 83, NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET. (ALL BEARINGS, DISTANCES, COORDINATES AND AREAS ARE GRID MEASUREMENTS UTILIZING A COMBINED SCALE FACTOR OF 0.99975697 CONVERGENCE ANGLE OF 0.07066669°.)






SHEET 2 OF 2
PREPARED BY:
R-SQUARED GLOBAL, LLC
510 TRENTON ST. UNIT B
WEST MONROE, LA 71291
318-323-6900 OFFICE
JOB No. R4195\_003





Choke Manifold Valve Choke Manifold Valve Choke Manifold Valve


## 10M Choke Panel







21. Vertical Choke Manifold Valve


\*All Valves 3" minimum








# 5/10M BOP Stack





CONFIDENTIAL					
SURFACE TREATMENT	DO NOT SC			CAMERON	SURFACE
	DRAWN BY: A. SKLENKA	26 Apr 22	W	A Schlumberger Company	SYSTEMS
MATERIAL & HEAT TREAT	A. SKLENKA	26 Apr 22	OXY ADAPT NST 10K 3 STAGE WELLHEAD		
	A. SKLENKA	26 Apr 22		ANDARD / EMERGENC	Y SYSTEM
ESTIMATED 7 WEIGHT:	968.4 LBS INTIAL USE BM: 3614.4 KG   T# 7836394		1 or 1	LO-096232-6	2

Sante Fe Main Office Phone: (505) 476-3441

General Information Phone: (505) 629-6116

Online Phone Directory <a href="https://www.emnrd.nm.gov/ocd/contact-us">https://www.emnrd.nm.gov/ocd/contact-us</a>

### State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

CONDITIONS

Action 446498

### **CONDITIONS**

Operator:	OGRID:
OXY USA INC	16696
P.O. Box 4294	Action Number:
Houston, TX 772104294	446498
	Action Type:
	[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

### CONDITIONS

Created By	Condition	Condition Date
melissaguidry	Cement is required to circulate on both surface and intermediate1 strings of casing.	3/28/2025
melissaguidry	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	3/28/2025
matthew.gomez	Administrative order required for non-standard spacing unit prior to production.	4/28/2025
matthew.gomez	Notify the OCD 24 hours prior to casing & cement.	4/30/2025
matthew.gomez	A [C-103] Sub. Drilling (C-103N) is required within (10) days of spud.	4/30/2025
matthew.gomez	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	4/30/2025
matthew.gomez	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	4/30/2025
matthew.gomez	File As Drilled C-102 and a directional Survey with C-104 completion packet.	4/30/2025