

C-104 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
--	---	----------------------

REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT**Section 1 - Operator and Well Information**

Submittal Type: ☐ Test Allowable (C-104RT) ☒ New Well (C-104NW) ☐ Recomplete (C-104RC) ☐ Pay Add (C-104RC) ☐ Amended	
Operator Name: OXY USA INC	OGRID: 16696
Property Name and Well Number: HEADS CC 9-4 FEDERAL COM 22H	Property Code: 328290
Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal	API Number: 30-0 15-47335
Pool Name: PIERCE CROSSING; BONE SPRING, EAST	Pool Code: 96473

Section 2 – Surface Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
C	16	24S	29E		782 FNL	1534 FWL	32.222712°	-103.993082°	EDDY

Section 3 – Completion Information

Producing Method	Ready Date	Perforations MD	Perforations TVD
Gas lift	04/29/24	9569-19876' MD	9252-9267' TVD

Section 4 – Action IDs for Submissions and Order Numbers

List Action IDs for Drilling Sundries	Was an Order required / needed (Y/N), if yes list Order number:
C-104 RT Action ID (if C-104NW): NA	Communitization Agreement ☒ Yes ☐ No, Order No. pending w/ BLM
Surface Casing Action ID: NA	Unit: ☐ Yes ☒ No, Order No.
Intermediate 1 Casing Action ID: NA	Compulsory Pooling: ☐ Yes ☒ No, Order No.
Intermediate 2 Casing Action ID: NA	Down Hole Commingling: ☐ Yes ☒ No, Order No.
Production Casing Action ID: NA	Surface Commingling: ☒ Yes ☐ No, Order No. PLC-925
All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No	Non-standard Location: ☐ Yes ☒ No ☐ Common ownership Order No.
Liner 1 Action ID: NA	Non-standard Proration: ☒ Yes ☐ No, Order No. R-21776
Casing was installed prior to OCD's Action ID system (Y/N): N	Simultaneous Dedication: ☐ Yes ☒ No, Order No.

Section 5 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Jana Mendiola	<i>Jana Mendiola</i>
Title Regulatory Advisor	Date 07/24/25

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION		Revised July 9, 2024	
			Submittal Type:	☐ Initial Submittal
				☐ Amended Report
		☒ As Drilled		

WELL LOCATION INFORMATION

API Number 30-015-47335	Pool Code 96473	Pool Name PIERCE CROSSING; BONE SPRING, EAST
Property Code 328290	Property Name HEADS CC 9_4 FED COM	Well Number 22H
OGRID No. 16696	Operator Name OXY USA INC.	Ground Level Elevation 2,927.9
Surface Owner: ☐ State ☒ Fee ☐ Tribal ☐ Federal		Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal

Surface Location

UL C	Section 16	Township 24S	Range 29E	Lot	Ft. from N/S 782 NORTH	Ft. from E/W 1,534 WEST	Latitude (NAD 83) 32.222712°	Longitude (NAD 83) -103.993082°	County EDDY
---------	---------------	-----------------	--------------	-----	---------------------------	----------------------------	---------------------------------	------------------------------------	----------------

Bottom Hole Location

UL C	Section 4	Township 24S	Range 29E	Lot 3	Ft. from N/S 25 NORTH	Ft. from E/W 2,157 WEST	Latitude (NAD 83) 32.253964°	Longitude (NAD 83) -103.991119°	County EDDY
---------	--------------	-----------------	--------------	----------	--------------------------	----------------------------	---------------------------------	------------------------------------	----------------

Dedicated Acres 1,278.94	Infill or Defining Well Infill	Defining Well API NA	Overlapping Spacing Unit (Y/N)	Consolidation Code NA
Order Numbers. R-21776		Well setbacks are under Common Ownership: ☐ Yes ☐ No		

Kick Off Point (KOP)

UL C	Section 16	Township 24S	Range 29E	Lot	Ft. from N/S 371 NORTH	Ft. from E/W 2,153 WEST	Latitude (NAD 83) 32.223845°	Longitude (NAD 83) -103.991077°	County EDDY
---------	---------------	-----------------	--------------	-----	---------------------------	----------------------------	---------------------------------	------------------------------------	----------------

First Take Point (FTP)

UL N	Section 9	Township 24S	Range 29E	Lot	Ft. from N/S 143 SOUTH	Ft. from E/W 2,191 WEST	Latitude (NAD 83) 32.225259°	Longitude (NAD 83) -103.990954°	County EDDY
---------	--------------	-----------------	--------------	-----	---------------------------	----------------------------	---------------------------------	------------------------------------	----------------

Last Take Point (LTP)


UL C	Section 4	Township 24S	Range 29E	Lot 3	Ft. from N/S 173 NORTH	Ft. from E/W 2,157 WEST	Latitude (NAD 83) 32.253557°	Longitude (NAD 83) -103.991119°	County EDDY
---------	--------------	-----------------	--------------	----------	---------------------------	----------------------------	---------------------------------	------------------------------------	----------------

Unitized Area or Area of Uniform Interest NA	Spacing Unit Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation:
--	--	-------------------------

OPERATOR CERTIFICATIONS <i>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</i> <i>If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.</i> Jana Mendiola 06/11/25		SURVEYOR CERTIFICATIONS <i>I hereby certify that the well location shown on this plat was plotted from the field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</i> 	
Signature _____ Date _____		Signature and Seal of Professional Surveyor	
Jana Mendiola		23782 July 05, 2023	
Printed Name _____		Certificate Number _____ Date of Survey _____	
janalyn_mendiola@oxy.com			
Email Address			

Note: No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

Property Name HEADS CC 9_4 FED COM	Well Number 22H	Drawn By T.J.S. 05-08-24	Revised By REV. 1 H.S.S. 06-09-25 (UPDATE FORMAT)
---------------------------------------	--------------------	-----------------------------	--

**NAD 83 (SURFACE HOLE LOCATION)**

LATITUDE = 32°13'21.76" (32.222712°)
 LONGITUDE = -103°59'35.09" (-103.993082°)

NAD 27 (SURFACE HOLE LOCATION)

LATITUDE = 32°13'21.32" (32.222590°)
 LONGITUDE = -103°59'33.33" (-103.992593°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 444923.21' E: 646555.96'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 444864.27' E: 605372.09'

NAD 83 (AS-DRILLED FTP)

LATITUDE = 32°13'30.93" (32.225259°)
 LONGITUDE = -103°59'27.43" (-103.990954°)

NAD 27 (AS-DRILLED FTP)

LATITUDE = 32°13'30.49" (32.225136°)
 LONGITUDE = -103°59'25.67" (-103.990465°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 445851.66' E: 647211.00'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 445792.70' E: 606027.15'

NAD 83 (AS-DRILLED LTP)

LATITUDE = 32°15'12.81" (32.253557°)
 LONGITUDE = -103°59'28.03" (-103.991119°)

NAD 27 (AS-DRILLED LTP)

LATITUDE = 32°15'12.36" (32.253435°)
 LONGITUDE = -103°59'26.27" (-103.990629°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 456145.95' E: 647127.02'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 456086.78' E: 605943.43'

NAD 83 (AS-DRILLED KOP)

LATITUDE = 32°13'25.84" (32.223845°)
 LONGITUDE = -103°59'27.88" (-103.991077°)

NAD 27 (AS-DRILLED KOP)

LATITUDE = 32°13'25.40" (32.223722°)
 LONGITUDE = -103°59'26.12" (-103.990588°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 445337.24' E: 647174.53'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 445278.29' E: 605990.67'

NAD 83 (AS-DRILLED LPP)

LATITUDE = 32°13'55.80" (32.232166°)
 LONGITUDE = -103°59'27.22" (-103.990895°)

NAD 27 (AS-DRILLED LPP)

LATITUDE = 32°13'55.36" (32.232043°)
 LONGITUDE = -103°59'25.46" (-103.990406°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 448364.43' E: 647221.24'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 448305.41' E: 606037.45'

NAD 83 (AS-DRILLED BHL)

LATITUDE = 32°15'14.27" (32.253964°)
 LONGITUDE = -103°59'28.03" (-103.991119°)

NAD 27 (AS-DRILLED BHL)

LATITUDE = 32°15'13.83" (32.253842°)
 LONGITUDE = -103°59'26.26" (-103.990628°)
 STATE PLANE NAD 83 (N.M. EAST)
 N: 456294.05' E: 647126.83'
 STATE PLANE NAD 27 (N.M. EAST)
 N: 456234.88' E: 605943.24'

OXY - Delaware Basin

Eddy County, NM (NAD27 - NM E 3001)

Heads Pad

Heads CC 9 4 Fed Com 22H

OH


Design: OH

Standard Survey Report

15 March, 2024





Project: Eddy County, NM (NAD27 - NM E 3001
Site: Heads Pad
Well: Heads CC 9 4 Fed Com 22H
Wellbore: OH
Design: OH
Lat: 32.222590
Long: -103.992593
GL: 2927.90
KB: HP 267 @ 2952.90usft



WELL DETAILS: Heads CC 9 4 Fed Com 22H					
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	444864.27	605372.09	32.222590	-103.992593

TD @ 20025 MD, 9281.09 TVD, 11370.61 N/S, 571.15 E/W

ANNOTATIONS		
MD	TVD	Annotation
498.00	497.95	Tie on
697.00	696.95	First AEP MWD Svy
19990.00	9278.39	Last AEP MWD Svy
20025.00	9281.09	Projection to BHL



Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Project	Eddy County, NM (NAD27 - NM E 3001)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Heads Pad				
Site Position:		Northing:	444,866.58 usft	Latitude:	32.222596
From:	Map	Easting:	605,342.19 usft	Longitude:	-103.992690
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "		

Well	Heads CC 9 4 Fed Com 22H					
Well Position	+N/-S	0.00 usft	Northing:	444,864.27 usft	Latitude:	32.222590
	+E/-W	0.00 usft	Easting:	605,372.09 usft	Longitude:	-103.992593
Position Uncertainty		1.79 usft	Wellhead Elevation:	usft	Ground Level:	2,927.90 usft
Grid Convergence:		0.18 °				

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HRGM	2/11/2024	6.56	59.80	47,376.43135959

Design	OH				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.00	0.00	0.00	359.73	

Survey Program	Date	3/12/2024			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
11.00	498.00	Surface (OH)	B004Mb_MWD+HRGM+SAC	OWSG MWD + HRGM + Sag Correction	
699.00	20,025.00	MWD (OH)	SQC_C705a_MWD+IFR1+S.	OWSG MWD + IFR1 + Sag + FDIR Correction	

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
11.00	0.00	0.01	11.00	0.00	0.00	0.00	0.00	0.00	0.00	
170.00	0.81	107.67	169.99	-0.34	1.07	-0.35	0.51	0.51	0.00	
256.00	1.02	149.09	255.98	-1.18	2.04	-1.19	0.79	0.24	48.16	
350.00	1.31	149.60	349.97	-2.83	3.02	-2.84	0.31	0.31	0.54	
442.00	0.43	144.13	441.95	-4.01	3.75	-4.03	0.96	-0.96	-5.95	
498.00	0.24	44.96	497.95	-4.10	3.96	-4.12	0.94	-0.34	-177.09	
Tie on										
697.00	0.51	38.95	696.95	-3.11	4.81	-3.13	0.14	0.14	-3.02	

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
First AEP MWD Svy									
795.00	0.65	37.86	794.94	-2.33	5.43	-2.36	0.14	0.14	-1.11
891.00	0.46	45.40	890.94	-1.63	6.04	-1.66	0.21	-0.20	7.85
987.00	0.23	73.95	986.94	-1.31	6.50	-1.34	0.29	-0.24	29.74
1,082.00	0.18	190.80	1,081.94	-1.40	6.65	-1.43	0.37	-0.05	123.00
1,178.00	0.63	221.14	1,177.93	-1.95	6.28	-1.98	0.50	0.47	31.60
1,273.00	0.71	221.09	1,272.93	-2.78	5.55	-2.81	0.08	0.08	-0.05
1,369.00	0.77	213.74	1,368.92	-3.77	4.80	-3.79	0.12	0.06	-7.66
1,464.00	0.78	214.44	1,463.91	-4.83	4.08	-4.85	0.01	0.01	0.74
1,559.00	0.91	206.20	1,558.90	-6.04	3.38	-6.06	0.19	0.14	-8.67
1,654.00	0.95	205.57	1,653.89	-7.43	2.71	-7.44	0.04	0.04	-0.66
1,749.00	0.90	209.04	1,748.88	-8.79	2.00	-8.80	0.08	-0.05	3.65
1,845.00	0.86	210.90	1,844.86	-10.07	1.27	-10.08	0.05	-0.04	1.94
1,940.00	0.94	212.87	1,939.85	-11.34	0.48	-11.34	0.09	0.08	2.07
2,035.00	1.00	213.85	2,034.84	-12.68	-0.40	-12.68	0.07	0.06	1.03
2,130.00	0.48	46.01	2,129.84	-13.09	-0.58	-13.09	1.55	-0.55	-176.67
2,225.00	1.52	78.41	2,224.82	-12.56	0.94	-12.57	1.20	1.09	34.11
2,320.00	1.67	78.05	2,319.78	-12.02	3.53	-12.04	0.16	0.16	-0.38
2,415.00	2.07	95.94	2,414.73	-11.91	6.59	-11.94	0.74	0.42	18.83
2,511.00	2.80	108.11	2,510.65	-12.82	10.54	-12.87	0.93	0.76	12.68
2,606.00	2.14	118.17	2,605.56	-14.38	14.31	-14.45	0.83	-0.69	10.59
2,701.00	1.64	114.34	2,700.51	-15.78	17.11	-15.86	0.54	-0.53	-4.03
2,796.00	0.69	71.17	2,795.49	-16.15	18.89	-16.24	1.30	-1.00	-45.44
2,891.00	0.83	9.11	2,890.48	-15.29	19.54	-15.38	0.83	0.15	-65.33
2,986.00	1.65	32.08	2,985.46	-13.45	20.38	-13.55	0.99	0.86	24.18
3,081.00	3.83	44.59	3,080.34	-10.03	23.33	-10.14	2.37	2.29	13.17
3,176.00	5.50	50.68	3,175.03	-4.89	29.08	-5.02	1.83	1.76	6.41
3,366.00	6.76	49.79	3,363.94	8.10	44.67	7.89	0.67	0.66	-0.47
3,462.00	7.13	43.99	3,459.23	16.04	53.12	15.79	0.83	0.39	-6.04
3,557.00	7.73	39.10	3,553.44	25.24	61.25	24.95	0.92	0.63	-5.15
3,652.00	8.04	39.04	3,647.54	35.36	69.46	35.03	0.33	0.33	-0.06
3,747.00	7.78	37.79	3,741.63	45.60	77.58	45.23	0.33	-0.27	-1.32
3,842.00	8.61	43.30	3,835.66	55.85	86.40	55.45	1.20	0.87	5.80
3,937.00	9.49	46.90	3,929.48	66.38	97.00	65.92	1.10	0.93	3.79
4,032.00	10.04	48.60	4,023.11	77.21	108.93	76.69	0.65	0.58	1.79
4,127.00	11.09	55.06	4,116.50	87.92	122.63	87.34	1.66	1.11	6.80
4,223.00	11.21	54.34	4,210.68	98.65	137.78	98.00	0.19	0.13	-0.75
4,318.00	11.11	54.12	4,303.89	109.39	152.70	108.67	0.11	-0.11	-0.23
4,412.00	10.98	53.82	4,396.15	119.99	167.26	119.20	0.15	-0.14	-0.32
4,508.00	10.81	53.29	4,490.42	130.76	181.86	129.91	0.21	-0.18	-0.55
4,603.00	10.87	53.38	4,583.72	141.43	196.19	140.51	0.07	0.06	0.09
4,698.00	11.17	53.24	4,676.97	152.28	210.75	151.29	0.32	0.32	-0.15
4,793.00	11.73	53.19	4,770.08	163.58	225.86	162.51	0.59	0.59	-0.05

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
4,888.00	11.98	53.12	4,863.05	175.28	241.47	174.14	0.26	0.26	-0.07	
4,983.00	12.31	53.02	4,955.93	187.29	257.45	186.07	0.35	0.35	-0.11	
5,078.00	11.96	53.08	5,048.80	199.29	273.41	198.00	0.37	-0.37	0.06	
5,173.00	11.98	53.45	5,141.74	211.08	289.20	209.71	0.08	0.02	0.39	
5,268.00	11.71	52.79	5,234.71	222.78	304.80	221.34	0.32	-0.28	-0.69	
5,363.00	11.44	52.48	5,327.78	234.35	319.95	232.84	0.29	-0.28	-0.33	
5,458.00	10.76	50.69	5,421.00	245.70	334.28	244.13	0.80	-0.72	-1.88	
5,553.00	10.63	50.15	5,514.35	256.94	347.87	255.29	0.17	-0.14	-0.57	
5,648.00	10.55	50.52	5,607.74	268.08	361.31	266.37	0.11	-0.08	0.39	
5,743.00	10.27	50.21	5,701.17	279.03	374.53	277.26	0.30	-0.29	-0.33	
5,838.00	10.10	49.88	5,794.68	289.82	387.41	287.99	0.19	-0.18	-0.35	
5,933.00	10.11	50.45	5,888.20	300.49	400.21	298.60	0.11	0.01	0.60	
6,028.00	10.12	49.90	5,981.73	311.18	413.02	309.23	0.10	0.01	-0.58	
6,124.00	10.16	50.16	6,076.23	322.04	425.97	320.03	0.06	0.04	0.27	
6,219.00	9.89	49.76	6,169.78	332.67	438.63	330.60	0.29	-0.28	-0.42	
6,314.00	9.70	49.64	6,263.39	343.13	450.96	341.00	0.20	-0.20	-0.13	
6,409.00	9.34	49.23	6,357.08	353.34	462.90	351.16	0.39	-0.38	-0.43	
6,504.00	9.27	48.58	6,450.83	363.44	474.47	361.20	0.13	-0.07	-0.68	
6,599.00	8.78	49.43	6,544.66	373.22	485.72	370.93	0.53	-0.52	0.89	
6,694.00	7.97	55.61	6,638.64	381.65	496.66	379.31	1.27	-0.85	6.51	
6,789.00	6.85	57.71	6,732.85	388.40	506.89	386.01	1.21	-1.18	2.21	
6,884.00	5.91	53.32	6,827.26	394.35	515.60	391.91	1.11	-0.99	-4.62	
6,979.00	4.69	54.45	6,921.85	399.53	522.68	397.06	1.29	-1.28	1.19	
7,074.00	3.39	52.89	7,016.61	403.48	528.08	400.99	1.37	-1.37	-1.64	
7,170.00	4.22	59.55	7,112.40	406.98	533.39	404.47	0.98	0.86	6.94	
7,265.00	4.46	61.41	7,207.13	410.52	539.65	407.98	0.29	0.25	1.96	
7,360.00	3.48	62.04	7,301.90	413.64	545.44	411.07	1.03	-1.03	0.66	
7,455.00	2.47	61.39	7,396.77	415.97	549.78	413.38	1.06	-1.06	-0.68	
7,550.00	2.73	80.25	7,491.68	417.34	553.81	414.72	0.94	0.27	19.85	
7,646.00	3.11	94.74	7,587.55	417.51	558.66	414.87	0.86	0.40	15.09	
7,741.00	3.03	92.74	7,682.42	417.18	563.73	414.52	0.14	-0.08	-2.11	
7,836.00	2.92	89.35	7,777.29	417.08	568.66	414.40	0.22	-0.12	-3.57	
7,931.00	2.53	84.68	7,872.18	417.31	573.17	414.60	0.47	-0.41	-4.92	
8,026.00	2.65	87.48	7,967.08	417.60	577.45	414.87	0.18	0.13	2.95	
8,122.00	3.76	87.50	8,062.93	417.83	582.81	415.08	1.16	1.16	0.02	
8,217.00	4.49	90.80	8,157.68	417.92	589.64	415.13	0.81	0.77	3.47	
8,312.00	4.19	90.73	8,252.41	417.82	596.83	415.00	0.32	-0.32	-0.07	
8,407.00	3.31	92.22	8,347.21	417.67	603.04	414.82	0.93	-0.93	1.57	
8,502.00	3.17	105.84	8,442.06	416.85	608.31	413.98	0.82	-0.15	14.34	
8,600.00	2.96	107.75	8,539.92	415.34	613.32	412.44	0.24	-0.21	1.95	
8,680.00	2.68	102.26	8,619.82	414.31	617.12	411.40	0.49	-0.35	-6.86	
8,712.00	2.64	100.21	8,651.79	414.02	618.58	411.10	0.32	-0.13	-6.41	
8,807.00	11.09	23.83	8,746.13	422.01	624.44	419.07	11.34	8.89	-80.40	
8,902.00	25.58	18.89	8,836.07	449.93	634.82	446.93	15.33	15.25	-5.20	

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,998.00	29.62	3.51	8,921.24	493.29	643.00	490.25	8.50	4.21	-16.02	
9,093.00	31.93	348.11	9,002.98	541.38	639.26	538.37	8.62	2.43	-16.21	
9,188.00	43.48	352.45	9,078.03	598.57	629.75	595.60	12.47	12.16	4.57	
9,284.00	52.89	4.37	9,142.09	669.78	628.32	666.82	13.45	9.80	12.42	
9,379.00	62.09	8.24	9,193.11	749.29	637.25	746.28	10.27	9.68	4.07	
9,474.00	73.82	5.12	9,228.71	836.59	647.37	833.53	12.72	12.35	-3.28	
9,569.00	78.21	4.46	9,251.66	928.43	655.06	925.33	4.67	4.62	-0.69	
9,664.00	86.99	2.17	9,263.89	1,022.38	660.48	1,019.26	9.55	9.24	-2.41	
9,759.00	90.64	1.07	9,265.85	1,117.31	663.17	1,114.17	4.01	3.84	-1.16	
9,819.00	92.01	1.26	9,264.46	1,177.28	664.39	1,174.13	2.31	2.28	0.32	
9,887.00	91.86	0.80	9,262.17	1,245.23	665.61	1,242.08	0.71	-0.22	-0.68	
9,982.00	89.56	357.96	9,260.99	1,340.20	664.58	1,337.05	3.85	-2.42	-2.99	
10,077.00	87.46	355.81	9,263.46	1,435.02	659.42	1,431.89	3.16	-2.21	-2.26	
10,173.00	87.96	356.87	9,267.30	1,530.74	653.30	1,527.65	1.22	0.52	1.10	
10,268.00	87.65	357.97	9,270.93	1,625.57	649.03	1,622.50	1.20	-0.33	1.16	
10,363.00	87.50	0.02	9,274.95	1,720.47	647.36	1,717.40	2.16	-0.16	2.16	
10,458.00	87.14	1.58	9,279.40	1,815.35	648.69	1,812.28	1.68	-0.38	1.64	
10,553.00	87.56	2.90	9,283.79	1,910.18	652.40	1,907.08	1.46	0.44	1.39	
10,648.00	88.19	2.44	9,287.31	2,005.01	656.82	2,001.89	0.82	0.66	-0.48	
10,743.00	90.60	3.41	9,288.31	2,099.87	661.66	2,096.73	2.73	2.54	1.02	
10,839.00	91.14	2.86	9,286.86	2,195.72	666.91	2,192.55	0.80	0.56	-0.57	
10,934.00	90.58	0.70	9,285.43	2,290.65	669.86	2,287.47	2.35	-0.59	-2.27	
11,029.00	90.73	2.06	9,284.35	2,385.62	672.15	2,382.42	1.44	0.16	1.43	
11,124.00	89.60	358.84	9,284.07	2,480.60	672.90	2,477.40	3.59	-1.19	-3.39	
11,219.00	89.04	358.35	9,285.20	2,575.56	670.57	2,572.37	0.78	-0.59	-0.52	
11,315.00	89.24	358.00	9,286.64	2,671.50	667.51	2,668.33	0.42	0.21	-0.36	
11,410.00	89.30	355.83	9,287.85	2,766.35	662.40	2,763.20	2.28	0.06	-2.28	
11,505.00	90.21	358.71	9,288.26	2,861.23	657.88	2,858.10	3.18	0.96	3.03	
11,600.00	91.22	359.47	9,287.07	2,956.21	656.37	2,953.09	1.33	1.06	0.80	
11,696.00	90.30	359.40	9,285.80	3,052.20	655.42	3,049.07	0.96	-0.96	-0.07	
11,792.00	90.44	2.61	9,285.18	3,148.17	657.10	3,145.04	3.35	0.15	3.34	
11,888.00	89.11	359.77	9,285.55	3,244.13	659.10	3,240.99	3.27	-1.39	-2.96	
11,984.00	90.36	2.57	9,286.00	3,340.10	661.06	3,336.95	3.19	1.30	2.92	
12,080.00	91.01	2.39	9,284.85	3,436.00	665.21	3,432.83	0.70	0.68	-0.19	
12,175.00	90.82	0.93	9,283.33	3,530.95	667.96	3,527.76	1.55	-0.20	-1.54	
12,271.00	91.72	358.06	9,281.21	3,626.91	667.12	3,623.73	3.13	0.94	-2.99	
12,367.00	91.67	0.00	9,278.37	3,722.85	665.49	3,719.67	2.02	-0.05	2.02	
12,463.00	90.31	357.16	9,276.71	3,818.80	663.11	3,815.63	3.28	-1.42	-2.96	
12,558.00	89.42	357.03	9,276.93	3,913.67	658.30	3,910.53	0.95	-0.94	-0.14	
12,653.00	90.56	0.08	9,276.95	4,008.63	655.90	4,005.49	3.43	1.20	3.21	
12,748.00	91.52	0.17	9,275.22	4,103.61	656.11	4,100.47	1.01	1.01	0.09	
12,843.00	88.60	356.68	9,275.12	4,198.55	653.50	4,195.43	4.79	-3.07	-3.67	
12,939.00	90.08	357.95	9,276.23	4,294.44	649.00	4,291.33	2.03	1.54	1.32	

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,033.00	88.26	356.95	9,277.59	4,388.33	644.82	4,385.24	2.21	-1.94	-1.06
13,129.00	90.63	357.40	9,278.52	4,484.20	640.09	4,481.13	2.51	2.47	0.47
13,224.00	91.74	1.22	9,276.56	4,579.15	638.95	4,576.09	4.19	1.17	4.02
13,319.00	90.43	358.46	9,274.76	4,674.12	638.68	4,671.06	3.22	-1.38	-2.91
13,414.00	91.02	359.47	9,273.55	4,769.10	636.97	4,766.04	1.23	0.62	1.06
13,509.00	89.90	356.98	9,272.79	4,864.04	634.02	4,861.00	2.87	-1.18	-2.62
13,604.00	90.37	355.22	9,272.57	4,958.82	627.56	4,955.80	1.92	0.49	-1.85
13,699.00	89.24	353.89	9,272.89	5,053.38	618.55	5,050.41	1.84	-1.19	-1.40
13,794.00	88.30	355.69	9,274.93	5,147.97	609.93	5,145.03	2.14	-0.99	1.89
13,890.00	89.33	355.02	9,276.92	5,243.63	602.15	5,240.73	1.28	1.07	-0.70
13,985.00	90.14	359.63	9,277.36	5,338.50	597.72	5,335.62	4.93	0.85	4.85
14,080.00	89.91	1.05	9,277.31	5,433.49	598.28	5,430.61	1.51	-0.24	1.49
14,175.00	89.14	356.49	9,278.10	5,528.44	596.25	5,525.57	4.87	-0.81	-4.80
14,270.00	89.90	357.77	9,278.90	5,623.32	591.49	5,620.47	1.57	0.80	1.35
14,365.00	89.16	357.94	9,279.68	5,718.25	587.93	5,715.41	0.80	-0.78	0.18
14,460.00	90.78	359.78	9,279.73	5,813.22	586.04	5,810.39	2.58	1.71	1.94
14,555.00	90.71	359.43	9,278.49	5,908.21	585.39	5,905.39	0.38	-0.07	-0.37
14,651.00	91.10	2.69	9,276.97	6,004.17	587.16	6,001.33	3.42	0.41	3.40
14,746.00	91.17	357.80	9,275.09	6,099.12	587.57	6,096.28	5.15	0.07	-5.15
14,841.00	91.01	357.58	9,273.28	6,194.02	583.74	6,191.21	0.29	-0.17	-0.23
14,936.00	90.10	1.59	9,272.36	6,289.00	583.05	6,286.18	4.33	-0.96	4.22
15,031.00	90.95	0.35	9,271.49	6,383.98	584.66	6,381.15	1.58	0.89	-1.31
15,127.00	90.61	0.62	9,270.19	6,479.96	585.47	6,477.13	0.45	-0.35	0.28
15,222.00	90.85	3.09	9,268.98	6,574.90	588.55	6,572.05	2.61	0.25	2.60
15,317.00	90.25	1.22	9,268.06	6,669.82	592.12	6,666.96	2.07	-0.63	-1.97
15,412.00	90.12	1.51	9,267.76	6,764.80	594.38	6,761.92	0.33	-0.14	0.31
15,508.00	90.23	1.61	9,267.46	6,860.76	597.00	6,857.87	0.15	0.11	0.10
15,603.00	89.96	3.98	9,267.31	6,955.64	601.63	6,952.73	2.51	-0.28	2.49
15,698.00	89.62	9.67	9,267.66	7,049.93	612.91	7,046.96	6.00	-0.36	5.99
15,793.00	89.39	11.71	9,268.48	7,143.27	630.54	7,140.22	2.16	-0.24	2.15
15,888.00	89.15	6.18	9,269.69	7,237.07	645.30	7,233.95	5.83	-0.25	-5.82
15,983.00	90.36	356.50	9,270.09	7,331.93	647.52	7,328.80	10.27	1.27	-10.19
16,079.00	89.83	357.16	9,269.94	7,427.78	642.21	7,424.67	0.88	-0.55	0.69
16,174.00	89.67	358.58	9,270.35	7,522.71	638.68	7,519.62	1.50	-0.17	1.49
16,269.00	89.78	359.79	9,270.81	7,617.70	637.33	7,614.61	1.28	0.12	1.27
16,364.00	89.94	359.66	9,271.04	7,712.70	636.87	7,709.61	0.22	0.17	-0.14
16,460.00	90.09	359.83	9,271.01	7,808.70	636.44	7,805.61	0.24	0.16	0.18
16,554.00	89.82	0.91	9,271.09	7,902.69	637.05	7,899.60	1.18	-0.29	1.15
16,649.00	89.95	0.48	9,271.28	7,997.69	638.20	7,994.59	0.47	0.14	-0.45
16,744.00	89.86	0.31	9,271.43	8,092.68	638.86	8,089.58	0.20	-0.09	-0.18
16,839.00	89.40	359.38	9,272.05	8,187.68	638.60	8,184.58	1.09	-0.48	-0.98
16,934.00	89.20	358.72	9,273.21	8,282.66	637.03	8,279.57	0.73	-0.21	-0.69
17,029.00	90.19	359.74	9,273.71	8,377.65	635.75	8,374.56	1.50	1.04	1.07

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
17,124.00	88.99	359.13	9,274.39	8,472.64	634.81	8,469.55	1.42	-1.26	-0.64	
17,219.00	90.82	358.96	9,274.55	8,567.62	633.23	8,564.54	1.93	1.93	-0.18	
17,315.00	90.85	357.51	9,273.15	8,663.56	630.27	8,660.50	1.51	0.03	-1.51	
17,409.00	89.54	357.73	9,272.83	8,757.48	626.37	8,754.43	1.41	-1.39	0.23	
17,504.00	89.56	358.94	9,273.58	8,852.43	623.61	8,849.40	1.27	0.02	1.27	
17,599.00	89.99	358.50	9,273.95	8,947.41	621.49	8,944.38	0.65	0.45	-0.46	
17,694.00	90.22	358.23	9,273.78	9,042.37	618.78	9,039.35	0.37	0.24	-0.28	
17,789.00	89.82	359.60	9,273.75	9,137.35	616.98	9,134.34	1.50	-0.42	1.44	
17,885.00	89.64	358.77	9,274.20	9,233.34	615.61	9,230.34	0.88	-0.19	-0.86	
17,980.00	88.88	358.31	9,275.42	9,328.30	613.19	9,325.31	0.94	-0.80	-0.48	
18,075.00	89.37	358.44	9,276.88	9,423.25	610.50	9,420.27	0.53	0.52	0.14	
18,170.00	89.46	358.38	9,277.85	9,518.21	607.86	9,515.24	0.11	0.09	-0.06	
18,265.00	90.80	359.06	9,277.63	9,613.18	605.74	9,610.22	1.58	1.41	0.72	
18,359.00	88.29	358.64	9,278.38	9,707.15	603.85	9,704.20	2.71	-2.67	-0.45	
18,454.00	91.14	358.66	9,278.85	9,802.11	601.62	9,799.17	3.00	3.00	0.02	
18,550.00	91.98	359.56	9,276.23	9,898.07	600.13	9,895.13	1.28	0.88	0.94	
18,645.00	91.60	359.15	9,273.27	9,993.01	599.06	9,990.08	0.59	-0.40	-0.43	
18,740.00	91.73	358.87	9,270.51	10,087.96	597.42	10,085.03	0.32	0.14	-0.29	
18,835.00	91.92	359.29	9,267.48	10,182.90	595.89	10,179.98	0.49	0.20	0.44	
18,930.00	89.46	357.82	9,266.34	10,277.85	593.50	10,274.94	3.02	-2.59	-1.55	
19,026.00	90.58	358.75	9,266.30	10,373.80	590.62	10,370.91	1.52	1.17	0.97	
19,121.00	91.56	359.00	9,264.53	10,468.77	588.76	10,465.88	1.06	1.03	0.26	
19,216.00	92.13	0.16	9,261.47	10,563.71	588.06	10,560.83	1.36	0.60	1.22	
19,311.00	91.51	358.91	9,258.45	10,658.66	587.29	10,655.78	1.47	-0.65	-1.32	
19,406.00	92.57	359.89	9,255.07	10,753.59	586.30	10,750.71	1.52	1.12	1.03	
19,501.00	89.97	359.81	9,252.97	10,848.56	586.05	10,845.68	2.74	-2.74	-0.08	
19,597.00	90.46	358.55	9,252.61	10,944.55	584.67	10,941.67	1.41	0.51	-1.31	
19,692.00	90.03	358.29	9,252.20	11,039.51	582.06	11,036.65	0.53	-0.45	-0.27	
19,787.00	85.08	356.12	9,256.25	11,134.28	577.43	11,131.43	5.69	-5.21	-2.28	
19,882.00	82.25	355.98	9,266.73	11,228.46	570.93	11,225.65	2.98	-2.98	-0.15	
19,977.00	84.96	1.74	9,277.32	11,322.80	569.06	11,320.00	6.67	2.85	6.06	
19,990.00	85.58	2.62	9,278.40	11,335.75	569.56	11,332.94	8.26	4.77	6.77	
Last AEP MWD Svy										
20,025.00	85.58	2.62	9,281.09	11,370.61	571.15	11,367.79	0.00	0.00	0.00	
Projection to BHL										

Survey Report

Company:	OXY - Delaware Basin	Local Co-ordinate Reference:	Well Heads CC 9 4 Fed Com 22H
Project:	Eddy County, NM (NAD27 - NM E 3001)	TVD Reference:	HP 267 @ 2952.90usft
Site:	Heads Pad	MD Reference:	HP 267 @ 2952.90usft
Well:	Heads CC 9 4 Fed Com 22H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	Fhartmann

Design Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment	
		+N/-S (usft)	+E/-W (usft)		
498.00	497.95	-4.10	3.96	Tie on	
697.00	696.95	-3.11	4.81	First AEP MWD Svy	
19,990.00	9,278.40	11,335.75	569.56	Last AEP MWD Svy	
20,025.00	9,281.09	11,370.61	571.15	Projection to BHL	

Checked By: _____

Approved By: _____

Date: _____

C-105 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
--	---	----------------------

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

Section 1 - Operator and Well Information

Submittal Type: ☒ New Well ☐ Workover ☐ Deepening ☐ Plugback ☐ Different Reservoir ☐ C-144 Closure Attachment ☐ Other	
Operator Name: OXY USA INC	OGRID: 16696
Property Name and Well Number: HEADS CC 9-4 FEDERAL COM 22H	Property Code: 328290
Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal	API Number: 30-0 15-47335
Pool Name: PIERCE CROSSING; BONE SPRING, EAST	Pool Code: 96473

Section 2 – Well Location

	UI or lot no.	Section	Township	Range	Lot Id	Feet from	N/S Line	Feet from	E/W Line	County
SHL:	C	16	24S	29E		782	FNL	1534	FWL	EDDY
BHL	C	4	24S	29E	3	25	FNL	2157	FWL	EDDY

Section 3 – Completion Information

Date T.D. Reached 03/04/24	Total Measured Depth of Well 20025' MD	Acid Volume (bbls) NA	☒ Directional Survey Submitted ☐ Deviation Survey Submitted
Date Rig Released 03/07/24	Plug-Back Measured Depth 19980' MD	Completion Fluid Used (bbls) 437540	Were Logs Ran (Y/N) Y
Completion Date 04/29/24	Perforations (MD and TVD) 9569-19876'MD/9252-9267'TVD	Completion Proppant Used (lbs) 25833848#	List Type of Logs Ran if applicable: CBL

Section 4 – Action IDs for Submissions and Order Numbers

Surface Casing Action ID: NA	UIC Permit/Order (UIC wells only) ☐ Yes ☒ No, Order No.
Intermediate 1 Casing Action ID: NA	NOI Recomplete Action ID (if applicable): NA
Intermediate 2 Casing Action ID: NA	NOI Plugback Action ID (if applicable): NA
Production Casing Action ID: NA	Cement Squeeze Action ID (if applicable): NA
Tubing Action ID: NA	All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No
Liner 1 Action ID: NA	Casing was installed prior to Action ID system (Y/N): N

Section 5 – Test Data

Date First Production 05/02/24	Production Method Gas lift	Well Status Producing	Gas – Oil Ratio 1453
Date of Test 05/11/24	Choke Size 78	Flowing Tubing Pressure NA	Casing Pressure 602
24 hr Oil (bbls) 2077	24 hr Gas (MCF) 3017	24 hr Water (bbls) 2404	Oil Gravity - API
Disposition of Gas: sold			

Section 6 – Pits


☐ A temporary pit was used at the well. If so, attach a plat with the location of the temporary pit.
☒ A Closed Loop System was used.
☐ If an on-site burial was used at the well, report the exact location of the on-site burial: LAT: _____ LONG: _____

Section 7 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Jana Mendiola	<i>Jana Mendiola</i>
Title Regulatory Advisor	Date 07/24/25

South Formations				North Formations			
Formation/Zone	MD	TVD	W/O/G	Formation/Zone	MD	TVD	W/O/G
T. Anhy	138	138	W	T. San Jose			
T. Salt	1298	1298		T. Nacimiento			
B. Salt	2873	2873		T. Ojo Alamo			
T. Yates				T. Kirtland			
T. 7 Rivers				T. Fruitland			
T. Queen				T. Pictured Cliffs			
T. Grayburg				T. Lewis Shale			
T. San Andres				T. Chacra			
T. Glorieta				T. Cliff House			
T. Yeso				T. Menefee			
T. Paddock				T. Point Lookout			
T. Blinebry				T. Mancos			
T.Tubb				T. Gallup			
T. Drinkard				T. Greenhorn			
T. Abo				T. Graneros			
T. Wolfcamp				T. Dakota			
T. Penn				T. Morrison			
T. Cisco				T. Bluff			
T. Canyon				T.Todilto			
T. Strawn				T. Entrada			
T. Atoka				T. Wingate			
T. Morrow				T. Chinle			
T. Barnett Shale				T. Permian			
T. Miss				T. Penn A"			
T. Woodford Shale				T. Penn. "B"			
T. Devonian				T. Penn. "C"			
T. Silurian				T. Penn. "D"			
T. Fusselman				T. Leadville			
T. Montoya				T. Madison			
T. Simpson				T. Elbert			
T. McKee				T. McCracken			
T. Waddell				T. Ignacio Otzte			
T. Connel				T. Granite			
T. Ellenburger				T. Hermosa			
T. Gr. Wash				T. De Chelly			
T. Delaware Sand				T. Pinkerton			
T. Lamar Lime	2842	2842	o/g				
T. Bell Canyon	2902	2902	o/g				
T. Cherry Canyon	3776	3776	o/g				
T. Brushy Canyon	5034	5034	o/g				
T. Bone Springs	6694	6591	o/g				
T. 1st BS Sand	7700	7609	o/g				
T. 2nd BS Carbonate							
T. 2nd BS Sand	8600	8434	o/g				
T. 3rd BS Carbonate							
T. 3rd BS Sand	8805	8729	o/g				

OXY USA Inc.
HEADS CC 9-4 FEDERAL COM 22H
API No. 30-015-47335



Well Name: HEADS CC 9-4 FED COM	Well Location: T24S / R29E / SEC 16 / NWNW / 32.22277 / -103.993885	County or Parish/State: EDDY / NM
Well Number: 22H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM99034	Unit or CA Name:	Unit or CA Number:
US Well Number: 3001547335	Operator: OXY USA INCORPORATED	

Subsequent Report

Sundry ID: 2788594

Type of Submission: Subsequent Report	Type of Action: Workover Operations
Date Sundry Submitted: 05/06/2024	Time Sundry Submitted: 01:14
Date Operation Actually Began: 04/06/2024	

Actual Procedure: RUPU 04/06/24, RIH & clean out to PBTD @ 19980', pressure test casing to 6000# for 30 min, good test. RIH & perf @ 9569-19876' Total 1230 holes. Frac in 41 stages w/ 410680BBL Produced Water + 26860BBL Brackish Water (> 1,000 mg/I TDS and 10,000 mg/I TDS) w/ 25833848# sand, RD Frac 04/15/24. Well ready to produce 04/29/24. OXY USA Inc. requests a tubing exception while continuing to flow back this well. The estimated date of tubing install is 07/31/2024.

Well Name: HEADS CC 9-4 FED COM	Well Location: T24S / R29E / SEC 16 / NWNW / 32.22277 / -103.993885	County or Parish/State: EDDY / NM
Well Number: 22H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM99034	Unit or CA Name:	Unit or CA Number:
US Well Number: 3001547335	Operator: OXY USA INCORPORATED	

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: JANA MENDIOLA	Signed on: MAY 06, 2024 01:14 PM
Name: OXY USA INCORPORATED	
Title: Regulatory Advisor	
Street Address: 1600 GEHRIG DR	
City: MIDLAND	State: TX
Phone: (432) 685-5936	
Email address: Janalyn_mendiola@oxy.com	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752345972	BLM POC Email Address: jshepard@blm.gov
Disposition: Accepted	Disposition Date: 05/15/2024
Signature: Jonathon Shepard	

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 488482

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 488482
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.
☒	I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 488482

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 488482
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 within 10 days of BLM Approval.	8/12/2025