

C-104 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
--	---	----------------------

REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

Section 1 - Operator and Well Information

Submittal Type: ☐ Test Allowable (C-104RT) ☒ New Well (C-104NW) ☐ Recomplete (C-104RC) ☐ Pay Add (C-104RC) ☐ Amended	
Operator Name: OXY USA INC	OGRID: 16696
Property Name and Well Number: DR PI UNIT 174H	Property Code:
Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal	API Number: 30-0 25-48954
Pool Name: Bilbrey Basin; Bone Spring, South	Pool Code: 97366

Section 2 – Surface Location

UL O	Section 17	Township 22S	Range 32E	Lot	Ft. from N/S 979'FSL	Ft. from E/W 1375'FEL	Latitude 32.387061°	Longitude -103.692679°	County LEA
---------	---------------	-----------------	--------------	-----	-------------------------	--------------------------	------------------------	---------------------------	---------------

Section 3 – Completion Information

Producing Method Gas lift	Ready Date 07/06/24	Perforations MD 10069-20137'MD	Perforations TVD 9899-9992'TVD
------------------------------	------------------------	-----------------------------------	-----------------------------------

Section 4 – Action IDs for Submissions and Order Numbers

List Action IDs for Drilling Sundries	Was an Order required / needed (Y/N), if yes list Order number:
C-104 RT Action ID (if C-104NW):	Communitization Agreement ☐ Yes ☒ No, Order No.
Surface Casing Action ID: 362448	Unit: ☒ Yes ☐ No, Order No. NMNM143828X
Intermediate 1 Casing Action ID: 362448	Compulsory Pooling: ☐ Yes ☒ No, Order No.
Intermediate 2 Casing Action ID: NA	Down Hole Commingling: ☐ Yes ☒ No, Order No.
Production Casing Action ID: 362448	Surface Commingling: ☒ Yes ☐ No, Order No. PLC-844-D
All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No	Non-standard Location: ☐ Yes ☒ No ☐ Common ownership Order No.
Liner 1 Action ID: NA	Non-standard Proration: ☐ Yes ☒ No, Order No.
Casing was installed prior to OCD's Action ID system (Y/N): N	Simultaneous Dedication: ☐ Yes ☒ No, Order No.

Section 5 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Jana Mendiola <i>Jana Mendiola</i>	
Title Regulatory Advisor	Date 09/19/24

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION		Revised July 9, 2024	
			Submittal Type:	☐ Initial Submittal
				☐ Amended Report
		☒ As Drilled		

WELL LOCATION INFORMATION

API Number 30-025-48954	Pool Code 97366	Pool Name Bilbrey Basin; Bone Spring, South
Property Code	Property Name DR PI UNIT	Well Number 174H
OGRID No. 16696	Operator Name OXY USA INC.	Ground Level Elevation 3,679.4'
Surface Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal		Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal

Surface Location

UL O	Section 17	Township 22S	Range 32E	Lot	Ft. from N/S 979 SOUTH	Ft. from E/W 1,375 EAST	Latitude (NAD 83) 32.387061°	Longitude (NAD 83) -103.692679°	County LEA
---------	---------------	-----------------	--------------	-----	---------------------------	----------------------------	---------------------------------	------------------------------------	---------------

Bottom Hole Location

UL A	Section 8	Township 22S	Range 32E	Lot	Ft. from N/S 62 NORTH	Ft. from E/W 528 EAST	Latitude (NAD 83) 32.413245°	Longitude (NAD 83) -103.689973°	County LEA
---------	--------------	-----------------	--------------	-----	--------------------------	--------------------------	---------------------------------	------------------------------------	---------------

Dedicated Acres 640	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
Order Numbers.		Well setbacks are under Common Ownership: ☐ Yes ☐ No		

Kick Off Point (KOP)

UL P	Section 17	Township 22S	Range 32E	Lot	Ft. from N/S 141 SOUTH	Ft. from E/W 773 EAST	Latitude (NAD 83) 32.384765°	Longitude (NAD 83) -103.690726°	County LEA
---------	---------------	-----------------	--------------	-----	---------------------------	--------------------------	---------------------------------	------------------------------------	---------------


First Take Point (FTP)

UL P	Section 17	Township 22S	Range 32E	Lot	Ft. from N/S 348 SOUTH	Ft. from E/W 610 EAST	Latitude (NAD 83) 32.385335°	Longitude (NAD 83) -103.690199°	County LEA
---------	---------------	-----------------	--------------	-----	---------------------------	--------------------------	---------------------------------	------------------------------------	---------------

Last Take Point (LTP)



UL A	Section 8	Township 22S	Range 32E	Lot	Ft. from N/S 188 NORTH	Ft. from E/W 524 EAST	Latitude (NAD 83) 32.412899°	Longitude (NAD 83) -103.689960°	County LEA
---------	--------------	-----------------	--------------	-----	---------------------------	--------------------------	---------------------------------	------------------------------------	---------------

Unitized Area or Area of Uniform Interest NMNM143828X	Spacing Unit Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation:
---	--	-------------------------

OPERATOR CERTIFICATIONS <i>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</i> <i>If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.</i>  09/19/24		SURVEYOR CERTIFICATIONS <i>I hereby certify that the well location shown on this plat was plotted from the field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</i> 	
Signature _____ Date _____		Signature and Seal of Professional Surveyor	
Printed Name Jana Mendiola		23782 October 26, 2022	
Email Address janalyn_mendiola@oxy.com		Certificate Number Date of Survey	

Note: No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

Property Name DR PI FED UNIT 17_8 DA	Well Number 74H	Drawn By D.M.C. 08-05-24	Revised By
---	--------------------	-----------------------------	------------



APPROXIMATE WELLBORE MEASURED DEPTH DISTANCE FROM FTP TO LTP	
LEASE	DISTANCE
NMNM 128362	4,968.46'
NMNM 090586	5,099.54'
TOTAL	10,068.00'

- = SURFACE HOLE LOCATION
- ◆ = AS-DRILLED KICK OFF POINT/FIRST TAKE POINT/ LAST TAKE POINT
- ☆ = AS-DRILLED LEASE CROSSING
- = AS-DRILLED BOTTOM HOLE LOCATION
- ▲ = SECTION CORNER LOCATED
- = HORIZONTAL SPACING UNIT
- = AS-DRILLED WELLBORE

NAD 83 (SURFACE HOLE LOCATION)	
LATITUDE = 32°23'13.42" (32.387061°)	
LONGITUDE = -103°41'33.65" (-103.692679°)	
NAD 27 (SURFACE HOLE LOCATION)	
LATITUDE = 32°23'12.98" (32.386938°)	
LONGITUDE = -103°41'31.89" (-103.692192°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 505136.40' E: 739095.55'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 505075.94' E: 697913.15'	

NAD 83 (AS-DRILLED KOP)	
LATITUDE = 32°23'05.16" (32.384765°)	
LONGITUDE = -103°41'26.61" (-103.690726°)	
NAD 27 (AS-DRILLED KOP)	
LATITUDE = 32°23'04.71" (32.384642°)	
LONGITUDE = -103°41'24.86" (-103.690238°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 504304.95' E: 739703.68'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 504244.51' E: 698521.25'	

NAD 83 (AS-DRILLED FTP)	
LATITUDE = 32°23'07.21" (32.385335°)	
LONGITUDE = -103°41'24.72" (-103.690199°)	
NAD 27 (AS-DRILLED FTP)	
LATITUDE = 32°23'06.76" (32.385212°)	
LONGITUDE = -103°41'22.96" (-103.689712°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 504513.11' E: 739864.89'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 504452.67' E: 698682.47'	

NAD 83 (AS-DRILLED LEASE CROSSING)	
LATITUDE = 32°23'56.02" (32.398896°)	
LONGITUDE = -103°41'23.96" (-103.689988°)	
NAD 27 (AS-DRILLED LEASE CROSSING)	
LATITUDE = 32°23'55.58" (32.398773°)	
LONGITUDE = -103°41'22.20" (-103.689500°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 509446.96' E: 739900.39'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 509386.38' E: 698718.10'	

NAD 83 (AS-DRILLED LTP)	
LATITUDE = 32°24'46.44" (32.412899°)	
LONGITUDE = -103°41'23.86" (-103.689960°)	
NAD 27 (AS-DRILLED LTP)	
LATITUDE = 32°24'46.00" (32.412776°)	
LONGITUDE = -103°41'22.10" (-103.689471°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 514541.51' E: 739878.48'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 514480.79' E: 698696.33'	

NAD 83 (AS-DRILLED BHL)	
LATITUDE = 32°24'47.68" (32.413245°)	
LONGITUDE = -103°41'23.90" (-103.689973°)	
NAD 27 (AS-DRILLED BHL)	
LATITUDE = 32°24'47.24" (32.413123°)	
LONGITUDE = -103°41'22.14" (-103.689485°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 514667.38' E: 739873.58'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 514606.66' E: 698691.44'	

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°30'51"W	2641.06'
L2	S89°37'22"W	2642.53'
L3	N00°10'37"W	2644.80'
L4	N00°10'34"W	2639.05'
L5	S89°38'44"W	2643.24'
L6	S89°42'05"W	2640.91'
L7	N00°09'34"W	2638.30'
L8	N00°10'50"W	2635.88'
L9	N00°10'15"W	2640.53'
L10	N00°09'25"W	2641.42'
L11	S89°39'10"W	2641.57'
L12	S89°38'35"W	2643.34'
L13	N00°09'21"W	5284.30'

NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
- Colored areas within section lines represent oil & gas leases.
- As-Drilled well head has not been field verified.
- Wellbore data provided by Oxy USA Inc.





OXY



Borehole:				Well:				Field:				Structure:							
Dr Pi Fed Unit 17-8 DA 74H				Dr Pi Fed Unit 17-8 DA 74H				NM Lea County (NAD 83)				OXY Dr Pi Fed Unit 17-8 DA PAD							
Gravity & Magnetic Parameters								Surface Location				NAD83 New Mexico State Plane, Eastern Zone, US Feet				Miscellaneous			
Model: IFR1		Dip: 60.072°		Date: 26-Apr-2024				Lat: N 32 23 13.42		Northing: 505136.4RUS		Grid Conv: 0.3432°		Slot: Dr Pi Fed Unit 17-8 DA 74H		TVD Ref: RKB (3705.400 ft above MSL)			
MagDec: 6.538°		FS: 47592.1nT		Gravity FS: 998.453mgn (9.80665 Based)				Lon: W 103 41 33.65		Easting: 739095.55RUS		Scale Fact: 0.99995388		Plan: Oxy Dr Pi Fed Unit 17-8 DA 74H Rev4 AR 01May24					

Critical Points								
Comments	Survey MD(ft)	Inclination(deg)	Azimuth(deg)	TVD(ft)	VS(ft)	NS(ft)	EW(ft)	Sub-Sea TVD DLS(°/100ft)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,705.40
SHL	26.00	0.00	0.00	26.00	0.00	0.00	0.00	-3,679.40
First 3rd Party Survey	132.00	0.22	261.78	132.00	-0.05	-0.03	-0.20	-3,573.40
Last 3rd Party Survey	1,040.00	0.61	355.58	1,039.98	0.43	0.75	-3.91	-2,665.42
First SLB Survey	1,144.00	1.07	351.97	1,143.97	1.92	2.26	-4.09	-2,561.43
Actual KOP	9,300.00	9.65	127.62	9,210.74	-779.65	-831.50	608.16	5,505.34
1st Bone Spring Intersection	9,833.13	25.82	26.56	9,720.00	-700.19	-759.60	704.72	6,014.60
Enter Lateral Window	10,193.30	69.44	12.26	9,955.40	-452.42	-518.62	798.43	6,250.00
Section 17-8 Line Cross	15,037.50	89.38	359.75	10,000.44	4,361.74	4,310.81	804.88	6,295.04
LTP / 100ft FNL	20,225.24	88.52	357.86	9,992.93	9,525.65	9,493.71	779.47	6,287.53
Final Survey	20,232.00	88.59	357.88	9,993.10	9,532.36	9,500.47	779.22	6,287.70
Projection to Total Depth	20,263.00	88.59	357.88	9,993.86	9,563.14	9,531.44	778.07	6,288.46





Oxy Dr Pi Fed Unit 17-8 DA 74H MWD+IFRI Surveys to 20263ft Survey

Geodetic Report Definitive Survey



Report Date: May 22, 2024 - 06:57 PM (UTC 0)
Client: OXY
Field: NM Lea County (NAD 83)
Structure / Slot: OXY Dr Pi Fed Unit 17-8 DA PAD / Dr Pi Fed Unit 17-8 DA 74H
Well: Dr Pi Fed Unit 17-8 DA 74H
Borehole: Dr Pi Fed Unit 17-8 DA 74H
UBH / API / JobNumber: Unknown / Unknown / Unknown
Survey Name / Version: Oxy Dr Pi Fed Unit 17-8 DA 74H MWD+IFRI Surveys to 20263ft / 2
Survey Date: April 25, 2024
Tort / AHD / DDI / ERD Ratio: 307.372' +/- 1542.872 ft / 6.856 / 1.152
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32°23'13.41864", W 103°41'33.64561"
Location Grid N/E Y/X: N 505136.400 RUS , E 739095.550 RUS
CRS Grid Convergence Angle: 0.343°
Grid Scale Factor: 0.99995388(Applied)
Engine Version: 2024.2.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 4.634 °(Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3705.400 ft above MSL
Seabed / Ground Elevation: 3679.400 ft above MSL
Magnetic Declination: 6.538°
Total Gravity Field Strength: 998.4525mgn (8.80665 Bases)
Gravity Model: GARM
Total Magnetic Field Strength: 47592.1 nT
Magnetic Dip Angle: 60.072°
Declination Date: April 26, 2024
Magnetic Declination Model: IFR1
North Reference: 6.195°
Total Corr Mag
Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (ft/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S °'")	Longitude (E/W °'")	Closure (ft)	Closure Azimuth (°)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3.705.40	0.00	505,136.40	739,095.55	N 32°23'13.42"	W 103°41'33.65"	0.00	0.00
SHL	26.00	0.00	0.00	26.00	0.00	0.00	0.00	-3.679.40	0.00	505,136.40	739,095.55	N 32°23'13.42"	W 103°41'33.65"	0.00	0.00
First 3rd Party Survey	132.00	0.22	261.78	132.00	-0.05	-0.03	-0.20	-3.573.40	0.21	505,136.37	739,095.35	N 32°23'13.42"	W 103°41'33.65"	0.20	261.78
	222.00	0.40	222.81	222.00	-0.33	-0.28	-0.59	-3.483.40	0.30	505,136.12	739,094.96	N 32°23'13.42"	W 103°41'33.65"	0.65	244.12
	280.00	0.42	222.51	280.00	-0.66	-0.59	-0.87	-3.425.40	0.03	505,135.81	739,094.68	N 32°23'13.41"	W 103°41'33.66"	1.05	235.79
	411.00	0.48	236.47	410.99	-1.38	-1.25	-1.65	-3.294.41	0.10	505,135.15	739,093.90	N 32°23'13.41"	W 103°41'33.66"	2.07	232.91
	497.00	0.39	254.36	496.99	-1.70	-1.52	-2.23	-3.208.41	0.19	505,134.88	739,093.32	N 32°23'13.40"	W 103°41'33.67"	2.70	235.66
	585.00	0.19	290.97	584.99	-1.76	-1.55	-2.66	-3.120.41	0.30	505,134.85	739,092.89	N 32°23'13.40"	W 103°41'33.68"	3.08	239.68
	672.00	0.40	301.18	671.99	-1.59	-1.34	-3.05	-3.033.41	0.25	505,135.06	739,092.50	N 32°23'13.41"	W 103°41'33.68"	3.33	246.22
	759.00	0.23	325.38	758.99	-1.32	-1.04	-3.41	-2.946.41	0.24	505,135.36	739,092.14	N 32°23'13.41"	W 103°41'33.69"	3.57	252.59
	845.00	0.33	357.20	844.99	-0.94	-0.65	-3.52	-2.860.41	0.21	505,135.75	739,092.03	N 32°23'13.41"	W 103°41'33.69"	3.58	259.48
	931.00	0.43	330.98	930.98	-0.42	-0.12	-3.69	-2.774.42	0.23	505,136.28	739,091.86	N 32°23'13.42"	W 103°41'33.69"	3.69	268.09
	1,017.00	0.49	352.78	1,016.98	0.21	0.53	-3.89	-2.688.42	0.21	505,136.93	739,091.67	N 32°23'13.42"	W 103°41'33.69"	3.92	277.71
	1,040.00	0.61	355.58	1,039.98	0.43	0.75	-3.91	-2.665.42	0.53	505,137.15	739,091.64	N 32°23'13.43"	W 103°41'33.69"	3.98	280.81
Last 3rd Party Survey	1,144.00	1.07	351.97	1,143.97	1.92	2.26	-4.09	-2.561.43	0.45	505,138.66	739,091.47	N 32°23'13.44"	W 103°41'33.69"	4.67	298.94
First SLB Survey	1,239.00	1.68	155.63	1,238.96	1.57	1.87	-3.63	-2.466.44	2.87	505,138.27	739,091.92	N 32°23'13.44"	W 103°41'33.69"	4.09	297.21
	1,334.00	1.68	154.56	1,333.92	-0.80	-0.60	-2.49	-2.371.48	0.09	505,135.80	739,093.06	N 32°23'13.41"	W 103°41'33.67"	2.56	256.51
	1,428.00	1.73	157.87	1,427.88	-3.20	-3.10	-1.39	-2.277.52	0.17	505,133.30	739,094.16	N 32°23'13.39"	W 103°41'33.66"	3.40	204.20
	1,523.00	1.62	142.81	1,522.84	-5.48	-5.49	-0.04	-2.182.56	0.48	505,130.91	739,095.51	N 32°23'13.36"	W 103°41'33.65"	5.50	180.42
	1,618.00	1.64	139.64	1,617.80	-7.44	-7.60	1.65	-2.087.60	0.10	505,128.80	739,097.20	N 32°23'13.34"	W 103°41'33.63"	7.78	167.74
	1,713.00	1.95	146.84	1,712.75	-9.68	-9.99	3.42	-1.992.65	0.40	505,126.41	739,098.97	N 32°23'13.32"	W 103°41'33.61"	10.56	161.12
	1,807.00	1.81	144.10	1,806.70	-12.07	-12.53	5.16	-1.898.70	0.19	505,123.87	739,100.71	N 32°23'13.29"	W 103°41'33.59"	13.55	157.61
	1,902.00	2.12	144.45	1,901.65	-14.56	-15.18	7.06	-1.803.75	0.33	505,121.22	739,102.61	N 32°23'13.27"	W 103°41'33.56"	16.74	155.04
	2,092.00	2.52	135.93	2,091.49	-20.00	-21.04	12.01	-1.613.91	0.28	505,115.36	739,107.56	N 32°23'13.21"	W 103°41'33.51"	24.22	150.27
	2,187.00	2.50	128.55	2,186.40	-22.53	-23.83	15.08	-1.519.00	0.34	505,112.57	739,110.63	N 32°23'13.18"	W 103°41'33.47"	28.20	147.66
	2,281.00	2.83	127.69	2,280.30	-24.94	-26.52	18.52	-1.425.10	0.35	505,109.88	739,114.07	N 32°23'13.16"	W 103°41'33.43"	32.35	145.07
	2,376.00	3.11	128.92	2,375.17	-27.67	-29.58	22.39	-1.330.23	0.30	505,106.82	739,117.93	N 32°23'13.12"	W 103°41'33.39"	37.09	142.88
	2,470.00	3.23	126.96	2,469.03	-30.52	-32.77	26.49	-1.236.37	0.17	505,103.63	739,122.03	N 32°23'13.09"	W 103°41'33.34"	42.14	141.06
	2,566.00	3.31	122.22	2,564.87	-33.25	-35.88	30.99	-1.140.53	0.29	505,100.53	739,126.54	N 32°23'13.06"	W 103°41'33.29"	47.41	139.18
	2,661.00	3.53	118.49	2,659.70	-35.71	-38.73	35.88	-1.045.70	0.33	505,097.67	739,131.43	N 32°23'13.03"	W 103°41'33.23"	52.80	137.19
	2,756.00	3.87	118.38	2,754.50	-38.18	-41.65	41.27	-950.90	0.36	505,094.75	739,136.82	N 32°23'13.00"	W 103°41'33.17"	58.64	135.26
	2,851.00	4.27	117.18	2,849.26	-40.83	-44.79	47.24	-856.14	0.43	505,091.61	739,142.79	N 32°23'12.97"	W 103°41'33.10"	65.10	133.48
	2,945.00	4.38	112.77	2,943.00	-43.29	-47.78	53.66	-762.40	0.37	505,088.62	739,149.21	N 32°23'12.94"	W 103°41'33.02"	71.85	131.68
	3,040.00	4.83	113.63	3,037.69	-45.78	-50.85	60.64	-667.71	0.50	505,085.55	739,156.19	N 32°23'12.91"	W 103°41'32.94"	79.14	129.86
	3,135.00	3.20	132.24	3,132.46	-48.77	-54.30	66.24	-572.94	0.23	505,082.10	739,161.79	N 32°23'12.88"	W 103°41'32.88"	86.65	129.34
	3,230.00	3.44	134.73	3,227.30	-52.19	-58.05	70.26	-478.10	0.17	505,078.35	739,165.81	N 32°23'12.84"	W 103°41'32.83"	91.14	129.56
	3,325.00	3.60	134.29	3,322.12	-55.89	-62.10	74.46	-383.28	0.18	505,074.30	739,170.01	N 32°23'12.80"	W 103°41'32.78"	96.96	129.83
	3,420.00	3.83	132.27	3,416.92	-59.73	-66.32	78.94	-288.48	0.27	505,070.08	739,174.49	N 32°23'12.76"	W 103°41'32.73"	103.10	130.03
	3,515.00	3.98	129.66	3,511.70	-63.56	-70.56	83.83	-193.70	0.24	505,065.84	739,179.37	N 32°23'12.72"	W 103°41'32.67"	109.57	130.09
	3,610.00	4.11	134.88	3,606.46	-67.65	-75.07	88.78	-98.94	0.41	505,061.34	739,184.32	N 32°23'12.67"	W 103°41'32.62"	116.26	130.22
	3,705.00	4.89	130.73	3,701.17	-72.23	-80.11	94.26	-4.23	0.89	505,056.29	739,189.56	N 32°23'12.62"	W 103°41'32.56"	123.70	130.36
	3,799.00	5.71	124.41	3,794.77	-76.92	-85.37	101.15	89.37	1.07	505,051.04	739,196.70	N 32°23'12.57"	W 103°41'32.47"	132.36	130.16
	3,894.00	6.93	120.48	3,889.19	-81.76	-90.95	109.99	183.79	1.36	505,045.46	739,205.54	N 32°23'12.51"	W 103°41'32.37"	142.72	129.59
	3,989.00	6.46	115.09	3,983.54	-86.13	-96.12	119.77	278.14	0.83	505,040.29	739,215.32	N 32°23'12.46"	W 103°41'32.26"	153.57	128.75
	4,179.00	7.35	115.79	4,172.16	-94.25	-105.94	140.39	466.76	0.47	505,030.47	739,235.94	N 32°23'12.36"	W 103°41'32.02"	175.88	127.04
	4,369.00	8.80	112.94	4,360.27	-103.20	-116.89	164.72	654.87	0.79	505,019.51	739,260.26	N 32°23'12.25"	W 103°41'31.73"	201.98	125.36
	4,454.00	8.80	120.20	4,454.25	-108.35	-123.06	177.14	749.14	0.59	505,018.36	739,272.68	N 32°23'12.19"	W 103°41'31.58"	215.69	124.79
	4,539.00	6.59	126.20	4,548.45	-114.21	-129.78	187.50	843.05	1.41	505,006.63	739,283.04	N 32°23'12.12"	W 103°41'31.47"	228.03	124.69
	4,654.00	6.67	124.03	4,642.78	-119.91	-136.25	196.69	937.38	0.38	505,000.16	739,292.23	N 32°23'12.06"	W 103°41'31.36"	239.27	124.71
	4,749.00	5.73	142.59	4,737.23	-126.14	-143.10	204.15	1,031.83	2.32	504,993.30	739,299.69	N 32°23'11.99"	W 103°41'31.27"	249.31	125.03
	4,844.00	5.56	144.37	4,831.77	-133.18	-150.61	209.71	1,126.37	0.26	504,985.80	739,305.25	N 32°23'11.92"	W 103°41'31.21"	258.19	125.69
	4,939.00	5.69	142.82	4,926.31	-140.20	-158.10	215.24	1,220.91	0.21	504,981.34	739,310.78	N 32°23'11.84"	W 103°41'31.15"	267.07	126.30
	5,034.00	5.80	140.93	5,020.88	-147.18	-165.58	221.11	1,315.45	0.22	504,970.82	739,317.82	N 32°23'11.77"	W 103°41'31.08"	276.04	126.84
	5,129.00	5.92	141.36	5,115.34	-154.22	-173.14	227.19	1,409.94	0.13	504,963.27	739,322.73	N 32°23'11.69"	W 103°41'31.01"	285.64	127.31
	5,223.00	6.04	149.36	5,208.83	-161.78	-181.18	232.74	1,503.43	0.90	504,955.23	739,328.28	N 32°23'11.61"	W 103°41'30.94"	294.95	127.90
	5,319.00	6.26	153.59	5,304.28	-170.39	-190.21	237.64	1,598.88	0.52	504,946.20	739,333.18	N 32°23'11.52"	W 103°41'30.89"	304.39	128.67
	5,413.00	6.33	154.15	5,397.71	-179.25	-199.47	242.18	1,692.31	0.10	504,936.94	739,337.72	N 32°23'11.43"	W 103°41'30.84"	313.75	129.48
	5,508.00	6.13	151.56	5,492.15	-188.01	-208.64	251.68	1,786.75	0.36	504,927.77	739,342.72	N 32°23'11.34"	W 103°41'30.78"	323.23	130.20
	5,603														

Enter Lateral Window	10,193.30	69.44	12.26	9,955.40	-452.42	-518.62	798.43	6,250.00	10.83	504,617.80	739,893.94	N 32°23'8.24"	W 103°41'24.37"	952.08	123.01
	10,208.00	70.96	11.75	9,960.38	-438.71	-505.09	801.30	6,254.98	10.83	504,631.33	739,896.82	N 32°23'8.37"	W 103°41'24.34"	947.21	122.22
10,303.00	82.80	13.45	9,981.91	-347.25	-414.57	821.48	6,276.51	12.58	504,721.45	739,916.99	N 32°23'9.26"	W 103°41'24.10"	930.34	116.80	
10,398.00	89.18	12.54	9,988.55	-253.54	-392.69	842.78	6,293.15	6.78	504,813.74	739,938.29	N 32°23'10.18"	W 103°41'23.87"	903.53	110.95	
10,493.00	88.76	8.11	9,990.26	-159.05	-229.26	859.80	6,284.86	4.68	504,907.16	739,955.31	N 32°23'11.10"	W 103°41'23.64"	889.84	104.93	
10,588.00	89.18	4.66	9,991.97	-64.12	-134.88	870.36	6,286.57	3.66	505,001.53	739,965.87	N 32°23'12.03"	W 103°41'23.51"	880.75	98.81	
10,683.00	90.16	0.56	9,992.51	30.80	-40.00	874.68	6,287.11	4.44	505,096.41	739,970.19	N 32°23'12.97"	W 103°41'23.45"	875.60	92.62	
10,777.00	86.65	358.93	9,995.13	124.40	53.95	874.27	6,289.73	4.12	505,190.35	739,969.78	N 32°23'13.90"	W 103°41'23.45"	875.93	86.47	
10,872.00	86.13	358.42	10,001.11	218.70	148.73	872.08	6,295.71	0.77	505,285.13	739,967.58	N 32°23'14.84"	W 103°41'23.47"	884.67	80.32	
10,967.00	87.63	359.17	10,006.28	313.06	243.57	870.08	6,300.88	1.76	505,379.96	739,965.59	N 32°23'15.78"	W 103°41'23.48"	903.53	74.36	
11,061.00	87.10	359.26	10,010.60	406.54	337.46	868.79	6,305.20	0.57	505,473.84	739,964.30	N 32°23'16.71"	W 103°41'23.49"	932.03	68.77	
11,156.00	86.40	358.66	10,015.99	500.92	432.29	867.07	6,310.59	0.97	505,568.67	739,962.58	N 32°23'17.64"	W 103°41'23.50"	968.86	63.50	
11,250.00	87.35	359.59	10,021.11	594.35	526.14	865.64	6,315.71	1.41	505,662.51	739,961.15	N 32°23'18.57"	W 103°41'23.51"	1,012.99	58.71	
11,345.00	90.42	1.36	10,022.96	689.07	621.10	866.43	6,317.56	3.73	505,757.47	739,961.94	N 32°23'19.51"	W 103°41'23.50"	1,066.05	54.37	
11,440.00	89.72	1.31	10,022.85	783.91	716.07	868.64	6,317.45	0.74	505,852.44	739,964.15	N 32°23'20.45"	W 103°41'23.47"	1,125.74	50.50	
11,534.00	91.57	0.67	10,021.67	877.71	810.05	870.27	6,316.31	2.18	505,946.41	739,965.77	N 32°23'21.38"	W 103°41'23.44"	1,188.92	47.05	
11,629.00	94.04	359.87	10,016.98	972.31	904.92	870.71	6,311.58	2.63	506,041.28	739,966.22	N 32°23'22.32"	W 103°41'23.43"	1,255.80	43.90	
11,674.00	92.16	358.51	10,014.54	1,017.03	949.85	870.08	6,309.14	5.15	506,086.20	739,965.59	N 32°23'22.77"	W 103°41'23.43"	1,288.12	42.49	
11,769.00	92.10	357.56	10,011.01	1,111.34	1,044.73	866.82	6,305.61	1.00	506,181.08	739,962.33	N 32°23'23.70"	W 103°41'23.46"	1,357.51	39.68	
11,863.00	92.46	357.35	10,007.27	1,204.53	1,138.56	862.65	6,301.87	0.44	506,274.90	739,958.16	N 32°23'24.63"	W 103°41'23.51"	1,428.46	37.15	
11,958.00	90.23	356.67	10,005.04	1,298.66	1,233.40	857.70	6,299.64	2.45	506,369.74	739,953.21	N 32°23'25.57"	W 103°41'23.56"	1,502.30	34.81	
12,053.00	89.61	357.78	10,005.17	1,392.86	1,328.28	853.10	6,299.77	1.34	506,464.62	739,948.61	N 32°23'26.51"	W 103°41'23.60"	1,578.64	32.71	
12,147.00	89.58	359.49	10,005.84	1,486.34	1,422.25	850.66	6,300.44	1.82	506,558.58	739,946.37	N 32°23'27.44"	W 103°41'23.62"	1,657.34	30.89	
12,236.00	89.39	0.08	10,007.54	1,674.65	1,611.24	850.15	6,302.14	0.33	506,747.56	739,945.66	N 32°23'29.31"	W 103°41'23.62"	1,821.77	27.82	
12,256.00	89.91	0.45	10,008.70	1,864.10	1,801.23	851.03	6,303.30	0.34	506,937.55	739,946.54	N 32°23'31.19"	W 103°41'23.60"	1,992.16	25.29	
12,621.00	88.51	0.24	10,009.18	1,958.83	1,896.23	851.60	6,303.78	0.48	507,032.54	739,947.11	N 32°23'32.13"	W 103°41'23.58"	2,078.68	24.18	
12,716.00	88.30	359.02	10,010.99	2,053.45	1,991.21	850.99	6,305.59	1.81	507,127.51	739,946.50	N 32°23'33.07"	W 103°41'23.58"	2,165.43	23.14	
12,811.00	88.41	359.65	10,013.72	2,147.92	2,086.15	849.06	6,308.32	0.41	507,222.45	739,944.57	N 32°23'34.01"	W 103°41'23.60"	2,252.31	22.15	
12,906.00	88.54	357.17	10,016.17	2,242.24	2,181.05	845.59	6,310.77	1.58	507,317.35	739,941.10	N 32°23'34.95"	W 103°41'23.62"	2,339.23	21.19	
13,000.00	89.70	355.38	10,017.53	2,335.22	2,274.84	839.49	6,312.13	2.21	507,411.13	739,935.00	N 32°23'35.88"	W 103°41'23.70"	2,424.80	20.26	
13,095.00	90.42	354.05	10,017.43	2,428.80	2,369.43	830.74	6,312.03	1.59	507,505.72	739,926.25	N 32°23'36.81"	W 103°41'23.79"	2,510.84	19.32	
13,190.00	91.26	355.20	10,016.04	2,522.34	2,464.00	821.84	6,310.64	1.50	507,600.28	739,917.35	N 32°23'37.75"	W 103°41'23.89"	2,597.45	18.45	
13,285.00	91.00	356.43	10,014.16	2,568.73	2,558.73	814.91	6,308.76	1.32	507,695.01	739,910.42	N 32°23'38.69"	W 103°41'23.96"	2,685.36	17.67	
13,380.00	91.59	357.50	10,012.02	2,710.32	2,653.57	809.88	6,306.62	1.29	507,789.84	739,905.39	N 32°23'39.63"	W 103°41'24.02"	2,774.41	16.97	
13,475.00	90.76	358.00	10,010.07	2,804.62	2,748.47	806.15	6,304.67	1.02	507,884.74	739,901.66	N 32°23'40.57"	W 103°41'24.05"	2,864.26	16.35	
13,564.00	90.20	0.59	10,008.48	2,902.77	2,907.44	803.83	6,303.08	1.40	508,073.07	739,899.34	N 32°23'42.44"	W 103°41'24.07"	3,045.43	15.30	
13,654.00	89.66	0.62	10,008.72	3,182.30	3,127.43	805.83	6,303.32	0.28	508,263.67	739,901.34	N 32°23'44.32"	W 103°41'24.03"	3,229.58	14.45	
13,749.00	89.75	0.63	10,009.21	3,277.07	3,222.42	806.87	6,303.81	0.10	508,358.66	739,902.38	N 32°23'45.26"	W 103°41'24.01"	3,321.90	14.06	
14,044.00	91.16	0.12	10,008.45	3,371.80	3,317.41	807.49	6,303.05	1.58	508,453.65	739,903.00	N 32°23'46.20"	W 103°41'24.00"	3,414.27	13.68	
14,139.00	91.15	359.38	10,006.54	3,466.44	3,412.39	807.08	6,301.14	0.78	508,548.63	739,902.59	N 32°23'47.14"	W 103°41'23.99"	3,506.53	13.31	
14,238.00	90.91	10,003.30	3,554.70	3,501.31	805.56	6,297.90	0.35	508,737.58	739,901.47	N 32°23'48.01"	W 103°41'23.98"	3,600.44	12.61		
14,423.00	91.02	0.25	10,001.79	3,749.39	3,696.35	806.11	6,296.39	0.39	508,832.57	739,902.62	N 32°23'49.94"	W 103°41'23.95"	3,783.22	12.30	
14,519.00	91.16	0.11	9,999.96	3,845.08	3,792.33	806.41	6,294.56	0.21	508,928.55	739,901.92	N 32°23'50.89"	W 103°41'23.98"	3,877.12	12.00	
14,613.00	90.25	359.66	9,998.80	3,938.75	3,886.32	806.22	6,293.40	1.08	509,022.53	739,901.74	N 32°23'51.82"	W 103°41'23.97"	3,969.06	11.72	
14,708.00	90.18	359.88	9,998.45	4,033.40	3,981.32	805.84	6,293.05	0.24	509,117.53	739,901.35	N 32°23'52.76"	W 103°41'23.97"	4,062.05	11.44	
14,803.00	89.64	0.03	9,998.60	4,128.09	4,076.32	805.77	6,293.20	0.59	509,212.52	739,901.28	N 32°23'53.70"	W 103°41'23.96"	4,155.19	11.18	
14,898.00	89.70	359.69	9,999.14	4,222.76	4,171.31	805.56	6,293.74	0.36	509,307.51	739,900.45	N 32°23'54.61"	W 103°41'23.98"	4,248.38	10.94	
14,993.00	89.34	359.75	9,999.94	4,317.40	4,266.31	805.07	6,294.54	0.38	509,402.51	739,900.58	N 32°23'55.58"	W 103°41'23.98"	4,341.61	10.69	
15,037.50	88.38	359.75	10,000.44	4,361.74	4,310.81	804.88	6,295.04	0.09	509,447.00	739,900.39	N 32°23'56.02"	W 103°41'23.96"	4,385.30	10.58	
15,183.00	89.52	359.75	10,001.83	4,506.70	4,456.30	804.24	6,296.43	0.09	509,592.48	739,899.75	N 32°23'57.46"	W 103°41'23.95"	4,528.29	10.23	
15,373.00	91.90	0.26	9,999.48	4,696.06	4,646.27	804.26	6,294.08	1.28	509,782.45	739,899.77	N 32°23'59.34"	W 103°41'23.94"	4,711.36	9.82	
15,468.00	90.61	0.36	9,997.39	4,790.76	4,741.24	804.77	6,291.99	1.36	509,877.42	739,900.29	N 32°24'0.28"	W 103°41'23.93"	4,809.06	9.63	
15,558.00	92.04	359.70	9,993.00	4,980.09	4,931.19	804.87	6,287.60	0.83	510,067.35	739,900.38	N 32°24'02.16"	W 103°41'23.91"	4,996.44	9.27	
15,753.00	92.70	359.82	9,989.07	5,074.67	5,024.53	804.56	6,283.67	0.73	510,162.26	739,900.07	N 32°24'03.10"	W 103°41'23.91"	5,089.09	9.09	
15,847.00	92.69	358.84	9,984.65	5,168.17	5,119.99	803.54	6,279.25	1.15	510,256.15	739,899.05	N 32°24'04.03"	W 103°41'23.92"	5,182.67	8.92	
15,943.00	92.05	357.46	9,980.68	5,263.48	5,215.86	800.45	6,275.28	1.58	510,352.01	739,895.96	N 32°24'04.98"	W 103°41'23.95"	5,276.92	8.72	
16,038.00	88.75	356.95	9,980.02	5,357.66	5,310.73	795.81	6,274.62	3.51	510,446.87	739,891.33	N 32°24'05.92"	W 103°41'23.99"	5,370.03	8.52	
16,133.00	88.57	359.08	9,982.24	5,452.00	5,405.64	792.52	6,276.84	2.25	510,541.78	739,888.04	N 32°24'06.86"	W 103°41'24.02"	5,463.43	8.34	
16,228.00	88.56	3.02	9,984.62	5,546.76	5,500.58	794.26	6,279.22	4.15	510,636.71	739,889.78	N 32°24'07.80"	W 103°41'24.00"	5,557.63	8.22	
16,323.00	89.57	357.64	9,986.17	5,641.45	5,595.53	794.81	6,280.77	2.76	510,731.66	739,890.32	N 32°24'08.74"	W 103°41'24.02"	5,651.69	8.08	
16,418.00	88.81	357.68	9,986.69	5,735.74	5,690.45	790.93	6,281.29	0.26	510,826.57	739,886.44	N 32°24'09.68"	W 103°41'24.02"	5,745.15	7.91	
16,513.00	90.66	0.66	9,986.30	5,830.30	5,785.42	789.56	6,280.90	3.26	510,921.55	739,885.07	N 32°24'10.62"	W			

C-105 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
--	---	----------------------

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

Section 1 - Operator and Well Information

Submittal Type: ☒ New Well ☐ Workover ☐ Deepening ☐ Plugback ☐ Different Reservoir ☐ C-144 Closure Attachment ☐ Other	
Operator Name: OXY USA INC	OGRID: 16696
Property Name and Well Number: DR PI UNIT 174H	Property Code:
Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal	API Number: 30-0 25-48954
Pool Name: Bilbrey Basin; Bone Spring, South	Pool Code: 97366

Section 2 – Well Location

	UI or lot no.	Section	Township	Range	Lot Id	Feet from	N/S Line	Feet from	E/W Line	County
SHL:	O	17	22S	32E		979	S	1375	E	LEA
BHL	A	8	22S	32E		62	N	528	E	LEA

Section 3 – Completion Information

Date T.D. Reached 05/20/24	Total Measured Depth of Well 20263'MD	Acid Volume (bbls)	☒ Directional Survey Submitted ☐ Deviation Survey Submitted
Date Rig Released 05/22/24	Plug-Back Measured Depth 20219'MD	Completion Fluid Used (bbls) 359463	Were Logs Ran (Y/N) Y
Completion Date 07/06/24	Perforations (MD and TVD) 10069'-20137'MD/9899-9992'TVD	Completion Proppant Used (lbs) 25256557#	List Type of Logs Ran if applicable: CBL

Section 4 – Action IDs for Submissions and Order Numbers

Surface Casing Action ID: 362448	UIC Permit/Order (UIC wells only) ☐ Yes ☒ No, Order No.
Intermediate 1 Casing Action ID: 362448	NOI Recomplete Action ID (if applicable):
Intermediate 2 Casing Action ID: NA	NOI Plugback Action ID (if applicable):
Production Casing Action ID: 362448	Cement Squeeze Action ID (if applicable):
Tubing Action ID: 382991	All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No
Liner 1 Action ID: NA	Casing was installed prior to Action ID system (Y/N): N

Section 5 – Test Data

Date First Production 07/13/24	Production Method Gas lift	Well Status Producing	Gas – Oil Ratio 1058
Date of Test 08/07/24	Choke Size 83	Flowing Tubing Pressure	Casing Pressure 298
24 hr Oil (bbls) 2549	24 hr Gas (MCF) 2696	24 hr Water (bbls) 3542	Oil Gravity - API
Disposition of Gas: sold			

Section 6 – Pits


☐ A temporary pit was used at the well. If so, attach a plat with the location of the temporary pit.
☒ A Closed Loop System was used.
☐ If an on-site burial was used at the well, report the exact location of the on-site burial: LAT: _____ LONG: _____

Section 7 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Jana Mendiola	
Title Regulatory Advisor	Date 09/19/24

South Formations				North Formations			
Formation/Zone	MD	TVD	W/O/G	Formation/Zone	MD	TVD	W/O/G
T. Anhy	868	868	W	T. San Jose			
T. Salt	1226	1226		T. Nacimiento			
B. Salt	3313	3311		T. Ojo Alamo			
T. Yates				T. Kirtland			
T. 7 Rivers				T. Fruitland			
T. Queen				T. Pictured Cliffs			
T. Grayburg				T. Lewis Shale			
T. San Andres				T. Chacra			
T. Glorieta				T. Cliff House			
T. Yeso				T. Menefee			
T. Paddock				T. Point Lookout			
T. Blinebry				T. Mancos			
T.Tubb				T. Gallup			
T. Drinkard				T. Greenhorn			
T. Abo				T. Graneros			
T. Wolfcamp				T. Dakota			
T. Penn				T. Morrison			
T. Cisco				T. Bluff			
T. Canyon				T.Todilto			
T. Strawn				T. Entrada			
T. Atoka				T. Wingate			
T. Morrow				T. Chinle			
T. Barnett Shale				T. Permian			
T. Miss				T. Penn A"			
T. Woodford Shale				T. Penn. "B"			
T. Devonian				T. Penn. "C"			
T. Silurian				T. Penn. "D"			
T. Fusselman				T. Leadville			
T. Montoya				T. Madison			
T. Simpson				T. Elbert			
T. McKee				T. McCracken			
T. Waddell				T. Ignacio Otzte			
T. Connel				T. Granite			
T. Ellenburger				T. Hermosa			
T. Gr. Wash				T. De Chelly			
T. Delaware Sand				T. Pinkerton			
T. Lamar Lime	4766	4754	o/g				
T. Bell Canyon	4807	4795	o/g				
T. Cherry Canyon	5673	5657	o/g				
T. Brushy Canyon	6990	6954	o/g				
T. Bone Springs	8677	8597	o/g				
T. 1st BS Sand	9765	9656	o/g				
T. 2nd BS Carbonate							
T. 2nd BS Sand							
T. 3rd BS Carbonate							
T. 3rd BS Sand							

OXY USA Inc.
DR PI UNIT 174H
API No. 30-025-48954



Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 422114

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 422114
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.
☒	I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 422114

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 422114
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 within 10 days of BLM Approval.	8/12/2025