



U.S. Department of the Interior
Bureau of Land Management

Application for Permit to Drill

APD Package Report

Date Printed:

APD ID:	Well Status:
APD Received Date:	Well Name:
Operator:	Well Number:

APD Package Report Contents

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
 - Operator Letter of Designation: 2 file(s)
 - Well Plat: 2 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 1 file(s)
 - Blowout Prevention BOP Diagram Attachment: 4 file(s)
 - Casing Design Assumptions and Worksheet(s): 8 file(s)
 - Hydrogen sulfide drilling operations plan: 2 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 4 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 4 file(s)
 - New Road Map: 2 file(s)
 - Attach Well map: 2 file(s)
 - Production Facilities map: 2 file(s)
 - Water source and transportation map: 2 file(s)
 - Well Site Layout Diagram: 6 file(s)
 - Recontouring attachment: 2 file(s)
- PWD Report
- PWD Attachments
 - None
- Bond Report
- Bond Attachments

-- None

Form 3160-3
(October 2024)FORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2027UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☐ DRILL ☐ REENTER		5. Lease Serial No.
1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: ☐ Hydraulic Fracturing ☐ Single Zone ☐ Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator		8. Lease Name and Well No.
3a. Address		9. API Well No. 30-015-58058
3b. Phone No. (include area code)		10. Field and Pool, or Exploratory
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		11. Sec., T. R. M. or Blk. and Survey or Area
14. Distance in miles and direction from nearest town or post office*		12. County or Parish
		13. State
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No of acres in lease	17. Spacing Unit dedicated to this well
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. in file
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will start*	23. Estimated duration
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature	Name (Printed/Typed)	Date
Title		
Approved by (Signature)	Name (Printed/Typed)	Date
Title		
Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)



Approval Date: 09/22/2025

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

0. SHL: SESE / 1275 FSL / 155 FEL / TWSP: 24S / RANGE: 26E / SECTION: 33 / LAT: 32.1699801 / LONG: -104.2898257 (TVD: 0 feet, MD: 0 feet)

PPP: NESW / 1981 FSL / 1326 FWL / TWSP: 24S / RANGE: 26E / SECTION: 34 / LAT: 32.1719088 / LONG: -104.285024 (TVD: 8444 feet, MD: 9535 feet)

PPP: NWSW / 1980 FSL / 330 FWL / TWSP: 24S / RANGE: 26E / SECTION: 34 / LAT: 32.1719142 / LONG: -104.2882436 (TVD: 8444 feet, MD: 8829 feet)

PPP: NWSE / 1976 FSL / 2681 FEL / TWSP: 24S / RANGE: 26E / SECTION: 35 / LAT: 32.1718706 / LONG: -104.2636404 (TVD: 8444 feet, MD: 16151 feet)

BHL: NESE / 1980 FSL / 330 FEL / TWSP: 24S / RANGE: 26E / SECTION: 35 / LAT: 32.1718564 / LONG: -104.2561786 (TVD: 8444 feet, MD: 18460 feet)

BLM Point of Contact

Name: MARIAH HUGHES

Title: Land Law Examiner

Phone: (575) 234-5972

Email: MHUGHES@BLM.GOV

CONFIDENTIAL

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	3R Operating LLC
LEASE NO.:	NMNM19593
COUNTY:	Eddy County, New Mexico

Wells:

McMuffin North Pad

McMuffin 34 35 Fed Com 701H

Surface Hole Location: 605 feet FNL and 155 feet FEL, Section 33, T. 24 S., R. 26 E.

Bottom Hole Location: 660 feet FNL and 330 feet FEL, Section 35, T. 24 S, R 26 E.

McMuffin 34 35 Fed Com 702H

Surface Hole Location: 635 feet FNL and 155 feet FEL, Section 33, T. 24 S., R. 26 E.

Bottom Hole Location: 1980 feet FNL and 330 feet FEL, Section 35, T. 24 S, R 26 E.

McMuffin South Pad

McMuffin 34 35 Fed Com 703H

Surface Hole Location: 1275 feet FSL and 155 feet FEL, Section 33, T. 26 S., R. 27 E.

Bottom Hole Location: 1980 feet FSL and 330 feet FEL, Section 35, T. 24 S, R 26 E.

McMuffin 34 35 Fed Com 704H

Surface Hole Location: 1245 feet FSL and 155 feet FEL, Section 33, T. 24 S., R. 26 E.

Bottom Hole Location: 660 feet FSL and 330 feet FEL, Section 35, T. 24 S, R 26 E.

TABLE OF CONTENTS

1. SPECIAL REQUIREMENTS 3

1.1. CAVE/KARST 3

1.1.1. General Construction..... 3

1.1.2. Pad Construction..... 3

1.1.3. Road Construction 3

1.1.4. Residual and Cumulative Mitigation 4

1.1.5. Plugging and Abandonment Mitigation..... 4

WILDLIFE 4

2.3.2. Texas Hornshell Mussel 4

1. SPECIAL REQUIREMENTS

1.1. CAVE/KARST

1.1.1. General Construction

- No blasting
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction, and no additional construction shall occur until clearance has been issued by the Authorized Officer.
- All linear surface disturbance activities will avoid sinkholes and other karst features to lessen the possibility of encountering near surface voids during construction, minimize changes to runoff, and prevent untimely leaks and spills from entering the karst drainage system.
- This is a sensitive area and all spills or leaks will be reported to the BLM immediately for their immediate and proper treatment, as defined in NTL 3A for Major Undesirable Events.

1.1.2. Pad Construction

- The pad will be constructed and leveled by adding the necessary fill and caliche. No blasting will be used for any construction or leveling activities.
- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised (i.e. an access road crossing the berm cannot be lower than the berm height).
- Following a rain event, all fluids will be vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

1.1.3. Road Construction

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

1.1.4. Residual and Cumulative Mitigation

The operator will perform annual pressure monitoring on all casing annuli. If the test results indicate a casing failure has occurred, contact a BLM Engineer immediately, and take remedial action to correct the problem.

1.1.5. Plugging and Abandonment Mitigation

Upon well abandonment in high cave karst areas, additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

WILDLIFE

2.3.2. Texas Hornshell Mussel

- Implement erosion control measures in accordance with the Reasonable and Prudent Practices for Stabilization ("RAPPS")
- Comply with SPCC requirements in accordance with 40 CFR Part 112;
- Comply with the United States Army Corp of Engineers (USACE) Nationwide 12 General Permit, where applicable;
- Utilize technologies (like underground borings for pipelines), where feasible;
- Educate personnel, agents, contractors, and subcontractors about the requirements of conservation measures, COAs, Stips and provide direction in accordance with the Permit.

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME: 3R OPERATING LLC
WELL NAME & NO.: MCMUFFIN 34 35 FED COM #703H
LOCATION: 33 – 24S – 26E, SESE (1275 FSL, 155 FEL)
COUNTY: Eddy County, New Mexico ▼

COA

H ₂ S	☒ No	☐ Yes
Potash / WIPP	☒ None ☐ Secretary ☐ R-111-Q ☐ Open Annulus Choose an option (including blank option.)	☐ WIPP
Cave / Karst	☐ Low ☐ Medium ☒ High ☐ Critical	
Wellhead	☐ Conventional ☒ Multibowl ☐ Both ☐ Diverter	
Cementing	☐ Primary Squeeze ☐ Cont. Squeeze ☐ EchoMeter ☐ DV Tool	
Special Req	☐ Capitan Reef ☐ Water Disposal ☒ COM ☐ Unit	
Waste Prev.	☐ Self-Certification ☒ Waste Min. Plan ☐ APD Submitted prior to 06/10/2024	
Additional Language	☒ Flex Hose ☐ Casing Clearance ☐ Pilot Hole ☐ Break Testing ☐ Four-String ☐ Offline Cementing ☐ Fluid-Filled	

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet 43 CFR 3176 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8 inch** surface casing shall be set at approximately **480 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite, above the salt, and below usable fresh water)** and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 pounds compressive strength**, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8 inch** intermediate casing shall be set at approximately **1,745 feet** is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, Capitan Reef, or potash.**
- ❖ **In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.**
3. The minimum required fill of cement behind the **5-1/2 inch** production casing shall be set at approximately **18,460 feet** is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, Capitan Reef, or potash.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)**Communitization Agreement**

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in 43 CFR 3171 and 3172.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Contact Eddy County Petroleum Engineering Inspection Staff:

Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220;
BLM_NM_CFO_DrillingNotifications@BLM.GOV; (575) 361-2822

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - i. Notify the BLM when moving in and removing the Spudder Rig.
 - ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the doghouse or stairway area.
3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hard band drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - iii. Manufacturer representative shall install the test plug for the initial BOP test.
 - iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
 - v. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive

strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- iv. The test shall be run on a 5000-psi chart for a 2-3M BOP/BOP, on a 10000-psi chart for a 5M BOP/BOPE and on a 15000-psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one-hour chart. A circular chart shall have a maximum 2-hour clock. If a twelve hour or twenty-four-hour chart is used, tester shall make a notation that it is run with a two-hour clock.
- v. The results of the test shall be reported to the appropriate BLM office.
- vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- vii. The BOP/BOPE test shall include a low-pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

YJ (04/18/2025)



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

09/23/2025

Operator

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: KALEN MELTON

Signed on: 12/18/2024

Title: PERMITTING SPECIALIST

Street Address: 3909 N CLASSEN BLVD

City: OKLAHOMA CITY

State: OK

Zip: 73118

Phone: (405)286-9326

Email address: KMELTON@REAGANSMITH.COM

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data

09/23/2025

APD ID: 10400102744

Submission Date: 12/20/2024

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Section 1 - General

APD ID: 10400102744

Tie to previous NOS? N

Submission Date: 12/20/2024

BLM Office: Carlsbad

User: KALEN MELTON

Title: PERMITTING SPECIALIST

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM19593

Lease Acres:

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? Y

Permitting Agent? YES

APD Operator: 3R OPERATING LLC

Operator letter of

NM_DOA_Designation_of_Agent_20241119081946.pdf

NM_DOA_Designation_of_Agent_20250910135357.pdf

Operator Info

Operator Organization Name: 3R OPERATING LLC

Operator Address: 20405 STATE HIGHWAY 249 STE 820

Zip: 77070

Operator PO Box:

Operator City: HOUSTON

State: TX

Operator Phone: (432)413-4148

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PURPLE SAGE

Pool Name: WOLFCAMP

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,OIL

Is the proposed well in a Helium production area? N

Use Existing Well Pad? N

New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:

Number: 703H, 704H

McMuffin South Pad

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: CONVENTIONAL GAS WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 5 Miles

Distance to nearest well: 30 FT

Distance to lease line: 155 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: McMUFFIN_34_35_FED_COM_703H_20241218141525.pdf

McMUFFIN_34_35_FED_COM_703H_20250916125530.pdf

Well work start Date: 08/01/2025

Duration: 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum: GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	1275	FSL	155	FEL	24S	26E	33	Aliquot SESE	32.1699801	-104.2898257	EDD Y	NEW MEXI CO	NEW MEXI CO	F	FEE	3329			N
KOP Leg #1	1980	FSL	230	FWL	24S	26E	34	Aliquot NWSW	32.1719149	-104.2885667	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 19593	-4542	7929	7871	Y

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-1	1980	FSL	330	FWL	24S	26E	34	Aliquot NWSW	32.1719142	- 104.2882436	EDD Y	NEW MEXICO	NEW MEXICO	F	NMNM 19593	- 5115	8829	8444	Y
PPP Leg #1-2	1981	FSL	1326	FWL	24S	26E	34	Aliquot NESW	32.1719088	- 104.285024	EDD Y	NEW MEXICO	NEW MEXICO	F	FEE	- 5115	9535	8444	Y
PPP Leg #1-3	1976	FSL	2681	FEL	24S	26E	35	Aliquot NWSE	32.1718706	- 104.2636404	EDD Y	NEW MEXICO	NEW MEXICO	F	NMNM 16625	- 5115	16151	8444	Y
EXIT Leg #1	1980	FSL	330	FEL	24S	26E	35	Aliquot NESE	32.1718564	- 104.2561786	EDD Y	NEW MEXICO	NEW MEXICO	F	NMNM 16625	- 5115	18460	8444	Y
BHL Leg #1	1980	FSL	330	FEL	24S	26E	35	Aliquot NESE	32.1718564	- 104.2561786	EDD Y	NEW MEXICO	NEW MEXICO	F	NMNM 16625	- 5115	18460	8444	Y

November 18, 2024

Bureau of Land Management
Carlsbad Field Office
620 E Greene St, Carlsbad, NM 88220
Attn: Land Law Examiner

Re: 3R Operating, LLC
Designation of Agent
Federal Applications for Permit to Drill
Eddy County, New Mexico

Land Law Examiner:

3R Operating, LLC has contracted with Reagan Smith, Inc. to assist in regulatory compliance associated with the Crystal N, Mongo, Mongo Ridge, McMuffin, Boudin, Delta Rey, and Gamma oil & gas projects. Reagan Smith has the authority to act as 3R Operating, LLC's agent to maintain regulatory compliance for the above-named oil & gas wells. This includes the submittal of Applications for Permit to Drill, Communitization Agreements, Designations of Operator, Sundry Notices, Enforcement Actions including Notices of Incompliance, and any other regulatory documents on behalf of 3R Operating, LLC, in order to maintain regulatory compliance with the Bureau of Land Management.

Sincerely,

A handwritten signature in black ink, reading "Brad Grandstaff", is written over a horizontal line.

Brad Grandstaff
COO
3R Operating, LLC

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	☒ Initial Submittal
			☐ Amended Report
			☐ As Drilled

WELL LOCATION INFORMATION

API Number	Pool Code 98220	Pool Name Purple Sage; Wolfcamp
Property Code	Property Name McMUFFIN 34 35 FED COM	Well Number 703H
OGRID No. 331569	Operator Name 3R OPERATING, LLC	Ground Level Elevation 3328.5
Surface Owner: ☐ State ☒ Fee ☐ Tribal ☐ Federal		Mineral Owner: ☐ State ☒ Fee ☐ Tribal ☒ Federal

Surface Location

UL P	Section 33	Township 24 S	Range 26 E	Lot	Ft. from N/S 1275 SOUTH	Ft. from E/W 155 EAST	Latitude 32.1699801°N	Longitude 104.2898257°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Bottom Hole Location

UL I	Section 35	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 EAST	Latitude 32.1718564°N	Longitude 104.2561786°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Dedicated Acres 640	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
Order Numbers.			Well setbacks are under Common Ownership: ☐ Yes ☐ No	

Offset lease operator(s) notified

Kick Off Point (KOP)

UL L	Section 34	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 230 WEST	Latitude 32.1719149°N	Longitude 104.2885667°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

First Take Point (FTP)

UL L	Section 34	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 WEST	Latitude 32.1719142°N	Longitude 104.2882436°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Last Take Point (LTP)

UL I	Section 35	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 EAST	Latitude 32.1718564°N	Longitude 104.2561786°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Unitized Area or Area of Uniform Interest Y	Spacing Unit Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation:
--	--	-------------------------

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest run leased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order here to fore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Brad Grandstaff 12/18/2024
Signature Date

Brad Grandstaff

Printed Name

bgrandstaff@3ROperating.com

Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



Signature and Seal of Professional Surveyor
FILIMON F. JARAMILLO

Certificate Number

PLS 12797

Date of Survey

OCTOBER 30, 2024

SURVEY NO. 10337

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.

McMUFFIN 34 35 FED COM 703H
EL. = 3328.5

LEGEND

--- SECTION LINE
--- QUARTER LINE
--- LEASE LINE
--- WELL PATH

GEODETTIC COORDINATES

NAD 83 NMSP EAST
SURFACE LOCATION
1275' FSL, 155' FEL
N.=425576.41
E.=554799.41
LAT.=32.1699801°N
LONG.=104.2898257°W

LAST TAKE POINT
1980' FSL, 330' FEL
N.=426264.82
E.=565209.82
LAT.=32.1718564°N
LONG.=104.2561786°W

PPP3
2681' FEL 1976' FSL,
N.=426268.40
E.=562901.07
LAT.=32.1718706°N
LONG.=104.2636404°W

KICK OFF POINT
1980' FSL, 230' FWL
N.=426280.41
E.=555188.68
LAT.=32.1719149°N
LONG.=104.2885667°W


BOTTOM OF HOLE
1980' FSL, 330' FEL
N.=426264.82
E.=565209.82
LAT.=32.1718564°N
LONG.=104.2561786°W

FIRST TAKE POINT
1980' FSL, 330' FWL
N.=426280.20
E.=555288.65
LAT.=32.1719142°N
LONG.=104.2882436°W

PPP2
1981' FSL, 1326' FWL
N.=426278.65
E.=556284.82
LAT.=32.1719088°N
LONG.=104.2850240°W

CORNER COORDINATES TABLE

NAD 83 NMSP EAST
A - N.=429599.02 E.=549648.90
B - N.=429557.13 E.=552313.86
C - N.=429515.24 E.=554978.83
D - N.=429569.97 E.=557627.08
E - N.=429625.16 E.=560293.81
F - N.=429590.39 E.=562915.46
G - N.=429555.61 E.=565537.11
H - N.=426954.45 E.=549639.22
I - N.=426908.12 E.=554962.60
J - N.=427013.46 E.=560212.37
K - N.=426917.28 E.=565539.20
L - N.=424308.86 E.=549630.09
M - N.=424307.30 E.=552290.42
N - N.=424301.41 E.=554946.51
O - N.=424295.83 E.=557601.13
P - N.=424292.44 E.=560241.79
Q - N.=424293.38 E.=562892.51
R - N.=424284.14 E.=565541.41





U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

09/23/2025

APD ID: 10400102744

Submission Date: 12/20/2024

Highlighted data
reflects the most
recent changes

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
16443743	PERMIAN	3329	0	0	SANDSTONE	USEABLE WATER	N
16443744	CASTILE	3304	25	25	ALLUVIUM	USEABLE WATER	N
16443745	LAMAR	1605	1724	1724	LIMESTONE	NONE	N
16443746	DELAWARE	1500	1829	1829	LIMESTONE, SANDSTONE, SHALE	NONE	N
16443747	BONE SPRING	-1905	5234	5274	LIMESTONE	NATURAL GAS, OIL	N
16443748	BONE SPRING 1ST	-2855	6184	6237	SANDSTONE	NATURAL GAS, OIL	N
16443749	BONE SPRING 2ND	-3325	6654	6712	SANDSTONE	NATURAL GAS, OIL	N
16443751	BONE SPRING 3RD	-4675	8004	8064	SANDSTONE	NATURAL GAS, OIL	N
16443753	WOLFCAMP	-5035	8364	8523	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 10000

Equipment: Ten thousand (10M) psi Blind Rams and Pipe Rams and a five thousand (5M) psi Annular Preventer will be installed on all casing. Per 5M system requirements, two (2) chokes will be used with at least one choke being remotely controlled from the rig floor.

Requesting Variance? YES

Variance request: (1) Variance requested to use a flex hose in place of a rigid line connection from BOP to choke manifold. Please see attachment for typical flex hose. (2) Variance requested to use multibowl wellhead. Please see attachment for typical multibowl wellhead.

Testing Procedure: A third party testing company will conduct pressure tests and record prior to drilling out below casing shoes. Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 70 percent of internal yield pressure of casing if BOP stack is not isolated from casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. The Annular Preventer will be tested to 50 percent of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer. In addition, the BOPE will be tested after any repairs to the equipment and prior to drilling out below any casing

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

string. Pipe rams, blind rams, and annular preventer will be activated on each trip and weekly BOP drills will be held with each crew.

Choke Diagram Attachment:

CHOKE_HOSE_M14945_20250916135027.pdf

BOP Diagram Attachment:

BOP_and_Choke_Manifold_20241119145251.pdf

Ridgerunner_Multibowl_20250204134354.pdf

BOP_and_Choke_Manifold_20250910135947.pdf

Ridgerunner_Multibowl_20250910140001.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	480	0	480	3329	2849	480	H-40	48	ST&C	3.59	8.06	DRY	13.98	DRY	23.48
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	1745	0	1745	3347	1584	1745	J-55	36	BUTT	5.18	4.51	DRY	8.98	DRY	10.17
3	PRODUCTION	8.75	5.5	NEW	API	N	0	18460	0	8444	3347	-5115	18460	P-110	20	BUTT	2.63	3	DRY	3.95	DRY	3.8

Casing Attachments

Casing ID: 1StringSURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Drilling_Plan_McMuffin_703H_12_19_24_20241219142508.pdf

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Casing Attachments**

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20241219142514.pdf

Drilling_Plan_McMuffin_703H_12_19_24_20250910140525.pdf

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20250910140529.pdf

Casing ID: 2 **String** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20241219142521.pdf

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20250910140535.pdf

Casing ID: 3 **String** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20241219142713.pdf

McMuffin_34_35_Fed_Com_703H___Casing_Calculator_20250910140545.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	180	140	1.79	13.5	251	100	Class C	4% Gel + 5% Salt +0.2% SA-1 + 0.25

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											pps Pol-E Flake + 0.005gps NOFoam V1A
SURFACE	Tail		180	480	314	1.33	14.8	418	100	Class C	1% calcium chloride + 0.005gps NoFoam V1A
INTERMEDIATE	Lead		0	1245	383	1.53	12.7	586	50	40% Class C + 60% POZ	5% Salt + 1% SMS + 2% CS-9 + 0.1% R-1300 + 0.25pps Pol-E Flake + 0.005gps NoFoam V1A
INTERMEDIATE	Tail		1245	1745	177	1.33	14.8	235	50	Class C	1% calcium chloride + 0.005gps NoFoam V1A
PRODUCTION	Lead		0	7429	647	3.34	10.7	2161	15	100% ProLite	5pps Plexcrete STE + 2% SMS + 0.1% RCKCAS-100 + .85% R-1300 + 0.2% FL-24 + .25pps Pol-E Flake + 0.005gps NoFoam V1A
PRODUCTION	Tail		7429	18460	2081	1.54	13.5	3205	15	50% Class H + 50% B POZ	6% Gell + 5% Slat + .2% SMS + .55% FR-5 + .4% FL-24 + 0.005gps NoFoam V1A

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

Describe what will be on location to control well or mitigate other conditions: Mud weight increases at shoe depths are for pressure control. Mud weight increases in the curve and lateral section of the hole are for hole stability, not pressure control. Mud weight assumptions for casing load designs exceed anticipated maximum mud weight for balanced drilling in all hole sections. Expected mud weights in producing formation will be 0.5 to 1.0 lbs/gal greater than formation pressure (i.e. overbalanced drilling). Sufficient materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: The mud system will run as a closed loop system. PVT system will be in place throughout the well, as well as visual checks.

Circulating Medium Table

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	480	WATER-BASED MUD	8.4	9.2							
480	1745	WATER-BASED MUD	8.4	8.6							
1745	1846 0	OIL-BASED MUD	9.2	9.6							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

The operator will comply with the BLM's logging requirements as stated in the COAs.

List of open and cased hole logs run in the well:

GAMMA RAY LOG, SPONTANEOUS POTENTIAL LOG, MEASUREMENT WHILE DRILLING, CEMENT BOND LOG, MUD LOG/GEOLOGICAL LITHOLOGY LOG,

Coring operation description for the well:

None planned

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4215

Anticipated Surface Pressure: 2357

Anticipated Bottom Hole Temperature(F): 180

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

3R_H2S_Plan_Eddy_20250204134453.pdf

3R_H2S_Plan_Eddy_20250910140610.pdf

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Section 8 - Other Information****Proposed horizontal/directional/multi-lateral plan submission:**

McMuffin_34_35_Fed_Com_703H_APD_Rev01_RPT_20241219143653.pdf

McMuffin_34_35_Fed_Com_703H_APD_Rev01_WM_20241219143657.pdf

McMuffin_34_35_Fed_Com_703H_APD_Rev01_RPT_20250910140621.pdf

McMuffin_34_35_Fed_Com_703H_APD_Rev01_WM_20250910140625.pdf

Other proposed operations facets description:

Per 43 CFR 3162.3-1(d)(4), only oil wells require a gas waste minimization plan as part of a submitted APD; accordingly, this gas well APD will not require a separate gas management plan attachment.

Other proposed operations facets attachment:**Other Variance request(s)?:** N**Other Variance attachment:**



GATES ENGINEERING & SERVICES NORTH AMERICA
7603 Pralrle Oak Dr. Suite 190
Houston, TX. 77086

PHONE: +1 (281) 602-4100

FAX: +1 (281) 602-4147


EMAIL: gesna.quality@gates.com

WEB: gates.com/oilandgas

CERTIFICATE OF CONFORMANCE

This is to verify that all Parts and/or Materials included in this shipment have been manufactured and/or processed in Conformance with applicable drawings and specifications, and that Records of Required Tests are on file and subject to examination. The following items were assembled at **Gates Engineering & Services North America** facilities in Houston, TX, USA. This hose assembly was designed and manufactured to meet requirements of API Spec 16C, 3rd Edition.

CUSTOMER: A-7 AUSTIN INC DBA AUSTIN HOSE
CUSTOMER P.O.#: 00620920 (MENA REF# 01LB10050, 01-012870, HOSE BATCH NO. 120463-07/20)
CUSTOMER P/N: 16C3.035.0CK4116FX-FLTSC/S
PART DESCRIPTION: 3" X 35' GATES API 16C FSL3 TEMP B CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FIXED X SWIVEL H2S SUITED FLANGE ENDS WITH BX 155 RING GROOVE SUPPLIED WITH SAFETY CLAMPS & SLINGS ATTACHED
SALES ORDER #: 522832
QUANTITY: 1
SERIAL #: F-041522-1

SIGNATURE: 
TITLE: QUALITY ASSURANCE
DATE: 8/15/2022



DRIVEN BY POSSIBILITY™

GATES ENGINEERING & SERVICES FZCO
 MENA HEADQUARTERS
 JEBEL ALI FREE ZONE, P. O. BOX 61046
 DUBAI, UNITED ARAB EMIRATES
 T: +971 4 886 1414
 F: +971 4 886 1413
 GATES.COM

جيتس للهندسة و الخدمات ش م ح
 المقر الرئيسي للشرق الأوسط و شمال أفريقيا
 جبل علي المنطقة الحرة، ص. ب. ٦١.٤٦
 دبي، الامارات العربية المتحدة
 هاتف: +٩٧١ ٤ ٨٨٦ ١٤١٤
 فاكس: +٩٧١ ٤ ٨٨٦ ١٤١٣
 GATES.COM

PRESSURE TEST CERTIFICATE

Certificate #	01-012870	Test Date	15-Apr-2022
Customer Name	GATES E & S NORTH AMERICA INC		
Customer Ref. #	1786392/ 2	Gates Ref. #	01CCLBSOA-10007
Gates Job #	01LB10050		
Product Description	3" X 35' GATES API 16C FSL3 TEMP B CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FIXED X SWIVEL H2S SUITED FLANGE ENDS WITH BX 155 RING GROOVE		
Part #	RAB000884-23	Quantity	1
Assembly Code / Serial No.	F-041522-1	Hose Batch No.	120463-07/20
Working Pressure	10000 PSI	Test Pressure	15000.0 PSI
Medium	Water	Duration	1 HOUR
Ref. Specifications			
Observation	No Leakage or Pressure Drop observed under testing condition.		

Gates Engineering & Services certifies that the hose has been assembled, inspected and tested as per Gates Technical Specification. The hose assembly has successfully passed the 60 minutes hydrostatic test as per as per API Spec 16C standard, 3rd edition, March 2021.

Pr. Gauge Sr.#	288223022	Calibrn. Exp.Date	13-Jul-2022
Chart Recorder Sr.#	11.02117.1-01	Calibrn. Exp.Date	13-Jul-2022
Reviewed By	Witnessed By		
			
Clifford G	Siva Mahalingam		
Supervisor / 15-Apr-2022	Operations / Quality Lead / 15-Apr-2022		





DRIVEN BY POSSIBILITY™

GATES ENGINEERING & SERVICES FZCO
 MENA HEADQUARTERS
 JEBEL ALI FREE ZONE, P. O. BOX 61046
 DUBAI, UNITED ARAB EMIRATES
 T: +971 4 886 1414
 F: +971 4 886 1413
 GATES.COM

جيتس للهندسة و الخدمات ش م ح
 المقر الرئيسي للشرق الأوسط و شمال أفريقيا
 جبل علي المنطقة الحرة، ص. ب. ٦١.٤٦
 دبي، الامارات العربية المتحدة
 هاتف: +٩٧١ ٤ ٨٨٦ ١٤١٤
 فاكس: +٩٧١ ٤ ٨٨٦ ١٤١٣
 GATES.COM

CERTIFICATE OF CONFORMANCE

Certificate #	01-012870	Date	15-Apr-2022
Customer Name	GATES E & S NORTH AMERICA INC		
Customer Ref. #	1786392/ 2	Gates Ref. #	01CCLBSOA-10007

Gates Engineering & Services certifies that the hose has been assembled, inspected and tested as per Gates Technical Specification. The hose assembly has successfully passed the 60 minutes hydrostatic test as per as per API Spec 16C standard, 3rd edition, March 2021.

Item Code	Product Description	Quantity
RNB-30E-16C-4F3T2-FG	3" X 35' GATES API 16C FSL3 TEMP B CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FIXED X SWIVEL H2S SUITED FLANGE ENDS WITH BX 155 RING GROOVE Hose Batch No. 120463-07/20 Assembly Code / Serial No. F-041522-1 Gates Job # 01LB10050	1


15-Apr-2022


Date




Sajid Rasheed


QHSE Manager








13 5/8" 5k Multi-Lock Dims



13 5/8" 5k Multi-Lock





Drilling Plan

Operator

3R Operating, LLC

Project Name

McMUFFIN 34 35 FED COM 703H

SHL: 1275' FSL & 155' FEL of Section 33-24S-26E, Eddy County, NM

BHL: 1980' FSL & 330' FEL of Section 35-24S-26E, Eddy County, NM

Prepared By

Reagan Smith, Inc.

Submitted To

Bureau of Land Management - Carlsbad Field Office

Please address any questions, inquiries, or deficiency statements to
Scott St. John and Monica Smith Griffin at the address below:

Reagan Smith
3909 N. Classen Blvd.
Oklahoma City, OK 73118
(405) 286-9326

1.0 Estimated Formation Tops

Formation	Depth	Primary Lithology	Primary Mineral Resources
Surface/Permian	GL	Sandstone	Usable Water
Castille	25	Alluvium	Usable Water
Lamar	1,724	Limestone	None
Delaware	1,829	Limestone, Sandstone, Shale	None
Bone Spring	5,234	Limestone	Nat. Gas, Oil
1st Bone Spring	6,184	Sandstone	Nat. Gas, Oil
2nd Bone Spring	6,654	Sandstone	Nat. Gas, Oil
3rd Bone Spring	8,004	Sandstone	Nat. Gas, Oil
Wolfcamp	8,364	Limestone, Sandstone, Shale	Nat. Gas, Oil

Total Depth and Target Formation

Total Vertical Depth (ft): 8,444

Total Measured Depth (ft): 18,460

Target Formation: Wolfcamp

2.0 Estimated Depths of Oil & Gas

Substance	Depth (ft)
Top of Hydrocarbons	5,234
Bottom of Hydrocarbons	TD

3.0 Pressure Control Equipment

Ten thousand (10M) psi working pressure Blind Rams & Pipe Rams and a five thousand (5M) psi Annular Preventer will be installed on all casing. Two (2) chokes, with at least one (1) being a remotely controlled hydraulic choke, will be used.

A variance to the requirement of a rigid steel line connecting the BOP to the choke manifold is requested. Specifications for the flex hose are provided with the BOP schematic in the exhibit section.

Operator testing procedures will meet minimum standards for well control equipment testing per CFR § 3172.6(b)(9). Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 70 percent of internal yield pressure of casing if BOP stack is not isolated from casing. Annular type preventers shall be tested to 50 percent of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

In addition, the BOP equipment will be tested after any repairs to the equipment and prior to drilling out below any casing string. Pipe rams, blind rams, and annular preventer will be activated on each trip and weekly BOP drills will be held with each crew.

Floor safety valves that are fully open and sized to fit drill pipe and collars will be available on the rig floor in the open position when the Kelly is not in use.

4.0 Proposed Casing and Design Analysis

4.1 Proposed Casing Program

Interval	Length (ft)	Size (in)	Weight/ft (lbs)	Grade	Thread	Condition	Hole size (in)
Surface	480	13.375	48	H-40	STC	NEW	17.5
Inter.	1,745	9.625	36	J-55	BTC	NEW	12.25
Prod.	18,460	5.5	20	P110	BTC	NEW	8.75

4.2 Casing Specifications

Interval	Total Vertical Depth (TVD)	Total Measured Depth (MD)	Weight/ft (lbs)	Grade	Collapse (psi)	Internal Yld (psi)	Body Yld Strength (psi)	Joint Strength (psi)
Surface	480	480	48	H-40	770	1,730	541,000	322,000
Inter.	1,745	1,745	36	J-55	2,020	3,520	564,000	639,000
Prod.	8,444	18,460	20	P110	11,080	12,640	641,000	667,000

5.0 Proposed Cement Program

Surface Casing Cement

Lead/Tail	TOC (MD)	Bottom of Cmt (MD)	Density (lbs/gal)	Yield (ft ³ /sk)	Excess (%)	Volume (ft ³)	# of Sks Cmt
Sur. Lead	0	180	13.50	1.79	100	251	140
Sur. Tail	180	480	14.80	1.33	100	418	314

Lead Cmt Type: Class C

Lead Additives: 4% Gel + 5% Salt +0.2% SA-1 + 0.25pps Pol-E Flake + 0.005gps NOFoam V1A

Tail Cmt Type: Class C

Tail Additives: 1% calcium chloride + 0.005gps NoFoam V1A

Intermediate Casing Cement

Lead/Tail	TOC (MD)	Bottom of Cmt (MD)	Density (lbs/gal)	Yield (ft ³ /sk)	Excess (%)	Volume (ft ³)	# of Sks Cmt
Int. Lead	0	1,245	12.70	1.53	50	586	383
Int. Tail	1,245	1,745	14.80	1.33	50	235	177

Lead Cmt Type: 40% Class C + 60% POZ

Lead Additives: 5% Salt + 1% SMS + 2% CS-9 + 0.1% R-1300 + 0.25pps Pol-E Flake + 0.005gps NoFoam V1A

Tail Cmt Type: Class C

Tail Additives: 1% calcium chloride + 0.005gps NoFoam V1A

Production Casing Cement

Lead/Tail	TOC (MD)	Bottom of Cmt (MD)	Density (lbs/gal)	Yield (ft ³ /sk)	Excess (%)	Volume (ft ³)	# of Sks Cmt
<i>Prod. Lead</i>	0	7,429	10.70	3.34	15	2,161	647
<i>Prod. Tail</i>	7,429	18,460	13.50	1.54	15	3,205	2,081

Lead Cmt Type: 100% ProLite

Lead Additives: 5pps Plexcrete STE + 2% SMS + 0.1% RCKCAS-100 + .85% R-1300 + 0.2% FL-24 + .25pps Pol-E Flake + 0.005gps NoFoam V1A

Tail Cmt Type: 50% Class H + 50% B POZ

Tail Additives: 6% Gell + 5% Slat + .2% SMS + .55% FR-5 + .4% FL-24 + 0.005gps NoFoam V1A

*** Operator reserves the right to change cement designs as hole conditions may warrant**

6.0 Proposed Mud Program

Interval	Top (MD)	Bottom (MD)	Type	Max Mud Weight Pressure Control Design	Max Mud Weight Hole Control Design	Viscosity (cP)	Formation Fracture Gradient	Fluid Loss
<i>Surface</i>	0	480	FW	9.2	8.4	32-36	0.75	NC
<i>Inter.</i>	480	1,745	FW	8.6	8.4	28-30	0.75	NC
<i>Prod.</i>	1,745	18,460	OBM	9.6	9.2	50-70	0.75	8-10 cc

Mud weight increases at shoe depths are for pressure control. Mud weight increases in the curve and lateral section of the hole are for hole stability, not pressure control. Mud weight assumptions for casing load designs exceed anticipated maximum mud weight for balanced drilling in all hole sections. Expected mud weights in producing formation will be 0.5 to 1.0 lbs/gal greater than formation pressure (i.e. overbalanced drilling).

The mud system will run as a closed loop system with PVT monitoring. All drill cuttings and liquid mud will be hauled to an approved site for disposal or soil farmed upon receiving appropriate approval.

An industry accepted medium will be stored on location in the event that there is a loss of circulation in the well bore.

7.0 Drilling Design Analysis**7.1 Casing Safety Factors**

**See separate SF attachment*

Interval	Burst Safety Factor	Collapse Safety Factor	Pipe Body Tensile Safety Factor	Joint Tension Safety Factor
<i>Surface</i>	8.06	3.59	23.48	13.98
<i>Inter.</i>	4.51	5.18	10.17	8.98
<i>Prod.</i>	3.00	2.63	3.80	3.95

7.2 Casing Design Assumptions

7.2.1 Surface Casing Design Assumptions

Burst Design Assumptions:

Calculations assume complete evacuation behind pipe.

Collapse Design Assumptions:

Calculations assume complete evacuation behind pipe.

Tension Design Assumptions:

Calculations assume string held in suspension to TVD.

7.2.2 Intermediate Casing Design Assumptions

Burst Design Assumptions:

Calculations assume complete evacuation behind pipe.

Collapse Design Assumptions:

Calculations assume complete evacuation behind pipe.

Tension Design Assumptions:

Calculations assume string held in suspension to TVD.

7.2.3 Production Casing Design Assumptions

Burst Design Assumptions:

Calculations assume complete evacuation behind pipe. Safety factor calculated using offset pressure gradient variance factor of a maximum of 0.22psi/ft.

Collapse Design Assumptions:

Calculations assume complete evacuation behind pipe. Safety factor calculated using offset pressure gradient variance factor of a maximum of 0.22psi/ft.

Tension Design Assumptions:

Calculations assume string held in suspension to TVD.

8.0 Completion Program and Casing Design

Hydraulic fracturing will occur through the production casing. The burst design calculation assumes TOC at 0 ft., therefore, the backside of the production casing is not evacuated. The maximum pumping pressure is 9500 psi with a maximum proppant fluid weight of 9.5 lbs/gal.

Upon request, operator will provide proof of cement bonding by bond log. Operator is responsible for log interpretation and certification prior to frac treatment.

Upon request, operator will provide estimated fracture lengths, flowback storage, volumes of fluids and amount of sand to be used, and number of stages of frac procedure. Furthermore, a report of the annulus pressures before and after each stage of treatment may be requested by the BLM. The report may include chemical additives (other than proprietary), dissolved solids in frac fluid, and depth of perforations.

9.0 Drilling Evaluation Program

Required Testing, Logging, and Coring procedures noted below:

- * Mud Logging/Gamma Ray/MWD – (MWD on horizontal wells only).
- * Open hole logs (GR/SP/DIL/LDT/CNL/ML) from TD (horizontal well - vertical portion of hole) to the top of the uppermost potential hydrocarbon intervals
- * Open hole logs (GR/SP/DIL) from the top of the uppermost hydrocarbon interval to the base of the surface casing and (GR) log from base of surface casing to surface.
- * Cased hole CBL on production casing.

Note: The above referenced logging requirements are mandatory unless:

- 1) The well is located off unit, or
- 2) The operator can provide the BLM adequate geologic information in which they based the location and drilling of the well, or
- 3) The operator can provide the BLM logging data from a well that is within a 1-mile radius from the proposed surface hole location. The logging data can be no more than 30 years old and must be at least to TD of the proposed well.

10.0 Downhole Conditions

Zones of Possible Lost Circulation:	N/A	
Zones of Possible Abnormal Pressure:	N/A	
Maximum Bottom Hole Temperature:	180	degrees F
Maximum Bottom Hole Pressure:	4,215	psi
Maximum Anticipated Surface Pressure:	2,358	psi

Casing Program: RRR-McMuffin 34 35 Fed Com 703H - 13/8" x 9 5/8" x 5 1/2"

Open Hole Size (Inches)	Casing Depth; From (ft)	Casing Setting Depth (ft) MD	Casing Setting Depth (ft) TVD	Casing Size (inches)	Casing Weight (lb/ft)	Casing Grade	Thread	Condition	Anticipated Mud Weight (ppg)	Burst (psi)	Burst SF (1.125)	Collapse (psi)	Collapse SF (1.125)	Tension Joint (klbs)	Air Weight (lbs)	Tension Joint SF (1.8)	Tension Body (klbs)	Air Weight (lbs)	Tension Body SF (1.8)
Surface																			
17.5"	0'	480'	480'	13 3/8"	48.0	H-40	BTC	New	8.6	1730	8.06	770	3.59	322,000	23,040	13.98	541,000	23,040	23.48
Intermediate																			
12.25"	0'	1,745'	1,745'	9 5/8"	36	J-55	LTC	New	8.6	3520	4.51	2020	5.18	564,000	62,820	8.98	639,000	62,820	10.17
Production																			
8.75"	0'	18,460'	8,444'	5 1/2"	20	P-110	BTC	New	9.6	12640	3.00	11080	2.63	667,000	168,880	3.95	641,000	168,880	3.80

Casing Design Criteria and Casing Loading Assumptions:	
<u>Surface</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Intermediate</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with 1/2 TVD internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Production</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	9.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	9.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	9.6 ppg

Casing Program: RRR-McMuffin 34 35 Fed Com 703H - 13/8" x 9 5/8" x 5 1/2"

Open Hole Size (Inches)	Casing Depth; From (ft)	Casing Setting Depth (ft) MD	Casing Setting Depth (ft) TVD	Casing Size (inches)	Casing Weight (lb/ft)	Casing Grade	Thread	Condition	Anticipated Mud Weight (ppg)	Burst (psi)	Burst SF (1.125)	Collapse (psi)	Collapse SF (1.125)	Tension Joint (klbs)	Air Weight (lbs)	Tension Joint SF (1.8)	Tension Body (klbs)	Air Weight (lbs)	Tension Body SF (1.8)
Surface																			
17.5"	0'	480'	480'	13 3/8"	48.0	H-40	BTC	New	8.6	1730	8.06	770	3.59	322,000	23,040	13.98	541,000	23,040	23.48
Intermediate																			
12.25"	0'	1,745'	1,745'	9 5/8"	36	J-55	LTC	New	8.6	3520	4.51	2020	5.18	564,000	62,820	8.98	639,000	62,820	10.17
Production																			
8.75"	0'	18,460'	8,444'	5 1/2"	20	P-110	BTC	New	9.6	12640	3.00	11080	2.63	667,000	168,880	3.95	641,000	168,880	3.80

Casing Design Criteria and Casing Loading Assumptions:	
<u>Surface</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Intermediate</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with 1/2 TVD internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Production</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	9.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	9.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	9.6 ppg

Casing Program: RRR-McMuffin 34 35 Fed Com 703H - 13/8" x 9 5/8" x 5 1/2"

Open Hole Size (Inches)	Casing Depth; From (ft)	Casing Setting Depth (ft) MD	Casing Setting Depth (ft) TVD	Casing Size (inches)	Casing Weight (lb/ft)	Casing Grade	Thread	Condition	Anticipated Mud Weight (ppg)	Burst (psi)	Burst SF (1.125)	Collapse (psi)	Collapse SF (1.125)	Tension Joint (klbs)	Air Weight (lbs)	Tension Joint SF (1.8)	Tension Body (klbs)	Air Weight (lbs)	Tension Body SF (1.8)
Surface																			
17.5"	0'	480'	480'	13 3/8"	48.0	H-40	BTC	New	8.6	1730	8.06	770	3.59	322,000	23,040	13.98	541,000	23,040	23.48
Intermediate																			
12.25"	0'	1,745'	1,745'	9 5/8"	36	J-55	LTC	New	8.6	3520	4.51	2020	5.18	564,000	62,820	8.98	639,000	62,820	10.17
Production																			
8.75"	0'	18,460'	8,444'	5 1/2"	20	P-110	BTC	New	9.6	12640	3.00	11080	2.63	667,000	168,880	3.95	641,000	168,880	3.80

Casing Design Criteria and Casing Loading Assumptions:	
<u>Surface</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Intermediate</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	8.6 ppg
Collapse A 1.125 design factor with 1/2 TVD internal evacuation and collapse force equal to a mud gradient of:	8.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	8.6 ppg
<u>Production</u>	
Tension A 1.8 design factor with effects of buoyancy with a fluid equal to a mud weight of:	9.6 ppg
Collapse A 1.125 design factor with full internal evacuation and collapse force equal to a mud gradient of:	9.6 ppg
Burst A 1.125 design factor with full external evacuation and burst force equal to a mud gradient of:	9.6 ppg

3R Operating, LLC
Ridge Runner Resources, LLC
1004 N . Big Spring St., Suite 325

Midland, TX 79701

H2S Contingency Plan
Eddy County, NM

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crew should then block entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are NO homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'
100 ppm H₂S concentration shall trigger activation of this plan

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the response.
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training
 - in the: Detection of
 - H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air=1	2 ppm	N/A	1000 ppm

Contacting Authorities

3 Bear Field Services personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. 3 Bear Field Services, LLC response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMERP).

Hydrogen Sulfide Drilling Operations Plan

1. All Company and Contract personnel admitted on location must be trained by a qualified H2S safety instructor to the following:
 - A. Characteristics of H2S
 - B. Physical effects and hazards
 - C. Principal and operation of H2S detectors, warning system and briefing areas.
 - D. Evacuation procedure, routes and first aid.
 - E. Proper use of safety equipment & life support systems
 - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30-minute pressure demand air packs.
2. H2S Detection and Alarm Systems:
 - a. H2S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary.
 - b. An audio alarm system will be installed on the derrick floor and in the top doghouse.
3. Windsock and/or wind streamers:
 - a. Windsock at mudpit area should be high enough to be visible.
 - b. Windsock on the rig floor and/ or top doghouse should be high enough to be visible.
4. Condition Flags and Signs
 - a. Warning sign on access road to location.
 - b. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H2S present in dangerous concentration). Only H2S trained and certified personnel

admitted to location.

5. Well control equipment:

- a. See exhibit BOP and Choke Diagrams

6. Communication:

- a. While working under masks chalkboards will be used for communication.
- b. Hand signals will be used where chalk board is inappropriate.
- c. Two-way radio will be used to communicate off location in case of emergency help is required. In most cases, cellular telephones will be available at most drilling foreman's trailer or living quarters.

7. Drill stem Testing:

No DSTs are planned at this time.

- 8. Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9. If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

Emergency Assistance Telephone List

Ridge Runner Resources, LLC

Ridge Runner Resources, LLC
CEO-Brian Cassens

Office: (432)686-2973
Office: (817)953-0480

Drilling Superintendent-Russell Simons
Production Superintendent-Paul Martinez

Cell: (830)285-7501
Cell: (325)206-1722

Public Safety Numbers

Eddy County Sheriff's Department	Number:	575-887-7551
Eddy County Fire & Rescue	Number:	575-628-5450
Carlsbad Police Department	Number:	575-885-2111
Carlsbad Fire Department	Number:	575-885-3125
Hospital – Carlsbad Medical Center	Number:	575-887-4100
Trans Aero Medevac	Number:	844-435-4911
NMDOT District 2 – Roswell	Number:	575-840-3035
NM OCD Dist. 2 – Artesia	Number:	575-626-0830
BLM Pecos District Office – Roswell	Number:	575-627-0272
BLM Carlsbad Field Office	Number:	575-234-5972
BLM Hobbs Field Station	Number:	575-393-3612
BLM CFO/Eddy Co. PET On-Call	Number:	575-361-2822



3R Operating, LLC

3R Operating LLC

Eddy County_NM (N83-NME)

McMuffin 34 35

McMuffin 34 35 Fed Com 703H

703H

Plan: APD-Rev01

Standard Planning Report

19 December, 2024



3R Operating, LLC

Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Project	Eddy County_NM (N83-NME)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		McMuffin 34 35			
Site Position:		Northing:	428,912.80 usft	Latitude:	32.17915155
From:	Map	Easting:	554,820.10 usft	Longitude:	-104.28975446
Position Uncertainty:		0.00 usft	Slot Radius:	13-3/16 "	

Well	McMuffin 34 35 Fed Com 703H					
Well Position	+N/-S	0.00 usft	Northing:	425,576.41 usft	Latitude:	32.16998008
	+E/-W	0.00 usft	Easting:	554,799.41 usft	Longitude:	-104.28982569
Position Uncertainty		0.00 usft	Wellhead Elevation:	usft	Ground Level:	3,329.00 usft
Grid Convergence:		0.02 °				

Wellbore	703H				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	12/18/2024	6.46	59.63	47,024.90230328

Design	APD-Rev01				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.00	0.00	0.00	90.09	

Plan Survey Tool Program	Date	12/19/2024			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.00	18,459.54	APD-Rev01 (703H)	OWSG MWD Rev 5	
				OWSG MWD - Standard	



Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,636.92	9.55	16.41	2,633.97	50.82	14.96	1.50	1.50	0.00	16.41	
6,421.47	9.55	16.41	6,366.03	653.38	192.39	0.00	0.00	0.00	0.00	
7,058.39	0.00	0.00	7,000.00	704.20	207.35	1.50	-1.50	0.00	180.00	
7,929.43	0.00	0.00	7,871.04	704.20	207.35	0.00	0.00	0.00	0.00	
8,829.42	90.00	90.09	8,444.00	703.32	780.31	10.00	10.00	10.01	90.09	
9,534.53	90.00	90.09	8,444.00	702.24	1,485.41	0.00	0.00	0.00	0.00	03-PPP2(MMFC-703H)
16,150.79	90.00	90.09	8,444.00	691.99	8,101.66	0.00	0.00	0.00	0.00	04-PPP3(MMFC-703H)
18,459.54	90.00	90.09	8,444.00	688.41	10,410.41	0.00	0.00	0.00	0.00	06-PBHL(MMFC-703H)



3R Operating, LLC

Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,724.00	0.00	0.00	1,724.00	0.00	0.00	0.00	0.00	0.00	0.00
Lamar									
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,829.00	0.00	0.00	1,829.00	0.00	0.00	0.00	0.00	0.00	0.00
Delaware									
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	1.50	16.41	2,099.99	1.26	0.37	0.37	1.50	1.50	0.00
2,200.00	3.00	16.41	2,199.91	5.02	1.48	1.47	1.50	1.50	0.00
2,300.00	4.50	16.41	2,299.69	11.30	3.33	3.31	1.50	1.50	0.00
2,400.00	6.00	16.41	2,399.27	20.07	5.91	5.88	1.50	1.50	0.00
2,500.00	7.50	16.41	2,498.57	31.35	9.23	9.18	1.50	1.50	0.00
2,600.00	9.00	16.41	2,597.54	45.11	13.28	13.21	1.50	1.50	0.00
2,636.92	9.55	16.41	2,633.97	50.82	14.96	14.88	1.50	1.50	0.00
2,700.00	9.55	16.41	2,696.18	60.86	17.92	17.83	0.00	0.00	0.00
2,800.00	9.55	16.41	2,794.79	76.79	22.61	22.49	0.00	0.00	0.00
2,900.00	9.55	16.41	2,893.40	92.71	27.30	27.15	0.00	0.00	0.00
3,000.00	9.55	16.41	2,992.02	108.63	31.99	31.81	0.00	0.00	0.00
3,100.00	9.55	16.41	3,090.63	124.55	36.67	36.48	0.00	0.00	0.00
3,200.00	9.55	16.41	3,189.24	140.47	41.36	41.14	0.00	0.00	0.00
3,300.00	9.55	16.41	3,287.86	156.39	46.05	45.80	0.00	0.00	0.00
3,400.00	9.55	16.41	3,386.47	172.32	50.74	50.47	0.00	0.00	0.00
3,500.00	9.55	16.41	3,485.08	188.24	55.43	55.13	0.00	0.00	0.00
3,600.00	9.55	16.41	3,583.69	204.16	60.11	59.79	0.00	0.00	0.00
3,700.00	9.55	16.41	3,682.31	220.08	64.80	64.46	0.00	0.00	0.00
3,800.00	9.55	16.41	3,780.92	236.00	69.49	69.12	0.00	0.00	0.00
3,900.00	9.55	16.41	3,879.53	251.92	74.18	73.78	0.00	0.00	0.00
4,000.00	9.55	16.41	3,978.15	267.84	78.87	78.45	0.00	0.00	0.00
4,100.00	9.55	16.41	4,076.76	283.77	83.55	83.11	0.00	0.00	0.00
4,200.00	9.55	16.41	4,175.37	299.69	88.24	87.77	0.00	0.00	0.00
4,300.00	9.55	16.41	4,273.99	315.61	92.93	92.43	0.00	0.00	0.00
4,400.00	9.55	16.41	4,372.60	331.53	97.62	97.10	0.00	0.00	0.00
4,500.00	9.55	16.41	4,471.21	347.45	102.31	101.76	0.00	0.00	0.00
4,600.00	9.55	16.41	4,569.83	363.37	106.99	106.42	0.00	0.00	0.00
4,700.00	9.55	16.41	4,668.44	379.30	111.68	111.09	0.00	0.00	0.00
4,800.00	9.55	16.41	4,767.05	395.22	116.37	115.75	0.00	0.00	0.00



3R Operating, LLC

Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,900.00	9.55	16.41	4,865.66	411.14	121.06	120.41	0.00	0.00	0.00
5,000.00	9.55	16.41	4,964.28	427.06	125.75	125.08	0.00	0.00	0.00
5,100.00	9.55	16.41	5,062.89	442.98	130.43	129.74	0.00	0.00	0.00
5,200.00	9.55	16.41	5,161.50	458.90	135.12	134.40	0.00	0.00	0.00
5,273.52	9.55	16.41	5,234.00	470.61	138.57	137.83	0.00	0.00	0.00
Bone Spring									
5,300.00	9.55	16.41	5,260.12	474.82	139.81	139.06	0.00	0.00	0.00
5,400.00	9.55	16.41	5,358.73	490.75	144.50	143.73	0.00	0.00	0.00
5,500.00	9.55	16.41	5,457.34	506.67	149.19	148.39	0.00	0.00	0.00
5,600.00	9.55	16.41	5,555.96	522.59	153.88	153.05	0.00	0.00	0.00
5,700.00	9.55	16.41	5,654.57	538.51	158.56	157.72	0.00	0.00	0.00
5,800.00	9.55	16.41	5,753.18	554.43	163.25	162.38	0.00	0.00	0.00
5,900.00	9.55	16.41	5,851.79	570.35	167.94	167.04	0.00	0.00	0.00
6,000.00	9.55	16.41	5,950.41	586.27	172.63	171.71	0.00	0.00	0.00
6,100.00	9.55	16.41	6,049.02	602.20	177.32	176.37	0.00	0.00	0.00
6,200.00	9.55	16.41	6,147.63	618.12	182.00	181.03	0.00	0.00	0.00
6,236.88	9.55	16.41	6,184.00	623.99	183.73	182.75	0.00	0.00	0.00
1st Bone Spring Sand									
6,300.00	9.55	16.41	6,246.25	634.04	186.69	185.70	0.00	0.00	0.00
6,400.00	9.55	16.41	6,344.86	649.96	191.38	190.36	0.00	0.00	0.00
6,421.47	9.55	16.41	6,366.03	653.38	192.39	191.36	0.00	0.00	0.00
6,500.00	8.38	16.41	6,443.60	665.12	195.84	194.80	1.50	-1.50	0.00
6,530.71	7.92	16.41	6,474.00	669.29	197.07	196.02	1.50	-1.50	0.00
2nd Bone Spring Carb									
6,600.00	6.88	16.41	6,542.71	677.85	199.59	198.53	1.50	-1.50	0.00
6,700.00	5.38	16.41	6,642.14	688.08	202.60	201.52	1.50	-1.50	0.00
6,711.91	5.20	16.41	6,654.00	689.14	202.91	201.83	1.50	-1.50	0.00
2nd Bone Spring Sand									
6,800.00	3.88	16.41	6,741.81	695.82	204.88	203.79	1.50	-1.50	0.00
6,900.00	2.38	16.41	6,841.66	701.05	206.42	205.32	1.50	-1.50	0.00
6,972.38	1.29	16.41	6,914.00	703.27	207.08	205.97	1.50	-1.50	0.00
3rd Bone Spring Carb									
7,000.00	0.88	16.41	6,941.62	703.77	207.22	206.12	1.50	-1.50	0.00
7,058.39	0.00	0.00	7,000.00	704.20	207.35	206.24	1.50	-1.50	0.00
7,100.00	0.00	0.00	7,041.61	704.20	207.35	206.24	0.00	0.00	0.00
7,200.00	0.00	0.00	7,141.61	704.20	207.35	206.24	0.00	0.00	0.00
7,300.00	0.00	0.00	7,241.61	704.20	207.35	206.24	0.00	0.00	0.00
7,400.00	0.00	0.00	7,341.61	704.20	207.35	206.24	0.00	0.00	0.00
7,500.00	0.00	0.00	7,441.61	704.20	207.35	206.24	0.00	0.00	0.00
7,600.00	0.00	0.00	7,541.61	704.20	207.35	206.24	0.00	0.00	0.00
7,700.00	0.00	0.00	7,641.61	704.20	207.35	206.24	0.00	0.00	0.00
7,800.00	0.00	0.00	7,741.61	704.20	207.35	206.24	0.00	0.00	0.00
7,900.00	0.00	0.00	7,841.61	704.20	207.35	206.24	0.00	0.00	0.00
7,929.43	0.00	0.00	7,871.04	704.20	207.35	206.24	0.00	0.00	0.00
KOP: 7929.43' MD/ 206.24' VS/7871.04' TVD									
7,950.00	2.06	90.09	7,891.61	704.20	207.72	206.61	10.00	10.00	0.00
8,000.00	7.06	90.09	7,941.44	704.19	211.69	210.58	10.00	10.00	0.00
8,050.00	12.06	90.09	7,990.73	704.18	219.99	218.88	10.00	10.00	0.00
8,063.61	13.42	90.09	8,004.00	704.18	222.99	221.88	10.00	10.00	0.00
3rd Bone Spring Sand									
8,100.00	17.06	90.09	8,039.11	704.16	232.55	231.45	10.00	10.00	0.00
8,150.00	22.06	90.09	8,086.21	704.14	249.29	248.18	10.00	10.00	0.00
8,200.00	27.06	90.09	8,131.67	704.10	270.06	268.95	10.00	10.00	0.00



3R Operating, LLC

Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,250.00	32.06	90.09	8,175.15	704.07	294.72	293.61	10.00	10.00	0.00	
8,300.00	37.06	90.09	8,216.31	704.02	323.07	321.96	10.00	10.00	0.00	
8,350.00	42.06	90.09	8,254.85	703.97	354.90	353.80	10.00	10.00	0.00	
8,400.00	47.06	90.09	8,290.47	703.92	389.97	388.87	10.00	10.00	0.00	
8,450.00	52.06	90.09	8,322.89	703.86	428.01	426.91	10.00	10.00	0.00	
8,488.68	55.93	90.09	8,345.63	703.81	459.29	458.19	10.00	10.00	0.00	
01-KOP(MMFC-703H)										
8,500.00	57.06	90.09	8,351.88	703.80	468.73	467.63	10.00	10.00	0.00	
8,523.02	59.36	90.09	8,364.00	703.77	488.30	487.19	10.00	10.00	0.00	
Wolfcamp XY*										
8,550.00	62.06	90.09	8,377.20	703.73	511.83	510.72	10.00	10.00	0.00	
8,558.30	62.89	90.09	8,381.04	703.72	519.19	518.08	10.00	10.00	0.00	
02-FTP(MMFC-703H)										
8,600.00	67.06	90.09	8,398.67	703.66	556.96	555.86	10.00	10.00	0.00	
8,650.00	72.06	90.09	8,416.13	703.59	603.80	602.69	10.00	10.00	0.00	
8,700.00	77.06	90.09	8,429.44	703.52	651.98	650.87	10.00	10.00	0.00	
8,750.00	82.06	90.09	8,438.50	703.44	701.14	700.03	10.00	10.00	0.00	
8,800.00	87.06	90.09	8,443.24	703.37	750.89	749.79	10.00	10.00	0.00	
8,829.42	90.00	90.09	8,444.00	703.32	780.30	779.20	10.00	10.00	0.00	
EOC: 8829.42' MD/ 779.20' VS/8444.00' TVD										
8,900.00	90.00	90.09	8,444.00	703.21	850.88	849.78	0.00	0.00	0.00	
9,000.00	90.00	90.09	8,444.00	703.06	950.88	949.78	0.00	0.00	0.00	
9,100.00	90.00	90.09	8,444.00	702.91	1,050.88	1,049.78	0.00	0.00	0.00	
9,200.00	90.00	90.09	8,444.00	702.75	1,150.88	1,149.78	0.00	0.00	0.00	
9,300.00	90.00	90.09	8,444.00	702.60	1,250.88	1,249.78	0.00	0.00	0.00	
9,400.00	90.00	90.09	8,444.00	702.45	1,350.88	1,349.78	0.00	0.00	0.00	
9,500.00	90.00	90.09	8,444.00	702.29	1,450.88	1,449.78	0.00	0.00	0.00	
9,534.53	90.00	90.09	8,444.00	702.24	1,485.41	1,484.31	0.00	0.00	0.00	
Target CL - 03-PPP2(MMFC-703H)										
9,534.96	90.00	90.09	8,444.00	702.24	1,485.84	1,484.74	0.00	0.00	0.00	
Exit NMMN 01953: 9534.96' MD										
9,600.00	90.00	90.09	8,444.00	702.14	1,550.88	1,549.78	0.00	0.00	0.00	
9,700.00	90.00	90.09	8,444.00	701.99	1,650.88	1,649.78	0.00	0.00	0.00	
9,800.00	90.00	90.09	8,444.00	701.83	1,750.88	1,749.78	0.00	0.00	0.00	
9,900.00	90.00	90.09	8,444.00	701.68	1,850.88	1,849.78	0.00	0.00	0.00	
10,000.00	90.00	90.09	8,444.00	701.53	1,950.88	1,949.78	0.00	0.00	0.00	
10,100.00	90.00	90.09	8,444.00	701.37	2,050.88	2,049.78	0.00	0.00	0.00	
10,200.00	90.00	90.09	8,444.00	701.22	2,150.88	2,149.78	0.00	0.00	0.00	
10,300.00	90.00	90.09	8,444.00	701.07	2,250.88	2,249.78	0.00	0.00	0.00	
10,400.00	90.00	90.09	8,444.00	700.91	2,350.88	2,349.78	0.00	0.00	0.00	
10,500.00	90.00	90.09	8,444.00	700.76	2,450.88	2,449.78	0.00	0.00	0.00	
10,600.00	90.00	90.09	8,444.00	700.61	2,550.88	2,549.78	0.00	0.00	0.00	
10,700.00	90.00	90.09	8,444.00	700.45	2,650.88	2,649.78	0.00	0.00	0.00	
10,800.00	90.00	90.09	8,444.00	700.30	2,750.88	2,749.78	0.00	0.00	0.00	
10,900.00	90.00	90.09	8,444.00	700.15	2,850.88	2,849.78	0.00	0.00	0.00	
11,000.00	90.00	90.09	8,444.00	699.99	2,950.88	2,949.78	0.00	0.00	0.00	
11,100.00	90.00	90.09	8,444.01	699.84	3,050.88	3,049.78	0.00	0.00	0.00	
11,200.00	90.00	90.09	8,444.01	699.69	3,150.88	3,149.78	0.00	0.00	0.00	
11,300.00	90.00	90.09	8,444.01	699.53	3,250.88	3,249.78	0.00	0.00	0.00	
11,400.00	90.00	90.09	8,444.01	699.38	3,350.88	3,349.78	0.00	0.00	0.00	
11,500.00	90.00	90.09	8,444.01	699.23	3,450.88	3,449.78	0.00	0.00	0.00	
11,600.00	90.00	90.09	8,444.01	699.07	3,550.88	3,549.78	0.00	0.00	0.00	
11,700.00	90.00	90.09	8,444.01	698.92	3,650.88	3,649.78	0.00	0.00	0.00	



Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
11,800.00	90.00	90.09	8,444.01	698.77	3,750.88	3,749.78	0.00	0.00	0.00	
11,900.00	90.00	90.09	8,444.01	698.61	3,850.88	3,849.78	0.00	0.00	0.00	
12,000.00	90.00	90.09	8,444.01	698.46	3,950.88	3,949.78	0.00	0.00	0.00	
12,100.00	90.00	90.09	8,444.01	698.31	4,050.88	4,049.78	0.00	0.00	0.00	
12,200.00	90.00	90.09	8,444.01	698.15	4,150.88	4,149.78	0.00	0.00	0.00	
12,300.00	90.00	90.09	8,444.01	698.00	4,250.88	4,249.78	0.00	0.00	0.00	
12,400.00	90.00	90.09	8,444.01	697.85	4,350.88	4,349.78	0.00	0.00	0.00	
12,500.00	90.00	90.09	8,444.01	697.69	4,450.88	4,449.78	0.00	0.00	0.00	
12,600.00	90.00	90.09	8,444.01	697.54	4,550.88	4,549.78	0.00	0.00	0.00	
12,700.00	90.00	90.09	8,444.01	697.39	4,650.88	4,649.78	0.00	0.00	0.00	
12,800.00	90.00	90.09	8,444.01	697.23	4,750.88	4,749.78	0.00	0.00	0.00	
12,900.00	90.00	90.09	8,444.01	697.08	4,850.88	4,849.78	0.00	0.00	0.00	
13,000.00	90.00	90.09	8,444.01	696.93	4,950.88	4,949.78	0.00	0.00	0.00	
13,100.00	90.00	90.09	8,444.01	696.77	5,050.88	5,049.78	0.00	0.00	0.00	
13,200.00	90.00	90.09	8,444.01	696.62	5,150.88	5,149.78	0.00	0.00	0.00	
13,300.00	90.00	90.09	8,444.01	696.47	5,250.88	5,249.78	0.00	0.00	0.00	
13,400.00	90.00	90.09	8,444.01	696.31	5,350.88	5,349.78	0.00	0.00	0.00	
13,500.00	90.00	90.09	8,444.01	696.16	5,450.88	5,449.78	0.00	0.00	0.00	
13,600.00	90.00	90.09	8,444.01	696.01	5,550.88	5,549.78	0.00	0.00	0.00	
13,700.00	90.00	90.09	8,444.01	695.85	5,650.88	5,649.78	0.00	0.00	0.00	
13,800.00	90.00	90.09	8,444.01	695.70	5,750.88	5,749.78	0.00	0.00	0.00	
13,900.00	90.00	90.09	8,444.01	695.55	5,850.88	5,849.78	0.00	0.00	0.00	
14,000.00	90.00	90.09	8,444.01	695.39	5,950.88	5,949.78	0.00	0.00	0.00	
14,100.00	90.00	90.09	8,444.01	695.24	6,050.88	6,049.78	0.00	0.00	0.00	
14,200.00	90.00	90.09	8,444.01	695.09	6,150.88	6,149.78	0.00	0.00	0.00	
14,300.00	90.00	90.09	8,444.02	694.93	6,250.88	6,249.78	0.00	0.00	0.00	
14,400.00	90.00	90.09	8,444.02	694.78	6,350.87	6,349.78	0.00	0.00	0.00	
14,500.00	90.00	90.09	8,444.02	694.63	6,450.87	6,449.78	0.00	0.00	0.00	
14,600.00	90.00	90.09	8,444.02	694.47	6,550.87	6,549.78	0.00	0.00	0.00	
14,700.00	90.00	90.09	8,444.02	694.32	6,650.87	6,649.78	0.00	0.00	0.00	
14,800.00	90.00	90.09	8,444.02	694.17	6,750.87	6,749.78	0.00	0.00	0.00	
14,900.00	90.00	90.09	8,444.02	694.01	6,850.87	6,849.78	0.00	0.00	0.00	
15,000.00	90.00	90.09	8,444.02	693.86	6,950.87	6,949.78	0.00	0.00	0.00	
15,100.00	90.00	90.09	8,444.02	693.70	7,050.87	7,049.78	0.00	0.00	0.00	
15,200.00	90.00	90.09	8,444.02	693.55	7,150.87	7,149.78	0.00	0.00	0.00	
15,300.00	90.00	90.09	8,444.02	693.40	7,250.87	7,249.78	0.00	0.00	0.00	
15,400.00	90.00	90.09	8,444.02	693.24	7,350.87	7,349.78	0.00	0.00	0.00	
15,500.00	90.00	90.09	8,444.02	693.09	7,450.87	7,449.78	0.00	0.00	0.00	
15,600.00	90.00	90.09	8,444.02	692.94	7,550.87	7,549.78	0.00	0.00	0.00	
15,700.00	90.00	90.09	8,444.02	692.78	7,650.87	7,649.78	0.00	0.00	0.00	
15,800.00	90.00	90.09	8,444.02	692.63	7,750.87	7,749.78	0.00	0.00	0.00	
15,900.00	90.00	90.09	8,444.02	692.48	7,850.87	7,849.78	0.00	0.00	0.00	
16,000.00	90.00	90.09	8,444.02	692.32	7,950.87	7,949.78	0.00	0.00	0.00	
16,100.00	90.00	90.09	8,444.02	692.17	8,050.87	8,049.78	0.00	0.00	0.00	
16,150.77	90.00	90.09	8,444.02	692.09	8,101.64	8,100.55	0.00	0.00	0.00	
Enter NMNM 016625: 16150.77' MD										
16,150.79	90.00	90.09	8,444.00	691.99	8,101.66	8,100.56	0.00	0.00	0.00	
04-PPP3(MMFC-703H)										
16,200.00	90.00	90.09	8,444.00	691.91	8,150.87	8,149.78	0.00	0.00	0.00	
16,300.00	90.00	90.09	8,444.00	691.76	8,250.87	8,249.78	0.00	0.00	0.00	
16,400.00	90.00	90.09	8,444.00	691.61	8,350.87	8,349.78	0.00	0.00	0.00	
16,500.00	90.00	90.09	8,444.00	691.45	8,450.87	8,449.78	0.00	0.00	0.00	
16,600.00	90.00	90.09	8,444.00	691.30	8,550.87	8,549.78	0.00	0.00	0.00	
16,700.00	90.00	90.09	8,444.00	691.15	8,650.87	8,649.78	0.00	0.00	0.00	



Planning Report

Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
16,800.00	90.00	90.09	8,444.00	690.99	8,750.87	8,749.78	0.00	0.00	0.00
16,900.00	90.00	90.09	8,444.00	690.84	8,850.87	8,849.78	0.00	0.00	0.00
17,000.00	90.00	90.09	8,444.00	690.69	8,950.87	8,949.78	0.00	0.00	0.00
17,100.00	90.00	90.09	8,444.00	690.53	9,050.87	9,049.78	0.00	0.00	0.00
17,200.00	90.00	90.09	8,444.00	690.38	9,150.87	9,149.78	0.00	0.00	0.00
17,300.00	90.00	90.09	8,444.00	690.23	9,250.87	9,249.78	0.00	0.00	0.00
17,400.00	90.00	90.09	8,444.00	690.07	9,350.87	9,349.78	0.00	0.00	0.00
17,500.00	90.00	90.09	8,444.00	689.92	9,450.87	9,449.78	0.00	0.00	0.00
17,600.00	90.00	90.09	8,444.00	689.77	9,550.87	9,549.78	0.00	0.00	0.00
17,700.00	90.00	90.09	8,444.01	689.61	9,650.87	9,649.78	0.00	0.00	0.00
17,800.00	90.00	90.09	8,444.01	689.46	9,750.87	9,749.78	0.00	0.00	0.00
17,900.00	90.00	90.09	8,444.01	689.31	9,850.87	9,849.78	0.00	0.00	0.00
18,000.00	90.00	90.09	8,444.01	689.15	9,950.87	9,949.78	0.00	0.00	0.00
18,100.00	90.00	90.09	8,444.01	689.00	10,050.87	10,049.78	0.00	0.00	0.00
18,200.00	90.00	90.09	8,444.01	688.85	10,150.87	10,149.78	0.00	0.00	0.00
18,300.00	90.00	90.09	8,444.01	688.69	10,250.87	10,249.78	0.00	0.00	0.00
18,400.00	90.00	90.09	8,444.01	688.54	10,350.87	10,349.78	0.00	0.00	0.00
18,459.54	90.00	90.09	8,444.01	688.45	10,410.41	10,409.32	0.00	0.00	0.00
TD: 18459.54' MD/ 10409.32' VS/8444.01' TVD - 06-PBHL(MMFC-703H) - 05-LTP(MMFC-703H)									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
03-PPP2(MMFC-703H) - plan hits target center - Point	0.00	0.00	8,444.00	702.24	1,485.41	426,278.65	556,284.82	32.17190875	-104.28502397
02-FTP(MMFC-703H) - plan misses target center by 69.72usft at 8558.30usft MD (8381.04 TVD, 703.72 N, 519.19 E) - Point	0.00	0.00	8,444.00	703.79	489.24	426,280.20	555,288.65	32.17191420	-104.28824356
06-PBHL(MMFC-703H) - plan misses target center by 0.04usft at 18459.54usft MD (8444.01 TVD, 688.45 N, 10410.41 E) - Point	0.00	0.00	8,444.00	688.41	10,410.41	426,264.82	565,209.82	32.17185643	-104.25617864
01-KOP(MMFC-703H) - plan misses target center by 120.75usft at 8488.68usft MD (8345.63 TVD, 703.81 N, 459.29 E) - Point	0.00	0.00	8,444.00	704.00	389.27	426,280.41	555,188.68	32.17191489	-104.28856666
04-PPP3(MMFC-703H) - plan hits target center - Point	0.00	0.00	8,444.00	691.99	8,101.66	426,268.40	562,901.07	32.17187060	-104.26364045
05-LTP(MMFC-703H) - plan misses target center by 0.04usft at 18459.54usft MD (8444.01 TVD, 688.45 N, 10410.41 E) - Point	0.00	0.00	8,444.00	688.41	10,410.41	426,264.82	565,209.82	32.17185643	-104.25617864



3R Operating, LLC

Planning Report


Database:	TZ USA 17.2	Local Co-ordinate Reference:	Well McMuffin 34 35 Fed Com 703H
Company:	3R Operating LLC	TVD Reference:	3329+25 @ 3354.00usft
Project:	Eddy County_NM (N83-NME)	MD Reference:	3329+25 @ 3354.00usft
Site:	McMuffin 34 35	North Reference:	Grid
Well:	McMuffin 34 35 Fed Com 703H	Survey Calculation Method:	Minimum Curvature
Wellbore:	703H		
Design:	APD-Rev01		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
1,724.00	1,724.00	Lamar				
1,829.00	1,829.00	Delaware				
5,273.52	5,234.00	Bone Spring				
6,236.88	6,184.00	1st Bone Spring Sand				
6,530.71	6,474.00	2nd Bone Spring Carb				
6,711.91	6,654.00	2nd Bone Spring Sand				
6,972.38	6,914.00	3rd Bone Spring Carb				
8,063.61	8,004.00	3rd Bone Spring Sand				
8,523.02	8,364.00	Wolfcamp XY*				
9,534.53	8,444.00	Target CL				

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
7,929.43	7,871.04	704.20	207.35	KOP: 7929.43' MD/ 206.24' VS/7871.04' TVD	
8,829.42	8,444.00	703.32	780.30	EOC: 8829.42' MD/ 779.20' VS/8444.00' TVD	
9,534.96	8,444.00	702.24	1,485.84	Exit NMNM 01953: 9534.96' MD	
16,150.77	8,444.02	692.09	8,101.64	Enter NMNM 016625: 16150.77' MD	
18,459.54	8,444.01	688.45	10,410.41	TD: 18459.54' MD/ 10409.32' VS/8444.01' TVD	

Released to Imaging: 4/13/2026 2:04:40 PM

Received by: OCD: 3/17/2026 2:19:03 PM





U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

09/23/2025

APD ID: 10400102744

Submission Date: 12/20/2024

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes

[Show Final Text](#)

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

McMUFFIN_SOUTH_ACCESS_ROUTE_20241219083312.pdf

McMUFFIN_SOUTH_LOCATION_TOPO_20241220104845.pdf

McMUFFIN_SOUTH_ACCESS_ROUTE_20250910140720.pdf

McMUFFIN_SOUTH_LOCATION_TOPO_20250910140726.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

McMUFFIN_SOUTH_PROPOSED_ROAD_20241219083642.pdf

McMUFFIN_SOUTH_PROPOSED_ROAD_20250910141000.pdf

New road type: COLLECTOR

Length: 607

Feet

Width (ft.): 30

Max slope (%): 5

Max grade (%): 5

Army Corp of Engineers (ACOE) permit required? N

ACOE Permit Number(s):

New road travel width: 25

New road access erosion control: The proposed lease road traverses mostly level terrain. The largest grade along the lease road may be approximately 5%. Existing bar ditches or any man-made ditch is not

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H

considered in determining max slope of preconstruction contours. Fencing, gates, and/or cattle guards may be installed as necessary per agreement with landowner or surface managing agency. To accommodate the natural drainage of the landscape, culverts or water diversions will be installed as necessary to allow proper drainage of the landscape and mitigate erosion.

New road access plan or profile prepared? N**New road access plan****Access road engineering design?** N**Access road engineering design****Turnout?** N**Access surfacing type:** OTHER**Access topsoil source:** ONSITE**Access surfacing type description:** Caliche**Access onsite topsoil source depth:** 6**Offsite topsoil source description:****Onsite topsoil removal process:** Bulldozer/Road Grader**Access other construction information:****Access miscellaneous information:****Number of access turnouts:****Access turnout map:**

Drainage Control

New road drainage crossing: CULVERT

Drainage Control comments: The lease road will be new construction and will provide all-weather access to this property. The lease road will be maintained with a motor grader in a prudent manner as an all-weather road. Maintenance activity shall include, but not be limited to, resurfacing, reshaping, compacting, and crowning said road as necessary. Any ruts, rills, and eroded areas will be filled/repared as necessary. Crown/ditch will be surfaced with caliche.

Road Drainage Control Structures (DCS) description: To accommodate the natural drainage of the landscape, culverts or water diversions will be installed as necessary to allow proper drainage of the landscape and mitigate erosion.

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Section 3 - Location of Existing Wells

Existing Wells Map? YES**Existing Well map Attachment:**

OMRP___McMuffin_North_South_DRAFT_12202024_20241220125902.pdf

OMRP___McMuffin_North_South_DRAFT_12202024_20250910141105.pdf

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: Proposed production facilities are located in the NE corner of the well pad. A site facility diagram will be submitted to the BLM upon the well being placed into production.

Production Facilities map:

McMUFFIN_SOUTH_FACILITIES_20241219084522.pdf
McMUFFIN_SOUTH_FACILITIES_20250910141154.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: PERENNIAL SURFACE

Water source use type:

DUST CONTROL
SURFACE CASING
INTERMEDIATE/PRODUCTION CASING
STIMULATION

Source latitude: 32.178834

Source longitude: -104.358989

Source datum: NAD83

City:

Water source permit type:

PRIVATE CONTRACT

Water source transport method:

TRUCKING
PIPELINE

Source land ownership: PRIVATE

Source transportation land ownership: OTHER

Describe transportation land ownership: Private, State, or Federal land. Temporary water line lies aboveground and will follow existing roads/routes.

Water source volume (barrels): 180000

Source volume (acre-feet): 23.20075734

Source volume (gal): 7560000

Water source and transportation

WTP_20241213102607.pdf
WTP_20250910141213.pdf

Water source comments: Existing frac pond. Temporary aboveground water line will follow edge of existing roads/routes. Trucking may be used along existing routes if necessary.

New water well? N

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Location will be graded and leveled with existing soil at proposed site. Construction material, particularly caliche, will be obtained via private contract for the construction of the well pad and lease road. Source of caliche is existing pit located on private surface (approx. 32.160285, -104.321481) in the SW/4-NW/4 of Sec. 05-25S-26E.

Construction Materials source location**Section 7 - Methods for Handling****Waste type:** GARBAGE**Waste content description:** Garbage produced during drilling and completions.**Amount of waste:** 1000 pounds**Waste disposal frequency :** Weekly**Safe containment description:** All garbage will be contained either in trash cans or dumpsters onsite.**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** COMMERCIAL**Disposal type description:**

Disposal location description: Third party vendor will be charged with disposal of waste (R360 Environmental Solutions). Waste will be hauled to an approved commercial disposal facility.

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Waste type:** DRILLING**Waste content description:** Drilling mud and cuttings**Amount of waste:** 3800 barrels**Waste disposal frequency :** One Time Only

Safe containment description: Drilling mud and cuttings will be contained in a closed system. During drilling activities trenches will surround all pumps, motors, and rig such that runoff will be directed to a sump area on the well site and pumped into a haul off tank.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Third party vendor will be charged with disposal of waste (R360 Environmental Solutions). Waste will be hauled to an approved commercial disposal facility.

Waste type: COMPLETIONS/STIMULATION**Waste content description:** Water associated with completion of the well.**Amount of waste:** 1000 barrels**Waste disposal frequency :** Weekly

Safe containment description: Completion water will be held in permanent above ground storage tanks on the well pad. The tank(s) will be contained by appropriate secondary containment.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Third party vendor will be charged with disposal of waste (R360 Environmental Solutions). Waste will be hauled to an approved commercial disposal facility.

Waste type: PRODUCED WATER**Waste content description:** Water produced from the target formation.**Amount of waste:** 1000 barrels**Waste disposal frequency :** Daily

Safe containment description: Water produced form target formation will be held in permanent above ground storage tanks on the well pad. The tank(s) will be contained by appropriate secondary containment.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: TBD - Disposal will occur at a regional wastewater disposal facility designed and approved to dispose of oilfield wastewater.

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Waste type:** SEWAGE**Waste content description:** Sewage associated with active drilling and completions operations.**Amount of waste:** 1000 gallons**Waste disposal frequency :** Weekly**Safe containment description:** All sewage will be held in onsite portable restrooms.**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL**Disposal type description:****Disposal location description:** Third party vendor will be charged with disposal of waste (R360 Environmental Solutions). Waste will be hauled to an approved commercial disposal facility.

Reserve Pit

Reserve Pit being used? NO**Temporary disposal of produced water into reserve pit?** NO**Reserve pit length (ft.)** **Reserve pit width (ft.)****Reserve pit depth (ft.)** **Reserve pit volume (cu. yd.)****Is at least 50% of the reserve pit in cut?****Reserve pit liner****Reserve pit liner specifications and installation description**

Cuttings Area

Cuttings Area being used? NO**Are you storing cuttings on location?** N**Description of cuttings location****Cuttings area length (ft.)** **Cuttings area width (ft.)****Cuttings area depth (ft.)** **Cuttings area volume (cu. yd.)****Is at least 50% of the cuttings area in cut?****Cuttings area liner****Cuttings area liner specifications and installation description**

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N**Ancillary Facilities****Comments:**

Section 9 - Well Site

Well Site Layout Diagram:

Rig_Layout_20241119153251.pdf

McMUFFIN_SOUTH_PAD_LAYOUT_20241219084656.pdf

McMUFFIN_SOUTH_PAD_DESIGN_20241219084659.pdf

Rig_Layout_20250910141233.pdf

McMUFFIN_SOUTH_PAD_LAYOUT_20250910141247.pdf

McMUFFIN_SOUTH_PAD_DESIGN_20250910141250.pdf

Comments:

Section 10 - Plans for Surface

Type of disturbance: New Surface Disturbance**Multiple Well Pad Name:** McMuffin South Pad**Multiple Well Pad Number:** 703H, 704H**Recontouring**

McMUFFIN_SOUTH_PAD_DESIGN_20241219084706.pdf

McMUFFIN_SOUTH_PAD_DESIGN_20250910141259.pdf

Drainage/Erosion control construction: To mitigate erosion and protect the natural drainage areas, erosion control methods (e.g. cut and fill ratios of 3:1) will be implemented during the construction and production phases of this project. The slopes of the well pad may be reseeded or replanted per agreement with the landowner. Erosion mitigation such as water diversions, silt fences, and hay bales will be located as necessary around the well pad.

Drainage/Erosion control reclamation: To mitigate erosion and protect the natural drainage areas, erosion control methods (e.g. cut and fill ratios of 3:1) will be implemented during the construction and production phases of this project. The slopes of the well pad may be reseeded or replanted per agreement with the landowner. Erosion mitigation such as water diversions, silt fences, and hay bales will be located as necessary around the well pad.

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well pad proposed disturbance (acres): 4.85	Well pad interim reclamation (acres): 0	Well pad long term disturbance (acres): 4.85
Road proposed disturbance (acres): 0.42	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0.42
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 0.3	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0.3
Total proposed disturbance: 5.569999999999999	Total interim reclamation: 0	Total long term disturbance: 5.569999999999999

Disturbance Comments:

Reconstruction method: The operator does not intend to downsize this well location at this time due to plans of future oil and gas development. In the event that it later becomes necessary to downsize or reclaim the well pad, the following methods will be implemented. The operator will restore topsoil to its original condition. The operator will backfill, level, and restore site to original contours with segregation of spoiled materials as needed. The operator will rehabilitate all disturbed areas. All areas of reclamation will be rehabilitated as per agreement with private surface owner or surface managing agency. Upon abandonment of the well, all waste will be hauled away and disposed of in an approved manner. All equipment and salvageable material will be removed from the drill site. All debris generated from the drilling and operating of the well, which is unsuited for burial at an approved landfill, will be disposed of according to applicable regulations. Cleaning operations will commence with completion of drilling activity and should be completed in approximately 10 days. The drill site will be restored as near as practicable to its reconstruction condition and topography. All surface drainage patterns, which may be affected by the proposed action, will be shaped and restored to preconstruction conditions. The soil will be graded and tilled to prepare its surface for seedbed in accordance with the applicable regulatory and conservation agencies. Erosion control techniques will be implemented when necessary. If applicable, construction of all pipelines will be in accordance with standard pipeline industry practices to assure prudent and safe operations and use of the land and in accordance with the conditions and stipulations of the BLM. The right-of-ways will be graded as necessary to provide a suitable work surface.

Topsoil redistribution: The operator does not intend to downsize this well location at this time due to plans of future oil and gas development. In the event that it later becomes necessary to downsize or reclaim the well pad, topsoil will be redistributed after the well pad has been returned to original contours, or as close as practical.

Soil treatment: No soil treatment will be needed.

Existing Vegetation at the well pad: The project area is located within the Chihuahuan Basins & Playas Level IV Ecoregion and situated in arid rangeland consisting of scrubland and sparse desert grassland communities. Overall vegetation cover is often less than 50% throughout the project area. Topography is gently to moderately sloping. Land use within and surrounding the project area is primarily limited to oil & gas development; however, a small amount of cattle grazing appears to occur within the area. Dominant species include creosote bush (*Larrea tridentata*), honey mesquite (*Neltuma glandulosa*), sideoats grama (*Bouteloua curtipendula*), and tobosa grass (*Hilaria mutica*).

Existing Vegetation at the well pad

Existing Vegetation Community at the road: The project area is located within the Chihuahuan Basins & Playas Level IV Ecoregion and situated in arid rangeland consisting of scrubland and sparse desert grassland communities. Overall vegetation cover is often less than 50% throughout the project area. Topography is gently to moderately sloping. Land use within and surrounding the project area is primarily limited to oil & gas development; however, a small amount of cattle grazing appears to occur within the area. Dominant species include creosote bush (*Larrea tridentata*), honey mesquite (*Neltuma glandulosa*), sideoats grama (*Bouteloua curtipendula*), and tobosa grass (*Hilaria mutica*).

Existing Vegetation Community at the road

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Existing Vegetation Community at the pipeline:** N/A**Existing Vegetation Community at the pipeline**

Existing Vegetation Community at other disturbances: TOPSOIL STOCKPILE - The project area is located within the Chihuahuan Basins & Playas Level IV Ecoregion and situated in arid rangeland consisting of scrubland and sparse desert grassland communities. Overall vegetation cover is often less than 50% throughout the project area. Topography is gently to moderately sloping. Land use within and surrounding the project area is primarily limited to oil & gas development; however, a small amount of cattle grazing appears to occur within the area. Dominant species include creosote bush (*Larrea tridentata*), honey mesquite (*Neltuma glandulosa*), sideoats grama (*Bouteloua curtipendula*), and tobosa grass (*Hilaria mutica*).

Existing Vegetation Community at other disturbances**Non native seed used?****Non native seed description:****Seedling transplant description:****Will seedlings be transplanted for this project?****Seedling transplant description attachment:****Will seed be harvested for use in site reclamation?****Seed harvest description:****Seed harvest description attachment:****Seed****Seed Table****Seed Summary****Total pounds/Acre:****Seed Type****Pounds/Acre****Seed reclamation****Operator Contact/Responsible Official****First Name:****Last Name:****Phone:****Email:****Seedbed prep:****Seed BMP:****Seed method:**

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Existing invasive species?** N**Existing invasive species treatment description:****Existing invasive species treatment****Weed treatment plan description:** Weeds will be mowed regularly to prevent them from becoming the dominant species within the project area.**Weed treatment plan****Monitoring plan description:** The project location will be periodically monitored by the operator's staff that are responsible for infrastructure maintenance.**Monitoring plan****Success standards:** Develop sufficient plant and root coverage to minimize erosion and maximize sediment control.**Pit closure description:** N/A**Pit closure attachment:**

Section 11 - Surface

Disturbance type: WELL PAD**Describe:****Surface Owner:** PRIVATE OWNERSHIP**Other surface owner description:****BIA Local Office:****BOR Local Office:****COE Local Office:****DOD Local Office:****NPS Local Office:****State Local Office:****Military Local Office:****USFWS Local Office:****Other Local Office:****USFS Region:****USFS Forest/Grassland:****USFS Ranger District:**

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: AGREEMENT

Surface Access Agreement Need description: A surface use agreement and SUPO will be finalized with the surface owner prior to construction.

Surface Access Bond BLM or Forest Service:

BLM Surface Access Bond number:

USFS Surface access bond number:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:


USFS Forest/Grassland:

USFS Ranger District:

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**Surface use plan certification:** NO**Surface use plan certification document:****Surface access agreement or bond:** AGREEMENT**Surface Access Agreement Need description:** A surface use agreement and SUPO will be finalized with the surface owner prior to construction.**Surface Access Bond BLM or Forest Service:****BLM Surface Access Bond number:****USFS Surface access bond number:****Section 12 - Other****Right of Way needed?** N**Use APD as ROW?****ROW Type(s):****ROW****SUPO Additional Information:****Use a previously conducted onsite?** N**Previous Onsite information:****Other SUPO**

McMUFFIN SOUTH PAD
3R OPERATING, LLC
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024

AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH

DRIVING DIRECTIONS: FROM THE INTERSECTION OF U.S. HWY. 62 AND MEANS ROAD, GO SOUTHEAST AND SOUTH APPROX 1.8 MILES TO A "Y" INTERSECTION, TAKE LEFT FORK (SOUTHEAST) CONTINUE ON MEANS ROAD (CALICHE) AND GO APPROX. 0.2 MILES, TURN LEFT ON CALICHE ROAD END GO EAST APPROX. 0.68 MILES TO A "Y" INTERSECTION, TAKE RIGHT FORK AND CONTINUE SOUTHEAST APPROX. 0.72 MILES, TURN LEFT (EAST) AND GO APPROX. 0.51 MILES TO A ROAD SURVEY ON LEFT (NORTH), FOLLOW ROAD SURVEY NORTH-NORTHEAST APPROX. 605' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SHEET: 5-7


MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3327

SURVEY NO. 10364
CARLSBAD, NEW MEXICO

McMUFFIN SOUTH PAD
3R OPERATING, LLC
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024

LOCATION VERIFICATION MAP



NOT TO SCALE

SHEET: 4-7

SURVEY NO. 10364


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3327 CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT

ACCESS ROAD FOR McMUFFIN SOUTH PAD

3R OPERATING, LLC

**CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024**



SEE NEXT SHEET (2-2) FOR DESCRIPTION

**GENERAL NOTES**

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3327

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 30TH DAY OF DECEMBER 2024

FILIMON F. JARAMILLO
NEW MEXICO
12797
PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327

SURVEY NO. 10364

ACCESS ROAD PLAT
ACCESS ROAD FOR McMUFFIN SOUTH PAD

3R OPERATING, LLC
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING FEE LAND IN SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S58°32'57"E, A DISTANCE OF 721.94 FEET;
THENCE N18°54'47"E A DISTANCE OF 606.97 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S23°47'15"E, A DISTANCE OF 1039.16 FEET;

SAID STRIP OF LAND BEING 606.97 FEET OR 36.79 RODS IN LENGTH, CONTAINING 0.418 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 606.97 L.F. 36.79 RODS 0.418 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 30TH DAY OF DECEMBER 2024

FILIMON F. JARAMILLO
12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327


GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3327

SURVEY NO. 10364



One Mile Radius Plat
McMuffin Pads
3R Operating, LLC


Sec. 33-T24S-26E, Eddy County, New Mexico

This map is a user generated static output from Reagan Smith and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.



**McMUFFIN SOUTH PAD
3R OPERATING, LLC**
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024

SITE MAP



I, FILIMON F. JARAMILLO, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND HAS BEEN MADE IN ACCORDANCE WITH THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

FILIMON F. JARAMILLO, PLS 1790

SHEET: 3

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3327 **CARLSBAD, NEW MEXICO**

SURVEY NO. 10364

water Source

De Leon Service

Legend

-  Frac Pond
-  Temp. Water Line (Boudin)
-  Temp. Water Line (McMuffin)

 32.178834, -104.358989


McMuffin
North & South Pad


Boudin
North & South Pad

Google Earth




1 mi



REVISION HISTORY						UNSPECIFIED TOLERANCES			PROPRIETARY INFORMATION	CONTACT INFORMATION		DRAWN BY:	DATE:	RIG 212 EQUIPMENT LAYOUT GENERAL ARRANGEMENT				
REV	DESCRIPTION	DATE	DRAWN BY	CHECKED BY	APPROVED BY	DIMENSIONS OVER	TO	MACHINED				WELDMENT	MC				03/17/2020	
A	ISSUED FOR REVIEW	02/12/2020	MC	JM	—	0	1.5	±0.008				±1/32	JM				03/17/2020	
0	GENERATORS CORRECTED	03/23/2020	MC	JM	—	1.5	7.0	±0.010				±1/32	JM				03/17/2020	
1	ADDED MP3, ADDED RIG SPECS, UPDATED FORMATTING	06/1/2020	JM	JM	—	7.0	20.0	±0.020				±1/16	—	—	THIRD ANGLE PROJECTION	SIZE: B	SCALE (UNO): 1:225	ESTIMATED WEIGHT (LBS): —
2	UPDATED RIG SPECS	07/23/2020	JM	JM	—	20.0	50.0	±0.030				±1/8				DWG NO. RIG212—GA—001	REV: 3	SHEET: 1 OF 1
3	ADDED GEN 4	05/24/2022	JM	JM	—	50.0	120.0	±0.060				±3/16						
—	—	—	—	—	—	120.0	240.0	±0.080				±1/4						
—	—	—	—	—	—	ANGLES ±0.1° ±0.5°												
—	—	—	—	—	—	BREAK ALL CORNERS .06 X 45° MACHINE FINISH 250 MAX. MACHINED DIAMETERS ON SAME CENTERLINE SHALL BE COAXIAL WITHIN .021250 DRILLED HOLE LOCATION (±.0000) CHAMFER ALL TAPPED HOLES 45° TO FIRST THREAD ROOT. DIMENSIONS MARKED () ARE FOR GENERAL REFERENCE ONLY, NOT TO BE USED FOR CONSTRUCTION.												

McMUFFIN SOUTH PAD
3R OPERATING, LLC
 IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
 SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 OCTOBER 30, 2024



SEE NEXT SHEET (2-7) FOR DESCRIPTION

GENERAL NOTES

1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A WELL PAD

2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM THE INTERSECTION OF U.S. HWY. 62 AND MEANS ROAD, GO SOUTHEAST AND SOUTH APPROX 1.8 MILES TO A "Y" INTERSECTION, TAKE LEFT FORK (SOUTHEAST) CONTINUE ON MEANS ROAD (CALICHE) AND GO APPROX. 0.2 MILES, TURN LEFT ON CALICHE ROAD END GO EAST APPROX. 0.68 MILES TO A "Y" INTERSECTION, TAKE RIGHT FORK AND CONTINUE SOUTHEAST APPROX. 0.72 MILES, TURN LEFT (EAST) AND GO APPROX. 0.51 MILES TO A ROAD SURVEY ON LEFT (NORTH), FOLLOW ROAD SURVEY NORTH-NORTHEAST APPROX. 605' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SHEET: 1-7

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER 2024

FILIMON F. JARAMILLO, PLS. 12797
 301 SOUTH CANAL
 (575) 234-3327
 PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3327

SURVEY NO. 10364

**McMUFFIN SOUTH PAD
3R OPERATING, LLC**
**IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO**
OCTOBER 30, 2024

DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN FEE LAND IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHEAST CORNER OF THE PARCEL, WHENCE THE SOUTHEAST CORNER OF SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S01°09'15"E, A DISTANCE OF 950.24 FEET;
THENCE N89°52'49"W A DISTANCE OF 400.00 FEET TO THE SOUTHWEST CORNER OF THE PARCEL;
THENCE N00°21'08"E A DISTANCE OF 500.03 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
THENCE S89°52'37"E A DISTANCE OF 400.01 FEET TO THE NORTHEAST CORNER OF THE PARCEL;
THENCE S00°21'14"W A DISTANCE OF 500.00 FEET TO THE SOUTHEAST CORNER OF THE PARCEL, THE POINT OF BEGINNING;
CONTAINING 4.592 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A WELL PAD
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 19TH DAY OF DECEMBER 2024

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327


SURVEY NO. 10364

SHEET: 2-7

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3327

McMUFFIN SOUTH PAD
3R OPERATING, LLC
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 30, 2024

SITE MAP



I, FILIMON F. JARAMILLO, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND HAS SURVEYED TO MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

FILIMON F. JARAMILLO, PLS 1790

SHEET: 3

MADRON SURVEYING, INC.


301 SOUTH CANAL
(575) 234-3327

SURVEY NO. 10364
CARLSBAD, NEW MEXICO




CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



I, FILIMON F. JARAMILA, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THE SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.



3R OPERATING, LLC
PAD ELEVATIONS AND CROSS SECTIONS
FOR McMUFFIN SOUTH PAD
SECTION 33, TOWNSHIP 24 SOUTH,
RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 30, 2024

301 SOUTH CANAL
(575) 234-3327

IRON SURVEYING, INC. CARLSBAD, NEW MEXICO

0 12 60 120 240
SCALE 1" = 120' - 1" = 20' VER

CUT	FILL	NET
5017 CU. YD	5116 CU. YD	99 CU. YD (FILL)


EARTHWORK QUANTITIES ARE ESTIMATED

SHEET 7-7
SURVEY NO. 10364




CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



I, FILIMON F. JARAMILA, a duly registered professional surveyor, certify that I am responsible for this survey, that this survey is true and correct to the best of my knowledge and belief, and that this survey and plat meet the minimum standards for surveying in New Mexico.



3R OPERATING, LLC
PAD ELEVATIONS AND CROSS SECTIONS
FOR McMUFFIN SOUTH PAD
SECTION 33, TOWNSHIP 24 SOUTH,
RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 30, 2024

301 SOUTH CANAL
(575) 234-3327

IRON SURVEYING, INC. CARLSBAD, NEW MEXICO

0 12 60 120 240
SCALE 1" = 120' - 1" = 20' VER

CUT	FILL	NET
5017 CU. YD	5116 CU. YD	99 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

SHEET 7-7
SURVEY NO. 10364



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

09/23/2025

APD ID: 10400102744

Submission Date: 12/20/2024

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD Surface Owner Description:

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Other PWD Surface Owner Description:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Precipitated Solids Permit

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

Operator Name: 3R OPERATING LLC**Well Name:** MCMUFFIN 34 35 FED COM**Well Number:** 703H**State****Unlined Produced Water Pit Estimated****Unlined pit: do you have a reclamation bond for the pit?****Is the reclamation bond a rider under the BLM bond?****Unlined pit bond number:****Unlined pit bond amount:****Additional bond information****Section 4 -****Would you like to utilize Injection PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Other PWD Surface Owner Description:****Injection PWD discharge volume (bbl/day):****Injection well mineral owner:****Injection well type:****Injection well number:****Injection well name:****Assigned injection well API number?****Injection well API number:****Injection well new surface disturbance (acres):****Minerals protection information:****Mineral protection****Underground Injection Control (UIC) Permit?****UIC Permit****Section 5 - Surface****Would you like to utilize Surface Discharge PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Other PWD Surface Owner Description :****Surface discharge PWD discharge volume (bbl/day):****Surface Discharge NPDES Permit?****Surface Discharge NPDES Permit attachment:****Surface Discharge site facilities information:****Surface discharge site facilities map:**

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Section 6 -

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

PWD Surface Owner Description:

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data

09/23/2025

APD ID: 10400102744

Submission Date: 12/20/2024

Operator Name: 3R OPERATING LLC

Well Name: MCMUFFIN 34 35 FED COM

Well Number: 703H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Bond

Federal/Indian APD: FED

BLM Bond number: NMB105811880

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

Form 3160-5
(October 2024)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0220
Expires: October 31, 2027

5. Lease Serial No.

6. If Indian, Allottee or Tribe Name

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

9. API Well No.

10. Field and Pool or Exploratory Area

11. Country or Parish, State

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well
☐ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

3a. Address

3b. Phone No. (include area code)

4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off	
☐ Subsequent Report	☐ Alter Casing	☐ Hydraulic Fracturing	☐ Reclamation	☐ Well Integrity	
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☐ Other	
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon		
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal		

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

Title

Signature

Date

THE SPACE FOR FEDERAL OR STATE OFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Location of Well

0. SHL: SESE / 1275 FSL / 155 FEL / TWSP: 24S / RANGE: 26E / SECTION: 33 / LAT: 32.1699801 / LONG: -104.2898257 (TVD: 0 feet, MD: 0 feet)

PPP: NESW / 1981 FSL / 1326 FWL / TWSP: 24S / RANGE: 26E / SECTION: 34 / LAT: 32.1719088 / LONG: -104.285024 (TVD: 8444 feet, MD: 9535 feet)

PPP: NWSW / 1980 FSL / 330 FWL / TWSP: 24S / RANGE: 26E / SECTION: 34 / LAT: 32.1719142 / LONG: -104.2882436 (TVD: 8444 feet, MD: 8829 feet)

PPP: NWSE / 1976 FSL / 2681 FEL / TWSP: 24S / RANGE: 26E / SECTION: 35 / LAT: 32.1718706 / LONG: -104.2636404 (TVD: 8444 feet, MD: 16151 feet)

BHL: NESE / 1980 FSL / 330 FEL / TWSP: 24S / RANGE: 26E / SECTION: 35 / LAT: 32.1718564 / LONG: -104.2561786 (TVD: 8444 feet, MD: 18460 feet)

CONFIDENTIAL

Well Name: MCMUFFIN 34 35 FED COM	Well Location: T24S / R26E / SEC 33 / SESE / 32.1699801 / -104.2898257	County or Parish/State: EDDY / NM
Well Number: 703H	Type of Well: CONVENTIONAL GAS WELL	Allottee or Tribe Name:
Lease Number: NMNM19593	Unit or CA Name:	Unit or CA Number:
US Well Number:	Operator: 3R OPERATING LLC	

Notice of Intent

Sundry ID: 2895769

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 02/12/2026

Time Sundry Submitted: 02:29

Date proposed operation will begin: 02/12/2026

Procedure Description: This sundry notice revises the Surface Hole Location of the MCMUFFIN 34 35 FED COM 703H AAPD (10400102744) from: • 1275' FSL & 155' FEL (SE/4-SE/4), 32.1699801, -104.2898257, Section 33-24S-26E NMPM, Eddy, NM, Fee Surface, to • 1200' FSL & 175' FEL (SE/4-SE/4), 32.1697741, -104.2898919, Section 33-24S-26E NMPM, Eddy, NM, Fee Surface. Additionally, this sundry notice serves to notify the BLM of the intent to relocate the proposed topsoil stockpile from the North end of the proposed well pad to the South end of the well pad as shown on plat. Platted topsoil stockpile area decreases from original AAPD by approximately 0.04 acre (0.28 acre to 0.24 acre). The lateral wellbore and drilling operations for this well will remain the same as the original AAPD. Please see attachments for more detailed information.

NOI Attachments

Procedure Description

- McMUFFIN_SOUTH_PAD_20260212142751.pdf
- McMUFFIN_34_35_FED_COM_703H_20260212142746.pdf
- McMuffin_34_35_FED_COM_703H_SHL_Sundry_2.12.26_20260212142733.pdf

Received by OCD: 3/17/2026 2:19:03 PM

Page 100 of 121

Well Name: MCMUFFIN 34 35 FED COM	Well Location: T24S / R26E / SEC 33 / SESE / 32.1699801 / -104.2898257	County or Parish/State: EDDY / NM
Well Number: 703H	Type of Well: CONVENTIONAL GAS WELL	Allottee or Tribe Name:
Lease Number: NMNM19593	Unit or CA Name:	Unit or CA Number:
US Well Number:	Operator: 3R OPERATING LLC	

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: KALEN MELTON	Signed on: FEB 12, 2026 01:04 PM
Name: 3R OPERATING LLC	
Title: PERMITTING SPECIALIST	
Street Address: 3909 N CLASSEN BLVD	
City: OKLAHOMA CITY	State: OK
Phone: (405) 286-9326	
Email address: KMELTON@REAGANSMITH.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752342234	BLM POC Email Address: CWALLS@BLM.GOV
Disposition: Approved	Disposition Date: 03/16/2026
Signature: Chris Walls	

Sundry ID: 2895769
3R Operating, LLC
MCMUFFIN 34 35 FED COM 703H
SHL REVISION

APD ID: 10400102744

3R Operating submits this Notice of Intent (APD Change) to revise the Surface Hole Location as follows:

Point	From (Old)	To (New)
SHL	1275' FSL & 155' FEL (SE/4-SE/4) 32.1699801, -104.2898257 Section 33-24S-26E NMPM, Eddy, NM Fee Surface	1200' FSL & 175' FEL (SE/4-SE/4) 32.1697741, -104.2898919 Section 33-24S-26E NMPM, Eddy, NM Fee Surface

Additionally, this sundry notice serves to notify the BLM of the intent to relocate the proposed topsoil stockpile from the North end of the proposed well pad to the South end of the well pad as shown on plat. Platted topsoil stockpile area decreases from original AAPD by approximately 0.04 acre (0.28 acre to 0.24 acre).

The lateral wellbore and drilling operations for this well will remain the same as the original AAPD. Please see attachments for more detailed information.

Please see the following related Sundry Notices:

Sundry ID: **2895774** – Revises SHL location of the MCMUFFIN 34 35 FED COM 704H

Additional attachments to this sundry:

- 1. Revised C-102 Plat
- 2. Revised Well Pad Plats

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION		Revised July 9, 2024	
	Submittal Type:	☒ Initial Submittal		
		☐ Amended Report		
		☐ As Drilled		

WELL LOCATION INFORMATION

API Number 30-015-58058	Pool Code 98220	Pool Name Purple Sage; Wolfcamp
Property Code 339062	Property Name McMUFFIN 34 35 FED COM	Well Number 703H
OGRID No. 331569	Operator Name 3R OPERATING, LLC	Ground Level Elevation 3328.5
Surface Owner: ☐ State ☒ Fee ☐ Tribal ☐ Federal		Mineral Owner: ☐ State ☒ Fee ☐ Tribal ☒ Federal

Surface Location

UL P	Section 33	Township 24 S	Range 26 E	Lot	Ft. from N/S 1200 SOUTH	Ft. from E/W 175 EAST	Latitude 32.1697741°N	Longitude 104.2898919°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Bottom Hole Location

UL I	Section 35	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 EAST	Latitude 32.1718564°N	Longitude 104.2561786°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Dedicated Acres 640	Infill or Defining Well defining	Defining Well API	Overlapping Spacing Unit (Y/N) N	Consolidation Code C
Order Numbers. pending comm agreement			Well setbacks are under Common Ownership: ☐ Yes ☒ No	

Offset lease operator(s) notified

Kick Off Point (KOP)

UL L	Section 34	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 230 WEST	Latitude 32.1719149°N	Longitude 104.2885667°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

First Take Point (FTP)

UL L	Section 34	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 WEST	Latitude 32.1719142°N	Longitude 104.2882436°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Last Take Point (LTP)

UL I	Section 35	Township 24 S	Range 26 E	Lot	Ft. from N/S 1980 SOUTH	Ft. from E/W 330 EAST	Latitude 32.1718564°N	Longitude 104.2561786°W	County EDDY
---------	---------------	------------------	---------------	-----	----------------------------	--------------------------	--------------------------	----------------------------	----------------

Unitized Area or Area of Uniform Interest Y	Spacing Unit Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation:
---	--	-------------------------

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest run leased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order here to fore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Austin Tramell 02/12/2026
Signature Date

Austin Tramell

Printed Name

atramell@3ROperating.com

Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



Signature and Seal of Professional Surveyor
FILIMON F. JARAMILLO

Certificate Number

PLS 12797

Date of Survey

FEBRUARY 11, 2026

SURVEY NO. 10337A

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.

McMUFFIN 34 35 FED COM 703H
EL. = 3328.5

LEGEND

--- SECTION LINE
--- QUARTER LINE
--- LEASE LINE
--- WELL PATH

GEODETTIC COORDINATES

NAD 83 NMSP EAST
SURFACE LOCATION
1200' FSL, 175' FEL
N.=425501.48
E.=554778.95
LAT.=32.1697741°N
LONG.=104.2898919°W

LAST TAKE POINT
1980' FSL, 330' FEL
N.=426264.82
E.=565209.82
LAT.=32.1718564°N
LONG.=104.2561786°W

PPP3
2681' FEL 1976' FSL,
N.=426268.40
E.=562901.07
LAT.=32.1718706°N
LONG.=104.2636404°W

CORNER COORDINATES TABLE


NAD 83 NMSP EAST
A - N.=429599.02 E.=549648.90
B - N.=429557.13 E.=552313.86
C - N.=429515.24 E.=554978.83
D - N.=429569.97 E.=557627.08
E - N.=429625.16 E.=560293.81
F - N.=429590.39 E.=562915.46
G - N.=429555.61 E.=565537.11
H - N.=426954.45 E.=549639.22
I - N.=426908.12 E.=554962.60
J - N.=427013.46 E.=560212.37
K - N.=426917.28 E.=565539.20
L - N.=424308.86 E.=549630.09
M - N.=424307.30 E.=552290.42
N - N.=424301.41 E.=554946.51
O - N.=424295.83 E.=557601.13
P - N.=424292.44 E.=560241.79
Q - N.=424293.38 E.=562892.51
R - N.=424284.14 E.=565541.41

KICK OFF POINT
1980' FSL, 230' FWL
N.=426280.41
E.=555188.68
LAT.=32.1719149°N
LONG.=104.2885667°W


BOTTOM OF HOLE
1980' FSL, 330' FEL
N.=426264.82
E.=565209.82
LAT.=32.1718564°N
LONG.=104.2561786°W

FIRST TAKE POINT
1980' FSL, 330' FWL
N.=426280.20
E.=555288.65
LAT.=32.1719142°N
LONG.=104.2882436°W

PPP2
1981' FSL, 1326' FWL
N.=426278.65
E.=556284.82
LAT.=32.1719088°N
LONG.=104.2850240°W



McMUFFIN SOUTH PAD
3R OPERATING, LLC
 IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
 SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 FEBRUARY 11, 2026

**GENERAL NOTES**

1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A WELL PAD

2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM THE INTERSECTION OF U.S. HWY. 62 AND MEANS ROAD, GO SOUTHEAST AND SOUTH APPROX 1.8 MILES TO A "Y" INTERSECTION, TAKE LEFT FORK (SOUTHEAST) CONTINUE ON MEANS ROAD (CALICHE) AND GO APPROX. 0.2 MILES, TURN LEFT ON CALICHE ROAD END GO EAST APPROX. 0.68 MILES TO A "Y" INTERSECTION, TAKE RIGHT FORK AND CONTINUE SOUTHEAST APPROX. 0.72 MILES, TURN LEFT (EAST) AND GO APPROX. 0.51 MILES TO A ROAD SURVEY ON LEFT (NORTH), FOLLOW ROAD SURVEY NORTH-NORTHEAST APPROX. 605' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SHEET: 1-7

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 11th DAY OF FEBRUARY 2026

FILMON F. JARAMILLO
 12797
 NEW MEXICO PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3327

SURVEY NO. 10364A

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3327

*McMUFFIN SOUTH PAD
3R OPERATING, LLC
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
FEBRUARY 11, 2026*

DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN FEE LAND IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHEAST CORNER OF THE PARCEL, WHENCE THE SOUTHEAST CORNER OF SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S01°09'15"E, A DISTANCE OF 950.24 FEET;
THENCE N89°52'49"W A DISTANCE OF 400.00 FEET TO THE SOUTHWEST CORNER OF THE PARCEL;
THENCE N00°21'08"E A DISTANCE OF 500.03 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
THENCE S89°52'37"E A DISTANCE OF 400.01 FEET TO THE NORTHEAST CORNER OF THE PARCEL;
THENCE S00°21'14"W A DISTANCE OF 500.00 FEET TO THE SOUTHEAST CORNER OF THE PARCEL, THE POINT OF BEGINNING;
CONTAINING 4.592 ACRES MORE OR LESS.

GENERAL NOTES

1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A WELL PAD

2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 11TH DAY OF FEBRUARY 2026

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327

SURVEY NO. 10364A

SHEET: 2-7

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3327

SITE MAP



FILIMON F. JARAMILLO PSD 12797


SHEET: 3

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3327

SURVEY NO. 10364A

McMUFFIN SOUTH PAD
 3R OPERATING, LLC
 IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
 SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 FEBRUARY 11, 2026

LOCATION VERIFICATION MAP



NOT TO SCALE


SHEET: 4-7

SURVEY NO. 10364A

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3327 CARLSBAD, NEW MEXICO

McMUFFIN SOUTH PAD
3R OPERATING, LLC
IN THE SE/4 NE/4 SE/4 & NE/4 SE/4 SE/4 OF
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
FEBRUARY 11, 2026

AERIAL ACCESS ROUTE MAP




NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH

DRIVING DIRECTIONS: FROM THE INTERSECTION OF U.S. HWY. 62 AND MEANS ROAD, GO SOUTHEAST AND SOUTH APPROX 1.8 MILES TO A "Y" INTERSECTION, TAKE LEFT FORK (SOUTHEAST) CONTINUE ON MEANS ROAD (CALICHE) AND GO APPROX. 0.2 MILES, TURN LEFT ON CALICHE ROAD END GO EAST APPROX. 0.68 MILES TO A "Y" INTERSECTION, TAKE RIGHT FORK AND CONTINUE SOUTHEAST APPROX. 0.72 MILES, TURN LEFT (EAST) AND GO APPROX. 0.51 MILES TO A ROAD SURVEY ON LEFT (NORTH), FOLLOW ROAD SURVEY NORTH-NORTHEAST APPROX. 605' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.





SHEET: 5-7

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3327 CARLSBAD, NEW MEXICO

SURVEY NO. 10364A




CROSS-SECTIONS



I, FILMON F. JARAN, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFICATE NO. 12297, AM RESPONSIBLE FOR THIS SURVEY, THAT THE SURVEYED LOTS AND CORNERS ARE THE BEST OF MY KNOWLEDGE AND BELIEF, AND THIS SURVEY AND PLAN MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

3R OPERATING, LLC
PAD ELEVATIONS AND CROSS SECTIONS
FOR McMUFFIN SOUTH PAD
SECTION 33, TOWNSHIP 24 SOUTH,
RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO




FILMON F. JARAN, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR
FEBRUARY 11, 2026
301 SOUTH CANAL
(979) 234-3327
CARLSBAD, NEW MEXICO
SHEET 7-7
SURVEY NO. 10364A

ACCESS ROAD PLAT

ACCESS ROAD FOR McMUFFIN SOUTH PAD

3R OPERATING, LLC

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
FEBRUARY 11, 2026



SEE NEXT SHEET (2-2) FOR DESCRIPTION

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 11th DAY OF FEBRUARY 2026

FILIMON F. JARAMILLO
12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327

SURVEY NO. 10364A

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

ACCESS ROAD PLAT
ACCESS ROAD FOR McMUFFIN SOUTH PAD

3R OPERATING, LLC
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
FEBRUARY 11, 2026

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING FEE LAND IN SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S58°32'57"E, A DISTANCE OF 721.94 FEET;
THENCE N18°54'47"E A DISTANCE OF 606.97 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 33, TOWNSHIP 24 SOUTH, RANGE 26 EAST, N.M.P.M. BEARS S23°47'15"E, A DISTANCE OF 1039.16 FEET;

SAID STRIP OF LAND BEING 606.97 FEET OR 36.79 RODS IN LENGTH, CONTAINING 0.418 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 606.97 L.F. 36.79 RODS 0.418 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 11th DAY OF FEBRUARY 2026

FILIMON F. JARAMILLO
12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3327

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3327

SURVEY NO. 10364A

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: 3R Operating LLC **OGRID:** 331569 **Date:** 4 / 13 / 26

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
See attached						

IV. Central Delivery Point Name: McMuffin CTB [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
See attached						

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan**EFFECTIVE APRIL 1, 2022**

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☒ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: <i>Austin Tramell</i>
Printed Name: Austin Tramell
Title: Director Environmental & Regulatory
E-mail Address: atramell@3roperating.com
Date: 04/13/2026
Phone: 832-810-1037
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)
Approved By:
Title:
Approval Date:
Conditions of Approval:

VI. Separation Equipment

Separation equipment will be sized by construction engineering staff based on stated manufacturer daily throughput capacities and anticipated daily production rates to ensure adequate capacity. Closed vent system piping, compression needs, and VRUs will be sized utilizing modeling software to ensure adequate capacity for anticipated production volumes and conditions. Production composition and the volumes will be utilized as inputs to a process model which predicts relative amounts of gas, oil and water throughout the process. The high-volume case will be used to size equipment, piping and instrumentation.

Each well has a dedicated 3-phase separator and gas from that separator is taken directly to gas sales. Facility piping and pipeline will be sized to allow peak volumes to flow with minimal pressure loss and deliver to the midstream gatherer at an acceptable pressure. Water will be conveyed directly to tankage. Oil from 3-phase separators will be conveyed to a heated separator for enhanced liquid-liquid separation and degassing. Vapors from the heater treater are routed to flare. Oil and water storage tanks vapor outlets utilize a closed vent vapor system to ensure all working & breathing and flashing losses are routed to the flare which is sized to accommodate peak expected production volume. Flash volumes are estimated using the high-volume case.

VII. Operational Practices

The operator will ensure pipeline connectivity before producing hydrocarbons and will operate a closed vent vapor capture system that is designed to capture all associated and evolved gas during normal operation. Venting will only occur during maintenance activities or equipment failure. The operator may utilize the following from Section 3 for its operations to minimize flaring:

- A. The operator will maximize the recovery of natural gas by minimizing the waste, as defined by 19.15.2 NMAC, of natural gas through venting and flaring. The operator will ensure that well(s) will be connected to a natural gas gathering system with sufficient capacity to transport natural gas. If there is no adequate takeaway for the gas, compression will be added to deliver volumes that are produced. Well production may also be curtailed to manage the flow of gas and not overrun compression.
- B. All drilling operations will be equipped with a rig flare located at least 100' from the nearest surface hole. Rig flare will be utilized to combust any natural gas that is brought to surface during normal drilling operations.
- C. During completion operations any natural gas brought to surface will be flared. Immediately following the finish of completion operations, all well flowback will be directed to permanent separation equipment. Produced natural gas from separation equipment will be sent to sales. It is not anticipated that gas will not meet pipeline standards; however, if natural gas does not meet gathering pipeline quality specifications, the operator will flare the natural gas for up to 60 days or until the natural gas meets the pipeline quality specifications, whichever is sooner. The operator will ensure that the flare is sized properly and is equipped with automatic igniter or continuous pilot. The gas sample will be analyzed twice per week and the gas will be routed into a gathering system as soon as pipeline specifications are met.
- D. Natural gas will not be flared with the exceptions and provisions listed in the 19.15.27.8 D.(l) through (4). If there is no adequate takeaway for the separator gas, well(s) will be curtailed until the natural gas gathering system is available with exception of emergency or malfunction situations. Venting and/or flaring volumes will be measured using a total flow meter and reported appropriately.
- E. The operator will comply with the performance standards requirements and provisions listed in 19.15.27.8 E.(l) through (8). All equipment will be designed and sized to handle maximum anticipated pressures and throughputs to minimize the waste. Production storage tanks constructed after May 25, 2021, will be equipped with automatic gauging system. Flares constructed after May 25, 2021, will be equipped with automatic igniter or continuous pilot. Flares will be located at least 100' from the well and storage tanks unless otherwise approved by the division. The operator will conduct AVO inspections as described in 19.15.27.8 E (5) (a) with frequencies specified in 19.15.27.8 E (5) (b) and (c). All emergencies will be resolved as quickly and safely as feasible to minimize waste.
- F. The volume of natural gas that is vented or flared as the result of malfunction or emergency during drilling and completions operations will be estimated. The volume of natural gas that is vented, flared, or beneficially used during production operations, will be measured, or estimated. The operator will install equipment to measure the volume of natural gas flared from existing process piping, or a flowline piped from equipment such as high-

pressure separators, heater treaters, or vapor recovery units associated with a well or facility associated with a well authorized by an APD issued after May 25, 2021, that has an average daily production greater than 60 Mcf/day. If metering is not practicable due to circumstances such as low flow rate or low pressure venting and flaring, the operator will estimate the volume of vented or flared natural gas. Measuring equipment will conform to industry standards and will not be designed or equipped with a manifold that allows the diversion of natural gas around the metering element except for the sole purpose of inspecting and servicing the measurement equipment.

VIII. Best Management Practices

The operator utilizes automated engineering controls included in facility design to minimize venting and flaring. Additionally, operator's SOP support the minimization of flare and venting.

If the main gas outlet becomes unavailable and pressure increases on the outlet sales line, produced gas will be routed directly to the facility flare. The facility control system will alert personnel to the need for maintenance and appropriate response to the temporary flaring event. The facility design includes a closed vent vapor capture system to route flash from the heater treater and tanks to the flare. For maintenance activities, the operator will utilize the facility flare to blowdown equipment and piping whenever practical to minimize venting.

XIV. Confidentiality

Uniqueness and variability of the formation encountered for this well is such that the Operator requests confidentiality in order to protect its proprietary data. After the responsible agency has conducted its review, the Operator requests the following information be REDACTED from the approved and posted permit(s), including anticipated production volumes and the Operator's planned development schedule. This information is expected to remain private between the submitting operator and the reviewing agency only.

III. Wells

Well Name	Legal Description	API	Anticipated Initial Oil Production BBL/D	Anticipated Initial Gas MCF/D	Anticipate Produced Water BBL/D
McMuffin 34 35 Fed Com 701H	33-24S-26E, 680' FNL & 175' FEL	pending	1100	2500	4500
McMuffin 34 35 Fed Com 702H	33-24S-26E, 680' FNL & 175' FEL	pending	1100	2500	4500
McMuffin 34 35 Fed Com 703H	33-24S-26E, 1,200 FSL & 175' FEL	pending	1100	2500	4500
McMuffin 34 35 Fed Com 704H	33-24S-26E, 1,170' FSL & 175' FEL	pending	1100	2500	4500

Well Name	Anticipated Oil Prod. after 3 years BBL/D	Anticipated Gas Prod. after 3 years MCF/D	
McMuffin 34 35 Fed Com 701H	137	374	See provided decline curve on next page for estimated production volumes over 36 months.
McMuffin 34 35 Fed Com 702H	137	374	
McMuffin 34 35 Fed Com 702H	137	374	
McMuffin 34 35 Fed Com 702H	137	374	

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flowback Date	First Production Date
McMuffin 34 35 Fed Com 701H		4/15/2026	5/15/2026	6/14/2026	6/24/2026	6/29/2026
McMuffin 34 35 Fed Com 702H		4/15/2026	5/7/2026	6/14/2026	6/24/2026	6/29/2026
McMuffin 34 35 Fed Com 703H		4/15/2026	4/30/2026	6/14/2026	6/24/2026	6/29/2026
McMuffin 34 35 Fed Com 704H		4/15/2026	4/23/2026	6/14/2026	6/24/2026	6/29/2026

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 563910

ACKNOWLEDGMENTS

Operator: 3R Operating, LLC 20405 State Highway 249 Houston, TX 77070	OGRID: 331569
	Action Number: 563910
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

ACKNOWLEDGMENTS

☒	I hereby certify that no additives containing PFAS chemicals will be added to the completion or recompletion of this well.
-------------------------------------	--

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 563910

CONDITIONS

Operator: 3R Operating, LLC 20405 State Highway 249 Houston, TX 77070	OGRID: 331569
	Action Number: 563910
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
atramell01	Cement is required to circulate on both surface and intermediate1 strings of casing.	3/17/2026
atramell01	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	3/17/2026
ward.rikala	Notify the OCD 24 hours prior to casing & cement.	4/13/2026
ward.rikala	File As Drilled C-102 and a directional Survey with C-104 completion packet.	4/13/2026
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	4/13/2026
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	4/13/2026
ward.rikala	If the method of isolation was not by circulation, a CBL must be performed; if strata isolation is not achieved, then remediation will be required before further operations.	4/13/2026