

RECEIVED: 06/20/2019	REVIEWER:	TYPE: SWD	APP NO: PMAM19175 5686
-------------------------	-----------	--------------	---------------------------

ABOVE THIS TABLE FOR OCD DIVISION USE ONLY

NEW MEXICO OIL CONSERVATION DIVISION
 - Geological & Engineering Bureau -
 1220 South St. Francis Drive, Santa Fe, NM 87505



ADMINISTRATIVE APPLICATION CHECKLIST

THIS CHECKLIST IS MANDATORY FOR ALL ADMINISTRATIVE APPLICATIONS FOR EXCEPTIONS TO DIVISION RULES AND REGULATIONS WHICH REQUIRE PROCESSING AT THE DIVISION LEVEL IN SANTA FE

Applicant: Delaware Energy, LLC	OGRID Number: 371195
Well Name: Frying Pan SWD #1	API: Pending
Pool: SWD, Devonian	Pool Code: 96101

SUBMIT ACCURATE AND COMPLETE INFORMATION REQUIRED TO PROCESS THE TYPE OF APPLICATION INDICATED BELOW

- 1) **TYPE OF APPLICATION:** Check those which apply for [A]
 A. Location - Spacing Unit - Simultaneous Dedication
☐ NSL ☐ NSP (PROJECT AREA) ☐ NSP (PRORATION UNIT) ☐ SD

B. Check one only for [I] or [II]

[I] Commingling - Storage - Measurement

☐ DHC ☐ CTB ☐ PLC ☐ PC ☐ OLS ☐ OLM

[II] Injection - Disposal - Pressure Increase - Enhanced Oil Recovery

☐ WFX ☐ PMX ☒ SWD ☐ IPI ☐ EOR ☐ PPR

- 2) **NOTIFICATION REQUIRED TO:** Check those which apply.

- A. ☒ Offset operators or lease holders
 B. ☐ Royalty, overriding royalty owners, revenue owners
 C. ☒ Application requires published notice
 D. ☒ Notification and/or concurrent approval by SLO
 E. ☐ Notification and/or concurrent approval by BLM
 F. ☒ Surface owner
 G. ☒ For all of the above, proof of notification or publication is attached, and/or,
 H. ☐ No notice required

FOR OCD ONLY

- ☐ Notice Complete
☐ Application Content Complete

- 3) **CERTIFICATION:** I hereby certify that the information submitted with this application for administrative approval is **accurate** and **complete** to the best of my knowledge. I also understand that **no action** will be taken on this application until the required information and notifications are submitted to the Division.

Note: Statement must be completed by an individual with managerial and/or supervisory capacity.

Sarah Presley

Print or Type Name

Signature

6/13/2019

Date

432-685-7005

Phone Number

s.presley@delawareenergy.com

e-mail Address

Delaware Energy, LLC
Application for Injection/SWD
Frying Pan SWD #1

JUN 20 2019 PM01:05

UL M, Sec. 14, T-26-S, R-36-E, 284' FSL & 402' FWL, Lea Co., NM

June 13, 2019

Contents:

1. Administrative Application Checklist
2. Form C-108: Application for Authority to Inject
3. Form C-108 Additional Questions Answered
4. Form C-102
5. Chemical Analysis of Devonian Formation Water Sample
6. Chemical Analysis of Bone Spring Formation Water Sample
7. Chemical Analysis of Delaware Formation Water Sample
8. Planned wellbore diagram for the Frying Pan SWD #1
9. ~~Tabular Data on All Wells of Public Record within the Area of Review which Penetrate the Proposed Injection Zone~~ (No applicable wells)
10. Map Identifying all Wells and Leases within Two Miles of Any Proposed Injection Well with a One Mile Radius Circle Drawn Around the Proposed Injection Well
11. Sample of Letter Sent with This Application Packet to Owner of Surface of the Land on Which the Well is to be Located and to each Leasehold Operator within One Mile of the Well Location
12. Legal Notice that was run as required in the Carlsbad Current-ARGUS
13. Formation Tops
14. Certified Mailers
15. Seismicity Assessment
16. Carlsbad Current-ARGUS Affidavit of publication

DISTRIBUTION LIST

Surface Owner:

State of New Mexico
310 Old Santa Fe Trail
Santa Fe NM 87501

Offset Operators/Leasehold Owners:

Ameredev LLC
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735

Bureau of Land Management
620 E Greene Street
Carlsbad, NM 88220

Burlington Res Oil & Gas Co LP
3300 N A St # 6
Midland, TX 79705


Chevron USA Inc.
6301 Deauville Blvd.
Midland, TX 79706

Tap Rock Operating, LLC
602 Park Point Dr. Ste 200
Golden, CO 80401

State of New Mexico Oil Conservation Division
District I
1625 N French Drive
Hobbs, NM 88240

State of New Mexico Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

APPLICATION FOR AUTHORIZATION TO INJECT

- I. PURPOSE: _____ Secondary Recovery _____ Pressure Maintenance _____ XXX _____ Disposal _____ Storage
Application qualifies for administrative approval? _____ XX _____ Yes _____ No
- II. OPERATOR: _____ Delaware Energy, LLC _____
ADDRESS: _____ 405 North Marienfeld, Suite 250, Midland TX 79701 _____
CONTACT PARTY: _____ Mike McCurdy _____ PHONE: _____ 432-312-5251 _____
- III. WELL DATA: Complete the data required on the reverse side of this form for each well proposed for injection.
Additional sheets may be attached if necessary.
- IV. Is this an expansion of an existing project? _____ Yes _____ XXXX _____ No
If yes, give the Division order number authorizing the project: _____
- V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review.
- VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.
- VII. Attach data on the proposed operation, including:
1. Proposed average and maximum daily rate and volume of fluids to be injected;
 2. Whether the system is open or closed;
 3. Proposed average and maximum injection pressure;
 4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and,
 5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).
- *VIII. Attach appropriate geologic data on the injection zone including appropriate lithologic detail, geologic name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such sources known to be immediately underlying the injection interval.
- IX. Describe the proposed stimulation program, if any.
- *X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division, they need not be resubmitted).
- *XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.
- XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground sources of drinking water.
- XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form.
- XIV. Certification: I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.
- NAME: _____ Mike McCurdy _____ TITLE: _____ Vice-President _____
- SIGNATURE: _____  _____ DATE: _____ 6/13/2019 _____
- E-MAIL ADDRESS: _____ m.mccurdy@delawareenergy.com _____
- * If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be resubmitted. Please show the date and circumstances of the earlier submittal: _____

III. WELL DATA

A. The following well data must be submitted for each injection well covered by this application. The data must be both in tabular and schematic form and shall include:

- (1) Lease name; Well No.; Location by Section, Township and Range; and footage location within the section.
- (2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined.
- (3) A description of the tubing to be used including its size, lining material, and setting depth.
- (4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used.

Division District Offices have supplies of Well Data Sheets which may be used or which may be used as models for this purpose. Applicants for several identical wells may submit a "typical data sheet" rather than submitting the data for each well.

B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

- (1) The name of the injection formation and, if applicable, the field or pool name.
- (2) The injection interval and whether it is perforated or open-hole.
- (3) State if the well was drilled for injection or, if not, the original purpose of the well.
- (4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations.
- (5) Give the depth to and the name of the next higher and next lower oil or gas zone in the area of the well, if any.

XIV. PROOF OF NOTICE

All applicants must furnish proof that a copy of the application has been furnished, by certified or registered mail, to the owner of the surface of the land on which the well is to be located and to each leasehold operator within one-half mile of the well location.

Where an application is subject to administrative approval, a proof of publication must be submitted. Such proof shall consist of a copy of the legal advertisement which was published in the county in which the well is located. The contents of such advertisement must include:

- (1) The name, address, phone number, and contact party for the applicant;
- (2) The intended purpose of the injection well; with the exact location of single wells or the Section, Township, and Range location of multiple wells;
- (3) The formation name and depth with expected maximum injection rates and pressures; and,
- (4) A notation that interested parties must file objections or requests for hearing with the Oil Conservation Division, 1220 South St. Francis Dr., Santa Fe, New Mexico 87505, within 15 days.

NO ACTION WILL BE TAKEN ON THE APPLICATION UNTIL PROPER PROOF OF NOTICE HAS BEEN SUBMITTED.

NOTICE: Surface owners or offset operators must file any objections or requests for hearing of administrative applications within 15 days from the date this application was mailed to them.

INJECTION WELL DATA SHEET

OPERATOR: Delaware Energy, LLCWELL NAME & NUMBER: Frying Pan SWD # 1WELL LOCATION: 284' FSL & 402' FWL M 14 SECTION 26S TOWNSHIP 36E RANGEWELLBORE SCHEMATIC see attached wellbore sketchWELL CONSTRUCTION DATASurface Casing

Hole Size: 17-1/2" Casing Size: 13-3/8", 54.5#
Cemented with: 500 sx. or ft³
Top of Cement: surface Method Determined: Plan to Circulate

Intermediate Casing


Hole Size: 12-1/4" Casing Size: 9-5/8", 47#, L-80
Cemented with: 2,500' sx. or ft³
Top of Cement: surface Method Determined: Plan to Circulate

Production Casing

Hole Size: 8-1/2" Casing Size: 7-5/8", 39#, P-110
Cemented with: 650 sx. or ft³
Top of Cement: Top of Liner Method Determined: Plan to Circulate to liner top

Total Depth: 16,414'Injection Interval

16,414' feet to 17,414'
(OPEN HOLE)



INJECTION WELL DATA SHEET

Tubing Size: 5.5" BTC x 5.5" Flush Joint Lining Material: Fiber Glass

Type of Packer: Weatherford Arrow Set IX

Packer Setting Depth: 16,364'

Other Type of Tubing/Casing Seal (if applicable): none

Additional Data

1. Is this a new well drilled for injection? XXXXX Yes No
 If no, for what purpose was the well originally drilled? N/A

2. Name of the Injection Formation: Devonian

3. Name of Field or Pool (if applicable): SWD; Devonian

4. Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail, i.e. sacks of cement or plug(s) used. N/A

5. Give the name and depths of any oil or gas zones underlying or overlying the proposed injection zone in this area: _____

Below: none

Next Higher: Delaware 5,314' - 7,514'; Bone Springs 7,514' - 10,539'; Wolfcamp 10,539' - 11,089'; Strawn 11,089' - 12,339'; Atoka 12,339' - 13,139'; Morrow 13,139' - 15,514'

Additional Questions on C-108

VII.

1. Proposed average and maximum daily rate and volume of fluids to be injected;

Average 15,000-20,000 BWPd, Max 25,000 BWPd

2. Whether the system is open or closed;

Open System, Commercial SWD

3. Proposed average and maximum injection pressure;

Average 1,500-2,500 PSI, Max 3,283 PSI

4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and,

Bone Spring, Delaware, and Wolfcamp produced water. No known incompatibility exists with these produced water types and the Devonian. Devonian formation is used as a disposal interval throughout the Delaware Basin for Wolfcamp, Bone Springs, and Delaware produced water. See attached water analysis from Bone Spring, Wolfcamp, and Delaware produced water.

5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).

See attached Lea County Devonian Water Samples

***VIII. Attach appropriate geologic data on the injection zone including appropriate lithologic detail, geologic name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such sources known to be immediately underlying the injection interval.**

The proposed disposal interval is in the Devonian formation 16,414'-17,414'. Devonian is an impermeable organic Shale at the very top (16,014 ft, Woodford Shale) 100ft thick followed by permeable lime, dolomite, and small amount of shale 1000ft thick. There are no fresh water zones underlying the proposed injection zone. Usable water depth is from surface to +/- 175', the water source is older alluvium (Quaternary). All the fresh water wells in the area have an average depth to water of 175ft per State Engineer.

IX. Describe the proposed stimulation program, if any.

60,000 gallons 20% HCL acid job with packer

X. Attach appropriate logging and test data on the well

Mud log will be filed after the well has been drilled. All cased hole and open hole Logs will be filed following drilling operations.

XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.

Attached is a water sample taken from 32.034796, -103.228489

XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground sources of drinking water.

Delaware Energy, L.L.C. has reviewed and examined available geologic and engineering data in the area of interest for the Frying Pan SWD #1 and have found no evidence of faults or other hydrologic connections between Devonian disposal zone and the underground sources of drinking water. Furthermore, there exist many impermeable intervals between the injection interval and the fresh ground water from the top of the Devonian Carbonate and the base of the ground water.

Mike McCurdy

Vice President

6/13/2019

Title

Date

III. WELL DATA

(1) Lease name; Well No.; Location by Section, Township and Range; and footage location within the section.

Frying Pan SWD #1, Sec. 14-T26S-R36E, 284' FSL & 402' FWL, UL M, Lea County, New Mexico

(2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined.

Casing Size	Setting Depth	Sacks of Cement	Hole Size	Top of Cement	Determined
13-3/8"	500'	500	17-1/2"	Surface	CIRC
9-5/8"	10,539'	2500	12-1/4"	Surface	CIRC
7-5/8"	10,339'-16,414'	650	8-1/2"	Liner Top	CIRC & CBL

(3) A description of the tubing to be used including its size, lining material, and setting depth.

5-1/2" BTC X 5-1/2" Flush Joint, Internally Fiber Glass Coated Tubing set 50 to 100ft above open hole

(4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used.

Weatherford Arrow Set 1X injection packer, nickel plated with on/off tool

B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

(1) The name of the injection formation and, if applicable, the field or pool name.

Devonian Formation

Pool Name: SWD (Devonian)

(2) The injection interval and whether it is perforated or open-hole.

16,414' to 17,414' (Open hole)

(3) State if the well was drilled for injection or, if not, the original purpose of the well.

Well is a planned new drill for SWD

(4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations.

None, well is a planned new drill

(5) Give the depth to and the name of the next higher and next lower oil or gas zone in the area of the well, if any.

Next Higher: Delaware 5,314' – 7,514'; Bone Springs 7,514' – 10,539'; Wolfcamp 10,539' – 11,089';
Strawn 11,089' – 12,339'; Atoka 12,339' – 13,139'; Morrow 13,139' – 15,514'

Next Lower: None


Frying Pan SWD # 1

API # PENDING
284' FSL & 402' FWL, Sec. 14, T26S, R36E, UL "M"
LEA COUNTY, NEW MEXICO

ELEVATION:

GL: 2,914'

PROPOSED WELLBORE



DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone (505) 393-8161 Fax: (505) 393-0720

DISTRICT II
511 S. First St., Artesia, NM 88210
Phone (505) 748-1283 Fax: (505) 748-0720

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone (505) 334-8178 Fax: (505) 334-8170

DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone (505) 478-3450 Fax: (505) 478-3450

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised August 1, 2011

Submit one copy to appropriate
District Office

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number	Pool Code 96101	Pool Name SWD; DEVONIAN
Property Code	Property Name FRYING PAN SWD	Well Number 1
OGRID No. 371195	Operator Name DELAWARE ENERGY	Elevation 2914'

Surface Location									
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	14	26 S	36 E		284	SOUTH	402	WEST	LEA

Bottom Hole Location If Different From Surface									
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

SURFACE LOCATION Lat - N 32.036809° Long - W 103.243228° NADSPCE- N 378834.2 E 879131.2 (NAD-83)		N.: 383852.7 E.: 881331.5 (NAD83)		N.: 383878.9 E.: 883968.5 (NAD83)	
		N.: 381188.6 E.: 878707.1 (NAD83)		N.: 378572.5 E.: 881375.6 (NAD83)	
402'		N.: 378546.1 E.: 878732.1 (NAD83)		N.: 378600.1 E.: 884021.3 (NAD83)	

OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: Sarah Presley Date: 6.13.19

Printed Name: Sarah Presley

Email Address: s.presley@delawareenergy.com

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

DATE SURVEYED: FEBRUARY 8, 2019

Date Surveyed: _____

Signature & Seal of Professional Surveyor: [Signature]

Certificate No.: 7977

Basin: FRYING PAN


Scale: 1" = 2000'

WO Num.: 34339


**SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.**

**CFRYING PAN SWD #1
ELEV. - 2914'**

Lat - N 32.036809°
Long - W 103.243228°
NMSPCE- N 378834.2
E 879131.2
(NAD-83)



JAL, NM IS ±6 MILES TO THE NORTHEAST OF LOCATION.



DELAWARE ENERGY

REF: FRYING PAN SWD #1 / WELL PAD TOPO

THE FRYING PAN SWD #1 LOCATED 284' FROM
THE SOUTH LINE AND 402' FROM THE WEST LINE OF
SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST.



N.M.P.M., LEA COUNTY, NEW MEXICO.

**basin
surveys**
focused on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basin-surveys.com

W.O. Number: 34339	Drawn By: J GOAD	Date: 2-15-2018	Survey Date: 2-8-2019	Sheet 1 of 1 Sheets
--------------------	------------------	-----------------	-----------------------	---------------------

**SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.**



DELAWARE ENERGY

REF: FRYING PAN SWD #1 / WELL PAD TOPO


THE FRYING PAN SWD #1 LOCATED 284' FROM
THE SOUTH LINE AND 402' FROM THE WEST LINE OF
SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST.

N.M.P.M., LEA COUNTY, NEW MEXICO.

**basin
surveys**

P.O. Box 1786 (575) 393-7316 - Office
focused on excellence 1120 N. West County Rd. (575) 392-2206 - Fax
in the oilfield Hobbs, New Mexico 88241 basin-surveys.com

W.O. Number: 34339	Drawn By: J GOAD	Date: 2-15-2018	Survey Date: 2-8-2019	Sheet 1 of 1 Sheets
--------------------	------------------	-----------------	-----------------------	---------------------



FRYING PAN SWD #1

Located 284' FSL and 402' FWL
 Section 14, Township 26 South, Range 36 East,
 N.M.P.M., Lea County, New Mexico.

basin
surveys
 focused on excellence
 in the oilfield

P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (575) 393-7316 - Office
 (575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'
 SCALE: 1" = 2000'


W.O. Number: JG 34339

Survey Date: 2-8-2019

YELLOW TINT - USA LAND
 BLUE TINT - STATE LAND
 NATURAL COLOR - FEE LAND



DELAWARE
ENERGY



FRYING PAN SWD #1

Located 284' FSL and 402' FWL
 Section 14, Township 26 South, Range 36 East,
 N.M.P.M., Lea County, New Mexico.

basin
surveys
 focused on excellence
 in the oilfield

P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (575) 393-7316 - Office
 (575) 392-2206 - Fax
 basinsurveys.com

0' 1000' 2000' 3000' 4000'
 SCALE: 1" = 2000'


W.O. Number: JG 34339

Survey Date: 2-8-2019

YELLOW TINT - USA LAND
 BLUE TINT - STATE LAND
 NATURAL COLOR - FEE LAND




DELAWARE
ENERGY



FRYING PAN SWD #1

Located 284' FSL and 402' FWL
 Section 14, Township 26 South, Range 36 East,
 N.M.P.M., Lea County, New Mexico.



P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (575) 393-7316 - Office
 (575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'
 SCALE: 1" = 2000'

W.O. Number: JG 34339



Survey Date: 2-8-2019

YELLOW TINT - USA LAND
 BLUE TINT - STATE LAND
 NATURAL COLOR - FEE LAND



**DELAWARE
 ENERGY**

**SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.**



DELAWARE ENERGY

REF: FRYING PAN SWD #1 / CUT & FILL

THE FRYING PAN SWD #1 LOCATED 284' FROM
THE SOUTH LINE AND 402' FROM THE WEST LINE OF
SECTION 14, TOWNSHIP 26 SOUTH, RANGE 36 EAST.

N.M.P.M., LEA COUNTY, NEW MEXICO.



P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basin-surveys.com

Water Analysis - Disposal Zone – DEVONIAN

NM WAIDS DATA				
S-T-R	FIELD	FORMATION	TDS	CHLRD
24-23S-29E	REMUDA	DEVONIAN	64582	37500
24-23S-29E	REMUDA	DEVONIAN	56922	29000
06-23S-34E	BELL LAKE NORTH	DEVONIAN	71078	42200
34-23S-34E	ANTELOPE RIDGE	DEVONIAN	80187	47900

Water Analysis - Source Zone – BONE SPRING

 BioTech LLC		Laboratory Analysis Endurance		Sample Date: 1/31/2014	
Requested by: T. Ratliff		Jazzmaster 17 State #4H		Lea Co. NM	
Water Analysis Measurements					
Oxygen (mg/L)	1.00	Oil in Water (ppm)	n/a	Calcium (Ca)	mg/L
Carbon Dioxide (mg/L)	809.16	Specific Gravity	1.150	Sodium (Na)	mg/L
Hydrogen Sulfide (mg/L)	0.0	Total Dissolved Solids (TDS)	186.650	Magnesium (Mg)	mg/L
pH	6.7	(mg/L) (Ca)	186.650	Sulfate (SO ₄)	mg/L
Temperature °F	73	Total Hardness (mg/L)	18.000	Iron (Fe)	mg/L
				Manganese (Mn)	mg/L
				Carbonate (CO ₃)	mg/L
				Bicarbonate (HCO ₃)	mg/L
				Chloride (mg/L)	118.500
				Sulfate (SO ₄)	319

Water Analysis - Source Zone - DELAWARE

P 808 1000
WILMINGTON, DELAWARE 19804
PH 383-5274 (20) 383-5400

Marlin Water Laboratories, Inc.
P.O. Box 11219, Midland, TX 79710

DESIGN OF WATER ANALYSES

LABORATORY NO 93293
SAMPLE RECEIVED 9-16-92
RESULTS REPORTED 9-18-92

TO Mr. Joe Small
P.O. Box 11219, Midland, TX 79710

COMPANY Meridian Oil Company
FIELD OR POOL Vildener
Digger, Lake #1

SECTION BLOCK SURVEY COUNTY Lamb STATE NM

SOURCE OF SAMPLE AND DATE TAKEN:
NO 1 Recovered water - taken from Digger Lake #1 9-9-92
NO 2
NO 3
NO 4

REMARKS Release

CHEMICAL AND PHYSICAL PROPERTIES			
	NO 1	NO 2	NO 3
Specific Gravity at 60°F.	1.1492		
pH at 25°C. Sample			
pH at 25°C. Reagent	6.29		
Oil percentage as H ₂ O	1.68		
Super-saturations as CaCO ₃			
Under-saturations as CaCO ₃			
Hardness as CaCO ₃	50.500		
Calcium as Ca	18.000		
Magnesium as Mg	1.336		
Sodium and/or Potassium	68.683		
Sulfate as SO ₄	9.62		
Chloride as Cl	160.618		
Iron as Fe	90.0		
Barium as Ba			
Fluoride as F			
Slime as %			
Total Solids	229.531		
Total Hardness			
Total Dissolved Solids as			
Dissolved Solids			
Hydrogen Sulfide	0.0		
Nonoxidizing Sulfur as S ₂ O ₃	0.053		
Suspended Solids			
Total Solids as Ign			
Volume Filtered as ml			
Total Dissolved Solids @ 180°C.	184.361		



P.O. Box 3394, Midland, Texas 79702
Phone (432) 684-4233 Fax (432) 684-4277

Water Analysis

Code 214744	
Client Information	Sample Information
Delaware Energy County: Lea	Lease/Well: Frying Pan/SWD
Rep: Derrick Boutwell	Sample Point: Date Sampled: 04/09/2019 Date Reported: 04/17/2019

Results

Cations

Ion	Concentration(mg/L)
Barium (as Ba)	0
Calcium (as Ca)	198
Iron (as Fe)	0
Sodium (as Na)	156
Magnesium (as Mg)	228

Other Measurements

Measurement	Value
pH	7.75
SG	1.002
Turbidity	11
CO ₂	
Total Dissolved Solids	1691.000

Anions

Ion	Concentration(mg/L)
Chlorides (as Cl)	832
Sulfate (as SO ₄)	228
Carbonate (as CO ₃)	0
Bicarbonates (as HCO ₃)	49
Sulfide (as S ²⁻)	0


Scaling Indices

Temp(F)	CaCO ₃	CaSO ₄ *2H ₂ O	CaSO ₄	BaSO ₄
80	0.1847	0.0000	0.0000	-27.9166
120	0.5147	0.0000	0.0000	-28.1264
160	0.8907	0.0000	0.0000	-28.2457
200	1.2317	0.0000	0.0000	-28.2937
250	1.5450	0.0000	0.0000	-28.2633

Low = < 0.200, Moderate = 0.200-0.999, High = > 1.00

Comments

Coordinates: 32.034796-103.228489




WELLS – ONE MILE RADIUS

NO WELLS PENETRATE THE DEVONIAN FORMATION IN THE AOR

SECTION 14-T26S-R36E



Frying Pan SWD #1
(Proposed Location)
Delaware Energy, LLC



LEASES – ONE MILE RADIUS

★ Frying Pan SWD #1
Sec. 14-T26S-R36E
Lea Co. NM

Frying Pan SWD #1

LEASES – ONE MILE RADIUS

Section 10, T26S-R36E

Fee

- **Ameredev LLC (Lessee)**
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735
- **Bureau of Land Management**
620 E Greene Street
Carlsbad, NM 88220

Section 11, T26S-R36E

State Lease (B02281)

- **Chevron USA Inc. (Lessee)**
6301 Deauville Blvd.
Midland, TX 79706

Section 13, T26S-R36E

Federal Lease (NMLC 0056927B)

- **Burlington Res Oil & Gas Co LP (Lessee)**
3300 N A St # 6
Midland, TX 79705
- **Bureau of Land Management**
620 E Greene Street
Carlsbad, NM 88220

Section 14, T26S-R36E

State Lease (B02283)

- **Ameredev LLC (Lessee)**
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735

Section 15, T26S-R36E

State Lease (B02283)

- **Ameredev LLC (Lessee)**
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735

Section 22, T26S-R36E

State Leases

- **Ameredev LLC (Lessee)**
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735

Section 23, T26S-R36E

State Leases

- **Ameredev LLC (Lessee)**
5707 Southwest Pkwy. Bldg. 1, Suite 275
Austin, TX 78735

Section 24, T26S-R36E

- **Bureau of Land Management**
620 E Greene Street
Carlsbad, NM 88220

Federal Lease (NMNM 137808)
- **Tap Rock Operating, LLC (lessee)**
602 Park Point Dr. Ste 200
Golden, CO 80401

Frying Pan SWD #1

Location: 284' FSL & 402' FWL

Sec. 14, T-26-S, R-36-E

Estimated Pre-Drill Formation Tops

Top of Salt	1,164'
Base Salt	3,114'
Yates	3,314'
Capitan Reef	3,514'
Delaware Mountain Group	5,314'
Bone Spring/Abo	7,514'
Wolfcamp	10,539'
Strawn	11,089'
Atoka	12,339'
Morrow	13,139'
Barnett	15,089'
Mississippian	15,514'
Woodford	16,014'
Devonian	16,414'

Statement Regarding Seismicity and Well Location (Frying Pan SWD #1)


Historically, the area near the proposed Frying Pan SWD #1 has not seen any major seismic activity. There have been two seismic events (as per public data available on the USGS database) in the area. All events are over 13.0 miles from the proposed SWD location. The most recent event was 13.3 miles to the east on May 3, 2017 and measured 2.6. The other is a group of small seismic events 13.1 miles southeast of the proposed SWD location with the closest event measuring 2.6 on April 26, 1977.

Delaware Energy does not own 2D or 3D seismic data near the proposed SWD location therefore the fault interpretations are based on data obtained from the USGS New Mexico Faults Database (2005) and other published data. Based on these sources the closest fault would be approximately 3.9 miles northeast of the location. A recent technical paper written by Snee and Zoback, "State of Stress in the Permian Basin, Texas and New Mexico: Implications for induced seismicity", was published in the February 2018 edition of The Leading Edge. The study evaluates the strike-slip probability of known faults using FSP analysis. The study predicts that the NW-SE trending fault NE of the location (green) should have a very low probability of being critically stressed resulting in an induced seismicity event. This is due to the relationship of the strike of the fault and the regional S_{hmax} orientation (approx. N 75 deg E) in the area. The exact position of this fault relative to the proposed location, and depth of the target formation, is unknown. Risk of contact with this fault should be reduced due to the distance of the proposed SWD well from the fault (3.9 miles).

The proposed Frying Pan SWD #1 is located well away from the nearest active Devonian SWD or other SWD wells (see map below). The well should meet current OCD and Industry recommended practices.


Kevin J. Schepel
Petrophysical Advisor
kevin.schepel@att.net
214-212-6540

Well Activity, Faulting, and Closest SWD




Modeled After Snee and Zoback (February 2018)

Proximity to Historic Earthquake Activity and Faults



Modeled After Snee and Zoback (February 2018)




Data and Interpretation Disclosure - Although care has been taken to ensure that these data are up to date and accurate, this information and data is being providing as is. The data are what is believed to be the best public data available based on published documents, reports, and information available through the USGS. The user assumes all responsibility and risk for use of the data and interpretations. Users of the data agree not to misuse, add to without permission, or misrepresent the data provided in any way. In no event will the provider of this document be liable to any party for any direct, indirect, incidental, consequential, special or exemplary damages, or lost profit resulting from any use or misuse of this data. Additionally, provider is not liable for any inaccurate data. No person, entity, or user shall use the information in a manner that is in violation of any federal, state, or local law or regulation.

Affidavit of Publication


STATE OF NEW MEXICO
COUNTY OF LEA

I, Daniel Russell, Publisher of the Hobbs News-Sun, a newspaper published at Hobbs, New Mexico, solemnly swear that the clipping attached hereto was published in the regular and entire issue of said newspaper, and not a supplement thereof for a period of 1 issue(s).

Beginning with the issue dated
March 28, 2019
and ending with the issue dated
March 28, 2019.


Publisher


Sworn and subscribed to before me this
28th day of March 2019.


Business Manager

My commission expires

January 29, 2023

(Seal)



This newspaper is duly qualified to publish legal notices or advertisements within the meaning of Section 3, Chapter 167, Laws of 1937 and payment of fees for said

LEGALS

LEGAL NOTICE MARCH 28, 2019

Delaware Energy, L.L.C., 405 N. Marienfeld St. Suite 200, Midland, TX 79701, has filed a form C-108 (Application for Authorization to Inject) with the Oil Conservation Division seeking administrative approval to drill the Frying Pan SWD #1 as a Commercial Salt Water Disposal well.

The Frying Pan SWD #1 is located at 284' FSL and 402' FWL, Unit Letter M, Section 14, Township 26 South, Range 36 East, Lea County, New Mexico. The well will dispose of water produced from oil and gas wells into the Devonian Formation from 16,414' to 17,414' at a maximum rate of 25,000 barrels of water per day at a maximum pressure of 3,283 psi.

Interested parties must file objections or requests for hearing with the Oil Conservation Division, 1220 South St. Francis Dr., Santa Fe, New Mexico 87505, within 15 days.

Additional information can be obtained by contacting Delaware Energy, L.L.C., at (432) 685-7005.
#33949

67114908

00226383

MIKE MCCURDY
DELAWARE ENERGY
405 N. MARIENFELD, STE 250
MIDLAND, TX 79701

7018 0680 0000 0580 7770

U.S. Postal Service
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
Amerodev, LLC
Street and Apt. No., or PO Box No.
5707 Southwest Pkwy. Ste 1-215
City, State, ZIP+4®
Austin, TX 78735
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7794

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
Burlington Resources Oil & Gas Co.
Street and Apt. No., or PO Box No.
3300 North A Street, Ste 6
City, State, ZIP+4®
Midland, TX 79705
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7817

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
Tap Rock Operating, LLC
Street and Apt. No., or PO Box No.
602 Park Point Dr. Ste 200
City, State, ZIP+4®
Golden, CO 80401
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7787

CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
Bureau of Land Management
Street and Apt. No., or PO Box No.
620 E. Greene Street
City, State, ZIP+4®
Carlsbad, NM 88220
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7800

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
Chevron USA Inc.
Street and Apt. No., or PO Box No.
6301 Deauville
City, State, ZIP+4®
Midland, TX 79706
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7824

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

OFFICIAL USE

Certified Mail Fee	\$
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy)	\$
☐ Return Receipt (electronic)	\$
☐ Certified Mail Restricted Delivery	\$
☐ Adult Signature Required	\$
☐ Adult Signature Restricted Delivery	\$
Postage	\$
Total Postage and Fees	\$

Sent To
Frying Pan SWD#1
Postmark Here
JUN 1 3 2019

Sent To
New Mexico State Land Office
Street and Apt. No., or PO Box No.
310 Old Santa Fe Trail
City, State, ZIP+4®
Santa Fe, NM 87501
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7018 0680 0000 0580 7831

U.S. Postal Service	
CERTIFIED MAIL® RECEIPT	
<i>Domestic Mail Only</i>	
For delivery information, visit our website at www.usps.com ®.	
OFFICIAL USE	
Certified Mail Fee	Frying Pan SWD#1 Postmark Here JUN 13 2019
\$	
Extra Services & Fees (check box, add fee as appropriate)	
☐ Return Receipt (hardcopy) \$	
☐ Return Receipt (electronic) \$	
☐ Certified Mail Restricted Delivery \$	
☐ Adult Signature Required \$	
☐ Adult Signature Restricted Delivery \$	
Postage	
\$	
Total Postage and Fees	
\$	
Sent To	
State of New Mexico OCD District 1	
Street and Apt. No., or P.O. Box No.	
1625 N. French Dr.	
City, State, ZIP+4®	
Hubbs, NM 88240	
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions	

Delaware Energy, L.L.C.
405 N. Marienfeld, Suite 200
Midland, TX 79701
Office: (432) 685-7005

June 13, 2019

Surface Owner / Offset Operators

Re: Notification of Application for Authorization to Inject
Frying Pan SWD #1 Well

Ladies and Gentlemen:


Delaware Energy, LLC is seeking administrative approval to utilize the proposed Frying Pan SWD #1 as a commercial Salt Water Disposal well. As required by the New Mexico Oil Conservation Division Rules, we are notifying you of the following proposed salt water disposal well. This letter is a notice only. No action is required unless you have questions or objections.

<u>Well:</u>	Frying Pan SWD #1
<u>Proposed Disposal Zone:</u>	Devonian Formation (from 16,414' - 17,414')
<u>Location:</u>	284' FSL & 402' FWL, UL M, Sec. 14, T26S, R36E, Lea Co., NM
<u>Applicants Name:</u>	Delaware Energy, L.L.C.
<u>Applicants Address:</u>	405 N. Marienfeld, Suite 200, Midland, TX 79701

This application for water disposal well will be filed with the New Mexico Oil Conservation Division. If they determine the application complies with the applicable regulations, then it will be approved. The New Mexico Conservation Division address is 1220 South St. Francis Dr., Santa Fe, NM 87505. And their phone number is 505-476-3460.

Please call Sarah Presley with Delaware Energy, LLC if you have any questions at 432-685-7005.

Sincerely,



Sarah Presley