

AP - 053

**HYDRO-
GEOLOGICAL
REPORT**

MARCH 2012

**HYDROGEOLOGY OF
NEW MEXICO SALT WATER DISPOSAL COMPANY SPILL SITES
SECTIONS 15, 21 & 22, TOWNSHIP 10 SOUTH, RANGE 34 EAST
LEA COUNTY, NEW MEXICO**

**Prepared for: Whole Earth Environmental, Inc.
2103 Arbor Cove
Katy, Texas 77494**

**Prepared by: Atkins Engineering Associates, Inc.
P.O. Box 3156
Roswell, New Mexico 88202-3156
(575) 624-2420**

Date: March 2012

Background & Scope

New Mexico Salt Water Disposal Company operates several produced water (brine) transmission pipelines in Lea County, New Mexico. Three produced water spill/leakage sites associated with the operation of these pipelines are located in Sections 15, 21 and 22 of Township 10 South, Range 34 East, N.M.P.M. in Lea County, New Mexico, approximately 15 miles northwest of Tatum, New Mexico (study area). The spills sites are known as *Station 11*, *6-Inch Leak (aka Johnson Leak)*, and *New Spill*. The site locations are shown on attached Figures 1 and 2.

The scope of this report is to characterize the subsurface hydrogeology for the study area, specifically a layer of fat yellow clay, and analyze said clay layer's ability to prevent spilled produced water from impacting the regional water table.

Study Area Hydrogeology

Hydrogeologic data for the study area is limited. Hydrogeologic investigations varying in size and scope have occurred at each of the subject spill sites. Select documents from investigations at each of the sites are included as Appendices 1, 2 and 3.

Reports by Havenor (2009) and Barnhill (2007) describe the hydrogeology at the Station 11 site as evidenced by several soil borings drilled at the site. The geology is characterized by approximately 50 to 60 feet of Quaternary sand, silt and caliche and Tertiary Ogallala sand, underlain by Cretaceous age sediments. The upper layer of the Cretaceous age sediments consists of approximately 30 to 40 feet of fat yellow clay. Havenor (2009) also describes this fat clay layer as shale and an aquitard or aquiclude.

Five soil borings drilled at the 6-Inch Leak site and two soil borings at the New Spill site show similar geologic layers and depths as reported for the Station 11 site. These geologic layers appear to be connected across the study area. The location of the various soil borings and monitoring wells are shown on attached Figures 2 through 6. Copies of all soil boring/monitoring well logs are found in the appendices. Figure A below shows geologic cross-section A-B-C, which emphasizes the disposition of the upper Cretaceous yellow clay across the study area.

Three separate zones of groundwater appear in the study area: the regional shallow aquifer and two upper perched zones. Water level data for the regional shallow aquifer is available for the Station 11 and 6-Inch Leak sites. Three soil borings at Station 11 were completed as monitoring wells MW-1, M-2 and MW-3 so as to draw water from this aquifer. One unnamed monitoring well at the 6-Inch Leak site was completed in the regional shallow aquifer as well, but due to imprecise location information, the well is not shown on the attached figures. It is understood to be near or adjacent to the 6-Inch Leak site's MW-3. All other soil borings within the study area do not reach this aquifer. Figure 3 shows groundwater elevation contours for the regional aquifer using water level data presented in Barnhill (2007), which show groundwater to be relatively flat with a slight downward gradient towards the northeast at the Station 11 site. Upon completion the 6-Inch Leak site's regional water table monitoring well in September, 2011, the water level in said well was measured at 102.05 feet below top of casing; the water table elevation in the




Figure A Geologic cross section A-B-C depicting upper Cretaceous fat yellow clay in relationship to the regional water table.

well at that time is estimated to have been 4,095 feet, which is similar to the elevations noted for Station 11 in 2007. Elevations of nearby lakes shown on USGS topographic maps (Figure 1) are also comparable to the regional water table elevations at Station 11 and 6-Inch Leak sites; it is likely that these lakes are occurring where the regional water table is exposed to land surface. Figure A below also gives an estimation of the regional water table elevation across the study area.

Evidence of the upper perched groundwater zone is found at two locations at the Station 11 site: monitoring well MW-5 and recovery well RW-1, which are completed to depths of 30 and 33 feet, respectively. According to Barnill (2007) recovery well RW-1 was drilled at nearly the same location as an earlier soil boring SB-4A and screened at depth where this upper perched water zone was noted in SB-4A. However, after drilling recovery well RW-1, very little water was found at the well on multiple occasions. Havenor (2007) reports the water thickness at MW-5 to be 0.9 of a foot. It should be noted that MW-2 was drilled between MW-5 and RW-1 and found no perched water above the regional groundwater table. Boring logs for MW-5 and SB-4A show the perched water to occur on top of brown clay. This is likely a localized clay lens within the Ogallala formation. Spilled produced water at the site appears to be the source of this groundwater zone.

Evidence of the lower perched groundwater zone is found across the study area. Numerous soil borings show a sandy layer at the bottom of the Ogallala formation varying from damp to wet (saturated) located directly on top of the fat yellow clay discussed above. In contrast to the clay lenses supporting the upper perched groundwater zone, the yellow clay layer supporting this lower perched groundwater zone appears to at least span across the study area. Boring logs at the Station 11 and New Spill sites show this lower perched groundwater zone to have a thickness of approximately 3 feet. At the Station 11 site the occurrence of the perched water appears limited to the area around monitoring wells MW-1, MW-6 and MW-4, as perched groundwater was not found during the drilling of MW-2 and MW-3. At the other sights it is not known how widespread this groundwater zone may be. Figures 4 and 5 show the estimated thickness of the lower perched groundwater zone at the Station 11 and New Spill sites.

Groundwater elevation data within the lower perched groundwater zone are available at the 6-Inch Leak site and shown as a contour map in Figure 6. The figure shows the groundwater zone to be mounded, with the highest point at monitoring well MW-2, which based on soil conductivity mapping appears to be at the center of the spill at this site. Coupling the measured water level data with boring log information, the thickness of the lower perched groundwater zone at this site appears to be from 6 to 14 feet. However, it should be noted that available boring logs for the 6-Inch Leak and New Spill sites were prepared by the well driller as opposed to the Station 11 site logs, which were prepared by a geologist. Well driller logs are likely not nearly as precise in establishing depths to varying geologic layers. The gradient of the lower perched groundwater at the 6-Inch Leak site indicates that the perched groundwater dissipates a short distance from the spill site.

Elsewhere in Lea County the Ogallala formation does carry water and in many places is the main shallow ground water aquifer. However, this does not appear to be the case in the study area. Tillery's (2008) Figure 2 depicts the saturated thickness of the High Plains (Ogallala) Aquifer across Lea County. The study area is located in a region described as having "variable or no saturation." Attached Figure 7 of this report shows the location of the study area within Tillery's Figure 2. The study area is also excluded from the domain of groundwater models of the Ogallala aquifer within Lea County by Musharrafieh and Chudnoff (1999) and McAda (1984). Very little recharge if any occurs in the study area. Annual recharge estimates for the Ogallala aquifer in Lea County range from 0.25 to 1 inch per year (Tillery, 2008, and Musharrafieh and Chudnoff, 1999). The New Mexico Office of the State Engineer's version of the model by Musharrafieh and Chudnoff (1999) used for water rights administration incorporates zero recharge in predicting future water level declines.

Groundwater analyses for chloride across the study area show samples from the perched groundwater zones to be of markedly poorer quality than those from the regional aquifer, as shown in Table 1.

The lower perched groundwater zones occurring at the three spill sites within the study area appear isolated from one another and sourced by the spilled produced water, with no connection to the regional aquifer. Some thin lenses of groundwater saturation may occur naturally in the area within the Ogallala formation, but would not be a significant water resource. Produced water contact with these lenses would be inconsequential.

Table 1 Groundwater chloride concentrations. *Assumed; insufficient data. ^Sampled during drilling.

Site	Sample Date	Well Name(s)	Groundwater Zone	Chloride (mg/L)
Station 11	June 13, 2007	MW-1^	Lower Perched	21,000
	July 9, 2007	MW-1	Regional Aquifer	550
		MW-2	Regional Aquifer	560
		MW-3	Regional Aquifer	620
		RW-1	Upper Perched	50,000
	June 21, 2011	MW-1	Regional Aquifer	230
		MW-2	Regional Aquifer	200
		MW-3	Regional Aquifer	200
		MW-4	Lower Perched	36,000
		MW-5	Upper Perched	18,800
		MW-6	Lower Perched	22,400
6-Inch Leak	May 20, 2011	MW-1, NW Background, West Background	Lower Perched	17,000
		MW-2, E. Leak Source, East 2"	Lower Perched	64,000
New Spill	November 18, 2011	B4	Lower Perched	19,200
Windmills	July 9, 2007	Sand Hill Windmill, NW Windmill	Regional Aquifer*	390
		Lucky Windmill, SW Windmill	Regional Aquifer*	460
	May 20, 2011	Sand Hill Windmill, NW Windmill	Regional Aquifer*	530
		Lucky Windmill, SW Windmill	Regional Aquifer*	530

Analysis of Produced Water Migration through Fat Yellow Clay

As discussed above, the occurrence of perched groundwater beneath each of the spill sites appears to be the result of produced water spills that appear to have been contained, at least in the present, by a layer of fat yellow clay at the top of the Cretaceous formation. Lab characterizations of this clay layer show it to be highly impermeable. Lab results presented by Barnhill (2007) for a soil sample collected at a depth interval of 65.6 to 66.1 feet during the drilling of monitoring well MW-1 at the Station 11 site show the saturated permeability, K_{sat} , to be 5.2×10^{-8} cm/sec. In anticipation of developing a numerical vadose zone model, a sample of the fat yellow clay was collected at a depth interval of 73 to 74 feet during the drilling of soil boring B4 at the New Spill site. The lab analyses report for this sample is found in Appendix 3. (B4 is referred to as Crossroads/Johnson Test Hole No. 2 in the laboratory report and Bore 2 on the attached boring log in Appendix 3.) The lab created three sub-samples, which were found to have K_{sat} values of 1.3×10^{-7} , 2.8×10^{-5} , and 1.4×10^{-6} cm/sec. In a telephone conversation with Joleen Hines, author of the laboratory analyses report, Ms. Hines indicated that the lab also analyzed a fourth sub-sample for K_{sat} , due to the variability in the results of the other three sub-samples, and found its value to be on the order of 10^{-9} cm/sec. She further indicated that the lower values are likely more reasonable, as the higher values could be the result of slight imperfections in the testing apparatus. The chart on Page 31 of the lab report shows the relative hydraulic conductivity as a fraction of K_{sat} for varying moisture contents. It can be seen that as the moisture content moves away from saturation the hydraulic conductivity decreases exponentially from the already very low saturated hydraulic conductivity value.

In order to determine the potential for spilled produced water to migrate through this clay layer where it could come in contact with the regional aquifer, a one-dimensional vadose zone numerical model was created and analyzed with HYDRUS-1D (Simunek and others, 2009), a

software package used for analysis of water flow and solute transport in variably saturated porous media. The software package incorporates the one-dimensional finite element model HYDRUS developed by the USDA-ARS U.S. Salinity Laboratory. A one-dimensional model was selected due to the limited information as to the horizontal extent of perched produced water. Among other things, the model computes flux and cumulative flux over time at the bottom of a soil profile, which can be used to predict the how long it will take for the perched produced water to migrate through the fat yellow clay layer.

The model represents the soil from ground surface to the bottom of the fat yellow clay layer in question. The stratigraphy is simplified into two materials – the upper mixture of sand, silts and clays of the Quaternary and Tertiary formations and the fat yellow clay layer. Representative thicknesses of 55 feet for the upper soil mixture and 30 feet for the fat yellow clay are used.

For the upper material, input parameters consistent with the soil properties of a typical sandy loam are provided by the HYDRUS software package. The input parameters for the clay were determined by lab analyses of a soil sample collected during the drilling of B4 at the New Spill site as discussed above. Table 2 below is a summary of the model input parameters selected for the model.

Table 2 Hydrus model input parameters

Parameter	HYDRUS “Sandy Loam”	Fat Yellow Clay
Residual soil water content, θ_r (%)	0.065	0.00
Saturated soil water content, θ_s (%)	0.40	0.41
α (cm^{-1})	0.075	0.00025
n (dimensionless)	1.89	1.30
Saturated permeability, K_{sat} (cm/sec)	0.0012272	1.3×10^{-7}

The upper boundary condition is atmospheric and the lower boundary condition is free drainage. The modeled initial soil moisture for the fat yellow clay is 33% for upper 10 feet, which is the average of the lab-reported moisture contents for the sample from B4, and 15% for the lower 20 feet. Boring logs in the study area show the fat yellow clay to be dry except where in contact with perched produced water. Two perched produced water thickness conditions were simulated. Simulation 1 is for a 5-foot perched produced water saturated thickness: for the upper soil mixture, the initial moisture content is 15% from surface down to 50 feet, and 41% (saturated) from 50 to 55 feet. Simulation 2 is for a 10-foot perched produced water saturated thickness: for the upper soil mixture, the initial moisture content is 15% from surface down to 45 feet, and 41% (saturated) from 45 to 55 feet. The model time is 10,000 years.

Figure B below gives the model-computed bottom flux over time and cumulative bottom flux over time, respectively, for Simulations 1 and 2. As the model is one-dimensional, flux has the dimensions of volume per unit area per unit time ($\text{L}^3/\text{L}^2/\text{T}$) and cumulative flux has the dimension of volume per unit area (L^3/L^2). Negative numbers indicate a downward flux out of the bottom of the fat yellow clay.




Figure C Model-computed flux and cumulative flux through the bottom of the fat yellow clay over time.


The bottom flux is the rate at which water is exiting the bottom of the fat yellow clay. In order to determine if the bottom flux includes any of the perched produced water, one must examine the cumulative bottom flux. The cumulative bottom flux can be described as the amount of water that would exit the fat yellow clay after a given period of time. These amounts can be divided by the moisture content to determine a thickness of the fat yellow clay layer through which moisture is displaced by the perched produced water. Once the thickness of displaced moisture equals the thickness of the fat yellow clay, the bottom flux begins to be perched produced water. In other words, perched produced water begins passing through or exiting the fat yellow clay after displacing all moisture in that clay. The 10 feet of fat yellow clay with 33% moisture content would have an equivalent water amount of $3.3 \text{ ft}^3/\text{ft}^2$, while the 20 feet of fat yellow clay with 15% moisture content would have an equivalent water amount of $3 \text{ ft}^3/\text{ft}^2$, for a total of $6.3 \text{ ft}^3/\text{ft}^2$ of water that must be displaced before the perched produced water begins exiting the bottom of the fat yellow clay. Cumulative fluxes at Year 10,000 were computed as 4.57 and $5.88 \text{ ft}^3/\text{ft}^2$, respectively, in Simulations 1 and 2. In both cases, after 10,000 years, the model-predicted flux of perched produced water through the fat yellow clay layer is zero.

As with any model, the more the model differs from actual conditions, the less useful it becomes. A limitation of the one-dimensional model is that flow of the perched produced water is limited to the vertical direction. Due to the considerable difference in permeability of the sand, silt and clay mixture and the permeability of the fat yellow clay, there could be a significant amount of horizontal movement of the perched produced water, which would eventually dissipate into a saturated layer much thinner than the 5 and 10 feet thicknesses simulated. As shown by a comparison of the two different perched produced water thicknesses simulated, the less saturated

thickness of perched produced water, the less downward movement of moisture out of the clay. Any reduction in the produced water saturated thickness due to horizontal movement would reduce the potential for its passing through the fat yellow clay.

Summary

The study area consists of three produced water spill sites that have contributed to the presence of perched groundwater, separate from a regional aquifer. A layer of fat yellow clay is present across the study area that acts as an aquitard, preventing the migration of perched produced groundwater from reaching the regional aquifer. Chloride data from groundwater samples across the site show the perched groundwater to not be in communication with the regional aquifer. A one-dimensional vadose zone numerical model, created to simulate the migration of perched groundwater through the fat yellow clay, shows under simulations of 5 and 10 feet of perched produced water on a 30-foot layer of fat yellow clay that no perched produced water is predicted to pass through the clay layer after 10,000 years.


James Reese, PE

3/22/12
Date

List of Attachments

Figure 1 – Area Map & Spill Sites

Figure 2 – Detailed Area Map

Figure 3 – Regional Aquifer at Station 11 Site

Figure 4 – Perched Produced Water Thickness at New Spill Site

Figure 5 – Perched Produced Water Thickness at Station 11 Site

Figure 6 – Perched Produced Water Surface at 6-Inch Leak Site (aka Johnson Leak)

Figure 7 – Detailed Area Map (Figure 2) Location Overlay on USGS SIM 3044


Appendix 1 – Select documents related to the Station 11 site

Appendix 2 – Select documents related to the 6-Inch Leak (aka Johnson Leak) site

Appendix 3 – Select documents related to the New Spill site

References

- Barnhill, Clayton, 2007, Abatement Plan / Monitor Well Installation Report for New Mexico Salt Water Disposal Company, Inc., unpublished report.
- Havenor, Kay, 2009, Geological and Hydrgeological Evaluation of Borings and Monitor Wells at and around New Mexico Salt Water Disposal Co., Inc., Station 11, unpublished report.
- McAda, Douglas P., 1984, Projected water-level declines in the Ogallal aquifer in Lea County, New Mexico, U.S. Geological Survey Water-Resources Investigations Report 84-4062.
- Musharrafieh, Ghassan and Mustafa Chudnoff, 1999, Numerical Simulation of Groundwater Flow for Water Rights Administration in the Lea County Underground Water Basin New Mexico, New Mexico Office of the State Engineer Technical Report 99-1.
- Simunek, J., M. Sejna, H. Saito, M. Sakai, and M. Th. van Genuchten, 2009, The HYDRUS-1D Software Package for Simulating the One-Dimensional Movement of Water, Heat, and Multiple Solutes in Variably-Saturated Media.
- Stephens, Daniel B., 1996, Vadose Zone Hydrology.
- Tillery, Anne, 2008, Currenr (2004-07) Conditions and Changes in Ground-Water Levels from Predevelopment to 2007, Southern High Plains Aquifer, Southeast New Mexico – Lea County Underground Water Basin, U.S. Geological Survey Scientific Investigations Map 3044.



Atkins
ENGINEERING ASSOCIATES INC.


0 2,000 4,000 8,000 Feet


Topo Basemap: USGS 7.5' Quad sheets
Lane Salt Lake & Johnson Ranch



Figure 1 Area Map & Spill Sites
Salt Water Disposal Company
Secs. 15, 21 & 22, Township 10S, Range 34 E

March 2012





Legend

- Recovery or Monitoring Well
- Regional Aquifer Water Table Elevation Contour - July 2007 (ft)

Basemap: Soil Conductivity provided by Whole Earth Environmental

Atkins
ENGINEERING ASSOCIATES INC.


0 50 100 200
Feet



**Figure 3 Regional Aquifer at Station 11 Site
Salt Water Disposal Company
Sec. 21, Township 10S, Range 34 E**

March 2012

NMSWD 1RP-2743
Bore Locations



Legend

- Soil Boring
- Estimated 3-ft Perched Produced Water Thickness Contour

Basemap: Soil Conductivity provided by Whole Earth Environmental



0 50 100 200
Feet




**Figure 4 Perched Produced Water Thickness at
New Spill Site - Salt Water Disposal Company
Sec. 21, Township 10S, Range 34 E**

March 2012

NMSWD SIMANOLA MAIN ST. #11
EM38 SURVEY WITH SITE INFO

white line lease road
red dashed lines batt. Fence
red small dotted line pit area north of line
blue dots mws/#
black dashed line targa p/l
light blue dashed line line to st. 28 swd



Legend

- Recovery Well or Monitoring Well (Appx. Perched Produced Water Thickness)
- - - Estimated 3-ft Perched Produced Water Thickness Contour

Basemap: Soil Conductivity provided by Whole Earth Environmental


Atkins
ENGINEERING ASSOCIATES INC.

0 50 100 200
Feet




**Figure 5 Perched Produced Water Thickness at
Station 11 Site - Salt Water Disposal Company
Sec. 21, Township 10S, Range 34 E**

March 2012



Note: Perched ground water elevation contours determined from monitoring well and water level data shown on survey of January 2011 by Basin Surveys, adjusted to NVD27 using reported MW-3 ground elevation and USGS 7.5' quad sheet topo Johnson Ranch 4195' contour next to the MW-3 location. A comparison of driller's logs for the monitoring well soil borings with water level data indicates the perched produced water thickness to vary from 6 to 14 feet.

Basemap: Soil Conductivity provided by Whole Earth Environmental



Appendix 1

Select documents related to the Station 11 site

July 14, 2011

ROY R. RASCON

WHOLE EARTH ENVIRONMENTAL, INC.

2103 ARBOR COVE

KATY, TX 77494

RE: NMSWD STA. #11

Enclosed are the results of analyses for samples received by the laboratory on 06/23/11 9:47.

Cardinal Laboratories is accredited through Texas NELAP for:

Method SW-846 8021	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method SW-846 8260	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method TX 1005	Total Petroleum Hydrocarbons

Certificate number T104704398-08-TX. Accreditation applies to solid and chemical materials and non-potable water matrices.


Cardinal Laboratories is accredited through the State of Colorado Department of Public Health and Environment for:

Method EPA 552.2	Haloacetic Acids (HAA-5)
Method EPA 524.2	Total Trihalomethanes (TTHM)
Method EPA 524.4	Regulated VOCs (V2, V3)

Accreditation applies to public drinking water matrices.

This report meets NELAP requirements and is made up of a cover page, analytical results, and a copy of the original chain-of-custody. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Celey D. Keene

Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson


Sample ID: RW #1 (H101296-01)

Bicarbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	190	5.00	06/28/2011	ND	976	97.6	1000	0.913	
Bromide, 4500 Br		mg/kg	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	118	12.5	07/12/2011	ND	0.580	116	0.500		
BTX 8260B		mg/L	Analyzed By: CMS						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	
Surrogate: Dibromofluoromethane		131 %	80-120						
Surrogate: Toluene-d8		90.8 %	80-120						
Surrogate: 4-Bromofluorobenzene		77.6 %	80-120						
Calcium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	6090	100	07/06/2011	ND	5.49	110	5.00	0.545	
Carbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson

Sample ID: RW #1 (H101296-01)
Chloride, SM4500Cl-B
mg/L
Analyzed By: HM

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Chloride	50000	4.00	06/28/2011	ND	112	112	100	0.00	

Conductivity 120.1
uS/cm
Analyzed By: HM

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Conductivity	150000	1.00	06/24/2011	ND	1430	101	1410	0.00	

Magnesium, 200.7
mg/L
Analyzed By: CK

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Magnesium	786	100	07/06/2011	ND	27.9	112	25.0	0.358	

pH
pH Units
Analyzed By: HM

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
pH	6.66	0.100	06/24/2011		7.01	100	7.00	0.300	

Potassium, 200.7
mg/L
Analyzed By: CK

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Potassium	<100	100	07/06/2011	ND	10.8	108	10.0	7.14	

Sodium, 200.7
mg/L
Analyzed By: CK

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Sodium	20600	100	07/06/2011	ND	9.01	111	8.10	0.553	

Sulfate 375.4
mg/L
Analyzed By: HM

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Sulfate	1140	10.0	06/27/2011	ND	40.1	100	40.0	1.61	


TDS 160.1
mg/L
Analyzed By: HM

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
---------	--------	-----------------	----------	--------------	----	------------	---------------	-----	-----------

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: RW #1 (H101296-01)

TDS 160.1		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
TDS	75300	5.00	06/27/2011	ND	229	95.4	240	6.45	
Total Alkalinity 310.1M		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Total	156	4.00	06/28/2011	ND	800	97.6	820	1.12	

Cardinal Laboratories

* = Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson

Sample ID: MW #1 (H101296-02)

Bicarbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	239	5.00	06/28/2011	ND	976	97.6	1000	0.913	

Bromide, 4500 Br		mg/kg	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	2.76	0.500	07/12/2011	ND	0.580	116	0.500		

BTX 8260B		mg/L	Analyzed By: CMS						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	

Surrogate: Dibromofluoromethane 146 % 80-120

Surrogate: Toluene-d8 93.4 % 80-120

Surrogate: 4-Bromofluorobenzene 81.0 % 80-120


Calcium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	48.2	5.00	07/06/2011	ND	5.49	110	5.00	0.545	

Carbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson


Sample ID: MW #1 (H101296-02)

Chloride, SM4500Cl-B		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	230	4.00	06/28/2011	ND	112	112	100	0.00		
Conductivity 120.1		uS/cm		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Conductivity	1650	1.00	06/24/2011	ND	1430	101	1410	0.00		
Magnesium, 200.7		mg/L		Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Magnesium	11.8	5.00	07/06/2011	ND	27.9	112	25.0	0.358		
pH		pH Units		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
pH	8.06	0.100	06/24/2011		7.01	100	7.00	0.300		
Potassium, 200.7		mg/L		Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Potassium	5.43	5.00	07/06/2011	ND	10.8	108	10.0	7.14		
Sodium, 200.7		mg/L		Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sodium	299	5.00	07/06/2011	ND	9.01	111	8.10	0.553		
Sulfate 375.4		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sulfate	320	10.0	06/27/2011	ND	40.1	100	40.0	1.61		
TDS 160.1		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #1 (H101296-02)

TDS 160.1		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
TDS	962	5.00	06/27/2011	ND	229	95.4	240	6.45		
Total Alkalinity 310.1M		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Total	196	4.00	06/28/2011	ND	800	97.6	820	1.12		

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celest D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #2 (H101296-03)

Bicarbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	378	5.00	06/28/2011	ND	976	97.6	1000	0.913	
Bromide, 4500 Br		mg/kg	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	3.27	0.500	07/12/2011	ND	0.580	116	0.500		
BTX 8260B		mg/L	Analyzed By: CMS						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	
Surrogate: Dibromofluoromethane		146 %	80-120						
Surrogate: Toluene-d8		93.9 %	80-120						
Surrogate: 4-Bromofluorobenzene		80.2 %	80-120						
Calcium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	47.0	5.00	07/06/2011	ND	5.49	110	5.00	0.545	
Carbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson


Sample ID: MW #2 (H101296-03)

Chloride, SM4500Cl-B		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	200	4.00	06/28/2011	ND	112	112	100	0.00		
Conductivity 120.1		uS/cm	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Conductivity	1580	1.00	06/24/2011	ND	1430	101	1410	0.00		
Magnesium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Magnesium	10.6	5.00	07/06/2011	ND	27.9	112	25.0	0.358		
pH		pH Units	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
pH	8.07	0.100	06/24/2011		7.01	100	7.00	0.300		
Potassium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Potassium	8.29	5.00	07/06/2011	ND	10.8	108	10.0	7.14		
Sodium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sodium	294	5.00	07/06/2011	ND	9.01	111	8.10	0.553		
Sulfate 375.4		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sulfate	382	10.0	06/27/2011	ND	40.1	100	40.0	1.61		
TDS 160.1		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #2 (H101296-03)

TDS 160.1		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
TDS	919	5.00	06/27/2011	ND	229	95.4	240	6.45	
Total Alkalinity 310.1M		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Total	310	4.00	06/28/2011	ND	800	97.6	820	1.12	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson

Sample ID: MW #3 (H101296-04)

Bicarbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	161	5.00	06/28/2011	ND	976	97.6	1000	0.913	

Bromide, 4500 Br		mg/kg	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	4.10	0.500	07/12/2011	ND	0.580	116	0.500		

BTX 8260B		mg/L	Analyzed By: CMS						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	

Surrogate: Dibromofluoromethane 140 % 80-120

Surrogate: Toluene-d8 92.5 % 80-120

Surrogate: 4-Bromofluorobenzene 77.3 % 80-120


Calcium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	65.0	5.00	07/06/2011	ND	5.49	110	5.00	0.545	

Carbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #3 (H101296-04)

Chloride, SM4500Cl-B		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	200	4.00	06/28/2011	ND	112	112	100	0.00		
Conductivity 120.1		uS/cm	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Conductivity	1840	1.00	06/24/2011	ND	1430	101	1410	0.00		
Magnesium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Magnesium	14.7	5.00	07/06/2011	ND	27.9	112	25.0	0.358		
pH		pH Units	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
pH	7.92	0.100	06/24/2011		7.01	100	7.00	0.300		
Potassium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Potassium	<5.00	5.00	07/06/2011	ND	10.8	108	10.0	7.14		
Sodium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sodium	341	5.00	07/06/2011	ND	9.01	111	8.10	0.553		
Sulfate 375.4		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sulfate	749	10.0	06/27/2011	ND	40.1	100	40.0	1.61		
TDS 160.1		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #3 (H101296-04)

TDS 160.1		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
TDS	1110	5.00	06/27/2011	ND	229	95.4	240	6.45	
Total Alkalinity 310.1M		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Total	132	4.00	06/28/2011	ND	800	97.6	820	1.12	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson

Sample ID: MW #4 (H101296-05)

Bicarbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	83.0	5.00	06/28/2011	ND	976	97.6	1000	0.913	

Bromide, 4500 Br		mg/kg	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	101	12.5	07/12/2011	ND	0.580	116	0.500		

BTX 8260B		mg/L	Analyzed By: CMS						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	

Surrogate: Dibromofluoromethane 134 % 80-120

Surrogate: Toluene-d8 91.0 % 80-120

Surrogate: 4-Bromofluorobenzene 78.8 % 80-120


Calcium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	5310	100	07/06/2011	ND	5.49	110	5.00	0.545	

Carbonate 310.1M		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson


Sample ID: MW #4 (H101296-05)

Chloride, SM4500Cl-B		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	36000	4.00	06/28/2011	ND	112	112	100	0.00		
Conductivity 120.1		uS/cm	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Conductivity	96200	1.00	06/24/2011	ND	1430	101	1410	0.00		
Magnesium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Magnesium	687	100	07/06/2011	ND	27.9	112	25.0	0.358		
pH		pH Units	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
pH	6.63	0.100	06/24/2011		7.01	100	7.00	0.300		
Potassium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Potassium	<100	100	07/06/2011	ND	10.8	108	10.0	7.14		
Sodium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sodium	13500	100	07/06/2011	ND	9.01	111	8.10	0.553		
Sulfate 375.4		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sulfate	466	10.0	06/27/2011	ND	39.2	98.0	40.0	1.70		
TDS 160.1		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #4 (H101296-05)

TDS 160.1		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
TDS	52500	5.00	06/27/2011	ND	229	95.4	240	6.45		
Total Alkalinity 310.1M		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Total	68.0	4.00	06/28/2011	ND	800	97.6	820	1.12		

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #5 (H101296-06)

Bicarbonate 310.1M		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Bicarbonate	102	5.00	06/28/2011	ND	976	97.6	1000	0.913		
Bromide, 4500 Br		mg/kg	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Bromide	52.8	10.0	07/12/2011	ND	0.580	116	0.500			
BTX 8260B		mg/L	Analyzed By: CMS							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71		
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46		
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52		
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78		
Surrogate: Dibromofluoromethane		135 %	80-120							
Surrogate: Toluene-d8		90.3 %	80-120							
Surrogate: 4-Bromofluorobenzene		82.0 %	80-120							
Calcium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Calcium	1820	50.0	07/06/2011	ND	5.49	110	5.00	0.545		
Carbonate 310.1M		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND						

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #5 (H101296-06)

Chloride, SM4500Cl-B		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	18800	4.00	06/28/2011	ND	112	112	100	0.00		
Conductivity 120.1		uS/cm	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Conductivity	39800	1.00	06/24/2011	ND	1430	101	1410	0.00		
Magnesium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Magnesium	198	50.0	07/06/2011	ND	27.9	112	25.0	0.358		
pH		pH Units	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
pH	7.28	0.100	06/24/2011		7.01	100	7.00	0.300		
Potassium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Potassium	<50.0	50.0	07/06/2011	ND	10.8	108	10.0	7.14		
Sodium, 200.7		mg/L	Analyzed By: CK							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sodium	6540	50.0	07/06/2011	ND	9.01	111	8.10	0.553		
Sulfate 375.4		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Sulfate	389	10.0	06/27/2011	ND	39.2	98.0	40.0	1.70		
TDS 160.1		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #5 (H101296-06)

TDS 160.1		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
TDS	22000	5.00	06/27/2011	ND	229	95.4	240	6.45		
Total Alkalinity 310.1M		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Total	84.0	4.00	06/28/2011	ND	800	97.6	820	1.12		

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson

Sample ID: MW #6 (H101296-07)

Bicarbonate 310.1M **mg/L** **Analyzed By: HM**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Bicarbonate	24.4	5.00	06/28/2011	ND	976	97.6	1000	0.913	

Bromide, 4500 Br **mg/kg** **Analyzed By: HM**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	92.4	12.5	07/12/2011	ND	0.580	116	0.500		

BTEX 8260B **mg/L** **Analyzed By: CMS**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Benzene*	<0.001	0.001	06/24/2011	ND	0.021	107	0.0200	4.71	
Toluene*	<0.001	0.001	06/24/2011	ND	0.021	106	0.0200	4.46	
Ethylbenzene*	<0.001	0.001	06/24/2011	ND	0.021	103	0.0200	4.52	
Total Xylenes*	<0.003	0.003	06/24/2011	ND	0.062	103	0.0600	3.78	

Surrogate: Dibromofluoromethane 137 % 80-120

Surrogate: Toluene-d8 90.2 % 80-120

Surrogate: 4-Bromofluorobenzene 80.6 % 80-120

Calcium, 200.7 **mg/L** **Analyzed By: CK**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Calcium	5260	50.0	07/06/2011	ND	5.49	110	5.00	0.545	


Carbonate 310.1M **mg/L** **Analyzed By: HM**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Alkalinity, Carbonate	<0.00	0.00	06/28/2011	ND					

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 06/23/2011
 Reported: 07/14/2011
 Project Name: NMSWD STA. #11
 Project Number: NONE GIVEN
 Project Location: NOT GIVEN

 Sampling Date: 06/21/2011
 Sampling Type: Water
 Sampling Condition: Cool & Intact
 Sample Received By: Jodi Henson


Sample ID: MW #6 (H101296-07)

Chloride, SM4500Cl-B		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Chloride	22400	4.00	06/28/2011	ND	112	112	100	0.00	
Conductivity 120.1		uS/cm	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Conductivity	53300	1.00	06/24/2011	ND	1430	101	1410	0.00	
Magnesium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Magnesium	539	50.0	07/06/2011	ND	27.9	112	25.0	0.358	
pH		pH Units	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
pH	6.59	0.100	06/24/2011		7.01	100	7.00	0.300	
Potassium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Potassium	<50.0	50.0	07/06/2011	ND	10.8	108	10.0	7.14	
Sodium, 200.7		mg/L	Analyzed By: CK						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Sodium	5610	50.0	07/06/2011	ND	9.01	111	8.10	0.553	
Sulfate 375.4		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Sulfate	597	10.0	06/27/2011	ND	39.2	98.0	40.0	1.70	
TDS 160.1		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 06/23/2011
Reported: 07/14/2011
Project Name: NMSWD STA. #11
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 06/21/2011
Sampling Type: Water
Sampling Condition: Cool & Intact
Sample Received By: Jodi Henson


Sample ID: MW #6 (H101296-07)

TDS 160.1		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
TDS	30400	5.00	06/27/2011	ND	229	95.4	240	6.45		
Total Alkalinity 310.1M		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Alkalinity, Total	20.0	4.00	06/28/2011	ND	800	97.6	820	1.12		

Cardinal Laboratories

* = Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.




Celey D. Keene, Lab Director/Quality Manager

Notes and Definitions

A-01a	One surrogate, dibromofluoromethane, exhibited a high bias. No target compounds were detected so reanalysis was not required.
A-01	One surrogate, dibromofluoromethane, exhibited a high bias. No target compounds were detected so reanalysis was not required
ND	Analyte NOT DETECTED at or above the reporting limit
RPD	Relative Percent Difference
**	Samples not received at proper temperature of 6°C or below.
***	Insufficient time to reach temperature.
-	Chloride by SM4500Cl-B does not require samples be received at or below 6°C Samples reported on an as received basis (wet) unless otherwise noted on report

Cardinal Laboratories***=Accredited Analyte**

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

CHAIN-OF-CUSTODY AND ANALYSIS REQUEST

2111 Beechwood, Abilene, TX 79601 101 East Marland, Hobbs, NM 88240
(325) 673-7001 FAX (325) 673-7020 (505) 393-2326 FAX (505) 393-2476

[illegible]

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising whether based in contract or tort, shall be limited to the amount paid by the client for the analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within 30 days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise.

Relinquished By: ROY R. RASCON Date: _____ Time: _____		Received By: <i>Godi Jensen</i> Date: _____ Time: _____		Phone Result: Yes <input type="checkbox"/> No <input type="checkbox"/> Add'l Phone #: _____ Fax Result: Yes <input type="checkbox"/> No <input type="checkbox"/> Add'l Fax #: _____	
Relinquished By: _____ Date: _____ Time: _____		Received By: _____ Date: _____ Time: _____		REMARKS: PLEASE E-MAIL TO: royr , mikeg elliotw, & mcgriffin@vadose.us	
Delivered By: (Circle One) Sampler - UPS - Bus - Other: _____		Sample Condition Cool <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Intact <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/>			

▲ Cardinal cannot accept verbal changes. Please fax written changes to 505-393-2476

26

<u>Monitor Well # 1</u>	<u>TPH GRO</u>	<u>TPH DRO</u>	<u>BTEX</u>	<u>Chloride</u>	<u>TDS</u>
Soil Sample Depth					
0'-2.0'	ND	ND	ND	ND	
4.0'-5.0'	ND	ND	ND	150	
9.0'-9.3'	ND	ND	ND	130	
14.0'-14.5'	ND	ND	ND	210	
19.0'-20.0'	ND	ND	ND	620	
24.0'-25.0'	ND	ND	ND	1000	
29.0'-30.0'	ND	ND	ND	3300	
34.0'-35.5'	ND	ND	ND	2700	
39.0'-40.0'	ND	ND	ND	2300	
40.7'-41.2'	ND	ND	ND	1500	
44.0'-45.3'	ND	ND	ND	3500	
49.0'-49.5'	ND	ND	ND	1800	
54.0'-54.3'	ND	ND	ND	720	
61.0'-63.5' (Aqueous)	ND	ND	ND	21000	51000
63.5'-64.0'	ND	ND	ND	460	
89.0'-90.8'	ND	ND	ND	ND	
104.4'-106.8'	ND	ND	ND	20	

All values are in PPM. Red Values indicate concentrations above WQCC standards.

New Mexico Salt Water Disposal Company
Groundwater Sampling July 09, 2007
By: CMB Environmental Geological Services Inc.

<u>Well:</u>	<u>TPH DRO</u>	<u>TPH GRO</u>	<u>BTEX</u>	<u>Fluoride</u>	<u>Chloride</u>	<u>Bromide</u>	<u>Nitrate</u>	<u>Phosphorus</u>	<u>Sulfate</u>	<u>Calcium</u>	<u>Magnesium</u>	<u>Potassium</u>	<u>Sodium</u>	<u>S.C.</u>	<u>pH</u>	<u>TDS</u>
MW-2	ND	ND	ND	1.6	560	2.6	ND	ND	260	120	22	8.8	350	2800	7.5	2600
MW-1	ND	ND	ND	1.6	550	1.3	1.3	ND	290	120	33	6.2	370	2500	7.31	1500
MW-3	ND	0.057	ND	1.6	620	2.7	ND	ND	360	210	42	11	350	3100	7.46	1800
NW Windmill				1.8	390	2.8	ND	ND	670	190	52	7.5	330	2900	7.5	2000
SW Windmill				0.66	460	1.8	26	ND	160	260	32	4.2	120	2300	7.8	1500
Tank Battery Fluid	35.1	55	20100	ND	83000	140	ND	ND	1600	3200	630	540	45000	280000	7.2	170000

New Mexico Salt Water Disposal Co., Inc.

Station #11, Unit D Sec. 21, T10S - R34E

Lea County, New Mexico





Figure 2 Monitor well locations, depth to water and water zone thickness

New Mexico Salt Water Disposal Company
Disposal Station # 11
Section 21, T.10S. R.34E.N.M.P.M.
Lea County, New Mexico



GROUNDWATER POTENTIOMETRIC SURFACE MAP
SCALE: 1" = 34.58' FEET



GROUNDWATER FLOW DIRECTION INDICATED BY BLUE FLOW LINES
CONTOUR INTERVAL IS 0.05' FOOT.

● 4103.23 to 4104


DEPTH TO WATER MEASURED FROM TOP OF MONITOR WELL CASING AND IS INDICATED BY BLACK NUMBERS ABOVE MONITOR WELL LOCATIONS.
GROUNDWATER CONTOURS ARE DEVELOPED BY SUBTRACTING DEPTH TO GROUNDWATER FROM THE SURVEYED TOP OF MONITOR WELL CASING (ASL).
GROUNDWATER ELEVATIONS (ASL) ARE POSTED BENEATH MONITOR WELL LOCATIONS.

PREPARED BY CLAYTON M. BARNHILL, PG, 08/01/07

FOR: NM SALT WATER DISPOSAL COMPANY

STAGE I ABATEMENT PLAN / MSA - MONITOR WELL INSTALLATION JUNE / JULY 2007.

SECTION 21, TOWNSHIP 10 SOUTH, RANGE 34 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO



WELL NO.	STATE PLANE COORDINATES	NORTH SIDE ELEVATIONS
MW #1	Y=887815.1 N X=803033.8 E	4218.10' GROUND 4218.51' TOP OF CONCRETE 4221.12' TOP OF 2" PVC PIPE
RW #1	Y=887941.7 N X=803032.8 E	4217.53' GROUND 4217.94' TOP OF CONCRETE 4220.13' TOP OF 4" PVC PIPE
MW #2	Y=888022.4 N X=803002.7 E	4217.09' GROUND 4217.39' TOP OF CONCRETE 4220.14' TOP OF 2" PVC PIPE
MW #3	Y=887828.2 N X=803210.2 E	4217.60' GROUND 4217.99' TOP OF CONCRETE 4220.54' TOP OF 2" PVC PIPE

LEGEND

- DENOTES FENCE GATE
- X— DENOTES FENCE LINE
- DENOTES GUY DOWN

I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

[Signature]
GARY G. BISHOP, SURVEYOR
RONALD J. EIDSON, N.M. P.S.

No. 12641
No. 3239

PROVIDING SURVEYING SERVICES
SINCE 1948
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(800) 393-3117

NOTE: COORDINATES SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983.

SCALE: 1" Inch = 75' Feet

NEW MEXICO SALT WATER DISPOSAL CO.

SURVEY OF DISPOSAL STATION #11 IN
SECTION 21, TOWNSHIP 10 SOUTH, RANGE 34 EAST,
N.M.P.M., LEA COUNTY, NEW MEXICO.

Survey Date: 07/02/07	Sheet 1 of 1 Sheets
W.O. Number: 07.11.0830	Dr By: J.R. Rev 1:
Date: 07/16/07 Disk: CD#7	07110830 1" = 75'

New Mexico Salt Water Disposal Company

Station # 11

Section 21, Township 10 South, Range 34 East, N.M. P. M.

Lea County, New Mexico

Location of Cross Section A - A'

CMB Environmental & Geological Services, Inc.

PO Box 2304 Roswell, NM 88202-2304

cmbenviro@dfn.com

(505) 622-2012 Fax (505) 625-0538

FIELD BOREHOLE LOG

BOREHOLE NO.: **MW-4**

TOTAL DEPTH: **65'**

PROJECT INFORMATION					DRILLING INFORMATION				
PROJECT:		NMSWD MW Drilling			DRILLING CO.:		Peterson Drilling Co.		
SITE LOCATION:		Lea County, NM			DRILLER:		Charles Johnson		
JOB NO.:					RIG TYPE:		IR TH-60		
LOGGED BY:		CM Barnhill, PG			METHOD OF DRILLING:		Air Rotary		
PROJECT MANAGER:		Rory McMin			SAMPLING METHODS:		Split Spoon		
DATES DRILLED:		04/14/09			HAMMER WT /DROP		N/A		
NOTES: Split Spoon Pushed by TH-60 Drilling Rig.					☒ Water level during drilling		Page 1 of 1		
					☒ Water level in completed well				
DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Rec. /feet.	PPM TPH / CL	BORING COMPLETION	WELL DESCRIPTION	
0		SE	SM Tan Brown 2.5 YR8/2 fine gr. to medium gr.sand , silt, & caliche	Split Spoon Soil Samples analyzed for TPH	0.5'	ND / 12		Cement / Grout	
-5		SE			0.5'	ND / 43			
-10		SW	SW: Brown med. gr sand, well sorted 2.5 YR 6/4	Mod 8015 GRO	1.0'	ND / 400		Bentonite	
-15		SC	SC: Clayey Silty Sand,						
-20		CL	CL: Brown Fat Clay	/DRO, BTEX, Chloride from surface to	1.0'	13 / 960			
-25		ML	ML: Clayey Silty Sand, yellow-redbrown,fn.sand, 25% clay	Total Depth of Boring	1.0'	59 / 1300		TD 65' Cement Grout 0'-	
-30		SW	SW: Very fine Brown Sand 7/5 YR 6/6, silt & clay trace gravel, perched water 60.22' BGS 63.49' from TOC Completed Well.	8 every 10' feet.	1.0'	ND / 1100		.5',Bentonite .5'-42'. 20/40 Sand 45-	
-35		SW			1.0'	ND / 1400		65',0.010 Slot Screen 45'-65'	
-40		CH	CH: Clay, light olive brown to light yellowish brown,						
-45									
-50									
-55									
-60									
-65									
-70									

Figure 4 Borehole log MW-4 (Barnhill, 2009)

CMB Environmental & Geological Services, Inc.

PO Box 2304 Roswell, NM 88202-2304

cmbenviro@dfn.com

(505) 622-2012 Fax (505) 625-0538

FIELD BOREHOLE LOG

BOREHOLE NO.: **MW-5**

TOTAL DEPTH: **30'**

PROJECT INFORMATION				DRILLING INFORMATION				
PROJECT:		NMSWD MW Drilling		DRILLING CO.:		Peterson Drilling		
SITE LOCATION:		Lea County, NM		DRILLER:		Charles Johnson		
JOB NO.:				RIG TYPE:		IR TH-60		
LOGGED BY:		C M Barnhill, PG		METHOD OF DRILLING:		Air Rotary		
PROJECT MANAGER:		Rory McMin		SAMPLING METHODS:		Split Spoon		
DATES DRILLED:		4/14/09		HAMMER WT./DROP		N/A		
NOTES: Split Spoon Pushed by TH-60 Drilling Rig.				<input checked="" type="checkbox"/> Water level during drilling <input checked="" type="checkbox"/> Water level in completed well		Page 1 of 1		
DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Rec. /feet.	PPM TPH/CL	BORING COMPLETION	WELL DESCRIPTION
0			SM: Tan, 2.5 YR 8/2 fine grained sand / caliche / silt mixture.	Split Spoon Soil Samples analyzed for TPH Mod 8015 GPO	0.5'	ND / 11		Cement / Grout
-5		SM			0.5'	ND / 1600		Bentonite
-10								
-15		SU	SW: Brown fn, gr., well sorted sand 2.5 YR 6/4	/DRG, BTEX, Chloride from surface to	1.0'	ND / 2000		
-20				Total Depth of Boring @ every 10' feet.				
-25		SC	SC: Brown clayey sand 2.5 YR 6/4 Perched water @ 29.60 feet BGS during drilling. Measured from TOC @ 31.57' completed					TD 30' Cement Grout 0'-2', Bentonite 2'-16', 20/40 Sand 16'-30, 0.010 Slot Screen 20'-30'
-30		CL	CL: Brown fat clay.		1.0'	ND / 2100		
-35								

Figure 5 Borehole log MW-5 (Barnhill, 2009)

CMB Environmental & Geological Services, Inc.

PO Box 2304 Roswell, NM 88202-2304

cmbenviro@dm.com

(505) 622-2012 Fax (505) 625-0538

FIELD BOREHOLE LOG

BOREHOLE NO.: **MW-6**

TOTAL DEPTH: **65'**

PROJECT INFORMATION					DRILLING INFORMATION				
PROJECT:		NMSWD MW Drilling			DRILLING CO.:		Peterson Drilling Co.		
SITE LOCATION:		Lea County, NM			DRILLER:		Charles Johnson		
JOB NO.:					RIG TYPE:		IR TH-60		
LOGGED BY:		CM Barnhill, PG			METHOD OF DRILLING:		Air Rotary		
PROJECT MANAGER:		Rory McMin			SAMPLING METHODS:		Split Spoon		
DATES DRILLED:		04/14/09			HAMMER WT./DROP		N/A		
NOTES: Split Spoon Pushed by TH-60 Drilling Rig.					<input checked="" type="checkbox"/> Water level during drilling		Page 1 of 1		
					<input checked="" type="checkbox"/> Water level in completed well				
DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Rec. / feet.	PPM TPH / CL	BORING COMPLETION	WELL DESCRIPTION	
0		SH	SM: Tan Brown 2.5 YR/8/2 fine gr. to medium gr. sand, silt, & caliche	Split Spoon	0.5'	ND / 22		Cement / Grout	
-5		SH		Soil Samples analyzed for TPH	0.5'	ND / 20			
-10		SW	SW: Brown med. gr. sand,	Mod	1.0'	63 / 630		Bentonite	
-15		SC	SC: Clayey Silty Sand, yellow - brown, fn. sand,	8015 GRO					
-20		CL	CL: Brown Fat Clay, No Perched water at 32' Set temp monitor well at 30' BGS and left open 24 hr.,	/DRO, BTEX, Chloride from surface to	1.0'	ND / 3500			
-25		ML		Total Depth of Boring @ every 10' feet.	1.0'	ND / 1700		TD 65' Cement Grout 0'-.5', Bentonite .5'-42'. 20/40 Sand 45-65', 0.010 Slot Screen 45'-65'	
-30		SW	SW: Very fine Brown Sand 7/5 YR 8/6 silt & clay trace gravel, perched water 59.87' BGS 63.23' from TOC Completed Well.		1.0'	ND / 160			
-35		SW			1.0'	53 / 1700			
-40		CH	CH: Clay, light olive brown to light yellowish brown,						
-45									
-50									
-55									
-60									
-65									
-70									

Figure 6 Monitor well MW-6 (Barnhill, 2009)

CMB Environmental & Geological Services, Inc.**PO Box 2304 Roswell, NM 88202-2304****cmbenviro@dfn.com****(505) 622-2012 Fax (505) 625-0538****FIELD BOREHOLE LOG****BOREHOLE NO.: MW-1****TOTAL DEPTH: 135'****PROJECT INFORMATION**

PROJECT: NMSWDCO ESA 06/07
 SITE LOCATION: Lea County, NM
 JOB NO.:
 LOGGED BY: Luana Rought, PhD
 PROJECT MANAGER: CM Barnhill, PG
 DATES DRILLED: 06/12/07 - 06/29/07

DRILLING INFORMATION

DRILLING CO.: GeoProjects International
 DRILLER: Jose Landeros
 RIG TYPE: CME-75
 METHOD OF DRILLING: Hollow Stem Auger 4 1/4"
 SAMPLING METHODS: Split Spoon
 HAMMER WT./DROP 140 lb., 30 in.

NOTES:

☒ Water level during drilling

☒ Water level in completed well

Page 1 of 1

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Rec. / inches	PID ppm	BORING COMPLETION	WELL DESCRIPTION
0								
-5		SM	SM: Brown fine gr. to medium gr. sand, silt, & caliche	Split Spoon	24"	0.3		Cement / Grout
-10		SM		Soil	12"	0.3		
-15				Samples analyzed for TPH	3"	NS		
-20		ML	ML: Clayey Silty Sand, yellow - red brown, fn. sand, 10% caliche, 25% clay, 34.8' - Keat 8.8E-08 Eff. Por. = -16.4%, 40.2" Keat = 3.8E-05 Eff. Por. = 13.6%	8015	5"	0.2		
-25				Mod	12"	0.1		
-30		ML		GRO	12"	0.1		
-35				/DRO,	12"	0.4		
-40		ML		BTEX,	12"	0.2		
-45				Chloride	12"	0.2		
-50		SW	SW: Very fine Brown Sand, silt & clay, trace gravel, perched water 61'-63'		13"	0.2		
-55					6"	NS		Cement Grout
-60		SW			2"	0 PPM		Set 6" Sch 40
-65		CH	CH: Clay, light olive brown to light yellowish brown, very tight fat clay, 10-15% very fine sand and silt. high plasticity. 65.6'-66.1' Keat 5.2E-08 Eff. Porosity 9.3%	Every 5' unless there was no sample recovery	6"	0 PPM		PVC surface casing surface to 65'
-70					17"	0 PPM		
-75		CH			NS	0 PPM		
-80					12"	0 PPM		
-85					NS	0 PPM		
-90		CH			NS	0 PPM		
-95					20"	0 PPM		
-100					NS	0 PPM		
-105		SS	SANDSTONE: Dark gray to very dark gray, very fine grained sand. 25% silt and 25% clay. Saturated at 117' bgs. Water @ 117.23' TOC		NS	0 PPM		
-110					4"	0 PPM		
-115					NS			
-120		SS			NS			
-125								
-130								
-135								

CMB Environmental & Geological Services, Inc.**PO Box 2304 Roswell, NM 88202-2304****cmbenviro@dfn.com****(505) 622-2012 Fax (505) 625-0536****FIELD BOREHOLE LOG****BOREHOLE NO.: MW-2****TOTAL DEPTH: 135'**

PROJECT INFORMATION					DRILLING INFORMATION				
PROJECT:		NMSWDCO ESA 06/07			DRILLING CO.:		GeoProjects International		
SITE LOCATION:		Lea County, NM			DRILLER:		Jose Landeros		
JOB NO.:					RIG TYPE:		CME-75		
LOGGED BY:		Luana Rought, PhD			METHOD OF DRILLING:		Hollow Stem Auger 4 1/4"		
PROJECT MANAGER:		CM Barnhill, PG			SAMPLING METHODS:		Split Spoon		
DATES DRILLED:		06/06/07 - 06/13/07			HAMMER WT./DROP		140 lb., 30 in.		
NOTES:					sz		Water level during drilling		Page 1 of 1
					≡		Water level in completed well		
DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Rec. / inches	PID ppm	BORING COMPLETION	WELL DESCRIPTION	
0		SM	SM: Brown fine gr. to medium gr.sand , silt, & caliche	Split Spoon	24"	4.8		Cement / Grout	
-5		SM		Soil	24"	0.1			
-10				Samples analyzed	24"	0.4			
-15				for TPH	24"	0.3			
-20		ML	ML: Clayey Silty Sand, yellow - red brown, fn.sand,	Mod	23"	0			
-25				8015	24"	0.3			
-30		CH	CH: Brown clay,31.5' Eff. Por. -23.7 Keat 2.4E-07	GRO	18"	0.3			
-35				/DRO,	24"	0			
-40				BTEX,	24"	0			
-45				Chloride	24"	0			
-50		SW	SW: Sand , fine gr.red-yellowish brown		8/10'	0.3		Cement Grout	
-55		SM	SM: Yellow silty sand		18"	0.4			
-60		CH	CH: Fat Clay, lt olive brown. fat clay, harder drilling at 75' Mudstone?	Every 5'	12"	0.3			
-65		CH		unless there was no sample recovery	18"	0.3			
-70		CH			18"	0			
-75		CH			18"	0.5			
-80		SS	SANDSTONE: Brown		4/10'	0			
-85		CH	CH: Clay, silt, sand, yellow brown with carbon?		2/10'	NS		TD 135' Cement Grout 0'-	
-90		CH			18"	0		106.3',Betonite	
-95					19"	3.0		106.3'-111'.	
-100					9/10'	NS		16/30 Sand	
-105		SS	SANDSTONE: Dark gray to very dark gray, very fine grained sand. 25% silt and 25% clay. Saturated at 117' bgs. Water @ 116.91' TOC		NS	NS		111'-135', 0.010	
-110					NS	NS		Slot Screen	
-115					NS	NS		114.5'-135'	
-120		SS			3/10'	NS			
-125					3/10'				
-130					1/10'				
-135					1/10'				

CMB Environmental & Geological Services, Inc.
 PO Box 2304
 1208 Highland Road
 Roswell, NM 88202-2304

FIELD BOREHOLE LOG

BOREHOLE NO.: **SB-4A**
 TOTAL DEPTH: **31'**

PROJECT INFORMATION

PROJECT: **NM SW Disposal Co.**
 SITE LOCATION: **Sec. 21 T10S R34E**
 JOB NO.: **NMSWDCO2003-02**
 LOGGED BY: **CM Barnhill, PG**
 PROJECT MANAGER: **John Maxey, Jr.**
 DATES DRILLED: **11/20/03**

DRILLING INFORMATION

DRILLING CO.: **Atkins Engineering**
 DRILLER: **Mort Bates**
 RIG TYPE: **Mobile Drill B-58**
 METHOD OF DRILLING: **Hollow Stem Auger**
 SAMPLING METHODS: **Split Spoon**
 HAMMER WT./DROP **140 lb., 30" inch**

NOTES:

☐ Water level during drilling
 ☐ Water level in completed well

Page # 1 of # 1

DEPTH	SOIL SYMBOLS	USCS	SOIL DESCRIPTION	SAMP. #	Blows / ft.	CL ppm	BORING COMPLETION	WELL DESCRIPTION
0		SW	SW: Tan Brown Sand, No Hydrocarbon Odor or Staining, Medium grained, well sorted sand, caliche nodules @ 4'-19', Non Detect TPH @ 0'-2', Non Detect BTEX, Non Detect TPH @ 4'-11' & Non Detect BTEX	0'-2'	50/24"	160 PPM		Drill Cuttings / backfill from surface to 10' BGS
5		SW		4'-6'	50/12"	800 PPM		
10		SW		9'-11'	52/6"	2100 PPM		
15		SW		14'-16'	50/12"	3400 PPM		Bentonite @ TD to 10' BGS
20		SC	SC: Tan Brown Clayey Sand, No Hydrocarbon Odor or staining. Water Sample from 30.82' BGS Cl = 45000 PPM, 26 PPM Acetone, all other VOC's Non-Detect, PAH's = ND, Mercury = ND RCRA8=ND	19'-21'	44/24"	4500 PPM		
25		SC		24'-26'	62/24"	5300 PPM		
30		CH	CH: Brown Tight Fat Clay, silty 29'-31', Perched Water @ 30.82' BGS Sampled for PAH's, VOC's, RCRA 8 Metals, TDS, Chloride	29'-31'	63/12"	3900 PPM		T.D. 31'
35		CH		34'-36'				

Appendix 2

Select documents related to the 6-Inch Leak (aka Johnson Leak) site

May 26, 2011

ROY R. RASCON

WHOLE EARTH ENVIRONMENTAL, INC.

2103 ARBOR COVE

KATY, TX 77494

RE: NMSWD 6" LINE LEAK

Enclosed are the results of analyses for samples received by the laboratory on 05/23/11 10:00.

Cardinal Laboratories is accredited through Texas NELAP for:

Method SW-846 8021	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method SW-846 8260	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method TX 1005	Total Petroleum Hydrocarbons

Certificate number T104704398-08-TX. Accreditation applies to solid and chemical materials and non-potable water matrices.


Cardinal Laboratories is accredited through the State of Colorado Department of Public Health and Environment for:

Method EPA 552.2	Haloacetic Acids (HAA-5)
Method EPA 524.2	Total Trihalomethanes (TTHM)
Method EPA 524.4	Regulated VOCs (V2, V3)

Accreditation applies to public drinking water matrices.

This report meets NELAP requirements and is made up of a cover page, analytical results, and a copy of the original chain-of-custody. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Celey D. Keene

Lab Director/Quality Manager

Analytical Results For:

 WHOLE EARTH ENVIRONMENTAL, INC.
 ROY R. RASCON
 2103 ARBOR COVE
 KATY TX, 77494
 Fax To: (281) 394-2051

 Received: 05/23/2011
 Reported: 05/26/2011
 Project Name: NMSWD 6" LINE LEAK
 Project Number: NONE GIVEN
 Project Location: CROSSROADS, NM

 Sampling Date: 05/20/2011
 Sampling Type: Water
 Sampling Condition: ** (See Notes)
 Sample Received By: Celey D. Keene

Sample ID: NW BCKGRD MW (H101039-01)

Bromide, 4500 Br		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	<0.100	0.100	05/25/2011	ND	0.580	96.7	0.600	0.00	
Chloride, SM4500Cl-B		mg/L		Analyzed By: HM					
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Chloride	17000	4.00	05/25/2011	ND	108	108	100	3.77	

Sample ID: S. LEAK SOURCE MW (H101039-02)

Bromide, 4500 Br		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Bromide	130	10.0	05/25/2011	ND	0.580	96.7	0.600	0.00		
Chloride, SM4500Cl-B		mg/L		Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	64000	4.00	05/25/2011	ND	108	108	100	0.00		


Sample ID: SAND HILL WINDMILL (H101039-03)

Bromide, 4500 Br		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Bromide	3.25	0.500	05/25/2011	ND	0.580	96.7	0.600	0.00		
Chloride, SM4500Cl-B		mg/L	Analyzed By: HM							
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier	
Chloride	530	4.00	05/25/2011	ND	108	108	100	0.00		

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 05/23/2011
Reported: 05/26/2011
Project Name: NMSWD 6" LINE LEAK
Project Number: NONE GIVEN
Project Location: CROSSROADS, NM

Sampling Date: 05/20/2011
Sampling Type: Water
Sampling Condition: ** (See Notes)
Sample Received By: Celey D. Keene


Sample ID: LUCKY WINDMILL (H101039-04)

Bromide, 4500 Br		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Bromide	2.12	0.200	05/25/2011	ND	0.580	96.7	0.600	0.00	
Chloride, SM4500Cl-B		mg/L	Analyzed By: HM						
Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Chloride	530	4.00	05/25/2011	ND	108	108	100	0.00	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager


Notes and Definitions

ND	Analyte NOT DETECTED at or above the reporting limit
RPD	Relative Percent Difference
**	Samples not received at proper temperature of 6°C or below.
***	Insufficient time to reach temperature.
-	Chloride by SM4500Cl-B does not require samples be received at or below 6°C Samples reported on an as received basis (wet) unless otherwise noted on report

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager



CHAIN-OF-CUSTODY AND ANALYSIS REQUEST

101 East Marland, Hobbs, NM 88240
(575) 393-2326 FAX (575) 393-2476

Company Name: <u>W.E. & Linc</u>		BILL TO		ANALYSIS REQUEST																							
Project Manager: <u>Ray R. Robinson</u>		P.O. #:		<div>LL-1 Broomfield RAIL</div>																							
Address:		Company:																									
City: State: Zip:		Attn:																									
Phone #: Fax #:		Address:																									
Project #: Project Owner:		City:																									
Project Name: <u>NM 560 6" Line Leak</u>		State: Zip:																									
Project Location:		Phone #:																									
Sampler Name: <u>Ray R. Robinson</u>		Fax #:																									
FOR LAB USE ONLY																											
Lab I.D.	Sample I.D.	(GRAB OR C/COMP)	# CONTAINERS	MATRIX					PRESERV		SAMPLING																
				GROUNDWATER	WASTEWATER	SOIL	OIL	SLUDGE	OTHER	ACID/BASE	ICE / COOL	OTHER	DATE	TIME													
4101039-																											
01	NW JACK GRD MIL	C	1	X							X		5-24-11	8:47P													
02	LEAK SOURCE MIL	C	1	X							X		5-24-11	7:59P													
03	SHRED MILL WASTEWATER	C	1	X							X		5-24-11	8:49P													
04	LUCKY LEAK MIL	C	1	X							X		5-23-11	7:56A													


PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising whether based in contract or tort, shall be limited to the amount paid by the client for the analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within 30 days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates, or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise.

Relinquished By: <u>Ray R. Robinson</u>	Date: <u>5-20-11</u>	Received By: <u>Colleen</u>	Phone Result: <input type="checkbox"/> Yes <input type="checkbox"/> No	Add'l Phone #:
	Time: <u>10:00</u>		Fax Result: <input type="checkbox"/> Yes <input type="checkbox"/> No	Add'l Fax #:
Relinquished By:	Date:	Received By:	REMARKS: <u>RUSH PLEASE EMAIL TO ALL</u>	
	Time:			
Delivered By: (Circle One)	Sample Condition	CHECKED BY: (Initials)		
Sampler: <u>UPS</u> - Bus - Other:	<u>25.5C</u> Cool Intact <input type="checkbox"/> Yes <input type="checkbox"/> No	<u>col</u>	<u>Need By Wednesday</u>	

† Cardinal cannot accept verbal changes. Please fax written changes to 505-393-2476

#26

SECTIONS 15&22, TOWNSHIP 10 SOUTH, RANGE 34 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.



ALL COORDINATES ARE BASED ON NMSPCE (NAD83)

NAME	NORTHING	EASTING	LATITUDE	LONGITUDE	ELEVATION NO. SIDE PVC	ELEVATION CONCRETE	ELEVATION GROUND
MW #1	N889031.293	E807750.318	N33°26'26.84"	W103°27'35.95"	4212.2'	4210.0'	4209.5'
MW #2	N888881.297	E808241.098	N33°26'25.31"	W103°27'30.17"	4207.9'	4205.9'	4205.4'
MW #3	N888657.823	E808094.439	N33°26'23.11"	W103°27'31.92"	4209.5'	4207.1'	4206.6'
BH #1	N888957.647	E808211.471	N33°26'26.07"	W103°27'30.51"			4205.5'
BH #2	N888849.976	E807937.402	N33°26'25.03"	W103°27'33.76"			4207.5'

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED
FROM FIELD NOTES OF AN ACTUAL SURVEY AND
MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND
SURVEYS AS SPECIFIED BY THIS STATE.

GARY L. JONES N.M. P.S. No. 7977
TEXAS P.L.S. No. 5074

Basin Surveys P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 23995 Drawn By: K. GOAD

Date: 01-17-2011 Disk: KJC - 23995MW.DWG

100 0 100 100

WHOLE EARTH ENVIROMENTAL, INC.

REF: MONITOR WELLS & BORE HOLES

MONITOR WELLS LOCATED IN

SECTIONS 15&22, TOWNSHIP 10 SOUTH, RANGE 34 EAST,
N.M.P.M., LEA COUNTY, NEW MEXICO.

Survey Date: 01-10-2011 Sheet 1 of 1 Sheets

EAST LEAK SOURCE WELL



Log of Boring East 2" Monitor Well

Whole Earth Environmental, Inc.
2103 Arbor Cove
Katy TX 77494

Contact: Mike Griffin

Job#: CROSSRD.DRL.10

Drill Start : 12/08/10 (07:00)


Drill End : 12/08/10 (13:30)

Boring Location : East side of spill

Site Location : NMSWD, Crossroads

Auger Type : 3 1/4" Hollow

Logged By : Mort Bates



NORTHWEST BACKGROUND WELL



Log of Boring West Background Well

Whole Earth Environmental, Inc.
2103 Arbor Cove
Katy TX 77494

Contact: Mike Griffin

Job#: CROSSRD.DRL.10

Drill Start : 12/08/10 (14:00)
Drill End : 12/09/10 (16:30)
Boring Location : NW of split 200±
Site Location : NMSWD, Crossroads
Auger Type : 3 1/4" Hollow

Logged By : Mort Bates

Depth in Feet	GRAPHIC	USCS	Sample	DESCRIPTION	West Background Well
0		SP		Sand, loose, tan, dry	4"x4"x5' Well Cover 2'x2' Concrete Pad
5				Caliche, firm, white, dry	
10					
15					
20		SP			
25					
30					Bentonite Seal 2" Sch. 40 PVC Casing
35				Sandstone, firm, reddish tan, dry	
40		SS			
45					
50		SS		Sandstone, firm, yellow, dry	
55		SS		Sandstone, hard, yellowish tan, dry	
60		SS		Sandstone, firm, yellowish tan, wet	
65				Clay, stiff, yellowish brown, moist	Silica sand pack 2" Sch. 40 PVC 0.020 slot screen
70		CL			
75					
80				Clayey sand, stiff, grayish black, damp	
85					
90					Bentonite Seal
95		SC			
100					
105					
110				Total Depth 110'	
115					

NORTHEAST BACKGROUND BORING



Log of Boring East Background Well

Whole Earth Environmental, Inc.
2103 Arbor Cove
Katy TX 77494

Contact: Mike Griffin

Job#: CROSSRD.DRL.10

Drill Start : 12/11/10 (10:30)
Drill End : 12/14/10 (16:30)
Boring Location : NE of spill 200'±
Site Location : NMSWD, Crossroads
Auger Type : 3¼ Hollow

Logged By : Mort Bates

Depth in Feet	GRAPHIC	USCS	Sample	DESCRIPTION	East Background Well
0		SP		Sand, loose, tan, dry	
5					
10				Caliche, hard, tan and white, dry	
15					
20					
25					
30					
35					
40		SS		Sandstone, firm, tan, dry	
45		SS		Sandstone, firm, damp	
50				Clay, stiff, yellow, damp	
55					
60		CL			
65					
70					
75					
80		CL		Clay, stiff, gray, damp	
85					
90					
95		CL		Clay, stiff, dark gray, damp	
100				Total Depth 100'	
105					

Bentonite Seal


WEST LEAK SOURCE BORING



Log of Boring West Side Leak Test Hole

Whole Earth Environmental, Inc. 2103 Arbor Cove Katy TX 77494 Contact: Mike Griffin Job#: CROSSRD.DRL.10	Drill Start	: 12/12/10 (11:30)	Logged By	: Mort Bates
	Drill End	: 12/30/10 (15:00)		
	Boring Location	: West side of leak area		
	Site Location	: NMSWD, Crossroads		
	Auger Type	: Air rotary		

Depth in Feet	GRAPHIC	USCS	sample	DESCRIPTION	West Side Leak Test Hole
0		SP		Poorly graded sand, loose, tan and black, damp	
5				Caliche, firm, tan, dry	
10					
15					
20					
25					
30					
35		SP		Poorly graded sand, loose, tan, damp	
40					
45		SS		Sandstone, firm, tan, damp	
50		SS		Sandstone, firm, yellowish tan, wet	
55		GW		Sand and gravel, loose, yellow, wet	
60		CL		Sandy clay, soft, yellowish tan, wet	
65		CL		Clay, stiff, yellow, moist	
70		CL		Clay, stiff, yellowish brown, dry	
75		CL			
80		LS		Limestone with clay, firm, gray, dry	
85		LS		Limestone, hard, gray, dry	
90					
95				Clay, firm, gray, dry	
100		CL			
105					
110				Total Depth 110'	
115					



01-06-2011 C:\Users\Pauly\Documents\Whole Earth\Crossroads\West Leak bor

SOUTH BACKGROUND WELL



Log of Boring Down Gradient Well


Whole Earth Environmental, Inc.
2103 Arbor Cove
Katy TX 77494
Contact: Mike Griffin
Job#: CROSSRD.DRL.10

Drill Start : 12/15/10 (07:30)
Drill End : 12/16/10 (12:00)
Boring Location : South of split 200±
Site Location : NMSWD, Crossroads
Auger Type : 3 1/4 Hollow

Logged By : Mort Bates

Depth in Feet	GRAPHIC	USCS	Sample	DESCRIPTION
0		SP		Sand, loose, tan, dry
5				Caliche, firm, white, dry
10				Caliche, hard, white, dry
15				
20				
25				
30				Clayey sand, loose, tan to yellow, dry
35		SC		
40				
45				
50		SC		Clayey sand, loose, tan to yellow, moist
55				Clayey sand, firm, yellow, wet
60				
65		SC		
70				
75				
80				
85				Clay, stiff, grayish black, damp
90		CL		
95				
100				Total Depth 100'
105				

Down Gradient Well



Appendix 3

Select documents related to the New Spill site

Crossroads/Johnson Test Hole No. 2

4 **a** **oa** **e** **e** **e** **e** **o** **1**



January 31, 2012

Jack Atkins
Atkins Engineering Associates Inc.
P.O. Box 3156
Roswell, NM 88202-3156
(575) 624-2420

Re: DBS&A Laboratory Report for Atkins Engineering Associates Inc. Crossroads/Johnson Test Hole No. 2

Dear Mr. Atkins:

Enclosed is the final report for the Atkins Engineering Associates Inc. Crossroads/Johnson Test Hole No. 2 sample. Please review this report and provide any comments as samples will be held for a maximum of 30 days. After 30 days samples will be returned or disposed of in an appropriate manner.

All testing results were evaluated subjectively for consistency and reasonableness, and the results appear to be reasonably representative of the material tested. However, DBS&A does not assume any responsibility for interpretations or analyses based on the data enclosed, nor can we guarantee that these data are fully representative of the undisturbed materials at the field site. We recommend that careful evaluation of these laboratory results be made for your particular application.

The testing utilized to generate the enclosed final report employs methods that are standard for the industry. The results do not constitute a professional opinion by DBS&A, nor can the results affect any professional or expert opinions rendered with respect thereto by DBS&A. You have acknowledged that all the testing undertaken by us, and the final report provided, constitutes mere test results using standardized methods, and cannot be used to disqualify DBS&A from rendering any professional or expert opinion, having waived any claim of conflict of interest by DBS&A.

We are pleased to provide this service to Atkins Engineering Associates Inc. and look forward to future laboratory testing on other projects. If you have any questions about the enclosed data, please do not hesitate to call.

Sincerely,

DANIEL B. STEPHENS & ASSOCIATES, INC.
SOIL TESTING & RESEARCH LABORATORY

Joleen Hines
Laboratory Supervising Manager

Enclosure

Daniel B. Stephens & Associates, Inc.
Soil Testing & Research Laboratory

5840 Osuna Rd. NE
Albuquerque, NM 87109

505-889-7752
FAX 505-889-0258

Summaries



Daniel B. Stephens & Associates, Inc.

Summary of Tests Performed

Location Date of Test	Number of Poles	Number of Poles	Number of Poles						Number of Poles	Number of Poles	Number of Poles	Number of Poles
	1	2	3	4	5	6	7	8	9	10	11	12
Location of Poles												
Location of Poles												
Location of Poles												
Location of Poles												

1. Location of Poles
2. Location of Poles
3. Location of Poles
4. Location of Poles
5. Location of Poles
6. Location of Poles
7. Location of Poles
8. Location of Poles
9. Location of Poles
10. Location of Poles
11. Location of Poles
12. Location of Poles



Notes

Sample Receipt and Preparation:

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

General Notes:

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.

The data are a summary of the data collected on 2/11/02 and 2/12/02. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data. The data are for the 2/11/02 and 2/12/02 data.



Summary of Sample Preparation/Volume Changes

Sample Location	Initial Sample Data ¹		Volume Change Post Saturation ²			Volume Change Post Drying Curve ³		
	Moisture Content (%)	Dry Bulk Density (g/cm ³)	Dry Bulk Density (g/cm ³)	Volume Change (%)	Moisture Content (%)	Dry Bulk Density (g/cm ³)	Volume Change (%)	Moisture Content (%)
Crossroads/Johnson Test Hole No. 2 #1	16.8	1.79	1.65	+ 8.0%	92.6%	NA	NA	NA
Crossroads/Johnson Test Hole No. 2 #2	21.6	1.57	1.57	---	100%	1.57	---	100%
Crossroads/Johnson Test Hole No. 2 #3	20.8	1.69	1.69	---	100%	1.69	---	100%

¹Initial Sample Data: The 'as received' dry bulk density and moisture content.

²Volume Change Post Saturation: Volume change measurements were obtained after saturated hydraulic conductivity testing.

³Volume Change Post Drying Curve: Volume change measurements were obtained throughout hanging column and pressure plate testing. The 'Volume Change Post Drying Curve' values represent the final sample dimensions after the last pressure plate point.

Notes:

"+" indicates sample swelling, "-" indicates sample settling, and "---" indicates no volume change occurred.

NA = Not Applicable.



Daniel B. Stephens & Associates, Inc.

**Summary of Initial Moisture Content, Dry Bulk Density
Wet Bulk Density and Calculated Porosity**

Sample Number	Moisture Content				Dry Bulk Density (g/cm ³)	Wet Bulk Density (g/cm ³)	Calculated Porosity (%)
	As Received		Remolded				
	Gravimetric (% g/g)	Volumetric (% cm ³ /cm ³)	Gravimetric (% g/g)	Volumetric (% cm ³ /cm ³)			
Crossroads/Johnson Test Hole No. 2 #1	16.8	30.0	---	---	1.79	2.09	31.3
Crossroads/Johnson Test Hole No. 2 #2	21.6	31.0	---	---	1.57	1.91	22.2
Crossroads/Johnson Test Hole No. 2 #3	20.8	35.1	---	---	1.69	2.01	38.0

NA = Not analyzed

--- = This sample was not remolded



Daniel B. Stephens & Associates, Inc.

Summary of Saturated Hydraulic Conductivity Tests

Sample Number	k_{sat} (cm/sec)	k_{sat} Corrected (cm/sec)	Method of Analysis	
			Falling Head Flexible Wall	Falling Head Rigid Wall
Crossroads/Johnson Test Hole No. 2 #1	1.3E-07	NA		
Crossroads/Johnson Test Hole No. 2 #2	2.8E-05	NA		
Crossroads/Johnson Test Hole No. 2 #3	1.E-06	NA		

--- = k_{sat} correction is unnecessary since coarse fraction $\geq 5\%$ of composite mass
 N = Not requested
 NA = Not applicable



Daniel B. Stephens & Associates, Inc.

Summary of Moisture Characteristics of the Initial Drainage Curve

Sample Number	Pressure Head (-cm water)	Moisture Content (%, cm ³ /cm ³)
Crossroads/Johnson Test Hole No. 2 #2	0	41.4
	17	40.7
	52	39.2
	130	38.1
	337	37.7
	1275	36.7
	1481	25.3
	3877	19.3
	197229	11.7
	89860	7.6
Crossroads/Johnson Test Hole No. 2 #3	0	40.9
	22	41.1
	73	40.9
	158	39.6
	337	39.4
	1275	38.6
	2236	24.0
	73120	17.1
	391195	9.4
	89860	8.2

□ Volume adjustments are applicable at this matric potential (see data sheet for this sample).



Daniel B. Stephens & Associates, Inc.

Summary of Calculated Unsaturated Hydraulic Properties

Sample Number	α (cm ⁻¹)	N (dimensionless)	θ_r (% vol)	θ_s (% vol)	versicle Corrected	
					θ_r (% vol)	θ_s (% vol)
Crossroads/Johnson Test Hole No. 2 #2	0.0003	1.2893	0.00	39.52	NA	NA
Crossroads/Johnson Test Hole No. 2 #3	0.0002	1.3125	0.00	0.05	NA	NA

--- = versicle correction is unnecessary since coarse fraction < 5% of composite mass

NA = Not requested

NA = Not applicable



Daniel B. Stephens & Associates, Inc.

Summary of Atterberg Tests

Sample Number	Liquid Limit	Plastic Limit	Plasticity Index	Classification
Crossroads/Johnson Test Hole No. 2	56	29	27	CH

--- = Soil requires visual-manual classification due to non-plasticity



Daniel B. Stephens & Associates, Inc.

Summary of Specific Gravity Tests

Sample Number	No. 75mm Material		No. 75mm Material		Bulk Sample
	Specific Gravity	Percent of Bulk Sample	Specific Gravity	Percent of Bulk Sample	Specific Gravity
Crossroads/Johnson Test Hole No. 2	2.73	100	---	0	2.73

--- = unnecessary since specified fraction $\leq 5\%$ of composite mass

\approx based on specific gravity of material No. 75 mm

Initial Properties



Daniel B. Stephens & Associates, Inc.

**Summary of Initial Moisture Content, Dry Bulk Density
Wet Bulk Density and Calculated Porosity**

Sample Number	Moisture Content				Dry Bulk Density (g/cm ³)	Wet Bulk Density (g/cm ³)	Calculated Porosity (%)
	As Received		Remolded				
	Gravimetric (% g/g)	Volumetric (% cm ³ /cm ³)	Gravimetric (% g/g)	Volumetric (% cm ³ /cm ³)			
Crossroads/Johnson Test Hole No. 2 #1	16.8	30.0	---	---	1.79	2.09	31.3
Crossroads/Johnson Test Hole No. 2 #2	21.6	31.0	---	---	1.57	1.91	22.2
Crossroads/Johnson Test Hole No. 2 #3	20.8	35.1	---	---	1.69	2.01	38.0

NA = Not analyzed

--- = This sample was not remolded



Daniel B. Stephens & Associates, Inc.

**Data for Initial Moisture Content,
Bulk Density, Porosity, and Percent Saturation**

Job Name: Atkins Engineering
Job Number: 11.0200
Sample Number: Crossroads/Johnson Test Hole No. 2 #1
Ring Number: NA
Depth: 72'-7"

	<u>As received</u>	<u>Remolded</u>
Test Date:	2-Dec-11	---
Field weight* of sample (g):	195	
Tare weight, ring (g):	0.00	
Tare weight, pan/plate (g):	0.00	
Tare weight, other (g):	0.00	
Dry weight of sample (g):	166.53	
Sample volume (cm ³):	93.21	
Measured particle density (g/cm ³):	2.72	

Gravimetric Moisture Content (% g/g):	16.8
Volumetric Moisture Content (% vol):	30.0
Dry bulk density (g/cm ³):	1.79
Wet bulk density (g/cm ³):	2.09
Calculated Porosity (% vol):	33
Percent Saturation:	87.6

Laboratory analysis by: D. Dowd
Data entered by: D. Dowd
Checked by: J. Hines

Comments:

195 eight including tares
NA = Not analyzed
--- = This sample was not remolded



Daniel B. Stephens & Associates, Inc.

**Data for Initial Moisture Content,
Bulk Density, Porosity, and Percent Saturation**

Job Name: Atkins Engineering
Job Number: LB11.0244.00
Sample Number: Crossroads/Johnson Test Hole No. 2 #2
Ring Number: NA
Depth: 72'-74'

	<u>As Received</u>	<u>Remolded</u>
Test Date:	2-Dec-11	---
Field weight* of sample (g):	175.35	
Tare weight, ring (g):	39.58	
Tare weight, pan/plate (g):	0.00	
Tare weight, other (g):	0.00	
Dry weight of sample (g):	111.67	
Sample volume (cm ³):	70.97	
Measured particle density (g/cm ³):	2.72	

Gravimetric Moisture Content (% g/g):	21.6
Volumetric Moisture Content (% vol):	34.0
Dry bulk density (g/cm ³):	1.57
Wet bulk density (g/cm ³):	1.91
Calculated Porosity (% vol):	42.2
Percent Saturation:	80.5

Laboratory analysis by: D. O'Dowd
Data entered by: D. O'Dowd
Checked by: J. Hines

Comments:

* Weight including tares
NA = Not analyzed
--- = This sample was not remolded



Daniel B. Stephens & Associates, Inc.

**Data for Initial Moisture Content,
Bulk Density, Porosity, and Percent Saturation**

Job Name: Atkins Engineering
Job Number: LB11.0244.00
Sample Number: Crossroads/Johnson Test Hole No. 2 #3
Ring Number: NA
Depth: 72'-74'

	<u>As Received</u>	<u>Remolded</u>
Test Date:	6-Dec-11	---
Field weight* of sample (g):	320.06	
Tare weight, ring (g):	126.71	
Tare weight, pan/plate (g):	0.00	
Tare weight, other (g):	0.00	
Dry weight of sample (g):	160.05	
Sample volume (cm ³):	94.97	
Measured particle density (g/cm ³):	2.72	

Gravimetric Moisture Content (% g/g):	20.8
Volumetric Moisture Content (% vol):	35.1
Dry bulk density (g/cm ³):	1.69
Wet bulk density (g/cm ³):	2.04
Calculated Porosity (% vol):	38.0
Percent Saturation:	92.2

Laboratory analysis by: D. O'Dowd
Data entered by: D. O'Dowd
Checked by: J. Hines

Comments:

* Weight including tares
NA = Not analyzed
--- = This sample was not remolded

Saturated Hydraulic Conductivity



Daniel B. Stephens & Associates, Inc.

Summary of Saturated Hydraulic Conductivity Tests

Sample Number	K_{sat} (cm/sec)	Oversize Corrected K_{sat} (cm/sec)	Method of Analysis	
			Falling Head Flexible Wall	Falling Head Rigid Wall
Crossroads/Johnson Test Hole No. 2 #1	1.3E-07	NA	X	
Crossroads/Johnson Test Hole No. 2 #2	2.8E-05	NA		X
Crossroads/Johnson Test Hole No. 2 #3	1.4E-06	NA		X

— = Oversize correction is unnecessary since coarse fraction < 5% of composite mass
 NR = Not requested
 NA = Not applicable



Daniel B. Stephens & Associates, Inc.

Saturated Hydraulic Conductivity Flexible Wall Falling Head-Rising Tail Method

Job name: Atkins Engineering

Job number: LB11.0244.00

Sample number: Crossroads/Johnson Test Hole No. 2 #1

Ring Number NA

Depth: 72'-74'

Remolded or Initial Sample Properties

Initial Mass (g): 194.54
Diameter (cm): 4.930
Length (cm): 4.883
Area (cm²): 19.09
Volume (cm³): 93.21
Dry Density (g/cm³): 1.79
Dry Density (pcf): 111.53
Water Content (% g/g): 16.8
Water Content (% vol): 30.0
Void Ratio (e): 0.52
Porosity (% vol): 34.3
Saturation (%): 87.6

Post Permeation Sample Properties

Saturated Mass (g): 207.53
Dry Mass (g): 166.53
Diameter (cm): 5.086
Length (cm): 4.954
Deformation (%)**: 1.44
Area (cm²): 20.32
Volume (cm³): 100.65
Dry Density (g/cm³): 1.65
Dry Density (pcf): 103.29
Water Content (% g/g): 24.6
Water Content (% vol): 40.7
Void Ratio (e): 0.64
Porosity (% vol): 39.2
Saturation (%)*: 104.0

Test and Sample Conditions

Permeant liquid used: Tap Water
Sample Preparation: ☒ In situ sample, extruded
☐ Remolded Sample
Number of Lifts: NA
Split: NA
Percent Coarse Material (%): NA
Particle Density (g/cm³): 2.72 ☐ Assumed ☒ Measured
Cell pressure (PSI): 82.0
Influent pressure (PSI): 81.0
Effluent pressure (PSI): 80.0
Panel Used: ☒ D ☐ E ☐ F
Reading: ☐ Annulus ☒ Pipette
Date/Time
B-Value (% saturation) prior to test*: 0.95 12/8/11 945
B-Value (% saturation) post to test: 0.98 12/8/11 1630

* Per ASTM D5084 percent saturation is ensured (B-Value \geq 95%) prior to testing, as post test saturation values may be exaggerated during depressurizing and sample removal.

**Percent Deformation: based on initial sample length and post permeation sample length.

Laboratory analysis by: D. O'Dowd

Data entered by: D. O'Dowd

Checked by: J. Hines



Daniel B. Stephens & Associates, Inc.

Saturated Hydraulic Conductivity Flexible Wall Falling Head-Rising Tail Method

Job name: Atkins Engineering

Job number: LB11.0244.00

Sample number: Crossroads/Johnson Test Hole No. 2 #1


Ring Number NA

Depth: 72'-74'

Date	Time	Temp (°C)	Influent Pipette Reading	Effluent Pipette Reading	Gradient ($\Delta H/\Delta L$)	Average Flow (cm^3)	Elapsed Time (s)	Ratio (outflow to inflow)	Change in Head (Not to exceed 25%)	k_{sat} T°C (cm/s)	k_{sat} Corrected (cm/s)
Test # 1:											
08-Dec-11	10:51:50	20.1	4.65	20.10	17.80	0.30	8605	1.00	1%	1.13E-07	1.13E-07
08-Dec-11	13:15:15	20.4	5.00	19.75	17.64	0.30	8605	1.00	1%	1.13E-07	1.13E-07
Test # 2:											
08-Dec-11	13:15:15	20.4	5.00	19.75	17.64	0.17	3895	1.00	1%	1.44E-07	1.42E-07
08-Dec-11	14:20:10	20.6	5.20	19.55	17.54	0.17	3895	1.00	1%	1.44E-07	1.42E-07
Test # 3:											
08-Dec-11	14:20:10	20.6	5.20	19.55	17.54	0.17	4580	1.00	1%	1.23E-07	1.21E-07
08-Dec-11	15:36:30	20.7	5.40	19.35	17.45	0.17	4580	1.00	1%	1.23E-07	1.21E-07
Test # 4:											
08-Dec-11	15:36:30	20.7	5.40	19.35	17.45	0.13	3175	1.00	0%	1.34E-07	1.32E-07
08-Dec-11	16:29:25	20.7	5.55	19.20	17.38	0.13	3175	1.00	0%	1.34E-07	1.32E-07

Average Ksat (cm/sec): 1.27E-07

Calculated Gravel Corrected Average Ksat (cm/sec): —



ASTM Required Range (+/- 25%)

Ksat (-25%) (cm/s): 9.53E-08

Ksat (+25%) (cm/s): 1.59E-07



Daniel B. Stephens & Associates, Inc.

Saturated Hydraulic Conductivity Falling Head Method

Job name: Atkins Engineering	Type of water used: TAP
Job number: LB11.0244.00	Backpressure (psi): 0.0
Sample number: Crossroads/Johnson Test Hole No. 2 #2	Offset (cm): 3.5
Ring Number: NA	Sample length (cm): 3.70
Depth: 72'-74'	Sample x-sectional area (cm ²): 19.20
	Reservoir x-sectional area (cm ²): 0.70


Date	Time	Temp (°C)	Reservoir head (cm)	Corrected head (cm)	Elapsed time (sec)	Ksat (cm/sec)	Ksat @ 20°C (cm/sec)
Test # 1:							
12-Dec-11	12:21:14	20.0	29.2	25.7	981	2.8E-05	2.8E-05
12-Dec-11	12:37:35	20.0	24.45	21.0			
Test # 2:							
12-Dec-11	12:37:35	20.0	24.45	21.0	1762	2.8E-05	2.8E-05
12-Dec-11	13:06:57	20.0	18.1	14.6			
Test # 3:							
12-Dec-11	13:06:57	20.0	18.1	14.6	1053	2.7E-05	2.7E-05
12-Dec-11	13:24:30	20.0	15.3	11.8			

Average Ksat (cm/sec): 2.8E-05

Oversize Corrected Ksat (cm/sec): NA

Comments:

— = Oversize correction is unnecessary since coarse fraction < 5% of composite mass
 NA = Not applicable



Laboratory analysis by: D. O'Dowd

Data entered by: D. O'Dowd

Checked by: J. Hines



Daniel B. Stephens & Associates, Inc.

Saturated Hydraulic Conductivity Falling Head Method

Job name: Atkins Engineering	Type of water used: TAP
Job number: LB11.0244.00	Backpressure (psi): 0.0
Sample number: Crossroads/Johnson Test Hole No. 2 #3	Offset (cm): 0.7
Ring Number: NA	Sample length (cm): 4.97
Depth: 72'-74'	Sample x-sectional area (cm ²): 19.10
	Reservoir x-sectional area (cm ²): 0.70


Date	Time	Temp (°C)	Reservoir head (cm)	Corrected head (cm)	Elapsed time (sec)	Ksat (cm/sec)	Ksat @ 20°C (cm/sec)
Test # 1:							
12-Dec-11	12:21:40	20.0	32.3	31.6	970	1.5E-06	1.5E-06
12-Dec-11	12:37:50	20.0	32.05	31.4			
Test # 2:							
12-Dec-11	13:07:17	20.0	31.7	31.0	1063	1.4E-06	1.4E-06
12-Dec-11	13:25:00	20.0	31.45	30.8			
Test # 3:							
12-Dec-11	13:25:00	20.0	31.45	30.8	2085	1.3E-06	1.3E-06
12-Dec-11	13:59:45	20.0	31	30.3			

Average Ksat (cm/sec): 1.4E-06

Oversize Corrected Ksat (cm/sec): NA

Comments:

-- = Oversize correction is unnecessary since coarse fraction < 5% of composite mass
 NA = Not applicable



Laboratory analysis by: D. O'Dowd

Data entered by: D. O'Dowd

Checked by: J. Hines

Moisture Retention Characteristics



Daniel B. Stephens & Associates, Inc.

Summary of Moisture Characteristics of the Initial Drainage Curve

Sample Number	Pressure Head (-cm water)	Moisture Content (%, cm ³ /cm ³)
Crossroads/Johnson Test Hole No. 2 #2	0	41.4
	17	40.7
	52	39.2
	130	38.1
	337	37.7
	1275	36.7
	14481	25.3
	34877	19.3
	197229	11.7
	849860	7.6
Crossroads/Johnson Test Hole No. 2 #3	0	40.9
	22	41.1
	73	40.9
	158	39.6
	337	39.4
	1275	38.6
	22436	24.0
	73120	17.1
	391195	9.4
	849860	8.2

†† Volume adjustments are applicable at this matric potential (see data sheet for this sample).



Daniel B. Stephens & Associates, Inc.

Summary of Calculated Unsaturated Hydraulic Properties

Sample Number	α (cm ⁻¹)	N (dimensionless)	θ_r (% vol)	θ_s (% vol)	Oversize Corrected	
					θ_r (% vol)	θ_s (% vol)
Crossroads/Johnson Test Hole No. 2 #2	0.0003	1.2893	0.00	39.52	NA	NA
Crossroads/Johnson Test Hole No. 2 #3	0.0002	1.3125	0.00	40.45	NA	NA

— = Oversize correction is unnecessary since coarse fraction < 5% of composite mass

NR = Not requested

NA = Not applicable



Daniel B. Stephens & Associates, Inc.

Moisture Retention Data
Hanging Column / Pressure Plate
 (Soil-Water Characteristic Curve)

Job Name: Atkins Engineering
 Job Number: LB11.0244.00
 Sample Number: Crossroads/Johnson Test Hole No. 2 #2
 Ring Number: NA
 Depth: 72'-74'

Dry wt. of sample (g): 111.67
 Tare wt., ring (g): 39.58
 Tare wt., screen & clamp (g): 27.24
 Initial sample volume (cm³): 70.97
 Initial dry bulk density (g/cm³): 1.57
 Measured particle density (g/cm³): 2.72
 Initial calculated total porosity (%): 42.16

	Date	Time	Weight* (g)	Matric Potential (-cm water)	Moisture Content [†] (% vol)
Hanging column:	12-Dec-11	15:15	207.85	0	41.37
	19-Dec-11	8:40	207.41	17.0	40.75
	27-Dec-11	9:30	206.29	52.0	39.17
	3-Jan-12	11:55	205.52	130.0	38.08
Pressure plate:	13-Jan-12	12:30	205.28	337	37.75
	22-Jan-12	13:15	204.51	1275	36.66

Volume Adjusted Data¹

	Matric Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calculated Porosity (%)
Hanging column:	0.0	---	---	---	---
	17.0	---	---	---	---
	52.0	---	---	---	---
	130.0	---	---	---	---
Pressure plate:	337	---	---	---	---
	1275	---	---	---	---

Comments:

¹ Applicable if the sample experienced volume changes during testing. 'Volume Adjusted' values represent each of the volume change measurements obtained after saturated hydraulic conductivity testing and throughout hanging column/pressure plate testing. "----" indicates no volume changes occurred.

² Represents percent volume change from original sample volume. A '+' denotes measured sample swelling, a '-' denotes measured sample settling, and '----' denotes no volume change occurred.

* Weight including tares

[†] Assumed density of water is 1.0 g/cm³

[‡] Volume adjustments are applicable at this matric potential (see comment #1). Changes in volume, if applicable, are estimated based on obtainable measurements of changes in sample length and diameter.

Technician Notes:

Laboratory analysis by: K. Wright
 Data entered by: C. Krous
 Checked by: J. Hines



Daniel B. Stephens & Associates, Inc.

Moisture Retention Data
Dew Point Potentiometer / Relative Humidity Box
(Soil-Water Characteristic Curve)

Sample Number: Crossroads/Johnson Test Hole No. 2 #2

Initial sample bulk density (g/cm³): 1.57

Fraction of bulk sample used (<2.00mm fraction) (%): 99.77

Dry weight* of dew point potentiometer sample (g): 155.14

Tare weight, jar (g): 117.74

	Date	Time	Weight* (g)	Water Potential (-cm water)	Moisture Content [†] (% vol)
Dew point potentiometer:	7-Dec-11	12:00	161.16	14481	25.27
	7-Dec-11	8:30	159.75	34877	19.35
	6-Dec-11	12:30	157.93	197229	11.71

Volume Adjusted Data¹

	Water Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calc. Porosity (%)
Dew point potentiometer:	14481	---	---	---	---
	34877	---	---	---	---
	197229	---	---	---	---

Dry weight* of relative humidity box sample (g): 80.89

Tare weight (g): 44.10

	Date	Time	Weight* (g)	Water Potential (-cm water)	Moisture Content [†] (% vol)
Relative humidity box:	9-Dec-11	9:20	82.68	849860	7.64

Volume Adjusted Data¹

	Water Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calc. Porosity (%)
Relative humidity box:	849860	---	---	---	---

Comments:

¹ Applicable if the sample experienced volume changes during testing. 'Volume Adjusted' values represent the volume change measurements obtained after the last hanging column or pressure plate point. "----" indicates no volume changes occurred.

² Represents percent volume change from original sample volume. A '+' denotes measured sample swelling, a '-' denotes measured sample settling, and '----' denotes no volume change occurred.

* Weight including tares

[†] Adjusted for >2.00mm (#10 sieve) material not used in DPP/RH testing. Assumed moisture content of material >2.00mm is zero, and assumed density of water is 1.0 g/cm³.

** Volume adjustments are applicable at this matric potential (see comment #1). Changes in volume, if applicable, are estimated based on obtainable measurements of changes in sample length and diameter.

Laboratory analysis by: D. O'Dowd


Data entered by: C. Krous

Checked by: J. Hines



Water Retention Data Points

Sample Number: Crossroads/Johnson Test Hole No. 2 #2






Daniel B. Stephens & Associates, Inc.

Predicted Water Retention Curve and Data Points

Sample Number: Crossroads/Johnson Test Hole No. 2 #2






Daniel B. Stephens & Associates, Inc.

Plot of Relative Hydraulic Conductivity vs Moisture Content

Sample Number: Crossroads/Johnson Test Hole No. 2 #2






Daniel B. Stephens & Associates, Inc.

Plot of Hydraulic Conductivity vs Moisture Content

Sample Number: Crossroads/Johnson Test Hole No. 2 #2






Daniel B. Stephens & Associates, Inc.

Plot of Relative Hydraulic Conductivity vs Pressure Head


Sample Number: Crossroads/Johnson Test Hole No. 2 #2





Daniel B. Stephens & Associates, Inc.

Plot of Hydraulic Conductivity vs Pressure Head
Sample Number: Crossroads/Johnson Test Hole No. 2 #2





Daniel B. Stephens & Associates, Inc.

Moisture Retention Data
Hanging Column / Pressure Plate
(Soil-Water Characteristic Curve)

Job Name: Atkins Engineering
Job Number: LB11.0244.00
Sample Number: Crossroads/Johnson Test Hole No. 2 #3
Ring Number: NA
Depth: 72'-74'

Dry wt. of sample (g): 160.05
Tare wt., ring (g): 126.71
Tare wt., screen & clamp (g): 27.96
Initial sample volume (cm³): 94.97
Initial dry bulk density (g/cm³): 1.69
Measured particle density (g/cm³): 2.72
Initial calculated total porosity (%): 38.04

	Date	Time	Weight* (g)	Matric Potential (-cm water)	Moisture Content [†] (% vol)
Hanging column:	12-Dec-11	13:20	353.60	0	40.94
	19-Dec-11	8:45	353.75	22.0	41.10
	26-Dec-11	12:00	353.57	73.0	40.91
	3-Jan-12	12:15	352.29	158.0	39.56
Pressure plate:	13-Jan-12	12:35	352.16	337	39.42
	27-Jan-12	13:10	351.35	1275	38.57

Volume Adjusted Data¹

	Matric Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calculated Porosity (%)
Hanging column:	0.0	---	---	---	---
	22.0	---	---	---	---
	73.0	---	---	---	---
	158.0	---	---	---	---
Pressure plate:	337	---	---	---	---
	1275	---	---	---	---

Comments:

¹ Applicable if the sample experienced volume changes during testing. 'Volume Adjusted' values represent each of the volume change measurements obtained after saturated hydraulic conductivity testing and throughout hanging column/pressure plate testing. "----" indicates no volume changes occurred.

² Represents percent volume change from original sample volume. A '+' denotes measured sample swelling, a '-' denotes measured sample settling, and '----' denotes no volume change occurred.

* Weight including tares

[†] Assumed density of water is 1.0 g/cm³

[‡] Volume adjustments are applicable at this matric potential (see comment #1). Changes in volume, if applicable, are estimated based on obtainable measurements of changes in sample length and diameter.

Technician Notes:

Laboratory analysis by: K. Wright
Data entered by: C. Krous
Checked by: J. Hines



Daniel B. Stephens & Associates, Inc.

Moisture Retention Data
Dew Point Potentiometer / Relative Humidity Box
(Soil-Water Characteristic Curve)

Sample Number: Crossroads/Johnson Test Hole No. 2 #3

Initial sample bulk density (g/cm³): 1.69

Fraction of bulk sample used (<2.00mm fraction) (%): 99.77

Dry weight* of dew point potentiometer sample (g): 155.14

Tare weight, jar (g): 117.74

	Date	Time	Weight* (g)	Water Potential (-cm water)	Moisture Content [†] (% vol)
Dew point potentiometer:	7-Dec-11	11:00	160.48	22436	24.01
	6-Dec-11	16:05	158.95	73120	17.13
	6-Dec-11	10:20	157.23	391195	9.40

Volume Adjusted Data¹

	Water Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calc. Porosity (%)
Dew point potentiometer:	22436	---	---	---	---
	73120	---	---	---	---
	391195	---	---	---	---

Dry weight* of relative humidity box sample (g): 80.89

Tare weight (g): 44.10

	Date	Time	Weight* (g)	Water Potential (-cm water)	Moisture Content [†] (% vol)
Relative humidity box:	9-Dec-11	9:20	82.68	849860	8.19

Volume Adjusted Data¹

	Water Potential (-cm water)	Adjusted Volume (cm ³)	% Volume Change ² (%)	Adjusted Density (g/cm ³)	Adjusted Calc. Porosity (%)
Relative humidity box:	849860	---	---	---	---

Comments:

¹ Applicable if the sample experienced volume changes during testing. 'Volume Adjusted' values represent the volume change measurements obtained after the last hanging column or pressure plate point. "----" indicates no volume changes occurred.

² Represents percent volume change from original sample volume. A '+' denotes measured sample swelling, a '-' denotes measured sample settling, and '----' denotes no volume change occurred.

* Weight including tares

[†] Adjusted for >2.00mm (#10 sieve) material not used in DPP/RH testing. Assumed moisture content of material >2.00mm is zero, and assumed density of water is 1.0 g/cm³.

†† Volume adjustments are applicable at this matric potential (see comment #1). Changes in volume, if applicable, are estimated based on obtainable measurements of changes in sample length and diameter.

Laboratory analysis by: D. O'Dowd


Data entered by: C. Krous

Checked by: J. Hines



Water Retention Data Points


Sample Number: Crossroads/Johnson Test Hole No. 2 #3





Predicted Water Retention Curve and Data Points

Sample Number: Crossroads/Johnson Test Hole No. 2 #3






Daniel B. Stephens & Associates, Inc.

Plot of Relative Hydraulic Conductivity vs Moisture Content

Sample Number: Crossroads/Johnson Test Hole No. 2 #3






Daniel B. Stephens & Associates, Inc.

Plot of Hydraulic Conductivity vs Moisture Content

Sample Number: Crossroads/Johnson Test Hole No. 2 #3






Daniel B. Stephens & Associates, Inc.

Plot of Relative Hydraulic Conductivity vs Pressure Head


Sample Number: Crossroads/Johnson Test Hole No. 2 #3





Daniel B. Stephens & Associates, Inc.

Plot of Hydraulic Conductivity vs Pressure Head
Sample Number: Crossroads/Johnson Test Hole No. 2 #3



Atterberg Limits/ Identification of Fines



Daniel B. Stephens & Associates, Inc.

Summary of Atterberg Tests

Sample Number	Liquid Limit	Plastic Limit	Plasticity Index	Classification
Crossroads/Johnson Test Hole No. 2	56	29	27	CH

--- = Soil requires visual-manual classification due to non-plasticity



Daniel B. Stephens & Associates, Inc.

Atterberg Limits

Job Name: Atkins Engineering
Job Number: LB11.0244.00
Sample Number: Crossroads/Johnson Test Hole No. 2
Ring Number: NA
Depth: 72'-74'
Test Date: 5-Dec-11

Liquid Limit

	Trial 1	Trial 2	Trial 3
Number of drops:	35	26	17
Pan number:	LL1	LL2	LL3
Weight of pan plus moist soil (g):	125.29	127.93	129.68
Weight of pan plus dry soil (g):	121.08	123.46	124.99
Weight of pan (g):	113.31	115.37	116.95
Gravimetric moisture content (% g/g):	54.18	55.25	58.33
Liquid Limit:	56		

Plastic Limit

	Trial 1	Trial 2
Pan number:	PL1	PL2
Weight of pan plus moist soil (g):	123.66	124.42
Weight of pan plus dry soil (g):	121.89	122.93
Weight of pan (g):	115.72	117.70
Gravimetric moisture content (% g/g):	28.69	28.49
Plastic Limit:	29	

Results

Percent of Sample Retained on #40 Sieve: NA
Liquid Limit: 56
Plastic Limit: 29
Plasticity Index: 27
Classification: CH

Comments:

- = Soil requires visual-manual classification due to non-plasticity
- * = 1-point method requested by client

Laboratory analysis by: D. O'Dowd
Data entered by: D. O'Dowd
Checked by: J. Hines

Specific Gravity



Daniel B. Stephens & Associates, Inc.

Summary of Specific Gravity Tests

Sample Number	<4.75mm Material		>4.75mm Material		Bulk Sample
	Specific Gravity	Percent of Bulk Sample	Specific Gravity	Percent of Bulk Sample	Specific Gravity
Crossroads/Johnson Test Hole No. 2	2.73	100	---	0	2.73

--- = Unnecessary since specified fraction <5% of composite mass

* = Based on specific gravity of material < 4.75 mm



Daniel B. Stephens & Associates, Inc.

**Data for Specific Gravity for Sample:
Crossroads/Johnson Test Hole No. 2**

Job Name: Atkins Engineering
Job Number: LB11.0244.00
Sample Number: Crossroads/Johnson Test Hole No. 2
Ring Number: NA
Depth: 72'-74'

ASTM D854 (<4.75mm Fraction)

Test Date:	19-Dec-11	
Percent of Test Sample (% g/g):	100.00	
Percent of Bulk Sample (% g/g):	100.00	
	<i>Trial 1</i>	<i>Trial 2</i>
Weight of pycnometer filled w/air (g):	95.80	93.69
Weight of pycnometer filled w/soil (g):	147.79	144.60
Weight of pycnometer filled w/soil & water (g):	377.95	375.30
Weight of pycnometer filled w/water (g):	345.06	343.05
Observed temperature (°C):	20.50	20.50
Density of water at observed temperature (g/cm ³):	0.9981	0.9981
Specific Gravity (g/g):	2.72	2.73
Correction factor, K:	0.9999	0.9999
Specific Gravity at 20°C (g/g):	2.72	2.73
Average Specific Gravity at 20°C (g/g):	2.73	
Average Particle Density at 20°C (g/cm ³):	2.72	

ASTM C127 (>4.75mm Fraction)

Test Date:	---	
Percent of Test Sample (% g/g):	0.00	
Percent of Bulk Sample (% g/g):	0.00	
Tare Weight (g):	---	--- = Test unnecessary since specified fraction <5% of composite mass.
Saturated Surface Dry (SSD) mass in Air & Tare (g):	---	
Saturated Apparent mass in Water & Tare (g):	---	
Oven Dry (OD) mass in Air & Tare (g):	---	
Observed Temperature (°C):	---	
Density of water at observed temperature (g/m ³):	---	
SSD Specific Gravity (g/g):	---	
Apparent Specific Gravity (g/g):	---	
OD Specific Gravity (g/g):	---	
Percent Absorption (%):	---	
Correction Factor, K:	---	
Average Specific Gravity (Apparent) at 20°C*:	---	
Average Particle Density (Apparent) at 20°C (g/cm ³)*:	---	
Specific Gravity (Apparent) at 20°C*:	2.73	* Weighted harmonic average, if more than one fraction used.
Particle Density (Apparent) at 20°C (g/cm ³)*:	2.72	

Laboratory analysis by: K. Wright
Data entered by: C. Krous
Checked by: J. Hines

Laboratory Tests and Methods



Daniel B. Stephens & Associates, Inc.

Tests and Methods

Dry Bulk Density:	ASTM D7263
Moisture Content:	ASTM D7263
Calculated Porosity:	ASTM D7263
Saturated Hydraulic Conductivity:	
Falling Head: (Rigid Wall)	Klute, A. and C. Dirksen. 1986. Hydraulic Conductivity and Diffusivity: Laboratory Methods. Chp. 28, pp. 700-703, in A. Klute (ed.), Methods of Soil Analysis, Part 1, American Society of Agronomy, Madison, WI
Falling Head Rising Tail: (Flexible Wall)	ASTM D5084
Hanging Column Method:	ASTM D6836 (modified apparatus)
Pressure Plate Method:	ASTM D6836 (modified apparatus)
Water Potential (Dewpoint Potentiometer) Method:	ASTM D6836
Relative Humidity (Box) Method:	Campbell, G. and G. Gee. 1986. Water Potential: Miscellaneous Methods. Chp. 25, pp. 631-632, in A. Klute (ed.), Methods of Soil Analysis. Part 1. American Society of Agronomy, Madison, WI; Karathanasis & Hajek. 1982. Quantitative Evaluation of Water Adsorption on Soil Clays. SSA Journal 46:1321-1325
Moisture Retention Characteristics & Calculated Unsaturated Hydraulic Conductivity:	ASTM D6836; van Genuchten, M.T. 1980. A closed-form equation for predicting the hydraulic conductivity of unsaturated soils. SSSAJ 44:892-898; van Genuchten, M.T., F.J. Leij, and S.R. Yates. 1991. The RETC code for quantifying the hydraulic functions of unsaturated soils. Robert S. Kerr Environmental Research Laboratory, Office of Research and Development, U.S. Environmental Protection Agency, Ada, Oklahoma. EPA/600/2091/065. December 1991
Specific Gravity Fine	ASTM D854
Atterberg Limits:	ASTM D4318

November 18, 2011

ROY R. RASCON

WHOLE EARTH ENVIRONMENTAL, INC.

2103 ARBOR COVE

KATY, TX 77494

RE: NMSWD 1RP-2743

Enclosed are the results of analyses for samples received by the laboratory on 11/18/11 13:07.

Cardinal Laboratories is accredited through Texas NELAP for:

Method SW-846 8021	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method SW-846 8260	Benzene, Toluene, Ethyl Benzene, and Total Xylenes
Method TX 1005	Total Petroleum Hydrocarbons

Certificate number T104704398-08-TX. Accreditation applies to solid and chemical materials and non-potable water matrices.


Cardinal Laboratories is accredited through the State of Colorado Department of Public Health and Environment for:

Method EPA 552.2	Haloacetic Acids (HAA-5)
Method EPA 524.2	Total Trihalomethanes (TTHM)
Method EPA 524.4	Regulated VOCs (V2, V3)

Accreditation applies to public drinking water matrices.

This report meets NELAP requirements and is made up of a cover page, analytical results, and a copy of the original chain-of-custody. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Celey D. Keene

Lab Director/Quality Manager

Analytical Results For:

WHOLE EARTH ENVIRONMENTAL, INC.
ROY R. RASCON
2103 ARBOR COVE
KATY TX, 77494
Fax To: (281) 394-2051

Received: 11/18/2011
Reported: 11/18/2011
Project Name: NMSWD 1RP-2743
Project Number: NONE GIVEN
Project Location: NOT GIVEN

Sampling Date: 11/18/2011
Sampling Type: Water
Sampling Condition: ** (See Notes)
Sample Received By: Jodi Henson


Sample ID: B4 @ 55.35' (H102520-01)**Chloride, SM4500Cl-B****mg/L****Analyzed By: AP**

Analyte	Result	Reporting Limit	Analyzed	Method Blank	BS	% Recovery	True Value QC	RPD	Qualifier
Chloride	19200	4.00	11/18/2011	ND	108	108	100	0.00	

Cardinal Laboratories

*=Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager


Notes and Definitions

ND	Analyte NOT DETECTED at or above the reporting limit
RPD	Relative Percent Difference
**	Samples not received at proper temperature of 6°C or below.
***	Insufficient time to reach temperature.
-	Chloride by SM4500Cl-B does not require samples be received at or below 6°C Samples reported on an as received basis (wet) unless otherwise noted on report

Cardinal Laboratories

* = Accredited Analyte

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of the services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



Celey D. Keene, Lab Director/Quality Manager



CHAIN-OF-CUSTODY AND ANALYSIS REQUEST

101 East Marland, Hobbs, NM 88240
(575) 393-2326 FAX (575) 393-2476

[illegible]

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising whether based in contract or tort, shall be limited to the amount paid by the client for the analysis. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within 30 days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including without limitation, business interruptions, loss of, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise.

Relinquished By: <i>Ray L. Rascon</i>		Date: <i>11-18-11</i>	Received By: <i>Archie Benson</i>		Phone Result: <input type="checkbox"/> Yes <input type="checkbox"/> No Add'l Phone #:
Relinquished By:		Time: <i>107</i>	Received By:		Fax Result: <input type="checkbox"/> Yes <input type="checkbox"/> No Add'l Fax #:
Delivered By: (Circle One) <i>Sampler</i> - UPS - Bus - Other:		Date:	CHECKED BY: (Initials) <i>AR</i>		REMARKS: <i>Please E-mail to All Rush!!!</i>
Sample Condition Cool Intact <i>20°C</i>		<input type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> No			

† Cardinal cannot accept verbal changes. Please fax written changes to 505-393-2476

Log of Boring Bore 1

Whole Earth Environmental
2103 Arbor Cove
Katy, TX 77494

Contact: Mike Griffin

Job # WENMIRP.MWD.11

Date : 11/16/11
Drill Start : 9:00
Drill End : 15:00
Boring Location : 33°17'46"N, 103°24'31"W
Site Location : 33°17'46"N, 103°24'31"W

Auger Type : 3 1/4 Hollow Stem
Logged By : K. Bates

Depth in Feet	GRAPHIC	USCS	Sample	DESCRIPTION
---------------	---------	------	--------	-------------

0				Clay with caliche, tan, loose, dry
5			1	
10		CL	2	
15			3	
20			4	Clay with caliche and sand, loose, dry
25		CL	5	
30			6	
35			7	Clay with caliche, small gravel, firm, stiff
40			8	
45		CL	9	
50			10	
55			11	Clay with sand, tan-yellow, sticky, damp
60		CH	12	
65			13	Clay, tan-yellow, moist to saturated
70		CH	14	Clay, brown-tan-yellow, saturated.
75		CH	15	Clay, yellow, stiff to firm, damp to dry
				Total Depth 75'



Baroid well grout

Log of Boring Bore 2

Whole Earth Environmental
2103 Arbor Cove
Katy, TX 77494

Contact: Mike Griffin

Job # WENMIRP.MWD.11

Drill Start : 11/17/11 (10:20)
Drill End : 12/13/11
Boring Location : 90' NE of Bore 1
Site Location : 33°17'48"N, 103°24'31"W
Auger Type : 3 1/4" Hollow Stem, 8 1/2" Air Rods

Logged By : K. Bates

Depth in Feet	GRAPHIC	USCS	Sample	DESCRIPTION
0				Clay with small gravel, tan, loose, dry
5			1	
10		CL	2	
15			3	
20			4	Clay, brown, stiff, loose, dry
25			5	
30		CL	6	
35			7	
40			8	clay, brownish red, firm, damp
45		CL	9	
50			10	Clay with sand and caliche, brown-tan, moist
55		CL	11	
60		CL	12	Clay with slight amount of caliche, tan-yellow, stiff
65				
70		CL		Clay with small amount of caliche, tan-yellow, sticky, stiff
75			13	Clay, yellow, stiff to firm, damp to dry Shelby tube sample 73-74'
80		CH		
85		LS		Limestone, light tan, hard, dry
90		CH		Clay, yellow, firm, dry
95				
100		CL		Mudstone, gray, firm, dry
105				Void. No returns. Stiff. Plugged bit (gray and dry on bit).
				Total depth 103'

Cement grout

Cement grout

4" PVC Sch. 40 Casing

Baroid well grout

3 3/8" drill hole w/ air tools