Recycling Facility and/or Recycling Containment
Type of Facility: Recycling Facility Recycling Containment*
Type of action:
* At the time C-147 is submitted to the division for a Recycling Containment, a copy shall be provided to the surface owner.
Be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.
I. Operator: Enduring Resources IV, LLC (For multiple operators attach page with information) OGRID #: 372286 Address: 200 Energy Court, Farmington, NM 87401
Facility or well name (include API# if associated with a well): Rincon 2706-32F
OCD Permit Number: 3kF - 38 (For new facilities the permit number will be assigned by the district office) U/L or Qtr/Qtr Section 32 Township 27N Range 6W County: San Juan Surface Owner: Federal State Private Tribal Trust or Indian Allotment
2.
Recycling Facility:
Location of recycling facility (if applicable): Latitude 36.531477 Longitude -107.495610 NAD83
Proposed Use: 🖓 Drilling* 🗌 Completion* 🗌 Pi
*The re-use of produced water may NOT be used u
*The re-use of produced water may NOT be used u Other, requires permit for other uses. Describe u DENIED XDoes Not meet Siting Criterian nsure there will be no adverse impact on
groundwater or surface water. BY: Cory Smith DATE: $1/719$ (505) 334-6178 Ext. 115 DTW = 32
Fluid Storage
Above ground tanks Recycling containment Activity permitted under 19.15.17 NMAC explain type
Activity permitted under 19.15.36 NMAC explain type:
For multiple or additional recycling containments, attach design and location information of each containment
Closure Report (required within 60 days of closure completion):
Recycling Containment:
✓ Annual Extension after initial 5 years (attach summary of monthly leak detection inspections for previous year) Center of Recycling Containment (if applicable): Latitude 36.531477 Longitude -107.495610 NAD83
Center of Recycling Containment (if applicable): Latitude <u>36.531477</u> Longitude <u>-107.495610</u> NAD83
Lined \square Liner type: Thickness 45 mil \square LLDPE \square HDPE \square PVC \square Other
String-Reinforced
Liner Seams: \bigvee Welded \bigvee Factory \square Other Volume: 300,226 bbl Dimensions: L 300' x W 400' x D 25'
Recycling Containment Closure Completion Date:



Smith, Cory, EMNRD

From:	Smith, Cory, EMNRD
Sent:	Wednesday, November 7, 2018 3:47 PM
То:	'Andrea Felix'
Cc:	Powell, Brandon, EMNRD; Fields, Vanessa, EMNRD; Jacob Ellis; Eric Stevens; James McDaniel
Subject:	RE: Rincon 2706-32F Recycling Containment Additional Ground water information
Categories:	Ground Water Investigation

Andrea,

After waiting 24 hours to let any ground water to equalize GeoMat measure the well today with a conductivity probe and found a water level at 32'. The recycling containment unfortunately does not meet the siting requirements as specified in 19.15.34.11.A(1) NMAC and therefore has been Denied.

The facility does not have an API# so I have assigned it Recycling Facility Admin Order 3RF-38 the denied application will be scanned into the online system as soon as possible for your records.

If you have any additional questions or concerns please contact me at your convenience.

Cory Smith Environmental Specialist Oil Conservation Division Energy, Minerals, & Natural Resources 1000 Rio Brazos, Aztec, NM 87410 (505)334-6178 ext 115 cory.smith@state.nm.us

From: Andrea Felix <AFelix@enduringresources.com>
Sent: Friday, November 2, 2018 9:53 AM
To: Smith, Cory, EMNRD <Cory.Smith@state.nm.us>
Cc: Powell, Brandon, EMNRD <Brandon.Powell@state.nm.us>; Fields, Vanessa, EMNRD <Vanessa.Fields@state.nm.us>; Jacob Ellis <JEllis@enduringresources.com>; Eric Stevens <EStevens@enduringresources.com>
Subject: [EXT] RE: Rincon 2706-32F Recycling Containment Additional Ground water information

Good morning Cory,

We have scheduled GEO Mat for Tuesday November 6th, 2018 at 10am to drill in the vicinity of BH-8 to a depth of at least 70' to provide sufficient ground water data as required.

Thank you,

Andrea R Felix, RWA Regulatory Manager Enduring Resources 200 Energy Court Farmington, NM 87401 Office: 505-636-9741 Cell: 505-386-8205



From: Smith, Cory, EMNRD [mailto:Cory.Smith@state.nm.us]
Sent: Friday, November 02, 2018 8:45 AM
To: Andrea Felix <<u>AFelix@enduringresources.com</u>>
Cc: Powell, Brandon, EMNRD <<u>Brandon.Powell@state.nm.us</u>>; Fields, Vanessa, EMNRD <<u>Vanessa.Fields@state.nm.us</u>>
Subject: Rincon 2706-32F Recycling Containment Additional Ground water information

Good morning Andrea,

While reviewing Enduring's Recycling Containment application for the Rincon 2706-32F there is some concerns in regards to the ground water information.

Enduring provided SJ-00061 and GeoMat Bore Holes for use as determination for Depth to water. Upon review SJ-00061 indicates depth to water is ~301' Below Grade Surface (BGS) after reviewing the online log available through the Iwater portal the well was cased from the Surface to 445' and with perforation at 282'-445'. Bore hole 6-7 from the GeoMat report were drilled with a 7.25" OD hollow stem auger and no casing. The bores were all consistent and indicated damp soil conditions between 20'-30' BGS. BH-8 drilling log indicates damp soils at 20' and a wet zone between 23'-25' BGS.

Due to the data provided, OCD is requiring Enduring to verify the depth to groundwater is greater than 50' from the bottom of the proposed containment. If Enduring wishes to continue with this location a test well will need to be drilled in the vicinity of BH-8. The test well will need to be drilled down to the depth of 70' BGS (50ft of separation and a 20' containment) and left open for 24 hours prior to testing due to the wet zone indicated on BH-8. Enduring will need to provide OCD DIII at least 48 hour notice prior to the drilling of the test well.

If you have any questions please let me know.

Cory Smith Environmental Specialist Oil Conservation Division Energy, Minerals, & Natural Resources 1000 Rio Brazos, Aztec, NM 87410 (505)334-6178 ext 115 cory.smith@state.nm.us

Bonding:

Covered under bonding pursuant to 19.15.8 NMAC per 19.15.34.15(A)(2) NMAC (These containments are limited to only the wells owned or

operated by the owners of the containment.)

Bonding in accordance with 19.15.34.15(A)(1). Amount of bond \$______ (work on these facilities cannot commence until bonding

amounts are approved)

Attach closure cost estimate and documentation on how the closure cost was calculated.

Fencing:

5.

V Four foot height, four strands of barbed wire evenly spaced between one and four feet

Alternate. Please specify_

Signs:

7.

12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers

Signed in compliance with 19.15.16.8 NMAC

Variances:

Justifications and/or demonstrations that the proposed variance will afford reasonable protection against contamination of fresh water, human health, and the environment.

Check the below box only if a variance is requested:

 \checkmark Variance(s): Requests must be submitted to the appropriate division district for consideration of approval. If a Variance is requested, include the variance information on a separate page and attach it to the C-147 as part of the application.

If a Variance is requested, it must be approved prior to implementation.

Siting Criteria for Recycling Containment

Instructions: The applicant must provide attachments that demonstrate compliance for each siting criteria below as part of the application. Potential examples of the siting attachment source material are provided below under each criteria.

General siting

Ground water is less than 50 feet below the bottom of the Recycling Containment. NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	□ Yes 🖉 No □ NA
 Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. Written confirmation or verification from the municipality; written approval obtained from the municipality 	□ Yes 🛛 No □ NA
 Within the area overlying a subsurface mine. Written confirmation or verification or map from the NM EMNRD-Mining and Minerals Division 	🗌 Yes 🗹 No
 Within an unstable area. Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; topographic map 	🗌 Yes 🔽 No
Within a 100-year floodplain. FEMA map	🗌 Yes 🗹 No
 Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). Topographic map; visual inspection (certification) of the proposed site 	🗌 Yes 💋 No
 Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. Visual inspection (certification) of the proposed site; aerial photo; satellite image 	🗌 Yes 🔽 No
 Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application. NM Office of the State Engineer - iWATERS database search; visual inspection (certification) of the proposed site 	🗌 Yes 🖉 No
 Within 500 feet of a wetland. US Fish and Wildlife Wetland Identification map; topographic map; visual inspection (certification) of the proposed site 	🗌 Yes 🔽 No

Recycling Facility and/or Containment Checklist:

Instructions: Each of the following items must be attached to the application. Indicate, by a check mark in the box, that the documents are attached.

- Design Plan based upon the appropriate requirements.
- Operating and Maintenance Plan based upon the appropriate requirements.
 Closure Plan based upon the appropriate requirements.
- Site Specific Groundwater Data -
- Siting Criteria Compliance Demonstrations –
- Certify that notice of the C-147 (only) has been sent to the surface owner(s)

10. **Operator Application Certification:**

I hereby certify that the information and attachments submitted with this application are true, accurate and complete to the best of my knowledge and belief.

Name (Print):	Andrea Felix	Title: Regulatory Manager
Signature:	sh	Date: 10-16-2018
e-mail address:	afelix@enduringresources.com	Telephone: (505) 386-8205
11.		

OCD Representative Sign		Approv	val Date:	
Title:	DENIED	OCD Permit Number:	3RF-38	
OCD Conditions				

C-147 Registration Package

Prepared for



Enduring Resources IV, LLC 200 Energy Court Farmington, NM 87401 (505) 386-8205

Developed by



Energy Inspection Services 479 Wolverine Drive Bayfield, Colorado 81122 Phone: (970) 881-4080

TABLE OF CONTENTS

1. Introduction1
2. Variance Explanation1
3. Siting Criteria1
3.1. Distance to Groundwater1
3.2. Distance to Surface Water
3.3. Distance to Structures
3.4. Distance to Non-Public Water Supply
3.5. Distance to Municipal Boundaries and Defined Fresh Water Fields
3.6. Distance to Subsurface Mines2
3.7 Distance to 100-Year Floodplain2
4. Design and Construction Plan2
4.1. Foundation Construction
4.2. Liner Construction
4.3. Leak Detection System4
4.4. Signage 5
4.5. Entrance Protection5
4.6. Wildlife Protection
5. Maintenance and Operating Plan5
5.1. Inspection Timing5
5.2. Maintenance
5.3. Cessation of Operations
6. Closure Plan6
6.1 Fluid Removal6
6.2 Soil Sampling6
6.3 Reclamation7
7. iWaters Report8
8. Aerial Map9
9. Торо Мар10
10. Mines Mills Map11
11. FEMA Map12
12. Hydrology Report13
Attachment A - Migratory Bird Plan14
Attachment B - Containment Construction Plans
Attachment C - GeoMat Report19

1. INTRODUCTION

Applicant	Enduring Resources IV, LLC
Project Name	Rincon 2706-32F
Project Type	Recycling Containment Registration
Legal Location	S/E NW/4, Section 32, T27N, R6W, San Juan County, NM
Lease Number(s)	Private

In accordance with NMAC 19.15.34, Enduring Resources IV, LLC (Enduring) requests the registration of the proposed Recycling Containment through the approval of this C-147 registration package. The facility and containments will be used to treat and recycle produced water for re-use in Enduring Resources IV, LLC completion activities.

This package contains the C-147 form and associated documents for registration of the Rincon 2706-32F Recycling Containment.

A copy of the C-147 has been submitted to the land owner, Enduring Resources IV, LLC.

2. VARIANCE EXPLANATION

All requested variance provide equal or better protection of fresh water, public health, and the environment.

C-147 #5 Fencing

19.15.34.12.D(1) NMAC states "Recycling containments shall be fenced with a four foot fence that has at least four strands of barbed wire evenly spaced in the interval between one foot and four feet above ground level."

Enduring will install an eight (8) foot chain link fence with one strand of barbed wire around the facility as requested by the surface owners to allow for greater protection to the facility than the requirements of 19.15.34.12.D(1)

3. SITING CRITERIA

3.1. Distance to Groundwater

The NM State Engineers Office iWaters Database shows a water well within section 32 of township 27N and range 6W. The elevation of the iWaters Data Point SJ00213 is 6634' with a groundwater depth of 485'. The Rincon 2706-32F has an elevation of 6627' which is an decrease of 7' establishing the estimated groundwater depth for the Rincon 2706-32F to be greater than 478'. Therefore the groundwater depth is greater than 50 feet below the bottom of the recycling containment.

3.2. Distance to Surface Water

There are not any continuously flowing watercourses within 300' nor any other significant watercourse and lakebed or playa lake within 200' of the recycling containment as shown on the Aerial or Topo maps provided.

3.3. Distance to Structures

There are no permanent residence, school, hospital, institution or church at the time of initial registration within 1000' of the recycling containment as shown on the Aerial and Topo maps provided.

3.4. Distance to Non-Public Water Supply

There are no springs or fresh water wells used for domestic or stock water purposes within 500' in existence at the time of initial registration as shown on the Aerial and Topo maps provided.

3.5. Distance to Municipal Boundaries and Defined Fresh Water Fields

The recycling facility is not within any incorporated municipal boundaries within a defined municipal fresh water well field covered by a municipal ordinance adopted pursuant to Section 3-27-3 NMSA 1978, as amended.

3.6. Distance to Subsurface Mines

The recycling containment is not located in an "unstable" area. The location is not over a mine and is not on the side of a hill. The location of the excavated surface material will not be located within 100 feet of a continuously flowing or significant watercourse. According to the NM EMNRD Mining and Mineral Divisions database there are no subsurface mines in Section 32, Township 27N, Range 6W of San Juan County.

3.7 Distance to 100-Year Floodplain

The Rincon 2706-32F proposed recycling containment is not located within a 100-year floodplain as demonstrated on the FEMA Map.

4. Design and Construction Plan

In accordance with Rule 19.15.34 the following information describes the design and construction of the recycling containment on Enduring's locations.

The Enduring Design and Construction Plan assists Enduring personnel in ensuring compliance with the minimum design and construction requirements for recycling containments as defined by the NMOCD outlined in 19.15.34.12 NMAC. The plan applies to any Enduring Employee(s) and subcontractor(s) whose job requires them to assist with the design and construction of the recycling facility. The plan is designed to ensure compliance with the minimum design and construction requirements for recycling facilities as defined by the NMOCD outlined in 19.15.34.12 NMAC.

Enduring shall design and construct a recycling containment in accordance with the following specifications.

4.1. Foundation Construction

Approximately 6" of topsoil will be stripped and stockpiled for final cover at the time of closure. The topsoil will be stored on the perimeter of the permitted facility.

The recycling containment will have a properly constructed foundation and interior slopes consisting of a firm, unyielding base, smooth and free of rocks, debris, sharp edges or irregularities to prevent the liner's rupture or tear. The containment will ensure confinement of produced water, to prevent releases and to prevent overtopping due to wave action or rainfall. A geotextile under the liner will be used, if needed, to reduce the localized stress-strain or protuberances that otherwise may compromise the liner's integrity. The final sub grade shall be scarified to a minimum depth of 12 inches, moisture conditioned to near Optimum Moisture and compacted to 95% of maximum dry density as determined by a Standard Proctor (ASTM 698).

Positive draining should be provided during construction and maintained throughout the life of the proposed project to prevent surface runoff from entering the pond. Protective slopes should be provided with a minimum grade of approximately 5 percent for at least 10 feet from the structures. Backfill against footings, exterior walls, and in utility trenches should be well compacted and free of all construction debris to reduce the possibility of moisture infiltration.

The pond inside Levey grade will be constructed no steeper than 2H:1V grade and the pond outside Levey grade will be constructed no steeper than 3H:1V grade.

4.2. Liner Construction

Enduring's recycling containment shall incorporate, a primary (upper) liner and a secondary (lower) liner with a leak detection system. The primary (upper) liner will be a 45-mil LLDPE string reinforced liner resistant to UV light, petroleum hydrocarbons, salt and acidic/alkaline solutions with a single sided texture to increase traction for emergency escape from the pit and shall cover the bottom and sides of the pit including the minimum three (3) feet of freeboard per NMOCD 19.15.17.11.G.9. Integrity of the primary liner shall be tested using the Dipole Method - Water Covered Geomembrane (ASTM D7007). The secondary liner will be a 45-mil LLDPE string reinforced liner with a single sided conductive coating for initial leak detection and shall cover the bottom and sides of the pit including the minimum three (3) feet of freeboard per NMOCD 19.15.17.11.G.9. Integrity of the secondary liner shall be tested using the Conductive-Backed Geomembrane Spark Testing Method (ASTM D7240).

A secondary leak detection system will be installed at the designated corner of each pit. The pit bottom will be sloped to the detection system that will be comprised of SDR-17 HDPE solid and perforated pipe with 1-1/2" Type F coarse drain rock bedding. Enduring will install manufacturer recommended Geoconduct 250 geocomposite with a conductive grid between non-woven needle-punched geotextiles produced by Afitex Texel. The product consists of two geotextile layers comprised of short synthetic fibers of 100% polypropylene or polyester which are needle punched together with a structural conductive grid. The conductive grid comprises two conductive inox

cables forming a 50 mm x 50 mm network. Geoconduct is compatible with geoelectrical leak location surveys.

Enduring shall ensure the subcontractor installing the recycling containment minimized liner seams and orient them up and down, not across, a slope of the levee. Enduring shall ensure that factory welded seams shall be used where possible. Enduring shall ensure the subcontractor installing the recycling containment ensures field seams in the geosynthetic material are thermally seamed and that prior to any field seaming, the installer overlaps the liners four to six inches. The subcontractor installing the liner shall minimize the number of field seams and corners and irregularly shaped areas. Enduring will only hire qualified personnel to perform field welding and testing.


Enduring shall install manufacturer recommended DrainTube gas ventilation geocomposite grid produced by Afitex Texel. This layer is intended to vent in situ gases that have potential to create "whale" in the produced water pit that would decrease storage capacity. The product consists of a drainage layer and a filter layer comprised of short synthetic staple fibers of 100% polypropylene needle-punched together with perforated corrugated polypropylene pipes regularly spaced, up to 4 pipes per meter, inside. The pipes have two perforations per corrugation at 180 degrees and alternating at 90 degrees. <u>https://www.draintube.net/docs/en/download/technical_data_sheet/draintube_300p_st_series_fos.pdf</u>

The liner system shall be anchored as designed in a 2 FT x 2.5 FT anchor trench and topped with 6 inches of road base.

At the point of discharge into or suction from the recycling containment, Enduring will insure that the liner is protected from excessive hydrostatic force and potential mechanical damage. External discharge and/or suction lines will not penetrate the liner.

4.3. Leak Detection System

Enduring shall place a leak detection system between the upper and lower geomembrane liners that shall consist of a 200-mil genet to facilitate drainage. The leak detection system shall consist of a properly designed drainage and collection and removal system placed above the lower geomembrane liner in depressions and sloped to facilitate the earliest possible leak detection. A 3 foot wide by 3 foot long by 2 foot deep depression will be contracted to allow for collection of any



leaking liquid. A 4 inch PVC liner will be installed in between the primary and secondary liners from the top of the tank to the depression to allow for detection and removal of liquid.

4.4. Signage

Enduring will sign the containment with an upright sign no less than 12" by 24" with lettering not less than 2" in height in a conspicuous place near the containment. Enduring will provide the operator's name, location of the containment by quarter-quarter or unit letter, Section, Township, Range and emergency telephone numbers.

4.5. Entrance Protection

Enduring will surround the containment with an eight foot chain link fence. All gates leading in and out of the containment will be closed and locked when personnel are not on-site. The fencing will be kept in good repair, and shall be inspected as part of the weekly inspection performed at the containment facility.

4.6. Wildlife Protection

Enduring will install a bird deterrent system pursuant to the attached *Migratory Bird Mitigation Plan*. The containment will be inspected weekly for dead migratory birds and will be reported accordingly.

5. MAINTENANCE AND OPERATING PLAN

In accordance with Rule 19.15.34 the following information describes the operation and maintenance of recycling containments on Enduring's locations.

5.1. Inspection Timing

Enduring shall inspect the recycling containment and associated leak detection systems weekly while it contains fluids. A current log of inspections will be maintained and the log will be made available for review upon division request. If fluids are found in the sump, a primary liner test utilizing the Dipole Method - Water Covered Geomembrane (ASTM D7007) will be conducted. In addition to human monitoring the pond fluid level will be determined via two (2) hydrostatic pressure gauges and a float gauge. At a fluid height of 22', an automated valve will close and prevent any more fluid from entering the containment.

5.2. Maintenance

- 1. Enduring shall maintain and operate the recycling containment as follows:
 - A. Removing any visible lay of oil from the surface of the containment.
 - B. Maintaining at least 3' of freeboard at each containment
 - C. The injection or withdrawal of fluids from the containment shall be accomplished through a header, diverter or other hardware that prevents damage to the liner by erosion, fluid jets, or impact from installation and removal of hoses and pipes
 - D. If the containment's primary liner is compromised above the fluid's surface, Enduring will repair the damage or initiate replacement of the primary liner within 48 hours of discovery or seek an extension from the division district office.

- E. If the primary liner is compromised below the fluid's surface, Enduring will remove all fluid above the damage or leak within 48 hours of discovery, notify the divisions distraction office and repair the damage or replace the primary liner.
- F. The containment will be operated to prevent the collection of surface water run-on with containment walls of 9.5' height.
- G. Enduring will install, or maintain on site, an oil absorbent boom or other device to contain an unanticipated release.
- H. Enduring will not store or discharge any hazardous waste at the facility or within the containment.

5.3. Cessation of Operations

Enduring will report the cessation of operations or if less than 20% of the total fluid capacity is used every six months following the first withdrawal of produced water for use to the appropriate division district office. If additional time is needed for closure, Enduring will request an extension from the appropriate division district office prior to the expiration of the initial six month time period.

6. Closure Plan

In accordance with Rule 19.15.34 the following information describes the closure requirements of recycling containments on Enduring's locations.

All closure activities will include proper documentation and be available for review upon request and will be submitted to the OCD within 60 days of closure. Closure report will be filed on C-147 and incorporate the following:

- Details on capping and covering, where applicable
- Inspection Reports
- Sampling Results

Once Enduring has ceased operations, all fluids will be removed within 60 days and the containment shall be closed within six months.

6.1 Fluid Removal

The containment will be closed by first removing all fluids, contents and synthetic liners and disposed of in a division-approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

6.2 Soil Sampling

Enduring will test the soils beneath the containment for contamination with a five-point composite sample which includes stained or wet soils, if any, and that sample shall be analyzed for the constituents listed in Table I below:

Components	Test Method	51' - 100' GW Depth Limit (mg/kg)	>100' GW Depth Limit (mg/kg)
Chloride	EPA 300.0	10,000	20,000
TPH (GRO+DRO+MRO)	EPA SW-846 Method 8015M	2,500	2,500
GRO + DRO	EPA SW-846 Method 8015M	1,000	1,000
BTEX	EPA SW-846 Method 8021B or 8260B	50	50
Benzene	EPA SW-846 Method 8021B or 8260B	10	10

a. If any containment concentration is higher than the parameters listed in Table I, Enduring will receive approval before proceeding with closures as the division may required additional delineation upon review of the results.

b. If all contaminant concentrations are less than or equal to the parameters listed in Table I then Enduring will proceed to backfill with non-waste containing, uncontaminated, earthen material.

6.3 Reclamation

The topsoil and subsoil will be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Enduring will reclaim and reseed the recycling containment area pursuant to the requirements listed in 19.15.34.14. Once Enduring has closed the recycling containment, we will reclaim the containment's location to a safe and stable condition that blends with the surrounding undisturbed area and matches the existing grade. Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to prevent ponding and erosion. The disturbed area shall then be reseeded in the first favorable growing season following closure of a recycling containment. Enduring will restore the impacted surface area to the condition that existed prior to the construction of the recycling containment.

Reclamation of all disturbed areas no longer in use shall be considered completed when all ground surface disturbing activities at the site have been completed, and a uniform vegetative cover has been established that reflects a life-form ratio of plug or minus fifty percent (50%) of predisturbance levels and a total percent plant cover of at least seventy percent (70%) of predisturbance levels, excluding noxious weeds.

The re-vegetation and reclamation obligations imposed by federal, state trust land or tribal agencies on lands managed by those agencies shall supersede these provisions and govern the obligations of any operator subject to those provisions, provided that the other requirements provide equal or better protection of fresh water, human health and the environment. Enduring will notify the OCD district office when reclamation and revegetation have been completed.

7. IWATERS REPORT



New Mexico Office of the State Engineer Water Column/Average Depth to Water

(A CLW##### in the POD suffix indicates the POD has been replaced & no longer serves a water right file.)	(R=POD replaced, O=orpha C=the file closed)	ned,	(qu						E 3=SW argest)		33 UTM in meters	.) (In	n feet)	
POD Number	Code	POD Sub-	County		Q 16			Tws	Rng	x	Y	Depth WellDepth		Water
<u>SJ 00061</u>	Coue	SJ	RA		3		32		06W	276278	4044923*	445	301	144
<u>SJ 00062</u>		SJ	RA	3	3	3	32	27N	06W	276278	4044923* 🌍	452	301	151
<u>SJ 00213</u>		SJ	RA	4	4	1	32	27N	06W	276897	4045750* 🌍	1308	485	823
<u>SJ 02403</u>		SJ	RA	3	1	3	30	27N	06W	274714	4047115* 🌍	505	300	205
<u>SJ 03001</u>		SJ	RA	1	2	2	07	27N	06W	276165	4052831* 🌍	141	41	100
<u>SJ 04031 POD1</u>		SJ	RA	4	4	2	12	27N	06W	284287	4052043 🌍	515	224	291
											Average Depth to	Water:	275 f	eet
											Minimu	m Depth:	41 fe	eet
											Maximur	m Depth:	485 fe	eet
Record Count: 6														

decord Count: 0

PLSS Search:

Township: 27N Range: 06W


*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.


10/2/18 9:48 AM


WATER COLUMN/ AVERAGE DEPTH TO WATER

8. AERIAL MAP




9. TOPO MAP





11. FEMA MAP



Hydrogeological report for Rincon 2706-32F

Regional Hydrogeological context:

The San Jose Formation of Eocene age occurs in New Mexico and Colorado, and its outcrop forms the land surface over much of the eastern half of the central basin. It overlies the Nacimiento Formation in the area generally south of the Colorado-New Mexico State line and overlies the Animas Formation in the area generally north of the State line.

The San Jose Formation was deposited in various fluvial-type environments. In general, the unit consists of an interbedded sequence of sandstone, siltstone, and variegated shale. Thickness of the San Jose Formation generally increases from west to east (200 feet in the west and south to almost 2,700 feet in the center of the structural basin). Ground water is associated with alluvial and fluvial sandstone aquifers. Thus, the occurrence of ground water is mainly controlled by the distribution of sandstone in the formation. The distribution of such sandstone is the result of original depositional extent plus any post-depositional modifications, namely erosion and structural deformation. Transmissivity data for San Jose Formation are minimal. Values of 40 and 120 feet squared per day were determined from two aquifer tests (Stone et al, 1983, table 5). The reported or measured discharge from 46 water wells completed in San Jose Formation ranges from 0.15 to 61 gallons per minute and the median is 5 gallons per minute. Most of the wells provide water for livestock and domestic use.

The San Jose Formation is a very suitable unit for recharge from precipitation because soils that form on the unit are sandy and highly permeable and therefore readily adsorb precipitation. However, low annual precipitation, relatively high transpiration and evaporation rates, and deep dissection of the San Jose Formation by the San Juan River and its tributaries all tend to reduce the effective recharge to the unit.

Stone et al., 1983, Hydrogeology and Water Resources of the San Juan Basin, New Mexico: Socorro, New Mexico Bureau of Mines and Mineral Resources Hydrologic Report 6, 70 p.

Enduring Resources, LLC's Recycling Containment Migratory Bird Mitigation Plan

Enduring Resources, LLC (Enduring) is proposing this Migratory Bird Mitigation Plan (Mitigation Plan) in compliance with the New Mexico Oil Conservation Division (NMOCD) Rule 19.15.34.12.E Enduring shall ensure that the recycling containment is protective of wildlife by implementing the following proposed Mitigation Plan. Enduring employees will inspect the containment weekly for and, within 30 days of discovery, report the discovery of dead migratory birds or other wildlife to the appropriate wildlife agency and to the division district office in order to facilitate assessment and implementation of measures to prevent incidents from reoccurring. This Mitigation Plan will utilize a combination of visual and audio deterrents to discourage wildlife, particularly birds and bats, from the recycling containment in order to mitigate potential impacts. This Mitigation Plan would be implemented while the Recycling Containment is active and in use, as to not desensitize birds to the deterrents.

The following mitigations will be implemented to reduce any wildlife impacts that may occur from the Recycling Containment:

- The following visual bird deterrents will be installed (Appendix A):
 - Bird-X Prowler Owl decoys will be installed at all four corners of the Containment.
 - Scare-Eye Balloons will be installed along the perimeter of the Containment.
- A Bird-X BroadBand PRO System will be installed at the Containment facility. It utilizes sonic (naturally-recorded bird destress calls & predator cries) to deter birds; as well as, ultrasonic high-frequency sound waves to deter bats. Bird propane cannons were avoided, so as not to disturb other wildlife species.
- The containment will be inspected on a monthly basis when water is present in the containment. All inspectors will insure the containment is receiving only filtered produced water with no hydrocarbons, as well as being trained to inspect the premises for, and respond to any wildlife incident, should it occur.
- Inspection will include:
 - An inspection of the filtration system and all visual and audio deterrents to insure they are in working order and functioning properly.
 - A thorough search of the entire containment facility, and just beyond, for the presence of any wildlife (entrapped, injured, dead, etc.).
- In the event a wildlife incident should occur, James McDaniel with Enduring will be contacted immediately and he will notify the appropriate wildlife agency and division district office. Enduring, appropriate wildlife agency, and division district office will then work collaboratively to address the incident appropriately to insure the incident does not reoccur.



Call Us 888.683.1834


All Bird-X Products

Animal/Rodent Products

Insect Products

Home About News Blog International GSA Retai Products Contact Knowledge Center FREE Evaluation Interactive Problem Solver

BroadBand PRO



- + Emits a combination of audible noises & high-frequency sound waves that are silent-to-most-humans · SONIC: Uses naturally-recorded bird distress calls & predator ones, covers up to 6 acres
 - ULTRASONIC: Uses high-frequency sound waves, covers up to 3 600 sq. ft.
- · 4 speakers included 4 independent speakers with 100 ft. of wire each
- + Fully programmable control volume: sound delays, & daylight / night operation
- · Weather resistant NEMA type box is designed to withstand outdoor use
- Option to add an assortment of three (3) high-quality visual scare products

Accessories

Retail Products


For Songbird Lovers

Remote Control Drone



	2							
4	None	Mout	Neve	8105	International	GS4	Retail Products	Contact
	Interaction	re Prob	lem Sol	Ver	Knowledge	Center	FREE Evaluation	

Prowler Owl





All Bird-X Products Electronic Bird Control

Sonic Bird Control

Ultrasonic Bird Control

Other Electronic Bird Deterrents Solar Panel Products

Bird Spikes

Bird Spikes Kits

Plastic Spikes

Laser Bird Control

Bird Balls


Bird Wire

Shock Track Systems

Bird Netting Drones

Stainless Steel Spikes

roh



Visual Scares and Predator Decoys >

Bird Geb. Taste Aversions. & OvoControl[®] P

For Songbird Lovers

Remote Control Drone

- Includes mylar eyes, mylar tails, and strings for each balloon


· Westherproof vinyl inflatable balloon

Design exaggerates the glanng stare and gaping mouth of natural predators
 Wind causes the Scare-Eye Balloons to move in the wind increasing efficacy

Easy installation


Rincon 2706-32F Registration Package

ATTACHMENT B - CONTAINMENT CONSTRUCTION PLANS




MORE MORE MORE CONT. ENGRETACE MANAMINAL CONT. ENGRETAL MANAMINAL MICHTE REPT MANAMINAL MANAMINAL <th>© Capyright 2018 Soudar, Miller & Associates - All Rights Reserved</th> <th>26. THE CONTRACTOR SHALL CONFORM TO ALL REQUIREMENTS SET FORTH BY THE TECHNOLL SPECIFICATIONS LOCATED IN THE PROJECT</th> <th>WITER POWD SWROVAL COUNTY, NETWIESCO GEDAM PROJECT NO. 152/3962 PREPARED BY GEDAM TINC, CATED OCTOBER 8, 2018 FOR MOSTURE CONTENT, MAXMAM COMPACTED LIFT DEPTHS, AND MINIMAM COMPACTION RECURREMENTS FOR THE PROJECT.</th> <th>25. THE CONTRACTOR SHULL REVIEW AND FOLLOW THE RECOMMENDATIONS PROVIDED IN THE "GEOTECHNICAL ENGINEERING REPORT W ESCHURD, UNIT IN LOWRY CHAIR RINGON FRACIONS SANDONS, SANDONS, BARRIE COLVINES, REWIERDOCT, PERCENT GEOWN THIC, DATED MAY THE "GEOTECHNICAL ENGINEERING AREAD COLVINES, REWIERDOCT, DEPORT</th> <th>TO INFORMATION PROVIDED BY THE CONTRACTOR THROUGH POTHOLING AND COORDINATION WITH UTILITY OWER. 23. NEW MEXICO 811 LOCATES SHALL BE FIELD VENIFIED BY THE CONTRACTOR THROUGH POTHOLING AND COORDINATION IF AND AND COORDINATION IF</th> <th>22. THE CONTRACTOR SHUL NOTIFY ALL UTLITY COMPARES BEFORE COMMENSA WORK AND SHUL BE RESPONSELE FOR COMPANYING WITH NEW MEDICO ONE CALL PROCEDURES. ANY DAMAGE TO EDISTING UTLITES MUST BE IMMEDIATELY REPORTED TO THE APPROPRIATE UTLITY SEPTEMBER 28, 2014, AND DESIGN IS BASED UPON THE SINFORMATION THE REVISION SHOWN ON THESE PLANS ARE ACCORDING</th> <th>CONTRACTOR. 51.</th> <th>S0. WARAANTED TO BE ACCIARTE CONTACT UTILITY PROVIDERS BEFORE STARTING ANY EXCAVATION WORK SHOLD COMPLETING ARCHIVENTO IN OR INTERFERENCE PROBLEMS APPEAR IN THE CONSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE CONTRACTOR OF THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE CONTRACTOR OF THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE DRAWE TO THE CONTRACTOR OF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE DRAWEER MARKEN MARKENT PROOF TO ANY EDWICTION TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO ANY EDWICTION TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRA</th> <th></th> <th>D IN AN ENVIRONMENTALLY SUITABLE</th> <th>RECEIVE ADDITIONAL COMPENSATION 49 THE CAMER MILL PROMOFIC CONSTRUCTION COSSERVERS AND MATERIAL TESTERS</th> <th>19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REMOVALS RECARED TO COMPLETE THE PROJECT. ADDITIONAL REMOVALS NOT SHOW ON THE PLANS MILL BE DESIGNATED BY THE OWNERS REPRESENTATIVE OR DESIGNEE. THIS WORK MILL BE CONSIDERED AS INCLUDED IN THE CONSTRUCTION, ALL STRUCTIONES SHOWING ON THE DAVIDER IN THE CONSIDERED AS INCLUDED IN THE</th> <th>18. TOPOGRUPHY SHOW ON THESE PLANS IS ACCORDING TO FELD LOCATION BY NCE SURVEYS, INC. JAMES C. EDWARDS P.LS. #15289, DATED AUGUST 5, 2018 MID SEPTEMBER 28, 2018.</th> <th>NT 46.</th> <th>SEDMENTATION POTENTIAL STIMUME WATER INFOLVATIONS STREAMS WATER INFOLD SHALL BE AFFECTED IN SICH A HEIGHT OF THE SILT FOR STIMUMET VECTATION REMOVEL SOL DISTURBANCE AND EROSION. CROSSINGS OF LIVE STREAMS WITH HEAVY EQUIPMENT IMAMER AS TO MINIMUZE VECETATION REMOVEL. SOL DISTURBANCE AND EROSION. CROSSINGS OF LIVE STREAMS WITH HEAVY EQUIPMENT PERMIT.</th> <th>16. THE CONTRACTOR SHULL MAILTANE AND DATE SETS OF A-SAULT PANE TARGET THESE PAUSICES THREAD AND SHULL BE KERN CHARGET THREAD ADDRESS OWNERS THREAD ADDRESS AND ADDRESS ADDRES</th> <th>AS DETERMINED BY THE OWNERS REPRESENTATIVE OR DESIGNATE. OF ANY LAVE CLOSURES WHICH WILL RESTRICT THE NORMAL RLOW OF 43, IN THE ENERTY A SERVICE OUTAGE IS REQUIRED. CONTRACTOR MILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE INTRACTOR WILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE INTRACTOR WILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE</th> <th>42. RECORD DRAWINGS OR WORK COMPLETED SHALL BE SUBMITTED TO OWNER PRIOR</th> <th></th> <th>40. RIO ARRIBA COUNTY SHALL BE NOTIFIED 72 HOURS PRIOR TO COMMENCING ANY W</th> <th>33. THE FINANCIAL DRAWLEY FOR CONCRETE MUD REINFORCING BARS SHALL BE BASED ON FUNUAMITTES. IF THE DESIGN IS REVISED DURING FROM FOUNDATIONS.</th> <th>1</th> <th>38.</th> <th>REPART OF DESCRIPTION OF A DESCRIPTION OF A DESCRIPTION OF A DESCRIPTION O</th> <th></th> <th></th> <th></th> <th>9. THERE IS NO CONSTRUCTION CLEW COME OF THIS PROJECT. THIS WORK CONTINUE CONTINUE TO THE CONT</th> <th></th> <th>3. THE PROJECT MALEMAN AND AND AND AND AND AND AND AND AND A</th> <th>7. THE EARTHWORK HAUL ON THIS PROJECT VILL BUILDEN FROMENTES BY PROVIDING EASY RIDING CONVECTIONS TO 31. THE EARTHWORK HAUL ON THIS PROJECT VILL BE CONSIDERED AS INCLUDED IN THE CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND TURINGUTS AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE DRIVENANS A DETERMINE OF RESPONSE THE DRIVENANS A DRI</th> <th>6. ALL EXSTMING TRAFFIC SINGS, MLEPOST MARKES AND DEULEX/ONSS WITHING CONSTRUMMING SAVEL REMOVED OR OFFSET BY THE CONTRACTOR AS DIRECTOR TO BE CREAKING SCIENCE. AND ALL OTHERS ARE TO BE REMOVED. 30. BACKFLL MATERIALS TO BE PLACED UNDER CONCRETE SLABS SMALL COMPLY WITH ALL APPLICABLE TECHNICAL SPECIFICATIONS. EXPANSIVE THIS WORK WILL BE INCLUED IN THE LINT BID PRICE FOR REMOVIL OF STRUCTURES AND DESTRUCTIONS.</th> <th>AGOREGANTE BASE BEREATH SLABS AND PAYEMENTS90</th> <th>A. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE REPAIR AND/OR REPLACEMENT OF ANY DAWAGE DETERMINED TO BE CAUSED BY THE CONSTRUCTION OF THIS PROJECT TO ROUGS. ENCLOSES, DRAWAGE STRUCTINES UTLINES, UTLINES</th> <th>(ASTM D988) ER'S RECOMMENDATIONS</th> <th>RECOMMENDATION(S) ARE ALTERED BY OTHERS.</th> <th>2. CLARIPICATIONS AND/OR REQUESTS REQUIRED AND INSORPCATIONS SHALL BE SUBMITTED TO THE ENGINEER PRICE OR UN-COMPACTED FILL UPTS SHOULD NOT EXCEED 10 NOVES. DURING CONSTRUCTION IN A FORMAL WATTER INECOMMITTED INTO THE ENGINEER SHALL NOT EXCEED 10 NOVES.</th> <th>AURE, THE UNRERSTAND, ANY SUCH OWNERS AND UNDER THE EXAMPLESS OF THE CAMPLE LISES OF THE PLAKE AND SECONFIDES, ANY SUCH OWNERS THE REAL ATONS WAY REQUIRE ADDITIONAL DESIGN SERVICES 28. PLACE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND CONTENTS AND DENSITIES THROUGHOUT THE LIFT.</th> <th>INCLUSES AND THE PARTY OF A STATE OF A DREAM AND AND AND A DREAM AND AN</th>	© Capyright 2018 Soudar, Miller & Associates - All Rights Reserved	26. THE CONTRACTOR SHALL CONFORM TO ALL REQUIREMENTS SET FORTH BY THE TECHNOLL SPECIFICATIONS LOCATED IN THE PROJECT	WITER POWD SWROVAL COUNTY, NETWIESCO GEDAM PROJECT NO. 152/3962 PREPARED BY GEDAM TINC, CATED OCTOBER 8, 2018 FOR MOSTURE CONTENT, MAXMAM COMPACTED LIFT DEPTHS, AND MINIMAM COMPACTION RECURREMENTS FOR THE PROJECT.	25. THE CONTRACTOR SHULL REVIEW AND FOLLOW THE RECOMMENDATIONS PROVIDED IN THE "GEOTECHNICAL ENGINEERING REPORT W ESCHURD, UNIT IN LOWRY CHAIR RINGON FRACIONS SANDONS, SANDONS, BARRIE COLVINES, REWIERDOCT, PERCENT GEOWN THIC, DATED MAY THE "GEOTECHNICAL ENGINEERING AREAD COLVINES, REWIERDOCT, DEPORT	TO INFORMATION PROVIDED BY THE CONTRACTOR THROUGH POTHOLING AND COORDINATION WITH UTILITY OWER. 23. NEW MEXICO 811 LOCATES SHALL BE FIELD VENIFIED BY THE CONTRACTOR THROUGH POTHOLING AND COORDINATION IF AND AND COORDINATION IF	22. THE CONTRACTOR SHUL NOTIFY ALL UTLITY COMPARES BEFORE COMMENSA WORK AND SHUL BE RESPONSELE FOR COMPANYING WITH NEW MEDICO ONE CALL PROCEDURES. ANY DAMAGE TO EDISTING UTLITES MUST BE IMMEDIATELY REPORTED TO THE APPROPRIATE UTLITY SEPTEMBER 28, 2014, AND DESIGN IS BASED UPON THE SINFORMATION THE REVISION SHOWN ON THESE PLANS ARE ACCORDING	CONTRACTOR. 51.	S0. WARAANTED TO BE ACCIARTE CONTACT UTILITY PROVIDERS BEFORE STARTING ANY EXCAVATION WORK SHOLD COMPLETING ARCHIVENTO IN OR INTERFERENCE PROBLEMS APPEAR IN THE CONSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE CONTRACTOR OF THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE CONTRACTOR OF THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE DRAWEER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE EDWIREER MARKENETLY PROOF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE DRAWE TO THE CONTRACTOR OF TO INSTRUCTION DRAMMOS THE CONTRACTORS SHALL BONG THAT INFORMATION TO THE ATTENTION OF THE DRAWEER MARKEN MARKENT PROOF TO ANY EDWICTION TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO ANY EDWICTION TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRAWE TO THE ATTENTION OF THE DRAWEER MARKENT PROOF TO THE DRAWE TO THE DRA		D IN AN ENVIRONMENTALLY SUITABLE	RECEIVE ADDITIONAL COMPENSATION 49 THE CAMER MILL PROMOFIC CONSTRUCTION COSSERVERS AND MATERIAL TESTERS	19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REMOVALS RECARED TO COMPLETE THE PROJECT. ADDITIONAL REMOVALS NOT SHOW ON THE PLANS MILL BE DESIGNATED BY THE OWNERS REPRESENTATIVE OR DESIGNEE. THIS WORK MILL BE CONSIDERED AS INCLUDED IN THE CONSTRUCTION, ALL STRUCTIONES SHOWING ON THE DAVIDER IN THE CONSIDERED AS INCLUDED IN THE	18. TOPOGRUPHY SHOW ON THESE PLANS IS ACCORDING TO FELD LOCATION BY NCE SURVEYS, INC. JAMES C. EDWARDS P.LS. #15289, DATED AUGUST 5, 2018 MID SEPTEMBER 28, 2018.	NT 46.	SEDMENTATION POTENTIAL STIMUME WATER INFOLVATIONS STREAMS WATER INFOLD SHALL BE AFFECTED IN SICH A HEIGHT OF THE SILT FOR STIMUMET VECTATION REMOVEL SOL DISTURBANCE AND EROSION. CROSSINGS OF LIVE STREAMS WITH HEAVY EQUIPMENT IMAMER AS TO MINIMUZE VECETATION REMOVEL. SOL DISTURBANCE AND EROSION. CROSSINGS OF LIVE STREAMS WITH HEAVY EQUIPMENT PERMIT.	16. THE CONTRACTOR SHULL MAILTANE AND DATE SETS OF A-SAULT PANE TARGET THESE PAUSICES THREAD AND SHULL BE KERN CHARGET THREAD ADDRESS OWNERS THREAD ADDRESS AND ADDRESS ADDRES	AS DETERMINED BY THE OWNERS REPRESENTATIVE OR DESIGNATE. OF ANY LAVE CLOSURES WHICH WILL RESTRICT THE NORMAL RLOW OF 43, IN THE ENERTY A SERVICE OUTAGE IS REQUIRED. CONTRACTOR MILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE INTRACTOR WILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE INTRACTOR WILL NOTIFY ALL AFFECTED PARTIES WHEN AND HOW LONG THEY WILL BE	42. RECORD DRAWINGS OR WORK COMPLETED SHALL BE SUBMITTED TO OWNER PRIOR		40. RIO ARRIBA COUNTY SHALL BE NOTIFIED 72 HOURS PRIOR TO COMMENCING ANY W	33. THE FINANCIAL DRAWLEY FOR CONCRETE MUD REINFORCING BARS SHALL BE BASED ON FUNUAMITTES. IF THE DESIGN IS REVISED DURING FROM FOUNDATIONS.	1	38.	REPART OF DESCRIPTION OF A DESCRIPTION OF A DESCRIPTION OF A DESCRIPTION O				9. THERE IS NO CONSTRUCTION CLEW COME OF THIS PROJECT. THIS WORK CONTINUE CONTINUE TO THE CONT		3. THE PROJECT MALEMAN AND AND AND AND AND AND AND AND AND A	7. THE EARTHWORK HAUL ON THIS PROJECT VILL BUILDEN FROMENTES BY PROVIDING EASY RIDING CONVECTIONS TO 31. THE EARTHWORK HAUL ON THIS PROJECT VILL BE CONSIDERED AS INCLUDED IN THE CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND TURINGUTS AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE THIS CONTRACT PRICE FOR UNCLASSIFIED EXCAVATION AND DRIVENANS A DETERMINE OF RESPONSE THE DRIVENANS A DETERMINE OF RESPONSE THE DRIVENANS A DRI	6. ALL EXSTMING TRAFFIC SINGS, MLEPOST MARKES AND DEULEX/ONSS WITHING CONSTRUMMING SAVEL REMOVED OR OFFSET BY THE CONTRACTOR AS DIRECTOR TO BE CREAKING SCIENCE. AND ALL OTHERS ARE TO BE REMOVED. 30. BACKFLL MATERIALS TO BE PLACED UNDER CONCRETE SLABS SMALL COMPLY WITH ALL APPLICABLE TECHNICAL SPECIFICATIONS. EXPANSIVE THIS WORK WILL BE INCLUED IN THE LINT BID PRICE FOR REMOVIL OF STRUCTURES AND DESTRUCTIONS.	AGOREGANTE BASE BEREATH SLABS AND PAYEMENTS90	A. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE REPAIR AND/OR REPLACEMENT OF ANY DAWAGE DETERMINED TO BE CAUSED BY THE CONSTRUCTION OF THIS PROJECT TO ROUGS. ENCLOSES, DRAWAGE STRUCTINES UTLINES, UTLINES	(ASTM D988) ER'S RECOMMENDATIONS	RECOMMENDATION(S) ARE ALTERED BY OTHERS.	2. CLARIPICATIONS AND/OR REQUESTS REQUIRED AND INSORPCATIONS SHALL BE SUBMITTED TO THE ENGINEER PRICE OR UN-COMPACTED FILL UPTS SHOULD NOT EXCEED 10 NOVES. DURING CONSTRUCTION IN A FORMAL WATTER INECOMMITTED INTO THE ENGINEER SHALL NOT EXCEED 10 NOVES.	AURE, THE UNRERSTAND, ANY SUCH OWNERS AND UNDER THE EXAMPLESS OF THE CAMPLE LISES OF THE PLAKE AND SECONFIDES, ANY SUCH OWNERS THE REAL ATONS WAY REQUIRE ADDITIONAL DESIGN SERVICES 28. PLACE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOSTURE AND CONTENTS AND DENSITIES THROUGHOUT THE LIFT.	INCLUSES AND THE PARTY OF A STATE OF A DREAM AND AND AND A DREAM AND AN
	P:S-Enduring Resources - 168 Pond Design (\$127383)(CAD)C/v/IRRINCON/5127363 RNC GEN			I.		I I	9	PROPOSED INTERMEDIATE CONTOURS	PROPOSED INDEX CONTOURS	EXISTING INTERMEDIATE CONTOURS							or MM	0	×		LINEAR FEET w	RIZ HORIZONTAL TYP	FEET TOP	FLOWAINE TOE	EXISTING SQ. YDS.	ELEVATION SQ. FT.	DIAMETER (Ø) RT.	CUBIC YARDS O.C.	CORRUGATED METAL PIPE MIN.	ABBREVIATIONS			(500) J96-986 /	ENUVENKA RESOURCES 312 COUMT RADU 3100 AZTEC, NEWIMEXICO, 87410	SURFACE OWNER	LAKEWOOD, COLORADO 80214 (303) 239-9011	HEATHER D. MCDAVIEL P.E. SOUDER, MILLER & ASSOCIATES (SMA) 3000 WEST FOURTEENTIA AVENUE	CIVIL ENGINEER	322 COUNTY ROAD 3100 AZTEC, NEW MEXICO, 87410 (505) 356-8887


P:15-Enduring 3 RNC GEN NOTES, dwg. 10/9/2018 1:24:14 PM JTN





© Copyright 2018 Souder, Miller & Associates - All Rights Reserved


P:IS-Enduring Resources - 16B Pond Design (5127383)/CADICivil/RINCON/5127383 RNC SITE PLAN.dwg, 10/9/2018 1:24:44 PM JTN
















Copyright 2018 Souder, Miller & Associates - All Rights Reserved


P:\5-Enduring Resources - 16B Pond Design (5127383)/CAD/Civil/RINCON\5127383 RNC DETAILS.dvg, 10/9/2018 1:26:30 PM JTN




© Copyright 2018 Souder, Miller & Associates - All Rights Reserved


P:15-Enduring Resources - 168 Pond Design (5127383)/CAD/Civil/RINCON/5127383 RNC DETAILS.dvrg, 10/9/2018 1:26:36 PM JTN






.









GEOTECHNICAL ENGINEERING REPORT W ESCAVADA UNIT & LOWRY CAMP RINCON FRACKING WATER PONDS SANDOVAL & RIO ARRIBA COUNTIES, NEW MEXICO

Submitted To:

NMOCD

James McDaniel Enduring Resources 332 CR 3100 Aztec, New Mexico 87410

Submitted By:

GEOMAT Inc. 915 Malta Avenue Farmington, New Mexico 87401

May 16, 2018 GEOMAT Project 182-2992 OCT 192018 District III



May 16, 2018

James McDaniel


Enduring Resources 332 CR 3100 Aztec, New Mexico 87410

RE: Geotechnical Engineering Study **Proposed Fracking Water Ponds** Sandoval and Rio Arriba Counties, New Mexico GEOMAT Project No. 182-2992

GEOMAT Inc. (GEOMAT) has completed the geotechnical engineering exploration for the proposed W Escavada Unit (WEU) and Lowry Camp Rincon (Rincon) fracking water ponds to be located in Sandoval and Rio Arriba Counties, New Mexico, respectively. This study was performed in general accordance with our Proposal No. 182-04-20 dated April 20, 2018.

The results of our engineering study, including the geotechnical recommendations, site plan, boring records, and laboratory test results are attached. Based on the geotechnical engineering analyses, subsurface exploration and laboratory test results, the proposed ponds could be constructed as incised, double synthetic-lined ponds as proposed. Other design and construction details, based upon geotechnical conditions, are presented in the report.

We have appreciated being of service to you in the geotechnical engineering phase of this project. If you have any questions concerning this report, please contact us.



Copies to: Addressee (1)

Matthew J. Cramer, P.E. Vice President

TABLE OF CONTENTS

Page No.
INTRODUCTION
PROPOSED CONSTRUCTION
SITE EXPLORATION
Field Exploration
Laboratory Testing
SITE CONDITIONS
SUBSURFACE CONDITIONS
Soil Conditions 4
Groundwater Conditions 4
Laboratory Test Results
OPINIONS AND RECOMMENDATIONS
Geotechnical Considerations
Pond Design and Construction
Slope Stability Analysis
Seismic Considerations
Lateral Earth Pressures
Earthwork7
General Considerations
Site Clearing7
Excavation
Fill Materials
Placement and Compaction
Compliance
Drainage
Surface Drainage
Subsurface Drainage
GENERAL COMMENTS

TABLE OF CONTENTS (continued)

APPENDIX A

Site Plans Logs of Borings Unified Soil Classification Drilling and Exploration Procedures

APPENDIX B

Laboratory Test Results Laboratory Test Procedures

APPENDIX C

Important Information About This Geotechnical Engineering Report (Taken From GBA)

GEOTECHNICAL ENGINEERING REPORT W ESCAVADA UNIT & LOWRY CAMP RINCON FRACKING WATER PONDS SANDOVAL & RIO ARRIBA COUNTIES, NEW MEXICO GEOMAT PROJECT NO. 182-2992

INTRODUCTION

This report contains the results of our geotechnical engineering exploration for the proposed W Escavada Unit (WEU) and Lowry Camp Rincon (Rincon) fracking water ponds to be located in Sandoval and Rio Arriba Counties, New Mexico, respectively, as shown on the Site Plans in Appendix A of this report.

The purpose of these services is to provide information and geotechnical engineering recommendations about:

subsurface soil conditions . groundwater conditions

- slopes for pond walls
- drainage
- lateral soil pressures .
- earthwork .

.

The opinions and recommendations contained in this report are based upon the results of field and laboratory testing, engineering analyses, and experience with similar soil conditions, structures, and our understanding of the proposed project as stated below.

PROPOSED CONSTRUCTION

The WEU pond will have dimensions of approximately 350 feet by 350 feet and will be located near 36.132769° north latitude by 107.589962° west longitude. The Rincon pond will have dimensions of approximately 300 feet wide by 400 feet long and will be located near 36.531088° north latitude by 107.495715° west longitude. We also understand the ponds will be excavated (incised) into the existing grades at the sites. We understand the total depth of each pond will be 20 feet. The maximum water depth in each pond will be 17 feet. Both ponds will and located on relatively flat terrain. The ponds will be lined with a double HDPE liner system.

SITE EXPLORATION

Our scope of services performed for this project included a site reconnaissance by a staff geologist, a subsurface exploration program, laboratory testing and engineering analyses.

Field Exploration:

Subsurface conditions at the sites were explored on April 23, 2018, by drilling four exploratory borings at each site at the approximate locations shown on the Site Plans in Appendix A. Borings B-1 through B-4 were drilled at the WEU site and B-5 through B-8 at the Rincon site. All the borings were drilled to depths of approximately 30 feet below existing ground surface.

The borings were advanced using a CME-55 truck-mounted drill rig with continuous-flight, 7.25inch O.D. hollow-stem auger. The borings were continuously monitored by a geologist from our office who examined and classified the subsurface materials encountered, obtained representative samples, observed groundwater conditions, and maintained a continuous log of each boring.

Soil samples were obtained from the borings using a combination of standard 2-inch O.D. split spoon and 3-inch O.D. modified California ring barrel samplers. The samplers were driven using a 140-pound hammer falling 30 inches. The standard penetration resistance was determined by recording the number of hammer blows required to advance the sampler in six-inch increments. Representative bulk samples of subsurface materials were also obtained.

Groundwater evaluations were made in each boring at the time of site exploration. Soils were classified in accordance with the Unified Soil Classification System described in Appendix A. Boring logs were prepared and are presented in Appendix A.

Laboratory Testing:

Samples retrieved during the field exploration were transported to our laboratory for further evaluation. At that time, the field descriptions were confirmed or modified as necessary, and laboratory tests were performed to evaluate the engineering properties of the subsurface materials.

SITE CONDITIONS

WEU Pond

The site of the proposed pond is located roughly 150 feet west of an existing unnamed dirt road in a currently undeveloped area approximately 7 miles south of US Highway 550 between Nageezi, NM and Counselor, NM. The ground surface across the site of the proposed pond slopes gently toward the middle part of the eastern side. The area was vegetated by a significant growth of native weeds, sage brush, shrubs, and small trees at the time of our exploration. No evidence of prior structural development was noted at the site. The photo below depicts the site's condition at the time of our exploration.



Drill Rig at Boring B-2 View toward the west

Rincon Pond

The site of the proposed pond is located several miles into the Largo Wash southeast of Blanco, New Mexico. The site is located approximately 150 west of the old Lowry Camp Buildings on what was once a developed area. The ground surface across the site of the proposed pond was relatively flat and was sparsely vegetated by native weeds at the time of our exploration. There is evidence of prior structural development at the site, as there are several utility lines in place from the previous development. The photo below depicts the site's condition at the time of our exploration.



Work Truck at Boring B-7 View toward the north

SUBSURFACE CONDITIONS

Soil Conditions:

WEU Pond

As presented on the Boring Logs in Appendix A, in all four borings, B-1 through B-4, we encountered sandy soils overlying formational sandstone. In borings B-3 and B-4, the sandstone was underlain by shale rock. The sandstone was encountered at approximately 16 feet in boring B-1, 18 feet in B-2, 14 feet in B-3, and 11 feet in B-4. The shale was encountered at approximately 24 feet in B-3 and 27 feet in B-4. The sandy soils varied in density from medium dense to very dense and were generally slightly damp to damp. The sandstone was generally weakly cemented, slightly to moderately weathered, and slightly damp. The shale rock underlying the sandstone both B-3 and B-4 was generally slightly damp, fissile and friable.

Rincon Pond

As presented on the Boring Logs in Appendix A, in all four borings, B-5 through B-8, we encountered sandy soils overlying clay soils. In boring B-6, the clay was underlain by siltsone. Fill was encountered on the surface of all four borings. The fill was generally loose and slightly damp. The native sandy soils varied in density from loose to medium dense and were generally slightly damp. The clay soils underlying the sandy soils were generally stiff and damp. The siltstone encountered in B-6 was slightly to moderately weathered and damp.

Groundwater Conditions:

Groundwater was not encountered in any of the eight borings with the exception of a wet zone in B-8 from approximately 23 to 25¹/₂ feet. The source of this moisture is unknown. Groundwater elevations can fluctuate over time depending upon precipitation, irrigation, runoff and infiltration of surface water. We do not have any information regarding the historical fluctuation of the groundwater level in this vicinity.

Laboratory Test Results:

Laboratory analyses of samples tested indicate the sandy and clayey soils have fines contents (silt- and/or clay-sized particles passing the U.S. No. 200 sieve) ranging from approximately 28 to 52 percent. Plasticity indices ranged from non-plastic to 14. In-place dry densities of the samples tested ranged from approximately 104 to 116 pounds per cubic foot (pcf), with natural moisture contents between approximately 3 and 10 percent.

Direct shear testing was performed on representative samples from the Rincon Pond site. The tests were performed on relatively undisturbed ring samples. The three samples tested had angles of internal friction (phi angles) ranging from 23.7 to 32.0 degrees.

Results of all laboratory tests are presented in Appendix B.

OPINIONS AND RECOMMENDATIONS

Geotechnical Considerations:

The sites are considered suitable for the proposed ponds, based on the geotechnical conditions encountered and tested for this report and our understanding of the project. Based on the results of our subsurface exploration, laboratory test results, and engineering analyses, the ponds could be constructed as incised basins as proposed.

Formational sandstone was encountered at depths ranging from approximately 11 to 18 feet below existing ground surface at the WEU Pond site. We anticipate that rock excavation will be required to construct the pond to its planned depth of 20 feet. Excavations in sandstone are anticipated to be difficult, and may necessitate the use of heavy-duty equipment and/or specialized techniques. As an alternate, consideration should be given to making the pond shallower, but with larger footprint to achieve the same volume.

If there are any significant deviations from the assumed finished elevations, structure locations and/or loads noted at the beginning of this report, the opinions and recommendations of this report should be reviewed and confirmed/modified as necessary to reflect the final planned design conditions.

Pond Design and Construction:

The water storage pond could be constructed as an incised basin as proposed. Synthetic liners should be installed in accordance with the manufacturer's recommendations.

Our recommendations are based on the information obtained from the borings performed during our subsurface exploration. It should be realized that subsurface conditions could vary across the extent of the pond areas, and these variations may not become apparent until construction is underway. If, during construction, soil types other than those encountered during our exploration are encountered, we should be contacted to observe the actual conditions and confirm/modify our recommendations, as appropriate.

Slope Stability Analysis:

A slope stability analysis was performed for each site to develop recommendations for the cut slope inclinations for the incised ponds. Galena Slope Stability software (version 6.1) was used as an aid in developing our recommendations. Printouts of the software analyses are available upon request.

Based on the results of our subsurface exploration, laboratory testing, and engineering analyses, the maximum recommended inclinations for the pond walls are 2:1 (horizontal:vertical) for the Rincon Pond. Likewise, the maximum recommended inclinations for the pond walls for the WEU Pond are 2.5:1 in soils and 1:1 in sandstone.

We understand that no above-grade embankments are planned for the project. If the project scope changes to include embankments, GEOMAT should be notified to review the plans and confirm or modify our recommendations as necessary.

Seismic Considerations:

Based on the subsurface conditions encountered in the borings, we estimate that Site Class C is appropriate for the site according to Table 1613.5.2 of the 2009 International Building Code. This parameter was estimated based on extrapolation of data beyond the deepest depth explored, using methods allowed by the code. Actual shear wave velocity testing/analysis and/or exploration to a depth of 100 feet were not performed as part of our scope of services for this project.

Lateral Earth Pressures:

For soils above any free water surface, recommended equivalent fluid pressures for unrestrained foundation elements are presented in the following table:

• <u>Active</u>:

Granular soil backfill	(on-site sand/clay)	35 psf/ft
Undisturbed subsoil		30 psf/ft

• Passive:

Shallow foundation walls	250 psf/ft
Shallow column footings	350 psf/ft
Sump walls	400 psf/ft

Where the design includes restrained elements, the following equivalent fluid pressures are recommended:

٠	At rest:
	Granular soil backfill (on-site sand)50 psf/ft
	Undisturbed subsoil60 psf/ft

Earthwork:

General Considerations:

The opinions contained in this report for the proposed construction are contingent upon compliance with recommendations presented in this section. Although underground facilities such as foundations, septic tanks, cesspools, basements and irrigation systems were not encountered during site reconnaissance, such features could exist and might be encountered during construction.

Site Clearing:

- 1. Strip and remove all existing fill, debris and other deleterious materials from the proposed construction areas.
- 2. If unexpected fills or underground facilities are encountered during site clearing, we should be contacted for further recommendations. All excavations should be observed by GEOMAT prior to backfill placement.
- 3. Stripped materials consisting of vegetation and organic materials should be removed from the site, or used to re-vegetate exposed slopes after completion of grading operations. If it is necessary to dispose of organic materials on-site, they should be placed in non-structural areas, and in fill sections not exceeding 5 feet in height.
- 4. Sloping areas steeper than 5:1 (horizontal:vertical) should be benched to reduce the potential for slippage between existing slopes and fills. Benches should be level and wide enough to accommodate compaction and earth moving equipment.

5. All exposed areas which will receive fill, once properly cleared and benched where necessary, should be scarified to a minimum depth of eight inches, conditioned to near optimum moisture content, and compacted to at least 95% of standard proctor (ASTM D698).

Excavation:

We present the following general comments regarding our opinion of the excavation conditions for the designers' information with the understanding that they are opinions based on our boring data. More accurate information regarding the excavation conditions should be evaluated by contractors or other interested parties from test excavations using the equipment that will be used during construction.

Based on our subsurface evaluation it appears that shallow excavations in soils at the sites will be possible using standard excavation equipment. Deeper excavations that encounter formational rock (at the WEU Pond site, for example) are expected to be difficult and may necessitate the use of heavy-duty equipment and/or specialized techniques.

On-site soils may pump or become unstable or unworkable at high water contents. Dewatering may be necessary to achieve a stable excavation. Workability may be improved by scarifying and drying. Over-excavation of wet zones and replacement with granular materials may be necessary. Lightweight excavation equipment may be required to reduce subgrade pumping.

Fill Materials:

- 1. Native soils could be used to replace existing fill areas and any areas cut for facilitation of the pond excavation.
- 2. Select granular materials should be used as backfill behind walls that retain earth.

3. On site or imported soils to be used in structural fills should conform to the following:

	Percent finer by weight
Gradation	(ASTM C136)
3"	
No. 4 Sieve	
No. 200 Sieve	50 Max
Maximum expansive potential (%)*	1.5
* Measured on a sample compacted to approximate	ately 95 percent of the ASTM
D698 maximum dry density at about 3 percent	below optimum water content.
The sample is confined under a 144-psf surcharg	ge and submerged.

4. Aggregate base should conform to Type I Base Course as specified in Section 303 of the 2014 New Mexico Department of Transportation (NMDOT) *"Standard Specifications for Road and Bridge Construction."*

Placement and Compaction:

- 1. Place and compact fill in horizontal lifts, using equipment and procedures that will produce recommended moisture contents and densities throughout the lift.
- 2. Un-compacted fill lifts should not exceed 10 inches loose thickness.
- 3. Materials should be compacted to the following:

	Minimum Percent
<u>Material</u>	(ASTM D698)
Liner Subgrade Per Liner Manufacturer's Re	commendations
Subgrade soils beneath fill areas	
On site or imported soil fills:	
Beneath footings and slabs on grade	
Aggregate base beneath slabs and pavements	
Miscellaneous backfill	

4. On-site and imported soils should be compacted at moisture contents near optimum.

Compliance:

To assess compliance, observation and testing should be performed by GEOMAT.

Drainage:

Surface Drainage:

Positive drainage should be provided during construction and maintained throughout the life of the proposed project to prevent surface runoff from entering the ponds.

Protective slopes should be provided with a minimum grade of approximately 5 percent for at least 10 feet from the structures. Backfill against footings, exterior walls, and in utility trenches should be well compacted and free of all construction debris to reduce the possibility of moisture infiltration.

Subsurface Drainage:

Free-draining, granular soils containing less than five percent fines (by weight) passing a No. 200 sieve should be placed adjacent to walls which retain earth. A drainage system consisting of either weep holes or perforated drain lines (placed near the base of the wall) should be used to intercept and discharge water which would tend to saturate the backfill. Where used, drain lines should be embedded in a uniformly graded filter material and provided with adequate clean-outs for periodic maintenance. An impervious soil should be used in the upper layer of backfill to reduce the potential for water infiltration.

GENERAL COMMENTS

It is recommended that GEOMAT be retained to provide a general review of final design plans and specifications in order to confirm that grading and foundation recommendations in this report have been interpreted and implemented. In the event that any changes of the proposed project are planned, the opinions and recommendations contained in this report should be reviewed and the report modified or supplemented as necessary.

GEOMAT should also be retained to provide services during excavation, grading, foundation, and construction phases of the work. Observation of footing excavations should be performed prior to placement of reinforcing and concrete to confirm that satisfactory bearing materials are present and is considered a necessary part of continuing geotechnical engineering services for the project. Construction testing, including field and laboratory evaluation of fill, backfill, pavement materials, concrete and steel should be performed to determine whether applicable project requirements have been met.

The analyses and recommendations in this report are based in part upon data obtained from the field exploration. The nature and extent of variations beyond the location of test borings may not become evident until construction. If variations then appear evident, it may be necessary to re-evaluate the recommendations of this report.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by reputable geotechnical engineers practicing in this or similar localities at the same time. No warranty, express or implied, is intended or made. We prepared the report as an aid in design of the proposed project. This report is not a bidding document. Any contractor reviewing this report must draw his own conclusions regarding site conditions and specific construction equipment and techniques to be used on this project.

This report is for the exclusive purpose of providing geotechnical engineering and/or testing information and recommendations. The scope of services for this project does not include, either specifically or by implication, any environmental assessment of the site or identification of contaminated or hazardous materials or conditions. If the owner is concerned about the potential for such contamination, other studies should be undertaken. This report has also not addressed any geologic hazards that may exist on or near the site.

This report may be used only by the Client and only for the purposes stated, within a reasonable time from its issuance. Land use, site conditions (both on and off site), or other factors may change over time and additional work may be required with the passage of time. Any party, other than the Client, who wishes to use this report, shall notify GEOMAT in writing of such intended use. Based on the intended use of the report, GEOMAT may require that additional work be performed and that an updated report be issued. Non-compliance with any of these requirements, by the Client or anyone else, will release GEOMAT from any liability resulting from the use of this report by an unauthorized party.

Appendix A

	B-1 0	B-2 0		
Approximate Not to Scale	SITE PLAN Boring Locations (approximate) GEOMAT Project No. 182-2992 Date of Exploration: April 23, 2018	WEU Enduring I Sandoval Count	Pond Resources	

		B-5	
	B-7	B-6 B-8	
Approximate Not to Scale	SITE PLAN Boring Locations (approximate) GEOMAT Project No. 182-2992 Date of Exploration: April 24, 2018	Rincon Pond Enduring Resources Rio Arriba County, New Mexico	

915 Malta Avenue Farmington, NM 87401 Tel (505) 327-7928 Fax (505) 326-5721										Borehole B-1 Page 1 of 1
Proj Clie Site Rig Drill San Har	oject ent: e Lo Typ Iling mpli mm	catic pe: Met ng W	nber: on: _ hod: letho	E E S C 7 od: <u>R</u> t: <u>1</u>	82-29 nduri ando ME-5 .25" (ing a 40 lb	992 ing F val/f 55 0.D. nd S s	Resou Rio A Hollo Split s	on Frack Irces rriba Co ow Stem poon sa	ounties, n Auger amples	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY Remarks: WEU Pond
Dry Density (pcf) % Passing			Moisture Content (%)	Blows per 6"	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
113.8	41	6	4.7	14-25-27 12-19-28 25-50/6"	18		SC- SM		2 - 3 - 4 - 5 - 6 - ta 7 - 8 - 9 - 10 - 11 - ta 12 - 13 - 14 -	Silty, clayey SAND, tan/orange, fine grained, medium dense to dense, slightly damp tan/gray, contains caliche tan/brown, very dense
				15-28-50 36-50/4" 20-30-19 21-36-	18 R 10 SS 18		RK		15 16 _ 17 _ 18 _ 19 _ 20 _ 21 _ 22 _ 23 _ 24 _ 25 _ 26 _ 27 _ 28 _ 28 _ 29 _ 30 _	SANDSTONE, gray/white, fine- to medium grained, weakly cemented, slightly to moderately weathered, slightly damp Clay in sandstone
				21-36- 50/5"	SS 17	X			31 _ 32 _ 33 _ 34 _ 35 _	Contains shale lenses Total Depth 31½ feet GRAB = Manual Grab Sample D = Disturbed Bulk Sample

-(GE	0/	MA			Farm Tel (Malta Aver ington, NI 505) 327- (505) 326-	Borehole B-2 Page 1 of 1	
P C S R D S H	rojec lient: ite Lo ig Ty rilling ampl	t Nur pcatic pe: Met ing N er W	nber: on: _ hod: /eigh	E E S C Od: _R t: _1	82-29 nduri ando ME-4 .25" (ling a	992 ing F oval/I 55 0.D. ond S s	Resou Rio A Hollo Split s	on Frack urces rriba Co ow Stem poon sa	ounties, n Auger amples	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY
Dry Density T (pcf) g	% Passing kara	Plasticity & A Index		Blows per 6"	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
113.3	28	NP		11-13-13 14-18-33	18	\mathbf{X}	SM		1	Silty SAND, tan/orange, fine grained, medium dense, slightly damp
105.2			4.0	26-36-35 30-50/5"	18		SC- SM		10 11 _ 12 _ 13 _ 14 _ 15 _ 16 _ 17 _ 18 _	Silty, clayey SAND, white/tan, fine- to medium grained, very dense, slightly damp tan/orange
				17-19-17 40-50/1"	SS 18 R 7		RK		19 _ 20 _ 21 _ 22 _ 23 _ 24 _ 25 _ 26 _ 27 _ 28 _	SANDSTONE, gray/white, fine- to medium grained, weakly cemented, slightly to moderately weathered, slightly damp
	= Auge	r Cuttir	nas R	50/6" = Ring-L	SS 6	arrel S	Sampler	SS = Spl	29 _ 30 _ 31 _ 32 _ 33 _ 34 _ 35 _	Total Depth 30½ feet GRAB = Manual Grab Sample D = Disturbed Bulk Sample

-(SE	0/	MA	TINC		Farm Tel (Malta Aver ington, NM 505) 327- (505) 326-	M 87401 7928	Borehole B-3 Page 1 of 1			
P	rojec	t Nar	ne:	V	/EU	and	Rinco	on Frack	ing Por	ndsDate Drilled:4/23/2018			
	-			1						Letitudes Not Determined			
С	lient:			E	ndur	ing F	Resou	irces					
S	ite Lo	catio	on: _	S	ando	oval/I	Rio A	rriba Co	NM Elevation: Not Determined				
R	ig Ty	pe:		С	ME-	55				Boring Location: See Site Plan			
							Hollo	w Stem	Auger	Groundwater Depth: None Encountered			
S	ampl	ing N	/lethc	d: _R	ing a	and S	Split s	poon sa	mples	Logged By:SY			
Н	amm	er W	/eigh	t: <u>1</u>	40 lb	S				Remarks: WEU Pond			
Н	amm	er Fa	all: _	3	0 inc	hes							
Labo	orator	y Res	sults	.9			e	_					
١y	g /e		(%)	L .	Sample Type & Length (in)		Material Type	Soil Symbol	(#)				
pcf)	ssin Siev	ticity	nt (%	Blows per	le T ngth	Symbol	rial	Syı	Depth (ft)	Soil Description			
ury uensity (pcf)	% Passing #200 Sieve	Plasticity Index	Moisture Content (%)	Blov	amp	S	late	Soil	De				
2	°#		Ŭ		w ∞		2	111.1.1.1					
									1 _ 2 _	Clayey SAND, tan/brown, fine grained, dense, slightly damp			
				14-15-17		\times			3				
					6				4				
111.2			5.7	13-19-22	R 18	$\overline{}$	SC		5 _ 6	medium dense			
					10	\triangle			0 _ 7				
									8				
									9_	Grades to silty, clayey sand			
				29-39-50	SS 18				10	Silty, clayey SAND, tan, fine grained, very dense, slightly			
						\square	SC-		12	damp			
							SM		13 _				
									14	SANDSTONE, gray/white, fine- to medium grained, weakly			
110.4			4.4	19-50/6"	R 12				15 _ 16 _	cemented, slightly to moderately weathered, slightly damp			
									17				
									18 _				
							RK		19 _ 20 _				
				12-22-49	SS 18	\bigtriangledown			20 _				
									22 _				
									23				
				20 50/0"					24 _ 25 _	SHALE, dark gray/green, very weakly fissile and friable,			
				30-50/3"	R 9	$\mathbf{\mathbf{x}}$			26 _	slightly damp			
									27				
							RK		28 _				
				10 10 00	00				29 _ 30 _				
				10-16-20	SS 18	\mathbf{X}			31 _				
						r)			32	Total Depth 311/2 feet			
									33 _ 34 _				
									35 _				
A =	= Auge	r Cutti	ngs R	= Ring-L	ined B	arrel S	Sample	r SS = Spl	it Spoon	GRAB = Manual Grab Sample D = Disturbed Bulk Sample			

-¢)(SE	0/	MA		(-) (-)	Farm Tel (Malta Aver ington, NI 505) 327- (505) 326-	M 87401 7928	Borehole B-4
Pro Clie Site Rig Drill San Har	oject ent: e Lo I Tyl Illing mpli mm	Nun catic pe: Met	nber on: _ hod: lethc eigh	:1 S 7 7 7 7 7 7	82-29 ndur ando ME-9 .25" (ing a 40 lb	992 ing F oval/I 55 0.D. and S s	Resou Rio A Hollo Split s	on Frack urces rriba Co ow Stem	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY Remarks: WEU Pond	
Dry Density (pcf) % Passing			~	Blows per 6"	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
116.4			5.0	16-23-31 17-20-19	18	X	SC		1 _ 2 _ 3 _ 5 _ 7 _ 8 _	Clayey SAND, tan/brown, fine grained, medium dense to dense, slightly damp Grades to silty, clayey sand Silty, clayey SAND, tan, fine grained, dense, damp
114.2			9.6	50/6"	R 6 SS	X	SC- SM		9 _ 10 _ 11 _ 12 _ 13 _ 14 _ 15 _	SANDSTONE, gray/white, fine- to medium grained, weakly cemented, slightly to moderately weathered, slightly damp
				46-50/2"	6 R 8	X	RK		16 _ 17 _ 18 _ 19 _ 20 _ 21 _ 22 _ 23 _	
102-2392.05-0 05CUMA1.001 0114/10				50/6" 7-11-13	SS 6 SS 18	X	RK		24 _ 25 _ 26 _ 27 _ 28 _ 29 _ 30 _ 31 _	SHALE, dark gray/green, very weakly fissile and friable, slightly damp
IMAI	Auger	Cuttir	ngs R	= Ring-L	ined B	arrel S	Sampler	r SS = Spli	32 _ 33 _ 34 _ 35 _ it Spoon (Total Depth 31½ feet GRAB = Manual Grab Sample D = Disturbed Bulk Sample

-	$\phi \epsilon$	GE	0/			1	Farm Tel	Malta Aven hington, NM (505) 327-7 (505) 326-	/ 87401 7928	Borehole B-5 Page 1 of 1
P C S R D S H	rojec lient: ite Lo kig Ty prilling ampl	t Nur ocatio pe: g Met ling N	nber: on: _ hod: /ethc	=1 5 7 7 7 7 7 7 7 7 7 7 7	82-29 Indur Sando ME-1 (.25) Ring a 40 lb	992 ing F oval/I 55 O.D. and S s	Resor Rio A Holle Split s	on Frack urces wriba Co ow Stem spoon sa	unties, Auger	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY Remarks: Rincon Pond
Lab	orator	ry Res	sults	.9			ье	0		
Dry Density (pcf)	% Passing #200 Sieve	Plasticity Index	Moisture Content (%)	Blows per	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
				21-9-6 8-7-9	R 18 SS 6	X	SC		1 - 2 - 3 - 4 - 5 - 6 -	Clayey SAND with trace gravel, tan/brown, fine- to coars grained, loose, slightly damp (FILL) Contains reclaimed asphalt/base coarse gravel
				9-7-9	R 18	×			7 - 8 - 9 - 10 _ 11 - 12 - 13 -	Clayey SAND, tan/brown, fine grained, loose, slightly da
				3-2-2	SS 18	\times	SC		14 _ 15 _ 16 _ 17 _ 18 _ 19 _	Fine- to medium grained
113.3			9.7	7-7-11	R 18	X			20 _ 21 _ 22 _ 23 _	Sandy lean CLAY, brown, stiff, damp
				5-5-7	SS 18	\times	CL		24 25 _ 26 27 28	
				3-5-7	SS 18	X			29 _ 30 _ 31 _ 32 _	Contains caliche Total Depth 31½ feet
A									33 _ 34 _ 35 _	

-(GE	0/	MA			Farm Tel (/lalta Aver ington, NI 505) 327- (505) 326-	И 87401 7928	Borehole B-6 Page 1 of 1
	rojec rojec				VEU a 82-29			on Frack		Not Determined
					nduri	ing F				
Client: <u>Enduring Resources</u> Site Location: <u>Sandoval/Rio Arriba Counties, NM</u>										•
R	ig Ty	pe:		C	ME-	55				Boring Location: See Site Plan
							Hollo	w Stem	Auger	Groundwater Depth: <u>None Encountered</u>
S	ampl	ing N	letho	d: _F	Ring a	ind S	Split s	poon sa	mples	Logged By:SY
н	amm	er W	eight	t: <u>1</u>	40 lb	S				Remarks: Rincon Pond
н	amm	er Fa	all: _	3	0 inc	hes				
Labo	orator	y Res	sults	.9	0.0		be			
ity	lg Ve	>	e (%	Blows per	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	
Dens (pcf)	Sie	ticit	sture int ('	SM	ole 7 ngth	ym!	erial	Sy	pth	Soil Description
Dry Density (pcf)	% Passing #200 Sieve	Plasticity Index	Moisture Content (%)	Blo	amp	S	late	Soil	De	
	0#		Ŭ		w ∞		∠ SC	×××××	1	Clayey SAND with trace gravel, tan/brown, fine- to coarse
							SC		2 _	grained, loose, slightly damp (FILL)
	39	9		9-6-6	SS 18	\bigtriangledown			3 _	Clayey SAND, tan/brown, fine grained, medium dense to loose, slightly damp
						\sim			4 _ 5 _	loose, signiy damp
108.2			4.8	5-7-13	R 18		SC		6 _	
									7 _	
								<i>[][[]</i>]	8_	Grades to silty sand Silty SAND, tan/brown, fine grained, loose, slightly damp
							SM		9 _ 10 _	Sity SAND, tan/brown, time grained, toose, slightly damp
				3-3-3	SS 18	\mathbf{X}			11	
									12 _	Clayey SAND, tan/brown to orange, fine grained, loose, slightly damp to damp
									13 _ 14 _	signify damp to damp
				4-7-9					15 _	
				4-7-9	R 18				16 _	
									17 _	
									18 _ 19 _	
				3-3-3	SS				20 _	
				000	18	\boxtimes			21 _	Grades to sandy lean clay
									22 _ 23 _	Sandy lean CLAY, brown, stiff, damp
									23 _	
				4-7-8	R				25 _	
					18		CL		26 _	
									27 _ 28 _	
									20 _	
				50/6"	SS		DIZ		30 _	
					6		RK		31_	SILTSTONE, gray, weakly cemented, slight to moderately veathered, slightly damp
									32 _ 33 _	Total Depth 30½ feet
A :									34 _	
									35 _	
A	= Auge	r Cutti	ngs R	= Ring-l	ined B	arrel	Sample	r SS = Spl	it Spoon	GRAB = Manual Grab Sample D = Disturbed Bulk Sample

-•	GE	0/	MA			Farm Tel (Malta Aver ington, NI 505) 327- (505) 326-	VI 87401 7928	Borehole B-7
Proje Client Site L Rig T Drillin Samp Hamr	ct Nu .ocati ype: g Me bling I mer V	on: on: thod: Veigh	=1 S 7 	82-29 nduri ando ME-5 .25" (ling a 40 lb	992 ing F oval/f 55 0.D. ond S s	Resou Rio A Hollo Split s	on Frack urces rriba Co ow Stem	ounties, Auger amples	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY Remarks: Rincon Pond
Pry Density (pcf) % Passing #200 Sieve	T		Blows per 6"	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
			6-8-8 10-16-24 5-6-6	SS 6 18 SS 18		SC SC		1	Clayey SAND with trace gravel, tan/brown, fine- to coarse grained, loose, slightly damp (FILL) Clayey SAND, tan/brown, fine grained, medium dense, slightly damp
52	14		6-9-11 3-4-5	R 18 SS 18	\mathbf{X}			13 - 14 - 15 - 16 - 17 - 18 - 20 - 21 - 22 - 23 -	loose Grades to sandy lean clay Sandy lean CLAY, brown, stiff, damp
			5-7-10	R 18 SS 18		CL		24 _ 25 _ 26 _ 27 _ 28 _ 29 _ 30 _ 31 _ 32 _ 33 _	Purple/brown to gray, contains trace gravel and calcareous veins
A = Aug	er Cutt	ings R	= Ring-L	ined B	arrel S	Sample	r SS = Spl	34 _ 35 _	GRAB = Manual Grab Sample D = Disturbed Bulk Sample

-••	GE	0	MA			Farm Tel (Malta Aver ington, NI 505) 327- (505) 326-	M 87401 7928	Borehole B-8
Projec Client Site L Rig Ty Drillin Samp Hamn	ct Nui : ocatio ype: g Me lling N ner W	mber on: thod: /eigh	:1 E S 7	82-29 nduri ando ME-5 .25" (ting a 40 lb	992 ing F oval/I 55 0.D. ond S s	Resou Rio A Hollo Split s	on Frack urces rriba Co ow Stem poon sa	ounties, Auger amples	Latitude: Not Determined Longitude: Not Determined NM Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered
Laborato	,	1	er 6"	in)	0	Type	lodi	(ft)	
(pcf) (pcf) (pcf) (pcf) % Passing #200 Sieve	Plasticity	Moisture Content (%)	Blows per	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
			5-5-7 3-3-3	R 18 SS 18		SC		1 - 2 - 3 - 4 - 5 - 7 - 8 - 9 -	Clayey SAND with trace gravel, tan/brown, fine- to coarse grained, loose, slightly damp (FILL) Clayey SAND, tan/brown, fine grained, loose, slightly damp
			5-7-8 3-4-5	R 18 SS 18	\mathbf{X}	SC		10 11 _ 12 _ 13 _ 14 _ 15 _ 16 _ 17 _ 18 _	Gray/brown, higher clay content Grades to sandy lean clay
			4-5-9	R 18	X			19 _ 20 _ 21 _ 22 _ 23 _ 24 _	Sandy lean CLAY, brown, stiff, damp
			4-5-7	SS 18	\times	CL		25 26 _ 27 _ 28 _ 29 _	Wet zone from approximately 23 to 25½ feet
			5-11-15	R 18	X			30	Purple/brown to gray, contains trace gravel and calcareous veins Total Depth 31½ feet
A = Aug	er Cutti	ngs R	 = Ring-L	ined B	arrel S	Sample	r SS = Spl	35 it Spoon	GRAB = Manual Grab Sample D = Disturbed Bulk Sample

	UNIFIE	D SOIL CLASSI	ICATION SYS	TEM	CONSIS	STENCY OR	RELATIVE	
	Major Divisions		Group Symbols	Typical Names	D	ENSITY CRIT	ERIA	
		Clean Gravels	GW	Well-graded gravels and gravel-sand mixtures, little or no fines		tandard Penetration Test Density of Granular Soils		
	Gravels 50% or more of	Clean Graveis	GP	Poorly graded gravels and gravel-sand mixtures, little or no fines	Penetration Resistance, N (blows/ft.)	Relative Density		
	coarse fraction retained on No. 4 sieve	Gravels with	GM	Silty gravels, gravel-sand-silt mixtures	0-4	Very Loose		
Coarse- Grained Soils		Fines	GC	Clayey gravels, gravel-sand-clay mixtures	5-10	Loose		
More than 50% retained on No. 200 sieve		Clean Sands	SW	Well-graded sands and gravelly sands, little or no fines	11-30	Medium De	nse	
	Sands More than 50% of	Glean Sanus	SP	Poorly graded sands and gravelly sands, little or no fines	31-50	Dense		
	coarse fraction passes No. 4 sieve	Sands with	SM	Silty sands, sand-silt mixtures	>50	>50 Very Dense		
		Fines	SC	Clayey sands, sand-clay mixtures		andard Penetrationsity of Fine-Grain		
			ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands	Penetration Resistance, N (blows/ft.)	Consistency	Unconfined Compressive Strength (Tons/ft2)	
		d Clays t 50 or less	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	<2	Very Soft	<0.25	
Fine-Grained Soils			OL	Organic silts and organic silty clays of low plasticity	2-4	Soft	0.25-0.50	
50% or more passes No. 200 sieve			MH	Inorganic silts, micaceous or diatomaceous free sands or silts, elastic silts	4-8	Firm	0.50-1.00	
		d Clays reater than 50	СН	Inorganic clays of high plasticity, fat clays	Stiff	1.00-2.00		
			ОН	Organic clays of medium to high plasticity	15-30	Very Stiff	2.00-4.00	
н	ighly Organic So	ils	PT	Peat, mucic & other highly organic soils	>30	Hard	>4.0	
U.S. Standar	d Sieve Sizes							
>12"	12" 3"	3/4" #4	#10	#40	#200			
Boulders	Cobbles	Gravel coarse fine	coarse	Sand medium	fine	fine Silt or Clay		
Dry	MOISTURE CO Absence of moist, dus			MATERIAL QU trace	1 <u>ANTITY</u> 0-5%	OTHER SY R Ring Sample		

				OTTEROTIE
Dry	Absence of moist, dusty, dry to the touch	trace	0-5%	R Ring Sample
Slightly Damp	Below optimum moisture content for compaction	few	5-10%	S SPT Sample
Moist	Near optimum moisture content, will moisten the hand	little	10-25%	B Bulk Sample
Very Moist	Above optimum moisture content	some	25-45%	 Ground Water
Wet	Visible free water, below water table	mostly	50-100%	

BASIC LOG FORMAT:

Group name, Group symbol, (grain size), color, moisture, consistency or relative density. Additional comments: odor, presence of roots, mica, gypsum, coarse particles, etc.

EXAMPLE:

SILTY SAND w/trace silt (SM-SP), Brown, loose to med. Dense, fine to medium grained, damp

UNIFIED SOIL CLASSIFICATION SYSTEM

TEST DRILLING EQUIPMENT & PROCEDURES

Description of Subsurface Exploration Methods

Drilling Equipment – Truck-mounted drill rigs powered with gasoline or diesel engines are used in advancing test borings. Drilling through soil or softer rock is performed with hollow-stem auger or continuous flight auger. Carbide insert teeth are normally used on bits to penetrate soft rock or very strongly cemented soils which require blasting or very heavy equipment for excavation. Where refusal is experienced in auger drilling, the holes are sometimes advanced with tricone gear bits and NX rods using water or air as a drilling fluid.

Sampling Procedures - Dynamically driven tube samples are usually obtained at selected intervals in the borings by the ASTM D1586 test procedure. In most cases, 2" outside diameter, 1 3/8" inside diameter, samplers are used to obtain the standard penetration resistance. "Undisturbed" samples of firmer soils are often obtained with 3" outside diameter samplers lined with 2.42" inside diameter brass rings. The driving energy is generally recorded as the number of blows of a 140-pound, 30-inch free fall drop hammer required to advance the samplers in 6-inch increments. These values are expressed in blows per foot on the boring logs. However, in stratified soils, driving resistance is sometimes recorded in 2- or 3-inch increments so that soil changes and the presence of scattered gravel or cemented layers can be readily detected and the realistic penetration values obtained for consideration in design. "Undisturbed" sampling of softer soils is sometimes performed with thin-walled Shelby tubes (ASTM D1587). Tube samples are labeled and placed in watertight containers to maintain field moisture contents for testing. When necessary for testing, larger bulk samples are taken from auger cuttings. Where samples of rock are required, they are obtained by NX diamond core drilling (ASTM D2113).


Boring Records - Drilling operations are directed by our field engineer or geologist who examines soil recovery and prepares boring logs. Soils are visually classified in accordance with the Unified Soil Classification System (ASTM D2487), with appropriate group symbols being shown on the logs.

Appendix B

	-	SAMPLE	ASTM	D698		DEN	SITY	ATTER	RBERG	IMITS	-	DIDEAT		
LAB NO.	BORING NO.	DEPTH (ft)	Density	Moisture	MOISTURE CONT. (%)			LL	PL	PI	SWELL (%)	DIRECT	% PASS #200 SIEVE	CLASSIFICATION
WEU														
6294	B1	10			-	-		23	17	6			41	SC-SM; Silty, Clayey SAND
6295	B2	2.5				-		NLL	NPL	NP			28	SM; Silty SAND
6327	B1	2.5		-	4.7	119.1	113.8						-	
6328	B1	10			2.9	106.9	103.8			_			-	
6330	B2	5		-	5.2	119.2	113.3						-	
6331	B2	15			4.0	109.4	105.2		-				-	
6333	B3	5			5.7	117.5	111.2		-	-			-	
6334	B3	15			4.4	115.2	110.4			-			-	
6336	B4	2.5			5.0	122.1	116.4							-
6337	B4	10			9.6	125.1	114.2			-			-	-
Rincon			-	_	-	-		-		_				
6296	B6	2.5		-	-	-		22	13	9			39	SC; Clayey SAND
6297	B7	20			-	-		27	13	14			52	CL; Sandy Lean CLAY
6339	B5	20			9.7	124.3	113.3							_
6340	B6	5			4.8	113.4	108.2					-	-	
6341	B5	10			-							Attached		
6342	B6	15			-							Attached		
6343	B7	5		-	-		-					Attached		
												Project		WEU & Rincon Fracking Ponds
						CI III	IMARY O		TEST	e		Job No.		182-2992
								r 301	. 1531	3	_	Location	1	Sandoval & Rio Arriba Countie
1										Date Drille	ed	4/23/2018		



Direct Shear of Soil Under Consolidated-Drained Conditions



2.65 was assumed for weight-volume calculations.

Analysis & Quality Review/Date

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality, TRI limits reported upon accept, except in Aut, without price approval of TRI.


TRI ENVIRONMENTAL, INC.

9063 BEE CAVES RD. - AUSTIN, TX 78733 - USA | PH: 800.880.TEST OR 512.263.2101

Jeffrey A. Kuhn, Ph.D., P.E., 5/9/18







2.65 was assumed for weight-volume calculations.

TRI ENVIRONMENTAL, INC.


9063 BEE CAVES RD. - AUSTIN, TX 78733 - USA PH: 800.880.TEST OR 512.263.2101

Analysis & Quality Review/Date

than those tested. TRI neither accepts respon rt. except in full, without prior approval of TRI. The testing herein is based upon accepted indus for nor makes claim as to the final use and purp nod listed. Test results reported herein do not apply to ad maintains client confidentiality. TRI limits reproduct







2.65 was assumed for weight-volume calculations.

Analysis & Quality Review/Date

The testing herein is based upon accepted industry practice as well as the test method listed. Test results reported herein do not apply to samples other than those tested. TRI neither accepts responsibility for nor makes claim as to the final use and purpose of the material. TRI observes and maintains client confidentiality. TRI limits reproduction of this report, except in full, without prior approval of TRI.

TRI ENVIRONMENTAL, INC.

9063 BEE CAVES RD. - AUSTIN, TX 78733 - USA PH: 800.880.TEST DR 512.263.2101

Jeffrey A. Kuhn, Ph.D., P.E., 5/10/18

LABORATORY TESTING PROCEDURES

Consolidation Tests: One-dimensional consolidation tests are performed using "Floating-ring" type consolidometers. The test samples are approximately 2.5 inches in diameter and 1.0 inch high and are usually obtained from test borings using the dynamically-driven ring samplers. Test procedures are generally as outlined in ASTM D2435. Loads are applied in several increments to the upper surface of the test specimen and the resulting deformations are recorded at selected time intervals for each increment. Samples are normally loaded in the in-situ moisture conditions to loads which approximate the stresses which will be experienced by the soils after the project is completed. Samples are usually then submerged to determine the effect of increased moisture contents on the soils. Each load increment is applied until compression/expansion of the sample is essentially complete (normally movements of less than 0.0003 inches/hour). Porous stones are placed on the top and bottom surfaces of the samples to facilitate introduction of the moisture.

Expansion Tests: Tests are performed on either undisturbed or recompacted samples to evaluate the expansive potential of the soils. The test samples are approximately 2.5 inches in diameter and 1.0 inch high. Recompacted samples are typically remolded to densities and moisture contents that will simulate field compaction conditions. Surcharge loads normally simulate those which will be experienced by the soils in the field. Surcharge loads are maintained until the expansion is essentially complete.

<u>Atterberg Limits/Maximum Density/Optimum Moisture Tests:</u> These tests are performed in accordance with the prescribed ASTM test procedures.

Appendix C

Important Information about This Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you - assumedly a client representative - interpret and apply this geotechnical-engineering report as effectively as possible. In that way, clients can benefit from a lowered exposure to the subsurface problems that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed below, contact your GBA-member geotechnical engineer. Active involvement in the Geoprofessional Business Association exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Geotechnical-Engineering Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical-engineering study conducted for a given civil engineer will not likely meet the needs of a civilworks constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnicalengineering report is unique, prepared *solely* for the client. *Those who rely on a geotechnical-engineering report prepared for a different client can be seriously misled*. No one except authorized client representatives should rely on this geotechnical-engineering report without first conferring with the geotechnical engineer who prepared it. *And no one – not even you – should apply this report for any purpose or project except the one originally contemplated*.

Read this Report in Full

Costly problems have occurred because those relying on a geotechnicalengineering report did not read it *in its entirety*. Do not rely on an executive summary. Do not read selected elements only. *Read this report in full*.

You Need to Inform Your Geotechnical Engineer about Change

Your geotechnical engineer considered unique, project-specific factors when designing the study behind this report and developing the confirmation-dependent recommendations the report conveys. A few typical factors include:

- the client's goals, objectives, budget, schedule, and risk-management preferences;
- the general nature of the structure involved, its size, configuration, and performance criteria;
- the structure's location and orientation on the site; and
- other planned or existing site improvements, such as retaining walls, access roads, parking lots, and underground utilities.

Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light-industrial plant to a refrigerated warehouse;
- the elevation, configuration, location, orientation, or weight of the proposed structure;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes – even minor ones – and request an assessment of their impact. The geotechnical engineer who prepared this report cannot accept responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.

This Report May Not Be Reliable

- Do not rely on this report if your geotechnical engineer prepared it:
- for a different client;
- for a different project;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, that it could be unwise to rely on a geotechnical-engineering report whose reliability may have been affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If your geotechnical engineer has not indicated an "apply-by" date on the report, ask what it should be*, and, in general, *if you are the least bit uncertain* about the continued reliability of this report, contact your geotechnical engineer before applying it. A minor amount of additional testing or analysis – if any is required at all – could prevent major problems.

Most of the "Findings" Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site's subsurface through various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing were performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgment to form opinions about subsurface conditions throughout the site. Actual sitewide-subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team from project start to project finish, so the individual can provide informed guidance quickly, whenever needed.

This Report's Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, *they are not final*, because the geotechnical engineer who developed them relied heavily on judgment and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* revealed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmationdependent recommendations if you fail to retain that engineer to perform construction observation*.

This Report Could Be Misinterpreted

Other design professionals' misinterpretation of geotechnicalengineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a full-time member of the design team, to:

- confer with other design-team members,
- help develop specifications,
- review pertinent elements of other design professionals' plans and specifications, and
- be on hand quickly whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction observation.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note conspicuously that you've included the material for informational purposes only.* To avoid misunderstanding, you may also want to note that "informational purposes" means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report, but they may rely on the factual data relative to the specific times, locations, and depths/elevations referenced. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled "limitations," many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely*. Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a "phase-one" or "phase-two" environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnicalengineering report does not usually relate any environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures*. If you have not yet obtained your own environmental information, ask your geotechnical consultant for risk-management guidance. As a general rule, *do not rely on an environmental report prepared for a different client, site, or project, or that is more than six months old.*

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold

While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, none of the engineer's services were designed, conducted, or intended to prevent uncontrolled migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer's recommendations will not of itself be sufficient to prevent moisture infiltration*. Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not buildingenvelope or mold specialists*.



Telephone: 301/565-2733 e-mail: info@geoprofessional.org www.geoprofessional.org

Copyright 2016 by Geoprofessional Business Association (GBA). Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with GBA's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of GBA, and only for purposes of scholarly research or book review. Only members of GBA may use this document or its wording as a complement to or as an element of a report of any kind. Any other firm, individual, or other entity that so uses this document without being a GBA member could be committing negligent



October 8, 2018

James McDaniel

Enduring Resources 332 CR 3100 Aztec, New Mexico 87410

RE: Geotechnical Engineering Study - Addendum No. 1 Lowry Camp Rincon Unit Fracking Water Pond Sandoval County, New Mexico GEOMAT Project No. 182-2992

The purpose of this letter report is to provide updated recommendations based upon revised information related to the design and construction of the Lowry Camp Rincon Unit (Rincon) fracking water pond located in in Rio Arriba County, New Mexico. This letter report should be considered as Addendum No. 1 to our Geotechnical Engineering Report No. 182-2992, dated May 16, 2018, and made a part thereof.

As requested by Enduring Resources in a meeting and confirmed in correspondence dated July 18, 2018, GEOMAT Inc. (GEOMAT) advanced two supplemental borings at the Rincon site to obtain additional samples specifically for evaluation of soil properties. The supplemental borings and analysis were a result of changes to the design of the pond from a fully incised pond to a partially incised pond with constructed embankments on the order of 2 to 15 feet. The proposed changes are shown in the attached 30% review drawings from Souder, Miller and Associates (SMA) as provided by Enduring Resources to GEOMAT on August 29, 2018.

PROJECT DESCRIPTION

Our scope of services performed for this addendum included advancing supplemental borings for sampling, laboratory testing of the samples and engineering analyses.

Field Work:

Supplemental samples were obtained from the Rincon site for laboratory analysis on July 20, 2018. Two additional exploratory borings, designated B-9 and B-10 were advanced at the approximate locations shown on the attached Site Plan. Borings were drilled to depths of approximately 20 feet below existing ground surface (bgs). The borings were advanced using a CME-55 truck-mounted drill rig with continuous-flight, 7.25-inch O.D. hollow-stem auger. Representative bulk samples of subsurface materials were obtained from the auger cuttings.

LABORATORY ANALYSIS

Laboratory Testing:

Bulk samples retrieved during the field exploration were transported to our laboratory for further evaluation. At that time, the samples were prepared and laboratory tests were performed to evaluate the engineering properties of the subsurface materials. Samples were compiled and sent to Knight Piésold and Co. - Soils Laboratory (KP) for direct shear testing remolded to approximately 95 percent of the maximum dry density and optimum moisture content as determined by ASTM D698.

Laboratory Test Results:

Laboratory analyses of the bulk samples tested indicate the soils had fines contents (silt- and/or clay-sized particles passing the U.S. No. 200 sieve) of 49 and 51 percent for supplemental borings B-9 and B-10, respectively. This is consistent with data from the May 2018 report. Plasticity indices for B-9 and B-10 were 9 and 6, respectively. Results of the ASTM D698 proctor test indicated maximum dry densities of 115.7 pcf and 116.2 pcf with optimum moisture contents of 12.5% and 12.6% for samples from B-9 and B-10, respectively.

Direct shear results of remolded samples from B-9 and B-10, indicate an effective friction angle, θ' , of approximately 28.6° and 31.1°, respectively and an effective cohesion, c', of approximately 86 psf and 41 psf for B-9 and B-10, respectively. Weighted averages of these values, equaling 30° for friction angle and 70 psf for cohesion, were utilized along with a dry density of 110 pcf in slope stability analysis of the revised pond embankments constructed with engineered fill at 95% compaction as recommended.

Results of both the GEOMAT testing and the KP direct shear are attached in Appendix B.

ENGINEERING ANALYSIS

Slope Stability Analysis:

A slope stability analysis was performed to evaluate both the cut slope inclinations for the incised portion of the pond and the constructed pond embankment. Data was taken directly from the supplied designs. Analysis was performed for the revised pond designs provided with 2.5:1 internal slopes with 3.0:1 external slopes (horizontal:vertical). A minimum access roadway width of 12 feet on the top of the pond embankments was used in the analyses. Light vehicle loads were added to the model as two 1500-pound point loads to represent the axle loads. Galena Slope Stability software (version 6.1) was used in developing our recommendations.

Seismic Considerations:

Seismic design parameters for the proposed KWU recycling pond were obtained utilizing the U.S. Geological Survey's (USGS) Unified Hazard Tool located at the web address - <u>https://earthquake.usgs.gov/hazards/interactive/</u>. The site replaces previously available information from the USGS and is part of the probabilistic seismic hazard analysis (PSHA) platform developed and maintained by the National Seismic Hazard Mapping Project (NSHMP) within the USGS earthquake hazards program.

The Earthquake Hazard and Probability Map for the Conterminous U.S. for 2014 (version 4.0.x) was selected to display the peak ground acceleration for n event with a probability of 2% in 50 years. From the projects location the site classification was determined to be on the B/C boundary. The resulting peak force produced an earthquake coefficient of 0.1006, which was enter into the Galena models for all sections to represent an overlying earthquake force.

Note that the seismic site classification was estimated based on site location, the results of our subsurface exploration, experience with similar projects in the area, and a review of a geologic map of the project area. Additional exploration to greater depths would be required to verify the subsurface conditions below the depth explored for this report.

Slope Stability Analysis Results:

Graphical printouts are attached in the Appendix and results are included in Table 1 below.

Table 1 - Slope Stability Analysis.

			Factor of	f Safety
		Slope	Base	Seismic Applied
Embankment	Internal Slope	2.5:1	2.02	1.59
Embankment	External Slope	3.0:1	2.25	1.72

Based on the results of our subsurface exploration, laboratory testing, and engineering analyses, the designed grades of the incised pond walls and the constructed embankments are acceptable at the proposed 2.5:1 internal and 3:1 external in the site soils if constructed as recommended herein.

If the project scope changes further or is altered, GEOMAT should be notified to review the plans and confirm or modify our recommendations as necessary.

Pond Design and Construction:

The revised fracking water pond design including pond embankments could be constructed as partially incised with embankments as proposed. The double HDPE liner system should be installed in accordance with the manufacturer's recommendations. Compaction of the subgrade within the incised portions of the pond below the liner should be in accordance with the liner manufacturer's recommendations. Subgrade and fill for the embankments should be constructed in accordance with the **Placement and Compaction** section of the original geotechnical report. Embankment fills should be compacted to a minimum 95 percent of the maximum dry density as determined by ASTM D698 at near optimum moisture content in lifts not exceeding 10-inches in loose thickness.

GENERAL COMMENTS

Our recommendations with respect to the construction of the NUE pond are based on the information obtained from the supplemental borings and remain consistent with those given in the original report. It should be realized that subsurface conditions could vary across the extent of the pond area, and these variations may not become apparent until construction is underway. If, during construction, soil types other than those encountered during our exploration are encountered, we should be contacted to observe the actual conditions and confirm/modify our recommendations, as appropriate. It is recommended that GEOMAT be retained to provide a general review of final design plans and specifications in order to confirm that grading recommendations in this report have been interpreted and implemented. In the event that any changes of the proposed project are planned, the opinions and recommendations contained in this report should be reviewed and the report modified or supplemented as necessary.

GEOMAT should also be retained to provide services during excavation, grading, and construction phases of the work. Construction testing, including field and laboratory evaluation of fill, backfill, and compacted slopes should be performed to determine whether applicable project requirements have been met.

We have appreciated being of service to you in the geotechnical engineering phase of this project. If you have any questions or concerns regarding this addendum or the associated report, please feel free to contact us.

Sincerely yours, GEOMAT Inc.



Robert "Bob" Flegal, P.E. Senior Engineer

Matthew J. Cramer, P.E. President

Copies to: Addressee (1); Heather McDaniel, P.E., C.F.M., SMA both via E-mail

Attachments: Vicinity Map Site Plan (Supplemental Borings) Laboratory Test Results SMA 30% Review Site Grading & Drainage Plan Slope Stability Figures

		В-#	nd rings drilled as part of Addendum tial Borings drilled
		B-10 B-8	
Approximate Not to Scale	SITE PLANBoring Locations (approximate)GEOMAT Project No. 182-2992Date of Exploration: April 24 & July 20, 2018	PROJECT Rincon Pond Enduring Resources Rio Arriba County, New Mexico	GEOMAT _{inc.}

UNIFIED SOIL CLASSIFICATION SYSTEM CONSISTENCY OR RELATIVE									
	Major Divisions		Group Symbols	Typical Names	=1	ENSITY CRIT			
			GW	Well-graded gravels and gravel-sand mixtures, little or no fines		Indard Penetration			
	Gravels 50% or more of	Clean Gravels	GP	Poorly graded gravels and gravel-sand mixtures, little or no fines	Penetration Resistance, N (blows/ft.)	Relative Density			
	coarse fraction retained on No. 4 sieve	Gravels with	GM	Silty gravels, gravel-sand-silt mixtures	0-4	Very Loose			
Coarse- Grained Soils		Fines	GC	Clayey gravels, gravel-sand-clay mixtures	5-10	Loose			
More than 50% retained on No. 200 sieve		Clean Sands	SW	Well-graded sands and gravelly sands, little or no fines	11-30	Medium De	nse		
	Sands More than 50% of		SP	Poorly graded sands and gravelly sands, little or no fines	31-50	Dense			
	coarse fraction passes No. 4 sieve	Sands with	SM	Silty sands, sand-silt mixtures	>50	Very Dense	Very Dense		
		Fines	SC	Clayey sands, sand-clay mixtures			ndard Penetration Test ty of Fine-Grained Soils		
			ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands	Penetration Resistance, N (blows/ft.)	Consistency	Unconfined Compressive Strength (Tons/ft2)		
Fire Oreined	Silts an Liquid Limi		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	<2	Very Soft	<0.25		
Fine-Grained Soils			OL	Organic silts and organic silty clays of low plasticity	2-4	Soft	0.25-0.50		
50% or more passes No. 200 sieve			MH	Inorganic silts, micaceous or diatomaceous free sands or silts, elastic silts	4-8	Firm	0.50-1.00		
	Silts an Liquid Limit g		СН	Inorganic clays of high plasticity, fat clays	8-15	Stiff	1.00-2.00		
			ОН	Organic clays of medium to high plasticity	15-30	Very Stiff	2.00-4.00		
н	ighly Organic So	ils	PT	Peat, mucic & other highly organic soils	>30	Hard	>4.0		
	d Sieve Sizes	0/4" #4	#40	#10					
>12" Boulders	12" 3" Cobbles	3/4" #4 Gravel	#10	#40 Sand	#200	011	or Clou		
		coarse fine	coarse	medium	fine	Silt	or Clay		
Dry Slightly Damp	MOISTURE CO Absence of moist, dus Below optimum moistu		on	MATERIAL QU trace few	0-5%	OTHER SY R Ring Sample S SPT Sample	MBOLS		
Moist Very Moist	Near optimum moistur Above optimum moistu	e content, will moisten t ure content	he hand	little some	10-25% 25-45%	B Bulk Sample ▼ Ground Wate	r		
Wet	Visible free water, belo	w water table		mostly	50-100%				

Slightly Damp	Below optimum moisture content for compaction
Moist	Near optimum moisture content, will moisten the hand
Very Moist	Above optimum moisture content
Wet	Visible free water, below water table

BASIC LOG FORMAT:

Group name, Group symbol, (grain size), color, moisture, consistency or relative density. Additional comments: odor, presence of roots, mica, gypsum, coarse particles, etc.

EXAMPLE:

SILTY SAND w/trace silt (SM-SP), Brown, loose to med. Dense, fine to medium grained, damp

UNIFIED SOIL CLASSIFICATION SYSTEM

TEST DRILLING EQUIPMENT & PROCEDURES

Description of Subsurface Exploration Methods

Drilling Equipment – Truck-mounted drill rigs powered with gasoline or diesel engines are used in advancing test borings. Drilling through soil or softer rock is performed with hollow-stem auger or continuous flight auger. Carbide insert teeth are normally used on bits to penetrate soft rock or very strongly cemented soils which require blasting or very heavy equipment for excavation. Where refusal is experienced in auger drilling, the holes are sometimes advanced with tricone gear bits and NX rods using water or air as a drilling fluid.

Sampling Procedures - Dynamically driven tube samples are usually obtained at selected intervals in the borings by the ASTM D1586 test procedure. In most cases, 2" outside diameter, 1 3/8" inside diameter, samplers are used to obtain the standard penetration resistance. "Undisturbed" samples of firmer soils are often obtained with 3" outside diameter samplers lined with 2.42" inside diameter brass rings. The driving energy is generally recorded as the number of blows of a 140-pound, 30-inch free fall drop hammer required to advance the samplers in 6-inch increments. These values are expressed in blows per foot on the boring logs. However, in stratified soils, driving resistance is sometimes recorded in 2- or 3-inch increments so that soil changes and the presence of scattered gravel or cemented layers can be readily detected and the realistic penetration values obtained for consideration in design. "Undisturbed" sampling of softer soils is sometimes performed with thin-walled Shelby tubes (ASTM D1587). Tube samples are labeled and placed in watertight containers to maintain field moisture contents for testing. When necessary for testing, larger bulk samples are taken from auger cuttings. Where samples of rock are required, they are obtained by NX diamond core drilling (ASTM D2113).

Boring Records - Drilling operations are directed by our field engineer or geologist who examines soil recovery and prepares boring logs. Soils are visually classified in accordance with the Unified Soil Classification System (ASTM D2487), with appropriate group symbols being shown on the logs.

LAB NO.	BORING	SAMPLE DEPTH	ASTM	D698	MOISTURE		ISITY	ATTER	RBERG	LIMITS	SWELL	WELL DIRECT % PASS		CLASSIFICATION
LAD NU.	NO.	(ft)	Density	Moisture	CONT. (%)	WET (pcf)	DRY (pcf)	LL	PL	PI	(%)	SHEAR	#200 SIEVE	CLASSIFICATION
WEU														
6294	B1	10						23	17	6	-		41	SC-SM; Silty, Clayey SAND
6295	B2	2.5			-		-	NLL	NPL	NP			28	SM; Silty SAND
6327	B1	2.5			4.7	119.1	113.8		-					-
6328	B1	10		-	2.9	106.9	103.8							-
6330	B2	5			5.2	119.2	113.3						-	-
6331	B2	15			4.0	109.4	105.2							-
6333	B3	5			5.7	117.5	111.2						-	-
6334	B3	15			4.4	115.2	110.4		-				-	-
6336	B4	2.5		-	5.0	122.1	116.4			-			-	-
6337	B4	10		-	9.6	125.1	114.2			-				-
Rincon				-			-		-			-		
6296	B6	2.5					-	22	13	9	-		39	SC; Clayey SAND
6297	B7	20					-	27	13	14			52	CL; Sandy Lean CLAY
6339	B5	20			9.7	124.3	113.3				-		-	_
6340	B6	5			4.8	113.4	108.2		-		-			_
6341	B5	10										Included in	-	
6342	B6	15					-			-		05/16/18		
6343	B7	5					-					Report	-	
6836 ¹	B9	0 - 10.0	115.7	12.5				25	16	9		Attached	49	SC; Clayey SAND
6837 ¹	B10	10 - 20.0	116.2	12.6				23	17	6		Attached	51	CL-ML; Silty CLAY with sand
											Project			WEU & Rincon Fracking Ponds
	G		N	ΔΤ	-	e1 14			TEOT	c		Job No.		182-2992
			501	IMARY O	r 301	- 1551	3		Location		Sandoval & Rio Arriba Counties			
											Date Drille	ed	4/23/2018 & ¹ 6/20/2018	


LABORATORY TESTING PROCEDURES

Consolidation Tests: One-dimensional consolidation tests are performed using "Floating-ring" type consolidometers. The test samples are approximately 2.5 inches in diameter and 1.0 inch high and are usually obtained from test borings using the dynamically-driven ring samplers. Test procedures are generally as outlined in ASTM D2435. Loads are applied in several increments to the upper surface of the test specimen and the resulting deformations are recorded at selected time intervals for each increment. Samples are normally loaded in the in-situ moisture conditions to loads which approximate the stresses which will be experienced by the soils after the project is completed. Samples are usually then submerged to determine the effect of increased moisture contents on the soils. Each load increment is applied until compression/expansion of the sample is essentially complete (normally movements of less than 0.0003 inches/hour). Porous stones are placed on the top and bottom surfaces of the samples to facilitate introduction of the moisture.

Expansion Tests: Tests are performed on either undisturbed or recompacted samples to evaluate the expansive potential of the soils. The test samples are approximately 2.5 inches in diameter and 1.0 inch high. Recompacted samples are typically remolded to densities and moisture contents that will simulate field compaction conditions. Surcharge loads normally simulate those which will be experienced by the soils in the field. Surcharge loads are maintained until the expansion is essentially complete.

<u>Atterberg Limits/Maximum Density/Optimum Moisture Tests:</u> These tests are performed in accordance with the prescribed ASTM test procedures.





Checked By: JDB

DIRECT SHEAR TEST

Date:	8/9/18									
Client:	Geomat									
Project:	Kimbeto, S.Escavada & Ri	Kimbeto, S.Escavada & Rincon Ponds								
Project No.:	DV108-00304/04									
Depth:	0-10'	Sample Number:	6836							
Description:										
Remarks:	Failure chosen at peak she	ar stress and 15% strain. Test wa	as inundated.							
Type of Sample:	Remolded									
Assumed Specific G	ravity=2.7 LL=	PL=	PI=							

	Parameters for Specimen No. 1										
Specimen Parameter	Initial	Consolidated	Final								
Moisture content: Moist soil+tare, gms.	149.700		553.620								
Moisture content: Dry soil+tare, gms.	132.390		528.000								
Moisture content: Tare, gms.	0.000		395.610								
Moisture, %	13.1	19.4	19.4								
Moist specimen weight, gms.	149.7										
Diameter, in.	2.42	2.42									
Area, in. ²	4.60	4.60									
Height, in.	1.00	0.99									
Net decrease in height, in.		0.01									
Wet density, pcf	124.0	132.1									
Dry density, pcf	109.7	110.7									
Void ratio	0.5372	0.5224									
Saturation, %	65.7	100.0									
	est Readin	ngs for Specimen No. 1									

Load ring constant = 31.408 lbs. per input unit Normal stress = 500 psf Strain rate, %/min. = 0.04

Fail. Stress = 332 psf at reading no. 20

Ult. Stress = 322 psf at reading no. 73

No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
0	0.0000	0.0000	0.0	0.0	0	0.0001
1	0.0050	0.2260	7.1	0.2	222	-0.0002
2	0.0100	0.2961	9.3	0.4	291	-0.0002
3	0.0150	0.3215	10.1	0.6	316	0.0001
4	0.0200	0.3215	10.1	0.8	316	0.0000
5	0.0250	0.3215	10.1	1.0	316	0.0001
6	0.0300	0.3152	9.9	1.2	310	-0.0003
7	0.0350	0.3215	10.1	1.4	316	-0.0005
8	0.0400	0.3247	10.2	1.7	319	-0.0009
9	0.0450	0.3279	10.3	1.9	322	-0.0013
10	0.0500	0.3279	10.3	2.1	322	-0.0016
11	0.0550	0.3343	10.5	2.3	329	-0.0018
12	0.0600	0.3343	10.5	2.5	329	-0.0020
13	0.0650	0.3343	10.5	2.7	329	-0.0021
					Knight F	Diesold G

Knight Piesold Geotechnical Lab.

8/18/2018

Horizontal Shear Vertical Def. Dial Load Load Strain Stress Def. Dial	
No. in. Dial Ibs. % psf in.	
14 0.0700 0.3343 10.5 2.9 329 -0.0022	
15 0.0750 0.3343 10.5 3.1 329 -0.0022	
16 0.0800 0.3343 10.5 3.3 329 -0.0023	
17 0.0850 0.3343 10.5 3.5 329 -0.0023	
18 0.0900 0.3343 10.5 3.7 329 -0.0024	
19 0.0950 0.3343 10.5 3.9 329 -0.0024	
20 0.1000 0.3375 10.6 4.1 332 -0.0024	
21 0.1050 0.3343 10.5 4.3 329 -0.0025	
22 0.1100 0.3343 10.5 4.5 329 -0.0025	
23 0.1150 0.3343 10.5 4.8 329 -0.0025	
24 0.1200 0.3311 10.4 5.0 326 -0.0025	
25 0.1250 0.3311 10.4 5.2 326 -0.0026	
26 0.1300 0.3279 10.3 5.4 322 -0.0026	
27 0.1350 0.3279 10.3 5.6 322 -0.0026	
28 0.1400 0.3279 10.3 5.8 322 -0.0026	
29 0.1450 0.3311 10.4 6.0 326 -0.0026	
30 0.1500 0.3343 10.5 6.2 329 -0.0026	
31 0.1550 0.3343 10.5 6.4 329 -0.0026	
32 0.1600 0.3311 10.4 6.6 326 -0.0026	
33 0.1650 0.3311 10.4 6.8 326 -0.0026	
34 0.1700 0.3311 10.4 7.0 326 -0.0026	
35 0.1750 0.3279 10.3 7.2 322 -0.0025	
36 0.1800 0.3279 10.3 7.4 322 -0.0025	
37 0.1850 0.3279 10.3 7.6 322 -0.0024	
38 0.1900 0.3279 10.3 7.9 322 -0.0025	
39 0.1950 0.3311 10.4 8.1 326 -0.0025	
40 0.2000 0.3343 10.5 8.3 329 -0.0024	
41 0.2050 0.3311 10.4 8.5 326 -0.0023	
42 0.2100 0.3279 10.3 8.7 322 -0.0022	
43 0.2150 0.3215 10.1 8.9 316 -0.0022	
44 0.2200 0.3215 10.1 9.1 316 -0.0022	
45 0.2250 0.3247 10.2 9.3 319 -0.0022 46 0.2200 0.2270 10.2 0.5 222 0.0022	
46 0.2300 0.3279 10.3 9.5 322 -0.0022 47 0.2350 0.3270 10.3 9.7 322 0.0021	
47 0.2350 0.3279 10.3 9.7 322 -0.0021 48 0.2400 0.3279 10.3 9.9 322 -0.0021	
48 0.2400 0.3279 10.3 9.9 322 -0.0021 49 0.2450 0.3279 10.3 10.1 322 -0.0021	
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	
51 0.2550 0.3279 10.3 10.5 322 -0.0021 51 0.2550 0.3279 10.3 10.5 322 -0.0021	
51 0.2550 0.3279 10.3 10.5 322 -0.0021 $52 0.2600 0.3279 10.3 10.7 322 -0.0021$	
53 0.2650 0.3279 10.3 11.0 322 -0.0021 53 0.2650 0.3279 10.3 11.0 322 -0.0022	
53 0.2030 0.3279 10.3 11.0 322 -0.0022 54 0.2700 0.3279 10.3 11.2 322 -0.0021	
55 0.2750 0.3279 10.3 11.4 322 -0.0020	
56 0.2800 0.3279 10.3 11.4 322 -0.0020 56 0.2800 0.3279 10.3 11.6 322 -0.0020	
50 0.2800 0.3279 10.3 11.0 322 -0.0020 57 0.2850 0.3279 10.3 11.8 322 -0.0019	
57 0.2850 0.3279 10.3 11.8 322 0.0019 58 0.2900 0.3279 10.3 12.0 322 -0.0018	
56 0.2900 0.3279 10.5 12.0 322 -0.0018 59 0.2950 0.3311 10.4 12.2 326 -0.0017	
60 0.3000 0.3311 10.4 12.4 326 -0.0016	
Knight Piesold Geotechnical Lab.	

				Т	est <u>Rea</u>	dings fo
	Horizontal				Shear	Vertical
No.	Def. Dial in.	Load Dial	Load Ibs.	Strain %	Stress psf	Def. Dial in.
61	0.3050	0.3279	10.3	12.6	-	-0.0016
62	0.3100	0.3279	10.3	12.8		-0.0017
63	0.3150	0.3279	10.3	13.0		-0.0017
64	0.3200	0.3279	10.3	13.2		-0.0017
65	0.3250	0.3279	10.3	13.4		-0.0016
66	0.3200	0.3279	10.3	13.4		-0.0015
67	0.3350	0.3279	10.3	13.8		-0.0013
68	0.3400	0.3279	10.3	14.0		-0.0014
69	0.3450	0.3279	10.3	14.0		-0.0012
70	0.3500	0.3247	10.2	14.5		-0.0012
70	0.3550	0.3213	10.1	14.7		-0.0012
72	0.3600	0.3247	10.2	14.9		-0.0010
73	0.3650	0.3279	10.2	15.1		-0.0009
74	0.3700	0.3279	10.3	15.3		-0.0009
75	0.3750	0.3279	10.3	15.5		-0.0009
76	0.3800	0.3279	10.3	15.7		-0.0007
70	0.3850	0.3247	10.3	15.9		-0.0007
78	0.3900	0.3247	10.2	16.1		-0.0007
79	0.3950	0.3213	10.1	16.3		-0.0007
80	0.3930	0.3247	10.2	16.5		-0.0006
			10.1	16.7		-0.0006
81	0.4050	0.3215	10.1	16.9		-0.0006
82 83	0.4100 0.4150	0.3215 0.3215	10.1	16.9		-0.0006
			10.1	17.1 17.4		-0.0006
84 85	0.4200	0.3215		17.4 17.6		-0.0006
85 86	0.4250	0.3215	10.1			
86 87	0.4300	0.3215	10.1	17.8		-0.0005
87	0.4350	0.3215	10.1	18.0		-0.0005
88	0.4400	0.3215	10.1	18.2		-0.0005
89	0.4450	0.3184	10.0	18.4		-0.0005
90	0.4500	0.3152	9.9	18.6		-0.0005
91	0.4550	0.3152	9.9	18.8		-0.0006
92	0.4600	0.3152	9.9	19.0		-0.0006
93	0.4650	0.3152	9.9	19.2		-0.0006
94	0.4700	0.3184	10.0	19.4		-0.0007
95 06	0.4750	0.3184	10.0	19.6		-0.0007
96 07	0.4800	0.3152	9.9	19.8		-0.0007
97	0.4850 0.4900	0.3152	9.9	20.0 20.2		-0.0008 -0.0009
98 99	0.4900	0.3152 0.3152	9.9 9.9	20.2		-0.0009
77	0.4930	0.5152	7.7	20.5	510	-0.0009

Parameters for Specimen No. 2											
Specimen Parameter	Initial	Consolidated	Final								
Moisture content: Moist soil+tare, gms.	149.990		533.360								
Moisture content: Dry soil+tare, gms.	132.650		507.750								
Moisture content: Tare, gms.	0.000		375.100								
Moisture, %	13.1	19.3	19.3								
Moist specimen weight, gms.	150.0										
Diameter, in.	2.42	2.42									
Area, in. ²	4.60	4.60									
Height, in.	1.00	0.99									
Net decrease in height, in.		0.01									
Wet density, pcf	124.2	132.2									
Dry density, pcf	109.9	110.8									
Void ratio	0.5342	0.5215									
Saturation, %	66.1	100.0									
	ant Deadlin	re for Creatman No. 2		and the second							

Test Readings for Specimen No. 2

Load ring constant = 31.408 lbs. per input unit

Normal stress = 1000 psf

Strain rate, %/min. = 0.04

Fail. Stress = 667 psf at reading no. 9

Ult.	Stress	= (529	psi	at	reading	no.	15

	Horizontal Def. Dial	Load	Load	Strain	Shear Stress	Vertical Def. Dial
No.	in.	Dial	lbs.	%	psf	i n.
0	0.0000	0.0000	0.0	0.0	0	0.0001
1	0.0010	0.0000	0.0	0.0	0	0.0000
2	0.0010	0.0287	0.9	0.0	28	0.0000
3	0.0050	0.4744	14.9	0.2	466	0.0003
4	0.0100	0.6081	19.1	0.4	598	0.0007
5	0.0150	0.6463	20.3	0.6	635	0.0010
6	0.0200	0.6654	20.9	0.8	654	0.0015
7	0.0250	0.6717	21.1	1.0	661	0.0020
8	0.0300	0.6749	21.2	1.2	664	0.0024
9	0.0350	0.6781	21.3	1.4	667	0.0028
10	0.0400	0.6781	21.3	1.7	667	0.0032
11	0.0450	0.6781	21.3	1.9	667	0.0035
12	0.0500	0.6749	21.2	2.1	664	0.0037
13	0.0550	0.6717	21.1	2.3	661	0.0039
14	0.0600	0.6717	21.1	2.5	661	0.0041
15	0.0650	0.6717	21.1	2.7	661	0.0043
16	0.0700	0.6686	21.0	2.9	657	0.0045
17	0.0750	0.6717	21.1	3.1	661	0.0047
18	0.0800	0.6686	21.0	3.3	657	0.0049
19	0.0850	0.6654	20.9	3.5	654	0.0051
20	0.0900	0.6654	20.9	3.7	654	0.0053
21	0.0950	0.6654	20.9	3.9	654	0.0054
22	0.1000	0.6622	20.8	4.1	651	0.0056
23	0.1050	0.6590	20.7	4.3	648	0.0058
24	0.1100	0.6558	20.6	4.5	645	0.0059
25	0.1150	0.6526	20.5	4.8	642	0.0060
26	0.1200	0.6526	20.5	5.0	642	0.0060

			1. J.	Ţ	est Rea	dings for s	Specimen No. 2
	Horizontal				Shear	Vertical	
No.	Def. Dial in.	Load Dial	Load Ibs.	Strain %	Stress psf	Def. Dial in.	
27	0.1250	0.6526	20.5	5.2	642	0.0061	
28	0.1300	0.6495	20.4	5.4	639	0.0062	
29	0.1350	0.6463	20.3	5.6	635	0.0062	
30	0.1400	0.6463	20.3	5.8	635	0.0063	
31	0.1450	0.6463	20.3	6.0	635	0.0064	
32	0.1500	0.6463	20.3	6.2	635	0.0065	
33	0.1550	0.6463	20.3	6.4	635	0.0066	
34	0.1600	0.6463	20.3	6.6	635	0.0067	
35	0.1650	0.6463	20.3	6.8	635	0.0068	
36	0.1700	0.6463	20.3	7.0	635	0.0069	
37	0.1750	0.6463	20.3	7.2	635	0.0070	
38	0.1800	0.6463	20.3	7.4	635	0.0070	
39	0.1850	0.6463	20.3	7.6	635	0.0071	
40	0.1900	0.6463	20.3	7.9	635	0.0072	
41	0.1950	0.6463	20.3	8.1	635	0.0073	
42	0.2000	0.6463	20.3	8.3	635	0.0073	
43	0.2050	0.6463	20.3	8.5	635	0.0073	
44	0.2100	0.6463	20.3	8.7	635	0.0074	
45	0.2150	0.6431	20.2	8.9	632	0.0074	
46	0.2200	0.6399	20.1	9.1	629	0.0075	
47	0.2250	0.6399	20.1	9.3	629	0.0075	
48	0.2300	0.6399	20.1	9.5	629	0.0076	
49	0.2350	0.6463	20.3	9.7	635	0.0076	
50	0.2400	0.6463	20.3	9.9	635	0.0076	
51	0.2450	0.6463	20.3	10.1	635	0.0077	
52	0.2500	0.6463	20.3	10.3	635	0.0077	
53	0.2550	0.6463	20.3	10.5	635	0.0077	
54	0.2600	0.6463	20.3	10.7	635	0.0077	
55	0.2650	0.6463	20.3	11.0	635	0.0078	
56	0.2700	0.6431	20.2	11.2	632	0.0078	
57	0.2750	0.6399	20.1	11.4	629	0.0079	
58	0.2800	0.6463	20.3	11.6	635	0.0079	
59	0.2850	0.6463	20.3	11.8	635	0.0079	
60	0.2900	0.6463	20.3	12.0	635	0.0079	
61	0.2950	0.6463	20.3	12.2	635	0.0080	
62	0.3000	0.6463	20.3	12.4	635	0.0080	
63	0.3050	0.6463	20.3	12.6	635	0.0080	
64	0.3100	0.6399	20.1	12.8	629	0.0080	
65	0.3150	0.6399	20.1	13.0	629	0.0081	
66	0.3200	0.6399	20.1	13.2	629	0.0081	
67	0.3250	0.6399	20.1	13.4	629	0.0081	
68 60	0.3300	0.6431	20.2	13.6	632	0.0081	
69 70	0.3350	0.6431	20.2	13.8	632	0.0081	
70	0.3400	0.6399	20.1	14.0	629	0.0081	
71	0.3450	0.6399	20.1	14.3	629	0.0081	
72	0.3500	0.6399	20.1	14.5	629	0.0081	
73	0.3550	0.6399	20.1	14.7	629	0.0081	
					Knight P	lesold Ge	otechnical Lab.

				Т	est Rea	dings for	Specimen No. 2
No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.	
74	0.3600	0.6335	19.9	14.9	623	0.0082	
75	0.3650	0.6399	20.1	15.1	629	0.0081	
76	0.3700	0.6399	20.1	15.3	629	0.0081	
77	0.3750	0.6399	20.1	15.5	629	0.0080	
78	0.3800	0.6399	20.1	15.7	629	0.0079	
79	0.3850	0.6399	20.1	15.9	629	0.0078	
80	0.3900	0.6399	20.1	16.1	629	0.0078	
81	0.3950	0.6399	20.1	16.3	629	0.0077	
82	0.4000	0.6399	20.1	16.5	629	0.0076	
83	0.4050	0.6399	20.1	16.7	629	0.0075	
84	0.4100	0.6463	20.3	16.9	635	0.0075	
85	0.4150	0.6495	20.4	17.1	639	0.0075	
86	0.4200	0.6526	20.5	17.4	642	0.0074	
87	0.4250	0.6495	20.4	17.6	639	0.0073	
88	0.4300	0.6495	20.4	17.8	639	0.0072	
89	0.4350	0.6463	20.3	18.0	635	0.0071	
90	0.4400	0.6495	20.4	18.2	639	0.0070	
91	0.4450	0.6526	20.5	18.4	642	0.0070	
92	0.4500	0.6526	20.5	18.6	642	0.0070	
93	0.4550	0.6526	20.5	18.8	642	0.0070	
94	0.4600	0.6463	20.3	19.0	635	0.0069	
95	0.4650	0.6463	20.3	19.2	635	0.0068	
96	0.4700	0.6463	20.3	19.4	635	0.0067	
97	0.4750	0.6399	20.1	19.6	629	0.0066	
98	0.4800	0.6399	20.1	19.8	629	0.0065	
99	0.4850	0.6367	20.0	20.0	626	0.0064	
100	0.4900	0.6399	20.1	20.2	629	0.0063	
101	0.4950	0.6399	20.1	20.5	629	0.0062	

	Parameters	for Specimen No. 3		The second second
Specimen Parameter	Initial	Consolidated	Final	
Moisture content: Moist soil+tare, gms.	151.210		561.350	
Moisture content: Dry soil+tare, gms.	133.620		536.510	
Moisture content: Tare, gms.	0.000		402.890	
Moisture, %	13.2	18.6	18.6	
Moist specimen weight, gms.	151.2			
Diameter, in.	2.42	2.42		
Area, in. ²	4.60	4.60		
Height, in.	1.00	0.99		
Net decrease in height, in.		0.01		
Wet density, pcf	125.2	133.1		
Dry density, pcf	110.7	112.2		
Void ratio	0.5230	0.5017		
Saturation, %	68.0	100.0		

 Test Readings for Specimen No. 3

 Load ring constant = 31.408 lbs. per input unit

Normal stress = 1500 psf

Strain rate, %/min. = 0.04


Fail. Stress = 936 psf at reading no. 31

Ult. Stress = 898 psf at reading no. 73

No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
0	0.0000	0.0000	0.0	0.0	0	0.0000
1	0.0050	0.4584	14.4	0.2	451	-0.0004
2	0.0100	0.6654	20.9	0.4	654	-0.0006
3	0.0150	0.7864	24.7	0.6	773	-0.0005
4	0.0200	0.8628	27.1	0.8	848	-0.0004
5	0.0250	0.9010	28.3	1.0	886	0.0001
6	0.0300	0.9201	28.9	1.2	905	0.0003
7	0.0350	0.9296	29.2	1.4	914	0.0006
8	0.0400	0.9392	29.5	1.7	923	0.0009
9	0.0450	0.9392	29.5	1.9	923	0.0012
10	0.0500	0.9424	29.6	2.1	927	0.0014
11	0.0550	0.9424	29.6	2.3	927	0.0017
12	0.0600	0.9455	29.7	2.5	930	0.0019
13	0.0650	0.9455	29.7	2.7	930	0.0021
14	0.0700	0.9487	29.8	2.9	933	0.0022
15	0.0750	0.9455	29.7	3.1	930	0.0023
16	0.0800	0.9455	29.7	3.3	930	0.0023
17	0.0850	0.9424	29.6	3.5	927	0.0024
18	0.0900	0.9392	29.5	3.7	923	0.0025
19	0.0950	0.9392	29.5	3.9	923	0.0025
20	0.1000	0.9392	29.5	4.1	923	0.0026
21	0.1050	0.9392	29.5	4.3	923	0.0026
22	0.1100	0.9455	29.7	4.5	930	0.0027
23	0.1150	0.9455	29.7	4.8	930	0.0028
24	0.1200	0.9455	29.7	5.0	930	0.0028
25	0.1250	0.9455	29.7	5.2	930	0.0028
26	0.1300	0.9455	29.7	5.4	930	0.0028

			19-1- N	Ţ	est Rea	gs for Specimen N	0. 3
No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	ertical f. Dial in.	
27	0.1350	0.9455	29.7	5.6	930	0028	
28	0.1350	0.9455	29.7	5.8	930	0028	
29	0.1450	0.9455	29.7	6.0	930	0028	
30	0.1500	0.9455	29.7	6.2	930	0027	
31	0.1550	0.9519	29.9	6.4	936	0028	
32	0.1600	0.9519	29.9	6.6	936	0028	
33	0.1650	0.9519	29.9	6.8	936	0028	
34	0.1700	0.9519	29.9	7.0	936	0029	
35	0.1750	0.9519	29.9	7.2	936	0030	
36	0.1800	0.9519	29.9	7.4	936	0030	
37	0.1850	0.9455	29.7	7.6	930	0031	
38	0.1900	0.9455	29.7	7.9	930	0031	
39	0.1950	0.9455	29.7	8.1	930	0031	
40	0.2000	0.9424	29.6	8.3	927	0032	
41	0.2050	0.9424	29.6	8.5	927	0031	
42	0.2100	0.9392	29.5	8.7	923	0031	
43	0.2150	0.9392	29.5	8.9	923	0031	
44	0.2200	0.9392	29.5	9.1	923	0031	
45	0.2250	0.9392	29.5	9.3	923	0031	
46	0.2300	0.9392	29.5	9.5	923	0032	
47	0.2350	0.9360	29.4	9.7	920	0032	
48	0.2400	0.9328	29.3	9.9	917	0032	
49	0.2450	0.9328	29.3	10.1	917	0032	
50	0.2500	0.9264	29.1	10.3	911	0031	
51	0.2550	0.9264	29.1	10.5	911	0032	
52	0.2600	0.9264	29.1	10.7	911	0032	
53	0.2650	0.9264	29.1	11.0	911	0032	
54	0.2700	0.9264	29.1	11.2	911	0032	
55	0.2750	0.9264	29.1	11.4	911	0032	
56	0.2800	0.9264	29.1	11.6	911	0032	
57	0.2850	0.9264	29.1	11.8	911	0032	
58	0.2900	0.9264	29.1	12.0	911	0032	
59	0.2950	0.9264	29.1	12.2	911	0032	
60	0.3000	0.9201	28.9	12.4	905	0032	
61	0.3050	0.9169	28.8	12.6	902	0032	
62	0.3100	0.9137	28.7	12.8	898	0033	
63	0.3150	0.9137	28.7	13.0	898	0033	
64	0.3200	0.9137	28.7	13.2	898	0033	
65	0.3250	0.9201	28.9	13.4	905	0033	
66	0.3300	0.9137	28.7	13.6	898	0033	
67	0.3350	0.9169	28.8	13.8	902	0033	
68	0.3400	0.9201	28.9	14.0	905	0033	
69	0.3450	0.9201	28.9	14.3	905	0034	
70	0.3500	0.9137	28.7	14.5	898	0034	
71	0.3550	0.9137	28.7	14.7	898	0035	
72	0.3600	0.9137	28.7	14.9	898	0035	
73	0.3650	0.9137	28.7	15.1	898	0036	
					Knight F	sold Geotechnical La	ab

				Т	est Rea	dings for
No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
74	0.3700	0.9137	28.7	15.3	898	0.0037
75	0.3750	0.9105	28.6	15.5	895	0.0037
76	0.3800	0.9073	28.5	15.7	892	0.0038
77	0.3850	0.9073	28.5	15.9	892	0.0038
78	0.3900	0.9137	28.7	16.1	898	0.0038
79	0.3950	0.9169	28.8	16.3	902	0.0038
80	0.4000	0.9137	28.7	16.5	898	0.0038
81	0.4050	0.9169	28.8	16.7	902	0.0038
82	0.4100	0.9201	28.9	16.9	905	0.0038
83	0.4150	0.9264	29.1	17.1	911	0.0037
84	0.4200	0.9264	29.1	17.4	911	0.0037
85	0.4250	0.9264	29.1	17.6	911	0.0037
86	0.4300	0.9296	29.2	17.8	914	0.0037
87	0.4350	0.9328	29.3	18.0	917	0.0037
88	0.4400	0.9328	29.3	18.2	917	0.0037
89	0.4450	0.9360	29.4	18.4	920	0.0037
90	0.4500	0.9392	29.5	18.6	923	0.0037
91	0.4550	0.9455	29.7	18.8	930	0.0036
92	0.4600	0.9424	29.6	19.0	927	0.0036
93	0.4650	0.9455	29.7	19.2	930	0.0036
94	0.4700	0.9455	29.7	19.4	930	0.0036
95	0.4750	0.9455	29.7	19.6	930	0.0036
96	0.4800	0.9455	29.7	19.8	930	0.0036
97	0.4850	0.9455	29.7	20.0	930	0.0035
98	0.4900	0.9455	29.7	20.2	930	0.0035
99	0.4950	0.9455	29.7	20.5	930	0.0035



Checked By: JDB

DIRECT SHEAR TEST

8/18/2018

Date:	8/10/18		
Client:	Geomat		
Project:	Kimbeto, S.Escavada & Rincon Po	nds	
Project No.:	DV108-00304/04		
Depth:	10-20'	Sample Number:	6837
Description:			
Remarks:	Failure chosen at 10% and 20% str	ain. Test was inundate	d.
Type of Sample:	Remolded		
Assumed Specific G	ravity=2.7 LL=	PL=	PI=

	Parameter	s for Specimen No. 1		
Specimen Parameter	Initial	Consolidated	Final	
Moisture content: Moist soil+tare, gms.	150.080		533.770	
Moisture content: Dry soil+tare, gms.	132.850		507.910	
Moisture content: Tare, gms.	0.000		375.060	
Moisture, %	13.0	19.5	19.5	
Moist specimen weight, gms.	150.1			
Diameter, in.	2.42	2.42		
Area, in. ²	4.60	4.60		
Height, in.	1.00	1.00		
Net decrease in height, in.		0.00		
Wet density, pcf	124.3	132.0		
Dry density, pcf	110.0	110.5		
Void ratio	0.5319	0.5257		
Saturation, %	65.8	100.0		
T	est Readin	gs for Specimen No. 1		

Load ring constant = 31.408 lbs. per input unit Normal stress = 500 psf Strain rate, %/min. = 0.04 Fail. Stress = 354 psf at reading no. 49

Ult. Stress = 341 psf at reading no. 99

No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
0	0.0000	0.0000	0.0	0.0	0	0.0000
1	0.0050	0.2642	8.3	0.2	260	0.0000
2	0.0100	0.3789	11.9	0.4	373	0.0004
3	0.0150	0.4489	14.1	0.6	441	0.0011
4	0.0200	0.4712	14.8	0.8	463	0.0021
5	0.0250	0.4680	14.7	1.0	460	0.0033
6	0.0300	0.4553	14.3	1.2	448	0.0043
7	0.0350	0.4362	13.7	1.4	429	0.0052
8	0.0400	0.4171	13.1	1.7	410	0.0059
9	0.0450	0.4043	12.7	1.9	398	0.0064
10	0.0500	0.3916	12.3	2.1	385	0.0068
11	0.0550	0.3820	12.0	2.3	376	0.0070
12	0.0600	0.3789	11.9	2.5	373	0.0073
13	0.0650	0.3757	11.8	2.7	369	0.0075
					Knight F	Discold C

				T	est Rea	ngs for Specimen No. 1	
	Horizontal				Shear	ertical	
No.	Def. Dial in.	Load Dial	Load Ibs.	Strain %	Stress psf	ıf. Dial in.	
14	0.0700	0.3725	11.7	2.9	366	0077	
15	0.0750	0.3725	11.7	3.1	366	.0079	
16	0.0800	0.3725	11.7	3.3	366	.0081	
17	0.0850	0.3693	11.6	3.5	363	.0082	
18	0.0900	0.3725	11.7	3.7	366	.0083	
19	0.0950	0.3693	11.6	3.9	363	.0084	
20	0.1000	0.3693	11.6	4.1	363	.0085	
21	0.1050	0.3693	11.6	4.3	363	.0086	
22	0.1100	0.3725	11.7	4.5	366	.0088	
23	0.1150	0.3693	11.6	4.8	363	.0089	
24	0.1200	0.3693	11.6	5.0	363	.0090	
25	0.1250	0.3661	11.5	5.2	360	.0091	
26	0.1300	0.3661	11.5	5.4	360	.0093	
27	0.1350	0.3661	11.5	5.6	360	.0094	
28	0.1400	0.3661	11.5	5.8	360	.0095	
29	0.1450	0.3661	11.5	6.0	360	.0096	
30	0.1500	0.3629	11.4	6.2	357	.0096	
31	0.1550	0.3661	11.5	6.4	360	.0097	
32	0.1600	0.3629	11.4	6.6	357	.0098	
33	0.1650	0.3661	11.5	6.8	360	.0099	
34	0.1700	0.3661	11.5	7.0	360	.0100	
35	0.1750	0.3629	11.4	7.2	357	.0100	
36	0.1800	0.3597	11.3	7.4	354	.0101	
37	0.1850	0.3597	11.3	7.6	354	.0102	
38	0.1900	0.3597	11.3	7.9	354	.0103	
39	0.1950	0.3597	11.3	8.1	354	.0104	
40	0.2000	0.3566	11.2	8.3	351	.0105	
41	0.2050	0.3566	11.2	8.5	351	.0105	
42	0.2100	0.3597	11.3	8.7	354	.0106	
43	0.2150	0.3597	11.3	8.9	354	.0107	
44	0.2200	0.3597	11.3	9.1	354	.0107	
45	0.2250	0.3597	11.3	9.3	354	.0108	
46	0.2300	0.3597	11.3	9.5	354	.0108	
47	0.2350	0.3597	11.3	9.7	354	.0108	
48	0.2400	0.3597	11.3	9.9	354	.0109	
49 50	0.2450 0.2500	0.3597	11.3	10.1	354 354	.0109	
50 51	0.2500	0.3597 0.3534	11.3 11.1	10.3 10.5	354 347	.0110	
51	0.2550	0.3554	11.1	10.5	347	.0111	
52	0.2600	0.3566	11.2	11.0	351	.0111	
55 54	0.2630	0.3597	11.2	11.0	354	.0111	
54 55	0.2700	0.3566	11.3	11.2	354	.0112	
56	0.2730	0.3536	11.2	11.4	347	.0112	
57	0.2800	0.3534	11.1	11.8	347	.0112	
58	0.2830	0.3566	11.1	12.0	351	.0113	
59	0.2900	0.3534	11.2	12.0	347	.0113	
60	0.3000	0.3566	11.1	12.2	351	.0113	
50	0.0000	0.0000				sold Geotechnical Lab.	

				Т	est Rea	dings fo
No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
61	0.3050	0.3597	11.3	12.6	354	0.0114
62	0.3100	0.3597	11.3	12.8	354	0.0114
63	0.3150	0.3597	11.3	13.0	354	0.0115
64	0.3200	0.3566	11.2	13.2	351	0.0115
65	0.3250	0.3534	11.1	13.4	347	0.0116
66	0.3300	0.3534	11.1	13.6	347	0.0116
67	0.3350	0.3534	11.1	13.8	347	0.0117
68	0.3400	0.3534	11.1	14.0	347	0.0118
69	0.3450	0.3534	11.1	14.3	347	0.0119
70	0.3500	0.3534	11.1	14.5	347	0.0120
71	0.3550	0.3534	11.1	14.7	347	0.0121
72	0.3600	0.3566	11.2	14.9	351	0.0121
73	0.3650	0.3534	11.1	15.1	347	0.0121
74	0.3700	0.3534	11.1	15.3	347	0.0122
75	0.3750	0.3534	11.1	15.5	347	0.0123
76	0.3800	0.3534	11.1	15.7	347	0.0124
77	0.3850	0.3534	11.1	15.9	347	0.0125
78	0.3900	0.3534	11.1	16.1	347	0.0126
79	0.3950	0.3534	11.1	16.3	347	0.0127
80	0.4000	0.3534	11.1	16.5	347	0.0128
81	0.4050	0.3502	11.0	16.7	344	0.0129
82	0.4100	0.3534	11.1	16.9	347	0.0130
83	0.4150	0.3534	11.1	17.1	347	0.0130
84	0.4200	0.3534	11.1	17.4	347	0.0132
85	0.4250	0.3534	11.1	17.6	347	0.0132
86	0.4300	0.3470	10.9	17.8	341	0.0133
87	0.4350	0.3534	11.1	18.0	347	0.0134
88	0.4400	0.3534	11.1	18.2	347	0.0136
89	0.4450	0.3534	11.1	18.4	347	0.0136
90	0.4500	0.3534	11.1	18.6	347	0.0137
91	0.4550	0.3502	11.0	18.8	344	0.0138
92	0.4600	0.3534	11.1	19.0	347	0.0139
93	0.4650	0.3470	10.9	19.2	341	0.0140
94	0.4700	0.3470	10.9	19.4	341	0.0140
95	0.4750	0.3470	10.9	19.6	341	0.0141
96	0.4800	0.3470	10.9	19.8	341	0.0141
97	0.4850	0.3470	10.9	20.0	341	0.0142
98	0.4900	0.3470	10.9	20.2	341	0.0142
99	0.4950	0.3470	10.9	20.5	341	0.0142

Specimen Parameter	Initial	Consolidated	Final	
Moisture content: Moist soil+tare, gms.	150.270		561.500	
Moisture content: Dry soil+tare, gms.	133.000		535.970	
Moisture content: Tare, gms.	0.000		402.970	
Moisture, %	13.0	19.2	19.2	
Moist specimen weight, gms.	150.3			
Diameter, in.	2.42	2.42		
Area, in. ²	4.60	4.60		
Height, in.	1.00	0.99		
Net decrease in height, in.		0.01		
Wet density, pcf	124.5	132.3		
Dry density, pcf	110.2	111.0		
Void ratio	0.5301	0.5182		
Saturation, %	66.1	100.0		
T	est Reading	s for Specimen No.	2	

Normal stress = 1000 psf

Strain rate, %/min. = 0.04

Fail. Stress = 639 psf at reading no. 49

Ult. Stress = 617 psf at reading no. 99

No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
0	0.0000	0.0000	0.0	0.0	psi 0	0.0000
1	0.0050	0.4680	14.7	0.0		
-				_	460	-0.0001
2	0.0100	0.6272	19.7	0.4	617	0.0002
3	0.0150	0.6845	21.5	0.6	673	0.0008
4	0.0200	0.6972	21.9	0.8	686	0.0015
5	0.0250	0.6908	21.7	1.0	679	0.0022
6	0.0300	0.6686	21.0	1.2	657	0.0027
7	0.0350	0.6495	20.4	1.4	639	0.0031
8	0.0400	0.6399	20.1	1.7	629	0.0033
9	0.0450	0.6335	19.9	1.9	623	0.0034
10	0.0500	0.6335	19.9	2.1	623	0.0034
11	0.0550	0.6399	20.1	2.3	629	0.0035
12	0.0600	0.6399	20.1	2.5	629	0.0035
13	0.0650	0.6463	20.3	2.7	635	0.0035
14	0.0700	0.6463	20.3	2.9	635	0.0036
15	0.0750	0.6526	20.5	3.1	642	0.0037
16	0.0800	0.6526	20.5	3.3	642	0.0038
17	0.0850	0.6558	20.6	3.5	645	0.0039
18	0.0900	0.6526	20.5	3.7	642	0.0041
19	0.0950	0.6526	20.5	3.9	642	0.0041
20	0.1000	0.6526	20.5	4.1	642	0.0042
21	0.1050	0.6526	20.5	4.3	642	0.0043
22	0.1100	0.6463	20.3	4.5	635	0.0043
23	0.1150	0.6463	20.3	4.8	635	0.0043
24	0.1200	0.6463	20.3	5.0	635	0.0044
25	0.1250	0.6463	20.3	5.2	635	0.0045
26	0.1300	0.6463	20.3	5.4	635	0.0045

				Т	est Rea	dings for Specimen No. 2
	Horizontal Def. Dial	Load	Load	Strain	Shear Stress	Vertical Def. Dial
No.	in.	Dial	lbs.	%	psf	in.
27	0.1350	0.6431	20.2	5.6	632	0.0046
28	0.1400	0.6463	20.3	5.8	635	0.0046
29	0.1450	0.6463	20.3	6.0	635	0.0047
30	0.1500	0.6463	20.3	6.2	635	0.0047
31	0.1550	0.6463	20.3	6.4	635	0.0048
32	0.1600	0.6463	20.3	6.6	635	0.0048
33	0.1650	0.6463	20.3	6.8	635	0.0049
34 35	0.1700 0.1750	0.6463 0.6463	20.3	7.0	635	0.0049 0.0050
35 36	0.1730	0.6463	20.3	7.2	635	0.0050
37	0.1800	0.6463	20.3 20.3	7.4 7.6	635 635	0.0051
38	0.1850	0.6463	20.3	7.9	635	0.0051
30 39	0.1900	0.6463	20.3	8.1	635	0.0051
39 40	0.1930	0.6463	20.3	8.3	635	0.0052
41	0.2050	0.6463	20.3	8.5	635	0.0052
42	0.2100	0.6463	20.3	8.7	635	0.0053
43	0.2150	0.6463	20.3	8.9	635	0.0053
44	0.2200	0.6463	20.3	9.1	635	0.0054
45	0.2250	0.6463	20.3	9.3	635	0.0055
46	0.2300	0.6463	20.3	9.5	635	0.0055
47	0.2350	0.6463	20.3	9.7	635	0.0055
48	0.2400	0.6495	20.3	9.9	639	0.0055
49	0.2450	0.6495	20.4	10.1	639	0.0056
50	0.2500	0.6495	20.4	10.3	639	0.0056
51	0.2550	0.6463	20.3	10.5	635	0.0056
52	0.2600	0.6463	20.3	10.7	635	0.0056
53	0.2650	0.6495	20.4	11.0	639	0.0056
54	0.2700	0.6495	20.4	11.2	639	0.0056
55	0.2750	0.6526	20.5	11.4	642	0.0056
56	0.2800	0.6526	20.5	11.6	642	0.0057
57	0.2850	0.6526	20.5	11.8	642	0.0058
58	0.2900	0.6526	20.5	12.0	642	0.0058
59	0.2950	0.6526	20.5	12.2	642	0.0059
60	0.3000	0.6526	20.5	12.4	642	0.0060
61	0.3050	0.6526	20.5	12.6	642	0.0060
62	0.3100	0.6495	20.4	12.8	639	0.0061
63	0.3150	0.6526	20.5	13.0	642	0.0061
64	0.3200	0.6526	20.5	13.2	642	0.0062
65	0.3250	0.6526	20.5	13.4	642	0.0063
66	0.3300	0.6526	20.5	13.6	642	0.0063
67	0.3350	0.6526	20.5	13.8	642	0.0064
68	0.3400	0.6495	20.4	14.0	639	0.0065
69	0.3450	0.6495	20.4	14.3	639	0.0066
70	0.3500	0.6463	20.3	14.5	635	0.0066
71	0.3550	0.6463	20.3	14.7	635	0.0067
72	0.3600	0.6463	20.3	14.9	635	0.0068
73	0.3650	0.6495	20.4	15.1	639	0.0069
					Knight P	Piesold Geotechnical Lab.

				Т	est R <u>ea</u>	dings fo
Mo	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
No. 74	0.3700	0.6495	20.4	⁷ • 15.3	psi 639	0.0070
	0.3700	0.6493	20.4	15.5	639	0.0070
75 76	0.3750	0.6463	20.4	15.7	635	0.0071
70	0.3850	0.6463	20.3	15.7	635	0.0072
78	0.3900	0.6431	20.3	16.1	632	0.0073
78	0.3900	0.6399	20.2	16.3	629	0.0074
	0.3930	0.6431	20.1	16.5	632	0.0075
80			20.2	16.7	632	0.0078
81	0.4050	0.6431		16.7		0.0077
82	0.4100	0.6399	20.1		629	0.0078
83	0.4150	0.6399	20.1	17.1	629	
84	0.4200	0.6335	19.9	17.4	623	0.0079
85	0.4250	0.6335	19.9	17.6	623	0.0080
86	0.4300	0.6335	19.9	17.8	623	0.0081
87	0.4350	0.6335	19.9	18.0	623	0.0082
88	0.4400	0.6335	19.9	18.2	623	0.0083
89	0.4450	0.6335	19.9	18.4	623	0.0084
90	0.4500	0.6335	19.9	18.6	623	0.0085
91	0.4550	0.6335	19.9	18.8	623	0.0086
92	0.4600	0.6335	19.9	19.0	623	0.0087
93	0.4650	0.6272	19.7	19.2	617	0.0088
94	0.4700	0.6272	19.7	19.4	617	0.0089
95	0.4750	0.6272	19.7	19.6	617	0.0089
96	0.4800	0.6272	19.7	19.8	617	0.0090
97	0.4850	0.6272	19.7	20.0	617	0.0090
98	0.4900	0.6272	19.7	20.2	617	0.0091
99	0.4950	0.6272	19.7	20.5	617	0.0092

	Parameters	for Specimen No. 3		
Specimen Parameter	Initial	Consolidated	Final	
Moisture content: Moist soil+tare, gms.	150.230		550.960	
Moisture content: Dry soil+tare, gms.	133.310		526.260	
Moisture content: Tare, gms.	0.000		392.950	
Moisture, %	12.7	18.5	18.5	
Moist specimen weight, gms.	150.2			
Diameter, in.	2.42	2.42		
Area, in. ²	4.60	4.60		
Height, in.	1.00	0.98		
Net decrease in height, in.		0.02		
Wet density, pcf	124.4	133.1		
Dry density, pcf	110.4	112.3		
Void ratio	0.5266	0.5005		
Saturation, %	65.1	100.0		

Test Readings for Specimen No. 3

Load ring constant = 31.408 lbs. per input unit

Normal stress = 1500 psf

Strain rate, %/min. = 0.04


Fail. Stress = 898 psf at reading no. 49

Ult. Stress = 930 psf at reading no. 99


No.	Horizontal Def. Dial in.	Load Dial	Load Ibs.	Strain %	Shear Stress psf	Vertical Def. Dial in.
0	0.0000	0.0000	0.0	0.0	0	0.0000
1	0.0050	0.5126	16.1	0.2	504	-0.0004
2	0.0100	0.6972	21.9	0.4	686	-0.0006
3	0.0150	0.7832	24.6	0.6	770	-0.0006
4	0.0200	0.8182	25.7	0.8	805	-0.0006
5	0.0250	0.8309	26.1	1.0	817	-0.0006
6	0.0300	0.8309	26.1	1.2	817	-0.0006
7	0.0350	0.8373	26.3	1.4	823	-0.0007
8	0.0400	0.8373	26.3	1.7	823	-0.0007
9	0.0450	0.8437	26.5	1.9	830	-0.0008
10	0.0500	0.8468	26.6	2.1	833	-0.0008
11	0.0550	0.8500	26.7	2.3	836	-0.0008
12	0.0600	0.8564	26.9	2.5	842	-0.0009
13	0.0650	0.8564	26.9	2.7	842	-0.0008
14	0.0700	0.8596	27.0	2.9	845	-0.0008
15	0.0750	0.8628	27.1	3.1	848	-0.0009
16	0.0800	0.8628	27.1	3.3	848	-0.0010
17	0.0850	0.8628	27.1	3.5	848	-0.0011
18	0.0900	0.8691	27.3	3.7	855	-0.0012
19	0.0950	0.8723	27.4	3.9	858	-0.0013
20	0.1000	0.8755	27.5	4.1	861	-0.0013
21	0.1050	0.8819	27.7	4.3	867	-0.0015
22	0.1100	0.8819	27.7	4.5	867	-0.0015
23	0.1150	0.8882	27.9	4.8	873	-0.0016
24	0.1200	0.8882	27.9	5.0	873	-0.0016
25	0.1250	0.8946	28.1	5.2	880	-0.0015
26	0.1300	0.8978	28.2	5.4	883	-0.0016


				Т	est Rea	dings for Specimen No. 3
	Horizontal Def. Dial	Load	Load	Strain	Shear Stress	Vertical Def. Dial
No.	in.	Dial	lbs.	%	psf	in.
27	0.1350	0.8978	28.2	5.6		
28	0.1400	0.9010	28.3	5.8		-0.0016
29	0.1450	0.9010	28.3	6.0		-0.0017
30	0.1500	0.9010	28.3	6.2		-0.0017
31	0.1550	0.9073	28.5	6.4		-0.0018
32	0.1600	0.9073	28.5	6.6		-0.0018
33	0.1650	0.9073	28.5	6.8		-0.0019
34	0.1700	0.9073	28.5	7.0		-0.0019
35	0.1750	0.9137	28.7	7.2		-0.0020
36	0.1800	0.9137	28.7	7.4		-0.0020
37	0.1850	0.9137	28.7	7.6		-0.0020
38	0.1900	0.9169	28.8	7.9		-0.0021
39	0.1950	0.9169	28.8	8.1		-0.0022
40	0.2000	0.9201	28.9	8.3		-0.0022
41	0.2050	0.9137	28.7	8.5		-0.0023
42	0.2100	0.9137	28.7	8.7		-0.0024
43	0.2150	0.9137	28.7	8.9		-0.0024
44	0.2200	0.9137	28.7	9.1		-0.0025
45	0.2250	0.9137	28.7	9.3		-0.0026
46	0.2300	0.9105	28.6	9.5		-0.0026
47	0.2350	0.9137	28.7	9.7		-0.0027
48	0.2400	0.9137	28.7	9.9		-0.0028
49	0.2450	0.9137	28.7	10.1		-0.0029
50	0.2500	0.9137	28.7	10.3		-0.0030
51	0.2550	0.9137	28.7	10.5		-0.0030
52	0.2600	0.9137	28.7	10.7		-0.0031
53	0.2650	0.9137	28.7	11.0		-0.0031
54	0.2700	0.9201	28.9	11.2		-0.0031
55	0.2750	0.9232	29.0	11.4		-0.0032
56	0.2800	0.9264	29.1	11.6		-0.0032
57	0.2850	0.9264	29.1	11.8		-0.0033
58	0.2900	0.9264	29.1	12.0		-0.0033
59	0.2950	0.9328	29.3	12.2		-0.0033
60	0.3000	0.9328	29.3	12.4		-0.0033
61	0.3050	0.9392	29.5	12.6		-0.0033
62	0.3100	0.9392	29.5	12.8		-0.0033
63	0.3150	0.9360	29.4	13.0		-0.0033
64	0.3200	0.9360	29.4	13.2		-0.0033
65	0.3250	0.9360	29.4	13.4		-0.0033
66	0.3300	0.9360	29.4	13.6		-0.0033
67	0.3350	0.9392	29.5	13.8		-0.0033
68	0.3400	0.9392	29.5	14.0		-0.0033
69	0.3450	0.9424	29.6	14.3		-0.0033
70	0.3500	0.9455	29.7	14.5		-0.0033
71	0.3550	0.9455	29.7	14.7		-0.0032
72	0.3600	0.9455	29.7	14.9		-0.0032
73	0.3650	0.9455	29.7	15.1		-0.0032
					Knight F	Piesold Geotechnical Lab.


and the				T	est R <u>ea</u>	dings fo
	Horizontal				Shear	Vertical
	Def. Dial	Load	Load	Strain	Stress	Def. Dial
No.	in.	Dial	lbs.	%	psf	in.
74	0.3700	0.9455	29.7	15.3		-0.0033
75	0.3750	0.9455	29.7	15.5		-0.0033
76	0.3800	0.9455	29.7	15.7		-0.0033
77	0.3850	0.9455	29.7	15.9	930	-0.0034
78	0.3900	0.9455	29.7	16.1	930	-0.0033
79	0.3950	0.9455	29.7	16.3	930	-0.0033
80	0.4000	0.9487	29.8	16.5	933	-0.0033
81	0.4050	0.9487	29.8	16.7	933	-0.0034
82	0.4100	0.9519	29.9	16.9	936	-0.0034
83	0.4150	0.9519	29.9	17.1	936	-0.0034
84	0.4200	0.9455	29.7	17.4	930	-0.0034
85	0.4250	0.9519	29.9	17.6	936	-0.0035
86	0.4300	0.9487	29.8	17.8	933	-0.0035
87	0.4350	0.9455	29.7	18.0	930	-0.0036
88	0.4400	0.9455	29.7	18.2	930	-0.0036
89	0.4450	0.9455	29.7	18.4	930	-0.0037
90	0.4500	0.9455	29.7	18.6	930	-0.0037
91	0.4550	0.9424	29.6	18.8	927	-0.0038
92	0.4600	0.9424	29.6	19.0	927	-0.0039
93	0.4650	0.9455	29.7	19.2	930	-0.0040
94	0.4700	0.9455	29.7	19.4	930	-0.0041
95	0.4750	0.9455	29.7	19.6	930	-0.0042
96	0.4800	0.9455	29.7	19.8	930	-0.0043
97	0.4850	0.9487	29.8	20.0	933	-0.0044
98	0.4900	0.9519	29.9	20.2	936	-0.0045
99	0.4950	0.9455	29.7	20.5	930	-0.0046




^{018 8 21 31} AM JT









Important Information about This Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you – assumedly a client representative - interpret and apply this geotechnical-engineering report as effectively as possible. In that way, clients can benefit from a lowered exposure to the subsurface problems that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed below. contact your GBA-member geotechnical engineer. Active involvement in the Geoprofessional Business Association exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Geotechnical-Engineering Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical-engineering study conducted for a given civil engineer will not likely meet the needs of a civilworks constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnicalengineering report is unique, prepared *solely* for the client. *Those who rely on a geotechnical-engineering report prepared for a different client can be seriously misled*. No one except authorized client representatives should rely on this geotechnical-engineering report without first conferring with the geotechnical engineer who prepared it. *And no one – not even you – should apply this report for any purpose or project except the one originally contemplated*.

Read this Report in Full

Costly problems have occurred because those relying on a geotechnicalengineering report did not read it *in its entirety*. Do not rely on an executive summary. Do not read selected elements only. *Read this report in full*.

You Need to Inform Your Geotechnical Engineer about Change

Your geotechnical engineer considered unique, project-specific factors when designing the study behind this report and developing the confirmation-dependent recommendations the report conveys. A few typical factors include:

- the client's goals, objectives, budget, schedule, and risk-management preferences;
- the general nature of the structure involved, its size, configuration, and performance criteria;
- the structure's location and orientation on the site; and
- other planned or existing site improvements, such as retaining walls, access roads, parking lots, and underground utilities.

Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light-industrial plant to a refrigerated warehouse;
- the elevation, configuration, location, orientation, or weight of the proposed structure;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes – even minor ones – and request an assessment of their impact. The geotechnical engineer who prepared this report cannot accept responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.

This Report May Not Be Reliable

- Do not rely on this report if your geotechnical engineer prepared it:
- for a different client;
- for a different project;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, that it could be unwise to rely on a geotechnical-engineering report whose reliability may have been affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If your geotechnical engineer has not indicated an "apply-by" date on the report, ask what it should be*, and, in general, *if you are the least bit uncertain* about the continued reliability of this report, contact your geotechnical engineer before applying it. A minor amount of additional testing or analysis – if any is required at all – could prevent major problems.

Most of the "Findings" Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site's subsurface through various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing were performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgment to form opinions about subsurface conditions throughout the site. Actual sitewide-subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team from project start to project finish, so the individual can provide informed guidance quickly, whenever needed.

This Report's Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, *they are not final*, because the geotechnical engineer who developed them relied heavily on judgment and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* revealed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmationdependent recommendations if you fail to retain that engineer to perform construction observation*.

This Report Could Be Misinterpreted

Other design professionals' misinterpretation of geotechnicalengineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a full-time member of the design team, to:

- confer with other design-team members,
- help develop specifications,
- review pertinent elements of other design professionals' plans and specifications, and
- be on hand quickly whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction observation.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note conspicuously that you've included the material for informational purposes only.* To avoid misunderstanding, you may also want to note that "informational purposes" means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report, but they may rely on the factual data relative to the specific times, locations, and depths/elevations referenced. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled "limitations," many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely*. Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a "phase-one" or "phase-two" environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnical-engineering report does not usually relate any environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures*. If you have not yet obtained your own environmental report guidance. As a general rule, *do not rely on an environmental report prepared for a different client, site, or project, or that is more than six months old.*

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold

While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, none of the engineer's services were designed, conducted, or intended to prevent uncontrolled migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer's recommendations will not of itself be sufficient to prevent moisture infiltration*. Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not buildingenvelope or mold specialists*.



Telephone: 301/565-2733 e-mail: info@geoprofessional.org www.geoprofessional.org

Copyright 2016 by Geoprofessional Business Association (GBA). Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with GBA's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of GBA, and only for purposes of scholarly research or book review. Only members of GBA may use this document or its wording as a complement to or as an element of a report of any kind. Any other firm, individual, or other entity that so uses this document without being a GBA member could be committing negligent