

**STATE OF NEW MEXICO
DEPARTMENT OF ENERGY, MINERALS AND NATURAL RESOURCES
OIL CONSERVATION DIVISION**

**APPLICATION OF NGL WATER
SOLUTIONS PERMIAN, LLC
TO APPROVE SALT WATER
DISPOSAL WELL IN LEA
COUNTY, NEW MEXICO.**

CASE NO. 16506

AMENDED APPLICATION

NGL Water Solutions Permian, LLC ("NGL"), OGRID No. 372338, through its undersigned attorneys, hereby submits this Amended Application to the Oil Conservation Division pursuant to the provisions of N.M. Stat. Ann. § 70-2-12, for an order approving drilling of a salt water disposal well in Lea County, New Mexico. In support of this application, NGL states as follows:

(1) NGL submitted an application to drill the Harpoon SWD #1 well on 10/01/18. NGL is providing this amended application to update the proposed location for drilling the well. NGL proposes to drill the Harpoon SWD #1 well at a surface location 172 feet from the South line and 2353 feet from the West line of Section 27, Township 24 South, Range 34 East, NMPM, Lea County, New Mexico for the purpose of operating a salt water disposal well.

(2) NGL seeks authority to inject salt water into the Silurian-Devonian formation at a depth of 16,960' to 18,850'.

(3) NGL further seeks approval of the use of 7 inch tubing inside the surface and intermediate casings and 5 ½ inch tubing inside the liner and requests that the Division approve a maximum daily injection rate for the well of 50,000 bbls per day.

(4) NGL anticipates using an average pressure of 2,544 psi for this well, and it requests that a maximum pressure of 3,392 psi be approved for the well.

(5) A proposed C-108 for the subject well is attached hereto in Attachment A.

(6) The granting of this application will avoid the drilling of unnecessary wells, will prevent waste, and will protect correlative rights.

WHEREFORE, NGL requests that this application be set for hearing before an Examiner of the Oil Conservation Division on January 10, 2018; and that after notice and hearing, the Division enter its order approving this application.

Respectfully submitted,

MODRALL, SPERLING, ROEHL, HARRIS
& SISK, P.A.

By: Deana M. Bennett

Jennifer Bradfute
Deana Bennett
Post Office Box 2168
Bank of America Centre
500 Fourth Street NW, Suite 1000
Albuquerque, New Mexico 87103-2168
Telephone: 505.848.1800
Attorneys for Applicant

CASE NO. 16506: Application of NGL Water Solutions Permian, LLC for approval of salt water disposal well in Lea County, New Mexico. Applicant seeks an order approving disposal into the Silurian-Devonian formation through the Harpoon SWD #1 well at a surface location 172 feet from the South line and 2353 feet from the West line of Section 27, Township 24 South, Range 34 East, NMPM, Lea County, New Mexico for the purpose of operating a salt water disposal well. NGL seeks authority to inject salt water into the Silurian-Devonian formation at a depth of 16,960' to 18,850'. NGL further seeks approval of the use of 7 inch tubing inside the surface and intermediate casings and 5 ½ inch tubing inside the liner and requests that the Division approve a maximum daily injection rate for the well of 50,000 bbls per day. Said area is located approximately 16.3 miles northwest of Jal, New Mexico.

RECEIVED:	REVIEWER:	TYPE:	APP NO:
-----------	-----------	-------	---------

ABOVE THIS TABLE FOR OCD DIVISION USE ONLY

NEW MEXICO OIL CONSERVATION DIVISION
 - Geological & Engineering Bureau -
 1220 South St. Francis Drive, Santa Fe, NM 87505



ADMINISTRATIVE APPLICATION CHECKLIST

THIS CHECKLIST IS MANDATORY FOR ALL ADMINISTRATIVE APPLICATIONS FOR EXCEPTIONS TO DIVISION RULES AND
 REGULATIONS WHICH REQUIRE PROCESSING AT THE DIVISION LEVEL IN SANTA FE

Applicant: <u>NGL WATER SOLUTIONS PERMIAN LLC</u>	OGRID Number: <u>372338</u>
Well Name: <u>HARPOON SWD #1</u>	API: <u>TBD</u>
Pool: <u>SWD; SILURIAN-DEVONIAN</u>	Pool Code: <u>96101</u>

**SUBMIT ACCURATE AND COMPLETE INFORMATION REQUIRED TO PROCESS THE TYPE OF APPLICATION
 INDICATED BELOW**

1) TYPE OF APPLICATION: Check those which apply for [A]

A. Location – Spacing Unit – Simultaneous Dedication

☐ NSL ☐ NSP (PROJECT AREA) ☐ NSP (PRORATION UNIT) ☐ SD

B. Check one only for [I] or [II]

[I] Commingling – Storage – Measurement

☐ DHC ☐ CTB ☐ PLC ☐ PC ☐ OLS ☐ OLM

[II] Injection – Disposal – Pressure Increase – Enhanced Oil Recovery

☐ WFX ☐ PMX ☒ SWD ☐ IPI ☐ EOR ☐ PPR

2) NOTIFICATION REQUIRED TO: Check those which apply.

- A. ☒ Offset operators or lease holders
 B. ☐ Royalty, overriding royalty owners, revenue owners
 C. ☒ Application requires published notice
 D. ☒ Notification and/or concurrent approval by SLO
 E. ☒ Notification and/or concurrent approval by BLM
 F. ☒ Surface owner
 G. ☐ For all of the above, proof of notification or publication is attached, and/or,
 H. ☐ No notice required

FOR OCD ONLY

☐ Notice Complete
☐ Application
 Content
 Complete

- 3) CERTIFICATION:** I hereby certify that the information submitted with this application for administrative approval is **accurate** and **complete** to the best of my knowledge. I also understand that **no action** will be taken on this application until the required information and notifications are submitted to the Division.

Note: Statement must be completed by an individual with managerial and/or supervisory capacity.

CHRIS WEYAND

Print or Type Name

Signature

11/21/2018
 Date


512-600-1764

Phone Number

CHRIS@LONQUIST.COM
 e-mail Address



APPLICATION FOR AUTHORIZATION TO INJECT

- I. PURPOSE: Secondary Recovery Pressure Maintenance X Disposal Storage
Application qualifies for administrative approval? X Yes No
- II. OPERATOR: NGL WATER SOLUTIONS PERMIAN, LLC
ADDRESS: 1509 W WALL ST // STE 306 // MIDLAND, TX 79701
CONTACT PARTY: SARAH JORDAN PHONE: (432) 685-0005 x1989
- III. WELL DATA: Complete the data required on the reverse side of this form for each well proposed for injection.
Additional sheets may be attached if necessary.
- IV. Is this an expansion of an existing project? Yes X No
If yes, give the Division order number authorizing the project: _____
- V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review.
- VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.
- VII. Attach data on the proposed operation, including:
1. Proposed average and maximum daily rate and volume of fluids to be injected;
 2. Whether the system is open or closed;
 3. Proposed average and maximum injection pressure;
 4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and,
 5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).
- *VIII. Attach appropriate geologic data on the injection zone including appropriate lithologic detail, geologic name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such sources known to be immediately underlying the injection interval.
- IX. Describe the proposed stimulation program, if any.
- *X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division, they need not be resubmitted).
- *XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.
- XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground sources of drinking water.
- XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form.
- XIV. Certification: I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.
- NAME: Christopher B. Weyand TITLE: Consulting Engineer
SIGNATURE:  DATE: 11/21/2010
E-MAIL ADDRESS: chris@lonquist.com
- * If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be resubmitted. Please show the date and circumstances of the earlier submittal: _____

III. WELL DATA

- A. The following well data must be submitted for each injection well covered by this application. The data must be both in tabular and schematic form and shall include:

- (1) Lease name; Well No.; Location by Section, Township and Range; and footage location within the section.
- (2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined.
- (3) A description of the tubing to be used including its size, lining material, and setting depth.
- (4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used.

Division District Offices have supplies of Well Data Sheets which may be used or which may be used as models for this purpose. Applicants for several identical wells may submit a "typical data sheet" rather than submitting the data for each well.

- B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

- (1) The name of the injection formation and, if applicable, the field or pool name.
- (2) The injection interval and whether it is perforated or open-hole.
- (3) State if the well was drilled for injection or, if not, the original purpose of the well.
- (4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations.
- (5) Give the depth to and the name of the next higher and next lower oil or gas zone in the area of the well, if any.

XIV. PROOF OF NOTICE

All applicants must furnish proof that a copy of the application has been furnished, by certified or registered mail, to the owner of the surface of the land on which the well is to be located and to each leasehold operator within one-half mile of the well location.

Where an application is subject to administrative approval, a proof of publication must be submitted. Such proof shall consist of a copy of the legal advertisement which was published in the county in which the well is located. The contents of such advertisement must include:

- (1) The name, address, phone number, and contact party for the applicant;
- (2) The intended purpose of the injection well; with the exact location of single wells or the Section, Township, and Range location of multiple wells;
- (3) The formation name and depth with expected maximum injection rates and pressures; and,
- (4) A notation that interested parties must file objections or requests for hearing with the Oil Conservation Division, 1220 South St. Francis Dr., Santa Fe, New Mexico 87505, within 15 days.

NO ACTION WILL BE TAKEN ON THE APPLICATION UNTIL PROPER PROOF OF NOTICE HAS BEEN SUBMITTED.

NOTICE: Surface owners or offset operators must file any objections or requests for hearing of administrative applications within 15 days from the date this application was mailed to them.

Side 1

INJECTION WELL DATA SHEET

OPERATOR: NGL WATER SOLUTIONS PERMIAN, LLC

WELL NAME & NUMBER: HARPOON SWD #1

WELL LOCATION: 172 FSL & 2,353' FWL N 27 24S 34E
FOOTAGE LOCATION UNIT LETTER SECTION TOWNSHIP RANGE

WELLBORE SCHEMATIC

WELL CONSTRUCTION DATA

Surface Casing

Hole Size: 24.000"

Casing Size: 20.000"

Cemented with: 1,544 sx.

or _____ ft³

Top of Cement: Surface

Method Determined: Circulation

1st Intermediate Casing

Hole Size: 17.500"

Casing Size: 13.375"

Cemented with: 2,973 sx.

or _____ ft³

Top of Cement: Surface

Method Determined: Circulation

2nd Intermediate Casing

Hole Size: 12.250"

Casing Size: 9.625"

Cemented with: 3,613 sx.

or _____ ft³

Top of Cement: Surface

Method Determined: Circulation

Production Liner

Hole Size: 8.500"

Casing Size: 7.625"

Cemented with: 409 sx.

or _____ ft³

Top of Cement: 11,800'

Method Determined: Calculation

Total Depth: 18,850'

Injection Interval

16,960 feet to 18,850 feet

(Open Hole)

INJECTION WELL DATA SHEET

Tubing Size: 7", 26 lb/ft, P-110, TCPC from 0' - 11,700' and 5,500", 17 lb/ft, P-110 TCPC from 11,700' - 16,900'
Lining Material: Duoline


Type of Packer: 7-5/8" x 5-1/2" TCPC Permanent Packer with High Temp Elastomer and Full Inconel

Packer Setting Depth: 16,900'

Other Type of Tubing/Casing Seal (if applicable): _____

Additional Data

1. Is this a new well drilled for injection? X Yes No
If no, for what purpose was the well originally drilled? N/A
2. Name of the Injection Formation: Devonian, Silurian, Fusselman and Montoya (Top 100')
3. Name of Field or Pool (if applicable): SWD; Silurian-Devonian
4. Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail, i.e. sacks of cement or plug(s) used. No, new drill.
5. Give the name and depths of any oil or gas zones underlying or overlying the proposed injection zone in this area:
Delaware: 5,370'
Bone Spring: 9,258'
Wolfcamp: 12,259'
Atoka: 13,927'
Strawn: 13,685'
Morrow: 14,738'

<div>  Harpoon SWD Revised Location Lea County NM Vertical Injection - Devonian, Silurian, Fusselman, Montoya </div>									
Geologic Tops (MD ft)			Location - Sec 27, Twp 24S, R 34E		TD	18,850		Directions to Site - Travel 14.3 miles from Jal NM along NM 128W. Turn left (south) on Battle Ave Road and travel 5.9 miles to location. Lat/Long: 32.18174722, -103.460000	
			Drilling Cost - \$10.73/MM		GL/KB	3,435			
			Section	Problems	Bit/BHA	Mud	Casing	Logging	Cement
									Injection String
<div> Rustler 1102 Surface TD - 1400' Top of Salt 1500' Salado 1,544' Base of Salt 4407' 1st Int TD - 5300' ECP DV Tool - 5350' Delaware 5370' Bell Canyon 5412' Cherry Canyon - 6460' Brushy Canyon - 8140' DV Tool - 9000' Bone Spring - 9258' 3rd Int Liner Top - 11,800' Wolfcamp - 12259' 2nd Int TD - 12,400' Strawn - 13685' Atoka - 13927' Morrow - 14738' Miss Lst - 14805' Woodford - 16763' Perm Packer - 16,900' 3rd Int TD - 16,960' Devonian - 16,940' Fusselman - 18000' Montoya - 18,750' TD - 18,850' </div>	Surface Drill 24" 0' - 1400' Set and Cement 20" Casing		Loss Circulation Hole Cleaning Wellbore stability in the Red Beds Anhydrite in the Rustler	24" Tricone 9-5/8" x 8" MM 9 jts: 8" DC 21 jts: 5" HWDP 5" DP to surface	Spud Mud MW< 9.0	1400' of 20" 106.5# J55 STC Centralizers - bottom 2 joints and every 3rd jt thereafter, Cement basket at 200'	No Logs	Lead - 680sx of HES Extenda Cem, 13.7ppg, 4.5hrs TT Tail - 703sx of Halcem 3hr TT 50% Excess 1000psi CSD after 10hrs	11700' of 7" P110 26# TCPC 5200' of 5-1/2" P110 17# TCPC Duoline Internally Coated Injection Tubing 7-5/8" x 5-1/2" TCPC Permanent Packer with High Temp Elastomer and full Inconel 925 trim
	1st Intermediate Drill 3900' of 17-1/2" Hole 1400' - 5300' Set and Cement 13-3/8" Casing		Seepage Losses Possible H2S Anhydrite Salt Sections	17-1/2" PDC 9-5/8" x 8" MM 9 jts: 8" DC 21 jts: 5" HWDP 5" DP to surface		5M A Section Casing Bowl 5300' of 13-3/8" 68# HCL80 BTC Centralizers - bottom jt, every 3rd joint in open hole and 2 jt inside the surface casing	Mudlogger on site by 1080'	2973sx of Halcem, 13.7ppg 30% Excess 1000psi CSD after 10 hrs Cement to Surface	
	2nd Intermediate Drill 7100' of 12-1/4" Hole 5300' - 12400' Set 95/8" Intermediate Casing and Cement in 3 Stages		Hard Drilling in the Brushy Canyon Seepage to Complete Loss Water Flows Some Anhydrite H2S possible Production in the Bone Spring and Wolfcamp Ballooning is possible in Cherry Canyon and Brushy if Broken Down	12-1/4" PDC 8" MM 9jts: 8" DC 8" Drilling Jars 21 jts: 5" HWDP 5" DP to Surface	8.5 ppg OBM High Vis Sweeps UBD/MPD using ADA	10M B Section 12400' of 9-5/8" 53.5# P110 BTC Special Drift to 8,535" Externally Coat 4820' Between DV Tools DV tool at at 9000' ECP DV Tool 15' Inside Previous Casing Centralizers - bottom jt, 100' aside of DV tool, every 3rd joint in open hole and 5 within the surface casing	MWD GR Triple combo + CBL of 13-3/8" Casing	Stage 3: 10% Excess 1111sx Halcem 13.7ppg 1000psi CSD after 10 hrs Cement to Surface Stage 2: 50% Excess 1206sx Halcem 13.7ppg 1000psi CSD after 10 hrs Stage 1: 50% Excess 1307sx Halcem 15.6ppg, 1000psi CSD after 10hrs	
	3rd Intermediate Drill 4560' of 8-1/2" Hole 12400' - 16960' Set 7-5/8" Liner and Cement in Single Stage		High Pressure (up to 15ppg) and wellbore instability (fracturing) expected in the Atoka 150 target radius Hard Drilling in the Morrow Clastic	8-1/2" PDC 6-3/4" MM 9 jts: 6" DC 21 jts: 5" HWDP 5" DP to Surface	12.5 ppg OBM UBD/MPD using ADA	5160' of 7-5/8" 39# Q125 - DTL (F14) FJ (Gas Tight) VersaFlex Packer Hanger Centralizers on and 1 jt above shoe jt and then every 2nd jt.	MWD GR Triple combo, CBL of 9 5/8" Casing	409sx Neocem 12.9 ppg 50% Excess 1000psi CSD after 12hrs	
	Injection Interval Drill 1890' of 6-1/2" hole 16960' - 18850'		Chert is possible Loss of Circulation and or Flows are expected H2S encountered on the Striker 3 well BHT estimated at 280F	6-1/2" PDC 4-3/4" MM 9 jts: 4-3/4" DC 4-3/4" Drilling Jars 18 jts: 4" FH HWDP 4" FH DP to Surface	Brine Water - flows possible	Openhole completion	MWD GR Triple Combo with FMI, CBL of 7-5/8"	Displace with 3% KCl (or heavier brine if necessary)	

NGL Water Solutions Permian, LLC

Harpoon SWD No. 1

FORM C-108 Supplemental Information

III. Well Data

A. Wellbore Information

1.

Well information	
Lease Name	Harpoon SWD
Well No.	1
Location	S-27 T-24S R-34E
Footage Location	172' FSL & 2,353' FWL

2.

a. Wellbore Description

Casing Information				
Type	Surface	Intermediate	Production	Liner
OD	20"	13.375"	9.625"	7.625"
WT	0.438"	0.480"	0.545"	0.500"
ID	19.124"	12.415"	8.535"	6.625"
Drift ID	18.937"	12.259"	8.535"	6.500"
COD	21.00"	14.375"	10.625"	7.625"
Weight	106.5 lb/ft	68 lb/ft	53.5 lb/ft	39 lb/ft
Grade	J-55	HCL-80	P-110	Q-125
Hole Size	24"	17.5"	12.25"	8.5"
Depth Set	1,400'	5,300'	12,400'	11,800' - 16,960'

b. Cementing Program

Cement Information				
Casing String	Surface	Intermediate	Production	Liner
Cement	Lead: Extenda Cem Tail: Halcem	Halcem	Halcem	Neocem
Cement Volume	Lead: 680 Tail: 703	2,973	Stage 1: 1,307 sks Stage 2: 1,206 sks Stage 3: 1,111 sks	409
Cement Excess	25%	30%	10%, 50%, 50%	50%
TOC	Surface	Surface	Surface	11,800'
Method	Circulate to Surface	Circulate to Surface	Circulate to Surface	Logged

3. Tubing Description

Tubing Information		
OD	7"	5.5"
WT	0.362"	0.304"
ID	6.276"	4.892"
Drift ID	7.875"	6.050"
COD	6.151"	4.767"
Weight	26 lb/ft	17 lb/ft
Grade	P-110 TCPC	P-110 TCPC
Depth Set	0'-11,700'	11,700'-16,900'

Tubing will be lined with Duoline.

4. Packer Description

7-5/8" x 5-1/2" TCPC Permanent Packer with High Temp Elastomer and full Inconel 925 trim

B. Completion Information

1. Injection Formation: Devonian, Silurian, Fusselman, Montoya (Top 100')
2. Gross Injection Interval: 16,960' – 18,850'

Completion Type: Open Hole

3. Drilled for injection.
4. See the attached wellbore schematic.
5. Oil and Gas Bearing Zones within area of well:

Formation	Depth
Delaware	5,370
Bone Spring	9,258
Wolfcamp	12,259
Strawn	13,685
Atoka	13,927
Morrow	14,738

VI. Area of Review

No wells within the area of review penetrate the proposed injection zone.

VII. Proposed Operation Data

1. Proposed Daily Rate of Fluids to be Injection:

Average Volume: 40,000 BPD
Maximum Volume: 50,000 BPD

2. Closed System

3. Anticipated Injection Pressure:

Average Injection Pressure: 2,544 PSI (surface pressure)
Maximum Injection Pressure: 3,392 PSI (surface pressure)

4. The injection fluid is to be locally produced water. It is expected that the water will be predominantly sourced from the Bone Spring and Wolfcamp formations. Attached are produced water sample analyses taken from the closest wells that feature samples from the Delaware, Bone Spring, Wolfcamp, Strawn, Atoka, and Morrow formations.
5. The disposal interval is non-productive. No water samples are available from the surrounding area.

VIII. Geological Data

The Devonian formation is a dolomitic ramp carbonate that occurs below the Woodford shale and above the Fusselman formation. Strata found in the Devonian formation include two major groups, the Wristen Buildups and the Thirtyone Deepwater Chert, with the Wristen being more abundant. The Wristen Groups is composed of mixed limestone and dolomites with mudstone to grainstone and boundstone textures. Porosity in the Wristen group is a result of both primary and secondary development. Present are moldic, vugular, karstic (including collapse breccia) features that allow for higher porosities and permeabilities. The Thirtyone Formation contains two end-member reservoir facies, skeletal packstones/grainstones and spiculitic chert, with most of the porosity and permeability found in the coarsely crystalline cherty dolomite. These particular characteristics allow for this formation to be a tremendous Salt Water Disposal horizon.

A. Injection Zone: Siluro-Devonian Formation

Formation	Depth
Rustler Anhydrite	1,102'
Salado Anhydrite	1,544'
Delaware	5,370'
Bone Spring	9,258'
Wolfcamp	12,259'
Strawn	13,685'
Atoka	13,927'
Morrow	14,738'
Mississippian	15,620'
Woodford	16,763'
Devonian	16,940'
Fusselman	18,000'
Montoya	18,750'

B. Underground Sources of Drinking Water

Within 1-mile of the proposed Harpoon SWD #1 location, there are no fresh water wells. However, water wells in the greater surrounding area have an average depth of 293 ft and an average water depth of 241 ft generally producing from the Santa Rosa. The upper Rustler may also be another USDW and will be protected.

IX. Proposed Stimulation Program

Stimulate with up to 50,000 gallons of acid.

X. Logging and Test Data on the Well

There are no logs or test data on the well. During the process of drilling and completion resistivity, gamma ray, and density logs will be run.

XI. Chemical Analysis of Fresh Water Wells

There are no water wells that exist within one mile of the well location. For this reason, fresh water analysis has not been included with the application.

XII. Affirmative Statement of Examination of Geologic and Engineering Data

Based on the available engineering and geologic data we find no evidence of open faults or any other hydrologic connection between the disposal zone (in the proposed Harpoon SWD #1) and any underground sources of drinking water.

NAME: John C. Webb

TITLE: Sr. Geologist

SIGNATURE: _____

John C. Webb

DATE: _____

9/24/2018

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy Minerals and Natural Resources
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-101
Revised July 18, 2013

☐ AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL, RE-ENTER, DEEPEN, PLUGBACK, OR ADD A ZONE

¹ Operator Name and Address NGL WATER SOLUTIONS PERMIAN, LLC 1509 W WALL ST, STE 306 MIDLAND, TX 79701		² OGRID Number 372338 ³ API Number TBD
⁴ Property Code	⁵ Property Name HARPOON SWD	⁶ Well No. 1

⁷ Surface Location

UL - Lot	Section	Township	Range	Lot Idn	Feet from	N/S Line	Feet From	E/W Line	County
N	27	24S	34E	N/A	172'	SOUTH	2,353'	WEST	LEA

⁸ Proposed Bottom Hole Location

UL - Lot	Section	Township	Range	Lot Idn	Feet from	N/S Line	Feet From	E/W Line	County
-	-	-	-	-	-	-	-	-	-

⁹ Pool Information

Pool Name SWD: Silurian-Devonian	Pool Code 96101
-------------------------------------	--------------------

Additional Well Information

¹¹ Work Type N	¹² Well Type SWD	¹³ Cable/Rotary R	¹⁴ Lease Type Private	¹⁵ Ground Level Elevation 3,435'
¹⁶ Multiple N	¹⁷ Proposed Depth 18,850'	¹⁸ Formation Siluro-Devonian	¹⁹ Contractor TBD	²⁰ Spud Date ASAP
Depth to Ground water 241'		Distance from nearest fresh water well > 1 mile		Distance to nearest surface water 3,015

☐ We will be using a closed-loop system in lieu of lined pits

²¹ Proposed Casing and Cement Program


Type	Hole Size	Casing Size	Casing Weight/ft	Setting Depth	Sacks of Cement	Estimated TOC
Surface	24"	20"	106.5 lb/ft	1,400'	1,544	Surface
Intermediate	17.5"	13.375"	68 lb/ft	5,300'	2,973	Surface
Production	12.25"	9.625"	53.5 lb/ft	12,400'	3,613	Surface
Prod. Liner	8.5"	7.625"	39 lb/ft	11,800' – 16,960'	409	11,800'
Tubing	N/A	7"	26 lb/ft	0' – 11,700'	N/A	N/A
Tubing	N/A	5.5"	17 lb/ft	11,700' – 16,900'	N/A	N/A

Casing/Cement Program: Additional Comments

See attached schematic.

²² Proposed Blowout Prevention Program

Type	Working Pressure	Test Pressure	Manufacturer
Double Hydraulic/Blinds, Pipe	10,000 psi	8,000 psi	TBD – Schaffer/Cameron

²³ I hereby certify that the information given above is true and complete to the best of my knowledge and belief. I further certify that I have complied with 19.15.14.9 (A) NMAC <input type="checkbox"/> and/or 19.15.14.9 (B) NMAC <input checked="" type="checkbox"/> if applicable. Signature:  Printed name: Christopher B. Weyand Title: Consulting Engineer E-mail Address: chris@lonquist.com Date: 11/20/2018	<div style="text-align: center; border-bottom: 1px solid black; padding-bottom: 5px;">OIL CONSERVATION DIVISION</div> <div style="border-bottom: 1px solid black; padding-bottom: 5px;">Approved By:</div> <div style="border-bottom: 1px solid black; padding-bottom: 5px;">Title:</div> <div style="display: flex; justify-content: space-between; border-bottom: 1px solid black; padding-bottom: 5px;"> <div>Approved Date:</div> <div>Expiration Date:</div> </div> <div style="border-bottom: 1px solid black; padding-bottom: 5px;">Conditions of Approval Attached</div>
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1,
2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number	² Pool Code 96101	³ Pool Name SWD; Silurian-Devonian
⁴ Property Code	⁵ Property Name HARPOON SWD	⁶ Well Number 1
⁷ OGRID No. 372338	⁸ Operator Name NGL WATER SOLUTIONS PERMIAN, LLC	⁹ Elevation 3435.00'±

¹⁰ Surface Location



UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	27	24 S	34 E	N/A	172'	SOUTH	2353'	WEST	LEA


¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
---------------	---------	----------	-------	---------	---------------	------------------	---------------	----------------	--------

¹² Dedicated Acres	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
-------------------------------	-------------------------------	----------------------------------	-------------------------


No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<div style="text-align: center; font-size: 2em;">SECTION 27</div>	<p>PROPOSED HARPOON SWD 1</p> <p>NMSP-E (NAD27) N: 430,892.67' E: 770,341.63'</p> <p>NMSP-E (NAD83) N: 430,951.15' E: 811,526.99' Lat: N32°10'54.29" Long: W103°27'36.03"</p>	<p>¹⁷ OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division</p> <p> 11/21/2018</p> <p>Signature Date</p> <p>Chris Weyand</p> <p>Printed Name</p> <p>chris@lonquist.com</p> <p>E-mail Address</p>
		<p>¹⁸ SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>10/23/18</p> <p>Date of Survey</p> <p> 23001</p> <p>Signature and Seal of Professional Surveyor</p> <p>Cody A. Clark</p> <p>Certificate Number</p>



**Harpoon SWD No. 1
1 Mile Area of Review List**

API (30-025-...)	WELL NAME	WELL TYPE	STATUS	OPERATOR	TVD (FT.)	LATITUDE (NAD83 DD)	LONGITUDE (NAD83 DD)	DATE DRILLED
27826	MADERA 28 FEDERAL COM #001	G	A	EOG RESOURCES INC	15300	32.18309780000	-103.47696690000	6/18/1982
28002	PITCHFORK 34 FEDERAL COM #001	G	A	EOG RESOURCES INC	15435	32.17219160000	-103.46417240000	11/11/1982
28321	PRE-ONGARD WELL #001	O	P	PRE-ONGARD WELL OPERATOR	15530	32.18671420000	-103.45993040000	1/1/1900
28387	PRE-ONGARD WELL #001	O	C	PRE-ONGARD WELL OPERATOR	0	32.19005347080	-103.44604207900	12/31/9999
28488	PITCHFORK RANCH 28 FEDERAL COM #001	G	A	EOG RESOURCES INC	15250	32.19035720000	-103.47274020000	12/2/1983
28596	MOORE 34 COM #001	O	P	JOHNNY G JONES	15376	32.17582320000	-103.45564270000	2/13/1984
28620	MADERA 33 FEDERAL COM #002	G	P	EOG RESOURCES INC	15159	32.17220310000	-103.47270200000	5/9/1984
29862	MADERA 28 FEDERAL COM #002	G	P	EOG RESOURCES INC	13945	32.18309780000	-103.47625730000	3/10/1987
29917	PRE-ONGARD WELL #001	G	P	PRE-ONGARD WELL OPERATOR	15142	32.19034960000	-103.46420290000	1/1/1900
29926	MADERA 33 FEDERAL COM #004	G	P	EOG RESOURCES INC	14000	32.17310330000	-103.47270200000	7/18/1987
30620	PITCHFORK 34 FEDERAL COM #002	O	C	EOG RESOURCES INC	0	32.16854643100	-103.45566780300	12/31/9999
39712	ORANGE RAIDER BPV STATE #001H	O	A	COG OPERATING LLC	9453	32.16764070000	-103.44710540000	4/1/2010
44872	STONEWALL 28 FEDERAL COM #707H	O	N	EOG RESOURCES INC	0	32.19524680000	-103.47499170000	12/31/9999
44873	STONEWALL 28 FEDERAL COM #708H	O	N	EOG RESOURCES INC	0	32.19524590000	-103.47488510000	12/31/9999
44874	STONEWALL 28 FEDERAL COM #713H	O	N	EOG RESOURCES INC	0	32.19524110000	-103.46861270000	12/31/9999
44875	STONEWALL 28 FEDERAL COM #714H	O	N	EOG RESOURCES INC	0	32.19524100000	-103.46850600000	12/31/9999
44926	STONEWALL 28 FEDERAL COM #709H	O	N	EOG RESOURCES INC	0	32.19524670000	-103.47477840000	12/31/9999
44927	STONEWALL 28 FEDERAL COM #710H	O	N	EOG RESOURCES INC	0	32.19524400000	-103.47181290000	12/31/9999
44928	STONEWALL 28 FEDERAL COM #711H	O	N	EOG RESOURCES INC	0	32.19524390000	-103.47170620000	12/31/9999
44929	STONEWALL 28 FEDERAL COM #712H	O	N	EOG RESOURCES INC	0	32.19524390000	-103.47159960000	12/31/9999
44930	STONEWALL 28 FEDERAL COM #715H	O	N	EOG RESOURCES INC	0	32.19524090000	-103.46839930000	12/31/9999



Harpoon SWD No. 1
1 Mile Offset Lessee(s) - BLM & SLO
NGL Water Solutions Permian, LLC
Lea Co., NM

PCS: NAD 1983 SPCS NM-E FIPS 3001 (US Ft.)		
Drawn by: ASG	Date: 11/01/2018	Approved by: ELR

LONQUIST & CO. LLC

**PETROLEUM
ENGINEERS** **ENERGY
ADVISORS**
AUSTIN • HOUSTON • WICHITA • DENVER • CALGARY

+ Harpoon SWD No. 1 SHL

ius

NM-PLSS 2nd Div.

PLSS 1st Div.)

range (NM-PLSS)

API (30-025-...) SHL Status-Type (Count)

Horizontal Surface Location (10)

Horizontal Surface Location (10)

Active - Gas (3)

Cancelled/Abandoned Location (2)

	Cancelled/Abandoned Location (Z)	Plugged/Site Released Gas (A)
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

Plugged/Site Released	Oil (2)	Flugged/Site Released - Gas (4)
1	1	1
2	2	2
3	3	3
4	4	4
5	5	5
6	6	6
7	7	7
8	8	8
9	9	9
10	10	10
11	11	11
12	12	12
13	13	13
14	14	14
15	15	15
16	16	16
17	17	17
18	18	18
19	19	19
20	20	20
21	21	21
22	22	22
23	23	23
24	24	24
25	25	25
26	26	26
27	27	27
28	28	28
29	29	29
30	30	30
31	31	31
32	32	32
33	33	33
34	34	34
35	35	35
36	36	36
37	37	37
38	38	38
39	39	39
40	40	40
41	41	41
42	42	42
43	43	43
44	44	44
45	45	45
46	46	46
47	47	47
48	48	48
49	49	49
50	50	50
51	51	51
52	52	52
53	53	53
54	54	54
55	55	55
56	56	56
57	57	57
58	58	58
59	59	59
60	60	60
61	61	61
62	62	62
63	63	63
64	64	64
65	65	65
66	66	66
67	67	67
68	68	68
69	69	69
70	70	70
71	71	71
72	72	72
73	73	73
74	74	74
75	75	75
76	76	76
77	77	77
78	78	78
79	79	79
80	80	80
81	81	81
82	82	82
83	83	83
84	84	84
85	85	85
86	86	86
87	87	87
88	88	88
89	89	89
90	90	90
91	91	91
92	92	92
93	93	93
94	94	94
95	95	95
96	96	96
97	97	97
98	98	98
99	99	99
100	100	100

Flipped/3ite Released - Oll (Z)

AFI (30-0000-...) BNC status-type (count)

- Active - Oil (1)

Permitted - Oil (9)

Lessee(s)

-AGS OG HOLDINGS #2 INC: -AGS

HOLDINGS INC.; -MIDWEST RES 2

INCOME ; -MIDWEST RES 98-1 O&G INC

AGS OG VENTURES INC.; -AGS OG

TE-RAY RESOURCES INC

-EOG RESOURCES INC

 -EOG RESOURCES INC

-EOG Y RESOURCES, INC.

-FEDERAL ABSTRACT COMPANY

-YATES JOHN A

-NON BLM/SLO LAND

Source: Well SHL Data - NM-OCD (2018)



Harpoon SWD #1: Offsetting Produced Water Analysis

wellname	api	section	township	range	unit	county	formation	ph	tds_mgl	sodium_mgl	calcium_mgl	iron_mgl	magnesium_mgl	manganese_mgl	chloride_mgl	bicarbonate_mgl	sulfate_mgl	co2_mgl
BELL LAKE UNIT #002	3002508489	30	23S	34E	N	LEA	DELAWARE		52115							32200	451	529
BELL LAKE UNIT A #007	3002508367		1 24S	33E	A	LEA	DELAWARE		87686							53920	391	749
BELL LAKE UNIT #009	3002520261	18	23S	34E	K	LEA	BONE SPRING		204652							130000	512	260
CORLANDER AOC STATE #002	3002533574	1	23S	32E	H	LEA	BONE SPRING	5.2				24176	0			167962	61.1	165
THISTLE UNIT #071H	3002542425	27	23S	33E	A	Lea	BONE SPRING 1ST SAND	5.6	171476.3	55363.2	9140	40.4	1023		1.1	104576.4	244	770
BELL LAKE 19 STATE #002H	3002541515	19	24S	33E	O	Lea	BONE SPRING 2ND SAND	6.2		47148	6419	15	854		0	86572	232	670
BELL LAKE 19 STATE #004H	3002541517	19	24S	33E	O	Lea	BONE SPRING 2ND SAND	6.3		47537	6950	11	886		0	88389	171	650
SALADO DRAW 6 FEDERAL #001H	3002541293	6	26S	34E	M	Lea	BONE SPRING 3RD SAND	6.5	99612.7	34586.5	3244	10.3	417.7	0.39	0.12	59986.5	158.6	820
GAUCHO UNIT #011H	3002541184	17	22S	34E	O	Lea	BONE SPRING 3RD SAND	6.5		48879	6182	11	802			88836	122	1240
SNAPPING 2 STATE #014H	3001542688	2	26S	31E	P	EDDY	WOLFCAMP	7.3	81366.4	26319.4	2687.4	26.1	326.7			50281.2		399.7
BELLOQ 2 STATE #002H	3001542895	2	23S	31E	C	EDDY	WOLFCAMP	6.8	119471.8	37359.2	5659.1	22.4	746.1			73172.5		100
PRONGHORN AHO FEDERAL #001	3002526496	6	23S	33E	G	LEA	STRAWN	5.5				20.1	12.2			35.5	61.1	48.8
ANTELOPE RIDGE UNIT #002	3002520444	4	24S	34E	B	LEA	ATOKA	6.7	51475							31000	317	340
CLUSTER MOUNTAIN UNIT #001	3002520756	9	24S	35E	K	LEA	MORROW		282741							176800	161	650