

HOLLAND & HART LLP



Ocean Munds-Dry  
Associate

omundsdry@hollandhart.com

December 20, 2007

**HAND-DELIVERED**

Mark E. Fesmire, P.E.  
Director  
Oil Conservation Division  
New Mexico Energy, Minerals and  
Natural Resources Department  
1220 South Saint Francis Drive  
Santa Fe, New Mexico 87505

RECEIVED  
2007 DEC 20 PM 3 48

*Case 14080*

Re: Application of Southern Union Gas Services for approval of an acid gas  
and wastewater injection well, Lea County, New Mexico.

Dear Mr. Fesmire:

Enclosed is the application of Southern Union Gas Services in the above-referenced case as well as a copy of a legal advertisement. SUGS requests that this matter be placed on the docket for the February 7, 2008 Examiner hearings.

Sincerely,

Ocean Munds-Dry

Enclosures

cc: Alberto Gutierrez (w/o enclosures)

Holland & Hart LLP

Phone [505] 988-4421 Fax [505] 983-6043 [www.hollandhart.com](http://www.hollandhart.com)

110 North Guadalupe Suite 1 Santa Fe, NM 87501 Mailing Address P.O. Box 2208 Santa Fe, NM 87504-2208

Aspen Billings Boise Boulder Cheyenne Colorado Springs Denver Denver Tech Center Jackson Hole Salt Lake City Santa Fe Washington, D.C. ♻

**CASE 14080: Application of Southern Union Gas Services, Ltd. for approval of an acid gas injection well, Lea County, New Mexico.** Applicant seeks approval to utilize its proposed Jal Plant AGI Well No. 1, to be drilled 1570 feet from the North line and 1050 feet from the West line in Unit E of Section 33, Township 24 South, Range 37 East, NMPM, to inject up to 7390 barrels of acid gas and produced water per day, at a maximum pressure of 1130 psi, into the San Andres Formation, at an approximate depth of 4350 feet to 5200 feet. SUGS may be contacted through its representative, Mr. Alberto Gutierrez, 500 Marquette Ave NW, Suite 1350, Albuquerque, New Mexico 87102 or (505) 842-8000. Said well is located approximately 3 ½ miles north of Jal, New Mexico

December 19, 2006

Mr. William Jones  
NM Oil Conservation Division  
1220 South St. Francis Drive  
Santa Fe, NM 87505

HAND DELIVERED

RE: C108 APPLICATION FOR AUTHORIZATION TO INJECT  
ON BEHALF OF SOUTHERN UNION GAS SERVICES JAL #3 PLANT  
SECTION 33, T24S, R37E; LEA COUNTY, NEW MEXICO

Dear Mr. Jones:

Enclosed you will find an application on behalf of Southern Union Gas Services (SUGS) to drill and operate a combined acid gas/Class II wastewater injection well 1570'FNL and 1050'FWL Section 33, T24S, R37E, Lea County, New Mexico. The location is on the SUGS Jal #3 Plant, approximately 200 feet east of the currently permitted Class II wastewater disposal well on the plant (Woolworth Estate WD#1) and, as you will see from the attached application, the primary target injection zone is the San Andres Formation. This well will replace the existing permitted SWD.

I am confident that the detail provided in the application will allow NMOCD to evaluate and administratively approve the application; however, since it is OCD's current policy that a hearing will be required, Ocean Munds-Dry and William Carr from Holland and Hart are working with your office to schedule this hearing for February 7, 2008. We have noticed all of the operators and land owners within the area of review to advise them of SUGS' intentions to drill the above-referenced well. As you will see from the application, proof-of-notice is provided that details our formal notification of the owners and operators in the area of review. As soon as the hearing is scheduled, we will place a legal notice in the *Hobbs News-Sun*, in the form shown in Appendix C of the enclosed C-108 application. We anticipate this notice to run next week. We will submit the affidavit of publication along with the return receipts from the affected operators and the surface owners as soon as we receive them.

We have coordinated the submittal of this application with an amendment to the Jal #3 discharge plan (GW-010) pursuant to discussions with Carl Chavez of the environmental bureau, which provides all the information that will be required by them to evaluate this proposed change in disposal well. We have also copied you on this proposed amendment. In addition, you will note that the revised Rule 118 plan with all applicable ROE calculations for the proposed system at the plant are included as Appendix E to this C-108.

Mr. William Jones  
December 19, 2007  
Page 2

I trust that you will find everything you need herein to evaluate the application and I would encourage that if you have any questions, please contact me at the address below or at my office in Albuquerque: 505-842-8000.

I look forward to working with you to assure the prompt and adequate review of this application and its timely approval.

Merry Christmas and Happy New Year.


Sincerely,  
Geolex, Inc.

Alberto A. Gutiérrez, C.P.G.  
President

AAG/lh

Enclosures

cc (w/enclosures):      Herb Harless, SUGS  
                                 Ross Boyd, SUGS  
                                 Tony Savoie, SUGS  
                                 Dwight Bennett, SUGS  
                                 Robert Gawlik, SUGS  
                                 Ocean Munds-Dry Esq., Holland & Hart  
                                 William Carr, Esq., Holland & Hart





December 18, 2007

Mr. Carl Chavez  
Environmental Engineer  
New Mexico Oil Conservation Division  
1220 South St. Francis Drive  
Santa Fe, New Mexico 87505

VIA FEDERAL EXPRESS  
PRIORITY OVERNIGHT

RE: AMENDMENT TO APPLICATION BY SOUTHERN UNION GAS SERVICES FOR  
RENEWAL OF DISCHARGE PLAN GW-010 - JAL #3 NATURAL GAS PLANT

Dear Mr. Chavez:

Pursuant to our conversation a couple of weeks ago regarding Southern Union Gas Services, Ltd. (SUGS) plans for replacing the existing Class II disposal well at the Jal #3 Plant with a combined acid gas/Class II wastewater disposal well, we hereby submit the enclosed amendment to the Discharge Plan Application submitted in August 2007 (which is still in completeness review) for renewal of a discharge plan for the Jal #3 Natural Gas Processing Plant. The Jal #3 Natural Gas Processing Plant, located in the West Half of the West Half of Section 33, Township 24 South, Range 37 East in Lea County, New Mexico (32°10'27" North, 103°10'27" West). The proposed injection well is the subject of a separate C-108 application being submitted to NMOCD which will be set for hearing in February 2008. The C-108 application is being noticed this week and is also being submitted to NMOCD this week.


The amendment to the discharge plan renewal application is attached. The Table of Contents in the amendment references the portions of the pending discharge plan application which will be affected by the proposed change in the disposal well. Since the plan is for the new well to be completed only about 200' east of the existing well on the Jal #3 plant and the well will continue to take all the plant wastewater, the wastewater piping changes are minimal. The other waste streams at the plant, as described in the original application, will not change. The details of the proposed acid gas/wastewater injection system are included in the C-108 application. I have also enclosed a copy of the entire C-108 application and Draft R118 plan revision for your reference as Appendix I.

Also included for your review is a revised draft of the public notice required in NMWQCC section 20.6.2.3108 (which was included as Appendix H to the August discharge plan renewal application). Following NMOCD review and acceptance, we propose to post this notice using a 2'x3' sign, in English and Spanish, at the gate of the above-named facility. Identified adjacent land owners will be provided with copies of this notice by mail, and any owners other than SUGS within 1/3 mile of the proposed discharge site will be notified by certified, receipt-requested mailing. The notice will also be advertised, in English and Spanish, in a 3" by 4" display advertisement in the *Hobbs News-Sun*.


Mr. Carl Chavez  
December 18, 2007  
Page 2 of 2

Please contact me in this matter, Alberto A. Gutierrez, RG (Geolex, Inc.) at (505) 842-8000, if you have any questions or require additional information regarding this submittal. I look forward to speaking with you regarding this in January. Have a happy holiday.

Sincerely,  
Geolex, Inc.®



Alberto A. Gutierrez, CPG  
President



Enclosures

Amendment to Renewal Application for NMOCD DP GW-010  
C-108 Application for SUGS Jal #3AGI #1 (Appendix I in amendment)


cc: Will Jones, NMOCD – Santa Fe, NM  
Bruce Williams, SUGS-Ft. Worth, TX  
Tony Savoie, SUGS – Jal, NM  
Herb Harless, SUGS – Ft. Worth, TX  
Ross Boyd, SUGS – Midland, TX  
Dwight Bennett, SUGS – Jal, NM  
William Carr, Holland & Hart, Santa Fe, NM



**Amendment to August 17, 2007 Application for Renewal of  
New Mexico Oil Conservation Division Discharge Plan GW-010**

**Jal # 3 Gas Plant**

(Section 33, Township 24 S, Range 37 E)



December 17, 2007

*Prepared For:*

New Mexico Oil Conservation Division  
1200 South Saint Francis Drive  
Santa Fe, New Mexico 87505

*On Behalf of:*

Southern Union Gas Services, Ltd.  
301 Commerce Street, Suite 700  
Fort Worth, Texas 76102  
Telephone: (817)-302-9400

*Prepared By:*

Geolex, Inc.  
500 Marquette Avenue, NE, Suite 1350  
Albuquerque, New Mexico 87102  
Telephone: (505) 842-8000

**LIST OF REVISIONS FOR DISCHARGE PLAN**  
**Jal # 3**

| Revision # | Revision  | Date     |
|------------|---|----------|
| 0          | Original Issue – Rewrite of Entire Plan   | 9/10/93  |
| 1          | Revised Paragraph 14, page 4 of Appendix H – Drain Line Testing Procedure   | 10/22/93 |
| 2          | Revisions for Renewal Application   | 06/29/98 |
| 3          | Revised for Renewal Application   | 04/05/04 |
| 4          | Revised Renewal Application – Revised to incorporate S-Plant and changes to drain system  | 08/17/07 |
| 5          | Amended Renewal Application – Revised to include proposed replacement of existing permitted Class II injection well to proposed combined acid gas and Class II injection well | 12/18/07 |

Please note that all sections from the pending August 17, 2007 renewal application that have been modified or added to address the proposed changes due to the replacement of the existing NMOCD approved Class II wastewater injection well with a combined acid gas/Class II wastewater injection well are highlighted in yellow in the Table of Contents. Only these sections are included in this amendment.


**Southern Union Gas Services Ltd.**  
**Jal # 3 Plant – Natural Gas Processing**  
**Discharge Plan GW-010**

**Natural Gas Processing Operation**

The purpose of the Jal # 3 Plant facility is natural gas processing. The main processes that occur at the plant are compression, sweetening and dehydration, cryogenic extraction of ethane and heavier hydrocarbons, sulfur recovery and steam generation.

**Affirmation**

I hereby certify that I am familiar with the information contained in and submitted with this amendment to the 8/17/07 application and that such information is true, accurate and complete to the best of my knowledge and belief.

  
\_\_\_\_\_  
(Signature)

12/18/07  
\_\_\_\_\_  
(Date)

Alberto A. Gutierrez  
\_\_\_\_\_  
(Name)

Consultant to SUGS  
\_\_\_\_\_  
(Title)

## TABLE OF CONTENTS

|  |          |
|--|----------|
| <b>1.0 TYPE OF OPERATION .....</b>   | <b>1</b> |
| 1.1 COMPRESSION .....  | 1        |
| 1.2 SWEETENING .....   | 1        |
| 1.3 DEHYDRATION .....  | 1        |
| 1.4 CRYOGENIC PLANT .....  | 1        |
| 1.5 SULFUR RECOVERY .....  | 2        |
| 1.6 STEAM GENERATION .....   | 2        |
| <b>2.0 OPERATOR/LEGALLY RESPONSIBLE PARTY .....</b>  | <b>3</b> |
| 2.1 OPERATOR/LEGALLY RESPONSIBLE PARTY .....   | 3        |
| 2.2 LOCAL REPRESENTATIVE .....   | 3        |
| 2.3 REGIONAL ENVIRONMENTAL MANAGER .....   | 3        |
| <b>3.0 LOCATION OF DISCHARGE/FACILITY .....</b>  | <b>3</b> |
| <b>4.0 LANDOWNER .....</b>   | <b>3</b> |
| <b>5.0 FACILITY DESCRIPTION .....</b>  | <b>4</b> |
| <b>6.0 SOURCES AND QUANTITIES OF MATERIAL USED AND STORED AT FACILITY .....</b>  | <b>5</b> |
| 6.1 PROCESS UNITS AND SOURCES OF MATERIALS AND WASTES .....  | 5        |
| 6.1.1 S-Plant .....  | 5        |
| 6.1.2 Separators .....   | 5        |
| 6.1.3 Boilers .....  | 5        |
| 6.1.4 Engine Cooling Water .....   | 5        |
| 6.1.5 Cooling Towers .....   | 5        |
| 6.1.6 Waste Lubricants, Motor Oils and Used Oil Filters .....  | 6        |
| 6.1.7 Waste and Slop Oil .....   | 6        |
| 6.1.8 Other Used Filters .....   | 6        |
| 6.1.9 Solids and Sludge .....  | 6        |
| 6.1.10 Cleaning Operations with Solvents, Degreasers and Soaps .....   | 6        |
| 6.1.11 Water Treating .....  | 6        |
| 6.1.12 Floor and Equipment Washdown .....  | 7        |
| 6.1.13 Sanitary Facilities .....   | 7        |
| 6.2 QUALITY CHARACTERISTICS OF GENERAL EFFLUENT WASTE STREAM .....   | 7        |
| <b>7.0 TRANSFER AND STORAGE OF PROCESS FLUIDS AND EFFLUENTS .....</b>  | <b>8</b> |
| 7.1 SUMMARY OF ON-SITE COLLECTION AND STORAGE SYSTEMS .....  | 8        |
| 7.2 DESCRIPTION OF PROCESS FLUIDS BY UNIT .....  | 8        |
| 7.2.1 S-Plant .....  | 8        |
| 7.2.2 Separators .....   | 8        |
| 7.2.3 Boilers .....  | 9        |
| 7.2.4 Engine Cooling Water .....   | 9        |
| 7.2.5 Cooling Towers .....   | 9        |
| 7.2.6 Waste Lubricants, Motor Oils, and Used Oil Filters .....   | 9        |
| 7.2.7 Waste and Slop Oil .....   | 9        |
| 7.2.8 Other Used Filters .....   | 9        |
| 7.2.9 Solids and Sludge .....  | 10       |
| 7.2.10 Cleaning Operations With Solvents, Degreasers and Soaps .....   | 10       |
| 7.2.11 Water treating .....  | 10       |
| 7.2.12 Equipment Washdown, Floor and Equipment Drains .....  | 10       |
| 7.2.13 Sanitary Drains and Septic Tanks .....  | 10       |
| 7.3 DISCHARGE POTENTIAL OF TRANSFER AND STORAGE COLLECTION UNIT(S) .....   | 10       |
| 7.4 METHODS USED TO PREVENT UNINTENTIONAL AND INADVERTENT DISCHARGES<br>FROM REACHING THE GROUND SURFACE AND POLLUTING ..... | 10       |

|   |           |
|---|-----------|
| 7.5 METHODS TO ENSURE INTEGRITY OF UNDERGROUND DRAIN LINES .....          | 11        |
| <b>8.0 WASTE DISPOSAL.....</b>  | <b>12</b> |
| 8.1 EXISTING ON-SITE EFFLUENT DISPOSAL FACILITIES .....                   | 12        |
| 8.2 OFF SITE DISPOSAL OF OTHER LIQUID OR SLUDGE WASTES .....              | 12        |
| 8.3 SOLID WASTE (GARBAGE, CONSTRUCTION DEBRIS).....                       | 12        |
| 8.4 STAINED SOILS FROM MINOR PLANT SPILLS OR OVERFLOWS .....              | 12        |
| <b>9.0 INSPECTION, MAINTENANCE AND REPORTING .....</b>                    | <b>13</b> |
| 9.1 INSPECTION PROCEDURES FOR COLLECTION, STORAGE AND DISPOSAL UNITS..... | 13        |
| 9.2 PROCEDURES FOR CONTAINMENT OF PRECIPITATION AND RUNOFF .....          | 13        |
| <b>10.0 SPILL/LEAK PREVENTION AND REPORTING (CONTINGENCY PLAN) .....</b>  | <b>14</b> |
| <b>11.0 SITE CHARACTERISTICS .....</b>                                    | <b>15</b> |
| 11.1 BODIES OF WATER NEAR JAL #3 .....                                    | 15        |
| 11.2 GROUNDWATER MOST LIKELY AFFECTED BY DISCHARGE.....                   | 15        |
| 11.3 FLOW DIRECTION OF GROUNDWATER MOST LIKELY AFFECTED BY DISCHARGE..... | 15        |
| 11.4 GEOLOGIC DESCRIPTION OF SITE .....                                   | 15        |
| 11.5 SOIL TYPES.....  | 16        |
| <b>12.0 CLOSURE PLAN.....</b>   | <b>17</b> |

### LIST OF FIGURES

|          |   |
|----------|---|
| Figure 1 | Location of Southern Union Gas Services Jal # 3 Plant                 |
| Figure 2 | Site Aerial Photograph of Southern Union Gas Services Jal # 3 Plant   |
| Figure 3 | Jal # 3 Water & Waste Water Flow Schematic                            |
| Figure 4 | Jal # 3 Wastewater Classifier Area Flow Diagram                       |
| Figure 5 | Surface Drainage Pathways – Southern Union Gas Services Jal # 3 Plant |
| Figure 6 | Wells Adjacent to Southern Union Gas Services Jal # 3 Plant           |
| Figure 7 | Regional Geologic Setting of Southern Union Gas Services Jal #3 Plant |

### PLATE

|         |   |
|---------|---|
| Plate 1 | Drain Line Schematic (Oversize – in pocket) |
|---------|---|

### LIST OF TABLES

|         |   |
|---------|---|
| Table 1 | Data on Jal #3 Compressors                                |
| Table 2 | Bulk Storage Containers – Jal #3 Plant                    |
| Table 3 | Summary of Water Well Records in Vicinity of Jal #3 Plant |

### APPENDICES

|            |  |
|------------|--|
| Appendix A | List of Substances Used at Facility and Associated MSDS              |
| Appendix B | NMOCD Data on Injection Well   |
| Appendix C | Drain Systems and Tank System Testing Procedures and Results         |
| Appendix D | List of Recycling and Disposal Contractors                           |
| Appendix E | Waste Characterization of Non-Exempt Effluent Waste Streams          |
| Appendix F | Jal # 3 SPCC Plan  |
| Appendix G | Information on Surficial Soils                                       |
| Appendix H | Draft Notice of Application, Locations and Newspaper for Publication |
| Appendix I | C-108 Application for Jal#3 AGI#1                                    |

## 8.0 WASTE DISPOSAL

### 8.1 EXISTING ON-SITE EFFLUENT DISPOSAL FACILITIES

All wastewater is routed through the classifier to remove suspended solids and oil. The classified water is currently then filtered and pumped into the disposal well (Woolworth Estate - SWD No. 1 E located in Unit E of Sec. 33, T-24-S, R-37-E (Appendix B). This well is to be replaced by a new combined acid gas and classified water injection well which is the subject of a C-108 application submitted to NMOCD in December 2007. The plant wastewater system currently injects approximately 1320 bbl/day of classified wastewater (1,662,000 gals/mo). The proposed injection well will inject acid gas taken from a slipstream to the SRU combined with the wastewater which is currently being injected into the Woolworth Estate – SWD No. 1. The new proposed Jal#3AGI#1 will be located approximately 200' east of the current well on the Jal #3 Plant, and a new pipe will be run from the location of the existing well (which is scheduled to be plugged before the new one is put into operation) to carry the wastewater to the wellhead inlet for mixing with the treated acid gas stream. Figures 2a, 2b, 3 and 5 from the C-108 application (attached to this amendment as Appendix I) show the modifications to the existing wastewater flow system, schematic of the wastewater/acid gas injection system, the process flow diagram for the wastewater/acid gas injection system and the schematic of the proposed acid gas well, respectively. Like the current well, the combined wastewater/acid gas stream will be injected into the San Andres Formation at a depth of approximately 4,750-5,200 feet. The existing well was completed in compliance with NMOCD administrative order No. SWD-231 dated November 6, 1980. The location of the existing well is shown in the August 17, 2007 DP application (aerial photograph Figure 2 and Figure(s) 3 and 4 show the wastewater flow schematics). A detailed description of the proposed injection well operation, the geology of the injection zone and the demonstration of no hydraulic connection with any fresh water sources in the area is included in the C-108 application which is attached herein as Appendix I. In addition, the draft revised Rule 118 plan is included as appendix E to the C-108 application.



## **APPENDIX H**

**Notice of Application by Southern Union Gas Services for Approval of a Discharge Plan for Natural Gas Processing Plant:** Southern Union Gas Services, whose offices are located at 301 Commerce St. Suite 700, Fort Worth, Texas (76102) seeks approval from the New Mexico Oil Conservation for renewal of a Discharge Plan for the Jal #3 Natural Gas Processing Plant, located in the West Half of the West Half of Section 33, Township 24 South, Range 37 East in Lea County, New Mexico (32°10'27" North, 103°10'27" West). This location is at an elevation of approximately 3260 feet, approximately 3.5 miles north of Jal, New Mexico. This natural gas plant is designed to have no intentional liquid discharges and disposes of wastewater and acid gas in a permitted injection well. The shallowest groundwater potentially impacted by this facility is at a depth of approximately 90 feet and has a total dissolved solids content of approximately 2,200 milligrams per liter. Additional information, comments or statements should be addressed Mr. Alberto A. Gutierrez, R.G. of Geolex, Inc., 500 Marquette NW, Suite 1350, Albuquerque, NM 87102, Tel. (505-842-8000).

### **PROPOSED POSTINGS, NOTIFICATIONS, AND PUBLICATION**

Following NMOCD review and acceptance, we propose to post this notice using a 2'x3' sign, in English and Spanish, at the gate of the above-named facility and to post the 2<sup>nd</sup> sign outside the SUGS office in Jal.

Identified owners of all properties within a 1/3-mile distance from the boundary of the property where the discharge site is located will be provided with copies of this notice by mail. If there are no properties other than properties owned by SUGS within a 1/3-mile distance from the boundary of property where the discharge site is located, notice will be provided to owners of record of the next nearest adjacent properties not owned by the discharger.

Any owners of the lands upon which the proposed discharge site is located not owned by SUGS will be notified by certified, receipt-requested mailing.


The notice will also be advertised, in English and Spanish, in a 3" by 4" display advertisement in the local newspaper, the Hobbs News-Sun.

**APPENDIX I**

**JAL #3 AGI #1 C-108 APPLICATION FILED 12/2007**



**C-108 Application For Approval to Drill and Operate a New Well  
For The Combined Injection of Acid Gas and Plant Wastewater  
SUGS Jal #3 Natural Gas Processing Plant  
(Unit E Section 33, Township 24 S, Range 37 E)**



**December 18, 2007**

*Prepared For:*

**Southern Union Gas Services, Ltd.  
301 Commerce Street, Suite 700  
Fort Worth, Texas 76102  
Telephone: (817)-302-9400**

*Submitted To:*


**New Mexico Oil Conservation Division  
1220 South St. Francis Drive  
Santa Fe, NM 87505**

*Prepared By:*

**Geolex, Inc.  
500 Marquette Avenue, NE, Suite 1350  
Albuquerque, New Mexico 87102  
Telephone: (505) 842-8000**

**GEOLEX<sup>®</sup>**  
INCORPORATED

**APPLICATION FOR AUTHORIZATION TO INJECT**

- I. PURPOSE: Secondary Recovery Pressure Maintenance X Disposal Storage  
Application qualifies for administrative approval? X Yes No
- II. OPERATOR: Southern Union Gas Services, Ltd.  
ADDRESS: 301 Commerce Street, Suite 700; Ft. Worth, TX 76102  
CONTACT PARTY: Alberto A. Gutierrez, R.G. PHONE: (505)-842-8000
- III. WELL DATA: Complete the data required on the reverse side of this form for each well proposed for injection.  
Additional sheets may be attached if necessary. **A CROSS REFERENCE TO THE APPLICABLE SECTIONS OR APPENDICES IN THE ATTACHED C108 APPLICATION FOR EACH ROMAN NUMERAL BELOW IS SPECIFIED BY SECTION AND/OR APPENDIX NUMBERS.**
- IV. Is this an expansion of an existing project? Yes X No  
If yes, give the Division order number authorizing the project: N/A
- V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review. **SECTIONS 5 AND 6; APPENDICES A, B, C AND D.**
- VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.  
**SECTIONS 4 AND 5; APPENDICES A, B, C AND D.**
- VII. Attach data on the proposed operation, including:
1. Proposed average and maximum daily rate and volume of fluids to be injected; **SECTIONS 1, 2, AND 3**
  2. Whether the system is open or closed; **SECTIONS 1, 2, AND 4**
  3. Proposed average and maximum injection pressure; **SECTIONS 1 AND 3**
  4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and, **SECTIONS 1, 3, 4, AND 5; APPENDIX A**
  5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.). **SECTIONS 3 AND 4; APPENDIX A**
- \*VIII. Attach appropriate geologic data on the injection zone including appropriate lithologic detail, geologic name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such sources known to be immediately underlying the injection interval. **SECTION 4**
- IX. Describe the proposed stimulation program, if any. N/A
- \*X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division, they need not be resubmitted). **WELL IS NOT YET DRILLED; SECTION 4 AND APPENDIX A (FOR EXISTING WELL)**
- \*XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken. **SECTION 4 AND JAL #3 DISCHARGE PLAN GW-010**
- XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground sources of drinking water.  
**SECTION 7**
- XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form. **APPENDICES C AND D**
- XIV. Certification: I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.
- NAME: Alberto A. Gutierrez, C.P.G. TITLE: President, Geolex, Inc.<sup>®</sup>; Consultant to SUGS
- SIGNATURE:  DATE: 12/18/07
- E-MAIL ADDRESS: aag@geolex.com
- \* If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be resubmitted. Please show the date and circumstances of the earlier submittal: **SEE ATTACHED APPLICATION AND PREVIOUSLY SUBMITTED RENEWAL OF NMOCD DISCHARGE PLAN GW-010**

### III. WELL DATA

A. The following well data must be submitted for each injection well covered by this application. The data must be both in tabular and schematic form and shall include:

(1) Lease name; Well No.; Location by Section, Township and Range; and footage location within the section.

**SECTIONS 1, 3 AND 4; APPENDIX A**

(2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined. **SEE SECTION 3 FOR PROPOSED WELL DESIGN AND APPENDIX A FOR DESIGN OF EXISTING WELL. FINAL DESIGN WILL BE SUBMITTED WHEN PROPOSED WELL IS DRILLED AND COMPLETED.**

(3) A description of the tubing to be used including its size, lining material, and setting depth. **SECTION 3**

(4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used. **SECTION 3**

Division District Offices have supplies of Well Data Sheets which may be used or which may be used as models for this purpose. Applicants for several identical wells may submit a "typical data sheet" rather than submitting the data for each well.

B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

(1) The name of the injection formation and, if applicable, the field or pool name. **SECTIONS 1 AND 4**

(2) The injection interval and whether it is perforated or open-hole. **SECTION 3**

(3) State if the well was drilled for injection or, if not, the original purpose of the well. **N/A**

(4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations. **N/A**

(5) Give the depth to and the name of the next higher and next lower oil or gas zone in the area of the well, if any. **SECTIONS 4 AND 5; APPENDICES A, B AND C**

### XIV. PROOF OF NOTICE

All applicants must furnish proof that a copy of the application has been furnished, by certified or registered mail, to the owner of the surface of the land on which the well is to be located and to each leasehold operator within one-half mile of the well location. **SECTION 5; APPENDICES C AND D**

Where an application is subject to administrative approval, a proof of publication must be submitted. Such proof shall consist of a copy of the legal advertisement which was published in the county in which the well is located. The contents of such advertisement must include: **SEE APPENDIX C FOR FORM OF PUBLIC NOTICE – ACTUAL NOTICE WILL BE PUBLISHED WHEN HEARING DATE IS SET**

(1) The name, address, phone number, and contact party for the applicant;

(2) The intended purpose of the injection well; with the exact location of single wells or the Section, Township, and Range location of multiple wells;

(3) The formation name and depth with expected maximum injection rates and pressures; and,

(4) A notation that interested parties must file objections or requests for hearing with the Oil Conservation Division, 1220 South St. Francis Dr., Santa Fe, New Mexico 87505, within 15 days.

NO ACTION WILL BE TAKEN ON THE APPLICATION UNTIL PROPER PROOF OF NOTICE HAS BEEN SUBMITTED.

---

NOTICE: Surface owners or offset operators must file any objections or requests for hearing of administrative applications within 15 days from the date this application was mailed to them.

**SEE SECTION 3 AND FIGURE 5 FOR PROPOSED WELL DESIGN SCHEMATIC; AND APPENDIX A FOR EXISTING WELL INFORMATION**

## TABLE OF CONTENTS

|  |           |
|--|-----------|
| <b>1.0 EXECUTIVE SUMMARY .....</b>   | <b>1</b>  |
| <b>2.0 INTRODUCTION AND ORGANIZATION OF THIS C-108 APPLICATION .....</b>   | <b>3</b>  |
| <b>3.0 PROPOSED CONSTRUCTION AND OPERATION OF JAL#3 AGI WELL .....</b>   | <b>4</b>  |
| <b>4.0 REGIONAL AND LOCAL GEOLOGY AND HYDROGEOLOGY .....</b>   | <b>7</b>  |
| 4.1 GENERAL GEOLOGIC SETTING .....   | 7         |
| 4.2 PERMIAN BEDROCK GEOLOGY .....  | 7         |
| 4.3 LITHOLOGIC AND RESERVOIR CHARACTERISTICS OF SAN ANDRES FORMATION .....   | 9         |
| 4.4 GROUNDWATER HYDROLOGY IN THE VICINITY OF THE PROPOSED<br>INJECTION WELL .....  | 10        |
| <b>5.0 OIL AND GAS WELLS IN THE JAL #3 AGI #1 AREA OF REVIEW AND VICINITY .....</b>  | <b>11</b> |
| 5.1 ACTIVE OIL AND GAS WELLS .....   | 11        |
| 5.2 PLUGGED OIL AND GAS WELLS .....  | 11        |
| <b>6.0 IDENTIFICATION AND REQUIRED NOTIFICATION OF OPERATORS AND<br/>    SURFACE OWNERS WITHIN AREA OF REVIEW .....</b>                            | <b>12</b> |
| <b>7.0 AFFIRMATIVE STATEMENT OF LACK OF HYDRAULIC CONNECTION BETWEEN<br/>    PROPOSED INJECTION ZONE AND KNOWN SOURCES OF DRINKING WATER .....</b> | <b>13</b> |

## LIST OF FIGURES

|   |
|---|
| FIGURE 1: Location of Southern Union Gas Services' Jal #3 Gas Plant   |
| FIGURE 2a: North Portion of Jal #3 Gas Plant Showing Location and Tie-In of Proposed AGI Well and<br>Compression Facilities to Existing Plant |
| FIGURE 2b: Schematic of SUGS Jal #3 Gas Plant Acid Gas Injection System Components  |
| FIGURE 3: 1.5 MMCFD Acid Gas Injection Compressor Process Flow Diagram  |
| FIGURE 4: 5 MMCFD Acid Gas Injection Compressor Process Flow Diagram  |
| FIGURE 5: Jal #3 AGI #1 Preliminary Design  |
| FIGURE 6: Map of San Andres Formation Thickness with Net Porosity >6%   |
| FIGURE 7: Type Structure Section 1 SW-NE  |
| FIGURE 8: Type Structure Section 2 N-SE   |
| FIGURE 9: Map Showing Location of Cross-Sections Shown in Figures 7 and 8   |
| FIGURE 10: Structure on Top of Grayburg Formation   |
| FIGURE 11: Maximum Extent of Injected Fluid for 2318 bbl/d and 7929 bbl/d after 30 years  |
| FIGURE 12: Locations of Water Wells in Vicinity of Southern Union Gas Services Jal #3 Plant   |

## LIST OF APPENDICES

|             |   |
|-------------|---|
| APPENDIX A: | Active Oil & Gas Well Data and Data on Existing SUGS Injection Well |
| APPENDIX B: | Permanently Plugged or Temporarily-Abandoned Oil & Gas Well Data    |
| APPENDIX C: | Operators and Leases in Area of Review and Applicable Notices       |
| APPENDIX D: | Surface Owners in Area of Review and Applicable Notices             |
| APPENDIX E: | Draft Revised Rule 118 Plan for Jal #3 and AGI                      |

## 1.0 EXECUTIVE SUMMARY

On behalf of Southern Union Gas Services Ltd. (SUGS), Geolex, Inc.® (Geolex) has prepared and is hereby submitting a complete C-108 application for approval to drill, complete and operate a combined acid gas and plant wastewater injection well at the SUGS Jal #3 Natural Gas Processing Plant (Plant), which is located on approximately 70 acres in the SW4NW4 and NW4SW4 of Section 33, Township 24 South, Range 37 East, Lea County, New Mexico (Figure 1). This proposed combined acid gas and plant wastewater injection well (Jal#3AGI) will replace the currently operating, permitted plant wastewater disposal well (Woolworth Estate WD #1E/API#30-025-27081).

The Jal#3AGI is anticipated to have a total depth of approximately 5200' at the base of the San Andres Formation. The proposed injection zone will be within the San Andres Formation for all or part of its thickness of approximately 850' in this location (4350'-5200'). The San Andres Formation in this area is a closed system separated from the overlying Grayburg Formation by low porosity carbonates and shales in the Grayburg-San Andres transition zone located at a depth of approximately 4300' in the proposed location. Geologic studies conducted for the selection this location combined with a 27-year history of operating a permitted Class II wastewater injection well at this location demonstrate that the proposed injection zone is readily capable accepting and containing the proposed combined acid gas and wastewater injection volumes well within NMOCD's recommended maximum injection pressures.

Initially the proposed total volume of injected fluid (acid gas and plant wastewater) will be approximately 2318 bbl/day with the possibility of injecting a maximum of up to approximately 7929 bbl/day at a maximum surface pressure of 986 pounds per square inch (psi). The characteristics of the plant wastewater will not change from the currently permitted stream which consists strictly of Class II wastewater from the plant operations. The acid gas which will be combined with the wastewater is a by-product of the treatment of natural gas that flows through the Plant for sweetening and dehydration.

In preparing this C-108 application Geolex conducted a detailed examination of all of the elements required to be evaluated in order to prepare, and obtain approval for, this application for injection. The elements of this evaluation include:

- Identification and characterization of all hydrocarbon-producing zones of wells that surround and are present on the Plant site
- The depths of perforated pay intervals in those wells relative to the depth of the target injection zone (San Andres Formation)
- The past and current use of the San Andres as a water injection zone
- Total feet of net porosity in the San Andres
- The stratigraphic and structural setting of the San Andres relative to any nearby active San Andres wells
- The identification and notification of all surface owners within a 1 mile radius of the proposed injection well
- The identification and notification of all wells within a 2-mile radius and of all operators within a 1 mile radius of the proposed injection well
- Identification and characterization of all plugged wells within a 1 mile radius of the proposed injection well
- The details of the proposed injection operation including general well design and average and maximum daily rates of injection and injection pressures
- Sources of injection fluid and compatibility with the formation fluid of the injection zone

- Location and identification of any fresh water bearing zones in the area, the depths and quality of available groundwater in the vicinity of the proposed well including a determination that there are no structures which could possibly communicate the disposal zone with any known sources of drinking water
- The preliminary revision of the existing Rule 118 plan for the facility to accommodate the proposed changes in operation and the new AGI facility (to be submitted in final form before commencing injection of acid gas)

Based upon this detailed evaluation, as summarized in this application, SUGS has determined that the proposed injection well is a safe and environmentally-sound project for the continued disposal of Class II plant wastewater in combination with the proposed volumes of acid gas from the Plant.

Furthermore, the project provides additional environmental benefit by permanently sequestering a significant volume of CO<sub>2</sub> which would otherwise continue to be released to the atmosphere through the operation of the existing sulfur reduction unit (SRU) at the Plant. Analysis of the reservoir characteristics of the San Andres in this area, and the experience gained from 27 years of operation of the existing plant wastewater injection well, confirms that it is an excellent closed-system reservoir in this area that should easily accommodate the future needs of SUGS for disposal of acid gas and wastewater from the Plant. The estimated total net porosity (over 6%) of the San Andres Formation in the area of the Plant disposal well exceeds 350 feet. This fact is confirmed by the ease with which the well has taken nearly 27 years of wastewater injection from the Plant. The San Andres Formation in the area is bounded vertically by tight carbonates, sandstones and shales of the Grayburg-San Andres transition, which serve to isolate the formation as a closed system from the overlying production in the Yates/Queen interval and the underlying potential production in the Blinberry zone, which only occurs outside the area of review to the east.

There are no wells within several miles of the Plant site that produce hydrocarbons from the San Andres or from the immediately overlying Grayburg or underlying Glorieta Formations. Therefore, the proposed AGI completed into the San Andres would not impact any offset operator's production. The only San Andres well within a one-mile radius of the proposed location is the SUGS Jal #3 Plant's own injection well. All other production or injection wells located within the area of review are associated with waterflood activity in the Yates-Seven Rivers-Queen producing zones well above the San Andres, and are perforated in those formations. The status of all the wells in the area of review that have been plugged has been confirmed and all the data on those wells is included as a part of this C-108 application.

All surface owners and operators within a one-mile radius of the proposed injection well have been provided notice pursuant to the requirements of NMOCD and the confirmation of those notices are included as part of this application.



## 2.0 INTRODUCTION AND ORGANIZATION OF THIS C-108 APPLICATION

The completed NMOCD Form C-108 is included before the Table of Contents of this document and references appropriate sections where data required to be submitted are included herein.

This application organizes and details all of the information required by NMOCD to evaluate and approve the submitted Form C-108 – Application for Authorization to Inject. This information is presented in the following categories:

- A detailed description of the location, construction and operation of the proposed injection well (Section 3.0)
- A summary of the regional and local geology, the hydrogeology, and the location of drinking water wells within the area of review (Section 4.0)
- The identification, location, status, production zones, and other relevant information on oil and gas wells within the area of review (Section 5.0)
- The identification and required notification for operators and surface land owners that are located within the area of review (Section 6.0)
- An affirmative statement, based on the analysis of geological conditions at the site, that there is no hydraulic connection between the proposed injection zone and any known sources of drinking water (Section 7.0), and

In addition, this application includes the following supporting information:

- Appendix A: Maps and spreadsheets showing all oil and gas wells included within the one-mile radius area of review of the proposed injection well. These spreadsheets show the locations, producing status, and producing formations of all wells included in the one-mile area of review. Data on existing SUGS injection well..
- Appendix B: Maps and spreadsheets showing all plugged oil and gas wells included within the one mile area of review and associated plugging diagrams.
- Appendix C: Maps and spreadsheets showing operators in the one-mile radius area of review including copies of notification letters and registered mail receipts
- Appendix D: Maps and spreadsheets showing land ownership in the one-mile radius area of review including copies of notification letters and registered mail receipts
- Appendix E: Draft Revised Rule 118 Plan for Jal #3 and AGI

It is anticipated that this application shall be the subject of a NMOCD hearing in early February 2008.

### 3.0 PROPOSED CONSTRUCTION AND OPERATION OF JAL#3 AGI WELL

The proposed injection well will be drilled approximately 200 feet east of the existing disposal well (Woolworth Estate WD #1; see Figure 1). The new well (Jal #3 AGI #1) will be positioned such that it is sufficiently far from the existing well so as not to encounter that well in the new borehole or to in any way impede the successful plugging and abandonment of the current disposal well. Figure 2a is a general plot plan of the northern portion of the Jal #3 Plant that shows the proposed location of the new well and compression facilities relative to existing features at the site including the existing disposal well. Figure 2b is a schematic process and piping diagram that shows the AGI/wastewater injection system components from tie-ins to current Jal #3 Plant facilities. The proposed location for the Jal #3 AGI #1 is 1570 feet FNL and 1050 feet FWL of Section 33, T24S, R37E.

SUGS will apply for an operator number and file the required plugging bond for the proposed Jal #3 AGI #1 upon approval of this C-108 prior to commencement of drilling.

The new well will be designed and constructed such that it will serve as the injection conduit for a mixed stream of treated acid gas in addition to the Class II plant wastewater which is currently being injected into the San Andres Formation via the Woolworth Estate WD#1. The treated acid gas stream (TAG) will be approximately of the following composition:

- 78% CO<sub>2</sub>
- 20% H<sub>2</sub>S
- 2% C<sub>1</sub>-C<sub>7</sub>

The wastewater to be injected with the treated acid gas consists of the exempt plant wastewater stream that has been characterized in the facility's NMOC discharge plan (GW-010) and which is currently approved for injection into the San Andres via the existing disposal well. Chemical and physical parameters of the currently injected wastewater are summarized in the discharge plan and in the information on the current injection well included in Appendix A.

The initial plan for the injection of acid gas is to inject approximately 1.5MMCF/D (578 bbl/d at operating injection pressure) and to ultimately scale up to inject 5MMCF/D (1929 bbl/d at operating injection pressure) when the additional capacity is required based on sulfur recovery unit (SRU) operating constraints.

Figure 3 is a process flow diagram for the injection process of both treated acid gas (TAG) and wastewater at a 1.5 MMCF/D rate. The figure shows that the total volume of fluid to be injected under this scenario is 2318 bbl/d (578bbl/d TAG and 1740 bbl/d wastewater). Figure 4 is a process flow diagram for the injection process of both treated acid gas (TAG) and wastewater at a 5 MMCF/D rate. The figure shows that the total volume of fluid to be injected under this scenario is 7929 bbl/d (1929 bbl/d TAG and 6000 bbl/d wastewater). Pressure reduction valves will be incorporated to assure that maximum surface injection pressure allowed by NMOC will not be exceeded.

The calculated maximum allowable injection pressure would be approximately 986 psi (depending on specific gravity of final TAG/H<sub>2</sub>O stream). It is likely that the average injection pressure will be significantly less based on the demonstrated performance of the existing well. The injection pressure for the existing Woolworth Estate WD#1 well has been running between 480-550psi; however, the well has a

NMOCD-permitted maximum injection pressure of 940 psi (see information on current well in Appendix A).

We have used the following method approved by NMOCD to calculate the preliminary proposed maximum injection pressure. The final maximum permitted surface injection pressure should be based on the final specific gravity of the injection fluid according to the following formula:

$$IP_{\max} = PG(D_{\text{top}}) \quad \text{where:} \quad \begin{array}{l} IP_{\max} = \text{maximum surface injection pressure (psi)} \\ PG = \text{pressure gradient of mixed injection fluid (psi/ft)} \\ D_{\text{top}} = \text{depth at top of perforated interval of injection zone (ft)} \end{array}$$

$$\text{and} \quad PG = 0.2 + 0.433 (1.04 - SG_{\text{bif}}) \quad \text{where:} \quad SG_{\text{bif}} = \text{specific gravity of blended injection fluid}$$

$$\text{and} \quad SG_{\text{bif}} = \frac{[(SG_{\text{ww}})(WW_{\text{vol}})] + [(SG_{\text{tag}})(TAG_{\text{vol}})]}{WW_{\text{vol}} + TAG_{\text{vol}}}$$

where:  $SG_{\text{ww}}$  = specific gravity of wastewater  
 $SG_{\text{tag}}$  = specific gravity of treated acid gas  
 $WW_{\text{vol}}$  = volume of wastewater in mix  
 $TAG_{\text{vol}}$  = volume of treated acid gas in mix

For the maximum requested injection volume, case it is assumed that:

$$\begin{array}{l} SG_{\text{ww}} = 1.04 \\ SG_{\text{tag}} = 0.80 \\ WW_{\text{vol}} = 6000 \\ TAG_{\text{vol}} = 1929 \\ D_{\text{top}} = 4375 \end{array}$$

Therefore:

$$SG_{\text{bif}} = \frac{[(SG_{\text{ww}})(WW_{\text{vol}})] + [(SG_{\text{tag}})(TAG_{\text{vol}})]}{WW_{\text{vol}} + TAG_{\text{vol}}} = \frac{6240 + 1543}{7929} = 0.9816$$

$$PG = 0.2 + 0.433 (1.04 - SG_{\text{bif}}) = 0.2 + 0.433 (1.04 - 0.9816) = 0.22529$$

$$IP_{\max} = PG(D_{\text{top}}) = .22529(4375) = 985.6$$

Based on the performance of the existing injection well, it is anticipated that the average injection pressure would not exceed 900-950 psi. Based on the above calculations, SUGS is requesting approval of a maximum injection pressure to be 986 psi at the surface.

Due to the corrosive nature of the injected fluid, the line that will convey the combined TAG/water stream to the well from the compression facilities will be a 3" stainless steel line (304 or 316). The final design for the compression facilities and associated piping and layout of H<sub>2</sub>S alarms and other safety equipment

will be submitted for NMOCD review prior to commencement of injection operations. The schematic of the new AGI facilities and the tie-in to existing Jal #3 Plant are shown in Figures 2a and 2b and the preliminary well design for the injection well is shown on Figure 5. The well will have each string of the telescoping casing cemented to the surface and will include a subsurface safety valve on the production tubing to assure that fluid cannot flow back out of the well in the event of a failure of the injection equipment. In addition, the annular space between the production tubing and the well bore will be filled with an inert fluid such as diesel fuel as a further safety measure which is consistent with injection well designs which have been previously approved by NMOCD for acid gas injection.

It is anticipated that the existing disposal well will be used for the continued injection of plant wastewater while the new well is being drilled. After the new well is drilled and tested to assure that it will be able to accept the volume of injection fluid (without using acid gas), it will be completed with the approved injection equipment for the new combined stream of acid gas and plant wastewater. The new well will then be used only for injection of the plant wastewater while the acid gas compression facilities are constructed. At that time the existing plant wastewater disposal well (Woolworth Estate WD #1) will be plugged and abandoned prior to when injection of acid gas commences in combination with plant wastewater in the new well.

The draft revised Rule 118 plan, which is included as Appendix E to this application, will be finalized when the compression facility design and well connection design is complete and will be submitted for NMOCD review and approval prior to commencement of mixed TAG/wastewater injection into the Jal #3 AGI #1.


## 4.0 REGIONAL AND LOCAL GEOLOGY AND HYDROGEOLOGY

### 4.1 GENERAL GEOLOGIC SETTING

The SUGS Jal #3 Plant (the Plant) is located in the western half of Section 33, T 24 S, R 37 E, in Lea County, New Mexico, approximately 3.5 miles north of Jal (Figure 1). The Plant is located within a physiographic area which has been referred to as the Eunice Plain by various authors including Nicholson & Clebsch (1961). This area is almost entirely covered at the surface by Holocene reddish brown dune sand underlain by a hard caliche surface or calcareous silts which may be found in buried valleys or internally drained Quaternary playas. These dune sands are largely stabilized with shin oak, mesquite and some bur-grass. There are no surface bodies of water or groundwater discharge sites within one mile of the Plant and where drainages exist in interdunal areas, they are ephemeral, discontinuous, dry washes. These Quaternary and Holocene deposits are underlain by the discontinuous Ogallala Formation and the underlying Triassic redbeds of the Dockum Group. The Triassic units are in turn underlain by the Rustler Formation and followed by the Ochoa series of evaporites including the Castile and the Salado Formations. Beneath these formations is the Permian sequence of the Central Basin Platform described generally below.

### 4.2 PERMIAN BEDROCK GEOLOGY

The figure shown below is a generalized stratigraphic column showing the Permian Formations that underlie the Plant site. The Plant is located on the west side of the Central Basin Platform province of the Permian Basin, where Permian rocks generally dip to the west as they transition from a sequence of shelf and shelf-edge carbonates and sandstones to basinal-equivalent shale, sandstones, and limestones to the west. The perforation symbols on the left of this column show the formations that have produced oil and gas in the general vicinity of the Plant, and include the Yates, Seven Rivers, Queen Formations which overlie the San Andres injection target. The Blinbry Formation which underlies the San Andres and Glorieta Formations has only been productive along a north south line located approximately two miles east of the proposed location of Jal#3 AGI and well outside the one-mile radius area of review (see Appendices A and B for additional information on oil and gas wells within the area of review, and unitization maps for the area are included in Appendix C).



C:\My Shared Folders\Projects\07-013\Reports\C108Application\Jal#3C-108text.doc

The Yates through Queen interval lies at depths ranging between 3,000 and 3,750 feet beneath the Plant surface. The San Andres is approximately 850 feet thick under the Plant, at depths between 4,350 and approximately 5,200 feet. The Blinberry, which does not produce within the area of review but rather approximately 2 miles east of the Plant site, is found at over 5,400 feet below the surface and the tight Glorieta Formation is between the base of the San Andres and the top of the Blinberry. The remainder of the Permian and older section below the Blinberry consists of rocks ranging in age to Ordovician deposited above Precambrian basement. A generalized stratigraphic section of the area taken from "The oil and gas fields of Southeastern New Mexico, 1960 Supplement" (Roswell Geological Society, 1960) is included below.

| CORRELATION CHART<br>SOUTHEASTERN NEW MEXICO |               |                                   |             |                     |               |           |               |
|--|---------------|-----------------------------------|-------------|---------------------|---------------|-----------|---------------|
| PERIOD                                       | SERIES        | NORTHWESTERN SHELF                | MARGIN      | DELAWARE BASIN      | SERIES        |           |               |
| QUATERNARY                                   | ESTUARY       | ALLUVIUM                          |             |                     | ESTUARY       |           |               |
| TERTIARY                                     | PALEOCENE     | OGALLALA                          |             |                     | PALEOCENE     |           |               |
|  | Eocene        |                                   |             |                     |               |           |               |
|  | Oligocene     |                                   |             |                     |               |           |               |
|  | MIOCENE       |                                   |             |                     |               |           |               |
| CRETACEOUS                                   |               | MURKIN REEF, LOMAS DENTONIAN      |             |                     |               |           |               |
| JURASSIC                                     |               |                                   |             |                     |               |           |               |
| TRIASSIC                                     |               | DOCKUM GROUP                      |             |                     |               |           |               |
| PERMIAN                                      | OCHOA         | DIBBY LAKE                        |             |                     | OCHOA         |           |               |
|  |               | MUTLER                            |             |                     |               |           |               |
|  |               | BALADO                            |             |                     |               |           |               |
|  |               | LASTILE                           |             |                     |               |           |               |
|  | GUADALUPE     | SAN ANTONIO                       | TOLEDO      | CAPITAN LIMESTONE   | BELL CANYON   | GUADALUPE |               |
|  |               |                                   | TOLEDO      |                     |               |           |               |
|  |               |                                   | TOLEDO      | GOAT DEEP LIMESTONE | CHERRY CANYON |           |               |
|  |               |                                   | TOLEDO      |                     |               |           |               |
|  |               |                                   | SAN ANTONIO |                     | SAN ANTONIO   |           | BRUSHY CANYON |
|  |               |                                   | SAN ANTONIO |                     |               |           |               |
|  | LEONARD       | LEONARD                           | TOLEDO      | VICTOR PEAR         | BONE SPRING   | LEONARD   |               |
|  |               |                                   | TOLEDO      |                     |               |           |               |
|  | WOLF CAMP     | WOLF CAMP                         | WOLF CAMP   | WOLF CAMP           | WOLF CAMP     | WOLF CAMP |               |
|  |               |                                   | WOLF CAMP   |                     |               |           |               |
|  | PENNSYLVANIAN | CHEROKEE                          | CHEROKEE    | CHEROKEE            | CHEROKEE      | CHEROKEE  |               |
| CANYON                                       |               | CANYON                            | CANYON      | CANYON              | CANYON        |           |               |
| STONY  |               | STONY                             | STONY       | STONY               | STONY         |           |               |
| ATOKA  |               | ATOKA                             | ATOKA       | ATOKA               | ATOKA         |           |               |
| MORROW                                       |               | MORROW                            | MORROW      | MORROW              | MORROW        |           |               |
| MISSISSIPPIAN                                | CHERRY        | "BARNETT SHALE"                   |             |                     | CHERRY        |           |               |
|  | CHERRY        | MISSISSIPPIAN LIMESTONE           |             |                     | CHERRY        |           |               |
|  | CHERRY        |                                   |             |                     | CHERRY        |           |               |
|  | CHERRY        | WOODFORD                          |             |                     | CHERRY        |           |               |
| DEVONIAN                                     | UPPER         | DEVONIAN (SOUTHERN PLATFORM ONLY) |             |                     | UPPER         |           |               |
| ILLINOIS                                     | UPPER         | FUGGELMAN                         |             |                     | UPPER         |           |               |
| ORDOVICIAN                                   | UPPER         | MONTANA                           |             |                     | UPPER         |           |               |
|  | MIDDLE        | SAMPSON                           |             |                     | MIDDLE        |           |               |
|  | LOWER         | EL PASO-ELLENBURGER               |             |                     | LOWER         |           |               |
| PRE-CAMBRIAN                                 |               | EL PASO                           |             |                     |               |           |               |

Directed by C. D. WILSON

STRATIGRAPHIC STUDIES COMMITTEE

#### 4.3 LITHOLOGIC AND RESERVOIR CHARACTERISTICS OF SAN ANDRES FORMATION

The San Andres Formation in the area of the Plant is composed largely of dolomites and shaly dolomites deposited in deeper water adjacent to basinal-transitional depositional environments. Porosity in these rocks is developed throughout the entire formation, where penetrated, but appears to be greater in the thicker-bedded portion of the upper half to two-thirds of the formation. Because of its high porosity and permeability, the San Andres has been used as a salt water disposal zone in a few wells in the area, and also as a source of water for secondary recovery operations in the nearby Yates-Queen fields. Formation fluids in the San Andres have total dissolved solids as high as 160,000 mg/l (Nicholson and Clebsch, 1961, Table 9, pp. 97-98). Only one well within the area of review in the vicinity of the Plant remains active in the San Andres; the Plant's own Class II disposal well (Woolworth Estate WD #1: API 3002527081)). This well will be plugged and abandoned when it is replaced by the proposed Jal #3 AGI as described above in section 3.

Figure 6 is a map of net porosity greater or equal to 6% in the San Andres Formation, based on the limited number of wells that penetrated at least  $\frac{2}{3}$  of the way through the unit. This map was generated from modern porosity logs (either density/neutron, sidewall neutron porosity, or sonic). Porosity generally increases to the west. The Woolworth Estate WD #1 well (existing Jal#3 wastewater disposal well) has over 330 feet of porosity (estimated at 355 feet because that well does not go all the way through the San Andres), and has been used as a wastewater disposal well for the Plant since it was drilled in 1980. The black arrow on Figure 6 points to the only water supply well that is still active in the San Andres, as determined from the records available from the New Mexico Oil Commission - this well is clearly outside the area of review of the proposed injection well and far from any area that might be affected by the proposed injection.

Figures 7 and 8 are representative structural cross-sections that illustrate the pay and injection zones typical of the area (red bars). The cross-sections are referenced on the location map (Figure 9). The yellow shading denotes porosity in the San Andres. The porous San Andres is separated from the Yates-Queen interval by tight carbonates, sandstones, and shale in the Grayburg and uppermost San Andres. The tight carbonates provide a barrier between the active hydrocarbon reservoirs above, and the wet San Andres dolomites below. Similarly, the underlying tight Glorieta Formation separates the San Andres from the lower, productive Blinberry. Therefore the San Andres is a closed system ideally suited for an injection zone.

Figure 10 is a structure map drawn on the top of the Grayburg, which is the nearest horizon above the San Andres that has enough wells that penetrated its top to construct a reliable structure map (the preceding cross-sections show that the tops of the San Andres and Grayburg generally track each other structurally). This map shows that the Jal #3 Plant site lies above a structurally low trough (outlined by a yellow dashed line), which is deepest under the area of the existing Class II disposal well (Woolworth WD #1E). This structural trough is nearly 500 acres in area. Class II wastewater currently injected into this well is most likely accumulated in the area of this trough as would the proposed combined wastewater and acid gas injection fluids. When combined with net porosity in excess of 6% over 350 feet in the San Andres, this structural trough will provide all the needed capacity for combined wastewater and AGI from the proposed Jal #3 AGI. Figure 11 shows the anticipated maximum extent of 30 years of injection through the proposed Jal#3 AGI #1 based on a conservative 350 feet of San Andres Formation with greater than 6% net porosity. The figure includes the anticipated maximum extent and of both the initial scenario of total blended TAG/Wastewater fluid injection of 2318 bbl/d and the maximum scenario of total blended TAG/Wastewater fluid injection of 7929 bbl/d.

#### 4.4 GROUNDWATER HYDROLOGY IN THE VICINITY OF THE PROPOSED INJECTION WELL

The Ogallala aquifer is the principal source of potable water in the area. The depth to groundwater is approximately 90 feet below ground surface. The background total dissolved solids (TDS) concentration for groundwater in the area is approximately 2,200 mg/l. See also Figure 12 for the location of the single water well within the area of review. Table 1 below summarizes all available information on other water wells located near the area of review shown on Figure 12 including the wells which the Jal #3 Plant uses for potable and fire water supply. The plant receives its water from water wells located in Section(s) 5 and 7, Township 25S, Range 38E (Hubb 1 through 5) and Section(s) 25 and 36, Township 24S, Range 37E (Cooper 1 through 8). Other water wells are located in the vicinity of Crawford Ranch in Section 31, Township 24S, Range 37E. For more information, see Section 11.2 of the Application for Renewal of New Mexico Oil Conservation Division – Jal #3 Discharge Plan (GW-010) dated August 17, 2007. The Ogallala groundwater in the area of the Jal #3 plant ranges from 600 to 2,000 mg/l (Nicholson and Clebsch, 1961, Table 8, pp. 94-95).

The Ogallala aquifer slopes to the southeast with a gradient of approximately 10-12 feet per mile and imparts an easterly or southeasterly movement to the groundwater. References: Cronin, 1969; El Paso Natural Gas Company, Discharge Plan, March 1981; Jal # 3 Approved Discharge Plan GW-010; Nicholson and Clebsch, 1961, Geology and Ground-water Conditions in Southern Lea County, NM; GW Report 6, NM Bureau of Mines and Mineral Resources, Socorro, NM. Based on the analysis of groundwater in the vicinity the certification that there is no evidence of potential communication between the proposed injection zone and any drinking water aquifer is included in Section 7.0 of this application.

**Table 1: Wells From New Mexico State Engineers' Files Near The Area of Review of Proposed AGII**

| DB File Nbr | Use | Owner                    | Tws | Rng | Sec | q | q | q | Easting | Northing | Drill Date | Completion Date | Well Depth | Water Depth |
|-------------|-----|--------------------------|-----|-----|-----|---|---|---|---------|----------|------------|-----------------|------------|-------------|
| CP 00304    | DOM | J.J. SMITH               | 24S | 37E | 27  | 1 | 4 |   | 674118  | 3563008  | N/A        | N/A             | N/A        | N/A         |
| CP 00309    | NON | J.J. SMITH               | 24S | 37E | 27  | 1 | 3 | 2 | 673815  | 3563100  | N/A        | N/A             | N/A        | N/A         |
| CP 00310    | NON | J.J. SMITH               | 24S | 37E | 27  | 1 | 1 | 1 | 673608  | 3563502  | N/A        | N/A             | N/A        | N/A         |
| CP 00311    | NON | J.J. SMITH               | 24S | 37E | 34  | 3 | 4 | 2 | 674260  | 3560694  | N/A        | N/A             | N/A        | N/A         |
| CP 00312    | NON | J.J. SMITH               | 24S | 37E | 34  | 4 | 1 | 1 | 674455  | 3561103  | N/A        | N/A             | N/A        | N/A         |
| CP 00501    | SAN | AMERADA HESS CORPORATION | 24S | 37E | 28  | 4 | 1 | 4 | 673019  | 3562484  | 3/13/1972  | 3/14/1972       | 110        | 70          |
| CP 00299    | DOM | J.J. SMITH               | 25S | 37E | 3   | 2 | 4 | 2 | 675081  | 3559901  | N/A        | N/A             | N/A        | N/A         |
| CP 00549    | N/A | N/A                      | 24S | 37E | 31  | 3 | 3 | 4 | 669102  | 3560195  | N/A        | N/A             | N/A        | N/A         |
| CP 00846    | N/A | N/A                      | 25S | 37E | 6   | 2 | 4 |   | 670203  | 3559513  | N/A        | N/A             | N/A        | N/A         |
| CP 00300    | STK | J.J. SMITH               | 25S | 37E | 3   | 4 | 2 | 1 | 674889  | 3559499  | N/A        | N/A             | N/A        | N/A         |
| CP 00507    | SAN | UNION TEX PETE CO.       | 25S | 37E | 5   | 4 | 2 |   | 671769  | 3559347  | 7/26/1973  | 8/16/1973       | N/A        | N/A         |



## 5.0 OIL AND GAS WELLS IN THE JAL #3 AGI #1 AREA OF REVIEW AND VICINITY

### 5.1 ACTIVE OIL AND GAS WELLS

Appendix A contains a complete list based on NMOCD records of all active and temporarily abandoned oil and gas wells within two miles (Figure A-1, Table A-1) and the one-mile radius (area of review) of the proposed AGI/wastewater disposal well. Information on the wells in the area of review includes their total depth, production or injection interval and current status. Figure A-2 and Table A-2 in Appendix A shows the location of all the active and temporarily abandoned wells within the area of review. This figure shows that only the existing SUGS SWD penetrates the San Andres section within the area of review. All available information on the existing SUGS injection well (Woolworth Estate WD#1), including pressure monitoring data, is included in Appendix A.

An earlier well (Langlie Mattix Woolworth Unit #009, API# 3002525373) in Section 28 was originally drilled to 4700 feet in the San Andres in 1976 as a water supply well. This well was plugged back to 4000 feet (above the Grayburg and San Andres) in April 1985, and recompleted as an oil production well in the Langlie Mattix pool. The well is currently an active producer.

The majority of the wells in this area are drilled to produce oil from the Yates-Queen interval. Deeper production from the Blinbry is only found well outside the area of review in an old and well-defined field (Justis Blinbry Field) located 2-3 miles east of the proposed Jal #3 AGI #1. The San Andres, which is a prolific producing zone higher up on the Central Basin Platform, is uniformly wet in the Plant area, and has been used for injection Class II wastewater from the Jal #3 Plant since 1980 and in other some other locations outside the area of review for the disposal of produced water from other zones. The Grayburg is tight and non-productive in this area and provides an excellent seal for the proposed injection in the San Andres Formation. Similarly, the tight Glorieta Formation below the San Andres isolates the proposed injection zone from lower formations.

### 5.2 PLUGGED OIL AND GAS WELLS

Appendix B contains a complete list based on NMOCD records of all plugged and abandoned and temporarily abandoned oil and gas wells within the one-mile radius (area of review) of the proposed AGI/wastewater disposal well (Table B-1) and includes plugging diagrams for each well. Appendix B also contains a CD with the complete NMOCD file on every plugged or temporarily-abandoned well within the area of review. Figure B-1 in Appendix B shows the location of all plugged and abandoned and temporarily abandoned wells within the area of review. Examination of all the available data shows that none of these wells ever reached the San Andres or even the Grayburg. These data show that there is no evidence of improperly plugged or abandoned wells within the area of review which might cause communication between the proposed injection zone in the San Andres and any other unit.

## **6.0 IDENTIFICATION AND REQUIRED NOTIFICATION OF OPERATORS AND SURFACE OWNERS WITHIN AREA OF REVIEW**

Appendix C includes the data on the leases, units, and operators in the area of review. Figures C-1 to C-4, taken from NMOCD internet files, show the unitized leases in the area surrounding the location of the proposed SUGS AGI well. The circles shown in these figures correspond to the 2-mile circle depicted in Figure A-1.

Production in the area of review is controlled by 12 operators as currently listed by the NMOCD internet database (see Table A-2). These operators' addresses are listed in Table C-2.


Since all leases and production in the area of interest is controlled by the listed lease operators, all of these entities have been noticed, along with the land owners, according to the requirements of Section XIV of the C-108. The proposed public notice for publication and copies of actual individual notices for operators within area of review are included in Appendix C.

Appendix D includes a map (Figure D-1) showing the locations of surface land ownership in the area of review, and Table D-1 summarizes the landowners of record in the area of review, as available from the Lea County land records. Copies of actual individual notices to surface owners within the area of review are also included in Appendix D.

## **7.0 AFFIRMATIVE STATEMENT OF LACK OF HYDRAULIC CONNECTION BETWEEN PROPOSED INJECTION ZONE AND KNOWN SOURCES OF DRINKING WATER**

As part of the work performed to support this application, a detailed investigation of the structure, stratigraphy and hydrogeology of the area surrounding the proposed Jal#3 AGI #1 injection well has been performed. This investigation included the analysis of available geologic data and hydrogeologic data from wells and literature identified in Sections 3, 4 and 5 above including related appendices. Based on this investigation and analysis of these data, it is clear that there are no open fractures, faults or other structures which could potentially result in the communication of the proposed injection zone with any known sources of drinking water in the vicinity as described above in Sections 4 and 5 of this application.


## FIGURES



**Figure 1:**  
**Location of Southern Union Gas Services' Jal #3 Gas Plant**



FIGURE 2a NORTH PORTION OF JAL #3 GAS PLANT SHOWING LOCATION AND TIE-IN OF  
PROPOSED AGI WELL AND COMPRESSION FACILITIES TO EXISTING PLANT






Figure 2b Schematic of SUGS Jal #3 Gas Plant Acid Gas Injection System Components



**Figure 3**  
**Southern Union Gas Services**  
**Jal 3 Gas Plant**  
**1.5 MMCFD Acid Gas Injection Compressor Process Flow Diagram**









Figure 4  
Southern Union Gas Services  
Jal 3 Gas Plant  
5 MMCFD Acid Gas Injection Compressor Process Flow Diagram





**Figure 5:**  
**Jal #3 AGI #1 Design**



THE BLUE ARROW  
POINTS TO THE SUBJECT WATER INJECTION  
WELL ON THE PLANT SITE; THE BLACK  
ARROW POINTS TO THE ONLY OTHER NEARBY,  
ACTIVE, SAN ANDRES INJECTION WELL.

NET POROSITY IS ESTIMATED IN THE  
NORTHWEST CORNER OF THE  
STUDY AREA BECAUSE OF THE  
ABSENCE OF ANY WELLS THERE  
THAT PENETRATED THE SAN  
ANDRES. WARMER COLORS  
DENOTE AREAS OF HIGHER NET  
POROSITY.

FIGURE 6

Geolex, Inc.

SUGS JAL #3 PLANT  
Lea County, New Mexico

San Andres Net Porosity  
>6%

CLIENT: Southern Union Gas Services DATE: 08/19/07







FIGURE 7

Geolex, Inc<sup>®</sup>

SUGS JAL #3 PLANT  
Lea County, New Mexico

TYPE STRUCTURE  
SECTION 1

CLIENT: Southern Union Gas Services DATE: 08/4/07



**FIGURE 8**

**Geolex, Inc<sup>®</sup>**

SUGS JAL #3 PLANT  
Lea County, New Mexico

TYPE STRUCTURE  
SECTION 2

CLIENT: Southern Union Gas Services DATE: 081407






**Figure 9:**  
**Location of Cross-Sections Shown in Figures 7 and 8**

★ Wells Used in Cross-Sections





Cooler (blues) colors are lower; location of subject WIW indicated by yellow circle. The dashed yellow line outlines the deepest part of the structural trough under the plant site.

FIGURE 10


Geolex, Inc.<sup>®</sup>

SUGS JAL#3 PLANT  
Lea County, New Mexico

STRUCTURE, TOP OF GRAYBURG  
C.I. = 10 Feet

CLIENT: Southern Union Gas Services DATE: R 081907





Cooler (blues) colors are lower; location of subject WTW indicated by yellow circle. The dashed yellow line outlines the deepest part of the structural trough under the plant site.


FIGURE 11

Geolex, Inc.

SUGS JAL#3 PLANT  
Lea County, New Mexico

MAXIMUM EXTENT OF INJECTED FLUID  
FOR 2318 and 7929 bbl/d AFTER 30 YEARS  
CLIENT: Southern Union Gas Services DATE: 12/11/2007






**Figure 12:**  
**Locations of Water Wells Adjacent to**  
**Southern Union Gas Services Jal #3 Plant**

- Water Wells Listed in NM State Engineers' Files
- Proposed AGI Well

**APPENDIX A**

**ACTIVE OIL & GAS WELL DATA**  
**AND**  
**DATA ON EXISTING SUGS INJECTION WELL**





**Figure A-1:**  
**Locations of Wells Within Two Miles of SUGS SWD Well**

- ★ Active
- TA
- Existing SUGS SWD
- ★ Plugged
- Not Drilled

**Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well**

| API #      | Well Name                        | Status  | Unit | Typ   | Rng | Sec | ftg  | ns | cd | ftg  | ew | cd | Operator                        | Well Type |
|------------|----------------------------------|---------|------|-------|-----|-----|------|----|----|------|----|----|---------------------------------|-----------|
| 3002511154 | LANGIE JACK UNIT 012             | Active  | I    | 24.0S | 37E | 20  | 1980 | S  |    | 660  | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511155 | LANGIE JACK UNIT 015             | Active  | P    | 24.0S | 37E | 20  | 660  | S  |    | 660  | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511156 | LANGIE JACK UNIT 009             | Active  | H    | 24.0S | 37E | 20  | 1980 | N  |    | 660  | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511157 | LANGIE JACK UNIT 008             | Active  | G    | 24.0S | 37E | 20  | 1980 | N  |    | 1980 | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511167 | LANGIE JACK UNIT 013             | Active  | J    | 24.0S | 37E | 20  | 1980 | S  |    | 1980 | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511168 | KING HARRISON C 003              | Active  | L    | 24.0S | 37E | 20  | 660  | S  |    | 660  | E  |    | PRIMAL ENERGY CORPORATION       | Gas       |
| 3002511169 | LANGIE JACK UNIT 014             | Active  | O    | 24.0S | 37E | 20  | 660  | S  |    | 1980 | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511175 | CALLEY A 001                     | Plugged | N    | 24.0S | 37E | 20  | 660  | S  |    | 2310 | W  |    | WISER OIL CO (THE)              | Gas       |
| 3002511176 | LANGIE JACK UNIT 011             | Active  | E    | 24.0S | 37E | 21  | 1980 | S  |    | 660  | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511177 | LANGIE JACK UNIT 010             | Active  | E    | 24.0S | 37E | 21  | 1980 | N  |    | 660  | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511178 | J F BLACK 001                    | Active  | G    | 24.0S | 37E | 21  | 1980 | N  |    | 1980 | E  |    | PRONGHORN MANAGEMENT CORP       | Oil       |
| 3002511179 | J F BLACK 002                    | Plugged | K    | 24.0S | 37E | 21  | 1980 | S  |    | 1980 | W  |    | TEXACO EXPLORATION              | Gas       |
| 3002511180 | BLACK 001                        | Active  | J    | 24.0S | 37E | 21  | 1980 | S  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511181 | BLACK 003                        | Active  | N    | 24.0S | 37E | 21  | 330  | S  |    | 2310 | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511183 | J F BLACK 004                    | Active  | F    | 24.0S | 37E | 21  | 1980 | N  |    | 1980 | W  |    | PRONGHORN MANAGEMENT CORP       | Oil       |
| 3002511184 | LANGIE JACK UNIT 016             | Active  | M    | 24.0S | 37E | 21  | 660  | S  |    | 660  | W  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511185 | SHELL BLACK 002                  | Plugged | O    | 24.0S | 37E | 21  | 660  | S  |    | 1980 | E  |    | MACK ENERGY CORP                | Gas       |
| 3002511186 | KNIGHT 001                       | Active  | I    | 24.0S | 37E | 21  | 1980 | S  |    | 660  | E  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511187 | KNIGHT 003                       | Active  | P    | 24.0S | 37E | 21  | 660  | S  |    | 660  | E  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511188 | JAMISON 031                      | Active  | H    | 24.0S | 37E | 21  | 2310 | N  |    | 990  | E  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511190 | KNIGHT 004                       | Active  | M    | 24.0S | 37E | 22  | 660  | S  |    | 660  | W  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511191 | KNIGHT 002                       | Active  | L    | 24.0S | 37E | 22  | 1980 | S  |    | 660  | W  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511198 | CORTLAND MYERS UNIT 004          | Active  | N    | 24.0S | 37E | 22  | 660  | S  |    | 1980 | W  |    | WHITING OIL AND GAS CORPORATION | Oil       |
| 3002511243 | LANGIE MATTIX WOOLWORTH UNIT 502 | Active  | E    | 24.0S | 37E | 27  | 1980 | N  |    | 660  | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511244 | LANGIE MATTIX WOOLWORTH UNIT 503 | Active  | C    | 24.0S | 37E | 27  | 660  | N  |    | 1980 | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511245 | LANGIE MATTIX WOOLWORTH UNIT 501 | Active  | D    | 24.0S | 37E | 27  | 660  | N  |    | 660  | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511246 | LANGIE MATTIX WOOLWORTH UNIT 504 | TA      | F    | 24.0S | 37E | 27  | 1980 | N  |    | 1980 | W  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511247 | LANGIE MATTIX WOOLWORTH UNIT 601 | Active  | L    | 24.0S | 37E | 27  | 1980 | S  |    | 660  | W  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511248 | LANGIE MATTIX WOOLWORTH UNIT 602 | Active  | M    | 24.0S | 37E | 27  | 660  | S  |    | 660  | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511249 | LANGIE MATTIX WOOLWORTH UNIT 603 | Active  | K    | 24.0S | 37E | 27  | 1980 | S  |    | 1980 | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511250 | LANGIE MATTIX WOOLWORTH UNIT 604 | TA      | N    | 24.0S | 37E | 27  | 660  | S  |    | 1980 | W  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511251 | LANGIE MATTIX WOOLWORTH UNIT 701 | Active  | B    | 24.0S | 37E | 27  | 660  | N  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511252 | LANGIE MATTIX WOOLWORTH UNIT 702 | Active  | G    | 24.0S | 37E | 27  | 1980 | S  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511253 | LANGIE MATTIX WOOLWORTH UNIT 703 | Plugged | J    | 24.0S | 37E | 27  | 1980 | S  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511254 | JACK B 27 004                    | Plugged | H    | 24.0S | 37E | 27  | 1980 | N  |    | 990  | E  |    | CONTINENTAL OIL CO              | Oil       |
| 3002511255 | LANGIE MATTIX WOOLWORTH UNIT 705 | Active  | I    | 24.0S | 37E | 27  | 1980 | S  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511256 | JACK B 27 006                    | Plugged | O    | 24.0S | 37E | 27  | 660  | S  |    | 1980 | E  |    | CONTINENTAL OIL CO              | Oil       |
| 3002511257 | LANGIE MATTIX WOOLWORTH UNIT 707 | Plugged | P    | 24.0S | 37E | 27  | 660  | S  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511260 | LANGIE MATTIX WOOLWORTH UNIT 401 | Active  | A    | 24.0S | 37E | 28  | 660  | N  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511261 | LANGIE MATTIX WOOLWORTH UNIT 304 | Active  | I    | 24.0S | 37E | 28  | 1980 | S  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511262 | LANGIE MATTIX WOOLWORTH UNIT 305 | Active  | G    | 24.0S | 37E | 28  | 1650 | N  |    | 2310 | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511263 | LANGIE MATTIX WOOLWORTH UNIT 306 | Active  | O    | 24.0S | 37E | 28  | 660  | S  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511264 | LANGIE MATTIX WOOLWORTH UNIT 307 | Active  | P    | 24.0S | 37E | 28  | 660  | S  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511265 | LANGIE MATTIX WOOLWORTH UNIT 102 | Active  | D    | 24.0S | 37E | 28  | 330  | N  |    | 990  | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511266 | LANGIE MATTIX WOOLW 103          | Plugged | F    | 24.0S | 37E | 28  | 1650 | N  |    | 2510 | W  |    | AMERADA HESS CORP               | Oil       |
| 3002511267 | WOOLWORTH 004                    | Plugged | E    | 24.0S | 37E | 28  | 1650 | N  |    | 990  | W  |    | BP AMERICA PRODUCTI             | Gas       |
| 3002511268 | LITIE WOOLWORTH 004              | Active  | L    | 24.0S | 37E | 28  | 1650 | S  |    | 990  | W  |    | MCDONNOLD OPERATING INC         | Gas       |
| 3002511269 | LITIE WOOLWORTH 003              | Active  | M    | 24.0S | 37E | 28  | 990  | S  |    | 990  | W  |    | MCDONNOLD OPERATING INC         | Gas       |
| 3002511270 | LANGIE MATTIX WOOLWORTH UNIT 201 | Active  | K    | 24.0S | 37E | 28  | 2310 | S  |    | 2310 | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511271 | LANGIE MATTIX WOOLWORTH UNIT 202 | Plugged | N    | 24.0S | 37E | 28  | 660  | S  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511272 | LANGIE MATTIX WOOLWORTH UNIT 301 | Active  | B    | 24.0S | 37E | 28  | 660  | N  |    | 1980 | E  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511273 | LANGIE MATTIX WOOLWORTH UNIT 302 | Active  | H    | 24.0S | 37E | 28  | 1980 | N  |    | 660  | E  |    | BETWELL OIL & GAS CO            | Injection |
| 3002511274 | WOOLWORTH 003                    | Active  | J    | 24.0S | 37E | 28  | 2310 | S  |    | 2310 | E  |    | WESTBROOK OIL CORP              | Gas       |
| 3002511275 | LANGIE MATTIX WOOLWORTH UNIT 101 | Active  | C    | 24.0S | 37E | 28  | 330  | N  |    | 2310 | W  |    | BETWELL OIL & GAS CO            | Oil       |
| 3002511276 | LANGIE MATTIX JACK UNIT 017      | Active  | A    | 24.0S | 37E | 29  | 330  | N  |    | 330  | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511277 | JACK A 29 002                    | Active  | I    | 24.0S | 37E | 29  | 2310 | S  |    | 330  | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511278 | JACK A 29 003                    | Active  | H    | 24.0S | 37E | 29  | 1970 | N  |    | 330  | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511279 | JACK A 29 004                    | Active  | O    | 24.0S | 37E | 29  | 990  | S  |    | 1650 | E  |    | MCDONNOLD OPERATING INC         | Injection |
| 3002511280 | JACK B 29 001                    | Active  | P    | 24.0S | 37E | 29  | 990  | S  |    | 330  | E  |    | MCDONNOLD OPERATING INC         | Oil       |
| 3002511281 | LANGIE MATTIX WOOLWORTH UNIT 164 | Active  | P    | 24.0S | 37E | 34  | 330  | S  |    | 990  | E  |    | BETWELL OIL & GAS CO            | Oil       |



**Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well**

| API #      | Well Name                        | Status       | Unit | Typ.  | Rdg. | Sect. | ftg. | ns | cd | ftg. | ew | cd | Operator                            | Well Type |
|------------|----------------------------------|--------------|------|-------|------|-------|------|----|----|------|----|----|-------------------------------------|-----------|
| 3002511282 | WM H HARRISON A WN COM 002       | Active       | D    | 24.05 | 37E  | 29    | 680  | N  |    | 680  | W  |    | BP AMERICA PRODUCTION COMPANY       | Gas       |
| 3002511283 | WM H HARRISON D WN COM 001       | Active       | L    | 24.05 | 37E  | 29    | 1980 | S  |    | 660  | W  |    | BP AMERICA PRODUCTION COMPANY       | Gas       |
| 3002511284 | JACK B 30 001                    | Active       | H    | 24.05 | 37E  | 30    | 1650 | N  |    | 990  | E  |    | PLANTATION OPERATING LLC            | Oil       |
| 3002511285 | C D WOOLWORTH 001                | Plugged      | I    | 24.05 | 37E  | 30    | 1980 | S  |    | 660  | E  |    | GULF OIL CORP                       | Gas       |
| 3002511286 | C D WOOLWORTH 002                | Plugged      | P    | 24.05 | 37E  | 30    | 330  | S  |    | 330  | E  |    | GULF OIL CORP                       | Gas       |
| 3002511287 | C D WOOLWORTH 003                | Plugged      | K    | 24.05 | 37E  | 30    | 1980 | S  |    | 1980 | W  |    | GULF OIL CORP                       | Gas       |
| 3002511289 | COOPER JAL UNIT 232              | Active       | F    | 24.05 | 37E  | 30    | 1980 | N  |    | 1917 | W  |    | SDG RESOURCES LP                    | Oil       |
| 3002511293 | LANGLIE JAL UNIT 011             | TA           | H    | 24.05 | 37E  | 31    | 1980 | N  |    | 660  | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511294 | MARTIN A 002                     | Active       | A    | 24.05 | 37E  | 31    | 990  | N  |    | 660  | E  |    | LEWIS B BURLISON INC                | Gas       |
| 3002511295 | MARTIN B 001                     | Active       | F    | 24.05 | 37E  | 31    | 1650 | N  |    | 1650 | W  |    | PLANTATION OPERATING LLC            | Gas       |
| 3002511297 | LANGLIE JAL UNIT 027             | Active       | P    | 24.05 | 37E  | 31    | 660  | S  |    | 660  | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511298 | LANGLIE JAL UNIT 018             | TA           | J    | 24.05 | 37E  | 31    | 1980 | S  |    | 330  | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511299 | LANGLIE JAL UNIT 016             | Active       | K    | 24.05 | 37E  | 31    | 1980 | S  |    | 1842 | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Oil       |
| 3002511300 | J W SHERRELL 005                 | Active       | N    | 24.05 | 37E  | 31    | 990  | S  |    | 2172 | W  |    | PLANTATION OPERATING LLC            | Gas       |
| 3002511301 | LANGLIE JAL UNIT 017             | Active       | J    | 24.05 | 37E  | 31    | 1980 | S  |    | 1930 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511302 | LANGLIE JAL UNIT 028             | Active       | O    | 24.05 | 37E  | 31    | 440  | S  |    | 1900 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Oil       |
| 3002511303 | LANGLIE JAL UNIT 012             | Active       | G    | 24.05 | 37E  | 31    | 2310 | N  |    | 1977 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Oil       |
| 3002511304 | LANGLIE JAL UNIT 001             | TA           | B    | 24.05 | 37E  | 31    | 990  | N  |    | 1977 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511307 | LANGLIE JAL UNIT 025             | Active       | N    | 24.05 | 37E  | 32    | 660  | S  |    | 1980 | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511308 | LANGLIE JAL UNIT 010             | Plugged      | E    | 24.05 | 37E  | 32    | 1980 | N  |    | 660  | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511309 | STATE B 32 001                   | Plugged      | J    | 24.05 | 37E  | 32    | 1650 | S  |    | 2310 | E  |    | JOHN M KELLY                        | Oil       |
| 3002511310 | LANGLIE JAL UNIT 009             | Active       | F    | 24.05 | 37E  | 32    | 1980 | N  |    | 1980 | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511311 | LANGLIE JAL UNIT 003             | TA           | D    | 24.05 | 37E  | 32    | 990  | N  |    | 660  | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511312 | HUMBLE L STATE 003               | Active       | I    | 24.05 | 37E  | 32    | 3300 | N  |    | 660  | E  |    | MIRAGE ENERGY INC                   | Gas       |
| 3002511313 | LANGLIE JAL UNIT 020             | Active       | K    | 24.05 | 37E  | 32    | 1980 | S  |    | 1980 | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511314 | LANGLIE JAL UNIT 007             | TA           | H    | 24.05 | 37E  | 32    | 1980 | N  |    | 660  | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511315 | LANGLIE JAL UNIT 021             | Active       | J    | 24.05 | 37E  | 32    | 1980 | S  |    | 1980 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511316 | PENROC STATE 001                 | Active       | C    | 24.05 | 37E  | 32    | 330  | N  |    | 2310 | W  |    | WESTBROOK OIL CORP                  | Oil       |
| 3002511317 | LANGLIE JAL UNIT 006             | Active       | A    | 24.05 | 37E  | 32    | 330  | N  |    | 330  | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Oil       |
| 3002511318 | JALMAT STATE GAS COM 003         | Active       | O    | 24.05 | 37E  | 32    | 330  | S  |    | 330  | E  |    | BP AMERICA PRODUCTION COMPANY       | Gas       |
| 3002511319 | JALMAT STATE GAS COM 002         | Active       | P    | 24.05 | 37E  | 32    | 990  | S  |    | 330  | E  |    | BP AMERICA PRODUCTION COMPANY       | Gas       |
| 3002511320 | LANGLIE JAL UNIT 005             | Active       | B    | 24.05 | 37E  | 32    | 990  | N  |    | 2310 | E  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511321 | JALMAT STATE GAS COM 001         | Active       | G    | 24.05 | 37E  | 32    | 2310 | N  |    | 2310 | E  |    | BP AMERICA PRODUCTION COMPANY       | Gas       |
| 3002511322 | LANGLIE JAL UNIT 026             | Active       | M    | 24.05 | 37E  | 32    | 660  | W  |    | 660  | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511323 | LANGLIE JAL UNIT 019             | Active       | L    | 24.05 | 37E  | 32    | 1980 | S  |    | 660  | W  |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection |
| 3002511324 | LANGLIE MATTX WOOLWORTH UNIT 001 | Active       | N    | 24.05 | 37E  | 33    | 990  | S  |    | 2310 | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511325 | LANGLIE MATTX WOOLWORTH UNIT 801 | Active       | C    | 24.05 | 37E  | 33    | 330  | N  |    | 2310 | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511326 | LANGLIE MATTX WOOLWORTH UNIT 802 | Plugged      | F    | 24.05 | 37E  | 33    | 2310 | N  |    | 2310 | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511327 | NORTH SHORE WOOLWORTH 003        | Plugged      | E    | 24.05 | 37E  | 33    | 2310 | N  |    | 330  | W  |    | BURLINGTON RESOURCES OIL & GAS CO   | Gas       |
| 3002511328 | C D WOOLWORTH 001                | Plugged      | C    | 24.05 | 37E  | 33    | 660  | N  |    | 1980 | W  |    | PHILLIPS PETROLEUM CO               | Oil       |
| 3002511329 | LANGLIE MATTX WOOLWORTH UNIT 111 | Plugged      | H    | 24.05 | 37E  | 33    | 1980 | N  |    | 660  | E  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511330 | LANGLIE MATTX WOOLWORTH UNIT 112 | Active       | I    | 24.05 | 37E  | 33    | 1980 | S  |    | 660  | E  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511331 | LANGLIE MATTX WOOLWORTH UNIT 113 | TA           | P    | 24.05 | 37E  | 33    | 660  | S  |    | 330  | E  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511332 | M C WOOLWORTH 004                | Active       | J    | 24.05 | 37E  | 33    | 1980 | S  |    | 1980 | E  |    | SOUTHWEST ROYALTIES INC             | Gas       |
| 3002511333 | LANGLIE MATTX WOOLWORTH UNIT 115 | Active       | O    | 24.05 | 37E  | 33    | 660  | S  |    | 1980 | E  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511334 | LANGLIE MATTX WOOLWORTH UNIT 116 | Active       | A    | 24.05 | 37E  | 33    | 660  | N  |    | 660  | E  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511335 | LANGLIE MATTX WOOLWORTH UNIT 117 | Active       | G    | 24.05 | 37E  | 33    | 1980 | N  |    | 1980 | E  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511336 | LANGLIE MATTX WOOLWORTH UNIT 118 | Active       | B    | 24.05 | 37E  | 33    | 660  | N  |    | 1980 | E  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511337 | LANGLIE MATTX WOOLWORTH UNIT 804 | TA           | D    | 24.05 | 37E  | 33    | 990  | N  |    | 990  | W  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511338 | LANGLIE MATTX WOOLWORTH UNIT 903 | Active       | K    | 24.05 | 37E  | 33    | 1800 | S  |    | 2310 | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511339 | WOOLWORTH 001                    | Plugged      | K    | 24.05 | 37E  | 33    | 1650 | S  |    | 2310 | W  |    | LEWIS B BURLISON INC                | Gas       |
| 3002511340 | LANGLIE MATTX WOOLWORTH UNIT 902 | TA           | L    | 24.05 | 37E  | 33    | 1650 | S  |    | 330  | W  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511341 | LANGLIE MATTX WOOLWORTH UNIT 142 | Zone Plugged | L    | 24.05 | 37E  | 34    | 2310 | S  |    | 990  | W  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511342 | LANGLIE MATTX WOOLWORTH UNIT 141 | Active       | K    | 24.05 | 37E  | 34    | 1650 | S  |    | 2319 | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511343 | LANGLIE MATTX WOOLWORTH UNIT 121 | Active       | H    | 24.05 | 37E  | 34    | 1980 | N  |    | 660  | E  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511344 | LANGLIE MATTX WOOLWORTH UNIT 122 | Active       | F    | 24.05 | 37E  | 34    | 1980 | N  |    | 1980 | W  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511345 | LANGLIE MATTX WOOLWORTH UNIT 123 | Active       | E    | 24.05 | 37E  | 34    | 1980 | N  |    | 660  | W  |    | BETWELL OIL & GAS CO                | Oil       |
| 3002511346 | LANGLIE MATTX WOOLWORTH UNIT 124 | Active       | D    | 24.05 | 37E  | 34    | 660  | N  |    | 660  | W  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511347 | LANGLIE MATTX WOOLWORTH UNIT 125 | TA           | B    | 24.05 | 37E  | 34    | 660  | N  |    | 1980 | E  |    | BETWELL OIL & GAS CO                | Injection |
| 3002511348 | LANGLIE MATTX WOOLWORTH UNIT 163 | Active       | M    | 24.05 | 37E  | 34    | 990  | S  |    | 990  | W  |    | BETWELL OIL & GAS CO                | Oil       |

| Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well |                                   |         |      |       |      |      |      |    |      |          |   |           |
|---|-----------------------------------|---------|------|-------|------|------|------|----|------|----------|---|-----------|
| API #   | Well Name                         | Status  | Unit | Trp.  | Rng. | Sec. | ftg  | ns | cd   | Operator | Well Type                                 |           |
| 3002511349  | LANGLIE MATTIX WOOLWORTH UNIT 126 | Active  | C    | 24.0S | 37E  | 34   | 660  | N  | 1980 | W        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511350  | LANGLIE MATTIX WOOLWORTH UNIT 127 | Active  | A    | 24.0S | 37E  | 34   | 660  | N  | 680  | E        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511351  | LANGLIE MATTIX WOOLWORTH UNIT 151 | Active  | J    | 24.0S | 37E  | 34   | 1980 | S  | 1980 | E        | BETWELL OIL & GAS CO                      | Injection |
| 3002511352  | LANGLIE MATTIX WOOLWORTH UNIT 152 | Active  | I    | 24.0S | 37E  | 34   | 1650 | S  | 990  | E        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511353  | LANGLIE MATTIX WOOLWORTH UNIT 131 | Active  | G    | 24.0S | 37E  | 34   | 1980 | N  | 1980 | E        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511354  | LANGLIE MATTIX WOOLWORTH UNIT 161 | Active  | O    | 24.0S | 37E  | 34   | 990  | S  | 2310 | E        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511355  | LANGLIE MATTIX WOOLWORTH UNIT 162 | Active  | N    | 24.0S | 37E  | 34   | 990  | S  | 2310 | W        | BETWELL OIL & GAS CO                      | Oil       |
| 3002511359  | GEORGE L ERWIN 001                | Active  | M    | 24.0S | 37E  | 35   | 660  | S  | 330  | W        | MCDONNOLD OPERATING INC                   | Oil       |
| 3002511360  | GEORGE L ERWIN 002                | Active  | L    | 24.0S | 37E  | 35   | 1980 | S  | 330  | W        | MCDONNOLD OPERATING INC                   | Injection |
| 3002511368  | C C FRISTOE A FEDERAL NCT 1 001   | Active  | E    | 24.0S | 37E  | 35   | 1980 | N  | 660  | W        | CHEVRON U S A INC                         | Oil       |
| 3002511371  | C C FRISTOE A FEDERAL NCT 1 006   | Active  | D    | 24.0S | 37E  | 35   | 660  | N  | 660  | W        | CHEVRON U S A INC                         | Injection |
| 3002511420  | HUMPHREY QUEEN UNIT 004           | Plugged | B    | 25.0S | 37E  | 3    | 330  | N  | 1650 | E        | PRIZE OPERATING COMPANY                   | Injection |
| 3002511421  | HUMPHREY QUEEN UNIT 003           | Active  | C    | 25.0S | 37E  | 3    | 330  | N  | 2310 | W        | KELTON OPERATING CORP                     | Oil       |
| 3002511422  | HUMPHREY QUEEN UNIT 002           | Active  | D    | 25.0S | 37E  | 3    | 330  | N  | 990  | W        | KELTON OPERATING CORP                     | Injection |
| 3002511423  | J B HUMPHREY 001                  | Plugged | N    | 25.0S | 37E  | 3    | 660  | S  | 1980 | W        | CULBERTSON IRWIN &                        | Oil       |
| 3002511424  | HUMPHREY QUEEN UNIT 010           | Active  | G    | 25.0S | 37E  | 3    | 1650 | N  | 1650 | E        | KELTON OPERATING CORP                     | Oil       |
| 3002511425  | HUMPHREY QUEEN UNIT 009           | Plugged | F    | 25.0S | 37E  | 3    | 1750 | N  | 2310 | W        | PRIZE OPERATING COMPANY                   | Injection |
| 3002511426  | HUMPHREY QUEEN UNIT 017           | Active  | J    | 25.0S | 37E  | 3    | 2310 | S  | 1650 | E        | KELTON OPERATING CORP                     | Injection |
| 3002511428  | HUMPHREY QUEEN UNIT 008           | Plugged | E    | 25.0S | 37E  | 3    | 1650 | N  | 660  | W        | MERIT ENERGY CO                           | Oil       |
| 3002511429  | LIBERTY 003                       | Plugged | L    | 25.0S | 37E  | 3    | 2310 | S  | 660  | W        | MOBIL PRODUCING TEX                       | Gas       |
| 3002511431  | HUMPHREY QUEEN UNIT 005           | Active  | A    | 25.0S | 37E  | 3    | 330  | N  | 990  | E        | KELTON OPERATING CORP                     | Oil       |
| 3002511432  | HUMPHREY QUEEN UNIT 011           | Active  | H    | 25.0S | 37E  | 3    | 1650 | N  | 990  | E        | KELTON OPERATING CORP                     | Oil       |
| 3002511435  | LANGLIE JAL UNIT 061              | Active  | L    | 25.0S | 37E  | 4    | 1980 | S  | 660  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511436  | LANGLIE JAL UNIT 040              | Active  | C    | 25.0S | 37E  | 4    | 330  | N  | 1980 | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511437  | LANGLIE JAL UNIT 041              | Active  | B    | 25.0S | 37E  | 4    | 330  | N  | 1980 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511438  | LANGLIE JAL UNIT 042              | Active  | G    | 25.0S | 37E  | 4    | 1650 | N  | 1980 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511439  | E J WELLS 012                     | Plugged | F    | 25.0S | 37E  | 4    | 1980 | N  | 1650 | W        | ANDERSON PRICHARD                         | Oil       |
| 3002511440  | WELLS FEDERAL 002                 | Active  | G    | 25.0S | 37E  | 4    | 1980 | N  | 1980 | E        | HERMAN L LOEB                             | Gas       |
| 3002511441  | WELLS FEDERAL 003                 | Plugged | K    | 25.0S | 37E  | 4    | 1980 | S  | 1980 | W        | BURLINGTON RESOURCES OIL & GAS CO         | Gas       |
| 3002511442  | LANGLIE JAL UNIT 039              | Active  | D    | 25.0S | 37E  | 4    | 330  | N  | 990  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511443  | LANGLIE JAL UNIT 044              | Active  | E    | 25.0S | 37E  | 4    | 2310 | N  | 990  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511444  | GEORGE SMITH 001                  | Plugged | P    | 25.0S | 37E  | 4    | 660  | S  | 660  | E        | LEWIS B BURLISON IN                       | Oil       |
| 3002511445  | HUMPHREY QUEEN UNIT 001           | Active  | A    | 25.0S | 37E  | 4    | 330  | N  | 330  | E        | KELTON OPERATING CORP                     | Oil       |
| 3002511446  | HUMPHREY QUEEN UNIT 007           | Active  | H    | 25.0S | 37E  | 4    | 1650 | N  | 330  | E        | KELTON OPERATING CORP                     | Oil       |
| 3002511447  | SMITH 003                         | Plugged | I    | 25.0S | 37E  | 4    | 2310 | S  | 660  | E        | MOBIL OIL CORP                            | Gas       |
| 3002511448  | G A SMITH 004                     | Plugged | P    | 25.0S | 37E  | 4    | 990  | S  | 990  | E        | SAM WEINER ETAL                           | Oil       |
| 3002511449  | WELLS FEDERAL 011                 | Plugged | N    | 25.0S | 37E  | 4    | 430  | S  | 2317 | W        | BURLINGTON RESOURCES OIL & GAS COMPANY LP | Gas       |
| 3002511450  | LANGLIE JAL UNIT 064              | Active  | O    | 25.0S | 37E  | 5    | 660  | S  | 1980 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511451  | LANGLIE JAL UNIT 063              | Active  | P    | 25.0S | 37E  | 5    | 660  | S  | 660  | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511452  | LANGLIE JAL UNIT 036              | Active  | C    | 25.0S | 37E  | 5    | 660  | N  | 1980 | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511453  | LANGLIE JAL UNIT 046              | Active  | G    | 25.0S | 37E  | 5    | 1980 | N  | 1980 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511454  | LANGLIE JAL UNIT 059              | Active  | J    | 25.0S | 37E  | 5    | 1650 | S  | 2310 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511455  | LANGLIE JAL UNIT 035              | Active  | D    | 25.0S | 37E  | 5    | 660  | N  | 660  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511456  | LANGLIE JAL UNIT 037              | Active  | B    | 25.0S | 37E  | 5    | 660  | N  | 1980 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511457  | LANGLIE JAL UNIT 048              | Active  | E    | 25.0S | 37E  | 5    | 1980 | N  | 660  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511458  | E J WELLS 013                     | TA      | L    | 25.0S | 37E  | 5    | 1980 | S  | 660  | W        | HERMAN L LOEB                             | Gas       |
| 3002511459  | E J WELLS 014                     | Plugged | N    | 25.0S | 37E  | 5    | 330  | S  | 1650 | W        | ANDERSON PRICHARD                         | Oil       |
| 3002511460  | WELLS B 5 001                     | TA      | A    | 25.0S | 37E  | 5    | 330  | N  | 990  | E        | HERMAN L LOEB                             | Gas       |
| 3002511461  | LANGLIE JAL UNIT 045              | Active  | H    | 25.0S | 37E  | 5    | 1650 | N  | 330  | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511462  | WELLS FEDERAL 001                 | Active  | I    | 25.0S | 37E  | 5    | 1980 | S  | 660  | E        | HERMAN L LOEB                             | Gas       |
| 3002511463  | LANGLIE JAL UNIT 066              | Active  | M    | 25.0S | 37E  | 5    | 660  | S  | 810  | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511464  | LANGLIE JAL UNIT 058              | Active  | K    | 25.0S | 37E  | 5    | 1980 | S  | 1980 | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511465  | WELLS FEDERAL 004                 | Active  | F    | 25.0S | 37E  | 5    | 1980 | N  | 1980 | W        | HERMAN L LOEB                             | Gas       |
| 3002511466  | WN WELLS 001                      | Active  | G    | 25.0S | 37E  | 6    | 1980 | N  | 1980 | E        | MCRAE & HENRY, LTD.                       | Gas       |
| 3002511467  | WELLS B 6 001                     | Active  | A    | 25.0S | 37E  | 6    | 330  | N  | 330  | E        | PLANTATION OPERATING LLC                  | Oil       |
| 3002511476  | LANGLIE JAL UNIT 055              | Active  | J    | 25.0S | 37E  | 6    | 2310 | S  | 1650 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Injection |
| 3002511478  | C D WOOLWORTH GROUP 3 002         | Plugged | H    | 25.0S | 37E  | 6    | 1963 | N  | 643  | E        | PHILLIPS PETROLEUM CO                     | Gas       |
| 3002511479  | LANGLIE JAL UNIT 056              | Active  | I    | 25.0S | 37E  | 6    | 1930 | S  | 710  | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511480  | LANGLIE JAL UNIT 033              | Active  | B    | 25.0S | 37E  | 6    | 330  | N  | 1650 | E        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |
| 3002511481  | LANGLIE JAL UNIT 032              | Active  | C    | 25.0S | 37E  | 6    | 660  | N  | 1920 | W        | PHOENIX HYDROCARBONS OPERATING CORP       | Oil       |


| Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well |                                  |              |      |       |      |      |         |         |                                     |              |
|---|----------------------------------|--------------|------|-------|------|------|---------|---------|-------------------------------------|--------------|
| API #   | Well Name                        | Status       | Unit | Twp.  | Rng. | Sec. | ftg. ns | ftg. ew | Operator                            | Well Type    |
| 3002511496  | LANGLE JAL UNIT 074              | Active       | A    | 25.0S | 37E  | 8    | 660 N   | 660 E   | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002511497  | LANGLE JAL UNIT 073              | Active       | B    | 25.0S | 37E  | 8    | 660 N   | 1980 E  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002511505  | LANGLE JAL D 003                 | Plugged      | B    | 25.0S | 37E  | 8    | 990 N   | 2310 E  | EL PASO NATURAL GAS                 | Gas          |
| 3002511506  | LANGLE JAL UNIT 072              | TA           | C    | 25.0S | 37E  | 8    | 660 N   | 2310 W  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002511510  | LANGLE JAL UNIT 075              | Active       | D    | 25.0S | 37E  | 9    | 660 N   | 660 W   | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002512341  | LANGLE MATIX WOOLWORTH UNIT 002  | Active       | M    | 24.0S | 37E  | 33   | 990 S   | 990 W   | BETWELL OIL & GAS CO                | Oil          |
| 3002520059  | LANGLE MATIX WOOLWORTH UNIT 001  | Active       | M    | 24.0S | 37E  | 27   | 1300 S  | 660 W   | BETWELL OIL & GAS CO                | Water Supply |
| 3002520085  | LANGLE MATIX WOOLWORTH UNIT 308  | Zone Plugged | J    | 24.0S | 37E  | 28   | 1980 S  | 1980 E  | BETWELL OIL & GAS CO                | Injection    |
| 3002520152  | MOSLEY 001                       | Active       | P    | 24.0S | 37E  | 34   | 330 S   | 330 E   | INFLUX PETROLEUM RESOURCES LP       | Oil          |
| 3002520350  | KNIGHT 011                       | Active       | M    | 24.0S | 37E  | 22   | 5 S     | 1315 W  | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520351  | KNIGHT 010                       | Active       | M    | 24.0S | 37E  | 22   | 1315 S  | 1315 W  | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520353  | KNIGHT 008                       | Plugged      | L    | 24.0S | 37E  | 22   | 2635 S  | 5 W     | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520354  | KNIGHT 007                       | Plugged      | I    | 24.0S | 37E  | 21   | 2635 S  | 1315 E  | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520355  | KNIGHT 006                       | Plugged      | P    | 24.0S | 37E  | 21   | 1315 S  | 1315 E  | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520356  | KNIGHT 005                       | Active       | M    | 24.0S | 37E  | 22   | 1315 S  | 5 W     | CELERO ENERGY, LP                   | Injection    |
| 3002520520  | MOSLEY 002                       | Plugged      | K    | 24.0S | 37E  | 34   | 330 S   | 1650 E  | KINGREA & PENDLETON                 | Oil          |
| 3002520612  | HUMPHREY QUEEN UNIT 016          | Active       | K    | 25.0S | 37E  | 3    | 1980 S  | 1980 W  | KELTON OPERATING CORP               | Oil          |
| 3002520613  | KNIGHT 013                       | Plugged      | P    | 25.0S | 37E  | 21   | 5 S     | 5 E     | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002520609  | BLACK 002                        | Active       | O    | 24.0S | 37E  | 21   | 560 S   | 1880 E  | BETWELL OIL & GAS CO                | Oil          |
| 3002520927  | C C FRISTOE A FEDERA 007         | Plugged      | A    | 25.0S | 37E  | 3    | 330 N   | 330 E   | TEXACO EXPLORATION                  | Oil          |
| 3002521083  | BLACK WSW 001                    | Zone Plugged | O    | 24.0S | 37E  | 21   | 1200 S  | 2320 E  | BETWELL OIL & GAS CO                | Water Supply |
| 3002521084  | BLACK 004                        | Plugged      | N    | 24.0S | 37E  | 21   | 5 S     | 1340 W  | SHELL OIL CO                        | Injection    |
| 3002521086  | BLACK 006                        | Plugged      | O    | 24.0S | 37E  | 21   | 1300 S  | 2660 W  | SHELL OIL CO                        | Injection    |
| 3002521087  | BLACK 007                        | Plugged      | J    | 24.0S | 37E  | 21   | 2620 S  | 2660 W  | SHELL WESTERN E & P                 | Injection    |
| 3002521154  | KNIGHT 012                       | Plugged      | P    | 24.0S | 37E  | 21   | 5 S     | 1315 E  | WHITING OIL AND GAS CORPORATION     | Injection    |
| 3002521198  | HUMPHREY QUEEN UNIT 021          | Active       | M    | 25.0S | 37E  | 3    | 330 S   | 990 W   | KELTON OPERATING CORP               | Oil          |
| 3002521401  | J F BLACK 005                    | Active       | K    | 24.0S | 37E  | 21   | 1980 S  | 2030 W  | PRONGHORN MANAGEMENT CORP           | Oil          |
| 3002521412  | C C FRISTOE A FEDERAL NCT 1 010  | Plugged      | E    | 24.0S | 37E  | 35   | 2080 N  | 660 W   | CHEVRON U S A INC                   | Oil          |
| 3002521414  | C C FRISTOE A FEDERAL NCT 1 011  | Plugged      | D    | 24.0S | 37E  | 35   | 560 N   | 660 W   | TEXACO EXPLORATION & PRODUCTION INC | Oil          |
| 3002521478  | J F BLACK 006                    | Active       | F    | 24.0S | 37E  | 21   | 2630 N  | 1340 W  | PRONGHORN MANAGEMENT CORP           | Injection    |
| 3002521606  | R L MOSLEY 001                   | Plugged      | I    | 24.0S | 37E  | 34   | 1650 S  | 330 E   | TENNECO OIL CO                      | Oil          |
| 3002521689  | C C FRISTOE B FEDERAL NCT 1 002  | Plugged      | H    | 24.0S | 37E  | 26   | 500 S   | 500 W   | TEXACO EXPLORATION & PRODUCTION INC | Oil          |
| 3002521748  | JOHN WILLIAMS 008                | Active       | H    | 24.0S | 37E  | 34   | 1980 N  | 330 E   | WESTBROOK OIL CORP                  | Oil          |
| 3002521765  | JOHN WILLIAMS 009                | Active       | A    | 24.0S | 37E  | 34   | 1120 N  | 330 E   | WESTBROOK OIL CORP                  | Oil          |
| 3002522201  | HUMPHREY QUEEN UNIT 014          | Plugged      | I    | 25.0S | 37E  | 4    | 2230 S  | 467 E   | PRIZE OPERATING COMPANY             | Oil          |
| 3002522243  | HUMPHREY QUEEN UNIT 015          | Active       | L    | 25.0S | 37E  | 3    | 1830 S  | 660 W   | KELTON OPERATING CORP               | Injection    |
| 3002522255  | LANGLE MATIX WOOLWORTH UNIT 709  | Active       | O    | 24.0S | 37E  | 27   | 560 S   | 1980 E  | BETWELL OIL & GAS CO                | Oil          |
| 3002522505  | LANGLE MATIX WOOLWORTH UNIT 505  | Active       | C    | 24.0S | 37E  | 27   | 75 N    | 2540 E  | BETWELL OIL & GAS CO                | Injection    |
| 3002522680  | LANGLE MATIX WOOLWORTH UNIT 203L | Unknown      | L    | 24.0S | 37E  | 28   | 999 S   | 999 W   | BETWELL OIL & GAS CO                | Oil          |
| 3002522681  | LANGLE MATIX WOOLWORTH UNIT 119  | TA           | J    | 24.0S | 37E  | 33   | 1880 S  | 1980 E  | BETWELL OIL & GAS CO                | Injection    |
| 3002523098  | LANGLE MATIX WOOLWORTH UNIT 105  | Active       | F    | 24.0S | 37E  | 28   | 1690 N  | 2020 W  | BETWELL OIL & GAS CO                | Injection    |
| 3002523112  | LANGLE MATIX WOOLWORTH UNIT 204  | TA           | M    | 24.0S | 37E  | 28   | 330 S   | 330 W   | BETWELL OIL & GAS CO                | Injection    |
| 3002523183  | HUMPHREY QUEEN UNIT 020          | TA           | M    | 25.0S | 37E  | 3    | 100 S   | 5 W     | KELTON OPERATING CORP               | Injection    |
| 3002523243  | HUMPHREY QUEEN UNIT 026          | Plugged      | F    | 25.0S | 37E  | 3    | 2420 N  | 2200 W  | MOBIL PRODUCING TEX                 | Injection    |
| 3002523255  | LANGLE MATIX WOOLWORTH UNIT 104  | Active       | E    | 24.0S | 37E  | 28   | 1700 N  | 835 W   | BETWELL OIL & GAS CO                | Oil          |
| 3002523256  | LANGLE MATIX WOOLWORTH UNIT 203  | Active       | L    | 24.0S | 37E  | 28   | 2220 S  | 1250 W  | BETWELL OIL & GAS CO                | Oil          |
| 3002523258  | LANGLE MATIX WOOLW 007           | Plugged      | I    | 24.0S | 37E  | 28   | 1530 S  | 135 E   | AMERADA HESS CORP                   | Water Supply |
| 3002523321  | JACK B 27 003                    | Plugged      | I    | 24.0S | 37E  | 27   | 1980 S  | 330 E   | CONOCO INC                          | Oil          |
| 3002523395  | HUMPHREY QUEEN UNIT 027          | Active       | H    | 25.0S | 37E  | 4    | 1570 N  | 990 E   | KELTON OPERATING CORP               | Injection    |
| 3002523463  | HUMPHREY QUEEN UNIT 013          | Plugged      | I    | 25.0S | 37E  | 4    | 1540 S  | 1220 E  | PRIZE OPERATING COMPANY             | Oil          |
| 3002523572  | LANGLE MATIX WOOLWORTH UNIT 165  | Plugged      | N    | 24.0S | 37E  | 34   | 330 S   | 2310 W  | BETWELL OIL & GAS CO                | Injection    |
| 3002523573  | LANGLE MATIX WOOLWORTH UNIT 166  | Plugged      | P    | 24.0S | 37E  | 34   | 100 S   | 125 E   | BETWELL OIL & GAS CO                | Injection    |
| 3002523598  | LANGLE MATIX WOOLWORTH UNIT 003  | Zone Plugged | N    | 24.0S | 37E  | 33   | 330 S   | 1650 W  | BETWELL OIL & GAS CO                | Injection    |
| 3002523599  | JACK A 29 005                    | Active       | B    | 24.0S | 37E  | 29   | 825 N   | 1750 E  | MCDONNOLD OPERATING INC             | Oil          |
| 3002523607  | LANGLE MATIX WOOLWORTH UNIT 805  | Active       | E    | 24.0S | 37E  | 33   | 2400 N  | 330 W   | BETWELL OIL & GAS CO                | Oil          |
| 3002523685  | JACK A 29 006                    | Active       | G    | 24.0S | 37E  | 29   | 1900 N  | 1700 E  | MCDONNOLD OPERATING INC             | Injection    |
| 3002523779  | JACK A 29 007                    | Active       | J    | 24.0S | 37E  | 29   | 2250 S  | 1750 E  | MCDONNOLD OPERATING INC             | Oil          |
| 3002523865  | LANGLE JAL UNIT 013              | TA           | F    | 24.0S | 37E  | 31   | 1980 N  | 1980 W  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523866  | LANGLE JAL UNIT 023              | Active       | P    | 24.0S | 37E  | 32   | 660 S   | 660 E   | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523867  | LANGLE JAL UNIT 029              | Active       | N    | 24.0S | 37E  | 31   | 660 S   | 1980 W  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |

Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well

| API #      | Well Name                         | Status  | Unit | Typ.      | Reg. | Sec. | ftg | ns   | cd | ftg  | ew | cd   | Operator                            | Well Type    |
|------------|-----------------------------------|---------|------|-----------|------|------|-----|------|----|------|----|------|-------------------------------------|--------------|
| 3002523888 | LANGLIE JAL UNIT 049              | Active  | H    | 25.0S 37E | 6    | 1980 | N   | 510  | E  | 1980 | W  | 510  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523882 | LANGLIE JAL UNIT 043              | Active  | F    | 25.0S 37E | 4    | 1980 | N   | 1885 | W  | 1885 | W  | 1885 | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523883 | LANGLIE JAL UNIT 047              | Active  | F    | 25.0S 37E | 5    | 1980 | N   | 810  | W  | 810  | W  | 810  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523884 | LANGLIE JAL UNIT 057              | Active  | L    | 25.0S 37E | 5    | 2030 | S   | 1980 | W  | 1980 | W  | 1980 | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002523885 | LANGLIE JAL UNIT 065              | Active  | N    | 25.0S 37E | 5    | 660  | S   | 2310 | W  | 2310 | W  | 2310 | KELTON OPERATING CORP               | Oil          |
| 3002523968 | HUMPHREY QUEEN UNIT 029           | Active  | C    | 25.0S 37E | 3    | 990  | N   | 1680 | W  | 1680 | W  | 1680 | PRIMAL ENERGY CORPORATION           | Gas          |
| 3002524071 | KING HARRISON C 005               | Active  | K    | 24.0S 37E | 20   | 1700 | S   | 1590 | W  | 1590 | W  | 1590 | C.W. TRAINER                        | Oil          |
| 3002524133 | SHERRELL 001                      | Plugged | N    | 24.0S 37E | 31   | 660  | S   | 750  | E  | 750  | E  | 750  | UNION TEXAS PETROLE                 | Water Supply |
| 3002524456 | LANGLIE JAL UNIT WSW 001          | Plugged | I    | 25.0S 37E | 5    | 2200 | S   | 660  | E  | 660  | E  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524478 | LANGLIE JAL UNIT 022              | Active  | I    | 24.0S 37E | 32   | 1830 | S   | 1880 | E  | 1880 | E  | 1880 | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524479 | LANGLIE JAL UNIT 024              | Active  | O    | 24.0S 37E | 32   | 660  | S   | 660  | E  | 660  | E  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524484 | LANGLIE JAL UNIT 038              | Active  | A    | 25.0S 37E | 5    | 660  | N   | 1980 | W  | 1980 | W  | 1980 | BP AMERICA PRODUCTION COMPANY       | Gas          |
| 3002524669 | WM H HARRISON D W N COM 006       | Active  | N    | 24.0S 37E | 29   | 660  | S   | 1980 | E  | 1980 | E  | 1980 | MCDONNOLD OPERATING LLC             | Gas          |
| 3002524788 | JACK A 29 008                     | Active  | J    | 24.0S 37E | 29   | 1980 | S   | 1880 | E  | 1880 | E  | 1880 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002524789 | JACK A 20 010                     | Active  | O    | 24.0S 37E | 20   | 760  | S   | 660  | E  | 660  | E  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002524837 | LANGLIE JAL UNIT 002              | Active  | D    | 24.0S 37E | 31   | 990  | N   | 1980 | W  | 1980 | W  | 1980 | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524838 | LANGLIE JAL UNIT 004              | Active  | C    | 24.0S 37E | 32   | 990  | N   | 1980 | E  | 1980 | E  | 1980 | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524839 | LANGLIE JAL UNIT 008              | Active  | G    | 24.0S 37E | 32   | 1930 | N   | 660  | E  | 660  | E  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524879 | LANGLIE JAL UNIT 060              | Active  | I    | 25.0S 37E | 5    | 1830 | S   | 660  | W  | 660  | W  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002524880 | LANGLIE JAL UNIT 062              | Plugged | M    | 25.0S 37E | 4    | 660  | S   | 660  | E  | 660  | E  | 660  | PHOENIX HYDROCARBONS OPERATING CORP | Injection    |
| 3002524889 | LANGLIE JAL UNIT 034              | Active  | A    | 25.0S 37E | 6    | 660  | N   | 1980 | E  | 1980 | E  | 1980 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002524890 | LANGLIE JAL UNIT 050              | Active  | G    | 25.0S 37E | 4    | 2130 | S   | 1830 | W  | 1830 | W  | 1830 | CIMAREX ENERGY CO OF COLORADO       | Oil          |
| 3002525240 | WELLS 012                         | Active  | K    | 25.0S 37E | 28   | 1330 | S   | 1350 | E  | 1350 | E  | 1350 | BETWELL OIL & GAS CO                | Oil          |
| 3002525373 | LANGLIE MATTIX WOOLWORTH UNIT 009 | Active  | I    | 24.0S 37E | 28   | 1330 | S   | 1650 | W  | 1650 | W  | 1650 | CIMAREX ENERGY CO OF COLORADO       | Oil          |
| 3002525385 | WELLS 013                         | Active  | N    | 25.0S 37E | 4    | 990  | S   | 1980 | E  | 1980 | E  | 1980 | PACIFIC ENTERPRISES                 | Oil          |
| 3002525391 | WELLS B 001                       | Plugged | J    | 25.0S 37E | 4    | 1980 | S   | 1650 | W  | 1650 | W  | 1650 | INFLOW PETROLEUM RESOURCES LP       | Gas          |
| 3002525429 | WOOLWORTH 002                     | Active  | K    | 24.0S 37E | 33   | 1980 | S   | 760  | E  | 760  | E  | 760  | POGO PRODUCING CO                   | Oil          |
| 3002525464 | C D WOOLWORTH 004                 | Active  | L    | 24.0S 37E | 30   | 2080 | S   | 660  | W  | 660  | W  | 660  | BRECK OPERATING CORP                | Gas          |
| 3002525491 | FLUOR HARRISON 001                | Active  | M    | 24.0S 37E | 20   | 660  | S   | 330  | N  | 330  | N  | 330  | HERMAN L LOEB                       | Gas          |
| 3002525498 | LANGLIE JAL FEDERAL 001           | Active  | A    | 25.0S 37E | 8    | 330  | N   | 1650 | W  | 1650 | W  | 1650 | RALPH C BRUTON                      | Oil          |
| 3002525615 | STUART 9 001                      | Active  | C    | 25.0S 37E | 9    | 330  | N   | 990  | E  | 990  | E  | 990  | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002525630 | ADELE SOWELL 001                  | Active  | P    | 24.0S 37E | 19   | 330  | S   | 990  | E  | 990  | E  | 990  | LEWIS B BURLISON INC                | Gas          |
| 3002525753 | SMITH 002                         | Plugged | P    | 25.0S 37E | 4    | 330  | S   | 1400 | W  | 1400 | W  | 1400 | HERMAN L LOEB                       | Gas          |
| 3002525845 | STATE A 32 004                    | Active  | F    | 24.0S 37E | 32   | 1780 | N   | 1980 | W  | 1980 | W  | 1980 | MCDONNOLD OPERATING INC             | Gas          |
| 3002525847 | LITIE WOOLWORTH 005               | Active  | N    | 24.0S 37E | 28   | 660  | S   | 1725 | E  | 1725 | E  | 1725 | PLANTATION OPERATING LLC            | Oil          |
| 3002525871 | JACK B 30 002                     | Active  | B    | 24.0S 37E | 30   | 330  | N   | 660  | W  | 660  | W  | 660  | PLANTATION OPERATING LLC            | Gas          |
| 3002525974 | SKELLY M STATE 004                | Active  | L    | 24.0S 37E | 32   | 1650 | S   | 1980 | W  | 1980 | W  | 1980 | BP AMERICA PRODUCTI                 | Oil          |
| 3002526031 | WOOLWORTH 005                     | Plugged | C    | 24.0S 37E | 28   | 990  | N   | 1650 | W  | 1650 | W  | 1650 | WESTBROOK OIL CORP                  | Gas          |
| 3002526036 | HENRY HARRISON 001                | Active  | N    | 24.0S 37E | 20   | 330  | S   | 660  | W  | 660  | W  | 660  | JOHN YURONKA                        | Gas          |
| 3002526060 | HARRISON 001                      | Plugged | E    | 24.0S 37E | 29   | 1980 | N   | 1650 | W  | 1650 | W  | 1650 | PLANTATION OPERATING LLC            | Gas          |
| 3002526070 | J W SHERRELL 009                  | Active  | J    | 24.0S 37E | 31   | 2250 | S   | 1650 | E  | 1650 | E  | 1650 | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002526086 | GULF EDDIE CORRIGAN 001           | Active  | P    | 24.0S 37E | 30   | 990  | S   | 330  | E  | 330  | E  | 330  | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002526100 | GULF EDDIE CORRIGAN 002           | Active  | I    | 24.0S 37E | 30   | 2310 | S   | 330  | E  | 330  | E  | 330  | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002526239 | HARRISON 002                      | Plugged | D    | 24.0S 37E | 29   | 990  | N   | 1650 | W  | 1650 | W  | 1650 | JOHN YURONKA                        | Oil          |
| 3002526243 | KIMMY K 001                       | Active  | C    | 24.0S 37E | 29   | 990  | N   | 1650 | W  | 1650 | W  | 1650 | FULFER OIL & CATTLE LLC             | Gas          |
| 3002526437 | KIMMY 003                         | Active  | L    | 24.0S 37E | 28   | 1650 | S   | 330  | W  | 330  | W  | 330  | FULFER OIL & CATTLE LLC             | Oil          |
| 3002526490 | KIMMY K 002                       | Active  | F    | 24.0S 37E | 29   | 2310 | N   | 1650 | W  | 1650 | W  | 1650 | FULFER OIL & CATTLE LLC             | SWD          |
| 3002526638 | KIMMY 004                         | Active  | M    | 24.0S 37E | 29   | 890  | S   | 660  | W  | 660  | W  | 660  | FULFER OIL & CATTLE LLC             | Oil          |
| 3002526664 | EL PASO SMITH 001                 | Active  | N    | 24.0S 37E | 21   | 990  | S   | 1650 | W  | 1650 | W  | 1650 | LANEXCO INC                         | Gas          |
| 3002526665 | NORTHSHORE WOOLWORTH 005          | TA      | C    | 24.0S 37E | 33   | 730  | N   | 1980 | W  | 1980 | W  | 1980 | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002526704 | J W SHERRELL 010                  | Active  | C    | 25.0S 37E | 6    | 660  | N   | 2000 | W  | 2000 | W  | 2000 | PLANTATION OPERATING LLC            | Gas          |
| 3002526951 | EL PASO WELLS FEDERAL 001         | Active  | E    | 25.0S 37E | 4    | 1980 | N   | 660  | W  | 660  | W  | 660  | HERMAN L LOEB                       | Gas          |
| 3002527081 | WOOLWORTH ESTATE 001              | Active  | E    | 24.0S 37E | 33   | 1570 | N   | 800  | W  | 800  | W  | 800  | SID RICHARDSON CARBON & GASOLINE CO | SWD          |
| 3002527367 | WM H HARRISON D W N COM 007       | Active  | K    | 24.0S 37E | 29   | 1980 | S   | 1980 | W  | 1980 | W  | 1980 | BP AMERICA PRODUCTION COMPANY       | Gas          |
| 3002527490 | KNIGHT 014                        | Active  | P    | 24.0S 37E | 21   | 1315 | S   | 660  | E  | 660  | E  | 660  | WHITING OIL AND GAS CORPORATION     | Oil          |
| 3002527531 | HUSKY WOOLWORTH 001               | Active  | M    | 24.0S 37E | 33   | 330  | S   | 430  | W  | 430  | W  | 430  | CIMAREX ENERGY CO OF COLORADO       | Gas          |
| 3002527840 | LANGLIE JAL UNIT 095              | Active  | M    | 24.0S 37E | 32   | 140  | S   | 1250 | W  | 1250 | W  | 1250 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002527841 | LANGLIE JAL UNIT 096              | TA      | N    | 24.0S 37E | 32   | 140  | S   | 2600 | W  | 2600 | W  | 2600 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002527842 | LANGLIE JAL UNIT 097              | Active  | P    | 24.0S 37E | 32   | 140  | S   | 1200 | E  | 1200 | E  | 1200 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |
| 3002527843 | LANGLIE JAL UNIT 098              | Active  | I    | 24.0S 37E | 32   | 1422 | S   | 1200 | E  | 1200 | E  | 1200 | PHOENIX HYDROCARBONS OPERATING CORP | Oil          |



| Table A-1: Identification of Wells Within Two Miles of Proposed SUGS AGI Well |                                 |         |      |       |      |      |      |     |      |                                     |
|---|---------------------------------|---------|------|-------|------|------|------|-----|------|-------------------------------------|
| API #   | Well Name                       | Status  | Unit | Twsp. | Reg. | Sec. | 1/4  | 1/2 | 3/4  | Well Type                           |
| 3002527844  | LANGLE JAL UNIT 099             | Active  | K    | 24.0S | 37E  | 32   | 1424 | W   | 2450 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002527845  | LANGLE JAL UNIT 100             | Active  | L    | 24.0S | 37E  | 32   | 1426 | W   | 1300 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528008  | KNIGHT 017                      | Plugged | M    | 24.0S | 37E  | 22   | 1315 | S   | 680  | WHITING OIL AND GAS CORPORATION     |
| 3002528012  | HUMPHREY QUEEN UNIT 030         | Active  | E    | 25.0S | 37E  | 3    | 2388 | N   | 1300 | KELTON OPERATING CORP               |
| 3002528013  | HUMPHREY QUEEN UNIT 031         | TA      | N    | 25.0S | 37E  | 3    | 1300 | S   | 1750 | KELTON OPERATING CORP               |
| 3002528094  | STATE 28 006                    | Active  | E    | 24.0S | 37E  | 33   | 1720 | N   | 310  | CIMAREX ENERGY CO OF COLORADO       |
| 3002528155  | WELLS B 5 002                   | Active  | G    | 25.0S | 37E  | 5    | 1552 | N   | 2230 | HERMAN L LOEB                       |
| 3002528404  | LANGLE JAL UNIT 101             | Active  | L    | 24.0S | 37E  | 32   | 2540 | S   | 1250 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528405  | LANGLE JAL UNIT 102             | Active  | K    | 24.0S | 37E  | 32   | 2630 | S   | 2630 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528406  | LANGLE JAL UNIT 103             | Active  | P    | 24.0S | 37E  | 31   | 1200 | S   | 131  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528407  | LANGLE JAL UNIT 104             | TA      | M    | 24.0S | 37E  | 32   | 140  | S   | 247  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528454  | LANGLE JAL UNIT 105             | Active  | D    | 25.0S | 37E  | 4    | 1000 | N   | 680  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002528592  | LANGLE MATIX WOOLWORTH UNIT 114 | Active  | G    | 24.0S | 37E  | 33   | 1539 | N   | 2407 | BETWELL OIL & GAS CO                |
| 3002528725  | WELLS FEDERAL 015               | Active  | D    | 25.0S | 37E  | 5    | 810  | N   | 460  | HERMAN L LOEB                       |
| 3002528731  | C D WOOLWORTH 006               | Active  | O    | 24.0S | 37E  | 30   | 660  | S   | 1950 | POGO PRODUCING CO                   |
| 3002528768  | E J WELLS 016                   | Active  | L    | 25.0S | 37E  | 5    | 2310 | S   | 610  | HERMAN L LOEB                       |
| 3002528798  | C D WOOLWORTH 007               | Active  | J    | 24.0S | 37E  | 30   | 1980 | S   | 1980 | POGO PRODUCING CO                   |
| 3002528850  | WELLS FEDERAL 017               | Active  | A    | 25.0S | 37E  | 5    | 1980 | S   | 1450 | HERMAN L LOEB                       |
| 3002528863  | LANGLE JAL UNIT 106             | Active  | J    | 24.0S | 37E  | 32   | 1075 | N   | 1100 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002529044  | LANGLE JAL UNIT 107             | Active  | C    | 25.0S | 37E  | 4    | 1142 | N   | 2518 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002529076  | WELLS FEDERAL 018               | Active  | M    | 25.0S | 37E  | 4    | 330  | S   | 660  | HERMAN L LOEB                       |
| 3002529264  | WELLS FEDERAL 019               | Active  | O    | 25.0S | 37E  | 4    | 660  | S   | 2310 | HERMAN L LOEB                       |
| 3002529447  | LANGLE JAL UNIT 108             | Active  | I    | 25.0S | 37E  | 5    | 2575 | N   | 1275 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002529448  | LANGLE JAL UNIT 109             | Active  | I    | 25.0S | 37E  | 5    | 2555 | N   | 120  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002529449  | LANGLE JAL UNIT 110             | Active  | J    | 25.0S | 37E  | 5    | 1400 | S   | 1350 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002529450  | LANGLE JAL UNIT 111             | Active  | O    | 25.0S | 37E  | 5    | 50   | S   | 2600 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002530703  | JACK A 20 011                   | Active  | J    | 24.0S | 37E  | 20   | 2180 | S   | 1980 | PLANTATION OPERATING LLC            |
| 3002530737  | RED CLOUD 001                   | Active  | C    | 25.0S | 37E  | 3    | 660  | N   | 1980 | WESTBROOK OIL CORP                  |
| 3002530870  | RED CLOUD 002                   | Active  | M    | 25.0S | 37E  | 3    | 660  | S   | 660  | MCDONNOLD OPERATING INC             |
| 3002530871  | LANGLE JAL UNIT 113             | Active  | G    | 25.0S | 37E  | 5    | 1400 | N   | 1350 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002530883  | LANGLE JAL UNIT 114             | Active  | B    | 25.0S | 37E  | 5    | 1270 | N   | 2600 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002530957  | RED CLOUD 004                   | Active  | A    | 25.0S | 37E  | 4    | 660  | N   | 660  | MCDONNOLD OPERATING INC             |
| 3002531014  | LANGLE JAL UNIT 115             | Active  | I    | 25.0S | 37E  | 5    | 2400 | S   | 750  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002531404  | WHITE CLOUD 001                 | Active  | A    | 25.0S | 37E  | 3    | 660  | N   | 660  | WESTBROOK OIL CORP                  |
| 3002532151  | FRICHARD B 001                  | Active  | B    | 25.0S | 37E  | 9    | 760  | N   | 1650 | GUADALUPE OPERATING CO, LLP         |
| 3002532641  | LANGLE JACK UNIT 019            | Active  | J    | 24.0S | 37E  | 20   | 1330 | S   | 1480 | MCDONNOLD OPERATING INC             |
| 3002532643  | JACK A 29 009                   | Active  | H    | 24.0S | 37E  | 29   | 2384 | N   | 1126 | MCDONNOLD OPERATING INC             |
| 3002532862  | C D WOOLWORTH 008               | Active  | K    | 24.0S | 37E  | 30   | 1930 | S   | 1980 | POGO PRODUCING CO                   |
| 3002532863  | C D WOOLWORTH 009               | Active  | N    | 24.0S | 37E  | 30   | 660  | S   | 1980 | POGO PRODUCING CO                   |
| 3002533234  | G L ERWIN A FEDERAL 008         | Active  | L    | 24.0S | 37E  | 35   | 2310 | S   | 330  | CHEVRON U S A INC                   |
| 3002533881  | C D WOOLWORTH 010               | Active  | J    | 24.0S | 37E  | 30   | 1400 | S   | 2630 | POGO PRODUCING CO                   |
| 3002533882  | C D WOOLWORTH 011               | Active  | N    | 24.0S | 37E  | 30   | 1185 | S   | 1330 | POGO PRODUCING CO                   |
| 3002534053  | C C FRISTOE A FEDERAL NCT 1 013 | Active  | E    | 24.0S | 37E  | 35   | 1400 | N   | 330  | CHEVRON U S A INC                   |
| 3002534057  | ENCO STATE 001                  | Active  | A    | 24.0S | 37E  | 32   | 660  | N   | 660  | LEWIS B BURLERSON INC               |
| 3002534555  | STATE A 32 005                  | Active  | D    | 24.0S | 37E  | 32   | 710  | N   | 660  | HERMAN L LOEB                       |
| 3002534614  | WELLS FEDERAL 021               | Active  | O    | 25.0S | 37E  | 5    | 660  | S   | 2310 | HERMAN L LOEB                       |
| 3002534618  | EL PASO WELLS FEDERAL 002       | TA      | C    | 25.0S | 37E  | 4    | 660  | N   | 1980 | HERMAN L LOEB                       |
| 3002535139  | JACK B 30 003                   | Active  | A    | 24.0S | 37E  | 30   | 660  | N   | 660  | PLANTATION OPERATING LLC            |
| 3002535577  | LANGLE JAL UNIT 120             | Active  | O    | 24.0S | 37E  | 31   | 1100 | S   | 2385 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002535681  | LANGLE JAL UNIT 126             | Active  | D    | 25.0S | 37E  | 5    | 990  | N   | 990  | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002535749  | LANGLE JAL UNIT 127             | Active  | N    | 25.0S | 37E  | 5    | 1270 | S   | 1370 | PHOENIX HYDROCARBONS OPERATING CORP |
| 3002535981  | C C FRISTOE A FEDERAL NCT 1 014 | Unknown | D    | 24.0S | 37E  | 35   | 660  | N   | 330  | CHEVRON U S A INC                   |
| 3002537452  | TRANULUA 3 FEDERAL 001          | Active  | A    | 25.0S | 37E  | 3    | 990  | N   | 330  | RANGE OPERATING NEW MEXICO INC      |
| 3002537959  | MARTIN B 003                    | Unknown | C    | 24.0S | 37E  | 31   | 660  | N   | 1917 | PLANTATION OPERATING LLC            |



**Figure A-2:**  
**Locations of Active Wells Within One Mile Radius**  
**of Southern Union Gas Services' SWD Well**

- Existing SUGS SWD
- ★ JALMAT ★ LANGLEIE MATTIX




| Table A-2: ACTIVE WELLS WITHIN ONE MILE OF SUGS PROPOSED AGI WELL |                                   |       |     |     |      |                                       |           |             |                                  |
|---|-----------------------------------|-------|-----|-----|------|---------------------------------------|-----------|-------------|----------------------------------|
| API #   | WELL NAME                         | TWN   | SEC | RNG | UNIT | OPERATOR                              | Well Type | Total Depth | PRODUCING POOL                   |
| 3002511261  | LANGLIE MATTIX WOOLWORTH UNIT 304 | 24.0S | 28  | 37E | J    | BETWELL OIL & GAS CO                  | Oil       | 3350        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511263  | LANGLIE MATTIX WOOLWORTH UNIT 306 | 24.0S | 28  | 37E | O    | BETWELL OIL & GAS CO                  | Oil       | 3250        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511264  | LANGLIE MATTIX WOOLWORTH UNIT 307 | 24.0S | 28  | 37E | P    | BETWELL OIL & GAS CO                  | Inject.   | 3519        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511268  | LITIE WOOLWORTH 004               | 24.0S | 28  | 37E | L    | MCDONNOLD OPERATING INC               | Gas       | 3500        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511269  | LITIE WOOLWORTH 003               | 24.0S | 28  | 37E | M    | MCDONNOLD OPERATING INC               | Gas       | 3475        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511270  | LANGLIE MATTIX WOOLWORTH UNIT 201 | 24.0S | 28  | 37E | K    | BETWELL OIL & GAS CO                  | Oil       | 3450        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511274  | WOOLWORTH 003                     | 24.0S | 28  | 37E | J    | WESTBROOK OIL CORP                    | Gas       | 3536        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511277  | JACK A 29 002                     | 24.0S | 29  | 37E | I    | MCDONNOLD OPERATING INC               | Inject.   | 3700        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511278  | JACK A 29 003                     | 24.0S | 29  | 37E | H    | MCDONNOLD OPERATING INC               | Oil       | 3600        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511279  | JACK A 29 004                     | 24.0S | 29  | 37E | O    | MCDONNOLD OPERATING INC               | Inject.   | 3600        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511280  | JACK B 29 001                     | 24.0S | 29  | 37E | P    | MCDONNOLD OPERATING INC               | Oil       | 3600        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511307  | LANGLIE JAL UNIT 025              | 24.0S | 32  | 37E | N    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3831        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511310  | LANGLIE JAL UNIT 009              | 24.0S | 32  | 37E | F    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 2450        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511312  | HUMBLE L STATE 003                | 24.0S | 32  | 37E | I    | MIRAGE ENERGY INC                     | Gas       | 3500        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511313  | LANGLIE JAL UNIT 020              | 24.0S | 32  | 37E | K    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3436        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511315  | LANGLIE JAL UNIT 021              | 24.0S | 32  | 37E | J    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3550        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511316  | PENROC STATE 001                  | 24.0S | 32  | 37E | C    | WESTBROOK OIL CORP                    | Oil       | 3586        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511317  | LANGLIE JAL UNIT 006              | 24.0S | 32  | 37E | A    | PHOENIX HYDROCARBONS OPERATING CORP   | Oil       | 3500        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511318  | JALMAT STATE GAS COM 003          | 24.0S | 32  | 37E | O    | BP AMERICA PRODUCTION COMPANY         | Gas       | 3450        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511319  | JALMAT STATE GAS COM 002          | 24.0S | 32  | 37E | P    | BP AMERICA PRODUCTION COMPANY         | Gas       | 3450        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511320  | LANGLIE JAL UNIT 005              | 24.0S | 32  | 37E | B    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3450        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511321  | JALMAT STATE GAS COM 001          | 24.0S | 32  | 37E | G    | BP AMERICA PRODUCTION COMPANY         | Gas       | 3450        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511324  | LANGLIE MATTIX WOOLWORTH UNIT 001 | 24.0S | 33  | 37E | N    | BETWELL OIL & GAS CO                  | Oil       | 3600        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511325  | LANGLIE MATTIX WOOLWORTH UNIT 801 | 24.0S | 33  | 37E | C    | BETWELL OIL & GAS CO                  | Oil       | 3548        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511330  | LANGLIE MATTIX WOOLWORTH UNIT 112 | 24.0S | 33  | 37E | I    | BETWELL OIL & GAS CO                  | Oil       | 3550        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511332  | M C WOOLWORTH 004                 | 24.0S | 33  | 37E | J    | SOUTHWEST ROYALTIES INC               | Gas       | 3520        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511333  | LANGLIE MATTIX WOOLWORTH UNIT 115 | 24.0S | 33  | 37E | O    | BETWELL OIL & GAS CO                  | Oil       | 3550        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511334  | LANGLIE MATTIX WOOLWORTH UNIT 116 | 24.0S | 33  | 37E | A    | BETWELL OIL & GAS CO                  | Oil       | 3550        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511335  | LANGLIE MATTIX WOOLWORTH UNIT 117 | 24.0S | 33  | 37E | G    | BETWELL OIL & GAS CO                  | Oil       | 3350        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511336  | LANGLIE MATTIX WOOLWORTH UNIT 118 | 24.0S | 33  | 37E | B    | BETWELL OIL & GAS CO                  | Inject.   | 3350        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511338  | LANGLIE MATTIX WOOLWORTH UNIT 903 | 24.0S | 33  | 37E | K    | BETWELL OIL & GAS CO                  | Oil       | 3500        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511345  | LANGLIE MATTIX WOOLWORTH UNIT 123 | 24.0S | 34  | 37E | E    | BETWELL OIL & GAS CO                  | Oil       | 3800        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511346  | LANGLIE MATTIX WOOLWORTH UNIT 124 | 24.0S | 34  | 37E | D    | BETWELL OIL & GAS CO                  | Inject.   | 3500        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511436  | LANGLIE JAL UNIT 040              | 25.0S | 4   | 37E |      | 3 PHOENIX HYDROCARBONS OPERATING CORP | Oil       | 3552        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511437  | LANGLIE JAL UNIT 041              | 25.0S | 4   | 37E |      | 2 PHOENIX HYDROCARBONS OPERATING CORP | Inject.   | 3530        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511442  | LANGLIE JAL UNIT 039              | 25.0S | 4   | 37E |      | 4 PHOENIX HYDROCARBONS OPERATING CORP | Inject.   | 3543        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511456  | LANGLIE JAL UNIT 037              | 25.0S | 5   | 37E |      | 2 PHOENIX HYDROCARBONS OPERATING CORP | Inject.   | 3552        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002511460  | WELLS B 5 001                     | 25.0S | 5   | 37E |      | 1 HERMAN L LOEB                       | Gas       | 3556        | JALMAT;TAN-YATES-7 RVRS          |
| 3002511461  | LANGLIE MATTIX WOOLWORTH UNIT 002 | 24.0S | 33  | 37E | M    | BETWELL OIL & GAS CO                  | Oil       | 3543        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002523255  | LANGLIE MATTIX WOOLWORTH UNIT 104 | 24.0S | 28  | 37E | E    | BETWELL OIL & GAS CO                  | Oil       | 3765        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002523256  | LANGLIE MATTIX WOOLWORTH UNIT 203 | 24.0S | 28  | 37E | L    | BETWELL OIL & GAS CO                  | Oil       | 3750        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002523607  | LANGLIE MATTIX WOOLWORTH UNIT 805 | 24.0S | 33  | 37E | E    | BETWELL OIL & GAS CO                  | Oil       | 3800        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002523779  | JACK A 29 007                     | 24.0S | 29  | 37E | J    | MCDONNOLD OPERATING INC               | Oil       | 3660        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002523866  | LANGLIE JAL UNIT 023              | 24.0S | 32  | 37E | P    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3600        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002524478  | LANGLIE JAL UNIT 022              | 24.0S | 32  | 37E | I    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3775        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002524479  | LANGLIE JAL UNIT 024              | 24.0S | 32  | 37E | O    | PHOENIX HYDROCARBONS OPERATING CORP   | Inject.   | 3774        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002524484  | LANGLIE JAL UNIT 038              | 25.0S | 5   | 37E |      | 1 PHOENIX HYDROCARBONS OPERATING CORP | Inject.   | 3725        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |
| 3002524669  | WM H HARRISON D WN COM 006        | 24.0S | 29  | 37E | N    | BP AMERICA PRODUCTION COMPANY         | Gas       | 3656        | JALMAT;TAN-YATES-7 RVRS          |
| 3002524788  | JACK A 29 008                     | 24.0S | 29  | 37E | J    | MCDONNOLD OPERATING INC               | Gas       | 3200        | JALMAT;TAN-YATES-7 RVRS          |
| 3002524838  | LANGLIE JAL UNIT 004              | 24.0S | 32  | 37E | C    | PHOENIX HYDROCARBONS OPERATING CORP   | Oil       | 3850        | LANGLIE MATTIX;7 RVRS-Q-GRAYBURG |

| Table A-2: ACTIVE WELLS WITHIN ONE MILE OF SUGS PROPOSED AGI WELL |                                   |       |        |   |                                       |         |      |                                  |  |
|---|-----------------------------------|-------|--------|---|---------------------------------------|---------|------|----------------------------------|--|
|   |                                   |       |        |   |                                       |         |      |                                  |  |
| 3002524839  | LANGLIE JAL UNIT 008              | 24.0S | 32 37E | G | PHOENIX HYDROCARBONS OPERATING CORP   | Inject. | 3850 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002525373  | LANGLIE MATTIX WOOLWORTH UNIT 009 | 24.0S | 28 37E | I | BETWELL OIL & GAS CO                  | Oil     | 4000 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002525429  | WOOLWORTH 002                     | 24.0S | 33 37E | K | INFLOW PETROLEUM RESOURCES LP         | Gas     | 3218 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002525845  | STATE A 32 004                    | 24.0S | 32 37E | F | HERMAN L LOEB                         | Gas     | 3211 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002525847  | LITIE WOOLWORTH 005               | 24.0S | 28 37E | N | MCDONNOLD OPERATING INC               | Gas     | 3210 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002527081  | WOOLWORTH ESTATE 001              | 24.0S | 33 37E | E | SOUTHERN UNION GAS SERVICES, LTD.     | SWD     | 4702 | DISPOSAL                         |  |
| 3002527531  | HUSKY WOOLWORTH 001               | 24.0S | 33 37E | M | CIMAREX ENERGY CO OF COLORADO         | Gas     | 3350 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002527842  | LANGLIE JAL UNIT 097              | 24.0S | 32 37E | P | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3720 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002527843  | LANGLIE JAL UNIT 098              | 24.0S | 32 37E | I | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3722 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002527844  | LANGLIE JAL UNIT 099              | 24.0S | 32 37E | K | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3720 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002528094  | STATE 28 006                      | 24.0S | 33 37E | E | CIMAREX ENERGY CO OF COLORADO         | Gas     | 3426 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002528404  | LANGLIE JAL UNIT 101              | 24.0S | 32 37E | L | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3750 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002528405  | LANGLIE JAL UNIT 102              | 24.0S | 32 37E | K | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3750 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002528454  | LANGLIE JAL UNIT 105              | 24.0S | 4 37E  | G | 4 PHOENIX HYDROCARBONS OPERATING CORP | Oil     | 3700 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002528592  | LANGLIE MATTIX WOOLWORTH UNIT 114 | 24.0S | 33 37E | G | BETWELL OIL & GAS CO                  | Oil     | 3718 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002528963  | LANGLIE JAL UNIT 106              | 24.0S | 32 37E | A | PHOENIX HYDROCARBONS OPERATING CORP   | Oil     | 3750 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002529044  | LANGLIE JAL UNIT 107              | 25.0S | 4 37E  | H | 3 PHOENIX HYDROCARBONS OPERATING CORP | Oil     | 3750 | LANGLIE MATTIX:7 RVRs-Q-GRAYBURG |  |
| 3002532643  | JACK A 29 009                     | 24.0S | 29 37E | H | MCDONNOLD OPERATING INC               | Gas     | 3700 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002534057  | ENCO STATE 001                    | 24.0S | 32 37E | A | LEWIS B BURLESON INC                  | Oil     | 3250 | JALMAT:TAN-YATES-7 RVRs          |  |
| 3002534618  | EL PASO WELLS FEDERAL 002         | 25.0S | 4 37E  | 3 | HERMAN L LOEB                         | Gas     | 3175 | JALMAT:TAN-YATES-7 RVRs          |  |

**APPENDIX B**

**PERMANENTLY PLUGGED OR  
TEMPORARILY-ABANDONED  
OIL & GAS WELL DATA**



**Figure B-1:**  
Locations of Temporarily Abandoned and Plugged & Abandoned Wells  
Within One Mile Radius of Southern Union Gas Services' SWD Well

- Existing SUGS SWD
- TA
- Plugged
- Zone Plugged




| Table B-1: Permanently Plugged or Temporarily Abandoned Wells Within One Mile (area of review) of Proposed SUGS AGI Well |                                  |             |       |         |       |      |      |    |    |      |    |     |    |                                     |           |             |                                |
|--|----------------------------------|-------------|-------|---------|-------|------|------|----|----|------|----|-----|----|-------------------------------------|-----------|-------------|--------------------------------|
| API #  | Well Name                        | Status      | Twshp | Section | Range | Unit | Fig. | ns | cd | fig. | ew | low | cd | Operator                            | Type      | Total Depth | Pool (s)                       |
| 3002511267   | WOOLWORTH 004                    | Plugged     | 24.0S | 28      | 37E   | E    | 1650 | N  |    | 990  | W  |     |    | BP AMERICA PRODUCTI                 | Gas       | 3594        | JALMAT;TAN-YATES-7 RVRs (GAS)  |
| 3002511271   | LANGLE MATTX WOOLWORTH UNIT 202  | Plugged     | 24.0S | 28      | 37E   | N    | 660  | S  |    | 660  | E  |     |    | BETWELL OIL & GAS CO                | Injection | 3536        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511309   | STATE B 32 001                   | Plugged     | 24.0S | 32      | 37E   | J    | 1650 | S  |    | 2310 | E  |     |    | JOHN M KELLY                        | Oil       | 3547        | LANGLE MATTX                   |
| 3002511314   | LANGLE JAL UNIT 007              | TA          | 24.0S | 32      | 37E   | F    | 1980 | N  |    | 660  | E  |     |    | PHOENIX HYDROCARBONS OPERATING CORP | Injection | 3624        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511326   | LANGLE MATTX WOOLWORTH UNIT 802  | Plugged     | 24.0S | 33      | 37E   | F    | 2310 | N  |    | 2310 | W  |     |    | BETWELL OIL & GAS CO                | Injection | 3720        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511327   | NORTH SHORE WOOLWORTH 003        | Plugged     | 24.0S | 33      | 37E   | E    | 2310 | N  |    | 330  | W  |     |    | BURLINGTON RESOURCES OIL & GAS CO   | Gas       | 3576        | JALMAT;TAN-YATES-7 RVRs (OIL)  |
| 3002511328   | C D WOOLWORTH 001                | Plugged     | 24.0S | 33      | 37E   | C    | 660  | N  |    | 1980 | W  |     |    | PHILLIPS PETROLEUM CO               | Oil       | 4200        | JALMAT;TAN-YATES-7 RVRs (OIL)  |
| 3002511329   | LANGLE MATTX WOOLWORTH UNIT 111  | Plugged     | 24.0S | 33      | 37E   | H    | 1980 | N  |    | 660  | E  |     |    | BETWELL OIL & GAS CO                | Injection | 3538        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511331   | LANGLE MATTX WOOLWORTH UNIT 113  | TA          | 24.0S | 33      | 37E   | P    | 660  | S  |    | 330  | E  |     |    | BETWELL OIL & GAS CO                | Injection | 3565        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511337   | LANGLE MATTX WOOLWORTH UNIT 804  | TA          | 24.0S | 33      | 37E   | D    | 990  | N  |    | 990  | W  |     |    | BETWELL OIL & GAS CO                | Injection | 3565        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002511339   | WOOLWORTH 001                    | Plugged     | 24.0S | 33      | 37E   | K    | 1650 | S  |    | 2310 | W  |     |    | LEWIS B BURLINSON INC               | Gas       | 3550        | JALMAT;TAN-YATES-7 RVRs (OIL)  |
| 3002511340   | LANGLE MATTX WOOLWORTH UNIT 902  | TA          | 24.0S | 33      | 37E   | L    | 1650 | S  |    | 330  | W  |     |    | BETWELL OIL & GAS CO                | Injection | 3784        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002520095   | LANGLE MATTX WOOLWORTH UNIT 203L | Plugged     | 24.0S | 28      | 37E   | J    | 1980 | S  |    | 1980 | E  |     |    | BETWELL OIL & GAS CO                | Injection | 3683        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002522880   | LANGLE MATTX WOOLWORTH UNIT 309  | Not Drilled | 24.0S | 28      | 37E   | L    | 999  | S  |    | 999  | W  |     |    | Pre-ONGARD                          | NA        | NA          | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002522881   | LANGLE MATTX WOOLWORTH UNIT 119  | TA          | 24.0S | 33      | 37E   | J    | 1980 | S  |    | 1980 | E  |     |    | BETWELL OIL & GAS CO                | Injection | 3708        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002523112   | LANGLE MATTX WOOLWORTH UNIT 204  | TA          | 24.0S | 28      | 37E   | M    | 330  | W  |    | 330  | W  |     |    | BETWELL OIL & GAS CO                | Injection | 3800        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002523598   | LANGLE MATTX WOOLWORTH UNIT 003  | Plugged     | 24.0S | 33      | 37E   | N    | 330  | S  |    | 1650 | W  |     |    | BETWELL OIL & GAS CO                | Injection | 3514        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |
| 3002526665   | NORTHSHORE WOOLWORTH 005         | TA          | 24.0S | 33      | 37E   | C    | 730  | N  |    | 1980 | W  |     |    | CIMAREX ENERGY CO OF COLORADO       | Gas       | 3600        | JALMAT;TAN-YATES-7 RVRs (GAS)  |
| 3002527841   | LANGLE JAL UNIT 096              | TA          | 24.0S | 32      | 37E   | N    | 140  | S  |    | 2600 | W  |     |    | PHOENIX HYDROCARBONS OPERATING CORP | Oil       | 3720        | LANGLE MATTX-7 RVRs-Q-GRAYBURG |

NOTE: Complete copies of NMOCD (<http://codrimage.emrmd.state.nm.us/Imaging/WellFileCriteria.aspx>) files are included in the attached CD

Well 3002522880 was permitted in November 1968 but its approval to drill was cancelled by NMOCD on March 10, 1969 for lack of progress. There are no NMOCD records that indicate that this well was ever drilled.


Woolworth 004  
API 3002511267  
As Plugged & Abandoned 1/16/1985



Plugging Diagram for Woolworth 004 - API # 3002511267  
Unit E, 1650' FNL, 990' FWL, Sec. 28, T24S, R37E  
Former Dual Completion in Jalmat (Gas) and Langlie Mattix (Oil)




Woolworth Unit 202  
API 3002511271  
As Plugged & Abandoned 1/19/05



Plugging Diagram for Woolworth 202 - API # 3002511271  
Unit N, 2310' FWL, 990' FSL, Sec. 28, T24S, R37E  
Oil & Gas Langlie Mattix Nov. 1938-1967 (TA), Inj. Well 1968-1988 (TA)

State B-32  
API 3002511309  
As Plugged & Abandoned 9/29/1953



Plugging Diagram for State B-32 - API # 3002511309  
Unit J, 1650' FSL, 2310' FWL, Sec. 28, T24S, R37E  
Langlie Mattix Well Drilled 1939, P&A 1953, Unsuccessful Re-Entry 3/1955, Re-Plugged

Langlie-Jal Unit 007  
API 3002511314  
As Temporarily Abandoned 2/27/2002

Surface Elev. 3269' GR

Tubing Capped @ Surface

12 1/4" Borehole Surface to 426'

NOTE: T&A Approval Expires 3/1/07

9 5/8" Set @ 426' w/225 SX Concrete

8 3/4" Borehole 426' to 3402'  
7' Casing to 3402'

Baker AD-1 7"  
Packer @ 3255'

7" Set @ 3402 w/360 SX Cement

8" Open Hole 3402' to 3550' (TD)


Deepened @ 3 7/8" to 3680 5/21/1974

Plugging Diagram for Langlie-Jal Unit 007 - API # 3002511314  
Unit H, 660' FEL, 1980 ' FNL, Sec. 32, T24S, R37E  
Langlie Mattix Well Drilled 1939, Conv. to Inj. 4/14/1972, T&A Feb. 2002

Langlie-Mattix Woolworth Unit #802


API 3002511326

As Plugged & Abandoned 10/1/2005




Plugging Diagram for Langlie-Mattix Woolworth Unit #802- API # 3002511326  
Unit F, 2310' FWL, 3210' FNL, Sec. 33, T24S, R37E  
Langlie Mattix Well Drilled 1939, T&A 1965-1968, Inj. 1968-1988, P&A Oct. 2005

Northshore Woolworth #3  
API 3002511327  
As Plugged & Abandoned 5/28/1992



Plugging Diagram for Northshore Woolworth #3- API # 3002511327  
Unit E, 2310' FNL, 330' FWL, Sec. 33, T24S, R37E  
Jalmat-TYS Well Drilled 1941, T&A 1983, P&A May 1992

C.D. Woolworth #1  
API 3002511328  
As Plugged & Abandoned 11/14/1935




Plugging Diagram for Northshore Woolworth #3- API # 3002511327  
Unit C, 660' FNL, 660' FEL, Sec. 33, T24S, R37E  
Langlie-Mattix Well Drilled Sept. 1935, No Production, P&A Nov. 14, 1935

Langlie-Mattix Woolworth #111  
API 3002511329  
As Temporarily Abandoned 12/14/1988

Surface Elev. 3253' TOC

Last Pressure Test Passed 10/11/88  
Closed Valves, TA 12/14/88



13 3/4" Borehole to 353'

10 3/4" Casing @ 353' w/ 400 SX Concrete

Inj. Packers 3174'-3178' 3/14/67

8 5/8" Borehole to 3545'

7" Set @ 3535' w/400 SX Concrete  
Open Hole to 3545'  
Redrilled to 3649' 12/8/67

Plugging Diagram for Langlie-Mattix Woolworth #111- API # 3002511329  
Unit H, 1980' FNL, 660' FEL, Sec. 33, T24S, R37E  
Langlie-Mattix Well Drilled Feb. 1938, Gas Well, T&A 12/22/65, Inj. Well 3/15/67, TA 12/20/1988

Langlie-Mattix Woolworth #113  
API 3002511331  
As Temporarily Abandoned 12/19/2003

Surface Elev. 3191' TOC

Last Pressure Test Passed 12/19/03  
Closed Valves, TA 12/19/03

13 3/4" Borehole to 315'

10 3/4" Casing @ 302' w/ 200 SX Concrete

NOTE: TA approval expires 1/7/09

Inj. Packer 3280' 4/15/72

8 5/8" Borehole to 3525'

7" Set @ 3524' w/400 SX Concrete

Open Hole to 3525'

Redrilled 6 1/8" to 3668' 4/15/72

Plugging Diagram for Langlie-Mattix Woolworth #113- API # 3002511331  
Unit P, 660' FSL, 330' FEL, Sec. 33, T24S, R37E  
Langlie-Mattix Well Drilled Aug. 1938, Oil&Gas Well, Inj. Well 1972-2003, TA



Langlie-Mattix Woolworth #804  
API 3002511337  
As Temporarily Abandoned 12/23/1988

Surface Elev. 3275' GR

Last Pressure Test Passed 10/18/05

22" Borehole to 40'

20" Casing @ 40' w/ 10 SX

NOTE: TA approval expires 10/18/2010

11' Borehole to 1226'

9 5/8" Casing @ 1226' w/ 250 SX Concrete

Inj. Packer 3277' 3/2/71

8 5/8" Borehole to 3565'

7" Set @ 3330' w/250 SX Concrete

Open Hole to 3565'

Redrilled 6 1/8" to 3821' 10/30/67

Plugging Diagram for Langlie-Mattix Woolworth #804- API # 3002511337  
Unit D, 990' FNL, 990' FWL, Sec. 33, T24S, R37E  
Langlie-Mattix Oil Well Drilled April. 1938, TA 10/61, Inj. 11/70, TA 12/23/88

Jalmat Woolworth #001  
API 3002511339  
As Plugged & Abandoned 3/31/83

Surface Elev. 3247' GR

Pump 275 SX, Circulate to  
surface between casings

Perf. 5 1/2" Casing @ 850'

10" Borehole to 1230'

8 5/8" Casing @ 1230' w/ 150 SX Concrete

CIBP @ 1800' w/ 35' Cement cap

7 7/8" Borehole to 3316'

5 1/2" Set @ 3316' w/250 SX Concrete

Open Hole to 3550'

Plugged back to 3139' w/cement 2/4/46

Plugging Diagram for Jalmat Woolworth #001- API # 3002511339  
Unit K, 1650' FSL, 2310' FWL, Sec. 33, T24S, R37E  
Jalmat Well Drilled Sept. 1938, TA 12/76, P&A 3/31/1983

Sam Weiner-Woolworth #902  
API 3002511340  
As Temporarily Abandoned 10/18/1988

Surface Elev. 3257 GR

Last Pressure Test Passed 9/19/05

12" Borehole to 60'

10 3/4" Casing @ 60' w/ 50 SX

NOTE: TA approval expires 9/19/2010

10" Borehole to 1029'

8 5/8" Casing @ 1029' w/ 150 SX Concrete

Inj. Packer 3194' 4/14/1972

7 7/8" Borehole to 3565'

5 3/16" Set @ 3299' w/150 SX Concrete


Open Hole to 3565'

Redrilled 4 3/4" to 3781' 4/14/1972

Plugging Diagram for Langlie-Mattix SAm Weiner-Woolworth #902- API # 3002511340  
Unit L, 1650' FSL, 330' FWL, Sec. 33, T24S, R37E  
Langlie-Mattix Oil Well Drilled Jan. 1939, TA 10/62, Inj. 4/72, TA 10/11/1988

Langlie-Mattix Woolworth #308  
API 3002520085  
As Plugged & Abandoned 10/01/05

Surface Elev. 3228' DF




Plugging Diagram for Langlie-Mattix Woolworth #308- API # 3002520085  
Unit J, 1980' FSL, 1980' FEL, Sec. 28, T24S, R37E  
Langlie-Mattix Well Drilled Sept. 1963 as Inj. Well, TA 9/85, P&A 10/01/05

Langlie-Mattix-Woolworth #119  
API 3002522881  
As Temporarily Abandoned 12/14/1988

Surface Elev. 3229 DF

Last Pressure Test Passed 2/22/05

NOTE: TA approval expires 2/22/2010



9 7/8" Borehole to 752'

7 5/8" Casing @ 747' w/ 400 SX Concrete

Inj. Packer 3430'

6 3/4" Borehole to 3708'

4 1/2" Set @ 3707' w/350 SX Concrete


Plugging Diagram for Langlie-Mattix Woolworth #119- API # 3002522881  
Unit J, 1880' FSL, 1980' FEL, Sec. 33, T24S, R37E  
Langlie-Mattix Oil Well Drilled Mar. 1969, Inj. Well, TA 12/14/1988

Langlie-Mattix-Woolworth #204  
API 3002523112  
As Temporarily Abandoned 12/14/1988

Surface Elev. 3287 DF

Last Pressure Test Passed 2/22/05

NOTE: TA approval expires 2/22/2010



9 7/8" Borehole to 760'

7 5/8" Casing @ 760' w/ 400 SX Concrete

Inj. Packer 3476'


6 3/4" Borehole to 3800'

4 1/2" Set @ 3800' w/300 SX Concrete

Plugging Diagram for Langlie-Mattix Woolworth #204- API # 3002532112  
Unit M, 330' FWL, 330' FSL, Sec. 28, T24S, R37E  
Langlie-Mattix Injection Well Drilled April 1969, TA 12/14/1988



Langlie-Mattix Woolworth #003  
API 3002523598  
As Plugged & Abandoned 01/17/05



Plugging Diagram for Langlie-Mattix Woolworth #003- API # 3002523598  
Unit N, 1650' FWL, 330' FSL, Sec. 33, T24S, R37E  
Langlie-Mattix Well Drilled Oct. 1970 as Inj. Well, TA 9/85, P&A 01/17/2005

Northshore Woolworth #005  
API 3002526665  
As Temporarily Abandoned 6/10/2005

Surface Elev. 3268 KB

Last Pressure Test Passed 5/18/05

NOTE: TA approval expires 5/18/2010

Set CIBP @ 2950', Tested 520# for  
30 min., passed

12 1/4" Borehole to 1203'  
8 5/8" Casing @ 1203' w/ 600 SX Concrete

7 7/8" Borehole to 3598'  
5 1/2" Set @ 3800' w/192 SX Concrete

Northshore Woolworth #005- API # 3002526665  
Unit C, 1980' FWL, 730 ' FNL, Sec. 33, T24S, R37E  
Northshore Well Drilled March 1980, TA 6/10/2005

Langlie-Jal Unit #096  
API 3002527841  
As Temporarily Abandoned 6/10/2002

Surface Elev. 3245 GR

Last Pressure Test Passed 6/10/2002

NOTE: TA approval expires 6/18/2007

12 1/4" Borehole to 810'

8 5/8" Casing @ 1203' w/ 600 SX Concrete

Set CIBP @ 3150', Tested 500# for  
30 min., passed


7 7/8" Borehole to 3719'

5 1/2" Set @ 3800' w/1800 SX Concrete

Langlie-Jal #096- API # 3002527841  
Unit N, 140' FSL, 2600' FWL, Sec. 32, T24S, R37E  
Langlie-Jal Well Drilled August 1982, TA 6/10/2002

**APPENDIX C**

**OPERATORS AND LEASES**  
**IN AREA OF REVIEW**  
**AND**  
**APPLICABLE NOTICES**  
**(INCLUDING PROPOSED PUBLIC NOTICE)**

 For Following Nomenclature Case Oil Pool

**Figure C-1: Unitized Tansill, Yates, and Seven Rivers Leases**



LAST UPDATE 08/15/2005

NOMENCLATURE FOR OCT 2005

For Following Nomenclature Case

GAS Pool

ASSOCIATED Pool

OIL Pool




Figure C-2: Unitized Langlie-Mattix, Seven Rivers, Queen and Grayburg Leases



LAST UPDATE 09/23/2005

■ NOMENCLATURE FOR OCT 2005

■ For Following Nomenclature Case

■ GAS Pool

■ ASSOCIATED Pool

■ OIL Pool




Figure C-3: Unit Status in San Andres Formation



LAST UPDATED: 01/20/2005

 NOMENCLATURE FOR OCT 2005  
 For Following Nomenclature Case

 GAS Pool  
 ASSOCIATED Pool  
 OIL Pool




Figure C-4: Unitization in the Blinebry Formation

**Table C-1: Operators and Land Status Within One Mile of Proposed SUGS AGI Well**

| Township | Range | Section | Unit | Quarter | Status | Surface Owner | Mineral Owner | Operator(s)   |
|----------|-------|---------|------|---------|--------|---------------|---------------|---|
| 24S      | 37E   | 27      | K    | NESW    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 27      | L    | NWSW    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 27      | M    | SWSW    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 27      | N    | SESW    |        | Fee           | Fee           | Betwell (1 well, TA)                                      |
| 24S      | 37E   | 28      | E    | SWNW    |        | Fee           | Fee           | Betwell (1 well, Active); BP (1, P&A)                     |
| 24S      | 37E   | 28      | F    | SENE    |        | Fee           | Fee           | Betwell (1 well, Active); Amarada Hess (1, P&A)           |
| 24S      | 37E   | 28      | G    | SWNE    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 28      | H    | SENE    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 28      | I    | NESE    |        | Fee           | Fee           | Betwell (2 wells, Active);                                |
| 24S      | 37E   | 28      | J    | NWSE    |        | Fee           | Fee           | Betwell (1, P&A); Westbrook (1, Active)                   |
| 24S      | 37E   | 28      | K    | NESW    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 28      | L    | NWSW    |        | Fee           | Fee           | McDonnold (1 well, Active); Betwell (1 well, Active)      |
| 24S      | 37E   | 28      | M    | SWSW    |        | Fee           | Fee           | McDonnold (1 well, Active); Betwell (1 well, TA)          |
| 24S      | 37E   | 28      | N    | SESW    |        | Fee           | Fee           | McDonnold (1 well, Active); Betwell (1 well, P&A)         |
| 24S      | 37E   | 28      | O    | SWSE    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 28      | P    | SESE    |        | Fee           | Fee           | Betwell (1 well, Active)                                  |
| 24S      | 37E   | 29      | G    | SWNE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 29      | H    | SENE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 29      | I    | NESE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 29      | J    | NWSE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 29      | K    | NESW    |        | Fee           | Fee           | BP (1 well, Active)                                       |
| 24S      | 37E   | 29      | L    | NWSW    |        | Fee           | Fee           | BP (1 well, Active); Fulfer Oil & Cattle (1 well, Active) |
| 24S      | 37E   | 29      | N    | SESW    |        | Fee           | Fee           | BP (1 well, Active)                                       |
| 24S      | 37E   | 29      | O    | SWSE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 29      | P    | SESE    |        | Fee           | Federal       | MCDONNOLD OPERATING INC                                   |
| 24S      | 37E   | 32      | A    | NENE    | Leased | State         | State         | Phoenix (2 wells, Active) Burleson (1 well, Active)       |
| 24S      | 37E   | 32      | B    | NWNE    | Leased | State         | State         | Phoenix (1 well, Active)                                  |
| 24S      | 37E   | 32      | C    | NENW    | Leased | State         | State         | Phoenix (1 well, Active); Westbrook (1 well, active)      |
| 24S      | 37E   | 32      | D    | NWNW    | Leased | State         | State         | Phoenix (1 well, TA), Loeb (1 well, Active)               |
| 24S      | 37E   | 32      | E    | SWNW    | Leased | State         | State         | Phoenix (1 well, P&A)                                     |
| 24S      | 37E   | 32      | F    | SENE    | Leased | State         | State         | Phoenix (1 well, Active), Loeb (1 well, Active)           |
| 24S      | 37E   | 32      | G    | SWNE    | Leased | State         | State         | BP (1 well, Active) Phoenix (1 well, Active)              |
| 24S      | 37E   | 32      | H    | SENE    | Leased | State         | State         | Phoenix (1 well, TA)                                      |
| 24S      | 37E   | 32      | I    | NESE    | Leased | State         | State         | Phoenix (2 wells, Active) Mirage (1 well, Active)         |
| 24S      | 37E   | 32      | J    | NWSE    | Leased | State         | State         | Phoenix (1 well, Active); Kelly (1 well, P&A)             |
| 24S      | 37E   | 32      | K    | NESW    | Leased | State         | State         | Phoenix (3 wells, Active)                                 |
| 24S      | 37E   | 32      | L    | NWSW    | Leased | State         | State         | Phoenix (3 wells, Active); Plantation (1 well, active)    |
| 24S      | 37E   | 32      | M    | SWSW    | Leased | State         | State         | Phoenix (2 wells, Active, 1 well TA)                      |
| 24S      | 37E   | 32      | N    | SESW    | Leased | State         | State         | Phoenix (1 well, Active, 1 well TA)                       |

**Table C-1: Operators and Land Status Within One Mile of Proposed SUGS AGI Well**

| Township | Range | Section | Unit | Quarter | Status | Surface Owner | Mineral Owner | Operator(s)   |
|----------|-------|---------|------|---------|--------|---------------|---------------|---|
| 24S      | 37E   | 32      | O    | SWSE    | Leased | State         | State         | Phoenix (1 well, Active); BP (1 well, Active)   |
| 24S      | 37E   | 32      | P    | SESE    | Leased | State         | State         | Phoenix (2 wells, Active); BP (1 well, Active)  |
| 24S      | 37E   | 33      | A    | NENE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | B    | NWNE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | C    | NENW    |        | Fee           | Fee           | Betwell (1 well, Active); Phillips (1, P&A); Cimarex (1, TA)                            |
| 24S      | 37E   | 33      | D    | NWNW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | E    | SWNW    |        | Fee           | Fee           | Betwell (1 well, Active); SUGS (1 SWD, Active), Cimarex (1, Active, Burlington (1, P&A) |
| 24S      | 37E   | 33      | F    | SENE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | G    | SWNE    |        | Fee           | Fee           | Betwell (2 wells, Active)   |
| 24S      | 37E   | 33      | H    | SENE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | I    | NESE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | J    | NWSE    |        | Fee           | Fee           | Betwell (1 well, TA); Southwest (1 well, Active)  |
| 24S      | 37E   | 33      | K    | NESW    |        | Fee           | Fee           | Betwell (1 well, Active); Inflow (1 well, Active); Burleson (1 well, P&A)               |
| 24S      | 37E   | 33      | L    | NWSW    |        | Fee           | Fee           | Betwell (1 well, TA)  |
| 24S      | 37E   | 33      | M    | SWSW    |        | Fee           | Fee           | Betwell (1 well, Active); Cimarex (1, Active)   |
| 24S      | 37E   | 33      | N    | SESW    |        | Fee           | Fee           | Betwell (2 wells, 1 Active. 1 P&A)  |
| 24S      | 37E   | 33      | O    | SWSE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 33      | P    | SESE    |        | Fee           | Fee           | Betwell (1 well, TA)  |
| 24S      | 37E   | 34      | C    | NENW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | D    | NWNW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | E    | SWNW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | F    | SENE    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | K    | NESW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | L    | NWSW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | M    | SWSW    |        | Fee           | Fee           | Betwell (1 well, Active)  |
| 24S      | 37E   | 34      | N    | SESW    |        | Fee           | Fee           | Betwell (2 wells, 1 Active. 1 P&A)  |
| 25S      | 37E   | 4       | B    | NWNE    |        | Federal       | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 4       | C    | NENW    |        | Federal       | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 4       | D    | NWNW    |        | Federal       | Federal       | HERMAN L LOEB   |
| 25S      | 37E   | 4       | E    | SWNW    |        | Fee           | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 4       | F    | SENE    |        | Fee           | Federal       | HERMAN L LOEB   |
| 25S      | 37E   | 4       | G    | SWNE    |        | Fee           | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 5       | A    | NENE    |        | Federal       | Federal       | ANDERSON PRICHARD   |
| 25S      | 37E   | 5       | B    | NWNE    |        | Federal       | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 5       | C    | NENW    |        | Federal       | Federal       | HERMAN L LOEB   |
| 25S      | 37E   | 5       | D    | NWNW    |        | Federal       | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 5       | E    | SWNW    |        | Fee           | Federal       | HERMAN L LOEB   |
| 25S      | 37E   | 5       | F    | SENE    |        | Fee           | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 5       | G    | SWNE    |        | Fee           | Federal       | PHOENIX HYDROCARBONS OPERATING CORP   |
| 25S      | 37E   | 5       | H    | SENE    |        | Fee           | Federal       | HERMAN L LOEB   |

| Table C-2: Operators Listed as Active in One-Mile Area of Review |                 |                               |               |       |       |
|--|-----------------|-------------------------------|---------------|-------|-------|
| OPERATOR   | Number of Wells | Address                       | City          | State | Zip   |
| PHOENIX HYDROCARBONS OPERATING CORP                              | 26              | P.O. Box 3638                 | Midland       | TX    | 79702 |
| BETWELL OIL & GAS CO   | 25              | P.O. Box 2577                 | Hileah        | FL    | 33012 |
| MCDONNOLD OPERATING INC  | 10              | 505 N. Big Springs, Suite 204 | Midland       | TX    | 79701 |
| BP AMERICA PRODUCTION COMPANY                                    | 4               | P.O. Box 22048                | Tulsa         | OK    | 74121 |
| CIMAREX ENERGY CO OF COLORADO                                    | 3               | 15 E. 5th St., Suite 1000     | Tulsa         | OK    | 74103 |
| HERMAN L LOEB  | 3               | RR#2, Country Club Rd.        | Lawrenceville | IL    | 62439 |
| WESTBROOK OIL CORP   | 2               | P.O. Box 2264                 | Hobbs         | NM    | 88241 |
| MIRAGE ENERGY INC  | 1               | P. O. Box 760                 | Eunice        | NM    | 88231 |
| SOUTHWEST ROYALTIES INC  | 1               | 6 Desta Dr., Suite 2100       | Midland       | TX    | 79705 |
| LEWIS B BURLESON INC   | 1               | P. O. Box 2479                | Midland       | TX    | 79702 |
| INFLOW PETROLEUM RESOURCES LP                                    | 1               | 13760 Noel Rd., Suite 104     | Dallas        | TX    | 75420 |

**PROPOSED PUBLIC NOTICE TO BE PUBLISHED IN THE  
HOBBS NEWS-SUN WHEN HEARING DATE IS SET**

CASE \_\_\_\_\_:

**Application of Southern Union Gas Services, Ltd. for approval of a combined wastewater and acid gas injection well, Lea County, New Mexico.** Applicant seeks approval to utilize its proposed Jal #3 AGI Well No. 1, to be drilled 1570 feet from the North line and 1050 feet from the West line in Section 33, Township 24 South, Range 37 East, NMPM, to inject up to 7390 barrels of acid gas and produced water per day, at a maximum pressure of 986 psi, into the San Andres Formation, at an approximate depth of 4350 feet to 5200 feet. SUGS may be contacted through its representative, Mr. Alberto Gutierrez, 500 Marquette Ave NW, Suite 1350, Albuquerque, New Mexico 87102 or (505) 842-8000. Said well is located on the SUGS Jal #3 Gas Plant approximately 3 ½ miles north of Jal, New Mexico and will replace the existing permitted disposal well at the Plant.



7006 0810 0001 2811 7781

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)                                 |         |            |                        |
|---|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>  |         |            |                        |
| MIDLAND TX 79702  |         |            |                        |
| Postage   | \$5.30  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee   | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)  | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)   | \$0.00  |            |                        |
| Total Postage & Fees  | \$10.10 | 12/18/2007 |                        |
| Sent To<br>Phoenix Hydrocarbons Oper. Co.<br>Street, Apt. No.,<br>or PO Box No. PO Box 3638<br>City, State, ZIP+4<br>Midland TX 79702 |         |            |                        |

7006 0810 0001 2811 7798

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)                    |         |            |                        |
|--|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>                             |         |            |                        |
| HIALEAH FL 33012   |         |            |                        |
| Postage  | \$7.00  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee  | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)   | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)  | \$0.00  |            |                        |
| Total Postage & Fees   | \$11.80 | 12/18/2007 |                        |
| Sent To<br>Betwell Oil & Gas<br>Street, Apt. No.,<br>or PO Box No. PO Box 2577<br>City, State, ZIP+4<br>Hialeah FL 33012 |         |            |                        |

7006 0810 0001 2811 7811

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)  |         |            |                        |
|--|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>   |         |            |                        |
| MIDLAND TX 79702   |         |            |                        |
| Postage  | \$5.30  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee  | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)   | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)  | \$0.00  |            |                        |
| Total Postage & Fees   | \$10.10 | 12/18/2007 |                        |
| Sent To<br>McDonnell Operating, Inc.<br>Street, Apt. No.,<br>or PO Box No. 505 N. Big Springs #204<br>City, State, ZIP+4<br>Midland TX 79701 |         |            |                        |

7006 0810 0001 2811 7828

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)            |         |            |                        |
|--|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>                     |         |            |                        |
| TULSA OK 74121   |         |            |                        |
| Postage  | \$6.20  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee  | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)   | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)  | \$0.00  |            |                        |
| Total Postage & Fees   | \$11.00 | 12/18/2007 |                        |
| Sent To<br>BP America<br>Street, Apt. No.,<br>or PO Box No. PO Box 22048<br>City, State, ZIP+4<br>Tulsa OK 74121 |         |            |                        |

7006 0810 0001 2811 7835

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)  |         |            |                        |
|--|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>   |         |            |                        |
| TULSA OK 74103   |         |            |                        |
| Postage  | \$6.20  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee  | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)   | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)  | \$0.00  |            |                        |
| Total Postage & Fees   | \$11.00 | 12/18/2007 |                        |
| Sent To<br>Cimarex Energy Co. of Colorado<br>Street, Apt. No.,<br>or PO Box No. 15 E. 15th St. #1000<br>City, State, ZIP+4<br>Tulsa OK 74103 |         |            |                        |

7006 0810 0001 2811 7842

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only. No Insurance Coverage Provided)                                  |         |            |                        |
|--|---------|------------|------------------------|
| For delivery information visit our website at <a href="http://www.usps.com">www.usps.com</a>   |         |            |                        |
| LAWRENCEVILLE IL 62439   |         |            |                        |
| Postage  | \$6.55  | 0129       | 05<br>Postmark<br>Here |
| Certified Fee  | \$2.65  |            |                        |
| Return Receipt Fee<br>(Endorsement Required)   | \$2.15  |            |                        |
| Restricted Delivery Fee<br>(Endorsement Required)  | \$0.00  |            |                        |
| Total Postage & Fees   | \$11.35 | 12/18/2007 |                        |
| Sent To<br>Herman L. Loeb<br>Street, Apt. No.,<br>or PO Box No. RR #2 Country Club Rd.<br>City, State, ZIP+4<br>Lawrenceville IL 62439 |         |            |                        |



7006 0810 0001 2811 7866

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information, visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

EUNICE NM 88231

|  |        |               |
|--|--------|---------------|
| Postage  | \$4.90 | 0129          |
| Certified Fee                                  | \$2.65 | 05            |
| Return Receipt Fee (Endorsement Required)      | \$2.15 | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$0.00 |               |
| Total Postage & Fees                           | \$9.70 | 12/18/2007    |

Sent To: Mingze Energy Inc.  
 Street, Apt. No., or PO Box No. PO Box 760  
 City, State, ZIP+4 Eunice NM 88231

PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7859

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information, visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

HOBBS NM 88241

|  |        |               |
|--|--------|---------------|
| Postage  | \$4.90 | 0129          |
| Certified Fee                                  | \$2.65 | 05            |
| Return Receipt Fee (Endorsement Required)      | \$2.15 | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$0.00 |               |
| Total Postage & Fees                           | \$9.70 | 12/18/2007    |

Sent To: Westbrook Oil Corp.  
 Street, Apt. No., or PO Box No. PO Box 2264  
 City, State, ZIP+4 Hobbs NM 88241

PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7873

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information, visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

MIDLAND TX 79705

|  |         |               |
|--|---------|---------------|
| Postage  | \$5.30  | 0129          |
| Certified Fee                                  | \$2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$0.00  |               |
| Total Postage & Fees                           | \$10.10 | 12/18/2007    |

Sent To: Southwestern Royalties Inc.  
 Street, Apt. No., or PO Box No. 6 Dests Dr. #2100  
 City, State, ZIP+4 Midland TX 79705

PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7880

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information, visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

MIDLAND TX 79702

|  |         |               |
|--|---------|---------------|
| Postage  | \$5.30  | 0129          |
| Certified Fee                                  | \$2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$0.00  |               |
| Total Postage & Fees                           | \$10.10 | 12/18/2007    |

Sent To: Lewis Burleson, Inc.  
 Street, Apt. No., or PO Box No. PO Box 2479  
 City, State, ZIP+4 Midland TX 79702

PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7897

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information, visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

DRASHEAR TX 75420

|  |         |               |
|--|---------|---------------|
| Postage  | \$5.30  | 0129          |
| Certified Fee                                  | \$2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$0.00  |               |
| Total Postage & Fees                           | \$10.10 | 12/18/2007    |

Sent To: Inflow Petroleum Resources  
 Street, Apt. No., or PO Box No. 13760 Noel Rd #104  
 City, State, ZIP+4 Dallas TX 75420

PS Form 3800, June 2002 See Reverse for Instructions

December 18, 2007

Phoenix Hydrocarbons Operating Corp.  
PO Box 3638  
Midland TX 79702

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Phoenix Hydrocarbons.DOC

December 18, 2007

Betwell Oil & Gas Co.  
PO Box 2577  
Hialeah FL 33012

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.


The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.

  
Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Betwell Oil and Gas.DOC

December 18, 2007

McDonnold Operating, Inc.  
505 N. Big Springs #204  
Midland TX 79701

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.


The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.

  
Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\McDonnold Operating.DOC

December 18, 2007

BP America Production Co.  
PO Box 22048  
Tulsa OK 74121

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.


The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.

  
Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\BP America.DOC



December 18, 2007

Cimarex Energy Co. of Colorado  
15 E. 5<sup>th</sup> Street #1000  
Tulsa OK 74103

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Cimarex Energy.DOC

December 18, 2007

Herman L. Loeb  
RR#2, Country Club Rd.  
Lawrenceville IL 62439

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Herman L Loeb.DOC

December 18, 2007

Westbrook Oil Corp.  
PO Box 2264  
Hobbs NM 88241

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.

  
Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Westbrook Oil.DOC

December 18, 2007

Mirage Energy, Inc.  
PO Box 760  
Eunice NM 88231

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Mirage Energy.DOC

December 18, 2007

Southwest Royalties, Inc.  
6 Desta Drive #2100  
Midland TX 79705

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Southwest Royalties.DOC



December 18, 2007

Lewis B. Burlison, Inc.  
PO Box 2479  
Midland TX 79702

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Lewis Burlison.DOC

December 18, 2007

Inflow Petroleum Resources, LP  
13760 Noel Rd. #104  
Dallas TX 75420

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Inflow Petroleum.DOC


**APPENDIX D**

**SURFACE OWNERS IN AREA OF REVIEW**  
**AND**  
**APPLICABLE NOTICES**

**TABLE D-1****SURFACE OWNERS WITHIN 1-MILE RADIUS OF JAL #3 PLANT**

1. Rebecca Joan Doom  
Jerold W. Doom  
Daniel J. Doom  
47 Doom Lane  
Jal NM 88252-9711
2. Jal Public Library Trust  
PO Box 178  
Jal NM 88252
3. C.D. Woolworth Trust  
Jal Public Library Fund  
PO Box 178  
Jal NM 88252
4. Southwestern Public Service Company  
Property Tax Department  
PO Box 840  
Denver CO 80201-0840
5. Henry H. Harrison, Jr.  
Ronald M. Harrison  
1120 Wilma  
Tyler TX 75701
6. LeaPartners L.P. FinCo  
PO Box 4967  
Houston TX 77210-4967
7. New Mexico State Lands  
State of New Mexico  
PO Box 1148  
Santa Fe NM 87504-1148
8. El Paso Natural Gas Company  
Ad Valorem Tax Department  
PO Box 1087  
Colorado Springs CO 80944

NOTE: See map for location of surface owners



**Figure D-1:**  
**Approximate Locations of Surface Land Owners Within One Mile of Proposed SUGS AGI Well**



7006 0810 0001 2811 7682

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

JAL NM 88252

|  |         |               |
|--|---------|---------------|
| Postage  | \$ 4.90 | 0129          |
| Certified Fee                                  | \$ 2.65 | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15 | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00 |               |
| Total Postage & Fees                           | \$ 9.70 | 12/18/2007    |

Sent To Doom  
 Street, Apt. No., or PO Box No. 47 Doom Lane  
 City, State, ZIP+4 Jal Nm 88252-9711  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7712

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

JAL NM 88252

|  |         |               |
|--|---------|---------------|
| Postage  | \$ 4.90 | 0129          |
| Certified Fee                                  | \$ 2.65 | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15 | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00 |               |
| Total Postage & Fees                           | \$ 9.70 | 12/18/2007    |

Sent To Jal Public Library Trust  
 Street, Apt. No., or PO Box No. PO Box 178  
 City, State, ZIP+4 Jal Nm 88252  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7736

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

DENVER CO 80201

|  |          |               |
|--|----------|---------------|
| Postage  | \$ 5.30  | 0129          |
| Certified Fee                                  | \$ 2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00  |               |
| Total Postage & Fees                           | \$ 10.10 | 12/18/2007    |

Sent To Sw Pub. Service Co; Property Tax Dept.  
 Street, Apt. No., or PO Box No. PO Box 840  
 City, State, ZIP+4 Denver CO 80201-0840  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7729

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

JAL NM 88252

|  |         |               |
|--|---------|---------------|
| Postage  | \$ 4.90 | 0129          |
| Certified Fee                                  | \$ 2.65 | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15 | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00 |               |
| Total Postage & Fees                           | \$ 9.70 | 12/18/2007    |

Sent To C.D. Woodworth Trust  
 Street, Apt. No., or PO Box No. Jal Public Library Trust  
 City, State, ZIP+4 PO Box 178  
Jal Nm 88252  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7743

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

TYLER TX 75701

|  |          |               |
|--|----------|---------------|
| Postage  | \$ 6.20  | 0129          |
| Certified Fee                                  | \$ 2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00  |               |
| Total Postage & Fees                           | \$ 11.00 | 12/18/2007    |

Sent To Harrison, Henry & Ronell  
 Street, Apt. No., or PO Box No. 1120 Wilma  
 City, State, ZIP+4 Tyler TX 75701  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7750

U.S. Postal Service  
**CERTIFIED MAIL RECEIPT**  
 (Domestic Mail Only. No Insurance Coverage Provided.)  
 For delivery information visit our website at [www.usps.com](http://www.usps.com)

HOUSTON TX 77210

|  |          |               |
|--|----------|---------------|
| Postage  | \$ 6.20  | 0129          |
| Certified Fee                                  | \$ 2.65  | 05            |
| Return Receipt Fee (Endorsement Required)      | \$ 2.15  | Postmark Here |
| Restricted Delivery Fee (Endorsement Required) | \$ 0.00  |               |
| Total Postage & Fees                           | \$ 11.00 | 12/18/2007    |

Sent To Lee Partners LP Fin Co  
 Street, Apt. No., or PO Box No. PO Box 4967  
 City, State, ZIP+4 Houston TX 77210-4967  
 PS Form 3800, June 2002 See Reverse for Instructions

7006 0810 0001 2811 7774

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only - No Insurance Coverage Provided) |         |            |               |
|--|---------|------------|---------------|
| For delivery information visit our website at www.usps.com   |         |            |               |
| COLORADO SPRINGS CO 80944  |         | L 3 E      |               |
| Postage  | \$ 4.90 | 0129       |               |
| Certified Fee  | \$2.65  | 05         | Postmark Here |
| Return Receipt Fee (Endorsement Required)  | \$2.15  |            |               |
| Restricted Delivery Fee (Endorsement Required)   | \$0.00  |            |               |
| Total Postage & Fees   | \$ 9.70 | 12/18/2007 |               |
| Sent To  |         |            |               |
| El Paso Natural Gas Co   |         |            |               |
| Street, Apt. No., or PO Box No. Ad Valorem Tax Dept.   |         |            |               |
| PO Box 1087  |         |            |               |
| City, State, ZIP+4 Colorado Springs CO 80944   |         |            |               |
| PS Form 3800, April 2002 See Reverse for Instructions  |         |            |               |

7006 0810 0001 2811 7767

| U.S. Postal Service<br>CERTIFIED MAIL RECEIPT<br>(Domestic Mail Only - No Insurance Coverage Provided) |         |            |               |
|--|---------|------------|---------------|
| For delivery information visit our website at www.usps.com   |         |            |               |
| SANTA FE NM 87504  |         | J A L 3 E  |               |
| Postage  | \$ 4.60 | 0129       |               |
| Certified Fee  | \$2.65  | 05         | Postmark Here |
| Return Receipt Fee (Endorsement Required)  | \$2.15  |            |               |
| Restricted Delivery Fee (Endorsement Required)   | \$0.00  |            |               |
| Total Postage & Fees   | \$ 9.40 | 12/18/2007 |               |
| Sent To  |         |            |               |
| Nm State Lands, State of NM  |         |            |               |
| Street, Apt. No., or PO Box No. PO Box 1148  |         |            |               |
| City, State, ZIP+4 Santa Fe NM 87504-1148  |         |            |               |
| PS Form 3800, April 2002 See Reverse for Instructions  |         |            |               |

December 18, 2007

Rebecca Joan Doom  
Jerold W. Doom  
Daniel J. Doom  
47 Doom Lane  
Jal NM 88252-9711

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Doom.DOC

December 18, 2007

Jal Public Library Trust  
PO Box 178  
Jal NM 88252

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.


The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.

  
Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Jal Public Library.DOC

December 18, 2007

C.D. Woolworth Trust  
Jal Public Library Fund.  
PO Box 178  
Jal NM 88252

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\CD Woolworth.DOC



December 18, 2007

Southwestern Public Service Co.  
Property Tax Dept.  
PO Box 840  
Denver CO 80201-0840

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\SW Public Service Co.DOC

December 18, 2007

Henry H. Harrison, Jr.  
Ronald M. Harrison  
1120 Wilma  
Tyler TX 75701

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Harrison.DOC

December 18, 2007

LeaPartners L.P. FinCo  
PO Box 4967  
Houston TX 77210-4967

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\Lea Partners.DOC

December 18, 2007

New Mexico State Lands  
State of New Mexico  
PO Box 1148  
Santa Fe NM 87504-1148

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\NM State Lands.DOC

December 18, 2007

El Paso Natural Gas Company  
Ad Valorem Tax Department  
PO Box 1087  
Colorado Springs CO 80944

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Re: **APPLICATION OF SOUTHERN UNION GAS SERVICES, LTD. FOR  
AUTHORIZATION TO INJECT, LEA COUNTY, NEW MEXICO**

Ladies and Gentlemen:

This letter is to advise you that Southern Union Gas Services, Ltd., (SUGS) has filed the enclosed application with the New Mexico Oil Conservation Division (NMOCD) seeking authorization to inject up to 7929 barrels per day of produced water and acid gas, from the Jal #3 Gas Plant, at a maximum pressure of 986 psi into the San Andres Formation between approximately 4350 and 5200 feet. SUGS' proposed Jal Plant AGI Well #1 will be drilled approximately 1570 feet from the North line and 1050 feet from the West line of Section 33, Township 24S, Range 37E, NMPM, Lea County, New Mexico, and will replace the existing Class II injection well currently permitted at the Plant.

The proposed well will be located within the Jal #3 Gas Plant, approximately 3½ miles north of Jal, New Mexico.

This application will be set for hearing before a Division Examiner at 8:15 a.m. on February 7, 2008 at the Oil Conservation Division's Santa Fe office located at 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. You are not required to attend this hearing, but as an owner of an interest that may be affected by this application, you may appear and present testimony. Failure to appear at that time and become a party of record will preclude you from challenging the matter at a later date.

Parties appearing in cases are required by Division Rule 1208.B to file a Pre-Hearing Statement with the Oil Conservation Division's Santa Fe office, four days in advance of a scheduled hearing, but at least on the Thursday preceding the hearing. This statement must include: the names of the parties and their attorneys; a concise statement of the case; the names of all witnesses the party will call to testify at the hearing; the approximate time the party will need to present its case; and identification of any procedural matters that are to be resolved prior to the hearing.

If you have questions concerning this application, you may contact Mr. Alberto Gutierrez at (505) 842-8000 or 500 Marquette Avenue NW, Suite 1350, Albuquerque, New Mexico, 87102.

Sincerely,  
Geolex, Inc.



Alberto A. Gutiérrez, C.P.G.  
Consultant to Southern Union Gas Services, Ltd.

AAG/lh

Enclosures

C:\My Shared Folders\Projects\07-013\Reports\C108Application\Notice Letters\El Paso Natural Gas.DOC



**APPENDIX E**

**DRAFT REVISED RULE 118 PLAN FOR JAL #3 AND AGI**



***DRAFT***

**H<sub>2</sub>S Contingency Plan**

**Acid Gas Injection Facility  
Jal #3 Gas Plant**

**Jal, New Mexico**

**December 2007**

# SOUTHERN UNION GAS SERVICES, LTD.

## DRAFT H<sub>2</sub>S Contingency Plan

### JAL #3 PLANT AGI WELL

#### TABLE OF CONTENTS

| Section | Description  | Page |
|---------|--|------|
| I.      | Introduction   | 1    |
| II.     | Definitions Used in This Plan  | 2    |
| III.    | Characteristics of Hydrogen Sulfide (H <sub>2</sub> S) and Sulfur Dioxide (SO <sub>2</sub> ) | 4    |
| IV.     | Emergency Response Policy and Authority  | 7    |
| V.      | Response Procedures for Unintentional (Accidental) Releases                                  | 8    |
| VI.     | Emergency Incident Management  | 10   |
| VII.    | Personnel Vehicles and Equipment   | 11   |
| VIII.   | Evacuation Procedure   | 12   |
| IX.     | Coordination with State Emergency Plans  | 13   |
| X.      | Notification of the Oil Conservation Division  | 14   |
| XI.     | Plan Activation  | 15   |
| XII.    | Training and Drills  | 16   |
| XIII.   | Emergency Contact Telephone Numbers  | 17   |
| XIV.    | Detail Information – Potentially Hazardous Areas   | 19   |
|         | Public Receptors Located Inside Radius of Exposure   | 20   |
| XV.     | Public Awareness Program   | 21   |
| XVI.    | Emergency Shutdown Equipment   | 22   |
| XVII.   | Listing of Attachments, Maps and Drawings  | 24   |
|         | 1. Worst Case Scenario   | 25   |
|         | 2. Calculated Radius of Exposure (ROE)   | 26   |
|         | 3. Site Plot Plan  | 27   |
|         | 4. Maps – Calculated Radius of Exposure  | 28   |
|         | 5. Emergency Equipment Location Plan   | 29   |
|         | 6. Plant H <sub>2</sub> S Alarm System Location Plan   | 30   |
|         | 7. Hazardous Material Incident Notification Information Checklist                            | 32   |
|         | 8. Hydrogen Sulfide Contingency Plan Simplified Flowchart.                                   | 33   |
| XIV.    | Distribution List  | 34   |



**Southern Union Gas Services, Ltd.  
Acid Gas Injection Facility  
Jal #3 Gas Plant  
Hydrogen Sulfide (H<sub>2</sub>S) Contingency Plan  
*DRAFT PLAN***

## **I. INTRODUCTION**

Southern Union Gas Services, Ltd. (SUGS) conducts its business responsibly by providing employees and any other person working or visiting, a safe work place. The Jal #3 Gas Plant Hydrogen Sulfide Contingency Plan for acid gas injection (AGI) was developed to satisfy the Oil Conservation Division Rule 118; and paragraph 7.6 of the guidelines published by the API in its publication entitled "Recommended Practices for Oil and Gas Producing and Gas Processing Plant Operations Involving Hydrogen Sulfide," RP-55.

This plan provides guidelines to assist in responding to and managing an emergency in the event of an H<sub>2</sub>S release from a pipeline or facility. The goals of this plan are to provide tools to enable an efficient, coordinated and effective response to emergencies. This plan contains written guidelines to evaluate and respond to an incident, and to prevent or minimize personal injury or loss, to avoid environmental hazards, and to reduce damage to property.

## II. DEFINITIONS USED IN THIS PLAN

|                        |  |
|------------------------|--|
| ANSI                   | The acronym "ANSI" means the American National Standards Institute.  |
| API                    | The acronym "API" means the American Petroleum Institute.  |
| Area of Exposure (AOE) | The phrase "area of exposure" means the area within a circle constructed with a point of escape at its center and the radius of exposure as its radius.  |
| ASTM                   | The acronym "ASTM" means the American Society for Testing and Materials.   |
| Dispersion Technique   | A "dispersion technique" is a mathematical representation of the physical and chemical transportation characteristics, dilution characteristics and transformation characteristics of hydrogen sulfide gas in the atmosphere.  |
| Division               | The "division" return to the N.M. Oil Conservation Division.   |
| Escape Rate            | <p>The "escape rate" is the maximum volume (Q) that is used to designate the possible rate of escape of a gaseous mixture containing hydrogen sulfide, as set forth herein.</p> <p>(a) For existing gas facilities or operations, the escape rate shall be calculated using the maximum daily rate of the gaseous mixture produced or handled or the best estimate thereof. For an existing gas well, the escape rate shall be calculated using the current daily absolute open flow rate against atmospheric pressure or the best estimate of that rate.</p> <p>(b) For new gas operations or facilities, the escape rate shall be calculated as the maximum anticipated flow rate through the system. For a new gas well, the escape rate shall be calculated using the maximum open flow rate of offset wells in the pool or reservoir, or the pool or reservoir average of maximum open flow rates.</p> <p>(c) For facilities or operations not mentioned, the escape rate shall be calculated using the actual flow of the gaseous mixture through the system or the best estimate thereof.</p> |
| GPA                    | The acronym "GPA" means the Gas Processors Association.  |
| LEPC                   | The acronym "LEPC" means the Local Emergency Planning Committee established pursuant to the Emergency Planning and Community Right-to-Know Act, 42 U.S.C. Section 11001.   |
| NACE                   | The acronym "NACE" means the National Association of Corrosion Engineers.  |
| PPM                    | The acronym "ppm" means "parts per million" by volume.   |
| PHV                    | <p>Potentially Hazardous Volume means the volume of hydrogen sulfide gas of such concentration that:</p> <p>(a) the 100-ppm radius of exposure includes any public area;</p> <p>(b) the 500-ppm radius of exposure includes any public road; or</p> <p>(c) the 100-ppm radius of exposure exceeds 3,000 feet.</p>  |
| Public Area            | A "public area" is any building or structure that is not associated with the well, facility or operation for which the radius of exposure is being calculated and that is used as a dwelling, office, place of business, church, school, hospital, or government building, or any portion of a park, city, town, village or designated school bus stop or other similar area where members of the public may reasonably be expected to be present.   |
| Public Road            | A "public road" is any federal, state, municipal or county road or highway.  |



Radius of Exposure (ROE)

The radius of exposure is that radius constructed with the point of escape as its starting point and its length calculated using the following Pasquill-Gifford derived equation, or by such other method as may be approved by the division:

- (a) For determining the 100-ppm radius of exposure:  $X = [(1.589)(\text{hydrogen sulfide concentration})(Q)]^{(0.6258)}$ , where "X" is the radius of exposure in feet, the "hydrogen sulfide concentration" is the decimal equivalent of the mole or volume fraction of hydrogen sulfide in the gaseous mixture, and "Q" is the escape rate expressed in cubic feet per day (corrected for standard conditions of 14.73 psia and 60 degrees F).
- (b) For determining the 500-ppm radius of exposure:  $X = [(0.4546)(\text{hydrogen sulfide concentration})(Q)]^{(0.6258)}$ , where "X" is the radius of exposure in feet, the "hydrogen sulfide concentration" is the decimal equivalent of the mole or volume fraction of hydrogen sulfide in the gaseous mixture, and "Q" is the escape rate expressed in cubic feet per day (corrected for standard conditions of 14.73 psia and 60 degrees F).

Regulatory Threshold

- (1) Determination of Hydrogen Sulfide Concentration.
  - (a) Each person, operator or facility shall determine the hydrogen sulfide concentration in the gaseous mixture within each of its wells, facilities or operations either by testing (using a sample from each well, facility or operation), testing a representative sample, or using process knowledge in lieu of testing. If a representative sample or process knowledge is used, the concentration derived from the representative sample or process knowledge must be reasonably representative of the hydrogen sulfide concentration within the well, facility or operation.
  - (b) The tests used to make the determination referred to in the previous subparagraph shall be conducted in accordance with applicable ASTM or GPA standards or by another method approved by the division.
  - (c) If a test was conducted prior to the effective date of this section that otherwise meets the requirements of the previous subparagraphs, new testing shall not be required.
  - (d) If any change or alteration may materially increase the concentration of hydrogen sulfide in a well, facility or operation, a new determination shall be required in accordance with this section.
- (2) Concentrations Determined to be Below 100 ppm. If the concentration of hydrogen sulfide in a given well, facility or operation is less than 100 ppm, no further actions shall be required pursuant to this section.
- (3) Concentrations Determined to be Above 100 ppm.
  - (a) If the concentration of hydrogen sulfide in a given well, facility or operation is determined to be 100 ppm or greater, then the person, operator or facility must calculate the radius of exposure and comply with applicable requirements of this section.
  - (b) If calculation of the radius of exposure reveals that a potentially hazardous volume is present, the results of the determination of the hydrogen sulfide concentration and the calculation of the radius of exposure shall be provided to the division. For a well, facility or operation existing on the effective date of this section, the determination, calculation and submission required herein shall be accomplished within 180 days of the effective date of this section; for any well, facility or operation that commences operations after the effective date of this section, the determination, calculation and submission required herein shall be accomplished before operations begin.

(4) Recalculation. The person, operator or facility shall calculate the radius of exposure if the hydrogen sulfide concentration in a well, facility or operation increases to 100 ppm or greater. The person, operator or facility shall also recalculate the radius of exposure if the actual volume fraction of hydrogen sulfide increases by a factor of twenty-five percent in a well, facility or operation that previously had a hydrogen sulfide concentration of 100 ppm or greater. If calculation or recalculation of the radius of exposure reveals that a potentially hazardous volume is present, the results shall be provided to the division within sixty (60) days.

### III. CHARACTERISTICS OF HYDROGEN SULFIDE (H<sub>2</sub>S) AND SULFUR DIOXIDE (SO<sub>2</sub>)

#### Hazards of Hydrogen Sulfide

At normal atmospheric conditions, hydrogen sulfide (H<sub>2</sub>S) is a colorless gas. It is commonly referred to by other names such as Rotten Egg Gas, Acid Gas, Sour Gas, Sewer Gas, Poison Gas and Sulfur Gas. It has a characteristic "rotten egg" smell at low concentrations. At higher concentrations, it has a sweet odor. At still higher concentrations, an odor cannot be detected at all due to olfactory nerve anesthesia. Odor must *not* be used as means of determining the concentration of H<sub>2</sub>S gas! Hydrogen sulfide can form explosive mixtures at concentrations between 4.3% and 46%, by volume. Its auto-ignition temperature is 500 degrees F (260 degrees C). When burning, its flame is practically invisible. It is denser than air (1.19 times heavier than air) and may accumulate in low places. Hydrogen sulfide gas tends to interact with high carbon steel, causing embitterment and fine fractures in metal components and piping.

H<sub>2</sub>S acts as a chemical asphyxiate, preventing the body from utilizing oxygen in the tissue. Breathing may stop after a few seconds of exposure to H<sub>2</sub>S gas in concentrations of 600-700 ppm. This produces symptoms such as panting, pallor, cramps, dilation of eye pupils and loss of speech. This is generally followed by immediate loss of consciousness. Death may occur quickly from respiratory paralysis and cardiac arrest. The table below illustrates the physical effects of hydrogen sulfide on a healthy adult.

**Table 1 Effect of exposure to Hydrogen Sulfide Gas on a Healthy Adult**

| Concentration |             |                            | Physical Effects  |
|---------------|-------------|----------------------------|---|
| percent (%)   | ppm         | grains per ft <sup>3</sup> |   |
| 0.001         | 10          | 0.65                       | Obvious and unpleasant odor. Safe for 8 hours exposure.   |
| 0.01          | 100         | 6.48                       | Kills smell in 3 to 15 minutes; may sting eyes and throat.  |
| 0.02          | 200         | 12.96                      | Kills smell shortly; stings eyes and throat.  |
| 0.05          | 500         | 32.96                      | Dizziness; breathing ceases in a few minutes; artificial respiration / oxygen must be given promptly. |
| 0.07          | <b>700</b>  | 45.36                      | <b>Unconscious quickly; death will result if not rescued promptly.</b>                                |
| 0.10          | <b>1000</b> | 64.80                      | <b>Unconscious at once; followed by death within minutes.</b>   |

### Properties of H<sub>2</sub>S

|                        |   |
|------------------------|---|
| COLOR                  | Colorless.  |
| ODOR                   | Very offensive, commonly referred to as the odor of rotten eggs.    |
| VAPOR DENSITY          | 1.189 (Air=1.0) H <sub>2</sub> S is heavier than air.               |
| BOILING POINT          | -76 degrees F (-24 degrees C).                                      |
| EXPLOSIVE LIMITS       | 4.3 to 46% by volume in air.  |
| IGNITION TEMPERATURE   | 500 degrees F (260 degrees C).                                      |
| WATER SOLUBLE          | Yes (4 volumes gas in 1 volume water at 32 degrees F (0 degrees C). |
| FLAMMABILITY CORROSIVE | Forms explosive mixtures with air or oxygen.                        |

### Toxicity Table – H<sub>2</sub>S

|                                    |   |
|------------------------------------|---|
| 1 ppm = .0001%<br>(1/10,000 of 1%) | Can smell (rotten egg odor).  |
| 10 ppm = .001%<br>(1/1000 OF 1%)   | Allowable for 8 hours exposure. (PEL & TLV)   |
| 100 ppm = .01%<br>(1/100 of 1%)    | Kills smell in 3-15 minutes. May burn eyes and throat. Considered to be IDLH atmosphere (Immediately Dangerous to Life and Health).                 |
| 200 ppm = .03%<br>(2/100 of 1%)    | Kills smell rapidly. Burns eyes and throat.   |
| 500 ppm = .05%<br>(5/100 of 1%)    | Loses sense of reasoning and balance. Respiratory disturbances in 2-15 minutes. Needs prompt artificial resuscitation.                              |
| 700 ppm = .07%<br>(7/100 of 1%)    | Will become unconscious quickly. Breathing will stop and death will result if not rescued promptly. Immediate artificial resuscitation is required. |
| 1000 ppm = .1%<br>(1/10 OF 1%)     | Unconscious at once. PERMANENT BRAIN DAMAGE MAY RESULT UNLESS RESCUED PROMPTLY.   |
|                                    | ppm=parts of gas per million parts of air by volume.<br>1% = 10,000 ppm.  |

## Properties of Sulfur Dioxide SO<sub>2</sub>

| Sulfur Dioxide - SO <sub>2</sub> | Physical and Chemical Properties   |
|----------------------------------|--|
| Chemical Formula                 | SO <sub>2</sub>  |
| Molecular Weight                 | 64   |
| Boiling Point                    | 14 degrees Fahrenheit  |
| Non-Combustible                  | Produced by burning of H <sub>2</sub> S Gas  |
| Vapor Pressure                   | >1 atm @ 68 degrees Fahrenheit   |
| Melting Point                    | -104 degrees Fahrenheit  |
| Specific Gravity                 | Heavier than air, 2.26 degrees gravity   |
| Colorless gas                    | SO <sub>2</sub> is colorless gas, very irritating to the eyes and lungs  |
| Odor                             | Pungent odor and can cause injury or death to persons exposed to it  |
| Reactions                        | Reacts with water or steam to produce toxic and corrosive gases  |
| Hazards of Sulfur Dioxide        |  |
| Toxicity                         | The physiological effects on humans when inhalation of SO <sub>2</sub> occurs, varies at different levels of concentration and may be as follows |
| Concentrations SO <sub>2</sub>   | Physiological Effects SO <sub>2</sub>  |
| 0.3-1 ppm                        | Detection level – pungent odor   |
| 2 ppm                            | Threshold Limit Value (TLV)<br>Time Weighted Average (TWA)   |
| 5 ppm                            | 15 minute Short Term Exposure Limit (STEL) permitted by OSHA   |
| 6 – 12 ppm                       | Irritation of the throat and nose  |
| 20 ppm                           | Eye irritation   |
| 100 ppm                          | Immediately Dangerous to Life or Health (IDLH) set by NIOSH  |



#### IV. EMERGENCY RESPONSE POLICY AND AUTHORITY

It is the policy of SUGS to take the necessary actions required to safeguard SUGS personnel and the public from emergency incidents. Such emergency incidents may include fires, hazardous materials releases, and incidents resulting from natural hazards such as tornadoes.

In the event of an emergency incident, SUGS personnel will take prompt action within their immediate work area to ensure that all appropriate SUGS personnel, corporate personnel, and the public are alerted or notified that an emergency incident exists.

Whenever possible, SUGS personnel will take immediate action to limit the effects of the emergency. Four objectives will be considered when developing an appropriate emergency response. These objectives are:

- Life safety.
- Environmental protection.
- Protection of company and public property.
- Preventing interruption of business and public services such as highway access, water, and utilities.

While all four of the above objectives are important, life safety will always remain the first and highest priority.

All SUGS personnel have the responsibility, if necessary, to immediately alert other SUGS personnel that an emergency condition exists and to take appropriate action to protect life, property, and the environment. All emergency response actions by SUGS personnel are voluntary. Emergency response actions taken by individuals should be within the limitations of their training, experience, and physical abilities. At no time will Jal #3 Gas Plant personnel assume an unreasonable risk during an emergency response. An unreasonable risk exists when:

- The task exceeds the physical abilities of the individual.
- The individual is not properly trained to complete the task.
- The individual does not have adequate experience to complete the task.

## V. RESPONSE PROCEDURES FOR UNINTENTIONAL (ACCIDENTAL) RELEASES

If an H<sub>2</sub>S leak is detected as a result of an accidental release, the following emergency plan of action should be put into effect to adequately ensure the safety of SUGS employees, contractors and the public. These response sequences should be altered to fit the prevailing situation and event/site-specific requirements.

1. Upon detecting a leak, immediately move away from the source and attempt to get out of the affected area by moving upwind, or cross wind if travel upwind is not possible.
2. Alert other personnel in the area. Assist personnel in distress if this can be done without endangering yourself. Proceed to the designated emergency assembly area.
3. If injury or death has occurred, immediately call emergency services (911).
4. If possible, take immediate measures to control present or potential discharge and to eliminate possible ignition sources.
5. Notify the supervisory foreman. Upon arriving at the scene, the supervisor should formally assume the role of the Incident Commander (IC). Until relieved by the supervisor, the senior employee having initially discovered the leak should fill the role of IC.
6. The IC will assess the situation and direct further actions to be taken. If assistance is required from law enforcement, safety or medical agencies, consult the emergency services telephone listing under Section XIII. The Division Operations Vice-President or his designee should also be notified.
7. If the IC deems it necessary, ensure that steps are taken to stop traffic through the area, most importantly, highway traffic. Roadblocks must be set up at the 10-ppm H<sub>2</sub>S boundary. The H<sub>2</sub>S boundary shall be delineated by using a calibrated H<sub>2</sub>S monitor. Call emergency services (911) for assistance in quarantining the area, if needed. Refer to maps in Section XVII for highway and pipeline locations.
8. Initiate evacuation of employees or any nearby residents, if deemed necessary. Coordinate with emergency services.
9. Personnel equipped with self-contained breathing apparatus (SCBA) and portable H<sub>2</sub>S monitoring equipment will determine the cause and extent of the leak. Personnel should enter the area from upwind of the site. If a reading of 10 ppm or higher of H<sub>2</sub>S is obtained, then backup personnel equipped with SCBA will also be required.
10. No one will be intentionally exposed to H<sub>2</sub>S concentrations in excess of 10 ppm without proper Personal Protection Equipment (PPE), IC authorization and backup personnel.
11. If possible, de-energize all sources of ignition, using lockout/tagout procedures.
12. If possible, perform shutdown on appropriate equipment and systems.

13. Trained personnel will continuously monitor H<sub>2</sub>S concentrations, wind direction and area of exposure and will advise public safety and emergency personnel on current conditions.
14. Protective measures shall be maintained until the threat of injury from H<sub>2</sub>S poisoning has been eliminated. The area must be checked with monitoring equipment and cleared below 10 ppm before allowing entry without proper PPE.
15. Notify the Division Health & Safety Manager. See Section XIII Assistance will be provided to ensure all proper notifications and reporting requirements are made to local, state and federal agencies.
16. As soon as possible, **but no more than one hour after plan activation**, notify the New Mexico Oil Conservation Division – Lea County (See Section XIII). At a minimum, the following information will be needed:
  - The company name.
  - Facility name.
  - Your name and telephone number for them to contact you.
  - The location and source of the discharge.
  - A description of the area affected by the discharge, the probable concentration of H<sub>2</sub>S in the region and the wind direction/velocity.
  - If necessary, request additional assistance from the agency.

## VI. EMERGENCY INCIDENT MANAGEMENT

Emergency incident management will follow the Incident Command System (ICS) as described by the Federal Emergency Management Act (FEMA). The intent of using ICS for all emergency incidents provides automatic continuity with outside agencies and assists in establishing a "unified command" of the incident. SUGS provides instruction and training on the ICS, which is beyond the scope of this contingency plan. However a brief overview of the system is provided below.

The Incident Command System (ICS) utilizes a flexible, modular approach to organizing resources to effectively respond to emergency events. FEMA suggests that the basic Incident Command System has five functional areas:

- Command;
- Operations;
- Planning;
- Logistics; and,
- Finance.

However, for incidents such as those described in this plan, it seems more likely that the basic Incident Command System would be comprised of: 1) Command; 2) Operations Chief; and, 3) Safety Officer. Larger incidents may require additional positions such as Public Information Officer, Logistics Chief, Planning Chief, Finance Chief, Staging Manager, Medical Group Supervisor and Environmental Group Supervisor. The exact number and combination of positions will vary depending upon the type, size and duration of the incident.

In every incident, command must first be established. The first person to discover the problem is, by default, the Incident Commander (IC) until this responsibility is transferred to someone else. This responsibility should be formally transferred to the Facility/Field Supervisor as soon as practical. Who is acting as the IC should be clear and apparent at all times.

The Incident Commander (IC) is responsible for the overall management of the incident. Where the IC does not delegate or assign a position, the IC retains that responsibility. The IC should be careful to have no more than 5 to 8 people reporting directly to him. The IC establishes the strategy and goals for the incident and is ultimately responsible for the safety and success of the response activities.

An Operations Chief (OPS) is responsible for implementing the strategy to accomplish the goals defined by the IC. OPS directs all tactical operations, oversees response personnel and may assist the IC in the development of the action plan.

The Safety Officer is assigned by and reports directly to the IC. This position is responsible for identifying hazardous or unsafe situations, and developing measures necessary to assure the safety of response personnel and any victims of the incident. He/she should ensure that any personnel responding to the incident are using the proper PPE and have adequate training. The Safety Officer has the authority and responsibility to terminate or suspend operations that is believed to be unsafe or will place people in imminent danger.

## **VII. PERSONNEL VEHICLES AND EQUIPMENT**

Plant personnel are equipped with personal H<sub>2</sub>S monitors and portable gas detection devices.

The plant has a fully equipped mobile breathing air system with work units. Also, there are self contained breathing apparatus (SCBA's) located strategically throughout the facility.

An Emergency Response Kit and Road Block Kits are located at the egress stations for easy access if the facility is evacuated.

Personnel have cellular phones for communication, as well as two-way radios for inter-company communication.

All SUGS personnel are equipped with personal H<sub>2</sub>S monitors and portable gas detection devices are available.

Communications to SUGS field personnel is via mobile cellular telephones or two-way radios.

Each SUGS field truck is also equipped with a fire extinguisher in order to enable assistance as needed.

Company vehicles are equipped with two-way radios, roadblock kits and mobile phones.

## VIII. EVACUATION PROCEDURE

Evacuation may become necessary to protect personnel and the public from hazards associated with an incident. Orderly evacuation is essential to protect the general public as well as SUGS personnel and property.

SUGS personnel have reviewed the affected area for this plan and have determined the safe evacuation routes and assembly areas to reduce confusion if evacuation becomes necessary. The SUGS Facility Operator may assign employees to direct evacuation and account for personnel during emergencies. (See Section XIV for evacuation routes).

Designated Assembly Areas shall be at a safe distance from the incident in an appropriate direction (upwind, upstream, and upgrade). If the Assembly Areas do not provide adequate shelter, transportation to a central shelter should be arranged after all personnel are accounted for. As the incident progresses, the IC must continuously evaluate the adequacy of the assembly area and necessity of the shelter.

SUGS personnel evacuating their work areas should evacuate the facility and initiate the plant ESD system, and proceed to the Designated Assembly Area. Facility personnel will account for all personnel, ensure the evacuated area is secured and report the status of the evacuation to the IC. Evacuated personnel shall remain at the assembly area or shelter until directed otherwise by the IC.

- Local law enforcement and/or emergency management authority must be notified in conjunction with any community evacuation or public protective measures initiated.
- Emergency Response Plan initiated.
- Assess the scene; protect yourself.
- Summon EMS to the scene; provide information on the nature and number of injuries.
- If trained, provide First Aid/CPR as necessary, until EMS arrives at the scene; injured personnel should not be moved unless the situation is life threatening.
- Evacuate unnecessary personnel from the area.
- Establish a secure perimeter around the area to prevent unauthorized entry.
- Initiate the site security plan.
- Notify Facility Supervisor and make appropriate notifications to local Fire and EMS.
- Make other internal management contact as appropriate.

In case of a fatality:

- Do not move the victim.
- Do not release name of victim(s).
- Contact local law enforcement.
- Contact local medical examiner.
- Preserve the accident site.
- Restrict all unauthorized communications concerning the incident.

Make appropriate government agency notification and conduct post-incident activities.



**IX. COORDINATION WITH STATE EMERGENCY PLANS**

The Hydrogen Sulfide Contingency Plan as described will be coordinated with the New Mexico Oil Conservation Division (NMOCD) and with the New Mexico State Police consistent with the New Mexico Hazardous Materials Emergency Response Plan (HMER). A copy of this plan will be submitted to the New Mexico State Police and Local Emergency Planning Committee for Lea County.

**LEPC**  
**505-396-8521**

**NEW MEXICO STATE POLICE**  
**505-392-5588**

**LEA COUNTY SHERIFF'S OFFICE**  
**505-396-3611**

**STATE EMERGENCY RESPONSE COMMISSION**  
**(SERC)**  
**(505) 393-6161**

**NEW MEXICO OFFICE OF EMERGENCY MANAGEMENT**  
**(505) 476-9600**

**X. NOTIFICATION OF THE OIL CONSERVATION DIVISION**

The person, operator or facility shall notify the New Mexico Oil Conservation Division (NMOCD) upon a release of hydrogen sulfide requiring activation of the Hydrogen Sulfide Contingency Plan as soon as possible, but no more than one hour after plan activation, recognizing that a prompt response should supercede notification. The person, operator or facility shall submit a full report of the incident to the NMOCD on Form C-141 no later than fifteen (15) days following the release.


**OIL CONSERVATION DIVISION  
LEA COUNTY**

505-393-6161

## XI. PLAN ACTIVATION

The Hydrogen Sulfide Contingency Plan shall be activated when the Incident Commander (IC) believes that a release creates a concentration of hydrogen sulfide that exceeds or is likely to exceed the following activation levels:

- 100 ppm in any defined public area;
- 500 ppm at any public road; or
- 100 ppm at a distance greater than 3000 feet from the site of the release.



## **XII. TRAINING AND DRILLS**

Training for all affected SUGS personnel will be conducted prior to completion of the project and introduction of product. Training will then be given as needed for any personnel who may later be affected by this project.

This training will include:

- Training on the responsibilities and duties of essential SUGS personnel.
- On-site or classroom tabletop drills which simulate a release or other situation affecting the facility.
- Annual H<sub>2</sub>S Hazard Training.

Initial training is to take place upon employment with the company and refresher training is to be conducted annually – or sooner if there is a change in the plan or the need for training is determined.

All training will be documented and training records will be maintained on file at the Monahans EHS office.

All drills will be evaluated and documented including any recommendations resulting from findings. Recommendations will be assigned to SUGS personnel for completion by an established date. Upon completion, the action plan will be documented and records will be filed at the Jal #3 Gas Plant.

*Only trained and certified personnel from responding agencies will participate in any rescue exercise.*

The Hydrogen Sulfide Contingency Plan will also provide for training of noted residents in this plan as appropriate on the proper protective measures to be taken in the event of a release, and shall provide for briefing of public officials on issues such as evacuation or shelter-in-place plans. Literature will be passed out to the noted residents with emergency numbers to be utilized in the event of an incident associated with this facility or any SUGS equipment and/or piping.

### **XIII. EMERGENCY SUGS CONTACT PHONE NUMBERS**

Use the following phone number in the event of a catastrophic release and/or emergency situation at the Jal #3 Acid Gas Injection facility.

#### **Telephone Numbers of SUGS Personnel**

**24 HOUR TELEPHONE NUMBER 800-435-1679**

Then Call:

| JAL #3 PLANT   |                       | (505) 395-2068 |                |
|----------------|-----------------------|----------------|----------------|
| NAME           | TITLE                 | HOME           | CELLULAR       |
| Dwight Bennett | Plant Manager         | (505) 395-2471 | (505) 390-6033 |
| I. A. Olivas   | Operations Supervisor | (505) 395-2445 | (505) 390-6034 |
| Bobby Tuck     | Technical Supervisor  | (432) 586-6144 | (505) 631-7741 |
| Clarence Rasco | Maintenance Foreman   | (432) 523-7116 | (505) 390-6032 |

| FORT WORTH     |                   | (817) 302-9400 |                |                |
|----------------|-------------------|----------------|----------------|----------------|
| NAME           | TITLE             | OFFICE         | HOME           | CELLULAR       |
| Bruce Williams | VP Gas Operations | (817) 302-9421 | (817) 441-9613 | (817) 946-0761 |
| Bob Milam      | VP Engineering    | (817) 302-9408 |                | (432) 661-5958 |
| Herb Harless   | Dir. EH&S         | (817) 302-9425 | (817) 885-8779 | (817) 692-9374 |
| Robert Gawlik  | Mgr. EH&S         | (817) 302-9426 | (817) 448-9880 | (817) 692-9366 |

| West Texas Area Safety |                   |                |                |                |
|------------------------|-------------------|----------------|----------------|----------------|
| NAME                   | TITLE             | OFFICE         | HOME           | CELLULAR       |
| John Crossman          | Regulatory Comp.  | (432) 943-1115 | (432) 943-7482 | (432) 940-5074 |
| Rose Slade             | EHS Coordinator   | (432) 943-1116 | (432) 943-7714 | (432) 940-5147 |
| Tony Savoie            | Envir. Supervisor | (505) 395-2116 | (505) 395-3336 | (505) 631-9376 |
| Jim Payne              | EHS Coordinator   | (432) 943-1155 | (432) 586-3501 | (432) 940-5123 |
| Mike Magee             | PSM Coordinator   | (432) 943-1160 |                | (432) 208-0753 |

| WEST TEXAS AREA OFFICE - MIDLAND |                   | (432) 570-6031 |                |                |
|----------------------------------|-------------------|----------------|----------------|----------------|
| NAME                             | TITLE             | OFFICE         | HOME           | CELLULAR       |
| Curtis Clark                     | Mgr Engineering   | (432) 571-4926 | (432) 520-5333 | (432) 553-8129 |
| Ross Boyd                        | Asset Op. Engr.   | (432) 571-4927 | (432) 687-5717 | (432) 553-7280 |
| Bill Webb                        | Mgr. Plant Op.    | (432) 571-4939 | (432) 684-4430 | (432) 770-4204 |
| Mary Valencia                    | Environmental Sup | (432) 571-4925 | (432) 687-1464 | (432) 940-1939 |

*Remember – Our FOUR Objectives in an Emergency Are:*

1. Life Safety.
2. Environmental Protection.
3. Protection of Company and Public Property.
4. Preventing interruption of business and public services such as Highway Access, Water & Utilities.

**Life Safety Will Always Remain the First and Highest Priority!**



In case of an emergency at the Jal #3 Gas Plant requiring assistance for fire, ambulance, medical authorities or HazMat issues – immediately call:

**911**

**Responder Emergency Numbers:**

| Facility           | Jal, New Mexico     |
|--------------------|---------------------|
| Fire Department    | 911 or 505-395-2221 |
| Medical Facility   | 505-395-2221        |
| State Police       | 505-392-5588        |
| Sheriff Department | 505-395-2121        |
| LEPC               | 505-396-8521        |

**Telephone Numbers of Public Agencies**

|  |              |
|--|--------------|
| Oil Conservation Division – Lea County     | 505-393-6161 |
| State Emergency Response Commission (SERC) | 505-393-6161 |
| New Mexico Office of Emergency Management  | 505-476-9600 |
| Bureau of Land Management - Hobbs          | 505-392-8736 |

**Telephone Numbers of Emergency Resources**

| Organization                          | Phone Number |
|---------------------------------------|--------------|
| <b>Spill – Cleanup Contractors</b>    |              |
| Contact Tony Savoie – SUGS            | 505-631-9376 |
| Ocotillo Environmental – Hobbs NM     | 505-393-6371 |
| Ecological Environmental – Midland TX | 800-375-0100 |
| GET #'S FROM JAL 3 DP                 |              |
| <b>Heavy Equipment Contractors</b>    |              |
| Merryman Construction – Jal NM        | 505-395-2592 |
| B&H Construction – Eunice NM          | 505-394-2588 |
|                                       |              |
|                                       |              |
| <b>Transportation Services</b>        |              |
| FULCO – Jal NM                        | 505-395-2650 |
| Riverside Transportation – Jal NM     | 505-395-3504 |
|                                       |              |
| <b>Other</b>                          |              |
|                                       |              |
|                                       |              |
|                                       |              |
|                                       |              |
|                                       |              |

#### **XIV. DETAIL INFORMATION - POTENTIALLY HAZARDOUS AREAS**

##### **Jal #3 Gas Plant and Jal #3 AGI #1**

###### **DRIVING DIRECTIONS:**

From Hobbs: Take Highway 18 South towards Jal 35 miles to Sid Richardson Road, turn east and go 1 mile to entrance to Jal #3 plant

Location: Section 33 T 24 S, R 37 E, Lea County, NM

Latitude: 32.1738 N

Longitude: 103.1740 W

###### **EVACUATION ROUTE:**

At all times note the wind direction before evacuating procedures begin. The primary evacuation assembly area will be the south west entrance to the plant off of Sid Richardson Road.

Evacuation for all persons inside of the AGI Facility fences would be west to the west side dirt road and then south to the plant entrance (wind conditions permitting) group assembly area #1 to account for all employees including any visitors. Visitor sign in sheet shall be used to account for all visitors.

###### **ROAD BLOCKS:**

In emergencies involving a large acid gas pipeline leak near the Jal #3 Gas Plant, US Highway 18 will be blocked at approximately one mile north and south of the plant.

###### **COMMAND POST:**

The Command Post will be established at one of the roadblock locations. The site will be dependent of the wind direction.

The Incident Commander, after arriving at the scene, has the authority to assess the situation and determine the severity level of the incident. The Incident Commander may determine that the Contingency Plan as written cannot be activated effectively. The Emergency Response Plan may then be activated depending on the Incident Commander's evaluation of the situation.

###### **PUBLIC RECEPTORS LOCATED INSIDE RADIUS OF EXPOSURE (ROE):**

There are no public receptors located within either the 500ppm or the 100ppm radii of exposure. The radii as calculated in Attachment 2 and shown in Attachments 4a and 4b are contained within the plant or adjacent unoccupied land.

## **XV. SUGS PUBLIC AWARENESS PROGRAM**

SUGS participates in an extensive annual Public Awareness Program and Damage Prevention Program.

SUGS installs pipeline markers and signs at all facilities and road crossings to identify our underground pipelines and maintains these markers on an annual schedule.

## **XVI. EMERGENCY SHUTDOWN EQUIPMENT**

SUGS has an installed automatic and manually activated emergency shutdown system (ESD) at the Acid Gas Injection Facility at the Jal #3 Gas Plant. The plant operator and/or Incident Commander (IC) may use these systems to shutdown and isolate the equipment in the facility. This is a fail safe system that will shut valves and equipment if any portion of the system fails. The Acid Gas Injection system will be normally controlled from the Jal #3 Plant Control Room and shutdown of equipment and ESD valves at the well-site may be accomplished from this system as well as at the well-site.

When activated the ESD shuts an automatic valve on the inlet acid gas feed stream, shuts an automatic valve on the compressed acid gas to the acid gas injection well, and sends a signal to the wellhead panel to shut down automatic valves on the wellhead. The major equipment is shutdown. The specific major equipment items at injection well site that are shutdown in an ESD include the acid gas compressors and associated coolers and pumps. The fuel gas, which is used for flare fuel and purge gas is left on-line; however an automatic valve is provided in this line at the well-site that can be actuated separately in the control system to close this valve.

In the wellhead control panel there is a separate shutdown for the subsurface safety valve (SSSV). The SSSV can be closed if required. The SSSV will close automatically upon detection of high pressure in the wellhead piping. The SSSV will shut if there is a fault in the wellhead control panel.

In addition to these systems the well-site facility contains portable fire extinguishers that may be used in an emergency. The well-site facility also has air packs used for escape or rescue located throughout the facility at key locations. The facility also has a breathing air system at the compressor units consisting of air bottles, tubing, and a manifold to connect 5 minute air packs. These are primarily used when performing maintenance work on the compressor units; however, they can also be used during an emergency if required. Refer to the "Emergency Equipment Location Plan" (See Attachment #5) for the location of this equipment.

SUGS has also installed hydrogen sulfide detectors throughout the Well-Site Facility in key locations to detect possible leaks. Upon detection of hydrogen sulfide at 10 ppm levels at any detector a visible beacon is activated at that detector and an alarm is sounded. Upon detection of hydrogen sulfide at 50 ppm levels at any detector, an evacuation alarm is sounded throughout the Facility. All personnel proceed immediately to a designated area near the Facility office outside the fence (or alternate area south of the plant depending on wind direction and their location in the well-site facility).

In addition to sounding evacuation alarm sirens, at concentrations of 50 ppm in the acid gas compressor area the acid gas compressor is shutdown and isolation valves upstream and downstream of the unit are closed, including the wellhead automatic wing valve. Refer to the "Plant H<sub>2</sub>S Alarm System Location Plan" for the locations of the hydrogen sulfide detectors.

For emergency equipment and shutdown descriptions within the existing Jal #3 Plant refer to the separate contingency plan for the plant. There will be additional hydrogen sulfide detectors installed at the plant site around the new acid gas compressor and near the new ESD valves.

Note that the Acid Gas Flare will flare large volumes at the Well-Site only under extreme emergencies in the event the compressor is over-pressured and a Process Safety Valve (PSV) relieves to the acid gas flare. During other shutdowns of the well-site compression or the injection well the acid gas will be flared at the Jal #3 Plant.

### Emergency Equipment on site at the Acid Gas Injection Facility

| Quantity | Description   |
|----------|---|
| 9        | Ansul 30# Fire Extinguishers  |
| 6        | 5# ABC Fire Extinguishers   |
| 5        | Wind Socks  |
| 1        | 150# Fire Extinguisher – Wheeled Units  |
| 22       | Fixed Ambient H <sub>2</sub> S Monitors   |
| 10       | SCBA – 30-Minute Breathing Air Packs  |
| 4        | First Aid Kits  |
| 2        | Fire Blankets (wool)  |
| 2        | Eye Wash Stations   |
| 1        | Emergency Showers   |
| 2        | PPE Boxes   |
|          | <i>NOTE: This equipment is separate from the existing plant emergency equipment</i> |

## **XVII. ATTACHMENTS, MAPS AND DRAWINGS**

### **LISTING OF ATTACHMENTS, MAP AND DRAWINGS**

1. Worst Case Scenario
2. Calculated Radius of Exposure (ROE)
3. Site Plot Plan
4. Maps Showing Calculated Radii of Exposure
5. Draft Emergency Equipment Location Plan
6. Draft Plant H<sub>2</sub>S Alarm System Location Plan
7. Hazardous Material Incident Notification Information Checklist
8. Contingency Plan Simplified Flowchart



## ATTACHMENT 1 Worst Case Scenario for Acid Gas Injection at the Jal #3 Gas Plant

The basis for worst case calculations is 20% hydrogen sulfide in the acid gas from the Jal #3 Gas Plant, which is at typical maximum concentration observed at the plant.

Note that essentially all of the hydrogen sulfide in the plant feed gas is separated from the processed gas and becomes the acid gas stream. Therefore, the worst case calculated radius of exposure will be the same for the Acid Gas Injection Facility and for the Jal #3 Gas Plant as a whole. Furthermore, the worst case scenario is being assumed in the standard calculations since it would be a rupture that results in release of all of the hydrogen sulfide from the acid gas. Calculations using the Pasquill-Gifford equations as described in OCD Rule 118 are presented on the following page (Attachment 2). Also included below is a diagrammatic representation of the AGI system (Figure 2b from C-108 Application).




Figure 2b Schematic of SUGS Jal #3 Gas Plant Acid Gas Injection System Components

# ATTACHMENT 2 STANDARD CALCULATIONS OF RADIUS OF EXPOSURE

Southern Union Gas Services, Jai #3 Plant H<sub>2</sub>S Radius of Exposure Calculations

## Calculate Volume of Release

| Pipe Section | Length of Pipe<br>ft | diameter of<br>pipe<br>ft | volume of<br>pipe<br>ft <sup>3</sup> | Pipe Section<br>Pressure<br>psi | Pipe Section<br>Temperature<br>F |
|--------------|----------------------|---------------------------|--------------------------------------|---------------------------------|----------------------------------|
| 1            | 1000                 |                           | 1 785.398163                         | 5                               | 83.86                            |
| 2            | 150                  |                           | 1 117.809725                         | 5                               | 112.00                           |
| 3a           | 125                  | 0.25                      | 6.13592315                           | 1600                            | 112.00                           |
| 3b           | 300                  | 0.29166667                | 20.0440156                           | 980                             | 112.00                           |

Pipe length, diameter, pressure and temperature are actual values

## Standardization

Per OCD, release parameters must be standardized to 60F and 14.7 psi

|                 |             |            |                     |   |  |
|-----------------|-------------|------------|---------------------|---|--|
| Elevation       | 3260        | 3260       | ft                  |   |  |
| concentration   | 100         | 500        | ppm                 |   | Concentrations of concern selected by OCD                |
| corrected       | 124971.4    | 624856.9   | µg/m <sup>3</sup>   | x | Concentration corrected for Elevation, using NMED method |
| χ               | 0.124971389 | 0.62485695 | g/m <sup>3</sup>    | χ | 1x10 <sup>6</sup> µg/g                                   |
| Specific Volume | 11.136      | 11.136     | ft <sup>3</sup> /lb |   | Specific Volume of H <sub>2</sub> S                      |

| Pipe Section | P1<br>psi | P2<br>psi | V1<br>ft <sup>3</sup> | T1<br>K | T2<br>K | Standardized<br>Pipe Release<br>Volume<br>V2<br>ft <sup>3</sup> | H2S<br>Concentration<br>% | H2S Release<br>Volume<br>ft <sup>3</sup> | H2S Release<br>Mass<br>lb | Time of<br>Release<br>min | Release<br>Concentration<br>Q<br>g/s |
|--------------|-----------|-----------|-----------------------|---------|---------|---|---------------------------|--|---------------------------|---------------------------|--------------------------------------|
| 1            | 19.7      | 14.7      | 785.3981634           | 302.1   | 288.7   | 1005.81674  | 20%                       | 201.1633478                              | 18.06423739               | 10                        | 13.65656347                          |
| 2            | 19.7      | 14.7      | 117.8097245           | 255.5   | 288.7   | 178.380813  | 20%                       | 35.67816268                              | 3.203678402               | 10                        | 2.421980872                          |
| 3a           | 1614.7    | 14.7      | 6.135923152           | 255.5   | 288.7   | 761.504599  | 20%                       | 152.3009197                              | 13.67644753               | 10                        | 10.33939434                          |
| 3b           | 994.7     | 14.7      | 20.04401563           | 255.5   | 288.7   | 1532.41934  | 20%                       | 308.4838677                              | 27.52189904               | 10                        | 20.80655567                          |

## Notes

- Pipeline Volume calculated using ideal gas law, (P1V1)/T1 = (P2V2)/T2, where:  
P1 = Actual pressure + standard pressure (14.7 psi)  
P2 = Standard pressure (14.7 psi)  
V1 = Volume of the pipe section to be released  
V2 = Release volume at standard conditions - equation is solved for this  
T1 = Temperature of gas in pipeline (in Kelvin)  
T2 = Standard Temperature (60F, expressed in Kelvin = 288.7K)  
°C = (°F - 32) x 5/9  
K = C + 273.3
- H2S Release volume is H2S Concentration \* Standardized Pipe Release Volume
- H2S Release Mass is H2S Release Volume \* Specific Volume of H2S
- Time of Release is 10 minutes, as a conservative estimate
- Release Concentration, Q, is H2S Mass (lb) \*.453 .6 g/lb / (10 min \* 60 sec/min)

## Distance Calculation

Calculated radius of impact is estimated from equations found in the Workbook of Atmospheric Dispersion Estimates (D. Bruce Turner).

- σ<sub>y</sub> σ<sub>z</sub> = Q / π u χ<sub>loc</sub> D. Bruce Turner, Workbook of Atmospheric Dispersion Estimates, Equation 2.6  
u = Windspeed, conservative estimate  
Q = Pollutant emission rate  
χ<sub>loc</sub> = Level-of-Concern concentration  
x = distance from source Based on the above calculation, x is interpolated from Table 2.5 (assuming Stability Class F), for the resulting σ<sub>y</sub> σ<sub>z</sub> Values for σ<sub>y</sub> σ<sub>z</sub>

## Radius of Exposure


| Pipe Section | Exposure<br>Concentration<br>ppm | u<br>m/s | Q<br>g/s | χ <sub>loc</sub><br>g/m <sup>3</sup> | σ <sub>y</sub> σ <sub>z</sub><br>m <sup>2</sup> | x<br>km | x<br>m | x<br>ft |
|--------------|----------------------------------|----------|----------|--------------------------------------|---|---------|--------|---------|
| 1            | 100                              | 1        | 13.66    | 0.12                                 | 34.78   | 0.22    | 222    | 677     |
|              | 500                              | 1        | 13.66    | 0.62                                 | 6.96  | 0.084   | 84     | 255     |
| 2            | 100                              | 1        | 2.42     | 0.12                                 | 6.17  | 0.078   | 78     | 238     |
|              | 500                              | 1        | 2.42     | 0.62                                 | 1.23  | 0.031   | 31     | 94      |
| 3            | 100                              | 1        | 31.15    | 0.12                                 | 79.33   | 0.34    | 343    | 1045    |
|              | 500                              | 1        | 31.15    | 0.62                                 | 15.87   | 0.135   | 135    | 410     |

In case 3, the emission rate Q is comprised of emission rates from both pipe sections 3a and 3b added together

Linear Interpolation of Distance vs. Sigma y times Sigma z


| Distance x (km) | sigma y * sigma z |
|-----------------|-------------------|
| 0.13            | 14.90             |
| 0.1348          | 15.87             |
| 0.14            | 17.00             |

## Facility Plot Plan





**ATTACHMENTS 4a and 4b Maps Showing Calculated Radius of Exposure for 100 and 500 ppm H<sub>2</sub>S**  
(Maps Prepared with calculated ROE from Pasquill-Gifford Equations as specified in OCD Rule 118 shown in Attachment 2)




Attachment 4A  
Radii of Hydrogen Sulfide Exposure at 100 Parts Per Million

Segment 1: 1000' x 12" Steel Line at 5 psi  
From Flare Line to Auto Safety Valve

Segment 2: 150' x 12" Steel Line at 5 psi  
From Auto Safety Valve to Compressor

Segment 3: 125' x 3" Stainless Steel Line  
at 1600 psi from Compressor to Well Head  
and 300' of 3.5" L-80 Tubing at 980 psi in Well





#### Attachment 4B Radii of Hydrogen Sulfide Exposure at 500 Parts Per Million


Segment 1: 1000' x 12" Steel Line at 5 psi  
From Flare Line to Auto Safety Valve

Segment 2: 150' x 12" Steel Line at 5 psi  
From Auto Safety Valve to Compressor

Segment 3: 125' x 3" Stainless Steel Line  
at 1600 psi from Compressor to Well Head  
and 300' of 3.5" L-80 Tubing at 980 psi in Well




## ATTACHMENT 5 DRAFT Emergency Equipment Location Drawing





**ATTACHMENT 6 DRAFT Plant H<sub>2</sub>S Alarm System Location Plan Drawing**






## ATTACHMENT 7 Hazardous Materials Incident Notification Information Checklist

The following information should be given to dispatch. Dispatch should be instructed to give all information received to response agencies.

|  |   |
|--|---|
| <u>Notification</u>                            | Time Dispatch<br>Notified:  |
| <u>Caller</u>                                  | Caller Name: _____<br>Caller Location: _____<br>Caller Phone Number: _____  |
| <u>Hazardous<br/>Materials<br/>Information</u> | Incident location<br>(Address or Nearest Milepost or Exit) _____<br>Time Incident Occurred _____<br>Container Type<br>(Truck, train car, drum storage, Tank, pipeline, etc.) _____<br>Substance _____<br>UN Identification Number _____<br>Other Identification<br>(Placards, shipping papers, etc.) _____<br>Amount of material<br>spilled/released _____<br>Current condition of material<br>(Flowing, on fire, vapors present, etc.) _____ |
| <u>Scene<br/>Description</u>                   | Weather conditions<br>(i.e., sunny, overcast, wet, dry,<br>etc.) _____<br>Wind direction _____<br>Wind speed _____<br>Terrain<br>(i.e., valley, stream bed, depression, asphalt, etc.) _____<br>Environmental Concerns<br>(Streams, sewers, etc.) _____   |
| <u>Affected<br/>Population</u>                 | Number of people<br>affected _____<br>Condition of people<br>affected _____   |
| <u>Resources</u>                               | Resources required<br>(EMS, HazMat Team, Fire Department, etc.) _____   |
| <u>Response</u>                                | Response actions<br>anticipated<br>And/or in progress<br>(i.e., rescue, fire suppression, containment, etc.)  |
| <u>Comments</u>                                | _____<br>_____<br>_____<br>_____<br>_____   |

# Hydrogen Sulfide Contingency Plan

## Flowchart (see plan pages 8 and 9)



# DISTRIBUTION LIST

|  |        |
|--|--------|
| NEW MEXICO OIL & GAS CONSERVATION DIVISION                                   | 1 COPY |
| NEW MEXICO DEPARTMENT OF PUBLIC SAFETY (Hobbs or Jal Office)<br>STATE POLICE | 1 COPY |
| NEW MEXICO DEPARTMENT OF PUBLIC SAFETY<br>STATE POLICE                       | 1 COPY |
| JAL FIRE DEPARTMENT  | 1 COPY |
| MEDICAL FACILITY (Eunice)  | 1 COPY |
| MEDICAL FACILITY (JAL)   | 1 COPY |
| LEA COUNTY SHERIFF DEPARTMENT (Eunice)                                       | 1 COPY |
| LEA COUNTY SHERIFF DEPARTMENT (JAL)  | 1 COPY |
| LOCAL EMERGENCY MANAGEMENT COMMISSIONER                                      | 1 COPY |
| SUGS JAL #3 PLANT OFFICE   | 1 COPY |
| SUGS FORT WORTH CORPORATE OFFICE   | 1 COPY |
| SUGS MIDLAND OFFICE  | 1 COPY |
| SUGS MONAHANS EHS OFFICE   | 1 COPY |