

ROCK QUEEN UNIT
Data on the Proposed Operation (VII), the Geologic Data (VIII), the
Stimulation Program (IX), and the Fresh Water Wells (XI)

March, 2009

Lease Location: All or portions of Sec. 22 through 27, 34 through 36, T13S, R31E, Chaves County, NM,
and all or portions of Sec. 19, 30, and 31, T13S, R32E, Lea County, NM.

Operator: Celero Energy II, LP

VII. Data on the Proposed Operation:

1. The proposed average water injection rate is 600 BWPDP per well and the proposed maximum injection rate is 1500 BWPDP per well. Assuming a total injection volume of 2.0 HCPV with 55% of that being the water injected, the total estimated volume of water injected is 34 MMB of water.

The proposed average CO₂ injection rate is 1250 MCFDP per well and the proposed maximum injection rate is 3000 MCFDP per well. Assuming a total injection volume of 2.0 HCPV with 45% of that being the CO₂ injected, the total estimated volume of CO₂ injected is 63 BCF of CO₂.

In this tertiary recovery project, Celero plans to flood the Queen reservoir using a "water alternating gas (CO₂)" (WAG) method. We are planning to use a tapered WAG flooding schedule initially and adjust it as needed depending on how the Queen reservoir responds and performs. We will begin the tertiary flood with a wetter WAG schedule of 1.2 to allow for reservoir fillup and reservoir repressurization, taper the WAG schedule down to a 0.5 ratio during the primary flooding phase of the project, and then increase the WAG ratio as the project reaches maturity and nears the end of its life.

2. The system will be closed.
3. The proposed average water injection pressure is 800 psi and the proposed maximum water injection pressure is 1000 psi. This maximum pressure is significantly higher than the 610 psi that the NMOCD would allow using their traditional calculation (0.2*3050' to top of the Queen formation). Celero has performed step rate tests on twelve water injection wells scattered throughout the Rock Queen CO₂ Pilot area and these tests show that Celero can safely inject up to 1000 psi without exceeding the parting pressure of the Queen formation. Attached are the results of these twelve step rate tests.

Celero is seeking approval to increase the maximum injection pressure for all of the injection wells in the Rock Queen Unit including the CO₂ pilot area injection wells, the surrounding water curtain injection wells, and any future injection wells in the Rock Queen Unit.

The proposed average CO₂ injection pressure is 900 psi. This is based on the CO₂ being a lighter injected fluid and assuming the friction losses down the tubing are about the same for the water and the CO₂. The proposed maximum CO₂ injection pressure is 1100 psi.

4. The source water for the waterflood is recycled produced water and fresh water (Ogallala formation) from local wells. Water analyses and compatibility tests are attached.

VIII. The Geologic Data:

- Geologic Age: Permian
- Geologic Name: Queen (a member of the Artesian Group)
- Average Thickness: 15 feet (calculated from available core data)
- Lithology: Shaly sandstone
- Measured Depth: 3000' to 3100'
- Sources of underground drinking water: Ogallala formation at depths from 100' to 200'.

IX. Data on the Proposed Stimulation Program:

- Celero will initially attempt to produce or inject into these wells as they are with no initial stimulation treatments.
- Should a stimulation treatment become needed due to skin damage, poor reservoir quality, reservoir heterogeneities, scale formation, etc., then a mild 7 ½% NEFE HCL treatment with the appropriate additives will be used at a volume of 50 to 100 gal/ft of perforated or open hole interval.
- Should a mild acid treatment not provide an adequate stimulation treatment, then a small 20,000# to 100,000# proppant gelled water frac will be considered and implemented as needed to provide the Queen formation with adequate stimulation.
- Also, depending on what type of scale or corrosion problems develop, appropriate chemical treatments will be designed and implemented to remediate the identified problem(s).

XI. Data on the Fresh Water Wells:

- There is one fresh water well within one mile of any injection well on the Rock Queen Unit. That well is located in Section 35 (F), T13S, R31E, Chaves County, NM. A recent chemical analysis of the well's water and a map showing the location of the water well are attached.




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	3/31/2008	12:27 PM	1875	404	
200	3/31/2008	1:00 PM	1875	475	
400	3/31/2008	1:30 PM	1890	600	
800	3/31/2008	2:00 PM	1915	675	
1200	3/31/2008	2:30 PM	1949	725	
1600	3/31/2008	3:00 PM	2005	825	
2000	3/31/2008	4:25 PM	2058	925	
2400	3/31/2008	4:55 PM	2134	1025	
2800	3/31/2008	6:37 PM	2224	1215	NO FRACTURE POINT ACHIEVED
3200	3/31/2008	7:07 PM	2310	1400	
3600	3/31/2008	7:37 PM	2403	1525	
4000	3/31/2008	8:07 PM	2498	1700	

Company:	CELERO ENERGY	Recorded By:	M. HOLMES
Well:	ROCK QUEEN #42	Witnessed By:	DON HALE
Field:	CAPROCK	Truck Number:	42
County:	CHAVES	District:	ODESSA
State:	NEW MEXICO	Tool Number:	SPARTEK 1 3/8"
Injector:	WATER	Test Type:	STEP RATE TEST
Shut In Time:	3/29/2008	NOTES: SET DOWN IN PACKER	
Tool Depth:	2900' IN TBG.		
Tubing Size:	2 3/8		
Tail Pipe Depth:	2967'		
Perfs:	3057-61, OH: 3067-88'		
Plug Back Depth:	3088'		

GWSi



No Fracture Point Achieved




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	4/3/2008	7:29 AM	1337	0	
200	4/3/2008	8:00 AM	2040	600	START FRACTURE
400	4/3/2008	8:30 AM	2350	1025	APPROX 2400 PSI
800	4/3/2008	9:00 AM	2593	1275	
1200	4/3/2008	9:30 AM	2815	1500	
1600	4/3/2008	10:00 AM	2973	1675	SUSTAINED FRAC
2000	4/3/2008	10:30 AM	3048	1800	APPROX. 2950 PSI
2400	4/3/2008	11:00 AM	3103	1900	
2800	4/3/2008	11:30 AM	3115	2000	
Company: CELERO ENERGY				Recorded By:	M. HOLMES
Well: ROCK QUEEN #44				Witnessed By:	DON HALE
Field: CAPROCK				Truck Number:	42
County: CHAVES				District:	ODESSA
State: NEW MEXICO				Tool Number:	SPARTEK 1 3/8"
Injector WATER				Test Type:	STEP RATE TEST
Shut In Time: 4/2/2008				NOTES:	
Tool Depth 3030'					
Tubing Size: 2 3/8					
Tail Pipe Depth: 2890'					
Perfs: 3032-50'					
Plug Back Depth 3065'					



GWSi



Fracture Point: 1530 BWP, 3000 psi BH, 1720 psi Surface




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	4/2/2008	2:44 AM	1251	0	
200	4/2/2008	3:15 PM	2065	625	
400	4/2/2008	3:45 PM	2362	1010	FRACTURE POINT
800	4/2/2008	4:15 PM	2484	1175	APPROX. 2400 PSI
1200	4/2/2008	4:45 PM	2575	1280	
1600	4/2/2008	5:15 PM	2665	1375	
Company:	CELERO ENERGY			Recorded By:	M. HOLMES
Well:	ROCK QUEEN #62			Witnessed By:	JOHN ANDERSON
Field:	CAPROCK			Truck Number:	42
County:	CHAVES			District:	ODESSA
State:	NEW MEXICO			Tool Number:	SPARTEK 1 3/8"
Injector	WATER			Test Type:	STEP RATE TEST
Shut In Time:	4/1/2008			NOTES:	
Tool Depth	3040'				
Tubing Size:	2 3/8				
Tail Pipe Depth:	2975'				
Perfs:	3053-70', OH: 3072-3100'				
Plug Back Depth	3100'				



GWSi



Fracture Point: 440 BWPD, 2395 BH psi, 1055 Surf. psi




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	4/1/2008	8:35 AM	1450	0	
200	4/1/2008	9:10 AM	2063	570	
400	4/1/2008	9:40 AM	2474	1140	FRACTURE POINT
800	4/1/2008	10:10 AM	2584	1250	APPROX. 2474 PSI
1200	4/1/2008	10:40 AM	2710	1400	
1600	4/1/2008	3:00 PM	2819	1550	
Company: CELERO ENERGY				Recorded By:	M. HOLMES
Well: ROCK QUEEN #66				Witnessed By:	JOHN ANDERSON
Field: CAPROCK				Truck Number:	42
County: CHAVES				District:	ODESSA
State: NEW MEXICO				Tool Number:	SPARTEK 1 3/8"
Injector: WATER				Test Type:	STEP RATE TEST
Shut In Time: 3/29/2008				NOTES:	
Tool Depth 3050'					
Tubing Size: 2 3/8					
Tail Pipe Depth: 2988'					
Perfs: 3052-69'					
Plug Back Depth 3077'					





Fracture Point: 400 BWPD, 2474 psi BH, 1140 psi Surf.



STEP RATE TESTS


monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	4/2/2008	7:40 AM	2048	524	
200	4/2/2008	8:15 AM	2069	625	
400	4/2/2008	8:45 AM	2103	675	
800	4/2/2008	9:15 AM	2165	850	
1200	4/2/2008	9:45 AM	2242	950	
1600	4/2/2008	10:15 AM	2333	1100	
2000	4/2/2008	10:45 AM	2416	1225	
2400	4/2/2008	11:15 AM	2497	1375	
2800	4/2/2008	11:45 AM	2574	1530	FRACTURE POINT
3200	4/2/2008	12:15 PM	2637	1630	APPROX. 2540 PSI
3600	4/2/2008	12:45 PM	2698	1730	

Company:	CELERO ENERGY	Recorded By:	M. HOLMES
Well:	ROCK QUEEN #70	Witnessed By:	JOHN ANDERSON
Field:	CAPROCK	Truck Number:	42
County:	CHAVES	District:	ODESSA
State:	NEW MEXICO	Tool Number:	SPARTEK 1 3/8"
Injector:	WATER	Test Type:	STEP RATE TEST

Shut In Time:	4/1/2008	NOTES:
Tool Depth:	3040'	
Tubing Size:	2 3/8	
Tail Pipe Depth:	2949'	
Perfs:	OH: 3047-90'	
Plug Back Depth:	3090'	

GWSI



Fracture Point: 2800 BWP, 2574 psi BH, 1530 psi Surf.




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/25/2008	10:23 AM	1368	VAC	
200	8/25/2008	11:00 AM	1368	0	
600	8/25/2008	11:30 AM	1387	100	
1000	8/25/2008	12:00 PM	1422	140	
1400	8/25/2008	12:30 PM	1466	200	
1800	8/25/2008	1:00 PM	1519	285	
2200	8/25/2008	1:30 PM	1580	395	
2600	8/25/2008	2:00 PM	1645	495	
3000	8/25/2008	2:30 PM	1712	610	
3400	8/25/2008	3:00 PM	1783	740	
3800	8/25/2008	3:30 PM	1858	890	
4200	8/25/2008	4:00 PM	1932	1020	OUT OF WATER
Company:	CELERO ENERGY			Recorded By:	M. HOLMES
Well:	ROCK QUEEN #85			Witnessed By:	DAN PARKHURST
Field:	CAPROCK			Truck Number:	42
County:	CHAVES			District:	ODESSA
State:	NEW MEXICO			Tool Number:	SPARTEK 1 3/8"
Injector	WATER			Test Type:	STEP RATE TEST
Shut In Time:	8/24/2008			NOTES: NO FRACTURE ACHIEVED	
Tool Depth	3040'				
Tubing Size:	2 3/8"				
Tail Pipe Depth:	2976'				
Perfs:	OPEN HOLE: 3041-80'				
Plug Back Depth	3080				





No fracture point achieved.



STEP RATE TESTS


monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/26/2008	9:07 AM	1091	VAC	
200	8/26/2008	9:45 AM	1820	500	
400	8/26/2008	10:15 AM	2382	1145	FRACTURE POINT
600	8/26/2008	10:45 AM	2475	1230	
800	8/26/2008	11:15 AM	2572	1340	
1000	8/26/2008	11:45 AM	2662	1440	

Company:	CELERO ENERGY	Recorded By:	M. HOLMES
Well:	ROCK QUEEN #87	Witnessed By:	DAN PARKHURST
Field:	CAPROCK	Truck Number:	42
County:	CHAVES	District:	ODESSA
State:	NEW MEXICO	Tool Number:	SPARTEK 1 3/8"
Injector:	WATER	Test Type:	STEP RATE TEST
Shut In Time:	8/25/2008		
Tool Depth:	2900' IN TBG		
Tubing Size:	2 3/8"		
Tail Pipe Depth:	2968'		
Perfs:	3057-71', OPE HOLE: 3063-3100'		
Plug Back Depth:	3100'		

NOTES:
UNABLE TO GET
THRU PACKER

GWSi



Fracture Point: 400 BWPD, 2382 psi BH, 1145 psi Surface




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/19/2008	10:40 AM	1147	VAC	
200	8/19/2008	11:15 AM	1205	VAC	
400	8/19/2008	11:45 AM	1220	VAC	
800	8/19/2008	12:15 PM	1244	VAC	
1200	8/19/2008	12:45 PM	1267	VAC	
1600	8/19/2008	1:15 PM	1290	VAC	
2000	8/19/2008	1:45 PM	1319	0	
2400	8/19/2008	2:15 PM	1355	200	
2800	8/19/2008	2:45 PM	1387	300	NO FRACTURE
3200	8/19/2008	3:15 PM	1435	450	POINT ACHIEVED

Company:	CELERO ENERGY	Recorded By:	M. HOLMES
Well:	ROCK QUEEN #6	Witnessed By:	DAN PARKHURST
Field:	CAPROCK	Truck Number:	42
County:	CHAVES	District:	ODESSA
State:	NEW MEXICO	Tool Number:	SPARTEK 1 3/8"
Injector:	WATER	Test Type:	STEP RATE TEST
Shut In Time:	8/18/2008	NOTES:	
Tool Depth:	3050'		
Tubing Size:	2 3/8		
Tail Pipe Depth:	2735'		
Perfs:	3052-67'		
Plug Back Depth:	3094'		

GWSi



No Fracture Point Achieved



STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/21/2008	8:43 AM	1602	118	
200	8/21/2008	9:15 AM	1608	200	
400	8/21/2008	9:45 AM	1621	375	
600	8/21/2008	10:15 AM	1657	425	
800	8/21/2008	10:45 AM	1690	465	
1000	8/21/2008	11:15 AM	1730	510	
1200	8/21/2008	11:45 AM	1770	570	
1400	8/21/2008	12:15 PM	1822	620	FRACTURE POINT
1600	8/21/2008	12:45 PM	1864	685	
1800	8/21/2008	1:15 PM	1913	745	
2000	8/21/2008	1:45 PM	1962	810	

Company: CELERO ENERGY

Well: ROCK QUEEN #48

Field: CAPROCK

County: CHAVES

State: NEW MEXICO

Injector: WATER

Shut In Time: 8/20/2008 PM

Tool Depth: 2900', IN TBG

Tubing Size: 2 3/8", 1.25" ID SN ?

Tail Pipe Depth: 2962'

Perfs: OPEN HOLE: 3028-74'

Plug Back Depth: 3074'

Recorded By: M. HOLMES

Witnessed By: EDDIE TAYLOR

Truck Number: 42


District: ODESSA

Tool Number: SPARTEK 1 3/8"

Test Type: STEP RATE TEST

NOTES:
UNABLE TO GET
THRU PACKER

GWSi



No Fracture Point Achieved.




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/20/2008	3:07 PM	733	0	
200	8/20/2008	3:45 PM	1364	0	
400	8/20/2008	4:15 PM	2178	875	FRACTURE POINT
600	8/20/2008	4:45 PM	2237	930	
800	8/20/2008	5:15 PM	2320	1030	
1000	8/20/2008	5:45 PM	2372	1100	
Company:	CELERO ENERGY			Recorded By:	M. HOLMES
Well:	ROCK QUEEN #50			Witnessed By:	EDDIE TAYLOR
Field:	CAPROCK			Truck Number:	42
County:	CHAVES			District:	ODESSA
State:	NEW MEXICO			Tool Number:	SPARTEK 1 3/8"
Injector	WATER			Test Type:	STEP RATE TEST
Shut In Time:	8/19/2008			NOTES:	
Tool Depth	3030'				
Tubing Size:	2 3/8"				
Tail Pipe Depth:	2940'				
Perfs:	3032-46'				
Plug Back Depth	3067'				



GWSi



Fracture Point: 400 BWPD, 2178 psi BH, 875 psi Surface



STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/20/2008	9:26 AM	1750	275	
200	8/20/2008	10:00 AM	1753	300	
400	8/20/2008	10:30 AM	1766	520	
800	8/20/2008	11:00 AM	1776	550	
1200	8/20/2008	11:30 AM	1797	580	
1600	8/20/2008	12:00 PM	1829	640	FRAGTURE POINT
2000	8/20/2008	12:30 PM	1855	720	
2400	8/20/2008	1:00 PM	1884	805	
2800	8/20/2008	1:30 PM	1918	900	

Company: CELERO ENERGY

Well: ROCK QUEEN #64

Field: CAPROCK

County: CHAVES

State: NEW MEXICO

Injector: WATER

Shut In Time: 8/19/2008

Tool Depth: 2900' in Tubing

Tubing Size: 2 3/8", 1.25" ID SN

Tail Pipe Depth: 2960'

Perfs: 3041-65'

Plug Back Depth: 3097'

Recorded By: M. HOLMES

Witnessed By: EDDIE TAYLOR

Truck Number: 42


District: ODESSA

Tool Number: SPARTEK 1 3/8"

Test Type: STEP RATE TEST

NOTES:

GWSI



No Fracture Point Achieved.




STEP RATE TESTS

monty.holmes@graywireline.com

RATE BPD	Date	Time	BH Press	Surf Press	Comments
0	8/22/2008	9:12 AM	665	VAC	
200	8/22/2008	9:45 AM	827	VAC	
600	8/22/2008	10:15 AM	1337	0	
1000	8/22/2008	10:45 AM	1760	490	FRACTURE POINT
1400	8/22/2008	11:15 AM	2015	760	1780 PSI
1800	8/22/2008	11:45 AM	2211	1000	
2200	8/22/2008	12:15 PM	2386	1200	

Company:	CELERO ENERGY	Recorded By:	M. HOLMES
Well:	ROCK QUEEN #68	Witnessed By:	EDDIE TAYLOR
Field:	CAPROCK	Truck Number:	42
County:	CHAVES	District:	ODESSA
State:	NEW MEXICO	Tool Number:	SPARTEK 1 3/8"
Injector:	WATER	Test Type:	STEP RATE TEST
Shut In Time:	8/21/2008	NOTES:	
Tool Depth:	3050'		
Tubing Size:	2 3/8"		
Tail Pipe Depth:	2974'		
Perfs:	OPEN HOLE: 3056-84'		
Plug Back Depth:	3084'		

GWSi



Fracture Point: 920 BWPD, 1710 psi BH, 430 psi surface

John Anderson

From: DON HALE [dth-jr@msn.com]
Sent: Monday, February 18, 2008 4:50 PM
To: bwoodard@celeroenergy.com
Cc: janderson@celeroenergy.com
Subject: FW: [Fwd: Celero Compatibility.pdf attached]
Attachments: Celero Compatibility.pdf

> From: prokem@windstream.net
> To: dth-jr@msn.com
> Subject: [Fwd: Celero Compatibility.pdf attached]
> Date: Mon, 18 Feb 2008 15:10:31 -0600
>
>
> >
> > From: "Jose L. Enriquez" <jose@interchem.us>
> > Date: 2008/02/18 Mon PM 02:34:43 CST
> > To: <prokem@windstream.net>
> > Subject: Celero Compatibility.pdf attached
> >
> > Attached please find the computer printout of the predicted compatibility
> > between the Celero Energy Produced Water and the Recovery Water. Results
> > indicate that these waters are very compatible, reducing the Calcium
> > Carbonate scaling tendencies substantially, from about 10% by volume
> > Produced Water up to about 60% by volume Produced Water. The Calcium
> > Sulfate scaling potential remains negligible. No other potential problems
> > are identified.
> >
> > If we may be of further assistance in the interpretation of the above
> > observations, please call at your convenience.
> >
> > Jose L. Enriquez
> > Technical Services
> >
> >


Comparison Between Two Waters

Requested by: Pro-Kem, Inc.

Sample No. 1
Celero Energy
Recovery Water

Sample No. 2
Celero Energy
Produced Water

Percent of #1 & #2	pH	TDS	SpGr	CaCO ₃ Saturation @80°F. @140°F.		Calcium Sulfate Scaling Potential
100 - 00	7.100	468	1.009	0.133	0.733	Nil
95 - 05	7.070	15,378	1.019	-0.751	0.109	Nil
90 - 10	7.040	30,289	1.029	-0.960	0.010	Nil
85 - 15	7.010	45,199	1.038	-0.952	-0.012	Nil
80 - 20	6.980	60,109	1.048	-0.908	0.002	Nil
75 - 25	6.950	75,020	1.058	-0.873	0.047	Nil
70 - 30	6.920	89,930	1.068	-0.823	0.107	Nil
65 - 35	6.890	104,840	1.077	-0.742	0.193	Nil
60 - 40	6.860	119,751	1.087	-0.679	0.226	Nil
55 - 45	6.830	134,661	1.097	-0.592	0.298	Nil
50 - 50	6.800	149,572	1.107	-0.480	0.400	Nil
45 - 55	6.770	164,482	1.116	-0.382	0.538	Nil
40 - 60	6.740	179,392	1.126	-0.307	0.653	Nil
35 - 65	6.710	194,303	1.136	-0.196	0.904	Nil
30 - 70	6.680	209,213	1.146	-0.067	1.153	Nil
25 - 75	6.650	224,123	1.155	0.080	1.500	Nil
20 - 80	6.620	239,034	1.165	0.175	1.785	Nil
15 - 85	6.590	253,944	1.175	0.367	2.467	Nil
10 - 90	6.560	268,854	1.185	0.608	2.548	Nil
05 - 95	6.530	283,765	1.194	0.898	2.528	Nil
00 - 100	6.500	298,675	1.204	1.125	2.505	Nil



Pro-Kem, Inc.

WATER ANALYSIS REPORT

SAMPLE

Oil Co. : **Celero Energy**
 Lease :
 Well No.: **Fresh Water**
 Location:
 Attention:

Date Sampled : **17-August-2007**
 Date Analyzed: **23-August-2007**
 Lab ID Number: **Aug2307.003- 2**
 Salesperson :
 File Name : **aug2307.003**

ANALYSIS

1. Ph 7.100
2. Specific Gravity 60/60 F. 1.009
3. CACO3 Saturation Index @ 80F
- @140F

0.133 **Mild**
0.733 **Moderate**

Dissolved Gasses

4. Hydrogen Sulfide Not Present
5. Carbon Dioxide Not Determined
6. Dissolved Oxygen Not Determined


Cations

- | | | | MG/L. | EQ. WT. | *MEQ/L |
|--------------|--------|--------------|----------------|----------|--------|
| 7. Calcium | (Ca++) | | 63 | / 20.1 = | 3.13 |
| 8. Magnesium | (Mg++) | | 13 | / 12.2 = | 1.07 |
| 9. Sodium | (Na+) | (Calculated) | 54 | / 23.0 = | 2.35 |
| 10. Barium | (Ba++) | | Not Determined | | |


Anions

- | | | | | | |
|--------------------------------------|---------|--|----------------|--------------------|------|
| 11. Hydroxyl | (OH-) | | 0 | / 17.0 = | 0.00 |
| 12. Carbonate | (CO3=) | | 0 | / 30.0 = | 0.00 |
| 13. Bicarbonate | (HCO3-) | | 193 | / 61.1 = | 3.16 |
| 14. Sulfate | (SO4=) | | 95 | / 48.8 = | 1.95 |
| 15. Chloride | (Cl-) | | 50 | / 35.5 = | 1.41 |
| 16. Total Dissolved Solids | | | 468 | | |
| 17. Total Iron | (Fe) | | 2.00 | / 18.2 = | 0.11 |
| 18. Manganese | (Mn++) | | Not Determined | | |
| 19. Total Hardness as CaCO3 | | | 208 | | |
| 20. Resistivity @ 75 F. (Calculated) | | | | 2.462 Ohm · meters | |

LOGARITHMIC WATER PATTERN



Calcium Sulfate Solubility Profile



PROBABLE MINERAL COMPOSITION

COMPOUND	*meq/L	X	EQ. WT.	=	mg/L.
Ca(HCO3)2	3.13		81.04		254
CaSO4	0.00		68.07		0
CaCl2	0.00		55.50		0
Mg(HCO3)2	0.02		73.17		2
MgSO4	1.04		60.19		63
MgCl2	0.00		47.62		0
NaHCO3	0.00		84.00		0
NaSO4	0.91		71.03		64
NaCl	1.41		58.46		82

* milliequivalents per Liter

Kevin Byrne, Analyst

Pro-Kem, Inc.

WATER ANALYSIS REPORT

SAMPLE

Oil Co. : Celero
Lease : Rock Queen
Well No.: 84
Location:
Attention:

Date Sampled : 17-July-2007
Date Analyzed: 20-July-2007
Lab ID Number: Jul2307.004- 1
Salesperson :
File Name : jul2307.004

ANALYSIS

1. Ph 6.500
2. Specific Gravity 60/60 F. 1.204
3. CACO3 Saturation Index @ 80F
@140F

1.125 Moderate
2.505 Severe

Dissolved Gasses

4. Hydrogen Sulfide Not Present
5. Carbon Dioxide 300
6. Dissolved Oxygen Not Determined


Cations

- | | | | | | |
|--------------|--------|--------------|----------------|----------|----------|
| 7. Calcium | (Ca++) | | 1,876 | / 20.1 = | 93.33 |
| 8. Magnesium | (Mg++) | | 5,310 | / 12.2 = | 435.25 |
| 9. Sodium | (Na+) | (Calculated) | 107,113 | / 23.0 = | 4,657.09 |
| 10. Barium | (Ba++) | | Not Determined | | |


Anions

- | | | | | | |
|--------------------------------------|---------|--|----------------|----------|--------------------|
| 11. Hydroxyl | (OH-) | | 0 | / 17.0 = | 0.00 |
| 12. Carbonate | (CO3=) | | 0 | / 30.0 = | 0.00 |
| 13. Bicarbonate | (HCO3-) | | 117 | / 61.1 = | 1.91 |
| 14. Sulfate | (SO4=) | | 1,300 | / 48.8 = | 26.64 |
| 15. Chloride | (Cl-) | | 182,959 | / 35.5 = | 5,153.77 |
| 16. Total Dissolved Solids | | | 298,675 | | |
| 17. Total Iron | (Fe) | | 11.50 | / 18.2 = | 0.63 |
| 18. Manganese | (Mn++) | | Not Determined | | |
| 19. Total Hardness as CaCO3 | | | 26,544 | | |
| 20. Resistivity @ 75 F. (Calculated) | | | | | 0.001 Ohm · meters |

LOGARITHMIC WATER PATTERN



Calcium Sulfate Solubility Profile



PROBABLE MINERAL COMPOSITION

COMPOUND	*meq/L	X	EQ. WT. =	mg/L.
Ca(HCO3)2	1.91		81.04	155
CaSO4	26.64		68.07	1,813
CaCl2	64.78		55.50	3,595
Mg(HCO3)2	0.00		73.17	0
MgSO4	0.00		60.19	0
MgCl2	435.25		47.62	20,726
NaHCO3	0.00		84.00	0
NaSO4	0.00		71.03	0
NaCl	4,653.75		58.46	272,058

* milliequivalents per Liter

Kevin Byrne, Analyst

Report Date: June 14, 2007
2972Work Order: 7052432
Celero Energy-Rock Queen ESAPage Number: 1 of 1
Chaves Co. NM

Summary Report

Ike Tavaréz
Highlander Environmental Services
1910 N. Big Spring Street
Midland, TX, 79705

Report Date: June 14, 2007

Work Order: 7052432


Project Location: Chaves Co. NM
Project Name: Celero Energy-Rock Queen ESA
Project Number: 2972

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
125351	Water Well 31-13-31	water	2007-05-22	00:00	2007-05-23

Location: Sec. 35(F), T13S, R31E1M

Sample: 125351 - Water Well 31-13-31

Param	Flag	Result	Units	RL
Hydroxide Alkalinity		<1.00	mg/L as CaCO ₃	1.00
Carbonate Alkalinity		<1.00	mg/L as CaCO ₃	1.00
Bicarbonate Alkalinity		152	mg/L as CaCO ₃	4.00
Total Alkalinity		152	mg/L as CaCO ₃	4.00
Dissolved Calcium		63.5	mg/L	0.500
Chloride		32.1	mg/L	0.500
Specific Conductance		546	uMHOS/cm	0.00
Fluoride		<1.00	mg/L	0.200
Dissolved Potassium		1.98	mg/L	0.500
Dissolved Magnesium		8.79	mg/L	0.500
Dissolved Sodium		28.5	mg/L	0.500
Nitrate-N		4.10	mg/L	0.200
pH		7.83	s.u.	0.00
Sulfate		43.6	mg/L	0.500
Total Dissolved Solids		327.0	mg/L	10.00



Queen Reservoir
Type Section
Rock Queen Unit
Caprock Field
Chaves Co., NM




Drickey Queen #144
Chaves Co., NM
3,200
T13S R31E S35

Trigg Federal 4 #38
TD 4808

Chaves Co., NM
T14S R21E S4

Major subdivisions and boundaries of the Permian Basin in west Texas and New Mexico



Stratigraphic nomenclature for the Permian section in the Permian Basin

System	Epoch/ Series/ Stage	Time (m.y.)	Delaware Basin	NW Shelf New Mexico	NW Shelf Texas	Central Basin Platform
Ochoan		251	Dewey Lake	Dewey Lake	Dewey Lake	Dewey Lake
			Rustler	Rustler	Rustler	Rustler
			Salado	Salado	Salado	Salado
			Castle	Castle	Castle	Castle
Guadalupian			Bell Canyon	Tanali	Tanali	Tanali
			Yates	Yates	Yates	Yates
			Seven Rivers	Seven Rivers	Seven Rivers	Seven Rivers
			Queen	Queen	Queen	Queen
Leonardian			Cherry Canyon	Grayburg	Grayburg	Grayburg
			Upper San Andres	Upper San Andres	Upper San Andres	Upper San Andres
			Brushy Canyon			
			Cutoff	Lower San Andres	Lower San Andres	Lower San Andres
Wolfcampian			Wolfcamp	Wolfcamp	Wolfcamp	Wolfcamp

Dutton et al, BEG 2004

Yates

Seven Rivers

Rustler

Salado

Tansill

Yates

Seven Rivers

Queen

Grayburg

Queen Mkr

Grayburg

San Andres



Queen Interval Log Detail


Resistivity & Gamma Ray Logs
Drickey Queen #144 Chaves Co., NM

Seven Rivers

Main Queen
Sand

Grayburg





A

A'

30005008770000
Rock Queen Unit
▲40
3,067

<3,546FT>

30005008820000
Rock Queen Unit
▲50
3,050

<5,604FT>


30005008620000
Rock Queen Unit
▲66
3,101

<3,435FT>

30025003120000
Rock Queen Unit
●71
3,064

<2,949FT>

30025002840000
Rock Queen Unit
▲106
3,058



Celero Energy

Caprock Field - Queen Reservoir

Rock Queen Unit

Stratigraphic Cross Section

Datum = Queen

Horizontal Scale = 1072.7
Vertical Scale = 20.0
Vertical Exaggeration = 53.6x

UWI
Well Name
Well Label
WELL - TD

Chaves & Lea Courties., NM

By: J. Baker

March 4, 2008 10:06 AM

PETRA 3/4/2008 10:06:11 AM (RCU Hearing Reservoir detail 5 wells only 0308.CSP)


Target zone

Rock Queen Unit – Queen Reservoir Cross Section

Chaves & Lea Cos., NM

B (W)

B' (E)




Rock Queen Unit Dip Cross Section

Chaves & Lea Cos., NM

C' (N)

C' (S)



Rock Queen Unit Strike Cross Section

Chaves & Lea Cos., NM



Celero Energy

Caprock Field

Rock Queen Unit

Structural Cross Section (Strike)

Chaves & Lea Counties, NM

Horizontal Scale = 647.7
Vertical Scale = 40.0
Vertical Exaggeration = 16.2x

Well Name
Well Label
WELL - TD


By: J.Baker
March 4, 2008 9:22 AM

1410 -
1370 -
1330 -
1290 -
1250 -

1325



Chaves & Lea Counties, NM



	Oil Well
	Gas Well
	Dry Hole
	Injection Well
	Service Well
	Dry Hole, With Show of Oil
	Inactive Oil Well
	Oil Well Plugged and Abandoned
	Water Injection Well
	Inactive Water Injection Well
	Plugged and Abandoned Water In

March 4, 2008