

BELOW GROUND DETAIL

All depths are referenced to the kelly bushing elevation of 13 feet. Surface elevation is 3610 feet.

1. Base of the USDW at 473'.

2. Casing: 8-5/8", 32 lb/ft, set at 1955' in an 11" hole. Cemented to surface with 700 sacks of cement.

3. Injection Tubing: 3-1/2".

4. DV Tool: at 5500'.

5. Annulus Fluid: Corrosion inhibited brine water.


6. Protection Casing: 5-1/2" set in a 7-7/8" hole. Casing cemented to surface. Calipered hole volume plus 20% excess.

7. Packer: Fullbore retrievable packer set 100' above the top perforated injection interval.

8. Perforations: Perforated in two intervals between 7270' and 8894'.

9. PBTD: 9200'

10. Cement Plug: 45 sacks from 9675' to 9775'.



ENVIROCORP

HOUSTON, TX
SOUTH BEND, IN.
BATON ROUGE, LA.

ATTACHMENT III-4
NAVAJO REFINING COMPANY
PROPOSED WDW-2
ARTESIA, NEW MEXICO

Date: 03/11/99 | Checked By: NLN | Job No.: 60A4937
Drawn By: LKM | Approved By: NLN | File: WDW2B.DS4