

Tree Showing Rams Closed

Drinkard Production

Tubb Flow Line

8⁵/₈" Casing Cemented @ 1223'
Cement Circulated to surface w/ 400
SXS. 340 & 200 SXS. Neat.

Casing Jet Perforated
w/ 4-21 grain shots / foot.
From 5988' to 6236'

Otis Side Door Choke
Blacked Off
@ 6455'

Baker Model "D" Retainer
Production Packer
set @ 6460'

Tubing Perforations

5¹/₂" casing perforated 6510-6630'

TD - 6636'

Detail of Mechanical Equipment To Be
Installed In Dually Completed Drinkard And
Tubb Wells For Submission To OIL
Conservation Commission