

13-3/8" OD Csg. Set @ 327'
Cemented w/500 Sx.
Cement Circulated

9-5/8" Csg. Set @ 3896'
Cemented w/2474 Sx.
TSITC @ 35'

2-1/2" Buttress Thread
Tubing

2" Buttress Thread
Tubing

7" Csg. Set @
7299' Cemented w/1125 Sx.
TSITC @ 100'

Parallel String Anchor
@ Approx. 7220'

Liner Hanger @
Approx. 7250'

Fusselman producing from
open hole interval 7299'-
7490'. Original TD 7550'
Original PBD 7490'

Proposed Fusselman
Perfs. @ Approx.
7320'-7360'

4-1/2" OD 13.50#
N-80 Liner

Cement to top of liner

Baker Model "D" packer
Set @ Approx. 9575'

Ellenburger Perforations
@ Approx. 9625'-9800'

Approximate new TD 10,100'

PROPOSED MECHANICAL INSTALLATION
DUAL COMPLETION
LILLIE WELL NO. 3

FOWLER FUSSELMAN - FOWLER ELLENBURGER OIL POOLS
LEA COUNTY, NEW MEXICO
GULF OIL CORPORATION
MAY 10, 1962

CASE NO. 2556
EXHIBIT NO. 4

*0/58 BNP 2245
been on pump since
37.1 pump - 50'*

BNP Hall - Knight #1

2/62 1949 @ - 6980

45° angle

*181,000 to
oil well
90,000 to
Baker &
dual comp.*