



Application for Permit to Drill

U.S. Department of the Interior
Bureau of Land Management

APD Package Report

Date Printed: 05/29/2020 11:27 AM

APD ID: 10400052808	Well Status: AAPD
APD Received Date: 01/02/2020 05:23 AM	Well Name: CORRAL CANYON 4 FEDER
Operator: XTO ENERGY INCORPORATED	Well Number: 168H

APD Package Report Contents

OCD REC'D 6/2/2020

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
 - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 16 file(s)
 - Blowout Prevention BOP Diagram Attachment: 16 file(s)
 - Casing Design Assumptions and Worksheet(s): 4 file(s)
 - Hydrogen sulfide drilling operations plan: 2 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 1 file(s)
 - Other Facets: 1 file(s)
 - Other Variances: 3 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Water source and transportation map: 1 file(s)
 - Well Site Layout Diagram: 3 file(s)
 - Recontouring attachment: 4 file(s)
 - Other SUPO Attachment: 1 file(s)
- PWD Report
- PWD Attachments
 - None
- Bond Report
- Bond Attachments

-- None

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM015302
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator XTO ENERGY INCORPORATED		8. Lease Name and Well No. CORRAL CANYON 4 FEDERAL 168H
3a. Address 22777 Springwoods Village Parkway, Spring, TX 77389	3b. Phone No. (include area code) (432) 620-6700	9. API Well No. 30-015-47160
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SESE / 140 FSL / 460 FEL / LAT 32.152311 / LONG -103.982352 At proposed prod. zone LOT 1 / 200 FNL / 330 FEL / LAT 32.165972 / LONG -103.165972		10. Field and Pool, or Exploratory WELCH/null
11. Sec., T. R. M. or Blk. and Survey or Area SEC 4/T25S/R29E/NMP		
14. Distance in miles and direction from nearest town or post office* 8 miles		12. County or Parish EDDY
13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 140 feet	16. No of acres in lease 1917.02	17. Spacing Unit dedicated to this well 320.0
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 0 feet	19. Proposed Depth 10881 feet / 16100 feet	20. BLM/BIA Bond No. in file FED: UTB000138
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3000 feet	22. Approximate date work will start* 04/01/2019	23. Estimated duration 90 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Stephanie Rabadue / Ph: (432) 620-6700	Date 01/02/2020
Title Regulatory Coordinator		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575) 234-5959	Date 05/27/2020
Title Assistant Field Manager Lands & Minerals		
Office Carlsbad Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

0. SHL: SESE / 140 FSL / 460 FEL / TWSP: 25S / RANGE: 29E / SECTION: 4 / LAT: 32.152311 / LONG: -103.982352 (TVD: 0 feet, MD: 0 feet)

PPP: SESE / 330 FSL / 330 FEL / TWSP: 25S / RANGE: 29E / SECTION: 4 / LAT: 32.152834 / LONG: -103.982352 (TVD: 10965 feet, MD: 11320 feet)

BHL: LOT 1 / 200 FNL / 330 FEL / TWSP: 25S / RANGE: 29E / SECTION: 4 / LAT: 32.165972 / LONG: -103.165972 (TVD: 10881 feet, MD: 16100 feet)

BLM Point of Contact

Name: Tyler Hill

Title: LIE

Phone: (575) 234-5972

Email: tjhill@blm.gov

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME: XTO Energy Incorporated
LEASE NO.: NMLC136870; NMNM015302
LOCATION: Section 4; Section 9, T.25 S., R.29 E., NMPM
COUNTY: Eddy County, New Mexico

Corral Canyon 4 Federal 124H

Surface Hole Location: 145' FNL & 2130' FWL, Section 9, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2010 FWL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 104H

Surface Hole Location: 175' FNL & 2130' FWL, Section 9, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2430' FWL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 103H

Surface Hole Location: 205' FNL & 2130' FWL, Section 9, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 1590' FWL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 164H

Surface Hole Location: 235' FNL & 2130' FWL, Section 9, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2130' FWL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 163H

Surface Hole Location: 265' FNL & 2130' FWL, Section 9, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 1650' FWL, Section 4, T. 25 S, R. 29 E.

Corral Canyon 4 Federal 125H

Surface Hole Location: 170' FSL & 2060' FEL, Section 4, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2430' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 105H

Surface Hole Location: 170' FSL & 2030' FEL, Section 4, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2010' FWL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 126H

Surface Hole Location: 170' FSL & 1980' FEL, Section 4, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 1590' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 165H

Surface Hole Location: 70' FSL & 2030' FEL, Section 4, T. 25 S., R. 29 E.
Bottom Hole Location: 200' FNL & 2310' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 166H

Surface Hole Location: 70' FSL & 1980' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 1650' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 108H

Surface Hole Location: 230' FSL & 460' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 330' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 127H

Surface Hole Location: 200' FSL & 460' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 750' FEL, Section 4, T. 25 S, R. 29 E.

Corral Canyon 4 Federal 107H

Surface Hole Location: 170' FSL & 460' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 1170' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 168H

Surface Hole Location: 140' FSL & 460' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 330' FEL, Section 4, T. 25 S, R 29 E.

Corral Canyon 4 Federal 167H

Surface Hole Location: 110' FSL & 460' FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200' FNL & 990' FEL, Section 4, T. 25 S, R 29 E.

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Wildlife: Texas Hornshell Boundary
 - Cave/Karst
 - Hydrology
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**

- ☐ **Production (Post Drilling)**
Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

I. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

II. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

III. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent

land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

IV. SPECIAL REQUIREMENT(S)

Wildlife:

Oil and Gas Zone D - CCA Boundary requirements.

- Implement erosion control measures in accordance with the Reasonable and Prudent Practices for Stabilization (“RAPPS”)
- Comply with SPCC requirements in accordance with 40 CFR Part 112;
- Comply with the United States Army Corp of Engineers (USACE) Nationwide 12 General Permit, where applicable;
- Utilize technologies (like underground borings for pipelines), where feasible;
- Educate personnel, agents, contractors, and subcontractors about the requirements of conservation measures, COAs, Stips and provide direction in accordance with the Permit.

Hydrology:

The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility. The berm would be maintained through the life of the wells and after interim reclamation has been completed.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production:

Construction:

General Construction:

- No blasting
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during

construction, and no additional construction shall occur until clearance has been issued by the Authorized Officer.

- All linear surface disturbance activities will avoid sinkholes and other karst features to lessen the possibility of encountering near surface voids during construction, minimize changes to runoff, and prevent untimely leaks and spills from entering the karst drainage system.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

Pad Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.
- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised (i.e. an access road crossing the berm cannot be lower than the berm height).
- Following a rain event, all fluids will vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

Tank Battery Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.
- All tank battery locations and facilities will be lined and bermed.
- The liner should be at least 20 mil in thickness and installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures.
- Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Road Construction:

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.

- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

Leak Detection System:

- A method of detecting leaks is required. The method could incorporate gauges to measure loss, siting valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present.
- A leak detection plan will be submitted to BLM that incorporates an automatic shut off system (see below) to minimize the effects of an undesirable event that could negatively sensitive cave/karst resources.
- Well heads, pipelines (surface and buried), storage tanks, and all supporting equipment should be monitored regularly after installation to promptly identify and fix leaks.

Automatic Shut-off Systems:

- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and groundwater concerns:

Closed Loop System:

- A closed loop system using steel tanks will be utilized during drilling – no pits
- All fluids and cuttings will be hauled off-site and disposed of properly at an authorized site

Rotary Drilling with Fresh Water:

- Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

- The kick off point for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

- ALL lost circulation zones between surface and the base of the cave occurrence zone will be logged and reported in the drilling report.
- If a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, regardless of the type of drilling machinery used, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

- Additional plugging conditions of approval may be required upon well abandonment in high and medium karst potential occurrence zones.
- The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

- The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice.
- If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

Range**Livestock Watering Requirement**

Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

V. CONSTRUCTION**A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes



Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VI. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

VIII. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	XTO Energy, Inc.
LEASE NO.:	NMNM-015302
WELL NAME & NO.:	Corral Canyon 4 Federal 168H
SURFACE HOLE FOOTAGE:	0140' FSL & 0460' FEL
BOTTOM HOLE FOOTAGE:	0200' FNL & 0330' FEL Sec. 04, T. 25 S., R. 29 E.
LOCATION:	Section 04, T. 25 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input checked="" type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

Medium Cave/Karst

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Rustler, Red Beds, and Delaware.

B. CASING

1. The **16** inch surface casing shall be set at approximately **637** feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **11-3/4** inch intermediate casing is:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**
 - ❖ In Medium Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

8-5/8" Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

3. The minimum required fill of cement behind the **8-5/8** inch intermediate casing, is:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. **DV tool must be 50 feet below previous shoe and minimum of 200 feet above current shoe.** The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool:
 - Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.

- b. Second stage above DV tool:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.
- 4. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
3. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the 11-3/4 inch intermediate casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 11-3/4 inch intermediate casing casing shoe shall be **10,000 (10M)** psi.
Variance approved to use a 5M annular. The annular must be tested to full working pressure (5000 psi.)
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
 - b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
 - c. BOPE tests (minimum of 4 hours)
 - ☒ Eddy County
- Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
4. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
5. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
6. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. A variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer.
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
 - g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 042320



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

05/29/2020

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Stephanie Rabadue

Signed on: 05/17/2018

Title: Regulatory Coordinator

Street Address: 500 W. Illinois St, Ste 100

City: Midland

State: TX

Zip: 79701

Phone: (432)620-6714

Email address: stephanie_rabadue@xtoenergy.com

Field Representative

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



APD ID: 10400052808

Submission Date: 01/02/2020

Highlighted data
reflects the most
recent changes

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400052808

Tie to previous NOS? N

Submission Date: 01/02/2020

BLM Office: CARLSBAD

User: Stephanie Rabadue

Title: Regulatory Coordinator

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM015302

Lease Acres: 1917.02

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: XTO ENERGY INCORPORATED

Operator letter of designation:

Operator Info

Operator Organization Name: XTO ENERGY INCORPORATED

Operator Address: 22777 Springwoods Village Parkway

Zip: 77389

Operator PO Box:

Operator City: Spring

State: TX

Operator Phone: (432)620-6700

Operator Internet Address: Richard_redus@xtoenergy.com

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: WELCH

Pool Name:

Is the proposed well in an area containing other mineral resources? USEABLE WATER,OTHER,NATURAL GAS,OIL

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Is the proposed well in an area containing other mineral resources? USEABLE WATER,OTHER,NATURAL GAS,OIL

Describe other minerals: Produced Water

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** N **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: CC 4 **Number:** 4

Well Class: HORIZONTAL

Fed

Number of Legs: 1

Well Work Type: Drill

Well Type: CONVENTIONAL GAS WELL

Describe Well Type:

Well sub-Type: DELINEATION

Describe sub-type:

Distance to town: 8 Miles

Distance to nearest well: 0 FT

Distance to lease line: 140 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: CC_4_Fed_168H_C102_20191226115840.pdf

Well work start Date: 04/01/2019

Duration: 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum: GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	140	FSL	460	FEL	25S	29E	4	Aliquot SESE	32.152311	-103.982352	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 015302	3000	0	0	Y
KOP Leg #1	140	FSL	460	FEL	25S	29E	4	Aliquot SESE	32.152311	-103.982352	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 015302	-2560	5560	5560	Y
PPP Leg #1-1	330	FSL	330	FEL	25S	29E	4	Aliquot SESE	32.152834	-103.982352	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 015302	-7965	11320	10965	Y

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
EXIT Leg #1	330	FNL	330	FEL	25S	29E	4	Lot 1	32.165615	- 103.981978	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 015302	- 7883	15970	10883	Y
BHL Leg #1	200	FNL	330	FEL	25S	29E	4	Lot 1	32.165972	- 103.165972	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 015302	- 7881	16100	10881	Y

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015- 47160	² Pool Code 98220	³ Pool Name Purple Sage; Wolfcamp
⁴ Property Code 328260	⁵ Property Name CORRAL CANYON 4 FEDERAL	
⁷ OGRID No. 005380	⁸ Operator Name XTO ENERGY, INC.	⁶ Well Number 168H
		⁹ Elevation 3,000'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	4	25 S	29 E		140	SOUTH	460	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
I	4	25 S	29 E		200	NORTH	330	EAST	EDDY

¹² Dedicated Acres 320	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--------------------------------------	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>¹⁶</p> <p>SEC. 33 T24S R29E</p> <p>SEC. 34</p> <p>SEC. 4 T25S R29E</p> <p>SEC. 3</p> <p>SEC. 9</p> <p>SEC. 10</p> <p>LOT 4 LOT 3 LOT 2 LOT 1</p> <p>GRID AZ.=359°38'23" HORIZ. DIST.=4,779.40'</p> <p>GRID AZ.=34°03'45" HORIZ. DIST.=230.22'</p> <p>LOT ACREAGE TABLE</p> <table border="1"> <tr> <td>LOT 1</td> <td>39.97 ACRES</td> </tr> <tr> <td>LOT 2</td> <td>39.91 ACRES</td> </tr> <tr> <td>LOT 3</td> <td>39.85 ACRES</td> </tr> <tr> <td>LOT 4</td> <td>39.79 ACRES</td> </tr> </table>	LOT 1	39.97 ACRES	LOT 2	39.91 ACRES	LOT 3	39.85 ACRES	LOT 4	39.79 ACRES	<p>SHL (NAD83 NME)</p> <p>Y = 419,323.1 X = 649,957.7 LAT. = 32.152311 °N LONG. = 103.982352 °W</p> <p>FTP (NAD83 NME)</p> <p>Y = 419,513.9 X = 650,086.6 LAT. = 32.152834 °N LONG. = 103.981933 °W</p> <p>CORNER COORDINATES (NAD83 NME)</p> <table> <tr> <td>A - Y = 424,488.9 N</td> <td>X = 649,052.0 E</td> </tr> <tr> <td>B - Y = 421,832.7 N</td> <td>X = 649,070.6 E</td> </tr> <tr> <td>C - Y = 419,178.7 N</td> <td>X = 649,088.9 E</td> </tr> <tr> <td>D - Y = 424,494.6 N</td> <td>X = 650,385.3 E</td> </tr> <tr> <td>E - Y = 421,839.9 N</td> <td>X = 650,402.3 E</td> </tr> <tr> <td>F - Y = 419,185.6 N</td> <td>X = 650,418.6 E</td> </tr> </table>	A - Y = 424,488.9 N	X = 649,052.0 E	B - Y = 421,832.7 N	X = 649,070.6 E	C - Y = 419,178.7 N	X = 649,088.9 E	D - Y = 424,494.6 N	X = 650,385.3 E	E - Y = 421,839.9 N	X = 650,402.3 E	F - Y = 419,185.6 N	X = 650,418.6 E	<p>LTP (NAD83 NME)</p> <p>Y = 424,163.2 X = 650,057.4 LAT. = 32.165615 °N LONG. = 103.981978 °W</p> <p>BHL (NAD83 NME)</p> <p>Y = 424,293.2 X = 650,056.5 LAT. = 32.165972 °N LONG. = 103.981980 °W</p>	<p>¹⁷ OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature: <u>Stephanie Rabadue</u> Date: <u>11/22/2019</u></p> <p>Printed Name: <u>Stephanie Rabadue</u></p> <p>E-mail Address: <u>stephanie_rabadue@xtoenergy.com</u></p>
	LOT 1	39.97 ACRES																					
	LOT 2	39.91 ACRES																					
	LOT 3	39.85 ACRES																					
LOT 4	39.79 ACRES																						
A - Y = 424,488.9 N	X = 649,052.0 E																						
B - Y = 421,832.7 N	X = 649,070.6 E																						
C - Y = 419,178.7 N	X = 649,088.9 E																						
D - Y = 424,494.6 N	X = 650,385.3 E																						
E - Y = 421,839.9 N	X = 650,402.3 E																						
F - Y = 419,185.6 N	X = 650,418.6 E																						
	<p>SHL (NAD27 NME)</p> <p>Y = 419,264.4 X = 608,773.7 LAT. = 32.152187 °N LONG. = 103.981864 °W</p> <p>FTP (NAD27 NME)</p> <p>Y = 419,455.1 X = 608,902.6 LAT. = 32.152710 °N LONG. = 103.981445 °W</p> <p>CORNER COORDINATES (NAD27 NME)</p> <table> <tr> <td>A - Y = 424,430.0 N</td> <td>X = 607,868.2 E</td> </tr> <tr> <td>B - Y = 421,773.9 N</td> <td>X = 607,886.7 E</td> </tr> <tr> <td>C - Y = 419,120.0 N</td> <td>X = 607,904.9 E</td> </tr> <tr> <td>D - Y = 424,435.7 N</td> <td>X = 609,201.4 E</td> </tr> <tr> <td>E - Y = 421,781.0 N</td> <td>X = 609,218.4 E</td> </tr> <tr> <td>F - Y = 419,126.8 N</td> <td>X = 609,234.6 E</td> </tr> </table>	A - Y = 424,430.0 N	X = 607,868.2 E	B - Y = 421,773.9 N	X = 607,886.7 E	C - Y = 419,120.0 N	X = 607,904.9 E	D - Y = 424,435.7 N	X = 609,201.4 E	E - Y = 421,781.0 N	X = 609,218.4 E	F - Y = 419,126.8 N	X = 609,234.6 E	<p>LTP (NAD27 NME)</p> <p>Y = 424,104.3 X = 608,873.5 LAT. = 32.165490 °N LONG. = 103.981490 °W</p> <p>BHL (NAD27 NME)</p> <p>Y = 424,234.3 X = 608,872.7 LAT. = 32.165848 °N LONG. = 103.981491 °W</p>	<p>¹⁸ SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>11-21-2019 Date of Survey</p> <p>Signature and Seal of Professional Surveyor:</p> <p>MARK DILLON HARP Certificate Number 23786 AR 2018010253</p>								
A - Y = 424,430.0 N	X = 607,868.2 E																						
B - Y = 421,773.9 N	X = 607,886.7 E																						
C - Y = 419,120.0 N	X = 607,904.9 E																						
D - Y = 424,435.7 N	X = 609,201.4 E																						
E - Y = 421,781.0 N	X = 609,218.4 E																						
F - Y = 419,126.8 N	X = 609,234.6 E																						



APD ID: 10400052808

Submission Date: 01/02/2020

Highlighted data
reflects the most
recent changes

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
619810	PERMIAN	3000	0	0	OTHER : Quaternary	NONE	N
619811	RUSTLER	2753	247	247	SILTSTONE	USEABLE WATER	N
619808	TOP SALT	2338	662	662	SALT	NONE	N
619805	BASE OF SALT	273	2727	2727	SALT	NONE	N
619812	DELAWARE	84	2916	2916	SANDSTONE	NATURAL GAS, OIL, OTHER : Produced Water	N
619813	BONE SPRING	-3687	6687	6687	SANDSTONE	NATURAL GAS, OIL, OTHER : Produced Water	N
619809	BONE SPRING 1ST	-4538	7538	7538	SANDSTONE	NATURAL GAS, OIL, OTHER : Produced Water	N
619806	BONE SPRING 2ND	-4884	7884	7884	SANDSTONE	NATURAL GAS, OIL, OTHER : Produced Water	N
619815	BONE SPRING 3RD	-5683	8683	8683	SANDSTONE	NATURAL GAS, OIL, OTHER, USEABLE WATER : produced water	N
619816	WOLFCAMP	-6877	9877	9877	SHALE	NATURAL GAS, OIL, OTHER, USEABLE WATER : produced water	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 10881

Equipment: Once the permanent WH is installed on the 13-3/8 casing, the blow out preventer equipment (BOP) will consist of a 13-5/8 minimum 5M Hydril and a 13-5/8 minimum 10M 3-Ram BOP. MASP should not exceed 5176 psi. In any instance where 10M BOP is required by BLM, XTO requests a variance to utilize 5M annular with 10M ram preventers (a common BOP configuration, which allows use of 10M rams in unlikely event that pressures exceed 5M). Also a variance is requested to test the 5M annular to 70% of working pressure at 3500 psi.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors. Wellhead: Temporary Wellhead - 16" SOW bottom x 16-3/4" 2M top flange. Permanent Wellhead - GE RSH Multibowl System A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

· Wellhead will be installed by manufacturer's representatives. · Manufacturer will monitor welding process to ensure appropriate temperature of seal. · Operator will test the 8-5/8" casing per BLM Onshore Order 2 · Wellhead Manufacturer representative will not be present for BOP test plug installation

Testing Procedure: All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 50% of the working pressure. When nipping up on the 11-3/4", 10M bradenhead and flange, the BOP test will be limited to 10000 psi. When nipping up on the 8-5/8", the BOP will be tested to a minimum of 10000 psi. All BOP tests will include a low pressure test as per BLM regulations. The 10M BOP diagrams are attached. Blind rams will be functioned tested each trip, pipe rams will be functioned tested each day.

Choke Diagram Attachment:

CC_4_Fed_10MCM_20191226112857.pdf

BOP Diagram Attachment:

CC_4_Fed_10M5MB_20191226112905.pdf

Pressure Rating (PSI): 2M

Rating Depth: 740

Equipment: The blow out preventer equipment (BOP) for this well consists of a 13-5/8 minimum 2M Hydril and a 13-5/8 minimum 2M Double Ram BOP.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturers certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors.

Testing Procedure: All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 50% of the working pressure. When nipping up, the BOP test will be limited to 2,000 psi. All BOP tests will include a low pressure test as per BLM regulations. The 2M BOP diagram is attached. Blind rams will be function tested each trip, pipe rams will be function tested each day.

Choke Diagram Attachment:

CC_4_Fed_2MCM_20191226120451.pdf

BOP Diagram Attachment:

CC_4_Fed_2MBOP_20191226120459.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	18.5	16.0	NEW	API	N	0	740	0	740	3000	2260	740	J-55	75	ST&C	3.05	2.94	DRY	12.79	DRY	12.79
2	INTERMEDIATE	14.75	11.75	NEW	API	N	0	2880	0	2880		120	2880	J-55	54	ST&C	2.28	1.19	DRY	3.65	DRY	3.65

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
3	INTERMEDIATE	10.625	8.625	NEW	API	N	0	10000	0	10000		-7000	10000	HCL-80	32	BUTT	1.67	1.08	DRY	2.29	DRY	2.29
4	PRODUCTION	7.875	5.5	NEW	API	N	0	16100	0	10881	2969	-7881	16100	P-110	20	BUTT	1.45	1.33	DRY	2.62	DRY	2.62

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CC_4_Fed_168H_Csg_20191226120544.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CC_4_Fed_168H_Csg_20191226120559.pdf

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Casing Attachments

Casing ID: 3 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CC_4_Fed_168H_Csg_20191226120609.pdf

Casing ID: 4 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CC_4_Fed_168H_Csg_20191226120529.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	740	220	1.87	12.9	411.4	100	Econocem-HLTRRC	None
SURFACE	Tail				200	1.35	14.8	270	100	Halcem-C	2% CaCl
INTERMEDIATE	Lead		0	2880	1060	1.87	12.9	1982.2	100	EconoCem-HLTRRC	None
INTERMEDIATE	Tail				370	1.35	14.8	499.5	100	Halcem-C	2% CaCl
INTERMEDIATE	Lead	2930	0	2930	540	1.88	12.9	1015.2	100	Halcem-C	2% CaCl

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Tail				150	1.33	14.8	199.5	100	Halcem-C	2%CaCl
INTERMEDIATE	Lead	2701	2701	1000 0	1350	1.88	12.9	2538	100	Halcem-C	2% CaCl
INTERMEDIATE	Tail				310	1.33	14.8	412.3	100	Halcem-C	2% CaCl
PRODUCTION	Lead		0	1610 0	810	2.69	10.5	2178. 9	30	NeoCem	None
PRODUCTION	Tail				870	1.61	13.2	1400. 7	30	VersaCem	None

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: The necessary mud products for weight addition a fluid loss control will be on location at all times.

Describe the mud monitoring system utilized: A Pason or Totco will be used to detect changes in loss or gain of mud volume.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	740	OTHER : FW/Native	8.4	8.8							A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hrs to determine: density, viscosity, strength, filtration and pH as necessary. Solids control equipment will be used to operate as a closed loop system.

Operator Name: XTO ENERGY INCORPORATED**Well Name:** CORRAL CANYON 4 FEDERAL**Well Number:** 168H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
740	2880	OTHER : Brine/Gel Sweeps	9.8	10.2							A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hrs to determine: density, viscosity, strength, filtration and pH as necessary. Solids control equipment will be used to operate as a closed loop system.
1000 0	1088 1	POLYMER	13.2	13.5							A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hrs to determine: density, viscosity, strength, filtration and pH as necessary. Solids control equipment will be used to operate as a closed loop system.
2880	1000 0	OTHER : FW / Cut Brine	8.7	10							A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hrs to determine: density, viscosity, strength, filtration and pH as necessary. Solids control equipment will be used to operate as a closed loop system.

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Mud logging Unit (2 man) on below intermediate casing. Catch 20' samples fr/10000' to TD

List of open and cased hole logs run in the well:

CEMENT BOND LOG,COMPENSATED NEUTRON LOG,DIRECTIONAL SURVEY,GAMMA RAY LOG,MUD LOG/GEOLOGIC LITHOLOGY LOG,

Coring operation description for the well:

No coring will take place on this well.

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 7468

Anticipated Surface Pressure: 5055

Anticipated Bottom Hole Temperature(F): 150

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

CC_4_Fed_H2S_D_P4_20191226115328.pdf

CC_4_Fed_H2S_Plan_20191226093238.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

CC_4_Fed_168H_DD_20191226120707.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:


CC_4_Fed_GCP_20191226100304.pdf

Other Variance attachment:

CC_4_Fed_11.75x5.5MBS_20191226093323.pdf


CC_4_Fed_FH_20191226093331.pdf

CC_4_Fed_WWC_20191226100313.pdf




5M Choke Manifold Diagram
XTO Energy, Inc

**Drilling Operations
Choke Manifold
5M Service**




SRR & A

2000# BOP
XTO




Drilling Operations Choke Manifold 10M Service

10M Choke Manifold Diagram
XTO Energy, Inc.




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

**Drilling Operations
Choke Manifold
2M & 3M Service**




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations Choke Manifold 2M & 3M Service




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations Choke Manifold 2M & 3M Service




Drilling Operations Choke Manifold 10M Service

10M Choke Manifold Diagram
XTO Energy, Inc.




2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service




Drilling Operations Choke Manifold 10M Service

10M Choke Manifold Diagram
XTO Energy, Inc.



2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service



2M & 3M Choke Manifold Diagram
XTO

Drilling Operations
Choke Manifold
2M & 3M Service

Fill Line

Flowline

5000# (5M)
BOP

Annular Preventer

Pipe Rams

Blind Rams

2" Minimum Kill Line

Kill Line

*2 Valves Minimum
(and 1 check valve)*

Drilling Spool


3" Minimum Choke Line


Choke Line


2 Valves Minimum


5000# BOP
XTO Energy, Inc

Wellhead
Assembly











SRR & A


2000# BOP
XTO







SRR & A

2000# BOP
XTO









SRR & A


2000# BOP
XTO




SRR & A

2000# BOP
XTO










SRR & A

2000# BOP
XTO







Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
18-1/2"	0' – 740'	16"	75	STC	J-55	New	2.94	3.05	12.79
14-3/4"	0' – 2880'	11-3/4"	54	STC	J-55	New	1.19	2.28	3.65
10-5/8"	0' – 10000'	8-5/8"	32	BTC	HCL-80	New	1.08	1.67	2.29
7-7/8"	0' – 16100'	5-1/2"	20	BTC	P-110	New	1.33	1.45	2.62

- | | | | |
|---|--|--|--|
| - XTO requests to not utilize centralizers in the curve and lateral | | | |
| - 11-3/4" Collapse analyzed using 50% evacuation based on regional experience. | | | |
| - 8-5/8" Collapse analyzed using 33% evacuation based on regional experience. | | | |
| - 5-1/2" Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35 | | | |
| - Test on 2M Annular & Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less | | | |

Wellhead:

Temporary Wellhead

- 16" SOW bottom x 16-3/4" 2M top flange.

Permanent Wellhead – GE RSH Multibowl System

A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom

B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

- | | |
|---|--|
| - Wellhead will be installed by manufacturer's representatives. | |
| - Manufacturer will monitor welding process to ensure appropriate temperature of seal. | |
| - Operator will test the 8-5/8" casing per BLM Onshore Order 2 | |
| - Wellhead Manufacturer representative will not be present for BOP test plug installation | |

Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
18-1/2"	0' – 740'	16"	75	STC	J-55	New	2.94	3.05	12.79
14-3/4"	0' – 2880'	11-3/4"	54	STC	J-55	New	1.19	2.28	3.65
10-5/8"	0' – 10000'	8-5/8"	32	BTC	HCL-80	New	1.08	1.67	2.29
7-7/8"	0' – 16100'	5-1/2"	20	BTC	P-110	New	1.33	1.45	2.62

- | | | | |
|---|--|--|--|
| - XTO requests to not utilize centralizers in the curve and lateral | | | |
| - 11-3/4" Collapse analyzed using 50% evacuation based on regional experience. | | | |
| - 8-5/8" Collapse analyzed using 33% evacuation based on regional experience. | | | |
| - 5-1/2" Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35 | | | |
| - Test on 2M Annular & Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less | | | |

Wellhead:

Temporary Wellhead

- 16" SOW bottom x 16-3/4" 2M top flange.

Permanent Wellhead – GE RSH Multibowl System

A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom

B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

- | | |
|---|--|
| - Wellhead will be installed by manufacturer's representatives. | |
| - Manufacturer will monitor welding process to ensure appropriate temperature of seal. | |
| - Operator will test the 8-5/8" casing per BLM Onshore Order 2 | |
| - Wellhead Manufacturer representative will not be present for BOP test plug installation | |

Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
18-1/2"	0' – 740'	16"	75	STC	J-55	New	2.94	3.05	12.79
14-3/4"	0' – 2880'	11-3/4"	54	STC	J-55	New	1.19	2.28	3.65
10-5/8"	0' – 10000'	8-5/8"	32	BTC	HCL-80	New	1.08	1.67	2.29
7-7/8"	0' – 16100'	5-1/2"	20	BTC	P-110	New	1.33	1.45	2.62

- | | | | |
|---|--|--|--|
| - XTO requests to not utilize centralizers in the curve and lateral | | | |
| - 11-3/4" Collapse analyzed using 50% evacuation based on regional experience. | | | |
| - 8-5/8" Collapse analyzed using 33% evacuation based on regional experience. | | | |
| - 5-1/2" Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35 | | | |
| - Test on 2M Annular & Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less | | | |

Wellhead:

Temporary Wellhead

- 16" SOW bottom x 16-3/4" 2M top flange.

Permanent Wellhead – GE RSH Multibowl System

A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom

B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

- | | |
|---|--|
| - Wellhead will be installed by manufacturer's representatives. | |
| - Manufacturer will monitor welding process to ensure appropriate temperature of seal. | |
| - Operator will test the 8-5/8" casing per BLM Onshore Order 2 | |
| - Wellhead Manufacturer representative will not be present for BOP test plug installation | |

Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
18-1/2"	0' – 740'	16"	75	STC	J-55	New	2.94	3.05	12.79
14-3/4"	0' – 2880'	11-3/4"	54	STC	J-55	New	1.19	2.28	3.65
10-5/8"	0' – 10000'	8-5/8"	32	BTC	HCL-80	New	1.08	1.67	2.29
7-7/8"	0' – 16100'	5-1/2"	20	BTC	P-110	New	1.33	1.45	2.62

- | | | | |
|---|--|--|--|
| - XTO requests to not utilize centralizers in the curve and lateral | | | |
| - 11-3/4" Collapse analyzed using 50% evacuation based on regional experience. | | | |
| - 8-5/8" Collapse analyzed using 33% evacuation based on regional experience. | | | |
| - 5-1/2" Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35 | | | |
| - Test on 2M Annular & Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less | | | |

Wellhead:

Temporary Wellhead

- 16" SOW bottom x 16-3/4" 2M top flange.

Permanent Wellhead – GE RSH Multibowl System

A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom


B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

- | | |
|---|--|
| - Wellhead will be installed by manufacturer's representatives. | |
| - Manufacturer will monitor welding process to ensure appropriate temperature of seal. | |
| - Operator will test the 8-5/8" casing per BLM Onshore Order 2 | |
| - Wellhead Manufacturer representative will not be present for BOP test plug installation | |



Prevailing Winds
Direction SW

H₂S Briefing Areas and Alarm Locations





HYDROGEN SULFIDE (H₂S) CONTINGENCY PLAN

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H₂S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the
 - o Detection of H₂S, and
 - o Measures for protection against the gas,
 - o Equipment used for protection and emergency response.

Ignition of Gas source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever this is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

All XTO location personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

CARLSBAD OFFICE – EDDY & LEA COUNTIES

3104 E. Greene St., Carlsbad, NM 88220
Carlsbad, NM

575-887-7329

XTO PERSONNEL:

Kendall Decker, Drilling Manager	903-521-6477
Milton Turman, Drilling Superintendent	817-524-5107
Jeff Raines, Construction Foreman	432-557-3159
Toady Sanders, EH & S Manager	903-520-1601
Wes McSpadden, Production Foreman	575-441-1147

SHERIFF DEPARTMENTS:

Eddy County	575-887-7551
Lea County	575-396-3611

NEW MEXICO STATE POLICE:

575-392-5588

FIRE DEPARTMENTS:

	911
Carlsbad	575-885-2111
Eunice	575-394-2111
Hobbs	575-397-9308
Jal	575-395-2221
Lovington	575-396-2359

HOSPITALS:

	911
Carlsbad Medical Emergency	575-885-2111
Eunice Medical Emergency	575-394-2112
Hobbs Medical Emergency	575-397-9308
Jal Medical Emergency	575-395-2221
Lovington Medical Emergency	575-396-2359

AGENT NOTIFICATIONS:

For Lea County:

Bureau of Land Management – Hobbs	575-393-3612
New Mexico Oil Conservation Division – Hobbs	575-393-6161

For Eddy County:

Bureau of Land Management - Carlsbad	575-234-5972
New Mexico Oil Conservation Division - Artesia	575-748-1283



XTO Energy

Eddy County, NM (NAD-27)

Corral Canyon 4 Fed

#168H

OH

Plan: PERMIT

Standard Planning Report

20 November, 2019



Project: Eddy County, NM (NAD-27)
Site: Corral Canyon 4 Fed
Well: #168H
Wellbore: OH
Design: PERMIT

PROJECT DETAILS: Eddy County, NM (NAD-27)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

WELL DETAILS: #168H

Rig Name:		RKB = 25' @ 3025.00usft		Ground Level: 3000.00	
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	419264.40	608773.70	32.1521866	-103.9818636

DESIGN TARGET DETAILS



Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
CC 4 #168H SHL: 140' FSL/ 460' FEL	0.00	0.00	0.00	419264.40	608773.70	32.1521866	-103.9818636
CC 4 #168H PBHL: 200' FNL/ 330' FEL	10881.58	4969.90	99.00	424234.30	608872.70	32.1658478	-103.9814912
CC 4 #168H LTP	10883.85	4839.90	99.80	424104.30	608873.50	32.1654904	-103.9814900
CC 4 #168H FTP	10965.00	190.70	128.90	419455.10	608902.60	32.1527096	-103.9814451

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	5560.00	0.00	0.00	5560.00	0.00	0.00	0.00	0.00	0.00
3	5809.91	5.00	163.31	5809.59	-10.43	3.13	2.00	163.31	-10.45
4	10362.05	5.00	163.31	10344.42	-390.33	117.00	0.00	0.00	-391.06
5	11320.00	91.00	359.64	10965.00	190.70	128.90	10.00	-163.59	189.89
6	15970.00	91.00	359.64	10883.85	4839.90	99.81	0.00	0.00	4839.18
7	16100.02	91.00	359.64	10881.58	4969.90	99.00	0.00	0.00	4969.18

FORMATION TOP DETAILS

TVDPath	Formation
349.00	Rustler
764.00	Top of Salt
2829.00	Base of Salt
3018.00	Delaware
3899.00	Cherry Canyon
5531.00	Brushy Canyon
6549.00	Basal Brushy
6789.00	Bone Spring
6811.00	Bone Spring Lime
6957.00	Upper Avalon
7387.00	Lower Avalon Shale
7640.00	1st Bone Springs Lime
7719.00	1st Bone Springs Sand
7986.00	2nd Bone Springs Lime
8489.00	2nd Bone Springs Sand
8785.00	3rd Bone Springs Lime
9608.00	3rd Bone Springs Sand
9979.00	Wolfcamp
9993.00	Wolfcamp X
10070.00	Wolfcamp Y
10113.00	Wolfcamp A
10413.00	Wolfcamp B
10613.00	Wolfcamp C
10814.00	Wolfcamp D
10965.00	LP



Vertical Section at 359.64° (1400 usft/in)

The customer should only rely on this document after independently verifying all paths, targets, coordinates, lease and hard lines represented. Any decisions made or wells drilled utilizing this or any other information supplied by Prototype are at the sole risk and responsibility of the user.

Plan: PERMIT (#168H/OH)

Created By: Matthew May Date: 21:05, November 20 2019

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office
☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015-	² Pool Code	³ Pool Name
⁴ Property Code	⁵ Property Name CORRAL CANYON 4 FEDERAL	⁶ Well Number 168H
⁷ OGRID No. 005380	⁸ Operator Name XTO ENERGY, INC.	⁹ Elevation 3,000'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	4	25 S	29 E		140	SOUTH	460	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
1	4	25 S	29 E		200	NORTH	330	EAST	EDDY

¹² Dedicated Acres	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
-------------------------------	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>¹⁶</p> <p>LOT ACREAGE TABLE</p> <table><tr><td>LOT 1</td><td>-</td><td>39.97 ACRES</td></tr><tr><td>LOT 2</td><td>-</td><td>39.91 ACRES</td></tr><tr><td>LOT 3</td><td>-</td><td>39.85 ACRES</td></tr><tr><td>LOT 4</td><td>-</td><td>39.79 ACRES</td></tr></table>	LOT 1	-	39.97 ACRES	LOT 2	-	39.91 ACRES	LOT 3	-	39.85 ACRES	LOT 4	-	39.79 ACRES	<p>SHL (NAD83 NME) Y = 419,323.1 X = 649,957.7 LAT. = 32.152311 °N LONG. = 103.982352 °W</p> <p>LTP (NAD83 NME) Y = 424,163.2 X = 650,057.4 LAT. = 32.165615 °N LONG. = 103.981978 °W</p> <p>FTP (NAD83 NME) Y = 419,513.9 X = 650,086.6 LAT. = 32.152834 °N LONG. = 103.981933 °W</p> <p>BHL (NAD83 NME) Y = 424,293.2 X = 650,056.5 LAT. = 32.165972 °N LONG. = 103.981980 °W</p> <p>CORNER COORDINATES (NAD83 NME) A - Y = 424,488.9 N , X = 649,052.0 E B - Y = 421,832.7 N , X = 649,070.6 E C - Y = 419,178.7 N , X = 649,088.9 E D - Y = 424,494.6 N , X = 650,385.3 E E - Y = 421,839.9 N , X = 650,402.3 E F - Y = 419,185.6 N , X = 650,418.6 E</p> <p>SHL (NAD27 NME) Y = 419,264.4 X = 608,773.7 LAT. = 32.152187 °N LONG. = 103.981864 °W</p> <p>LTP (NAD27 NME) Y = 424,104.3 X = 608,873.5 LAT. = 32.165490 °N LONG. = 103.981490 °W</p> <p>FTP (NAD27 NME) Y = 419,455.1 X = 608,902.6 LAT. = 32.152710 °N LONG. = 103.981445 °W</p> <p>BHL (NAD27 NME) Y = 424,234.3 X = 608,872.7 LAT. = 32.165848 °N LONG. = 103.981491 °W</p> <p>CORNER COORDINATES (NAD27 NME) A - Y = 424,430.0 N , X = 607,868.2 E B - Y = 421,773.9 N , X = 607,886.7 E C - Y = 419,120.0 N , X = 607,904.9 E D - Y = 424,435.7 N , X = 609,201.4 E E - Y = 421,781.0 N , X = 609,218.4 E F - Y = 419,126.8 N , X = 609,234.6 E</p>	<p>¹⁷ OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature _____ Date _____</p> <p>Printed Name _____</p> <p>E-mail Address _____</p> <p>¹⁸ SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>11-14-2019 Date of Survey</p> <p>Signature and Seal of Professional Surveyor: _____</p> <p>PRELIMINARY, THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED OR VIEWED OR RELIED UPON AS A FINAL SURVEY DOCUMENT</p> <p>MARK DILLON HARP 23786 Certificate Number AR 2018010253</p>
LOT 1	-	39.97 ACRES												
LOT 2	-	39.91 ACRES												
LOT 3	-	39.85 ACRES												
LOT 4	-	39.79 ACRES												



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Project	Eddy County, NM (NAD-27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site		Corral Canyon 4 Fed			
Site Position:		Northing:	418,905.60 usft	Latitude:	32.1512244
From:	Map	Easting:	606,049.80 usft	Longitude:	-103.9906686
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.18 °

Well	#168H					
Well Position	+N/-S	358.80 usft	Northing:	419,264.40 usft	Latitude:	32.1521866
	+E/-W	2,723.90 usft	Easting:	608,773.70 usft	Longitude:	-103.9818636
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	3,000.00 usft

Wellbore	OH				
-----------------	----	--	--	--	--

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	11/20/19	6.88	59.90	47,606

Design	PERMIT			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	359.64

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,560.00	0.00	0.00	5,560.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,809.91	5.00	163.31	5,809.59	-10.43	3.13	2.00	2.00	0.00	163.31	
10,362.05	5.00	163.31	10,344.42	-390.33	117.00	0.00	0.00	0.00	0.00	
11,320.00	91.00	359.64	10,965.00	190.70	128.90	10.00	8.98	-17.09	-163.59	CC 4 #168H FTP
15,970.00	91.00	359.64	10,883.85	4,839.90	99.81	0.00	0.00	0.00	0.00	CC 4 #168H LTP
16,100.02	91.00	359.64	10,881.58	4,969.90	99.00	0.00	0.00	0.00	0.00	CC 4 #168H PBHL:



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
349.00	0.00	0.00	349.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler									
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
764.00	0.00	0.00	764.00	0.00	0.00	0.00	0.00	0.00	0.00
Top of Salt									
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,829.00	0.00	0.00	2,829.00	0.00	0.00	0.00	0.00	0.00	0.00
Base of Salt									
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,018.00	0.00	0.00	3,018.00	0.00	0.00	0.00	0.00	0.00	0.00
Delaware									
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,899.00	0.00	0.00	3,899.00	0.00	0.00	0.00	0.00	0.00	0.00
Cherry Canyon									
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	0.00	0.00
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	0.00	0.00
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00
5,531.00	0.00	0.00	5,531.00	0.00	0.00	0.00	0.00	0.00	0.00
Brushy Canyon									
5,560.00	0.00	0.00	5,560.00	0.00	0.00	0.00	0.00	0.00	0.00
5,600.00	0.80	163.31	5,600.00	-0.27	0.08	-0.27	2.00	2.00	0.00
5,700.00	2.80	163.31	5,699.94	-3.28	0.98	-3.28	2.00	2.00	0.00
5,809.91	5.00	163.31	5,809.59	-10.43	3.13	-10.45	2.00	2.00	0.00
5,900.00	5.00	163.31	5,899.34	-17.95	5.38	-17.99	0.00	0.00	0.00
6,000.00	5.00	163.31	5,998.96	-26.30	7.88	-26.35	0.00	0.00	0.00
6,100.00	5.00	163.31	6,098.58	-34.64	10.38	-34.71	0.00	0.00	0.00
6,200.00	5.00	163.31	6,198.20	-42.99	12.89	-43.07	0.00	0.00	0.00
6,300.00	5.00	163.31	6,297.82	-51.34	15.39	-51.43	0.00	0.00	0.00
6,400.00	5.00	163.31	6,397.44	-59.68	17.89	-59.79	0.00	0.00	0.00
6,500.00	5.00	163.31	6,497.06	-68.03	20.39	-68.15	0.00	0.00	0.00
6,552.14	5.00	163.31	6,549.00	-72.38	21.70	-72.51	0.00	0.00	0.00
Basal Brushy									
6,600.00	5.00	163.31	6,596.68	-76.37	22.89	-76.51	0.00	0.00	0.00
6,700.00	5.00	163.31	6,696.30	-84.72	25.39	-84.88	0.00	0.00	0.00
6,793.06	5.00	163.31	6,789.00	-92.48	27.72	-92.66	0.00	0.00	0.00
Bone Spring									
6,800.00	5.00	163.31	6,795.92	-93.06	27.90	-93.24	0.00	0.00	0.00
6,815.14	5.00	163.31	6,811.00	-94.33	28.27	-94.50	0.00	0.00	0.00
Bone Spring Lime									
6,900.00	5.00	163.31	6,895.54	-101.41	30.40	-101.60	0.00	0.00	0.00
6,961.70	5.00	163.31	6,957.00	-106.56	31.94	-106.76	0.00	0.00	0.00
Upper Avalon									
7,000.00	5.00	163.31	6,995.16	-109.75	32.90	-109.96	0.00	0.00	0.00
7,100.00	5.00	163.31	7,094.78	-118.10	35.40	-118.32	0.00	0.00	0.00
7,200.00	5.00	163.31	7,194.40	-126.44	37.90	-126.68	0.00	0.00	0.00
7,300.00	5.00	163.31	7,294.02	-134.79	40.40	-135.04	0.00	0.00	0.00
7,393.34	5.00	163.31	7,387.00	-142.58	42.74	-142.85	0.00	0.00	0.00
Lower Avalon Shale									
7,400.00	5.00	163.31	7,393.64	-143.14	42.91	-143.40	0.00	0.00	0.00
7,500.00	5.00	163.31	7,493.26	-151.48	45.41	-151.76	0.00	0.00	0.00
7,600.00	5.00	163.31	7,592.88	-159.83	47.91	-160.12	0.00	0.00	0.00
7,647.30	5.00	163.31	7,640.00	-163.77	49.09	-164.08	0.00	0.00	0.00
1st Bone Springs Lime									
7,700.00	5.00	163.31	7,692.50	-168.17	50.41	-168.49	0.00	0.00	0.00
7,726.61	5.00	163.31	7,719.00	-170.39	51.08	-170.71	0.00	0.00	0.00
1st Bone Springs Sand									
7,800.00	5.00	163.31	7,792.12	-176.52	52.91	-176.85	0.00	0.00	0.00
7,900.00	5.00	163.31	7,891.74	-184.86	55.41	-185.21	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
7,994.62	5.00	163.31	7,986.00	-192.76	57.78	-193.12	0.00	0.00	0.00
2nd Bone Springs Lime									
8,000.00	5.00	163.31	7,991.36	-193.21	57.92	-193.57	0.00	0.00	0.00
8,100.00	5.00	163.31	8,090.98	-201.55	60.42	-201.93	0.00	0.00	0.00
8,200.00	5.00	163.31	8,190.59	-209.90	62.92	-210.29	0.00	0.00	0.00
8,300.00	5.00	163.31	8,290.21	-218.25	65.42	-218.65	0.00	0.00	0.00
8,400.00	5.00	163.31	8,389.83	-226.59	67.92	-227.01	0.00	0.00	0.00
8,499.54	5.00	163.31	8,489.00	-234.90	70.41	-235.34	0.00	0.00	0.00
2nd Bone Springs Sand									
8,500.00	5.00	163.31	8,489.45	-234.94	70.42	-235.37	0.00	0.00	0.00
8,600.00	5.00	163.31	8,589.07	-243.28	72.93	-243.74	0.00	0.00	0.00
8,700.00	5.00	163.31	8,688.69	-251.63	75.43	-252.10	0.00	0.00	0.00
8,796.67	5.00	163.31	8,785.00	-259.70	77.85	-260.18	0.00	0.00	0.00
3rd Bone Springs Lime									
8,800.00	5.00	163.31	8,788.31	-259.97	77.93	-260.46	0.00	0.00	0.00
8,900.00	5.00	163.31	8,887.93	-268.32	80.43	-268.82	0.00	0.00	0.00
9,000.00	5.00	163.31	8,987.55	-276.66	82.93	-277.18	0.00	0.00	0.00
9,100.00	5.00	163.31	9,087.17	-285.01	85.43	-285.54	0.00	0.00	0.00
9,200.00	5.00	163.31	9,186.79	-293.36	87.93	-293.90	0.00	0.00	0.00
9,300.00	5.00	163.31	9,286.41	-301.70	90.44	-302.26	0.00	0.00	0.00
9,400.00	5.00	163.31	9,386.03	-310.05	92.94	-310.62	0.00	0.00	0.00
9,500.00	5.00	163.31	9,485.65	-318.39	95.44	-318.99	0.00	0.00	0.00
9,600.00	5.00	163.31	9,585.27	-326.74	97.94	-327.35	0.00	0.00	0.00
9,622.82	5.00	163.31	9,608.00	-328.64	98.51	-329.25	0.00	0.00	0.00
3rd Bone Springs Sand									
9,700.00	5.00	163.31	9,684.89	-335.08	100.44	-335.71	0.00	0.00	0.00
9,800.00	5.00	163.31	9,784.51	-343.43	102.94	-344.07	0.00	0.00	0.00
9,900.00	5.00	163.31	9,884.13	-351.77	105.45	-352.43	0.00	0.00	0.00
9,995.23	5.00	163.31	9,979.00	-359.72	107.83	-360.39	0.00	0.00	0.00
Wolfcamp									
10,000.00	5.00	163.31	9,983.75	-360.12	107.95	-360.79	0.00	0.00	0.00
10,009.29	5.00	163.31	9,993.00	-360.89	108.18	-361.57	0.00	0.00	0.00
Wolfcamp X									
10,086.58	5.00	163.31	10,070.00	-367.34	110.11	-368.03	0.00	0.00	0.00
Wolfcamp Y									
10,100.00	5.00	163.31	10,083.37	-368.46	110.45	-369.15	0.00	0.00	0.00
10,129.74	5.00	163.31	10,113.00	-370.95	111.19	-371.64	0.00	0.00	0.00
Wolfcamp A									
10,200.00	5.00	163.31	10,182.99	-376.81	112.95	-377.51	0.00	0.00	0.00
10,300.00	5.00	163.31	10,282.61	-385.16	115.45	-385.87	0.00	0.00	0.00
10,362.05	5.00	163.31	10,344.42	-390.33	117.00	-391.06	0.00	0.00	0.00
10,400.00	1.73	125.01	10,382.31	-392.25	117.95	-392.98	10.00	-8.61	-100.93
10,430.71	2.51	33.91	10,413.00	-391.96	118.70	-392.69	10.00	2.53	-296.65
Wolfcamp B									
10,450.00	4.24	19.06	10,432.26	-390.93	119.17	-391.67	10.00	9.00	-76.99
10,500.00	9.11	8.50	10,481.91	-385.27	120.36	-386.01	10.00	9.74	-21.12
10,550.00	14.07	5.30	10,530.87	-375.29	121.51	-376.05	10.00	9.92	-6.39
10,600.00	19.05	3.76	10,578.78	-361.09	122.60	-361.85	10.00	9.96	-3.10
10,636.63	22.70	3.04	10,613.00	-348.06	123.37	-348.83	10.00	9.98	-1.95
Wolfcamp C									
10,650.00	24.04	2.83	10,625.28	-342.77	123.64	-343.54	10.00	9.98	-1.57
10,700.00	29.03	2.21	10,669.99	-320.46	124.61	-321.23	10.00	9.98	-1.24



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,750.00	34.03	1.76	10,712.60	-294.33	125.51	-295.12	10.00	9.99	-0.91
10,800.00	39.02	1.41	10,752.77	-264.60	126.33	-265.39	10.00	9.99	-0.70
10,850.00	44.02	1.13	10,790.19	-231.47	127.06	-232.27	10.00	9.99	-0.56
10,884.11	47.43	0.96	10,814.00	-207.06	127.50	-207.86	10.00	9.99	-0.48
Wolfcamp D									
10,900.00	49.02	0.89	10,824.59	-195.21	127.69	-196.01	10.00	9.99	-0.44
10,950.00	54.01	0.69	10,855.70	-156.09	128.23	-156.89	10.00	10.00	-0.40
11,000.00	59.01	0.51	10,883.28	-114.40	128.67	-115.21	10.00	10.00	-0.35
11,050.00	64.01	0.35	10,907.12	-70.47	129.00	-71.28	10.00	10.00	-0.32
11,100.00	69.01	0.21	10,927.04	-24.63	129.22	-25.45	10.00	10.00	-0.29
11,150.00	74.00	0.07	10,942.90	22.77	129.33	21.96	10.00	10.00	-0.27
11,200.00	79.00	359.94	10,954.56	71.37	129.34	70.56	10.00	10.00	-0.26
11,250.00	84.00	359.81	10,961.95	120.81	129.23	119.99	10.00	10.00	-0.25
11,300.00	89.00	359.69	10,965.00	170.70	129.02	169.88	10.00	10.00	-0.25
LP									
11,320.00	91.00	359.64	10,965.00	190.70	128.90	189.89	10.00	10.00	-0.25
11,400.00	91.00	359.64	10,963.60	270.68	128.40	269.87	0.00	0.00	0.00
11,500.00	91.00	359.64	10,961.86	370.67	127.77	369.86	0.00	0.00	0.00
11,600.00	91.00	359.64	10,960.11	470.65	127.15	469.84	0.00	0.00	0.00
11,700.00	91.00	359.64	10,958.37	570.63	126.52	569.83	0.00	0.00	0.00
11,800.00	91.00	359.64	10,956.62	670.61	125.90	669.81	0.00	0.00	0.00
11,900.00	91.00	359.64	10,954.88	770.60	125.27	769.79	0.00	0.00	0.00
12,000.00	91.00	359.64	10,953.13	870.58	124.65	869.78	0.00	0.00	0.00
12,100.00	91.00	359.64	10,951.39	970.56	124.02	969.76	0.00	0.00	0.00
12,200.00	91.00	359.64	10,949.64	1,070.55	123.40	1,069.75	0.00	0.00	0.00
12,300.00	91.00	359.64	10,947.90	1,170.53	122.77	1,169.73	0.00	0.00	0.00
12,400.00	91.00	359.64	10,946.15	1,270.51	122.14	1,269.72	0.00	0.00	0.00
12,500.00	91.00	359.64	10,944.41	1,370.49	121.52	1,369.70	0.00	0.00	0.00
12,600.00	91.00	359.64	10,942.66	1,470.48	120.89	1,469.69	0.00	0.00	0.00
12,700.00	91.00	359.64	10,940.92	1,570.46	120.27	1,569.67	0.00	0.00	0.00
12,800.00	91.00	359.64	10,939.17	1,670.44	119.64	1,669.66	0.00	0.00	0.00
12,900.00	91.00	359.64	10,937.43	1,770.43	119.02	1,769.64	0.00	0.00	0.00
13,000.00	91.00	359.64	10,935.68	1,870.41	118.39	1,869.63	0.00	0.00	0.00
13,100.00	91.00	359.64	10,933.94	1,970.39	117.77	1,969.61	0.00	0.00	0.00
13,200.00	91.00	359.64	10,932.19	2,070.37	117.14	2,069.60	0.00	0.00	0.00
13,300.00	91.00	359.64	10,930.44	2,170.36	116.51	2,169.58	0.00	0.00	0.00
13,400.00	91.00	359.64	10,928.70	2,270.34	115.89	2,269.57	0.00	0.00	0.00
13,500.00	91.00	359.64	10,926.95	2,370.32	115.26	2,369.55	0.00	0.00	0.00
13,600.00	91.00	359.64	10,925.21	2,470.31	114.64	2,469.54	0.00	0.00	0.00
13,700.00	91.00	359.64	10,923.46	2,570.29	114.01	2,569.52	0.00	0.00	0.00
13,800.00	91.00	359.64	10,921.72	2,670.27	113.39	2,669.51	0.00	0.00	0.00
13,900.00	91.00	359.64	10,919.97	2,770.25	112.76	2,769.49	0.00	0.00	0.00
14,000.00	91.00	359.64	10,918.23	2,870.24	112.14	2,869.48	0.00	0.00	0.00
14,100.00	91.00	359.64	10,916.48	2,970.22	111.51	2,969.46	0.00	0.00	0.00
14,200.00	91.00	359.64	10,914.74	3,070.20	110.89	3,069.44	0.00	0.00	0.00
14,300.00	91.00	359.64	10,912.99	3,170.18	110.26	3,169.43	0.00	0.00	0.00
14,400.00	91.00	359.64	10,911.25	3,270.17	109.63	3,269.41	0.00	0.00	0.00
14,500.00	91.00	359.64	10,909.50	3,370.15	109.01	3,369.40	0.00	0.00	0.00
14,600.00	91.00	359.64	10,907.76	3,470.13	108.38	3,469.38	0.00	0.00	0.00
14,700.00	91.00	359.64	10,906.01	3,570.12	107.76	3,569.37	0.00	0.00	0.00
14,800.00	91.00	359.64	10,904.27	3,670.10	107.13	3,669.35	0.00	0.00	0.00
14,900.00	91.00	359.64	10,902.52	3,770.08	106.51	3,769.34	0.00	0.00	0.00
15,000.00	91.00	359.64	10,900.78	3,870.06	105.88	3,869.32	0.00	0.00	0.00
15,100.00	91.00	359.64	10,899.03	3,970.05	105.26	3,969.31	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,200.00	91.00	359.64	10,897.28	4,070.03	104.63	4,069.29	0.00	0.00	0.00
15,300.00	91.00	359.64	10,895.54	4,170.01	104.00	4,169.28	0.00	0.00	0.00
15,400.00	91.00	359.64	10,893.79	4,270.00	103.38	4,269.26	0.00	0.00	0.00
15,500.00	91.00	359.64	10,892.05	4,369.98	102.75	4,369.25	0.00	0.00	0.00
15,600.00	91.00	359.64	10,890.30	4,469.96	102.13	4,469.23	0.00	0.00	0.00
15,700.00	91.00	359.64	10,888.56	4,569.94	101.50	4,569.22	0.00	0.00	0.00
15,800.00	91.00	359.64	10,886.81	4,669.93	100.88	4,669.20	0.00	0.00	0.00
15,900.00	91.00	359.64	10,885.07	4,769.91	100.25	4,769.19	0.00	0.00	0.00
15,970.00	91.00	359.64	10,883.85	4,839.90	99.81	4,839.18	0.00	0.00	0.00
16,000.00	91.00	359.64	10,883.32	4,869.89	99.63	4,869.17	0.00	0.00	0.00
16,100.02	91.00	359.64	10,881.58	4,969.90	99.00	4,969.18	0.00	0.00	0.00

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
CC 4 #168H SHL: 140' - plan hits target center - Point	0.00	0.00	0.00	0.00	0.00	419,264.40	608,773.70	32.1521866	-103.9818636
CC 4 #168H PBHL: 210' - plan hits target center - Point	0.00	0.00	10,881.58	4,969.90	99.00	424,234.30	608,872.70	32.1658478	-103.9814912
CC 4 #168H LTP - plan misses target center by 0.01usft at 15970.00usft MD (10883.85 TVD, 4839.90 N, 99.81 E) - Point	0.00	0.00	10,883.85	4,839.90	99.80	424,104.30	608,873.50	32.1654904	-103.9814900
CC 4 #168H FTP - plan hits target center - Point	0.00	0.00	10,965.00	190.70	128.90	419,455.10	608,902.60	32.1527097	-103.9814451



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #168H
Company:	XTO Energy	TVD Reference:	RKB = 25' @ 3025.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 25' @ 3025.00usft
Site:	Corral Canyon 4 Fed	North Reference:	Grid
Well:	#168H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PERMIT		

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
349.00	349.00	Rustler			
764.00	764.00	Top of Salt			
2,829.00	2,829.00	Base of Salt			
3,018.00	3,018.00	Delaware			
3,899.00	3,899.00	Cherry Canyon			
5,531.00	5,531.00	Brushy Canyon			
6,552.14	6,549.00	Basal Brushy			
6,793.06	6,789.00	Bone Spring			
6,815.14	6,811.00	Bone Spring Lime			
6,961.70	6,957.00	Upper Avalon			
7,393.34	7,387.00	Lower Avalon Shale			
7,647.30	7,640.00	1st Bone Springs Lime			
7,726.61	7,719.00	1st Bone Springs Sand			
7,994.62	7,986.00	2nd Bone Springs Lime			
8,499.54	8,489.00	2nd Bone Springs Sand			
8,796.67	8,785.00	3rd Bone Springs Lime			
9,622.82	9,608.00	3rd Bone Springs Sand			
9,995.23	9,979.00	Wolfcamp			
10,009.29	9,993.00	Wolfcamp X			
10,086.58	10,070.00	Wolfcamp Y			
10,129.74	10,113.00	Wolfcamp A			
10,430.71	10,413.00	Wolfcamp B			
10,636.63	10,613.00	Wolfcamp C			
10,884.11	10,814.00	Wolfcamp D			
11,300.00	10,965.00	LP			

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office

GAS CAPTURE PLAN

Date: 11/22/2019

☒ Original Operator & OGRID No.: XTO Energy, Inc [005380] _____
☐ Amended - Reason for Amendment: _____

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).

Well(s)/Production Facility – Name of facility: Corral Canyon Org CTB

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Corral Canyon 9-4 Fed 102H		L-9-25S-29E	2112'FSL & 362'FWL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 9-4 Fed 121H		L-9-25S-29E	2081'FSL & 363'FWL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 9-4 Fed 122H		L-9-25S-29E	2051'FSL & 364'FWL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 9-4 Fed 161H		L-9-25S-29E	2021'FS: & 365'FWL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 9-4 Fed 162H		L-9-25S-29E	1991'FSL & 366'FWL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 124H		C-9-25S-29E	145'FNL & 2130'FWL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 104H		C-9-25S-29E	175'FNL & 2130'FWL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 103H		C-9-25S-29E	205'FNL & 2130'FWL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 164H		C-9-25S-29E	235'FNL & 2130'FWL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 163H		C-9-25S-29E	265'FNL & 2130'FWL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 125H		O-4-25S-29E	170'FSL & 2060'FEL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 105H		O-4-25S-29E	170'FSL & 2030'FEL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 126H		O-4-25S-29E	170'FSL & 1980'FEL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 165H		O-4-25S-29E	70'FSL & 2030'FEL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 166H		O-4-25S-29E	70'FSL & 1980'FEL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 108H		P-4-25S-29E	230'FSL & 460'FEL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 127H		P-4-25S-29E	200'FSL & 460'FEL	6500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 107H		P-4-25S-29E	170'FSL & 460'FEL	4500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 168H		P-4-25S-29E	140'FSL & 460'FEL	8500MCF/D	Flared/Sold	CTB Connected to PL
Corral Canyon 4 Federal 167H		P-4-25S-29E	110'FSL & 460'FEL	8500MCF/D	Flared/Sold	CTB Connected to PL

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to Enlink and will be connected to Enlink low/high pressure gathering system located in Loving County, Texas. It will require 0' of pipeline to connect the facility to low/high pressure gathering system. XTO Energy, Inc. provides (periodically) to Enlink a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, XTO Energy, Inc. and Enlink have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at Enlink Processing Plant located in Block 27, Section 4, Loving County, Texas. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on Enlink system at that time. Based on current information, it is XTO Energy, Inc.'s belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
 - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
 - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
 - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines



GATES E & S NORTH AMERICA, INC
DU-TEX
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405


PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: crpe&s@gates.com
WEB: www.gates.com


GRADE D PRESSURE TEST CERTIFICATE

Customer:	AUSTIN DISTRIBUTING	Test Date:	6/8/2014
Customer Ref.:	PENDING	Hose Serial No.:	D-060814-1
Invoice No.:	201709	Created By:	NORMA
Product Description:	FD3-042.0R41/16.5KFLGE/E LE		
End Filling 1:	4 1/16 in.5K FLG	End Filling 2:	4 1/16 in.5K FLG
Gates Part No.:	4274-6001	Assembly Code:	L33090011513D-060814-1
Working Pressure:	5,000 PSI	Test Pressure:	7,500 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 7,500 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality:	Signature:	Technical Supervisor:	Signature:
Date:	Date:	Date:	Date:
6/8/2014	6/8/2014	6/8/2014	6/8/2014
QUALITY		PRODUCTION	





10,000 PSI Annular BOP Variance Request

XTO Energy/XTO Permian Op. request a variance to use a 5000 psi annular BOP with a 10,000 psi BOP stack. The component and compatibility tables along with the general well control plans demonstrate how the 5000 psi annular BOP will be protected from pressures that exceed its rated working pressure (RWP). The pressure at which the control of the wellbore is transferred from the annular preventer to another available preventer will not exceed 3500 psi (70% of the RWP of the 5000 psi annular BOPL).

1. Component and Preventer Compatibility Tables

The tables below outline the tubulars and the compatible preventers in use. This table, combined with the drilling fluid, documents that two barriers to flow will be maintained at all times.

8-1/2" Production Hole Section 10M psi Requirement					
Component	OD	Primary Preventer	RWP	Alternate Preventer(s)	RWP
Drillpipe	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
HWDP	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
Jars	6.500"	Annular	5M	-	-
DCs and MWD tools	6.500"-8.000"	Annular	5M	-	-
Mud Motor	6.750"-8.000"	Annular	5M	-	-
Production Casing	5-1/2"	Annular	5M	-	-
Open-Hole	-	Blind Rams	10M	-	-

2. Well Control Procedures

Below are the minimal high-level tasks prescribed to assure a proper shut-in while drilling, tripping, running casing, pipe out of the hole (open hole), and moving the BHA through the BOPs. At least one well control drill will be performed weekly per crew to demonstrate compliance with the procedure and well control plan. The well control drill will be recorded in the daily drilling log. The type of drill will be determined by the ongoing operations, but reasonable attempts will be made to vary the type of drill conducted (pit, trip, open hole, choke, etc.). This well control plan will be available for review by rig personnel in the XTO Energy/Permian Operating drilling supervisor's office on location and on the rig floor. All BOP equipment will be tested as per Onshore O&G Order No. 2 with the exception of the 5000 psi annular which will be tested to 70% of its RWP.

General Procedure While Drilling

1. Sound alarm (alert crew)
2. Space out drill string
3. Shut down pumps (stop pumps and rotary)
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan

9. If pressure has built or is anticipated during the kill to reach 70% or greater of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure While Tripping

1. Sound alarm (alert crew)
2. Stab full-opening safety valve & close
3. Space out drill string
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan
9. If pressure has built or is anticipated during the kill to reach 70% of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure While Running Production Casing

1. Sound alarm (alert crew)
2. Stab crossover and full-opening safety valve and close
3. Space out string
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan
9. If pressure has built or is anticipated during the kill to reach 70% or greater of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure With No Pipe In Hole (Open Hole)

1. Sound alarm (alert crew)
2. Shut-in with blind rams (HCR & choke will already be in the closed position)
3. Confirm shut-in
4. Notify toolpusher/company representative
5. Read and record the following:
 - a. SICP
 - b. Pit gain
 - c. Time
6. Regroup and identify forward plan

General Procedures While Pulling BHA Through Stack

1. PRIOR to pulling last joint of drillpipe through stack:
 - a. Perform flow check. If flowing, continue to (b).
 - b. Sound alarm (alert crew)
 - c. Stab full-opening safety valve and close
 - d. Space out drill string with tool joint just beneath the upper variable bore rams
 - e. Shut-in using upper variable bore rams (HCR & choke will already be in the closed position)
 - f. Confirm shut-in
 - g. Notify toolpusher/company representative
 - h. Read and record the following:
 - i. SIDPP & SICP
 - ii. Pit gain
 - iii. Time
 - i. Regroup and identify forward plan
2. With BHA in the stack and compatible ram preventer and pipe combination immediately available:
 - a. Sound alarm (alert crew)
 - b. Stab crossover and full-opening safety valve and close
 - c. Space out drill string with upset just beneath the upper variable bore rams
 - d. Shut-in using upper variable bore rams (HCR & choke will already be in the closed position)
 - e. Confirm shut-in
 - f. Notify toolpusher/company representative
 - g. Read and record the following:
 - i. SIDPP & SICP

- ii. Pit gain
 - iii. Time
 - h. Regroup and identify forward plan
- 3. With BHA in the stack and NO compatible ram preventer and pipe combination immediately available:
 - a. Sound alarm (alert crew)
 - b. If possible, pull string clear of the stack and follow "Open Hole" procedure.
 - c. If impossible to pull string clear of the stack:
 - d. Stab crossover, make up one joint/stand of drillpipe and full-opening safety valve and close
 - e. Space out drill string with tooljoint just beneath the upper variable bore ram
 - f. Shut-in using upper variable bore ram (HCR & choke will already be in the closed position)
 - g. Confirm shut-in
 - h. Notify toolpusher/company representative
 - i. Read and record the following:
 - i. SIDPP & SICP
 - ii. Pit gain
 - iii. Time
 - j. Regroup and identify forward plan



APD ID: 10400052808

Submission Date: 01/02/2020

Highlighted data
reflects the most
recent changes

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

CC_4_Fed_168H_ERoad_20191226115714.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? YES

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

CC_4_Fed_1Mile_20191226090730.pdf

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Estimated Production Facilities description: Production Facilities. No additional production facility is required for the wells. Existing facilities in the area will suffice for the project. Which facility the wells flow to will be determined based on surface commingling and facility capability in addition to existing takeaway. Once known, a 3160-5 sundry notification will be submitted with associated flowline needs for the allocated central tank battery. Flowlines. Flowlines are not included in this application. Flowlines and associated routing will be determined once a central tank battery is identified for the wells. Gas & Oil Pipeline. Gas and oil pipelines are not required with this application. All central tank batteries in the area are connected via gas and oil pipeline. Disposal Facilities. Produced water will be piped from location to a disposal facility as needed. Once wells are drilled and completed, a 3160-5 sundry notification will be submitted to BLM in compliance with Onshore Order 7. Flare. A flare is not associated with this application. Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as shale green that reduce the visual impacts of the built environment. Containment Berms. Containment berms will be constructed completely around any production facilities designed to hold fluids. The containment berms will be constructed of compacted subsoil, be sufficiently impervious, hold 1 times the capacity of the largest tank and away from cut or fill areas. Electrical. Electrical is not included with this application. If additional electrical is required, application will be made via 3160-5 sundry notification.

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: OTHER

Describe type: Fresh Water 27-25S-30E

Water source use type: SURFACE CASING
INTERMEDIATE/PRODUCTION
CASING

Source latitude: **Source longitude:**

Source datum:

Water source permit type: PRIVATE CONTRACT

Water source transport method: TRUCKING
PIPELINE

Source land ownership: FEDERAL

Source transportation land ownership: STATE

Water source volume (barrels): 200000

Source volume (acre-feet): 25.77861927

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Source volume (gal): 8400000

Water source type: OTHER

Describe type: Fresh Water, Section 6-25S-29E

Water source use type: SURFACE CASING
INTERMEDIATE/PRODUCTION
CASING

Source latitude:

Source longitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Water source transport method: PIPELINE
TRUCKING

Source land ownership: FEDERAL

Source transportation land ownership: FEDERAL

Water source volume (barrels): 200000

Source volume (acre-feet): 25.77861927

Source volume (gal): 8400000

Water source and transportation map:

CC_4_Fed_168H_Wtr_20191226115737.pdf

Water source comments:

New water well? N

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Pit 1: Federal Caliche Pit, Section 17-T25S-R30E Pit 2: Federal Caliche Pit, Section 34-T25S-R29E

Construction Materials source location attachment:

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Cuttings

Amount of waste: 2100 pounds

Waste disposal frequency : One Time Only

Safe containment description: The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: R360 Environmental Solutions, 4507 W Carlsbad HWY, Hobbs, NM 88240, 575-393-1079

Waste type: DRILLING

Waste content description: Fluids

Amount of waste: 500 barrels

Waste disposal frequency : One Time Only

Safe containment description: Steel mud pits

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: R360 Environmental Solutions, 4507 W Carlsbad HWY, Hobbs, NM 88240, 575-393-1079

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Waste type: SEWAGE

Waste content description: Human Waste

Amount of waste: 250 gallons

Waste disposal frequency : Weekly

Safe containment description: Portable, self-contained toilets will be provided for human waste disposal. Upon completion of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and dispose human waste

Waste type: GARBAGE

Waste content description: Garbage, junk and non-flammable waste materials

Amount of waste: 250 pounds

Waste disposal frequency : Weekly

Safe containment description: All garbage, junk and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed and deposited in an approve sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and safely dispose garbage, junk and non-flammable waste materials.

Reserve Pit

Reserve Pit being used? N

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? Y

Description of cuttings location Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

CC_4_Fed_168H_Well_20191226115758.pdf

CC_4_Fed_168H_CF_20200420060951.pdf

CC_4_Fed_168H_RL_20200420061006.pdf

Comments: Multi-Well Pad

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: CC 4 Fed

Multiple Well Pad Number: 4

Recontouring attachment:

CC_4_Fed_Pad1_IR_20191226090915.pdf

CC_4_Fed_Pad2_IR_20191226090924.pdf

CC_4_Fed_Pad3_IR_20191226090932.pdf

CC_4_Fed_Pad4_IR_20191226090939.pdf

Drainage/Erosion control construction: All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches.

Drainage/Erosion control reclamation: Erosion features are equal to or less than surrounding area and erosion control is

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

sufficient so that water naturally infiltrates into the soil and gullying, headcutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

Well pad proposed disturbance (acres): 19.74	Well pad interim reclamation (acres): 5.14	Well pad long term disturbance (acres): 14.6
Road proposed disturbance (acres): 0.089	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0.089
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 0	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 19.828999999999997	Total interim reclamation: 5.14	Total long term disturbance: 14.689

Disturbance Comments:

Reconstruction method: The original stock piled topsoil will be spread over the areas being reclaimed and the original landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors as close as possible to the original topography. The location will then be ripped and seeded.

Topsoil redistribution: The original stock piled topsoil will be spread over the areas being reclaimed and the original landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors as close as possible to the original topography. The location will then be ripped and seeded.

Soil treatment: A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

Existing Vegetation at the well pad: Soil area is a combination of Pajarito-Dune land complex, loamy sand with 0-3% slopes, and Potter-Simona complex, shallow sandy soil with 5 to 25% slopes. These soils support grassland dominated by black grama throughout with dropseeds and bluestems more prevalent in the loamier areas. The areas with shallower soil have fewer shrubs and more litter cover with shrubs such as sand sage, shinnery oak and mesquite appearing as the soil presents more loam. Other vegetation such as creosote, mesquite, catclaw, snakeweed, and soapweed yucca grow within the area.

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road: Soil area is a combination of Pajarito-Dune land complex, loamy sand with 0-3% slopes, and Potter-Simona complex, shallow sandy soil with 5 to 25% slopes. These soils support grassland dominated by black grama throughout with dropseeds and bluestems more prevalent in the loamier areas. The areas with shallower soil have fewer shrubs and more litter cover with shrubs such as sand sage, shinnery oak and mesquite appearing as the soil presents more loam. Other vegetation such as creosote, mesquite, catclaw, snakeweed, and soapweed yucca grow within the area.

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: Soil area is a combination of Pajarito-Dune land complex, loamy sand with 0-3% slopes, and Potter-Simona complex, shallow sandy soil with 5 to 25% slopes. These soils support grassland dominated by black grama throughout with dropseeds and bluestems more prevalent in the loamier areas. The areas with shallower soil have fewer shrubs and more litter cover with shrubs such as sand sage, shinnery oak and mesquite appearing as the soil presents more loam. Other vegetation such as creosote, mesquite, catclaw, snakeweed, and soapweed yucca grow within the area.

Existing Vegetation Community at the pipeline attachment:

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Existing Vegetation Community at other disturbances: Soil area is a combination of Pajarito-Dune land complex, loamy sand with 0-3% slopes, and Potter-Simona complex, shallow sandy soil with 5 to 25% slopes. These soils support grassland dominated by black grama throughout with dropseeds and bluestems more prevalent in the loamier areas. The areas with shallower soil have fewer shrubs and more litter cover with shrubs such as sand sage, shinnery oak and mesquite appearing as the soil presents more loam. Other vegetation such as creosote, mesquite, catclaw, snakeweed, and soapweed yucca grow within the area.

Existing Vegetation Community at other disturbances attachment:

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed Summary

Total pounds/Acre:

Seed Type	Pounds/Acre
-----------	-------------

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name: Jeff

Last Name: Raines

Phone: (432)620-4349

Email: jeff_raines@xtoenergy.com

Seedbed prep: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left rough enough to trap seed and snow, control erosion, and increase water infiltration.

Seed BMP: If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

Seed method: Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used. If the site is harrowed or

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

dragged, seed will be covered by no more than 0.25 inch of soil.

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Weed control for all phases will be through the use of approved pesticides and herbicides according to applicable State, Federal and local laws.

Weed treatment plan attachment:

Monitoring plan description: Monitoring of invasive and noxious weeds will be visual and as-needed. If it is determined additional methods are required to monitor invasive and noxious weeds, appropriate BLM authorities will be contacted with a plan of action for approval prior to implementation.

Monitoring plan attachment:

Success standards: 100% compliance with applicable regulations.

Pit closure description: There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop mud system will meet the NMOCD requirements 19.15.17.

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? Y

Use APD as ROW? Y

ROW Type(s): 281001 ROW - ROADS,288100 ROW – O&G Pipeline,288101 ROW – O&G Facility Sites,289001 ROW-O&G Well Pad,FLPMA (Powerline)

ROW Applications

SUPO Additional Information:

Use a previously conducted onsite? N

Previous Onsite information:


Other SUPO Attachment

CC_4_Fed_List_20191226100611.pdf

TOPOGRAPHICAL AND ACCESS ROAD MAP

DIRECTIONS TO THIS LOCATION:

FROM THE INTERSECTION OF HIGHWAY 285 (PECOS HWY.) AND WHITEHORN RD. GO NORTHEAST ON WHITEHORN RD. APPROX. 2.4 MILES. TURN SLIGHT LEFT (NORTHEAST) ONTO LONGHORN RD. AND GO APPROX. 1.8 MILES. TURN LEFT (NORTHEAST) ONTO PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON ROCK DOVE ROAD AND GO APPROX. 1.8 MILES TO A "Y" INTERSECTION. TURN LEFT (NORTHWEST) ON LEASE ROAD AND GO APPROX. 2.6 MILES TO A "Y" INTERSECTION. TURN RIGHT (NORTHWEST) ON LEASE ROAD AND GO APPROX. 1.0 MILE TO A CURVE. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 1.0 MILE TO A "T" INTERSECTION. TURN RIGHT (WEST) ON LEASE ROAD AND GO 1.1 MILES, THE LOCATION IS TO THE SOUTH.




CORRAL CANYON 4-33 FED #127H
LOCATED 460 FEET FROM THE EAST LINE
AND 200 FEET FROM THE SOUTH LINE OF
SECTION 4, TOWNSHIP 25 SOUTH, RANGE 29
EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO




550 Bailey Ave., 205 - Fort Worth, TX 76107
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPLS Firm 10193887
www.fscinc.net
© COPYRIGHT 2019 - ALL RIGHTS RESERVED

DATE:	11-22-2019	PROJECT NO:	2018010255
DRAWN BY:	TM/LB	SCALE:	1" = 5,000'
CHECKED BY:	DH	SHEET:	1 OF 1
FIELD CREW:	RE/PH	REVISION:	2

Corral Canyon 4 Federal/9-4 Federal 1-Mile Radius Map



VICINITY MAP



CORRAL CANYON 4 FED #127H
LOCATED 460 FEET FROM THE EAST LINE
AND 200 FEET FROM THE SOUTH LINE OF
SECTION 4, TOWNSHIP 25 SOUTH, RANGE 29
EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO



0 5,000' 10,000'
1" = 10,000 FEET



FSC INC
SURVEYORS+ENGINEERS

550 Bailey Ave., 205 - Fort Worth, TX 76107
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPLS Firm 10193887
www.fscinc.net


DATE: 11-22-2019
DRAWN BY: TM/LB
CHECKED BY: DH
FIELD CREW: RE
PROJECT NO: 2018010255
SCALE: 1" = 10,000'
SHEET: 1 OF 1
REVISION: 2

© COPYRIGHT 2016 - ALL RIGHTS RESERVED

SECTION 4

TOWNSHIP 25 SOUTH, RANGE 29 EAST
NEW MEXICO PRIME MERIDIAN
OWNER: U.S.A.

SE/4 SE/4



SECTION 9

TOWNSHIP 25 SOUTH, RANGE 29 EAST
NEW MEXICO PRIME MERIDIAN
OWNER: U.S.A.

NE/4 NE/4

NOTE:

- SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP" FOR PROPOSED ROAD LOCATION

DIRECTIONS TO THIS LOCATION:

FROM THE INTERSECTION OF HIGHWAY 285 (PECOS HWY.) AND WHITEHORN RD. GO NORTHEAST ON WHITEHORN RD. APPROX. 2.4 MILES. TURN SLIGHT LEFT (NORTHEAST) ONTO LONGHORN RD. AND GO APPROX. 1.8 MILES. TURN LEFT (NORTHEAST) ONTO PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON ROCK DOVE ROAD AND GO APPROX. 1.8 MILES TO A "Y" INTERSECTION. TURN LEFT (NORTHWEST) ON LEASE ROAD AND GO APPROX. 2.6 MILES TO A "Y" INTERSECTION. TURN LEFT (NORTHWEST) ON LEASE ROAD AND GO APPROX. 1.0 MILE TO A CURVE. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 1.0 MILE TO A "T" INTERSECTION. TURN RIGHT (WEST) ON LEASE ROAD AND GO 1.1 MILES, THE LOCATION IS TO THE SOUTH.



LEGEND

- EXISTING PAD
- PROPOSED PAD EXPANSION
- EXISTING ROAD
- SURVEY LINE

I, MARK DILLON HARP, NEW MEXICO PROFESSIONAL SURVEYOR NO. 23786, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

[Signature]

MARK DILLON HARP
REGISTERED PROFESSIONAL LAND SURVEYOR
STATE OF NEW MEXICO NO. 23786



XTO ENERGY, INC.

WELL SITE PLAN

CORRAL CANYON 4 FED #168H
LOCATED 460 FEET FROM THE EAST LINE
AND 140 FEET FROM THE SOUTH LINE OF
SECTION 4, TOWNSHIP 25 SOUTH, RANGE 29
EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO

DATE:	11-13-2019	PROJECT NO:	2018010253
DRAWN BY:	RR	SCALE:	1" = 100'
CHECKED BY:	DH	SHEET:	1 OF 1
FIELD CREW:	RE	REVISION:	2




550 Bailey Ave., 205 - Fort Worth, TX 76107
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPLS Firm 10193887
www.fscinc.net

© COPYRIGHT 2016 - ALL RIGHTS RESERVED

SECTION 4

TOWNSHIP 25 SOUTH, RANGE 29 EAST
NEW MEXICO PRIME MERIDIAN



SECTION 9

TOWNSHIP 25 SOUTH, RANGE 29 EAST
NEW MEXICO PRIME MERIDIAN

CUT	FILL	NET
21,700 (CY)	8,900 (CY)	(+) 12,800 (CY)

EARTHWORK QUANTITIES ARE ESTIMATED



2205 WALNUT STREET / COLUMBUS, TX 78934
1.855.637.5725 / WWW.FSCINC.NET
TBPE FIRM # 17957 / TBPLS # 10000100



01/07/2020

CORRAL CANYON 4 FED
108H, 127H, 107H, 168H, 167H
EDDY COUNTY, NEW MEXICO




PAD SITE LAYOUT

REVISIONS		
NO.	DATE	DESCRIPTION

Project No.: 2018010245
Issued: 02/07/2020
Drawn By: FSC
Checked By: KL

1 OF 2
SHEET

XTO ENERGY, INC.
6401 HOLIDAY HILL RD. #200
MIDLAND, TEXAS 79707
(432) 571-8232



CUT	FILL	NET
21,700 (CY)	8,900 (CY)	(+) 12,800 (CY)

EARTHWORK QUANTITIES ARE ESTIMATED

SCALE
H: 1"=100'
V: 1"=25'

FSC INC
SURVEYORS+ENGINEERS
2205 WALNUT STREET / COLUMBUS, TX 78934
1.855.637.5725 / WWW.FSCINC.NET
TBPE FIRM # 17957 / TBPLS # 10000100



[Signature]
01/07/2020

CORRAL CANYON 4 FED
108H, 127H, 107H, 168H, 167H
EDDY COUNTY, NEW MEXICO

PAD CROSS-SECTIONS

REVISIONS		
NO.	DATE	DESCRIPTION


Project No.: 2018010245
Issued: 02/07/2020
Drawn By: FSC
Checked By: KL
2 OF 2
SHEET

XTO ENERGY, INC.
6401 HOLIDAY HILL RD. #200
MIDLAND, TEXAS 79707
(432) 571-8232

Rig Layout



Access Road





Interim Reclamation Diagram


Corral Canyon 9-4 Federal 102H, 121H, 122H, 161H, 162H
V-Door North (All Wells)

Diagram Not to Scale

LEGEND



Existing Wells: Corral Canyon Federal #6H & #18H
New Wells: Corral Canyon 4 Fed 124H, 104H, 103H, 164H, 163H
V-Door South (All Wells)
Diagram Not to Scale



Interim Reclamation Diagram


Previously Permitted Wells: Corral Canyon Federal #7H & #19H

Repermitting As: Corral Canyon 4 Fed 165H & 166H, Respectively

New Wells: Corral Canyon 4 Fed 125H, 105H, 126H

V-Door South (All Wells)

Diagram Not to Scale




Interim Reclamation Diagram

Existing Wells: Corral Canyon Federal #8H & #20H



New Wells: Corral Canyon 4 Fed 108H, 127H, 107H, 168H, 167H

V-Door South (All Wells)

Diagram Not to Scale



LEGEND



XTO Energy, Inc.

Corral Canyon 9-4 Fed / Corral Canyon 4 Federal Well List

11/22/2019

Pad 1

Corral Canyon 9-4 Fed #102H

Surface Hole Location: 2112'FSL & 362'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 750'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 9-4 Fed #121H

Surface Hole Location: 2081'FSL & 363'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 330'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 9-4 Fed #122H

Surface Hole Location: 2051'FSL & 364'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1170'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 9-4 Fed #161H

Surface Hole Location: 2021'FSL & 365'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 330'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 9-4 Fed #162H

Surface Hole Location: 1991'FSL & 366'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 990'FWL, Section 4, T. 25 S., R. 29 E.

Pad 2

Corral Canyon 4 Federal #124H

Surface Hole Location: 145'FNL & 2130'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2010'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #104H

Surface Hole Location: 175'FNL & 2130'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2430'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #103H

Surface Hole Location: 205'FNL & 2130'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1590'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #164H

Surface Hole Location: 235'FNL & 2130'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2310'FWL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #163H

Surface Hole Location: 265'FNL & 2130'FWL, Section 9, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1650'FWL, Section 4, T. 25 S., R. 29 E.

Pad 3

Corral Canyon 4 Federal #125H

Surface Hole Location: 170'FSL & 2060'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2430'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #105H

Surface Hole Location: 170'FSL & 2030'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2010'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #126H

Surface Hole Location: 170'FSL & 1980'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1590'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #165H

Surface Hole Location: 70'FSL & 2030'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 2310'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #166H

Surface Hole Location: 70'FSL & 1980'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1650'FEL, Section 4, T. 25 S., R. 29 E.

Pad 4

Corral Canyon 4 Federal #108H

Surface Hole Location: 230'FSL & 460'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 330'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #127H

Surface Hole Location: 200'FSL & 460'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 750'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #107H

Surface Hole Location: 170'FSL & 460'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 1170'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #168H

Surface Hole Location: 140'FSL & 460'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 330'FEL, Section 4, T. 25 S., R. 29 E.

Corral Canyon 4 Federal #167H

Surface Hole Location: 110'FSL & 460'FEL, Section 4, T. 25 S., R. 29 E.

Bottom Hole Location: 200'FNL & 990'FEL, Section 4, T. 25 S., R. 29 E.



APD ID: 10400052808

Submission Date: 01/02/2020

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

05/29/2020

APD ID: 10400052808

Submission Date: 01/02/2020

Highlighted data
reflects the most
recent changes

Operator Name: XTO ENERGY INCORPORATED

Well Name: CORRAL CANYON 4 FEDERAL

Well Number: 168H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Bond Information

Federal/Indian APD: FED

BLM Bond number: UTB000138

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: