

1R-119

**Plains
Monument #10**

**Annual Report
2013**

**2013
ANNUAL MONITORING REPORT**

**MONUMENT 10
SE ¼ NE¼ Section 30, Township 19 South, Range 37 East
LEA COUNTY, NEW MEXICO
PLAINS SRS NUMBER: TNM MONUMENT-10
NMOCD Reference Number 1R-0119**

Prepared For:

PLAINS MARKETING, L.P.
333 CLAY STREET, SUITE 1600
HOUSTON, TEXAS 77002



Prepared By:

NOVA Safety and Environmental
2057 Commerce Street
Midland, Texas 79703

March 2014


Jonathan Repman
Project Manager



Brittan K. Byerly, P.G.
President

TABLE OF CONTENTS

INTRODUCTION	1
SITE DESCRIPTION AND BACKGROUND INFORMATION	1
FIELD ACTIVITIES	1
LABORATORY RESULTS	2
SUMMARY	4
ANTICIPATED ACTIONS.....	4
LIMITATIONS.....	4
DISTRIBUTION.....	6

FIGURES

Figure 1 – Site Location Map

Figure 2A – Inferred Groundwater Gradient Map – February 5, 2013

2B – Inferred Groundwater Gradient Map – May 9, 2013

2C – Inferred Groundwater Gradient Map – August 1, 2013

2D – Inferred Groundwater Gradient Map – November 7, 2013

Figure 3A – Groundwater Concentration and Inferred PSH Extent Map – February 5, 2013

3B – Groundwater Concentration and Inferred PSH Extent Map – May 9, 2013

3C – Groundwater Concentration and Inferred PSH Extent Map – August 1, 2013

3D – Groundwater Concentrations and Inferred PSH Extent Map – November 7, 2013

TABLES

Table 1 – 2013 Groundwater Elevation Data

Table 2 – 2013 Concentrations of BTEX in Groundwater

Table 3 – 2013 Concentrations of PAH in Groundwater

APPENDICES

Appendix A – Release Notification and Corrective Action (Form C-141)

ENCLOSED ON DATA DISK

2013 Annual Monitoring Report

2013 Tables 1, 2 and 3 – Groundwater Elevation, BTEX Concentration Data, and PAH Tables

2013 Figures 1, 2A-2D, and 3A-3D

Electronic Copies of Laboratory Reports

Historic Tables 1, 2 and 3 – Groundwater Elevation, BTEX and PAH Concentration Tables

INTRODUCTION

On behalf of Plains Marketing, L.P., (Plains), NOVA Safety and Environmental (NOVA) is pleased to submit this 2013 Annual Monitoring Report in compliance with the New Mexico Oil Conservation Division (NMOCD) letter of May 1998, requiring submittal of an Annual Monitoring Report by April 1 of each year. Beginning on May 29, 2004, project management responsibilities were assumed by NOVA. The Monument 10 Site (the site), formally the responsibility of Enron Oil Trading and Transportation (EOTT), is now the responsibility of Plains. This report is intended to be viewed as a complete document with figures, attachments, tables and text. The report presents the results of the quarterly groundwater monitoring events conducted in calendar year 2013 only. For reference, the Site Location Map is provided as Figure 1. Cumulative tables and laboratory data are provided on the enclosed data disk.

Groundwater monitoring was conducted each quarter of 2013 to assess the levels and extent of dissolved phase constituents and Phase Separated Hydrocarbon (PSH). The groundwater monitoring events consisted of measuring static water levels in the monitor wells, checking for the presence of PSH and purging and sampling of each well exhibiting sufficient recharge. Monitor wells containing a thickness of PSH greater than 0.01 foot were not sampled.

SITE DESCRIPTION AND BACKGROUND INFORMATION

The legal description of the site location is SE $\frac{1}{4}$ NE $\frac{1}{4}$ Section 30, Township 19 South, Range 37 East. No information with respect to the release date, volume of crude oil released or recovered, excavation volumes, or pipeline repair details is available. The Release Notification and Corrective Action (Form C-141) is provided as Appendix A. The initial site investigation, consisting of the installation of seven groundwater monitor wells (MW-1 through MW-7), was performed by a previous consultant.

Seven groundwater monitor wells (MW-1 through MW-7) are currently on-site. An automated recovery system recovers PSH from monitor wells MW-2 and MW-3.

FIELD ACTIVITIES

Product Recovery Efforts

During the reporting period, monitor wells MW-2 and MW-3 exhibited measurable thicknesses of PSH during the four quarters of the reporting period. The average PSH thickness for the year from the two (2) monitor wells displaying PSH was 0.74 feet. The maximum measured PSH thickness of 2.89 feet was observed in monitor well MW-2 on December 10, 2013.

Approximately 113.54 gallons (approximately 2.7 barrels) of PSH were recovered from the site during the reporting period. Approximately 2,336.54 gallons (approximately 55.7 barrels) of PSH have been recovered from this site since the project inception. To maximize product recovery efforts, Plains installed a solar recovery system during the 4th quarter of 2011 which utilizes two total fluid pumps powered by two 12 volt solar panels and a 12 volt wind turbine installed in monitor wells MW-2 and MW-3. The pumps operate on a cycle of approximately 3 minutes every 3 hours at an average pumping rate of approximately 2 gallons per minute.

Recovered PSH is reintroduced into the Plains transportation system at the Plains Lea Station Facility, near Monument, New Mexico. Measurable thicknesses of PSH are recorded in Table 1 and Figures 3A-3D.

Groundwater Monitoring

Quarterly monitoring events for the reporting period were performed according to the following sampling schedule, which was approved by the NMOCD in correspondence dated April 28, 2004 and amended by NMOCD correspondences dated June 22, 2005, January 26, 2006, and October 31, 2012.

NMOCD Approved Sampling Schedule	
MW-1	Quarterly
MW-2	Quarterly
MW-3	Quarterly
MW-4	Annually
MW-5	Annually
MW-6	Semi-Annually
MW-7	Semi-Annually

The site monitor wells were gauged and sampled on February 5, May 9, August 1, and November 7, 2013. During each sampling event, monitor wells were purged of a minimum of three well volumes of water or until the wells failed to produce water. Purging was performed using a disposable polyethylene bailer for each well or electrical Proactive Mini-Monsoon pump and dedicated tubing. Groundwater was allowed to recharge and samples were collected using disposable Teflon samplers. Water samples were placed in clean glass containers provided by the laboratory and placed on ice in the field. Purge water was collected in a polystyrene tank and disposed of at a licensed disposal facility.

Locations of the monitor wells and the inferred groundwater gradient, which were constructed from measurements collected during quarterly sampling events performed in 2013, are depicted on the Inferred Groundwater Gradient Map(s), Figures 2A-2D. Groundwater elevation data for 2013 is provided as Table 1. Historic groundwater elevation data beginning at project inception is provided on the enclosed data disk.

The most recent Groundwater Gradient Map, Figure 2D, indicates a general gradient of 0.012 feet/foot to the southeast. This is consistent with data presented on Figures 2A through 2C from earlier in the year. The corrected groundwater elevations ranged between 3,605.03 and 3,609.58 feet above mean sea level, in monitor well MW-6 on May 9, 2013 and monitor well MW-4 on August 1, 2013, respectively.

LABORATORY RESULTS

Monitor wells MW-2 and MW-3 contained PSH during the four quarters of the reporting period and were not sampled.

Groundwater samples obtained during the quarterly sampling events of 2013 were delivered to Trace Analysis, Inc. in Midland, Texas for determination of Benzene, Toluene, Ethylbenzene and Xylene (BTEX) constituent concentrations by EPA Method 8021B. Polynuclear Aromatic Hydrocarbons (PAH) analysis on monitor wells MW-2 and MW-3 was scheduled during the year

2013, but was suspended due to the presence of PSH. Based upon historic PAH analytical data, only those wells exhibiting elevated constituent concentrations above WQCC standards will be sampled, with the exclusion of those wells containing measurable PSH thicknesses. No other wells warrant PAH analysis based upon NMOCD directive. A listing of BTEX constituent concentrations for 2013 is summarized in Table 2. Copies of the laboratory reports generated for 2013 are provided on the enclosed data disk. The quarterly groundwater sample results for BTEX constituent concentrations are depicted on Figures 3A through 3D.

Monitor well MW-1 is sampled on a quarterly schedule and analytical results indicate BTEX constituent concentrations ranged from below the laboratory method detection limit (MDL) for the 1st, 2nd, and 3rd quarters to 0.0031 mg/L during the 4th quarter of the reporting period. Benzene concentrations were below the NMOCD guidelines during the reporting period. Toluene and Ethyl-benzene concentrations were below the laboratory MDL and NMOCD guidelines during the reporting period. Xylene concentrations ranged from below the MDL during the 1st, 2nd, and 4th quarters to 0.0039 mg/L for the 3rd quarter of the reporting period. Xylene concentrations were below the NMOCD guidelines during the reporting period. PAH analysis was not conducted during the 4th quarter sampling event.

Monitor well MW-2 is monitored on a quarterly schedule. Monitor well MW-2 was not sampled during the four quarters of the reporting period, due to the presence of PSH. PSH thicknesses of 0.57 feet, 0.22 feet, 0.76 feet, and 0.26 feet were reported during the 1st, 2nd, 3rd and 4th quarters of 2013, respectively. PAH analysis was not conducted during the 4th quarter sampling event due to the presence of PSH.

Monitor well MW-3 is monitored on a quarterly schedule. Monitor well MW-3 was not sampled during the four quarters of the reporting period, due to the presence of PSH. PSH thicknesses of 2.86 feet, 0.26 feet, 1.63 feet, and 0.08 feet were reported during the 1st, 2nd, 3rd and 4th quarters of 2013, respectively. PAH analysis was not conducted during the 4th quarter sampling event due to the presence of PSH.

Monitor well MW-4 is sampled on an annual schedule and analytical results indicate BTEX constituent concentrations were below MDL and NMOCD regulatory guidelines for each BTEX constituent during the 4th quarter sampling event. Monitor well MW-4 has exhibited 32 consecutive monitoring events below NMOCD regulatory guidelines. PAH analysis was not conducted during the 4th quarter sampling event.

Monitor well MW-5 is sampled on an annual schedule and analytical results indicate BTEX constituent concentrations were below MDL and NMOCD regulatory guidelines for each BTEX constituent during the 4th quarter sampling event. Monitor well MW-5 has exhibited 35 consecutive monitoring events below NMOCD regulatory guidelines. PAH analysis was not conducted during the 4th quarter sampling event.

Monitor well MW-6 is sampled on a semi-annual schedule and analytical results indicate BTEX constituent concentrations were below MDL and NMOCD regulatory guidelines for each BTEX constituent during the 2nd and 4th quarter sampling events. Monitor well MW-6 has exhibited 36 consecutive monitoring events below NMOCD regulatory guidelines. PAH analysis was not conducted during the 4th quarter sampling event.

Monitor well MW-7 is sampled on a semi-annual schedule and analytical results indicate BTEX constituent concentrations were below MDL and NMOCD regulatory guidelines for each BTEX constituent during the 2nd and 4th quarter sampling events. Monitor well MW-7 has exhibited 41 consecutive monitoring events below NMOCD regulatory guidelines. PAH analysis was not conducted during the 4th quarter sampling event.

Laboratory analytical results were compared to NMOCD regulatory guidelines based on the New Mexico groundwater guidelines found in section 20.6.2.3103 of the New Mexico Administrative Code.

SUMMARY

This report presents the results of monitoring activities for the 2013 annual monitoring period. Currently, there are seven groundwater monitor wells on the site. Two (2) monitor wells (MW-2 and MW-3) exhibited measurable thicknesses of PSH during each of the four sampling events of the reporting period and were not sampled. An automated recovery system recovers PSH from monitor wells MW-2 and MW-3. The most recent Groundwater Gradient Map, Figure 2D, indicates a general gradient of 0.012 feet/foot to the southeast.

Approximately 113.54 gallons (approximately 2.7 barrels) of PSH were recovered from the site during the reporting period. Approximately 2,336.5 gallons (approximately 55.7 barrels) of PSH have been recovered from this site since the project inception.

Review of the laboratory analytical results of the groundwater samples obtained during the reporting period indicated BTEX constituent concentrations remain below applicable NMOCD regulatory guidelines in five (5) of the seven (7) site monitor wells. PSH impact is limited to the vicinity of monitor wells MW-2 and MW-3.

ANTICIPATED ACTIONS

Quarterly monitoring, automated PSH recovery, and groundwater sampling will continue in 2014. Manual product recovery and gauging well be conducted on a weekly schedule and will be adjusted according to site conditions. Additional MDPE events will be scheduled as necessary.

An Annual Monitoring Report will be submitted to the NMOCD before April 1, 2015.

LIMITATIONS

NOVA has prepared this Annual Monitoring Report to the best of its ability. No other warranty, expressed or implied, is made or intended.


NOVA has examined and relied upon documents referenced in the report and has relied on oral statements made by certain individuals. NOVA has not conducted an independent examination of the facts contained in referenced materials and statements. We have presumed the genuineness of the documents and that the information provided in documents or statements is true and accurate. NOVA has prepared this report, in a professional manner, using the degree of skill and care exercised by similar environmental consultants. NOVA also notes that the facts

and conditions referenced in this report may change over time and the conclusions and recommendations set forth herein are applicable only to the facts and conditions as described at the time of this report.


This report has been prepared for the benefit of Plains. The information contained in this report, including all exhibits and attachments, may not be used by any other party without the express consent of NOVA and/or Plains.

DISTRIBUTION

- Copy 1: Jim Griswold
New Mexico Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Drive
Santa Fe, NM 87505
- Copy 2: Geoffrey R. Leking
New Mexico Energy, Minerals and Natural Resources Department
Oil Conservation Division, District 1
1625 French Drive
Hobbs, NM 88240
- Copy 3: Camille Bryant
Plains Marketing, L.P.
2530 State Highway 214
Denver City, TX 79323
cjbryant@paalp.com
- Copy 4: Jeff Dann
Plains Marketing, L.P.
333 Clay Street
Suite 1600
Houston, TX 77002
jpdann@paalp.com
- Copy 5: NOVA Safety and Environmental
2057 Commerce Street
Midland, TX 79703
jrepman@novatraining.cc



LEGEND:



NMOCD Reference #1R-0119

Figure 1
Site Location Map
Monument 10
Plains Marketing, L.P.
Lea County, NM





2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

February 4, 2013	Scale: 1" = 2000'	CAD By: CS	Checked By:
------------------	-------------------	------------	-------------

LATITUDE & LONGITUDE COORDINATES: N 32° 38' 8.77" W 103° 17' 3.42"



LEGEND:

- Monitor Well Location
- Pipeline
- Groundwater Elevation Contour Line
- Groundwater Elevation (feet)
- Groundwater Gradient and Magnitude

NOTE:

- Contour Interval : 0.50'
- Groundwater Gradient Measured Between MW-4 and MW-7



Figure 2A
Inferred Groundwater
Gradient Map
(2/5/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

April 11, 2013	Scale: 1" = 60'	CAD By: CAS	Checked By:
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



LEGEND:

- Monitor Well Location
- Pipeline
- Groundwater Elevation Contour Line
- Groundwater Elevation (feet)
- Groundwater Gradient and Magnitude

NOTE:

- Contour Interval : 0.50'
- Groundwater Gradient Measured Between MW-4 and MW-7


Figure 2B
Inferred Groundwater
Gradient Map
(5/9/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

June 12, 2013	Scale: 1" = 60'	CAD By: CAS	Checked By:
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



- LEGEND:**
- Monitor Well Location
 - Pipeline
 - Groundwater Elevation Contour Line
 - Groundwater Elevation (feet)
 - Groundwater Gradient and Magnitude

NOTE:

- Contour Interval : 0.50'
- Groundwater Gradient Measured Between MW-4 and MW-7

Figure 2C
Inferred Groundwater
Gradient Map
(8/1/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119




2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

September 26, 2013 Scale: 1" = 60' CAD By: TA Checked By: CJB

Lat. N 32° 38' 14" Long. W 103° 17' 4"

NE1/4 Section 30 T19S R37E



LEGEND:

-  Monitor Well Location
-  Pipeline
-  Groundwater Elevation Contour Line
-  Groundwater Elevation (feet)
-  Groundwater Gradient and Magnitude

NOTE:

- Contour Interval : 0.50'
- Groundwater Gradient Measured Between MW-4 and MW-7


Figure 2D
Inferred Groundwater
Gradient Map
(11/7/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

December 23, 2013	Scale: 1" = 60'	CAD By: TA	Checked By: CS
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



LEGEND:

- Monitor Well Location
- Pipeline
- Inferred Extent of PSH
- Not Sampled
- Constituent Concentration (mg/L)
- Depth of PSH (feet)


Figure 3A
Groundwater Concentration and
Inferred PSH Extents Map
(2/5/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

April 9, 2013	Scale: 1" = 60'	CAD By: CAS	Checked By:
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



LEGEND:

- Monitor Well Location
- Pipeline
- Inferred Extent of PSH
- Not Sampled
- Constituent Concentration (mg/L)
- Depth of PSH (feet)


Figure 3B
Groundwater Concentration and
Inferred PSH Extents Map
(5/9/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

June 18, 2013	Scale: 1" = 60'	CAD By: CAS	Checked By:
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



LEGEND:

- Monitor Well Location
- Pipeline
- Inferred Extent of PSH
- Not Sampled
- Constituent Concentration (mg/L)
- Depth of PSH (feet)


Figure 3C
Groundwater Concentration and
Inferred PSH Extents Map
(8/1/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

September 26, 2013	Scale: 1" = 60'	CAD By: TA	Checked By: CJB
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	



LEGEND:

-  Monitor Well Location
-  Pipeline
-  Inferred Extent of PSH
-  (NS) Not Sampled
-  <0.001 Constituent Concentration (mg/L)
-  3.48' Depth of PSH (feet)

Figure 3D
Groundwater Concentration and
Inferred PSH Extents Map
(11/7/2013)
Plains Marketing, L.P.
Monument 10
Lea County, NM
NMOCD Reference # 1R-0119



2057 Commerce Drive
Midland, Texas 79703
432.520.7720

www.novasafetyandenvironmental.com

December 23, 2013	Scale: 1" = 60'	CAD By: TA	Checked By: CS
Lat. N 32° 38' 14" Long. W 103° 17' 4"		NE1/4 Section 30 T19S R37E	

TABLE 1
2013 GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	01/14/13	3,629.33	-	21.83	0.00	3,607.50
MW - 1	02/04/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	02/05/13	3,629.33	-	21.82	0.00	3,607.51
MW - 1	02/20/13	3,629.33	-	21.83	0.00	3,607.50
MW - 1	03/26/13	3,629.33	-	21.78	0.00	3,607.55
MW - 1	04/10/13	3,629.33	-	21.99	0.00	3,607.34
MW - 1	04/17/13	3,629.33	-	21.95	0.00	3,607.38
MW - 1	04/24/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	05/02/13	3,629.33	-	21.86	0.00	3,607.47
MW - 1	05/09/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	05/17/13	3,629.33	-	21.81	0.00	3,607.52
MW - 1	05/22/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	05/29/13	3,629.33	-	21.77	0.00	3,607.56
MW - 1	06/03/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	06/20/13	3,629.33	-	21.67	0.00	3,607.66
MW - 1	06/25/13	3,629.33	-	21.69	0.00	3,607.64
MW - 1	07/02/13	3,629.33	-	21.89	0.00	3,607.44
MW - 1	07/09/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	07/16/13	3,629.33	-	21.85	0.00	3,607.48
MW - 1	07/24/13	3,629.33	-	21.81	0.00	3,607.52
MW - 1	07/31/13	3,629.33	-	21.80	0.00	3,607.53
MW - 1	08/01/13	3,629.33	-	21.73	0.00	3,607.60
MW - 1	08/06/13	3,629.33	-	21.71	0.00	3,607.62
MW - 1	08/07/13	3,629.33	-	21.66	0.00	3,607.67
MW - 1	08/16/13	3,629.33	-	21.69	0.00	3,607.64
MW - 1	08/27/13	3,629.33	-	21.63	0.00	3,607.70
MW - 1	09/12/13	3,629.33	-	21.64	0.00	3,607.69
MW - 1	09/19/13	3,629.33	-	22.10	0.00	3,607.23
MW - 1	09/25/13	3,629.33	-	22.05	0.00	3,607.28
MW - 1	09/30/13	3,629.33	-	22.07	0.00	3,607.26
MW - 1	10/09/13	3,629.33	-	21.99	0.00	3,607.34
MW - 1	10/14/13	3,629.33	-	21.78	0.00	3,607.55
MW - 1	10/22/13	3,629.33	-	21.72	0.00	3,607.61
MW - 1	10/30/13	3,629.33	-	22.03	0.00	3,607.30
MW - 1	11/07/13	3,629.33	-	22.00	0.00	3,607.33
MW - 1	11/27/13	3,629.33	-	21.86	0.00	3,607.47
MW - 1	12/04/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	12/10/13	3,629.33	-	21.76	0.00	3,607.57
MW - 1	12/16/13	3,629.33	-	21.62	0.00	3,607.71

TABLE 1

2013 GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
 MONUMENT 10
 LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	12/24/13	3,629.33	-	21.75	0.00	3,607.58
MW - 2	01/14/13	3,629.43	22.56	23.08	0.52	3,606.79
MW - 2	02/04/13	3,629.43	22.57	23.27	0.70	3,606.76
MW - 2	02/05/13	3,629.43	22.54	23.11	0.57	3,606.80
MW - 2	02/20/13	3,629.43	22.50	23.36	0.86	3,606.80
MW - 2	03/04/13	3,629.43	22.65	22.72	0.07	3,606.77
MW - 2	03/07/13	3,629.43	22.60	22.65	0.05	3,606.82
MW - 2	03/26/13	3,629.43	22.59	22.63	0.04	3,606.83
MW - 2	04/10/13	3,629.43	22.55	22.66	0.11	3,606.86
MW - 2	04/17/13	3,629.43	22.55	22.60	0.05	3,606.87
MW - 2	04/24/13	3,629.43	22.67	22.81	0.14	3,606.74
MW - 2	05/02/13	3,629.43	22.57	22.84	0.27	3,606.82
MW - 2	05/09/13	3,629.43	22.50	22.72	0.22	3,606.90
MW - 2	05/17/13	3,629.43	22.55	22.80	0.25	3,606.84
MW - 2	05/22/13	3,629.43	22.58	22.78	0.20	3,606.82
MW - 2	05/29/13	3,629.43	22.60	23.03	0.43	3,606.77
MW - 2	06/03/13	3,629.43	22.59	22.64	0.05	3,606.83
MW - 2	06/20/13	3,629.43	22.59	22.85	0.26	3,606.80
MW - 2	06/25/13	3,629.43	23.11	23.28	0.17	3,606.29
MW - 2	07/02/13	3,629.43	22.58	22.88	0.30	3,606.81
MW - 2	07/09/13	3,629.43	22.58	23.19	0.61	3,606.76
MW - 2	07/16/13	3,629.43	22.69	23.33	0.64	3,606.64
MW - 2	07/24/13	3,629.43	22.69	23.32	0.63	3,606.65
MW - 2	07/31/13	3,629.43	22.69	23.30	0.61	3,606.65
MW - 2	08/01/13	3,629.43	22.67	23.43	0.76	3,606.65
MW - 2	08/06/13	3,629.43	22.58	22.91	0.33	3,606.80
MW - 2	08/16/13	3,629.43	22.49	23.17	0.68	3,606.84
MW - 2	09/12/13	3,629.43	22.53	22.79	0.26	3,606.86
MW - 2	09/19/13	3,629.43	22.56	22.72	0.16	3,606.85
MW - 2	09/25/13	3,629.43	22.48	23.02	0.54	3,606.87
MW - 2	09/30/13	3,629.43	22.49	22.89	0.40	3,606.88
MW - 2	10/09/13	3,629.43	22.55	22.66	0.11	3,606.86
MW - 2	10/14/13	3,629.43	22.54	22.70	0.16	3,606.87
MW - 2	10/22/13	3,629.43	22.54	22.83	0.29	3,606.85
MW - 2	10/30/13	3,629.43	22.58	22.96	0.38	3,606.79
MW - 2	11/07/13	3,629.43	22.53	22.79	0.26	3,606.86
MW - 2	11/27/13	3,629.43	22.44	23.22	0.78	3,606.87
MW - 2	12/04/13	3,629.43	22.46	23.25	0.79	3,606.85

TABLE 1

2013 GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
 MONUMENT 10
 LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	12/10/13	3,629.43	22.46	25.35	2.89	3,606.54
MW - 2	12/16/13	3,629.43	22.45	23.38	0.93	3,606.84
MW - 2	12/24/13	3,629.43	22.41	23.41	1.00	3,606.87
MW - 3	01/14/13	3,628.90	22.41	22.44	0.03	3,606.49
MW - 3	02/04/13	3,628.90	22.11	24.94	2.83	3,606.37
MW - 3	02/05/13	3,628.90	22.11	24.97	2.86	3,606.36
MW - 3	02/20/13	3,628.90	22.01	25.14	3.13	3,606.42
MW - 3	03/04/13	3,628.90	23.43	24.21	0.78	3,605.35
MW - 3	03/26/13	3,628.90	22.71	24.60	1.89	3,605.91
MW - 3	04/10/13	3,628.90	22.33	24.52	2.19	3,606.24
MW - 3	04/17/13	3,628.90	22.41	24.39	1.98	3,606.19
MW - 3	04/24/13	3,628.90	22.72	25.47	2.75	3,605.77
MW - 3	05/02/13	3,628.90	22.37	23.46	1.09	3,606.37
MW - 3	05/09/13	3,628.90	22.56	22.82	0.26	3,606.30
MW - 3	05/17/13	3,628.90	22.42	22.97	0.55	3,606.40
MW - 3	05/22/13	3,628.90	22.52	22.65	0.13	3,606.36
MW - 3	05/29/13	3,628.90	22.62	23.15	0.53	3,606.20
MW - 3	06/03/13	3,628.90	22.42	22.89	0.47	3,606.41
MW - 3	06/20/13	3,628.90	22.51	22.78	0.27	3,606.35
MW - 3	06/25/13	3,628.90	22.67	23.19	0.52	3,606.15
MW - 3	07/02/13	3,628.90	22.42	23.09	0.67	3,606.38
MW - 3	07/09/13	3,628.90	22.57	23.51	0.94	3,606.19
MW - 3	07/16/13	3,628.90	22.54	23.99	1.45	3,606.14
MW - 3	07/24/13	3,628.90	22.56	23.97	1.41	3,606.13
MW - 3	07/31/13	3,628.90	22.55	23.96	1.41	3,606.14
MW - 3	08/01/13	3,628.90	22.48	24.11	1.63	3,606.18
MW - 3	08/06/13	3,628.90	22.14	24.29	2.15	3,606.44
MW - 3	08/07/13	3,628.90	22.43	23.37	0.94	3,606.33
MW - 3	08/16/13	3,628.90	22.33	23.93	1.60	3,606.33
MW - 3	09/12/13	3,628.90	22.45	22.47	0.02	3,606.45
MW - 3	09/25/13	3,628.90	22.43	22.46	0.03	3,606.47
MW - 3	09/30/13	3,628.90	22.40	22.75	0.35	3,606.45
MW - 3	10/09/13	3,628.90	22.45	22.51	0.06	3,606.44
MW - 3	10/14/13	3,628.90	22.46	22.48	0.02	3,606.44
MW - 3	10/22/13	3,628.90	22.42	22.77	0.35	3,606.43
MW - 3	10/30/13	3,628.90	22.32	23.33	1.01	3,606.43
MW - 3	11/07/13	3,628.90	22.43	22.51	0.08	3,606.46
MW - 3	11/27/13	3,628.90	22.25	23.68	1.43	3,606.44

TABLE 1

2013 GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
 MONUMENT 10
 LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	12/04/13	3,628.90	22.41	22.42	0.01	3,606.49
MW - 3	12/10/13	3,628.90	22.36	23.05	0.69	3,606.44
MW - 3	12/16/13	3,628.90	22.33	23.43	1.10	3,606.41
MW - 3	12/24/13	3,628.90	22.45	22.48	0.03	3,606.45
MW - 4	02/05/13	3,629.97	-	20.44	0.00	3,609.53
MW - 4	05/09/13	3,629.97	-	20.46	0.00	3,609.51
MW - 4	08/01/13	3,629.97	-	20.39	0.00	3,609.58
MW - 4	11/07/13	3,629.97	-	20.41	0.00	3,609.56
MW - 5	02/05/13	3,629.36	-	21.64	0.00	3,607.72
MW - 5	05/09/13	3,629.36	-	21.67	0.00	3,607.69
MW - 5	08/01/13	3,629.36	-	21.58	0.00	3,607.78
MW - 5	11/07/13	3,629.36	-	21.63	0.00	3,607.73
MW - 6	02/05/13	3,629.17	-	24.13	0.00	3,605.04
MW - 6	05/09/13	3,629.17	-	24.14	0.00	3,605.03
MW - 6	08/01/13	3,629.17	-	24.11	0.00	3,605.06
MW - 6	11/07/13	3,629.17	-	24.13	0.00	3,605.04
MW - 7	02/05/13	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/09/13	3,628.07	-	22.85	0.00	3,605.22
MW - 7	08/01/13	3,628.07	-	22.83	0.00	3,605.24
MW - 7	11/07/13	3,628.07	-	22.82	0.00	3,605.25

TABLE 2

2013 CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 1	02/05/13	<0.00500	<0.00500	<0.00500	<0.00500	
MW - 1	05/09/13	<0.00100	<0.00100	<0.00100	<0.00100	
MW - 1	08/01/13	<0.00100	<0.00100	<0.00100	0.0039	
MW - 1	11/07/13	0.0031	<0.00100	<0.00100	<0.00300	
MW - 2	02/05/13	Not sampled Due to PSH in Well				
MW - 2	05/09/13	Not sampled Due to PSH in Well				
MW - 2	08/01/13	Not sampled Due to PSH in Well				
MW - 2	11/07/13	Not sampled Due to PSH in Well				
MW - 3	02/05/13	Not sampled Due to PSH in Well				
MW - 3	05/09/13	Not sampled Due to PSH in Well				
MW - 3	08/01/13	Not sampled Due to PSH in Well				
MW - 3	11/07/13	Not sampled Due to PSH in Well				
MW - 4	02/05/13	Not Sampled on Current Sample Schedule				
MW - 4	05/09/13	Not Sampled on Current Sample Schedule				
MW - 4	08/01/13	Not Sampled on Current Sample Schedule				
MW - 4	11/07/13	<0.00100	<0.00100	<0.00100	<0.00300	
MW - 5	02/05/13	Not Sampled on Current Sample Schedule				
MW - 5	05/09/13	Not Sampled on Current Sample Schedule				
MW - 5	08/01/13	Not Sampled on Current Sample Schedule				
MW - 5	11/07/13	<0.00100	<0.00100	<0.00100	<0.00300	
MW - 6	02/05/13	Not Sampled on Current Sample Schedule				
MW - 6	05/09/13	<0.00100	<0.00100	<0.00100	<0.00100	
MW - 6	08/01/13	Not Sampled on Current Sample Schedule				
MW - 6	11/07/13	<0.00100	<0.00100	<0.00100	<0.003000	
MW - 7	02/05/13	Not Sampled on Current Sample Schedule				
MW - 7	05/09/13	<0.00100	<0.00100	<0.00100	<0.00100	
MW - 7	08/01/13	Not Sampled on Current Sample Schedule				
MW - 7	11/07/13	<0.00100	<0.00100	<0.00100	<0.00300	

Note : m, p & o xylenes are combined when analyzed by Trace Laboratories, Inc. only.
Concentrations in **BOLD** are above the applicable NMOCD Regulatory Limit.

POLYNUCLEAR AROMATIC HYDROCARBON CONCENTRATIONS IN GROUNDWATER

All water concentrations are reported in mg/L

Page 1 of 2

TABLE 3

POLYNUCLEAR AROMATIC HYDROCARBON CONCENTRATIONS IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO
NMOCD REFERENCE NUMBER R1-0119

All water concentrations are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	EPA SW846-8270C, 3510																	
		Acenaphthene	Acenaphthylene	Anthracene	Benzo[a]anthracene	Benzo[a]pyrene	Benzo[b]fluoranthene	Benzo[g,h,i]perylene	Benzo[k]fluoranthene	Chrysene	Dibenz[a,h]anthracene	Fluoranthene	Fluorene	Indeno[1,2,3-cd]pyrene	Phenanthrene	Pyrene	Naphthalene	1-Methylnaphthalene	2-Methylnaphthalene
Maximum Contaminant Levels from NM WQCC Drinking water standards Sections 1-101.UU and 3-103.A.		—	—	0.001 mg/L	0.0001 mg/L	0.0007 mg/L	0.001 mg/L	—	0.001 mg/L	0.0002 mg/L	0.0003 mg/L	0.001 mg/L	0.001 mg/L	0.0004 mg/L	0.001 mg/L	0.001 mg/L	0.03 mg/L		—
MW-5	11/19/08	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183
	11/06/09	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																	
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																	
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																	
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																	
MW-6	11/19/08	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183
	11/06/09	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																	
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																	
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																	
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																	
MW-7	11/19/08	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	0.000237	<0.000186	<0.000186	0.00034	<0.000186	0.000338
	11/06/09	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																	
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																	
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																	
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																	

District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-141
Revised October 10, 2003

Submit 2 Copies to appropriate
District Office in accordance
with Rule 116 on back
side of form

Release Notification and Corrective Action

OPERATOR

x Initial Report ☐ Final Report

Name of Company	Plains Pipeline, LP	Contact:	Camille Reynolds
Address:	3705 E. Hwy 158, Midland, TX 79706	Telephone No.	505-441-0965
Facility Name	Monument #10	Facility Type:	Steel Pipeline

Surface Owner:	New Mexico State Land	Mineral Owner	Lease No.
----------------	-----------------------	---------------	-----------

LOCATION OF RELEASE

Unit Letter	Section	Township	Range	Feet from the	North/South Line	Feet from the	East/West Line	County
H	30	19S	37E					Lea

Latitude 32 degrees 38' 9.2" **Longitude** 103 degrees 17' 2.4"

NATURE OF RELEASE

Type of Release:	Volume of Release:	Volume Recovered
Source of Release:	Date and Hour of Occurrence Unknown	Date and Hour of Discovery
Was Immediate Notice Given? Yes ☐ No ☐ Not Required	If YES, To Whom?	
By Whom?	Date and Hour	
Was a Watercourse Reached? ☐ Yes ☒ No	If YES, Volume Impacting the Watercourse.	

If a Watercourse was Impacted, Describe Fully.*

Describe Cause of Problem and Remedial Action Taken.*

Describe Area Affected and Cleanup Action Taken.*

NOTE: Texas-New Mexico Pipeline was the owner/operator of the pipeline system at the time of the release, initial response information is unavailable.

I hereby certify that the information given above is true and complete to the best of my knowledge and understand that pursuant to NMOCD rules and regulations all operators are required to report and/or file certain release notifications and perform corrective actions for releases which may endanger public health or the environment. The acceptance of a C-141 report by the NMOCD marked as "Final Report" does not relieve the operator of liability should their operations have failed to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD acceptance of a C-141 report does not relieve the operator of responsibility for compliance with any other federal, state, or local laws and/or regulations.

Federal, State, or local laws and/or Regulations:		<u>OIL CONSERVATION DIVISION</u>	
Signature:		Approved by District Supervisor:	
Printed Name: Camille Reynolds			
Title: Remediation Coordinator		Approval Date:	Expiration Date:
E-mail Address: cjreynolds@paalp.com		Conditions of Approval:	Attached ☐
Date: 3/21/2005 Phone: (505)441-0965			

* Attach Additional Sheets If Necessary

Summary Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX 79703

Report Date: February 12, 2013

Work Order: 13020603



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
320345	MW-1	water	2013-02-05	13:02	2013-02-06

Sample - Field Code	BTEX			
	Benzene (mg/L)	Toluene (mg/L)	Ethylbenzene (mg/L)	Xylene (mg/L)
320345 - MW-1	<0.00500 ¹	<0.00500	<0.00500	<0.00500

¹Dilution due to surfactant.



6701 Aberdeen Avenue, Suite 9
200 East Sunset Road, Suite E
5002 Basin Street, Suite A1
(BioAquatic) 2501 Mayes Rd., Suite 100

Lubbock, Texas 79424
El Paso, Texas 79922
Midland, Texas 79703
Carrollton, Texas 75006

800-378-1296 806-794-1296 FAX 806-794-1298
915-585-3443 FAX 915-585-4944
432-689-6301 FAX 432-689-6313
972-242-7750
E-Mail: lab@traceanalysis.com WEB: www.traceanalysis.com

Certifications

WBE HUB NCTRCA DBE NELAP DoD LELAP Kansas Oklahoma ISO 17025

Analytical and Quality Control Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX, 79703

Report Date: February 12, 2013

Work Order: 13020603



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Enclosed are the Analytical Report and Quality Control Report for the following sample(s) submitted to TraceAnalysis, Inc.

Sample	Description	Matrix	Date	Time	Date
			Taken	Taken	Received
320345	MW-1	water	2013-02-05	13:02	2013-02-06

These results represent only the samples received in the laboratory. The Quality Control Report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your sample(s) were analyzed.

This report consists of a total of 10 pages and shall not be reproduced except in its entirety, without written approval of TraceAnalysis, Inc.

Dr. Blair Leftwich, Director
Dr. Michael Abel, Project Manager

Report Contents

Case Narrative	3
Analytical Report	4
Sample 320345 (MW-1)	4
Method Blanks	5
QC Batch 98865 - Method Blank (1)	5
Laboratory Control Spikes	6
QC Batch 98865 - LCS (1)	6
QC Batch 98865 - MS (1)	6
Calibration Standards	8
QC Batch 98865 - CCV (1)	8
QC Batch 98865 - CCV (2)	8
Appendix	9
Report Definitions	9
Laboratory Certifications	9
Standard Flags	9
Result Comments	9
Attachments	10

Case Narrative

Samples for project Monument #10 were received by TraceAnalysis, Inc. on 2013-02-06 and assigned to work order 13020603. Samples for work order 13020603 were received intact without headspace and at a temperature of 4.8 C.

Samples were analyzed for the following tests using their respective methods.

Test	Method	Prep Batch	Prep Date	QC Batch	Analysis Date
BTEX	S 8021B	83768	2013-02-11 at 12:00	98865	2013-02-11 at 12:00

Results for these samples are reported on a wet weight basis unless data package indicates otherwise.

A matrix spike (MS) and matrix spike duplicate (MSD) sample is chosen at random from each preparation batch. The MS and MSD will indicate if a site specific matrix problem is occurring, however, it may not pertain to the samples for work order 13020603 since the sample was chosen at random. Therefore, the validity of the analytical data reported has been determined by the laboratory control sample (LCS) and the method blank (MB). These quality control measures are performed with each preparation batch to ensure data integrity.

All other exceptions associated with this report have been footnoted on the appropriate analytical page to assist in general data comprehension. Please contact the laboratory directly if there are any questions regarding this project.

Analytical Report

Sample: 320345 - MW-1

Laboratory: Midland
Analysis: BTEX
QC Batch: 98865
Prep Batch: 83768

Analytical Method: S 8021B
Date Analyzed: 2013-02-11
Sample Preparation: 2013-02-11

Prep Method: S 5030B
Analyzed By: YG
Prepared By: YG

Parameter	Flag	Cert	RL		Units	Dilution	RL	
			Result					
Benzene	U	1	<0.00500		mg/L	5		0.00100
Toluene	U	1	<0.00500		mg/L	5		0.00100
Ethylbenzene	U	1	<0.00500		mg/L	5		0.00100
Xylene	U	1	<0.00500		mg/L	5		0.00100

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)	Qsr	Qsr	0.573	mg/L	5	0.500	115	75.7 - 109
4-Bromofluorobenzene (4-BFB)			0.503	mg/L	5	0.500	101	68.1 - 109

Method Blanks

Method Blank (1) QC Batch: 98865

QC Batch: 98865
Prep Batch: 83768

Date Analyzed: 2013-02-11
QC Preparation: 2013-02-11

Analyzed By: YG
Prepared By: YG

Parameter	Flag	Cert	MDL Result	Units	RL
Benzene		1	<0.000200	mg/L	0.001
Toluene		1	<0.000300	mg/L	0.001
Ethylbenzene		1	<0.000400	mg/L	0.001
Xylene		1	<0.00120	mg/L	0.001

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)	Qsr	Qsr	0.116	mg/L	1	0.100	116	75.7 - 109
4-Bromofluorobenzene (4-BFB)			0.101	mg/L	1	0.100	101	68.1 - 109

Laboratory Control Spikes

Laboratory Control Spike (LCS-1)

QC Batch: 98865
Prep Batch: 83768

Date Analyzed: 2013-02-11
QC Preparation: 2013-02-11

Analyzed By: YG
Prepared By: YG

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	0.106	mg/L	1	0.100	<0.000200	106	80 - 120
Toluene		1	0.107	mg/L	1	0.100	<0.000300	107	80 - 120
Ethylbenzene		1	0.111	mg/L	1	0.100	<0.000400	111	70.6 - 120
Xylene		1	0.345	mg/L	1	0.300	<0.00120	115	79.2 - 120

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Param	F	C	LCSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.102	mg/L	1	0.100	<0.000200	102	80 - 120	4	20
Toluene		1	0.104	mg/L	1	0.100	<0.000300	104	80 - 120	3	20
Ethylbenzene		1	0.108	mg/L	1	0.100	<0.000400	108	70.6 - 120	3	20
Xylene		1	0.335	mg/L	1	0.300	<0.00120	112	79.2 - 120	3	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate			LCS Result	LCSD Result	Units	Dil.	Spike Amount	LCS Rec.	LCSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	Q _{sr}	Q _{sr}	0.116	0.115	mg/L	1	0.100	116	115	75.7 - 109
4-Bromofluorobenzene (4-BFB)			0.103	0.102	mg/L	1	0.100	103	102	68.1 - 109

Matrix Spike (MS-1) Spiked Sample: 320428

QC Batch: 98865
Prep Batch: 83768

Date Analyzed: 2013-02-11
QC Preparation: 2013-02-11

Analyzed By: YG
Prepared By: YG

Param	F	C	MS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene	2	1	0.104	mg/L	1	0.100	<0.000200	104	25.7 - 139
Toluene		1	0.105	mg/L	1	0.100	<0.000300	105	32.7 - 134
Ethylbenzene		1	0.108	mg/L	1	0.100	<0.000400	108	45.9 - 120
Xylene		1	0.334	mg/L	1	0.300	<0.00120	111	34.9 - 128

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Param	F	C	MSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.106	mg/L	1	0.100	<0.000200	106	25.7 - 139	2	20
Toluene		1	0.108	mg/L	1	0.100	<0.000300	108	32.7 - 134	3	20
Ethylbenzene		1	0.112	mg/L	1	0.100	<0.000400	112	45.9 - 120	4	20
Xylene		1	0.341	mg/L	1	0.300	<0.00120	114	34.9 - 128	2	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate			MS Result	MSD Result	Units	Dil.	Spike Amount	MS Rec.	MSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	Q _{sr}	Q _{sr}	0.113	0.114	mg/L	1	0.1	113	114	75.7 - 109
4-Bromofluorobenzene (4-BFB)			0.100	0.102	mg/L	1	0.1	100	102	68.1 - 109

Calibration Standards

Standard (CCV-1)

QC Batch: 98865

Date Analyzed: 2013-02-11

Analyzed By: YG

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.104	104	80 - 120	2013-02-11
Toluene		1	mg/L	0.100	0.105	105	80 - 120	2013-02-11
Ethylbenzene		1	mg/L	0.100	0.110	110	80 - 120	2013-02-11
Xylene		1	mg/L	0.300	0.340	113	80 - 120	2013-02-11

Standard (CCV-2)

QC Batch: 98865

Date Analyzed: 2013-02-11

Analyzed By: YG

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.104	104	80 - 120	2013-02-11
Toluene		1	mg/L	0.100	0.105	105	80 - 120	2013-02-11
Ethylbenzene		1	mg/L	0.100	0.110	110	80 - 120	2013-02-11
Xylene		1	mg/L	0.300	0.340	113	80 - 120	2013-02-11

Appendix

Report Definitions

Name	Definition
MDL	Method Detection Limit
MQL	Minimum Quantitation Limit
SDL	Sample Detection Limit

Laboratory Certifications

C	Certifying Authority	Certification Number	Laboratory Location
-	NCTRCA	WFWB384444Y0909	TraceAnalysis
-	DBE	VN 20657	TraceAnalysis
-	HUB	1752439743100-86536	TraceAnalysis
-	WBE	237019	TraceAnalysis
1	NELAP	T104704392-12-4	Midland

Standard Flags

F	Description
B	Analyte detected in the corresponding method blank above the method detection limit
H	Analyzed out of hold time
J	Estimated concentration
Jb	The analyte is positively identified and the value is approximated between the SDL and MQL. Sample contains less then ten times the concentration found in the method blank. The result should be considered non-detect to the SDL.
Je	Estimated concentration exceeding calibration range.
MI1	Split peak or shoulder peak
MI2	Instrument software did not integrate
MI3	Instrument software misidentified the peak
MI4	Instrument software integrated improperly
MI5	Baseline correction
Qc	Calibration check outside of laboratory limits.
Qr	RPD outside of laboratory limits
Qs	Spike recovery outside of laboratory limits.
Qsr	Surrogate recovery outside of laboratory limits.
U	The analyte is not detected above the SDL

Result Comments

Report Date: February 12, 2013
NM-2007

Work Order: 13020603
Monument #10

Page Number: 10 of 10
Monument NM

- 1 Dilution due to surfactant.
- 2 pH >2 per client.

Attachments

The scanned attachments will follow this page.
Please note, each attachment may consist of more than one page.

TraceAnalysis, Inc.

6701 Aberdeen Avenue, Suite 9
Lubbock, Texas 79424
Tel (806) 794-1296
Fax (806) 794-1298
1 (800) 378-1296

200 East Sunset Rd., Suite E
El Paso, Texas 79922
Tel (915) 585-3443
Fax (915) 585-4944
1 (888) 588-3443

BioAquatic Testing
2501 Mayes Rd., Ste 100
Carrollton, Texas 75006
Tel (972) 242-7750

email: lab@traceanalysis.com

Company Name:	Nova	Phone #:	432 520 7720
Address:	(Street, City, Zip) 2057 Commerce Drive	Fax #:	432 520 7701
Contact Person:	Camille Bryant	E-mail:	
Invoice to:	(If different from above)		
Project #:	TUM Monument 10	Project Name:	Monument #10
Project Location (including state):	Sample Signature: <i>[Signature]</i>		

[illegible]

Relinquished by:	Company:	Date:	Time:	Received by:	Company:	Date:	Time:	INST
<i>[Signature]</i>	Nova	06 Feb 13	0927	<i>[Signature]</i>	TA	26/13	9:24	OBS 48° COR 48°
Relinquished by:	Company:	Date:	Time:	Received by:	Company:	Date:	Time:	INST OBS COR
Relinquished by:	Company:	Date:	Time:	Received by:	Company:	Date:	Time:	INST OBS COR

[illegible]

LAB USE ONLY	REMARKS:	<i>Medland .all</i> <i>Engl</i> ☐ Dry Weight Basis Required ☐ TRRP Report Required ☒ Check If Special Reporting Limits Are Needed
	Infant ☒ N Headspace ☒ N Log-in-Review ☒ N	

Submittal of samples constitutes agreement to Terms and Conditions listed on reverse side of C. O. C.

ORIGINAL COPY

Summary Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX 79703

Report Date: May 16, 2013

Work Order: 13051005



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
328898	MW-6	water	2013-05-09	12:40	2013-05-10
328899	MW-7	water	2013-05-09	12:36	2013-05-10
328900	MW-1	water	2013-05-09	12:20	2013-05-10

Sample - Field Code	BTEX			
	Benzene (mg/L)	Toluene (mg/L)	Ethylbenzene (mg/L)	Xylene (mg/L)
328898 - MW-6	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs
328899 - MW-7	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs
328900 - MW-1	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs	<0.00100 Qr,Qs



6701 Aberdeen Avenue, Suite 9
200 East Sunset Road, Suite E
5002 Basin Street, Suite A1
(BioAquatic) 2501 Mayes Rd., Suite 100

Lubbock, Texas 79424
El Paso, Texas 79922
Midland, Texas 79703
Carrollton, Texas 75006

800-378-1296

806-794-1296

FAX 806-794-1298

915-585-3443

FAX 915-585-4944

432-689-6301

FAX 432-689-6313

972-242-7750

E-Mail: lab@traceanalysis.com WEB: www.traceanalysis.com

Certifications

WBE HUB NCTRCA DBE NELAP DoD LELAP Kansas Oklahoma ISO 17025

Analytical and Quality Control Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX, 79703

Report Date: May 16, 2013

Work Order: 13051005



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Enclosed are the Analytical Report and Quality Control Report for the following sample(s) submitted to TraceAnalysis, Inc.

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
328898	MW-6	water	2013-05-09	12:40	2013-05-10
328899	MW-7	water	2013-05-09	12:36	2013-05-10
328900	MW-1	water	2013-05-09	12:20	2013-05-10

These results represent only the samples received in the laboratory. The Quality Control Report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your sample(s) were analyzed.

This report consists of a total of 11 pages and shall not be reproduced except in its entirety, without written approval of TraceAnalysis, Inc.

Dr. Blair Leftwich, Director
Dr. Michael Abel, Project Manager

Report Contents

Case Narrative	3
Analytical Report	4
Sample 328898 (MW-6)	4
Sample 328899 (MW-7)	4
Sample 328900 (MW-1)	4
Method Blanks	6
QC Batch 101437 - Method Blank (1)	6
Laboratory Control Spikes	7
QC Batch 101437 - LCS (1)	7
QC Batch 101437 - MS (1)	7
Calibration Standards	9
QC Batch 101437 - CCV (1)	9
QC Batch 101437 - CCV (2)	9
QC Batch 101437 - CCV (3)	9
Appendix	10
Report Definitions	10
Laboratory Certifications	10
Standard Flags	10
Result Comments	10
Attachments	11

Case Narrative

Samples for project Monument #10 were received by TraceAnalysis, Inc. on 2013-05-10 and assigned to work order 13051005. Samples for work order 13051005 were received intact without headspace and at a temperature of 3.1 C.

Samples were analyzed for the following tests using their respective methods.

Test	Method	Prep Batch	Prep Date	QC Batch	Analysis Date
BTEX	S 8021B	85958	2013-05-15 at 11:00	101437	2013-05-15 at 11:00

Results for these samples are reported on a wet weight basis unless data package indicates otherwise.

A matrix spike (MS) and matrix spike duplicate (MSD) sample is chosen at random from each preparation batch. The MS and MSD will indicate if a site specific matrix problem is occurring, however, it may not pertain to the samples for work order 13051005 since the sample was chosen at random. Therefore, the validity of the analytical data reported has been determined by the laboratory control sample (LCS) and the method blank (MB). These quality control measures are performed with each preparation batch to ensure data integrity.

All other exceptions associated with this report have been footnoted on the appropriate analytical page to assist in general data comprehension. Please contact the laboratory directly if there are any questions regarding this project.

Report Date: May 16, 2013
NM-2007

Work Order: 13051005
Monument #10

Page Number: 4 of 11
Monument NM

Analytical Report

Sample: 328898 - MW-6

Laboratory: Midland
Analysis: BTEX
QC Batch: 101437
Prep Batch: 85958

Analytical Method: S 8021B
Date Analyzed: 2013-05-15
Sample Preparation: 2013-05-15

Prep Method: S 5030B
Analyzed By: AH
Prepared By: AH

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Toluene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Xylene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0971	mg/L	1	0.100	97	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0959	mg/L	1	0.100	96	70 - 130

Sample: 328899 - MW-7

Laboratory: Midland
Analysis: BTEX
QC Batch: 101437
Prep Batch: 85958

Analytical Method: S 8021B
Date Analyzed: 2013-05-15
Sample Preparation: 2013-05-15

Prep Method: S 5030B
Analyzed By: AH
Prepared By: AH

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Toluene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Xylene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0994	mg/L	1	0.100	99	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0985	mg/L	1	0.100	98	70 - 130

Report Date: May 16, 2013
NM-2007

Work Order: 13051005
Monument #10

Page Number: 5 of 11
Monument NM

Sample: 328900 - MW-1

Laboratory: Midland
Analysis: BTEX
QC Batch: 101437
Prep Batch: 85958

Analytical Method: S 8021B
Date Analyzed: 2013-05-15
Sample Preparation: 2013-05-15

Prep Method: S 5030B
Analyzed By: AH
Prepared By: AH

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Toluene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100
Xylene	Qr, Qs, U	1	<0.00100	mg/L	1	0.00100

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0950	mg/L	1	0.100	95	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0953	mg/L	1	0.100	95	70 - 130

Method Blanks

Method Blank (1) QC Batch: 101437

QC Batch: 101437
Prep Batch: 85958

Date Analyzed: 2013-05-15
QC Preparation: 2013-05-15

Analyzed By: AH
Prepared By: AH

Parameter	Flag	Cert	MDL Result	Units	RL
Benzene		1	<0.000200	mg/L	0.001
Toluene		1	<0.000300	mg/L	0.001
Ethylbenzene		1	<0.000400	mg/L	0.001
Xylene		1	<0.00120	mg/L	0.001

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.101	mg/L	1	0.100	101	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0955	mg/L	1	0.100	96	70 - 130

Laboratory Control Spikes

Laboratory Control Spike (LCS-1)

QC Batch: 101437
Prep Batch: 85958

Date Analyzed: 2013-05-15
QC Preparation: 2013-05-15

Analyzed By: AH
Prepared By: AH

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	0.102	mg/L	1	0.100	<0.000200	102	70 - 130
Toluene		1	0.104	mg/L	1	0.100	<0.000300	104	70 - 130
Ethylbenzene		1	0.103	mg/L	1	0.100	<0.000400	103	70 - 130
Xylene		1	0.306	mg/L	1	0.300	<0.00120	102	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Param	F	C	LCSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.102	mg/L	1	0.100	<0.000200	102	70 - 130	0	20
Toluene		1	0.106	mg/L	1	0.100	<0.000300	106	70 - 130	2	20
Ethylbenzene		1	0.106	mg/L	1	0.100	<0.000400	106	70 - 130	3	20
Xylene		1	0.309	mg/L	1	0.300	<0.00120	103	70 - 130	1	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	LCS Result	LCSD Result	Units	Dil.	Spike Amount	LCS Rec.	LCSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	0.0998	0.0995	mg/L	1	0.100	100	100	70 - 130
4-Bromofluorobenzene (4-BFB)	0.100	0.0999	mg/L	1	0.100	100	100	70 - 130

Matrix Spike (MS-1) Spiked Sample: 328546

QC Batch: 101437
Prep Batch: 85958

Date Analyzed: 2013-05-15
QC Preparation: 2013-05-15

Analyzed By: AH
Prepared By: AH

Param		F	C	MS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene	¹ Qs	Qs	1	0.0130	mg/L	1	0.100	<0.000200	13	70 - 130
Toluene	Qs	Qs	1	0.0143	mg/L	1	0.100	<0.000300	14	70 - 130
Ethylbenzene	Qs	Qs	1	0.0191	mg/L	1	0.100	<0.000400	19	70 - 130
Xylene	Qs	Qs	1	0.0568	mg/L	1	0.300	<0.00120	19	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Report Date: May 16, 2013
NM-2007

Work Order: 13051005
Monument #10

Page Number: 8 of 11
Monument NM

Param		F	C	MSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit	
Benzene	²	Q _r , Q _s	Q _r , Q _s	1	0.0247	mg/L	1	0.100	<0.000200	25	70 - 130	62	20
Toluene		Q _r , Q _s	Q _r , Q _s	1	0.0256	mg/L	1	0.100	<0.000300	26	70 - 130	57	20
Ethylbenzene		Q _r , Q _s	Q _r , Q _s	1	0.0280	mg/L	1	0.100	<0.000400	28	70 - 130	38	20
Xylene		Q _r , Q _s	Q _r , Q _s	1	0.0828	mg/L	1	0.300	<0.00120	28	70 - 130	37	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	MS Result	MSD Result	Units	Dil.	Spike Amount	MS Rec.	MSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	0.0949	0.0938	mg/L	1	0.1	95	94	70 - 130
4-Bromofluorobenzene (4-BFB)	0.0945	0.0941	mg/L	1	0.1	94	94	70 - 130

Calibration Standards

Standard (CCV-1)

QC Batch: 101437

Date Analyzed: 2013-05-15

Analyzed By: AH

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.0970	97	80 - 120	2013-05-15
Toluene		1	mg/L	0.100	0.0996	100	80 - 120	2013-05-15
Ethylbenzene		1	mg/L	0.100	0.0989	99	80 - 120	2013-05-15
Xylene		1	mg/L	0.300	0.291	97	80 - 120	2013-05-15

Standard (CCV-2)

QC Batch: 101437

Date Analyzed: 2013-05-15

Analyzed By: AH

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.0971	97	80 - 120	2013-05-15
Toluene		1	mg/L	0.100	0.100	100	80 - 120	2013-05-15
Ethylbenzene		1	mg/L	0.100	0.0994	99	80 - 120	2013-05-15
Xylene		1	mg/L	0.300	0.292	97	80 - 120	2013-05-15

Standard (CCV-3)

QC Batch: 101437

Date Analyzed: 2013-05-15

Analyzed By: AH

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.100	100	80 - 120	2013-05-15
Toluene		1	mg/L	0.100	0.102	102	80 - 120	2013-05-15
Ethylbenzene		1	mg/L	0.100	0.102	102	80 - 120	2013-05-15
Xylene		1	mg/L	0.300	0.298	99	80 - 120	2013-05-15

Appendix

Report Definitions

Name	Definition
MDL	Method Detection Limit
MQL	Minimum Quantitation Limit
SDL	Sample Detection Limit

Laboratory Certifications

C	Certifying Authority	Certification Number	Laboratory Location
-	NCTRCA	WFWB384444Y0909	TraceAnalysis
-	DBE	VN 20657	TraceAnalysis
-	HUB	1752439743100-86536	TraceAnalysis
-	WBE	237019	TraceAnalysis
1	NELAP	T104704392-12-4	Midland

Standard Flags

F	Description
B	Analyte detected in the corresponding method blank above the method detection limit
H	Analyzed out of hold time
J	Estimated concentration
Jb	The analyte is positively identified and the value is approximated between the SDL and MQL. Sample contains less then ten times the concentration found in the method blank. The result should be considered non-detect to the SDL.
Je	Estimated concentration exceeding calibration range.
MI1	Split peak or shoulder peak
MI2	Instrument software did not integrate
MI3	Instrument software misidentified the peak
MI4	Instrument software integrated improperly
MI5	Baseline correction
Qc	Calibration check outside of laboratory limits.
Qr	RPD outside of laboratory limits
Qs	Spike recovery outside of laboratory limits.
Qsr	Surrogate recovery outside of laboratory limits.
U	The analyte is not detected above the SDL

Result Comments

- 1 Prep error, LCS LCSD within range show spikes to be under control.
- 2 Prep error, LCS LCSD within range show spikes to be under control.

Attachments

The scanned attachments will follow this page.

Please note, each attachment may consist of more than one page.

Page 1 of 1

6701 Aberdeen Avenue, Suite 9
Lubbock, Texas 79424
Tel (806) 794-1296
Fax (806) 794-1298
1 (800) 378-1296

5002 Basin Street, Suite A1
Midland, Texas 79703
Tel (432) 689-6301
Fax (432) 689-6313

200 East Sunset Rd., Suite E
El Paso, Texas 79922
Tel (915) 585-3443
Fax (915) 585-4944
1 (888) 588-3443

BioAquatic Testing
2501 Mayes Rd., Ste 100
Carrollton, Texas 75006
Tel (972) 242-7750

Fax (806) 794-1298
1 (800) 378-1296

Fax (432) 689-6313
1 (888) 588-3443

Fax (915) 385-1944
1 (888) 588-3443

lei (912) 242-1750

Company Name: A	Phone #: 1-2-3-4-5-6-7-8-9-0	ANALYSIS REQUEST
-----------------	------------------------------	------------------

Address:	(Street, City, Zip)	Fax #:	(Circle or Specify Method No.)
----------	---------------------	--------	--------------------------------

[illegible]

Invoice to:

Project #:	Project Name:
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

Project Location (Including state):	
Sampler Signature:	
TX#	050 /
CD	22-2
Pr	
Co	

27024488NONO, E, E

[illegible][illegible]

Sweden

Notes
5/10/13 DU
Wala
11/13 0.10
COR 31.0
ONLY

Delinquency by:	Company:	Date:	Time:
Receivable by:	Company:	Date:	Time:
INST			

relinquished by: _____ Date: _____
 Company: _____
 Title: _____
 Received by: _____ Date: _____
 Company: _____
 Title: _____
 CBS _____
 Instruct Y / N _____
 Instruct Y / N _____

[illegible][illegible]

Relinquished by: _____
 Date: _____
 Time: _____
 Company: _____

Received by: _____
 Date: _____
 Time: _____
 Company: _____

INST _____
 TRRP Report Required _____

OBS _____ **C** _____ **Log-in-Review** _____ **Check If Special Reporting** _____

 1. 0-100% 2. 0-100% 3. 0-100% 4. 0-100% 5. 0-100% 6. 0-100% 7. 0-100% 8. 0-100% 9. 0-100% 10. 0-100% 11. 0-100% 12. 0-100% 13. 0-100% 14. 0-100% 15. 0-100% 16. 0-100% 17. 0-100% 18. 0-100% 19. 0-100% 20. 0-100% 21. 0-100% 22. 0-100% 23. 0-100% 24. 0-100% 25. 0-100% 26. 0-100% 27. 0-100% 28. 0-100% 29. 0-100% 30. 0-100% 31. 0-100% 32. 0-100% 33. 0-100% 34. 0-100% 35. 0-100% 36. 0-100% 37. 0-100% 38. 0-100% 39. 0-100% 40. 0-100% 41. 0-100% 42. 0-100% 43. 0-100% 44. 0-100% 45. 0-100% 46. 0-100% 47. 0-100% 48. 0-100% 49. 0-100% 50. 0-100% 51. 0-100% 52. 0-100% 53. 0-100% 54. 0-100% 55. 0-100% 56. 0-100% 57. 0-100% 58. 0-100% 59. 0-100% 60. 0-100% 61. 0-100% 62. 0-100% 63. 0-100% 64. 0-100% 65. 0-100% 66. 0-100% 67. 0-100% 68. 0-100% 69. 0-100% 70. 0-100% 71. 0-100% 72. 0-100% 73. 0-100% 74. 0-100% 75. 0-100% 76. 0-100% 77. 0-100% 78. 0-100% 79. 0-100% 80. 0-100% 81. 0-100% 82. 0-100% 83. 0-100% 84. 0-100% 85. 0-100% 86. 0-100% 87. 0-100% 88. 0-100% 89. 0-100% 90. 0-100% 91. 0-100% 92. 0-100% 93. 0-100% 94. 0-100% 95. 0-100% 96. 0-100% 97. 0-100% 98. 0-100% 99. 0-100% 100. 0-100%

COR	c	Limits Are Needed

Carrier #
 Submittal of samples constitutes agreement to Terms and Conditions listed on reverse side of C. O. C.

Journal of Interpersonal Violence 30(10) 1799-1816

ORIGINAL COPY

Summary Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX 79703

Report Date: August 8, 2013

Work Order: 13080204



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
337353	MW-1	water	2013-08-01	13:24	2013-08-02

Sample - Field Code	BTEX			
	Benzene (mg/L)	Toluene (mg/L)	Ethylbenzene (mg/L)	Xylene (mg/L)
337353 - MW-1	<0.00100	<0.00100	<0.00100	0.00390



TRACEANALYSIS, INC.

6701 Aberdeen Avenue, Suite 9	Lubbock, Texas 79424	800-378-1296	806-794-1296	FAX 806-794-1298
200 East Sunset Road, Suite E	El Paso, Texas 79922		915-585-3443	FAX 915-585-4944
5002 Basin Street, Suite A1	Midland, Texas 79703		432-689-6301	FAX 432-689-6313
(BioAquatic) 2501 Mayes Rd., Suite 100	Carrollton, Texas 75006		972-242-7750	
E-Mail: lab@traceanalysis.com		WEB: www.traceanalysis.com		

Certifications

WBE HUB NCTRCA DBE NELAP DoD LELAP Kansas Oklahoma ISO 17025

Analytical and Quality Control Report

Camille Bryant
Nova Safety & Environmental
2057 Commerce St.
Midland, TX, 79703

Report Date: August 8, 2013

Work Order: 13080204



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Enclosed are the Analytical Report and Quality Control Report for the following sample(s) submitted to TraceAnalysis, Inc.

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
337353	MW-1	water	2013-08-01	13:24	2013-08-02

These results represent only the samples received in the laboratory. The Quality Control Report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your sample(s) were analyzed.

This report consists of a total of 10 pages and shall not be reproduced except in its entirety, without written approval of TraceAnalysis, Inc.



Dr. Blair Leftwich, Director
Dr. Michael Abel, Project Manager

Report Contents

Case Narrative	3
Analytical Report	4
Sample 337353 (MW-1)	4
Method Blanks	5
QC Batch 103804 - Method Blank (1)	5
Laboratory Control Spikes	6
QC Batch 103804 - LCS (1)	6
QC Batch 103804 - MS (1)	6
Calibration Standards	8
QC Batch 103804 - CCV (1)	8
QC Batch 103804 - CCV (2)	8
QC Batch 103804 - CCV (3)	8
Appendix	9
Report Definitions	9
Laboratory Certifications	9
Standard Flags	9
Attachments	9

Case Narrative

Samples for project Monument #10 were received by TraceAnalysis, Inc. on 2013-08-02 and assigned to work order 13080204. Samples for work order 13080204 were received intact without headspace and at a temperature of 4.3 C.

Samples were analyzed for the following tests using their respective methods.

Test	Method	Prep Batch	Prep Date	QC Batch	Analysis Date
BTEX	S 8021B	87952	2013-08-07 at 16:30	103804	2013-08-08 at 09:39

Results for these samples are reported on a wet weight basis unless data package indicates otherwise.

A matrix spike (MS) and matrix spike duplicate (MSD) sample is chosen at random from each preparation batch. The MS and MSD will indicate if a site specific matrix problem is occurring, however, it may not pertain to the samples for work order 13080204 since the sample was chosen at random. Therefore, the validity of the analytical data reported has been determined by the laboratory control sample (LCS) and the method blank (MB). These quality control measures are performed with each preparation batch to ensure data integrity.

All other exceptions associated with this report have been footnoted on the appropriate analytical page to assist in general data comprehension. Please contact the laboratory directly if there are any questions regarding this project.

Report Date: August 8, 2013
NM-2007

Work Order: 13080204
Monument #10

Page Number: 4 of 10
Monument NM

Analytical Report

Sample: 337353 - MW-1

Laboratory: Midland
Analysis: BTEX
QC Batch: 103804
Prep Batch: 87952

Analytical Method: S 8021B
Date Analyzed: 2013-08-08
Sample Preparation: 2013-08-07

Prep Method: S 5030B
Analyzed By: KC
Prepared By: KC

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	U	1	<0.00100	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene		1	0.00390	mg/L	1	0.00100

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0953	mg/L	1	0.100	95	70 - 130
4-Bromofluorobenzene (4-BFB)			0.114	mg/L	1	0.100	114	70 - 130

Method Blanks

Method Blank (1) QC Batch: 103804

QC Batch: 103804
Prep Batch: 87952

Date Analyzed: 2013-08-08
QC Preparation: 2013-08-07

Analyzed By: KC
Prepared By: KC

Parameter	Flag	Cert	MDL Result	Units	RL
Benzene		1	<0.000200	mg/L	0.001
Toluene		1	<0.000300	mg/L	0.001
Ethylbenzene		1	<0.000400	mg/L	0.001
Xylene		1	<0.00120	mg/L	0.001

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0967	mg/L	1	0.100	97	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0964	mg/L	1	0.100	96	70 - 130

Laboratory Control Spikes

Laboratory Control Spike (LCS-1)

QC Batch: 103804
Prep Batch: 87952

Date Analyzed: 2013-08-08
QC Preparation: 2013-08-07

Analyzed By: KC
Prepared By: KC

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	0.115	mg/L	1	0.100	<0.000200	115	70 - 130
Toluene		1	0.113	mg/L	1	0.100	<0.000300	113	70 - 130
Ethylbenzene		1	0.113	mg/L	1	0.100	<0.000400	113	70 - 130
Xylene		1	0.341	mg/L	1	0.300	<0.00120	114	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.116	mg/L	1	0.100	<0.000200	116	70 - 130	1	20
Toluene		1	0.115	mg/L	1	0.100	<0.000300	115	70 - 130	2	20
Ethylbenzene		1	0.114	mg/L	1	0.100	<0.000400	114	70 - 130	1	20
Xylene		1	0.344	mg/L	1	0.300	<0.00120	115	70 - 130	1	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	LCS Result	LCS Result	Units	Dil.	Spike Amount	LCS Rec.	LCS Rec.	Rec. Limit
Trifluorotoluene (TFT)	0.0963	0.0989	mg/L	1	0.100	96	99	70 - 130
4-Bromofluorobenzene (4-BFB)	0.103	0.105	mg/L	1	0.100	103	105	70 - 130

Matrix Spike (MS-1) Spiked Sample: 337375

QC Batch: 103804
Prep Batch: 87952

Date Analyzed: 2013-08-08
QC Preparation: 2013-08-07

Analyzed By: KC
Prepared By: KC

Param	F	C	MS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	0.113	mg/L	1	0.100	<0.000200	113	70 - 130
Toluene		1	0.112	mg/L	1	0.100	<0.000300	112	70 - 130
Ethylbenzene		1	0.111	mg/L	1	0.100	<0.000400	111	70 - 130
Xylene		1	0.331	mg/L	1	0.300	<0.00120	110	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Report Date: August 8, 2013
NM-2007

Work Order: 13080204
Monument #10

Page Number: 7 of 10
Monument NM

Param	F	C	MSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.113	mg/L	1	0.100	<0.000200	113	70 - 130	0	20
Toluene		1	0.113	mg/L	1	0.100	<0.000300	113	70 - 130	1	20
Ethylbenzene		1	0.112	mg/L	1	0.100	<0.000400	112	70 - 130	1	20
Xylene		1	0.333	mg/L	1	0.300	<0.00120	111	70 - 130	1	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	MS Result	MSD Result	Units	Dil.	Spike Amount	MS Rec.	MSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	0.0941	0.0936	mg/L	1	0.1	94	94	70 - 130
4-Bromofluorobenzene (4-BFB)	0.101	0.100	mg/L	1	0.1	101	100	70 - 130

Calibration Standards

Standard (CCV-1)

QC Batch: 103804

Date Analyzed: 2013-08-08

Analyzed By: KC

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.116	116	80 - 120	2013-08-08
Toluene		1	mg/L	0.100	0.114	114	80 - 120	2013-08-08
Ethylbenzene		1	mg/L	0.100	0.114	114	80 - 120	2013-08-08
Xylene		1	mg/L	0.300	0.343	114	80 - 120	2013-08-08

Standard (CCV-2)

QC Batch: 103804

Date Analyzed: 2013-08-08

Analyzed By: KC

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.112	112	80 - 120	2013-08-08
Toluene		1	mg/L	0.100	0.111	111	80 - 120	2013-08-08
Ethylbenzene		1	mg/L	0.100	0.111	111	80 - 120	2013-08-08
Xylene		1	mg/L	0.300	0.332	111	80 - 120	2013-08-08

Standard (CCV-3)

QC Batch: 103804

Date Analyzed: 2013-08-08

Analyzed By: KC

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.112	112	80 - 120	2013-08-08
Toluene		1	mg/L	0.100	0.111	111	80 - 120	2013-08-08
Ethylbenzene		1	mg/L	0.100	0.110	110	80 - 120	2013-08-08
Xylene		1	mg/L	0.300	0.330	110	80 - 120	2013-08-08

Appendix

Report Definitions

Name	Definition
MDL	Method Detection Limit
MQL	Minimum Quantitation Limit
SDL	Sample Detection Limit

Laboratory Certifications

C	Certifying Authority	Certification Number	Laboratory Location
-	NCTRCA	WFWB384444Y0909	TraceAnalysis
-	DBE	VN 20657	TraceAnalysis
-	HUB	1752439743100-86536	TraceAnalysis
-	WBE	237019	TraceAnalysis
1	NELAP	T104704392-12-4	Midland

Standard Flags

F	Description
B	Analyte detected in the corresponding method blank above the method detection limit
H	Analyzed out of hold time
J	Estimated concentration
Jb	The analyte is positively identified and the value is approximated between the SDL and MQL. Sample contains less than ten times the concentration found in the method blank. The result should be considered non-detect to the SDL.
Je	Estimated concentration exceeding calibration range.
MI1	Split peak or shoulder peak
MI2	Instrument software did not integrate
MI3	Instrument software misidentified the peak
MI4	Instrument software integrated improperly
MI5	Baseline correction
Qc	Calibration check outside of laboratory limits.
Qr	RPD outside of laboratory limits
Qs	Spike recovery outside of laboratory limits.
Qsr	Surrogate recovery outside of laboratory limits.
U	The analyte is not detected above the SDL

Attachments

Report Date: August 8, 2013
NM-2007

Work Order: 13080204
Monument #10

Page Number: 10 of 10
Monument NM

The scanned attachments will follow this page.
Please note, each attachment may consist of more than one page.

Summary Report

Curt Stanley
Nova Safety & Environmental
2057 Commerce St.
Midland, TX 79703

Report Date: November 12, 2013


Work Order: 13110802



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
346059	MW-4	water	2013-11-07	13:55	2013-11-08
346060	MW-5	water	2013-11-07	14:15	2013-11-08
346061	MW-6	water	2013-11-07	14:24	2013-11-08
346062	MW-7	water	2013-11-07	14:40	2013-11-08
346063	MW-1	water	2013-11-07	14:53	2013-11-08

Sample - Field Code	BTEX			
	Benzene (mg/L)	Toluene (mg/L)	Ethylbenzene (mg/L)	Xylene (mg/L)
346059 - MW-4	<0.00100	<0.00100	<0.00100	<0.00300
346060 - MW-5	<0.00100	<0.00100	<0.00100	<0.00300
346061 - MW-6	<0.00100	<0.00100	<0.00100	<0.00300
346062 - MW-7	<0.00100	<0.00100	<0.00100	<0.00300
346063 - MW-1	0.00310	<0.00100	<0.00100	<0.00300



Certifications

WBE HUB NCTRCA DBE NELAP DoD LELAP Kansas Oklahoma ISO 17025

Analytical and Quality Control Report

Curt Stanley
Nova Safety & Environmental
2057 Commerce St.
Midland, TX, 79703

Report Date: November 12, 2013

Work Order: 13110802



Project Location: Monument NM
Project Name: Monument #10
Project Number: NM-2007
SRS #: TNM Monument 10

Enclosed are the Analytical Report and Quality Control Report for the following sample(s) submitted to TraceAnalysis, Inc.

Sample	Description	Matrix	Date Taken	Time Taken	Date Received
346059	MW-4	water	2013-11-07	13:55	2013-11-08
346060	MW-5	water	2013-11-07	14:15	2013-11-08
346061	MW-6	water	2013-11-07	14:24	2013-11-08
346062	MW-7	water	2013-11-07	14:40	2013-11-08
346063	MW-1	water	2013-11-07	14:53	2013-11-08

These results represent only the samples received in the laboratory. The Quality Control Report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your sample(s) were analyzed.

This report consists of a total of 13 pages and shall not be reproduced except in its entirety, without written approval of TraceAnalysis, Inc.

A handwritten signature in black ink that reads "Michael Abel". The signature is written in a cursive style with a large, prominent 'M' and 'A'.

Dr. Blair Leftwich, Director
Dr. Michael Abel, Project Manager

Report Contents

Case Narrative	4
Analytical Report	5
Sample 346059 (MW-4)	5
Sample 346060 (MW-5)	5
Sample 346061 (MW-6)	5
Sample 346062 (MW-7)	6
Sample 346063 (MW-1)	6
Method Blanks	8
QC Batch 106702 - Method Blank (1)	8
Laboratory Control Spikes	9
QC Batch 106702 - LCS (1)	9
QC Batch 106702 - MS (1)	9
Calibration Standards	11
QC Batch 106702 - CCV (1)	11
QC Batch 106702 - CCV (2)	11
QC Batch 106702 - CCV (3)	11
Appendix	12
Report Definitions	12
Laboratory Certifications	12
Standard Flags	12
Attachments	12

Case Narrative

Samples for project Monument #10 were received by TraceAnalysis, Inc. on 2013-11-08 and assigned to work order 13110802. Samples for work order 13110802 were received intact without headspace and at a temperature of 3.8 C.

Samples were analyzed for the following tests using their respective methods.

Test	Method	Prep Batch	Prep Date	QC Batch	Analysis Date
BTEX	S 8021B	90343	2013-11-11 at 08:56	106702	2013-11-11 at 10:00

Results for these samples are reported on a wet weight basis unless data package indicates otherwise.

A matrix spike (MS) and matrix spike duplicate (MSD) sample is chosen at random from each preparation batch. The MS and MSD will indicate if a site specific matrix problem is occurring, however, it may not pertain to the samples for work order 13110802 since the sample was chosen at random. Therefore, the validity of the analytical data reported has been determined by the laboratory control sample (LCS) and the method blank (MB). These quality control measures are performed with each preparation batch to ensure data integrity.

All other exceptions associated with this report have been footnoted on the appropriate analytical page to assist in general data comprehension. Please contact the laboratory directly if there are any questions regarding this project.

Report Date: November 12, 2013
NM-2007

Work Order: 13110802
Monument #10

Page Number: 5 of 13
Monument NM

Analytical Report

Sample: 346059 - MW-4

Laboratory: Midland
Analysis: BTEX
QC Batch: 106702
Prep Batch: 90343

Analytical Method: S 8021B
Date Analyzed: 2013-11-11
Sample Preparation: 2013-11-11

Prep Method: S 5030B
Analyzed By: AK
Prepared By: AK

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	U	1	<0.00100	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene	U	1	<0.00300	mg/L	1	0.00300

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0812	mg/L	1	0.100	81	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0748	mg/L	1	0.100	75	70 - 130

Sample: 346060 - MW-5

Laboratory: Midland
Analysis: BTEX
QC Batch: 106702
Prep Batch: 90343

Analytical Method: S 8021B
Date Analyzed: 2013-11-11
Sample Preparation: 2013-11-11

Prep Method: S 5030B
Analyzed By: AK
Prepared By: AK

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	U	1	<0.00100	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene	U	1	<0.00300	mg/L	1	0.00300

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0807	mg/L	1	0.100	81	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0735	mg/L	1	0.100	74	70 - 130

Report Date: November 12, 2013
NM-2007

Work Order: 13110802
Monument #10

Page Number: 6 of 13
Monument NM

Sample: 346061 - MW-6

Laboratory: Midland

Analysis: BTEX

QC Batch: 106702

Prep Batch: 90343

Analytical Method: S 8021B

Date Analyzed: 2013-11-11

Sample Preparation: 2013-11-11

Prep Method: S 5030B

Analyzed By: AK

Prepared By: AK

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	U	1	<0.00100	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene	U	1	<0.00300	mg/L	1	0.00300

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0820	mg/L	1	0.100	82	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0741	mg/L	1	0.100	74	70 - 130

Sample: 346062 - MW-7

Laboratory: Midland

Analysis: BTEX

QC Batch: 106702

Prep Batch: 90343

Analytical Method: S 8021B

Date Analyzed: 2013-11-11

Sample Preparation: 2013-11-11

Prep Method: S 5030B

Analyzed By: AK

Prepared By: AK

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene	U	1	<0.00100	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene	U	1	<0.00300	mg/L	1	0.00300

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0836	mg/L	1	0.100	84	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0755	mg/L	1	0.100	76	70 - 130

Report Date: November 12, 2013
NM-2007

Work Order: 13110802
Monument #10

Page Number: 7 of 13
Monument NM

Sample: 346063 - MW-1

Laboratory: Midland

Analysis: BTEX

QC Batch: 106702

Prep Batch: 90343

Analytical Method: S 8021B

Date Analyzed: 2013-11-11

Sample Preparation: 2013-11-11

Prep Method: S 5030B

Analyzed By: AK

Prepared By: AK

Parameter	Flag	Cert	RL Result	Units	Dilution	RL
Benzene		1	0.00310	mg/L	1	0.00100
Toluene	U	1	<0.00100	mg/L	1	0.00100
Ethylbenzene	U	1	<0.00100	mg/L	1	0.00100
Xylene	U	1	<0.00300	mg/L	1	0.00300

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0847	mg/L	1	0.100	85	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0799	mg/L	1	0.100	80	70 - 130

Method Blanks

Method Blank (1) QC Batch: 106702

QC Batch: 106702
Prep Batch: 90343

Date Analyzed: 2013-11-11
QC Preparation: 2013-11-11

Analyzed By: AK
Prepared By: AK

Parameter	Flag	Cert	MDL Result	Units	RL
Benzene		1	<0.000600	mg/L	0.001
Toluene		1	<0.000400	mg/L	0.001
Ethylbenzene		1	<0.000600	mg/L	0.001
Xylene		1	<0.00130	mg/L	0.003

Surrogate	Flag	Cert	Result	Units	Dilution	Spike Amount	Percent Recovery	Recovery Limits
Trifluorotoluene (TFT)			0.0808	mg/L	1	0.100	81	70 - 130
4-Bromofluorobenzene (4-BFB)			0.0731	mg/L	1	0.100	73	70 - 130

Laboratory Control Spikes

Laboratory Control Spike (LCS-1)

QC Batch: 106702
Prep Batch: 90343

Date Analyzed: 2013-11-11
QC Preparation: 2013-11-11

Analyzed By: AK
Prepared By: AK

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	0.0868	mg/L	1	0.100	<0.000600	87	70 - 130
Toluene		1	0.0859	mg/L	1	0.100	<0.000400	86	70 - 130
Ethylbenzene		1	0.0855	mg/L	1	0.100	<0.000600	86	70 - 130
Xylene		1	0.257	mg/L	1	0.300	<0.00130	86	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Param	F	C	LCS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	0.0857	mg/L	1	0.100	<0.000600	86	70 - 130	1	20
Toluene		1	0.0852	mg/L	1	0.100	<0.000400	85	70 - 130	1	20
Ethylbenzene		1	0.0845	mg/L	1	0.100	<0.000600	84	70 - 130	1	20
Xylene		1	0.255	mg/L	1	0.300	<0.00130	85	70 - 130	1	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	LCS Result	LCS Result	Units	Dil.	Spike Amount	LCS Rec.	LCS Rec.	Rec. Limit
Trifluorotoluene (TFT)	0.0873	0.0842	mg/L	1	0.100	87	84	70 - 130
4-Bromofluorobenzene (4-BFB)	0.0906	0.0902	mg/L	1	0.100	91	90	70 - 130

Matrix Spike (MS-1) Spiked Sample: 346058

QC Batch: 106702
Prep Batch: 90343

Date Analyzed: 2013-11-11
QC Preparation: 2013-11-11

Analyzed By: AK
Prepared By: AK

Param	F	C	MS Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit
Benzene		1	5.63	mg/L	50	5.00	1.4	85	70 - 130
Toluene		1	4.18	mg/L	50	5.00	<0.0200	84	70 - 130
Ethylbenzene		1	4.38	mg/L	50	5.00	0.19	84	70 - 130
Xylene		1	12.5	mg/L	50	15.0	<0.0650	83	70 - 130

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Report Date: November 12, 2013
NM-2007

Work Order: 13110802
Monument #10

Page Number: 10 of 13
Monument NM

Param	F	C	MSD Result	Units	Dil.	Spike Amount	Matrix Result	Rec.	Rec. Limit	RPD	RPD Limit
Benzene		1	5.93	mg/L	50	5.00	1.4	91	70 - 130	5	20
Toluene		1	4.43	mg/L	50	5.00	<0.0200	89	70 - 130	6	20
Ethylbenzene		1	4.64	mg/L	50	5.00	0.19	89	70 - 130	6	20
Xylene		1	13.2	mg/L	50	15.0	<0.0650	88	70 - 130	5	20

Percent recovery is based on the spike result. RPD is based on the spike and spike duplicate result.

Surrogate	MS Result	MSD Result	Units	Dil.	Spike Amount	MS Rec.	MSD Rec.	Rec. Limit
Trifluorotoluene (TFT)	4.24	4.33	mg/L	50	5	85	87	70 - 130
4-Bromofluorobenzene (4-BFB)	4.57	4.59	mg/L	50	5	91	92	70 - 130

Calibration Standards

Standard (CCV-1)

QC Batch: 106702

Date Analyzed: 2013-11-11

Analyzed By: AK

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.0889	89	80 - 120	2013-11-11
Toluene		1	mg/L	0.100	0.0878	88	80 - 120	2013-11-11
Ethylbenzene		1	mg/L	0.100	0.0879	88	80 - 120	2013-11-11
Xylene		1	mg/L	0.300	0.264	88	80 - 120	2013-11-11

Standard (CCV-2)

QC Batch: 106702

Date Analyzed: 2013-11-11

Analyzed By: AK

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.0867	87	80 - 120	2013-11-11
Toluene		1	mg/L	0.100	0.0856	86	80 - 120	2013-11-11
Ethylbenzene		1	mg/L	0.100	0.0850	85	80 - 120	2013-11-11
Xylene		1	mg/L	0.300	0.256	85	80 - 120	2013-11-11

Standard (CCV-3)

QC Batch: 106702

Date Analyzed: 2013-11-11

Analyzed By: AK

Param	Flag	Cert	Units	CCVs True Conc.	CCVs Found Conc.	CCVs Percent Recovery	Percent Recovery Limits	Date Analyzed
Benzene		1	mg/L	0.100	0.0889	89	80 - 120	2013-11-11
Toluene		1	mg/L	0.100	0.0877	88	80 - 120	2013-11-11
Ethylbenzene		1	mg/L	0.100	0.0865	86	80 - 120	2013-11-11
Xylene		1	mg/L	0.300	0.260	87	80 - 120	2013-11-11

Appendix

Report Definitions

Name	Definition
MDL	Method Detection Limit
MQL	Minimum Quantitation Limit
SDL	Sample Detection Limit

Laboratory Certifications

C	Certifying Authority	Certification Number	Laboratory Location
-	NCTRCA	WFWB384444Y0909	TraceAnalysis
-	DBE	VN 20657	TraceAnalysis
-	HUB	1752439743100-86536	TraceAnalysis
-	WBE	237019	TraceAnalysis
1	NELAP	T104704392-12-4	Midland

Standard Flags

F	Description
B	Analyte detected in the corresponding method blank above the method detection limit
H	Analyzed out of hold time
J	Estimated concentration
Jb	The analyte is positively identified and the value is approximated between the SDL and MQL. Sample contains less then ten times the concentration found in the method blank. The result should be considered non-detect to the SDL.
Je	Estimated concentration exceeding calibration range.
MI1	Split peak or shoulder peak
MI2	Instrument software did not integrate
MI3	Instrument software misidentified the peak
MI4	Instrument software integrated improperly
MI5	Baseline correction
Qc	Calibration check outside of laboratory limits.
Qr	RPD outside of laboratory limits
Qs	Spike recovery outside of laboratory limits.
Qsr	Surrogate recovery outside of laboratory limits.
U	The analyte is not detected above the SDL

Attachments

Report Date: November 12, 2013
NM-2007

Work Order: 13110802
Monument #10

Page Number: 13 of 13
Monument NM

The scanned attachments will follow this page.
Please note, each attachment may consist of more than one page.

Page 1 of 1

BioAquatic Testing
2501 Mayes Rd., Ste 100
Carrollton, Texas 75006
Tel (972) 242-7750

1 (888) 588-3443

Phone #:

Fax #:

E-mail:

Invoice to:
(If different from above)

Project #:	TNm monument 10
Project Name:	Monument 10

Project Location (including state):

[illegible][illegible]

Submittal of samples constitutes agreement to Terms and Conditions listed on reverse side of C. O. C.

ORIGINAL COPY

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	05/02/97	3,629.59	-	21.64	0.00	3607.95
MW - 1	08/15/97	3,629.59	-	21.66	0.00	3607.93
MW - 1	10/23/97	3,629.59	-	21.57	0.00	3608.02
MW - 1	11/01/97	3,629.59	-	21.60	0.00	3607.99
MW - 1	12/03/97	3,629.59	-	21.60	0.00	3607.99
MW - 1	01/02/98	3,629.59	-	21.57	0.00	3608.02
MW - 1	02/06/98	3,629.33	-	21.59	0.00	3,607.74
MW - 1	02/19/98	3,629.33	-	21.58	0.00	3,607.75
MW - 1	03/04/98	3,629.33	-	21.55	0.00	3,607.78
MW - 1	03/06/00	3,629.33	-	21.80	0.00	3,607.53
MW - 1	05/16/00	3,629.33	-	21.65	0.00	3,607.68
MW - 1	08/31/00	3,629.33	-	21.64	0.00	3,607.69
MW - 1	11/17/00	3,629.33	-	21.64	0.00	3,607.69
MW - 1	03/07/01	3,629.33	-	21.55	0.00	3,607.78
MW - 1	05/30/01	3,629.33	-	21.58	0.00	3,607.75
MW - 1	08/27/01	3,629.33	-	21.65	0.00	3,607.68
MW - 1	10/12/01	3,629.33	-	21.63	0.00	3,607.70
MW - 1	02/25/02	3,629.33	-	21.62	0.00	3,607.71
MW - 1	05/13/02	3,629.33	-	21.65	0.00	3,607.68
MW - 1	09/10/02	3,629.33	-	21.68	0.00	3,607.65
MW - 1	11/15/02	3,629.33	-	21.62	0.00	3,607.71
MW - 1	05/13/03	3,629.33	-	21.59	0.00	3,607.74
MW - 1	08/22/03	3,629.33	-	21.72	0.00	3,607.61
MW - 1	12/15/03	3,629.33	-	21.67	0.00	3,607.66
MW - 1	03/04/04	3,629.33	-	21.65	0.00	3,607.68
MW - 1	05/25/04	3,629.33	-	21.59	0.00	3,607.74
MW - 1	08/31/04	3,629.33	-	21.69	0.00	3,607.64
MW - 1	12/10/04	3,629.33	sheen	20.44	0.00	3,608.89
MW - 1	12/13/04	3,629.33	sheen	20.44	0.00	3,608.89
MW - 1	01/10/05	3,629.33	-	21.09	0.00	3,608.24
MW - 1	01/17/05	3,629.33	sheen	21.15	0.00	3,608.18
MW - 1	01/24/05	3,629.33	sheen	21.10	0.00	3,608.23
MW - 1	01/31/05	3,629.33	sheen	21.19	0.00	3,608.14
MW - 1	01/31/05	3,629.33	sheen	21.19	0.00	3,608.14
MW - 1	02/07/05	3,629.33	sheen	21.22	0.00	3,608.11
MW - 1	02/14/05	3,629.33	sheen	21.29	0.00	3,608.04
MW - 1	02/21/05	3,629.33	sheen	21.33	0.00	3,608.00
MW - 1	02/28/05	3,629.33	sheen	21.37	0.00	3,607.96
MW - 1	03/07/05	3,629.33	sheen	21.30	0.00	3,608.03

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	03/14/05	3,629.33	sheen	21.37	0.00	3,607.96
MW - 1	03/16/05	3,629.33	sheen	21.44	0.00	3,607.89
MW - 1	03/21/05	3,629.33	sheen	21.38	0.00	3,607.95
MW - 1	03/28/05	3,629.33	sheen	21.39	0.00	3,607.94
MW - 1	04/04/05	3,629.33	sheen	21.37	0.00	3,607.96
MW - 1	04/13/05	3,629.33	sheen	21.38	0.00	3,607.95
MW - 1	04/18/05	3,629.33	21.35	21.36	0.01	3,607.98
MW - 1	05/23/05	3,629.33	sheen	21.40	0.00	3,607.93
MW - 1	06/02/05	3,629.33	sheen	21.44	0.00	3,607.89
MW - 1	06/07/05	3,629.33	sheen	21.41	0.00	3,607.92
MW - 1	06/13/05	3,629.33	-	21.45	0.00	3,607.88
MW - 1	06/14/05	3,629.33	sheen	21.45	0.00	3,607.88
MW - 1	06/21/05	3,629.33	sheen	21.51	0.00	3,607.82
MW - 1	07/13/05	3,629.33	sheen	21.55	0.00	3,607.78
MW - 1	07/19/05	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	07/26/05	3,629.33	sheen	21.57	0.00	3,607.76
MW - 1	08/01/05	3,629.33	sheen	21.56	0.00	3,607.77
MW - 1	08/15/05	3,629.33	sheen	21.60	0.00	3,607.73
MW - 1	08/24/05	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	08/30/05	3,629.33	sheen	21.56	0.00	3,607.77
MW - 1	09/12/05	3,629.33	-	21.50	0.00	3,607.83
MW - 1	09/20/05	3,629.33	sheen	21.63	0.00	3,607.70
MW - 1	09/26/05	3,629.33	sheen	21.59	0.00	3,607.74
MW - 1	10/07/05	3,629.33	sheen	21.62	0.00	3,607.71
MW - 1	10/11/05	3,629.33	sheen	21.61	0.00	3,607.72
MW - 1	10/18/05	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	10/25/05	3,629.33	sheen	21.60	0.00	3,607.73
MW - 1	11/14/05	3,629.33	sheen	21.60	0.00	3,607.73
MW - 1	11/23/05	3,629.33	sheen	21.57	0.00	3,607.76
MW - 1	12/06/05	3,629.33	-	21.60	0.00	3,607.73
MW - 1	12/12/05	3,629.33	sheen	21.51	0.00	3,607.82
MW - 1	12/19/05	3,629.33	sheen	21.50	0.00	3,607.83
MW - 1	12/28/05	3,629.33	sheen	21.50	0.00	3,607.83
MW - 1	01/04/06	3,629.33	sheen	21.53	0.00	3,607.80
MW - 1	01/10/06	3,629.33	sheen	21.49	0.00	3,607.84
MW - 1	01/17/06	3,629.33	sheen	21.47	0.00	3,607.86
MW - 1	01/26/06	3,629.33	sheen	21.48	0.00	3,607.85
MW - 1	01/31/06	3,629.33	sheen	21.50	0.00	3,607.83
MW - 1	02/07/06	3,629.33	sheen	21.53	0.00	3,607.80

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	02/13/06	3,629.33	sheen	21.52	0.00	3,607.81
MW - 1	02/22/06	3,629.33	sheen	21.53	0.00	3,607.80
MW - 1	02/27/06	3,629.33	sheen	21.55	0.00	3,607.78
MW - 1	03/07/06	3,629.33	sheen	21.53	0.00	3,607.80
MW - 1	03/10/06	3,629.33	-	21.52	0.00	3,607.81
MW - 1	03/15/06	3,629.33	sheen	21.54	0.00	3,607.79
MW - 1	03/22/06	3,629.33	sheen	21.55	0.00	3,607.78
MW - 1	03/29/06	3,629.33	sheen	21.53	0.00	3,607.80
MW - 1	04/03/06	3,629.33	sheen	21.57	0.00	3,607.76
MW - 1	04/18/06	3,629.33	sheen	21.54	0.00	3,607.79
MW - 1	04/25/06	3,629.33	sheen	21.56	0.00	3,607.77
MW - 1	05/02/06	3,629.33	sheen	21.62	0.00	3,607.71
MW - 1	05/10/06	3,629.33	sheen	21.55	0.00	3,607.78
MW - 1	05/16/06	3,629.33	sheen	21.54	0.00	3,607.79
MW - 1	05/23/06	3,629.33	sheen	21.55	0.00	3,607.78
MW - 1	05/31/06	3,629.33	21.56	21.57	0.01	3,607.77
MW - 1	06/06/06	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	06/09/06	3,629.33	-	21.57	0.00	3,607.76
MW - 1	06/13/06	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	06/20/06	3,629.33	sheen	21.60	0.00	3,607.73
MW - 1	07/05/06	3,629.33	-	21.63	0.00	3,607.70
MW - 1	07/18/06	3,629.33	-	21.62	0.00	3,607.71
MW - 1	07/26/06	3,629.33	-	21.61	0.00	3,607.72
MW - 1	07/31/06	3,629.33	-	21.59	0.00	3,607.74
MW - 1	08/08/06	3,629.33	-	21.62	0.00	3,607.71
MW - 1	08/18/06	3,629.33	-	21.52	0.00	3,607.81
MW - 1	08/22/06	3,629.33	-	22.33	0.00	3,607.00
MW - 1	09/12/06	3,629.33	19.99	20.01	0.02	3,609.34
MW - 1	09/16/06	3,629.33	20.07	20.13	0.06	3,609.25
MW - 1	10/31/06	3,629.33	20.90	21.08	0.18	3,608.40
MW - 1	11/15/06	3,629.33	20.86	21.02	0.16	3,608.45
MW - 1	11/28/06	3,629.33	21.13	21.51	0.38	3,608.14
MW - 1	01/31/07	3,629.33	21.35	21.80	0.45	3,607.91
MW - 1	02/07/07	3,629.33	21.41	21.49	0.08	3,607.91
MW - 1	02/22/07	3,629.33	21.48	21.88	0.40	3,607.79
MW - 1	03/07/07	3,629.33	21.39	21.54	0.15	3,607.92
MW - 1	03/29/07	3,629.33	21.44	21.47	0.03	3,607.89
MW - 1	04/02/07	3,629.33	21.68	21.74	0.06	3,607.64
MW - 1	04/30/07	3,629.33	21.41	21.45	0.04	3,607.91

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	05/17/07	3,629.33	21.44	21.52	0.08	3,607.88
MW - 1	06/20/07	3,629.33	21.47	21.54	0.07	3,607.85
MW - 1	06/29/07	3,629.33	sheen	21.71	0.00	3,607.62
MW - 1	07/02/07	3,629.33	sheen	21.59	0.00	3,607.74
MW - 1	08/01/07	3,629.33	sheen	21.63	0.00	3,607.70
MW - 1	08/09/07	3,629.33	sheen	21.66	0.00	3,607.67
MW - 1	08/21/07	3,629.33	sheen	21.69	0.00	3,607.64
MW - 1	09/18/07	3,629.33	sheen	21.73	0.00	3,607.60
MW - 1	10/03/07	3,629.33	sheen	21.65	0.00	3,607.68
MW - 1	10/10/07	3,629.33	sheen	21.62	0.00	3,607.71
MW - 1	10/17/07	3,629.33	sheen	21.58	0.00	3,607.75
MW - 1	11/26/07	3,629.33	sheen	21.53	0.00	3,607.80
MW - 1	01/18/08	3,629.33	-	21.52	0.00	3,607.81
MW - 1	01/23/08	3,629.33	-	21.69	0.00	3,607.64
MW - 1	02/21/08	3,629.33	-	21.74	0.00	3,607.59
MW - 1	02/26/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	03/14/08	3,629.33	-	21.68	0.00	3,607.65
MW - 1	03/20/08	3,629.33	-	21.17	0.00	3,608.16
MW - 1	04/04/08	3,629.33	-	21.68	0.00	3,607.65
MW - 1	04/10/08	3,629.33	-	21.71	0.00	3,607.62
MW - 1	04/17/08	3,629.33	-	21.61	0.00	3,607.72
MW - 1	04/24/08	3,629.33	-	21.69	0.00	3,607.64
MW - 1	05/01/08	3,629.33	-	21.69	0.00	3,607.64
MW - 1	05/08/08	3,629.33	-	21.67	0.00	3,607.66
MW - 1	05/15/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	05/20/08	3,629.33	-	21.72	0.00	3,607.61
MW - 1	05/26/08	3,629.33	-	21.70	0.00	3,607.63
MW - 1	05/30/08	3,629.33	-	21.76	0.00	3,607.57
MW - 1	06/04/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	06/12/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	06/17/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	06/24/08	3,629.33	-	21.73	0.00	3,607.60
MW - 1	07/03/08	3,629.33	-	21.70	0.00	3,607.63
MW - 1	07/09/08	3,629.33	-	21.84	0.00	3,607.49
MW - 1	07/14/08	3,629.33	-	21.78	0.00	3,607.55
MW - 1	08/19/08	3,629.33	-	21.81	0.00	3,607.52
MW - 1	08/28/08	3,629.33	-	21.68	0.00	3,607.65
MW - 1	09/25/08	3,629.33	-	21.72	0.00	3,607.61
MW - 1	10/03/08	3,629.33	-	21.60	0.00	3,607.73

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	10/07/08	3,629.33	-	21.79	0.00	3,607.54
MW - 1	10/15/08	3,629.33	-	21.71	0.00	3,607.62
MW - 1	10/22/08	3,629.33	-	21.69	0.00	3,607.64
MW - 1	10/28/08	3,629.33	-	21.61	0.00	3,607.72
MW - 1	11/06/08	3,629.33	-	21.69	0.00	3,607.64
MW - 1	11/13/08	3,629.33	-	21.63	0.00	3,607.70
MW - 1	11/19/08	3,629.33	-	21.68	0.00	3,607.65
MW - 1	12/16/08	3,629.33	-	21.68	0.00	3,607.65
MW - 1	02/13/09	3,629.33	-	21.66	0.00	3,607.67
MW - 1	05/20/09	3,629.33	-	21.74	0.00	3,607.59
MW - 1	05/20/09	3,629.33	-	21.58	0.00	3,607.75
MW - 1	06/02/09	3,629.33	-	21.60	0.00	3,607.73
MW - 1	06/04/09	3,629.33	-	31.98	0.00	3,597.35
MW - 1	07/10/09	3,629.33	-	21.61	0.00	3,607.72
MW - 1	08/15/09	3,629.33	-	21.56	0.00	3,607.77
MW - 1	11/06/09	3,629.33	-	21.54	0.00	3,607.79
MW - 1	01/12/10	3,629.33	-	21.57	0.00	3,607.76
MW - 1	02/05/10	3,629.33	-	21.60	0.00	3,607.73
MW - 1	05/03/10	3,629.33	-	21.64	0.00	3,607.69
MW - 1	08/02/10	3,629.33	-	21.55	0.00	3,607.78
MW - 1	11/01/10	3,629.33	21.41	21.65	0.24	3,607.88
MW - 1	02/07/11	3,629.33	21.43	21.66	0.23	3,607.87
MW - 1	05/02/11	3,629.33	22.16	25.03	2.87	3,606.74
MW - 1	05/09/11	3,629.33	21.56	21.60	0.04	3,607.76
MW - 1	05/10/11	3,629.33	21.55	21.62	0.07	3,607.77
MW - 1	07/12/11	3,629.33	sheen	21.52	0.00	3,607.81
MW - 1	07/22/11	3,629.33	-	21.45	0.00	3,607.88
MW - 1	08/04/11	3,629.33	-	21.62	0.00	3,607.71
MW - 1	08/08/11	3,629.33	21.57	21.62	0.05	3,607.75
MW - 1	08/11/11	3,629.33	-	21.92	0.00	3,607.41
MW - 1	08/24/11	3,629.33	-	22.01	0.00	3,607.32
MW - 1	09/02/11	3,629.33	-	21.87	0.00	3,607.46
MW - 1	09/07/11	3,629.33	Sheen	21.85	0.00	3,607.48
MW - 1	09/09/11	3,629.33	Sheen	21.80	0.00	3,607.53
MW - 1	09/14/11	3,629.33	-	21.80	0.00	3,607.53
MW - 1	09/22/11	3,629.33	sheen	21.80	0.00	3,607.53
MW - 1	09/26/11	3,629.33	sheen	21.80	0.00	3,607.53
MW - 1	10/14/11	3,629.33	-	21.69	0.00	3,607.64
MW - 1	10/26/11	3,629.33	21.66	21.69	0.03	3,607.67

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	11/10/11	3,629.33	-	21.72	0.00	3,607.61
MW - 1	11/14/11	3,629.33	-	21.72	0.00	3,607.61
MW - 1	12/02/11	3,629.33	-	21.70	0.00	3,607.63
MW - 1	12/09/11	3,629.33	-	21.75	0.00	3,607.58
MW - 1	12/13/11	3,629.33	-	21.75	0.00	3,607.58
MW - 1	12/23/11	3,629.33	-	21.65	0.00	3,607.68
MW - 1	12/29/11	3,629.33	-	21.56	0.00	3,607.77
MW - 1	01/04/12	3,629.33	-	21.64	0.00	3,607.69
MW - 1	01/13/12	3,629.33	-	21.48	0.00	3,607.85
MW - 1	01/30/12	3,629.33	-	21.56	0.00	3,607.77
MW - 1	02/06/12	3,629.33	-	21.60	0.00	3,607.73
MW - 1	02/13/12	3,629.33	-	21.83	0.00	3,607.50
MW - 1	02/14/12	3,629.33	-	21.83	0.00	3,607.50
MW - 1	03/13/12	3,629.33	-	21.90	0.00	3,607.43
MW - 1	03/15/12	3,629.33	-	21.80	0.00	3,607.53
MW - 1	03/20/12	3,629.33	-	21.80	0.00	3,607.53
MW - 1	03/22/12	3,629.33	-	21.71	0.00	3,607.62
MW - 1	03/27/12	3,629.33	-	21.69	0.00	3,607.64
MW - 1	03/29/12	3,629.33	-	21.70	0.00	3,607.63
MW - 1	04/02/12	3,629.33	-	21.67	0.00	3,607.66
MW - 1	04/09/12	3,629.33	-	21.71	0.00	3,607.62
MW - 1	04/12/12	3,629.33	-	21.72	0.00	3,607.61
MW - 1	04/17/12	3,629.33	-	21.83	0.00	3,607.50
MW - 1	04/19/12	3,629.33	-	21.69	0.00	3,607.64
MW - 1	04/23/12	3,629.33	-	21.75	0.00	3,607.58
MW - 1	04/26/12	3,629.33	-	21.71	0.00	3,607.62
MW - 1	05/21/12	3,629.33	-	21.76	0.00	3,607.57
MW - 1	06/06/12	3,629.33	-	21.60	0.00	3,607.73
MW - 1	06/11/12	3,629.33	-	21.61	0.00	3,607.72
MW - 1	06/18/12	3,629.33	-	21.61	0.00	3,607.72
MW - 1	06/25/12	3,629.33	-	21.73	0.00	3,607.60
MW - 1	07/02/12	3,629.33	-	21.62	0.00	3,607.71
MW - 1	07/09/12	3,629.33	-	27.77	0.00	3,601.56
MW - 1	07/16/12	3,629.33	-	21.69	0.00	3,607.64
MW - 1	08/01/12	3,629.33	-	21.71	0.00	3,607.62
MW - 1	08/14/12	3,629.33	-	21.73	0.00	3,607.60
MW - 1	08/21/12	3,629.33	-	21.78	0.00	3,607.55
MW - 1	09/04/12	3,629.33	-	21.74	0.00	3,607.59
MW - 1	09/10/12	3,629.33	-	21.80	0.00	3,607.53

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	09/19/12	3,629.33	-	21.77	0.00	3,607.56
MW - 1	09/24/12	3,629.33	-	21.66	0.00	3,607.67
MW - 1	10/01/12	3,629.33	-	21.68	0.00	3,607.65
MW - 1	10/08/12	3,629.33	-	21.63	0.00	3,607.70
MW - 1	10/15/12	3,629.33	-	21.64	0.00	3,607.69
MW - 1	10/22/12	3,629.33	-	21.76	0.00	3,607.57
MW - 1	10/29/12	3,629.33	-	21.80	0.00	3,607.53
MW - 1	11/06/12	3,629.33	-	21.68	0.00	3,607.65
MW - 1	12/04/12	3,629.33	-	21.74	0.00	3,607.59
MW - 1	12/10/12	3,629.33	-	21.76	0.00	3,607.57
MW - 1	12/17/12	3,629.33	-	21.70	0.00	3,607.63
MW - 1	12/27/12	3,629.33	-	21.82	0.00	3,607.51
MW - 1	01/14/13	3,629.33	-	21.83	0.00	3,607.50
MW - 1	02/04/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	02/05/13	3,629.33	-	21.82	0.00	3,607.51
MW - 1	02/20/13	3,629.33	-	21.83	0.00	3,607.50
MW - 1	03/04/13	3,629.33	-	21.96	0.00	3,607.37
MW - 1	03/26/13	3,629.33	-	21.78	0.00	3,607.55
MW - 1	04/10/13	3,629.33	-	21.99	0.00	3,607.34
MW - 1	04/17/13	3,629.33	-	21.95	0.00	3,607.38
MW - 1	04/24/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	05/02/13	3,629.33	-	21.86	0.00	3,607.47
MW - 1	05/09/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	05/17/13	3,629.33	-	21.81	0.00	3,607.52
MW - 1	05/22/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	05/29/13	3,629.33	-	21.77	0.00	3,607.56
MW - 1	06/03/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	06/20/13	3,629.33	-	21.67	0.00	3,607.66
MW - 1	06/25/13	3,629.33	-	21.69	0.00	3,607.64
MW - 1	07/02/13	3,629.33	-	21.89	0.00	3,607.44
MW - 1	07/09/13	3,629.33	-	21.87	0.00	3,607.46
MW - 1	07/16/13	3,629.33	-	21.85	0.00	3,607.48
MW - 1	07/24/13	3,629.33	-	21.81	0.00	3,607.52
MW - 1	07/31/13	3,629.33	-	21.80	0.00	3,607.53
MW - 1	08/01/13	3,629.33	-	21.73	0.00	3,607.60
MW - 1	08/06/13	3,629.33	-	21.71	0.00	3,607.62
MW - 1	08/07/13	3,629.33	-	21.66	0.00	3,607.67
MW - 1	08/16/13	3,629.33	-	21.69	0.00	3,607.64
MW - 1	08/27/13	3,629.33	-	21.63	0.00	3,607.70

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 1	09/12/13	3,629.33	-	21.64	0.00	3,607.69
MW - 1	09/19/13	3,629.33	-	22.10	0.00	3,607.23
MW - 1	09/25/13	3,629.33	-	22.05	0.00	3,607.28
MW - 1	09/30/13	3,629.33	-	22.07	0.00	3,607.26
MW - 1	10/09/13	3,629.33	-	21.99	0.00	3,607.34
MW - 1	10/14/13	3,629.33	-	21.78	0.00	3,607.55
MW - 1	10/22/13	3,629.33	-	21.72	0.00	3,607.61
MW - 1	10/30/13	3,629.33	-	22.03	0.00	3,607.30
MW - 1	11/07/13	3,629.33	-	22.00	0.00	3,607.33
MW - 1	11/27/13	3,629.33	-	21.86	0.00	3,607.47
MW - 1	12/04/13	3,629.33	-	21.79	0.00	3,607.54
MW - 1	12/10/13	3,629.33	-	21.76	0.00	3,607.57
MW - 1	12/16/13	3,629.33	-	21.62	0.00	3,607.71
MW - 1	12/24/13	3,629.33	-	21.75	0.00	3,607.58
MW - 2	05/02/97	3,629.66	-	25.52	3.42	3,604.14
MW - 2	08/15/97	3,629.66	-	27.32	0.00	3,602.34
MW - 2	10/23/97	3,629.66	-	27.48	0.00	3,602.18
MW - 2	11/01/97	3,629.66	-	27.49	0.00	3,602.17
MW - 2	12/03/97	3,629.66	-	27.52	0.00	3,602.14
MW - 2	12/09/97	3,629.66	-	25.94	0.00	3,603.72
MW - 2	12/17/97	3,629.66	-	25.54	0.00	3,604.12
MW - 2	01/02/98	3,629.66	-	25.80	0.00	3,603.86
MW - 2	01/07/98	3,629.66	-	24.99	0.00	3,604.67
MW - 2	01/15/98	3,629.66	-	25.04	0.00	3,604.62
MW - 2	01/20/98	3,629.66	-	23.97	0.00	3,605.69
MW - 2	01/30/98	3,629.66	-	25.03	0.00	3,604.63
MW - 2	02/06/98	3,629.43	-	24.73	0.00	3,604.70
MW - 2	02/13/98	3,629.43	-	24.72	0.00	3,604.71
MW - 2	02/21/98	3,629.43	-	24.53	0.00	3,604.90
MW - 2	02/25/98	3,629.43	-	24.42	0.00	3,605.01
MW - 2	03/04/98	3,629.43	-	24.62	0.00	3,604.81
MW - 2	03/13/98	3,629.43	-	24.79	0.00	3,604.64
MW - 2	03/17/98	3,629.43	-	24.41	0.00	3,605.02
MW - 2	03/24/98	3,629.43	-	24.60	0.00	3,604.83
MW - 2	03/06/00	3,629.43	21.93	27.48	5.55	3,606.67
MW - 2	05/16/00	3,629.43	21.97	27.49	5.52	3,606.63
MW - 2	08/31/00	3,629.43	21.96	27.51	5.55	3,606.64
MW - 2	11/17/00	3,629.43	20.35	26.82	6.47	3,608.11

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	03/07/01	3,629.43	22.18	25.11	2.93	3,606.81
MW - 2	05/30/01	3,629.43	22.25	24.80	2.55	3,606.80
MW - 2	08/27/01	3,629.43	21.87	24.83	2.96	3,607.12
MW - 2	10/12/01	3,629.43	22.21	25.23	3.02	3,606.77
MW - 2	02/25/02	3,629.43	21.99	26.90	4.91	3,606.70
MW - 2	03/18/02	3,629.43	21.96	26.96	5.00	3,606.72
MW - 2	03/28/02	3,629.43	22.16	26.61	4.45	3,606.60
MW - 2	04/03/02	3,629.43	22.20	24.92	2.72	3,606.82
MW - 2	04/12/02	3,629.43	22.18	25.12	2.94	3,606.81
MW - 2	04/16/02	3,629.43	22.26	24.59	2.33	3,606.82
MW - 2	05/03/02	3,629.43	22.12	25.55	3.43	3,606.80
MW - 2	05/10/02	3,629.43	22.17	25.43	3.26	3,606.77
MW - 2	05/13/02	3,629.43	22.27	25.00	2.73	3,606.75
MW - 2	05/24/02	3,629.43	22.18	25.75	3.57	3,606.71
MW - 2	06/10/02	3,629.43	21.91	26.73	4.82	3,606.80
MW - 2	06/19/02	3,629.43	22.18	26.47	4.29	3,606.61
MW - 2	07/03/02	3,629.43	22.19	25.90	3.71	3,606.68
MW - 2	07/11/02	3,629.43	22.11	26.21	4.10	3,606.71
MW - 2	07/16/02	3,629.43	22.22	25.30	3.08	3,606.75
MW - 2	08/21/02	3,629.43	22.11	26.18	4.07	3,606.71
MW - 2	08/27/02	3,629.43	22.09	26.19	4.10	3,606.73
MW - 2	09/05/02	3,629.43	22.22	25.29	3.07	3,606.75
MW - 2	09/10/02	3,629.43	22.35	24.70	2.35	3,606.73
MW - 2	10/03/02	3,629.43	22.34	24.53	2.19	3,606.76
MW - 2	10/08/02	3,629.43	22.29	24.58	2.29	3,606.80
MW - 2	10/14/02	3,629.43	22.24	24.99	2.75	3,606.78
MW - 2	11/15/02	3,629.43	22.22	25.29	3.07	3,606.75
MW - 2	12/27/02	3,629.43	22.05	26.18	4.13	3,606.76
MW - 2	01/07/03	3,629.43	22.14	25.55	3.41	3,606.78
MW - 2	03/05/03	3,629.43	22.05	26.51	4.46	3,606.71
MW - 2	03/06/03	3,629.43	22.26	25.03	2.77	3,606.75
MW - 2	03/12/03	3,629.43	22.14	25.76	3.62	3,606.75
MW - 2	03/20/03	3,629.43	22.46	24.60	2.14	3,606.65
MW - 2	03/27/03	3,629.43	22.19	25.26	3.07	3,606.78
MW - 2	04/03/03	3,629.43	22.21	25.05	2.84	3,606.79
MW - 2	04/16/03	3,629.43	22.16	24.56	2.40	3,606.91
MW - 2	05/13/03	3,629.43	22.30	24.78	2.48	3,606.76
MW - 2	05/15/03	3,629.43	22.36	26.09	3.73	3,606.51
MW - 2	05/21/03	3,629.43	22.21	25.98	3.77	3,606.65

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	05/28/03	3,629.43	22.30	25.49	3.19	3,606.65
MW - 2	06/05/03	3,629.43	22.23	25.32	3.09	3,606.74
MW - 2	07/10/03	3,629.43	22.30	26.13	3.83	3,606.56
MW - 2	07/31/03	3,629.43	22.15	26.08	3.93	3,606.69
MW - 2	08/06/03	3,629.43	22.47	25.56	3.09	3,606.50
MW - 2	08/13/03	3,629.43	22.57	25.55	2.98	3,606.41
MW - 2	08/22/03	3,629.43	22.25	26.30	4.05	3,606.57
MW - 2	08/25/03	3,629.43	22.52	25.62	3.10	3,606.45
MW - 2	09/11/03	3,629.43	22.62	24.31	1.69	3,606.56
MW - 2	09/30/03	3,629.43	22.11	26.40	4.29	3,606.68
MW - 2	10/06/03	3,629.43	22.24	25.35	3.11	3,606.72
MW - 2	10/14/03	3,629.43	22.47	26.23	3.76	3,606.40
MW - 2	10/21/03	3,629.43	22.55	25.61	3.06	3,606.42
MW - 2	10/27/03	3,629.43	22.57	25.34	2.77	3,606.44
MW - 2	11/06/03	3,629.43	22.35	25.33	2.98	3,606.63
MW - 2	11/10/03	3,629.43	22.72	25.20	2.48	3,606.34
MW - 2	11/17/03	3,629.43	22.35	25.13	2.78	3,606.66
MW - 2	12/04/03	3,629.43	22.24	26.02	3.78	3,606.62
MW - 2	12/15/03	3,629.43	22.13	25.52	3.39	3,606.79
MW - 2	12/22/03	3,629.43	22.12	25.84	3.72	3,606.75
MW - 2	12/31/03	3,629.43	22.09	26.07	3.98	3,606.74
MW - 2	01/27/04	3,629.43	22.41	25.21	2.80	3,606.60
MW - 2	02/03/04	3,629.43	22.32	25.19	2.87	3,606.68
MW - 2	02/10/04	3,629.43	22.05	26.44	4.39	3,606.72
MW - 2	02/18/04	3,629.43	22.03	26.86	4.83	3,606.68
MW - 2	02/26/04	3,629.43	22.34	25.89	3.55	3,606.56
MW - 2	03/04/04	3,629.43	22.26	26.27	4.01	3,606.57
MW - 2	03/11/04	3,629.43	22.31	26.45	4.14	3,606.50
MW - 2	03/16/04	3,629.43	22.61	26.85	4.24	3,606.18
MW - 2	03/19/04	3,629.43	23.10	25.42	2.32	3,605.98
MW - 2	03/23/04	3,629.43	23.15	25.38	2.23	3,605.95
MW - 2	03/30/04	3,629.43	22.47	26.75	4.28	3,606.32
MW - 2	04/07/04	3,629.43	22.69	25.71	3.02	3,606.29
MW - 2	04/13/04	3,629.43	22.70	26.17	3.47	3,606.21
MW - 2	04/20/04	3,629.43	22.08	25.80	3.72	3,606.79
MW - 2	04/27/04	3,629.43	21.14	25.23	4.09	3,607.68
MW - 2	05/25/04	3,629.43	22.08	25.79	3.71	3,606.79
MW - 2	06/03/04	3,629.43	22.06	25.94	3.88	3,606.79
MW - 2	06/17/04	3,629.43	22.06	26.16	4.10	3,606.76

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	06/23/04	3,629.43	22.05	26.22	4.17	3,606.75
MW - 2	06/25/04	3,629.43	22.08	26.25	4.17	3,606.72
MW - 2	07/01/04	3,629.43	22.11	26.08	3.97	3,606.72
MW - 2	07/12/04	3,629.43	22.03	26.37	4.34	3,606.75
MW - 2	07/15/04	3,629.43	22.02	26.39	4.37	3,606.75
MW - 2	07/21/04	3,629.43	22.03	26.43	4.40	3,606.74
MW - 2	08/02/04	3,629.43	22.01	26.49	4.48	3,606.75
MW - 2	08/11/04	3,629.43	22.03	26.51	4.48	3,606.73
MW - 2	08/13/04	3,629.43	22.05	26.49	4.44	3,606.71
MW - 2	08/16/04	3,629.43	22.02	26.58	4.56	3,606.73
MW - 2	08/19/04	3,629.43	22.05	26.60	4.55	3,606.70
MW - 2	08/26/04	3,629.43	22.16	25.70	3.54	3,606.74
MW - 2	08/31/04	3,629.43	22.26	25.15	2.89	3,606.74
MW - 2	09/13/04	3,629.43	22.25	25.17	2.92	3,606.74
MW - 2	09/21/04	3,629.43	22.28	25.10	2.82	3,606.73
MW - 2	09/29/04	3,629.43	21.22	24.03	2.81	3,607.79
MW - 2	10/05/04	3,629.43	21.52	24.86	3.34	3,607.41
MW - 2	10/12/04	3,629.43	21.39	25.30	3.91	3,607.45
MW - 2	10/19/04	3,629.43	21.63	24.85	3.22	3,607.32
MW - 2	10/25/04	3,629.43	21.75	24.55	2.80	3,607.26
MW - 2	11/01/04	3,629.43	21.97	24.50	2.53	3,607.08
MW - 2	11/09/04	3,629.43	21.80	24.11	2.31	3,607.28
MW - 2	11/16/04	3,629.43	22.22	24.45	2.23	3,606.88
MW - 2	11/22/04	3,629.43	21.67	23.93	2.26	3,607.42
MW - 2	11/29/04	3,629.43	21.79	23.99	2.20	3,607.31
MW - 2	12/10/04	3,629.43	21.32	24.30	2.98	3,607.66
MW - 2	12/13/04	3,629.43	21.32	24.30	2.98	3,607.66
MW - 2	12/20/04	3,629.43	21.47	25.00	3.53	3,607.43
MW - 2	12/27/04	3,629.43	21.56	24.45	2.89	3,607.44
MW - 2	01/10/05	3,629.43	21.41	24.67	3.26	3,607.53
MW - 2	01/17/05	3,629.43	21.72	24.76	3.04	3,607.25
MW - 2	01/24/05	3,629.43	21.73	24.78	3.05	3,607.24
MW - 2	01/31/05	3,629.43	21.80	24.62	2.82	3,607.21
MW - 2	02/07/05	3,629.43	21.84	24.56	2.72	3,607.18
MW - 2	02/14/05	3,629.43	21.89	24.50	2.61	3,607.15
MW - 2	02/21/05	3,629.43	21.93	24.45	2.52	3,607.12
MW - 2	02/28/05	3,629.43	21.95	24.42	2.47	3,607.11
MW - 2	03/07/05	3,629.43	22.00	24.47	2.47	3,607.06
MW - 2	03/14/05	3,629.43	21.97	24.45	2.48	3,607.09

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	03/16/05	3,629.43	21.88	24.30	2.42	3,607.19
MW - 2	03/21/05	3,629.43	21.98	24.40	2.42	3,607.09
MW - 2	03/28/05	3,629.43	21.93	24.83	2.90	3,607.07
MW - 2	04/04/05	3,629.43	21.95	24.66	2.71	3,607.07
MW - 2	04/13/05	3,629.43	22.03	24.41	2.38	3,607.04
MW - 2	04/18/05	3,629.43	22.00	24.25	2.25	3,607.09
MW - 2	05/23/05	3,629.43	22.00	24.81	2.81	3,607.01
MW - 2	06/02/05	3,629.43	22.09	24.80	2.71	3,606.93
MW - 2	06/07/05	3,629.43	21.98	24.99	3.01	3,607.00
MW - 2	06/13/05	3,629.43	22.05	24.47	2.42	3,607.02
MW - 2	06/14/05	3,629.43	22.05	24.47	2.42	3,607.02
MW - 2	06/21/05	3,629.43	22.04	24.95	2.91	3,606.95
MW - 2	06/28/05	3,629.43	22.06	24.60	2.54	3,606.99
MW - 2	07/13/05	3,629.43	22.13	24.41	2.28	3,606.96
MW - 2	07/19/05	3,629.43	22.10	24.30	2.20	3,607.00
MW - 2	07/26/05	3,629.43	22.10	24.80	2.70	3,606.93
MW - 2	08/01/05	3,629.43	22.15	24.47	2.32	3,606.93
MW - 2	08/10/05	3,629.43	22.13	24.56	2.43	3,606.94
MW - 2	08/15/05	3,629.43	22.14	24.31	2.17	3,606.96
MW - 2	08/24/05	3,629.43	22.12	24.53	2.41	3,606.95
MW - 2	08/30/05	3,629.43	22.12	24.35	2.23	3,606.98
MW - 2	09/07/05	3,629.43	22.10	24.48	2.38	3,606.97
MW - 2	09/12/05	3,629.43	22.11	24.21	2.10	3,607.01
MW - 2	09/13/05	3,629.43	22.12	24.34	2.22	3,606.98
MW - 2	09/20/05	3,629.43	22.16	24.40	2.24	3,606.93
MW - 2	09/26/05	3,629.43	22.10	24.84	2.74	3,606.92
MW - 2	10/07/05	3,629.43	22.10	24.80	2.70	3,606.93
MW - 2	10/11/05	3,629.43	22.13	24.50	2.37	3,606.94
MW - 2	10/18/05	3,629.43	22.11	24.70	2.59	3,606.93
MW - 2	10/25/05	3,629.43	22.05	24.75	2.70	3,606.98
MW - 2	11/01/05	3,629.43	22.08	25.67	3.59	3,606.81
MW - 2	11/14/05	3,629.43	22.13	24.37	2.24	3,606.96
MW - 2	11/23/05	3,629.43	22.20	24.30	2.10	3,606.92
MW - 2	11/28/05	3,629.43	22.06	25.33	3.27	3,606.88
MW - 2	12/06/05	3,629.43	22.10	24.68	2.58	3,606.94
MW - 2	12/07/05	3,629.43	21.11	24.78	3.67	3,607.77
MW - 2	12/12/05	3,629.43	22.21	24.30	2.09	3,606.91
MW - 2	12/19/05	3,629.43	22.29	24.39	2.10	3,606.83
MW - 2	12/28/05	3,629.43	22.35	24.48	2.13	3,606.76

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	01/04/06	3,629.43	22.30	24.58	2.28	3,606.79
MW - 2	01/10/06	3,629.43	22.20	24.80	2.60	3,606.84
MW - 2	01/17/06	3,629.43	22.18	24.73	2.55	3,606.87
MW - 2	01/26/06	3,629.43	22.20	24.75	2.55	3,606.85
MW - 2	01/31/06	3,629.43	22.15	24.70	2.55	3,606.90
MW - 2	02/07/06	3,629.43	22.20	24.63	2.43	3,606.87
MW - 2	02/13/06	3,629.43	22.23	24.60	2.37	3,606.84
MW - 2	02/22/06	3,629.43	22.24	24.69	2.45	3,606.82
MW - 2	02/27/06	3,629.43	22.20	24.65	2.45	3,606.86
MW - 2	03/07/06	3,629.43	22.19	24.75	2.56	3,606.86
MW - 2	03/10/06	3,629.43	22.19	24.37	2.18	3,606.91
MW - 2	03/15/06	3,629.43	22.21	24.69	2.48	3,606.85
MW - 2	03/22/06	3,629.43	22.10	24.85	2.75	3,606.92
MW - 2	03/29/06	3,629.43	22.15	24.84	2.69	3,606.88
MW - 2	04/03/06	3,629.43	22.24	24.36	2.12	3,606.87
MW - 2	04/11/06	3,629.43	22.19	24.58	2.39	3,606.88
MW - 2	04/18/06	3,629.43	22.19	24.60	2.41	3,606.88
MW - 2	04/25/06	3,629.43	22.23	24.51	2.28	3,606.86
MW - 2	05/02/06	3,629.43	22.20	25.02	2.82	3,606.81
MW - 2	05/10/06	3,629.43	22.16	24.98	2.82	3,606.85
MW - 2	05/16/06	3,629.43	22.23	24.58	2.35	3,606.85
MW - 2	05/23/06	3,629.43	22.15	24.96	2.81	3,606.86
MW - 2	05/31/06	3,629.43	22.23	24.72	2.49	3,606.83
MW - 2	06/06/06	3,629.43	22.19	25.03	2.84	3,606.81
MW - 2	06/09/06	3,629.43	22.26	24.43	2.17	3,606.84
MW - 2	06/13/06	3,629.43	22.22	24.83	2.61	3,606.82
MW - 2	06/20/06	3,629.43	22.22	24.70	2.48	3,606.84
MW - 2	07/05/06	3,629.43	22.18	25.14	2.96	3,606.81
MW - 2	07/18/06	3,629.43	22.17	25.09	2.92	3,606.82
MW - 2	07/26/06	3,629.43	22.21	24.86	2.65	3,606.82
MW - 2	07/31/06	3,629.43	22.24	24.54	2.30	3,606.85
MW - 2	08/08/06	3,629.43	22.25	22.64	0.39	3,607.12
MW - 2	08/18/06	3,629.43	22.12	24.72	2.60	3,606.92
MW - 2	08/22/06	3,629.43	23.67	24.86	1.19	3,605.58
MW - 2	09/12/06	3,629.43	21.04	24.14	3.10	3,607.93
MW - 2	09/16/06	3,629.43	21.06	24.36	3.30	3,607.88
MW - 2	10/31/06	3,629.43	21.54	25.55	4.01	3,607.29
MW - 2	11/15/06	3,629.43	22.96	25.10	2.14	3,606.15
MW - 2	11/28/06	3,629.43	21.73	25.29	3.56	3,607.17

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	01/31/07	3,629.43	21.88	25.56	3.68	3,607.00
MW - 2	02/07/07	3,629.43	21.99	24.93	2.94	3,607.00
MW - 2	02/22/07	3,629.43	22.04	25.09	3.05	3,606.93
MW - 2	03/07/07	3,629.43	21.56	25.36	3.80	3,607.30
MW - 2	03/27/07	3,629.43	22.10	24.53	2.43	3,606.97
MW - 2	04/02/07	3,629.43	22.18	24.38	2.20	3,606.92
MW - 2	04/11/07	3,629.43	22.11	24.55	2.44	3,606.95
MW - 2	04/16/07	3,629.43	22.12	24.17	2.05	3,607.00
MW - 2	04/23/07	3,629.43	22.15	24.29	2.14	3,606.96
MW - 2	04/27/07	3,629.43	22.21	23.92	1.71	3,606.96
MW - 2	04/30/07	3,629.43	22.23	23.60	1.37	3,606.99
MW - 2	05/17/07	3,629.43	22.12	24.63	2.51	3,606.93
MW - 2	05/18/07	3,629.43	21.07	24.69	3.62	3,607.82
MW - 2	06/07/07	3,629.43	22.07	24.90	2.83	3,606.94
MW - 2	06/12/07	3,629.43	22.17	24.20	2.03	3,606.96
MW - 2	06/20/07	3,629.43	22.19	24.33	2.14	3,606.92
MW - 2	06/29/07	3,629.43	22.17	24.34	2.17	3,606.93
MW - 2	07/02/07	3,629.43	22.24	23.94	1.70	3,606.94
MW - 2	07/11/07	3,629.43	22.19	24.24	2.05	3,606.93
MW - 2	07/18/07	3,629.43	22.21	24.16	1.95	3,606.93
MW - 2	07/24/07	3,629.43	22.25	23.87	1.62	3,606.94
MW - 2	08/01/07	3,629.43	22.24	24.12	1.88	3,606.91
MW - 2	08/09/07	3,629.43	22.22	24.11	1.89	3,606.93
MW - 2	08/14/07	3,629.43	22.26	23.83	1.57	3,606.93
MW - 2	08/21/07	3,629.43	22.24	24.03	1.79	3,606.92
MW - 2	08/25/07	3,629.43	22.21	24.34	2.13	3,606.90
MW - 2	08/29/07	3,629.43	22.29	23.75	1.46	3,606.92
MW - 2	09/05/07	3,629.43	22.26	23.93	1.67	3,606.92
MW - 2	09/18/07	3,629.43	22.19	24.44	2.25	3,606.90
MW - 2	09/26/07	3,629.43	22.21	24.22	2.01	3,606.92
MW - 2	10/03/07	3,629.43	22.22	24.32	2.10	3,606.90
MW - 2	10/10/07	3,629.43	22.20	24.10	1.90	3,606.95
MW - 2	10/17/07	3,629.43	22.18	24.31	2.13	3,606.93
MW - 2	11/07/07	3,629.43	22.10	24.76	2.66	3,606.93
MW - 2	11/16/07	3,629.43	22.17	24.44	2.27	3,606.92
MW - 2	11/26/07	3,629.43	22.21	24.35	2.14	3,606.90
MW - 2	11/30/07	3,629.43	22.15	24.59	2.44	3,606.91
MW - 2	12/07/07	3,629.43	22.19	24.22	2.03	3,606.94
MW - 2	12/18/07	3,629.43	22.19	24.43	2.24	3,606.90

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	01/18/08	3,629.43	22.12	24.96	2.84	3,606.88
MW - 2	01/23/08	3,629.43	22.18	23.75	1.57	3,607.01
MW - 2	02/13/08	3,629.43	22.13	24.90	2.77	3,606.88
MW - 2	02/21/08	3,629.43	22.20	24.68	2.48	3,606.86
MW - 2	02/26/08	3,629.43	22.22	24.54	2.32	3,606.86
MW - 2	03/14/08	3,629.43	22.18	24.77	2.59	3,606.86
MW - 2	03/20/08	3,629.43	22.23	24.47	2.24	3,606.86
MW - 2	04/04/08	3,629.43	22.19	24.76	2.57	3,606.85
MW - 2	04/10/08	3,629.43	22.23	24.45	2.22	3,606.87
MW - 2	04/17/08	3,629.43	22.20	24.76	2.56	3,606.85
MW - 2	04/24/08	3,629.43	22.24	24.55	2.31	3,606.84
MW - 2	05/01/08	3,629.43	22.28	24.42	2.14	3,606.83
MW - 2	05/08/08	3,629.43	26.26	24.35	-1.91	3,603.46
MW - 2	05/15/08	3,629.43	22.28	24.21	1.93	3,606.86
MW - 2	05/20/08	3,629.43	23.30	24.05	0.75	3,606.02
MW - 2	05/26/08	3,629.43	22.27	24.27	2.00	3,606.86
MW - 2	05/30/08	3,629.43	22.25	24.44	2.19	3,606.85
MW - 2	06/04/08	3,629.43	22.28	24.19	1.91	3,606.86
MW - 2	06/12/08	3,629.43	22.28	24.34	2.06	3,606.84
MW - 2	06/17/08	3,629.43	22.33	23.97	1.64	3,606.85
MW - 2	06/24/08	3,629.43	22.31	24.26	1.95	3,606.83
MW - 2	07/03/08	3,629.43	22.31	24.39	2.08	3,606.81
MW - 2	07/09/08	3,629.43	22.31	24.18	1.87	3,606.84
MW - 2	07/14/08	3,629.43	22.32	24.01	1.69	3,606.86
MW - 2	07/23/08	3,629.43	22.29	24.31	2.02	3,606.84
MW - 2	08/01/08	3,629.43	22.24	24.45	2.21	3,606.86
MW - 2	08/05/08	3,629.43	22.24	24.58	2.34	3,606.84
MW - 2	08/11/08	3,629.43	22.30	24.24	1.94	3,606.84
MW - 2	08/19/08	3,629.43	22.31	24.22	1.91	3,606.83
MW - 2	08/28/08	3,629.43	22.25	24.23	1.98	3,606.88
MW - 2	09/09/08	3,629.43	22.26	24.54	2.28	3,606.83
MW - 2	09/25/08	3,629.43	22.28	24.71	2.43	3,606.79
MW - 2	10/03/08	3,629.43	22.30	24.40	2.10	3,606.82
MW - 2	10/07/08	3,629.43	21.33	23.86	2.53	3,607.72
MW - 2	10/15/08	3,629.43	23.35	24.11	0.76	3,605.97
MW - 2	10/22/08	3,629.43	22.25	24.09	1.84	3,606.90
MW - 2	10/28/08	3,629.43	22.31	24.09	1.78	3,606.85
MW - 2	11/06/08	3,629.43	22.28	24.12	1.84	3,606.87
MW - 2	11/13/08	3,629.43	22.22	24.19	1.97	3,606.91

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	11/19/08	3,629.43	22.28	24.04	1.76	3,606.89
MW - 2	12/16/08	3,629.43	22.24	24.55	2.31	3,606.84
MW - 2	01/07/09	3,629.43	22.22	24.82	2.60	3,606.82
MW - 2	01/16/09	3,629.43	21.34	24.39	3.05	3,607.63
MW - 2	01/29/09	3,629.43	22.25	24.41	2.16	3,606.86
MW - 2	02/09/09	3,629.43	22.27	24.46	2.19	3,606.83
MW - 2	02/13/09	3,629.43	22.32	23.89	1.57	3,606.87
MW - 2	02/26/09	3,629.43	22.32	24.70	2.38	3,606.75
MW - 2	03/02/09	3,629.43	23.33	24.00	0.67	3,606.00
MW - 2	03/04/09	3,629.43	22.35	23.57	1.22	3,606.90
MW - 2	03/09/09	3,629.43	22.35	23.80	1.45	3,606.86
MW - 2	03/17/09	3,629.43	23.37	24.02	0.65	3,605.96
MW - 2	03/19/09	3,629.43	23.38	24.03	0.65	3,605.95
MW - 2	03/25/09	3,629.43	22.31	24.12	1.81	3,606.85
MW - 2	03/27/09	3,629.43	23.35	23.96	0.61	3,605.99
MW - 2	03/30/09	3,629.43	23.37	23.93	0.56	3,605.98
MW - 2	04/06/09	3,629.43	23.39	23.91	0.52	3,605.96
MW - 2	04/08/09	3,629.43	22.24	24.41	2.17	3,606.86
MW - 2	04/13/09	3,629.43	22.34	23.89	1.55	3,606.86
MW - 2	04/15/09	3,629.43	23.37	23.89	0.52	3,605.98
MW - 2	04/21/09	3,629.43	23.39	23.86	0.47	3,605.97
MW - 2	04/27/09	3,629.43	22.25	24.44	2.19	3,606.85
MW - 2	05/07/09	3,629.43	23.42	23.84	0.42	3,605.95
MW - 2	05/20/09	3,629.43	22.23	24.59	2.36	3,606.85
MW - 2	05/21/09	3,629.43	22.24	24.58	2.34	3,606.84
MW - 2	05/27/09	3,629.43	22.30	24.20	1.90	3,606.85
MW - 2	06/02/09	3,629.43	22.32	24.10	1.78	3,606.84
MW - 2	06/10/09	3,629.43	23.44	23.87	0.43	3,605.93
MW - 2	06/15/09	3,629.43	23.43	26.84	3.41	3,605.49
MW - 2	07/01/09	3,629.43	22.23	24.70	2.47	3,606.83
MW - 2	07/10/09	3,629.43	22.28	24.43	2.15	3,606.83
MW - 2	07/15/09	3,629.43	22.24	24.68	2.44	3,606.82
MW - 2	07/21/09	3,629.43	22.38	24.86	2.48	3,606.68
MW - 2	07/23/09	3,629.43	22.40	23.33	0.93	3,606.89
MW - 2	07/28/09	3,629.43	22.41	23.35	0.94	3,606.88
MW - 2	07/30/09	3,629.43	22.32	23.96	1.64	3,606.86
MW - 2	08/05/09	3,629.43	22.33	23.97	1.64	3,606.85
MW - 2	08/07/09	3,629.43	22.26	23.31	1.05	3,607.01
MW - 2	08/10/09	3,629.43	22.36	23.75	1.39	3,606.86

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	08/15/09	3,629.43	22.38	23.74	1.36	3,606.85
MW - 2	08/17/09	3,629.43	22.33	23.93	1.60	3,606.86
MW - 2	08/27/09	3,629.43	22.27	24.17	1.90	3,606.88
MW - 2	08/31/09	3,629.43	22.24	24.13	1.89	3,606.91
MW - 2	09/11/09	3,629.43	22.29	24.12	1.83	3,606.87
MW - 2	09/17/09	3,629.43	22.32	23.98	1.66	3,606.86
MW - 2	09/24/09	3,629.43	22.27	24.26	1.99	3,606.86
MW - 2	09/29/09	3,629.43	22.35	23.85	1.50	3,606.86
MW - 2	09/30/09	3,629.43	22.39	23.45	1.06	3,606.88
MW - 2	10/06/09	3,629.43	22.39	23.71	1.32	3,606.84
MW - 2	10/20/09	3,629.43	22.32	23.82	1.50	3,606.89
MW - 2	10/27/09	3,629.43	22.36	23.87	1.51	3,606.84
MW - 2	11/05/09	3,629.43	22.34	23.71	1.37	3,606.88
MW - 2	11/06/09	3,629.43	22.34	23.71	1.37	3,606.88
MW - 2	11/09/09	3,629.43	22.37	23.68	1.31	3,606.86
MW - 2	11/20/09	3,629.43	22.28	24.22	1.94	3,606.86
MW - 2	11/25/09	3,629.43	22.35	23.60	1.25	3,606.89
MW - 2	12/04/09	3,629.43	22.25	24.18	1.93	3,606.89
MW - 2	12/08/09	3,629.43	22.27	24.15	1.88	3,606.88
MW - 2	12/18/09	3,629.43	22.29	24.12	1.83	3,606.87
MW - 2	12/23/09	3,629.43	22.35	23.70	1.35	3,606.88
MW - 2	12/31/09	3,629.43	22.42	23.79	1.37	3,606.80
MW - 2	01/12/10	3,629.43	22.32	24.11	1.79	3,606.84
MW - 2	01/21/10	3,629.43	22.27	24.41	2.14	3,606.84
MW - 2	02/05/10	3,629.43	22.32	24.36	2.04	3,606.80
MW - 2	02/18/10	3,629.43	22.22	24.62	2.40	3,606.85
MW - 2	02/25/10	3,629.43	22.44	23.64	1.20	3,606.81
MW - 2	03/01/10	3,629.43	22.37	24.54	2.17	3,606.73
MW - 2	03/04/10	3,629.43	22.36	23.56	1.20	3,606.89
MW - 2	03/09/10	3,629.43	22.39	24.51	2.12	3,606.72
MW - 2	03/11/10	3,629.43	22.40	24.16	1.76	3,606.77
MW - 2	03/15/10	3,629.43	22.38	23.74	1.36	3,606.85
MW - 2	03/16/10	3,629.43	22.42	23.74	1.32	3,606.81
MW - 2	03/22/10	3,629.43	22.41	23.89	1.48	3,606.80
MW - 2	03/30/10	3,629.43	22.33	24.39	2.06	3,606.79
MW - 2	04/05/10	3,629.43	22.39	23.96	1.57	3,606.80
MW - 2	04/08/10	3,629.43	22.36	23.73	1.37	3,606.86
MW - 2	04/12/10	3,629.43	22.30	24.02	1.72	3,606.87
MW - 2	04/15/10	3,629.43	22.31	23.99	1.68	3,606.87

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	04/28/10	3,629.43	22.35	24.34	1.99	3,606.78
MW - 2	05/03/10	3,629.43	22.42	23.76	1.34	3,606.81
MW - 2	05/05/10	3,629.43	22.32	23.63	1.31	3,606.91
MW - 2	05/12/10	3,629.43	22.35	23.59	1.24	3,606.89
MW - 2	05/14/10	3,629.43	22.32	23.52	1.20	3,606.93
MW - 2	05/21/10	3,629.43	22.35	23.53	1.18	3,606.90
MW - 2	05/28/10	3,629.43	22.22	24.58	2.36	3,606.86
MW - 2	06/04/10	3,629.43	22.37	23.55	1.18	3,606.88
MW - 2	06/07/10	3,629.43	22.33	24.51	2.18	3,606.77
MW - 2	06/09/10	3,629.43	22.36	23.72	1.36	3,606.87
MW - 2	06/16/10	3,629.43	22.32	23.89	1.57	3,606.87
MW - 2	06/29/10	3,629.43	22.36	23.91	1.55	3,606.84
MW - 2	07/09/10	3,629.43	21.64	23.96	2.32	3,607.44
MW - 2	07/16/10	3,629.43	21.57	24.35	2.78	3,607.44
MW - 2	07/23/10	3,629.43	21.73	23.79	2.06	3,607.39
MW - 2	07/30/10	3,629.43	21.80	23.86	2.06	3,607.32
MW - 2	08/02/10	3,629.43	22.33	23.87	1.54	3,606.87
MW - 2	08/04/10	3,629.43	21.92	23.53	1.61	3,607.27
MW - 2	08/20/10	3,629.43	21.99	24.28	2.29	3,607.10
MW - 2	08/27/10	3,629.43	22.04	23.86	1.82	3,607.12
MW - 2	09/03/10	3,629.43	22.08	24.17	2.09	3,607.04
MW - 2	09/10/10	3,629.43	22.14	23.77	1.63	3,607.05
MW - 2	09/17/10	3,629.43	22.11	23.96	1.85	3,607.04
MW - 2	09/23/10	3,629.43	21.88	24.35	2.47	3,607.18
MW - 2	10/01/10	3,629.43	21.89	24.34	2.45	3,607.17
MW - 2	10/08/10	3,629.43	22.19	24.40	2.21	3,606.91
MW - 2	10/13/10	3,629.43	22.24	23.95	1.71	3,606.93
MW - 2	11/01/10	3,629.43	22.13	24.32	2.19	3,606.97
MW - 2	11/05/10	3,629.43	22.15	23.46	1.31	3,607.08
MW - 2	11/12/10	3,629.43	22.23	23.82	1.59	3,606.96
MW - 2	11/19/10	3,629.43	22.45	24.05	1.60	3,606.74
MW - 2	12/03/10	3,629.43	22.13	24.67	2.54	3,606.92
MW - 2	12/10/10	3,629.43	22.06	24.51	2.45	3,607.00
MW - 2	12/17/10	3,629.43	22.16	24.79	2.63	3,606.88
MW - 2	01/20/11	3,629.43	21.87	23.50	1.63	3,607.32
MW - 2	02/07/11	3,629.43	22.15	24.30	2.15	3,606.96
MW - 2	05/02/11	3,629.43	22.16	25.03	2.87	3,606.84
MW - 2	05/09/11	3,629.43	22.52	22.61	0.09	3,606.90
MW - 2	05/10/11	3,629.43	22.11	22.61	0.50	3,607.25

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	05/19/11	3,629.43	22.42	23.02	0.60	3,606.92
MW - 2	05/27/11	3,629.43	22.40	23.30	0.90	3,606.90
MW - 2	06/10/11	3,629.43	22.44	23.15	0.71	3,606.88
MW - 2	06/24/11	3,629.43	22.45	23.23	0.78	3,606.86
MW - 2	07/01/11	3,629.43	22.40	23.60	1.20	3,606.85
MW - 2	07/12/11	3,629.43	22.35	23.97	1.62	3,606.84
MW - 2	07/22/11	3,629.43	22.31	23.88	1.57	3,606.88
MW - 2	08/04/11	3,629.43	22.28	24.15	1.87	3,606.87
MW - 2	08/08/11	3,629.43	22.14	22.63	0.49	3,607.22
MW - 2	08/11/11	3,629.43	22.35	23.70	1.35	3,606.88
MW - 2	08/24/11	3,629.43	22.37	23.45	1.08	3,606.90
MW - 2	09/02/11	3,629.43	22.44	23.37	0.93	3,606.85
MW - 2	09/07/11	3,629.43	21.39	23.60	2.21	3,607.71
MW - 2	09/09/11	3,629.43	22.03	23.64	1.61	3,607.16
MW - 2	09/14/11	3,629.43	22.66	22.74	0.08	3,606.76
MW - 2	09/22/11	3,629.43	22.50	22.78	0.28	3,606.89
MW - 2	10/26/11	3,629.43	22.40	23.38	0.98	3,606.88
MW - 2	10/14/11	3,629.43	22.45	23.10	0.65	3,606.88
MW - 2	11/10/11	3,629.43	22.37	23.46	1.09	3,606.90
MW - 2	11/14/11	3,629.43	22.37	23.46	1.09	3,606.90
MW - 2	12/02/11	3,629.43	22.33	23.80	1.47	3,606.88
MW - 2	12/09/11	3,629.43	22.37	23.52	1.15	3,606.89
MW - 2	12/13/11	3,629.43	22.36	23.50	1.14	3,606.90
MW - 2	12/23/11	3,629.43	22.40	23.46	1.06	3,606.87
MW - 2	12/29/11	3,629.43	22.41	23.31	0.90	3,606.89
MW - 2	01/04/12	3,629.43	22.41	23.23	0.82	3,606.90
MW - 2	01/13/12	3,629.43	22.44	23.20	0.76	3,606.88
MW - 2	01/30/12	3,629.43	22.43	23.18	0.75	3,606.89
MW - 2	02/06/12	3,629.43	22.40	23.35	0.95	3,606.89
MW - 2	02/13/12	3,629.43	22.51	22.68	0.17	3,606.89
MW - 2	02/14/12	3,629.43	22.51	22.68	0.17	3,606.89
MW - 2	03/13/12	3,629.43	22.64	23.00	0.36	3,606.74
MW - 2	03/15/12	3,629.43	22.60	22.83	0.23	3,606.80
MW - 2	03/20/12	3,629.43	22.59	22.84	0.25	3,606.80
MW - 2	03/22/12	3,629.43	22.65	22.85	0.20	3,606.75
MW - 2	03/27/12	3,629.43	22.54	22.61	0.07	3,606.88
MW - 2	03/29/12	3,629.43	22.75	22.76	0.01	3,606.68
MW - 2	04/02/12	3,629.43	22.64	22.67	0.03	3,606.79
MW - 2	04/09/12	3,629.43	22.67	23.08	0.41	3,606.70

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	04/12/12	3,629.43	22.65	23.04	0.39	3,606.72
MW - 2	04/17/12	3,629.43	22.65	23.07	0.42	3,606.72
MW - 2	04/19/12	3,629.43	22.56	23.05	0.49	3,606.80
MW - 2	04/23/12	3,629.43	22.51	22.97	0.46	3,606.85
MW - 2	04/26/12	3,629.43	22.72	22.73	0.01	3,606.71
MW - 2	05/21/12	3,629.43	22.64	22.69	0.05	3,606.78
MW - 2	06/06/12	3,629.43	22.55	23.14	0.59	3,606.79
MW - 2	06/11/12	3,629.43	22.54	23.23	0.69	3,606.79
MW - 2	06/18/12	3,629.43	22.58	22.61	0.03	3,606.85
MW - 2	06/25/12	3,629.43	22.52	23.46	0.94	3,606.77
MW - 2	07/02/12	3,629.43	22.59	22.63	0.04	3,606.83
MW - 2	07/09/12	3,629.43	22.43	23.50	1.07	3,606.84
MW - 2	07/16/12	3,629.43	22.41	23.62	1.21	3,606.84
MW - 2	08/01/12	3,629.43	22.47	23.72	1.25	3,606.77
MW - 2	08/14/12	3,629.43	22.26	25.73	3.47	3,606.65
MW - 2	08/21/12	3,629.43	22.44	23.53	1.09	3,606.83
MW - 2	09/04/12	3,629.43	22.27	25.43	3.16	3,606.69
MW - 2	09/10/12	3,629.43	22.54	23.85	1.31	3,606.69
MW - 2	09/19/12	3,629.43	22.49	23.86	1.37	3,606.73
MW - 2	09/24/12	3,629.43	22.44	23.44	1.00	3,606.84
MW - 2	10/01/12	3,629.43	22.46	23.32	0.86	3,606.84
MW - 2	10/08/12	3,629.43	22.45	23.25	0.80	3,606.86
MW - 2	10/10/12	3,629.43	22.51	23.08	0.57	3,606.83
MW - 2	10/15/12	3,629.43	22.46	23.23	0.77	3,606.85
MW - 2	10/22/12	3,629.43	22.47	23.12	0.65	3,606.86
MW - 2	10/24/12	3,629.43	22.50	22.93	0.43	3,606.87
MW - 2	10/29/12	3,629.43	22.66	22.81	0.15	3,606.75
MW - 2	11/06/12	3,629.43	22.69	23.00	0.31	3,606.69
MW - 2	12/04/12	3,629.43	22.60	22.61	0.01	3,606.83
MW - 2	12/10/12	3,629.43	22.60	22.68	0.08	3,606.82
MW - 2	12/17/12	3,629.43	22.30	23.55	1.25	3,606.94
MW - 2	12/27/12	3,629.43	22.54	22.78	0.24	3,606.85
MW - 2	01/14/13	3,629.43	22.56	23.08	0.52	3,606.79
MW - 2	02/04/13	3,629.43	22.57	23.27	0.70	3,606.76
MW - 2	02/05/13	3,629.43	22.54	23.11	0.57	3,606.80
MW - 2	02/20/13	3,629.43	22.50	23.36	0.86	3,606.80
MW - 2	03/04/13	3,629.43	22.65	22.72	0.07	3,606.77
MW - 2	03/07/13	3,629.43	22.60	22.65	0.05	3,606.82
MW - 2	03/26/13	3,629.43	22.59	22.63	0.04	3,606.83

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 2	04/10/13	3,629.43	22.55	22.66	0.11	3,606.86
MW - 2	04/17/13	3,629.43	22.55	22.60	0.05	3,606.87
MW - 2	04/24/13	3,629.43	22.67	22.81	0.14	3,606.74
MW - 2	05/02/13	3,629.43	22.57	22.84	0.27	3,606.82
MW - 2	05/09/13	3,629.43	22.50	22.72	0.22	3,606.90
MW - 2	05/17/13	3,629.43	22.55	22.80	0.25	3,606.84
MW - 2	05/22/13	3,629.43	22.58	22.78	0.20	3,606.82
MW - 2	05/29/13	3,629.43	22.60	23.03	0.43	3,606.77
MW - 2	06/03/13	3,629.43	22.59	22.64	0.05	3,606.83
MW - 2	06/20/13	3,629.43	22.59	22.85	0.26	3,606.80
MW - 2	06/25/13	3,629.43	23.11	23.28	0.17	3,606.29
MW - 2	07/02/13	3,629.43	22.58	22.88	0.30	3,606.81
MW - 2	07/09/13	3,629.43	22.58	23.19	0.61	3,606.76
MW - 2	07/16/13	3,629.43	22.69	23.33	0.64	3,606.64
MW - 2	07/24/13	3,629.43	22.69	23.32	0.63	3,606.65
MW - 2	07/31/13	3,629.43	22.69	23.30	0.61	3,606.65
MW - 2	08/01/13	3,629.43	22.67	23.43	0.76	3,606.65
MW - 2	08/06/13	3,629.43	22.58	22.91	0.33	3,606.80
MW - 2	08/16/13	3,629.43	22.49	23.17	0.68	3,606.84
MW - 2	09/12/13	3,629.43	22.53	22.79	0.26	3,606.86
MW - 2	09/19/13	3,629.43	22.56	22.72	0.16	3,606.85
MW - 2	09/25/13	3,629.43	22.48	23.02	0.54	3,606.87
MW - 2	09/30/13	3,629.43	22.49	22.89	0.40	3,606.88
MW - 2	10/09/13	3,629.43	22.55	22.66	0.11	3,606.86
MW - 2	10/14/13	3,629.43	22.54	22.70	0.16	3,606.87
MW - 2	10/22/13	3,629.43	22.54	22.83	0.29	3,606.85
MW - 2	10/30/13	3,629.43	22.58	22.96	0.38	3,606.79
MW - 2	11/07/13	3,629.43	22.53	22.79	0.26	3,606.86
MW - 2	11/27/13	3,629.43	22.44	23.22	0.78	3,606.87
MW - 2	12/04/13	3,629.43	22.46	23.25	0.79	3,606.85
MW - 2	12/10/13	3,629.43	22.46	25.35	2.89	3,606.54
MW - 2	12/16/13	3,629.43	22.45	23.38	0.93	3,606.84
MW - 2	12/24/13	3,629.43	22.41	23.41	1.00	3,606.87
MW - 3	05/02/97	3,629.17	-	24.85	3.85	3,604.32
MW - 3	03/06/00	3,628.90	21.73	27.76	6.03	3,606.27
MW - 3	05/16/00	3,628.90	21.73	27.74	6.01	3,606.27
MW - 3	08/31/00	3,628.90	21.75	27.81	6.06	3,606.24
MW - 3	11/17/00	3,628.90	21.78	27.33	5.55	3,606.29

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	03/07/01	3,628.90	21.90	24.10	2.20	3,606.67
MW - 3	05/30/01	3,628.90	21.88	25.85	3.97	3,606.42
MW - 3	08/27/01	3,628.90	22.18	24.97	2.79	3,606.30
MW - 3	10/12/01	3,628.90	21.92	26.10	4.18	3,606.35
MW - 3	02/25/02	3,628.90	21.76	27.26	5.50	3,606.32
MW - 3	03/18/02	3,628.90	21.78	27.50	5.72	3,606.26
MW - 3	03/28/02	3,628.90	21.80	26.81	5.01	3,606.35
MW - 3	04/03/02	3,628.90	21.89	26.51	4.62	3,606.32
MW - 3	04/12/02	3,628.90	21.91	26.35	4.44	3,606.32
MW - 3	04/16/02	3,628.90	22.03	25.64	3.61	3,606.33
MW - 3	05/03/02	3,628.90	21.90	26.21	4.31	3,606.35
MW - 3	05/10/02	3,628.90	21.96	26.04	4.08	3,606.33
MW - 3	05/13/02	3,628.90	22.03	25.56	3.53	3,606.34
MW - 3	05/24/02	3,628.90	21.96	26.31	4.35	3,606.29
MW - 3	06/10/02	3,628.90	22.11	26.32	4.21	3,606.16
MW - 3	06/19/02	3,628.90	21.93	26.93	5.00	3,606.22
MW - 3	07/03/02	3,628.90	21.95	26.67	4.72	3,606.24
MW - 3	07/11/02	3,628.90	21.62	26.81	5.19	3,606.50
MW - 3	07/16/02	3,628.90	21.94	26.25	4.31	3,606.31
MW - 3	08/21/02	3,628.90	21.87	26.77	4.90	3,606.30
MW - 3	08/27/02	3,628.90	21.91	26.53	4.62	3,606.30
MW - 3	09/05/02	3,628.90	21.95	26.22	4.27	3,606.31
MW - 3	09/10/02	3,628.90	22.06	25.68	3.62	3,606.30
MW - 3	10/03/02	3,628.90	22.14	25.11	2.97	3,606.31
MW - 3	10/08/02	3,628.90	22.02	25.88	3.86	3,606.30
MW - 3	10/14/02	3,628.90	22.00	26.12	4.12	3,606.28
MW - 3	11/15/02	3,628.90	21.96	26.14	4.18	3,606.31
MW - 3	12/27/02	3,628.90	21.85	26.63	4.78	3,606.33
MW - 3	01/07/03	3,628.90	21.87	26.34	4.47	3,606.36
MW - 3	03/05/03	3,628.90	21.83	26.87	5.04	3,606.31
MW - 3	03/06/03	3,628.90	22.08	25.33	3.25	3,606.33
MW - 3	03/12/03	3,628.90	21.90	26.42	4.52	3,606.32
MW - 3	03/20/03	3,628.90	22.19	26.64	4.45	3,606.04
MW - 3	03/27/03	3,628.90	21.92	26.05	4.13	3,606.36
MW - 3	04/03/03	3,628.90	21.94	25.81	3.87	3,606.38
MW - 3	04/16/03	3,628.90	21.93	26.26	4.33	3,606.32
MW - 3	05/13/03	3,628.90	22.10	25.54	3.44	3,606.28
MW - 3	05/15/03	3,628.90	23.16	24.87	1.71	3,605.48
MW - 3	05/21/03	3,628.90	22.03	26.45	4.42	3,606.21

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	05/28/03	3,628.90	22.04	26.25	4.21	3,606.23
MW - 3	06/05/03	3,628.90	22.02	26.03	4.01	3,606.28
MW - 3	07/10/03	3,628.90	22.07	26.67	4.60	3,606.14
MW - 3	07/31/03	3,628.90	21.93	26.59	4.66	3,606.27
MW - 3	08/06/03	3,628.90	22.17	26.38	4.21	3,606.10
MW - 3	08/13/03	3,628.90	22.25	26.30	4.05	3,606.04
MW - 3	08/22/03	3,628.90	23.91	24.33	0.42	3,604.93
MW - 3	08/25/03	3,628.90	22.26	26.33	4.07	3,606.03
MW - 3	09/11/03	3,628.90	22.49	24.46	1.97	3,606.11
MW - 3	09/30/03	3,628.90	21.88	26.76	4.88	3,606.29
MW - 3	10/06/03	3,628.90	22.00	26.15	4.15	3,606.28
MW - 3	10/14/03	3,628.90	22.25	26.76	4.51	3,605.97
MW - 3	10/21/03	3,628.90	22.30	26.38	4.08	3,605.99
MW - 3	10/27/03	3,628.90	22.33	25.99	3.66	3,606.02
MW - 3	11/06/03	3,628.90	22.13	25.96	3.83	3,606.20
MW - 3	11/10/03	3,628.90	22.47	25.76	3.29	3,605.94
MW - 3	11/17/03	3,628.90	22.12	25.70	3.58	3,606.24
MW - 3	12/04/03	3,628.90	22.05	26.35	4.30	3,606.21
MW - 3	12/15/03	3,628.90	21.97	26.08	4.11	3,606.31
MW - 3	12/22/03	3,628.90	21.92	26.24	4.32	3,606.33
MW - 3	12/31/03	3,628.90	21.88	26.40	4.52	3,606.34
MW - 3	01/27/04	3,628.90	22.01	25.80	3.79	3,606.32
MW - 3	02/03/04	3,628.90	21.94	25.72	3.78	3,606.39
MW - 3	02/10/04	3,628.90	21.88	26.63	4.75	3,606.31
MW - 3	02/18/04	3,628.90	22.16	25.83	3.67	3,606.19
MW - 3	02/26/04	3,628.90	22.07	26.65	4.58	3,606.14
MW - 3	03/04/04	3,628.90	22.04	26.83	4.79	3,606.14
MW - 3	03/11/04	3,628.90	22.07	26.97	4.90	3,606.10
MW - 3	03/16/04	3,628.90	22.37	27.30	4.93	3,605.79
MW - 3	03/19/04	3,628.90	22.56	26.20	3.64	3,605.79
MW - 3	03/23/04	3,628.90	22.51	26.15	3.64	3,605.84
MW - 3	03/30/04	3,628.90	22.70	26.10	3.40	3,605.69
MW - 3	04/07/04	3,628.90	22.46	26.05	3.59	3,605.90
MW - 3	04/13/04	3,628.90	22.55	26.51	3.96	3,605.76
MW - 3	04/20/04	3,628.90	21.87	26.12	4.25	3,606.39
MW - 3	04/27/04	3,628.90	21.91	25.83	3.92	3,606.40
MW - 3	05/25/04	3,628.90	21.88	26.20	4.32	3,606.37
MW - 3	06/03/04	3,628.90	21.87	26.42	4.55	3,606.35
MW - 3	06/17/04	3,628.90	21.86	26.62	4.76	3,606.33

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	06/23/04	3,628.90	21.84	26.65	4.81	3,606.34
MW - 3	06/25/04	3,628.90	21.88	26.69	4.81	3,606.30
MW - 3	07/01/04	3,628.90	21.92	26.53	4.61	3,606.29
MW - 3	07/12/04	3,628.90	21.84	26.81	4.97	3,606.31
MW - 3	07/15/04	3,628.90	21.83	26.88	5.05	3,606.31
MW - 3	07/21/04	3,628.90	21.83	26.88	5.05	3,606.31
MW - 3	08/02/04	3,628.90	21.81	26.90	5.09	3,606.33
MW - 3	08/11/04	3,628.90	21.83	26.69	4.86	3,606.34
MW - 3	08/13/04	3,628.90	21.88	26.94	5.06	3,606.26
MW - 3	08/16/04	3,628.90	21.83	27.00	5.17	3,606.29
MW - 3	08/19/04	3,628.90	21.82	27.06	5.24	3,606.29
MW - 3	08/26/04	3,628.90	22.88	26.50	3.62	3,605.48
MW - 3	08/31/04	3,628.90	22.03	26.09	4.06	3,606.26
MW - 3	09/13/04	3,628.90	21.96	25.86	3.90	3,606.36
MW - 3	09/21/04	3,628.90	22.00	25.85	3.85	3,606.32
MW - 3	09/29/04	3,628.90	21.58	24.35	2.77	3,606.90
MW - 3	10/05/04	3,628.90	21.21	24.30	3.09	3,607.23
MW - 3	10/12/04	3,628.90	21.25	24.45	3.20	3,607.17
MW - 3	10/19/04	3,628.90	21.43	24.72	3.29	3,606.98
MW - 3	10/25/04	3,628.90	21.60	24.69	3.09	3,606.84
MW - 3	11/01/04	3,628.90	22.56	25.66	3.10	3,605.88
MW - 3	11/09/04	3,628.90	22.40	24.99	2.59	3,606.11
MW - 3	11/16/04	3,628.90	21.64	25.50	3.86	3,606.68
MW - 3	11/22/04	3,628.90	21.04	24.86	3.82	3,607.29
MW - 3	11/29/04	3,628.90	21.36	24.61	3.25	3,607.05
MW - 3	12/10/04	3,628.90	21.04	24.70	3.66	3,607.31
MW - 3	12/13/04	3,628.90	21.04	24.70	3.66	3,607.31
MW - 3	12/20/04	3,628.90	21.10	25.27	4.17	3,607.17
MW - 3	12/27/04	3,628.90	21.29	24.93	3.64	3,607.06
MW - 3	01/10/05	3,628.90	21.69	24.97	3.28	3,606.72
MW - 3	01/17/05	3,628.90	21.40	25.10	3.70	3,606.95
MW - 3	01/24/05	3,628.90	21.47	25.13	3.66	3,606.88
MW - 3	01/31/05	3,628.90	21.53	25.15	3.62	3,606.83
MW - 3	02/07/05	3,628.90	21.55	25.13	3.58	3,606.81
MW - 3	02/14/05	3,628.90	21.62	25.10	3.48	3,606.76
MW - 3	02/21/05	3,628.90	21.64	25.14	3.50	3,606.74
MW - 3	02/28/05	3,628.90	21.69	25.13	3.44	3,606.69
MW - 3	03/07/05	3,628.90	21.76	25.05	3.29	3,606.65
MW - 3	03/14/05	3,628.90	21.70	25.00	3.30	3,606.71

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	03/16/05	3,628.90	21.56	25.08	3.52	3,606.81
MW - 3	03/21/05	3,628.90	21.71	25.00	3.29	3,606.70
MW - 3	03/28/05	3,628.90	21.69	25.08	3.39	3,606.70
MW - 3	04/04/05	3,628.90	21.73	25.09	3.36	3,606.67
MW - 3	04/13/05	3,628.90	21.75	25.01	3.26	3,606.66
MW - 3	04/18/05	3,628.90	21.76	25.06	3.30	3,606.65
MW - 3	05/23/05	3,628.90	21.72	25.52	3.80	3,606.61
MW - 3	06/02/05	3,628.90	21.81	25.40	3.59	3,606.55
MW - 3	06/07/05	3,628.90	21.72	25.70	3.98	3,606.58
MW - 3	06/13/05	3,628.90	21.76	25.43	3.67	3,606.59
MW - 3	06/14/05	3,628.90	21.76	25.43	3.67	3,606.59
MW - 3	06/21/05	3,628.90	21.74	25.70	3.96	3,606.57
MW - 3	06/28/05	3,628.90	21.81	25.54	3.73	3,606.53
MW - 3	07/13/05	3,628.90	21.84	25.12	3.28	3,606.57
MW - 3	07/19/05	3,628.90	21.93	25.15	3.22	3,606.49
MW - 3	07/26/05	3,628.90	21.82	25.40	3.58	3,606.54
MW - 3	08/01/05	3,628.90	21.87	25.33	3.46	3,606.51
MW - 3	08/10/05	3,628.90	21.86	25.45	3.59	3,606.50
MW - 3	08/15/05	3,628.90	21.90	25.16	3.26	3,606.51
MW - 3	08/24/05	3,628.90	21.87	25.30	3.43	3,606.52
MW - 3	08/30/05	3,628.90	21.88	25.11	3.23	3,606.54
MW - 3	09/07/05	3,628.90	21.86	25.14	3.28	3,606.55
MW - 3	09/12/05	3,628.90	21.89	25.00	3.11	3,606.54
MW - 3	09/13/05	3,628.90	21.85	25.08	3.23	3,606.57
MW - 3	09/20/05	3,628.90	21.90	25.09	3.19	3,606.52
MW - 3	09/26/05	3,628.90	21.84	25.50	3.66	3,606.51
MW - 3	10/07/05	3,628.90	21.87	25.44	3.57	3,606.49
MW - 3	10/11/05	3,628.90	21.90	25.30	3.40	3,606.49
MW - 3	10/18/05	3,628.90	21.86	25.25	3.39	3,606.53
MW - 3	10/25/05	3,628.90	21.86	25.27	3.41	3,606.53
MW - 3	11/01/05	3,628.90	22.06	25.31	3.25	3,606.35
MW - 3	11/14/05	3,628.90	21.90	25.07	3.17	3,606.52
MW - 3	11/23/05	3,628.90	21.99	25.00	3.01	3,606.46
MW - 3	11/28/05	3,628.90	21.80	25.76	3.96	3,606.51
MW - 3	12/06/05	3,628.90	21.86	25.34	3.48	3,606.52
MW - 3	12/07/05	3,628.90	21.91	24.43	2.52	3,606.61
MW - 3	12/12/05	3,628.90	22.01	25.01	3.00	3,606.44
MW - 3	12/28/05	3,628.90	22.11	25.25	3.14	3,606.32
MW - 3	12/29/05	3,628.90	22.11	25.15	3.04	3,606.33

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	01/04/06	3,628.90	22.07	25.09	3.02	3,606.38
MW - 3	01/10/06	3,628.90	22.05	25.53	3.48	3,606.33
MW - 3	01/17/06	3,628.90	21.90	25.50	3.60	3,606.46
MW - 3	01/26/06	3,628.90	21.94	25.47	3.53	3,606.43
MW - 3	01/31/06	3,628.90	21.89	25.40	3.51	3,606.48
MW - 3	02/07/06	3,628.90	21.90	25.51	3.61	3,606.46
MW - 3	02/13/06	3,628.90	21.93	25.45	3.52	3,606.44
MW - 3	02/22/06	3,628.90	21.95	25.33	3.38	3,606.44
MW - 3	02/27/06	3,628.90	21.90	25.25	3.35	3,606.50
MW - 3	03/07/06	3,628.90	22.01	25.52	3.51	3,606.36
MW - 3	03/10/06	3,628.90	21.94	25.18	3.24	3,606.47
MW - 3	03/15/06	3,628.90	22.06	25.41	3.35	3,606.34
MW - 3	03/22/06	3,628.90	21.95	25.55	3.60	3,606.41
MW - 3	03/29/06	3,628.90	21.87	25.69	3.82	3,606.46
MW - 3	04/03/06	3,628.90	21.95	25.34	3.39	3,606.44
MW - 3	04/11/06	3,628.90	21.90	25.46	3.56	3,606.47
MW - 3	04/18/06	3,628.90	21.92	25.43	3.51	3,606.45
MW - 3	04/25/06	3,628.90	21.96	25.41	3.45	3,606.42
MW - 3	05/02/06	3,628.90	21.94	25.87	3.93	3,606.37
MW - 3	05/10/06	3,628.90	21.89	25.71	3.82	3,606.44
MW - 3	05/16/06	3,628.90	21.93	24.89	2.96	3,606.53
MW - 3	05/23/06	3,628.90	21.85	25.72	3.87	3,606.47
MW - 3	05/31/06	3,628.90	21.94	25.45	3.51	3,606.43
MW - 3	06/06/06	3,628.90	21.92	25.83	3.91	3,606.39
MW - 3	06/09/06	3,628.90	22.01	25.11	3.10	3,606.43
MW - 3	06/13/06	3,628.90	21.96	25.58	3.62	3,606.40
MW - 3	06/20/06	3,628.90	21.96	25.52	3.56	3,606.41
MW - 3	07/05/06	3,628.90	21.93	25.81	3.88	3,606.39
MW - 3	07/18/06	3,628.90	21.94	25.81	3.87	3,606.38
MW - 3	07/26/06	3,628.90	21.97	25.68	3.71	3,606.37
MW - 3	07/31/06	3,628.90	22.03	25.36	3.33	3,606.37
MW - 3	08/08/06	3,628.90	22.05	25.47	3.42	3,606.34
MW - 3	08/18/06	3,628.90	21.93	25.43	3.50	3,606.45
MW - 3	08/22/06	3,628.90	22.39	25.61	3.22	3,606.03
MW - 3	09/12/06	3,628.90	20.70	24.32	3.62	3,607.66
MW - 3	09/16/06	3,628.90	20.72	24.60	3.88	3,607.60
MW - 3	10/31/06	3,628.90	21.31	25.48	4.17	3,606.96
MW - 3	11/15/06	3,628.90	22.03	25.16	3.13	3,606.40
MW - 3	11/28/06	3,628.90	21.49	26.84	5.35	3,606.61

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	01/31/07	3,628.90	21.64	26.17	4.53	3,606.58
MW - 3	02/07/07	3,628.90	21.70	25.80	4.10	3,606.59
MW - 3	02/22/07	3,628.90	21.81	25.99	4.18	3,606.46
MW - 3	03/07/07	3,628.90	21.64	26.00	4.36	3,606.61
MW - 3	03/27/07	3,628.90	21.82	25.59	3.77	3,606.51
MW - 3	04/02/07	3,628.90	21.83	25.73	3.90	3,606.49
MW - 3	04/11/07	3,628.90	21.82	25.62	3.80	3,606.51
MW - 3	04/16/07	3,628.90	21.87	25.21	3.34	3,606.53
MW - 3	04/23/07	3,628.90	21.87	25.30	3.43	3,606.52
MW - 3	04/27/07	3,628.90	21.92	24.87	2.95	3,606.54
MW - 3	04/30/07	3,628.90	21.93	24.51	2.58	3,606.58
MW - 3	05/17/07	3,628.90	21.86	25.43	3.57	3,606.50
MW - 3	05/18/07	3,628.90	21.82	24.45	2.63	3,606.69
MW - 3	06/07/07	3,628.90	21.83	25.66	3.83	3,606.50
MW - 3	06/12/07	3,628.90	21.88	25.16	3.28	3,606.53
MW - 3	06/20/07	3,628.90	21.89	25.21	3.32	3,606.51
MW - 3	06/29/07	3,628.90	21.86	25.34	3.48	3,606.52
MW - 3	07/02/07	3,628.90	21.94	24.77	2.83	3,606.54
MW - 3	07/11/07	3,628.90	21.89	25.25	3.36	3,606.51
MW - 3	07/18/07	3,628.90	21.94	25.08	3.14	3,606.49
MW - 3	07/24/07	3,628.90	21.96	24.96	3.00	3,606.49
MW - 3	08/01/07	3,628.90	21.96	25.02	3.06	3,606.48
MW - 3	08/09/07	3,628.90	21.96	25.05	3.09	3,606.48
MW - 3	08/14/07	3,628.90	22.00	24.74	2.74	3,606.49
MW - 3	08/21/07	3,628.90	21.96	24.83	2.87	3,606.51
MW - 3	08/25/07	3,628.90	21.96	25.14	3.18	3,606.46
MW - 3	08/29/07	3,628.90	22.02	24.63	2.61	3,606.49
MW - 3	09/05/07	3,628.90	21.98	24.76	2.78	3,606.50
MW - 3	09/18/07	3,628.90	21.93	25.18	3.25	3,606.48
MW - 3	09/26/07	3,628.90	21.96	25.06	3.10	3,606.48
MW - 3	10/03/07	3,628.90	21.93	25.12	3.19	3,606.49
MW - 3	10/10/07	3,628.90	21.91	25.09	3.18	3,606.51
MW - 3	10/17/07	3,628.90	21.90	25.14	3.24	3,606.51
MW - 3	11/07/07	3,628.90	21.90	25.26	3.36	3,606.50
MW - 3	11/16/07	3,628.90	21.90	25.21	3.31	3,606.50
MW - 3	11/26/07	3,628.90	21.93	25.19	3.26	3,606.48
MW - 3	11/30/07	3,628.90	21.90	25.36	3.46	3,606.48
MW - 3	12/07/07	3,628.90	21.93	25.11	3.18	3,606.49
MW - 3	12/18/07	3,628.90	21.92	25.92	4.00	3,606.38

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	01/18/08	3,628.90	21.87	25.71	3.84	3,606.45
MW - 3	01/23/08	3,628.90	21.95	25.35	3.40	3,606.44
MW - 3	02/13/08	3,628.90	21.89	25.70	3.81	3,606.44
MW - 3	02/21/08	3,628.90	21.89	25.63	3.74	3,606.45
MW - 3	02/26/08	3,628.90	21.96	25.53	3.57	3,606.40
MW - 3	03/14/08	3,628.90	21.91	25.76	3.85	3,606.41
MW - 3	03/20/08	3,628.90	21.93	25.43	3.50	3,606.45
MW - 3	04/04/08	3,628.90	21.93	25.20	3.27	3,606.48
MW - 3	04/10/08	3,628.90	21.95	25.23	3.28	3,606.46
MW - 3	04/17/08	3,628.90	21.93	25.64	3.71	3,606.41
MW - 3	04/24/08	3,628.90	21.94	25.43	3.49	3,606.44
MW - 3	05/01/08	3,628.90	21.94	25.33	3.39	3,606.45
MW - 3	05/08/08	3,628.90	21.97	25.23	3.26	3,606.44
MW - 3	05/15/08	3,628.90	21.96	25.19	3.23	3,606.46
MW - 3	05/20/08	3,628.90	22.03	24.88	2.85	3,606.44
MW - 3	05/26/08	3,628.90	22.01	25.06	3.05	3,606.43
MW - 3	05/30/08	3,628.90	22.00	25.28	3.28	3,606.41
MW - 3	06/04/08	3,628.90	21.99	24.96	2.97	3,606.46
MW - 3	06/12/08	3,628.90	22.02	25.12	3.10	3,606.42
MW - 3	06/17/08	3,628.90	22.07	24.82	2.75	3,606.42
MW - 3	06/24/08	3,628.90	22.03	25.06	3.03	3,606.42
MW - 3	07/03/08	3,628.90	22.01	25.16	3.15	3,606.42
MW - 3	07/09/08	3,628.90	22.05	24.98	2.93	3,606.41
MW - 3	07/14/08	3,628.90	22.08	24.74	2.66	3,606.42
MW - 3	07/23/08	3,628.90	22.09	25.08	2.99	3,606.36
MW - 3	08/01/08	3,628.90	22.00	25.12	3.12	3,606.43
MW - 3	08/05/08	3,628.90	21.98	25.33	3.35	3,606.42
MW - 3	08/11/08	3,628.90	22.04	24.98	2.94	3,606.42
MW - 3	08/19/08	3,628.90	22.02	25.02	3.00	3,606.43
MW - 3	08/28/08	3,628.90	22.10	25.04	2.94	3,606.36
MW - 3	09/09/08	3,628.90	21.98	25.30	3.32	3,606.42
MW - 3	09/25/08	3,628.90	21.98	25.46	3.48	3,606.40
MW - 3	10/03/08	3,628.90	22.50	24.95	2.45	3,606.03
MW - 3	10/07/08	3,628.90	22.08	24.70	2.62	3,606.43
MW - 3	10/15/08	3,628.90	22.07	24.79	2.72	3,606.42
MW - 3	10/22/08	3,629.43	22.06	24.72	2.66	3,606.97
MW - 3	10/28/08	3,628.90	22.03	24.62	2.59	3,606.48
MW - 3	11/06/08	3,628.90	22.03	24.70	2.67	3,606.47
MW - 3	11/13/08	3,628.90	22.00	24.80	2.80	3,606.48

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	11/19/08	3,628.90	22.05	24.71	2.66	3,606.45
MW - 3	12/16/08	3,628.90	21.98	25.26	3.28	3,606.43
MW - 3	01/07/09	3,628.90	21.93	25.52	3.59	3,606.43
MW - 3	01/16/09	3,628.90	21.91	25.15	3.24	3,606.50
MW - 3	01/29/09	3,628.90	22.08	24.79	2.71	3,606.41
MW - 3	02/09/09	3,628.90	22.01	24.99	2.98	3,606.44
MW - 3	02/13/09	3,628.90	22.13	24.23	2.10	3,606.46
MW - 3	02/26/09	3,628.90	22.08	25.25	3.17	3,606.34
MW - 3	03/02/09	3,628.90	22.12	25.38	3.26	3,606.29
MW - 3	03/04/09	3,628.90	22.17	23.87	1.70	3,606.48
MW - 3	03/09/09	3,628.90	22.10	24.38	2.28	3,606.46
MW - 3	03/17/09	3,628.90	22.15	25.40	3.25	3,606.26
MW - 3	03/19/09	3,628.90	22.17	25.42	3.25	3,606.24
MW - 3	03/25/09	3,628.90	22.05	24.82	2.77	3,606.43
MW - 3	03/27/09	3,628.90	22.23	25.35	3.12	3,606.20
MW - 3	03/30/09	3,628.90	22.24	25.29	3.05	3,606.20
MW - 3	04/06/09	3,628.90	22.22	25.21	2.99	3,606.23
MW - 3	04/08/09	3,628.90	22.00	25.21	3.21	3,606.42
MW - 3	04/13/09	3,628.90	22.17	24.22	2.05	3,606.42
MW - 3	04/15/09	3,628.90	22.20	25.19	2.99	3,606.25
MW - 3	04/21/09	3,628.90	22.21	25.16	2.95	3,606.25
MW - 3	04/27/09	3,628.90	22.04	25.05	3.01	3,606.41
MW - 3	05/07/09	3,628.90	22.24	25.16	2.92	3,606.22
MW - 3	05/20/09	3,628.90	21.99	25.28	3.29	3,606.42
MW - 3	05/21/09	3,628.90	22.00	25.33	3.33	3,606.40
MW - 3	05/27/09	3,628.90	22.08	24.85	2.77	3,606.40
MW - 3	06/02/09	3,628.90	22.06	24.88	2.82	3,606.42
MW - 3	06/04/09	3,628.90	sheen	31.72	0.00	3,597.18
MW - 3	06/10/09	3,628.90	22.27	25.14	2.87	3,606.20
MW - 3	06/15/09	3,628.90	22.25	25.12	2.87	3,606.22
MW - 3	07/01/09	3,628.90	21.93	25.45	3.52	3,606.44
MW - 3	07/10/09	3,628.90	22.02	25.00	2.98	3,606.43
MW - 3	07/15/09	3,628.90	21.94	25.36	3.42	3,606.45
MW - 3	07/21/09	3,628.90	22.16	24.38	2.22	3,606.41
MW - 3	07/23/09	3,628.90	22.26	23.31	1.05	3,606.48
MW - 3	07/28/09	3,628.90	22.25	23.33	1.08	3,606.49
MW - 3	07/30/09	3,628.90	22.16	24.21	2.05	3,606.43
MW - 3	08/05/09	3,628.90	22.15	23.98	1.83	3,606.48
MW - 3	08/07/09	3,628.90	22.42	23.36	0.94	3,606.34

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	08/10/09	3,628.90	22.16	24.05	1.89	3,606.46
MW - 3	08/15/09	3,628.90	22.21	24.24	2.03	3,606.39
MW - 3	08/17/09	3,628.90	22.17	24.24	2.07	3,606.42
MW - 3	08/27/09	3,628.90	22.10	24.53	2.43	3,606.44
MW - 3	08/31/09	3,628.90	22.09	24.47	2.38	3,606.45
MW - 3	09/11/09	3,628.90	22.24	24.85	2.61	3,606.27
MW - 3	09/17/09	3,628.90	22.19	24.42	2.23	3,606.38
MW - 3	09/24/09	3,628.90	22.03	24.08	2.05	3,606.56
MW - 3	09/29/09	3,628.90	22.19	24.01	1.82	3,606.44
MW - 3	09/30/09	3,628.90	22.20	23.53	1.33	3,606.50
MW - 3	10/06/09	3,628.90	22.21	23.99	1.78	3,606.42
MW - 3	10/20/09	3,628.90	22.15	24.17	2.02	3,606.45
MW - 3	10/27/09	3,628.90	22.18	24.09	1.91	3,606.43
MW - 3	11/05/09	3,628.90	22.13	24.20	2.07	3,606.46
MW - 3	11/06/09	3,628.90	22.13	24.20	2.07	3,606.46
MW - 3	11/09/09	3,628.90	22.19	24.04	1.85	3,606.43
MW - 3	11/20/09	3,628.90	22.07	24.68	2.61	3,606.44
MW - 3	11/25/09	3,628.90	22.20	23.78	1.58	3,606.46
MW - 3	12/04/09	3,628.90	22.07	24.64	2.57	3,606.44
MW - 3	12/08/09	3,628.90	22.08	24.60	2.52	3,606.44
MW - 3	12/18/09	3,628.90	22.10	24.46	2.36	3,606.45
MW - 3	12/23/09	3,628.90	22.18	23.90	1.72	3,606.46
MW - 3	12/31/09	3,628.90	22.21	24.21	2.00	3,606.39
MW - 3	01/12/10	3,628.90	21.12	24.65	3.53	3,607.25
MW - 3	01/21/10	3,628.90	22.03	25.00	2.97	3,606.42
MW - 3	02/05/10	3,628.90	22.09	24.92	2.83	3,606.39
MW - 3	02/18/10	3,628.90	21.97	25.22	3.25	3,606.44
MW - 3	02/25/10	3,628.90	22.23	24.08	1.85	3,606.39
MW - 3	03/01/10	3,628.90	22.11	25.16	3.05	3,606.33
MW - 3	03/04/10	3,628.90	22.17	23.97	1.80	3,606.46
MW - 3	03/09/10	3,628.90	22.13	25.11	2.98	3,606.32
MW - 3	03/11/10	3,628.90	22.15	24.89	2.74	3,606.34
MW - 3	03/15/10	3,628.90	22.22	23.95	1.73	3,606.42
MW - 3	03/16/10	3,628.90	22.26	23.90	1.64	3,606.39
MW - 3	03/22/10	3,628.90	22.21	23.97	1.76	3,606.43
MW - 3	03/30/10	3,628.90	22.09	24.99	2.90	3,606.38
MW - 3	04/05/10	3,628.90	22.19	24.41	2.22	3,606.38
MW - 3	04/08/10	3,628.90	22.25	23.92	1.67	3,606.40
MW - 3	04/12/10	3,628.90	22.13	23.40	1.27	3,606.58

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	04/15/10	3,628.90	22.15	23.39	1.24	3,606.56
MW - 3	04/28/10	3,628.90	22.09	24.88	2.79	3,606.39
MW - 3	05/03/10	3,628.90	22.25	23.89	1.64	3,606.40
MW - 3	05/05/10	3,628.90	22.05	24.05	2.00	3,606.55
MW - 3	05/12/10	3,628.90	22.07	24.00	1.93	3,606.54
MW - 3	05/14/10	3,628.90	22.05	23.97	1.92	3,606.56
MW - 3	05/21/10	3,628.90	22.03	23.96	1.93	3,606.58
MW - 3	05/28/10	3,628.90	22.00	25.07	3.07	3,606.44
MW - 3	06/04/10	3,628.90	22.02	23.97	1.95	3,606.59
MW - 3	06/07/10	3,628.90	22.12	24.94	2.82	3,606.36
MW - 3	06/09/10	3,628.90	22.17	23.95	1.78	3,606.46
MW - 3	06/16/10	3,628.90	22.11	24.55	2.44	3,606.42
MW - 3	06/29/10	3,628.90	22.13	24.53	2.40	3,606.41
MW - 3	07/09/10	3,628.90	21.34	23.39	2.05	3,607.25
MW - 3	07/16/10	3,628.90	21.44	23.64	2.20	3,607.13
MW - 3	07/23/10	3,628.90	21.52	24.03	2.51	3,607.00
MW - 3	07/30/10	3,628.90	21.57	24.20	2.63	3,606.94
MW - 3	08/02/10	3,628.90	22.13	24.54	2.41	3,606.41
MW - 3	08/04/10	3,628.90	21.66	24.08	2.42	3,606.88
MW - 3	08/20/10	3,628.90	20.77	24.65	3.88	3,607.55
MW - 3	08/27/10	3,628.90	21.86	24.37	2.51	3,606.66
MW - 3	09/03/10	3,628.90	21.83	24.86	3.03	3,606.62
MW - 3	09/10/10	3,628.90	21.88	24.46	2.58	3,606.63
MW - 3	09/17/10	3,628.90	21.85	24.52	2.67	3,606.65
MW - 3	09/23/10	3,628.90	22.06	23.85	1.79	3,606.57
MW - 3	10/01/10	3,628.90	22.08	23.83	1.75	3,606.56
MW - 3	10/08/10	3,628.90	21.85	25.15	3.30	3,606.56
MW - 3	10/13/10	3,628.90	21.92	24.68	2.76	3,606.57
MW - 3	11/01/10	3,628.90	21.92	25.14	3.22	3,606.50
MW - 3	11/05/10	3,628.90	21.86	24.53	2.67	3,606.64
MW - 3	11/12/10	3,628.90	21.28	24.61	3.33	3,607.12
MW - 3	11/19/10	3,628.90	21.82	25.40	3.58	3,606.54
MW - 3	12/03/10	3,628.90	21.82	25.53	3.71	3,606.52
MW - 3	12/10/10	3,628.90	21.93	23.87	1.94	3,606.68
MW - 3	12/17/10	3,628.90	21.90	24.42	2.52	3,606.62
MW - 3	01/20/11	3,628.90	21.71	24.02	2.31	3,606.84
MW - 3	02/07/11	3,628.90	21.91	25.16	3.25	3,606.50
MW - 3	05/02/11	3,628.90	21.88	26.02	4.14	3,606.40
MW - 3	05/09/11	3,628.90	22.35	22.75	0.40	3,606.49

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	05/10/11	3,628.90	22.37	22.74	0.37	3,606.47
MW - 3	05/19/11	3,628.90	22.22	24.18	1.96	3,606.39
MW - 3	05/27/11	3,628.90	22.09	24.46	2.37	3,606.45
MW - 3	06/10/11	3,628.90	22.13	24.38	2.25	3,606.43
MW - 3	06/24/11	3,628.90	22.20	24.46	2.26	3,606.36
MW - 3	07/01/11	3,628.90	22.18	24.75	2.57	3,606.33
MW - 3	07/12/11	3,628.90	22.03	25.15	3.12	3,606.40
MW - 3	07/22/11	3,628.90	22.05	25.05	3.00	3,606.40
MW - 3	08/04/11	3,628.90	22.01	25.41	3.40	3,606.38
MW - 3	08/08/11	3,628.90	22.37	22.78	0.41	3,606.47
MW - 3	08/11/11	3,628.90	22.08	24.91	2.83	3,606.40
MW - 3	08/24/11	3,628.90	22.10	24.79	2.69	3,606.40
MW - 3	09/02/11	3,628.90	22.07	25.16	3.09	3,606.37
MW - 3	09/07/11	3,628.90	22.11	24.56	2.45	3,606.42
MW - 3	09/09/11	3,628.90	22.08	24.73	2.65	3,606.42
MW - 3	09/14/11	3,628.90	22.52	22.71	0.19	3,606.35
MW - 3	09/22/11	3,628.90	22.27	23.54	1.27	3,606.44
MW - 3	10/26/11	3,628.90	22.04	25.10	3.06	3,606.40
MW - 3	10/14/11	3,628.90	22.08	24.70	2.62	3,606.43
MW - 3	11/10/11	3,628.90	22.02	25.14	3.12	3,606.41
MW - 3	11/14/11	3,628.90	22.02	25.14	3.12	3,606.41
MW - 3	12/02/11	3,628.90	21.96	25.40	3.44	3,606.42
MW - 3	12/09/11	3,628.90	22.01	24.86	2.85	3,606.46
MW - 3	12/13/11	3,628.90	22.02	24.89	2.87	3,606.45
MW - 3	12/23/11	3,628.90	22.04	24.87	2.83	3,606.44
MW - 3	12/29/11	3,628.90	22.11	24.41	2.30	3,606.45
MW - 3	01/04/12	3,628.90	22.11	24.26	2.15	3,606.47
MW - 3	01/13/12	3,628.90	22.17	24.28	2.11	3,606.41
MW - 3	01/30/12	3,628.90	22.13	24.20	2.07	3,606.46
MW - 3	02/06/12	3,628.90	22.07	24.80	2.73	3,606.42
MW - 3	02/13/12	3,628.90	22.34	23.04	0.70	3,606.46
MW - 3	02/14/12	3,628.90	22.34	23.04	0.70	3,606.46
MW - 3	03/13/12	3,628.90	22.62	22.79	0.17	3,606.25
MW - 3	03/15/12	3,628.90	22.66	22.97	0.31	3,606.19
MW - 3	03/20/12	3,628.90	22.43	23.29	0.86	3,606.34
MW - 3	03/22/12	3,628.90	21.55	22.52	0.97	3,607.20
MW - 3	03/27/12	3,628.90	22.30	23.60	1.30	3,606.41
MW - 3	03/29/12	3,628.90	22.69	24.08	1.39	3,606.00
MW - 3	04/02/12	3,628.90	22.45	24.09	1.64	3,606.20

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	04/09/12	3,628.90	22.81	22.88	0.07	3,606.08
MW - 3	04/12/12	3,628.90	22.78	22.86	0.08	3,606.11
MW - 3	04/17/12	3,628.90	22.81	22.90	0.09	3,606.08
MW - 3	04/19/12	3,628.90	22.65	22.66	0.01	3,606.25
MW - 3	04/23/12	3,628.90	22.48	22.51	0.03	3,606.42
MW - 3	04/26/12	3,628.90	22.64	23.02	0.38	3,606.20
MW - 3	05/21/12	3,628.90	22.54	23.98	1.44	3,606.14
MW - 3	06/06/12	3,628.90	22.55	24.95	2.40	3,605.99
MW - 3	06/11/12	3,628.90	23.34	25.03	1.69	3,605.31
MW - 3	06/18/12	3,628.90	22.39	24.03	1.64	3,606.26
MW - 3	06/25/12	3,628.90	22.36	25.16	2.80	3,606.12
MW - 3	07/02/12	3,628.90	22.40	24.05	1.65	3,606.25
MW - 3	07/09/12	3,628.90	22.08	24.70	2.62	3,606.43
MW - 3	07/16/12	3,628.90	22.06	25.05	2.99	3,606.39
MW - 3	08/01/12	3,628.90	22.33	25.27	2.94	3,606.13
MW - 3	08/14/12	3,628.90	22.46	24.00	1.54	3,606.21
MW - 3	08/21/12	3,628.90	21.99	24.46	2.47	3,606.54
MW - 3	09/04/12	3,628.90	22.51	23.74	1.23	3,606.21
MW - 3	09/10/12	3,628.90	22.08	25.17	3.09	3,606.36
MW - 3	09/19/12	3,628.90	22.31	25.81	3.50	3,606.07
MW - 3	09/24/12	3,628.90	22.20	24.27	2.07	3,606.39
MW - 3	10/01/12	3,628.90	22.20	24.30	2.10	3,606.39
MW - 3	10/08/12	3,628.90	22.20	24.25	2.05	3,606.39
MW - 3	10/10/12	3,628.90	21.31	23.60	2.29	3,607.25
MW - 3	10/15/12	3,628.90	22.23	24.03	1.80	3,606.40
MW - 3	10/22/12	3,628.90	22.21	24.11	1.90	3,606.41
MW - 3	10/24/12	3,628.90	22.25	23.68	1.43	3,606.44
MW - 3	10/29/12	3,628.90	22.49	23.38	0.89	3,606.28
MW - 3	11/06/12	3,628.90	22.59	23.40	0.81	3,606.19
MW - 3	12/04/12	3,628.90	22.41	23.71	1.30	3,606.30
MW - 3	12/10/12	3,628.90	22.36	23.31	0.95	3,606.40
MW - 3	12/17/12	3,628.90	22.55	22.78	0.23	3,606.32
MW - 3	12/27/12	3,628.90	22.31	23.77	1.46	3,606.37
MW - 3	01/14/13	3,628.90	22.41	22.44	0.03	3,606.49
MW - 3	02/04/13	3,628.90	22.11	24.94	2.83	3,606.37
MW - 3	02/05/13	3,628.90	22.11	24.97	2.86	3,606.36
MW - 3	02/20/13	3,628.90	22.01	25.14	3.13	3,606.42
MW - 3	03/04/13	3,628.90	23.43	24.21	0.78	3,605.35
MW - 3	03/26/13	3,628.90	22.71	24.60	1.89	3,605.91

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 3	04/10/13	3,628.90	22.33	24.52	2.19	3,606.24
MW - 3	04/17/13	3,628.90	22.41	24.39	1.98	3,606.19
MW - 3	04/24/13	3,628.90	22.72	25.47	2.75	3,605.77
MW - 3	05/02/13	3,628.90	22.37	23.46	1.09	3,606.37
MW - 3	05/09/13	3,628.90	22.56	22.82	0.26	3,606.30
MW - 3	05/17/13	3,628.90	22.42	22.97	0.55	3,606.40
MW - 3	05/22/13	3,628.90	22.52	22.65	0.13	3,606.36
MW - 3	05/29/13	3,628.90	22.62	23.15	0.53	3,606.20
MW - 3	06/03/13	3,628.90	22.42	22.89	0.47	3,606.41
MW - 3	06/20/13	3,628.90	22.51	22.78	0.27	3,606.35
MW - 3	06/25/13	3,628.90	22.67	23.19	0.52	3,606.15
MW - 3	07/02/13	3,628.90	22.42	23.09	0.67	3,606.38
MW - 3	07/09/13	3,628.90	22.57	23.51	0.94	3,606.19
MW - 3	07/16/13	3,628.90	22.54	23.99	1.45	3,606.14
MW - 3	07/24/13	3,628.90	22.56	23.97	1.41	3,606.13
MW - 3	07/31/13	3,628.90	22.55	23.96	1.41	3,606.14
MW - 3	08/01/13	3,628.90	22.48	24.11	1.63	3,606.18
MW - 3	08/06/13	3,628.90	22.14	24.29	2.15	3,606.44
MW - 3	08/07/13	3,628.90	22.43	23.37	0.94	3,606.33
MW - 3	08/16/13	3,628.90	22.33	23.93	1.60	3,606.33
MW - 3	09/12/13	3,628.90	22.45	22.47	0.02	3,606.45
MW - 3	09/25/13	3,628.90	22.43	22.46	0.03	3,606.47
MW - 3	09/30/13	3,628.90	22.40	22.75	0.35	3,606.45
MW - 3	10/09/13	3,628.90	22.45	22.51	0.06	3,606.44
MW - 3	10/14/13	3,628.90	22.46	22.48	0.02	3,606.44
MW - 3	10/22/13	3,628.90	22.42	22.77	0.35	3,606.43
MW - 3	10/30/13	3,628.90	22.32	23.33	1.01	3,606.43
MW - 3	11/07/13	3,628.90	22.43	22.51	0.08	3,606.46
MW - 3	11/27/13	3,628.90	22.25	23.68	1.43	3,606.44
MW - 3	12/04/13	3,628.90	22.41	22.42	0.01	3,606.49
MW - 3	12/10/13	3,628.90	22.36	23.05	0.69	3,606.44
MW - 3	12/16/13	3,628.90	22.33	23.43	1.10	3,606.41
MW - 3	12/24/13	3,628.90	22.45	22.48	0.03	3,606.45
MW - 4	03/06/00	3,629.97	-	20.48	0.00	3,609.49
MW - 4	05/16/00	3,629.97	-	20.51	0.00	3,609.46
MW - 4	08/31/00	3,629.97	-	20.51	0.00	3,609.46
MW - 4	11/17/00	3,629.97	-	20.48	0.00	3,609.49
MW - 4	03/07/01	3,629.97	-	20.44	0.00	3,609.53

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 4	05/30/01	3,629.97	-	20.47	0.00	3,609.50
MW - 4	08/27/01	3,629.97	-	20.51	0.00	3,609.46
MW - 4	10/12/01	3,629.97	-	20.48	0.00	3,609.49
MW - 4	02/28/02	3,629.97	-	20.45	0.00	3,609.52
MW - 4	05/13/02	3,629.97	-	20.50	0.00	3,609.47
MW - 4	09/10/02	3,629.97	-	20.56	0.00	3,609.41
MW - 4	11/15/02	3,629.97	-	20.48	0.00	3,609.49
MW - 4	05/13/03	3,629.97	-	20.49	0.00	3,609.48
MW - 4	08/22/03	3,629.97	-	20.59	0.00	3,609.38
MW - 4	12/15/03	3,629.97	-	20.50	0.00	3,609.47
MW - 4	03/04/04	3,629.97	-	20.51	0.00	3,609.46
MW - 4	05/25/04	3,629.97	-	20.45	0.00	3,609.52
MW - 4	08/31/04	3,629.97	-	20.55	0.00	3,609.42
MW - 4	12/10/04	3,629.97	-	19.68	0.00	3,610.29
MW - 4	03/14/05	3,629.97	-	20.14	0.00	3,609.83
MW - 4	06/13/05	3,629.97	-	20.22	0.00	3,609.75
MW - 4	09/12/05	3,629.97	-	20.28	0.00	3,609.69
MW - 4	12/06/05	3,629.97	-	20.29	0.00	3,609.68
MW - 4	03/10/06	3,629.97	-	20.34	0.00	3,609.63
MW - 4	06/09/06	3,629.97	-	20.41	0.00	3,609.56
MW - 4	07/05/06	3,629.97	-	21.13	0.00	3,608.84
MW - 4	09/12/06	3,629.97	-	19.51	0.00	3,610.46
MW - 4	11/28/06	3,629.97	-	20.03	0.00	3,609.94
MW - 4	02/22/07	3,629.97	-	20.26	0.00	3,609.71
MW - 4	05/17/07	3,629.97	-	20.29	0.00	3,609.68
MW - 4	08/21/07	3,629.97	-	20.36	0.00	3,609.61
MW - 4	11/26/07	3,629.97	-	20.35	0.00	3,609.62
MW - 4	02/26/08	3,629.97	-	20.38	0.00	3,609.59
MW - 4	05/26/08	3,629.97	-	20.41	0.00	3,609.56
MW - 4	08/28/08	3,629.97	-	20.41	0.00	3,609.56
MW - 4	11/19/08	3,629.97	-	21.45	0.00	3,608.52
MW - 4	02/13/09	3,629.97	-	20.39	0.00	3,609.58
MW - 4	05/20/09	3,629.97	-	20.43	0.00	3,609.54
MW - 4	06/04/09	3,629.97	-	31.27	0.00	3,598.70
MW - 4	08/15/09	3,629.97	-	20.39	0.00	3,609.58
MW - 4	11/06/09	3,629.97	-	20.38	0.00	3,609.59
MW - 4	01/12/10	3,629.97	-	20.39	0.00	3,609.58
MW - 4	02/05/10	3,629.97	-	20.39	0.00	3,609.58
MW - 4	05/03/10	3,629.97	-	20.38	0.00	3,609.59

TABLE 1
GROUNDWATER ELEVATION DATA
PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 4	08/02/10	3,629.97	-	20.40	0.00	3,609.57
MW - 4	11/01/10	3,629.97	-	20.27	0.00	3,609.70
MW - 4	02/07/11	3,629.97	-	20.29	0.00	3,609.68
MW - 4	05/02/11	3,629.97	-	20.38	0.00	3,609.59
MW - 4	05/09/11	3,629.97	-	20.37	0.00	3,609.60
MW - 4	05/10/11	3,629.97	-	20.37	0.00	3,609.60
MW - 4	08/08/11	3,629.97	-	20.31	0.00	3,609.66
MW - 4	09/14/11	3,629.97	-	20.43	0.00	3,609.54
MW - 4	11/10/11	3,629.97	-	20.39	0.00	3,609.58
MW - 4	02/06/12	3,629.97	-	20.41	0.00	3,609.56
MW - 4	05/21/12	3,629.97	-	20.44	0.00	3,609.53
MW - 4	08/01/12	3,629.97	-	20.45	0.00	3,609.52
MW - 4	11/06/12	3,629.97	-	20.44	0.00	3,609.53
MW - 4	02/05/13	3,629.97	-	20.44	0.00	3,609.53
MW - 4	05/09/13	3,629.97	-	20.46	0.00	3,609.51
MW - 4	08/01/13	3,629.97	-	20.39	0.00	3,609.58
MW - 4	11/07/13	3,629.97	-	20.41	0.00	3,609.56
MW - 5	03/06/00	3,629.36	-	21.61	0.00	3,607.75
MW - 5	05/16/00	3,629.36	-	21.70	0.00	3,607.66
MW - 5	08/31/00	3,629.36	-	21.70	0.00	3,607.66
MW - 5	11/17/00	3,629.36	-	21.69	0.00	3,607.67
MW - 5	03/07/01	3,629.36	-	21.63	0.00	3,607.73
MW - 5	05/30/01	3,629.36	-	21.65	0.00	3,607.71
MW - 5	08/27/01	3,629.36	-	21.70	0.00	3,607.66
MW - 5	10/12/01	3,629.36	-	21.65	0.00	3,607.71
MW - 5	02/25/02	3,629.36	-	21.65	0.00	3,607.71
MW - 5	05/13/02	3,629.36	-	21.66	0.00	3,607.70
MW - 5	09/10/02	3,629.36	-	21.74	0.00	3,607.62
MW - 5	11/15/02	3,629.36	-	21.66	0.00	3,607.70
MW - 5	05/13/03	3,629.36	-	21.67	0.00	3,607.69
MW - 5	08/22/03	3,629.36	-	21.74	0.00	3,607.62
MW - 5	12/15/03	3,629.36	-	21.67	0.00	3,607.69
MW - 5	03/04/04	3,629.36	-	21.68	0.00	3,607.68
MW - 5	05/25/04	3,629.36	-	21.64	0.00	3,607.72
MW - 5	08/31/04	3,629.36	-	21.75	0.00	3,607.61
MW - 5	12/10/04	3,629.36	-	20.90	0.00	3,608.46
MW - 5	03/14/05	3,629.36	-	21.35	0.00	3,608.01
MW - 5	06/13/05	3,629.36	-	21.45	0.00	3,607.91

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 5	09/12/05	3,629.36	-	21.50	0.00	3,607.86
MW - 5	12/06/05	3,629.36	-	21.52	0.00	3,607.84
MW - 5	03/10/06	3,629.36	-	21.58	0.00	3,607.78
MW - 5	06/09/06	3,629.36	-	21.63	0.00	3,607.73
MW - 5	07/05/06	3,629.36	-	21.66	0.00	3,607.70
MW - 5	09/12/06	3,629.36	-	20.74	0.00	3,608.62
MW - 5	11/28/06	3,629.36	-	21.29	0.00	3,608.07
MW - 5	02/22/07	3,629.36	-	21.52	0.00	3,607.84
MW - 5	05/17/07	3,629.36	-	21.52	0.00	3,607.84
MW - 5	08/21/07	3,629.36	-	21.58	0.00	3,607.78
MW - 5	11/26/07	3,629.36	-	21.58	0.00	3,607.78
MW - 5	02/26/08	3,629.36	-	21.60	0.00	3,607.76
MW - 5	05/26/08	3,629.36	-	21.62	0.00	3,607.74
MW - 5	08/28/08	3,629.36	-	21.61	0.00	3,607.75
MW - 5	11/19/08	3,629.36	-	21.54	0.00	3,607.82
MW - 5	02/13/09	3,629.36	-	21.62	0.00	3,607.74
MW - 5	05/20/09	3,629.36	-	21.62	0.00	3,607.74
MW - 5	08/15/09	3,629.36	-	21.63	0.00	3,607.73
MW - 5	01/12/10	3,629.36	-	21.62	0.00	3,607.74
MW - 5	02/05/10	3,629.36	-	21.62	0.00	3,607.74
MW - 5	05/03/10	3,629.36	-	21.62	0.00	3,607.74
MW - 5	08/02/10	3,629.36	-	21.63	0.00	3,607.73
MW - 5	11/01/10	3,629.36	-	21.53	0.00	3,607.83
MW - 5	02/07/11	3,629.36	-	21.53	0.00	3,607.83
MW - 5	05/02/11	3,629.36	-	21.58	0.00	3,607.78
MW - 5	05/09/11	3,629.36	-	21.62	0.00	3,607.74
MW - 5	05/10/11	3,629.36	-	21.62	0.00	3,607.74
MW - 5	08/08/11	3,629.36	-	21.58	0.00	3,607.78
MW - 5	09/14/11	3,629.36	-	21.71	0.00	3,607.65
MW - 5	11/10/11	3,629.36	-	21.60	0.00	3,607.76
MW - 5	02/06/12	3,629.36	-	21.62	0.00	3,607.74
MW - 5	05/21/12	3,629.36	-	21.65	0.00	3,607.71
MW - 5	08/01/12	3,629.36	-	21.66	0.00	3,607.70
MW - 5	11/06/12	3,629.36	-	21.65	0.00	3,607.71
MW - 5	02/05/13	3,629.36	-	21.64	0.00	3,607.72
MW - 5	05/09/13	3,629.36	-	21.67	0.00	3,607.69
MW - 5	08/01/13	3,629.36	-	21.58	0.00	3,607.78
MW - 5	11/07/13	3,629.36	-	21.63	0.00	3,607.73

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 6	03/06/00	3,629.87	-	23.45	0.00	3,606.42
MW - 6	05/16/00	3,629.87	-	23.45	0.00	3,606.42
MW - 6	08/31/00	3,629.87	-	23.47	0.00	3,606.40
MW - 6	11/17/00	3,629.87	-	23.46	0.00	3,606.41
MW - 6	03/07/01	3,629.87	-	23.42	0.00	3,606.45
MW - 6	05/30/01	3,629.87	-	23.38	0.00	3,606.49
MW - 6	08/27/01	3,629.87*	-	-	-	-
MW - 6	10/12/01	3,629.17**	-	23.40	0.00	3,605.77
MW - 6	02/25/02	3,629.17	-	24.10	0.00	3,605.07
MW - 6	05/13/02	3,629.17	-	24.12	0.00	3,605.05
MW - 6	09/10/02	3,629.17	-	24.16	0.00	3,605.01
MW - 6	11/15/02	3,629.17	-	24.12	0.00	3,605.05
MW - 6	05/13/03	3,629.17	-	24.13	0.00	3,605.04
MW - 6	08/22/03	3,629.17	-	24.19	0.00	3,604.98
MW - 6	12/15/03	3,629.17	-	24.14	0.00	3,605.03
MW - 6	03/04/04	3,629.17	-	24.14	0.00	3,605.03
MW - 6	05/25/04	3,629.17	-	24.12	0.00	3,605.05
MW - 6	08/31/04	3,629.17	-	24.16	0.00	3,605.01
MW - 6	12/10/04	3,629.17	-	23.42	0.00	3,605.75
MW - 6	03/14/05	3,629.17	-	23.93	0.00	3,605.24
MW - 6	06/13/05	3,629.17	-	23.98	0.00	3,605.19
MW - 6	09/12/05	3,629.17	-	24.03	0.00	3,605.14
MW - 6	12/06/05	3,629.17	-	24.23	0.00	3,604.94
MW - 6	03/10/06	3,629.17	-	24.07	0.00	3,605.10
MW - 6	06/09/06	3,629.17	-	24.09	0.00	3,605.08
MW - 6	07/05/06	3,629.17	-	25.36	0.00	3,603.81
MW - 6	09/12/06	3,629.17	-	23.25	0.00	3,605.92
MW - 6	11/28/06	3,629.17	-	23.85	0.00	3,605.32
MW - 6	02/22/07	3,629.17	-	24.02	0.00	3,605.15
MW - 6	05/17/07	3,629.17	-	24.03	0.00	3,605.14
MW - 6	08/21/07	3,629.17	-	24.07	0.00	3,605.10
MW - 6	11/26/07	3,629.17	-	24.07	0.00	3,605.10
MW - 6	02/26/08	3,629.17	-	24.10	0.00	3,605.07
MW - 6	05/26/08	3,629.17	-	24.11	0.00	3,605.06
MW - 6	08/28/08	3,629.17	-	24.12	0.00	3,605.05
MW - 6	11/19/08	3,629.17	-	24.11	0.00	3,605.06
MW - 6	02/13/09	3,629.17	-	24.11	0.00	3,605.06
MW - 6	05/20/09	3,629.17	-	24.14	0.00	3,605.03
MW - 6	08/15/09	3,629.17	-	24.13	0.00	3,605.04

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 6	11/06/09	3,629.17	-	24.13	0.00	3,605.04
MW - 6	01/12/10	3,629.17	-	24.00	0.00	3,605.17
MW - 6	02/05/10	3,629.17	-	24.13	0.00	3,605.04
MW - 6	05/03/10	3,629.17	-	24.14	0.00	3,605.03
MW - 6	08/02/10	3,629.17	-	24.14	0.00	3,605.03
MW - 6	11/01/10	3,629.17	-	24.04	0.00	3,605.13
MW - 6	02/07/11	3,629.17	-	24.06	0.00	3,605.11
MW - 6	05/02/11	3,629.17	-	24.12	0.00	3,605.05
MW - 6	05/09/11	3,629.17	-	24.15	0.00	3,605.02
MW - 6	05/10/11	3,629.17	-	24.15	0.00	3,605.02
MW - 6	08/08/11	3,629.17	-	24.13	0.00	3,605.04
MW - 6	09/14/11	3,629.17	-	24.24	0.00	3,604.93
MW - 6	11/10/11	3,629.17	-	24.11	0.00	3,605.06
MW - 6	02/06/12	3,629.17	-	24.12	0.00	3,605.05
MW - 6	05/21/12	3,629.17	-	24.15	0.00	3,605.02
MW - 6	08/01/12	3,629.17	-	24.14	0.00	3,605.03
MW - 6	11/06/12	3,629.17	-	24.13	0.00	3,605.04
MW - 6	02/05/13	3,629.17	-	24.13	0.00	3,605.04
MW - 6	05/09/13	3,629.17	-	24.14	0.00	3,605.03
MW - 6	08/01/13	3,629.17	-	24.11	0.00	3,605.06
MW - 6	11/07/13	3,629.17	-	24.13	0.00	3,605.04
MW - 7	08/31/00	3,628.07	-	22.86	0.00	3,605.21
MW - 7	11/17/00	3,628.07	-	22.85	0.00	3,605.22
MW - 7	03/07/01	3,628.07	-	22.80	0.00	3,605.27
MW - 7	05/30/01	3,628.07	-	22.80	0.00	3,605.27
MW - 7	08/27/01	3,628.07	-	22.84	0.00	3,605.23
MW - 7	10/12/01	3,628.07	-	22.80	0.00	3,605.27
MW - 7	02/25/02	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/13/02	3,628.07	-	22.83	0.00	3,605.24
MW - 7	09/10/02	3,628.07	-	22.88	0.00	3,605.19
MW - 7	11/15/02	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/13/03	3,628.07	-	22.85	0.00	3,605.22
MW - 7	08/22/03	3,628.07	-	22.88	0.00	3,605.19
MW - 7	12/15/03	3,628.07	-	22.86	0.00	3,605.21
MW - 7	03/04/04	3,628.07	-	22.85	0.00	3,605.22
MW - 7	05/25/04	3,628.07	-	22.80	0.00	3,605.27
MW - 7	08/31/04	3,628.07	-	22.90	0.00	3,605.17
MW - 7	12/10/04	3,628.07	-	21.91	0.00	3606.16

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 7	03/14/05	3,628.07	-	22.60	0.00	3,605.47
MW - 7	06/13/05	3,628.07	-	22.69	0.00	3,605.38
MW - 7	09/12/05	3,628.07	-	22.73	0.00	3,605.34
MW - 7	12/06/05	3,628.07	-	22.74	0.00	3,605.33
MW - 7	03/10/06	3,628.07	-	22.77	0.00	3,605.30
MW - 7	06/09/06	3,628.07	-	22.81	0.00	3,605.26
MW - 7	07/05/06	3,628.07	-	22.82	0.00	3,605.25
MW - 7	09/12/06	3,628.07	-	21.81	0.00	3,606.26
MW - 7	11/28/06	3,628.07	-	22.55	0.00	3,605.52
MW - 7	02/22/07	3,628.07	-	22.74	0.00	3,605.33
MW - 7	05/17/07	3,628.07	-	22.72	0.00	3,605.35
MW - 7	08/21/07	3,628.07	-	22.77	0.00	3,605.30
MW - 7	11/26/07	3,628.07	-	22.78	0.00	3,605.29
MW - 7	02/26/08	3,628.07	-	22.79	0.00	3,605.28
MW - 7	05/26/08	3,628.07	-	22.82	0.00	3,605.25
MW - 7	11/19/08	3,628.07	-	22.82	0.00	3,605.25
MW - 7	02/13/09	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/20/09	3,628.07	-	22.84	0.00	3,605.23
MW - 7	08/15/09	3,628.07	-	22.82	0.00	3,605.25
MW - 7	11/06/09	3,628.07	-	22.83	0.00	3,605.24
MW - 7	01/12/10	3,628.07	-	22.81	0.00	3,605.26
MW - 7	02/05/10	3,628.07	-	22.81	0.00	3,605.26
MW - 7	05/03/10	3,628.07	-	23.82	0.00	3,604.25
MW - 7	08/02/10	3,628.07	-	23.84	0.00	3,604.23
MW - 7	11/01/10	3,628.07	-	22.76	0.00	3,605.31
MW - 7	12/17/10	3,628.07	-	19.22	0.00	3,608.85
MW - 7	02/07/11	3,628.07	-	22.76	0.00	3,605.31
MW - 7	05/02/11	3,628.07	-	22.81	0.00	3,605.26
MW - 7	05/09/11	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/10/11	3,628.07	-	22.83	0.00	3,605.24
MW - 7	08/08/11	3,628.07	-	22.87	0.00	3,605.20
MW - 7	09/14/11	3,628.07	-	22.90	0.00	3,605.17
MW - 7	11/10/11	3,628.07	-	22.83	0.00	3,605.24
MW - 7	02/06/12	3,628.07	-	22.81	0.00	3,605.26
MW - 7	05/21/12	3,628.07	-	22.83	0.00	3,605.24
MW - 7	08/01/12	3,628.07	-	22.84	0.00	3,605.23
MW - 7	11/06/12	3,628.07	-	22.83	0.00	3,605.24
MW - 7	02/05/13	3,628.07	-	22.83	0.00	3,605.24
MW - 7	05/09/13	3,628.07	-	22.85	0.00	3,605.22

TABLE 1
GROUNDWATER ELEVATION DATA

PLAIN MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

WELL NUMBER	DATE MEASURED	TOP OF CASING ELEVATION	DEPTH TO PRODUCT	DEPTH TO WATER	PSH THICKNESS	CORRECTED GROUND WATER ELEVATION
MW - 7	08/01/13	3,628.07	-	22.83	0.00	3,605.24
MW - 7	11/07/13	3,628.07	-	22.82	0.00	3,605.25

*Well damaged, not gauged or sampled this event.

**Denotes change in TOC elevation due to wellhead repairs.

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 1	5/2/1997	ND	ND	ND	ND	
MW - 1	8/15/1997	0.0020	ND	ND	ND	
MW - 1	11/1/1997	0.0080	ND	0.002	0.0070	
MW - 1	2/19/1998	0.0090	ND	ND	0.0030	
MW - 1	01/23/99	0.0100	<0.001	<0.001	<0.002	<0.001
MW - 1	05/20/99	0.0080	<0.001	<0.001	<0.002	<0.001
MW - 1	09/07/99	0.0030	0.0020	<0.001	0.0010	0.002
MW - 1	12/10/99	0.0020	0.0010	<0.001	0.0010	<0.001
MW - 1	03/06/00	<0.001	0.0020	<0.001	0.0010	<0.001
MW - 1	05/16/00	<0.001	0.0020	0.001	<0.001	<0.001
MW - 1	08/31/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	11/17/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	03/07/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	05/30/01	0.0080	<0.005	0.015	<0.005	
MW - 1	08/27/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	10/12/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	02/25/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	05/13/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	09/10/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	11/15/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	02/11/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	05/13/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	08/22/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 1	12/15/03	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 1	03/04/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 1	08/31/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 1	12/10/04	0.0126	<0.005	0.008	0.0320	
MW - 1	03/14/05	Not Sampled on Current Sample Schedule				
MW - 1	06/13/05	Not Sampled on Current Sample Schedule				
MW - 1	09/12/05	Not Sampled on Current Sample Schedule				
MW - 1	12/06/05	<0.005	<0.005	<0.005	<0.005	
MW - 1	03/10/06	Not Sampled on Current Sample Schedule				
MW - 1	06/09/06	Not Sampled on Current Sample Schedule				
MW - 1	09/12/06	Not Sampled on Current Sample Schedule				
MW - 1	11/28/06	<0.001	<0.001	0.0031	0.0341	
MW - 1	02/22/07	Not Sampled on Current Sample Schedule				
MW - 1	05/17/07	Not Sampled on Current Sample Schedule				
MW - 1	08/21/07	<0.001	<0.001	<0.001	<0.001	
MW - 1	11/26/07	<0.001	<0.001	<0.001	0.0052	
MW - 1	02/26/08	Not Sampled on Current Sample Schedule				
MW - 1	05/26/08	<0.005	<0.005	<0.005	<0.005	

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 1	08/28/08	0.0022	0.0011	<0.00100	0.0041	
MW - 1	11/19/08	<0.001	<0.001	<0.001	0.0061	
MW - 1	02/13/09	<0.001	<0.001	<0.001	<0.001	
MW - 1	05/20/09	Not Sampled on Current Sample Schedule				
MW - 1	08/15/09	Not Sampled on Current Sample Schedule				
MW - 1	11/06/09	0.0035	<0.001	<0.001	<0.001	
MW - 1	02/05/10	Not Sampled on Current Sample Schedule				
MW - 1	05/03/10	Not Sampled on Current Sample Schedule				
MW - 1	08/02/10	Not Sampled on Current Sample Schedule				
MW - 1	11/01/10	Not sampled Due to PSH in Well				
MW - 1	02/07/11	Not sampled Due to PSH in Well				
MW - 1	05/10/11	Not sampled Due to PSH in Well				
MW - 1	08/08/11	Not sampled Due to PSH in Well				
MW - 1	11/10/11	Not sampled Due to PSH in Well				
MW - 1	02/16/12	Not Sampled on Current Sample Schedule				
MW - 1	05/12/12	Not Sampled on Current Sample Schedule				
MW - 1	08/01/12	Not Sampled on Current Sample Schedule				
MW - 1	11/06/12	<0.005	<0.005	<0.005	<0.005	
MW - 1	02/05/13	<0.005	<0.005	<0.005	<0.005	
MW - 1	05/09/13	<0.001	<0.001	<0.001	<0.001	
MW - 1	08/01/13	<0.001	<0.001	<0.001	0.0039	
MW - 1	11/07/13	0.0031	<0.001	<0.001	<0.00300	
MW - 2	03/14/05	Not sampled Due to PSH in Well				
MW - 2	06/13/05	Not sampled Due to PSH in Well				
MW - 2	09/12/05	Not sampled Due to PSH in Well				
MW - 2	12/06/05	Not sampled Due to PSH in Well				
MW - 2	03/10/06	Not sampled Due to PSH in Well				
MW - 2	06/09/06	Not sampled Due to PSH in Well				
MW - 2	09/12/06	Not sampled Due to PSH in Well				
MW - 2	11/28/06	Not sampled Due to PSH in Well				
MW - 2	02/22/07	Not sampled Due to PSH in Well				
MW - 2	05/17/07	Not sampled Due to PSH in Well				
MW - 2	08/21/07	Not sampled Due to PSH in Well				
MW - 2	11/26/07	Not sampled Due to PSH in Well				
MW - 2	02/26/08	Not sampled Due to PSH in Well				
MW - 2	05/26/08	Not sampled Due to PSH in Well				
MW - 2	08/28/08	Not sampled Due to PSH in Well				
MW - 2	11/19/08	0.5710	0.4380	0.044	0.2110	
MW - 2	02/13/09	Not sampled Due to PSH in Well				
MW - 2	05/20/09	Not sampled Due to PSH in Well				

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 2	08/15/09	Not sampled Due to PSH in Well				
MW - 2	11/06/09	0.0201	<0.02	<0.02	0.0584	
MW - 2	02/05/10	Not sampled Due to PSH in Well				
MW - 2	05/03/10	Not sampled Due to PSH in Well				
MW - 2	08/02/10	Not sampled Due to PSH in Well				
MW - 2	11/01/10	Not sampled Due to PSH in Well				
MW - 2	02/07/11	Not sampled Due to PSH in Well				
MW - 2	05/10/11	Not sampled Due to PSH in Well				
MW - 2	08/08/11	Not sampled Due to PSH in Well				
MW - 2	11/10/11	Not sampled Due to PSH in Well				
MW - 2	02/16/12	Not sampled Due to PSH in Well				
MW - 2	05/12/12	Not sampled Due to PSH in Well				
MW - 2	08/01/12	Not sampled Due to PSH in Well				
MW - 2	11/06/12	Not sampled Due to PSH in Well				
MW - 2	02/05/13	Not sampled Due to PSH in Well				
MW - 2	05/09/13	Not sampled Due to PSH in Well				
MW - 2	08/01/13	Not sampled Due to PSH in Well				
MW - 2	11/07/13	Not sampled Due to PSH in Well				
MW - 3	03/14/05	Not sampled Due to PSH in Well				
MW - 3	06/13/05	Not sampled Due to PSH in Well				
MW - 3	09/12/05	Not sampled Due to PSH in Well				
MW - 3	12/06/05	Not sampled Due to PSH in Well				
MW - 3	03/10/06	Not sampled Due to PSH in Well				
MW - 3	06/09/06	Not sampled Due to PSH in Well				
MW - 3	09/12/06	Not sampled Due to PSH in Well				
MW - 3	11/28/06	Not sampled Due to PSH in Well				
MW - 3	02/22/07	Not sampled Due to PSH in Well				
MW - 3	05/17/07	Not sampled Due to PSH in Well				
MW - 3	08/21/07	Not sampled Due to PSH in Well				
MW - 3	11/26/07	Not sampled Due to PSH in Well				
MW - 3	02/26/08	Not sampled Due to PSH in Well				
MW - 3	05/26/08	Not sampled Due to PSH in Well				
MW - 3	08/28/08	Not sampled Due to PSH in Well				
MW - 3	11/19/08	2.4100	1.7400	0.215	0.6940	
MW - 3	02/13/09	Not sampled Due to PSH in Well				
MW - 3	05/20/09	Not sampled Due to PSH in Well				
MW - 3	08/15/09	Not sampled Due to PSH in Well				
MW - 3	11/06/09	0.0594	<0.05	<0.05	0.0604	
MW - 3	02/05/10	Not sampled Due to PSH in Well				
MW - 3	05/03/10	Not sampled Due to PSH in Well				

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 3	08/02/10	Not sampled Due to PSH in Well				
MW - 3	11/01/10	Not sampled Due to PSH in Well				
MW - 3	02/07/11	Not sampled Due to PSH in Well				
MW - 3	05/10/11	Not sampled Due to PSH in Well				
MW - 3	08/08/11	Not sampled Due to PSH in Well				
MW - 3	11/10/11	Not sampled Due to PSH in Well				
MW - 3	02/16/12	Not sampled Due to PSH in Well				
MW - 3	05/12/12	Not sampled Due to PSH in Well				
MW - 3	08/01/12	Not sampled Due to PSH in Well				
MW - 3	11/06/12	Not sampled Due to PSH in Well				
MW - 3	02/05/13	Not sampled Due to PSH in Well				
MW - 3	05/09/13	Not sampled Due to PSH in Well				
MW - 3	08/01/13	Not sampled Due to PSH in Well				
MW - 3	11/07/13	Not sampled Due to PSH in Well				
MW - 4	02/19/98	ND	ND	ND	ND	
MW - 4	01/23/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 4	05/20/99	<0.001	<0.001	<0.002	<0.001	<0.002
MW - 4	09/07/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	12/10/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	03/06/00	<0.001	<0.001	<0.001	0.0010	<0.001
MW - 4	05/16/00	<0.001	0.0020	0.001	0.0010	<0.001
MW - 4	08/31/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	11/17/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	03/07/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	05/30/01	0.0067	<0.005	<0.005	<0.005	
MW - 4	08/27/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	10/12/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	02/25/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	05/13/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	09/10/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	11/15/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	02/11/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	05/13/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	08/22/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 4	12/15/03	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 4	03/04/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 4	12/10/04	<0.001	<0.001	<0.001	<0.001	
MW - 4	03/14/05	Not Sampled on Current Sample Schedule				
MW - 4	06/13/05	Not Sampled on Current Sample Schedule				
MW - 4	09/12/05	Not Sampled on Current Sample Schedule				

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 4	12/06/05	<0.001	<0.001	<0.001	<0.001	
MW - 4	03/10/06	Not Sampled on Current Sample Schedule				
MW - 4	06/09/06	Not Sampled on Current Sample Schedule				
MW - 4	09/12/06	Not Sampled on Current Sample Schedule				
MW - 4	11/28/06	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/22/07	Not Sampled on Current Sample Schedule				
MW - 4	05/17/07	Not Sampled on Current Sample Schedule				
MW - 4	08/21/07	Not Sampled on Current Sample Schedule				
MW - 4	11/26/07	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/26/08	Not Sampled on Current Sample Schedule				
MW - 4	05/26/08	Not Sampled on Current Sample Schedule				
MW - 4	08/28/08	Not Sampled on Current Sample Schedule				
MW - 4	11/19/08	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/13/09	Not Sampled on Current Sample Schedule				
MW - 4	05/20/09	Not Sampled on Current Sample Schedule				
MW - 4	08/15/09	Not Sampled on Current Sample Schedule				
MW - 4	11/06/09	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/05/10	Not Sampled on Current Sample Schedule				
MW - 4	05/03/10	Not Sampled on Current Sample Schedule				
MW - 4	08/02/10	Not Sampled on Current Sample Schedule				
MW - 4	11/01/10	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/07/11	Not Sampled on Current Sample Schedule				
MW - 4	05/10/11	Not Sampled on Current Sample Schedule				
MW - 4	08/08/11	Not Sampled on Current Sample Schedule				
MW - 4	11/10/11	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/16/12	Not Sampled on Current Sample Schedule				
MW - 4	05/12/12	Not Sampled on Current Sample Schedule				
MW - 4	08/01/12	Not Sampled on Current Sample Schedule				
MW - 4	11/06/12	<0.001	<0.001	<0.001	<0.001	
MW - 4	02/05/13	Not Sampled on Current Sample Schedule				
MW - 4	05/09/13	Not Sampled on Current Sample Schedule				
MW - 4	08/01/13	Not Sampled on Current Sample Schedule				
MW - 4	11/07/13	<0.001	<0.001	<0.001	<0.00300	
MW - 5	02/19/98	ND	ND	ND	ND	
MW - 5	01/23/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	05/20/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	09/07/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	12/10/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	03/06/00	<0.001	<0.001	<0.001	0.0010	<0.001
MW - 5	05/16/00	<0.001	<0.001	<0.001	<0.001	<0.001

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 5	08/31/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	11/17/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	03/07/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	05/30/01	0.0067	<0.005	<0.005	<0.005	
MW - 5	08/27/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	10/12/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	02/25/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	05/13/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	09/10/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	11/15/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	02/11/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	05/13/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	08/22/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 5	12/15/03	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	03/04/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	05/25/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	08/31/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 5	12/10/04	<0.001	<0.001	<0.001	<0.001	
MW - 5	03/14/05	<0.001	<0.001	<0.001	<0.001	
MW - 5	06/13/05	<0.001	<0.001	<0.001	<0.001	
MW - 5	09/12/05	Not Sampled on Current Sample Schedule				
MW - 5	12/06/05	<0.001	<0.001	<0.001	<0.001	
MW - 5	03/10/06	Not Sampled on Current Sample Schedule				
MW - 5	06/09/06	Not Sampled on Current Sample Schedule				
MW - 5	09/12/06	Not Sampled on Current Sample Schedule				
MW - 5	11/28/06	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/22/07	Not Sampled on Current Sample Schedule				
MW - 5	05/17/07	Not Sampled on Current Sample Schedule				
MW - 5	08/21/07	Not Sampled on Current Sample Schedule				
MW - 5	11/26/07	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/26/08	Not Sampled on Current Sample Schedule				
MW - 5	05/26/08	Not Sampled on Current Sample Schedule				
MW - 5	08/28/08	Not Sampled on Current Sample Schedule				
MW - 5	11/19/08	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/13/09	Not Sampled on Current Sample Schedule				
MW - 5	05/20/09	Not Sampled on Current Sample Schedule				
MW - 5	08/15/09	Not Sampled on Current Sample Schedule				
MW - 5	11/06/09	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/05/10	Not Sampled on Current Sample Schedule				
MW - 5	05/03/10	Not Sampled on Current Sample Schedule				
MW - 5	08/02/10	Not Sampled on Current Sample Schedule				

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 5	11/01/10	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/07/11	Not Sampled on Current Sample Schedule				
MW - 5	05/10/11	Not Sampled on Current Sample Schedule				
MW - 5	08/08/11	Not Sampled on Current Sample Schedule				
MW - 5	11/10/11	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/16/12	Not Sampled on Current Sample Schedule				
MW - 5	05/12/12	Not Sampled on Current Sample Schedule				
MW - 5	08/01/12	Not Sampled on Current Sample Schedule				
MW - 5	11/06/12	<0.001	<0.001	<0.001	<0.001	
MW - 5	02/05/13	Not Sampled on Current Sample Schedule				
MW - 5	05/09/13	Not Sampled on Current Sample Schedule				
MW - 5	08/01/13	Not Sampled on Current Sample Schedule				
MW - 5	11/07/13	<0.001	<0.001	<0.001	<0.0030	
MW - 6	02/19/98	ND	ND	ND	ND	
MW - 6	01/23/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 6	05/20/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 6	09/07/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	12/10/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	03/06/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	05/16/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	08/31/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	11/17/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	03/07/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	05/30/01	<0.005	<0.005	<0.005	<0.005	
MW - 6	02/25/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	05/13/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	09/10/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	11/15/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	02/11/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	05/13/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	08/22/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 6	12/15/03	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 6	03/04/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 6	12/10/04	0.0036	<0.001	<0.001	0.0032	
MW - 6	03/14/05	Not Sampled on Current Sample Schedule				
MW - 6	06/13/05	<0.001	<0.001	<0.001	<0.001	
MW - 6	09/12/05	Not Sampled on Current Sample Schedule				
MW - 6	12/06/05	<0.001	<0.001	<0.001	<0.001	
MW - 6	03/10/06	Not Sampled on Current Sample Schedule				
MW - 6	06/09/06	<0.001	<0.001	<0.001	<0.001	

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 6	09/12/06	Not Sampled on Current Sample Schedule				
MW - 6	11/28/06	<0.001	<0.001	<0.001	0.0013	
MW - 6	02/22/07	Not Sampled on Current Sample Schedule				
MW - 6	05/17/07	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/21/07	Not Sampled on Current Sample Schedule				
MW - 6	11/26/07	<0.001	<0.001	<0.001	<0.001	
MW - 6	02/26/08	Not Sampled on Current Sample Schedule				
MW - 6	05/26/08	<0.001	<0.001	<0.001	0.0017	
MW - 6	08/28/08	Not Sampled on Current Sample Schedule				
MW - 6	11/19/08	<0.001	<0.001	<0.001	0.0017	
MW - 6	02/13/09	Not Sampled on Current Sample Schedule				
MW - 6	05/20/09	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/15/09	Not Sampled on Current Sample Schedule				
MW - 6	11/06/09	<0.001	<0.001	<0.001	<0.001	
MW - 6	02/05/10	Not Sampled on Current Sample Schedule				
MW - 6	05/03/10	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/02/10	Not Sampled on Current Sample Schedule				
MW - 6	11/01/10	<0.001	<0.001	<0.001	<0.001	
MW - 6	02/07/11	Not Sampled on Current Sample Schedule				
MW - 6	05/10/11	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/08/11	Not Sampled on Current Sample Schedule				
MW - 6	11/10/11	<0.001	<0.001	<0.001	<0.001	
MW - 6	02/16/12	Not Sampled on Current Sample Schedule				
MW - 6	05/12/12	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/01/12	Not Sampled on Current Sample Schedule				
MW - 6	11/06/12	<0.001	<0.001	<0.001	<0.001	
MW - 6	02/05/13	Not Sampled on Current Sample Schedule				
MW - 6	05/09/13	<0.001	<0.001	<0.001	<0.001	
MW - 6	08/01/13	Not Sampled on Current Sample Schedule				
MW - 6	11/07/13	<0.001	<0.001	<0.001	<0.0030	
MW - 7	02/19/98	ND	ND	ND	ND	
MW - 7	01/23/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 7	05/20/99	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 7	09/07/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	12/10/99	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	03/06/00	<0.001	<0.001	<0.001	0.0010	<0.001
MW - 7	05/16/00	0.0010	0.0040	0.001	0.0010	0.002
MW - 7	08/31/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	11/17/00	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	03/07/01	<0.001	<0.001	<0.001	<0.001	<0.001

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p - XYLENES	o - XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 7	05/30/01	0.0065	<0.005	<0.005	<0.005	
MW - 7	08/27/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	10/12/01	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	02/25/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	05/13/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	09/10/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	11/15/02	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	02/11/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	05/13/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	08/22/03	<0.001	<0.001	<0.001	<0.001	<0.001
MW - 7	12/15/03	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 7	03/04/04	<0.001	<0.001	<0.001	<0.002	<0.001
MW - 7	12/10/04	<0.001	<0.001	<0.001	<0.001	
MW - 7	03/14/05	Not Sampled on Current Sample Schedule				
MW - 7	06/13/05	<0.001	<0.001	<0.001	<0.001	
MW - 7	09/12/05	Not Sampled on Current Sample Schedule				
MW - 7	12/06/05	<0.001	<0.001	<0.001	<0.001	
MW - 7	03/10/06	Not Sampled on Current Sample Schedule				
MW - 7	06/09/06	<0.001	<0.001	<0.001	<0.001	
MW - 7	09/12/06	Not Sampled on Current Sample Schedule				
MW - 7	11/28/06	<0.001	<0.001	<0.001	<0.001	
MW - 7	02/22/07	Not Sampled on Current Sample Schedule				
MW - 7	05/17/07	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/21/07	Not Sampled on Current Sample Schedule				
MW - 7	11/26/07	0.0031	<0.001	<0.001	<0.001	
MW - 7	02/26/08	Not Sampled on Current Sample Schedule				
MW - 7	05/26/08	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/28/08	Not Sampled on Current Sample Schedule				
MW - 7	11/19/08	<0.001	<0.001	<0.001	<0.001	
MW - 7	02/13/09	Not Sampled on Current Sample Schedule				
MW - 7	05/20/09	0.0071	<0.001	<0.001	<0.001	
MW - 7	08/15/09	Not Sampled on Current Sample Schedule				
MW - 7	11/06/09	0.0013	<0.001	<0.001	<0.001	
MW - 7	02/05/10	Not Sampled on Current Sample Schedule				
MW - 7	05/03/10	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/02/10	Not Sampled on Current Sample Schedule				
MW - 7	11/01/10	<0.001	<0.001	<0.001	<0.001	
MW - 7	02/07/11	Not Sampled on Current Sample Schedule				
MW - 7	05/10/11	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/08/11	Not Sampled on Current Sample Schedule				
MW - 7	11/10/11	<0.001	<0.001	<0.001	<0.001	

TABLE 2

CONCENTRATIONS OF BTEX IN GROUNDWATER

PLAINS MARKETING, L.P.
 MONUMENT 10
 LEA COUNTY, NEW MEXICO

Results are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	Methods: EPA SW 846-8021, 5030				
		BENZENE	TOLUENE	ETHYL-BENZENE	m, p -XYLENES	o -XYLENE
NMOCD REGULATORY GUIDELINE		0.01	0.75	0.75	0.62	
MW - 7	02/16/12	Not Sampled on Current Sample Schedule				
MW - 7	05/12/12	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/01/12	Not Sampled on Current Sample Schedule				
MW - 7	11/06/12	<0.001	<0.001	<0.001	<0.001	
MW - 7	02/05/13	Not Sampled on Current Sample Schedule				
MW - 7	05/09/13	<0.001	<0.001	<0.001	<0.001	
MW - 7	08/01/13	Not Sampled on Current Sample Schedule				
MW - 7	11/07/13	<0.001	<0.001	<0.001	<0.00300	

POLYNUCLEAR AROMATIC HYDROCARBON CONCENTRATIONS IN GROUNDWATER

All water concentrations are reported in mg/L

Page 1 of 2

TABLE 3

POLYNUCLEAR AROMATIC HYDROCARBON CONCENTRATIONS IN GROUNDWATER

PLAINS MARKETING, L.P.
MONUMENT 10
LEA COUNTY, NEW MEXICO
NMOCD REFERENCE NUMBER R1-0119

All water concentrations are reported in mg/L.

SAMPLE LOCATION	SAMPLE DATE	EPA SW846-8270C, 3510																		
		Acenaphthene	Acenaphthylene	Anthracene	Benzo[a]anthracene	Benzo[a]pyrene	Benzo[b]fluoranthene	Benzo[g,h,i]perylene	Benzo[k]fluoranthene	Chrysene	Dibenz[a,h]anthracene	Fluoranthene	Fluorene	Indeno[1,2,3-cd]pyrene	Phenanthrene	Pyrene	Naphthalene	1-Methylnaphthalene	2-Methylnaphthalene	Dibenzofuran
Maximum Contaminant Levels from NM WQCC Drinking water standards Sections 1-101.UU and 3-103.A.		--	--	0.001 mg/L	0.0001 mg/L	0.0007 mg/L	0.001 mg/L	--	0.001 mg/L	0.0002 mg/L	0.0003 mg/L	0.001 mg/L	0.001 mg/L	0.0004 mg/L	0.001 mg/L	0.001 mg/L	0.03 mg/L		--	
MW-5	11/19/08	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	
	11/06/09	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	<0.000185	
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																		
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																		
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																		
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																		
MW-6	11/19/08	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	<0.000183	
	11/06/09	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																		
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																		
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																		
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																		
MW-7	11/19/08	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	<0.000186	0.000237	<0.000186	<0.000186	0.00034	<0.000186	0.000338	
	11/06/09	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	<0.000184	
	11/01/10	Not Sampled as part of Quarterly Monitoring Event.																		
	11/10/11	Not Sampled as part of Quarterly Monitoring Event.																		
	12/04/12	Not Sampled as part of Quarterly Monitoring Event.																		
	11/07/13	Not Sampled as part of Quarterly Monitoring Event.																		