GW - <u>1</u> MONITORING REPORTS

DATE: 2005

2004 GROUNDWATER REMEDIATION AND MONITORING ANNUAL REPORT APRIL 2005 VOLUME I



SAN JUAN REFINING COMPANY GIANT – BLOOMFIELD REFINERY



April 11, 2005

Wayne Price Environmental Bureau New Mexico Oil Conservation Division 1220 South Francis Drive Santa Fe, New Mexico 87505 Hope Monzeglio New Mexico Environmental Department Hazardous Waste Bureau 2905 Ródeo Park Dr. East Bldg. 1 Santa Fe, New Mexico 87505

RE: Corrective Measures Study and Corrective Measures Implementation (Site Investigation and Abatement Plan) Groundwater Remediation and Monitoring Annual Report Giant Refining Company, Bloomfield Refinery EPA ID# NMD089416416 GW – 001

Dear Wayne and Hope:

Giant Refining Company, Bloomfield Refinery submits the 2004 Annual Groundwater Report as required by NMED and OCD directives. This report summarizes all soil and groundwater monitoring activities that occurred in 2004.

If you have questions or would like to discuss any aspect of the report, please contact me at (505) 632-4171.

Sincerely

James R. Schmaltz Environmental Manager San Juan Refining Company Bloomfield Refinery

cc: Robert Wilkinson, EPA Region VI Denny Foust, NMOCD Aztec District Office Ed Riege, Environmental Superintendent – Giant Refinery

PHONE 505-632-8013 FAX 505-632-3911 50 ROAD 4990 P.O. BOX 159 BLOOMFIELD NEW MEXICO 87413

CONTENTS

	CONTENTS
Section	Title
VOLUME	<u>= 1</u>
1.0	Executive Summary
2.0	Introduction
3.0	Scope of Services
4.0	Regulatory Criteria / Groundwater Cleanup Standards
5.0	Groundwater Monitoring Results
6.0	Groundwater Chemical Analytical Data
7.0	Remediation System Monitoring
8.0	Summary
9.0	List of Tables
10.0	List of Figures
11.0	BTEX & MTBE Concentration vs Time
12.0	Field Methods
13.0	Waste Disposition
14.0	Drilling Logs and Installation Diagrams
15.0	Below Grade Testing
16.0	Correspondence
VOLUM	E_2
17.0	Chemical Analytical Program

A

0

0

18.0 Chemical Analytical Reports

Section 1.0 Executive Summary

Executive Summary

The primary remediation system in place at Bloomfield is separate phase hydrocarbon (SPH) removal utilizing total fluids pumping. Total fluids pumping is used to bring SPH and hydrocarbon impacted groundwater to the surface for treatment or disposal. In 2004 the total gallons pumped from the recovery wells was 1,168,147 gallons.

In August 2004 recent emergence of active petroleum hydrocarbon seeps were found in two small tributaries (draws) on the north side of the refinery. Hydrocarbon staining had migrated down the draws toward the San Juan River. Upon receiving the Emergency Action Directive, Giant implemented the following tasks. The visually contaminated soils were removed and the vertical and horizontal extent of the contamination was investigated. Daily progress reports were sent to the agencies. Compacted soil barriers were constructed in each tributary to prevent migration into the river. Lined collection and barrier systems were installed at the point of the seeps. The collection points are monitored and pumped for recovery. Giant prepared a Monitoring and Contingency Plan, which stipulated river sampling and monitoring of the draws.

The river was sampled at the mouth of the draws on a monthly basis and analyzed for BTEX/MTBE (8021), TPH (8015 DRO and GRO), WQCC metals, semi-volatiles organics (8270) and general chemistry. After four months of sampling and no evidence of pollutants the sampling frequency will be reduced to quarterly. All analysis results were below the NM WQCC standards. BTEX and MTBE results for September through December were all below detection limits. All draws were inspected every other week for visual hydrocarbon staining starting in August.

Sheet pilings and a bentonite slurry wall are in place along the San Juan River's edge. The sheet pilings extend around the perimeter of the riverbank to the river inlet station. The purpose of the sheet piling and the slurry wall is to prevent any SPH and dissolved-phase hydrocarbons in the groundwater from migrating to the west, into the San Juan River. There are two piezometers located near the river P-4 and P-5 with P-5 located on the riverside of the sheet piling. Piezometers #4 and #5 continue to see benzene, ethyl benzene and xylene levels above the NM WQCC standards.

In October 2004 a field investigation was performed in the river terrace sheet-pile area. The purpose of the investigation was to 1) install two new monitoring wells at the river terrace to supplement P-4 and P-5 currently used for water quality monitoring and 2) evaluate the presence and extent of fuel hydrocarbons in groundwater on the refinery side of the sheet-pile barrier. The investigation

involved the installation of eight temporary well points (TP-1 through TP-8) and two permanent wells (MW-48 and MW-49).

On the refinery side of the sheet-pile barrier, the groundwater sampling results indicate fuel hydrocarbon contamination extends from the barrier to the east to temporary well point TP-4. Fuel hydrocarbons were also reported in well point TP-3, the farthest east well point, but the concentrations were low compared to the results closer to the barrier.

Comparing the groundwater sampling results from well MW-49 (river side of barrier) to those from MW-48, fuel hydrocarbons were reported to be significantly lower on the riverside of the barrier. The data indicates the sheet-pile wall is acting as a significant barrier against fuel hydrocarbon migration to the river.

An aquifer (pump) test was performed in December on MW-48. Malcolm Pirnie, an independent environmental engineering firm, was contracted to administer the test. The purpose of the pump test was to obtain aquifer hydraulic properties of the river terrace alluvial aquifer below the refinery.

After running multiple iterations of the capture zone model, Malcolm Pirnie determined that an adequate capture zone could be obtained at a pumping rate of 2 to 5 gpm.

The north collection system consists of recovery tank #37, which collects groundwater from two 8-inch influent lines connected to the perforated sub-drain beneath the Hammond ditch irrigation canal. The water is pumped to a 4 inch steel line beneath the road canal and up the embankment south of the tank, which transport the groundwater to the API separator. The total volume pumped in 2004 was 242,453 gallons.

Groundwater samples were collected in March and August of 2004. The semiannual monitoring event occurred the first week of March. Annual sampling began August 16, and continued for two weeks.

Since the lining of the Hammond Ditch in 2001, it is no longer a contributor to local groundwater recharge at the site. Prior to the lining of the Hammond Ditch, the infiltration of source water through the shallow zone soils served as a hydraulic curtain for the migration of Phase-Separated Hydrocarbon (PSH) along the north property boundary. Sampling of the monitor wells MW-45 and MW-47 on the outside (river side) of the Hammond Ditch indicate that some BTEX is not being contained by this collection system. BTEX was found above NM WQCC standards in MW#45 and BEX in MW#47 during the March sampling event. This is probably due to the lack of hydraulic curtain from the ditch.

The east outfall is collected into a pipe, which flows, to Tank #38 and then to Tank #33 located just south of the western fresh water pond. Hydrocarbons are

skimmed off the top of the tank into a secondary tank, which is emptied with a vacuum truck and taken to the API separator. The remaining water from Tank #33 is then piped to the fresh water pond. The total gallons pumped in 2004 were 7,088,402 gallons.

In November Giant submitted a voluntary. Corrective Measures Plan, which was approved, by OCD and NMED in December. As a corrective measure to mitigate further migration of petroleum hydrocarbons towards the San Juan River and beyond the northern property boundaries of the refinery, Giant committed to the installation of a containment barrier wall (soil-bentonite slurry wall) and fluid collection systems approximately 2,600 feet in length along the north side of the Hammond Ditch and extending from County Road 4990 to a location approximately 200 feet east of the pipeline corridor.

In November Giant submitted a voluntary Corrective Measures Plan, which was approved, by OCD and NMED in December. This is a corrective measure to mitigate further migration of petroleum hydrocarbons towards the San Juan River in the River Terrace Sheet Pile Area.



1 11.

10

INTRODUCTION

101 103

- í. 1

11. 18

Owner:	San Juan Refining C 23733 North Scottsd Scottsdale, Arizona 8	ale Road	(parent corporation)
Operator:	Giant Refining Comp P.O. Box 159 Bloomfield, New Mex	-	(postal address)
	Giant Refining Comp #50 Rd 4990 Bloomfield, New Mex	-	(physical address)
Facility Name:	Bloomfield Refinery: #50 Rd 4990 Bloomfield, New Mex	kico 87413	(physical address)
Facility Status	Corrective Action/Co	ompliance	
US EPA ID	NMD089416416		
SIC Code	2911		
Purpose of Grou	ndwater Monitoring:	To evaluate	present contamination
Type of Groundw	vater Monitoring:	Semi-annua	al and Annual

BACKGROUND INFORMATION

SITE LOCATION AND DESCRIPTION

The Bloomfield Refinery is a crude oil refining facility with a crude capacity of 18,000 barrels per day. It is located approximately 1 mile south of Bloomfield, New Mexico, in San Juan County, latitude N36 41' 87", longitude W107 58' 70". It is further located approximately ½ mile east of State Route 550 on Count Road 4990 (a.k.a. Sullivan Road).

The refinery is located on a bluff 120 feet above the south side of the San Juan River. The top of the bluff is relatively flat and is at an elevation of 5,540 feet above sea level. The geological units that comprise the site include, in order of increasing depth, San Juan River Alluvium, Quaternary apron deposits, Aeolian sand and silt, Jackson Lake Terrace, and the Tertiary Nacimiento Formation. An unnamed arroyo flows toward the San Juan River on the southern and western edges of the site. East of the site, a welldefined arroyo cuts a small canyon from the bluff to the San Juan River. Hammond Ditch lies on the bluff between the limit of the Jackson Lake Terrace and the refinery.

Refinery offices are on the western end of the facility, along with warehouse space, maintenance areas, and a storage yard containing used material (e.g., pipes, valves). Petroleum processing units, located in the northwest portion of the refinery, include the crude unit, fluidized cracking unit, catalytic polymerization unit, and hydrodesulfurization unit. The API Separator is located in the northwestern portion of the site. The aeration lagoons are located in the north central section of the refinery.

In the central portion of the site, aboveground storage tanks (AST's) occupy a large percentage of refinery property. South of the refinery and across Sullivan Road are terminals for loading product and off-loading crude, as well as gas storage and hazardous waste storage.

The Refinery owner is San Juan Refining Company (SJRC) and is operated by Giant Refining Company. The historical and current activities conducted at the refinery are petroleum processing, crude and product storage, crude unloading and product loading, waste management (closed and existing facilities), and offices and non-petroleum material storage

HISTORY OF FACILITY MODIFICATIONS AND IMPROVEMENTS

Previous Owner's Activities

Local entrepreneur, Kimball Campbell, constructed the crude topping unit that eventually became the GRC facility in the late 1950s. O.L. Garretson bought the facility in the early 1960s, renamed it Plateau, Inc. and sold it in 1964 to Suburban Propane of New Jersey.

Operationally, the facility has steadily evolved through a series of improvements, modifications and expansions. Suburban upgraded the facility in 1966, increasing the Crude Unit throughput to 4,100 bpcd and adding 1,850 bpcd Reformer and Naphtha Hydrotreater. In 1975, the Crude Unit was expanded to 8,400 bpcd.

In 1979, the Crude Unit was expanded again to 16,800 bpcd (later demonstrated to have a hydraulic capacity in excess of 18,000 bpcd). A Fluidized Catalytic Cracker (FCC) with a nominal capacity of 6,000 bpcd, an Unsaturated Gas Plant and a Treater Unit were also added at that time. The capacity of the Reformer / Hydrotreater was increased to 2,250 bpcd. The FCC was upgraded in 1982 to conform to State and Federal air quality standards.

Bloomfield Refining Activities

Bloomfield Refining Company (BRC) acquired the facility from Suburban Propane (Plateau) on October 31, 1984. BRC made many improvements to facility operations and equipment. These improvements are summarized below.

1986

Relocated the spent caustic tank onto a concrete pad with retaining walls.

1987

Upgraded the Reformer and increased its capacity to 3,600 bpcd, modified the Laboratory and Treater Unit and increased tank storage capacity.

Cleaned up the North and South bone yards.

Decommissioned and dismantled old tanks 6 and 7.

Relocated the API recoverd oil tanks 8 & 9 to concrete pads with concrete retaining walls.

Established a systematic inspection, maintenance and repair program for tanks.

1988

Added a 2,000 bpcd Catalytic Polymerization Unit. Removed the facility's two underground storage tanks and replaced them with aboveground storage tanks.

Completed installation of cathodic protection system for the tank farm and underground piping.

Rebuilt the process area sewer system and added curbed, concrete paving to the unpaved process areas.

1989

Increased Reformer throughput to 4,000 bpcd.

Activated the groundwater hydrocarbon recovery system.

Constructed the first double-lined Evaporation Pond as part of discharge plan improvements.

1990

Constructed the second double-lined Evaporation Pond as part of discharge plan improvements.

Constructed a drum storage shed and converted to bulk chemical usage where possible in order to minimize the use of drummed chemicals.

1991

Revamped the burner fuel sales rack with concrete paving and curbing.

Submitted the permit application for a Class 1 disposal well.

Upgraded the groundwater hydrocarbon recovery system.

1992

Submitted an air quality permit application proposing the installation of a Diesel Hydrodesulferization (HDS) Unit and a Sulfur Recovery Unit (SRU) to comply with new EPA low-sulfur diesel regulations and to decrease air emissions.

1993

Began a program under a consent agreement with the US EPA to conduct interim measures (IM), a RCRA facility investigation (RFI) and a corrective measures study (CMS) addressing groundwater contamination.

Replaced portions of the underground cooling water piping.

Added concrete paving around the API Separator.

Added process units: HDS Unit (2,000 bpcd) and SRU.

Improved (eliminated) storm water runoff to the North.

1994

Completed the Class 1 injection well.

Retrofitted the Aeration Lagoons with two additional liners.

Installed a floating cover for the API Separator.

Closed the clay-lined evaporation ponds and spray evaporation area.

Giant Activities

In 1995, San Juan Refining Company, a wholly owned subsidiary of Giant Industries Arizona, Inc., purchased the Bloomfield Refinery from BRC.

1995

Improved the diking South of the Refinery to further reduce storm water runoff.

Began implementation of additional corrective measures for groundwater cleanup as determined from the CMS.

1998

Converted the former evaporation ponds on the East side of the Refinery to raw water storage ponds.

1999

Installed sheet piling and a bentonite slurry wall adjacent to the San Juan River, North of the process units, in order to intercept a small hydrocarbon seep that had been detected in the area.

2001

Began a program to inoculate the Aeration Lagoons with sludge-consuming micro-organisms.

2002

A concrete liner was installed on the Hammond Ditch. At that time, Giant constructed the Hammond Ditch French Drain Recovery System to address contamination under the ditch.

2003

Converted several monitoring wells into recovery wells to further enhance the continuing ground water remediation efforts. Installed MW #45, #46 & #47 to replace unreliable seeps. Installed East Outfall #1 Recovery System to return impacted water back to the refinery.

2004

Installed MW #48 & MW #49 and 8 temporary piezometers to launch a River Terrace Investigation. Drilled several temporary piezometers on the north side of Hammond Ditch to chart the Naciemento Formation. Initiated the development of a slurry wall that will be constructed on the north side of Hammond Ditch to prevent the spread of hydrocarbons to the San Juan River. Construction will begin in 2005.

Replaced sewer lines in the Treater and FCC.

Section 3.0 Scope of Services

TE D

- **1**

11 11

-1

1 1

1. 0.

Scope of Services

The semi-annual monitoring event occurred during the first week of March 2004. Groundwater samples were collected from MW #1, MW #12, MW #13, MW #20, MW #32, MW #33, MW #35, MW #37, MW #38, MW #45, MW #47, P #4, P #5, P #6, O/F #2, and O/F #3. Field data (Tables 1 & 3) will verify that MW #6, MW #24, and MW #46 were dry and not sampled. Outfall #1 flows into Tk #38 and is not sampled. P-#6 is a temporary piezometer drilled 25 feet to the east of MW #24. However, P #6 has been destroyed with the construction of the slurry wall. Samples were analyzed for BTEX and MTBE using EPA Method 8021B. Semi-annual results are summarized in Table 4.

Annual sampling began August 16, 2004 and continued for two weeks. During an August 11, 2004 meeting, NMED and OCD requested that Giant sample all monitor and recovery wells that do not contain separate phase hydrocarbon. The following wells were sampled; MW #1, MW #3, MW #7, MW #8, MW #11, MW #12, MW #13, MW #21, MW #26, MW #27, MW #29, MW #30, MW #31, MW #32, MW #33, MW #34, MW #35, MW #36, MW #37, MW #38, MW #39, MW #44, P #4, P #5, O/F #2, O/F #3, RW #3, RW #14, RW #15, MW #16. As per the August meeting, the water was analyzed for BTEX and MTBE, RCRA 8 Metals, WQCC Dissolved Metals, Cations, Anions, and Carbon Dioxide. Results are summarized in Tables 5, 6, 7, & 8. Field data (Tables 2 & 3) will confirm that MW #3 had only enough water to conduct field measurements and sample for BTEX and MTBE. MW #5, MW #6, MW #24, and MW #46 were dry. MW #25, MW #45, MW #47, RW #17, P-#6, Storm water Outfall #2, and the Draw North of MW #45 were sampled for TPH (8015B) to discern fuel fingerprinting. Table 8 summarizes that data.

From August 2004 through December 2004, Bloomfield Refinery conducted San Juan River sampling events per the "Monitoring and Contingency Plan". Samples were analyzed for BTEX/MTBE (8021B), TPH (8015B), WQCC metals(6010C), semi-volatile organics (8270), and general chemistry. Analysis is summarized in Table 13 and sample locations are identified in Figure 11.

Remediation activities took place in August. Impacted soil was removed from several draws north of Hammond Ditch. The top layer was removed and placed in 16 55-gallon drums. The drummed soil was analyzed for BTEX (8021), TPH (8015), TCLP Metals (3050B & 6010B). The rest of the soil was stockpiled at the Hydroblast Pad and near Tank #36. A composite sample of each stockpile site was analyzed for BTEX (8021), TPH (8015), TCLP Metals(3050B & 6010B), and RCI. Table 12 summarizes all results.

The River Terrace Investigation ensued in October with the installation of eight Temporary Piezometers, MW #48, and MW #49. The piezometers were sampled and analyzed for BTEX/MTBE (8021B), and TPH (8015B). During the drilling of Mw #48 and MW #49, soil samples were taken at five-foot intervals and analyzed

for TPH (8015B), and volatile organic compounds (8260). After well development, water samples were grabbed from Mw #48 and MW #49 and analyzed for Volatile Organics (8260B), Polynuclear Aromatic Hydrocarbons (8310), WQCC Metals - Dissolved and Total (6010C), Cations, and Anions. In December, MW #48 and MW #49 were sampled and analyzed for BTEX/MTBE (6021B), TPH (8015B), and Polynuclear Aromatic Hydrocarbons (8310). River Terrace Investigation field data can be found in Table 14, analytical summaries are in Tables 9, 10 & 11, and sample locations are in Figure 10.

Field Data Collection

All facility monitoring wells, recovery wells, and piezometers were gauged in March and August. Recovery well pumps were shut off and removed 24 hours prior to water elevation measurements. MW #45 was converted to recovery well service due to an emergency action in August. The pump was not shut down and MW #45 was not gauged at that time.

All water/product levels were measured to an accuracy of 0.01 foot using a Geotech Interface Meter. After determining water levels, well volumes were calculated.

At least three well volumes were purged from each well prior to sampling. Electrical conductance, pH, and temperature were monitored during purging using an Ultrameter 6P. The wells were considered satisfactorily purged when the pH, E.C., and temperature values did not vary by more than 10 percent for at least three measurements.

Field data and well elevations can be found in Tables 1, 2, 3, & 14.

All purged water was collected in a fifty-five gallon drum and disposed of through the refinery wastewater system.

Section 4.0 Regulatory Criteria / Groundwater Cleanup Standards



TABLE OF NEW MEXICO AND THE U. S. EPA'SGROUNDWATER STANDARDS

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppm)	EPA HA (ppm)
General Properties				
non-aqueous phase liquid (NAPL)	NP			-
petroleum				
floating product	NP			
undesirable odor (a)	NP			
pH (units) (a)	6 - 9	6.5 - 8.5		
total dissolved solids (TDS) (a)	1000	500		
turbidity		tt		
Biological Contaminants				
giardia lambia	tt	Zero		
legionella	tt	Zero		
total coliform	<5%+	Zero		
viruses	tt	Zero		
Inorganic Contaminants				
aluminum	5.0(i)	0.05 - 0.2 (a)		
ammonia				30
antimony		0.006	0.006	
arsenic	0.1	0.05	0.05	
asbestos-fibers/liter (longer than 10 um)		7 million	7 million	
barium	1.0	2	2	
beryllium		0.004	0.004	
boron	0.75(i)			0.06
bromate		0.01(p)	Zero (p)	
cadmium	0.01	0.005	0.005	
chlorate				0.01

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppm)	EPA HA (ppm)
chloride (a)	250	250	· · · · · · · · · · · · · · · · · · ·	0.01
chlorine				1
chlorine dioxide				0.08
chlorite		1.0(p)	0.08(p)	
chromium	0.05	0.1	0.1	
cobalt (i)	0.05			
copper		1.3 (al)	1.3	
cyanide	0.2	0.2	0.2	
fluoride	1.6	4.0		
fluoride (a)		2		
iron (a)	1.0	0.3		
lead	0.05	0.015 (al)	Zero	
manganese (a)	0.2	0.05		
mercury	0.002	0.002	0.002	
molybdenum	1.0(i)			0.05
nickel	0.2 (i)	0.1	0.1	· • •
nitrate - N	10	10	10	
nitrite - N		1	1	
nitrate + nitrite (as N)		10	10	
selenium	0.05	0.05	0.05	
silver	0.05	0.05	0.05	
silver (a)		0.1		
sodium				20
strontium				17
sulfate	600(a)	250 (a) / 400 (p)	400	
thallium	•	0.002	0.0005	
vanadium				0.02
zinc (a)	10.0	5		
Radioactive Contaminants				
Gross alpha (pCi/L) *		15	Zero	
Gross beta & photon emitters (mrem	/yr) **	4	Zero	

I

i

i

i

11 11 11

1 8 26 1

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppm)	EPA HA (ppm)
radium 226 (pCi/L)		20(p)	Zero	
radium 228 (pCi/L)		20(p)	Zero	
radium 226 + 228 (pCi/L)	30	5	Zero	
radon 222 (pCi/L)		300(p)	Zero	
uranium	5	0.02(p)	Zero	
Benzenes				
benzene	0.01	0.005	Zero	
Alkyl Benzenes				
methylbenzene (toluene)	0.75	l(p)/0.04(a)	1	
ethylbenzene	0.75	0.7(p)/0.03(a)	0.7	
dimethyl benzene isomers (xylenes)	0.62	10(p)/0.02(a)	10	
vinylbenzene (styrene)		0.1	0.1	
trimethyl benzene isomers		· · .		
propyl benzene isomers				
butyl benzene isomers				
Chlorinated Benzenes				
chlorobenzene	tox	0.1	0.1	
o-dichlorobenzene	tox	0.6	0.6	
m-dichlorobenzene	tox			
p-dichlorobenzene	tox	0.075(p)/ 0.005 (a)	0.075	
1,2,4-trichlorobenzene		0.07	0.07	
1,3,5-trichlorobenzene				0.04
1,2,4,5-tetrachlorobenzene	tox			
pentachlorobenzene	tox			
hexachlorobenzene	tox	0.001	Zero	
Toluenes				
o-chlorotoluene				0.1
p-chlorotoluene				0.1
2,4-dinitrotoluene (2,4-DNT)	tox			

11 No.

T

i

٠

0

COM DE



İ

ĺ

ī.

L

I

ţ

. 1

ļ

Ì

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppin)	EPA H# (ppm)
2,4,6-trinitrotoluene (TNT)				0.002
isopropyltoluene				
Nitrogenated Benzenes				
aminobenzene (aniline)				
nitrobenzene	tox			
1,3-dinitrobenzene				0.001
Phenols (hydroxybenzenes)	0.005(a)			
phenol (carbolic acid)	tox			4
2-chlorophenol				0.04
2,4-dichlorophenol	tox			0.02
2,4-dinitro-o-creosol	tox			
2,4-dimethylphenol				
2-methylphenol				
4-methylphenol				
2-nitrophenol				
dinitrophenols	tox			
2,4,5-trichlorophenol	tox			
2,4,6-trichlorophenol	tox			
2,4,6-trichlorophenol	tox			
pentachlorophenol	tox	0.001 (p) / 0.03 (a)	Zero	
p-cresol				
Polycyclics				
acenapthene			•	
anthracene	tox			
benz(a)anthracene		0.0001(p)	Zero	
benzo(a)pyrene	0.0007	0.0002	Zero	
benzo(b)fluoranthene		0.0002(p)	Zero	
benzo(k)fluoranthene	tox	0.0002(p)	Zero	
chrysene		0.0002(p)	Zero	
dibenz(a)anthracene		0.0003(p)	Zero	
diphenylhydrazine	tox			





8-255V

1.111

ik I



PARAMETER	NEW MEXICO (ppin)	EPA MCL (ppm)	EPA MCLG (ppin)	EPA HA (ppm)
fluoranthene	tox			
fluorene	tox			
indeno(1,2,3-c,d)pyrene		0.0004(p)	Zero	
naphthalene	tox			0.3
naphthalenes ****	0.03			
phenanthrene	tox			
polychlorinated biphenyls (PCBs)	0.001			
PCBs as decachlorobiphenyl		0.0005	Zero	
pyrene	tox			
Methanes				
chloromethane (methyl chloride)	tox			0.003
dichloromethane (methylene chloride)	0.1	0.005	Zero	
trichloromethane (chloroform)	0.1		Zero (p)	
tetrachloromethane (carbon tetrachloride)	0.01	0.005	Zero	
bromomethane (methyl bromide)	tox			0.01
bromochloromethane				0.09
bromodichloromethane	tox		Zero (p)	
chlorodibromomethane			Zero (p)	0.1
tribromomethane (bromoform)	tox		Zero (p)	
trihalomethanes (THMs) ***		0.1/0.08(p)	Zero	
fluorotrichloromethane (Freon 11)	tox			2
dichlorodifluoromethane (Freon 12)	tox			1
Ethanes				
1,2-dibromoethane (ethylene dibromide, EDB)	0.0001	0.00005	Zero	
1,1-dichloroethane	0.025			
1,2-dichloroethane (ethylene dichloride, EDC)	0.01	0.005	Zero	
1,1,1-trichloroethane (TCA)	0.06	0.2	0.2	
1,1,2-trichloroethane	0.01	0.005	0.003	
1,1,1,2-tetrachloroethane				0.07

. 1

1 16

h í i

2

ar al 11 - 1

the late in

in the life

I.

ł

I

i

٠

•

5 [] . j. i. i . i . i

Star Sills



ī.

l

Ì

I

ī

0.01			EPA HA (ppm)	
tox				
0.001	0.002	Zero		
0.005	0.007	0.007		
tox	0.07	0.07		
tox	0.1	0.1		
0.1	0.005	Zero		
0.02	0.005	Zero		
	0.005	Zero		
			0.04	
	0.0002	Zero		
tox				
tox			0.01	
tox				
tox			0.3	
tox				
			0.568	
			1	
tox		•	0.1	
			0.1	
0.1 (a)			0.04	
	tox 0.1 0.02 tox tox tox tox tox	0.005 0.007 tox 0.1 0.1 0.005 0.02 0.005 0.0002 tox 0.0002 tox tox	0.005 0.007 0.007 tox 0.07 0.07 tox 0.1 0.1 0.1 0.005 Zero 0.02 0.005 Zero 0.005 Zero 0.0002 Zero tox zero	

1 1

1.216

-			•			•		
	•		5			•	1	
		÷						

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppm)	EPA HA (ppm)
Nitrosamines				
N-nitrosodiethylamine	tox			
N-nitrosodimethylamine (NDMA)	tox			
N-nitrosodibutylamine	tox			
N-nitrosodiphenylamine	tox			
N-nitrosopyrrolidine	tox			
Phthalate Esters				
dibutyl phthalate	tox			
di-2-ethylhexyl phthalate	tox	0.006	Zero	
dièthyl phthalate	tox			
dimethyl phthlate	tox			
Explosives				
dinitrophenols	tox			
2,4-dinitrotoluene (2,4-DNT)	tox			
hexahydro-1,3,5-trinitro-s-triazine (RDX)				0.002
НМХ				0.4
nitroglycerin (glycerol trinitrate)				0.005
nitroguanidine				0.7
2,4,6-trinitrotoluene (TNT)		•		0.002
Other Organics	:			
acrolein	tox			
acrylamide		ť	Zero	
acrylonitrile	tox			0.004
benzidine	tox			
chloral hydrate		tt (p)	0.04(p)	
chloramine				0.3



L

· · · · · ·

i

.

PARAMETER	PARAMETER NEW MEXICO (ppm)		EPA MCLG (ppm)	EPA HA (ppm)	
dibromoacetonitrile				0.02	
dichloroacetic acid	· · · · · · · · · · · · · · · · · · ·			0.003	
dichloroacetonitrile				0.006	
dichlorobenzidine	tox				
di(2-ethylhexyl)adipate		0.4	0.4		
diisopropyl methylphosphonate				0.6	
epichlorohydrin (1-chlor-2,3- epoxypropane)		tt	Zero		
ethylene glycol (1,2-ethanediol)				7	
Haloacetic Acids ****		0.06(p)			
dichloroacetic acid			Zero (p)		
trichloroacetic acid			0.3 (p)		
hexachlorobutadiene	tox			0.001	
hexachlorocyclopentadiene	tox	0.05(p)/0.008 (a)	0.05		
n-hexane				4.0	
acifluorfen				0.1	
alachlor		0.002	Zero		
aldicarb		0.003(p)	0.001		
aldicarb sulfone		0.002(p)	0.001		
aldicarb sulfoxide		0.004 (p)	0.001		
aldrin	tox			0.001	
ametryn				0.06	
ammonium sulfamate					
				2	
arsenal (imazapyr)	:			2	
	:	0.003	0.003	2	
arsenal (imazapyr)	:	0.003	0.003	2 0.003	
arsenal (imazapyr) atrazine	:	0.003	0.003		
arsenal (imazapyr) atrazine baygon		0.003	0.003	0.003	
arsenal (imazapyr) atrazine baygon bentazon		0.003	0.003	0.003 0.02	
arsenal (imazapyr) atrazine baygon bentazon bromacil		0.003	0.003	0.003 0.02 0.09	

.

-tik -t

, kët ai la

NHE LE

i i i i i i i i i i

0

T

Ì

i

i

İ

ļ

I

AL ALLAN PARTY

1 411

1.1.1

PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppin)	EPA HA
carboxin .				0.7
chloramben				0.1
chlordane	tox	0.002	Zero	
chlorothalonil				0.5
chlorpyrifos				0.02
cyanazine				0.01
2,4-D (2,4-dichlorophenoxyacetic acid)		0.07	0.07	
dacthal				4
dalapon		0.2	0.2	
DDT (dichloro diphenyl trichloroethane)	tox			
4,4'-DDD				
4,4'-DDE				
diazinon				0.0006
dicamba				0.2
dieldrin	tox			0.002
dimethrin			•	2
dinoseb		0.007	0.007	
dioxin		0.00000005	Zero	
diphenamid				0.2
diquat		0.02	0.02	
disulfoton				0.0003
diuron				0.01
endosulfan	tox			
endothall		0.1	0.1	
endrin	tox	0.002	0.002	
ethylene thiourea			·	0.001
fenamiphos				0.002
fluometuron				0.09
fonofos				0.01
glyphosate		0.7	0.7	
heptachlor	tox	0.0004	Zero	
heptachlor epoxide		0.0002	Zero	
hexazinone				0.2
lindane (gamma-BHC)	tox	0.0002	0.0002	

1 312 1



•

53. 9mt



PARAMETER	NEW MEXICO (ppm)	EPA MCL (ppm)	EPA MCLG (ppm)	EPA HA (ppm)
alpha-BHC	tox		· ·	
beta-BHC	tox			
delta-BHC				
malathion				0.2
maleic hydrazide				4
methomyl				0.2
methoxychlor		0.04	0.04	
methyl chlorophenoxyacetic acid (MCPA)				0.011
methyl parathion				0.002
metolachlor				0.1
metribuzin				0.2
oxamyl (vydate)		0.2	0.2	
paraquat				0.03
picloram		0.5	0.5	
prometon				0.1
pronamide				0.05
propachlor				0.09
propazine				0.01
propham				0.1
simazine		0.004	0.004	
2,4,5-T (2,4,5-trichlorophenoxyacetic acid)	i -			0.07
tebuthiuron				0.5
terbacil				0.09
terbufos				0.0009
toxaphene	tox	0.003	Zero	
2,4,5-TP (silvex)		0.05	0.05	
trifluralin				0.005

Abbreviations

al Action Level that, if exceeded, requires water treatment BHC benzene hexachloride, also called hexachlorocyclohexane DDD 1,1'-(2,2-dichloroethylidene) -bis/4-chlorobenzene

DDE 1,1'-(2,2-dichloroetheneylidene) -bis/4-chlorobenzene

IIA Health Advisory

HMX octahydro-1,3,5,7-tetranitro-1,3,5,7-tetrazocine

MCL Maximum Contaminant Level

MCLG Maximum Contaminant Level Goal

mg/L milligrams per liter

mrem/yr millirem per year

mrem ede/yr dose committed over a 50-year period to a "reference man" from an annual intake rate of 2 liters drinking water per day

MTBE methyl tertiary butyl ether, a synonym for 2-methoxy-2-methyl propane (the standard includes other ether-based gasoline additives)

NP the contaminant shall Not be Present

pCi/L picocuries per liter

tox a numerical standard has not been established, but the contaminant is listed in a narrative standard of "toxic pollutant" defined in WQCC regulations

2.4.5-TP 2,4,5-trichlorophenoxpropionic acid

tt Treatment Technique that public water system operators must adhere to instead of a numerical standard

um micrometer

U.S. EPA Uniter States Environmental Protection Agency

WQCC New Mexico Water Quality Control Commission

Footnotes

* The proposed standard excludes radon 222, radium 226 and uranium activity

** This standard excludes radium 228 activity. Units for the existing standard are mrem/yr.

U.S. EPA has proposed to change the units to mrem ede/yr.

*** The "THMs" standard applies to the sum of chloroform, dichlorobromomethane, dibromochloromethane, and bromoform.

**** This standard applies to the sum of naphthalene and monomethylnaphthalene isomers. **** This standard applies to the sum of mono-, di-, and trichloroacetic acids, and mono- and dibromoacetic acids.

Use and Applicability of Standards

All New Mexico standards are adopted by the WQCC except for the MTBE and petroleum (floating product and undesirable odor) standards, which are adopted by the New Mexico Environmental Improvement Board.

U.S. EPA's MCLGs are set at levels that would result in no known or anticipated adverse health effects with an adequate margin of safety. MCLGs do not take treatment costs into considerartion and are not enforceable. Health-based proposed MCLs and final enforceable MCLs are set as close to MCLGs as feasible with use of best technology, treatment techniques and other means.



U.S. EPA's HAs serve as informal technical guidance to assist Federal, State and Local officials responsible for protecting public health when emergency spills or contamination situations occur. They are not to be construed as legally enforceable Federal standards and are subject to change as new information becomes available. All HAs listed are for lifetime exposures except for p-dioxane (10 day) and n-hexane (7 year).

Section 5.0 Groundwater Monitoring Results

A

Title	Table/Figure	Section
Measured Depth to Groundwater	Tables1 & 2	9.0
Direction of Groundwater Flow	Figures 4 & 5	10.0
Field Water Quality Measurements	Tables 3 & 14	9.0
Comparison to Previous Monitoring	Tables 2, 4 and 14	9.0

Section 6.0 Chemical Analytical Data

Title	Table	Section
March – Organics	Table 5	9.0
August – Organics	Table 6	9.0
August – General Chemistry	Table 7	9.0
August – Dissolved Metals	Table 8	9.0
August – Total Metals	Table 9	9.0
August – Fuel Fingerprinting	Table 10	9.0

Section 7.0 Remediation System Monitoring

BA

Remediation System Monitoring

Summary of System Capabilities and Performance/Monitoring Data/System Failures-Modifications

Total Fluids Pumping

The primary remediation system in place at Bloomfield is separate phase hydrocarbon (SPH) removal utilizing total fluids pumping. Total fluids pumping is used to bring SPH and hydrocarbon impacted groundwater to the surface for treatment or disposal. This is accomplished by pumping wells within the SPH plume. The recovery wells pump SPH and hydrocarbon impacted groundwater to the refinery API separator and through the refinery process wastewater treatment system. Pumping is most effective in saturated zones with high hydraulic conductivities such as those measured at the refinery. Each pump can discharge up to 1.5 to 2 gpm. In 2004 total fluids pumping was accomplished through the use of thirteen recovery wells: RW# 1, 2, 9, 14, 15, 16, 17, 18, 19, 22, 23, 28 and 45.

In 2004, two skimmer pumps RW # 42 & 43 were also used to target the SPH source. Skimmer pumps are triggered into operation by sensors that detect a measurable thickness of the SPH.

In 2004 the total gallons pumped from the recovery wells was 1,168,147 gallons as shown in the Table in Section 7. Over sixty-eight percent of the gallons pumped were from RW-19.

MW-45 was converted to a RW on August 12, 2004 in response to hydrocarbon surfacing in a couple of the draws on the north side of the refinery. The pump from RW #14 was used in RW #45 and RW #14 has not been reactivated.

North Tributaries (draws)

In August 2004 recent emergence of active petroleum hydrocarbon seeps were found in two small tributaries (draws) on the north side of the refinery. Hydrocarbon staining had migrated down the draws toward the San Juan River. Upon receiving the Emergency Action Directive, Giant implemented the following tasks. The visually contaminated soils were removed and the vertical and horizontal extent of the contamination was investigated. Daily progress reports were sent to the agencies. Compacted soil barriers were constructed in each tributary to prevent migration into the river. Lined collection and barrier systems were installed at the point of the seeps. The collection points are monitored and pumped for recovery.

The top layer of the impacted soil was removed from the draws and placed into sixteen, 55-gallon drums and sampled. The rest of the soil was stockpiled at the Hydro blast Pad and near Tank #36 and sampled. Giant received OCD and NMED approval to dispose of the 16 barrels of hydrocarbon contaminated soil in the San Juan County Landfill. A copy of the waste shipment record can be found on the last page of Section 13. The stockpiled soil was approved for on-site utilization.

In response to these discharges MW-45 was converted into a recovery well in August.

Also Giant prepared a Monitoring and Contingency Plan, which stipulated river sampling and monitoring of the draws. To review the entire Plan refer to Section 16, Tab 9.

The river was sampled at the mouth of the draws on a monthly basis and analyzed for BTEX/MTBE (8021), TPH (8015 DRO and GRO), WQCC metals, semi-volatiles organics (8270) and general chemistry. After four months of sampling and no evidence of pollutants the sampling frequency will be reduced to quarterly. All analysis results were below the NM WQCC standards. BTEX and MTBE results for September through December were all below detection limits. A summary of San Juan River Analytical Data can be found in Section 9, Table 13.

All draws were inspected every other week for visual hydrocarbon staining starting in August.

River Sheet Pilings-Slurry Wall

Sheet pilings and a bentonite slurry wall are in place along the San Juan River's edge. The sheet pilings extend around the perimeter of the riverbank to the river inlet station. The purpose of the sheet piling and the slurry wall is to prevent any SPH and dissolved-phase hydrocarbons in the groundwater from migrating to the west, into the San Juan River. There are two piezometers located near the river P-4 and P-5 with P-5 located on the riverside of the sheet piling.

BTEX, General Chemistry, Dissolved Metals, Total Metals (RCRA 8) Piezometers #4 and #5 continue to see benzene, ethyl benzene and xylene levels above the NM WQCC standards. General chemistry results indicate all parameters are below the standards except for TDS (P4- 1700 ppm and P5-1400 ppm). Dissolved metals are below the standards for both piezometers except for Fe and Mn, which are just above the respective standard. In October 2004 a field investigation was performed in the river terrace sheet-pile area. The purpose of the investigation was to 1) install two new monitoring wells at the river terrace to supplement P-4 and P-5 currently used for water quality monitoring and 2) evaluate the presence and extent of fuel hydrocarbons in groundwater on the refinery side of the sheet-pile barrier. The investigation involved the installation of eight temporary well points (TP-1 through TP-8) and two permanent wells (MW-48 and MW-49).

Data Review -

On the refinery side of the sheet-pile barrier, the groundwater sampling results indicate fuel hydrocarbon contamination extends from the barrier to the east to temporary well point TP-4. Fuel hydrocarbons were also reported in well point TP-3, the farthest east well point, but the concentrations were low compared to the results closer to the barrier. For example, benzene was detected in TP-3, but the concentration was below 5 ug/L. The highest BTEX concentrations were reported near the barrier in TP-1, TP-8, and MW-48.

Comparing the groundwater sampling results from well MW-49 (river side of barrier) to those from MW-48, fuel hydrocarbons were reported to be significantly lower on the riverside of the barrier. For example, the November sampling results indicate benzene and toluene concentrations in MW-49 were reported below the laboratory detection limit of 10 ug/L. Ethyl benzene and xylenes were detected, but were reported at concentrations approximately two orders of magnitude less than reported in well MW-48. The December 27, sampling results for MW-48 and MW-49 were very similar to the November 1, sampling results. These data indicate the sheet-pile wall is acting as a significant barrier against fuel hydrocarbon migration to the river.

Low concentrations of diesel and gasoline-range organics were reported in the soil samples taken from monitoring wells MW-48 and MW-49. The depth of occurrence appears to be similar in both locations, suggesting the existence of these hydrocarbons in the soil predates the barrier installation. The concentrations reported in the soil samples from MW-49 (river side of barrier) are generally one-half those reported from MW-48.

Separate phase hydrocarbon (SPH) was not observed during the installation of the two monitoring wells (MW-48 and MW-49) and eight temporary well points (TP-1 through TP-8) in the River Terrace.

An aquifer (pump) test was performed in December on MW-48. Malcolm Pirnie, an independent environmental engineering firm, was contracted to administer the test. The purpose of the pump test was to obtain aquifer hydraulic properties of the river terrace alluvial aquifer below the refinery. To review the complete report refer to Section 16, Tab 10. Data from the aquifer test was utilized from both the pumping and recovery phases. The aquifer test data was used to estimate hydraulic conductivity of the aquifer. The draw down curves for piezometers located near the barrier wall and the bluff face (TP-1, 2 and-8) show continuous draw down when pumping at 4.7 gpm. As the cone of depression from the pumping well spreads laterally and intercepts the barrier wall and bedrock face, draw down increases in these areas due to their impermeable characteristics. In contrast, the water levels east or up gradient of well MW-48 only slightly declined during the test.

After running multiple iterations of the capture zone model, Malcolm Pirnie determined that an adequate capture zone could be obtained at a pumping rate of 2 to 5 gpm.

Hammond Ditch Recovery System

The north collection system consists of recovery tank #37, which collects groundwater from two 8-inch influent lines connected to the perforated sub-drain beneath the Hammond ditch irrigation canal. The water is pumped to a 4 inch steel line beneath the road canal and up the embankment south of the tank, which transport the groundwater to the API separator. The total volume pumped in 2004 was 242,453 gallons.

Since the lining of the Hammond Ditch in 2001, it is no longer a contributor to local groundwater recharge at the site. Prior to the lining of the Hammond Ditch, the infiltration of source water through the shallow zone soils served as a hydraulic curtain for the migration of Phase-Separated Hydrocarbon (PSH) along the north property boundary. Sampling of the monitor wells MW-45 and MW-47 on the outside (river side) of the Hammond Ditch indicate that some BTEX is not being contained by this collection system. This is probably due to the lack of hydraulic curtain from the ditch.

East Outfall

S 2 12

The east outfall is collected into a pipe, which flows, to Tank #38 and then to Tank #33 located just south of the western fresh water pond. Hydrocarbons are skimmed off the top of the tank into a secondary tank, which is emptied with a vacuum truck and taken to the API separator. The remaining water from Tank #33 is then piped to the fresh water pond. The total gallons pumped in 2004 were 7,088,402 gallons.

In January the meter was freezing and not operating properly. It was replaced and back in service on February 10.

Bloomfield Refinery Recovery Wells

Well #	Date In Service	Flowrate Mar-04	Flowrate Aug-04	Annual Total (gallons)
RW #1	Aug-03	28 gpd	28 gpd	10,220
RW #2	Aug-88	530 gpd	379 gpd	165,892
RW #9	Nov-03	114 gpd	87 god	36,682
RW #14	Aug-90	568 gpd	246 gpd	9,0761 *
RW #15	Aug-90	568 gpd	95 gpd	120,997
RW #16	Aug-90	O/S	189 gpd	51,030
RW #17	Aug-90	381 gpd	114 gpd	90,337
RW #18	Aug-90	O/S	3 gpd	810
RW #19	Aug-90	436 gpd	663 gpd	802,270
RW #22	Nov-03	130 gpd	68 gpd	36,135
RW #23	Jun-03	O/S	49 gpd	13,230
RW #28	May-03	60 gpm	133 gpd	35,222
RW #42	May-00	O/S	O/S	
RW #43	Mar-00	O/S	0.43 gpd	116
RW #45	Aug-04		900 gpw	18,000
			TOTAL =	1,168,147 GPY

. .

Mw #45 was put in service as a RW on August 12, 2004. Approxiamatley 900 gallon per week is pumped out of that well. The pump was pulled from RW #14 to use at MW #45. RW #14 was not reactivated.

Recovery Well flows were measured using a 500 ml graduated cylinder. At the time of a pump cycle, the discharge line was disconnected and placed in the graduated cylinder. A measurement was taken over time and then calculated to a gallons per day rate.



TANK #37 METER READING

2004

Date	Time	Hours	Reading	Gallons	Flow Rate(gal/min)
12/31/2003	9:00 AM	504.00	9535.6		
1/13/2004	10:00 AM	313.00	9634.2	4141.2	0.2
4/12/2004	1:30 PM	2212.00	10700.9	44801.4	0.3
5/25/2004	10:00 AM	1032.00	12440.6	73067.4	1.2
7/21/2004	8:00 AM	1368.00	13709.3	53285.4	0.6
8/9/2004	11:00 AM	435.00	13974.9	11155.2	0.4
9/27/2004	10:30 AM	1176.00	14624	27262.2	0.4
10/12/2004	12:30 PM	361.50	15194	23940.0	1.1
1/4/2005	8:00 AM	2011.00	16473.6	53743.2	0.4

Total Volume pumped in 2004 = 242,453 gallons

1

DATE	MTD	DAILY GPM
Jan-04	172,100.00	*
Feb-04	370,398.00	14
Mar-04	647,430.00	15
Apr-04	787,962.00	18
May-04	829,500.00	19
Jun-04	770,448.00	15
Jul-04	742,434.00	15
Aug-04	627,438.00	13
Sep-04	510,003.00	11
Oct-04	564,141.00	10
Nov-05	438,312.00	7
Dec-05	628,236.00	14

TANK #38 FLOW 2004 (EAST OUTFALL)

Operations reads the meter at midnight every night. Operations Manager compiles the monthly operating summary and the MTD number is from that summary.

* Meter was freezing up and not operating properly. Replaced and back in service 2-10-04

Total Volume Pumped in 2004 = 7,088,402 gallons

1. 10.0 Sec. 2.

i ali

113

11

di di

Section 8.0 Summary

1 14

- H H

1

Summary

Groundwater Monitoring Discussion

Monitor Wells

Groundwater samples were collected in March and August of 2004. In March samples were collected from the following monitor wells: MW1, MW12, MW13, MW20, MW32, MW33, MW35, MW37, MW38, MW45, MW47. In August samples were collected from the following wells: MW1, MW3, MW7, MW8, MW11, MW12, MW13, MW21, MW26, MW27, MW29, MW30, MW31, MW32, MW33, MW34, MW35, MW36, MW37, MW38, MW39 and MW44.

BTEX and MTBE Summary (March 2004 all analysis are in ppm)

Monitor well MW1, MW12, MW32 and MW33 were non detect for all of these parameters. Benzene was detected in MW20 (21), MW45 (1), MW47 (.56) & MW35 (.006). Toluene was only found in MW20 (1.2). Ethylbenzene was detected in MW45 (7.5), MW47 (.9) MW20 (.1) and MW35 (.0061). MTBE was detected in MW20 (95), MW13 (.02), MW38 (.015), MW35 (.011), MW37 (.004). Xylene was detected in MW45 (28), MW47 (7.9), MW20 (.5), MW35 (.0033), MW38 (.0014), MW37 (.0006).

BTEX and MTBE Summary (August 2004 all analysis are in ppm)

Monitor well MW1, MW3, MW7, MW8, MW27, MW32 and MW33 were non detect for all of these parameters. Benzene was detected in MW31 (3.7), MW11 (1.7), MW30 (1.7), MW26 (.74), MW39 (.46), MW21 (.13), MW35 (.0082), MW36 (0009). Toluene was detected in MW31 (.4), MW30 (.37), MW39 (.15) and MW34 (.0039). Ethylbenzene was detected in MW30 (1.9), MW39 (.55), MW26 (.46), MW31 (.32) and MW11 (.064), MW34 (.019), MW21 (.0098), MW35 (.0061), MW37 (.0012, MW38 (.0012). MTBE was detected in MW21 (.028), MW13 (.027), MW35 (.0096), MW36 (.0085), MW38 (.0085), MW44 (.0048), MW29 (.0026), MW37 (.0026). Xylene was detected in most of the wells with the high detected in MW30 (2.5) to a low found in MW37 (.00062).

Groundwater Monitoring Conclusions

Comparison of Results to Cleanup Levels and Historical Groundwater Monitoring and Analytical Data

Monitor Wells

BTEX March

The key area of concern is the BTEX above NM WQCC standards found in MW#45 and the BEX found in MW#47 during the March sampling event. These wells are located on the outside (river side) of the Hammond ditch, indicating that contamination has moved past the Hammond Ditch recovery system.

BTEX August

All wells except for MW20 continue to see decreased levels of BTEX over time. The following wells were less than detection for BTEX: MW1, MW3, MW7, MW8, MW27, MW32 and MW33. None of the wells were above the standard of .75 ppm for toluene. The wells that exceeded the standard of .01 for benzene were. MW11, MW21, MW26, MW30, MW31 and MW39. The year 2004 was the first year that MW21, MW30, MW31 and MW39 were sampled for BTEX. MW20 was the only well to see increased levels of BTEX with the NM WQCC standard of .01 ppm for benzene exceeded at 21 ppm, toluene standard of .75 ppm standard was exceeded (1.2 ppm) and the MTBE level was 95 ppm.

General Chemistry

In the August sampling event all the wells were below the New Mexico WQCC standards for fluoride and nitrogen. The TDS for all the monitor wells sampled except for MW1 and MW29 were above the NM standard. The wells that exceeded the standard for more than one parameter (chloride and sulfate) were MW8, MW13, MW21, MW30, MW31 and MW33.

Dissolved Metals

In the August monitor well sampling event, As, Cd, Ag, and U were all less than detectable and Cr, Cu, and Pb were all found below the NM standards. The only wells to have multiple metals above the standards were MW11, MW21 and MW26 which exceeded for Ba and Mn. MW11 also exceeded the zinc standard of 10 ppm (63 ppm). The following wells exceeded for both Fe and Mn: MW34, MW35, MW36, MW37 and MW38.

Total Metals (RCRA 8)

In the August monitor well sampling event As, Se and Ag were all below detectable levels, and Cd and Hg were below the MCLs in all wells except for MW12 (Cd-.003 ppm) and (Hg- .005ppm). Cr exceeded the MCL in MW8, MW12, MW37, MW38, MW39, MW41 and Pb in MW11, MW12, MW26, MW27, MW39 and MW44. The two wells to exceed the MCL for both Cr and Pb were MW12 and MW39.

Historical comparison could not be made for the monitor well sampling for general chemistry, dissolved metals and total metals as analysis were only started for some wells in 2003 and others in 2004.

Piezometers

BTEX, General Chemistry, Dissolved Metals, Total Metals (RCRA 8) Piezometers #4 and #5 continue to see benzene, ethylbenzene and xylene levels above the NM WQCC standards. General chemistry results indicate all parameters are below the standards except for TDS (P4- 1700 ppm and P5-1400 ppm). Dissolved metals are below the standards for both piezometers except for Fe and Mn, which are just above the respective standards.

<u>Outfalls</u>

BTEX, General Chemistry, Dissolved Metals, Total Metals (RCRA 8) Outfalls 2 and 3 were less than detection limits for BTEX and MTBE which is consistent with 2003 results. The general chemistry, dissolved metals and total metals results were all below NM WQCC standards and many were below detection limits.

Recommendations for Future Remedial Action

In November Giant submitted a voluntary Corrective Measures Plan, which was approved, by OCD and NMED in December(Section 16, Tab 11). As a corrective measure to mitigate further migration of petroleum hydrocarbons towards the San Juan River and beyond the northern property boundaries of the refinery, Giant has committed to the installation of a containment barrier wall (soilbentonite slurry wall) and fluid collection systems approximately 2,600 feet in length along the north side of the Hammond Ditch and extending from County Road 4990 to a location approximately 200 feet east of the pipeline corridor.

Giant will abide by the approval conditions stated by the agencies in their letters The key conditions include:

- Submit the fluid collection system design for approval before actual installation.
- Submit a plan for approval to evaluate the effectiveness of the wall.

In November Giant submitted a voluntary Corrective Measures Plan, which was approved, by OCD and NMED in December (Section 16, Tab12). This is a corrective measure to mitigate further migration of petroleum hydrocarbons towards the San Juan River in the River Terrace Sheet Pile Area. The key conditions include:

- Provide NMED with a map containing proposed well locations for NMED approval prior to installation
- Submit the results and findings of the 24-hour aquifer test performed on MW-48
- Submit the results of the capture zone analysis

Section 9.0 List of Tables

Title	Table
Groundwater Elevation and Depth to Water	Tables 1 & 2
Water Quality Field Measurements	Tables 3 & 14
Summary of Groundwater Chemical Analytical Data	
March – Organics August – Organics August – General Chemistry August – Dissolved & Total Metals August – Fuel Fingerprinting River Terrace Investigation	Table 5 Table 6 Table 7
Temporary Piezometers Monitoring Wells #48 & 49 – Soil Monitoring Wells #48 & 49 – Water	.Table 10
Soil Composite From Remediation Activities	.Table 12
Summary of San Juan River Analytical Data	.Table 13

dil fin d

Margaret P.

ii i

Groundwater Elevation March 2004

Table1

0	н Т	oundwater	1	n March			Table1			
	Date	Well ID	Collar Elevation	Well Casing Height	Total Well Depth	Depth To SPH	Depth To Water	Corrected Groundwater Elevation		
	3/2/2004	MW-01	5514.08	1.64	21.56	0	17.43	5498.29		
	3/2/2004	MW-03	5535.05	0.65	36.75	0	36.33	5499.37		
	3/2/2004	MW-04	5522.03	1.5	30.48	27.24	27.86	5496.17		
	3/2/2004	MW-05	5545.03	0.33	37.2		DRY			
	3/2/2004	MW-06	5549.84	1.19	48		DRY			
	3/2/2004	MW-07	5522.87	1.62	62.61	0	27.36	5497.13		
	3/2/2004	MW-08	5530.49	1.84	35.93	0	32.77	5499.56		
	3/2/2004	MW-11	5503.41	3.41	22.94	0	11.32	5495.50		
ĺ	3/2/2004	MW-12	5495.87	3.08	14.98	0	11.95	5487.00		
	3/3/2004	MW-13	5535.62	2.83	52.89	0	40.41	5498.04		
[3/4/2004	MW-20	5514.92	1.36	27.13	21.05	21.47	5495.15		
	3/2/2004	MW-21	5518.45	1.27	30.38	22.32	22.35	5497.39		
ſ	3/4/2004	MW-24	5505.05	1.12	15.14		DRY			
	3/4/2004	MW-25	5527.37	3	41.2	32.64	33.61	5497.54		
Y	3/2/2004	MW-26	5512.13	2.11	25.11	0	17.32	5496.92		
	3/2/2004	MW-27	5512.17	2.76	24.42	0	18.71	5496.22		
ſ	3/2/2004	MW-29	5517.22	2.88	28.62	0	23.32	5496.78		
	3/3/2005	MW-30	5531.29	1.96	40.13	0	33.96	5499.29		
	3/4/2004	MW-31	5531.13	1.52	39.16	0	34.13	5498.52		
	3/2/2004	MW-32	5521.2	0.75	27.51	0	24.98	5496.97		
	3/2/2004	MW-33	5516.16	1.93	25.51	0	22.38	5495.71		
[3/2/2004	MW-34	5505.59	2.35	20.96	0	14.5	5493.44		
	3/2/2004	MW-35	5512.61	3.11	26.45	0	22.98	5492.74		
[3/2/2004	MW-36	5510.38	2.94	23.26	0	21.23	5492.09		
	3/2/2004	MW-37	5513.12	2.88	27.58	0	23.94	5492.06		
	3/2/2004	MW-38	5513	2.82	26.82	0	24.32	5491.50		
	3/4/2004	MW-39	5515.86	2.1	38.34	0	24.45	5493.51		
	3/4/2004	MW-40	5524.13	0	30.07	29.05	29.95	5494.90		
	3/4/2004	MW-41	5523.9	0	31.62	27.3	28.41	5496.38		
	3/3/2004	MW-44	5528.87	3.19	50.91	0	33.4	5498.66		
U	3/3/2004	MW-45	5496.33	2.1	16.92	9.32	15.85	5487.80		
	3/3/2004	MW-46	5496.43	1.79	10.39		DRY			

Page 1 of 2

11

ALL AND A REPORT OF

0

Groundwater Elevation March 2004

Table1

Date	Well ID	Collar Elevation	Well Casing Height	Total Well Depth	Depth To SPH	Depth To Water	Corrected Groundwater Elevation
3/3/2004	MW-47	5496.43	2.64	14.28	10.31	11.79	5488.46
3/4/2004	P-03	5506.72	0.3	22.73	0	10.07	5496.95
3/4/2004	P-04	5426.31	3.25	13.94	ა	8.29	5421.27
3/4/2004	P-05	5424.4	2.94	14.27	0	9.54	5417.80
3/4/2004	P-06(SB8-1103)	5492.86	1.24	14.46	0	10.83	5483.27
3/4/2004	P-07(SB9-1103)	5495.48	0	9.62	0	5.99	5489.49
3/4/2004	P-08(SB7-1103)	5495.15	0	10.19	8.64	9	5486.44
3/4/2004	P-09(SB6-1103)	5494.77	0	9.29	0	6.55	5488.22
3/2/2004	P10(SB11-1103)	5517.74	1.26	24.48	0	20.99	5498.01
3/2/2004	P-11(SB12-1103	5513.5	1.02	19.8	0	16.41	5498.11
3/3/2004	RW-01	5524.86	0.88	40.8	31.32	32.1	5494.26
3/3/2004	RW-02	5522.61	0.78	35.86	27.29	27.36	5496.09
3/4/2004	RW-03	5515.44	1.92	34.57	22.43	22.49	5494.92
3/3/2004	RW-09	5517.98	1.63	34.04	25.23	26.29	5494.17 ⁻
3/3/2004	RW-14	5532.33	2.45	41.94	35.21	36.65	5499.28
3/3/2004	RW-15	5531.74	2.36	43.43	0	35.93	5498.17
3/3/2004	RW-16	5530.43	2.43	41.48	0	35.04	5497.82
3/3/2004	RW-17	5528.86	2.45	41.89	35.45	35.55	5495.84
3/3/2004	RW-18	5523.3	2.52	37.58	31.3	33.61	5494.06
3/3/2004	RW-19	5525.56	1.33	36.64	30.86	31.93	5495.82
3/3/2004	RW-22	5518.36	2.49	35.6	25.88	26.66	5494.81
3/3/2004	RW-23	5515.86	1.98	35.53	23.72	23.93	5494.08
3/3/2004	RW-28	5522.44	1.84	36.99	29.55	31.83	5494.27
3/3/2004	RW-42	5523.97	0	32.02	27.23	28.55	5496.48
3/3/2004	RW-43	5515.74	0.5	24.03	21.89	21.96	5494.34

đ

: İ.

ll, dl



- --

Sector and

. 11 - 1

Τ



Groundwater Elevation A

I had a start

139 741

+ 1 i + i

❶

Ø

0

August 2004

Table 2

Date	Well ID	Collar Elevation	Well Casing Height	Total Well Depth	Depth To SPH	Depth To Water	Corrected Groundwater Elevation
8/23/2004	MW-01	5514.08	1.64	21.56	0	17.15	5512.29
8/23/2004	MW-03	5535.05	0.65	36.75	0	36.31	5528.44
8/25/2004	MW-04	5522.03	1.5	30.48	27.31	27.96	5496.09
8/26/2004	MW-05	5545.03	0.33	37.2	0	DRY	
8/24/2004	MW-06	5549.84	1.19	48	0	DRY	
8/25/2004	MW-07	5522.87	1.62	62.61	0	27.79	5518.93
8/19/2004	MW-08	5530.49	1.84	35.93	0	32.9	5525.75
8/16/2004	MW-11	5503.41	3.41	22.94	0	11.72	5504.48
8/16/2004	MW-12	5495.87	3.08	14.98	0	12.38	5496.47
8/18/2004	MW-13	5535.62	2.83	52.89	0	40.51	5530.35
8/26/2004	MW-20	5514.92	1.36	27.13	21.10	21.44	5495.11
8/23/2004	MW-21	5518.45	1.27	30.38	22.25	22.27	5497.47
8/26/2004	MW-24	5505.05	1.12	15.14		DRY	
8/19/2004	MW-25	5527.37	3	41.2	32.64	33.61	5497.54
8/19/2004	MW-26	5512.13	2.11	25.11	0	17.39	5510.76
8/18/2004	MW-27	5512.17	2.76	24.42	0	18.7	5511.19
8/19/2004	MW-29	5517.22	2.88	28.62	0	23.15	5515.47
8/23/2004	MW-30	5531.29	1.96	40.13	0	33.95	5526.46
8/19/2004	MW-31	5531.13	1.52	39.16	0	34.21	5525.81
8/17/2004	MW-32	5521.20	0.75	27.51	0	24.93	5516.96
8/17/2004	MW-33	5516.16	1.93	25.51	0	22.29	5513.63
8/17/2004	MW-34	5505.59	2.35	20.96	0	14.24	5505.09
8/17/2004	MW-35	5512.61	3.11	26.45	0	22.81	5511.16
8/17/2004	MVV-36	5510.38	2.94	23.26	0	21.3	5509.06
8/17/2004	MW-37	5513.12	2.88	27.58	0	23.99	5511.20
8/17/2004	MW-38	5513.00	2.82	26.82	0	24.51	5510.92
8/26/2004	MW-39	5515.86	2.1	38.34	0	24.59	5513.04
8/25/2004	MW-40	5524.13	0	30.07	28.94	29.76	5495.03
8/25/2004	MVV-41	5523.90	0	31.62	27.43	28.34	5496.29
8/23/2004	MW-44	5528.87	3.19	50.91	0	33.8	5525.30
8/16/2004	MW-45	5496.33	2.1	16.92	Not Measure	ed - Pumping	
8/16/2004	MW-46	5496.43	1.79	10.39	0	DRY	

Page 1 of 2

BLARK OF

Groundwater Elevation August 2004

i i i Ghi

1

estation ()

Surger.

Table 2

Date	Well ID	Collar Elevation	Well Casing Height	Total Well Depth	Depth To SPH	Depth To Water	Corrected Groundwater Elevation
8/16/2004	MW-47	5496.43	2.64	14.28	10.32	11.55	5488.50
8/26/2004	P-03	5506.72	0.3	22.73	0	11.44	5504.73
8/18/2004	P-04	5426.31	3.25	13.94	0	8.41	5427.88
8/18/2004	P-05	5424.40	2.94	14.27	0	9.24	5425.49
8/25/2004	RW-01	5524.86	0.88	40.8	31.32	31.84	5494.32
8/25/2004	RW-02	5522.61	0.78	35.86	26.53	27.22	5496.72
8/26/2004	RW-03	5515.44	1.92	34.57	22.71	22.74	5494.64
8/25/2004	RW-09(MW-09)	5517.98	1.63	34.04	25.13	25.72	5494.36
8/23/2004	RW-14	5532.33	2.45	41.94	0	35.11	5527.76
8/25/2004	RW-15	5531.74	2.36	43.43	0	34.92	5527.12
8/25/2004	RW-16	5530.43	2.43	41.48	0	35.05	5525.85
8/25/2004	RW-17	5528.86	2.45	41.89	33.37	33.63	5497.89
8/25/2004	RW-18	5523,30	2.52	37.58	30.48	30.86	5495.26
8/25/2004	RW-19	5525.56	1.33	36.64	30.40	31.42	5496.29
8/25/2004	RW-22	5518.36	2.49	35.6	29.95	29.98	5490.89
8/25/2004	RW-23	5515.86	1.98	35.53	23.53	23.63	5494.29
8/25/2004	RW-28(MW-28)	5522.44	1.84	36.99	29.38	31.22	5494.53
8/25/2004	RW-42(MW42)	5523.97	0	32.02	27.39	28.4	5496.38
8/25/2004	RW-43(MW-43)	5515.74	0.5	24.03	21.00	21.28	5495.18
8/30/2004	P-06(SB8-1103)	5492.86	1.24	14.46	10.86	11.22	5483.17
8/30/2004	P-07(SB9-1103)	5495.48	0	9.62	0	6.18	5494.24
8/30/2004	P-08(SB7-1103)	5495.15	0	10.19	8.66	8.76	5486.47
8/30/2004	P-09(SB6-1103)	5494.77	0	9.29	0	6.47	5493.48
8/25/2004	P10(SB11-1103)	5517.74	1.26	24.48	0	20.81	5514.84
8/25/2004	P-11(SB12-1103	5513.50	1.02	19.8	0	16.23	5511.27
9/1/2004	SB1-0704	5495.28	0	10	0	7.01	5493.88
8/30/2004	SB2-0704	5494.96	0	11.5	0	6.81	5493.60
9/1/2004	SB3-0704	5495.21	0	11.5	6.75	7.76	5488.26
9/1/2004	SB4-0704	5495.96	0	11	0	7.55	5494.45
9/1/2004	SB5-0704	5497.78					
8/30/2004	SB6-0704	5496.86	0	10.5	0	6.78	5495.50
8/30/2004	SB7-0704	5496.70	0	10.5	6.12	6.69	5490.47
9/1/2004	SB8-0704	5497.91	0	10.5	0	5.94	5496.72

II M

Table 3

TE	RW/MW	DEPTH TO LIQUID (ft)	SPH	WELL DEPTH	E.C.	рН	TEMP.	D.O	ORP
Aug-04	MW #1	17.15	0	21.56	927	6.90	63	5.4	-532
Mar-04		17.43	0	21.56	887	7.51	53		
Aug-03		17.16	0	21.62	1001	7.41	63	6.5	105
Aug-04	MW #3	36.31	0	36.75	7558	6.96	64		-11
Mar-04		36.33	0	36.75					
Aug-03		36.31	0	36.75	7818	6.96	66		57
Aug-04	MW #4	27.96	27.31	30.5	no sample	well	contains	hydrocarbon	
Mar-04		27.86	27.24	30.5	no sample	well	contains	hydrocarbon	and the second
Aug-03		27.95	27.07	30.5	no sample	well	contains	hydrocarbon	
Aug-04	MW #5	0	0	36.92	dry	well			
Mar-04		0	0	36.92	dry	well			
Aug-03		0	0	36.92	dry	well			
Aug-04	MW #6	0	0	47.92	dry	well			
Mar-04		0	0	47.92	dry	well			
Aug-03		0	0	47.92	dry	well	And the second second second second second second second second second second second second second second second		
Aug-04	MW #7	27.79	0	62.61	8693	7.00	63	2.8	84
Mar-04		27.36	0	62.61					
Aug-03		27.57	0	62.61				<u></u>	
g-04	MW #8	32.9	0	35.93	2600	7.02	62	2.9	142
Mar-04		32.77	0	35.93					
Aug-03		32.93	0	35.93	2654	6.98	60	7.1	176
Aug-04	MW #11	11.72	0	22.94	2093	6.81	68	13.8	-36
Mar-04		11.32	0	22.94					
Aug-03		11.69	0	22.93	2338	6.82	66	5.6	-53
Aug-04	MW #12	12.38	0	14.98	2164	6.85	66	9.3	151
Mar-04		11.95	0	14.98	1464	7.22	49		
Aug-03		11.39	0	14.98	5920	7.06	64	5.8	81
Aug-04	MW #13	40.51	0	52.89	3638	6.79	62	5.0	158
Mar-04		40.41	0	52.89	3895	6.96	59		
Aug-03		40.23	0	52.9	4573	6.77	64	5.6	86
Aug-04	MW #20	21.44	21.10	27.15	no sample	well	contains	hydrocarbon	
Mar-04		21.47	21.05	27.15	1576	7.05	62		
Aug-03		21.87	20.99	27.15	no sample	well	contains	hydrocarbon	
Aug-04	MW #21	22.27	22.25	30.38	4405	6.81	63	4.0	-43
Mar-04		22.35	22.32	30.38	15 31	18 S S	<u>Referri</u> s		
Aug-03		22.46	22.33	30.38		Set S			

Τü

Table 3

TE	RW/MW	DEPTH TO LIQUID (ft)	SPH	WELL DEPTH	E.C.	рН	TEMP.	D.O	ORP
Aug-03	MW #24	14.93	14.91	15.13	not enoug	h to sample	- contains	hydrocarbon	
Mar-04		0	0	15.13	dry	well			
Aug-03		14.93	14.91	15.13	not enoug	h to sample	- contains	hydrocarbon	
Aug-04	MW #25	33.4	32.77	41.2	fuel fin	ngerprint - c	ontains hyd	drocarbon	
Mar-04		33.61	32.64	41.2					
Aug-03		33.57	32.42	41.2					
Aug-04	MW #26	17.39	0	25.11	2422	6.81	65	7.5	-33
Mar-04		17.32	0	25.11		Sec. 3.			
Aug-03		33.57	32.42	41.2	2267	6.65	68	4.9	-69
Aug-04	MW #27	18.70	0	24.42	2474	6.89	65	1.7	-143
Mar-04		18.71	0	24.42		I Section Section			
Aug-03		18.50	0	24.42	2776	6.73	65	4.1	-188
Aug-04	MW #29	23.15	0	28.62	850	7.03	62	4.7	115
Mar-04		23.32	0	28.62	e de la composition de la composition de la composition de la composition de la composition de la composition d				
Aug-03		23.24	0	28.62					
Aug-04	MW #30	33.95	0	40.13	4480	6.90	62	over range	-196
Mar-04		33.96	0	40.13					
g -03		33.90	0	40.13	an der	the Martin		Carlos, R. Maria	
Aug-03	MW #31	34.21	0	39.16	3945	7.07	64	3.4	-19
Mar-04		34.13	0	39.16	A H		and the second sec		
Aug-03		34.02	0	39.16					
Aug-04	MW #32	24.93	0	27.51	3576	6.88	62	5.6	79
Mar-04		24.98	0	27.51	4898	6.71	58		
Aug-03		24.8	0	27.51	5346	6.87	63	7.4	64
Aug-04	MW #33	22.29	0	25.51	4630	6.81	63	5.6	106
Mar-04		22.38	0	25.51	4950	7.35	57		
Aug-03		22.11	0	25.51	4373	6.89	66	5.0	110
Aug-04	MW #34	14.24	0	20.96	2144	6.80	64	1.7	-51
Mar-04		14.5	0	20.96					And And And And And And And And And And
Aug-03		14.57	0	20.97	2220	6.75	70	4.9	-76
Aug-04	MW #35	22.81	0	26.45	2000	6.81	60	3.6	-63
Mar-04		22.98	0	26.45	2026	6.97	58		
Aug-03		23.04	0	26.45	2005	6.72	66	5.4	-95
Aug-04	MW #36	21.30	0	23.26	1880	6.85	68	8.4	-111
Mar-04		21.23	0	23.26					Single
Aug-03		21.44	0	23.26					

i all all all a lat

6.111



I TRANSFORM

Table 3

DATE	RW/MW	DEPTH TO LIQUID (ft)	SPH	WELL DEPTH	E.C.	рН	TEMP.	D.O	ORP
Aur 04					2005	7.00		4.2	102
Aug-04	<u>MW #37</u>	23.99	0	27.58	2085	7.06	62	4.3	-103
Mar-04	<u> </u>	22.94	0	27.58	2033	7.29	57		
Aug-03	 	24.11	0	27.58	2061	7.16	68	6.4	-129
Aug-04	MW #38	24.51	0	26.82	2058	6.84	63	12.3	-124
Mar-04	ļ	24.32	0	26.82	1967	7.11	55		
Aug-03		24.6	0	26.82	1866	6.90	69	4.7	-145
Aug-04	MW #39	24.59	0	38.34	5424	7.51	65	4.7	-162
Mar-04	L	24.45	0	38.34					
Aug-03									d Sel I
Aug-04	MW #40	29.76	28.94	30.07	no sample	well	contains	hydrocarbon	
Mar-04		29.95	29.05	30.07	no sample	well	contains	hydrocarbon	
Aug-03		29.99	28.85	30.07	no sample	well	contains	hydrocarbon	
Aug-04	MW #41	28.34	27.43	31.62	no sample	well	contains	hydrocarbon	
Mar-04		28.41	27.3	31.62	no sample	well	contains	hydrocarbon	
Aug-03		28.52	27.31	31.62	no sample	well	contains	hydrocarbon	
 Aug-04	MW #44	33.8	0	50.91	5589	6.90	60	5.3	-52
Mar-04		33.4	0	50.91					
g-03		33.75	0	50.91					
Aug-03	MW #45	well is		hydrocarbon		fuel fingerprint			
Mar-04		15.85	9.32	16.92		6.97	52		hydrocar
Aug-03	<u> </u>	13.19	9.35	16.92	no sample	well	contains	hydrocarbon	i ju com
Aug-04	MW #46	0	0	10.32	dry	well		nyurocarbon	
Mar-04	10100 #40	0	0	10.39	dry	well		<u>San San San</u> Marine Marine San San San San San San San San San San	
Aug-03		0	0	10.39		well			
	MW #47	11.55			dry fuel fin		ontoine bur	drooorbon	in in internet Second
Aug-04	10100 #47		10.32	14.28		gerprint - co		S. N. 5" 5. 1	
Mar-04		11.79	10.31	14.28	3440	7.01	52	70	75
Aug-03		10.58	0	14.39	3848	6.88	69	7.9	-75
Aug-03	P-#4	8.41	0	13.94	2316	6.92	69	8.4	-240
Mar-04	 	8.29	0	13.94	22398	7.56	46		
Aug-03		8.22	0	13.94	2606	7.06	69	0.2	-284
Aug-04	P-#5	9.24	0	14.27	2014	6.93	67	5.4	-124
Mar-04	 	9.54	0	14.27	2097	7.38	46		a di sa ang
Aug-03	 	10.29	0	14.27	2006	7.16	69	4.5	-104
Aug-04	O/F #2	n/a	n/a	n/a	996	6.88	67	6.3	74
Mar-04	<u> </u>	n/a	n/a	n/a	1199	7.23	47		
Aug-03]	DRY	no sample	DRY	no sample	DRY	no sample		

i din di i v

- 11

Page 3 of 4

1 1

A REPAIR AND A REPAIR AND A REPAIR

Table 3

ATE	RW/MW	DEPTH TO LIQUID (ft)	SPH	WELL DEPTH	E.C.	рН	TEMP.	D.O	ORP
Aug-04	O/F #3	n/a	n/a	n/a	980	6.81	64	9.8	103
Mar-04		n/a	n/a	n/a	1224	7.36	49		
Aug-03		n/a	n/a	n/a	904	7.02	63	7.8	194
Aug-04	RW #3	22.74	22.71	34.57	3138	6.82	67	5.5	-47
Mar-04		22.49	22.43	34.57					
Aug-03		22.68	0	34.57	1.1.1				
Aug-04	RW #14	35.11	2.45	41.94	4422	6.87	62	6.4	-83
Mar-04		36.65	35.21	41.94					
Aug-03		35.14	0	41.94			*		
Aug-04	RW #15	34.92	0	43.43	3481	6.83	61	over range	-85
Mar-04		35,93	0	43.43					SSTAN
Aug-03		34.93	0	43.43					
Aug-04	RW #16	34.03	0	41.94	3162	6.93	62	8.7	-139
Mar-04		35.04	0	41.94					
Aug-03		34.03	0	41.94					
Aug-04	RW #17	33.63	33.37	41.89	fuel fin	ngerprint - c	ontains hyd	drocarbon	and the second second
Mar-04		35.55	35.45	41.89					
g-03		33.34	33.29	41.89					

The second second

- fei i

Table 4

MARCH 2004 - BTEX & MTBE

The second second			HOUT ALS	Solution 11	EPA Me	Method 8021B	8				and the second second	
mg/L	Date Sampled	WQCC 20 NMAC 6.2.3103	1#	MW #12	MW #13	MW #20	MW #32	MW #33	MW #35	MW #37	MW #38	MW #45
Benzene	Benzene Mar-04	0.01	<0.0005	<0.0005	<0.0005	24	<0.0005	<0.0005	0.006	<0.0005	<0.0005	1
Toluene	Mar-04	0.75	<0.0005	<0.0005	<0.0005	12	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.86
EthylBen Mar-04	Mar-04	0.75	<0.0005	<0.0005	<0.0005	0.1	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	7.5
Xylene	Mar-04	0.62	<0.0005	<0.0005	<0.0005	0.5	<0.0005	<0.0005	0.003	0.006	0.001	28
MTBE	MTBE Mar-04		<0.0025	<0.0025	0.02	95	<0.0025	<0.0025	0.011	0.004	0.015	<4.3

MARCH 2004 - BTEX & MTBE

A STATE	The sha	Hallow II. States	E	EPA Method	8021B	Service of the servic			The second second
mg/L	Date Sampled	WQCC 20 NMAC 6.2.3103	MW #47	d #	с ≵	d ₿	O/F #1	0/F #2	0/F #3
Benzene Mar-04	Mar-04	0.01	0.56	4.5	12	13	NOT	<0.0005	<0.0005
Toluene	Mar-04	0.75	<0.05	0.3	<0.05	0.62	SAMPLED <0.0005 <0.0005	<0.0005	<0.0005
EthylBen Mar-04	Mar-04	0.75	0.9	3.6	2	9.1		<0.0005	<0.0005 <0.0005
Xylene	Mar-04	0.62	7.9	15	12	31	er ret	<0.0005	<0.0005
MTBE	Mar-04		<0.25	<0.25	<0.25	26		<0.0025	<0.0025 <0.0025



WQCC 20 NMAC 6.2.3103 0.75 0.75 0.01 0.62 <0.0025 <0.0025 <0.0025 <0.0025 <0.013 <0.0001 <0.0001 <0.0001 <0.0001 <0.0001 MW #27 <0.130 <0.025 <0.05 <0.05 0.46 0.63 0.19 0.35 0.74 MW #26 1.4 <0.0025 0.0098 0.003 0.028 0.13 MW #21 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.001 0.0012 0.049 <0.001 <0.001 <0.001 0.027 0.061 0.02 MM #13 <0.0005 <0.0005 <0.0005 <0.0005 <0.0005 <0.0025 <0.0005 <0.0025 <0.0005 <0.0005 0.00087 <0.0025 0.0013 0.00094 <0.001 <0.001 <0.001 0.015 <0.001 <0.001 MW #12 <0.010 <0.02 0.015 0.079 0.064 0.65 0.17 <0.1 11# MW 1.7 2.7 <0.0005 <0.0005 <0.0005 <0.0025 <0.0005 <0.001 <0.001 <0.001 <0.001 <0.001 **MW** 8# <0.0005 <0.0005 <0.0005 <0.0005 <0.0025 AWW <0.0005 <0.0005 <0.0005 <0.0005 <0.0025 <0.001 <0.001 <0.001 <0.001 <0.001 WW #3 <0.0005 <0.0005 <0.0005 <0.0005 <0.0025 <0.0005 <0.0005 0.00065 <0.0025 <0.0025 <0.0005 <0.0005 <0.0005 <0.001 <0.001 <0.001 0.00063 <0.001 0.0043 <0.001 MW # SAMPLED Aug-04 Aug-03 Aug-03 Aug-03 Aug-04 Aug-04 Aug-04 Mar-04 Aug-04 Mar-04 Mar-03 Aug-03 Mar-03 Mar-04 Mar-03 Mar-04 Aug-03 Mar-03 Mar-03 Mar-04 DATE EthylBen Benzene Toluene Xylene MTBE mg/L **Brsoos bortiem Aga**

(page 1 of 3)

AUG - 2003 Analysis by 8260B

Table 5

ORGANICS AUGUST 2004

Table 5

mg/L	Benzene				Toluene		1		EthylBen				Xylene	inter de		Ben	MTBE			
	_	2	A	2		2	A	2		2	4	2		2	A	2	-	2	A	2
DATE	Aug-04	Mar-04	Aug-03	Mar-03	Aug-04	Mar-04	Aug-03	Mar-03	Aug-04	Mar-04	Aug-03	Mar-03	Aug-04	Mar-04	Aug-03	Mar-03	Aug-04	Mar-04	Aug-03	Mar-03
MW #29	<0.0005		新市市市		<0.0005				<0.0005				<0.0005				0.0026			「「「「「「」」」
MW #30	1.7				0.37				1.9				2.5				<0.10			
MW #31	3.7				0.4				0.32				1.2				<0.250			
MW #32	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	<0.001	<0.001	<0.0025	<0.0025	<0.001	<0.001
MM #33	<0.0005	<0.0005	<0.001	<0.0005	<0.0005	<0.0005	<0.001	<0.0005	<0.0005	<0.0005	<0.001	<0.0005	<0.0005	<0.0005	<0.001	0.00086	<0.0025	<0.0025	<0.001	<0.0025
MW #34	<0.0025		<0.001		0.0039		<0.001		0.019		<0.001		0.013	の神戸の	<0.001	いいための後端	<0.013		<0.001	<0.0025
MW #35	0.00082	0.006	<0.010	0.0038	<0.0005	<0.0005	<0.010	<0.0025	0.0061	<0.0005	<0.010	0.0027	0.0033	0.003	<0.010	0.021	0.0096	0.011	0.02	0.014
MW #36	0.0009				<0.0005				<0.0005				0.004				0.0085			A Real Party
WW #37	<0.0005		0.0013	<0.0025	<0.0005		<0.001	0.0033	0.0012		0.0014	0.0038	0.00062		0.0097	0.031	0.0026		0.0059	<0.013
MW #38	<0.0005		<0.001	<0.0005	<0.0005		<0.001	<0.0005	0.0012		<0.001	<0.0005	0.00068		<0.001	0.0014	0.0085		0.017	0.016
WQCC 20 NMAC 6.2.3103	0.01				0.75				0.75				0.62							

Table 5

ORGANICS AUGUST 2004

-	mg/L	DATE	MW #39	MW #44	RW #3	RW #14	RW #15	RW #16	с <u>‡</u>	с #	0/F #2	0/F #3	WQCC 20 NMAC 6.2.3103
distant distant	Benzene	Aug-04	0.46	<0.0005	0.33	1.9	9.4	2.1	4.1	1	<0.0005	<0.0005	0.01
		Mar-04							4.5	1.2	<0.0005	<0.0005	なななない
-		Aug-03		主要の教育					2.7	1.5		<0.001	
-		Mar-03							4.1	1.3	<0.0005	<0.0005	
and the owned	Toluene	Aug-04	0.15	<0.0005	<0.020	17	15	<005	<005	<005	<0.0005	<0.0005	0.75
		Mar-04							0.3	<0.05	<0.0005	<0.0005	「「大大大学」」
and the second		Aug-03							1.1	<0.25		<0.001	
		Mar-03							0.63	0.078	<0.0005	<0.0005	
and the second	EthylBen	Aug-04	0.55	<0.0005	<0.020	3.2	2.8	0.17	3.3	1.6	<0.0005	<0.0005	0.75
		Mar-04							3.6	2	<0.0005	<0.0005	
And a subset		Aug-03							3	3.3		<0.001	
		Mar-03				Here's and			3.1	3.5	<0.0005	<0.0005	の一般の中心の時代
Concession of the local division of the loca	Xylene	Aug-04	0.92	<0.0005	1.4	20	22	0.82	12	5.8	<0.0005	<0.0005	0.62
A Grand and a state		Mar-04							15	12	<0.0005	<0.0005	
-		Aug-03							8.4	14		<0.001	
		Mar-03							10	19	<0.0005	<0.0005	
	MTBE	Aug-04	<0.050	0.0048	<0.10	<0.10	<0.25	<0.25	<0.25	<0.25	<0.0025	<0.0025	
the state of the s		Mar-04							<0.25	<0.25	<0.0025	<0.0025	
distant of the		Aug-03							<0.25	<0.25		<0.001	
and some of		Mar-03					Salar Charles		<0.10	<0.05	<0.0025	<0.0025	大学のない
1		AUG - 2003	3 Analysis	AUG - 2003 Analysis by 8260B								(page 3 of 3	

ma/L	DATE	MM	MM	MM	MM	MM	MM	MM	MM	MM	MW	-
	SAMPLED	#1	#3	#7	#8	#11	#12	#13	#21	#26	#27	
Fluoride	Aug-04	0.63		0.75	0.64	0.41	0.52	0.2	0.18	0.29	0.2	
	Aug-03	0.58	0.17		0.66	0.44	0.32	0.19		0.39	0.22	
	Aug-02									a state of the second se		
	Sep-01							「日本のある」と			The second	
Chloride	Aug-04	29		25	250	97	130	330	420	230	290	-
	Aug-03	33	1400		260	150	130	510		160	360	_
	Aug-02				Contraction of the local distance of the loc					「「「ない」	Section 1	
	Sep-01			States of the second second second second second second second second second second second second second second	A CONTRACTOR	の時間				ないない	Ballion	
Nitrite	Aug-04	<0.10		<0.10				1.6	<0.10	<0.10	<0.10	0
	Aug-03	<0.10			<0.10	<0.10	<0.10	<0.10		<0.10	<0.10	0
	Aug-02	Receiption of	and the second se	and the second					and the states			
	Sep-01	The state of the		All and a second	A DESCRIPTION OF							影
Bromide	Aug-04	0.14		0.14	1.2	0.97	0.78	4.3	3.4	4.2	3.1	
	Aug-03	0.32	22	のないのでの	5	5.3	3.7	13		2.9	4.7	
	Aug-02											4
	Sep-01											
Nitrogen	Aug-04	1.9	大学を	<0.10				6.6	<0.10	<0.10	<0.10	0
	Aug-03	1.6	41		14	<0.10	<0.10	12		<0.10	<0.10	0
	Aug-02											
	Sep-01										din to the	
٩	Aug-04	<0.50		<0.50	<0.50	<0.50		<0.50	<0.50	<0.50	<0.50	0
	Aug-03	<0.50	<0.50		<0.50	<0.50	<0.50	<0.50		<0.50	<0.50	0
	Aug-02			の日本の								
	Sep-01		の一般のないの									
Sulfate	Aug-04	220		5100	920	13	680	950	1400	<0.50	120	-
	Aug-03	200	1900		950	4.2	3100	840		-	6.8	_
	Aug-02				970	<5.0	a state of	Reserves and	a strategy			RI
	Sep-01	and the second		and the second	760	<5.0	R					
TDS	Aug-04	650		7400	2100	1500	1600	2800	3400	1600	1700	0
	Aug-03	610	5700		2100	1100	5500	3100		1400	1700	0
	Aug-02	「「「「「「」」」」	の一般のない			「「「「」」						
	Sen-01	A CONTRACTOR	日本の日本のための	Party and the		「日日かられた」	No. of a lot of the lo		のいいであるないであるとうと	NV7 PALICIC HOUSE PAR	COLOR DALL	

		U	GENERAL CHEMISTRY	- CHEN	IISTRY	AUGU	AUGUST 2004					Tahlo 6	
	mg/L	DATE	MW #1	MW #3	AWW	WW #8	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	WQCC 20 NMAC 6.2.3103
r.0	E.C.	Aug-04	870		7800	2600	2100	1900	3400	4000	2200	2400	
130		Aug-03	820	8500		2900	2500	6600	5000		1900	3100	
Aqa		Aug-02	795	7358		3263	2140	3010		and the second second	Constant of the	2825	
the second		Sep-01		States and	And the second second	2000	2130		ないの議論				
	D.O.	Aug-04	5.4		2.8	2.9	13.8	9.3	5	4	7.5	1.7	
		Aug-03	6.5	6.5	A CONTRACTOR	7.1	5.6	5.3	5.6	Constantion of	4.9	4.1	
		Aug-02	2.8	4.8		3.8	1.1	ALC: NOT				1.5	
		Sep-01			and a second	13.1	13.9						「東京」と記録の
	O.R.P.	Aug-04	-532	-11	84	142	-36	151	158	-43	-33	-143	South States of the
		Aug-03	105	105		176	-5.3	81	86		-63	-188	
		Aug-02	South States of the second			A NAME OF A							
		Sep-01	Several and a several several several several several several several several several several several several s		Contraction of the local distribution of the					A STATE			
the second	C02	Aug-04	220		98	210	330	970	860	600	910	890	
		Aug-03	240	and the second se		220	1300	310	1000		1300	1200	
1.01		Aug-02	のないない	t in the						All and and and and and and and and and and			
EA		Sep-01									Sector Marine	語の時間で	States of states
EP	AIK	Aug-04	240		110	230	390	1100	950	670	1000	970	
		Aug-03	262			208	1120	319	917	A STATE OF A	1090	1040	
		Aug-02						A STATUTE					
State of the		Sep-01			「「「「「「		「「「「「「」」」		State of the	Sector Sector			

(page 2 of 6)

ĩ						Province of							
	-Jôu	SAMPLED	MW #29	MW #30	MW #31	MW #32	MW #33	MW #34	MW #35	MW #36	WW #37	WW #38	WQCC 20 NMAC
1"	Fluoride	Aug-04	0.31	0.18	0.19	0.24	0.21	0.62	0.36	0.4	0.46	0.53	1.6
110		Aug-03				0.18	0.24	0.57	0.39		0.49	0.67	
		Aug-02									の設定に		
100		Sep-01											
0	Chloride	Aug-04	35	360	370	650	550	100	110	100	86	140	250
THE R		Aug-03				940	750	120	120		110	120	
1955		Aug-02										時にいるのない	A State of the second se
1		Sep-01											
	Nitrite	Aug-04	<0.10	<0.10	<0.10	<0.10		<0.10	<0.10	<0.10	<0.10	<0.10	
2473		Aug-03				<1.0	<1.0	<0.10	<0.10		<0.10	<0.10	「「「「「「「「」」」」」」」」」」」」」」」」」」」」」」」」」」」」」」
-		Aug-02											の日本の
8849		Sep-01											
8	Bromide	Aug-04	<0.10	5.6	7.2	2.9	3.2	1.2	1.2	+	-	1.3	がいた。
		Aug-03				13	19	5.1	2.1		1.3	1.3	
		Aug-02											
L HERE		Sep-01											
Z	Nitrogen	Aug-04	0.6	<0.10	0.14	5		<0.10	<0.10	<0.10	<0.10	<0.10	10
5.00		Aug-03				22	26	<0.10	<0.10		<0.10	<0.10	
2452		Aug-02											の時間にある
FROM:		Sep-01											「「「「「「「」」」」
100	٩	Aug-04	<0.50	<0.10	<0.50	<0.50	QN	<0.50	<0.50	<0.50	<0.50	<0.50	「「「「「「」」」
10.00		Aug-03	調査を	の記録		<0.50	<0.50	<0.50	<0.50		<0.50	<0.50	State
		Aug-02											
1		Sep-01											語りの現代
55	Sulfate	Aug-04	150	720	750	580	1600	29	1.7	16	15	330	600
0.000		Aug-03				1200	1200	150	6.6		19	310	- the second second
10.0		Aug-02						9.1	28				「「「「「「「「」」」」
1042		Sep-01						<5.0	27				
	TDS	Aug-04	550	3100	2800	2400	3700	1500	1400	1200	1300	1500	1000
91 1		Aug-03	構成などの			3800	3400	1700	1300		1400	1600	- Destanging the start
		Aug-02	and a second sec							のないの言語を			
1		Sep-01	State State State		あっていたいであっ	「「「「「」」			Property and color with	and the second second second	C. Brief Contraction		のないです。ここの時間でも

	_	
1		
1		

GENERAL CHEMISTRY AUGUST 2004

Table 6

mg/L	DATE	MW #29	MW #30	MW #31	MW #32	MW #33	MW #34	MW #35	MW #36	MW #37	MW #38	WQCC 20 NMAC 6.2.3103
E.C.	Aug-04	760	3900	3700	3300	4400	2100	2000	1700	1800	1800	
	Aug-03		Service of the servic	Service Service	5800	5000	2800	1900	and a start	1800	1900	
	Aug-02	Sector Sector		a statement			2130	1923	1386			
	Sep-01	の変換する		Section 2			2020	2200	Same and	の言語		
D.O.	Aug-04	4.7	over range	3.4	5.6	5.6	1.7	3.6	8.4	4.3	12.3	
	Aug-03			Total Andrews	7.4	5	4.9	5.4		6.4	4.7	
	Aug-02	and the second					2	2.1	2.4			
	Sep-01	「日本のない」という		a strange			4.2	6.9	。"法也 ,通知			
O.R.P.	Aug-04	115	-196	-19	6/	-7.3	-51	-63	-111	-103	-124	
	Aug-03	A States		- Handard	64	110	-76	-95		-129	-145	
	Aug-02							Sector Sector				
	Sep-01	States of					and the second		Same and	States of the		
C02	Aug-04	210	1200	980	280	140	066	910	880	940	590	The state of the second second second second second second second second second second second second second se
	Aug-03				250	190	1300	1100		960	670	
	Aug-02			and a second								
	Sep-01			「「「「「」								
AIk	Aug-04	240	1400	1100	310	150	1100	1000	970	1000	660	
	Aug-03				242	198	1130	984	のないの	1010	600	
	Aug-02			のないです。		の時代		構築であ				語を行うに認め
	Sep-01	and the second	「「「「「「「」」」		「小人」という		Station of the					ないという

(page 4 of 6)

RW P #16 #4 0.3 0.24 0.3 0.24 0.3 0.24 460 77 460 77 460 74 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -0.10 -0.1 -1.4 -0.1 -1.4 -0.1 -1.4 -0.5 -1.14 -0.5 -1.17 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14 -0.1 -1.14<	R 0.29 0.24 0.24 0.24 0.24 77 7 7 7 7 74 7 74 7 74 7 74 7 74 7 74 7 74 7 74 7 74 7 1.4 1.4 1.4 1.5 1.4 1.4 1.4 1.4 1.4 1.5 1.4 1.4 1.4 1.5 1.4 1.4<
	F O/F #2 0.09 0.637 0.67 0.089 0.67 0 0.09 23 23 100 23 23 72 0.13 23 73 0.13 23 74 0.13 23 155 2010 235 0.944 0.13 25 155 2.5 200 2010 2.5 2.5 2010 2.5 2.5 2010 2.5 2.5 200 2.5 2.5 200 2.5 2.5 200 2.5 2.5 200 2.5 2.5 200 2.5 2.5 200 2.5 2.5 2.55 2.500 5.5



GENERAL CHEMISTRY AUGUST 2004



Table 6

	DATE SAMPLED Aug-04	MM	MM	RW	RW	Ma	DW		0	UN OF		
	Aug-04	#39	#44	84	#14	#15	#16	r #	1 #	#2	5 \$	WGCC 20 NMAC 6.2.3103
L.021		5200	5200	2800	4000	3100	2800	2300	2000	880	830	
P.OSF O.	Aug-03	- States						2800	2400		780	
	Aug-02	States of the second			and the second	3910			「「「「「」」	Statistics.	a statistical sector	
	Sep-01	State of the			and the second	2900	A State					
\vdash	Aug-04	4.7	5.3	5.5	6.4	over range	8.7	8.4	5.4	6.3	9.8	
	Aug-03						Constanting of the	0.2	4.5		7.8	A CONTRACTOR
	Aug-02					2		ALC: NO.		のないという	A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A	
	Sep-01	A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A	And the second second	Service of the servic		6.3						
O.R.P.	Aug-04	-162	-52	-47	-83	-85	-139	-240	-126	74	103	
	Aug-03							-284	-104		194	たなないである
4	Aug-02							States and		a state of the second	and the second second	
	Sep-01	Later	A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A COLUMN TO A C					ないである		State of the second second second second second second second second second second second second second second		
C02 /	Aug-04	35	400	1100	1100	1100	006	1300	1000	250	240	
	Aug-03		Sector Sector					1300	1100		270	
	Aug-02			And a state of the	Developments Longeronness					のです。	and the second	
	Sep-01									instanting in		
E Alk /	Aug-04	38	450	1200	1200	1300	1000	1500	1200	280	270	
高麗	Aug-03			- States				1390	1170		252	
1	Aug-02	「「「「「	のないである。		Stand State			Constanting of the second		All solutions		
	Sep-01			and the second se	and the second second			and the second second	A Designation	Statistics and		

(page 6 of 6)

	3	102210	DISSOLVED MEIAL	וארמ	- DOCK	1004 0000	-				1 217121	
EPA Me	EPA Method 6010C	Columnation of the second		The second second				THE REAL PROPERTY IN				
mg/L	DATE	MW #1	MW #3	14 WW	MW #8	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	WQCC 20 NMAC 6.2.3103
Arsenic	Aug-04	<0.02	No Sample	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.10
	Aug-03	<0.02	<0.02		<0.02	<0.02	<0.02	<0.02		<0.02	<0.02	
	Aug-02											
	Sep-01											
Barium	Aug-04	0.025	No Sample	0.0097	0.021	0.47	0.06	0.022	0.028	1.8	0.083	1.00
	Aug-03	0.46	0.3		0.36	1.2	0.12	0.33		2.3	0.52	
	Aug-02											
	Sep-01											
Cadmium	Aug-04	<0.002	No Sample	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.01
	Aug-03	<0.002	<0.002		<0.002	<0.002	<0.002	<0.002		<0.002	<0.002	
	Aug-02											
	Sep-01								Salah Salah			
Calcium	Aug-04	67	No Sample	300	210	100	130	210	450	75	170	
	Aug-03	61	490		200	120	420	270		91	210	
	Aug-02											
	Sep-01											
Ċ	Aug-04	<0.006	No Sample	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	0.05
	Aug-03	<0.006	<0.006		<0.006	<0.006	0.0066	<0.006		0.0089	<0.006	
	Aug-02											
	Sep-01											
Copper	Aug-04	<0.006	No Sample	<0.006	<0.006	0.021	<0.006	<0.006	<0.006	<0.006	<0.006	1.00
	Aug-03	<0.006	<0.006		<0.006	<0.006	<0.006	0.0096		<0.006	<0.006	
	Aug-02											
	Sep-01											
Iron	Aug-04	0.27	No Sample	0.081	0.059	6.9	0.044	0.046	2.9	5.1	0.15	1.00
	Aug-03	<0.005	0.27		0.044	7.6	0.024	0.04		5	0.44	
	Aug-02	and the second	「「「「「「」」」」」」」」」」」」」」」」」」」」」」」」」」」」」」」		1.5	10		a desired				
	Sep-01		States and						and the second	- 0000		秋 日本 2018年
												010111

DISSOLVED METALS AUGUST 2004

Table 7

mg/L	g/L DATE SAMPLED	MW #1	MW #3	MM #L	MW #8	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	WECC 20 NMAC 6.2.3103
Lead	Aug-04	<0.005	No Sample	<0.005	<0.005	0.022	<0.005	<0.005	<0.005	0.0056	<0.005	0.05
	Aug-03	<0.005	<0.005		<0.005	<0.005	<0.005	<0.005		<0.005	<0.005	
	Aug-02											
	Sep-01											
Mg	Aug-04	18	No Sample	31	35	23	31	80	97	27	26	
	Aug-03	16	140		38	25	130	110		32	34	
	Aug-02											
	Sep-01	「大学の変化										
Mn	Aug-04	0.13	No Sample	0.28	0.57	1.7	0.55	0.58	1.4	2	0.94	0.20
	Aug-03	0.08	0.58		0.68	2	1.8	1.1		2.4	1.4	
	Aug-02											
	Sep-01											
¥	Aug-04	2.1	No Sample	8.1	3	1.5	1.5	3.6	6.8	2.6	206	
	Aug-03	2.6	10		4	2.3	4.3	5.3		4.2	4	
	Aug-02											
	Sep-01											
Se	Aug-04	<0.05	No Sample	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03	0.043	0.024		0.09	0.15	0.084	0.16		0.1	0.13	
	Aug-02				and a second				Real Andrews		Section 2	
	Sep-01											
Silver	Aug-04	<0.005	No Sample	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.05
	Aug-03	<0.005	<0.005		<0.005	<0.005	<0.005	<0.005		<0.005	<0.005	
	Aug-02											
	Sep-01							and the second				
Sodium	Aug-04	110	No Sample	1100	360	390	320	610	600	440	390	
	Aug-03	150	1100		350	420	960	680		430	420	
	Aug-02											
	Sep-01											

Page 2 of 12

DISSOLVED METALS AUGUST 2004

Table 7

I Me	Method 6010C	No. of Concession, No.				0						•
mg/L	DATE	MW #1	8# #3	L#	8#	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	WECC 20 NMAC 6.2.3103
Uranium	Aug-04	<0.1	No Sample	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	5.00
	Aug-03	<0.1	<0.1		<0.1	<0.1	<0.1	<0.1		<0.1	<0.1	
	Aug-02											
	Sep-01											
Zinc	Aug-04	0.021	No Sample	0.0096	0.022	63	0.035	0.021	0.028	0.013	0.011	10.00
	Aug-03	0.12	0.094		0.13	0.18	0.088	0.09		0.19	0.037	
	Aug-02											
	Sep-01											
										Contraction of the local division of the loc	Contraction of the local division of the loc	Characteristics in the second s

DISSOLVED METALS AUGUST 2004

MW MM MW MW MW<	EPA Me	EPA Method 6010C											
Aug-04 <0.02	mg/L	DATE	MW #29	MW #30	MW #31	MW #32	MW #33	MW #34	MW #35	MW #36	MW #37	MW #38	WQCC 20 NMAC 6.2.3103
Aug-03 ···· <	Arsenic	Aug-04	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.10
Aug-02 Sep-01 Sep-01 Solution S		Aug-03		「「「「「」」		<0.02	<0.02	<0.02	<0.02		<0.02	<0.02	
SepO1 SepO1 <th< th=""><th></th><th>Aug-02</th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th></th<>		Aug-02											
Aug-04 0.025 0.13 0.35 0.022 0.02 0.78 0.71 0.59 0.28 Aug-03 wug-03 wug-		Sep-01											
Aug-03 Lug-03 0.35 0.02 1.5 1 1.5 Aug-02 Aug-02 N <t< th=""><th>Barium</th><th>Aug-04</th><th>0.025</th><th>0.13</th><th>0.35</th><th>0.022</th><th>0.02</th><th>0.78</th><th>0.71</th><th>0.59</th><th>0.28</th><th>0.19</th><th>1.00</th></t<>	Barium	Aug-04	0.025	0.13	0.35	0.022	0.02	0.78	0.71	0.59	0.28	0.19	1.00
Aug-02 Aug-02 Sep-01 Sep-01<		Aug-03				0.35	0.02	1.5			1.5	0.37	
Sep-01 Sep-01<		Aug-02											
Aug-04 <	1	Sep-01								の一般			のないという
Aug-03 Verture Co.002 C0.002	Cadmium		<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.01
Aug-02 Aug-02 Sep-01		Aug-03				<0.002	<0.002	<0.002	<0.002		<0.002	<0.002	
Sep-01 Sep-01		Aug-02											
Aug-04 55 350 220 170 350 110 130 150 Aug-03 370 330 110 130 150 Aug-02 370 330 110 130 150 Sep-01 <td< th=""><th></th><td>Sep-01</td><td></td><td></td><td></td><td>のないである。</td><td></td><td></td><td></td><td>の時代の</td><td></td><td></td><td></td></td<>		Sep-01				のないである。				の時代の			
370 330 110 130	Calcium	Aug-04	55	350	220	170	350	110	130	150	100	180	
Aug-02 Sep-01		Aug-03		のないため		370	330	110	130	A THE	100	170	
Sep-01		Aug-02		の時代	「「「「「」」						a state of the second se		
		Sep-01											

Page 3 of 12

Me Me	Method 6010C	0										
mg/L	DATE	MW #29	MW #30	MW #31	MW #32	MW #33	MW #34	MW #35	MW #36	MW #37	MW #38	WECC 20 NMAC 6.2.3103
IJ	Aug-04	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	0.05
	Aug-03				<0.006	<0.008	<0.006	<0.006		<0.006	<0.006	
	Aug-02											
	Sep-01											
Copper	Aug-04	<0.006	0.0061	<0.006	<0.006	0.0062	0.015	0.0065	<0.006	<0.006	<0.006	1.00
	Aug-03				<0.006	<0.006	<0.006	<0.006		<0.006	<0.006	
	Aug-02						Apple and the second					
	Sep-01											
Iron	Aug-04	<0.005	4.7	0.46	0.056	0.11	5.6	7.2	3.1	1.5	8	1.00
	Aug-03				0.031	<0.005	5.5	6.3		0.6	7.5	
	Aug-02						9.6	9.3				
	Sep-01											
Lead	Aug-04	<0.005	0.0051	<0.005	<0.005	<0.005	<0.005	0.0063	<0.005	<0.005	<0.005	0.05
	Aug-03				<0.005	<0.005	<0.005	<0.005		<0.005	<0.005	
	Aug-02											
	Sep-01											
Mg	Aug-04	15	88	67	26	54	20	23	30	19	32	
	Aug-03				56	51	21	22		20	28	
	Aug-02											
	Sep-01											
Mn	Aug-04	0.82	2.1	0.58	<0.002	0.013	4.3	3.1	4.1	1.3	3.6	0.20
	Aug-03				0.0037	0.01	4.6	3.3		1.4	3	
	Aug-02											
	Sep-01											
¥	Aug-04	2.7	<10.0	4.8	2.7	5.3	1.3	S	7.2	5	4.7	
	Aug-03				5	6.2	2.1	3.7		6.6	6.6	
	Aug-02											
	Con 01	「「「「「「」」」」				のないとないのないの			のなどの意見したない	のなどのなどのないという	いたいであるとなっていた	「「「「「「「「「「「「「」」」」」

Page 4 of 12

in property

2004	
AUGUST	
S AL	
METAL	
LVED	
DISSOL	

Table 7

A Me	A Method 6010C	0				0		and the second se				
mg/L	DATE	MW #29	MW #30	MW #31	MW #32	MW #33	MW #34	MW #35	MW #36	MW #37	MW #38	WOCC 20 NMAC 6.2.3103
Se	Aug-04	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03				0.05	0.023	0.15	0.15		0.13	0.11	
-	Aug-02	「「「「										
	Sep-01										State of the	All and a second second
Silver	Aug-04	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.05
	Aug-03		No. of the other		<0.005	<0.005	<0.005	<0.005		<0.005	<0.005	一人は彼なな
	Aug-02	and the state							and the second second	日間間間		A STATE OF A
	Sep-01											
Sodium	Aug-04	100	750	640	550	670	400	300	180	350	250	
	Aug-03				800	660	470	330		370	240	
	Aug-02								and the second			
	Sep-01		a a second a second							のであると		
Uranium	Aug-04	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	5.00
	Aug-03				<0.1	<0.1	<0.1	<0.1		<0.1	<0.1	
	Aug-02											
	Sep-01								ないたので			
Zinc	Aug-04	0.017	0.046	0.019	0.019	0.031	0.02	0.022	0.018	0.028	0.035	10.00
	Aug-03	No. of Concession, State	la serie de la ser	and the second second	0.095	0.0072	0.15	0.078		0.29	0.31	
	Aug-02											
	Sep-01							and a state of	South States			のないという

4
2004
N
F
3
AUGUST
Ď
4
5
F
F
METALS
/ED
2
1
0
IOSSIC
ž
-

Table 7

mg/L												The second second second second second second second second second second second second second second second se
	DATE	MW #39	MW #44	RW #3	RW #14	RW #15	RW #16	с #	#5 #	0/F #2	0/F #3	WECC 20 NMAC 6.2.3103
Arsenic	Aug-04	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.10
	Aug-03							<0.02	<0.02		<0.02	
	Aug-02											
	Sep-01											
Barium	Aug-04	0.15	0.046	0.12	1.7	1.2	0.35	0.43	0.42	0.048	0.03	1.00
	Aug-03							0.91	0.71		0.25	
	Aug-02											
	Sep-01											
Cadmium		<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.01
	Aug-03							<0.002	<0.002		<0.002	
	Aug-02											
	Sep-01											
Calcium	Aug-04	290	520	85	180	160	100	84	150	95	98	- Patrices
	Aug-03							120	150		79	
	Aug-02											
	Sep-01											
ŗ	Aug-04	<0.006	0.034	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	0.0071	<0.006	0.05
	Aug-03							<0.006	<0.006		<0.006	
	Aug-02									のないで、		
	Sep-01									「「「「「「「」」		
Copper	Aug-04	<0.006	0.027	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	1.00
	Aug-03					and a state		<0.006	<0.006	A DAMAGE	<0.006	
	Aug-02			大学の記録								
	Sep-01											
Iron	Aug-04	0.18	76	0.48	8.5	8	1.9	0.067		<0.02	0.024	1.00
	Aug-03							<0.02	0.91		<0.02	
	Aug-02		東京	All and a second				「「「「「「「「」」」」」」」」」」」」」」」」」」」」」」」」」」」」」」		1. C. S. C.	の時間に	
	Sep-01							English of				

Page 6 of 12

(DISSOL	DISSOLVED METAL	ETALS	AUGU	AUGUST 2004	_				Table 7	
A Me	Method 6010C	0						THE R			ABA LA	
mg/L	DATE	MW #39	MW #44	RW #3	RW #14	RW #15	RW #16	4 P	4 \$	0/F #2	0/F #3	WGCC 20 NMAC 6.2.3103
Lead	Aug-04	<0.005	0.015	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.05
	Aug-03						A State	<0.005	<0.005		<0.005	
	Aug-02	a state of the second			A DESCRIPTION						時代であるという	
	Sep-01											
Mg	Aug-04	28	87	21	87	52	56	19	31	23	22	
	Aug-03	のないなど					State State	35	16		18	
	Aug-02	The second second										
	Sep-01											
Mn	Aug-04	0.3	1.7	1.1	3.6	3.3	1.7	0.021	0.26	0.0038	0.019	0.20
	Aug-03							0.17	2.1		0.017	
	Aug-02											
	Sep-01	No. of the second second second second second second second second second second second second second second s										
¥	Aug-04	8.7	44	3.4	<10.0	3.7	3.3	4	3.7	2.3	1.8	
	Aug-03							5.3	2.8		2.1	
	Aug-02		* CENERAL PARTY	and the second								
	Sep-01						and the second se					
Se	Aug-04	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03	A STATE OF						0.11	0.13		0.032	
	Aug-02											「「「「「
	Sep-01						- la fata an					
Silver	Aug-04	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.05
	Aug-03		構築が必要				a state of the second se	<0.005	<0.005		<0.005	
	Aug-02				の一般の		にいたのと言語	State State				
	Sep-01											and the second second of the second s
Sodium	Aug-04	750	970	620	810	580	560	510	330	100	06	
	Aug-03					A State	日本での	340	130		88	
	Aug-02					and the second second						
	Sep-01											

Page 7 of 12

DISSOLVED METALS AUGUST 2004

Table 7

A Mé	Method 6010C	0		The second second second second second second second second second second second second second second second se	の記載を	-	States and		記録後の話	A Constant of the	ALC: NO.	
mg/L	DATE	MW #39	MW #44	RW #3	RW #14	RW #15	RW #16	4 A	#2	0/F #2	0/F #3	WECC 20 NMAC 6.2.3103
Uranium	Aug-04	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	5.00
	Aug-03							<0.10	<0.10		<0.10	
	Aug-02											
	Sep-01										States and the second	
Zinc	Aug-04	<0.005	0.084	0.036	0.044	0.043	0.029	0.016	0.029	0.034	0.014	10.00
	Aug-03							0.07	0.093		0.04	
	Aug-02											
	Sep-01											

		14	TOTAL ME	L META	1	AUGUST 2004	2004			.0.02/	Table 7	
AME	A Method 6010C	, EPA	Viet		ercury							40 R141.62
mg/L	Date Sampled	MW #1	WW #3	MW #7	MW #8	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	MCL
Arsenic	Aug-04	<0.02	No Sample	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.01
	Aug-03											
	Aug-02											
10074	Sep-01											
Barium	Aug-04	0.052	No Sample	<0.002	0.071	0.54	0.19	0.028	0.029	2	0.13	2
	Aug-03											
echuste.	Aug-02											
	Sep-01											
Cadmium	-	<0.002	No Sample	<0.002	<0.002	<0.002	0.003	<0.002	<0.002	<0.002	<0.002	0.005
	Aug-03											
	Aug-02											
	Sep-01											
Ċ	Aug-04	<0.006	No Sample	<0.006	1.9	<0.006	0.11	0.085	<0.006	<0.006	0.019	0.1
	Aug-03	0.013	0.029		0.72	0.011	0.51	0.45		0.017	0.014	
	Aug-02											
111 Har - 11	Sep-01											
Lead	Aug-04	<0.005	No Sample	<0.005	<0.005	0.027	0.18	<0.005	<0.005	<0.005	<0.005	0.015
8	Aug-03	<0.005	0.022		<0.005	0.02	0.16	<0.005		0.0084	<0.005	
	Aug-02											
	Sep-01											
Se	Aug-04	<0.05	No Sample	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03											
	Aug-02							and the second second second second second second second second second second second second second second secon				
	Sep-01											
Silver	Aug-04	<0.005	No Sample	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	
	Aug-03											
3	Aug-02											
	Sep-01											

Page 9 of 12

(TOTA	L META	A SUN	FOTAL METALS AUGUST 2004	2004				Table 7	
AMe	thod 6010	C, EPA	Nethod 74	70: Mercury	, Ann					A REPORT		FR141.62
mg/L	Date Sampled	MM #1	MW #3	L#	MW #8	MW #11	MW #12	MW #13	MW #21	MW #26	MW #27	MCL
Mercury	Aug-04	<0.0002	No Sample	<0.0002	<0.0002	<0.0002	0.0005	<0.0002	<0.0002	<0.0002 <0.0002 <0.0002	<0.0002	0.002
	Aug-03	<0.0002	<0.0002		<0.0002	0.00026	<0.0002	<0.0002		<0.0002	<0.0002	
	Aug-02		の理論の言語									
	Sep-01											

TOTAL METALS AUGUST 2004

EPA Me	EPA Method 6010C, EPA Method	C, EFAN	- nolliau	Incioin							A LOW TO A L	70-1+11100+
mg/L	Date	MM	MM	MM	MM	MM	MM	MM	MM	MM	MM	
	Sampled	#29	#30	#31	#32	#33	#34	#35	#36	#37	#38	MCL
Arsenic	Aug-04	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.01
	Aug-03					A State of the second se			and the second second			
	Aug-02											
	Sep-01						and the second second					
Barium	Aug-04	0.039	0.24	0.35	0.049	0.038	0.94	1.2	2.6	1.3	0.74	2
	Aug-03											
	Aug-02											
	Sep-01											
Cadmium	Aug-04	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.005
	Aug-03											
	Aug-02	ting the second	and the second second	A STATISTICS								
	Sep-01								and the second second			建筑和 此外生产。
ŗ	Aug-04	<0.006	0.0073	0.0088	<0.006	<0.006	<0.006	<0.006	0.025	0.018	0.079	0.1
	Aug-03	なないない			<0.006	<0.006	0.018	0.011		0.18	0.31	
	Aug-02	Statistics of			のないである	States and						
	Sep-01						「「「「「「」」」					
Lead	Aug-04	<0.005	0.011	<0.005	<0.005	0.0067	<0.005	0.0067	0.0072	0.05	0.028	0.015
	Aug-03	and the state			<0.005	<0.005	<0.005	<0.005	and the second s	0.18	0.21	記録のため、
	Aug-02					ないためでした。			学校に			
	Sep-01											

Page 10 of 12

-	
	L
C	2
C	3
~	1
2004	٠
	7
(1	٦
-	2
ALIGUST	3
	ā.
C)
-	
-	,
-	٢
-	4
U	0
U	
V	
V	
V	
V	
V	
V	
METAI	
METAI	
V	
TAI METAI	
TAI METAI	
TAI METAI	
METAI	

	A REAL PROPERTY OF THE PARTY OF		AIUI			AUGUSI 2004	2004				lable 7	
I WO		C, EFAN		HU: Mercul	ury MM		MM	MAN	MW	MAN	MAN	4 CH 141.62
1/511	Sampled	#29	#30	#31	#32	#33	#34	#35	#36	#37	#38	MCL
Se	Aug-04	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03											
	Aug-02											
	Sep-01											
Silver	Aug-04	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	
	Aug-03											「「「「「「「「「」」」「「」」」「「」」」」
	Aug-02											
	Sep-01											
Mercury	Aug-04	<0.0002	0.00023	0.00022	<0.0002		0.00069 <0.0002	<0.0002	0.00031	0.00044	0.0012	0.002
	Aug-03				<0.0002	<0.0002	<0.0002	<0.0002		<0.0002	<0.0002	P. B. S. S. S. S. S. S. S. S. S. S. S. S. S.
	Aug-02		and the second second	の一般なない			Active Augure					
	Sep-01											

TOTAL METALS AUGUST 2004

mg/L I Sa Arsenic A		No. of Concession, Name of			A REAL PROPERTY OF THE PARTY OF						The second secon	
-	Campled	WW	MW	RW #3	RW	RW #15	RW #15	d ž	d #	O/F	0/F	
	Aug-04	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.01
-	Aug-03	Non-										
A	Aug-02											の時間になった。
Ō	Sep-01					All All All All All All All All All All		Section 1				
Barium	Aug-04	0.71	0.084	0.17	1.8	1.2	0.67	0.58	0.52	0.055	0.032	2
A	Aug-03											
A	Aug-02											
S	Sep-01											
Cadmium A	Aug-04	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.005
A	Aug-03											の時間に
A	Aug-02										1998년 1999년 1999년 1999년 >1999년 1999년	
S	Sep-01			and the second se				and the second second				

Page 11 of 12

-
2004
2
2
5
5
10
2
AUGUST
-
-
5
-
METALS
F
ш
5
-
_
•
F
O
TOTAL
-

1		-
		-
	2	2
	2	2
1	6	
1	Ľ	-
1		

mg/L	g/L Date MW MW RW	MM	MM		RW	RW	RW	۹.	۹.	OF	OF	
	Sampled	60#	#44	の神	#14	#15	91#	-	0#	7#	2#	MCL
Cr	Aug-04	0.59	0.1	<0.006	<0.006	<0.006	0.012	<0.006	<0.006	0.0069	<0.006	0.1
	Aug-03			and the second				<0.006	<0.006	「「「「「	<0.006	
	Aug-02									一日の語の		「「「「「「「」」」
	Sep-01			in state of the			and the second second		No.	A STATE OF		の時間に
Lead	Aug-04	0.019	0.036	0.0068	<0.005	<0.005	<0.005	0.0082	0.011	<0.005	<0.005	0.015
	Aug-03							0.007	0.0066		<0.005	
	Aug-02						State State		「本市市市市」	and the second second		
	Sep-01											
Se	Aug-04	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
	Aug-03			and the second second		the state of the s				Contraction of the second	No. States of the second second second second second second second second second second second second second s	
	Aug-02		Constantion (Service Servic			a state of the second se		
	Sep-01					South States			Part of the	State State		
Silver	Aug-04	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	
	Aug-03		A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A STATE OF A	Solution and	and the second second							
	Aug-02											
	Sep-01											
Mercury	Aug-04	0.00021	0.00033	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	0.002
	Aug-03							<0.0002	<0.0002	などの	<0.0002	
	Aug-02		の変要が					A STATE STATE				
	Sep-01											

FUEL FINGERPRINTING AUGUST 2004

Table 8

	「日本の		EP	A Method 8015	8			
wt%	Date Sampled	Ч \$	MW #25	Draw North of MW #45	MW #45	MW #47	#2 Stormwater Outfall	RW #17
Diesel Range	Aug-04	4.4	11	79	72	10	Q	50
Motor Oil Range	Aug-04	QN	QN	Q	Q	Q	Q	Q
Gasoline Range	Aug-04	82	6.2	9.3	30	84	2.4	25

Temporary Piezometers 2004

					WCCC 20 NMAC 6.2.3103		0.01	0.75	0.75	0.62
TP #8		4.4	<5.0	89		<0.25	0.87	0.34	3.1	33
TP #7		<1.0	<5.0	1.7		<0.25	0.0055	<0.05	0.015	0.22
TP #6		<1.0	<5.0	13		<0.25	0.098	<0.05	:	3.9
TP #5		<1.0	<5.0	67		<0.25	0.28	<0.05	22	3
TP #4	0158	1.3	<5.0	22	0218	<0.25	<0.05	<0.05	0.81	1.6
тр #3	EPA Method 8015B	<1.0	<5.0	1.8	EPA Method 8021B	<0.25	0.0035	0.023	0.051	0.31
TP #2	EP/	1.3	<5.0	92	ŝ	<0.25	3.1	8.2	4.2	27
TP #1	and the second	6.1	<5.0	140		<0.25	1.2	0.34	5.2	39
mg/L	A CONTRACTOR OF A CONTRACTOR OF A CONTRACTOR OF A CONTRACTOR OF A CONTRACTOR OF A CONTRACTOR OF A CONTRACTOR A	Diesel Range	Motor Oil Range	Gasoline Range		MTBE	Benzene	Touluene	Ethylbenzene	Xylenes
Date Sampled		10/28/04	10/28/04	10/28/04		10/28/04	10/28/04	10/28/04	10/28/04	10/28/04



			Monitori	onitoring Well #48		Insta	Installed 10/28/04	8/04		
A STATUS	States and a state of the	and the second	EPA	A Method 8260B	the state of the state of the		And a state of the	EPAN	Method 8(1168
Depth	DATE	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG
Sampled	SAMPLED	benzene	toluene	ethylbenzene	naphthalene	total xylene	MTBE	DRO	GRO	MRO
5' - 6.5'	10/28/04	<1.0	<1.0	6.9	14	110	<1.0	140	1500	<50
10' - 11.5'	10/28/04	<0.05	<0.05	0.7	0.24	4.5	<0.05	<10	55	<50
15' - 16.5'	15' - 16.5' 10/28/04	<0.05	<0.05	0.12	0.16	0.78	<0.05	<10	20	<50

Soil Analysis

			Monitori	Monitoring Well #49		Insta	Installed 10/28/04	8/04		
			EPA	Method 8260B		AND ADDRESS AND ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS		EPA	Method 8	015B
Depth	DATE	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG	mg/KG
Sampled	SAMPLED	benzene	toluene	ethylbenzene	-	naphthalene total xylene	MTBE	DRO	GRO	MRO
5' - 6.5'	10/28/04	<0.25	<0.25	0.35	0.9	2.4	<0.25	39	550	<50
10' - 11.5'	10/28/04	<0.05	<0.05	0.13	0.45	2.3	<0.05	<10	110	<50
15' - 16.5' 10/28/0	10/28/04	<0.05	<0.05	<0.05	<0.1	<0.05	<0.05	<10	<5.0	<50



Water Analysis

Table 11

Organics

MONITORING WELL #48

Installed 10/28/04

		EPA Method 8260B / 8021B	lethod 8021B				EPA Method 8015B			EPA Methaod 8310	
DATE	ppm benzene	ppm ppm benzene toluene	ppm ethylbenzene	ppm MTBE	ppm total xylene	mg/L DRO	mg/L MRO	mg/L GRO	ppm Napthalene	ppm 1-Methyl Naphthalene	ppm 2-Methyl Naphthalene
WQCC 20NMAC 6.2.3103	0.01	0.75	0.75		0.62			3(10)	0.03	0.03	0.03
11/1/2004 (8260B)	0.89	<0.1	3.7	<0.1	24	1.5	<5.0	51	0.56	0.16	0.25
12/27/2004 (8021B)	0.69	<0.05	1.9	<025	8.2	<1.0	<5.0	28	0.19	0.069	0.076

General Chemistry

			EPAN	EPA Method 300.0				EPA 160.1	EPA 120.1	150.1
	DATE m SAMPLED Flu	mg/L Fluoride	mg/L Chloride	mg/L Nitrite	mg/L Nitrogen	mg/L	mg/L Sulfate	mg/L TDS	mg/L E.C.	풥
WQCC 20N	MAC	1.6	250		10		600	1000		6.0 - 9.0
	11/1/04	0.54	120	<0.10	<0.10	<0.50	250	1500	2700	7.88
	S LANGER									



Dissolved Metals

Table 11

MONITORING WELL #48

and the second s	A NAME AND A DESCRIPTION OF A DESCRIPTIO	all and the			EPA Method 6010C	od 6010C			S. New Mark	A DESCRIPTION OF THE OWNER OWNER OF THE OWNER OWNER OF THE OWNER	and a set of the	
WQCC 20 NMAC 6.2.3103	0.10	1.00	0.01	0.05	10.0	1.00	0.05		0.20			10.00
DATE	mg/L Arsenic	mg/L Barium	mg/L Cadmium	mg/L Cr	mg/L Cu	mg/L Iron	mg/L Lead	mg/L Mg	mg/L Mn	mg/L K	mg/L Sodium	mg/L Zn
11/1/04	<0.02	0.21	<0.002	<0.006	<0.006	0.16	0.014		0.55			0.026

Total Metals

御史のため、あいしいの		ないというという	たいための自己を知	- The manual of the	EPA Method 5010C	d 6010C	and the second second	Sand Street Street	THE WAY AND AND	IN STATISTICS IN STATISTICS	International Internation	THE REPORT OF
40 CFR 141.62 MCL	0.01	2.00	0.01		0.10		0.02					
DATE	mg/L Arsenic	mg/L Barium	mg/L Cadmium	mg/L Calcium	mg/L Cr	mg/L Iron	mg/L Lead	mg/L Mg	mg/L Mn	mg/L K	mg/L Sodium	zn Zn
11/1/04	<0.02	0.32	<0.002	130	0.0092	19	0.023	22	2.4	6.9	400	0.056

0

Water Analysis

Organics

MONITORING WELL #49

Installed 10/28/04

Table 11

		EPA Method 8260B / 8021B	Nethod 8021B				EPA Method 8015B			EPA Methaod 8310	
DATE Sampled	ppm benzene	ppm ppm benzene toluene	ppm ethylbenzene	ppm MTBE	ppm total xylene	mg/L DRO	mg/L MRO	mg/L GRO	ppm Napthalene	ppm ppm 1-Methyl Napthalene Naphthalene	ppm 2-Methyl Naphthalene
WQCC 20NMAC 6.2.3103	0.01	0.75	0.75		0.62				0.03	0.03	0.03
11/1/2004 (8260B)	<0.01	<0.01	0.015	<0.01	0.32	<1.0	<5.0	1.8	0.0067	0.01	0.006
12/27/2004 (8021B) 0.0097	0.0097	<0.05	0.0019	<0.25	0.0005	<1.0	<5.0	0.23	<0.0025	<0.0025	<0.0025

General Chemistry

			EPAN	EPA Method 300.0				EPA 160.1	EPA 120.1	150.1
SAM	DATE m SAMPLED Fluc	mg/L Fluoride	mg/L Chloride	mg/L Nitrite	mg/L Nitrogen	mg/L P	mg/L Sulfate	mg/L TDS	mg/L E.C.	H
NQCC 20NMAC 6.2.3103	tan para la la constanta la constanta la constanta la constanta	1.6	250		10		600	1000		6.0 - 9.0
111	1/04	0.48	130	<0.10	<0.10	<0.50	280	1400	1900	7.73



Dissolved Metals

Table 11

MONITORING WELL #49

	10.00	mg/L Zn	0.0089	
		mg/L Sodium		
の見ていていてい	and the second second second second second second second second second second second second second second second	mg/L K		
A TANK A RANK	0.20	mg/L Mn	2.1	
ALL ALL AND		mg/L Mg		
States - States	0.05	mg/L Lead	<0.005	
d 6010C	1.00	mg/L Iron	0.18	
EPA Method	0.01	mg/L Cu	<0.006	
A DESCRIPTION OF	0.05	mg/L Cr	<0.006	
	0.01	mg/L Cadmium	<0.002	
	1.00	mg/L Barium	0.3	
A MARINE	0.10	mg/L Arsenic	<0.02	
「「ない」を言いてい	WQCC 20 NMAC 6.2.3103	DATE SAMPLED	11/1/04	

Total Metals

				State State State	EPA Metho	00 6010C	- Allower	Section and		No. of the local division of the local divis	A PARTICULATION OF	
40 CFR 141.62 MCL	0.01	2.00	0.01		0.10	and a strain of the second second second second second second second second second second second second second	0.02					
DATE	mg/L Arsenic	mg/L Barium	mg/L Cadmium	mg/L Calcium	mg/L Cr	mg/L Iron	mg/L Lead	mg/L Mg	mg/L Mn	mg/L K	mg/L Sodium	mg/L Zn
11/1/04	<0.02	0.48	<0.002	160	<0.006	19	0.014	31	4.4	7.9	330	0.061



Soil Composites from Remediation Efforts North of Hammond Ditch

Es	mg/Kg	Date Sampled	16 barrels of Impacted Soil	Date Sampled	Hydroblast Pad Composite	Tank #36 Composite
808	Benzene	8/13/2004	1.19	8/31/2004	0.097	0.011
	Toluene	8/13/2004	0.671	8/31/2004	0.086	0.015
051 poq	Ethylbenzene	8/13/2004	0.792	8/31/2004	0.105	0.014
10000	Xylene	8/13/2004	2.91	8/31/2004	0.434	0.109
8510	Gasoline Range	8/13/2004	3,880	8/31/2004	57.2	85.1
)8 pc	Diesel Range	8/13/2004	5,400	8/31/2004	244	266
Metho	Total Petroleum Hydrocarbons	8/13/2004	9,280	8/31/2004	301	351
	mg/L				「「「「「「」」	
	Arsenic	8/13/2004	0.009	8/31/2004	0.002	0.003
801	Barium	8/13/2004	0.422	8/31/2004	0.068	0.073
09 8	Cadmium	8/13/2004	<0.001	8/31/2004	<0.001	<0.001
809	Chromium	8/13/2004	0.002	8/31/2004	0.001	0.001
306	Lead	8/13/2004	0.001	8/31/2004	<0.001	<0.001
pou	Mecury	8/13/2004	<0.001	8/31/2004	<0.001	<0.001
9M	Selenium	8/13/2004	0.006	8/31/2004	<0.001	<0.001
	Silver	8/13/2004	<0.001	8/31/2004	<0.001	<0.001
hedt 23	Ignitability	8/13/2004		8/31/2004	Negative	Negative
192 - 905 1	Corrosivity	8/13/2004		8/31/2004	Negative	Negative
61.21 12.13	Reactivity	8/13/2004		8/31/2004	Negative	Negative
C (S 40Cl	Hd	8/13/2004	8.00	8/31/2004	7.43	7.69



DISSOLVED METALS

EPA Method 60100	od 60100	Contraction of the second					Desta			and the second	Wacc
mg/L	DATE Sampled	North of MW #46	North of MW #45	Upstream of Refinery	Jpstream of Down stream Refinery of Refinery	DATE Sampled	North of MW #46	North of MW #45	Upstream of Refinery	Downstream of Refinery	20 NMAC 6.2.3103
Arsenic	8/14/04					9/7/04	<0.02	<0.02	<0.02		0.10
Barium	8/14/04					9/7/04	0.082	0.081	0.081		1.00
Cadmium	8/14/04					9/7/04	<0.002	<0.002	<0.002		0.01
Calcium	8/14/04	41.6	39	39		9/7/04	39	39	39		
Cr	8/14/04					9/7/04	<0.006	<0.006	<0.006		0.05
Copper	8/14/04					9/7/04	<0.006	<0.006	<0.006		1.00
Iron	8/14/04	0.01	0.009	0.001		9/1/04	0.036	0.057	0.031		1.00
Lead	8/14/04	7				9/7/04	<0.005	<0.005	<0.005		0.05
Mg	8/14/04	6.93	6.54	6.1		9/7/04	7.5	7.5	7.5		
Mn	8/14/04					9/7/04	0.004	0.0052	0.0054		0.20
K	8/14/04	1.63	1.4	12		9/7/04	2.1	2.1	2.1		
Se	8/14/04					9/7/04	<0.05	<0.05	<0.05		0.05
Silver	8/14/04					9/7/04	<0.005	<0.005	<0.005		0.05
Sodium	8/14/04	30.2	36	37		9/7/04	21	21	20		
Uranium	8/14/04					9/7/04	<0.1	<0.1	<0.1		5.00
Zinc	8/14/04					9/7/04	0.023	0.023	0.0057		10.00



Table 13

DISSOLVED METALS

EPA Method 6010C	Real Property lies		Survey and a survey	A PARTICIPAL OF		and the second second	and house	RUSSING AR	Same - and an	WQCC
DATE	North of MW #46	North of MW #45	Upstream of Refinery	Jpstream of Down stream Refinery of Refinery	DATE Sampled	North of MW #46	North of MW #45	Upstream of Refinery	Downstream of Refinery	20 NMAC 6.2.3103
10/7/04	<0.02	<0.02	<0.02		11/3/04	<0.02	<0.02	<0.02		0.10
10/7/04	0.063	0.063	0.065		11/3/04	0.075	0.073	0.076	たっていた。	1.00
10/7/04	<0.002	<0.002	<0.002		11/3/04	<0.002	<0.002	<0.002		0.01
10/7/04	46	44	45		11/3/04	43	44	43		
10/7/04	<0.006	<0.006	<0.006		11/3/04	<0.006	<0.006	<0.006		0.05
10/7/04	<0.006	<0.006	<0.006		11/3/04	<0.006	<0.006	<0.006		1.00
10/7/04	0.36	0.11	0.058		11/3/04	0.03	<0.02	0.021		1.00
10/7/04	<0.005	<0.005	<0.005		11/3/04	<0.005	0.0071	<0.005		0.05
10/7/04	8.1	7.8	8.1		11/3/04	7.6	7.8	7.6		
10/7/04	0.0084	0.0074	0.0081		11/3/04	0.011	0.017	0.012		0.20
10/7/04	2.2	2.1	2.2		11/3/04	2	2	2.1		
10/7/04	<0.05	<0.05	<0.05		11/3/04	<0.05	<0.05	<0.05		0.05
10/7/04	<0.005	<0.005	<0.005		11/3/04	<0.005	<0.005	<0.005		0.05
10/7/04	<0.1	<0.1	<0.1		11/3/04	30	31	31		
10/7/04	QN	QN	QN		11/3/04	<0.1	<0.1	<0.1		5.00
10/7/04	0.041	0.027	0.037		11/3/04	0.017	0.011	0.012		10.00

Table 13

DISSOLVED METALS

EPA Method 6010C	10d 6010	0	The state				A STATE OF		ではないたの	and the second second	WQCC
mg/L	DATE Sampled	North of MW #46	North of MW #45	Upstream of Refinery	pstream of Down stream Refinery of Refinery	DATE Sampled	North of MVV #46	North of MW #45	Upstream of Refinery	Downstream of Refinery	20 NMAC 6.2.3103
Arsenic	12/7/04	<0.02	<0.02	<0.02	<0.02						0.10
Barium	12/7/04	0.069	0.068	0.068	0.068						1.00
Cadmium	12/7/04	<0.002	<0.002	<0.002	<0.002						0.01
Calcium	12/7/04	44	44	43	46						
ວ່	12/7/04	<0.006	<0.006	<0.006	<0.006						0.05
Copper	12/7/04	<0.006	<0.006	<0.006	<0.006						1.00
Iron	12/7/04	<0.02	0.062	<0.02	<0.02						1.00
Lead	12/7/04	<0.005	<0.005	<0.005	<0.005						0.05
BM	12/7/04	7.7	7.6	7.6	7.9						
Mn	12/7/04	0.01	0.012	0.011	0.033						0.20
¥	12/7/04	2	2	2	2						
Se	12/7/04	<0.05	<0.05	<0.05	<0.05						0.05
Silver	12/7/04	<0.005	<0.005	<0.005	<0.005						0.05
Sodium	12/7/04	30	30	29	32						
Uranium	12/7/04	<0.1	<0.1	<0.1	<0.1						5.00
Zinc	12/1/04	0.012	0.035	0.024	0.013						10.00





5
1
4
5
ළ
2
_
4
0
-

EPA Meth	EPA Method 6010C, EPA Method 747	N EPAN	Nethod 7	470: Mercuny	N			States and			40CFR141.62
mg/L	DATE	North of MW #46	North of North of U MW #46 MW #45	Upstream of Refinery	pstream of Down stream Refinery of Refinery	DATE	North of MW #46	North of MW #45	Upstream of Refinery	North of North of Upstream of Down stream MW #46 MW #45 Refinery of Refinery	MCL
Arsenic	8/14/04 0.001	0.001	0.001	<0.001		9/7/04	<0.02	<0.02	<0.02		0.01
Barium	8/14/04 0.027	0.027	0.016	0.005		9/7/04	0.11	0.11	0.1		2
Cadmium	COLUMN 2	8/14/04 <0.001	<0.001	<0.001		9/7/04	<0.002	<0.002	<0.002		0.005
ŗ	8/14/04	8/14/04 <0.001	<0.001	<0.001		9/7/04	<0.006	<0.006	<0.006		0.1
Lead	8/14/04	8/14/04 <0.001	<0.001	<0.001		9/7/04	<0.005	<0.005	<0.005		0.015
Se	8/14/04	8/14/04 <0.001	<0.001	<0.001		9/7/04	<0.05	<0.05	<0.05		0.05
Silver	8/14/04	<0.001	<0.001	<0.001		9/7/04	<0.005	<0.005	<0.005		
Mercury	8/14/04					9/7/04	<0.0002	<0.0002	<0.0002		0.002

Table 13

TOTAL METALS

EPA Meth	EPA Method 6010C, EPA Method 747	; , EPA N	Viethod 7	470: Mercury	N. States			第二部 第二部 第二			40CFR141.62
mg/L	DATE Sampled	North of MW #46	North of North of U MW #46 MW #45	Upstream of Refinery	pstream of Down stream DATE Refinery of Refinery Sampled	DATE		North of MW #45	Upstream of Refinery	North of North of Upstream of Down stream MW #46 MW #45 Refinery of Refinery	MCL
Arsenic	10/7/2004	<0.02	<0.02	<0.02		11/3/04	<0.02	<0.02	<0.02		0.01
Barium	10/7/04	0.074	0.072	0.083		11/3/04	0.088	0.1	0.086		2
Cadmium	10/7/04	<0.002	<0.002	<0.002		11/3/04	<0.002	<0.002	<0.002		0.005
ŗ	10/7/04	<0.006	<0.006	<0.006		11/3/04	<0.006	<0.006	<0.006		0.1
Lead	10/7/04	<0.005	<0.005	<0.005		11/3/04	<0.005	<0.005	<0.005		0.015
Se	10/7/04	<0.05	<0.05	<0.05		11/3/04	<0.05	<0.05	<0.05		0.05
Silver	10/07/04	<0.005	<0.005	<0.005		11/3/04	<0.005	<0.005	<0.005		
Mercury	10/7/04	10/7/04 <0.0002 <0.0002	<0.0002	<0.0002		11/3/04	11/3/04 <0.0002	<0.0002	<0.0002		0.002





TOTAL METALS

EPA Method 6010C EPA Method	lod 60100	C EPAN	Nethod 7	470: Mercury	V				State of the second sec		40CFR141.62
mg/L	DATE	North of MW #46	North of North of MW #46 MW #45	Upstream of Refinery	pstream of Down stream Refinery of Refinery	DATE	North of MW #46	North of MW #45	Upstream of Refinery	North of North of Upstream of Down stream MW #46 MW #45 Refinery of Refinery	MCL
Arsenic	12/7/04	<0.02	<0.02	<0.02	<0.02						0.01
Barium	12/7/04	0.087	0.08	0.077	0.08						2
Cadmium		12/7/04 <0.002	<0.002	<0.002	<0.002						0.005
c	12/7/04	12/7/04 <0.006	<0.006	<0.006	<0.006						0.1
Lead	12/7/04	12/7/04 <0.005	<0.005	<0.005	<0.005						0.015
Se	12/7/04	<0.05	<0.05	<0.05	<0.05						0.05
Silver	12/7/04	<0.005	<0.005	<0.005	<0.005						
Mercury		12/7/04 <0.0002 <0.0002	<0.0002	<0.0002	<0.0002						0.002





					EPA Method 300.0				EPA 160.1	EPA 120.1	E SI	EPA No.1
	DATE mg/L SAMPLED Fluoride		mg/L Chloride	mg/L Nitrite	mg/L Bromide	mg/L Nitrogen	mg/L	mg/L Sulfate	mg/L TDS	mg/L E.C.	mg/L CO3	mg/L Alk
WQCC 20NI 6.2.3103	DNMAC 03	1.6	250			-0		600	1000			
North of MW #46	8/14/04	0.18	23	0.004		0.2	0.4	91	228	402	<0.1	87
North of MW #45	8/14/04	0.6	26	0.003		0.2	0.2	89	244	398	<0.1	89
Upstream of Refinery 8/14/04	8/14/04	0.45	23	0.2		0.007	0.2	95	242	391	<0.1	86
Down from Refinery	8/14/04											

North of MW #46	9/7/04	0.19	3.7	<0.1	<0.1	0.16	<0.5	74	230	310	<4.0	100
North of MW #45	9/7/04	0.22	3.7	<0.1	<0.1	0.18	<0.5	74	220	310	<4.0	100
Upstream of Refinery	9/7/04	0.2	3.8	<0.1	<0.1	0.11	<0.5	74	220	310	<4.0	100
Down from Refinery	9/7/04											

North of	- and	010		101		CT 0	201		000	UEC		440
North of	Turnet	0.18	4.	20.1	1.02	CI-0	C.02	02	nnc	2/0	0.4	011
MW #45	10/7/04	0.21	4.2	<0.1	<0.1	0.13	<0.5	88	260	360	<4.0	100
Upstream		010		101	101	910	E C	30	USC	260		5
or Kennery	10/1/04	0.19	6.4	20.1	<0.1	0.10	C.U2	8	007	200	0.45	201
Down from					加加になる						の語をいた	
Refinery			Line and			and the second second second second second second second second second second second second second second second						

Page 6 of 9



General Chemistry

Table 13

					EPA Method				EPA	EPA		GA
		「「「「「「」」	The second		300.0		THE COLOR		160.1	120.1	31	0.1
	DATE mg/L mg/L SAMPLED Fluoride Chloride	mg/L Fluoride	mg/L Chloride	mg/L Nitrite	mg/L Bromide	mg/L Nitrogen	P P	mg/L Sulfate	mg/L TDS	mg/L E.C.	mg/L CO3	mg/L Alk
WQCC ZONMAC 6.2.3103	ONMAC 103	1.6	250			10 10		600	1000			
North of MW #46	11/3/04	0.24	4.7	<0.1	<0.1	0.11	<0.5	110	290	370	8	110
North of MW #45	11/3/04	0.25	5	<0.1	<0.1	<0.1	<0.5	110	290	370	<2.0	110
Upstream of Refinery 11/3/04	11/3/04	0.23	4.5	<0.1	<0.1	0.1	<0.5	100	280	360	<2.0	120
Down from Refinery												

WQCC 20NMAC 6.2.3103	ONMAC 103	9 7	250			01		em	, 100			
North of MW #46	12/7/04	0.19	4.6	<0.1	<0.1	0.19	<0.5	110	300	410	<4.0	100
North of MW #45	12/7/04	0.02	4.5	<0.1	<0.1	0.16	<0.5	110	320	410	<4.0	100
Upstream of Refinery	12/7/04	0.19	4.4	<0.1	<0.1	0.16	<0.5	100	280	400	<4.0	92
Down from Refinery	12/7/04	0.18	4.6	<5.0	<0.1	<5.0	<0.5	120	310	440	<4.0	98

ORGANICS

				EPA Method 8021B				EPA Method 8015B	
	DATE	DATE mg/L SAMPLED Benzene	mg/L Toluene	mg/L EthylBen	mg/L Xylene	mg/L MTBE	mg/L DRO	mg/L MRO	mg/L GRO
WQCC 20NMAC 6.2.3103	DNMAC 103	0.01	0.75	0.75	0.62				
North of MW #46	8/14/04	0.006	0.085	0.029	0.11	<0.0002	<0.1		0.3
North of MW #45	8/14/04	0.0097	0.061	0.022	0.081	<0.0002	<0.1		0.2
Upstream of Refinery 8/14/04	8/14/04	<0.0002 <0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.1		<0.2
Down from Refinery									

MW #46	The second secon								
	9/7/04	<0.0005 <0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
North of MW #45	9/7/04	<0.0005 <0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Upstream of Refinery	9/7/04	<0.0005 <0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Down from Refinery	9/30/04	<0.0005	<0.0005 <0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05

North of MW #46	10/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
North of MW #45	10/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0		<0.05
Upstream of Refinery	10/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Down from Refinery	10/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05

Table 13

ORGANICS

				EPA Method 8021B				EPA Method 8015B	8
	DATE	MPLED Benzene	mg/L Toluene	mg/L EthylBen	mg/L Xylene	mg/L MTBE	mg/L DRO	mg/L MRO	mg/L GRO
WQCC 20NA 6.2.3103	20NMAC 3103	0.01	0.75	0.75	0.62				
North of MW #46	11/3/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
North of MW #45	11/3/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Upstream of Refinery	11/3/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Down from Refinery	E	/3/04 <0.0005 <0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05

				EPA Method 8021B				EPA Method 8015B	8
	DATE mg/L SAMPLED Benzene	mg/L Benzene	mg/L Toluene	mg/L EthylBen	mg/L Xylene	mg/L MTBE	mg/L DRO	mg/L MRO	mg/L GRO
WQCC 20NA 6.2.3103	20NMAC 3103	0.01	0.75	0.75	0.62				
North of MW #46	12/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
North of MW #45	12/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Upstream of Refinery	12/7/04	<0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05
Down from Refinery	2	2/7/04 <0.0005 <0.0005	<0.0005	<0.0005	<0.0005	<0.0025	<1.0	<5.0	<0.05

Table 13

Water Quality Field Measurements

Table 14

DATE	RW/MW	V/MW DEPTH TO LIQUID (ft)	SPH	WELL DEPTH	E.C.	Ηq	TEMP.	D.0	ORP
Nov-04 MV	MW #48	7.73	0	17.32	2648	7.01	54		
Dec-04		7.97	0	17.32	2773	7.01	54		
Nov-04 MW	MW #49	6	0	16.48	2448	6.91	55		
Dec-04		9.3	0	16.48	2450	6.93	55		

Section 10.0 List of Figures

Title	Figure
Vicinity Maps	Figures 1 & 2
Facility Site Plan	Figure 3
Groundwater Elevation and Flow Direction - March	Figure 4
Groundwater Elevation and Flow Direction – August	Figure 5
Groundwater Dissolved Phase Constituents Map – March	Figure 6
Groundwater Dissolved Phase Constituents Map – August	Figure 7
Product Thickness Map – March	Figure 8
Product Thickness Map – August	Figure 9
River Terrace Sampling Locations	Figure 10
San Juan River Sampling Points	Figure 11

Figure 1










Figure 2







SCALE	
DRAW	
	CHK.
4 Updated To Indicate Changes As Per Enviro. Dept. Red-Line Mark-Ups. NHB 2/04 FINAL	CHK.
3 Updated To Indicate Under Ground Pipe Ways In The Tank Farm Area NHB12/03	
2 Updated As Per Enviromental Dept. Mark-Up. (C. Hurtado) NHB 5/03 ENGR.	
1 Updated As Per Enviromental Dept. Mark Up BY DATE BY DATE BY DATE BY DATE APPR.	BY
RENCE DWGS. NO. DRAWN CHECKED APPROVED AFE/W	/0 No.
7 8 9 10 11 12	I













Product Thickness



MW-33⊕


Product Thickness



MW-32⊕

MW-33⊕


Figure 9



- Existing Barrier Alignment


0


- = Proposed Grab-Sample Location 0





San Juan River Sampling Points















































Momoring Well #33







Momoring Well #35













OBTFALL #3








PE2ometer #4







-

Field Methods

Groundwater Elevation

All water/product levels are determined to an accuracy of 0.01 foot using a Geotech Interface Meter. The technician records separate phase hydrocarbon, depth to water, and total well depth using this probe.

Water Quality/Groundwater Sampling

Water quality parameters are measured using an Ultrameter 6P by the Myron L Company. Electrical conductance, pH, and temperature are monitored during purging. After the well is satisfactorily purged, the Ultrameter 6P can also measure Oxidation Reduction Potential. Dissolved oxygen is determined using the Hach High Range Dissolved Oxygen AccuVac method within thirty minutes of sampling.

Well Purging Technique

At least three well volumes are purged from the well. Purge volumes are determined using the following equation:

Well Depth – Casing Height – Depth to Liquid X Conversion Factor X Three. The conversion factor is determined by the diameter of the well casing.

Casing	Conversion Factor
6"	1.50 gal/ft
5"	1.02 gal/ft
4"	0.74 gal/ft
3"	0.367 gal/ft
2"	0.163 gal/ft

Typically disposable bailers are used for purging and sampling. Each bailer holds one liter of liquid. Three well volumes can be calculated by counting the number of times a well is bailed.

On occasion, the submersible pump is used for purging wells that have a large volume of water. All purged water is poured/pumped into a 55-gallon drum designated for sampling events.

Well Sampling and Sample Handling Procedure

Equipment and supplies needed for collecting representative groundwater samples include:

- Interface Meter
- Ultrameter 6P
- Distilled Water
- Disposable Latex Gloves
- Disposable Bailers
- Submersible pump and Generator (if needed)
- String/Twine
- Cooler with Ice

- Bottle kits with Preservatives (provided by the contract laboratory)
- Disposable 0.45 micron Field Filters and Syringes
- Glass Jar (usually 4 oz.)
- Sharpie Permanent Marker
- Field Paperwork/Logsheet
- Two 5-gallon buckets
- Trash container (plastic garbage bag)
- Ziploc Bags
- Paper towels

After sufficient purging, samples are collected with the bailer and poured into the appropriate sample containers. Two people are usually utilized for sampling. Sampling takes place over a bucket to insure that spills are contained

For dissolved metals, sample water is poured into a jar and then extracted with a syringe. The syringe is then used to push water through a field filter into the proper sample bottle to collect the dissolved metals sample. Volatile organic analysis samples are collected as to allow no head space in the container.

Samples are labeled immediately with location, date, time, analysis, preservative, and sampler. Then they are put in a Ziploc and placed in a cooler holding sufficient ice to keep them cool. The field logsheet is reviewed to verify all entries.

Purge and Decontamination Water Disposal

The Ultrameter 6P and the interface probe are rinsed with distilled water after every well. The rinse procedure takes place over a bucket to insure that spills are contained.

All rinse and purge water is contained and then disposed of through the refinery wastewater system.

The submersible pump is decontaminated by placing it in a 55-gallon barrel filled with plant water and some Alconox. The pump is activated and will pump down the barrel twice. External areas are washed down and rinsed, also. All wash and rinse water is on containment and runs to the refinery wastewater system. Any glassware used is taken to the refinery laboratory and washed with Alconox and water and rinsed with reverse osmosis water. Laboratory wastewater runs through the refinery system.

Remediation System Measurement

Recovery well flows are measured using a 500 ml graduated cylinder. The discharge line of the pump is disconnected and placed in the graduated cylinder. During a pump cycle, a measurement is taken over time and then calculated to a gallon per day rate.

Recovery rates at Tk #37 (Hammond Ditch French Drain) and Tk #38 (#1 East Outfall) are determined through flow meters installed in those systems. Refinery personnel record the rates periodically.

Section 13.0 Waste Disposition

Title	Tab Number
Correspondence	1
Staging Piles – Analytical	2
Landfarm Background Analytical	3

Mr. Wayne Price New Mexico Oil Conservation Division 1220 South St. Frances Dr. Santa Fe, New Mexico 87505

October 20, 2004

Re: Request to Utilize Non-Hazardous Soil -Release North of MW #45

Dear Mr. Price,

Giant Refining Company – Bloomfield Refinery requests permission for on-site utilization of the non-hazardous impacted soil removed from the release North of Monitoring Well #45. This soil will be placed in a low-lying area on the East end of the refinery property. An earthen berm will be constructed around this area to prevent storm water contamination.

Please find enclosed the analytical results from composite samples taken from this material:

- 1. Hydro Blast Pad Composite (1200 cubic yards)
 - BTEX Non-hazardous for any chemical.
 - Benzene = .097 (mg/Kg)Total BTEX= .722 (mg/Kg) TCLP-Arsenic 0.002 (mg/Kg)Barium $0.068 \,(mg/Kg)$ Cadmium ND Chromium 0.001 (mg/Kg) Lead ND Mercury ND Selenium ND Silver ND
 - TPH 301 (mg/kg) GRO = 57.2 (mg/Kg) DRO = 244 (mg/Kg)

- Ignitability Negative
- Corrosivity Negative
- Reactivity Negative
- PH = 7.43
- Flash Point >350 C
- 2. Tank 36 Composite (3600 cubic yards)
 - BTEX Non-hazardous for any chemical.

Benzene =.011 (mg/Kg) Total BTEX= .149 (mg/Kg)

- TCLP-Arsenic 0.003 (mg/Kg)Barium 0.073 (mg/Kg) Cadmium ND Chromium 0.001 (mg/Kg)Lead ND Mercury ND Selenium ND Silver ND
- TPH 351 (mg/kg) GRO = 85.1 (ng/Kg) DRO = 266 (mg/Kg)
- Ignitability Negative
- Corrosivity Negative
- Reactivity Negative
- PH = 7.69
- Flash Point >350 C

Your prompt attention to this matter will be greatly appreciated. If you need more information, please contact me at (505) 632-4171.

Sincerely,

Randy Schmaltz Environmental Supervisor Giant Refining Company – Bloomfield

Cc: Hope Monzeglio. NMED Denny Foust, New Mexico Oil Conservation Division – Aztec

Ed Riege

|

ļ

:

1

.

.

i

Cindy Hurtado

om: Lot: To: Subject: Randy Schmaltz Monday, October 25, 2004 7:16 AM Cindy Hurtado; Ed Riege FW: Soil Request

----Original Message----From: Price, Wayne [mailto:WPrice@state.nm.us] Sent: Thursday, October 21, 2004 8:31 AM To: 'Randy Schmaltz'; Price, Wayne Cc: 'Hope Monzeglio'; Foust, Denny Subject: RE: Soil Request

OCD hereby approves of your request with the following conditions:

1. One treatment zone soil sample shall be collected three feet below the approximate center of the temporary landfarm area before placement of any soils. The soil sample shall be analyzed for TPH, BTEX, and general chemistry.

2. On the general site plot plan mark this location and submit for our files.

Please be advised that NMOCD approval of this plan does not relieve (Giant) of liability should their operations fail to adequatery investigate and remediate contamination that pose a threat to ground water, surface ter, human health or the environment. In addition, NMOCD approval does t relieve (Giant) of responsibility for compliance with any other federal, state, or local laws and/or regulations.

----Original Message----From: Randy Schmaltz [mailto:rschmaltz@giant.com] Sent: Wednesday, October 20, 2004 4:48 PM To: 'Wayne Price' Cc: 'Hope Monzeglio'; 'Denny Foust' Subject: Soil Request

<<Release N. MW #45 Soil Request.doc>> DISCLAIMER: The information contained in this e-mail message may be privileged, confidential and protected from disclosure. If you are not the intended recipient, any further disclosure, use, dissemination, distribution or copying of this message or any attachment is strictly prohibited. If you think you have received this e-mail message in error, please e-mail the sender at the above address and permanently delete the e-mail. Although this e-mail and any attachments are believed to be free of any virus or other defect that might affect any computer system into which they are received and opened, it is the responsibility of the recipient to ensure that they are virus free and no responsibility is accepted by Giant Industries, Inc. or its affiliates for any loss or damage arising in any way from their use.

"bis email has been scanned by the MessageLabs Email Security System. : more information please visit http://www.messagelabs.com/email

Confidentiality Notice: This e-mail, including all attachments is for the sole use of the

1

intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited unless specifically provided under the New Mexico Inspection of Public Records Act. If you are not the intended recipient, please contact the sender and destroy all copies of this message. is email has been scanned by the MessageLabs Email Security System.

i

2



Mr. Wayne Price New Mexico Oil Conservation Division 1220 South St. Frances Dr. Santa Fe, New Mexico 87505

September 8, 2004

Re: Soil Final Disposition-Release North of MW #45

Dear Mr. Price,

As you are aware of Giant Refining Company – Bloomfield Refinery removed all the impacted soil from the release North of Monitoring Well #45 as directed in the "Emergency Action Directive". The heavily impacted soil was sampled, removed and placed into 55-gallon drums. The remainder of the soil placed into staging piles. The staging piles were segregated into two categories based upon visual inspection of the soil.

Giant collected composite samples from the staging piles of each category. All samples were analyzed for Method 6010C (RCRA 8 metals) TCLP, BTEX, Reactivity, Corrosivity, Ignitability, Flash point, and TPH.

The following is a summary of sample results including quantity of material:

- 1. Drummed Soil (16 barrels)
 - BTEX Hazardous for Benzene

TCLP –	Arsenic	0.009 (mg/Kg)
	Barium	0.422 (mg/Kg)
	Cadmium	ND
	Chromium	0.002 (mg/Kg)
	Lead	0.001 (mg/Kg)
	Mercury	ND
	Selenium	0.006 (mg/Kg)
	Silver	ND

• TPH – 9280 (mg/Kg)

2. Hydro Blast Pad Composite (1200 cubic yards)

• BTEX – Non-hazardous for any chemical. Benzene =.097 (mg/Kg)

Total BTEX= .722 (mg/Kg)

PHONE 505-632-8013 FAX 505-632-3911 50 ROAD 4990 P.O. BOX 159 BLOOMFIELD NEW MEXICO 87413

TCLP

LP-	Arsenic	0.002 (mg/Kg)
	Barium	0.068 (mg/Kg)
	Cadmium	ND
	Chromium	0.001 (mg/Kg)
	Lead	ND
	Mercury	ND
	Selenium	ND
	Silver	ND

- TPH 301 (mg/kg) GRO = 57.2 (mg/Kg) DRO = 244 (mg/Kg)
- Ignitability Negative
- Corrosivity Negative
- Reactivity Negative
- PH = 7.43
- Flash Point >350 C

3. Tank 36 Composite (3600 cubic yards)

• BTEX – Non-hazardous for any chemical. Benzene =.011 (mg/Kg) Total BTEX= .149 (mg/Kg)

• TCLP-

· ·	Arsenic	0.003 (mg/Kg)
	Barium	0.073 (mg/Kg)
	Cadmium	ND
	Chromium	0.001 (mg/Kg)
	Lead	ND
	Mercury	ND
	Selenium	ND
	Silver	ND

- TPH 351 (mg/kg) GRO = 85.1 (mg/Kg) DRO = 266 (mg/Kg)
- Ignitability Negative
- Corrosivity Negative
- Reactivity Negative
- PH = 7.69
- Flash Point >350 C

Based on these results Giant will send the 16 barrels of soil to an EPA permitted TSD facility. Giant requests the Agency's permission to use the remaining soil for beneficial use at the refinery (dike material and leveling low lying areas).

Your prompt attention to this matter will be greatly appreciated. If you need more information, please contact me at (505) 632-4171.

Sincerely

Randy Schmaltz Environmental Supervisor Giant Refining Company – Bloomfield

Cc: Hope Monzeglio, NMED Denny Foust, New Mexico Oil Conservation Division – Aztec Ed Riege



Wayne Price New Mexico Oil Conservation Division 1220 South St. Frances Dr. Santa Fe, New Mexico 87505

Hope Monzeglio New Mexico Environmental Department Hazardous Waste Bureau 2905 Rodeo Park Dr. East Bldg 1 Santa Fe, New Mexico 87505

October 26, 2004

Re: Request for Disposal of Impacted Soil

Dear Mr. Price and Ms. Monzeglio,

Giant Refining Company – Bloomfield Refinery requests for approval for final disposition of 16 barrels of impacted soil from the MW #45 Release to the San Juan County Landfill. The waste will be treated at the Landfill Facility to New Mexico State standards and directly disposed of at the San Juan County Landfill.

Enclosed; please find analytical data and Waste Management's profile and approval. Hard copies for your records will follow.

Your prompt attention to this matter will be greatly appreciated. If you need more information, please contact me at (505) 632-4161.

Sincerely,

indy Hurtado

Cindy Húrtado Environmental Assistant Giant Refining Company – Bloomfield

Cc: Dave Cobrain, NMED Robert Wilkinson, EPA Denny Foust, New Mexico Oil Conservation Division – Aztec Ed Riege

> SO ROAD 4990 P.O. BOX 159 BLOOMFIELD NEW MEXICO

PHONE	
505-632-801	3
FAX	
505-632-391	t

Cindy Hurtado

om: Hope Monzeglio [hope_monzeglio@nmenv.state.nm.us] Wednesday, October 27, 2004 3:57 PM it: Cindy Hurtado; Price, Wayne · ...: Bob Wilkinson; Randy Schmaltz; Ed Riege; Denny Foust; David Cobrain Cc: **RE: Soil Disposal Request** Subject: NMED is in agreement with OCD, this email constitutes NMED's approval of Giant's request to dispose of hydrocarbon contaminated soil in the San Juan Co. Landfill. A follow up letter will follow. Hope Monzeglio ----Original Message-----From: Price, Wayne Sent: Wednesday, October 27, 2004 2:52 PM To: 'Cindy Hurtado'; Price, Wayne; 'Hope Monzeglio' Cc: Foust, Denny; 'Robert Wilkinson'; 'Dave Cobrain'; Randy Schmaltz; Ed Riege Subject: RE: Soil Disposal Request OCD hereby approves of Giant's request to dispose of hydrocarbon contaminated soil in the San Juan Co. Landfill with the following conditions: The soil must be RCRA non-hazardous and NMED-haz waste must approve. 1. 2. Giant shall provide proof of disposal, waste manifest, etc. This approval is good for 30 days and only for soils generated ring the emergency response approved by OCD. sase be advised that NMOCD approval of this plan does not relieve (Giant) of liability should their operations fail to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD approval does not relieve (Giant) of responsibility for compliance with any other federal, state, or local laws and/or regulations. ----Original Message-----From: Cindy Hurtado [mailto:churtado@giant.com] Sent: Wednesday, October 27, 2004 2:15 PM To: 'Wayne Price'; 'Hope Monzeglio' Cc: 'Denny Foust'; 'Robert Wilkinson'; 'Dave Cobrain'; Randy Schmaltz; Ed Riege Subject: Soil Disposal Request <<Soil Disposal Request.doc>> <<Drummed soil (MW #45).doc>> This email has been scanned by the MessageLabs Email Security System. For more information please visit http://www.messagelabs.com/email Confidentiality Notice: This e-mail, including all attachments, is for the sole use of the rtended recipient(s) and may contain confidential and privileged information. Any authorized review, use, disclosure or distribution is prohibited unless specifically permission of the New Mexico Environment Department. If you are not the intended recipient, please contact the sender and destroy all copies of this message.

EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	Giant	Project #:	96012-028
Sample ID:	001	Date Reported:	08-18-04
Laboratory Number:	30030	Date Sampled:	08-13-04
Chain of Custody:	12752	Date Received:	08-13-04
Sample Matrix:	Soil	Date Analyzed:	08-18-04
Preservative:	Cool	Date Extracted:	08-16-04
Condition:	Cool & Intact	Analysis Requested:	BTEX-MTBE

Parameter	Concentration (ug/Kg)	Det. Limit (ug/Kg)
Methyl-tert-butyl Ether	ND	2.1
Benzene	1,190	1.8
Toluene	671	1.7
Ethylbenzene	792	1.5
p,m-Xylene	2,180	2.2
o-Xylene	728	1.0
Total BTEX	5,560	÷

ND - Parameter not detected at the stated detection limit.

Surrogate Recoveries:	Parameter	Percent Recovery
	Fluorobenzene	99 %
	1,4-difluorobenzene	99 %
	Bromochlorobenzene	99 %

References: Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

Outfali Area Top of Spill.

Analyst

Mistine Multers Review

EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Client:	Giant	Project #:	96012-028
Sample ID:	001	Date Reported:	08-18-04
Laboratory Number:	30030	Date Sampled:	08-13-04
Chain of Custody No:	12752	Date Received:	08-13-04
Sample Matrix:	Soil	Date Extracted:	08-16-04
Preservative:	Cool	Date Analyzed:	08-18-04
Condition:	Cool and Intact	Analysis Requested:	8015 TPH

Parameter	Concentration (mg/Kg)	Det. Limit (mg/Kg)
Gasoline Range (C5 - C10)	3,880	0.2
Diesel Range (C10 - C28)	5,400	0.1
Total Petroleum Hydrocarbons	9,280	0.2

ND - Parameter not detected at the stated detection limit.

References: Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments: Outfall Area Top of Spill.

Analyst

1)noton MINTIN MI Review

Ē

TRACE METAL ANALYSIS

Client:	Giant	Project #:	96012-028
Sample ID:	001	Date Reported:	08-17-04
Laboratory Number:	30030	Date Sampled:	08-13-04
Chain of Custody:	12752	Date Received:	08-13-04
Sample Matrix:	Soil	Date Analyzed:	08-17-04
Preservative:	Cool	Date Digested:	08-16-04
Condition:	Cool & Intact	Analysis Needed:	RCRA Metals
	····	Det.	CLP Regulatory
	Concentration	Limit	Level
Parameter	(mg/Kg)	(mg/Kg)	(mg/Kg)
Arsenic	0.009	0.001	5.0
Barium	0.422	0.001	100
Cadmium	ND	0.001	1.0
Chromium	0.002	0.001	5.0
Lead	0.001	0.001	5.0
Mercury	ND	0.001	0.2
Selenium	0.006	0.001	1.0
Silver	ND	0.001	5.0

ND - Parameter not detected at the stated detection limit.

References:

Method 3050B, Acid Digestion of Sediments, Sludges and Soils. SW-846, USEPA, December 1996.

Method 6010B, Analysis of Metals by Inductively Coupled Plasma Atomic Emmision Spectroscopy, SW-846, USEPA, December 1996.

Note:

Regulatory Limits based on 40 CFR part 261 subpart C section 261.24, August 24, 1998.

Comments:

Outfall Area Top of Spill.

Analyst

Walter Review

<u>,</u>

CATION / ANION ANALYSIS

				····	··.
Client:	Giant		Project #:		12-028
Sample ID:	001		Date Reported:		19-04
Laboratory Number:	30057		Date Sampled:		14-04
Chain of Custody:	12756		Date Received:		14-04
Sample Matrix:	Soil Ext	ract	Date Extracted:		17-04
Preservative:	Cool		Date Analyzed:	08-1	18-04
Condition:	Cool & I	Intact			
		Analytical			
Paramete	er	Result	Units		Units
рН		8.00	s.u.		
Conductivity @ 25° C		267	umhos/cm		
Total Dissolved Solids	@ 180C	236	mg/L		
Total Dissolved Solids	(Calc)	218	mg/L		
SAR		1.8	ratio	· .	
Total Alkalinity as Ca	CO3	53.6	mg/L		
Total Hardness as Ca	CO3	88.0	mg/L		
Bicarbonate as H	CO3	53.6	mg/L	0.88	meq/L
Carbonate as CO	3	<0.1	mg/L	0.00	meq/L
Hydroxide as OH	λ.	<0.1	mg/L	0.00	meq/L
Nitrate Nitrogen		1.7	mg/L	0.03	meq/L
Nitrite Nitrogen		0.025	mg/L	0.00	meq/L
Chloride		28.8	mg/L	0.81	meq/L
Fluoride		0.27	mg/L	0.01	meq/L
Phosphate		8.3	mg/L	0.26	meq/L
Sulfate		74.0	mg/L	1.54	meq/L
Iron		0.266	mg/L	0.01	meq/L
Calcium		25.6	mg/L	1.28	meq/L
Magnesium		5.86	mg/L	0.48	meq/L
Potassium		2.08	mg/L	0.05	meq/L
Sodium		39.0	mg/L	1.70	meq/L
Cations				3.52	meq/L
Anions			·	3.54	meq/L
Cation/Anion Differe	200			0.48%	

Reference: U.S.E.P.A., 600/4-79-020, "Methods for Chemical Analysis of Water and Wastes", 1983. Water And Waste Water", 18th ed., 1992.

Comments: Outfall Area Top of Spill.

ine Mualters Analyst

Review

EPA Method 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Quality Assurance Report

Client:	QA/QC		Project #:		N/A
Sample ID:	08-18-TPH QA	/QC	Date Reported:		08-18-04
Laboratory Number:	30030		Date Sampled:		N/A
Sample Matrix:	Methylene Chlori	ide	Date Received:		N/A
Preservative:	N/A		Date Analyzed:		08-18-04
Condition:	N/A		Analysis Reques	ted:	ТРН
	I-Cal Dáte	-Cal RF:	C-Cal RE:	% Difference	Accept: Range
Gasoline Range C5 - C10	02-19-04	1.8591E-002	1.8572E-002	0.10%	0 - 15%
Diesel Range C10 - C28	02-19-04	1.5507E-002	1.5492E-002	0.10%	0 - 15%
Blank Conc. (mg/L - mg/K	g)	Concentration		Detection Lim	iit
Gasoline Range C5 - C10	a —	ND		0.2	Curren - 40
Diesel Range C10 - C28		ND		0.1	
Total Petroleum Hydrocarbons	5	ND		0.2	
Duplicate Conc. (mg/Kg)	Sample	Duplicate	% Difference	Accept Range	9
Gasoline Range C5 - C10	3,880	3,860	0.5%	0 - 30%	
Diesel Range C10 - C28	5,400	5,380	0.4%	0 - 30%	
Spike Conc. (mg/Kg)	Sample	Spike Added	Spike Result	% Recovery	Accept Rang
	2 0 0 0	250	4,120	99.8%	75 - 125%
Gasoline Range C5 - C10	3,880	250	4,120	00.070	10 12070

ND - Parameter not detected at the stated detection limit.

References: Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

QA/QC for samples 30030 - 30034, 30055 - 30056.

Analyst

Review Walter

TRACE METAL ANALYSIS Quality Control / Quality Assurance Report

Client:		QAVQC		Project #:			N/A
Sample ID:		08-17-04 Q	A/AC	Date Repo	orted:		08-17-04
Laboratory Number:		30030		Date Sam	pled:		N/A
Sample Matrix:		Soil		Date Rece	eived:		N/A
Analysis Requested:		Total RCR/	A Metals	Date Anal	yzed:		08-17-04
Condition:		N/A		Date Dige	sted:		08-16-04
Blank & Duplicate Conc. (mg/Kg)	Instrumen Blank (mg/l		Detectio	n Sample	Duplicate	% Diff.	Acceptance Range
Arsenic	ND	ND	0.001	0.009	0.009	0.0%	0% - 30%
Barium	ND	ND	0.001	0.422	0.419	0.7%	0% - 30%
Cadmium	ND	ND	0.001	ND	ND	0.0%	0% - 30%
Chromium	ND	ND	0.001	0.002	0.002	0.0%	0% - 30%
Lead	ND	ND	0.001	0.001	0.001	0.0%	0% - 30%
Mercury	ND	ND	0.001	ND	ND	0.0%	0% - 30%
Selenium	ND	ND	0.001	0.006	0.006	0.0%	0% - 30%
Silver	ND	ND	0.001	ND	ND	0.0%	0% - 30%
Spike	· Column	Spike	Sampl	Sniker	I Percent _		Acceptance
Conc. (mg/Kg)		Added	Jan	the provincial of the former of the second sec	e Recovery		Range
	، ئۇدېغىرىقىمىما بىر						
Arsenic		0.500	0.009	0.508	99.8%		80% - 120%
Barium		0.500	0.422	0.920	99.8%		80% - 120%
Cadmium		0.500	ND	0.500	100.0%		80% - 120%
Chromium		0.500	0.002	0.502	100.0%		80% - 120%
Lead		0.500	0.001	0.500	99.8%		80% - 120%
Mercury		0.050	ND	0.050	100.0%		80% - 120%
Selenium		0.500	0.006	0.505	99.8%		80% - 120%
Silver		0.500	ND	0.500	100.0%		80% - 120%

ND - Parameter not detected at the stated detection limit.

References:

Method 3050B, Acid Digestion of Sediments, Sludges and Soils. SW-846, USEPA, December 1996.

Method 6010B, Analysis of Metals by Inductively Coupled Plasma Atomic Emmision Spectorscopy, SW-846, USEPA, December 1996.

Comments:

ents: QA/QC for samples 30030 - 30034.

Analyst

Misting Walters Review

EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	N/A	F	Project #:	1	N/A
Sample ID:	08-18-BTEX QA/QC		Date Reported:	(08-18-04
Laboratory Number:	30030	C	Date Sampled:	1	N/A
Sample Matrix:	Soil	C	Date Received:	1	N/A
Preservative:	N/A		Date Analyzed:		08-18-04
Condition:	N/A	ł	Analysis:	E	BTEX
Calibration and	I-Cal RF:	C-Cal RF:	⊱_%Diff.	Blank	Detect.
Detection Limits (ug/L)		Accept. Rang	e 0 - 15%	Conc	Limit
Methyl-tert-butyl Ether	7.7848E-001	7.8002E-001	0.2%	ND	0.2
Benzene	2.899CE-001	2.9077E-001	0.3%	ND	0.2
Toluene	2.546CE-002	2.5511E-002	0.2%	ND	0.2
Ethylbenzene	3.8451E-002	3.8567E-002	0.3%	ND	0.2
p,m-Xylene	3.2988E-002	3.3088E-002	0.3%	ND	0.2
o-Xylene	3.3333E-002	3.3400E-002	0.2%	ND	0.1
Duplicate Conc. (ug/Kg) Methyl-tert-butly Ether	Sample ND	Duplicate ND	0.0%	0 - 30%	2.1
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene	ويتهمون بيهم ومراجع المراجع والمراجع المراجع المراجع المراجع المراجع المراجع المراجع المراجع المراجع المراجع	ND 1,220 657 776 2,240	0.0% 2.5% 2.0% 2.0% 2.8%	internet a state of the second second second second second second second second second second second second se	Contract of the second state of the second sta
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene	ND 1,190 671 792 2,180 728	ND 1,220 657 776 2,240 750	0.0% 2.5% 2.0% 2.0% 2.8% 3.0%	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30%	2.1 1.8 1.7 1.5 2.2 1.0
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene Spike Conc. (ug/Kg)	ND 1,190 671 792 2,180 728	ND 1,220 657 776 2,240 750	0.0% 2.5% 2.0% 2.0% 2.8%	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30%	2.1 1.8 1.7 1.5 2.2
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene	ND 1,190 671 792 2,180 728 Sample ND	ND 1,220 657 776 2,240 750	0.0% 2.5% 2.0% 2.0% 2.8% 3.0% Spiked Sample 24 40	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30%	2.1 1.8 1.7 1.5 2.2 1.0
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene Spike Conc. (ug/Kg)	ND 1,190 671 792 2,180 728 728 <u>Sample</u> ND 1,190	ND 1,220 657 776 2,240 750 Amount Spiked 50.0 50.0	0.0% 2.5% 2.0% 2.8% 3.0% Spiked Sample 1 40 1,230	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30%	2.1 1.8 1.7 1.5 2.2 1.0 Accept Range 80 - 120
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene Spike Conc. (ug/Kg) Methyl-tert-butly Ether Benzene Toluene	ND 1,190 671 792 2,180 728 <u>Sample</u> ND 1,190 671	ND 1,220 657 776 2,240 750 Amount Spiked 50.0 50.0 50.0	0.0% 2.5% 2.0% 2.8% 3.0% Spiked Sample 40 1,230 719	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% % <u>Recovery</u> 80.0% 99.2% 99.8%	2.1 1.8 1.7 1.5 2.2 1.0 Accept Range 80 - 120 39 - 150 46 - 148
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene Spike Conc. (ug/Kg) Methyl-tert-butly Ether Benzene Toluene Ethylbenzene	ND 1,190 671 792 2,180 728 <u>Sample</u> ND 1,190 671 792	ND 1,220 657 776 2,240 750 Amount Spiked 50.0 50.0 50.0 50.0	0.0% 2.5% 2.0% 2.8% 3.0% Spiked Sample 40 1,230 719 840	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	2.1 1.8 1.7 1.5 2.2 1.0 Accept Range 80 - 120 39 - 150 46 - 148 32 - 160
Methyl-tert-butly Ether Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene Spike Conc. (ug/Kg) Methyl-tert-butly Ether Benzene Toluene	ND 1,190 671 792 2,180 728 <u>Sample</u> ND 1,190 671	ND 1,220 657 776 2,240 750 Amount Spiked 50.0 50.0 50.0	0.0% 2.5% 2.0% 2.8% 3.0% Spiked Sample 40 1,230 719	0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% 0 - 30% % <u>Recovery</u> 80.0% 99.2% 99.8%	2.1 1.8 1.7 1.5 2.2 1.0 Accept Range 80 - 120 39 - 150 46 - 148

ND - Parameter not detected at the stated detection limit.

References:

Method 50308, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996. Method 80218, Aromatic and Halogenated Volatiles by Gas Chromatography Using Photoionization and/or Electrolytic Conductivity Detectors, SW-846, USEPA December 1996.

QA/QC for samples 30030 - 30034, 30055. Comments: Ánalyst

Mistine of Walter Review



PO Box 15700 Rio Rancho, NM 87174

Monday, October 04, 2004

Giant Refinery #50 Road 4990 P.O Box 159 Bloomfield, NM 87413

To: Cindy Hurtado

Effective 10/4/04 the waste material on Profile # SJC 06765 B has been approved for disposal at WASTE MANAGEMENT INC. San Juan County Landfill pending the return and approval of account set up information. The waste material will be treated on site to acceptable New Mexico State standards and directly disposed of at the San Juan County Landfill. This approval is limited to the waste described on the profile # stated above and is valid until 4/4/05. The San Juan County Facility reserves the right to reject any shipment of waste that fails to conform with profile sheet information/documentation.

Sincerely,

Waste Management Industrial Landfill Sales New Mexico

Mark Allen

1.AL

				<i>i</i>		NSFER		-	Ø 002
21 SEP-2:	04 12:16p 1-2024 10:03	RR LAN GIRNT	DFILL REFINING	S BLUUMH 1	ΕLD		5058922057 505	635 3211	р.2 2017
			·	FOR'S WA		orti e g	иггт		
		海		PRINTININ				0/	NER
Sel	vice Agreement on File	? XIYES TNO					Profile Number, WM		765B
	Hazardous XINon-H	azardous TTSC	<u>CA</u>				Renewal Date:	OVE	TIME
1.	Waste Selierator Infor Generator Name:	<u>ייין איינאין יחסווכחת</u> זבור הקצ) והבוס			2.	SIC Code	3:	tule. 19	
3 5.	Facility Streat Address Facility City - Ello	s #50 Road . omfeld	4990		به <u>م</u>	Phone: State/Pro	505-632-4751		
7.	Zip/Postel Code	87413			8.	Generate	or USEPA/Federal ID	: NMD	08941641G
9 זו	County' <u>SAA</u> Customer Name:	PHILIP TISASPO			16 12	Custom		2524405	
	Customer Contact: Billing Adviress	Scott Daties	-11-FTd.	АЗ Абр	14	Custom	er Fax: <u>602-262</u>	1520-	TIC 83 300VE
	Waste Striam Informa								
		· 철말 한 (영문) 고려 : 고려 : 지역						- · ·	
							<u>e ja kanga</u> na ka <u>ng</u>		and a second second second second second second second second second second second second second second second s
1.	Description 2 Name of Waste.	Petroleum cor	TRAINING BO	211					
	b. Proorss General	ng Waste: _S	liate mandale	d cleanup of	petroleum	hydrocast	cons leaching from unc	ter oil refinery.	
		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					lover	g. Free ho	
	c. Coloi Black	d, Strong odor (describe):		Physical sti solid	are (g 70-1	r   ^{c.}	Loyers Øsingle Layer	ß	
	brown	Dil		⊡G3¢ ⊡Other	Sludge	=  X		h, pH; Ra <u>616</u> 8	nge
				·					
	i. Liquid Flash Poi j. Ch <u>amical</u> Comp	nt: 🔲 3*F 🛛 🔲<br Notition (List of constants	73-99*F [	]100-139"F	-041 [] Lindeb .com	1997F 	DOGEN IN ENV CONCERNING	BODICBOIE	ESCALOFIED ONBITOLES
	Constituints Soil		56 - 100%	tion Range		nstituenta	·····	Concent	ration Range
	Potroleum hydrocard	2013	0-2%						
	h (Dixidizer )		alasva Mi	Radiozclive		onen [	CEED 100%	_	Wobr Reactive
	<ol> <li>Does the waste re- if yes</li> <li>m. Does the waste</li> </ol>	Pyrophonic Ex prosented by this p represented by this	plosivo DF rofile contain profile contain	Radiozclive #3bc3t657	Carcin	ogon [	Intectious Eshoc	_	
	<ol> <li>Does the waste re- if yes</li></ol>	Pyrophane Ex presented by this p represented by this	plosivo DF rafile contain protike contain	Radiozclive asbcotos7 n benzané?	Carcin	<b>000 [</b>	Infectious Shoc	_	TYES MO
2.	I. Does the waste re If yest	Pyrophane Ex presented by this p represented by this tion <u>1.190 pr</u> cantain debrie? (liat	plosivo DF rafile contain protike contain	Radiozciwe sobcotos? n benzaná?	Carcin	2001 (	Infectious Shoc	n-Inable	TYES NO
. <b></b> 2. 3.	<ol> <li>Does the waste re if yes, concentration if yes, concentration, n. Does the waste Quantity of Waste Estimated Annual Volume Estimated Annual Volume</li> </ol>	Pyrophonic Expresented by this prepresented by this prepresented by this prepresented by this contain debrie? (list blume 16	plosivo DF rafile contain protile contain ob In Section B	Radiozciwe sobcotos? n benzaná?	Carcin	naço Tards (	Infectious Shoc	n-Inable œci(y)	TYES NO
	<ol> <li>Does the waste re if yest</li></ol>	Pyrophonic Expresented by this presented by this presented by this presented by this contain debrie? (liat blume 15 contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie? (liat contain debrie?	plosivo rafile contain protile contai	Radiozclive sobcotos7 n benzana? T.)) Bulk Liquik	Carcin Tons C J. Type/Siz	ogon ()  )Yards () 	Intectious Shoc Inable Ino Soums Other (so Soum, Type, arter I Year Sone	n-Inable weify) Size:55 pal	UYES ONO
	<ol> <li>Does the waste re if yest</li></ol>	Pyrophone Ex presented by this tion 1.190 py cantel debrie? (list put Sold: Type/Size ncy: Units partment of Transpo	iplosivo []]F irafile contain protile contain of in Section B	Radiozclive sobootos7 n benzana? T.)) Bulk Liquid P OT) Hazardou	Carcin Tons C J. Type/Siz	2300 (IT 2015) 	Intectious Shoc Inable Ino Drums Other (so Drum, Type, arter Year Mone kip d, s, and f)	n-Inable weify) Size:55 pal	THES MO
	<ol> <li>Does the waste re If yet:</li></ol>	Pyrophonic Ex prosented by this p represented by this tion <u>1.190 py</u> contain debrit? (flat blume <u>16</u> pontain debrit? (flat pontain	eplosivo DF rafile contain profile contain pro	Radiozclive sobcotos7 n benzana? T.)) Bulk Liquik	Carcin Tons C J. Type/Siz	2300 (IT 2015) 	Intectious Shoc Inable Ino Soums Other (so Soum, Type, arter I Year Sone	n-Inable weify) Size:55 pal	UYES ONO
3.	<ol> <li>Does the waste re</li></ol>	Pyrophane Ex presented by this represented by this ion <u>1.190</u> py cantain debrie? (liat plume <u>16</u> phume <u>16</u> phume <u>16</u> phume <u>16</u> phume <u>16</u> phume, <u>17</u> represented by this represented by this part of the represented by this part ment of Transpo http://www.link. Name.	iplosivo []]F irafile contain protile contain to Section B 16 x 55 gal. ontation (USD	Radiozclive soboot657 n bonzana? T.)) Bulk Liquk P OT) Hazardou	Carcin Tons C J. Type/Siz More: More Material	ogon []  ]Yards [] re; IT no. si o Hazen Ne cistow	]Infectious ☐Shoc ☐fnable ☐no ∬Drums ☐Other (so , ⊠Drum, Type, arter ☐Year ⊠One kip d, ø, and t) d ClassJID #:	n-Inable secify) Size:55 gal timeOthor	
3.	<ol> <li>Does the waste re If yet:</li></ol>	Pyrophonic Ex presented by this p represented by this tion <u>1.130 py</u> contain debrie? (flat blume <u>16</u> put Solid: Type/Size ncy: Units put ment of Transpo- ntly (bs.; kps.): Ivanc. Iva Equipment Requ Instratolis vests (40 way ALL USEPA liste	cplosivo []]F irafi(e contain profile contain profile contain po in Section B 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 0 dation (USD University) CFH Hart 28 d and charged	Radiozclive sobcotos7 n benzaná? 1,) Bulk Liquk OT) Hazardou P OT) Hazardou 1)7 lí the answ gristič wastie C	Carcin Tons J. Type/Siz J. Type/Siz Mer: More wa Material Material Material Material	2000 [ 	]Infectious Shoc ☐fnable ☐no Sours Other (so , ⊗Drum, Type. arter ☐Year ⊠One kip d, e, and t)	n-Inable secify) Size:55 gal timeOthor	UYES ONO
3. <b>KG</b> 1	<ol> <li>Does the waste re If yes, concentrat If yes, concentrat Rotes the waste Quantity of Waste Estimated Annual Vo Shipping Informatic a Packaging Bit b. Shipping Freque c, is this a U.S. Dej d. Recontable Quart 1. USCHOT Shipping Personal Protect Is this out USEPA a. It yes, ide b. It a charact USEPA         a. It yes, ide b. It a charact USEPA         a. It yes, ide b. It a charact         b. It a</li></ol>	Pyrophone Ex presented by this icon 1.100 py cantel a brit? (list plume 15 phi ulk Solid: Type/Size nay: Units partment of Transpo- ntity (los.; kgs.): Name. Ive Equipment Red Units Solid: Solid: 40 why ALL USEPA Iste and the Size (40 why ALL USEPA Iste and the Size (40 why ALL USEPA Iste and the Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (40) why a size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size (10) Size	iplosivo []]F irafile contain protile contain protile contain protile contain protile contain the section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B in Section B i	Radiozclive szbcztóś? in benzana? i.) Bulk Liquk P OT) Hazardou ristic wzety c yring hazardou	Tons Tons J. Type/Siz Ver: More vas Material ver is no, siz cas numbe a constituer	2000 []  ]Yards []  Ith []Qu: I ³ (If no. 51 o Hazar Hazar Ite cc.cov up to 2 its [], F, K	]Infectious ☐Shoc ☐fnable ☐no ☐fnable ☐no ③Drums ☐Other (so , ⊠Drum, Type. arter ☐Year ⊠One kip d, e, and f) d ClassJID #: 	n-Inable &cify)	YES ⊠NO ⊗YES □ND YES ⊠NO □Outhor: □YES □NO TYES ⊠NO
3.	<ol> <li>Does the waste re If yest.</li> <li>Does the waster If yest, concentrat n. Does the waster Quantity of Waster Estimated Annual Vo Shipping Information Packaging Bit b. Shipping Freque c. Is this a U.S. Dej d. Recontable Quait 1. USCHOT Shipping g. Personal Protect first a USEPA a. If yes, idea b. If a characa (UHCS) applications is the bas to the a size has be the a size has be the size the basis</li> </ol>	Pyrophone Ex presented by this represented by this tion <u>1.190 py</u> cantain debrit? (list bume <u>15</u> partment of Transpo- nity (bs.; kgs.): Namo. Namo. Namo. Namo. Namo. Namo. Namo. Namo. Namo. Set Control (State Chief hazardous wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos wash? Martin Set (400 ergin maxardoos w	in Section B in	Radiozctive szbcotos7 n benzane? T.)) Bulk Liquid Bulk Liquid P OT) Hazardou Isascontes. S y? if the anne ying hazardou	Tone Tone J. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Type/Siz G. Typ	2000 [] 	]Infectious ☐Shoe ☐Inable ☐no ☐Inable ☐no ③Drums ☐Other (so , ◎Drum, Type, arter ☐Year ◎One kip d, e, and t) d Class/ID #: 	n-Iriable seci(y)	YES ⊠NO         ⊗YES ⊡NO         □YES ⊠NO         □YES ⊡NO         □YES ⊡NO
3. <b>KG</b> 1	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this represented by this represented by this contain debrie? (flat blume 15 phills partment of Transpo- nity (los.; kgs.): I Name. Ivo Equipment Requires hazardolls wester (40 why ALL USEPA Ister entern mexandous waster of a CERCLA (40 CFR a CERCLA (40 CFR	iplosivo []]F irafile contain protile	Radiozclive szbcotós7 n benzáné? T.)) Bulk Liquid P OT) Hazardou ristic waztł oc yring hazardou wing hazardou x 8) or stale m 122 oldor or ci	Tons Tons Tons J. Type/Siz J. Type/Si	Copon Tards ( ce: ath □Qu: 12 (If no, Si 0 Hazar 12 C(P, K 15 12 (C, P, K 15 12 (C, P, K 15 12 (C, P, K 15 12 (C, P, K 15 15 15 15 15 15 15 15 15 15	]Infectious ☐Shoc ☐Inable ☐no ☐Inable ☐no ③Drums ☐Other (so , ◎Drum, Type, arter ☐Year ⊠One kip d, e, and t) d Closs/ID #: 	n-Iriable seci(y)	YES ⊠NO ⊗YES □ND YES ⊠NO □Outhor: □YES □NO TYES ⊠NO
3. 1 2.	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this represented by this tion <u>1.190 py</u> carue)n debrit? (lint blume <u>15</u> partment of Transpo- nity (Ins.; kgs.): I Namo. Itivo Equipment Red. httpn://sizechar hazardolls weste (400 wy ALL USEPA Isto partment of CFR is CERCLA (40 CFR ord of Decision (ROD mandaled Gear-up, mandaled Gear-up,	colosivo []]F rafile contain protile c	Radiozclive szcotosz n berizana? T.)) Bulk Liquid P CT) Hazardou ristic watty c ristic ristic watty c ristic ristic ristic watty c ristic ristic ristic watty c ristic ristic watty c ristic ristic ristic watty c ristic ristic ristic watty c ristic ristic	Tone Tone Tone J. Type/Siz J. Type/Siz	Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon Copon C	Juntectious Shoe Intectious Shoe Inable Ino Source Interest Source State Source	n-Iriable Deci(y)	YES ⊠NO         ⊗YFS □NO         YES ⊠NO         □YES ⊠NO         □YES □NO         □YES ⊠NO         □YES ⊠NO         □YES ⊠NO
3. 1 2. 3	<ol> <li>Does the waste re</li></ol>	Pyrophone EX presented by this p represented by this p tion <u>1.190 pp</u> contain debrie? (flat blume <u>15</u> on ulk Solid: Type/Size ney: Units pattment of Transpo- nity (fos.; kps.): Name. Ivo Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires the Equipment Requires t	colosivo []]F rafi(e contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain (USD Unrements: e) (USD Unrements: e) (USD Unrements: e) (USD Unrements: e) (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (USD (	Radiozclive sobcotos7 n benzands? 1,j) Bulk Liquk P (T) Hazardou (T) Carcine Tons Tons J. Type/Siz J. Type/Siz	Tards ( Tards	]Infectious ☐Shoc ☐Inable ☐no ☐Inable ☐no ☐Inable ☐no ☐Drums ☐Other (so , ☑Drum, Type. arter ☐Year ☑One kip d. ø. and f) d Class/IO #: 	n-Iriable secily)	YES ⊠NO         ⊗YFS □NO         YES ⊠NO         Outhor         Outhor         YES □NO         □YES □NO         □YES □NO         □YES □NO         □YES □NO	
3. 1 2. 3	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this represented by this ion <u>1.190</u> ps carua)n debrit? (liat blume <u>15</u> partment of Transpo- nity (hos.; kgs.): I Namo. Ilva Equipment Red hazardolls weste (40 way ALL USEPA Istic Partment of CFR in Sectors waster bly? (il yes, list in Sec cardous waster a CERCIA (40 CFR ord of Decision (ROD mandaled Gash-up, procented by this was regulated by 40 CFR	cplosivo []]F rafile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 16 x 52 gal. 17 x 52 gal. 16 x 52 gal. 17 x 52 gal. 16 x 52 gal. 17 x 52 gal. 17 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18 x 52 gal. 18	Radiozclive szbcotos7 n benzane? T.)) Bulk Liquid P CT) Hazardou right watte right watte right watte Radionaes si right watte right watt	Carcin Tone Tone Tone Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz	by an example of the second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second s	Juntectious Shoe Inable Ino Inable Ino Sources Other (see , ⊠Drum, Type, arter IYear ⊠One kip d, e, and the d Class/ID #: . P, U) s site clean-up s dispeal point-site	n-Iriable secily)	YES ⊠NO         ⊗YFS □NO         YES ⊠NO         □YES ⊠NO         □YES □NO         □YES ⊠NO         □YES ⊠NO         □YES ⊠NO
3. 1 2. 3	<ol> <li>Does the waste re</li></ol>	Pyrophonic Ex presented by this p represented by this p tion 1.190 pp cantain debrit? (list putk Solid: Type/Size ncy: Units pattment of Transpo- nity (los.; kga.): Namo. Iting Equipment Req Martine (State Chart hazardous waise (AD My ALL USEPA Iste entit in the state of the a CERCLA (40 CFR ord of Deceson (ROCE mandated dean-up, spreanted by this way Nidear Regulatory (CFR or epulated by this way Nidear Regulatory (CFR of Deceson (ROCE mandated dean-up, spreanted by this way Nidear Regulatory (CFR of Deceson (ROCE) mandated dean-up, spreanted by this way Nidear Regulatory (CFR of Deceson (ROCE) mandated dean-up, spreanted by this way Nidear Regulatory (CFR of Deceson (ROCE) mandated dean-up, spreanted by this way Nidear Regulatory (CFR) of Deceson (ROCE)	colosivo []]F rafile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain 16 x 52 gal. 16 x 53 gal. 17 x 54 gal. 17 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 54 gal. 18 x 5	Radiozclive sobootos7 in benzand? i,) Bulk Liquid P Bulk Liquid P CT) Hazardou rightic earsur yring hazardou yring hazardou solution set earsur at contain con mist in Chemidan at contain con mist in Chemidan	Curcial Carcine Tons C Tons C Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Type/Siz Constitution Type/Siz Constitution Constitution Curcial description Curcial desc	agon () )Yards () arth ()Qu. )7 (If no. 5) o Hazen (If o Course up to 2	Jutectious Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Shoe Sh	n-Iriable ====================================	YES ONO
3. 1 2. 3 4 5 6	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by the p represented by the p represented by the ion <u>1.190 p</u> carue)n debrit? (flat plume <u>15</u> partment of Transpo- nity (bs.; kgs.): Nama. Ivon 12(5)(3-(3-1)) hazardous veste (40 w/y ALL USEPA 1st in Sec provident Requirement Requirement hazardous veste (40 w/y ALL USEPA 1st in Sec provident analytic veste a CERCLA (40 CFR or dol Decision (ROD mandaled deam-up, spreached by this was required	cplosivo []]F rafile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain the second second and charped char B.1;) protile second provide relevant provide relevan	Radiozclive szcotos7 n benzáné? T.)) Bulk Liquik P OT) Hazardou ristoniacs, sz viny hazardou viny hazardou sz contacs, sz viny hazardou kaloniacs, sz viny hazardou kaloniacs, sz viny hazardou sz contacs, sz un trug and no postassion of un trug and no postassion of contact viny bug and no	Curote desc Curote	Dyards ( Trards	Juntectious Shoc Strable Ino Sources Other (so Sources Sources) Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources	n-Iriable Size:55 gal time D#por	YES ⊠NO         ⊠YES ⊡NO         □YES ⊠NO         □YES ⊠NO         □YES ⊡NO         □YES ⊡NO         □YES ⊡NO         □YES ⊠NO
3. 1 2. 3 5 5	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this p represented by this p tion <u>1.190 pg</u> cantain debrit? (lifet blume <u>15</u> outk Solid: Type/Size ney: Units partment of Transpon nity (bs.; kga.); Name. Ivo Equipment Req thom (196566 Cheff hazardolis veste (400 erkin maxardools val bly? (if yes, list in Sco provide a car-up, a CERCLA (400 FR ord of Occasion (ROD mendaled dar-up, portanted by this was inequisited by t	colosivo []]F rafi(e contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain 16 x 52 g24. 16 x 52 g24. 16 x 52 g24. District contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain	Radiozctive szbcztos? n benzane? T.)) Bulk Liquik P CT) Hazardou Radonnica, S 17 the article P CT) Hazardou right azardou right azardou signonica, S 122 ordor or cu sont documenta art contain core nist in Che.mentai closed to the C waste be identi	Carcine Tons Type/Siz I. Type/Siz I. Type/	Dyards ( Tards ( Ta	Infectious Shoe Inable no Inable	n-Iriable Size:55 gal time D#por	YES ⊠NO         ⊠YES ⊡NO         □YES ⊠NO         □YES ⊠NO         □YES ⊡NO         □YES ⊡NO         □YES ⊡NO         □YES ⊠NO
3. 1 2. 3 5 5	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this p represented by this p tion <u>1.190 pg</u> cantain debrit? (lifet blume <u>15</u> outk Solid: Type/Size ney: Units partment of Transpon nity (bs.; kga.); Name. Ivo Equipment Req thom (196566 Cheff hazardolis veste (400 erkin maxardools val bly? (if yes, list in Sco provide a car-up, a CERCLA (400 FR ord of Occasion (ROD mendaled dar-up, portanted by this was inequisited by t	colosivo []]F rafi(e contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain 16 x 52 g24. 16 x 52 g24. 16 x 52 g24. District contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain	Radiozctive szbcztos? n benzane? T.)) Bulk Liquik P CT) Hazardou Radonnica, S 17 the article P CT) Hazardou right azardou right azardou signonica, S 122 ordor or cu sont documenta art contain core nist in Che.mentai closed to the C waste be identi	Carcine Tons Type/Siz I. Type/Siz I. Type/	Dyards ( Tards ( Ta	Infectious Shoe Inable no Inable	n-Iriable Size:55 gal time D#por	YES ⊠NO         ⊠YES ⊡NO         □YES ⊠NO         □YES ⊠NO         □YES ⊡NO         □YES ⊡NO         □YES ⊡NO         □YES ⊠NO
3. 1 2. 3 5 5	<ol> <li>Does the waste re</li></ol>	Pyrophone Ex presented by this p represented by this p tion <u>1.190 pg</u> cantain debrit? (lifet blume <u>15</u> outk Solid: Type/Size ney: Units partment of Transpon nity (bs.; kga.); Name. Ivo Equipment Req thom (196566 Cheff hazardolis veste (400 erkin maxardools val bly? (if yes, list in Sco provide a car-up, a CERCLA (400 FR ord of Occasion (ROD mendaled dar-up, portanted by this was inequisited by t	colosivo []]F rafi(e contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain 16 x 52 g24. 16 x 52 g24. 16 x 52 g24. District contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain protile contain	Radiozctive szbcztos? n benzane? T.)) Bulk Liquik P CT) Hazardou Radonnica, S 17 the article P CT) Hazardou right azardou right azardou signonica, S 122 ordor or cu sont documenta art contain core nist in Che.mentai closed to the C waste be identi	Carcine Tons Type/Siz I. Type/Siz I. Type/	Dyards ( Tards ( Ta	Juntectious Shoc Strable Ino Sources Other (so Sources Sources) Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources Sources	n-Iriable Size:55 gal time D#por	YES ⊠NO         ØYFS ☐NO         YES ⊠NO         ÛOUNOT         ÛOUNOT         ÎOUNOT         YES ⊡NO         ÎYES ⊡NO         ÎYES ⊠NO         ÎYES ⊠NO

10/	04/	04	16:14	FAX	60245	42070	)	SKY	HARBOR TRA	N <u>ŞFER</u>			Ø 003
				100			ANDFI	1.	· ·	50	J58922	057	p.3
еP	21	0	412;	16p				ם נאוויה	CURF IELU			505 632 3911	P.03
			M	ir va a			CEN	ERATOR	'S WASTE PR	ofile sin	eet		
					و. *•	Any so	manie submitt	ed is reneated	NT IN INX OR TYPE	40 000 304		or by using the equiva	
		i≉uth( suth	yixe WMi; Nixed ⊐ces	) obtain :	sample								
		3331	indini lano	alona	K has de	amined	to be reason		Concernings in this Pri Or If Deprived for a			to by a braker, the rin provided by the par- as all the necroscry p	
			e waxie (hi fication Si		on chorse	77		CY I SHA ADDOD	ed profile.			Connental A	
			e (Type or		1	Carda H	4 Hauts	ag	Company NAM				
		-					ck if addition	vit informatio	is attached ind	Calle the num	ber of allac	ery - Bloom Field	Data: <u>9-71-04</u>
			Û	AU	red,	Are	, dit	it and		Jum		Terry	When The
		1-4	/			[]			Instructions				1 1
		netan Noun	na noisen i manner	this form This inf	is used	fa delon	mine if the w	aslo may be	transported, trans	id, sloved or t	diaposed in	a legal sale, and an	vilonm=ntally
		10.0	17030. A	respons	60 NU	NE DIC		ii(CaDie) Can I	be made if annon	unha iladrida	Analenate i	s ecoded inducute	an the form that
		9000	iniori iniori	naivon is	andchei	J. 200 21		n nauon in C	enerator's Waste	Profile Sheet	. If you have	e questions conceir	ing this form,
	1	Dieas A.V	ASIC GO	INC LONG	(BC(or 3		presentative,		the all is a state				
		1	Generato	i Name.	. Enter th	e name	of the facility	v where the i	waste is generaled				
		2	SIC Code	<ul> <li>Einter 1</li> </ul>	ne lour d	figit Star	ndard Industi	rial Classifics	tion Cone for the !	acility where I	the waste is	generated,	
		4	Phone - E	Nar Ger	veralor's	⊐rea co	de and phon	ensinsing Enginder	Box) of the facility	i where the w	aste is gane	rated.	
		3.	Facility C	🖓 - Enti	er the ch	where	the waste is	cenerated.					
		6. 7.	Stats/Posts Zio/Posts	LCode - E	Soler the	sigle or e depart	province wh ading (acility's	ere the wasi	ic is generaled.				
		8	Generato	/ USEP#	VFedera	1104-6	Enter the Ide	ntilication nu	Imber issued by th	USEPA, CA	hadian, or M	Aexican Federal	
			Agency to	ne taci	ay gener	⊐ring the	e wosle (f ⊐e	selicable)	-				
		10.	Slate/Pro-	since ID	# - Ente	n bha ida	e waste is g	oneratod. Iniber insuer	I by the stats of pr	wiece in the i	facility datas	roline the	
			W38VC (# 3	ODICASK									
		11	Customer	Name -	Entity It	bl the C	ioniracior is i e se Above"	cirectly work	ing with regarding	the represent	icd wriate St	cam, if the	
		12.	Customa	Phone	- Enter to	schnical	contact's en	cz code and	серлона питро				
		13.	ÇVSlómei	Contac	s - Enter	the nam	te of the per-	sca who can	20Swer technical	Suestiona abo	out the wast	<b>C.</b>	
		14.	Custoner Billing Ad	ilmets	rea code Address	and fac	Simde numb	er for the cut	Stomer.				
	:	B M	laste Stre	m inter	manion	2,11,1	وروافية المعرز الم		and the second second		Park Prov		at the state of the light
		1 a.	Name of \	il'aste - (	Euler a u	ame ger	nerally descr	uplive of this	Waste (o n paint	Cludina Tiutura	scant hulbs		
		1.0	FOUCSES (	jonerati depera	ng Waci Ior Ibo y	o - Desc	Tibe the proc	cess general	and the waste in di Dal refuse, especie	all List the	specific pro	cess/operation or	
			building m	ានស្រុកទាំង	ice),								
			At a musim	um, the C	Severator	should	mawor the fo	licwing quest	ions in determining	ina process go	charaling the	wasta	
		-	la th	e waste d	ienerated	ned and	for used at the	e lacility? na hulachinne	of any of the follow	ing ladiaries:		nuelion :	
			-norg	CANC DIGH	hemis; erg	יפוס סייזבן	האטוב: המצויב	iuur, auplosiv	er: panoloun reinj	to: iron and st	hel concer	lead or zinc promietic	n7
		•	io (h treati	a wésté a ment (stu	ו ירשטון לני בנופב), פי	on dogra Obcirool	tating, solver lating?	si parta peani	ng. recovery/radua	nud of topisti	6 (bollonis),	waslewater	
		1.6	Color - Do	:: cribe tr	ne color a	tho wa	1516 (o.g., b).	e, transpare	int, varies).				
				lor • <u>DO</u>	NOT SM	ELL TH	E WASTE!	lf (he waste l	has a known oder.	then doscube	e (e.g., acrid	, pungons, solvans,	
			sweep. Physical :	Late (b)	70°E - 11	lhe four	boxes prove	tes do not a	pply, a descriptive	bhase may t	te enterted a	fter "Other" (e.a.	
			multi-phas	a).									
			Layers - S (e.g., oil/w			15 Ule w	aste is home	ogenous. Mi	lli-layer means the	wasie ia con	nonisod of N	to of more layers	
		1 g	Free liqui	egner b	Range	(in perci	ent by volum	c) of free ka	uids in the weste				
		15,	pH Range	<ul> <li>Indical</li> </ul>	to the p⊦	l range							
		11	Liquid F)# Chemical	i≶h Poin Carnon	t - indica Litilori - T	19 159 18 151 39 ce	osnic Sadiol	laised using Triomanic cr	the appropriate les	il method. Iomra uziaa ci	hemical e	we. It trade names	
			are used,	alloch M	atemai S.	elety Da	ta Sheets or	other secur	nents that adequat	nly describe t	he composi	tion of the waste	
			For each o	:::mpone	nt, estam	ato the i	range (in ber	CERC IN Which	the component i	s present, Ide	entify any ek	ment, chemical cor	hpound, or
		1,5.	Check all t	inat appl	⊔oiu,1p: V.	encent o	r greater wa	f iti continen	ed a carcinogen o	privential can	cinegen pui	suant to OSHA	
		7.1. I	ndicate il t	his waste	contain	s asbesi	los. Indicate	if the action	tos 14 friable.		_		
							onc, the lave = {list size an		d whether k is sub	ect to the ber	Nzane NESP	IAP.	
										collona) that	will be race	wed by the ultimate	
		_	managem	cul laciti	ly This	rolume :	autorut is uo	t intended fo	x use in complying	with state an	d/or permit	restrictions.	
									with a description her" along with a c	-zenetiaa			
									liner along with a d Lardous motorial?		e apôrconati	- 10500n3#:	
			yes of no.										
		30.	Reportab	In Quan	illy (lbs.)	: kgs.) -	If the answe	r to 3,c, is w	cs. enter the Repo waste, Indicate th	silneuD alden	y (RO) aso	blished by 40 CFR	
		3 🗧							proper USDOT »				
		31	USDOT S	nipping	Nome .	iF lne ar	nswar to 3.c.	o yes, ente	t the proper USDC	11 вырыля па	ime for the	NASIC.	
		. <b>ل</b> وا . ل	waste ste		YE EQUI	procent F	acquerementen.	15 - AU (C110	nal protective equ	MUEUL UÇÇAR	sery to sale	y manage the	
										Celtra !			

Oct 26 04 01:58p	RR LANDFILL		5058922057		p.2
18/25/2084 22:14	15053348768	SJC LF	FAY	PAGE UI	
DOT DC 0004 48:07	GTONE DEETNING RU	DOMELELD	525 632 3911	P. 92	

Niedzij 1625 N. Franch I.V., Hobba, NM 182200 Dereiciji	State of New Mexico Energy Minerals and Natural Resources	Form C-131 Revised Jone 10, 500
130) W. Grond Averaic, Artecia, NM 84210 Olinetic III 1000 Kin Beneos Rond, Astuc, NM 87410 Daties: IV 1220 S. St. Francis Dr., Sama Pc, NM 87505	Oil Conservation Division 1220 South St. Francis Dr. Santa Fe. NM 87505	Submit Origina Phas I Copy to Appropriat District Office

#### REQUEST FOR APPROVAL TO ACCEPT SOLID WASTE

1. RCRA Excoupt: D Non-Excoupt: 2	4. Generator Glant Refining Company
·: Verbel Approval Received: Yes No	5. Originating Site Clant Refinery-Bloomfield
2. Maragement Facility Destination San Juan County Regional Landfill	6. Transporter Waste Management
3 Address of Facility Operator \$78 CR 3140 Artec, NM 87410	8. State New Maxico
7. Location of Material (Street Address or ULSTR) #49 CR 4990 Bloomfield, NY 87413	

9. Cirolo One:

- A. All requests for approval to accept oilfield exempt wastes will be accompanied by a coefficient of waste from the Generator, one contribute per job. B. All requests for approval to accept non-exempt wastes must be accompanied by nucleasing chemical analysis to PROVE the
- E. All requests for approval to accept non-exempt water must be accompanied by nocessary chemical analysis to PROVE the material is not-hozardous and the Ocacrutar's certification of origin. No waste classified bazardous by listing or tosting will be approved
- All transporters must certify the wester delivered are only those consigned for transport.

BRIEF DESCRIPTION OF MATERIAL:

Petroleum Impacted Soil

Must have OCA approval letter At SAN JUAN County LAND Gill. At SAN JUAN County LAND Gill. All SAN JUAN County LAND GILSON 20126101

Estimated Volume	~/	• • •	r at the end of the haul)	
	Antherical Agent	TITLE Dictrict	Mg. R. DATE: 101	= 6/04
TYPE OR PRINT NAME:	John	HAMMERTELEPH	DNENO. 505 334 1	112.1
F-MAIL AUDRESS	Jhannen	Q U.M.	C. 0 1 M	
(This sporse for State User				
APPROVED BY:		TITLE:	DATE	
APPROVED BY:		TITLE:	DATE:	]

	1. Merel	The program and the second
SPECIAL WASTE SHIPMENT RE		
SAN JUAN COUNTY REGIONAL LANDFILL -		Shipment # 7277
Mailing Address: Physical Address: Physical Address: Physical Address: #78 CR 314	<u>arooo.</u>	Shipment # 72/7
⇒c, New Mexico 87410 4ztec, New 505/334-1121		06765B Profile # (Required)
A Waste Management Company		(Required)
1. Generator's Work site name and address	INDUSTRIES, 50 CR 4990, B	LOOMFIELD, NM 87413
2. Generator's name and address BLANT INDUSTRIES		Operator's Telephone no.
50 CR 4990 BLOOMFIELD, NM 87413		(505) 632-4161
3. Authorized Agent name and address		Owner's Telephone no.
GLANI INDUSTRIES 50 CR 4990 BLOOMFIELD, NM 37413		(505) 632-4161
4. Description materials	5. Container's	6. Total Quantity
	No. Type	m3 (yd3) Human
PETROLEUM CONTAMINATED SOIL	20YD "3"	<u></u>
8. AUTHORIZED AGENT CERTIFICATION: I hereby rately described above and are classified, packed for transport by highway in accordance with appli that the above named material does not contain that hazardous waste as defined by 40CFR 261 or an	d, marked and labeled, and are in cable international and governme free liquid as defined by 40CFR P	all respects in proper condition nt regulations. I hereby certify
Printed/typed name and title	Authorized Agents Signature	Month/Day/Year
Tome & R. Thomas & Reparation Sec.	and low K Para	11 14/144
9. Transporter 1 (Acknowlegement of receipt of mate		<u> </u>
Printed/typed name & title, address, telephone no. SHANE MOORE, DRIVER #49386	Authorized Agents Signature	Month/Day/Year
WASEEMMANAGEMENT, 101 SPRUCE ST. FARMINGTON, NM 87401 (505)327-6284	Strand Million	
10. Transporter 2 (Acknowledgement of receipt of n	naterials)	
Printed/typed name & title, address, telephone no.	Authorized Agents Signature	Month/Day/Year
		1 1
11. Discrepancy indication space	the Il Vacas	
12. Waste disposal site certification of receipt of ma	terials covered by this manifest ex	ccept as noted in item 11.
1		
Printed/typed name and title	Signature	Month / Day / Year
White/GEN Yellow/LANDFILL Pink/TRANSF	PORTER Golden/GEN	san juan reproduction 98-165

September 6, 2004

Mr. Randy Schmaltz Giant Refinery P.O. Box 159 Bloomfield, NM 87413

Phone: (505) 632-4171

Client No.: 96012-009

Dear Mr. Schmaltz,

Enclosed are the analytical results for the soil samples collected by Giant designated personnel on 8/31/04, and received by the Envirotech laboratory on 8/31/04 for Total Petroleum Hydrocarbons (TPH) per USEPA Method 8015, BTEX per USEPA Method 8021, RCRA 8 List Metals, Flashpoint, Ignitability, Corrosivity and Reactivity analysis.

The samples were documented on Envirotech Chain of Custody No. 12882. The samples were assigned Laboratory Nos. 30341 (Hydroblast Comp)and 30342 (Tank 36 Comp) for tracking purposes.

The samples were analyzed on 9/01/04 and 9/02/04 using USEPA or equivalent methods.

Should you have any questions or require additional information, please do not hesitate to contact us at (505) 632-0615.

Respectfully submitted, **Envirotech**, **Inc**.

Christine M. Walters / Laboratory Coordinator / Environmental Scientist

enc.

CMW/cmw

C:/files/labreports/Giant.wpd

1

#### EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Hydroblast Comp.	Date Reported:	09-01-04
Laboratory Number:	30341	Date Sampled:	08-31-04
Chain of Custody:	12882	Date Received:	08-31-04
Sample Matrix:	Soil	Date Analyzed:	09-01-04
Preservative:	Cool	Date Extracted:	09-01-04
Condition:	Cool & Intact	Analysis Requested:	BTEX

Parameter	Concentration (ug/Kg)	Det. Limit (ug/Kg)
Benzene	\$ <b>9</b> ,7,4	1.8
Toluene	<u>بچ 9</u> ,7.4 85.9	1.7
Ethylbenzene	105	1.5
p,m-Xylene	285	2.2
o-Xylene	149	1.0
Total BTEX	722	

ND - Parameter not detected at the stated detection limit.

		-
Surrogate Recoveries:	Parameter	Percent Recovery
	Fluorobenzene	95 %
	1,4-difluorobenzene	95 %
	Bromochlorobenzene	95 %

References: Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

Analyst

Mustine muceters Review

#### EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Tank 36 Comp.	Date Reported:	09-01-04
_aboratory Number:	30342	Date Sampled:	08-31-04
Chain of Custody:	12882	Date Received:	08-31-04
Sample Matrix:	Soil	Date Analyzed:	09-01-04
Preservative:	Cool	Date Extracted:	09-01-04
Condition:	Cool & Intact	Analysis Requested:	BTEX

Parameter	Concentration (ug/Kg)	Det. Limit (ug/Kg)
Benzene	11.3	1.8
Toluene	14.6	1.7
Ethylbenzene	14.0	1.5
p,m-Xylene	50.1	2.2
o-Xylene	58.8	1.0
Total BTEX	149	

ND - Parameter not detected at the stated detection limit.

Surrogate Recoveries:	Parameter	Percent Recovery
W	Fluorobenzene	95 %
	1,4-difluorobenzene	95 %
	Bromochlorobenzene	95 %

References: Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

Analyst

ne of Walter Review

### ENVIROTECH LABS PRACTICAL SOLUTIONS FOR A BETTER TOMORROW

#### EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

lient:	N/A		Project #:	N	I/A
ample ID:	09-01-BTEX QA/	oc	Date Reported:		9-01-04
aboratory Number:	30341	40	Date Sampled:		1/A
ample Matrix:	Soil		Date Received:		νΑ
reservative:	N/A		Date Analyzed:		9-01-04
Condition:	N/A		Analysis:		STEX
alibration and	I-Cal RF:	C-Cal RF:	%Diff.	Blank	Detect.
Detection Limits			nge 0 - 15%	Conc	Limit
Benzene	2.8990E-001	2.9077E-001	0.3%	ND	0.2
oluene	2.5460E-002	2.5511E-002	0.2%	ND	0.2
Ethylbenzene	3.8451E-002	3.8567E-002	0.3%	ND	0.2
o,m-Xylene	3.2988E-002	3.3088E-002	0.3%	ND	0.2
o-Xylene	3.3333E-002	3.3400E-002	0.2%	ND	0.1
Duplicate Conc. (i	g/Kg) Sample	Duplicate	%Diff.	Accept Range	Detect
Benzene	97.	4 96.2	2 1.2%	0 - 30%	1.8
Toluene	85.	9 84.2	2 2.0%	0 - 30%	1.7
Ethylbenzene	10			0 - 30%	1.5
	28			0 - 30%	2.2
U.m. Aviene					
o-Xylene	14	9 14	7 1.2%	0 - 30%	1.0
o-Xylene	14	9 14	•	0 - 30%	
o-Xylene Spike Conc. (ug/M	14	9 14 Amount Spikes	7 1.2%	0 - 30%	1.0
o-Xylene Spike Conc. (ug/P Benzene	14 (g)	9 14 Amount Spikes .4 50.	7 1.2% <u>1 Spiked Sample</u> 0 147	0 - 30%	1.0
o-Xylene Spike Conc. (ug/ł Benzene Toluene	14 (g) <u>Sample</u> 97 85	9 14 Amount Spiker .4 50. .9 50.	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135	0 - 30% % Recovery 99.9% 99.6%	1.0 <u>Accept Range</u> 39 - 150 46 - 148
p,m-Xylene o-Xylene Spike Conc. (ug/r Benzene Toluene Ethylbenzene n m-Yylene	14 (g) Sample 97 85 10	9 14 Amount Spikes .4 50. .9 50. 05 50.	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154	0 - 30% % Recovery 99.9% 99.6% 99.8%	1.0 Accept Range 39 - 150 46 - 148 32 - 160
o-Xylene Spike Conc. (ug/P Benzene Toluene Ethylbenzene p,m-Xylene	14 (g) <u>Sample</u> 97 85 10 28	9 14 Amount Spikes .4 50. .9 50. 05 50. 35 10	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384	0 - 30% 	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148
o-Xylene Spike Conc. (ug/M Benzene Toluene Ethylbenzene	14 (g) Sample 97 85 10	9 14 Amount Spikes .4 50. .9 50. 05 50. 35 10	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384	0 - 30% 	1.0 Accept Range 39 - 150 46 - 148 32 - 160
o-Xylene Spike Conc. (ug/P Benzene Toluene Ethylbenzene p,m-Xylene	14 (g) <u>Sample</u> 97 85 10 28	9 14 Amount Spikes .4 50. .9 50. 05 50. 35 10	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384	0 - 30% 	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148
o-Xylene Spike Conc. (ug/r Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene	14 (g) <u>Sample</u> 97 85 10 28	9 14 Amount Spikes .4 50. .9 50. 05 50. 35 10	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384	0 - 30% 	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148
o-Xylene Spike Conc. (ug/r Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene	14 (g) Sample 97 85 10 28 14 detected at the stated detection limit. Method 50308, Purge-and-Trap, Test	9 14 Amount Spikes 4 50. 9 50. 9 50. 35 10 49 50.	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384 0 198	0 - 30% 99.9% 99.6% 99.8% 99.8% 99.7%	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148 46 - 148
o-Xylene Spike Conc. (ug/P Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene ND - Parameter not	14 (g) Sample 97 85 10 28 14 14	9 14 Amount Spikes 4 50. 9 50. 9 50. 9 50. 35 10 49 50. Methods for Evaluationated Volatiles by Ga	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384 0 198 ng Solid Waste, SW-8 s Chromatography Us	0 - 30% 99.9% 99.6% 99.8% 99.8% 99.7% 46. USEPA, ing	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148 46 - 148
o-Xylene Spike Conc. (ug/P Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene ND - Parameter not	14 (g) Sample 97 85 10 28 14 detected at the stated detection limit. Method 50308, Purge-and-Trap, Test December 1996. Method 80218, Aromatic and Haloger	9 14 Amount Spiked 4 50. 9 50. 9 50. 9 50. 35 10 49 50. Methods for Evaluationated Volatiles by Gal	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384 0 198 mg Solid Waste, SW-8 s Chromatography Us SW-846, USEPA Dec	0 - 30% 99.9% 99.6% 99.8% 99.8% 99.7% 46. USEPA, ing	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148 46 - 148
o-Xylene Spike Conc. (ug/F Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene ND - Parameter not References:	14 (g) ?Sample 97 85 10 28 14 detected at the stated detection limit. Method 50308, Purge-and-Trap, Test December 1996. Method 80218, Aromatic and Haloger Photoionization and/or Electrolytic Co	9 14 Amount Spiked 4 50. 9 50. 9 50. 9 50. 35 10 49 50. Methods for Evaluationated Volatiles by Gal	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384 0 198 mg Solid Waste, SW-8 s Chromatography Us SW-846, USEPA Dec	0 - 30% 99.9% 99.6% 99.8% 99.8% 99.7% 46. USEPA, ing	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148 46 - 148
o-Xylene Spike Conc. (ug/F Benzene Toluene Ethylbenzene p,m-Xylene o-Xylene ND - Parameter not References:	14 (g) ?Sample 97 85 10 28 14 detected at the stated detection limit. Method 50308, Purge-and-Trap, Test December 1996. Method 80218, Aromatic and Haloger Photoionization and/or Electrolytic Co	9 14 Amount Spiked 4 50. 9 50. 9 50. 9 50. 35 10 49 50. Methods for Evaluationated Volatiles by Gal	7 1.2% <u>1 Spiked Sample</u> 0 147 0 135 0 154 0 384 0 198 mg Solid Waste, SW-8 s Chromatography Us SW-846, USEPA Dec	0 - 30% 99.9% 99.6% 99.8% 99.8% 99.7% 46. USEPA, ing	1.0 Accept Range 39 - 150 46 - 148 32 - 160 46 - 148 46 - 148



### EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Tank 36 Comp.	Date Reported:	09-01-04
Laboratory Number:	30342	Date Sampled:	08-31-04
Chain of Custody No:	12882	Date Received:	08-31-04
Sample Matrix:	Soil	Date Extracted:	09-01-04
Preservative:	Cool	Date Analyzed:	09-01-04
Condition:	Cool and Intact	Analysis Requested:	8015 TPH

Parameter	Concentration (mg/Kg)	Det. Limit (mg/Kg)
Gasoline Range (C5 - C10)	85.1	0.2
Diesel Range (C10 - C28)	266	0.1
Total Petroleum Hydrocarbons	351	0.2

ND - Parameter not detected at the stated detection limit.

References: Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

Analyst

ſ Review

3

NUS Wahway 64 - Formington NM 87401 • Tel 505 • 632 • 0615 • Fax 505 • 632 • 1865



### EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Hydroblast Comp.	Date Reported:	09-01-04
Laboratory Number:	30341	Date Sampled:	08-31-04
Chain of Custody No:	12882	Date Received:	08-31-04
Sample Matrix:	Soil	Date Extracted:	09-01-04
Preservative:	Cool	Date Analyzed:	09-01-04
Condition:	Cool and Intact	Analysis Requested:	8015 TPH

Parameter	Concentration (mg/Kg)	Det. Limit (mg/Kg)
Gasoline Range (C5 - C10)	57.2	0.2
Diesel Range (C10 - C28)	244	0.1
Total Petroleum Hydrocarbons	301	0.2

ND - Parameter not detected at the stated detection limit.

References: Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

_____

Analyst

MIDTIN  $\sim$ Review

Ē

ACCONTRACTOR AND ADDRESS

EPA Method 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

**Quality Assurance Report** 

Client:	QA/QC		Project #:		N/A
Sample ID:	09-01-TPH QA	JQC	Date Reported:		09-01-04
_aboratory Number:	30341		Date Sampled:		N/A
Sample Matrix:	Methylene Chlor	ide	Date Received:		N/A
Preservative:	N/A		Date Analyzed:		09-01 <b>-</b> 04
Condition:	N/A		Analysis Reques	sted:	ТРН
	-I-Cal Date	, I-Cal RF:	C-Cal RF:	% Difference	Accept. Range
Gasoline Range C5 - C10	02-19-04	1.8591E-002	1.8572E-002	0.10%	0 - 15%
Diesel Range C10 - C28	02-19-04	1.5507E-002	1.5492E-002	0.10%	0 - 15%
Blank Conc. (mg/L-mg/Kg)				Detection Limi	Ę
Gasoline Range C5 - C10		ND		0.2	
Diesel Range C10 - C28		ND		0.1	
Total Petroleum Hydrocarbons		ND		0.2	
Duplicate Conc. (mg/Kg)	Sample		% Difference	Accept. Range	
Gasoline Range C5 - C10	57.2	57.0	0.3%	0 - 30%	
Diesel Range C10 - C28	244	243	0.3%	0 - 30%	
Spike Conc. (mg/Kg)	Sample -	Spike Added	Spike Result	% Recovery	-Accept: Range
Gasoline Range C5 - C10	57.2	250	307	99.8%	75 - 125%

ND - Parameter not detected at the stated detection limit.

**References:** 

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846, USEPA, December 1996.

Comments:

QA/QC for samples 30341 - 30345.

Analyst

Mistine of Walles

Ē



#### EPA METHOD 1311 TOXICITY CHARACTERISTIC LEACHING PROCEDURE TRACE METAL ANALYSIS

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Hydroblast Comp.	Date Reported:	09-02-04
Laboratory Number:	30341	Date Sampled:	08-31-04
Chain of Custody:	12882	Date Received:	08-31-04
Sample Matrix:	TCLP Extract	Date Analyzed:	09-02-04
Preservative:	Cool	Date Extracted:	09-01-04
Condition:	Cool & Intact	Analysis Needed:	TCLP metals
		Det.	Regulatory
	Concentration	Limit	Level
Parameter	(mg/L)	(mg/L)	(mg/L)
Arsenic	0.002	0.001	5.0
Barium	0.068	0.001	100
Cadmium	ND	0.001	1.0
Chromium	0.001	0.001	5.0
Lead	ND	0.001	5.0
Mercury	ND	0.001	0.2
Selenium	ND	0.001	1.0
Silver	ND	0.001	5.0

ND - Parameter not detected at the stated detection limit.

References:

Method 1311, Toxicity Characteristic Leaching Procedure, SW-846, USEPA, December 1996.

Methods 3010, 3020, Acid Digestion of Aqueous Samples and Extracts for Total Metals, SW-846, USEPA, December 1996.

Methods 6010B Analysis of Metals by Inductively Coupled Plasma-Atomic Emission SW-846, USEPA. December 1996.

Note:

Regulatory Limits based on 40 CFR part 261 subpart C section 261.24, August 24, 1998.

Comments:

Analyst

rem Walters Review

÷



#### EPA METHOD 1311 **TOXICITY CHARACTERISTIC** LEACHING PROCEDURE TRACE METAL ANALYSIS

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Tank 36 Comp.	Date Reported:	09-02-04
Laboratory Number:	30342	Date Sampled:	08-31-04
Chain of Custody:	12882	Date Received:	08-31-04
Sample Matrix:	TCLP Extract	Date Analyzed:	09-02-04
Preservative:	Cool	Date Extracted:	09-01-04
Condition:	Cool & Intact	Analysis Needed:	TCLP metals
		Det.	Regulatory
	Concentration	Limit	Level
Parameter .	(mg/L)	(mg/L)	(mg/L)
Arsenic	0.003	0.001	5.0
Barium	0.073	0.001	100
Cadmium	ND	0.001	1.0
Chromium	0.001	0.001	5.0
Lead	ND	0.001	5.0
Mercury	ND	0.001	0.2
Selenium	ND	0.001	1.0
	ND	0.001	5.0

References: Method 1311, Toxicity Characteristic Leaching Procedure, SW-846, USEPA, December 1996.

> Methods 3010, 3020, Acid Digestion of Aqueous Samples and Extracts for Total Metals, SW-846, USEPA, December 1996.

Methods 6010B Analysis of Metals by Inductively Coupled Plasma-Atomic Emission SW-846, USEPA. December 1996.

Regulatory Limits based on 40 CFR part 261 subpart C Note: section 261.24, August 24, 1998.

Comments:

Analyst

Mintine mluaeters Review



#### EPA METHOD 1311 TOXICITY CHARACTERISTIC LEACHING PROCEDURE TRACE METAL ANALYSIS Quality Assurance Report

Client: Sample ID: Laboratory Number: Sample Matrix: Analysis Requested: Condition:		N/A 09-02-TCM 30341 TCLP Extrac TCLP Metal N/A	ot	Project #: Date Report Date Sampl Date Receiv Date Analyz Date Extrac	ed: ved: :ed:		N/A 09-02-04 N/A N/A 09-02-04 09-01-04
Blank & Duplicate Conc. (mg/L) Arsenic Barium Cadmium Chromium Lead Mercury Selenium Silver	Instrument Blank ND ND ND ND ND ND ND ND	Method Blank ND ND ND ND ND ND ND	Detection Limit 0.001 0.001 0.001 0.001 0.001 0.001 0.001 0.001	Sample 0.002 0.068 ND 0.001 ND ND ND ND ND	Duplicate 0.002 0.067 ND 0.001 ND ND ND ND ND	% Difference 0.0% 1.5% 0.0% 0.0% 0.0% 0.0% 0.0%	Acceptance Range 0% - 30% 0% - 30% 0% - 30% 0% - 30% 0% - 30% 0% - 30% 0% - 30%
Spike Conc. (mg/L) Arsenic Barium Cadmium Chromium Lead Mercury Selenium Silver		Spike Added 0.500 0.500 0.500 0.500 0.500 0.500 0.500 0.500	Sample 0.002 0.068 ND 0.001 ND ND ND ND ND	Spiked Sample 0.502 0.566 0.500 0.501 0.499 0.050 0.499 0.499	Percent Recovery 100.0% 99.6% 100.0% 99.8% 100.0% 99.8% 99.8%		Acceptance Range 80% - 120% 80% - 120% 80% - 120% 80% - 120% 80% - 120% 80% - 120% 80% - 120%

ND - Parameter not detected at the stated detection limit.

**References:** 

ences: Method 1311, Toxicity Characteristic Leaching Procedure, SW-846, USEPA, Dec. 1996

Methods 3010, 3020, Acid Digestion of Aqueous Samples and Extracts for Total Metals, SW-846, USEPA, December 1996.

Methods 6010B Analysis of Metals by Inductively Coupled Plasma-Atomic Emission, SW-846, USEPA, December 1996.

Comments:

QA/QC for sample 30341 - 30342.

Analyst

Mistin Review

28
<del>~~~</del>
۵
OR
Ш С Ш
<ul><li>A</li></ul>
00
Š

I

I

#### SUSPECTED HAZARDOUS WASTE ANALYSIS

. .

Client:	Giant Refinery	Project #:	96012-009		
Sample ID:	Hydroblast Comp.	Date Reported:	09-01-04		
Lab ID#:	30341	Date Sampled:	08-31-04		
Sample Matrix:	Soil	Date Received:	08-31-04		
Preservative:	Cool	Date Analyzed:	09-01-04		
Condition:	Cool and Intact	Chain of Custody:	12882		
Parameter	Result				
IGNITABILITY:	Negative				
CORROSIVITY:	Negative	pH = 7.43	x.		
REACTIVITY:	Negative				
RCRA Hazardous Waste Criter	ia				
Parameter	Hazardous Waste Criteric	n			
IGNITABILITY:	5	ty as defined by 40 CFR, Subpart C, S direct contact with flame or flash poin			
CORROSIVITY:	Characteristic of Corrosivity as defined by 40 CFR, Subpart C, Sec. 261.22. (i.e. pH less than or equal to 2.0 or pH greater than or equal to 12.5 )				
REACTIVITY:	Characteristic of Reactivity as defined by 40 CFR, Subpart C, Sec. 261.23. (i.e. Violent reaction with water, strong base, strong acid, or the generation of Sulfide or Cyanide gases at STP with pH between 2.0 and 12.5)				
Reference:	40 CFR part 261 Subpar	t C sections 261.21 - 261.23, July 1, 1	1992.		

· . :

Comments:

Analyst

Jaeters Review



#### SUSPECTED HAZARDOUS WASTE ANALYSIS

Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Tank 36 Comp.	Date Reported:	09-01-04
Lab ID#:	30342	Date Sampled:	08-31-04
Sample Matrix:	Soil	Date Received:	08-31-04
Preservative:	Cool	Date Analyzed:	09-01-04
Condition:	Cool and Intact	Chain of Custody:	12882
Parameter	Result		
IGNITABILITY:	Manakar		
IGNITADILITT:	Negative		
CORROSIVITY:	Negative	pH = 7.69	
REACTIVITY:	Negative		
RCRA Hazardous Waste Criteri	а		
Parameter	Hazardous Waste Criter	ion	•••
IGNITABILITY:		ility as defined by 40 CFR, Subpart C, S on direct contact with flame or flash poin	
CORROSIVITY:		ivity as defined by 40 CFR, Subpart C, s al to 2.0 or pH greater than or equal to	
REACTIVITY:	(i.e. Violent reaction wit	vity as defined by 40 CFR, Subpart C, S h water, strong base, strong acid, or the ide gases at STP with pH between 2.0 a	generation
Reference:	40 CFR part 261 Subpa	art C sections 261.21 - 261.23, July 1, 1	1992.

Comments:

in Analyst

<u>Aistnen Walters</u> view ۱ Review



#### FLASH POINT ANALYSIS

· ·			
Client:	Giant Refinery	Project #:	96012-009
Sample ID:	Hydroblast Comp.	Date Reported:	09-01-04
_ab ID#:	30341	Date Sampled:	08-31-04
Sample Matrix:	Soil	Date Received:	08-31-04
Preservative:	Cool	Date Analyzed:	09-01-04
Condition:	Cool & Intact	Chain of Custody:	12882

#### Parameter

Result

**FLASH POINT** 

> 350° C



Reference:

Method 1010, Pensky-Metrens Closed-Cup Method For Determining Flash Point. SW846, USEPA September 1986.

Comments:

Analyst

m Walter Review

· .



#### FLASH POINT ANALYSIS

Parameter	Result		
Condition:	Cool & Intact	Chain of Custody:	12882
Preservative:	Cool	Date Analyzed:	09-01-04
Sample Matrix:	Soil	Date Received:	08-31-04
_ab ID#:	30342	Date Sampled:	08-31-04
Sample ID:	Tank 36 Comp.	Date Reported:	09-01-04
Client:	Giant Refinery	Project #:	96012-009

**FLASH POINT** 

> 350° C



Reference:

Method 1010, Pensky-Metrens Closed-Cup Method For Determining Flash Point. SW846, USEPA September 1986.

Comments:

Analyst

m Waeters Review

Ξ



### COVER LETTER

November 10, 2004

Cindy Hurtado San Juan Refining #50 CR 4990 Bloomfield, NM 87413 TEL: (505) 632-4161 FAX (505) 632-3911

RE: Landfarm - Background

Order No.: 0410292

Dear Cindy Hurtado:

Hall Environmental Analysis Laboratory received 1 sample on 10/29/2004 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent.

Reporting limits are determined by EPA methodology. No determination of compounds below these (denoted by the ND or < sign) has been made.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

Andy Freeman, Business Manager Nancy McDuffie, Laboratory Manager



4901 Hawkins NE∎ Suite D∎ Albuquerque, NM 87109 505.345.3975∎ Fax 505.345.4107 www.hallenvironmental.com

			.01 y				····
CLIENT:	San Juan Refining			Clie	ent Sample ID: 1	andfarn	n
Lab Order:	0410292				Collection Date:	10/28/2	2004 2:30:00 PM
Project:	Landfarm - Backgrour	nd					
Lab ID:	0410292-01				Matrix:	SOIL	
Analyses		Result	PQL	Qual	Units	DF	Date Analyzed
EPA METHOD	9056A: ANIONS						Analyst: MAP
Fluoride		3.1	0.30		mg/Kg	1	11/3/2004 11:01:59 PM
Chloride		180	3.0		mg/Kg	10	11/4/2004 4:08:06 PM
Nitrogen, Nitrate	e (As N)	20	0.30		mg/Kg	1	11/3/2004 11:01:59 PM
Sulfate		1400	15		mg/Kg	10	11/4/2004 4:08:06 PM
Nitrogen, Nitrite	e (As N)	ND	0.30		mg/Kg	1	11/3/2004 11:01:59 PM
Phosphorus, Or	rthophosphate (As P)	ND	1.5		mg/Kg	1	11/3/2004 11:01:59 PM
EPA METHOD	8015B: DIESEL RANGE						Analyst: JMP
Diesel Range C	Organics (DRO)	ND	10		mg/Kg	1	11/1/2004 2:18:51 PM
Motor Oil Rang	e Organics (MRO)	ND	50		mg/Kg	1	11/1/2004 2:18:51 PM
Surr: DNOP		98.0	60-124		%REC	1	11/1/2004 2:18:51 PM
EPA METHOD	8015B: GASOLINE RAN	GE					Analyst: NSB
Gasoline Range	e Organics (GRO)	ND	5.0		mg/Kg	1	11/3/2004 5:10:12 PM
Surr: BFB		108	74-118		%REC	1	11/3/2004 5:10:12 PM
EPA METHOD	8021B: VOLATILES						Analyst: NSB
Methyl tert-buty	/i ether (MTBE)	ND	0.10		mg/Kg	1	11/3/2004 5:10:12 PM
Benzene		ND	0.025		mg/Kg	1	11/3/2004 5:10:12 PM
Toluene		ND	0.025		mg/Kg	1	11/3/2004 5:10:12 PM
Ethylbenzene		ND	0.025		mg/Kg	1	11/3/2004 5:10:12 PM
Xylenes, Total		ND	0.025		mg/Kg	1	11/3/2004 5:10:12 PM
Surr: 4-Brom	ofluorobenzene	104	74-118		%REC	1	11/3/2004 5:10:12 PM
SPECIFIC CO	NDUCTANCE						Analyst: MAF
Specific Condu	uctance	910	0.010		µmhos/cm	1	11/9/2004
	6010C: SOIL METALS						Analyst: NMC
Calcium		12000	250		mg/Kg	10	11/4/2004 7:50:07 AM
Magnesium		2100	25		mg/Kg	1	11/3/2004 3:25:22 PM
Potassium		890	50		mg/Kg	1	11/3/2004 3:25:22 PM
Sodium		450	25		mg/Kg	1	11/3/2004 3:25:22 PM
EPA METHOD	150.1: PH			÷			Analyst: MAI
pН		7.73	0.010	·	pH Units	1	11/9/2004

### Hall Environmental Analysis Laboratory

Date: 10-Nov-04

Qualifiers:

ND - Not Detected at the Reporting Limit

J - Analyte detected below quantitation limits

B - Analyte detected in the associated Method Blank

- * Value exceeds Maximum Contaminant Level 1 / 8
- S Spike Recovery outside accepted recovery limits
- R RPD outside accepted recovery limits

E - Value above quantitation range



Hall Envir	Hall Environmental Analysis Laboratory	is Laborate	yıc							Date: 16-Nov-04	v-04	
CLJENT: Work Order: Project:	San Juan Refining 0410292 Landfarm - Background	puno						v	QC SUM	QC SUMMARY REPORT Method Blank	Y REPORT Method Blank	R A
Sample ID MB-6785 Client ID:	6785 Batch ID: 6785	: 6785	Test Code: E300 Run ID: LC_0	: E300 LC_041103A	Units: mg/Kg		Analysis SeqNo:	Analysis Date 11/3/2004 8:30:44 PM SeqNo: 317399	3:30:44 PM	Prep Date 11/3/2004	1/3/2004	
Analyte		Result	Pal	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RPD Ref Val	Ref Val	%RPD RPD	RPDLimit QI	Qual
Fluoride Chloride		22	0.3 0.3						· · · · · · · · · · · · · · · · · · ·	:		
Nitrogen, Nitrate (As N) Sulfate	(As N)		0.3									
Nitrogen, Nitrite (AS N) Phosphorus, Orthopho	Nitrogen, Nitrite (As N) Phosphorus, Orthophosphate (As P)	D Q	0.3 1.5									
Sample ID MB-6759	5759 Batch ID: 6759	6759	Test Code: SW8015	SW8015	Units: mg/Kg		Analysis	Analysis Date 11/1/2004 11:52:23 AM	1:52:23 AM	Prep Date 11/1/2004	1/1/2004	1
Client ID:			Run ID:	FID(17A) 2_041101A	A1101A		SeqNo:	316689				
Analyte		Result	Pal	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD RPD	RPDLimit QL	Qual
Diesel Range Organics (DRO) Motor Oil Range Organics (MRO) Surr: DNOP	ganics (DRO) Organics (MRO)	ND ND 9.379	10 50	10	0	93.8	60	124	o		-	
Sample ID MB-6768 Client ID:	3768 Batch ID: 6768	6768	Test Code: SW8015 Run ID: PIDFID	SW8015 U	Units: mg/Kg 03A		Analysis SegNo:	Analysis Date 11/3/2004 2:41:12 PM SegNo: 317530	::41:12 PM	Prep Date 11/1/2004	/1/2004	I
Analyte		Result	Par	SPK value	SPK Ref Val	%REC	LowLimit	Highl	Ref Val	%RPD RPDLimit		Qual
Gasoline Range Organics (GRO) Surr: BFB	Organics (GRO)	0401 0400	цС	1000	0	104	74	118	O	• 4 1		
Qualifiers:	ND - Not Detected at the Reporting Limit	Reporting Limit		S - Sp	S - Spike Recovery outside accepted recovery limits	iccepted reco	very limits	B - Anal	lyte detected in	<ul> <li>B - Analyte detected in the associated Method Blank</li> </ul>	ethod Blank	
	J - Analyte detected below quantilation limits	r quantitation limit	S	R - RF	R - RPD outside accepted recovery limits	covery limits	~				Ι	

**۱** 

I

ļ

,

2/8

İ

CLIENT: San Juan Work Order: 0410292 Project: Landfarn	San Juan Refining 0410292 Landfarm - Background							QC SUN	QC SUMMARY REPORT Method Blank	Y REPORT Method Blank
Sample ID MB-6768	Batch ID: 6768	Test Code: SW8021	SW8021	Units: mg/Kg		Analysis SeeNo:	5 Date 11/3/20	Analysis Date 11/3/2004 2:41:12 PM	Prep Date 11/1/2004	2004
Cilent IU: Analyte	Result		SPK value SP	SPK Ref Val	%REC	begivu. LowLimit		HighLimit RPD Ref Val	%RPD RPDLimit	it Qual
Methyl tert-butyl ether (MTBE) Benzene Toluene Ethylbenzene Xylenes, Total Surr: 4-Bromofluorobenzene	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0.1 0.025 0.025 0.025 0.025 0.025	-	0	101	74	118	o		
Sample ID MB-6773 Client ID:	Batch ID: 6773	Test Code: Run ID:	SW6010A ICP_041110B	Units: mg/Kg		Analysis SeqNo:	Date 11/10/2 319433	Analysis Date 11/10/2004 4:13:49 PM SeqNo: 319433	Prep Date 11/2/2004	004
Analyte	Result	Pal	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD RPDLimit	t Qual
Całcium Magnesium	38.66 ND	50 25	00	00	00	00	00	00		ſ
Potassium	QN	50	0	0	0	0	0	0		
	48.13	50	0	0	0	0	0	0		<b>¬</b>
Qualifiers: ND - Not Det	ND - Not Detected at the Reporting Limit		S - Spi	S - Snike Recovery outside accented recovery limits	ccented reco	verv limits	8	B - Analyte detected in the associated Method Black	bothe according to the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of the pothese of th	Blank

 $\sim$ 

R - RPD outside accepted recovery limits

J - Analyte detected below quantitation limits

- ----

ł

į

\$

i

I

1 1

-

•

3/8

Hall Environm	Hall Environmental Analysis Laboratory	tory				, , , , ,			Date: 16-Nov-04	
CLIENT: Sa Work Order: 04 Project: La	San Juan Refining 0410292 Landfarm - Background							QC SUN	QC SUMMARY REPORT Sample Matrix Spike	<b>ORT</b> Spike
Sample ID 0410292-01a ms Client ID: Landfarm	a ms Batch ID: 6768	Test Code: Run ID:	SW8015 U PIDFID_041103A	Units: mg/Kg 03A		Analysis SeqNo:	Analysis Date 11/3/2004 7:39:02 PM SeqNo: 317540	04 7:39:02 PM	Prep Date 11/1/2004	04
Analyte Gasoline Range Organics (GRO) Surr: BFB	Result s (GRO) 27.77 1148	5 5 0	SPK value 25 1000	SPK Ref Val 1.08 0	%REC 107 115	LowLimit 73.8 74	HighLimit RF 120 118	RPD Ref Val 0 0	%RPD RPDLimit	Qual
Samole ID 0410292-01a msd	t msd Batch ID: 6768	Test Code:	SW8015	Units: mg/Kg		Analysis	Analysis Date 11/3/2004 8:08:43 PM	04 8:08:43 PM	Prep Date 11/1/2004	04
Client ID: Landfarm		Run ID:	PIDFID_041103A	03A		SeqNo:	317542			
Analyte	Result	Pal	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RPD Ref Val	D Ref Val	%RPD RPDLimit	Qual
Gasoline Range Organics (GRO) Surr: BFB	s (GRO) 27.84 1167	02	25 1000	1.08	107 117	73.8 74	120 118	27.77 1148	0.252 11.6 1.67 0	
Sample ID 0410292-01a ms	t ms Batch ID: 6768	Test Code:	SW8021	Units: mg/Kg		Analysis	Analysis Date 11/3/2004 7:39:02 PM	14 7:39:02 PM	Prep Date 11/1/2004	04
Client ID: Landfarm		Run ID:	PIDFID_041103A	03A		SeqNo:	317519			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RF	RPD Ref Val	%RPD RPDLimit	Qual
Methyl tert-butyl ether (MTBE)	TBE) 1.867	0.1	2	0	93.4	65	132	0		
Benzene	0.4022	0.025	0.42	0	95.8	77	122	0		
Toluene	1.755	0.025	1.9	0	92.4	81	115	0		
Ethylbenzene Xvlenes Total	0.3842	0.025 0.025	0.41	0 0	93.7 96.7	84 84	117 116			
Surr: 4-Bromofluorobenzene		0	-	0	104	74	118	0		
Qualifiers: ND - J - Ar	ND - Not Detected at the Reporting Limit J - Analyte detected below quantitation limits	its	S - Spi R - RP	<ul> <li>S - Spike Recovery outside accepted recovery limits</li> <li>R - RPD outside accepted recovery limits</li> </ul>	accepted reco	overy limits	B	Analyte detected in	B - Analyte detected in the associated Method Blank	Blank <i>I</i>

4/8

ı

١

I

ļ

-----

ł

CLIENT: Work Order:	San Juan Refining 0410292	Refining			•••				QC SUN	AMARY	QC SUMMARY REPORT	QC SUMMARY REPORT
Project:	Landfarm	Landfarm - Background							Sample	Sample Matrix Spike Duplicate	ike Dupli	cate
Sample ID 0410292-01a msd	12-01a msd	Batch ID: 6768	Test Code: SW8021	SW8021	Units: mg/Kg		Analysis	Date 11/3/20	Analysis Date 11/3/2004 8:08:43 PM	Prep Date	Prep Date 11/1/2004	
Client ID: Landfarm	Lm		Run ID:	PIDFID_041103A	03A		SeqNo:	317520				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RPD Ref Val	RPD Ref Val	%RPD F	RPDLimit	Qual
Methvi tert-butvl ether (MTBE)	ier (MTBE)	1.881	0.1	2	0	94.0	65	132	1.867	0.713	28	
Benzene		0.4084	0.025	0.42	0	97.2	77	122	0.4022	1.54	27	
Toluene		1.814	0.025	1.9	0	95.5	81	115	1.755	3.25	19	
Ethylbenzene		0.3953	0.025	0.41	0	96.4	84	117	0.3842	2.83	10	
Xylenes, Total		1.859	0.025	1.9	0	97.8	84	116	1.837	1.19	13	
Surr: 4-Bromofluorobenzene	orobenzene	1.044	0	~	0	104	74	118	1.044	0.00670	0	
ı							-					
					· • .							
Qualifiers:	ND - Not Dete	ND - Not Detected at the Reporting Limit		S - Spi	S - Spike Recovery outside accepted recovery limits	ccepted recov	very limits	B-	B - Analyte detected in the associated Method Blank	n the associate	d Method Bla	¥
	J - Analyte dei	J - Analyte detected below quantitation limits	nits	R - RP	R - RPD outside accepted recovery limits	sovery limits						$\sim$

i

5/8

e to fato t

Hall Envirc	nmental	Hall Environmental Analysis Laboratory	tory							Date: 16-Nov-04	v-04	
CLIENT: Work Ordon	San Juan	San Juan Refining							QC SUM	QC SUMMARY REPORT	EPOR	۲۲
Project:	Landfarn	Landfarm - Background							Laboratory (	Laboratory Control Spike - generic	e - gene	nic
Sample ID_LCS-6785	1785	Batch ID: 6785	Test Code: E300	E300	Units: ma/Ka		Analysi	is Date 11/3/20	Analysis Date 11/3/2004 8:47:33 PM	Prep Date 11/3/2004	1/3/2004	
Client ID:			Run ID:	LC_041103A			SeqNo:	: 317400				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD RPD	RPDLimit Q	Qual
Fluoride		1.418	0.3	1.5	0	94.6	06	110	0		;	
Chloride		13.89	0.3	15	0	92.6	06	110	0			
Nitrogen, Nitrate (As N)	As N)	7.225	0.3	7.5	0	96.3	06	110	0			
Sulfate		28.84	1.5	30	0	96.1	06	110	0			
Nitrogen, Nitrite (As N)	(N S	2.72	0.3	e	0	90.7	06	110	0			
Phosphorus, Orthophosphate (As P)	ophosphate (/	ls P) 14.21	1.5	15	0	94.8	06	110	0			
Sample ID LCS-6759	1759	Batch ID: 6759	Test Code: SW8015	SW8015	Units: mg/Kg		Analysi	Analysis Date 11/1/2004 1:20:20 PM	04 1:20:20 PM	Prep Date 11/1/2004	/1/2004	1
Client ID:			Run ID:	FID(17A) 2_041101A	41101A		SeqNo:	316691				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RPD Ref Val	PD Ref Val	%RPD RPDLimit		Qual
Diesel Range Organics (DRO)	anics (DRO)	48.9	10	50	0	97.8	67.4	117	0			
Sample ID LCSD-6759	-6759	Batch ID: 6759	Test Code:	SW8015	Units: mg/Kg		Analysis	Analysis Date 11/1/2004 1:49:36 PM	04 1:49:36 PM	Prep Date 11/1/2004	/1/2004	Į
Client ID:			Run ID:	FID(17A) 2_041101A	41101A		SeqNo:	316692				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RPD Ref Val	PD Ref Val	%RPD RPDLimit		Qual
Diesel Range Organics (DRO)	inics (DRO)	46.99	10	50	0	94.0	67.4	117	48.9	4.00	17.4	
Sample ID LCS-6768	768	Batch ID: 6768	Test Code: SW8015	SW8015	Units: mg/Kg		Analysis	Analysis Date 11/3/2004 3:10:58 PM	04 3:10:58 PM	Prep Date 11/1/2004	11/2004	
Client ID:			Run ID:	PIDFID_041103A	03 <b>A</b>		SeqNo:	317532				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit Rf	RPD Ref Val	%RPD RPDLimit		Qual
Gasoline Range Organics (GRO)	rganics (GRO	) 28.15	5	25	0	113	73.8	120	0	•		
		tini I animan Data Patro		0	La Danviari outrida o	and soot	indiana limite	6	- Forester	. M L		
Qualifiers:	ND - Not Del J - Analyte de	ND - Not Detected at the Keporting Limit J - Analyte detected below quantitation limits	its	s - spi R - RP	<ul> <li>S - Spike recovery outside accepted recovery minits</li> <li>R - RPD outside accepted recovery limits</li> </ul>	iccepted recc covery limits	s	, ,	b - Analyte detected in the associated Method Blank	i the associated Me	sthod Blank	

۰.

6/8

i

CLJENT: Work Order: Project:		San Juan Refining 0410292 Landfarm - Background							QC SUMMARY REPORT Laboratory Control Spike - generic	IMARY Control S	<b>Y REPC</b> Spike - ge	<b>DRT</b> meric
Sample ID LC	LCS-6768	Batch ID: 6768	Test Code: SW8021 Run fD: PIDFID	SW8021 U PIDFID 041103A	Units: mg/Kg 03A		Analysis Date SeqNo:	Date	11/3/2004 3:10:58 PM 317513	Prep Dat	Prep Date 11/1/2004	4
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit R	RPD Ref Val	%RPD	RPDLimit	Qual
Methyl tert-butyl ether (MTBE)	l ether (MTBE)	1.783	0.1	2	0	89.1	65	132	0			
Benzene		0.4238	0.025	0.42	0	101	77	122	0			
Toluene		1.888	0.025	1.9	0	99.3	81	115	0			
Ethylbenzene Xylenes, Total		0.4007 1.924	0.025 0.025	0.41 1.9	00	97.7 101	84 84	117 116	0 0			
Sample ID LC	LCS-6773	Batch ID: 6773	Test Code:	SW6010A	Units: mg/Kg		Analysis	Date 11/10/2	Analysis Date 11/10/2004 4:16:18 PM	Prep Dat	Prep Date 11/2/2004	
Client ID:			Run ID:	ICP_041110B			SeqNo:	319434				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit R	RPD Ref Val	%RPD	RPDLimit	Qual
Calcium		2432	50	2500	38.66	95.7	80	120	0		-	
Magnesium		2464	25	2500	0	98.6	80	120	0			
Potassium		2616	50	2500	0	105	80	120	0			
Sodium		2901	50	2500	48.13	114	80	120	0			
Sample ID LCS	LCSD-6773	Batch ID: 6773	Test Code:	SW6010A	Units: mg/Kg		Analysis	Date 11/10/2	Analysis Date 11/10/2004 4:26:48 PM	Prep Dat	Prep Date 11/2/2004	
Client ID:			Run ID:	ICP_041110B			SeqNo:	319436				
Analyte		Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit RI	RPD Ref Val	%RPD	RPDLimit	Qual
Calcium		2394	50	2500	38.66	94.2	80	120	2432	1.61	20	
Magnesium		2444	25	2500	0	97.8	80	120	2464	0.808	20	
Potassium		2605	50	2500	0	104	80	120	2616	0.410	20	
Sodium		2900	50	2500	48.13	114	80	120	2901	0.0100	20	
Oualifiers:	ND - Not De	ND - Not Detected at the Reporting Limit		S - Spil	S - Spike Recovery outside accepted recovery limits	ccepted reco	very limits	B -	B - Analyte detected in the associated Method Blank	the associat	ed Method Bl	ank
	J - Analyte c	J - Analyte detected below quantitation limits	nits	R - RPI	R - RPD outside accepted recovery limits	covery limits			<b>.</b>			~

.

-----

-

7/8

Hall Environmental Analysis Laboratory
----------------------------------------

.,

ļ

I.

	Sample Rece	ipt Ch	ecklist		
Client Name SJR			Date and Time	Received:	10/29/2004
Work Order Number 0410292			Received by	AT	
Checklist completed by	h-	Date	0/29/04		
Matrix	Carrier name UPS				
Shipping container/cooler in good condition?	Yes		No 🗌	Not Present	
Custody seals intact on shipping container/cooler?	Yes		No 🗔	Not Present 🗹	Not Shipped
Custody seals intact on sample bottles?	Yes		No 🗔	N/A	
Chain of custody present?	Yes		No 🗌		
Chain of custody signed when relinquished and rece	ived? Yes	$\checkmark$	No 🗌		
Chain of custody agrees with sample labels?	Yes		No 🗔		
Samples in proper container/bottle?	Yes	$\checkmark$	No 🗌		
Sample containers intact?	Yes		No 🗌		
Sufficient sample volume for indicated test?	Yes	$\checkmark$	No 🗆		
All samples received within holding time?	Yes	$\checkmark$	No 🗔		· .
Nater - VOA vials have zero headspace?	lo VOA vials submitted	<u> </u>	Yes 🗹	No 🗌	
Water - pH acceptable upon receipt?	Yes		No 🗆	N/A 🗹	
Container/Temp Blank temperature?		3°	4° C ± 2 Accepta		
COMMENTS:					
=======================================	=========				=======================================
Client contacted Da	te contacted:		Pers	son contacted	
Contacted by: Re	egarding	·	<u> </u>		·····
Comments:				turana - tao any tao amin'ny sama-designa	
<u> </u>					
Corrective Action					
		. <u>-</u> .			
					·

HALL ENVIRONMENTAL ANALYSIS LABORATORY 4901 Hawkins NE, Suite D Albuquerque, New Mexico 87109 Tel. 505.345.3975 Fax 505.345.4107 www.hallenvironmental.com		(	NTBE + TPI and 80158 shod 80158 shod 504.1 shod 504.1 thod 504.1 thod 8021) thod 80210 thod 80210 thod 80210 thod 802100 thod 802100000000000000000000000000000000000	A H Meth TPH Meth TPH (Meth EDB (Met B310 (PM B310 (PM B310 (PM B310 (PM B310 (PM B310 (V) B320 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B20 (V) B2					Remarks:
Accreditation Applied. NELAC USACE USACE DOther:	LAND Farm - BACKGrout ND Project #:	Project Manager:	Sampler (why Huntzido Sample Temperature: 3,0	Preservative         HEAL No.           H ₉ Cl ₂ HNO.3	1-2620140 Sar ( pol-2				Remarks 10/29/04
CHAIN-OF-CUSTODY RECORD	CL1	Bloom Fred, WW OTTIC	Phone #:505-632-4161 Fax #: 505-632-3911	Date Time Matrix Sample I.D. No.	1008-04 23per-Soil LAND Farm				10-2804 3300. Relinquished By: (Sighature) 10-2804 3300. Lucou Nuntado Date: Time: Relinquished By: (Signature)

# Section 14.0 Drilling Logs and Installation Diagrams


Title	Tab Number
Installation Diagrams	4
July 2004 Boring Logs	5
October 2004 Boring Logs	6
MW #48 & MW #49 Boring Logs	7
Temporary Piezometers Boring Logs	8

















Sheet: 1 of 8 Bore Point: See plan 'ater Elevation: 6.90 Boring No 1 SB1-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5495.28 Date: 7/6/2004

## Log of Test Borings

1		BLOW			MATERIAL CHARACTERISTICS				
_AB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS
	0-2		****		Sand, sility, brown, moist				
			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
	2-8.0		0*0*0*0	<u>2.5</u>	Cobbles, gravel, silty. sand, brown, moist				
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
ļ			0*0*0*0	1	Black with hydrocarbon odor	}			
			0`010'0						
	8.0-9.0		<u>0*0*0*0</u> = = = = =	· · · · · · · · · · · · · · · · · · ·	Nacimiento Formation		Ì		
	0.0-8.0		====		T.D. 8.0		ļ		
				<u>10.0</u>					
				<u> </u>	Placed 2" PVC, 4' hand slotted screen,				
					backfilled with cuttings		ļ		
					17.5' N of canal edge		ļ	l	
							-		
						ļ	ļ	ļ	
				<u>15.0</u>					
			1	]			Ì		
							1		
			l						1
		1		1					
				<u>20.0</u>		1	1		
							ļ		
								}	
,								1	
			1						
	1	i	1	1	W STEMMED AUGER	1	1	1	WHK

Sheet: 2 of 8 Bore Point: See plan 'ater Elevation: 6.85 Boring No.: SB2-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5494.96 Date: 7/6/2004

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	PI	CLASS
	0-2.5		*_**_*_*		Sand, fine, silty, brown, muist, moderately				
			*_**_*_*		dense				
			*_**_*_*						
			*_**_*_*						
			*_**_*_*	<u>2.5</u>					
	2.5-9.0		0*0*0*0		Cobbles, very dense, cobbles to 12", grey, dry				
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	<u>5.0</u>					
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	<u>7.5</u>			ĺ		
			0*0*0*0						
		•	0*0*0*0		• •				
			0*0*0*0						
	9.0-10.0		* * * * *		Sand, black, water bearing, hydrocarbon odor,				
			* * * * *	10.0	loose				
	10.0-11.5		====		Nacimiento Formation				
			====						
			====		T.D. 11.5				
				<u>15.0</u>	Placed 2" PVC, 4' hand slotted screen, backfilled with cuttings 16' N of cana ^l edge				
				<u>20.0</u>					
SIZE	& TYPE (	DF BORING	+ • 4 1/4" II		N STEMMED AUGER	1060	- ED	BY	WHK

Sheet: 3 of 8 Bore Point: See plan 'ater Elevation: 6.79 Boring No.: SB3-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5495.21 Date: 7/6/2004

	<u> </u>	BLOW			MATERIAL CHARACTERISTICS	_			· · · · · · · · · · · · · · · · · · ·
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS
	0-4.0		*_**_*_*		Sand, fine, silty, brown, damp, loose				
			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
			*_**_**	<u>2.5</u>					
1			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
	4.0-8.5		0*0*0*0		<u>Cobbles</u> , gravelly, grey, dry, dense-very dense				
			0*0*0*0						
			0*0*0*0				ļ		
			0*0*0*0						
			0*0*0*0						
			0101010						
			0*0*0*0 0*0*0*0						
	8.5-10.0		0*0*0*0 * * * * *		Sand, fine, black, water bearing, loose				
	0.5-10.0		* * * * *		Sand, line, black, water bearing, loose				
			* * * * *	10.0					
	10.0-11.5		====		Nacimiento Formation, mudstone, moist, not				
	10.5 11.0		= = = = =		water bearing below 10.5, grey-black, hard				
			====		T.D. 11.5				
				<u>15.0</u>	Placed 2" PVC, 4' hand slotted screen, backfilled with cuttings SPH 6.78 (total .1')				
				20.0					
	I I		1				1	1	

Sheet: 4 of 8 Bore Point: See plan ``'ater Elevation: 7.50 Boring No.: SB4-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5495.21 Date: 7/6/2004

		BLOW	<b>.</b>		MATERIAL CHARACTERISTICS				
.AB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLAS
	0-2.75		*_**_*_*_*		<u>Sand</u> , silty: some fine gravel, brown, moist,				
			*_**_*_* *_**_*_*		loose				
			) ^_^^_^ *_**_*_*						
			*_** <u>*</u> *_*	<u> </u>					
			* ** * *	<u>2.5</u>					
	2.75-8.0		0*0*0*0		Cobbles, gravelly, grey, dry, very dense				
	2.75-0.0		0*0*0*0		CODDIES, gravely, grey, dry, very dense				
	Ì		0*0*0*0						
			0*0*0*0	1					
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	<u>7.5</u>					
			0*0*0*0						
	8.0-9.5	•	0*0*0*0		<u>Sand</u> , fine, some fine gravel, clayey, grey				
			****						
			* * * * *						
	9.5-11.0		====	<u>10.0</u>	Nacimiento Formation, mudstone, very sandy,				
			====		grey, moist-wet				
		·	====		T.D. 11.0				
					1.0. 11.0				
			1		Placed 2" PVC, 4' hand slotted screen, @ 10.5'			1	
					backfilled with cuttings				
					SPH 7.49 (total .1')			1	
				15.0					
								}	
									1
									1
				-					
	ļ			<u>20.0</u>					
									l
	L			1	N STEMMED AUGER	l	1	1	WHK

Sheet: 5 of 8 Bore Point: See plan **'ater** Elevation: 6.95 Boring No.: SB5-0704

Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5497.98 Date: 7/6/2004

		BLOW			MATERIAL CHARACTERISTICS			_	
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS.
	0-2.5		***_*_*		Sand, fine, silty, brown, damp-moist				
			*_**_*_*						
			*_**_*_*				1		
	-		*_**_*_*	~ -					
	2.5-8.5	·····	*_**_*_*	2.5					<u> </u>
	2.5-8,5		0*0*0*0 0*0*0*0		<u>Cobbles</u> , gravelly, grey, dry, very dense				
			0*0*0*0						
l i			0*0*0*0						
			0*0*0*0						
	1		0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			<b>o*o*</b> o*o						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0 * * * * *						
	8.5-9.25		* * * * *		Sand, fine, some fine gravel, grey, moist				
	9.25-10.5		====	10.0	Nacimiento Formation, mudstone, very sandy,				
	5.20 10.0		====		grey, moist-wet				
					1 [°] .D. 10.5				
					Placed 2" PVC, 4' hand slotted screen,				
					backfilled with cuttings				
				15.0					
				<u>15.0</u>					
						1	ļ		
				1					
				20.0					
			ļ						
SIZF	& TYPE		: <b>4</b> 1/4" I!			LOG	L GED	BY	WHK
		.xls]Sheet1							

Sheet: 6 of 8 Bore Point: See plan **''ater** Elevation: 6.68 Boring No.: SB6-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5496.86 Date: 7/6/2004

I	T	BLOW			MATERIAL CHARACTERISTICS				
.AB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS
	0-1.0		*_**_*_*		<u>Sand</u> , fine. silty, brown. damp, loose				
			*_**_*_*						
	1.0-6.5		0*0*0*0		<u>Cobbles;</u> some gravel, grey, dry, very dense				
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0			i			
			0*0*0*0	1					
			0*0*0*0	1					
	6.5-8.0		0*0*0*0	 	Sand, fine. black, strong hydrocarbon odor,				<u> </u>
	0.0-0.0		* * * * *	7.5	wet. water bearing @ 7.0'				
			****	<u>1.5</u>	wet, water bearing @ 1.0				
	8.0-10.5	· · · · · · · · · · · · · · · · · · ·	====		Nacimiento Formation, sandstone, green-grey				
			====		very dense,				
			====						
			====	<u>10.0</u>					
		,	====						
					T.D. 10.5				
					Placed 2'' PVC, 4' hand slotted screen, backfilled with cuttings				
				<u>15.0</u>					
				<u>20.0</u>					
SIZE	E & TYPE (	OF BORING	: 4 1/4" II	D HOLLO	N STEMMED AUGER	LOG	GED	BY:	WHK

· · · ·

Sheet: 7 of 8 Bore Point: See plan ^{*}ater Elevation: 6.35 Boring No.: SB7-0704

Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5496.86 Date: 7/7/2004

		BLOW			MATERIAL CHARACTERISTICS				
<u>_AB #</u>		COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS
	0-1.5		*_**_*_*		<u>Sand</u> , fine, silty, brown, damp, loose				
			*_***_*						
			* * * * * *						
	1.5-8.5		0*0*0*0		Cobbles, grey, damp, very dense				
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	1					
			0*0*0*0						
			0*0*0*0 0*0*0*0						
			0*0*0*0						
	· .		0 0 0 0 0 0*0*0*0						
	8.5-9.0		****		Sand, fine, black,				
	9.0-10.5		====		Nacimiento Formation, mudstone, sandstone,				
	0.0 10.0		====		green-grey				
			====						
					T.D. 10.5				
					Placed 2" PVC, 4' hand slotted screen,				
1					backfilled with cuttings				1
					, j				
				<u>15.0</u>					
							ļ	ļ	ļ
									1
									1
	l								
			1						1
						l			ł
				20.0					
						l			
	1								
	J	·	· • · · · · · · · · · · · · · · · · · ·	·	N STEMMED AUGER	·		<u>+</u>	WHK

Sheet: 8 of 8 Bore Point: See plan **``'ater** Elevation: 5.92 Boring No.: SB8-0704 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5497.91 Date: 7/7/2004

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS.
	0-5.0		*_**_*_*		<u>Sand</u> , fine, silty, brown, moist, loose				
			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
			*_**_*_*	<u>2.5</u>					
			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
			*_**_*_*						
			*_**_*_*	<u>5.0</u>				<u> </u>	
	5.0-8.5		<b>0*0</b> ໃບ [*] ວ		Cobbles, gravelly, grey, dry-damp, very dense				
			0*0*0*0	1					
			0*0*0*0						
			<b>o*o*o</b> *o						
			0*0*0*0	<u>7.5</u>					
			<b>o*o*o</b> *o		· .				
	2500	·	0*0*0*0		Cond along find and a start black				· · · ·
	8.5-9.0		====		Sand, clayey, fine, green-grey-black,				
	9.0-11.0		====	10.0	Nacimiento Formation, mudstone, moist,				
			====	<u>10.0</u>	green-grey				
					T.D. 10.5				
	ļ								
					Placed 2" PVC, 4' hand slotted screen,				
					backfilled with cuttings				
							1		
				<u>15.0</u>					
								[	
				<u>20.0</u>					
		1							
	ł								ļ
SIZE	E & TYPE	OF BORING	: 4 1/4"	D HOLLO	N STEMMED AUGER	LOG	GED	BY:	WHK
C-\unzi		3.xls1Sheet1							

Sheet: 1 of 8 Bore Point: Vater Elevation: Boring No.: SB1-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date:

LAB #	DEPTH	BLOW COUNT	PLOT	SCALE	MATERIAL CHARACTERISTICS (MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS.
	DEFIN	COONT		JUALL	(MOISTORE, CONDITION, COLOR, ETC.)	7011		<u> </u>	<u>CLASS.</u>
				2.5					
				<u>2.5</u>					
				50					
				903 1 <u>06-</u> , AN	له ب ایپ ایو او او است ای ا				
				<u>7.5</u>					
							· .		
				<u>10.0</u>					
				<u>15.0</u>					
<u>*</u>									
				<u>20.0</u>					
S171	F&TVPE		S. 4 1/4" 1		W STEMMED AUGER	100			: KM
C:\Doci	uments and	Settings\cind	yh\Local :	Settings\Te	emporary Internet Files\OL				

Sheet: 2 of 8 Bore Point: 21' 7'' W of canal edge Water Elevation: 8.0' below ground surface Boring No.: SB2-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5489.17 Date: 10/28/2004

## Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%М	LL	PI	CLASS.
	0-3.0		*_**_*_*		Sand, fine to coarse, silty, damp, tan				
			*_**_*_*						
			*_**_*_*						
			*_**_*_*					ļ	
			*_**_*_*	<u>2.5</u>					
			*_**_*_*						
	3.0-5.0		***0***		Cobbles, gravel, sand, silty, tan, damp				
			0*0*0*0						
			o*o*o*o	5.0					
40450	5054		0*0*0*0	<u>5.0</u>	Cond firs to second day stores top	2.0			
46450	5.0-5.4		******		<u>Sand</u> , fine to coarse, dry, clean, tan, moderately dense	3.8		N/P	SP-SM A-3
	6.0-7.0		******	<b>-</b>	Gravel, sand, medium, dry, tan.				A-3
	0.0-7.0		*******		<u>oraver</u> , sand, medium, dry, tan,				
	7.0-11.5		*******	7.5	Sand, medium, gravel, dark grey,	ļ			
			******		hydrocarbon odor, moist				
	· ·		*******		, , , , , , , , , , , , , , , , , , , ,				
			******						
			******		wet at 8'				
			******	<u>10.0</u>			ļ		
			******						
46451	11.0-11.5		*******		Sand, medium, gravel, dark grey, moist	15.6		N/P	SP/A-1-b
			******						
	11.5-12.0		====		Nacimiento Formation mudstone, dry				
46456	12.0-12.5		====		Sample Number HC 1				
					Total depth bottom of well 12'				
				15.0	5' of hand slotted screen				
				<u>15.0</u>	no water for first 8 hours				
,									
							l		
							1		
				<u>20.0</u>					
									1
				1		1			1
				1					1
SIZE	E & TYPE					LOG	GED	BY:	KM

Sheet: 2 of 8 Bore Point: 17' 7" W of canal edge Vater Elevation: 7.2' below ground surface Boring No.: SB3-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5487.02 Date: 10/28/2004

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS
	0-1		*_**_*_*		<u>Silt</u> , sandy, very fine to fine, brown, moist				
	1-8.0		*_**-*_* 0*0*0*0		Cobbles, gravel, sand, fine, silty, moist, brown				
	1-0.0		0*0*0*0		<u>CODDIES</u> , gravel, sand, ime, sitty, moist, brown				
			0*0*0*0	<u>2.5</u>					
			0*0*0*0						
			0*0*0*0						1
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	1					
			0*0*0*0	1					
			0*0*0*0 0*0*0*0						
			0 0 0 0 0						
			0*0*0*0						
	8-10.5		**0**0**		Sand, fine to coarse, gravel,				
	_		**o**o**		dark grey, wet, hydrocarbon odor				
			**o**o**						
			**o**o**	<u>10.0</u>					
			**0**0**						
	10.5-11.5		*******		Sand, medium, argillaceous, damp				
<u> </u>	12.0		====		Nacimiento Formation, mudstone			-	
	12.0				Total depth 11' 9"				· · · · · · · · · · · · · · · · · · ·
					5' of hand slotted screen				1
				<u>15.0</u>	8' 5" top of pipe				
					no water for first 8 hours				
₹						}			
					·				
				20.0				1	
						1		1	4
									· 1/ M
					W STEMMED AUGER	LOG	GEL	) BY	

Sheet: 4 of 8 Bore Point: 16' 2" W of canal edge Water Elevation: 8.5' below ground surface Boring No.: SB4-1004

Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5486.72 Date: 10/28/2004

## Log of Test Borings

វ		<u>1</u>					1		1	
		DEDTU	BLOW			MATERIAL CHARACTERISTICS				01.400
ł	LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS.
		0-6.0		*_**_*_*		<u>Silt</u> , sandy, very fine to fine, brown, damp			•	
				 *_**_*_*						
				*_**_*_*						
				*_**_*_*	<u>2.5</u>					
				*_**_*_*	<u></u>					
				*_**_*_*						
				*_**_*_*						
				*_**_*_*						
				*_**_*_*	<u>5.0</u>			ļ		
				*_**_*_*						
				*_**_*_*						
		6.0-9.0		0*0*0*0	3	Cobbles, gravel, sand, fine to medium, silty,				
				0*0*0*0		brown, damp				
				0*0*0*0						
				0*0*0*0	1					
				0*0*0*0	1					
		0.0.40.5		0*0*0*0		Cand madium to same much				
		9.0-10.5		*******	10.0	<u>Sand</u> , medium to coarse, grey, wet hydrocarbon odor				
				*******	10.0					
		10.5-11.0		====		Nacimiento Formation, mudstone				
		10.0 11.0						<u> </u>		
								1		
						Total depth 10' 1/2"				
						5' of hand slotted screen				
					<u>15.0</u>	no water for first 8 hours				
	1									
	्र									
									1	
	1								1	
					20.0					
				ļ	<u></u>				1	
				l						
	SIZE	E & TYPE	OF BORING	6: 4 <u>1/4"</u> I	D HOLLO	W STEMMED AUGER	LOG	GED	) BY	: KM
	CilDeer	imonto and	Sattings laind	(h)Local	Settings\Te	emporary Internet Files\OL				·

Sheet: 5 of 8 Bore Point: 16' 10'' W of canal edge Water Elevation: 8.7' below ground surface Boring No.: SB5-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5487.51 Date: 10/28/2004

## Log of Test Borings

Γ			BLOW			MATERIAL CHARACTERISTICS				
	LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS.
ſ		0-6.0		*_**_*_*		<u>Silt</u> , sandy, very fine to fine, brown, moist				
				*_**_*_*						
				*_**_*_*						
				*_**_*_*						
				*_**_*_*	<u>2.5</u>					
				*_**_*_*						
				*_**_*_*						
				*_**_*_*						
				*_**_*_*						
				*_**_*_*	<u>5.0</u>					
				*_**_*_*						
L				*_**_*_*			ļ			
		6.0-9.0		0*0*0*0		<b><u>Cobbles</u></b> , gravel, sand, fine to medium, silty,				
				0*0*0*0		brown, moist				
				0*0*0*0	<u>7.5</u>	hydrocarbon odor				
	·			0*0*0*0						
	)			0*0*0*0						
				0*0*0*0			<b></b>		}	
	46452	9.0-10.0		*******		<u>Sand</u> , medium, brown, wet	5.6		N/P	SM/A-1-b
				******	<u>10.0</u>		ļ		ļ	
	46453	10.0-10.5		====		Nacimiento Formation, mudstone, moist	16.1			
	46454	9.5-10.5			ļ	Sample Number HC 2		ļ		
					<u>15.0</u> 20.0	Total depth 10' 7" 5' of hand slotted screen no water for first 8 hours				
		E & TYPE		 3 [.] 4 1/4" I		W STEMMED AUGER	LOG			: KM
			JI DOMAC	····	2.0000					

Sheet: 6 of 8 Bore Point: 22' 7" W of canal edge Water Elevation: Not Encountered Boring No.: SB6-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5489.95 Date: 10/28/2004

# Log of Test Borings

		T	BLOW			MATERIAL CHARACTERISTICS				
LAB	# DEPT	Н	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS.
	0-0.5			*_**_*_*		Silt, sandy, very fine to fine, brown, damp				
	0.5-7.0	0		0*0*0*0		Cobbles, gravel, sand, very fine to medium,				
				0*0*0*0		silty, brown. damp				
ĺ				0*0*0*0						
				0*0*0*0	<u>2.5</u>					
				0*0*0*0						
				0*0*0*0						
				0*0*0*0						
				0*0*0*0	r				Į	
				0*0*0*0	<u>5.0</u>					
				0*0*0*0						
				0*0*0*0						
				0*0*0*0						
				<u>o*o*o*o</u>					ļ	
	7.0-7.		·····	******	7.5	<u>Sand</u> , medium to coarse, brown, occasional				
4645	55 7.5-8.	5		====		gravel, damp, slight hydrocarbon odor				
		-	• •	====		Nacimiento Formation, mudstone; moist	9.3			
I			<u>.</u>	====		very compact, grey to black			<u> </u>	
					10.0					
					<u>10.0</u>					
									1	
						Total depth 8' 6"				
1 I						5' of hand slotted screen				ļ
					15.0					
			÷				1			
1.									1	
									ļ	
							1			
									1	
				1	<u>20.0</u>					
					1					
<u> </u>				<u> </u>	<u> </u>					
		_	and the second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second se			W STEMMED AUGER	LOG	GEL	<u> </u>	, <u>NIVI</u>

Sheet: 7 of 8 Bore Point: 12' 11" N of canal edge Water Elevation: 8.6' below ground surface Boring No.: SB7-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5490.37 Date: 11/1/2004

# Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS.
	0-0.5		*_**_*_*		Silt, sandy, very fine to fine, brown, damp				
	0.5-9.0		.0*0*0*0		Cobbles, gravel, sand, fine to coarse,				
			0*0*0*0		silty, brown, moist				
			0*0*0*0						
			0*0*0*0	<u>2.5</u>					
			0*0*0*0			•			
			0*0*0*0						
			0*0*0*0				Į		
			0*0*0*0					ļ	
			0*0*0*0	<u>5.0</u>					
			0*0*0*0				-		
			0*0*0*0				ł		
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	<u>7.5</u>		1	1		
	· .		0*0*0*0		Sand, fine to coarse, brown, occasional				1
			0*0*0*0		gravel, wet, slight hydrocarbon odor			Į	
			0*0*0*0						
	9.0-9.5		******		Sand, fine to coarse, grey, occasional				
			******	<u>10.0</u>	wet, slight hydrocarbon odor				
46457			====		Nacimiento Formation, mudstone, moist	11.8			
			====		gray to black				
					Total depth 10' 2"	1	1	1	
					5' of hand slotted screen				
					does not produce water in the first 8 hours	[			
								ł	
	ł			<u>15.0</u>					
		-							
						}		1	
2									
						1			
				<u>20.0</u>		1			
	l							l	
		1	}						
SIZE	E & TYPE	OF BORING	6: 4 1/4" I	D HOLLO	W STEMMED AUGER	LOG	GEC	) BY	: KM
					emporary Internet Files\OL				

Sheet: 8 of 8 Bore Point: 11' N of canal edge Water Elevation: 9.8' below ground surface Boring No.: SB8-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: 5492.02 Date: 10/27/2004

## Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS			·	
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS.
	0-0.5	000111	*_**_*_*	UUNLL	Silt, sandy, very fine to fine, brown, damp	70101			01/00.
	0.5-10.0		0*0*0*0		<u>Cobbles</u> , gravel, sand, fine to coarse,				
	0.0-10.0		0*0*0*0		silty, brown, moist				
			0*0*0*0		Sity; brown, moist				
			0*0*0*0	2.5					
				<u>2.5</u>					
			0*0*0*0						
			0*0*0*0						
			0*0*0*0			l			
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0						
			0*0*0*0	<u>10.0</u>					
46458	10.0-11.0		******		Sand, fine to coarse, grey, strong hydrocarbon	19.2		N/P	SP/A-1-b
			******		odor, water bearing				
46459	11.0-12.5		====		Nacimiento Formation, argillaceous sandstone	16.5			
46460	12-12.5		====		moist, gray to green gray				
			====		Sample number HC3	5.5	L		
					Total Depth 12.5'				
}				<u>15.0</u>	5' of hand slotted screen			1	
						1			
2									
							1		
									1
						1			
							1		
				20.0					
							Ì		
						1			
-1								1	1
				}					
SI7	E & TYPF		+ ; 4 1/4" I	D HOLLO	W STEMMED AUGER	LOG	GED	BY	KM
					emporary Internet Files\OL				

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 7.70 Boring No.: MW-48 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

# Log of Test Borings

Γ		<u> </u>	BLOW			MATERIAL CHARACTERISTICS				
	LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	PI	CLASS.
		0-1		*_**_*_*		Silt, sand, very fine to fine, brown, damp, a few				
				*-*0-*-*		cobbles				
		1-15.0		*-*0-*-*		Sand, silty, very fine to fine, brown, damp,				
				*-*o-*-*		gravelly				
		2.0		*-*0-*-*	<u>2.5</u>	Black with hydrocarbon odor				
				*-*0-*-*						
	.	1		*-*0-*-*						
				*-*0-*-*						1
				*******		medium to coarse sand				
				******	<u>5.0</u>			1		
				*******						
				******						
				******						
				******						
				******	<u>7.5</u>					
			· · ·	*******		water bearing				
				******						
1	, ,			******						
				*******	40.0					
				***o**** ***o****	<u>10.0</u>	some gravel				
ł				***0****						
				***0****						
				***o****						
				0 ***0****					ļ	
				***0****						
				***0****					1	
				***0****	1					
				***0****					ļ	
ŀ					10.0	T.D. 15.0				
						Bottom of well 15'				
						Placed 4" PVC, 10' factory slotted .020" screen		1		
	¥					Sanded with 8-12 Silica Sand to 3' bgs				
						Bentonite Plug to 1' bgs				
				]	t		ł			
					20.0		1			
							ł			
			-				1			
	1									
							ļ			
							LOG	GE	) BY	: KM

Sheet: 1 of 1 Bore Point: See plan Vater Elevation: 9.00 Boring No.: MW49 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

# Log of Test Borings

[		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS.
	0-3		*0*-*-0		<u>Cobbles</u> , sand, very fine to fine, gravel, brown,				
			*0*-*-0		damp, cobbles				
			*0*-*-0						
			*0*-*-0						
			*0*-*-0	<u>2.5</u>					
			*0*-*-0						
	3-15.0		*-*0-*-*		<u>Sand</u> , silty, very fine to fine, brown, moist,				
			*-*'0-*-* ********						
			*******	5.0					
			*****	<u>5.0</u>		•			
			******		fine to medium sand				
			******		Black with hydrocarbon odor, wet				
			**0**0*		some cobbles		1		
			**0**0*	<u>7.5</u>					
			**0**0*	1.10					
			******		water bearing			) ·	
			******		č				
			******						
			******	<u>10.0</u>					
			******						
			******		-				
			******						
			*******						
			*******						
			*******				1		
			******	ŀ	medium to coarse sand, grey				
			******	15.0					
			1	15.0	T.D. 15.0		+	<u> </u>	
					Bottom of well 14'				1
1					Placed 4" PVC, 10' factory slotted .020" screen				
					Sanded with 8-12 Silica Sand to 2' bgs	l			
					Bentonite Plug to gs		1		
		1						1	
				<u>20.0</u>					
				]					
			1	<u> </u>					
the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the statement of the st					W STEMMED AUGER emporary Internet Files\OL	LOG	GEL	) BA	: KM

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 4.6' below ground surface Boring No.: TP1-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/27/2004

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE	(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	ΡI	CLASS.
	0-2		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
			0-*0*-			}			
			0-*0*-			[			
	2-2.5		*_**_*	<u>2.5</u>	Clay, sandy, very fine, brown, wet				
	2.5-9.0		*****		Sand, fine to medium, black, damp,				
			****						
			*******						
			*******	50					
			*******	<u>5.0</u>	water bearing				
			*******						
			******					ł	
			******						
			*****	<u>7.5</u>					
			******						
			******		) / ·			[	
			******				-		
				<u>10.0</u>	T.D. 9.0 Placed 2" PVC, 5' hand slotted screen Backfilled with clean cuttings				
×				<u>15.0</u>					
SIZ	E & TYPE		) 5: 4 1/4" I	20.0	W STEMMED AUGER	LOG	GE	) BY	: KM
					emporary Internet Files\OL				

Sheet: 1 of 1 Bore Point: See plan Vater Elevation: 6.3' below ground surface Boring No.: TP2-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/27/2004

# Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	PI	CLASS.
	0-2		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
			0-*0*-						
			0-*0*-						
	2-2.5		*_**_*	<u>2.5</u>	Clay, sandy, very fine, brown, wet				
	2.5-9.0		********		<u>Sand</u> , fine to medium, black, damp,				
			*******						
			*******						
			******	5.0					
			******	<u>5.0</u>	water bearing				
			******						
			******						
		ļ	*******						
			******	<u>7.5</u>			ŀ		
			******						
			******				ļ		
			******						
			T		T.D. 9.0				
				<u>10.0</u>	Placed 2" PVC, 5' hand slotted screen				
					Backfilled with clean cuttings				
								1	
		-							
				15.0					
				<u>15.0</u>	· · ·			1	
1 K									
			Į						
1	1							1	
				20.0			1		
			1						
			1					ļ	
			1					1	
SIZ	E & TYPE					LOG	GEE	) BY	: KM

Sheet: 1 of 1 Bore Point: See plan Vater Elevation: 5.8' below ground surface Boring No.: TP3-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

## Log of Test Borings

	· · ·	BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS.
	0-2		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
			0-*0*-						
			0-*0*-						
\$	2-3.5		***	<u>2.5</u>	<u>Clay</u> , sandy, very fine, brown				
			**** ****						
}	3.5-13.0		*******		Cand madium to second harmonic		<u> </u>		
	3.5-13.0		******		<u>Sand</u> , medium to coarse, brown, damp,				
			******	<u>5.0</u>					
			*****	<u>9.0</u>					
			*****						
			******						
			******						
			******	<u>7.5</u>					
			*****						· · ·
			*******						
			******						
			******						
			******	<u>10.0</u>					
			******						
			******				ļ	ļ	
			******					ľ	
			*******						
1			******						
			******				<u> </u>	<u> </u>	
					T.D. 13.0				
				<u>15.0</u>	Placed 2" PVC, 5' hand slotted screen				
				15.0	Backfilled with clean cuttings				
					· ·				
۲. ۲									
								1	
								ļ	
1									
				<u>20.0</u>				1	
						1			
						1			
		<u> </u>							
SIZ	E & TYPE					LOG	GED	) BY	: <u>KM</u>

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 5.4' below ground surface Boring No.: TP4-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

## Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS.
	0-2		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
			0-*0*-						
			0-*0*-						
	2-10.0		*_**_*	<u>2.5</u>	Sand, silty, very fine, gravel to 2", brown				
			*_**_*				l		
			******						
			*******				l		
			*******						
			*******	<u>5.0</u>					
			******						
			*******						
			*******		black, hydrocarbon odor				
			*******		water bearing				
				<u>7.5</u>					
			*******				1		
			*****						
1			*****						
			******	10.0					
				10.0	T.D. 10.0				
					Placed 2" PVC, 5' hand slotted screen				
					Backfilled with clean cuttings			l	
}									
		}		1				1	
				<u>15.0</u>					
•									
		Į							
		1							
				<u>20.0</u>					
			l			1			
									1
			}						
			ļ	<u> </u>			1		
SIZ	E & TYPE	OF BORING	<u>5: 4 1/4"  </u>	D HOLLO	W STEMMED AUGER	_LOG	GEL	) BY	: KM

Sheet: 1 of 1 Bore Point: See plan Vater Elevation: 5.4' below ground surface Boring No.: TP5-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

0-2       0-*O*- O-*O*- O-*O*- O-*O*- O-*O*-       Silt, sand, very fine to fine, cobbles, gravel, brown, moist         2-10.0       ****o**** ****o**** ****o**** ****o****       2.5 Sand, silty, very fine, gravel to 2", brown         ****o**** ****o****       5.0 ************       sand, coarse, black Hydrocarbon odor	CLASS.
0-2       O-*-O*- O-*-O*- O-*-O*- O-*-O*-       Silt, sand, very fine to fine, cobbles, gravel, brown, moist         2-10.0       ****o**** ****o**** ****o**** ****o****       2.5       Sand, silty, very fine; gravel to 2", brown         ****o****       5.0       ********       5.0         ********       5.0       sand, coarse, black         Hydrocarbon odor       *********	
O-*O*-         Sand, silty, very fine, gravel to 2", brown           2-10.0         ****o****           ****o****         5.0           ************         5.0           ************         sand, coarse, black           ********************         sand, coarse, black	
Q-*Q*-         Sand, silty, very fine; gravel to 2", brown           2-10.0         ****o****           *****o****           ********           ********           *********           *********           *********           *********           *********           ********           ********           ********           *********           ********           ********           *********           ********           *********           ********           ********           ********           *********           *********           **********           *********           **********           **********	
2-10.0 2-10.0 2-10.0 2-10.0 2-10.0 2-5 Sand, silty, very fine, gravel to 2", brown 5.0 ****o**** ****o**** ****o**** *****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ****o**** ********	
****o***** ****o***** ****o***** *****o***** ********	
****o****         ****o****         ****o****         ****o****         ****o****         ****o****         ****o****         ********         **********         **********         **********         **************         *********************         ************************************	
*****o****         *****o****         *****o****         *****o****         *****o****         ***********         ***********         *************         ************         ************         ***********         **********         **********         ***********         **********         **********         **********         **********         **********         ***********         **********         **********         *********         **********         **********         **********         **********         *********         *********         *********         *********         *********         *********         *********         **********         **********         **********         **********         **********         **********         ***********         ***********         **********         ************         ************	
*****o***** **************************	
**********     5.0       **********     sand, coarse, black       *********     Hydrocarbon odor	
*********     *********       **********     sand, coarse, black       **********     Hydrocarbon odor	
************************************	
************************************	
*****	
**************************************	
******	
******	
******	
*****	
********** 10.0	
T.D. 10.0	
Placed 2" PVC, 5' hand slotted screen	
Backfilled with clean cuttings	
15.0	
20.0	
SIZE & TYPE OF BORING: 4 1/4" ID HOLLOW STEMMED AUGER LOGGED BY: K	(M
C:\Documents and Settings\cindyh\Local Settings\Temporary Internet Files\OL	

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 4.8' below ground surface Boring No.: TP6-1004 Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674

File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT	SCALE		%M	LL	ΡI	CLASS.
	0-1		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
	1-10.0		****0****	. •	Sand, silty, very fine, cobbly, brown				
			****0****						
			****0***	<u>2.5</u>					
			****0****						
			****0****						
			*********						
			******						
				<u>5.0</u>					
			********				1		
			******				1		
			********						
			******	7 5	and seems black				
	· .		*******	<u>7.5</u>	sand, coarse, black				
			*******		·Hydrocarbon·odor				
			*****					-	
			******						
			*****	<u>10.0</u>					
				10.0	T.D. 10.0				
					1.0.10.0	}			
					Placed 2" PVC, 5' machine slotted screen				
					Backfilled with clean cuttings	ł		ļ	
					Dackined with clean countys				
							1	ĺ	
			1	<u>15.0</u>					1
				15.0				ļ	
1	1		1			1	1		1
				20.0				ŀ	
			1					1	
S17	E & TYPE	OF BORING			W STEMMED AUGER	LOG	GEL	BY	: KM
					emporary Internet Files\OL				

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 5.7' below ground surface Boring No.: TP7-1004 Precision Engineering, Inc. P.O. Box 422

Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

### Log of Test Borings

		BLOW			MATERIAL CHARACTERISTICS				
LAB #	DEPTH	COUNT	PLOT		(MOISTURE, CONDITION, COLOR, ETC.)	%M	LL	PI	CLASS.
	0-2		0-*0*-		Silt, sand, very fine to fine, cobbles, gravel,				
			0-*0*-		brown, moist				
			0-*0*-						
			0-*0*-		· · · · · · · · · · · · · · · · · · ·	<u> </u>			
	2-5.0		*-*0-*	<u>2.5</u>	<u>Sand</u> , silty, very fine, cobbly, brown				
			*-*0-*						
			*-*0-* *-*0-*						
			*_*0-*						
			*-*0-*	5.0					
	5-10.0		******	<u> </u>	Sand, fine to medium, dark brown, moist				
	0.10.0		*******						
			*****						
			*******				}		
			*****	<u>7.5</u>	slight hydrocarbon odor, black				
	• •		******						
			*******				1		
1			******						
			******						
			*******	<u>10.0</u>					
					T.D. 10.0				
					Placed 2" PVC, 5' hand slotted screen				
					Backfilled with clean cuttings		1		
				ļ	Dacklined will clean cuttings		·		
		1							
				<u>15.0</u>					
18									
							1		
							1		
								1	
			ļ	20.0					
			1						
SIZ	E & TYPE	OF BORING	); 3:4 1/4"	D HOLLO	W STEMMED AUGER	LOG	GED	BY	: KM

Sheet: 1 of 1 Bore Point: See plan Water Elevation: 4.6' below ground surface Boring No.: TP8-1004

Precision Engineering, Inc. P.O. Box 422 Las Cruces, NM 88004 505-523-7674 File #: 03-122 Site: Bloomfield Giant Refining Elevation: Date: 10/28/2004

# Log of Test Borings

BLOW <u>MATERIAL CHARACTERISTICS</u>		1	1	
	%M	LL	PI	CLASS.
0-1 O-*O*- Silt, sand, very fine to fine, cobbles, gravel,				
O-*O*- brown, moist				
1-3.5 ****O**** Sand, silty, very fine, cobbly, brown				
****O****				
****O**** <u>2.5</u>			1	
****0****				
****O****		<u> </u>		
3.5-10.0 ********* Sand, silty, fine to medium, cobbly, grey,				
********* Hydrocarbon odor, moist,				
***************************************				
				l l
**************************************				
**************************************				
*******************         10.0           T.D. 10.0         T.D. 10.0		+		
Placed 2" PVC, 5' machine, slotted screen				
Backfilled with clean cuttings				ł
		1		
<u>15.0</u>				
20.0			ļ	
SIZE & TYPE OF BORING: 4 1/4" ID HOLLOW STEMMED AUGER	LOG	GE	) BY	: KM





ļ





1

ļ

2004 Below Grade Testing

System ID	Drawing Reference	Test Date	Test Method	Pass/Fail	Repair Information
FCC North Sewer System	D-201-500-001	1/20/2004	Hydrotest	Fail	Replaced Corroded Sewer Lines
		2/24/2004	Hydrotest	Pass	
Lab to Main Sewer in FCC	D-201-500-001	4/8/2004	Hydrotest	Pass	
FCC South Sewer System	D-201-500-233 4/12/2004	4/12/2004	Hydrotest	Fail	Replaced Corroded Sewer Lines
	2	8/7/2004	Hydrotest	Pass	
Treater	D-500-500-122 3/18/2004	3/18/2004	Hydrotest	Fail	Entire Replacement of Treater Sewer Lines
		7/21/2004	Hydrotest	Pass	

# Section 16.0 Correspondence

Title	Tab Number
Monitoring and Contingency Plan	9
Aquifer Pump Test	10
Corrective Action Plan	11
Voluntary Corrective Measure – River Terrace	12

Í.

# Giant Bloomfield Refinery Monitoring and Contingency Plan Prepared August 2004

**River Sampling:** The river will be sampled at the mouth of the draws on a monthly basis and analyzed for BTEX/MTBE (8021), TPH (8015 DRO and GRO), WQCC metals, semi-volatiles organics (8270) and general chemistry. After four months of sampling and no evidence of pollutants the sampling frequency will be reduced to quarterly.

Monitoring of the draws: All draws will be inspected every other week for visual hydrocarbon staining.

**Record Keeping:** Records of monitoring and sampling will be kept onsite and available for inspection. A recap summarizing all events will be submitted to OCD in the annual report. Any new discovery of hydrocarbon will require immediate reporting.

**Immediate containment and corrective actions to be taken in the event of a release to the river:** In the event of a release to the river containment booms will be deployed on the river to contain the release. The earthen containment structures will be constructed at the point of release. Downstream containment booms will be deployed in the event the release gets out side of the immediate containment.

#### **Emergency Resources:**

- 1-100 foot floating containment boom.
- 1-75 foot floating containment boom
- Various sizes of absorbent pads
- Vacuum truck
- Backhoe

### **Outside Contractors:**

- Envirotech Morgan Killion (work) 632-0615, (cell) 320-1436, (home) 324-8465
- Envirotech Morris Young (work) 632-0615.
- Riley Industrial Services George Riley 327-4947.
- Key Energy 327-0416, (24 hr dispatch) 325-6892.

**Emergency notification:** In the event of a release to the river, the Bloomfield Refinery will notify the following agencies and water users pursuant to OCD Rule 116 and WQCC 1203:

- Denny Foust, OCD Aztec, 334-6178.
- Wayne Price, OCD Santa Fe, 476-3487.
- William Olson, OCD Santa Fe, 476-3491
- Dave Cobrain, NMED Santa Fe, 428-2553
- Hope Monzeglio, NMED Santa Fe, 428-2545
- Robert Wilkinson, EPA Dallas Tex. (214) 665-8316

# **Downstream Water Users**

- Lower Valley Water Users Cooperative Association, (emergency) 598-5175
- BHP 598-4200
- PNM, San Juan Generating Station 598-7200
- Williams Field Service, (24 hr emergency) 632-4600

# AQUIFER TEST RESULTS SUMMARY REPORT San Juan River Terrace Site Giant Refinery, Bloomfield, NM

#### GENERAL

This report describes the aquifer (pump) test that was performed in December 2004 on well MW-48 at the Giant Refinery Facility located in Bloomfield, New Mexico. The purpose of the pump test was to obtain aquifer hydraulic properties of the river terrace alluvial aquifer below the refinery. Monitoring well MW-48 was pump tested at a constant pumping rate of 4.7 gallons per minute for a period of over 17 hours. Water levels were monitored in the test well, well MW-49, and six piezometers throughout the test. A temporary staff gage was placed in the San Juan River located adjacent to well MW-49 and hourly stage river level readings were recorded. Once the pump test was terminated, water level recovery measurements were recorded in the test well and 2 piezometers for a period of approximately 5 hours. The locations of the wells and piezometers are shown on Figure 1.

The test well and piezometers are located on the San Juan River floodplain located at the Giant refinery. Well MW-48 was drilled and installed in October 28, 2004. The well consists of a 4-inch diameter, schedule 40 well casing and 0.020-inch slotted screen. The well extends to a depth of 15-feet and is gravel packed with Colorado Silica 8 -12 sand. The screen length is 10 feet and is positioned 5 to 15-feet below ground surface. The lithologic materials encountered during drilling and installation of the well ranged from fine sands to gravel and cobbles. Observation of nearby bluff exposures along the river suggests that bedrock is present at a depth of about 15 to 20 feet below ground surface at the terrace.

Well MW-48 is located approximately 65 feet east and 100 feet south of the San Juan River. An exposed bedrock (Nacimiento Formation) bluff face is located about 65 feet to the south. The barrier wall was installed in the early 1990s, and is located approximately 15 to 20 feet east of the San Juan River. The barrier wall is approximately 150 to 180 feet in length, beginning near the bedrock bluff to the south, running north and parallel to the San Juan River. Well MW-48 is located approximately 40 feet east of the barrier wall, 100 feet south from the San Juan River, and approximately 70 feet north of the bedrock bluff.

A pre-pump test "kick off" meeting was held prior to the pump test with Malcolm Pirnie (MPI), Giant, and Envirotech, Inc. personnel. Pump test procedures, personnel duties, individual assignments, equipment checks, and other requirements for the test were

finalized at that time. A geologist was assigned to manage the test and that person was responsible for the operation of the pumping test.

# EQUIPMENT

Envirotech Inc. provided the pump, discharge equipment, generator, piping and related accessories to perform the test. Envirotech personnel operated the pump throughout the testing activities. A 4-inch, 3/4 horsepower pump capable of pumping 25 gallons per minute was installed in well MW-48. The discharge water was piped to and contained in a temporary 16,000 gallon tank provided by Giant. The tank was located approximately 25 feet from well MW-48. The outlet for the discharge pipe entered the tank from the top.

Refer to Table 1 for the list of equipment used during the pre-pumping and final pump tests. In addition to the equipment listed, a micro processor-based data acquisition system (In-Situ) was utilized to collect water level information during the pumping periods in piezometers TP-6 and TP-8. In all observation wells identified for monitoring, water levels were measured using battery-powered water level sensing devices.

	TABLE 1 Equipment List				
0	Pump test forms (Write-in-Rain [™] paper)	ò	Log Paper – 3-cycle semi-log graph		
0	Ruler – Engineer Scale	0	Flashlights (with extra batteries)		
0	Water Level Measuring Devices (with assigned number on each device)	o	Metal Clipboard (with cover)		
0	Extra batteries with each device	٥	Stop Watches		
•	Calculator	<b>o</b>	Base Map of pumping well & observation wells		
•	Pencils and Erasers	o	Boring logs and Piezometer Construction Details		
0	Table and Chair		-		

#### **MONITORING LOCATIONS**

Water levels were monitored in the pumping well and seven observation wells (six piezometers and one monitoring well) throughout the pumping test. The piezometers included TP-1, TP-2, TP-5, TP-6, TP-7, and TP-8. Monitoring well MW-49, located on the river side of the existing barrier wall, was also monitored. A temporary staff gage was placed in the river adjacent to well MW-49 and was monitored hourly throughout the test. The locations of all observation wells are shown on Figure 1.

# **Pre-pumping Test**

One day prior to the pump test, a 10- to 30-minute pre-pumping test was run in the pumping well. The objectives of the pre-pumping test were as follows:

- Select a pumping rate for the optional final pumping test.
- Determine the expected drawdown in the test well at various pumping rates.
- Calibrate and verify the operational capacity of all equipment being used in pump test.

These trial runs were needed to make final adjustments to the pump test plan, which included making final decisions on equipment changes and measurement of water levels. The pre-pump test procedures were as follows:

- Coordinate installation of the test pump, power supply, discharge line, and flow meter with Envirotech.
- Install battery-powered electrical depth gages in all observation wells to measure groundwater levels during the test.
- Install In-Situ data acquisition system and transducers (mini trolls) in piezometers TP-6 and TP-8 to monitor groundwater levels during the test.
- Start the pre-test, measuring pump discharge during the test. At least three pumping rates were run to determine the optimum pumping rate for the long-term pump test.
- Collect water level readings at 5-minute levels to the nearest 0.01 foot. The depth to water was referenced from the top of the monitoring well casing.

# **CONSTANT-RATE PUMP TEST**

A 17-hour Constant-Rate Pump Test was performed in well MW-48. The constant rate aquifer test began at 1:15 PM on December 9, 2004. All of the equipment, including pumping, discharge piping, water flow, and water depth measuring equipment, was assembled, proven operational, and inspected the day before initiation of the constant rate drawdown test.

#### Scheduling, Planning, and Coordination

A meeting of all pump test field personnel was held at the test well site one hour prior to commencing the pump test. The data acquisition and transducer systems were checked and proven operational. Personnel were given a final brief on their individual duties and responsibilities and a final equipment check was conducted at that time, including synchronization of stop watches.

### **Rest Period**

Static non-pumping water level readings were recorded at least one hour prior to the start of pumping. The last readings were recorded immediately before starting the pump.

### **Data Collection**

The pumping test was started at 1:15 PM on December 9, 2004. Any adjustments of the pumping rate required to maintain a nearly constant pumping rate throughout the test were noted on the field forms. The exact time of each recorded measurement was documented on the pumping well and observation well forms. As discussed above, the depth-to-water level measurements were referenced from the top of the monitoring well or top of the steel casing. Measurements were made to the nearest 0.01 foot. MPI, Giant, and Envirotech personnel assisted in recording water level measurement readings. In addition, river stage readings were recorded on an hourly basis.

#### **Pumping Rate**

The well was pumped at a constant pumping rate of 4.7 gpm determined from the pre-test pumping. The pumping rate remained constant for the duration of the pumping test. The pumping rate was measured by using both a totalizing flow meter and using the "bucket test".

### **Recovery Period**

After completion of the pump test, we recorded the exact time of pump shutdown, and the rate of recovery of the water levels in wells being monitored and recorded these levels for a 5-hour period.

# FIELD REDUCTION OF DATA

During the pump test, the field data was compiled and reduced to estimate drawdown and calculated recovery in the pumping well. Drawdown and recovery measurements for the pumping well and piezometers are presented in Appendix A.

The distances from test well MW-48 to well MW-49 and all the peizometers were measured in the field using a 100-foot tape measure. Table 2 shows a summary of the distances from MW-48 to each respective well or piezometer.

TABLE 2         Summary of Well / Piezometer Distances from MW-48			
Well / Piezometer ID	Distance from MW-48 (ft)	Location	
MW-49	53	Outside Barrier Wall	
TP-1	66	Inside Barrier Wall	
TP-2	52	Adjacent to Bluff	
TP-5	99	East of Well MW-48	
TP-6	44	East of Well MW-48	
TP-7	96	North End of Barrier Wall	
TP-8	42	Inside Barrier Wall	

# **AQUIFER TEST RESULTS**

Drawdown was measured in pumping well MW-48 and piezometers TP-1, TP-2, TP-5, TP-6, TP-7, and TP-8 (Appendix A). The pumping test ran for approximately 1,050 minutes until the generator failed. Recovery measurements began shortly there after.

The following is a summary of the results observed after 1,000 minutes of pumping:

- The drawdown observed in MW-48 showed a water level decline of approximately 2.5 feet.
- The maximum drawdown observed in all piezometers was 0.45 feet measured in TP-8.
- A minimum drawdown observed in the piezometers was 0.10 feet in TP-6.
- The staff gage showed no significant change in river stage height (>0.10 foot of decline) during the test.
- No drawdown was observed in well MW-49, except for a slight decline measured near the end of the test. The water level declined <0.05 feet. The water level fully recovered prior to terminating the pumping test, suggesting the decline was caused by a variation in river stage height.

Recovery water levels were taken in well MW-48 and piezometers TP-6 and TP-8 for approximately 5 hours after the pump test was terminated. The water level in the test well MW-48 recovered 2.24 feet, or 88% of recovery to static level after 5 hours. Water levels in TP-6, located east of pumping well MW-48, did not recover during that period. Water levels in piezometer in TP-8 recovered 0.16 feet, or 36 % of recovery from static water level.

# **AQUIFER TEST INTERPRETATION**

Data from the aquifer test was utilized from both the pumping and recovery phases. The aquifer test data was used to estimate hydraulic conductivity of the aquifer. The drawdown data was plotted on a semi-log cycle graph and analyzed over a single time log cycle. The transmissivity was determined from the Cooper and Jacob (1946) equation,  $T = 264 \text{ Q}/\Delta s$ , and the hydraulic conductivity was calculated using a 10-foot aquifer thickness.

Analysis of the drawdown data revealed two distinct types of curves. These curves indicate the presence of distinct hydraulic boundaries in the vicinity of each well. At TP-8, the slope of the drawdown curve increases sharply as the test progresses, while TP-6 remains relatively flat. The response at TP-8 is characteristic of an impermeable boundary (i.e. barrier wall and/or bedrock face). The results from TP-6 are more characteristic of a recharging boundary (i.e. San Juan River).

For piezometers TP-1 and TP-2, the slopes of the drawdown curves "steepen" or increase throughout the test. These piezometers are located adjacent to either the barrier wall or to the bedrock face. The increased drawdown observed is typically encountered when the cone of depression reaches an impermeable boundary, causing the rate of drawdown to increase in that direction.

The drawdown curves for piezometer TP-5 and well MW-49, like TP-6, indicate an opposite effect. The drawdown response is relatively flat, which reflects recharge effects from the San Juan River. Piezometers TP-5 and TP-6 are located upgradient of the pumping well, between well MW-48 and the river. Very little drawdown was observed at these two locations and at MW-49 until the later portion of the aquifer test. The observed drawdown in MW-49 was likely due to a slight change in river stage near the end of the pumping test.

## Distribution of Drawdown

The semi-log drawdown curves for piezometers located near the barrier wall and the bluff face (TP-1,-2 and -8) show continuous drawdown when pumping at 4.7 gpm. As the cone of depression from the pumping well spreads laterally and intercepts the barrier wall and bedrock face, drawdown increases in these areas due to their impermeable characteristics (lack of available water for the well to draw in). In contrast, the water levels east or upgradient of well MW-48 only slightly declined during the test.

Impermeable Boundary Effects

. .:

The semi-log drawdown curves for the three piezometers by the barrier wall and the bluff face show nearly 0.5 feet of drawdown after 17 hours of pumping. The drawdown data

suggests the barrier wall and bluff face (impermeable boundary) have a large affect on water level declines in TP-1, TP-2, TP-6 and TP-7. After several hundred minutes of pumping, the drawdown curves show an increasing rate of drawdown. The drawdown curves, if extrapolated out to several days and weeks, suggest drawdown would likely accelerate due to the effects of the impermeable boundaries.

# **River Recharge Effects**

The semi-log drawdown curves for the two piezometers (TP-5 and TP-6) and well MW-49 show little to effect from pumping well MW-48. A slight drawdown was observed after several hours of pumping in all three observation points. However, when recovery levels measured in TP-6 were reviewed, no recovery was evident as the water level had stabilized for 5 hours, suggesting the San Juan River stage had decreased about 0.10 foot. This drop likely caused aquifer levels to drop in response to the change. It appears that the area east of pumping well MW-48 is affected by recharge from the river.

# **Parameter Estimation Results**

Transmissivity (T) and hydraulic conductivity (K) were calculated for well MW-48 and piezometers TP-1, TP-2, and TP-8 using the Jacob method (semi-log straight line method). Drawdown and recovery curves were analyzed. Each curve yielded a different hydraulic conductivity. An aquifer thickness of 10 feet (bedrock is shallow below the alluvial aquifer) was assumed. T and K values calculated for each well or piezometer decreased significantly from early time to late time analyses. Average T and K values were calculated as follows:

- Early Time : T=1,200 ft2/day; K= 120 ft/d Boundary effects are absent in the early time response.
- Mid-Late Time: T =500 ft2/day; K-50 ft/d Boundary effects are significant during late time response.

### CAPTURE ZONE ANALYSIS

*...* 

The hydraulic conductivities determined from the pump test analysis were used to estimate the capture zone for a pumping well located on the river terrace. A groundwater spreadsheet (D.K. Todd. Groundwater Hydrology. John Wiley and Sons, Inc., New York, 1990, 2nd Edition.) was used to calculate and model the area of capture. The formulas in the spreadsheet assume an aquifer of uniform thickness that is homogeneous, isotropic and infinite in aerial extent.

The hydraulic conductivity input was evaluated based on the proximity of the pumping well to a hydraulic boundary. As the boundary conditions were observed to drive the

hydraulic response of the aquifer during the pump test, similarly the capture zone of a pumping well will be affected by the boundaries.

In addition to the hydraulic conductivity, a pumping rate, aquifer thickness and hydraulic gradient were input parameters for the capture model. A sensitivity analysis of each parameter revealed various capture zone shapes and sizes. The hydraulic gradient was determined from a topographic map of the San Juan river basin, and ranged from 0.0005 foot per foot (ft/ft) to 0.001 ft/ft. The aquifer thickness was varied between 10 feet and 15 feet, and the pumping rate was varied between 1 gpm and 5 gpm. In this range of inputs, the area of capture for a pumping well located on the river terrace extended as far as 500 feet downgradient, 1600 feet upgradient and 3000 feet wide.

After running multiple iterations of the capture zone model, Malcolm Pirnie determined that an adequate capture zone can be obtained at a pumping rate of 2 to 5 gpm.

8

# **CORRECTIVE ACTION PLAN** GIANT BLOOMFIELD REFINERY

November 17, 2004

Prepared for: Giant Refining Company 50 Road 4990 Bloomfield, New Mexico 87413

Prepared by: Malcolm Pirnie, Inc. 4646 E. Van Buren St., Suite 400 Phoenix, AZ 85008

# TABLE OF CONTENTS

1.0	INTRODUCTION
	1.1 Purpose
	1.2 Facility Description
	1.3 Corrective Action Description
2.0	SITE GEOLOGY5
3.0	HYDROLOGY
4.0	SITE CHARACTERIZATION DATA
	4.1 Water Level & Phase-Separated Hydrocarbon (PSH) Data7
	4.2 Slug Tests
	4.3 Nacimiento Formation Surface Contour Model Development
5.0	HYDROGEOLOGY OF SHALLOW-ZONE SOILS 10
	5.1 Nacimiento Formation Surface Conceptual Model 10
	5.2 Shallow-Zone Groundwater Conditions
	5.3 Aquifer Test Results
	5.4 Conclusions
	5.5 Additional Monitoring Plan 12
6.0	PROPOSED CORRECTIVE ACTION PLAN
	6.1 Barrier Concept
	6.1.1 Utility Crossings
	6.2 Fluids Collection Concept
	6.3 Implementation Concept
	6.4 Construction Permits15
7.0	SCHEDULE16
8.0	REFERENCES

Bloomfield Refining CAP

November 17, 2004

 Table 1 – Groundwater and Phase-Separated Hydrocarbon (PSH) Level Data

 Table 2 – Monthly Monitoring Schedule

# LIST OF FIGURES

Figure 1 - Facility Location Map

Figure 2 – July 2004 Nacimiento Formation Surface Contour Model

Figure 3 – North Boundary Soil Boring Location Map

Figure 4 – Updated Nacimiento Formation Surface Contour Model –November 2004

Figure 5 - North Boundary Barrier Cross-Section A-A'

Figure 6 – Estimated Corrective Action Implementation Schedule

# APPENDICES

Appendix A- November 11, 2004 Report from Precision Engineering, Inc. (with boring logs)

Bloomfield Refining CAP

November 17, 2004

·..

# **1.0 INTRODUCTION**

# 1.1 PURPOSE

This Corrective Action Plan describes Giant's proposed actions to mitigate the off-site migration of petroleum hydrocarbons within the shallow-zone soils along the north property boundary of the Giant Refinery in Bloomfield, New Mexico. For the Corrective Action, Giant has committed to the installation of a containment barrier and fluid collection systems along the north refinery boundary, extending from County Road 4990 to a location approximately 200 feet east of the El Paso Natural Gas Pipelines.

# 1.2 FACILITY DESCRIPTION

The Bloomfield refinery was originally built in the late 1950's and has been operated by Kimball Campbell, O.L. Garretson (Plateau), Suburban Propane, Inc. (Plateau), Bloomfield Refining Company and Giant Refining Company. The facility consists of approximately 285 acres and is located approximately one mile south of Bloomfield, New Mexico on a bluff overlooking the San Juan River (Figure 1).

# **1.3** CORRECTIVE ACTION DESCRIPTION

Recent emergence of active seeps of petroleum hydrocarbons at the face of the river bluff on the north side of the refinery prompted the New Mexico Oil Conservation Division (OCD) to issue Giant an Emergency Action Directive stating the actions required by the agency. Upon receiving the Emergency Action Directive, Giant implemented the tasks outlined therein, which included the installation of temporary catchments and excavation of hydrocarbon-stained soil from the identified areas along the San Juan River bluff. In addition, Giant collected water samples from the San Juan River upstream of the refinery and at the mouth of each draw of concern. Giant continues to provide progress reports of these activities to OCD.

As a corrective action to mitigate further migration of petroleum hydrocarbons towards the San Juan River and beyond the northern property boundaries of the refinery, Giant Bloomfield Refining CAP

November 17, 2004

#### Page 4 of 16

has committed to the installation of a containment barrier wall approximately 2,600 feet in length along the north side of the Hammond Ditch and extending from County Road 4990 to a location approximately 200 feet east of the El Paso Natural Gas Pipelines. In addition, a fluids collection system consisting of multiple recovery wells and/or collection galleries positioned along the plant side of the barrier will be installed to provide hydraulic control of fluids accumulating upgradient of the barrier.

Results from previous site characterization activities, information collected during boring campaigns conducted between November 2003 and October 2004, and a conceptual model of the Nacimiento Formation surface elevation will be used to determine the containment barrier design, develop performance specifications for construction of the containment barrier, and prepare a preliminary design for the fluids collection system. Final design of the collection system will be completed upon installation of the containment barrier and collection of additional groundwater and product level data.

#### 2.0 SITE GEOLOGY

The Bloomfield Refinery is located within the San Juan Basin, a sub-province of the Colorado Plateau physiographic province, about 120 ft above the present river level and 500 feet from the river.

There are three distinct stratigraphic units that underlay the Bloomfield Refinery. From oldest to youngest these units are: the Nacimiento Formation, the Jackson Lake Terrace, and an unnamed structureless loess unit composed of silts and fine windblown sand that have been deposited as the result of eolian deposition.

#### GEOLOGY ALONG NORTH BOUNDARY

#### Surficial Windblown Sands

- Depth: 0 to 4 feet deep
  - Permeability: Low to Moderate
  - Saturation: Dry

#### Jackson Lake Terrace

- ✓ Depth: 6 to 10 feet deep
- Permeability: Moderate to High
   Saturation: Dry to 1-ft depth; water bearing
- ✓ Seeps located in erosional channels

#### **Nacimiento Formation**

- ✓ Perching unit for Jackson Lake Terrace
- Thickness: Approximately 900 feet
- ✓ Permeability: Low
- ✓ Saturation: Non-water bearing

Bloomfield Refining CAP November 17, 2004

Page 5 of 16

During the last glacial retreat, wind blown sand and silt from the floodplains settled over the course clastics to form structureless loess deposits.

The underlining Quaternary Jackson Lake Terrace deposits consist of 10 to 15 feet of course-grained fluvioglacial outwash. It is primarily composed of well rounded gravels, cobbles, and sand sized rocks placed as the result of high energy deposition during melting of the last glacial advance. The cobbles and gravel is often disk-shaped. Cobbles and boulders are commonly observed in the deposits.

The Nacimiento Formation is described as an inter-bedded black carbonaceous mudstone/clay stone with white, medium to coarse-grained sandstones approximately 570 feet thick in this area. The Nacimiento Formation at the outcrop is a tight unfractured rock unit. A permeable saturated cobble and sand layer directly overlies the bedrock (Nacimiento Formation) at the site in areas of depressions (draws) within the bedrock formation. The morphology of the contact between the Quaternary cobble and silt of the Jackson Lake Terrace in the vicinity of the facility and the underlying Nacimiento Formation is important in that it influences control over the direction of the groundwater and SPH flow.

# **3.0 HYDROLOGY**

Surface water in the vicinity of the refinery includes the San Juan River (to the north) and the Hammond Ditch along the north property boundary. The town of Bloomfield and the surrounding areas derive their potable water from the San Juan River, which is controlled by the Navajo Dam. The San Juan River level is approximately 75 feet lower than the Hammond Ditch, and the Hammond Ditch in turn is approximately 25 feet lower than the grade level in the northwestern part of the refinery. Water within the Hammond Ditch, a concrete lined channel, is used for irrigation and watering of livestock and not intended for human consumption.

Bloomfield Refining CAP November 17, 2004

Page 6 of 16

Since the lining of the Hammond Ditch in 2001, it is no longer a contributor to local groundwater recharge at the site. Stormwater within the facility is collected in the curbed, concrete-paved process areas connected to sewers leading to the wastewater treatment system. Some areas not served by sewers collect process and stormwater in sumps, which are then emptied by a vacuum truck for delivery to the wastewater treatment system.

Prior to the lining of the Hammond Ditch, the infiltration of source water through the shallow-zone soils served as a hydraulic curtain for the migration of Phase-Separated Hydrocarbon (PSH) along the north property boundary. Lining of the Hammond Ditch and the decommissioning of unlined surface water ponds within the process area of the refinery has resulted in a significant reduction in groundwater recharge to the shallow-zone water-bearing zone on top of the Nacimiento Formation.

# 4.0 SITE CHARACTERIZATION DATA

This section describes recent site characterization and routine monitoring data that will be used to design and construct the north boundary barrier and fluids collection system.

#### 4.1 WATER LEVEL & PHASE-SEPARATED HYDROCARBON (PSH) DATA

Giant conducts routine monitoring activities at the refinery, which include monthly groundwater and product level measurements in monitoring wells and peizometers (installed in soil borings made to investigate the depth to the Nacimiento Formation) along the north property boundary. Groundwater and product level measurements were collected during the months of August and October of 2004 from these location points along the north property boundary. Table 1 summarizes these data with respect to the well depth and Nacimiento Formation surface elevation. This information, combined with the collection of additional monitoring data, will be used to design the fluids collection system and provide the barrier installation contractor with soil saturation information for excavation purposes.

Bloomfield Refining CAP November 17, 2004

Page 7 of 16

# 4.2 SLUG TESTS

In order to further understand the nature and variability of the shallow-zone soils and their hydraulic behavior, additional site characterization activities were conducted by Malcolm Pirnie, Inc. and Precision Engineering, Inc. during October 2004. Field activities included the completion of slug tests on monitoring wells MW-45 and MW-47.

The slug tests were performed to monitor the recovery rate of fluids through the shallowzone soils. Results from the slug tests were used to estimate the aquifer properties of the shallow-zone soils and the anticipated amount of fluids accumulation along the barrier. This information will also be provided to the barrier installation contractor for estimating slurry loss into the formation during barrier construction. The following summarizes the hydraulic properties estimated from the slug test data:

Well ID	Transmissivity (Ft ² /day)	Hydraulic Conductivity (Ft/day)
MW-45	N/A	N/A
MW-47	19.6	31.6

# Summary of Hydraulic Properties from Slug Tests

It should be noted that MW-45 penetrates into the Nacimiento Formation approximately 10 feet. In addition, the groundwater level measured in MW-45 during October 2004 was below the top of the Nacimiento formation. As such, the results of the slug test performed on MW-45 are not representative of the hydraulic properties of the shallow-zone soils, but rather the impermeable nature of the Nacimiento Formation.

# 4.3 NACIMIENTO FORMATION SURFACE CONTOUR MODEL DEVELOPMENT

Giant has conducted several drilling campaigns over the years to assess the environmental impacts of historic product releases at the refinery. In 1997, Giant Bloomfield Refining CAP

November 17, 2004

Page 8 of 16

commissioned the development of a Nacimiento Formation conceptual model to assess its topographic character beneath the refinery. An initial conceptual model was developed using information from previous drilling activities. Data collected from additional borings made in November 2003 and July 2004 to specifically investigate the Nacimiento Formation were added to the conceptual model to develop a July 2004 version of the contour model (Figure 2).

A review of the July 2004 Nacimiento Formation contour model identified some uncertainties with respect to the elevation of the Nacimiento Formation along the western and far eastern portions of the proposed barrier alignment. As such, seven (7) additional soil borings were installed by Precision Engineering, Inc. during October 2004; five (5) borings were installed along the west portion and two (2) along the east portion of the proposed barrier alignment. Figure 3 shows the location of the July and October 2004 borings with respect to the proposed barrier alignment.

Each boring installed during the October 2004 drilling campaign was drilled 3 to 5 feet into the Nacimiento Formation. Soil samples were collected every 2.5 ft and submitted to a geotechnical laboratory for grain size analysis to estimate properties important for the design of the barrier and collection system. Samples collected of the Nacimiento Formation were also submitted to the lab for hydraulic conductivity testing. The following summarizes the hydraulic conductivity test results for the samples collected during the October 2004 boring campaign.

Depth of Sample (ft)	Hydraulic Conductivity (cm / sec)
12 - 12.5	6.0 x 10 ⁻⁷
9.5 – 10.5	1.2 x 10 ⁻⁹

#### Hydraulic Conductivity Data of Nacimiento Formation

Bloomfield Refining CAP November 17, 2004 The lithologic logs for the borings installed in July and October 2004 are included in Appendix A. It is our understanding that OCD has copies of the previous borings on file.

# 5.0 HYDROGEOLOGY OF SHALLOW-ZONE SOILS

The hydraulic properties of the shallow-zone soils are key factors in estimating the hydraulic effects of the containment barrier, as well as in the design of the fluids collection system. Results from site characterization activities, in conjunction with the Nacimiento Formation contour model, provide a conceptual understanding of the hydrogeologic behavior of the shallow-zone soils.

#### 5.1 NACIMIENTO FORMATION SURFACE CONCEPTUAL MODEL

As discussed in Section 2.0, the shallow-zone soils (windblown sands and Jackson Lake Terrace deposits) are underlain by the non-water bearing Nacimiento Formation. The surface contour model of the Nacimiento Formation, as discussed in Section 4.3, indicates that depressions (troughs) exist within the Nacimiento Formation surface in areas along the north property boundary and underlying the refinery process areas. With the significant reduction of groundwater recharge after the lining of the Hammond Ditch and decommissioning of unlined surface water ponds within the process areas of the refinery, the surface contours of the Nacimiento Formation likely influence the migration and accumulation of groundwater and PSH beneath the refinery. This notion is further discussed in Section 5.2. Figure 4 shows the updated version of the Nacimiento Formation surface contour model based on information collected during the October 2004 drilling campaign.

# 5.2 SHALLOW-ZONE GROUNDWATER CONDITIONS

Based on the groundwater and product level measurements collected in August and October 2004 (shown in Table 1), the occurrence of fluids along the north property boundary varies based on the underlying topography of the Nacimiento Formation.

Bloomfield Refining CAP November 17, 2004

Page 10 of 16

These fluids level measurements were used to develop a cross-sectional profile along the proposed barrier alignment (Figure 5). As shown in Figure 5, there were areas where no groundwater was detected, which support the notion that the surface contours of the Nacimiento Formation likely influence the collection of fluids within the overlying thin water-bearing zone. Figure 4 shows the location of the north boundary wells containing detectable PSH with respect to the updated surface contour of the Nacimiento Formation.

# 5.3 AQUIFER TEST RESULTS

The hydraulic properties of the perched aquifer located above the Nacimiento Formation were previously tested during several aquifer tests conducted by Groundwater Technologies in June 1994. Two types of tests were attempted: a short-term, variable discharge rate (step-drawdown test), and a long-term pumping test. The objective of the short-term, variable discharge rate test was to estimate the specific capacity of the well and estimate the sustainable flowrate. The objective of the long-term aquifer test was to estimate the hydraulic properties of the saturated zone, which include the transmissivity, hydraulic conductivity, and specific yield. The following is a summary of the estimated hydraulic properties of the shallow-zone developed from these tests (Groundwater Technology, 1994).

Well	Transmissivity	Hydraulic Conductivity	Storativity
No.	(ft ² / day)	(ft/day)	(Dimensionless)
MP-3	1412	177	0.015
MP-4	1260	158	0.003
RW-22	353	44	NA

Summary of	of Hvd	raulic	Properti	es
------------	--------	--------	----------	----

The calculated values of transmissivity and hydraulic conductivity from the June 1994 aquifer tests are indicative of a high-permeability saturated zone, representing sand and gravel deposits.

Bloomfield Refining CAP November 17, 2004 A slug test was performed on MW-47, as discussed in Section 4.2. The results from the slug test have similar hydraulic properties to the wells tested above. Note, the above wells were located in the plant facility and had much greater saturated thickness. Based on the aquifer test and slug test results, the Jackson Lake Terrace Deposits have hydraulic conductivity, ranging between 40 to 180 ft/day, averaging 150 ft/day. The deposits exhibit high permeability characteristics, but have minimal saturated thickness near the Hammond Ditch.

# 5.4 CONCLUSIONS

Based on the hydraulic properties of the shallow-zone soils and limited saturation, groundwater flow and fluids accumulating along the proposed barrier are estimated to be below 10 gallons per minute (gpm). This estimate was determined based on the following:

$Q = \underline{KIA}$	where	K = 150  ft/day
η		$\eta = 40\%$ porosity
	:	I = .002ft/ft gradient
		A = 2600 feet x 2 feet saturation

It is our opinion that groundwater that flows toward the barrier will accumulate in the depressions on the surface of the Nacimiento Formation. Collection methods to extract the groundwater behind the barrier may include collection trenches, wells, or other methods. It is believed that extracting groundwater only in the depressions will provide sufficient capture of groundwater behind the barrier. This approach will cause groundwater to move from the higher elevations to the lower areas of depressions and limit potential groundwater level rise away from the collection areas.

# 5.5 ADDITIONAL MONITORING PLAN

Continued monitoring of the groundwater and PSH levels along the north property boundary, including the soil borings installed in October 2004, will be conducted by Giant on a monthly basis through January 2005. The water level information will be used

Bloomfield Refining CAP November 17, 2004

Page 12 of 16

to confirm preliminary conclusions with respect to the amount of fluids that may accumulate at the barrier and to prepare a final design for the fluids collection system (Section 6.2). Table 2 includes the list of monitoring wells and soil borings along the north property boundary that will be included in the on-going monitoring activities.


# 6.0 **PROPOSED CORRECTIVE ACTION PLAN**

As a corrective action to mitigate further off-site migration of petroleum hydrocarbons, Giant has committed to the installation of a containment barrier and fluids collection system along the north property boundary. The containment barrier will extend from County Road 4990 to a location approximately 200 feet east of the El Paso Natural Gas Pipelines. The approximately 2,600-foot long barrier will be installed along the north side of and parallel to the Hammond Ditch, within the existing service roadway. A fluids collection system, consisting of multiple fluids recovery location points along the refinery side of the barrier, will serve to provide hydraulic control of fluids accumulating along the barrier.

# 6.1 BARRIER CONCEPT

In general, the north boundary barrier will be constructed by excavating a narrow trench, typically 3 to 5 feet wide, through the Jackson Lake Terrace and into the Nacimiento Formation. The barrier, varying in depth from approximately 10 to 15 feet along the alignment, will key into the top of the Nacimiento Formation a minimum of 3 feet to mitigate potential underflow of fluids.

The barrier design and method of construction will be determined by Giant based on competitive proposals solicited from experienced barrier contractors. The performance requirement will be to install a finished barrier that provides a hydraulic conductivity (permeability (k)) of  $1 \times 10^{-7}$  cm/sec or less.



Bloomfield Refining CAP November 17, 2004

Page 13 of 16

Several designs and construction methods are available to achieve this performance objective: soil-bentonite slurry trench walls; soil-cement slurry trench walls; slurry trench with geo-membrane barrier; and shallow soil mixing using bentonite and/or cement to create an in-place wall. Contractor proposals will be evaluated based on their ability to achieve the required performance specifications, constructability considering site conditions, ability to meet the desired installation schedule, and cost effectiveness.

Appropriate construction quality control measures will be applied during barrier construction to verify that the performance requirements will be achieved.

Clean soil excavated from the trench may be utilized by the contractor for barrier construction (if appropriate) and for backfill purposes. Contaminated soil will be segregated to the extent possible and properly stock-piled in a separate location on-site for proper characterization and subsequent management. Giant will determine the management approach (e.g., on-site treatment or off-site disposal) for the contaminated soil once the quantity and character of the soil is determined.

### 6.1.1 Utility Crossings

Subsurface utilities have been identified at three locations along the proposed barrier alignment. Those locations are:

- Tank 37 (French Drain Collection System), located approximately 50 feet east of SB1-0704,
- Fire water supply pipeline, located approximately 100 feet west of the El Paso Pipeline easement, and
- El Paso Natural Gas Pipelines, located within a 100-foot easement west of P8 (SB7-1103).

In locations where it is possible to install sufficient barrier height to achieve the desired performance, the barrier will pass beneath the utilities. However, depending on the depth of the subsurface utilities with respect to the Nacimiento Formation in those locations, utilities may be required to penetrate the barrier. If so, proper sealing techniques will be employed at those locations to mitigate leakage. Bloomfield Refining CAP

November 17, 2004


Page 14 of 16

# 6.2 FLUIDS COLLECTION CONCEPT

Hydraulic control of fluids (groundwater and PSH) captured by the barrier will be accomplished by installing a series of collection wells and/or interceptor trenches at locations along the length of the barrier. Conceptually, collection wells or trenches will

be located at Nacimiento trough intersections along the barrier. Additional collection points may be required along the barrier based on the results of the additional water level monitoring (Section 5.5) and/or operational experience after the barrier is installed.

Fluids will be removed from the collection points using a vacuum truck when necessary based on fluids level monitoring results. Collected fluids will delivered to the existing French Drain collection tank near SB2-0704.



### 6.3 IMPLEMENTATION CONCEPT

Implementation of the barrier and fluids collection system will be completed in two phases. Phase I will include development of construction documents and solicitation of bids for the containment barrier, followed by construction of the barrier. Phase II will consist of the design and installation of the fluids collection system. The fluids collection system will be installed after completion of the containment barrier construction.

# 6.4 **CONSTRUCTION PERMITS**

Giant will comply with all permitting requirements associated with the construction of the containment barrier.

Bloomfield Refining CAP November 17, 2004

Page 15 of 16

Preliminarily, it appears only a construction stormwater permit will be required. Giant will submit a Notice of Intent (NOI) to United States Environmental Protection Agency (USEPA) Region 6 prior to the start of construction activities. The NOI process will include an Endangered Species Act Review by United States Fish and Wildlife Services (USFWS) for the adjacent reach of the San Juan River, and development of a Storm Water Pollution Prevention Plan (SWPPP).


VOC air emissions during the excavation activities are expected to be insignificant and not trigger any state permitting requirements. On-site treatment (e.g., landfarming) of petroleum-contaminated soils may require air permitting activities. Giant will further evaluate that issue if on-site soil treatment is pursued.

# 7.0 SCHEDULE

Construction of the northern boundary containment barrier is anticipated to start by January 17, 2004. Figure 6 shows the estimated implementation schedule.

# 8.0 **REFERENCES**

Groundwater Technology, 1994. Uppermost Aquifer Hydraulic Testing and Modeling; Giant Refining Company.





BILL RICHARDSON GOVERNOR State of New Mexico ENVIRONMENT DEPARTMENT Hazardous Waste Bureau 2905 Rodeo Park Drive East, Building 1 Santa Fe, New Mexico 87505-6303 Telephone (505) 428-2500 Fax (505) 428-2567 www.nmenv.state.nm.us



RON CURRY SECRETARY

DERRITH WATCHMAN-MOORE DEPUTY SECRETARY

# CERTIFIED MAIL RETURN RECEIPT REQUESTED

December 21, 2004

Mr. Randy Schmaltz Environmental Supervisor Giant Refining Company P.O. Box 159 Bloomfield, New Mexico 87413 Mr. Ed Riege Environmental Superintendent Giant Refining Company Route 3, Box 7 Gallup, New Mexico 87301

# SUBJECT: APPROVAL WITH CONDITIONS VOLUNTARY CORRECTIVE MEASURES PLAN BLOOMFIELD REFINING COMPANY RCRA PERMIT NO. NMD 089416416 HWB-GRCB-04-005

Dear Mr. Schmaltz and Mr. Riege:

The New Mexico Environment Department (NMED) has completed its review of the Voluntary Corrective Measures Plan titled *Corrective Action Plan* (CAP) dated November 17, 2004, submitted on behalf of Giant Refining Company Bloomfield (GRCB). NMED hereby approves the CAP with the conditions listed below:

- 1. In addition to NMED, all requested information shall be submitted to the Oil Conservation Division Santa Fe office and the OCD District office.
- 2. The barrier wall shall be imbedded a minimum of 5 feet into the Nacimiento Formation. A barrier wall conceptional "flow net study" shall be conducted to ensure the wall is buried deep enough to stop significant seepage from going under the wall. Please provide the results of the study for NMED approval before actual installation of the wall.

Randy Schmaltz Giant Refining Company Bloomfield December 21, 2004 Page 2 of 4

- 3. The final barrier wall type shall be submitted to NMED for approval before installation. GRCB shall demonstrate to NMED that the barrier wall type and design will meet any structural requirement and hydraulic conductivity (k) of 1 x 10⁻⁷ cm/sec.
- 4. Detailed "as built drawings" and photo documentation shall be supplied at the completion of construction. At least one of the drawings shall show a cross section along the entire wall.
- 5. Daily logs shall be kept during the construction phase. All pertinent information shall be logged such as contamination observed, soil characteristics, water levels, depth to Nacimiento Formation, progress made each day, dewatering or contaminant removal activities, general weather, and all other pertinent information that should be logged that may cause a deviation of the approved design and/or any anomalies found in the trench which may cause GRCB to deviate from the plan or be of a concern. GRCB shall notify NMED of any deviations from the plan within one business day of making the change.
- 6. GRCB shall submit a weekly progress report and photos via E-mail on Monday morning.
- 7. GRCB shall submit the fluid collection system design for approval before actual installation. This should include a map identifying the locations of recovery wells or trenches and all other pertinent information. The Permittee may remove fluids during the course of the project for logistic and safety reasons. All fluids and waste removed shall be disposed or recycled in an approved manner.
- 8. GRCB shall maintain a qualified technical person on site during the construction phase to ensure quality assurance and control of the project. This person shall be experienced in identifying the Nacimiento Formation. Ample confirmation bottom hole soil samples shall be collected in areas where the proposed collection systems may be placed. Samples shall be collected and preserved to properly identify/classify the soils.
- 9. GRCB will notify the NMED at least 72 hours in advance of the start of construction and all scheduled sampling activities throughout the construction process such that the NMED has the opportunity to witness the events and/or collect split samples during NMED's normal business hours.
- GRCB shall submit a plan for NMED approval to evaluate the effectiveness of the barrier wall. This plan should include monitoring points on both sides of the barrier wall.

Randy Schmaltz Giant Refining Company Bloomfield December 21, 2004 Page 3 of 4

- 11. GRCB must submit construction diagrams for the peizometers along the north property boundary installed during the November 2003, July 2004, and October 2004 drilling programs. This information must include the slot-size and slot intervals of the PVC hand-slotted screens, length of screen, depth at which the screens were set, and depth of water bearing zones. The "Log of Test Borings" (boring logs) found in the CAP do not include all of this information.
- 12. Boring log SB1-0704 states "[b]lack with hydrocarbon odor;" the term black is also used in other boring logs SB2-0704, SB3-0704, SB6-0704, and SB7-0704. GRCB must clarify the use of the term "black" in the boring logs. (e.g. is black referring to hydrocarbon staining or is black the actual mineral color in the sand).
- 13. The CAP, Sections 4.2 contains a table presenting the hydraulic properties from a slug test. GRCB must provide the results of the slug test and the associated calculations. Include graphs as necessary.
- 14. The CAP, Section 4.3 states "[e]ach boring installed during the October 2004 drilling campaign was drilled 3 to 5 feet into the Nacimiento Formation. Soil samples were collected every 2.5 ft and submitted to a geotechnical laboratory for grain size analysis to estimate the properties important for the design of the barrier and collection system. Samples collected of the Nacimiento Formation were also submitted to the lab for hydraulic conductivity testing."

GRCB must submit the results of the grain size analyses and hydraulic conductivity testing for all borings.

15. CAP, page 2 of Section 6.1 Barrier Concept, states "Appropriate construction quality control measures will be applied during barrier construction to verify that the performance requirements will be achieved."

GRCB must identify the quality control measures that will be used and the performance requirements that will be achieved.

16. The CAP, Section 6.2 Fluids Collection Concept, states "[f]luids will be removed from the collection points using a vacuum truck when necessary based on fluids level monitoring results. Collection fluids will be delivered to the existing French Drain collection tank near SB2-0704."

Randy Schmaltz Giant Refining Company Bloomfield December 21, 2004 Page 4 of 4

> GRCB must clarify if a vacuum truck is the only method of fluid collection removal to be employed upon completion of the barrier wall and fluid collection system.

- 17. Appendix A provides results from a sieve analysis. GRCB must identify what soil samples are associated with "PEI Lab No." 46464, 46465, 46461, 46462, and 46463 because these were not identified in the October boring logs.
- 18. The barrier wall installation may cause the displacement of hydrocarbons. In the future, NMED may require additional sampling and monitoring from the monitoring wells located in the southern portion of the refinery (e.g. MW-32, 33, 34, 35, 36, 36, and 38) and the three outfall locations.

The Permittees must submit the requested information within 30 days of receipt of this letter or NMED will rescind approval.

If you have any questions regarding this approval please contact me at (505) 428-2545.

Sincerely,

Hope Monzifle

Hope Monzeglio Project Leader Hazardous Waste Bureau

HCM:hcm

cc: J. Bearzi, NMED HWB
J. Kieling, NMED HWB
D. Cobrain, NMED HWB
W. Price, OCD
D. Foust, OCD Aztec Office
B. Wilkinson, EPA

Reading File and GRCB 2004 File

#### **Cindy Hurtado**

From: Sent: To: Subject: Randy Schmaltz Wednesday, March 30, 2005 2:23 PM Cindy Hurtado FW: Giant Bloomfield Corrective Action Plan



Corrective Action plan approva...

----Original Message----From: Price, Wayne [mailto:WPrice@state.nm.us] Sent: Friday, December 17, 2004 1:23 PM To: Randy Schmaltz (E-mail); Ed Rigie (E-mail) Cc: Hope Monzeglio (E-mail); Foust, Denny; Bob Wilkinson (E-mail) Subject: Giant Bloomfield Corrective Action Plan

Please find enclosed a letter that is going out today approving of the plan.

<<Corrective Action plan approval DEC 17 2004.doc>>

Sincerely:

::



Wayne Price New Mexico Oil Conservation Division 1220 S. Saint Francis Drive Santa Fe, NM 87505 505-476-3487 fax: 505-476-3462 E-mail: WPRICE@state.nm.us

Confidentiality Notice: This e-mail, including all attachments is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited unless specifically provided under the New Mexico Inspection of Public Records Act. If you are not the intended recipient, please contact the sender and destroy all copies of this message. -- This email has been scanned by the MessageLabs Email Security System.

December 17, 2004

Mr. James R. Schmaltz Environmental Manager Giant Refining Company (Giant) P.O. Box 159 Bloomfield, New Mexico 87413

Re: Corrective Action Plan

Dear Mr. Schmaltz:

.

The New Mexico Oil Conservation Division (OCD) is in receipt of the Corrective Action Plan and cover letter dated November 16, 2004. The plan outlines how Giant proposes to mitigate the off-site migration of petroleum hydrocarbons within the shallow-zone soils along the north property boundary of the Bloomfield refinery.

#### OCD hereby approves of the plan with the following conditions:

- 1. All information and or actions required by the New Mexico Environment Department Hazardous Waste Bureau shall become part of this approval.
- 2. The barrier wall shall be imbedded a minimum of 5 feet into the Nacimiento Formation. A barrier wall conceptional "flow net study" shall be conducted to ensure the wall is buried deep enough to stop significant seepage from going under the wall. Please provide for OCD approval before actual installation of wall.
- 3. The final barrier wall type shall be submitted to OCD for approval before installation. Giant shall demonstrate to OCD that the barrier wall type and design will meet any structural requirement and hydraulic conductivity (permeability (k)) of  $1 \times 10^{-7}$  cm/sec.
- 4. Detail "as built drawings" and photo documentation shall be supplied at the end of construction. At least one of the drawings shall show a side view along the entire wall.

Mr. James R. Schmaltz Environmental Manager Giant Refining Company (Giant)

Daily logs shall be kept during the construction phase. All pertinent information shall be logged such as contamination observed, soil characteristics, water levels, depth to Nacimiento formation, progress made each day, general weather, and any other pertinent information that should be logged that may cause a deviation of the approved design and/or any anomalies found in the trench which may cause Giant to deviate from the plan or be of a concern.

- 5. Giant shall submit a weekly progress report and photos via E-mail on Monday morning.
- 6. Giant shall submit the fluid collection system design for approval before actual installation. Giant may remove fluids during the course of the project for logistic and safety reasons. All fluids and waste removed shall be disposed of or recycled in an approved manner.
- 7. Giant shall maintain a qualified technical person on site during the construction phase to ensure quality assurance and control of the project. This person shall be experienced in identifying the Nacimiento Formation. Ample confirmation bottom hole soil samples shall be collected in areas where the proposed collection systems may be placed. Samples shall be collected and preserved to properly identify/classify the soils and perform permeability test in a certified soils laboratory if deemed warranted by OCD.
- 8. Giant will notify the OCD Santa Fe office and the OCD District office at least 72 hours in advance of all scheduled activities such that the OCD has the opportunity to witness the events and/or split samples during OCD's normal business hours.
- 9. Giant shall submit a plan for OCD approval to measure and monitor the effectiveness of the barrier wall. This plan should include any area where contamination as been discovered and various monitoring points behind the barrier wall.

Please be advised that NMOCD approval of this plan does not relieve (Giant) of liability should their operations fail to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD approval does not relieve (Giant) of responsibility for compliance with any other federal, state, or local laws and/or regulations.

Mr. James R. Schmaltz Environmental Manager Giant Refining Company (Giant) December 17, 2004 Page 3

If you have any questions please do not hesitate to contact me at 505-476-3487 or e-mail <u>WPRICE@state.nm.us</u>.

Sincerely;

Mapur Pini

Wayne Price-Pet. Engr. Spec.

cc: OCD Aztec Office



November 24, 2004

Mr. Wayne Price New Mexico Oil Conservation Division 1220 S. Saint Francis Drive Santa Fe, New Mexico 87505

# Re: Giant Bloomfield Refinery – River Terrace Sheet Pile Area

Dear Mr. Price:

As a follow up to our letter dated October 27, 2004, Giant is submitting this letter report summarizing the field investigation performed in the river terrace sheet-pile area at the Bloomfield facility.

The purpose of the investigation was to 1) install two new monitoring wells at the river terrace to supplement the two existing piezometers currently used for water quality monitoring and 2) evaluate the presence and extent of fuel hydrocarbons in groundwater on the refinery side of the sheet-pile barrier. The investigation resulted from Giant's meeting with NMOCD in Santa Fe, New Mexico on October 18, 2004.

# **Field Investigation Activities**

The investigation involved the installation of eight temporary well points (TP-1 through TP-8) and two permanent wells (MW-48 and MW-49). Precision Engineering from Las Cruces, New Mexico installed the well points and monitoring wells on October 27 and October 28, 2004 using a hollow-stem auger drill rig. The location of the eight well points and the two wells are shown on Figure 1. Logs of the well points and monitoring wells are attached in Appendix A.

The well points were constructed using two-inch diameter hand-slotted PVC casing placed approximately five feet below the water table. The two monitoring wells were constructed with four-inch diameter PVC well casing and ten feet of 0.020-inch machine slotted screen. All the well screens intersect the water table.

Soil samples were collected from Wells MW-48 and MW-49 and were submitted to Hall Environmental Analysis Laboratory for analysis for the following parameters:

PHONE 505-632-8013 FAX 505-632-3911 50 ROAD 4990 P.O. BOX 159 BLOOMFIELD NEW MEXICO 87413 Mr. Wayne Price November 23, 2004

- Total Petroleum Hydrocarbons Diesel and Motor Oil Range Organics (DRO & MRO) by EPA Modified Method 8015B,
- Total Petroleum Hydrocarbons Gasoline Range Organics (GRO) by EPA Modified Method 8015B, and
- Volatile Organic Compounds by EPA Method 8260B.

Following the installation and development of the well points and wells, Giant collected groundwater samples from them on October 28 and November 1, 2004. The samples were submitted to Hall Environmental Analysis Laboratory for analysis. Groundwater samples collected from the temporary well points were analyzed for the following parameters:

- Total Petroleum Hydrocarbons Diesel and Motor Oil Range Organics (DRO & MRO) by EPA Modified Method 8015B
- Total Petroleum Hydrocarbons Gasoline Range Organics (GRO) by EPA Modified Method 8015B
- Volatile Organic Compounds by EPA Method 8021B

Groundwater samples collected from MW-48 and MW-49 were analyzed for the following parameters:

- Total Petroleum Hydrocarbons Diesel and Motor Oil Range Organics (DRO & MRO) by EPA Modified Method 8015B
- Total Petroleum Hydrocarbons Gasoline Range Organics (GRO) by EPA Modified Method 8015B
- Volatile Organic Compounds by EPA Method 8260B
- Anions (Fluoride, Chloride, Nitrite, Nitrate, Phosphorus, Sulfate) by EPA Method 300.0
- Polynuclear Aromatic Hydrocarbons by EPA Method 8310
- Specific Conductance by EPA Method 120.1
- Mercury by EPA Method 7470
- Dissolved Metals by EPA Method 6010C
- Total Recoverable Metals by EPA Method 6010C
- pH by EPA Method 150.1

;

• Total Dissolved Solids by EPA Method 160.1

A summary of the fuel hydrocarbon results from each well are presented on Figure 2. All soil and groundwater analytical results obtained from this investigation are presented in Table 1.

Mr. Wayne Price November 23, 2004

# Preliminary Data Review

On the refinery side of the sheet-pile barrier, the groundwater sampling results indicate fuel hydrocarbon contamination extends from the barrier to the east to temporary well point TP-4. Fuel hydrocarbons were also reported in well point TP-3, the farthest east well point. but the concentrations were low compared to the results closer to the barrier. For example, benzene was detected in TP-3, but the concentration was below 5 ug/L. The highest BTEX concentrations were reported near the barrier in TP-1, TP-8, and MW-48.

Comparing the groundwater sampling results from well MW-49 (river side of barrier) to those from MW-48, fuel hydrocarbons were reported to be significantly lower on the river side of the barrier. For example, the benzene and toluene concentrations in MW-49 were reported below the laboratory detection limit of 10 ug/L. Ethylbenzene and xylenes were detected, but were reported at concentrations approximately two orders of magnitude less than reported in well MW-48. These data indicate the sheet-pile wall is acting as a significant barrier against fuel hydrocarbon migration to the river.

Low concentrations of diesel and gasoline-range organics were reported in the soil samples taken from monitoring wells MW-48 and MW-49. The depth of occurrence appears to be similar in both locations, suggesting the existence of these hydrocarbons in the soil predates the barrier installation. The concentrations reported in the soil samples from MW-49 (river side of barrier) are generally one-half those reported from MW-48.

# **Proposed Additional Activities**

*,

Based on the results of this investigation, we recommend the following activities:

- Conduct a 24-hour aquifer test on well MW-48 to evaluate aquifer properties. Monitor drawdown in the monitoring wells MW-48 and MW-49, and selected well points surrounding MW-48. Collect groundwater samples in MW-48 and MW-49 during the test.
- 2) Complete a capture zone analysis and estimate the number of extraction wells and related pumping rates that would be needed to control the impacted groundwater on the refinery side of the barrier and further mitigate migration of hydrocarbons to the San Juan River. The effectiveness of implementing a pumping approach will then be evaluated as part of a feasibility study of alternatives.
- 3) It appears the extent of groundwater impacts has not been fully delineated along the San Juan River upstream of the barrier and east of TP-3. As such, install additional temporary well points in these locations
- 4) Sample wells MW-48 and MW-49 on a monthly schedule to evaluate water quality trends. The wells will be sampled for TPH (GRO), BTEX, and PAHs.
- 5) Conduct a feasibility study to evaluate alternatives for reducing fuel hydrocarbon concentrations in the shallow aquifer beneath the river terrace.
- 6) Submit the feasibility study to NMOCD for approval.

Mr. Wayne Price November 23, 2004

Giant anticipates the aquifer test will be performed in early December 2004. Following analysis of the data obtained, the feasibility study will be conducted to identify an approach to reduce the concentrations of fuel hydrocarbons on the refinery side of the barrier and further mitigate fuel hydrocarbon migration to the river. Giant anticipates submitting a feasibility study report, which will include the aquifer test results, to NMOCD by mid-January 2005. Installation of the additional temporary well points will occur in parallel with the feasibility study, and the results of that work will be reported to NMOCD within two weeks of receiving laboratory results.

If you have any questions in this matter, please contact me at 505-632-4171.

Sincerely,

GIANT REFINING COMPANY

James R. Schmaltz Environmental Manager

Cc: Denny Foust - OCD Aztec Office Hope Monzeglio/Dave Cobrain – NMED Hazardous Waste Bureau Bob Wilkinson – EPA Ed Riege Chad King



BILL RICHARDSON GOVERNOR State of New Mexico ENVIRONMENT DEPARTMENT Hazardous Waste Bureau 2905 Rodeo Park Drive East, Building 1 Santa Fe, New Mexico 87505-6303 Telephone (505) 428-2500 Fax (505) 428-2567 www.nmeny.state.nm.us



RON CURRY SECRETARY

DERRITH WATCHMAN-MOORE DEPUTY SECRETARY

# CERTIFIED MAIL RETURN RECEIPT REQUESTED

December 29, 2004

Mr. Randy Schmaltz Environmental Supervisor Giant Refining Company P.O. Box 159 Bloomfield, New Mexico 87413 Mr. Ed Riege Environmental Superintendent Giant Refining Company Route 3, Box 7 Gallup, New Mexico 87301

# SUBJECT: APPROVAL WITH CONDITIONS VOLUNTARY CORRECTIVE MEASURES BLOOMFIELD REFINING COMPANY RCRA PERMIT NO. NMD 089416416 HWB-GRCB-04-006

Dear Mr. Schmaltz and Mr. Riege:

The New Mexico Environment Department (NMED) has completed its review of the Voluntary Corrective Measures Plan (VCM Plan) titled *Giant Bloomfield Refinery – River Terrace Sheet Pile Area* (RTSPA Plan) dated November 24, 2004, submitted on behalf of Giant Refining Company Bloomfield Refinery (GRCB). NMED hereby approves the RTSPA Plan with the conditions listed below:

1. GRCB must submit construction diagrams for permanent wells MW-48 and MW-49.

2. GRCB must survey the top of the well casings of monitoring wells MW- 48, MW-49 and temporary wells TP-1 through TP-8 relative to a common benchmark to determine the elevations of the well casing rims. GRCB must measure depth to water from the casing rim in each well and, based on the well casing elevation data, determine the groundwater elevations to the nearest 0.01 ft. The groundwater elevation data, including the date(s) of Randy Schmaltz Giant Refining Company Bloomfield December 29, 2004 Page 2 of 3

measurement, must be submitted to NMED in conjunction with the RTSPA Plan conditions.

- 3. GRCB must submit construction diagrams for the eight recently installed temporary well points (TP-1 through TP-8). This information must include slot size and slot intervals of the PVC hand-slotted screens, identify if the screened intervals intersect the water table, and provide the depth at which the screen was set.
- 4. GRCB must indicate if separate phase hydrocarbon (SPH) was observed during the installation process and sampling of monitoring wells MW-48, MW-49 and temporary well points TP-1 through TP-8.
- 5. The "Log of Test Borings" (boring logs) states "<u>Sand</u>, fine to medium, black, damp" in boring log TP1-1004; the term "black" is also used in other boring logs (TP2-1004, TP4-1004, TP5-1004, TP6-1004; TP7-1004, TP8-1004, MW-48, and MW-49). GRCB must clarify the use of the term "black" in the boring logs. (i.e; is black referring to hydrocarbon stained sand or is black the natural color of the sand).
- 6. GRCB must provide all laboratory analytical results from this investigation. (NMED has received laboratory analytical results from 10/28/04 MW-48 & MW-49 soil sampling, 11/1/04 MW# 48 & MW #49 water sampling, and 10/28/04 TP-1 TP-8 water sampling)
- 7. NMED requires GRCB to determine the extent of contamination east of TP-3. GRCB must provide NMED with a map containing proposed well locations for NMED approval prior to installation. NMED requires GRCB to use factory machine-slotted PVC well screen and not hand-slotted screened PVC because the closer spacing of the slots.
- The RTSPA Plan, Proposed Additional Activities Section, recommends activities #1 6. NMED requires the following: (comments 1-6 correspond to the proposed activities 1-6 in the RTSPA Plan).
  - 1) Submit the results and findings of the 24-hour aquifer test performed on MW-48.
  - 2) Submit the results of the capture zone analysis.
  - 3) See comment #7.

-----

- 4) Submit all monthly sampling laboratory analytical and monitoring results from MW-48 and MW-49 collected since their installation.
- 5) Provide a comment clarifying that the term "feasibility study" was used to describe the implementation of voluntary corrective measures at the riverbank for containment of contaminants.

Randy Schmaltz Giant Refining Company Bloomfield December 29, 2004 Page 3 of 3

6) Submit the results of the "interim voluntary corrective measures" for NMED's review.

GRCB must submit the requested information by January 31, 2005. If any of these activities will not be performed, an explanation for the change in scope must be provided to NMED.

If you have any questions regarding this conditional approval please call me at (505) 428-2545.

Sincerely,

Hope Manye lies

Hope Monzeglio Project Leader Hazardous Waste Bureau

HCM:hcm

cc: J. Kieling, NMED HWB D. Cobrain, NMED HWB W. Price, OCD D. Foust, OCD Aztec Office B. Wilkinson, EPA

Reading File and GRCB 2004 File

#### **Cindy Hurtado**

From:	Price, Wayne [WPrice@state.nm.us]
Sent:	Friday, December 17, 2004 2:58 PM
То:	'Randy Schmaltz'; Dave Cobrain; Foust, Denny; Hope Monzeglio; Robert Wilkinson; Price, Wayne
Cc:	Ed Řiege; Chad King; Cindy Hurtado
Subject:	RE: Giant Bloomfield River Terrace Investigation

Dear Mr. Schmaltz:

OCD hereby approves of the submitted plan. Please provide a report of your findings including recommendations by January 31, 2005.

Please be advised that NMOCD approval of this plan does not relieve (Giant)of liability should their operations fail to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD approval does not relieve (Giant) of responsibility for compliance with any other federal, state, or local laws and/or regulations.

-----Original Message-----From: Randy Schmaltz [mailto:rschmaltz@giant.com] Sent: Wednesday, November 24, 2004 11:05 AM To: Dave Cobrain; Denny Foust; Hope Monzeglio; Robert Wilkinson; Wayne Price Cc: Ed Riege; Chad King; Cindy Hurtado Subject: Giant Bloomfield River Terrace Investigation

Please find enclosed a report summarizing Giant's field investigation of the river terrace sheet-pile area. Hard copies of the report will follow.

<<River Terrace Investigation Letter 11-22-04.doc>> <<Figure 1_Sample Location Map.ppt>> <<Figure 2_Analytical Result Summary Location Map-River Tearrace.ppt>> <<River Terrace Appendix A_Boring Logs.pdf>> <<River Terrace Table 1 Analytical Summary.xls>>

DISCLAIMER: The information contained in this e-mail message may be privileged, confidential and protected from disclosure. If you are not the intended recipient, any further disclosure, use, dissemination, distribution or copying of this message or any attachment is strictly prohibited. If you think you have received this e-mail message in error, please e-mail the sender at the above address and permanently delete the e-mail. Although this e-mail and any attachments are believed to be free of any virus or other defect that might affect any computer system into which they are received and opened, it is the responsibility of the recipient to ensure that they are virus free and no responsibility is accepted by Giant Industries, Inc. or its affiliates for any loss or damage arising in any way from their use.

This email has been scanned by the MessageLabs Email Security System. For more information please visit http://www.messagelabs.com/email

Confidentiality Notice: This e-mail, including all attachments is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited unless specifically provided under the New Mexico Inspection of Public Records Act. If you are not the intended recipient, please contact the sender and destroy all copies of this message. --This email has been scanned by the MessageLabs Email Security System.