

# CONDITIONS OF APPROVAL

API #	Operator	Well name & Number
30-025-46473	Solaris Water Midstream	Mills 19 SWD # 001

Applicable conditions of approval marked with **XXXXXX**

## Administrative Orders Required

<b>XXXXXXX</b>	Review order SWD 1878 for additional conditions of approval

## Other wells

## Casing

<b>XXXXXXX</b>	SURFACE, INTERMEDIATE(1) & PRODUCTION CASING - Cement must circulate to surface -- Liner(1) Cement come to top of liner
<b>XXXXXXX</b>	<b>Surface casing must be set 25' below top of Rustler Anhydrite in order to seal off protectable water</b>

## Lost Circulation

<b>XXXXXXX</b>	Must notify OCD Hobbs Office if lost circulation is encountered at 575-370-3186

## Water flows

<b>XXXXXXX</b>	Must notify OCD Hobbs Office of any water flow in the Salado formation at 575-370-3186. Report depth and flow rate.

## Stage Tool

<b>XXXXXXX</b>	Must notify OCD Hobbs Office prior to running Stage Tool at 575-370-3186
<b>XXXXXXX</b>	If using Stage Tool on Surface casing, Stage Tool must be greater than 350' and a minimum 200 feet above surface shoe.
<b>XXXXXXX</b>	When using a Stage Tool on Intermediate or Production Casing Stage must be a minimum of 50 feet below previous casing shoe.

## Completion & Production

<b>XXXXXXX</b>	Will require a deviation survey with the C-105
<b>XXXXXXX</b>	Must notify Hobbs OCD office prior to conducting MIT (575) 393-6161 ext. 114
<b>XXXXXXX</b>	Must conduct & pass MIT prior to any injection
<b>XXXXXXX</b>	Approval of this APD does not approve your tubing sizes. Please see SWD order for approved tubing sizes.
<b>XXXXXXX</b>	Must conduct & pass MIT prior to any injection