

APD Surface Use Plan of Operations

Existing Roads (Exhibit 1)

- Driving directions are from Jal, New Mexico. The location is approximately 50.5 miles from the nearest town, which is Jal, New Mexico. From Jal, NM. Proceed West on Highway 128 approximately 30 miles and turn left (South) onto CR1 and go approximately 14.2 miles to Battle Axe road (CR 2) and turn left or east, and go approximately 6.7 miles and turn left (North) and follow lease road approximately 3.5 miles to the well.

New or Reconstructed Access Roads – Survey plat (Exhibit 2)

- There will be 48' to well pad, entering at southeast of new road construction for this proposal. The road will follow the contours of the landscape.
- Road Width: The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed 14'. The maximum width of surface disturbance shall not exceed 25'.
- Maximum Grade: less than 5%
- Crown Design: Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2%. The road shall conform to cross section and plans for typical road construction found in the BLM Gold Book.
- Turnouts: No turnouts will be needed.
- Ditch Design: Ditching will be constructed on both sides of road.
- Cattle guards: No cattle guards will be needed.
- Major Cuts and Fills: 2:1 during drilling and completions. Cuts and fills taken back to 3:1 at interim.
- Type of Surfacing Material: Caliche

Location of Existing Wells (Exhibit 3)

- 1-Mile radius map is attached

Location of Existing and/or Proposed Production Facilities (Exhibit 4)

- Facilities: Production facilities will be placed in the center of sec. 14, T26S, R32E along the south section line where oil and gas sales will take place.
 - The facility is in Sec. 14, T26, R32E; off-lease measurement will be required for Sec. 23, T26, R32E, Federal lease NMNM118723 production.

- Gas purchaser has not decided where sales line will be, ROW will be filed and approved prior to surface disturbing activities.
- Open top tanks or open containments will be netted.
- Open vent exhaust stacks will be modified to prevent birds or bats from entering, discourage perching, roosting, and nesting.
- Facilities will have a secondary containment 1.5 times the holding capacity of largest storage tank.
- All above ground structures will be painted non-reflective shale green for blending with surrounding environment.
- The permanent water disposal system will be determined prior to construction of any water transfer pipeline. Until permanent water takeaway is available, produced water will be hauled off location in trucks.

Infrastructure (see Exhibit 5)

- Pipelines: A 3,074 foot, 4" surface flex line with less than 125 psi working pressure will be laid along existing disturbances from well to production facility.
 - A ROW will be applied for through the BLM.
 - All construction activity will be confined to the approved ROW.
 - Pipeline will run parallel to road on north and will stay within approved ROW.
- Pipelines: A 4" buried flex line with greater than 125 psi working pressure, approximately 2,641 feet long will be laid along existing disturbances from gas lift compression facility to well.
 - A ROW will be applied for through the BLM.
 - All construction activity will be confined to the approved ROW.
 - Pipeline will run parallel to road on north and will stay within approved ROW.
- Power lines: The permanent electrical supply route is shown in Exhibit 5. The length of power line is approximately 292 feet from well pad running south from well pad to existing power line. A generator will be utilized until permanent power is connected.
 - A ROW will be applied for through the BLM.
 - All construction activity will be confined to the approved ROW.
 - Power line will run parallel to road on south and will stay within approved ROW.

Location and Types of Water Supply (Exhibit 5)

- Water supply will be obtained from a private water source.
- Chevron will utilize an existing frac pond in section 19-T26S-R33E for fresh water.
- A temporary 10" expanding pipe transfer line will run approx. 2.5 miles from Section 19-T26S-R33E to Section 14-T26S-R32E. Transfer lines will be laid along existing lease roads.

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723

SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

- Fresh water line will run parallel to road on north and will stay within 10' of access road.
- A ROW will be applied for through the BLM.

Construction Material

- Caliche will be used to construct well pad and roads. Material will be purchased from the nearest federal, state, or private permitted pit.
- The proposed source of construction material will be located and purchased by construction contractor.
 - Payment shall be made by contractor prior to any removal of federal minerals material by contacting agent at (575) 234-5972.
 - Notification shall be given to BLM at (575) 234-5909 at least 3 working days prior to commencing construction of access road and/or well pad.

Methods for Handling Waste

- Drilling fluids and produced oil and water from the well during drilling and completion operations will be stored safely and disposed of properly in an NMOCD approved disposal facility.
- Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around the well site will be collected for disposal.
- Human waste and grey water will be properly contained and disposed of properly at a state approved disposal facility.
- After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a state approved disposal facility.
- The well will be drilled utilizing a closed loop system. Drill cutting will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

Ancillary Facilities

- Ancillary Facilities will not be required for this proposed project.

Well Site Layout

- Surveyor Plat (Exhibit 6a)
 - Usable surface well pad dimensions are 370' X 330'
 - Interior well pad dimensions from point of entry (well head) are N-125', S-205', E-125', W-245'. The length to the west includes 25' spacing between four proposed drills on this multi-well pad.

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723

SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

- Total disturbance area needed for construction activities of well pad will be 2.80 acres.
 - Topsoil placement is on the north.
 - Cut and fill: will be minimal.
- Rig Layout (Exhibit 6b)
 - The proposed site layout plat is attached showing the Nabors Rig orientation and equipment location.

Plans for Surface Reclamation

Reclamation Objectives

- The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat and forage loss, visual impact, and weed infestation, during the life of the well or facilities.
- The long-term objective of final reclamation is to return the land to a condition similar to what existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.
- The BLM will be notified at least 3 days prior to commencement of any reclamation procedures.
- If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on the location has been completed or plugged. We will gain written permission from the BLM if more time is needed.
- Reclamation will be performed by using the following procedures:

Interim Reclamation Procedures

- Within 6 months, Chevron will contact BLM Surface Management Specialists to devise the best strategies to reduce the size of the location. Current plans for interim reclamation will consist of reclaiming the pad to approximately 2 acres.
- Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production. A plan will be submitted showing where interim reclamation will be completed in order to allow for safe operations, protection of the environment outside of drilled well, and following best management practices found in the BLM "Gold Book".
- In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723

SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

- Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used.
- Proper erosion control methods will be used on the area to control erosion, runoff and siltation of the surrounding area.
- The interim reclamation will be monitored periodically to ensure that vegetation has reestablished

Final Reclamation (well pad, buried pipelines, and power lines, etc.)

- Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.
- All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends in distinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.
- After all the disturbed areas have been properly prepared; the areas will be seeded with the proper BLM seed mixture, free of noxious weeds.
- Proper erosion control methods will be used on the entire area to control erosion, runoff and siltation of the surrounding area.

Surface Ownership

- Bureau of Land Management
- All access roads are located on Federal Lands.
- Surface Tenant – Oliver Kiehne

Other Information

- On-site performed by BLM NRS: Trishia Bad Bear on November 4, 2014
- Cultural report attached: Letter attached.
- Erosion / Drainage: Drainage control system shall be constructed on the entire length of road by the use of any of the following: ditches, side hill out-sloping and in-sloping, lead-off ditches, culvert installation, or low water crossings.

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723

SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

- Exclosure fencing will be installed around open cellar to prevent livestock or large wildlife from being trapped after installation. Fencing will remain in place while no activity is present and until backfilling takes place.
- Terrain: Landscape is flat
- Soil: Sandy loam
- Vegetation: Vegetation present in surrounding area includes mesquite, shrubs, and grass (needle-grass, burro grass, dropseed).
- Wildlife: No wildlife observed, but it is likely that deer, rabbits, coyotes, and rodents pass through the area.
- Surface Water: No surface water concerns.
- Cave Karst: Low Karst area with no caves or visual signs of caves found.
- Watershed Protection: The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- Water wells: No known water wells within the 1- mile radius.
- Residences and Buildings: No dwellings within the immediate vicinity of the proposed location.
- Well Signs: Well signs will be in compliance per federal and state requirements and specifications.

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723
SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

Chevron Representative

Primary point of contact:

Jennifer Van Curen

Jennifer.VanCuren@arcadis-us.com

M- 432-270-8753

Chevron Functional Contacts

Project Manager James Ward 1400 Smith Street, 40055 Houston, TX 77002 Office: 713-372-1748 JWGB@chevron.com	Drilling Engineer Vicente Ruiz 1400 Smith Street, 43104 Houston, TX 77002 Office: +1 (713) 372-6181 vruiz@chevron.com
Surface Land Representative Kevin Dickerson 15 Smith Road, 5103 Claydesta Plaza Midland, TX 79705 Office: +1 432-687-7104 Cell: +1 432-250-4489 Kevin.Dickerson@chevron.com	Facility Engineer Nick Wann 15 Smith Road, 6220 Claydesta Plaza Midland, TX 79705 Office: +1 504-224-0597 NWann@chevron.com
Geologist Patrick Taha 1400 Smith Street, 40034 Houston, TX 77002 Office: +1 713-372-1543 PatrickTaha@chevron.com	Execution Technical Team Lead Clayton Williams 1400 Smith Street, 40029 Houston, TX 77002 Office: 713-372-0978 clay.williams@chevron.com
Regulatory Specialist Cindy Herrera-Murillo 1616 W Bender Blvd, 134 Hobbs, NM 88240 Office: +1 575-263-0431 CHerreraMurillo@chevron.com	Land Robert Morrison 1400 Smith Street. 45010 Houston, TX 77002 Office: 713-372-6707 UAMZ@Chevron.com

CHEVRON U.S.A. Inc
SD WE 14 FEDERAL P7 #3H
NMNM119723
SHL – SEC. 14, T26S, R32E
215' FSL & 698' FEL

BHL – SEC. 14, T26S, R32E
180' FNL & 990' FEL

EXHIBITS:

Exhibit 1 -- Existing Roads (APD map)

Exhibit 2 -- Survey Plat: New or Reconstructed Roads Map: if road is outside 600' x 600'.

Exhibit 3 -- 1-mile Radius Map

Exhibit 4 -- Location of Existing and/or Proposed Production Facilities (Tank Battery)

Exhibit 5 -- Survey Plat: Infrastructure: roads, pipelines, power lines, frac pond

Exhibit 6 -- Rig Layout: Well Site Layout Map / Diagram

C-102 doesn't need an exhibit number – nothing should refer back to the state form.

Need Exhibit 1, 3, 4 - need location name added to battery layout, & 5 - this will include the facility pad, production and power.

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Executed this 15th day of May, 2015

Name: 


James Ward - Project Manager

Address: 1400 Smith Street, 40050
Houston, TX 77002

Office 713-372-1748

E-mail: jwgb@chevron.com

Exhibit 4



ISSUED FOR CONSTRUCTION - JACSON 07/12/15		REVISIONS		IFC ISSUED FOR CONSTRUCTION		Chevron U.S.A. Inc.		HOBBS FMT - SALADO DRAW SEC. 19 CTB DELAWARE BASIN	
△	△	△	△	△	△	△	△	△	△
△	△	△	△	△	△	△	△	△	△
△	△	△	△	△	△	△	△	△	△
PLOT PLAN		PLOT PLAN		PLOT PLAN		PLOT PLAN		PLOT PLAN	
SLDRW-SDW-19CTB-MCB-STB-FDN-2005-1		SLDRW-SDW-19CTB-MCB-STB-FDN-2005-1		SLDRW-SDW-19CTB-MCB-STB-FDN-2005-1		SLDRW-SDW-19CTB-MCB-STB-FDN-2005-1		SLDRW-SDW-19CTB-MCB-STB-FDN-2005-1	
API		LEASE		LEASE		LEASE		LEASE	




Exhibit 6

NOTE:

Please be advised, that while reasonable efforts are made to locate and verify pipelines and anomalies using our standard pipeline locating equipment, it is impossible to be 100% effective. As such, we advise using caution when performing work as there is a possibility that pipelines and other hazards, such as fiber optic cables, PVC pipelines, etc. may exist undetected on site.

NOTE:

Many states maintain information centers that establish links between those who dig (excavators) and those who own and operate underground facilities (operators). It is advisable and in most states, law, for the contractor to contact the center for assistance in locating and marking underground utilities. For guidance: New Mexico One Call - www.nmonecall.org

DISCLAIMER: At this time, C.H. Fenstermaker & Associates, LLC has not performed nor was asked to perform any type of engineering, hydrological modeling, flood plain, or "No Rise" certification analyses, including but not limited to determining whether the project will impact flood hazards in connection with federal/FEMA, state, and/or local laws, ordinances and regulations. Accordingly, Fenstermaker makes no warranty or representation of any kind as to the foregoing issues, and persons or entities using this information shall do so at their own risk.

SD WE 14 FED P7 3H WELL	SD WE 23 FED P7 3H WELL	SD WE 14 FED P7 4H WELL	SD WE 23 FED P7 4H WELL
X= 715,223 NAD 27	X= 715,248 NAD 27	X= 715,273 NAD 27	X= 715,298 NAD 27
Y= 377,548	Y= 377,548	Y= 377,548	Y= 377,549
LAT. 32.036092	LAT. 32.036092	LAT. 32.036092	LAT. 32.036092
LONG 103.638790	LONG 103.638789	LONG 103.638798	LONG 103.638548
X= 756,410 NAD83	X= 756,435 NAD83	X= 756,460 NAD83	X= 756,485 NAD83
Y= 377,605	Y= 377,605	Y= 377,605	Y= 377,606
LAT. 32.036217	LAT. 32.036217	LAT. 32.036217	LAT. 32.036217
LONG 103.639259	LONG 103.639178	LONG 103.639098	LONG 103.639017
ELEVATION +3165 NAVD 88	ELEVATION +3165 NAVD 88	ELEVATION +3165 NAVD 88	ELEVATION +3165 NAVD 88


R 32 E

Sec. 14

Bureau of Land Management

Future Interim
Reclamation Area


T
26
S



FOR THE EXCLUSIVE USE OF
CHEVRON U.S.A. INC.
I, WM. J. Daniel III, Registered Professional
Land Surveyor, do hereby state this plat is true
and correct to the best of my knowledge.

Sec. 23

Bureau of Land Management



WM. J. Daniel III
Registration No. 15078

DEVELOPMENT PAD DETAIL

SCALE: 1"=100'
100' 0 50' 100'

CHEVRON U.S.A. INC.
PROPOSED DEVELOPMENT PAD
SD WE 14 & 23 FED P7 3H & 4H WELLS
SECTION 14, T26S-R32E
LEA COUNTY, NEW MEXICO



135 Regency Sq. Lafayette, LA 70508
Ph. 337-237-2200 Fax. 337-232-3299
www.fenstermaker.com

DRAWN BY: VHV

REVISIONS

PROJ. MGR.: VHV

No.

DATE:

REVISED BY:

DATE: 04/14/2015

No.

DATE:

REVISED BY:

FILENAME: T:\2014\214673\IDWG\SD WE 14 & 23 Fed P7 3H-4H_PadDetail.dwg