

# COG Operating, LLC - Square Bill Federal Com 21H

## 1. Geologic Formations

TVD of target	12,700' EOL	Pilot hole depth	NA
MD at TD:	19,907'	Deepest expected fresh water:	207'

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Rustler	1143	Water	
Top of Salt	1518	Salt	
Base of Salt	5151	Salt	
Lamar	5362	Salt Water	
Bell Canyon	5397	Salt Water	
Cherry Canyon	6382	Oil/Gas	
Brushy Canyon	7948	Oil/Gas	
Bone Spring Lime	9240	Oil/Gas	
U. Avalon Shale	9293	Oil/Gas	
L. Avalon Shale	9569	Oil/Gas	
1st Bone Spring Sand	10385	Oil/Gas	
2nd Bone Spring Sand	10925	Oil/Gas	
3rd Bone Spring Sand	12055	Oil/Gas	
Wolfcamp	12485	Target Oil/Gas	

## 2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	1170	10.75"	45.5	N80	BTC	4.61	1.17	19.54
9.875"	0	12080	7.875"	29.7	P110	BTC	1.26	1.15	3.03
6.75"	0	11580	5.5"	23	P110	BTC	2.00	2.11	3.19
6.75"	11580	19,907	5"	18	P110	BTC	2.00	2.11	3.19
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

**COG Operating, LLC - Square Bill Federal Com 21H**

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary?	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

## 3. Cementing Program

Casing	# Sk	Wt. lb/ gal	Yld ft3/ sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	180	13.5	1.75	9	12	Lead: Class C + 4% Gel + 1% CaCl <sub>2</sub>
	250	14.8	1.34	6.34	8	Tail: Class C + 2% CaCl <sub>2</sub>
Inter.	990	10.3	3.6	21.48	16	Tuned Light Blend
	250	16.4	1.08	4.32	8	Tail: Class H
Prod	130	11.9	2.5	19	72	Lead: 50:50:10 H Blend
	940	14.4	1.24	5.7	19	Tail: 50:50:2 Class H Blend

Volumes Subject to Observed Hole Conditions and/or Fluid Caliper Results

Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
Surface	0'	50%
1 <sup>st</sup> Intermediate	0'	50%
Production	11,580'	35% OH in Lateral (KOP to EOL)

## 4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	---

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	x	Tested to:
9-7/8"	13-5/8"	3M	Annular	x	3000 psi
			Blind Ram		3M
			Pipe Ram		
			Double Ram		
			Other*		
6-3/4"	13-5/8"	5M	Annular	x	50% testing pressure
			Blind Ram	x	5M
			Pipe Ram	x	
			Double Ram		
			Other*		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

## 5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. Shoe	FW Gel	8.6 - 8.8	28-34	N/C
Surf csg	9-5/8" Int shoe	Brine Diesel Emulsion	8.4 - 9	28-34	N/C
7-5/8" Int shoe	Lateral TD	OBM	9.6 - 11	35-45	<20

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

## 6. Logging and Testing Procedures

## Logging, Coring and Testing.

Y	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
Y	No Logs are planned based on well control or offset log information.
N	Drill stem test? If yes, explain.
N	Coring? If yes, explain.

Additional logs planned		Interval
N	Resistivity	Pilot Hole TD to ICP
N	Density	Pilot Hole TD to ICP
Y	CBL	Production casing (If cement not circulated to surface)
Y	Mud log	Intermediate shoe to TD
N	PEX	

## COG Operating, LLC - Square Bill Federal Com 21H

### 7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	7265 psi at 12700' TVD
Abnormal Temperature	NO 180 Deg. F.

No abnormal pressure or temperature conditions are anticipated. Sufficient mud materials to maintain mud properties and weight increase requirements will be kept on location at all times.

Sufficient supplies of Paper/LCM for periodic sweeps to control seepage and losses will be maintained on location.

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N H<sub>2</sub>S is present


Y H<sub>2</sub>S Plan attached

### 8. Other Facets of Operation


Y	Is it a walking operation?
N	Is casing pre-set?

x	H <sub>2</sub> S Plan.
x	BOP & Choke Schematics.
x	Directional Plan


# 3M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)




# 5M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



# 3,000 psi BOP Schematic





# 5,000 psi BOP Schematic





Midwest Hose  
& Specialty, Inc.

### Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	Hobbs	Hose Assembly Type	Rotary/Vibrator
MWH Sales Representative	Ryan Rynolds	Certification	API 7K/FSL Level 2
Date Assembled	11/19/2015	Hose Grade	D
Location Assembled	OKC	Hose Working Pressure	5000
Sales Order #	271739	Hose Lot # and Date Code	11834 11/14
Customer Purchase Order #	302337	Hose I.D. (Inches)	3.5"
Assembly Serial # (Pick Ticket #)	326000	Hose O.D. (Inches)	4.89"
Hose Assembly Length	25'	Aarmor (yes/no)	No
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.5X64WB	Stem (Part and Revision #)	R3.5X64WB
Stem (Heat #)	A144783	Stem (Heat #)	A144783
Ferrule (Part and Revision #)	RF3.5	Ferrule (Part and Revision #)	RF3.5
Ferrule (Heat #)	J1628	Ferrule (Heat #)	J1628
Connection . Flange Hammer Union Part	4-1/16 5000	Connection (Part #)	4-1/16 5000
Connection (Heat #)	14032501	Connection (Heat #)	1404H321
Nut (Part #)	N/A	Nut (Part #)	N/A
Nut (Heat #)	N/A	Nut (Heat #)	N/A
Dies Used	5.49"	Dies Used	5.49"
Hydrostatic Test Requirements			
Test Pressure (psi)	10,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	11 1/2		
Date Tested	Tested By	Approved By	
11/19/2015			



Midwest Hose  
& Specialty, Inc.

### Certificate of Conformity

Customer: **Hobbs**

Customer P.O.# **302337**

Sales Order # **271739**

Date Assembled: **11/19/2015**

### Specifications

Hose Assembly Type: **Rotary/Vibrator**

Assembly Serial # **326000**

Hose Lot # and Date Code **11834 11/14**

Hose Working Pressure (psi) **5000**

Test Pressure (psi) **10000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

**Midwest Hose & Specialty, Inc.**

**3312 S I-35 Service Rd**

**Oklahoma City, OK 73129**

Comments:

Approved By

*Kim Thomas*

Date

**11/19/2015**



Midwest Hose  
& Specialty, Inc.

## Internal Hydrostatic Test Graph

November 19, 2015

Customer: Hobbs

Pick Ticket #: 326000

### Hose Specifications

#### Hose Type

D

#### I.D.

3.5"

#### Working Pressure

5000 PSI

#### Length

25'

#### O.D.

4.89"

#### Burst Pressure

Standard Safety Multiplier Applies

### Verification

#### Type of Fitting

4 1/16 5K

#### Die Size

5.49"

#### Hose Serial #

11834

#### Coupling Method


Swage

#### Final O.D.

5.50"

#### Hose Assembly Serial #

326000



#### Test Pressure

10000 PSI

#### Time Held at Test Pressure

11 2/4 Minutes

#### Actual Burst Pressure

#### Peak Pressure

10473 PSI

**Comments:** Hose assembly pressure tested with water at ambient temperature.

**Tested By:** James Hawkins

**Approved By:** Kim Thomas

X \_\_\_\_\_

X \_\_\_\_\_

## Hose Assembly & Test Report

General Information		Hose Specifications	
Customer	Hobbs	Hose Assembly Type	chase + 2 1/2"
Date Assembled	6-26-14	Certification	AP7K
Location Assembled	OKC	Hose Grade	D
Sales Order #	216297	Hose Working Pressure	5,000
Customer Purchase Order #	237512	Hose Lot #	8309
Hose Assembly Serial #	260212	Hose Date Code	04/12
Pick Ticket Line Item	0010	Hose I.D. (Inches)	3.5 inches
Hose Assembly Length (Feet and Inches)	50 feet	Hose O.D. (Inches)	5.45
Contact Information Phone #		Armor (yes/no)	yes
Fittings			
End A		End B	
Stern (Part and Revision #)	R3.5 x L4 WD	Stern (Part and Revision #)	R3.5 x L4 WD
Stern (Heat #)	13114050225	Stern (Heat #)	13114050225
Stern (Rockwell Hardness HRB #)	—	Stern (Rockwell Hardness HRB #)	—
Ferrule (Part and Revision #)	RF3.5	Ferrule (Part and Revision #)	RF3.5
Ferrule (Heat #)	126151	Ferrule (Heat #)	372114
Ferrule (Rockwell Hardness HRB #)	—	Ferrule (Rockwell Hardness HRB #)	—
Connection (Part #)	4 1/16 SK	Connection (Part #)	4 1/16 SK
Connection (Heat #)	U3360	Connection (Heat #)	U3360
Connection (Brinell Hardness HB #)	—	Connection (Brinell Hardness HB #)	—
Stress Relief #	17614	Stress Relief #	17614
Welding #	MKR	Welding #	MKR
X-ray #	—	X-ray #	—
Assembly Information			
End A		End B	
Skive O.D. (Inches)	5.04	Skive O.D. (Inches)	4.92
Swager Dies (1st pass)	5.12	Swager Dies (1st pass)	5.53
Swager Dies (2nd pass)	—	Swager Dies (2nd pass)	—
Final Swage O.D. (Inches)	5.14	Final Swage O.D. (Inches)	4.98
Compression % (See Crimp Calculator)	94%	Compression % (See Crimp Calculator)	22%
Swaged By		Charles Ash	
Hydrostatic Test Requirements			
Test Pressure (psi)	10,000	Hold Time (minutes)	13 1/4
Tested By	Charles Ash	Date Tested	6-26-14
This is to certify that the above Hose Assembly has been satisfactorily tested in accordance with MHSI procedure 8.2.4.2			
Final Verification			
Inspected	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Hammer Unions	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Witnessed	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Safety Clamps	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Third Party Witness	Customer or Third Party Witnessed By:		