

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1090 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

**HOBBS OCD**

**OCT 30 2017**

**RECEIVED**

**GAS CAPTURE PLAN**

Date: 05/23/2017

☒ Original Operator & OGRID No.: EOG Resources, Inc. 7377  
☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomplete to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

**Well(s)/Production Facility – Name of facility**

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (U/L STR)	Footages	Expected MCF/D	Flared or Vented	Comments
Barlow 34 Fed Com 704H	30-025-	4-34-26S-33E	500' TSI & 1615' TWT	~ 3000	None Planned	APD Submission

**Gathering System and Pipeline Notification**

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to **Regency Field Services** and will be connected to **EOG Resources** low/high pressure gathering system located in Lea County, New Mexico. It will require **N/A** of pipeline to connect the facility to low/high pressure gathering system. **EOG Resources** provides (periodically) to **Regency Field Services** a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, **EOG Resources** and **Regency Field Services** have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at **Regency Field Services** Processing Plant located in Sec. **33**, Twn. **24S**, Rng. **37E**, **Lea** County, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

**Flowback Strategy**

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on **Regency Field Services** system at that time. Based on current information, it is **EOG Resources'** belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

**Alternatives to Reduce Flaring**

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation -- On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas -- On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGH Removal -- On lease

BLM APD Waste Minimization Plan Checklist

Well Name: Barlow 34 Fed Com 704H (APD)

Well Location: 300' FSL & 1615' FWL, SENW 34-26S-33E, Lea County

Production Facility Name: Barlow 34 Fed Com Central Tank Battery

Production Facility Location: CTB Located in NW/ 4 of section 19. Gas is gathered at CTB and piped through EOG gathering system to Regency Field Services gas pipeline tie-in.

Anticipated Well Completion Date: Estimated 04/01/2018

- Initial Production Volumes: Estimated ~3000 – 7000 MCFPD initial rate.

In accordance with 3162.3-1(j)(3), one or more third-party, midstream processors have been notified of our development plan. Information provided includes anticipated completion dates and gas production rates.

NMOCD gas capture plan attached.