

Submit 1 Copy To Appropriate District Office

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
Revised July 18, 2013

District I - (575) 393-6161
1625 N. French Dr., Hobbs, NM 88240
District II - (575) 748-1283
811 S. First St., Artesia, NM 88201
District III - (505) 334-6178
1000 Rio Brazos Rd., Aztec, NM 87410
District IV - (505) 476-3460
1220 S. St. Francis Dr., Santa Fe, NM 87505

HOBBS OGD

SEP 27 2018

CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-041-20865
5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No. V-2096
7. Lease Name or Unit Agreement Name Fox C State
8. Well Number 4
9. OGRID Number 025575
10. Pool name or Wildcat Allison; Upper Penn

SUNDRY RECORDS AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

1. Type of Well: Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/>
2. Name of Operator EOG Y Resources, Inc.
3. Address of Operator 104 South Fourth Street, Artesia, NM 88210
4. Well Location Unit Letter <u>A</u> : <u>660</u> feet from the <u>North</u> line and <u>510</u> feet from the <u>East</u> line Section <u>36</u> Township <u>8S</u> Range <u>36E</u> NMPM <u>Roosevelt</u> County
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 4060' GR

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:	SUBSEQUENT REPORT OF:
PERFORM REMEDIAL WORK <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>
DOWNHOLE COMMINGLE <input type="checkbox"/>	CASING/CEMENT JOB <input type="checkbox"/>
CLOSED-LOOP SYSTEM <input type="checkbox"/>	OTHER: <input type="checkbox"/>
OTHER: <input type="checkbox"/>	

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

**See Attached
Conditions of Approval**

EOG Y Resources, Inc. plans to plug and abandon this well as follows:

1. MIRU all safety equipment as needed. POOH with production equipment.
2. RIH with GR/JB to 9625'.
3. Set a CIBP at 9600' with 35' cement on top. Pressure test casing. This will place a plug over open perforations and Cisco top.
4. Tag TOC and load hole with plugging mud.
5. Spot a 25 sx Class "H" cement plug from 8690'-8920'. This will place a plug across Wolfcamp top.
6. Spot a 25 sx Class "H" cement plug from 7560'-7790'. This will place a plug across Abo top.
7. Spot a 25 sx Class "C" cement plug from 5340'-5600'. This will place a plug across Glorieta top.
8. Spot a 25 sx Class "C" cement plug from 3990'-4250'. This will place a plug across the 8-5/8" casing shoe and San Andres top.
9. Perforate at 400'. Establish circulation.
10. Squeeze a 105 sx Class "C" inside/outside cement plug from 400' up to surface. This will place a plug across 13-3/8" casing shoe and to surface.
11. Cut off wellhead. Install Dry Hole marker and clean location as per regulated.

Wellbore schematics attached

SPOT 25 SX CMT @ 2400' (T. SALT)

Spud Date:

Rig Release Date:

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Tina Huerta TITLE Regulatory Specialist DATE September 25, 2018

Type or print name Tina Huerta E-mail address: tina_huerta@eogresources.com PHONE: 575-748-4168

For State Use Only
APPROVED BY: Mark Whitaker TITLE P.E.S. DATE 09/27/2018

Conditions of Approval (if any):

WELL NAME: Fox C State #4 FIELD: _____
LOCATION: 660' FNL & 510' FEL Sec.36-8S-36E
GL: 4,060' ZERO: _____ KB: _____
COMMENTS: API No.: 30-041-20865


CASING PROGRAM

13 3/8" 72#	341'
8 5/8" 32# J-55	4,193'
5 1/2" 20# N-80	9,800'

Before

TOPS

San Andres	4,110'
Glorieta	5,550'
Abo	7,740'
Wolfcamp	8,870'
Cisco	9,648'



Not to Scale
9/24/18
JDE

WELL NAME: Fox C State #4 FIELD: _____


LOCATION: 660' FNL & 510' FEL Sec.36-8S-36E

GL: 4,060' ZERO: _____ KB: _____

COMMENTS: API No.: 30-041-20865

CASING PROGRAM

13 3/8" 72#	341'
8 5/8" 32# J-55	4,193'
5 1/2" 20# N-80	9,800'



GENERAL CONDITIONS OF APPROVAL:

- 1) Insure all bradenheads have been exposed, identified, and valves are operational prior to rigging up on well.
- 2) Contact the appropriate NMOCD District Office no later than 24 hours prior to moving in and rigging up.
- 3) A copy of the approved C103 intent to P&A should be distributed to the onsite company and plugging representatives. Approved procedures are good for a period of one year from approved date, unless otherwise specified on the C103 intent. Approvals past this date will require the submission and approval of a new C103 intent.
- 4) A company representative is required to be present to witness all operations including setting CIBP's, circulation of mud laden fluids, perforating, squeezing or spotting cement plugs, tags, or any other operations approved on the C103 intent to P&A. Company representative should contact the NMOCD and report all operations.
- 5) Any changes that may be required during plugging operations should be approved by the NMOCD before proceeding.
- 6) A closed loop system is to be used for all plugging operations. Contents of the steel pits to be hauled to a NMOCD permitted disposal facility.
- 7) Mud laden fluids must be placed between all cement plugs mixed at 25 sacks of salt gel per 100 barrels of brine.
- 8) All cement plugs will be 100' or 25 sacks cement, whichever is greater. Class 'C' cement will be used above 7500' and Class 'H' below 7500'.