

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTNMOCD
HobbsFORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.***SUBMIT IN TRIPLICATE - Other instructions on page****HOBBS OCD**
OCT 17 2019
RECEIVED

5. Lease Serial No.
NMNM86168
6. If Indian, Allottee or Tribe Name
7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

Well Name and No.
SEVERUS 31-5 FEDERAL COM 10H

2. Name of Operator
XTO ENERGY INCORPORATED

Contact: CASSIE EVANS
E-Mail: cassie_evans@xtoenergy.com

9. API Well No.
30-025-46375-00-X1

- 3a. Address
6401 HOLIDAY HILL ROAD BLDG 5
MIDLAND, TX 79707

- 3b. Phone No. (include area code)
Ph: 432-218-3671

10. Field and Pool or Exploratory Area
WILDCAT

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec 30 T20S R34E SWSE 80FSL 2262FEL
32.537094 N Lat, 103.598358 W Lon

11. County or Parish, State
LEA COUNTY, NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Change to Original A
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	PD

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

XTO Permian Operating, LLC respectfully requests the following changes to the original APD:

1. Change BHL fr/2401?FNL & 1650?FWL to 2558?FNL & 1650?FWL
2. Update Casing/Cement/Mud Program from a 3-String Design to a 4-String Design.

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #485323 verified by the BLM Well Information System
For XTO ENERGY INCORPORATED, sent to the Hobbs
Committed to AFMSS for processing by JENNIFER SANCHEZ on 09/26/2019 (19JAS0094SE)

Name (Printed/Typed) CASSIE EVANS	Title REGULATORY ANALYST
Signature (Electronic Submission)	Date 09/26/2019

APPROVED

THIS SPACE FOR FEDERAL OR STATE OFFICIAL USE

Approved By _____ Title **BUREAU OF LAND MANAGEMENT** Date _____
ROSWELL FIELD OFFICE

Office _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2) **** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ****

Revisions to Operator-Submitted EC Data for Sundry Notice #485323

	Operator Submitted	BLM Revised (AFMSS)
Sundry Type:	APDCH NOI	APDCH NOI
Lease:	NMNM86168	NMNM86168
Agreement:		
Operator:	XTO ENERGY INC 6401 HOLIDAY HILL RD #5 MIDLAND, TX 79707 Ph: 432-218-3671	XTO ENERGY INCORPORATED 6401 HOLIDAY HILL ROAD BLDG 5 MIDLAND, TX 79707 Ph: 432.683 2277
Admin Contact:	CASSIE EVANS REGULATORY ANALYST E-Mail: cassie_evans@xtoenergy.com Ph: 432-218-3671	CASSIE EVANS REGULATORY ANALYST E-Mail: cassie_evans@xtoenergy.com Ph: 432-218-3671
Tech Contact:	CASSIE EVANS REGULATORY ANALYST E-Mail: cassie_evans@xtoenergy.com Ph: 432-218-3671	CASSIE EVANS REGULATORY ANALYST E-Mail: cassie_evans@xtoenergy.com Ph: 432-218-3671
Location:		
State:	NM	NM
County:	LEA	LEA
Field/Pool:	WILDCAT BONE SPRING	WILDCAT
Well/Facility:	SEVERUS 31-5 Sec 30 T20S R34E Mer NMP SWSE 80FSL 2262FEL 32.537095 N Lat, 103.598359 W Lon	SEVERUS 31-5 FEDERAL COM 10H Sec 30 T20S R34E SWSE 80FSL 2262FEL 32.537094 N Lat, 103.598358 W Lon

DRILLING PLAN: BLM COMPLIANCE
(Supplement to BLM 3160-3)

XTO Energy Inc.
Severus 31-5 Fed Com 10H
Projected TD: 18689' MD / 10597' TVD
SHL: 80' FSL & 2262' FEL , Section 30, T20S, R34E
BHL: 2558' FNL & 1650' FEL , Section 5, T21S, R33E
Eddy County, NM

1. Geologic Name of Surface Formation

A. Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

Formation	Well Depth (TVD)	Water/Oil/Gas
Rustler	1561'	Water
Top of Salt	1912'	Water
Base of Salt	3157'	Water
Capitan Reef	3725'	Water
Delaware	5633'	Water
Bone Spring	8670'	Water/Oil/Gas
1st Bone Spring Ss	9664'	Water/Oil/Gas
2nd Bone Spring Ss	10196'	Water/Oil/Gas
Target/Land Curve	10597'	Water/Oil/Gas

*** Hydrocarbons @ Brushy Canyon

*** Groundwater depth 40' (per NM State Engineers Office).

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 16 inch casing @ 1670' (242' above the salt) and circulating cement back to surface. The salt will be isolated by setting 11-3/4 inch casing at 3180' and circulating cement to surface. 8-5/8 inch intermediate casing will be set at 5733'. A 7-7/8 inch curve and lateral hole will be drilled to TD, where 5-1/2 inch casing will be set and cemented back up to the 8-5/8 inch casing shoe.

3. Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
20"	0' - 1670'	16"	75	STC	J-55	New	2.76	1.83	5.67
14-3/4"	0' - 3180'	11-3/4"	47	STC	J-55	New	1.92	2.07	4.27
10-5/8"	0' - 5733'	8-5/8"	32	STC	J-55	New	1.41	1.56	2.03
7-7/8"	0' - 18689'	5-1/2"	17	LTC	P-110	New	1.33	2.16	2.36

- XTO requests to utilize centralizers only in the curve above the KOP and only a minimum of one every other joint.
- 16" Collapse analyzed using 75% evacuation. Casing to be filled while running.
- 11-3/4" & 8-5/8" Collapse analyzed using 50% evacuation based on regional experience.
- 5-1/2" tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35
- Test on 2M Annular & Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less

WELLHEAD:

Temporary Wellhead

- 16" SOW bottom x 16-3/4" 3M top flange.

Permanent Wellhead - GE RSH Multibowl System

A. Starting Head: 13-5/8" 5M top flange x 11-3/4" SOW bottom

B. Tubing Head: 13-5/8" 5M bottom flange x 7" 10M top flange

- Wellhead will be installed by manufacturer's representatives.
- Manufacturer will monitor welding process to ensure appropriate temperature of seal.
- Operator will test the 8-5/8" casing per BLM Onshore Order 2
- Wellhead manufacturer representative will not be present for BOP test plug installation

4. Cement Program

Surface Casing: 16", 75 New J-55, STC casing to be set at +/- 1670'

Lead: 1320 sxs Class C + Salt (mixed at 12.8 ppg, 1.88 ft³/sx, 11.45 gal/sx water)

Tail: 190 sxs Class C (mixed at 14.8 ppg, 1.33 ft³/sx, 6.39 gal/sx water)

Compressives: 12-hr = 1000 psi 24 hr = 2000 psi

1st Intermediate Casing: 11-3/4", 47 New J-55, STC casing to be set at +/- 3180'

Lead: 1320 sxs Class C + Poz + Fluid Loss FL-25 + Retarder R-3 + Salt + Bentonite (mixed at 12.8 ppg, 1.88 ft³/sx, 9.93 gal/sx water)

Tail: 190 sxs Class C + Retarder R-3 (mixed at 14.8 ppg, 1.33 ft³/sx, 6.30 gal/sx water)

Compressives: 12-hr = 1000 psi 24 hr = 2000 psi

2nd Intermediate Casing: 8-5/8", 32 New J-55, STC casing to be set at +/- 5733'

ECP/DV Tool to be set at 3280'

1st Stage

Lead 1: 680 sxs Class C + Glass Beads + IntegraSeal + Bonding Agent BA-90 + Foam Preventer FP-6L + Sodium Metasilicate A-2 + Anti Settling ASA-301 + Retarder R-21 + Extender LW-5E (mixed at 9.5 ppg, 3.8 ft³/sx, 18.7 gal/sx water)

Lead 2: 300 sxs Class C + Poz + IntegraSeal Cello + IntegraSeal Kol + Salt + Sodium Metasilicate A-2 + Retarder R-21 + Fluid Loss FL-52 + Bentonite (mixed at 11.5 ppg, 2.68 ft³/sx, 15.46 gal/sx water)

Tail: 150 sxs Class C + Foam Preventer FP-6L + Retarder R-21 + Fluid Loss FL-52 (mixed at 14.8 ppg, 1.33 ft³/sx, 6.39 gal/sx water)

Compressives: 12-hr = 1000 psi 24 hr = 2000 psi

2nd Stage

Lead: 620 sxs Class C + Poz + IntegraSeal Cello + IntegraSeal Kol + Salt + Retarder R-3 + Sodium Metasilicate A-2 + Fluid Loss FL-52 + Bentonite (mixed at 12.8 ppg, 1.88 ft³/sx, 9.61 gal/sx water)

Tail: 150 sxs Class C + Fluid Loss FL-52 (mixed at 14.8 ppg, 1.33 ft³/sx, 6.39 gal/sx water)

Compressives: 12-hr = 1000 psi 24 hr = 2000 psi

Production Casing: 5-1/2", 17 New P-110, LTC casing to be set at +/- 18689'

Lead 1: 10 sxs Class C + Glass Beads + IntegraSeal Kol + Bonding Agent BA-90 + Foam Preventer FP-6L + Sodium Metasilicate A-2 + Anti Settling ASA-301 + Retarder R-21 + Bentonite (mixed at 9.5 ppg, 3.8 ft³/sx, 18.7 gal/sx water)

Lead 2: 350 sxs Class C + Poz + IntegraSeal Cello + IntegraSeal Kol + Foam Preventer FP-6L + Salt + Sodium Metasilicate A-2 + Bentonite (mixed at 11.5 ppg, 2.72 ft³/sx, 15.9 gal/sx water)

Tail: 1280 sxs Class C + IntegraSeal Kol + Foam Preventer FP-6L + Salt + Fluid Loss FL-52 + Dispersant CS-32 + Retarder R-21 + Bonding Agent BA-90 (mixed at 13.2 ppg, 1.61 ft³/sx, 9.36 gal/sx water)

Compressives: 12-hr = 9 psi 24 hr = 1800 psi

5. Pressure Control Equipment

The blow out preventer (BOP) on surface casing/temp. wellhead will consist of a 20" minimum 2M Hydril. MASP should not exceed 954 psi.

Once the permanent WH is installed on the 11-3/4" casing, the blow out preventer equipment (BOP) will consist of a 13-5/8" minimum 5M Hydril and a 13-5/8" minimum 3M 2-Ram BOP. MASP should not exceed ~~2795~~ psi.

All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 50% of the working pressure. When nipping up on the 13-5/8" 3M bradenhead and flange, the BOP test will be limited to 3000 psi. Since a multibowl system will be used, subsequent BOP pressure tests will be performed as necessary based on required testing schedule (i.e., at least every 30 days). All BOP tests will include a low pressure test as per BLM regulations. The 3M BOP diagrams are attached. Blind rams will be functioned tested each trip, pipe rams will be functioned tested each day.

A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer

5m BOP
system will
be used for
multibowl and
tested to 5m
Rating.

does not require anchors.

6. Proposed Mud Circulation System


INTERVAL	Hole Size	Mud Type	MW (ppg)	Viscosity (sec/qt)	Fluid Loss (cc)
0' - 1670'	20"	FW/Native	8.3-9.5	35-50	NC
1670' - 3180'	14-3/4"	Brine	9.5-10.2	30-35	NC
3180' to 5733'	10-5/8"	FW	8.3-9.8	30-32	NC
5733' to 18689'	7-7/8"	FW / Cut Brine / Polymer	8.2-9.3	29-32	NC - 20

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Spud with fresh water/native mud. Drill out from under 16" surface casing with brine solution. A 9.5ppg-10.2ppg brine mud will be used while drilling through the salt formation. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.



GE Oil & Gas



ALL DIMENSIONS ARE APPROXIMATE


This drawing is the property of GE Oil & Gas Pressure Control LP and is considered confidential. Unless otherwise approved in writing, neither it nor its contents may be used, copied, transmitted or reproduced except for the sole purpose of GE Oil & Gas Pressure Control LP.

XTO ENERGY, INC.


11-3/4" x 8-5/8" x 5-1/2" 10M RSH-2 Wellhead
Assembly, With T-EBS-F Tubing Head

DRAWN	VJK	31OCT16
APPRV	KN	31OCT16

FOR REFERENCE ONLY
DRAWING NO. 10012358





SRR & A



Drilling Operations Choke Manifold 2M & 3M Service

2M & 3M Choke Manifold Diagram
XTO





**Drilling Operations
Choke Manifold
5M Service**

**5M Choke Manifold Diagram
XTO**



GATES E & S NORTH AMERICA, INC
DU-TEX
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405


PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: crpe@s@gates.com
WEB: www.gates.com

GRADE D PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	6/8/2014
Customer Ref. :	PENDING	Hose Serial No.:	D-060814-1
Invoice No. :	201709	Created By:	NORMA
Product Description:	FD3.042.0R41/16.5KFLGE/E LE		
End Fitting 1 :	4 1/16 in.5K FLG	End Fitting 2 :	4 1/16 in.5K FLG
Gates Part No. :	4774-6001	Assembly Code :	L33090011S13D-060814-1
Working Pressure :	5,000 PSI	Test Pressure :	7,500 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 7,500 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality:	QUALITY	Technical Supervisor :	PRODUCTION
Date :	6/8/2014	Date :	6/8/2014
Signature :		Signature :	



MOON


NOSE I.D. 2.531" LENGTH 42" END 1 4 1/16 84F 3 4 1/16 84F 3
END 2

GRADE 25000 WORKING PRESSURE 5000 P.S.I.

TEST PRESSURE 7500 P.S.I. ASSEMBLY DATE 6-8-14

TEST DATE 6-8-14 SERIAL 6330960715130-060814-1000

NAME D-1745 CR 250B





XTO ENERGY, INC.

Santa Fe, NM

Sec. 30, 20-S, 34-E

Severus 31-5 Federal Com #10H

Wellbore #1

Plan: Design #2

QES Well Planning Report

22 August, 2019





Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Project	Santa Fe, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Sec. 30, 20-S, 34-E		
Site Position:		Northing:	559,845.40 usft
From: Map		Easting:	726,703.90 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 32' 13.099 N
		Longitude:	103° 35' 51.746 W
		Grid Convergence:	0.40 °

Well	Severus 31-5 Federal Com #10H		
Well Position	+N/-S	0.6 usft	Northing:
	+E/-W	-49.7 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	Ground Level:
			3,698.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	7/22/2019	6.62	60.40	48,119.40000000

Design	Design #2			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	178.46

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,900.0	0.00	0.00	5,900.0	0.0	0.0	0.00	0.00	0.00	0.00	
6,265.3	5.48	354.06	6,264.7	17.4	-1.8	1.50	1.50	0.00	354.06	
9,987.3	5.48	354.06	9,969.8	370.9	-38.6	0.00	0.00	0.00	0.00	
10,936.5	89.47	167.40	10,597.0	-179.1	91.4	10.00	8.85	18.26	173.32	FTP (Shifted) - Sev
11,545.4	89.47	179.58	10,602.6	-782.9	160.3	2.00	0.00	2.00	90.05	
18,689.6	89.47	179.58	10,668.4	-7,926.7	212.9	0.00	0.00	0.00	0.00	PBHL - Severus 31-



Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
Rustler									
1,561.0	0.00	0.00	1,561.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
Salado									
1,912.0	0.00	0.00	1,912.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
Base Salt									
3,157.0	0.00	0.00	3,157.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
Yates									
3,344.0	0.00	0.00	3,344.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
Seven Rivers									
3,576.0	0.00	0.00	3,576.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
Capitan Reef									
3,725.0	0.00	0.00	3,725.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00



Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00
5,100.0	0.00	0.00	5,100.0	0.0	0.0	0.0	0.00	0.00	0.00
5,200.0	0.00	0.00	5,200.0	0.0	0.0	0.0	0.00	0.00	0.00
5,300.0	0.00	0.00	5,300.0	0.0	0.0	0.0	0.00	0.00	0.00
5,400.0	0.00	0.00	5,400.0	0.0	0.0	0.0	0.00	0.00	0.00
5,500.0	0.00	0.00	5,500.0	0.0	0.0	0.0	0.00	0.00	0.00
5,600.0	0.00	0.00	5,600.0	0.0	0.0	0.0	0.00	0.00	0.00
Delaware									
5,633.0	0.00	0.00	5,633.0	0.0	0.0	0.0	0.00	0.00	0.00
5,700.0	0.00	0.00	5,700.0	0.0	0.0	0.0	0.00	0.00	0.00
5,800.0	0.00	0.00	5,800.0	0.0	0.0	0.0	0.00	0.00	0.00
Build 1.5°/100'									
5,900.0	0.00	0.00	5,900.0	0.0	0.0	0.0	0.00	0.00	0.00
6,000.0	1.50	354.06	6,000.0	1.3	-0.1	-1.3	1.50	1.50	0.00
6,100.0	3.00	354.06	6,099.9	5.2	-0.5	-5.2	1.50	1.50	0.00
6,200.0	4.50	354.06	6,199.7	11.7	-1.2	-11.7	1.50	1.50	0.00
EOB @ 5.48° Inc. / 354.06° Azm									
6,265.3	5.48	354.06	6,264.7	17.4	-1.8	-17.4	1.50	1.50	0.00
6,300.0	5.48	354.06	6,299.3	20.7	-2.2	-20.7	0.00	0.00	0.00
6,400.0	5.48	354.06	6,398.8	30.2	-3.1	-30.2	0.00	0.00	0.00
6,500.0	5.48	354.06	6,498.4	39.7	-4.1	-39.7	0.00	0.00	0.00
6,600.0	5.48	354.06	6,597.9	49.1	-5.1	-49.3	0.00	0.00	0.00
6,700.0	5.48	354.06	6,697.5	58.6	-6.1	-58.8	0.00	0.00	0.00
6,800.0	5.48	354.06	6,797.0	68.1	-7.1	-68.3	0.00	0.00	0.00
6,900.0	5.48	354.06	6,896.5	77.6	-8.1	-77.8	0.00	0.00	0.00
7,000.0	5.48	354.06	6,996.1	87.1	-9.1	-87.4	0.00	0.00	0.00
Brushy Canyon									
7,033.1	5.48	354.06	7,029.0	90.3	-9.4	-90.5	0.00	0.00	0.00
7,100.0	5.48	354.06	7,095.6	96.6	-10.1	-96.9	0.00	0.00	0.00
7,200.0	5.48	354.06	7,195.2	106.1	-11.1	-106.4	0.00	0.00	0.00
7,300.0	5.48	354.06	7,294.7	115.6	-12.0	-115.9	0.00	0.00	0.00
7,400.0	5.48	354.06	7,394.3	125.1	-13.0	-125.4	0.00	0.00	0.00
7,500.0	5.48	354.06	7,493.8	134.6	-14.0	-135.0	0.00	0.00	0.00
7,600.0	5.48	354.06	7,593.3	144.1	-15.0	-144.5	0.00	0.00	0.00
7,700.0	5.48	354.06	7,692.9	153.6	-16.0	-154.0	0.00	0.00	0.00
7,800.0	5.48	354.06	7,792.4	163.1	-17.0	-163.5	0.00	0.00	0.00
7,900.0	5.48	354.06	7,892.0	172.6	-18.0	-173.0	0.00	0.00	0.00
8,000.0	5.48	354.06	7,991.5	182.1	-19.0	-182.6	0.00	0.00	0.00
8,100.0	5.48	354.06	8,091.1	191.6	-19.9	-192.1	0.00	0.00	0.00
8,200.0	5.48	354.06	8,190.6	201.1	-20.9	-201.6	0.00	0.00	0.00
8,300.0	5.48	354.06	8,290.1	210.6	-21.9	-211.1	0.00	0.00	0.00
8,400.0	5.48	354.06	8,389.7	220.1	-22.9	-220.6	0.00	0.00	0.00
8,500.0	5.48	354.06	8,489.2	229.6	-23.9	-230.2	0.00	0.00	0.00
8,600.0	5.48	354.06	8,588.8	239.1	-24.9	-239.7	0.00	0.00	0.00



Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
Bone Spring									
8,681.6	5.48	354.06	8,670.0	246.8	-25.7	-247.4	0.00	0.00	0.00
8,700.0	5.48	354.06	8,688.3	248.6	-25.9	-249.2	0.00	0.00	0.00
8,800.0	5.48	354.06	8,787.9	258.1	-26.9	-258.7	0.00	0.00	0.00
Upper Avalon Shale									
8,848.4	5.48	354.06	8,836.0	262.7	-27.3	-263.3	0.00	0.00	0.00
8,900.0	5.48	354.06	8,887.4	267.6	-27.9	-268.2	0.00	0.00	0.00
9,000.0	5.48	354.06	8,986.9	277.1	-28.8	-277.8	0.00	0.00	0.00
9,100.0	5.48	354.06	9,086.5	286.6	-29.8	-287.3	0.00	0.00	0.00
Lower Avalon Shale									
9,175.9	5.48	354.06	9,162.0	293.8	-30.6	-294.5	0.00	0.00	0.00
9,200.0	5.48	354.06	9,186.0	296.1	-30.8	-296.8	0.00	0.00	0.00
9,300.0	5.48	354.06	9,285.6	305.6	-31.8	-306.3	0.00	0.00	0.00
9,400.0	5.48	354.06	9,385.1	315.1	-32.8	-315.8	0.00	0.00	0.00
9,500.0	5.48	354.06	9,484.7	324.6	-33.8	-325.4	0.00	0.00	0.00
9,600.0	5.48	354.06	9,584.2	334.1	-34.8	-334.9	0.00	0.00	0.00
1st Bone Spring Sand									
9,680.2	5.48	354.06	9,664.0	341.7	-35.6	-342.5	0.00	0.00	0.00
9,700.0	5.48	354.06	9,683.7	343.6	-35.8	-344.4	0.00	0.00	0.00
9,800.0	5.48	354.06	9,783.3	353.1	-36.8	-353.9	0.00	0.00	0.00
1st Bone Spring Lower									
9,861.0	5.48	354.06	9,844.0	358.9	-37.4	-359.7	0.00	0.00	0.00
9,900.0	5.48	354.06	9,882.8	362.6	-37.7	-363.4	0.00	0.00	0.00
2nd Bone Spring A Lime									
9,976.5	5.48	354.06	9,959.0	369.8	-38.5	-370.7	0.00	0.00	0.00
Build 10°/100'									
9,987.3	5.48	354.06	9,969.8	370.9	-38.6	-371.8	0.00	0.00	0.00
10,000.0	4.22	356.06	9,982.4	371.9	-38.7	-372.8	10.00	-9.91	15.80
10,100.0	5.86	161.19	10,082.2	370.8	-37.3	-371.6	10.00	1.64	165.13
10,200.0	15.84	165.16	10,180.3	352.7	-32.2	-353.4	10.00	9.98	3.97
Second Bone Spring									
10,216.3	17.47	165.38	10,196.0	348.2	-31.0	-348.9	10.00	9.99	1.36
10,300.0	25.83	166.09	10,273.7	318.3	-23.4	-318.8	10.00	10.00	0.85
10,400.0	35.83	166.52	10,359.4	268.5	-11.3	-268.7	10.00	10.00	0.43
10,500.0	45.83	166.79	10,435.0	205.0	3.7	-204.8	10.00	10.00	0.26
2nd Bone Spring B Sand									
10,594.5	55.28	166.96	10,495.0	134.0	20.3	-133.4	10.00	10.00	0.19
10,600.0	55.83	166.97	10,498.1	129.6	21.3	-129.0	10.00	10.00	0.16
10,700.0	65.83	167.12	10,546.8	44.6	40.8	-43.5	10.00	10.00	0.15
10,800.0	75.83	167.25	10,579.6	-47.4	61.8	49.0	10.00	10.00	0.12
10,900.0	85.83	167.36	10,595.5	-143.6	83.4	145.8	10.00	10.00	0.11
EOB @ 89.47° Inc. / 167.40° Azm / Turn 2°/100'									
10,936.5	89.47	167.40	10,597.0	-179.1	91.4	181.5	10.00	10.00	0.11
11,000.0	89.47	168.67	10,597.6	-241.3	104.6	244.0	2.00	0.00	2.00
11,100.0	89.47	170.67	10,598.5	-339.6	122.5	342.8	2.00	0.00	2.00
11,200.0	89.47	172.67	10,599.4	-438.6	137.0	442.1	2.00	0.00	2.00
11,300.0	89.47	174.67	10,600.4	-538.0	148.0	541.7	2.00	0.00	2.00
11,400.0	89.47	176.67	10,601.3	-637.7	155.6	641.6	2.00	0.00	2.00
11,500.0	89.47	178.67	10,602.2	-737.6	159.6	741.6	2.00	0.00	2.00
EOT @ 89.47° Inc. / 179.58° Azm									
11,545.4	89.47	179.58	10,602.6	-782.9	160.3	786.9	2.00	0.00	2.00
11,600.0	89.47	179.58	10,603.1	-837.6	160.7	841.6	0.00	0.00	0.00
11,700.0	89.47	179.58	10,604.1	-937.5	161.5	941.5	0.00	0.00	0.00



Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,800.0	89.47	179.58	10,605.0	-1,037.5	162.2	1,041.5	0.00	0.00	0.00
11,900.0	89.47	179.58	10,605.9	-1,137.5	162.9	1,141.5	0.00	0.00	0.00
12,000.0	89.47	179.58	10,606.8	-1,237.5	163.7	1,241.5	0.00	0.00	0.00
12,100.0	89.47	179.58	10,607.7	-1,337.5	164.4	1,341.5	0.00	0.00	0.00
12,200.0	89.47	179.58	10,608.7	-1,437.5	165.1	1,441.4	0.00	0.00	0.00
12,300.0	89.47	179.58	10,609.6	-1,537.5	165.9	1,541.4	0.00	0.00	0.00
12,400.0	89.47	179.58	10,610.5	-1,637.5	166.6	1,641.4	0.00	0.00	0.00
12,500.0	89.47	179.58	10,611.4	-1,737.5	167.3	1,741.4	0.00	0.00	0.00
12,600.0	89.47	179.58	10,612.3	-1,837.5	168.1	1,841.3	0.00	0.00	0.00
12,700.0	89.47	179.58	10,613.3	-1,937.5	168.8	1,941.3	0.00	0.00	0.00
12,800.0	89.47	179.58	10,614.2	-2,037.5	169.5	2,041.3	0.00	0.00	0.00
12,900.0	89.47	179.58	10,615.1	-2,137.5	170.3	2,141.3	0.00	0.00	0.00
13,000.0	89.47	179.58	10,616.0	-2,237.5	171.0	2,241.2	0.00	0.00	0.00
13,100.0	89.47	179.58	10,616.9	-2,337.5	171.8	2,341.2	0.00	0.00	0.00
13,200.0	89.47	179.58	10,617.9	-2,437.4	172.5	2,441.2	0.00	0.00	0.00
13,300.0	89.47	179.58	10,618.8	-2,537.4	173.2	2,541.2	0.00	0.00	0.00
13,400.0	89.47	179.58	10,619.7	-2,637.4	174.0	2,641.2	0.00	0.00	0.00
13,500.0	89.47	179.58	10,620.6	-2,737.4	174.7	2,741.1	0.00	0.00	0.00
13,600.0	89.47	179.58	10,621.5	-2,837.4	175.4	2,841.1	0.00	0.00	0.00
13,700.0	89.47	179.58	10,622.5	-2,937.4	176.2	2,941.1	0.00	0.00	0.00
13,800.0	89.47	179.58	10,623.4	-3,037.4	176.9	3,041.1	0.00	0.00	0.00
13,900.0	89.47	179.58	10,624.3	-3,137.4	177.6	3,141.0	0.00	0.00	0.00
14,000.0	89.47	179.58	10,625.2	-3,237.4	178.4	3,241.0	0.00	0.00	0.00
14,100.0	89.47	179.58	10,626.1	-3,337.4	179.1	3,341.0	0.00	0.00	0.00
14,200.0	89.47	179.58	10,627.1	-3,437.4	179.9	3,441.0	0.00	0.00	0.00
14,300.0	89.47	179.58	10,628.0	-3,537.4	180.6	3,540.9	0.00	0.00	0.00
14,400.0	89.47	179.58	10,628.9	-3,637.4	181.3	3,640.9	0.00	0.00	0.00
14,500.0	89.47	179.58	10,629.8	-3,737.4	182.1	3,740.9	0.00	0.00	0.00
14,600.0	89.47	179.58	10,630.8	-3,837.3	182.8	3,840.9	0.00	0.00	0.00
14,700.0	89.47	179.58	10,631.7	-3,937.3	183.5	3,940.8	0.00	0.00	0.00
14,800.0	89.47	179.58	10,632.6	-4,037.3	184.3	4,040.8	0.00	0.00	0.00
14,900.0	89.47	179.58	10,633.5	-4,137.3	185.0	4,140.8	0.00	0.00	0.00
15,000.0	89.47	179.58	10,634.4	-4,237.3	185.7	4,240.8	0.00	0.00	0.00
15,100.0	89.47	179.58	10,635.4	-4,337.3	186.5	4,340.8	0.00	0.00	0.00
15,200.0	89.47	179.58	10,636.3	-4,437.3	187.2	4,440.7	0.00	0.00	0.00
15,300.0	89.47	179.58	10,637.2	-4,537.3	187.9	4,540.7	0.00	0.00	0.00
15,400.0	89.47	179.58	10,638.1	-4,637.3	188.7	4,640.7	0.00	0.00	0.00
15,500.0	89.47	179.58	10,639.0	-4,737.3	189.4	4,740.7	0.00	0.00	0.00
15,600.0	89.47	179.58	10,640.0	-4,837.3	190.2	4,840.6	0.00	0.00	0.00
15,700.0	89.47	179.58	10,640.9	-4,937.3	190.9	4,940.6	0.00	0.00	0.00
15,800.0	89.47	179.58	10,641.8	-5,037.3	191.6	5,040.6	0.00	0.00	0.00
15,900.0	89.47	179.58	10,642.7	-5,137.3	192.4	5,140.6	0.00	0.00	0.00
16,000.0	89.47	179.58	10,643.6	-5,237.3	193.1	5,240.5	0.00	0.00	0.00
16,100.0	89.47	179.58	10,644.6	-5,337.2	193.8	5,340.5	0.00	0.00	0.00
16,200.0	89.47	179.58	10,645.5	-5,437.2	194.6	5,440.5	0.00	0.00	0.00
16,300.0	89.47	179.58	10,646.4	-5,537.2	195.3	5,540.5	0.00	0.00	0.00
16,400.0	89.47	179.58	10,647.3	-5,637.2	196.0	5,640.5	0.00	0.00	0.00
16,500.0	89.47	179.58	10,648.2	-5,737.2	196.8	5,740.4	0.00	0.00	0.00
16,600.0	89.47	179.58	10,649.2	-5,837.2	197.5	5,840.4	0.00	0.00	0.00
16,700.0	89.47	179.58	10,650.1	-5,937.2	198.3	5,940.4	0.00	0.00	0.00
16,800.0	89.47	179.58	10,651.0	-6,037.2	199.0	6,040.4	0.00	0.00	0.00
16,900.0	89.47	179.58	10,651.9	-6,137.2	199.7	6,140.3	0.00	0.00	0.00
17,000.0	89.47	179.58	10,652.8	-6,237.2	200.5	6,240.3	0.00	0.00	0.00
17,100.0	89.47	179.58	10,653.8	-6,337.2	201.2	6,340.3	0.00	0.00	0.00



Well Planning Report



Database: EDM 5000.1 Single User Db
 Company: XTO ENERGY, INC.
 Project: Santa Fe, NM
 Site: Sec. 30, 20-S, 34-E
 Well: Severus 31-5 Federal Com #10H
 Wellbore: Wellbore #1
 Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
 TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
 MD Reference: RKB @ 3722.5usft (Engisn-T #225)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Bulld Rate (°/100usft)	Turn Rate (°/100usft)
17,200.0	89.47	179.58	10,654.7	-6,437.2	201.9	6,440.3	0.00	0.00	0.00
17,300.0	89.47	179.58	10,655.6	-6,537.2	202.7	6,540.2	0.00	0.00	0.00
17,400.0	89.47	179.58	10,656.5	-6,637.2	203.4	6,640.2	0.00	0.00	0.00
17,500.0	89.47	179.58	10,657.4	-6,737.1	204.1	6,740.2	0.00	0.00	0.00
17,600.0	89.47	179.58	10,658.4	-6,837.1	204.9	6,840.2	0.00	0.00	0.00
17,700.0	89.47	179.58	10,659.3	-6,937.1	205.6	6,940.2	0.00	0.00	0.00
17,800.0	89.47	179.58	10,660.2	-7,037.1	206.4	7,040.1	0.00	0.00	0.00
17,900.0	89.47	179.58	10,661.1	-7,137.1	207.1	7,140.1	0.00	0.00	0.00
18,000.0	89.47	179.58	10,662.1	-7,237.1	207.8	7,240.1	0.00	0.00	0.00
18,100.0	89.47	179.58	10,663.0	-7,337.1	208.6	7,340.1	0.00	0.00	0.00
18,200.0	89.47	179.58	10,663.9	-7,437.1	209.3	7,440.0	0.00	0.00	0.00
18,300.0	89.47	179.58	10,664.8	-7,537.1	210.0	7,540.0	0.00	0.00	0.00
18,400.0	89.47	179.58	10,665.7	-7,637.1	210.8	7,640.0	0.00	0.00	0.00
18,500.0	89.47	179.58	10,666.7	-7,737.1	211.5	7,740.0	0.00	0.00	0.00
18,600.0	89.47	179.58	10,667.6	-7,837.1	212.2	7,839.9	0.00	0.00	0.00
TD @ 18689.6' MD / 10668.4' TVD									
18,689.6	89.47	179.58	10,668.4	-7,926.7	212.9	7,929.6	0.00	0.00	0.00

Design Targets

Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
FTP (Shifted) - Severi - plan hits target center - Point	0.00	0.00	10,597.0	-179.1	91.4	559,666.88	726,745.60	32° 32' 11.329 N	103° 35' 51.273 W
FTP - Severus 31-5 F - plan misses target center by 63.6usft at 10949.3usft MD (10597.1 TVD, -191.7 N, 94.2 E) - Point	0.00	0.00	10,597.0	-178.5	156.4	559,667.50	726,810.60	32° 32' 11.331 N	103° 35' 50.514 W
LTP - Severus 31-5 F - plan misses target center by 39.7usft at 18600.0usft MD (10667.6 TVD, -7837.1 N, 212.2 E) - Point	0.00	0.00	10,664.9	-7,876.7	212.5	551,969.30	726,866.70	32° 30' 55.153 N	103° 35' 50.480 W
PBHL - Severus 31-5 - plan hits target center - Point	0.00	0.00	10,668.4	-7,926.7	212.9	551,919.30	726,867.10	32° 30' 54.658 N	103° 35' 50.479 W



Well Planning Report



Database: EDM 5000.1 Single User Db
Company: XTO ENERGY, INC.
Project: Santa Fe, NM
Site: Sec. 30, 20-S, 34-E
Well: Severus 31-5 Federal Com #10H
Wellbore: Wellbore #1
Design: Design #2

Local Co-ordinate Reference: Well Severus 31-5 Federal Com #10H
TVD Reference: RKB @ 3722.5usft (Engisn-T #225)
MD Reference: RKB @ 3722.5usft (Engisn-T #225)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,561.0	1,561.0	Rustler		0.00	
1,912.0	1,912.0	Salado		0.00	
3,157.0	3,157.0	Base Salt		0.00	
3,344.0	3,344.0	Yates		0.00	
3,576.0	3,576.0	Seven Rivers		0.00	
3,725.0	3,725.0	Capitan Reef		0.00	
5,633.0	5,633.0	Delaware		0.00	
7,033.1	7,029.0	Brushy Canyon		0.00	
8,681.6	8,670.0	Bone Spring		0.00	
8,848.4	8,836.0	Upper Avalon Shale		0.00	
9,175.9	9,162.0	Lower Avalon Shale		0.00	
9,680.2	9,664.0	1st Bone Spring Sand		0.00	
9,861.0	9,844.0	1st Bone Spring Lower		0.00	
9,976.5	9,959.0	2nd Bone Spring A Lime		0.00	
10,216.3	10,196.0	Second Bone Spring		0.00	
10,594.5	10,495.0	2nd Bone Spring B Sand		0.00	

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
5,900.0	5,900.0	0.0	0.0	Build 1.5°/100'
6,265.3	6,264.7	17.4	-1.8	EOB @ 5.48° Inc. / 354.06° Azm
9,987.3	9,969.8	370.9	-38.6	Build 10°/100'
10,936.5	10,597.0	-179.1	91.4	EOB @ 89.47° Inc. / 167.40° Azm / Turn 2°/100'
11,545.4	10,602.6	-782.9	160.3	EOT @ 89.47° Inc. / 179.58° Azm
18,689.6	10,668.4	-7,926.7	212.9	TD @ 18689.6' MD / 10668.4' TVD

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	XTO Energy, Inc.
LEASE NO.:	NMNM-086168
WELL NAME & NO.:	Severus 31-5 Federal Com 10H
SURFACE HOLE FOOTAGE:	0080' FSL & 2262' FEL
BOTTOM HOLE FOOTAGE	2558' FNL & 1650' FWL Sec. 05, T. 21 S., R 33 E.
LOCATION:	Section 30, T. 20 S., R 34 E., NMPM
COUNTY:	Lea County, New Mexico

Communitization Agreement

The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- Spudding well (minimum of 24 hours)
- Setting and/or Cementing of all casing strings (minimum of 4 hours)
- BOPE tests (minimum of 4 hours)

☒ **Lea County**

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,
(575) 393-3612

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the Yates formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Potash Areas:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

R-111-P Potash

Capitan Reef

Possibility of water flows in the Artesia Group, Salado, and Capitan Reef.

Possibility of lost circulation in the Rustler, Red Beds, Artesia Group, Capitan Reef, and Delaware.

1. The 20 inch surface casing shall be set at approximately 1670 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

The 11-3/4" 1st Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

2. The minimum required fill of cement behind the 11-3/4 inch 1st intermediate casing is:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Potash**

Special Capitan Reef requirements:

If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:

- **Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.**
- **Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.**

The 8-5/8 2nd Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

3. The minimum required fill of cement behind the 8-5/8 inch 2nd intermediate casing is:

Operator has proposed DV tool at depth of 3280', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

a. First stage to DV tool:

- ☒ **Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.**

b. Second stage above DV tool:

- ☒ **Cement to surface. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Potash and Capitan Reef.**

Formation below the 8-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required through the curve and a minimum of one every other joint.

4. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- ☒ Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 3761'). Operator shall provide method of verification. **Excess calculates to 20% - Additional cement may be required.**

- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 6. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
- 2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 2000 (2M) psi.
4. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the 11-3/4 inch 1st intermediate casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 11-3/4 inch 1st intermediate casing shoe shall be 5000 (5M) psi.**
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Operator shall perform the 8-5/8 inch 2nd intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.

- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 092619