F. Metallurgy:

All drill strings, casing, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.

G. Communication:

- 1. Cellular telephone communications in company vehicles and mud logging trailer.
- 2. Land line (telephone) communications at area office.

H. Well Testing:

Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity which are necessary to safely and adequately conduct the test. The drill stem testing is an H2S environment will be conducted during the daylight hours.