

Eunice Monument South Unit #867
Lea County, New Mexico

Summarized Workover Procedure

This workover was designed to upsize the existing pump with larger equipment in order to increase fluid production. Ultimately, the excess water will be pumped off and an increase in oil production will occur.

1. MIRU pulling unit.
2. POH with old rods and old pump. NU BOP.
3. ND BOP. RIH with new pump and rods.
4. Space out and clamp off.
5. Hang well on and RDMO pulling unit.
6. Test pump and put back on production.
7. Notify field office personnel of well status.