

R. T. HICKS CONSULTANTS, LTD.

901 Rio Grande Blvd NW ▲ Suite F-142 ▲ Albuquerque, NM 87104 ▲ 505.266.5004 ▲ Fax: 505.266-0745

September 7, 2016

Mr. Jamie Keyes
NMOCD District 1
1625 French Drive
Hobbs, NM 88240
Via E-Mail

RE: Temporary Pit Closure Report
Convoy "BUC" State No. 1H
API 30-025-41647 Ut P, Section 28, T24 R33E
Lea County


Dear Mr. Keyes:

On behalf of Yates Petroleum Corporation, R.T. Hicks Consultants submits this closure report for the above-referenced temporary pit in accordance with the approved C-144 closure plan. This report includes the following information listed in Part 21 of the C-144 form:

Requirements	Location in this Submission
Proof of Closure Notice (to surface owner and Division)	Attachment 1
Proof of Deed Notice (on-site closure on private land only)	Not applicable; State Land (no deed)
Plot Plan, C-105 form (for on-site closures and temporary pits)	Attachment 2
Confirmation Sampling Analytical Results	Not applicable.
Waste Material Sampling Analytical Results (required for on-site closure)	Attachment 3
Disposal Facility Name and Permit Number	Not applicable; on-site closure
Soil Backfilling and Cover Installation	Attachment 4
Re-vegetation Application Rates and Seeding Technique	Attachment 5
Site Reclamation (photo documentation)	To follow
Updated C-144 form	Attachment 6

R.T. Hicks Consultants will notify NMOCD and provide photo-documentation when re-vegetation obligations described in subsection H of 19.15.17.13 NMAC are met.

Sincerely,
R.T. Hicks Consultants



Mike Stubblefield
Project Manager

ATTACHMENT 1

R. T. HICKS CONSULTANTS, LTD.

Midland, TX ▲ Durango, CO ▲ Carlsbad, NM ▲ Artesia, NM

901 Rio Grande Blvd NW ▲ Suite F-142 ▲ Albuquerque, NM 87104 ▲ 505.266.5004 ▲ Fax: 505.266-0745

June 22, 2016

Mr. Jamie Keyes
NMOCD District 1
1625 French Drive
Hobbs, New Mexico 88240
VIA EMAIL

RE: Convoy BUC State 1H Temporary Pit, In-place Burial Notice
API #30-025-41647, Pit Permit #P1-
P-28-24S-33E, Lea County


Mr. Keyes:

On behalf of Yates Petroleum Corporation, R. T. Hicks Consultants provides this notice to NMOCD with a copy to the State Land office (e-mail/received verified) that **closure operations** at the above-referenced pit is scheduled to **begin as early as Monday June 27, 2016**. The closure process should require about two weeks, depending on the weather conditions and the availability of machinery.

The "In-place Burial" closure plan for the pit was approved by NMOCD with the C-144 temporary pit application. The drilling rig was released on December 14, 2014.

On March 4, 2015, in accordance with the Pit Rule¹, 5-point composite samples were collected from the inner horseshoe cell, outer horseshoe cell, and from the clean soil of the berms (beneath the liner) of the pit for laboratory analyses. The calculated value mathematically mixes 3 parts clean soil (mixing dirt) with 1 part of the weighted pit composite calculation, as depicted in the adjacent chart.

The table below demonstrates the calculated concentration for "3:1 stabilized cuttings" that results when the pit contents are combined with 3 parts available mixing soil during the closure process. The pit composite consists of 32% solids from the inner cell of the



¹ (5) The operator shall collect, at a minimum, a five point composite of the contents of the temporary pit or drying pad/tank associated with a closed-loop system to demonstrate that, after the waste is solidified or stabilized with soil or other non-waste material at a ratio of no more than 3:1 soil or other non-waste material to waste, the concentration of any contaminant in the stabilized waste is not higher than the parameters in Table II of 19.15.17.13 NMAC.

drilling pit and 68% of solids from the outer cell, representative of the volume of cuttings in each cell. As shown in the table below, all Table II constituents meet the standard.


Well Name	Sample Name	Sample Type	Sample Date	Chloride 80,000	Benzene 10	BTEX 50	GRO+DRO 1000	TPH 418.1 2500	GRO+DRO+ DROext	GRO	DRO	MRO	T	E	X	Lab	Report
Convoy 1H Pit	Outer Composite		3/4/2015	23000	0.97	0	12		2470	160	1800	510	4.5	1.4	6.3	Hall	1
Convoy 1H Pit	Inner Composite		3/4/2015	110000	0	0	0		12	0	12	0	0	0	0	Hall	1
Convoy 1H Pit	Mixing Dirt Comp.		3/4/2015	0	0	0	0		0	0	0	0	0	0	0	Hall	1
Convoy 1H Pit	3:1 Stabilized	CALCULATED		12710	0.08	0.00	0.99	0.00	205.76								PASS

The formula used in the table to calculate the 3:1 Stabilized Cuttings is:

$$3:1 \text{ Stabilized Cuttings} = \frac{[(\text{Outer Composite} * 0.68) + (0.32 * \text{Inner Composite}) + (\text{Mixing Dirt} * 3)]}{4}$$

Thank you for your consideration of this notice of in-place closure. I will follow-up this notice to you with a phone call today as required by the Pit Rule.

Sincerely,
R.T. Hicks Consultants



Mike Stubblefield
Project Manager

Copy: Yates Petroleum Corporation
Ed Martin, State Land Office



Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

March 17, 2015

Mike Stubblefield

R.T. Hicks Consultants, LTD

901 Rio Grande Blvd. NW

Suite F-142

Albuquerque, NM 87104

TEL: (505) 266-5004

FAX (505) 266-0745

RE: Convoy BUC State No 1H

OrderNo.: 1503283

Dear Mike Stubblefield:

Hall Environmental Analysis Laboratory received 3 sample(s) on 3/6/2015 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. To access our accredited tests please go to www.hallenvironmental.com or the state specific web sites. In order to properly interpret your results it is imperative that you review this report in its entirety. See the sample checklist and/or the Chain of Custody for information regarding the sample receipt temperature and preservation. Data qualifiers or a narrative will be provided if the sample analysis or analytical quality control parameters require a flag. When necessary, data qualifiers are provided on both the sample analysis report and the QC summary report, both sections should be reviewed. All samples are reported, as received, unless otherwise indicated. Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH and residual chlorine are qualified as being analyzed outside of the recommended holding time.

Please don't hesitate to contact HEAL for any additional information or clarifications.

ADHS Cert #AZ0682 -- NMED-DWB Cert #NM9425 -- NMED-Micro Cert #NM0190

Sincerely,

A handwritten signature in black ink, appearing to read 'Andy Freeman', is written over a horizontal line.

Andy Freeman

Laboratory Manager

4901 Hawkins NE

Albuquerque, NM 87109

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order 1503283

Date Reported: 3/17/2015

CLIENT: R.T. Hicks Consultants, LTD

Client Sample ID: 4 pt Outer Comp

Project: Convoy BUC State No 1H

Collection Date: 3/4/2015 10:00:00 AM

Lab ID: 1503283-001

Matrix: SOIL

Received Date: 3/6/2015 10:40:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed	Batch
EPA METHOD 8015D: DIESEL RANGE ORGANICS							Analyst: JME
Diesel Range Organics (DRO)	1800	100		mg/Kg	10	3/10/2015 9:10:52 PM	18038
Motor Oil Range Organics (MRO)	510	500		mg/Kg	10	3/10/2015 9:10:52 PM	18038
Surr: DNOP	0	63.5-128	S	%REC	10	3/10/2015 9:10:52 PM	18038
EPA METHOD 8015D: GASOLINE RANGE							Analyst: NSB
Gasoline Range Organics (GRO)	160	5.0		mg/Kg	1	3/11/2015 2:06:38 AM	18043
Surr: BFB	418	80-120	S	%REC	1	3/11/2015 2:06:38 AM	18043
EPA METHOD 8021B: VOLATILES							Analyst: NSB
Benzene	0.97	0.050		mg/Kg	1	3/11/2015 2:06:38 AM	18043
Toluene	4.5	0.050		mg/Kg	1	3/11/2015 2:06:38 AM	18043
Ethylbenzene	1.4	0.050		mg/Kg	1	3/11/2015 2:06:38 AM	18043
Xylenes, Total	6.3	0.10		mg/Kg	1	3/11/2015 2:06:38 AM	18043
Surr: 4-Bromofluorobenzene	156	80-120	S	%REC	1	3/11/2015 2:06:38 AM	18043
EPA METHOD 300.0: ANIONS							Analyst: LGT
Chloride	23000	750		mg/Kg	500	3/11/2015 11:05:30 AM	18083

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
	O	RSD is greater than RSDlimit	P	Sample pH Not In Range
	R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
	S	Spike Recovery outside accepted recovery limits		

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order 1503283

Date Reported: 3/17/2015

CLIENT: R.T. Hicks Consultants, LTD

Client Sample ID: 4 pt Inner Comp

Project: Convoy BUC State No 1H

Collection Date: 3/4/2015 10:15:00 AM

Lab ID: 1503283-002

Matrix: SOIL

Received Date: 3/6/2015 10:40:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed	Batch
EPA METHOD 8015D: DIESEL RANGE ORGANICS							Analyst: JME
Diesel Range Organics (DRO)	12	9.8		mg/Kg	1	3/10/2015 9:32:18 PM	18038
Motor Oil Range Organics (MRO)	ND	49		mg/Kg	1	3/10/2015 9:32:18 PM	18038
Surr: DNOP	106	63.5-128		%REC	1	3/10/2015 9:32:18 PM	18038
EPA METHOD 8015D: GASOLINE RANGE							Analyst: NSB
Gasoline Range Organics (GRO)	ND	5.0		mg/Kg	1	3/11/2015 2:35:12 AM	18043
Surr: BFB	101	80-120		%REC	1	3/11/2015 2:35:12 AM	18043
EPA METHOD 8021B: VOLATILES							Analyst: NSB
Benzene	ND	0.050		mg/Kg	1	3/11/2015 2:35:12 AM	18043
Toluene	ND	0.050		mg/Kg	1	3/11/2015 2:35:12 AM	18043
Ethylbenzene	ND	0.050		mg/Kg	1	3/11/2015 2:35:12 AM	18043
Xylenes, Total	ND	0.099		mg/Kg	1	3/11/2015 2:35:12 AM	18043
Surr: 4-Bromofluorobenzene	113	80-120		%REC	1	3/11/2015 2:35:12 AM	18043
EPA METHOD 300.0: ANIONS							Analyst: LGT
Chloride	110000	7500		mg/Kg	5E	3/16/2015 12:20:02 PM	18083

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
	O	RSD is greater than RSDlimit	P	Sample pH Not In Range
	R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
	S	Spike Recovery outside accepted recovery limits		

Hall Environmental Analysis Laboratory, Inc.

Analytical Report

Lab Order 1503283

Date Reported: 3/17/2015

CLIENT: R.T. Hicks Consultants, LTD

Client Sample ID: 5 pt Mixing Dirt

Project: Convoy BUC State No 1H

Collection Date: 3/4/2015 10:30:00 AM

Lab ID: 1503283-003

Matrix: SOIL

Received Date: 3/6/2015 10:40:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed	Batch
EPA METHOD 8015D: DIESEL RANGE ORGANICS				Analyst: JME			
Diesel Range Organics (DRO)	ND	10		mg/Kg	1	3/10/2015 9:53:58 PM	18038
Motor Oil Range Organics (MRO)	ND	52		mg/Kg	1	3/10/2015 9:53:58 PM	18038
Surr: DNOP	99.0	63.5-128		%REC	1	3/10/2015 9:53:58 PM	18038
EPA METHOD 8015D: GASOLINE RANGE				Analyst: NSB			
Gasoline Range Organics (GRO)	ND	5.0		mg/Kg	1	3/11/2015 3:03:55 AM	18043
Surr: BFB	92.9	80-120		%REC	1	3/11/2015 3:03:55 AM	18043
EPA METHOD 8021B: VOLATILES				Analyst: NSB			
Benzene	ND	0.050		mg/Kg	1	3/11/2015 3:03:55 AM	18043
Toluene	ND	0.050		mg/Kg	1	3/11/2015 3:03:55 AM	18043
Ethylbenzene	ND	0.050		mg/Kg	1	3/11/2015 3:03:55 AM	18043
Xylenes, Total	ND	0.099		mg/Kg	1	3/11/2015 3:03:55 AM	18043
Surr: 4-Bromofluorobenzene	107	80-120		%REC	1	3/11/2015 3:03:55 AM	18043
EPA METHOD 300.0: ANIONS				Analyst: LGT			
Chloride	ND	30		mg/Kg	20	3/11/2015 12:07:30 PM	18083

Refer to the QC Summary report and sample login checklist for flagged QC data and preservation information.

Qualifiers:	*	Value exceeds Maximum Contaminant Level.	B	Analyte detected in the associated Method Blank
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not Detected at the Reporting Limit
	O	RSD is greater than RSDlimit	P	Sample pH Not In Range
	R	RPD outside accepted recovery limits	RL	Reporting Detection Limit
	S	Spike Recovery outside accepted recovery limits		

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1503283

17-Mar-15

Client: R.T. Hicks Consultants, LTD

Project: Convoy BUC State No 1H

Sample ID	MB-18083		SampType:	MBLK		TestCode:	EPA Method 300.0: Anions				
Client ID:	PBS		Batch ID:	18083		RunNo:	24785				
Prep Date:	3/11/2015		Analysis Date:	3/11/2015		SeqNo:	730064		Units: mg/Kg		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual	
Chloride	ND	1.5									

Sample ID	LCS-18083		SampType: LCS		TestCode: EPA Method 300.0: Anions					
Client ID:	LCSS		Batch ID: 18083		RunNo: 24785					
Prep Date:	3/11/2015		Analysis Date: 3/11/2015		SeqNo: 730065		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Chloride	14	1.5	15.00	0	92.0	90	110			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
E Value above quantitation range
J Analyte detected below quantitation limits
O RSD is greater than RSDlimit
R RPD outside accepted recovery limits
S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
P Sample pH Not In Range
RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1503283

17-Mar-15

Client: R.T. Hicks Consultants, LTD

Project: Convoy BUC State No 1H

Sample ID	MB-18038	SampType: MBLK		TestCode: EPA Method 8015D: Diesel Range Organics						
Client ID:	PBS	Batch ID: 18038		RunNo: 24711						
Prep Date:	3/9/2015	Analysis Date: 3/10/2015		SeqNo: 728323		Units: mg/Kg				
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Diesel Range Organics (DRO)	ND	10								
Motor Oil Range Organics (MRO)	ND	50								
Surr: DNOP	8.4		10.00		84.2	63.5	128			

Sample ID	LCS-18038		SampType: LCS		TestCode: EPA Method 8015D: Diesel Range Organics					
Client ID:	LCSS		Batch ID: 18038		RunNo: 24711					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728325		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Diesel Range Organics (DRO)	45	10	50.00	0	90.9	67.8	130			
Surr: DNOP	4.5		5.000		89.3	63.5	128			

Qualifiers:

* Value exceeds Maximum Contaminant Level.
E Value above quantitation range
J Analyte detected below quantitation limits
O RSD is greater than RSDlimit
R RPD outside accepted recovery limits
S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
P Sample pH Not In Range
RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1503283

17-Mar-15

Client: R.T. Hicks Consultants, LTD

Project: Convoy BUC State No 1H

Sample ID	MB-18044		SampType: MBLK		TestCode: EPA Method 8015D: Gasoline Range					
Client ID:	PBS		Batch ID: 18044		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728732		Units: %REC			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: BFB	900		1000		89.5	80	120			

Sample ID	LCS-18044		SampType: LCS		TestCode: EPA Method 8015D: Gasoline Range					
Client ID:	LCSS		Batch ID: 18044		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728733		Units: %REC			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: BFB	1100		1000		108	80	120			

Sample ID	MB-18043		SampType:	MBLK		TestCode:	EPA Method 8015D: Gasoline Range				
Client ID:	PBS		Batch ID:	18043		RunNo:	24730				
Prep Date:	3/9/2015		Analysis Date:	3/10/2015		SeqNo:	728754		Units:		mg/Kg
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual	
Gasoline Range Organics (GRO)	ND	5.0									
Surr: BFB	910		1000		90.8	80	120				

Sample ID	LCS-18043		SampType: LCS		TestCode: EPA Method 8015D: Gasoline Range					
Client ID:	LCSS		Batch ID: 18043		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728755		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Gasoline Range Organics (GRO)	26	5.0	25.00	0	105	64	130			
Surr: BFB	980		1000		97.5	80	120			

Sample ID	LCSD-18043		SampType: LCSD		TestCode: EPA Method 8015D: Gasoline Range					
Client ID:	LCSS02		Batch ID: 18043		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728756		Units: %REC			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: BFB	990							0	0	

Qualifiers:

* Value exceeds Maximum Contaminant Level.
E Value above quantitation range
J Analyte detected below quantitation limits
O RSD is greater than RSDlimit
R RPD outside accepted recovery limits
S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
P Sample pH Not In Range
RL Reporting Detection Limit

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1503283

17-Mar-15

Client: R.T. Hicks Consultants, LTD

Project: Convoy BUC State No 1H

Sample ID	MB-18044		SampType: MBLK		TestCode: EPA Method 8021B: Volatiles					
Client ID:	PBS		Batch ID: 18044		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728766		Units: %REC			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: 4-Bromofluorobenzene	1.0		1.000		102	80	120			

Sample ID	LCS-18044		SampType:	LCS		TestCode:	EPA Method 8021B: Volatiles				
Client ID:	LCSS		Batch ID:	18044		RunNo:	24730				
Prep Date:	3/9/2015		Analysis Date:	3/10/2015		SeqNo:	728767		Units: %REC		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual	
Surr: 4-Bromofluorobenzene	1.1		1.000		112	80	120				

Sample ID	MB-18043		SampType: MBLK		TestCode: EPA Method 8021B: Volatiles					
Client ID:	PBS		Batch ID: 18043		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728781		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	ND	0.050								
Toluene	ND	0.050								
Ethylbenzene	ND	0.050								
Xylenes, Total	ND	0.10								
Surr: 4-Bromofluorobenzene	1.0		1.000		103	80	120			

Sample ID	LCS-18043		SampType: LCS		TestCode: EPA Method 8021B: Volatiles					
Client ID:	LCSS		Batch ID: 18043		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728782		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	1.1	0.050	1.000	0	111	76.6	128			
Toluene	1.1	0.050	1.000	0	109	75	124			
Ethylbenzene	1.1	0.050	1.000	0	109	79.5	126			
Xylenes, Total	3.2	0.10	3.000	0	108	78.8	124			
Surr: 4-Bromofluorobenzene	1.1		1.000		112	80	120			

Sample ID	LCSD-18043		SampType: LCSD		TestCode: EPA Method 8021B: Volatiles					
Client ID:	LCSS02		Batch ID: 18043		RunNo: 24730					
Prep Date:	3/9/2015		Analysis Date: 3/10/2015		SeqNo: 728783		Units: mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	1.1	0.050	1.000	0	107	76.6	128	3.68	20	
Toluene	1.1	0.050	1.000	0	105	75	124	3.09	20	
Ethylbenzene	1.1	0.050	1.000	0	107	79.5	126	2.53	20	
Xylenes, Total	3.2	0.10	3.000	0	106	78.8	124	1.71	20	

Qualifiers:

- | | |
|---|--|
| * Value exceeds Maximum Contaminant Level. | B Analyte detected in the associated Method Blank |
| E Value above quantitation range | H Holding times for preparation or analysis exceeded |
| J Analyte detected below quantitation limits | ND Not Detected at the Reporting Limit |
| O RSD is greater than RSDlimit | P Sample pH Not In Range |
| R RPD outside accepted recovery limits | RL Reporting Detection Limit |
| S Spike Recovery outside accepted recovery limits | |

QC SUMMARY REPORT

Hall Environmental Analysis Laboratory, Inc.

WO#: 1503283

17-Mar-15

Client: R.T. Hicks Consultants, LTD

Project: Convoy BUC State No 1H

Sample ID	LCSD-18043	SampType:	LCSD	TestCode:	EPA Method 8021B: Volatiles					
Client ID:	LCSS02	Batch ID:	18043	RunNo:	24730					
Prep Date:	3/9/2015	Analysis Date:	3/10/2015	SeqNo:	728783	Units:	mg/Kg			
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Surr: 4-Bromofluorobenzene	1.1		1.000		111	80	120	0		

Qualifiers:

* Value exceeds Maximum Contaminant Level.
E Value above quantitation range
J Analyte detected below quantitation limits
O RSD is greater than RSDlimit
R RPD outside accepted recovery limits
S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
ND Not Detected at the Reporting Limit
P Sample pH Not In Range
RL Reporting Detection Limit



Hall Environmental Analysis Laboratory
4901 Hawkins NE
Albuquerque, NM 87109
TEL: 505-345-3975 FAX: 505-345-4107
Website: www.hallenvironmental.com

Sample Log-In Check List

Client Name: RT HICKS

Work Order Number: 1503283

RcptNo: 1

Received by/date:

AT 03/06/15

Logged By: Anne Thorne

3/6/2015 10:40:00 AM

Anne Thorne

Completed By: Anne Thorne

3/9/2015

Anne Thorne

Reviewed By:

[Signature]

03/09/15

Chain of Custody

1. Custody seals intact on sample bottles? Yes ☐ No ☐ Not Present ☒
2. Is Chain of Custody complete? Yes ☒ No ☐ Not Present ☐
3. How was the sample delivered? Client

Log In

4. Was an attempt made to cool the samples? Yes ☒ No ☐ NA ☐
5. Were all samples received at a temperature of $>0^{\circ}\text{C}$ to 6.0°C ? Yes ☒ No ☐ NA ☐
6. Sample(s) in proper container(s)? Yes ☒ No ☐
7. Sufficient sample volume for indicated test(s)? Yes ☒ No ☐
8. Are samples (except VOA and ONG) properly preserved? Yes ☒ No ☐
9. Was preservative added to bottles? Yes ☐ No ☒ NA ☐
10. VOA vials have zero headspace? Yes ☐ No ☐ No VOA Vials ☒
11. Were any sample containers received broken? Yes ☐ No ☒
12. Does paperwork match bottle labels?
(Note discrepancies on chain of custody) Yes ☒ No ☐
13. Are matrices correctly identified on Chain of Custody? Yes ☒ No ☐
14. Is it clear what analyses were requested? Yes ☒ No ☐
15. Were all holding times able to be met?
(If no, notify customer for authorization.) Yes ☒ No ☐

of preserved
bottles checked
for pH: _____
(<2 or >12 unless noted)
Adjusted? _____
Checked by: _____

Special Handling (if applicable)

16. Was client notified of all discrepancies with this order? Yes ☐ No ☐ NA ☒

Person Notified:	_____	Date:	_____
By Whom:	_____	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	_____		
Client Instructions:	_____		

17. Additional remarks:

18. Cooler Information

Cooler No	Temp $^{\circ}\text{C}$	Condition	Seal Intact	Seal No	Seal Date	Signed By
1	1.2	Good	Not Present			

Mike Stubblefield

From: Martin, Ed <emartin@slo.state.nm.us>
Sent: Friday, June 24, 2016 7:30 AM
To: mike@rthicksconsult.com
Cc: jamie.keyes@state.nm.us
Subject: RE: Landowner Notice for Closure on temporary pit at Yates Petroleum Corporation Convoy BUC State Com. 1H

Receipt acknowledged. Thanks.

Ed Martin
Oil and Gas Manager
Oil Gas and Minerals Division
505.827.5746
New Mexico State Land Office
310 Old Santa Fe Trail
P.O. Box 1148
Santa Fe, NM 87504-1148
emartin@slo.state.nm.us



.....
CONFIDENTIALITY NOTICE: This e-mail, including all attachments is for the sole use of the intended recipient[s] and may contain confidential and/or privileged information. Any unauthorized review, use, copying, disclosure or distribution is prohibited, unless specifically provided under the New Mexico Inspection of Public Records Act. If you are not the intended recipient, please contact the sender at once and destroy all copies of this message.

From: Mike Stubblefield [mailto:mike@rthicksconsult.com]
Sent: Wednesday, June 22, 2016 2:06 PM
To: Martin, Ed <emartin@slo.state.nm.us>
Cc: jamie.keyes@state.nm.us
Subject: Landowner Notice for Closure on temporary pit at Yates Petroleum Corporation Convoy BUC State Com. 1H

Dear Ed Martin,

R.T. Hicks Consultants is sending the landowner Notice for Closure for the temporary pit located at Yates Petroleum Corporation Convoy BUC State Com. No.1H. Please send me a response for this email as received to verify delivery.

Sincerely,

Mike Stubblefield
R.T. Hicks Consultants
575-365-5034

This email has been scanned by the Symantec Email Security.cloud service.
For more information please visit <http://www.symanteccloud.com>

ATTACHMENT 2

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised August 18,2016														
		1. WELL API NO. 30-025-41647																		
		2. Type of Lease <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/> FED/INDIAN																		
		3. State Oil & Gas Lease No. VB-1743																		
WELL COMPLETION OR RECOMPLETION REPORT AND LOG																				
4. Reason for filing: <input type="checkbox"/> COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) <input checked="" type="checkbox"/> C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name Convoy 'BUC' State 6. Well Number: 1H														
7. Type of Completion: <input checked="" type="checkbox"/> NEW WELL <input type="checkbox"/> WORKOVER <input type="checkbox"/> DEEPENING <input type="checkbox"/> PLUGBACK <input type="checkbox"/> DIFFERENT RESERVOIR <input type="checkbox"/> OTHER _____																				
8. Name of Operator Yates Petroleum Corporation						9. OGRID 025575														
10. Address of Operator 105 South Fourth Street Artesia, New Mexico						11. Pool name or Wildcat Triple X Bone Spring, West														
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County										
Surface:	P	28	24S	33E		15'	S	400'	E	Lea										
BH:																				
13. Date Spudded 11/14/14	14. Date T.D. Reached 12/11/14		15. Date Rig Released 12/14/14			16. Date Completed (Ready to Produce) NA		17. Elevations (DF and RKB, RT, GR, etc.)												
18. Total Measured Depth of Well			19. Plug Back Measured Depth			20. Was Directional Survey Made?		21. Type Electric and Other Logs Run												
22. Producing Interval(s), of this completion - Top, Bottom, Name																				
23. CASING RECORD (Report all strings set in well)																				
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED										
24. LINER RECORD						25. TUBING RECORD														
SIZE	TOP	BOTTOM		SACKS CEMENT	SCREEN	SIZE	DEPTH SET		PACKER SET											
26. Perforation record (interval, size, and number)						27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC. <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th style="width:50%;">DEPTH INTERVAL</th> <th style="width:50%;">AMOUNT AND KIND MATERIAL USED</th> </tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>					DEPTH INTERVAL	AMOUNT AND KIND MATERIAL USED								
DEPTH INTERVAL	AMOUNT AND KIND MATERIAL USED																			
28. PRODUCTION																				
Date First Production		Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>)				Well Status (<i>Prod. or Shut-in</i>)														
Date of Test	Hours Tested	Choke Size	Prod'n For Test Period	Oil - Bbl	Gas - MCF	Water - Bbl.	Gas - Oil Ratio													
Flow Tubing Press.	Casing Pressure	Calculated 24-Hour Rate	Oil - Bbl.	Gas - MCF	Water - Bbl.	Oil Gravity - API - (<i>Corr.</i>)														
									30. Test Witnessed By											
31. List Attachments																				
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.																				
33. If an on-site burial was used at the well, report the exact location of the on-site burial:0 Latitude 32.18170N Longitude 103.56956 W NAD 1983																				
<i>I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief</i>																				
Signature Date 9/7/16		Printed Name Mike Stubblefield				Title Agent for YPC														
E-mail Address mike@rthicksconsult.com																				

INSTRUCTIONS

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

INDICATE FORMATION TOPS IN CONFORMANCE WITH GEOGRAPHICAL SECTION OF STATE

Southeastern New Mexico		Northwestern New Mexico	
T. Anhy_____	T. Canyon_____	T. Ojo Alamo_____	T. Penn A"_____
T. Salt_____	T. Strawn_____	T. Kirtland_____	T. Penn. "B"_____
B. Salt_____	T. Atoka_____	T. Fruitland_____	T. Penn. "C"_____
T. Yates_____	T. Miss_____	T. Pictured Cliffs_____	T. Penn. "D"_____
T. 7 Rivers_____	T. Devonian_____	T. Cliff House_____	T. Leadville_____
T. Queen_____	T. Silurian_____	T. Menefee_____	T. Madison_____
T. Grayburg_____	T. Montoya_____	T. Point Lookout_____	T. Elbert_____
T. San Andres_____	T. Simpson_____	T. Mancos_____	T. McCracken_____
T. Glorieta_____	T. McKee_____	T. Gallup_____	T. Ignacio Otzte_____
T. Paddock_____	T. Ellenburger_____	Base Greenhorn_____	T.Granite_____
T. Blinebry_____	T. Gr. Wash_____	T. Dakota_____	
T.Tubb_____	T. Delaware Sand_____	T. Morrison_____	
T. Drinkard_____	T. Bone Springs_____	T.Todilto_____	
T. Abo_____	T. _____	T. Entrada_____	
T. Wolfcamp_____	T. _____	T. Wingate_____	
T. Penn_____	T. _____	T. Chinle_____	
T. Cisco (Bough C)_____	T. _____	T. Permian_____	

OIL OR GAS SANDS OR ZONES

No. 1, from.....to.....

No. 3, from.....to.....

No. 2, from.....to.....

No. 4, from.....to.....

IMPORTANT WATER SANDS

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....

No. 2, from.....to.....feet.....

No. 3, from.....to.....feet.....

LITHOLOGY RECORD (Attach additional sheet if necessary)

From	To	Thickness In Feet	Lithology

From	To	Thickness In Feet	Lithology



2

Middle of drilling pit 32.18170-103.56956

Convoy BUC State No.1H
32.18138-103.57002



1996

© SPOT IMAGE
© 2016 Google

Google earth

Imagery Date: 2/13/2014 32°10'52.40" N 103°34'08.52" W elev 3482 ft eye alt 5790 ft

ATTACHMENT 3

Waste Material Sampling Analytical Results



On March 3, 2015, eight-point composite samples were collected from the temporary pit. Clean mixing soil was collected from under the liner. The composite samples was submitted to Hall Environmental Analysis Laboratory in Albuquerque, New Mexico for BTEX (8260B), GRO/GRO (8015M), TPH (418.1), and Chloride (SM4500) analyses.

The table below depicts the samples collected from the cuttings in this pit and their concentrations of the parameters listed in Table II of 19.15.17.13 NMAC (June 2013 Pit Rule). These analyses demonstrate that this site meets the criteria for in-place closure.

Well Name	Sample Name	Sample Type	Sample Date	Chloride 80,000	Benzene 10	BTEX 50	GRO+DRO 1000	TPH 418.1 2500	GRO+DRO+ DROext	GRO	DRO	MRO	T	E	X	Lab	Report
Convoy 1H Pit	Outer Composite		3/4/2015	23000	0.97	0	12		2470	160	1800	510	4.5	1.4	6.3	Hall	1
Convoy 1H Pit	Inner Composite		3/4/2015	110000	0	0	0		12	0	12	0	0	0	0	Hall	1
Convoy 1H Pit	Mixing Dirt Comp.		3/4/2015	0	0	0	0		0	0	0	0	0	0	0	Hall	1
Convoy 1H Pit	3:1 Stabilized	CALCULATED		12710.00	0.08	0.00	0.99	0.00	205.76								PASS

ATTACHMENT 4

SOIL BACKFILLING & COVER INSTALLATION

In accordance with the requirements listed in paragraph D of 19.15.17.13 NMAC, the operator employed the following steps for in-place burial of the waste material from the temporary pit:


1. The on-site burial location and its depth is in compliance with the siting criteria presented in the C-144 application and the Pit Rule under which it was submitted to the NMOCD on March 3, 2014 and approved on July 11, 2014. After the drilling rig was released on December 14, 2014, fluid contents in the pit were removed to be recycled for the drilling of other wells while the cuttings were allowed to dry. The Convoy "BUC" No.1 is currently waiting on completion.
2. On March 3, 2015, prior to the initiation of closure activities, composite samples from the inner and outer cells and clean soil from the berms of the pit below the liner were recovered from the pit. Samples were analyzed for Chloride, TPH, GRO, DRO, MRO, Benzene, and BTEX at Hall Environmental Analysis Laboratory in Albuquerque, New Mexico. The results, as noted in the subsequent closure notice, demonstrate that the mathematic mixed pit contents would not exceed the parameter limits listed in Table II of the new Pit Rule (June 2013).
3. On June 13, 2014, R.T. Hicks Consultants submitted a admended C-144 form and closure plan to NMOCD for approval to close the pit under the June 2013 Pit Rule. NMOCD granted approval on July 11, 2014, a closure notice was submitted on June 22, 2016 to the NMOCD, District 1 office in Hobbs and to the State Land Office on the same day. Verbal notice in the form of a phone call to NMOCD followed on June 23, 2016.
4. On June 27, 2016, closure activities commenced and stabilization of the pit contents was achieved by mixing the pit contents with the dry soil beneath the liner of the pit. Stabilization continued until July 18, 2016 when a paint filter test was performed by R.T. Hicks Consultants that confirmed that the process was complete and that the resultant floor of the excavation was at least 4 feet deep.
5. Following the July 18, 2016 inspection, having achieved all applicable stabilization requirements associated with in-place burial, a 20 Mil. geomembrane liner was installed to completely cover the stabilized cuttings on July 22, 2016. The pit contents and liner were shaped to shed infiltrating water, sloping from East to West.

Closure Letter Attachment 4
Yates Petroleum Corporation – Convoy “BUC” State 1H
API #30-025-41647

6. Once the geomembrane cover was in place, 4 feet or more of non-waste containing, uncontaminated, earthen material and the reserved topsoil were replaced to their relative positions in accordance with Subsection (3) of Paragraph H of 19.15.17.13 NMAC. The soil cover consists of at least four feet of compacted, non-waste containing, earthen material. The uppermost topsoil is equal to the background thickness at least one foot.
7. The surface was contoured to blend with the surrounding topography and to prevent erosion and the ponding of water over the on-site closure. This work was completed on August 2, 2016.



Viewing West 20 Mil. liner installation



Paint filter test on 7/18/2016



Liner Installation completed on 7/22/2016.

Viewing to East.

ATTACHMENT 5

RE-VEGETATION PROCEDURES

There were no roads or surface drainage features nearby that required restoration or preservation.

1. On August 2, 2016 TNT Backhoe Services of Artesia did reseed the topsoil on the on-site burial and interim reclamation areas using a tractor that prepared the seedbed. The seed furrows will be oriented perpendicular to the prevailing western wind to minimize erosion.
2. Approximately 70 pounds of a seed mixture consisting of lesser prairie chicken seed mix was applied in accordance with the supplier's instructions to approximately 1 acre of the former temporary pit area. Species constituents of lesser prairie chicken seed blend are listed below and are appropriate for the soil type and conditions at this site.

*Lesser Prairie
chicken mix*
Bluestem Big
"KAW"
Bluestem Little
"Cimarron"
Bluestem Sand
Dropseed Sand
Bristlegrass
Plains

3. The seeded area will be monitored for growth and the operator will repeat seeding until a successful vegetative cover is achieved as outlined in Subsection (5) of Paragraph H of 19.15.17.13 NMAC.
4. If conditions are not favorable for the establishment of vegetation, such as periods of drought, the operator may request that the division allow a delay in additional seeding until soil moisture conditions become favorable. The operator will notify the division and provide photo-documentation when it successful re-vegetation is achieved.

Labels on seed sacks describing composition species

Closure Letter Attachment 5
Yates Petroleum Corporation– Convoy BUC State1H
API #30-025-41647



Completed drilling pit – viewing to

Bamert Seed Company Inc.					
1897 CR 1018 Muleshoe, TX 79347		(800) 262-9892		Permit # TX	
Lesser Prairie Chicken Blend 1 acre				Sales # SO-	
Description	Pure Seed	Germ	Dormant	Hard Seed	C
Bluestem Big, "Kaw" (Andropogon gerardii)	18.31%	94.00%	0.00%	0.00%	
Bluestem Sand, "Woodward" (Andropogon tallii)	16.87%	95.00%	0.00%	0.00%	
Bluestem, Little "Cimarron" (Schizachyrium scoparium)	9.96%	88.00%	0.00%	0.00%	
Wetgrass Plains, (Setaria vulpiseta)	16.64%	2.00%	88.00%	0.00%	
Coreopsis, "Plains" (Coreopsis tinctoria)	6.02%	82.00%	15.00%	0.00%	
Dropseed, Sand (Sporobolus cryptandrus)	2.98%	93.00%	0.00%	0.00%	
Purity: 70.78%	Inert Matter: 21.37%	Other Crop Seed: 7.82%		Weed Seed	
Weeds: None					
Test Date: 04/2016		Net V			

Bamert Seed Company Inc.									
1897 CR 1018 Muleshoe, TX 79347		(800) 262-9892		Permit # TX					
Lesser Prairie Chicken .5 acre				INV59680					
Description	Pure Seed	Germ	Dormant	Hard Seed	C				
Bluestem Big, "Kaw" (Andropogon gerardii)	19.23%	94.00%	0.00%	0.00%					
Bluestem Sand, "Woodward" (Andropogon tallii)	15.86%	95.00%	0.00%	0.00%					
Bluestem, Little "Cimarron" (Schizachyrium scoparium)	10.16%	89.00%	0.00%	0.00%					
Wetgrass Plains (Setaria vulpiseta)	16.74%	2.00%	88.00%	0.00%					
Coreopsis, "Plains" (Coreopsis tinctoria)	6.21%	82.00%	15.00%	0.00%					
Dropseed, Sand (Sporobolus cryptandrus)	3.24%	93.00%	0.00%	0.00%					
Purity: 71.44%	Inert Matter: 21.21%	Other Crop Seed: 7.32%		Weed Seed					
Weeds: None									
Test Date: 03/2016									
Net									

Labels on seed sacks describing composition species

ATTACHMENT 6

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144
Revised June 6, 2013

For temporary pits, below-grade tanks, and multi-well fluid management pits, submit to the appropriate NMOCD District Office.
For permanent pits submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

Pit, Below-Grade Tank, or
Proposed Alternative Method Permit or Closure Plan Application

Type of action: ☐ Below grade tank registration
☐ Permit of a pit or proposed alternative method
☒ Closure of a pit, below-grade tank, or proposed alternative method

S

☐ Closure plan only submitted for an existing permitted or non-permitted pit, below-grade tank, or proposed alternative method

Instructions: Please submit one application (Form C-144) per individual pit, below-grade tank or alternative request

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.

Operator: Yates Petroleum Corporation OGRID #: 025575
Address: 105 South 4th Street, Artesia, New Mexico 88210
Facility or well name: Convoy "BUC" State 1H
API Number: 30-025-41647 OCD Permit Number: P1-06551
U/L or Qtr/Qtr P Section 28 Township T24S Range R33E County: Eddy
Center of Proposed Design: Latitude _____ Longitude _____ NAD: 1927 X 1983 Surface Owner ☒ Federal
X State ☐ Private ☐ Tribal Trust of Indian Allotment

2.

X **Pit:** Subsection F, G or J of 19.15.17.11 NMAC

Temporary: X Drilling ☐ Workover

☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Multi-Well Fluid Management Low Chloride Drilling Fluid ☐ yes ☐ no

X Lined ☐ Unlined Liner type: Thickness 20 mil X LLDPE ☐ HDPE ☐ PVC ☐ Other _____ X ☐

String-Reinforced

Liner Seams: ☒ Welded ☐ Factory ☐ Other _____ Volume: 78,500 bbl Dimensions: L 275' x W 250' x D 6'-10'

3.

☐ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC

Volume: _____ bbl Type of fluid: _____

Tank Construction material: _____

☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off

☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other _____

Liner type: Thickness _____ mil ☐ HDPE ☐ PVC ☐ Other _____

4.

☐ **Alternative Method:**

Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

5.

Fencing: Subsection D of 19.15.17.11 NMAC (*Applies to permanent pits, temporary pits, and below-grade tanks*)

☐ Chain link, six feet in height, two strands of barbed wire at top (*Required if located within 1000 feet of a permanent residence, school, hospital, institution or church*)

☐ Four foot height, four strands of barbed wire evenly spaced between one and four feet

☐ Alternate. Please specify _____

6.

Netting: Subsection E of 19.15.17.11 NMAC (*Applies to permanent pits and permanent open top tanks*)

- ☐ Screen ☐ Netting ☐ Other _____
- ☐ Monthly inspections (If netting or screening is not physically feasible)

7.

Signs: Subsection C of 19.15.17.11 NMAC

- ☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
- ☐ Signed in compliance with 19.15.16.8 NMAC

8.

Variations and Exceptions:

Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.

Please check a box if one or more of the following is requested, if not leave blank:

- ☐ Variance(s): Requests must be submitted to the appropriate division district for consideration of approval.
- ☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

9.

Siting Criteria (regarding permitting): 19.15.17.10 NMAC

Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Siting criteria does not apply to drying pads or above-grade tanks.

General siting

Ground water is less than 25 feet below the bottom of a low chloride temporary pit or below-grade tank.

- ☐ NM Office of the State Engineer - iWATERS database search; ☐ USGS; ☐ Data obtained from nearby wells

☐ Yes ☒ No
☐ NA

Ground water is less than 50 feet below the bottom of a Temporary pit, permanent pit, or Multi-Well Fluid Management pit.

NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☒ No
☐ NA

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. **(Does not apply to below grade tanks)**

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☒ No

Within the area overlying a subsurface mine. **(Does not apply to below grade tanks)**

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☒ No

Within an unstable area. **(Does not apply to below grade tanks)**

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☒ No

Within a 100-year floodplain. **(Does not apply to below grade tanks)**

- FEMA map

☐ Yes ☒ No

Below Grade Tanks

Within 100 feet of a continuously flowing watercourse, significant watercourse, lake bed, sinkhole, wetland or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a fresh water well used for public or livestock consumption;.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit using Low Chloride Drilling Fluid (maximum chloride content 15,000 mg/liter)

Within 100 feet of a continuously flowing watercourse, or any other significant watercourse or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). (Applies to low chloride temporary pits.)

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a occupied permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 300feet of any other fresh water well or spring, in existence at the time of the initial application.

NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 100 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit Non-low chloride drilling fluid

Within 300 feet of a continuously flowing watercourse, or any other significant watercourse, or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☒ No

Within 500 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 1000 feet of any other fresh water well or spring, in the existence at the time of the initial application;

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within 300 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Permanent Pit or Multi-Well Fluid Management Pit

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

10.

Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☒ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC
- ☒ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☒ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☒ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☒ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

11.

Multi-Well Fluid Management Pit Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ A List of wells with approved application for permit to drill associated with the pit.
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
- ☐ Hydrogeologic Data - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

12.
Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Climatological Factors Assessment
- ☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Quality Control/Quality Assurance Construction and Installation Plan
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Nuisance or Hazardous Odors, including H₂S, Prevention Plan
- ☐ Emergency Response Plan
- ☐ Oil Field Waste Stream Characterization
- ☐ Monitoring and Inspection Plan
- ☐ Erosion Control Plan
- ☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

13.
Proposed Closure: 19.15.17.13 NMAC

Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.

- Type: ☒ Drilling ☐ Workover ☐ Emergency ☐ Cavitation ☐ P&A ☐ Permanent Pit ☐ Below-grade Tank ☐ Multi-well Fluid Management Pit
☐ Alternative
- Proposed Closure Method: ☐ Waste Excavation and Removal
☐ Waste Removal (Closed-loop systems only)
☒ On-site Closure Method (Only for temporary pits and closed-loop systems)
☒ In-place Burial ☐ On-site Trench Burial
☐ Alternative Closure Method

14.
Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) **Instructions:** Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)
- ☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

15.
Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC

Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria require justifications and/or demonstrations of equivalency. Please refer to 19.15.17.10 NMAC for guidance.

Ground water is less than 25 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA
Ground water is between 25-50 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Within 100 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 horizontal feet of a private, domestic fresh water well or spring used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Written confirmation or verification from the municipality; Written approval obtained from the municipality	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 feet of a wetland. US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	

adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☒ No

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☒ No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☒ No

Within a 100-year floodplain.

- FEMA map

☐ Yes ☒ No

16.

On-Site Closure Plan Checklist: (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☒ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection E of 19.15.17.13 NMAC
- ☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of Subsection K of 19.15.17.11 NMAC
- ☒ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☒ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☒ Waste Material Sampling Plan - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)
- ☒ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☒ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☒ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

17.

Operator Application Certification:

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): _____ Title: _____

Signature _____ Date _____

e-mail address: _____ Telephone: _____

18.

OCD Approval: ☐ Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)

OCD Representative Signature: _____ **Approval Date:** _____

Title: _____ **OCD Permit Number:** _____

19.

Closure Report (required within 60 days of closure completion): 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☐ **Closure Completion Date:** _____

20.

Closure Method:

- ☐ Waste Excavation and Removal ☒ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)
- ☐ If different from approved plan, please explain.

21.

Closure Report Attachment Checklist: *Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Proof of Closure Notice (surface owner and division)
- ☐ Proof of Deed Notice (required for on-site closure for private land only)
- ☒ Plot Plan (for on-site closures and temporary pits)
- ☒ Confirmation Sampling Analytical Results (if applicable)
- ☐ Waste Material Sampling Analytical Results (required for on-site closure)
- ☐ Disposal Facility Name and Permit Number
- ☒ Soil Backfilling and Cover Installation
- ☒ Re-vegetation Application Rates and Seeding Technique
- ☐ Site Reclamation (Photo Documentation)


On-site Closure Location: Latitude N 32.18170 Longitude W 103.56956 NAD: 1927 1983 ☒

22.

Operator Closure Certification:

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): Mike Stubblefield Title: Project Manager/R.T. Hicks Consultants, LTD

Signature:  Date September 7, 2016

e-mail address: mike@rthicksconsult.com Telephone: 575-365-5034