

**OCD - HOBBS**  
**04/03/2020**  
**RECEIVED**

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. <b>NMNM127892</b>
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator <b>ASCENT ENERGY LLC 325830</b>		8. Lease Name and Well No. <b>BIG STAGG FED COM 327306 603H</b>
3a. Address <b>1621 18th Street, Suite 200, Denver, CO 80202</b>	3b. Phone No. (include area code) <b>(720) 710-8999</b>	9. API Well No. <b>30-025-47066</b>
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface <b>SWSE / 30 FSL / 2280 FEL / LAT 32.500766 / LONG -103.6272207</b> At proposed prod. zone <b>NWNE / 1220 FNL / 2310 FEL / LAT 32.4828157 / LONG -103.6273337</b>		10. Field and Pool, or Exploratory <b>XXXXX MALAGA/BONESPRING 97895</b>
11. Sec., T. R. M. or Blk. and Survey or Area <b>SEC 1/T21S/R32E/NMP</b>		
14. Distance in miles and direction from nearest town or post office* <b>22 miles</b>		12. County or Parish <b>LEA</b>
13. State <b>NM</b>		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>30 feet</b>	16. No of acres in lease <b>480</b>	17. Spacing Unit dedicated to this well <b>200.0</b>
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>30 feet</b>	19. Proposed Depth <b>11580 feet / 17977 feet</b>	20. BLM/BIA Bond No. in file <b>FED: NMB001698</b>
21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>3794 feet</b>	22. Approximate date work will start* <b>11/01/2019</b>	23. Estimated duration <b>90 days</b>
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) <b>Brian Wood / Ph: (720) 710-8999</b>	Date <b>09/24/2019</b>
Title <b>President</b>		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) <b>Cody Layton / Ph: (575) 234-5959</b>	Date <b>03/06/2020</b>
Title <b>Assistant Field Manager Lands &amp; Minerals</b>		
Office <b>Carlsbad Field Office</b>		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

GCP Rec 04/03/2020

**APPROVED WITH CONDITIONS**  
**Approval Date: 03/06/2020**

**Kz**  
**04/12/2020**

SL

(Continued on page 2)

\*(Instructions on page 2)



APD ID: 10400047855

Submission Date: 09/24/2019

Highlighted data  
reflects the most  
recent changes

Operator Name: ASCENT ENERGY LLC

Well Name: BIG STAGG FED COM

Well Number: 603H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

## Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
545022	PERMIAN	3794	0	0	SANDSTONE	USEABLE WATER	N
545019	RUSTLER	2215	1579	1579	ANHYDRITE	NONE	N
545020	SALADO	2075	1719	1719	SALT	NONE	N
545029	CASTILE	605	3189	3189	ANHYDRITE	NONE	N
545021	YATES	490	3304	3304	OTHER : CARBONATES	NATURAL GAS, OIL	N
545030	CAPITAN REEF	96	3698	3698	LIMESTONE	USEABLE WATER	N
545031	BELL CANYON	-1820	5614	5614	SANDSTONE	NATURAL GAS, OIL	N
545024	CHERRY CANYON	-2085	5879	5879	SANDSTONE	NATURAL GAS, OIL	N
545028	BRUSHY CANYON	-3170	6964	6964	SANDSTONE	NATURAL GAS, OIL	N
545025	BONE SPRING	-5040	8834	8834	LIMESTONE	NATURAL GAS, OIL	N
545026	BONE SPRING	-5165	8959	8959	OTHER : AVALON SHALE	NATURAL GAS, OIL	N
545023	BONE SPRING 1ST	-6000	9794	9794	SANDSTONE	NATURAL GAS, OIL	N
545032	BONE SPRING 2ND	-6278	10072	10072	OTHER : CARBONATE	NATURAL GAS, OIL	N
545027	BONE SPRING 2ND	-6580	10374	10377	SANDSTONE	NATURAL GAS, OIL	N
545424	BONE SPRING 3RD	-7120	10914	10914	OTHER : Carbonate	NATURAL GAS, OIL	N
545425	BONE SPRING 3RD	-7535	11329	11339	SANDSTONE	NATURAL GAS, OIL	Y

## Section 2 - Blowout Prevention

**Operator Name:** ASCENT ENERGY LLC

**Well Name:** BIG STAGG FED COM

**Well Number:** 603H

**Pressure Rating (PSI):** 5M

**Rating Depth:** 10000

**Equipment:** Minimum blow out preventer equipment (BOPE) will consist of a single ram, mud cross and double ram type (10,000 psi WP) preventer, and an annular preventer (5000 psi WP). Both units will be hydraulically operated. Ram type will be equipped with blind rams on the bottom and drill pipe rams on the top. Auxiliary equipment: A Kelly cock will be kept in the drill string at all times. A full opening drill pipe stabbing valve (inside BOP) with proper drill pipe connections will always be on the rig floor. Minimum working pressure of the BOP and related BOPE below the surface casing will be 5000-psi.

**Requesting Variance?** YES

**Variance request:** Variance is requested to use a co-flex line between the BOP and choke manifold instead of using a 4" O. D. steel line. Choke and kill line data book is attached. If this hose is unavailable, then a hose of equal or higher rating will be used. Variance is requested to use a speed head (aka, multi-bowl wellhead). Diagram is attached. After running the 13.375" surface casing, a 13.625" BOP/BOPE system with a >5000 psi WP will be installed on the wellhead system. It will be pressure tested to 250-psi low, followed by a test to 5000-psi high. Pressure test will be repeated at least every 30 days as required by Onshore Order 2. Speed head will be installed by the vendor's representative(s). Well head welding will be monitored by the vendor's representative.

**Testing Procedure:** All BOPE will be tested in accordance with Onshore Order 2. All BOPE will be tested using a conventional test plug – not a cup or J packer. Both surface and intermediate casing will be tested as required by Onshore Order 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

**Choke Diagram Attachment:**

Big\_Stagg\_603H\_BOP\_Choke\_20190924082543.pdf

**BOP Diagram Attachment:**

Big\_Stagg\_603H\_BOP\_Choke\_20190924082550.pdf

### Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1600	0	1600	3794	2194	1600	J-55	54.5	ST&C	1.125	1.125	DRY	1.6	DRY	1.6
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3600	0	3600		194	3600	J-55	40	LT&C	1.125	1.125	DRY	1.6	DRY	1.6
3	INTERMEDIATE	8.75	7.625	NEW	API	Y	0	5600	0	5600		-1806	5600	HCP-110	29.7	OTHER - EZGO FJ3	1.125	1.125	DRY	1.6	DRY	1.6
4	PRODUCTION	6.75	5.5	NEW	API	N	0	17977	0	11580		-7786	17977	HCP-110	20	OTHER - EZGO FJ3	1.125	1.125	DRY	1.6	DRY	1.6

**Casing Attachments**

**Operator Name:** ASCENT ENERGY LLC

**Well Name:** BIG STAGG FED COM

**Well Number:** 603H

### Casing Attachments

---

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Big\_Stagg\_603H\_Casing\_Design\_Assumptions\_20190924083012.pdf

---

**Casing ID:** 2      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Big\_Stagg\_603H\_Casing\_Design\_Assumptions\_20190924083036.pdf

---

**Casing ID:** 3      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

Big\_Stagg\_603H\_7.625in\_Casing\_Spec\_20190924083109.pdf

**Casing Design Assumptions and Worksheet(s):**

Big\_Stagg\_603H\_Casing\_Design\_Assumptions\_20190924083053.pdf

---

**Operator Name:** ASCENT ENERGY LLC

**Well Name:** BIG STAGG FED COM

**Well Number:** 603H

## Casing Attachments

**Casing ID:** 4      **String Type:** PRODUCTION

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

### Casing Design Assumptions and Worksheet(s):

Big\_Stagg\_603H\_Casing\_Design\_Assumptions\_20190924083136.pdf

Big\_Stagg\_603H\_5.5in\_Casing\_Spec\_20190924083143.pdf

## Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1600	865	1.73	13.5	1494	100	CLASS C HALCEM SYSTEM	4% BENTONITE
SURFACE	Tail		0	1600	550	1.33	14.8	733	100	CLASS C HALCEM	None
INTERMEDIATE	Lead		0	3600	700	1.73	12.7	1209	100	CLASS C HALCEM SYSTEM	4% BENTONITE
INTERMEDIATE	Tail		0	3600	485	1.33	14.8	646	100	CLASS C HALCEM SYSTEM	None
INTERMEDIATE	Lead		0	5600	245	2.04	12.7	499	50	CLASS C ECONOCEM HLC	5% SALT + 3% MICROBOND + 3 LB/SK KOL-SEAL + 0.3% HR-800
INTERMEDIATE	Tail		0	5600	155	1.37	14.8	212	50	CLASS C HALCEM SYSTEM	3% MICROBOND
PRODUCTION	Lead		0	1797 7	600	2.89	11	1732	50	NEOCEM PL	3% MICROBOND
PRODUCTION	Tail		0	1797 7	1845	1.47	13.2	2715	50	NEOCEM PL	3% MICROBOND

**Operator Name:** ASCENT ENERGY LLC

**Well Name:** BIG STAGG FED COM

**Well Number:** 603H

## Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** All necessary additives (e. g., barite, bentonite, LCM) to maintain mud properties and meet minimum lost circulation and weight increase needs will be on site at all times.

**Describe the mud monitoring system utilized:** An electronic pit volume totalizer (PVT) will be used to monitor volume, flow rate, pump pressure, and stroke rate.

## Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1600	3600	OTHER : BRINE WATER	10	10							
3600	5600	OTHER : FRESH WATER	8.4	8.6							
5600	1797 7	OTHER : CUT BRINE	8.5	9.2							
0	1600	OTHER : FRESH WATER	8.4	9.6							

## Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

No core, drill stem test, or open hole log is planned.

**List of open and cased hole logs run in the well:**

GAMMA RAY LOG,

**Coring operation description for the well:**

GR-CCL will be run in cased hole during completion phase of operations.

**Operator Name:** ASCENT ENERGY LLC

**Well Name:** BIG STAGG FED COM

**Well Number:** 603H

## Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 5033

**Anticipated Surface Pressure:** 2653

**Anticipated Bottom Hole Temperature(F):** 165

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

Big\_Stagg\_603H\_H2S\_Plan\_20190924083833.pdf

## Section 8 - Other Information

**Proposed horizontal/directional/multi-lateral plan submission:**

Big\_Stagg\_603H\_Horizontal\_Plan\_20190924083939.pdf

**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Big\_Stagg\_603H\_Drill\_Plan\_20190924083957.pdf

Big\_Stagg\_603H\_Co\_Flex\_Certs\_20190924084010.pdf

Big\_Stagg\_Speedhead\_Specs\_20190924084020.pdf

Big\_Stagg\_603H\_Anti\_Collision\_Report\_20190924084236.pdf

**Other Variance attachment:**

Big\_Stagg\_603H\_Casing\_Variance\_20190924084248.pdf

Ascent Energy, LLC  
 Big Stagg Fed Com 603H  
 SHL 30' FSL & 2280' FEL Sec. 1  
 BHL 1270' FNL & 2310' FEL Sec. 13  
 T. 21 S., R. 32 E., Lea County, NM

DRILL PLAN PAGE 1

Drilling Program

1. ESTIMATED TOPS

Formation	TVD	MD	Bearing
Upper Permian sandstone	000'	000'	water
Rustler anhydrite	1579'	1579'	N/A
Salado salt	1719'	1719'	N/A
Castile anhydrite	3189'	3189'	N/A
Yates carbonates	3304'	3304'	hydrocarbons
Capitan Reef limestone	3698'	3698'	water
Bell Canyon sandstone	5614'	5614'	hydrocarbons
Cherry Canyon sandstone	5879'	5879'	hydrocarbons
Brushy Canyon sandstone	6964'	6964'	hydrocarbons
Bone Spring limestone	8834'	8834'	hydrocarbons
Avalon shale of Bone Spring	8959'	8959'	hydrocarbons
1st Bone Spring sandstone	9794'	9794'	hydrocarbons
2 <sup>nd</sup> Bone Spring carbonate	10072'	10072'	hydrocarbons
2 <sup>nd</sup> Bone Spring sandstone	10374'	10377'	hydrocarbons
3rd Bone Spring carbonate	10914'	10914'	hydrocarbons
(KOP	11103'	11103'	hydrocarbons)
3d Bone Spring sandstone	11329'	11339'	hydrocarbons
TD	11580''	17977'	hydrocarbons

2. NOTABLE ZONES

Third Bone Spring sandstone is the goal. Closest water well (CP 00793 POD1) is 0.93 mile NNW. Depth to water was not reported in the 1,000' deep well. Two windmills 1-1/4 miles southeast are 160' to 170' deep.

Ascent Energy, LLC  
Big Stagg Fed Com 603H  
SHL 30' FSL & 2280' FEL Sec. 1  
BHL 1270' FNL & 2310' FEL Sec. 13  
T. 21 S., R. 32 E., Lea County, NM

DRILL PLAN PAGE 2

### 3. PRESSURE CONTROL

Minimum blow out preventer equipment (BOPE) will consist of a single ram, mud cross and double ram type (10,000 psi WP) preventer, and an annular preventer (5000 psi WP). Both units will be hydraulically operated. Ram type will be equipped with blind rams on the bottom and drill pipe rams on the top.

Auxiliary equipment:

A Kelly cock will be kept in the drill string at all times.

A full opening drill pipe stabbing valve (inside BOP) with proper drill pipe connections will always be on the rig floor.

Minimum working pressure of the BOP and related BOPE below the surface casing will be 5000-psi.

All BOPE will be tested in accordance with Onshore Order 2. All BOPE will be tested using a conventional test plug – not a cup or J packer. Both surface and intermediate casing will be tested as required by Onshore Order 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

Before drilling out the surface casing:

ram type BOP and accessory equipment will be tested to 5000/250 psig

annular preventer will be tested to 3500/250 psig

surface casing will be tested to 1500 psi for 30 minutes

Before drilling out the intermediate casing:

ram type BOP and accessory equipment will be tested to 5000/250 psig

annular preventer will be tested to 3500/250 psig

intermediate casing will be tested to 2000 psi for 30 minutes

Intermediate casing will be landed using a mandrel hanger and separate pack off. After installation, the pack off and lower flange will be pressure tested to 5000 psi. A hydraulically operated choke will be installed before drilling out of the intermediate casing shoe.

Ascent Energy, LLC  
 Big Stagg Fed Com 603H  
 SHL 30' FSL & 2280' FEL Sec. 1  
 BHL 1270' FNL & 2310' FEL Sec. 13  
 T. 21 S., R. 32 E., Lea County, NM

## DRILL PLAN PAGE 3

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each TOOH. These checks will be noted on the daily tour sheets.

Variance is requested to use a co-flex line between the BOP and choke manifold instead of using a 4" O. D. steel line. Choke and kill line data book is attached. If this hose is unavailable, then a hose of equal or higher rating will be used.

Variance is requested to use a speed head (aka, multi-bowl wellhead). Diagram is attached. After running the 13.375" surface casing, a 13.625" BOP/BOPE system with a  $\geq 5000$  psi WP will be installed on the wellhead system. It will be pressure tested to 250-psi low, followed by a test to 5000-psi high. Pressure test will be repeated at least every 30 days as required by Onshore Order 2.

Speed head will be installed by the vendor's representative(s). Well head welding will be monitored by the vendor's representative.

### 4. CASING & CEMENT

All casing will be API and new. See attached casing assumption worksheet.

Hole O. D.	Set MD	Set TVD	Casing O. D.	Weight (lb/ft)	Grade	Joint	Collapse	Burst	Tension
17.5"	0' - 1600'	0' - 1600'	Surface 13.375"	54.5	J-55	STC	1.125	1.125	1.6
12.25"	0' - 3600'	0' - 3600'	Inter. 1 9.625"	40	J-55	LTC	1.125	1.125	1.6
8.75"	0' - 5600'	0' - 5600'	Inter. 2 7.625"	29.7	HCP-110	EZGO FJ3	1.125	1.125	1.6
6.75"	0' - 17977'	0' - 11580'	Product. 5.5"	20	HCP-110	EZGO FJ3	1.125	1.125	1.6

Variance is requested to waive centralizer requirements for the 7.625" flush joint casing. An expansion additive will be used in the cement slurry for the entire length of the 8.75" hole to maximize cement bond and zone isolation.

Ascent Energy, LLC  
 Big Stagg Fed Com 603H  
 SHL 30' FSL & 2280' FEL Sec. 1  
 BHL 1270' FNL & 2310' FEL Sec. 13  
 T. 21 S., R. 32 E., Lea County, NM

## DRILL PLAN PAGE 4

Variance is also requested to waive centralizers requirements for the 5.5" casing. An expansion additive will be used in the cement slurry for the entire length of the 6.75" hole to maximize cement bond and zone isolation.

Name	Type	Sacks	Yield	Cu. Ft.	Weight	Blend
Surface	Lead	865	1.728	1494	13.5	Class C HALCEM system + 4% bentonite
	Tail	550	1.332	733	14.8	Class C HALCEM system
TOC = GL		100% Excess				
Intermediate 1	Lead	700	1.728	1209	12.7	Class C HALCEM system + 4% bentonite
	Tail	485	1.332	646	14.8	Class C HALCEM system
TOC = GL		100% Excess				
Intermediate 2	Lead	245	2.039	499	12.7	Class C EconoCem HLC + 5% salt + 3% Microbond + 3 lb/sk Kol-seal + 0.3% HR-800
	Tail	155	1.368	212	14.8	Class C HALCEM system + 3% Microbond
TOC = GL		50% Excess				
Production	Lead	600	2.887	1732	11.0	NeoCem PL + 3% Microbond
	Tail	1845	1.472	2715	13.2	NeoCem PT + 3% Microbond
TOC = GL		50% Excess				

### 5. MUD PROGRAM

An electronic pit volume totalizer (PVT) will be used to monitor volume, flow rate, pump pressure, and stroke rate. All necessary additives (e. g., barite, bentonite, LCM) to maintain mud properties and meet minimum lost circulation and weight increase needs will be on site at all times. Mud program may change due to hole conditions. A closed loop system will be used.

Ascent Energy, LLC  
Big Stagg Fed Com 603H  
SHL 30' FSL & 2280' FEL Sec. 1  
BHL 1270' FNL & 2310' FEL Sec. 13  
T. 21 S., R. 32 E., Lea County, NM

DRILL PLAN PAGE 5

Type	Interval (MD)	lb/gal	Viscosity	Fluid Loss
fresh water	0' - 1600'	8.4 – 9.6	34-38	N/C
brine water	1600' - 3600'	10	28-34	N/C
fresh water	3600' – 5600'	8.4 – 8.6	28-34	N/C
cut brine/gel	5600' - 17977'	8.5 – 9.2	28-34	N/C

#### 6. CORES, TESTS, & LOGS

No core, drill stem test, or open hole log is planned.

GR-CCL will be run in cased hole during completion phase of operations.

#### 7. DOWN HOLE CONDITIONS

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is  $\approx 5033$  psig. Expected bottom hole temperature is  $\approx 165^{\circ}$  F.

H2S monitoring and detection equipment will be used from surface casing point to TD.

#### 8. OTHER INFORMATION

Anticipated spud date is upon approval. It is expected it will take  $\approx 3$  months to drill and complete the well.

Variance is requested for the option to contract a surface rig to drill surface hole, set surface casing, and cement the surface casing. If the timing between rigs is such that Ascent would not be able to preset the surface casing, then the primary rig will MIRU and drill the well in its entirety.







Project: LEA COUNTY, NEW MEXICO (NAD 83)  
Site: SEC. 1 T21S R32E N.M.PM.  
Well: BIG STAGG FED COM 603H  
Wellbore: ORIGINAL WELLBORE  
Design: PROPOSAL #1

ANNOTATIONS									PROPOSED LOCAL COORDINATES:  SHL: 30ft FSL & 2280ft FEL Sec 1  SHL: 30ft FSL & 2280ft FEL Sec 1  LP: 427.46ft FNL & 2310ft FEL Sec 12  BHL *NEW*: 1270ft FNL & 2310ft FEL Sec 13
TVD	MD	Inc	Azi	+N/-S	+E/-W	VSect	Dep	Annotation	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL: 30ft FSL & 2280ft FEL of Sec 1	
3000.00	3000.00	0.00	0.00	0.00	0.00	0.00	0.00	START NUDGE (1.5"/100ft BUR)	
3199.91	3200.00	3.00	303.54	2.89	-4.36	-2.89	5.23	EOB TO 3" INC	
3687.64	3688.40	3.00	303.54	17.02	-25.67	-17.00	30.80	END OF TANGENT	
3887.55	3888.40	0.00	0.00	19.91	-30.03	-19.89	36.03	EOD TO VERTICAL	
11102.54	11103.39	0.00	0.00	19.91	-30.03	-19.89	36.03	KOP (12"/100ft BUR)	
11450.01	11492.54	46.70	180.04	-130.09	-30.13	130.11	186.12	FTP: 100ft FNL & 2310ft FEL of Sec 12	
11580.00	11853.39	90.00	180.04	-457.55	-30.36	457.58	513.50	HZ LP: 427.46ft FNL & 2310ft FEL of Sec 12	
11580.00	17926.68	90.00	180.04	-6530.84	-34.86	6530.86	6586.78	LTP: 1220ft FNL & 2310ft FEL of Sec 13	
11580.00	17976.68	90.00	180.04	-6580.84	-34.90	6580.86	6636.78	BHL *NEW*: 1270ft FNL & 2310ft FEL of Sec 13	

#### WELLBORE TARGET DETAILS (LAT/LONG)

Name	TVD	+N/-S	+E/-W	Latitude	Longitude
KOP - BIG STAGG FED COM 603H	11102.54	19.91	-30.03	32.500821	-103.627318
LTP - BIG STAGG FED COM 603H	11580.00	-6530.84	-34.86	32.482816	-103.627334
BHL *NEW* - BIG STAGG FED COM 603H	11580.00	-6580.84	-34.90	32.482678	-103.627334
FTP - BIG STAGG FED COM 603H	11450.02	-130.09	-30.13	32.500408	-103.627318
HZ LP - BIG STAGG FED COM 603H	11580.00	-457.55	-30.36	32.499508	-103.627319



# Planning Report



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

<b>Project</b>	LEA COUNTY, NEW MEXICO (NAD 83)		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		Using geodetic scale factor

Site	SEC. 1 T21S R32E N.M.PM.				
Site Position:		Northing:	546,845.25 usft	Latitude:	32.501395
From:	Lat/Long	Easting:	756,934.17 usft	Longitude:	-103.634008
Position Uncertainty:	0.00 usft	Slot Radius:	1.10 ft	Grid Convergence:	0.38 °

Well	BIG STAGG FED COM 603H					
Well Position	+N/-S	-228.79 usft	Northing:	546,630.20 usft	Latitude:	32.500766
	+E/-W	2,092.78 usft	Easting:	759,028.33 usft	Longitude:	-103.627221
Position Uncertainty		0.00 usft	Wellhead Elevation:	usft	Ground Level:	3,794.00 usft

<b>Wellbore</b>	ORIGINAL WELLBORE				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2015	09/08/2019	6.77	60.28	47,872

<b>Design</b>	PROPOSAL #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (usft)</b>	<b>+N/-S (usft)</b>	<b>+E/-W (usft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	180.04

<b>Plan Sections</b>											
MD (usft)	Inc (°)	Azi (°)	Vertical Depth	SS (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usf)	Build Rate (°/100usf)	Turn Rate (°/100usf)	TFO (°)	Target
0.00	0.00	0.00	0.00	-3,819.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,000.00	0.00	0.00	3,000.00	-819.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,200.00	3.00	303.54	3,199.91	-619.09	2.89	-4.36	1.50	1.50	0.00	303.54	
3,688.40	3.00	303.54	3,687.64	-131.36	17.02	-25.67	0.00	0.00	0.00	0.00	
3,888.40	0.00	0.00	3,887.55	68.55	19.91	-30.03	1.50	-1.50	0.00	180.00	
11,103.39	0.00	0.00	11,102.54	7,283.54	19.91	-30.03	0.00	0.00	0.00	0.00	KOP - BIG STAGG
11,853.39	90.00	180.04	11,580.00	7,761.00	-457.55	-30.36	12.00	12.00	0.00	180.04	
17,926.68	90.00	180.04	11,580.00	7,761.00	-6,530.84	-34.86	0.00	0.00	0.00	88.93	LTP - BIG STAGG
17,976.68	90.00	180.04	11,580.00	7,761.00	-6,580.84	-34.90	0.01	0.00	-0.01	-92.53	BHL - BIG STAGG

# Planning Report



Database:	Database 1	Local Co-ordinate Reference:	Well BIG STAGG FED COM 603H
Company:	ASCENT ENERGY	TVD Reference:	KB 25' @ 3819.00usft (Original Well Elev)
Project:	LEA COUNTY, NEW MEXICO (NAD 83)	MD Reference:	KB 25' @ 3819.00usft (Original Well Elev)
Site:	SEC. 1 T21S R32E N.M.PM.	North Reference:	True
Well:	BIG STAGG FED COM 603H	Survey Calculation Method:	Minimum Curvature
Wellbore:	ORIGINAL WELLBORE		
Design:	PROPOSAL #1		

## Planned Survey

MD (usft)	Inc (°)	Azi (°)	TVD (usft)	SS (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
<b>SHL: 30ft FSL &amp; 2280ft FEL of Sec 1</b>										
0.00	0.00	0.00	0.00	3,819.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	3,719.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	3,619.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	3,519.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	3,419.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	3,319.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	3,219.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	3,119.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	3,019.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	2,919.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	2,819.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	2,719.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	2,619.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	2,519.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	2,419.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	2,319.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Rustler</b>										
1,579.00	0.00	0.00	1,579.00	2,240.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	2,219.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	2,119.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Salado</b>										
1,719.00	0.00	0.00	1,719.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	2,019.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	1,919.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	1,819.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	1,719.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	1,619.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	1,519.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	1,419.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	1,319.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	1,219.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	1,119.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	1,019.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	919.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>START NUDGE (1.5°/100ft BUR)</b>										
3,000.00	0.00	0.00	3,000.00	819.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	1.50	303.54	3,099.99	719.01	0.72	-1.09	-0.72	1.50	1.50	0.00
<b>Castille</b>										
3,189.08	2.84	303.54	3,189.00	630.00	2.59	-3.90	-2.58	1.50	1.50	0.00
<b>EOB TO 3° INC</b>										
3,200.00	3.00	303.54	3,199.91	619.09	2.89	-4.36	-2.89	1.50	1.50	0.00
3,300.00	3.00	303.54	3,299.77	519.23	5.78	-8.72	-5.78	0.00	0.00	0.00
<b>Yates</b>										
3,304.23	3.00	303.54	3,304.00	515.00	5.91	-8.91	-5.90	0.00	0.00	0.00
3,400.00	3.00	303.54	3,399.63	419.37	8.68	-13.09	-8.67	0.00	0.00	0.00
3,500.00	3.00	303.54	3,499.50	319.50	11.57	-17.45	-11.56	0.00	0.00	0.00
3,600.00	3.00	303.54	3,599.36	219.64	14.46	-21.81	-14.45	0.00	0.00	0.00
<b>END OF TANGENT</b>										
3,688.40	3.00	303.54	3,687.64	131.36	17.02	-25.67	-17.00	0.00	0.00	0.00
<b>Capitan Reef</b>										
3,698.77	2.84	303.54	3,698.00	121.00	17.31	-26.11	-17.29	1.50	-1.50	0.00
3,700.00	2.83	303.54	3,699.22	119.78	17.34	-26.16	-17.32	1.50	-1.50	0.00

# Planning Report



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

## Planned Survey

MD (usft)	Inc (°)	Azi (°)	TVD (usft)	SS (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
3,800.00	1.33	303.54	3,799.16	19.84	19.34	-29.18	-19.32	1.50	-1.50	0.00
<b>EOD TO VERTICAL</b>										
3,888.40	0.00	0.00	3,887.55	-68.55	19.91	-30.03	-19.89	1.50	-1.50	0.00
3,900.00	0.00	0.00	3,899.15	-80.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,000.00	0.00	0.00	3,999.15	-180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,100.00	0.00	0.00	4,099.15	-280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,200.00	0.00	0.00	4,199.15	-380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,300.00	0.00	0.00	4,299.15	-480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,400.00	0.00	0.00	4,399.15	-580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,500.00	0.00	0.00	4,499.15	-680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,600.00	0.00	0.00	4,599.15	-780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,700.00	0.00	0.00	4,699.15	-880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,800.00	0.00	0.00	4,799.15	-980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
4,900.00	0.00	0.00	4,899.15	-1,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,000.00	0.00	0.00	4,999.15	-1,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,100.00	0.00	0.00	5,099.15	-1,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,200.00	0.00	0.00	5,199.15	-1,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,300.00	0.00	0.00	5,299.15	-1,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,400.00	0.00	0.00	5,399.15	-1,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,500.00	0.00	0.00	5,499.15	-1,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,600.00	0.00	0.00	5,599.15	-1,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>Top Delaware Sand</b>										
5,614.85	0.00	0.00	5,614.00	-1,795.00	19.91	-30.03	-19.89	0.00	0.00	0.00
5,700.00	0.00	0.00	5,699.15	-1,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
5,800.00	0.00	0.00	5,799.15	-1,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>Cherry Canyon</b>										
5,879.85	0.00	0.00	5,879.00	-2,060.00	19.91	-30.03	-19.89	0.00	0.00	0.00
5,900.00	0.00	0.00	5,899.15	-2,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,000.00	0.00	0.00	5,999.15	-2,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,100.00	0.00	0.00	6,099.15	-2,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,200.00	0.00	0.00	6,199.15	-2,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,300.00	0.00	0.00	6,299.15	-2,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,400.00	0.00	0.00	6,399.15	-2,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,500.00	0.00	0.00	6,499.15	-2,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,600.00	0.00	0.00	6,599.15	-2,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,700.00	0.00	0.00	6,699.15	-2,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,800.00	0.00	0.00	6,799.15	-2,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
6,900.00	0.00	0.00	6,899.15	-3,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>Brushy Canyon</b>										
6,964.85	0.00	0.00	6,964.00	-3,145.00	19.91	-30.03	-19.89	0.00	0.00	0.00
7,000.00	0.00	0.00	6,999.15	-3,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,100.00	0.00	0.00	7,099.15	-3,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,200.00	0.00	0.00	7,199.15	-3,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,300.00	0.00	0.00	7,299.15	-3,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,400.00	0.00	0.00	7,399.15	-3,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,500.00	0.00	0.00	7,499.15	-3,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,600.00	0.00	0.00	7,599.15	-3,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,700.00	0.00	0.00	7,699.15	-3,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,800.00	0.00	0.00	7,799.15	-3,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
7,900.00	0.00	0.00	7,899.15	-4,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,000.00	0.00	0.00	7,999.15	-4,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,100.00	0.00	0.00	8,099.15	-4,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,200.00	0.00	0.00	8,199.15	-4,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

## Planned Survey

MD (usft)	Inc (°)	Azi (°)	TVD (usft)	SS (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,300.00	0.00	0.00	8,299.15	-4,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,400.00	0.00	0.00	8,399.15	-4,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,500.00	0.00	0.00	8,499.15	-4,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,600.00	0.00	0.00	8,599.15	-4,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,700.00	0.00	0.00	8,699.15	-4,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
8,800.00	0.00	0.00	8,799.15	-4,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>Bone Spring Lime</b>										
8,834.85	0.00	0.00	8,834.00	-5,015.00	19.91	-30.03	-19.89	0.00	0.00	0.00
8,900.00	0.00	0.00	8,899.15	-5,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>Avalon</b>										
8,959.85	0.00	0.00	8,959.00	-5,140.00	19.91	-30.03	-19.89	0.00	0.00	0.00
9,000.00	0.00	0.00	8,999.15	-5,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,100.00	0.00	0.00	9,099.15	-5,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,200.00	0.00	0.00	9,199.15	-5,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,300.00	0.00	0.00	9,299.15	-5,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,400.00	0.00	0.00	9,399.15	-5,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,500.00	0.00	0.00	9,499.15	-5,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,600.00	0.00	0.00	9,599.15	-5,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,700.00	0.00	0.00	9,699.15	-5,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>1st Bone Spring Sand</b>										
9,794.85	0.00	0.00	9,794.00	-5,975.00	19.91	-30.03	-19.89	0.00	0.00	0.00
9,800.00	0.00	0.00	9,799.15	-5,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
9,900.00	0.00	0.00	9,899.15	-6,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,000.00	0.00	0.00	9,999.15	-6,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>2nd Bone Spring Carb</b>										
10,072.85	0.00	0.00	10,072.00	-6,253.00	19.91	-30.03	-19.89	0.00	0.00	0.00
10,100.00	0.00	0.00	10,099.15	-6,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,200.00	0.00	0.00	10,199.15	-6,380.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,300.00	0.00	0.00	10,299.15	-6,480.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>2nd Bone Spring Sand</b>										
10,374.85	0.00	0.00	10,374.00	-6,555.00	19.91	-30.03	-19.89	0.00	0.00	0.00
10,400.00	0.00	0.00	10,399.15	-6,580.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,500.00	0.00	0.00	10,499.15	-6,680.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,600.00	0.00	0.00	10,599.15	-6,780.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,700.00	0.00	0.00	10,699.15	-6,880.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,800.00	0.00	0.00	10,799.15	-6,980.15	19.91	-30.03	-19.89	0.00	0.00	0.00
10,900.00	0.00	0.00	10,899.15	-7,080.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>3rd Bone Spring Carb</b>										
10,914.85	0.00	0.00	10,914.00	-7,095.00	19.91	-30.03	-19.89	0.00	0.00	0.00
11,000.00	0.00	0.00	10,999.15	-7,180.15	19.91	-30.03	-19.89	0.00	0.00	0.00
11,100.00	0.00	0.00	11,099.15	-7,280.15	19.91	-30.03	-19.89	0.00	0.00	0.00
<b>KOP (12°/100ft BUR)</b>										
11,103.39	0.00	0.00	11,102.54	-7,283.54	19.91	-30.03	-19.89	0.00	0.00	0.00
11,200.00	11.59	180.04	11,198.49	-7,379.49	10.17	-30.04	-10.15	12.00	12.00	0.00
11,300.00	23.59	180.04	11,293.64	-7,474.64	-20.00	-30.06	20.02	12.00	12.00	0.00
<b>3rd Bone Spring Sand</b>										
11,339.34	28.31	180.04	11,329.00	-7,510.00	-37.21	-30.07	37.23	12.00	12.00	0.00
11,400.00	35.59	180.04	11,380.44	-7,561.44	-69.29	-30.09	69.31	12.00	12.00	0.00
<b>FTP: 100ft FNL &amp; 2310ft FEL of Sec 12</b>										
11,492.54	46.70	180.04	11,450.01	-7,631.01	-130.09	-30.13	130.11	12.00	12.00	0.00
11,500.00	47.59	180.04	11,455.09	-7,636.09	-135.56	-30.14	135.58	12.00	12.00	0.00
11,600.00	59.59	180.04	11,514.33	-7,695.33	-215.89	-30.19	215.91	12.00	12.00	0.00

# Planning Report



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

## Planned Survey

MD (usft)	Inc (°)	Azi (°)	TVD (usft)	SS (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
<b>3rd Bone Spring Sand Top Target</b>										
11,695.08	71.00	180.04	11,554.00	-7,735.00	-302.13	-30.25	302.15	12.00	12.00	0.00
11,700.00	71.59	180.04	11,555.58	-7,736.58	-306.79	-30.26	306.81	12.00	12.00	0.00
11,800.00	83.59	180.04	11,577.02	-7,758.02	-404.27	-30.33	404.29	12.00	12.00	0.00
<b>HZ LP: 427.46ft FNL &amp; 2310ft FEL of Sec 12</b>										
11,853.39	90.00	180.04	11,580.00	-7,761.00	-457.55	-30.36	457.58	12.00	12.00	0.00
11,900.00	90.00	180.04	11,580.00	-7,761.00	-504.16	-30.40	504.18	0.00	0.00	0.00
12,000.00	90.00	180.04	11,580.00	-7,761.00	-604.16	-30.47	604.18	0.00	0.00	0.00
12,100.00	90.00	180.04	11,580.00	-7,761.00	-704.16	-30.54	704.18	0.00	0.00	0.00
12,200.00	90.00	180.04	11,580.00	-7,761.00	-804.16	-30.61	804.18	0.00	0.00	0.00
12,300.00	90.00	180.04	11,580.00	-7,761.00	-904.16	-30.68	904.18	0.00	0.00	0.00
12,400.00	90.00	180.04	11,580.00	-7,761.00	-1,004.16	-30.75	1,004.18	0.00	0.00	0.00
12,500.00	90.00	180.04	11,580.00	-7,761.00	-1,104.16	-30.82	1,104.18	0.00	0.00	0.00
12,600.00	90.00	180.04	11,580.00	-7,761.00	-1,204.16	-30.89	1,204.18	0.00	0.00	0.00
12,700.00	90.00	180.04	11,580.00	-7,761.00	-1,304.16	-30.96	1,304.18	0.00	0.00	0.00
12,800.00	90.00	180.04	11,580.00	-7,761.00	-1,404.16	-31.03	1,404.18	0.00	0.00	0.00
12,900.00	90.00	180.04	11,580.00	-7,761.00	-1,504.16	-31.10	1,504.18	0.00	0.00	0.00
13,000.00	90.00	180.04	11,580.00	-7,761.00	-1,604.16	-31.17	1,604.18	0.00	0.00	0.00
13,100.00	90.00	180.04	11,580.00	-7,761.00	-1,704.16	-31.24	1,704.18	0.00	0.00	0.00
13,200.00	90.00	180.04	11,580.00	-7,761.00	-1,804.16	-31.32	1,804.18	0.00	0.00	0.00
13,300.00	90.00	180.04	11,580.00	-7,761.00	-1,904.16	-31.39	1,904.18	0.00	0.00	0.00
13,400.00	90.00	180.04	11,580.00	-7,761.00	-2,004.16	-31.46	2,004.18	0.00	0.00	0.00
13,500.00	90.00	180.04	11,580.00	-7,761.00	-2,104.16	-31.53	2,104.18	0.00	0.00	0.00
13,600.00	90.00	180.04	11,580.00	-7,761.00	-2,204.16	-31.60	2,204.18	0.00	0.00	0.00
13,700.00	90.00	180.04	11,580.00	-7,761.00	-2,304.16	-31.68	2,304.18	0.00	0.00	0.00
13,800.00	90.00	180.04	11,580.00	-7,761.00	-2,404.16	-31.75	2,404.18	0.00	0.00	0.00
13,900.00	90.00	180.04	11,580.00	-7,761.00	-2,504.16	-31.82	2,504.18	0.00	0.00	0.00
14,000.00	90.00	180.04	11,580.00	-7,761.00	-2,604.16	-31.89	2,604.18	0.00	0.00	0.00
14,100.00	90.00	180.04	11,580.00	-7,761.00	-2,704.16	-31.97	2,704.18	0.00	0.00	0.00
14,200.00	90.00	180.04	11,580.00	-7,761.00	-2,804.16	-32.04	2,804.18	0.00	0.00	0.00
14,300.00	90.00	180.04	11,580.00	-7,761.00	-2,904.16	-32.11	2,904.18	0.00	0.00	0.00
14,400.00	90.00	180.04	11,580.00	-7,761.00	-3,004.16	-32.19	3,004.18	0.00	0.00	0.00
14,500.00	90.00	180.04	11,580.00	-7,761.00	-3,104.16	-32.26	3,104.18	0.00	0.00	0.00
14,600.00	90.00	180.04	11,580.00	-7,761.00	-3,204.16	-32.33	3,204.18	0.00	0.00	0.00
14,700.00	90.00	180.04	11,580.00	-7,761.00	-3,304.16	-32.41	3,304.18	0.00	0.00	0.00
14,800.00	90.00	180.04	11,580.00	-7,761.00	-3,404.16	-32.48	3,404.18	0.00	0.00	0.00
14,900.00	90.00	180.04	11,580.00	-7,761.00	-3,504.16	-32.56	3,504.18	0.00	0.00	0.00
15,000.00	90.00	180.04	11,580.00	-7,761.00	-3,604.16	-32.63	3,604.18	0.00	0.00	0.00
15,100.00	90.00	180.04	11,580.00	-7,761.00	-3,704.16	-32.70	3,704.18	0.00	0.00	0.00
15,200.00	90.00	180.04	11,580.00	-7,761.00	-3,804.16	-32.78	3,804.18	0.00	0.00	0.00
15,300.00	90.00	180.04	11,580.00	-7,761.00	-3,904.16	-32.85	3,904.18	0.00	0.00	0.00
15,400.00	90.00	180.04	11,580.00	-7,761.00	-4,004.16	-32.93	4,004.18	0.00	0.00	0.00
15,500.00	90.00	180.04	11,580.00	-7,761.00	-4,104.16	-33.00	4,104.18	0.00	0.00	0.00
15,600.00	90.00	180.04	11,580.00	-7,761.00	-4,204.16	-33.08	4,204.18	0.00	0.00	0.00
15,700.00	90.00	180.04	11,580.00	-7,761.00	-4,304.16	-33.15	4,304.18	0.00	0.00	0.00
15,800.00	90.00	180.04	11,580.00	-7,761.00	-4,404.16	-33.23	4,404.18	0.00	0.00	0.00
15,900.00	90.00	180.04	11,580.00	-7,761.00	-4,504.16	-33.30	4,504.18	0.00	0.00	0.00
16,000.00	90.00	180.04	11,580.00	-7,761.00	-4,604.16	-33.38	4,604.18	0.00	0.00	0.00
16,100.00	90.00	180.04	11,580.00	-7,761.00	-4,704.16	-33.45	4,704.18	0.00	0.00	0.00
16,200.00	90.00	180.04	11,580.00	-7,761.00	-4,804.16	-33.53	4,804.18	0.00	0.00	0.00
16,300.00	90.00	180.04	11,580.00	-7,761.00	-4,904.16	-33.61	4,904.18	0.00	0.00	0.00
16,400.00	90.00	180.04	11,580.00	-7,761.00	-5,004.16	-33.68	5,004.18	0.00	0.00	0.00
16,500.00	90.00	180.04	11,580.00	-7,761.00	-5,104.16	-33.76	5,104.18	0.00	0.00	0.00
16,600.00	90.00	180.04	11,580.00	-7,761.00	-5,204.16	-33.84	5,204.18	0.00	0.00	0.00

# Planning Report



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

## Planned Survey

MD (usft)	Inc (°)	Azi (°)	TVD (usft)	SS (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
16,700.00	90.00	180.04	11,580.00	-7,761.00	-5,304.16	-33.91	5,304.18	0.00	0.00	0.00
16,800.00	90.00	180.04	11,580.00	-7,761.00	-5,404.16	-33.99	5,404.18	0.00	0.00	0.00
16,900.00	90.00	180.04	11,580.00	-7,761.00	-5,504.16	-34.07	5,504.18	0.00	0.00	0.00
17,000.00	90.00	180.04	11,580.00	-7,761.00	-5,604.16	-34.14	5,604.18	0.00	0.00	0.00
17,100.00	90.00	180.04	11,580.00	-7,761.00	-5,704.16	-34.22	5,704.18	0.00	0.00	0.00
17,200.00	90.00	180.04	11,580.00	-7,761.00	-5,804.16	-34.30	5,804.18	0.00	0.00	0.00
17,300.00	90.00	180.04	11,580.00	-7,761.00	-5,904.16	-34.37	5,904.18	0.00	0.00	0.00
17,400.00	90.00	180.04	11,580.00	-7,761.00	-6,004.16	-34.45	6,004.18	0.00	0.00	0.00
17,500.00	90.00	180.04	11,580.00	-7,761.00	-6,104.16	-34.53	6,104.18	0.00	0.00	0.00
17,600.00	90.00	180.04	11,580.00	-7,761.00	-6,204.16	-34.61	6,204.18	0.00	0.00	0.00
17,700.00	90.00	180.04	11,580.00	-7,761.00	-6,304.16	-34.69	6,304.18	0.00	0.00	0.00
17,800.00	90.00	180.04	11,580.00	-7,761.00	-6,404.16	-34.76	6,404.18	0.00	0.00	0.00
17,900.00	90.00	180.04	11,580.00	-7,761.00	-6,504.16	-34.84	6,504.18	0.00	0.00	0.00
<b>LTP: 1220ft FNL &amp; 2310ft FEL of Sec 13</b>										
17,926.68	90.00	180.04	11,580.00	-7,761.00	-6,530.84	-34.86	6,530.86	0.00	0.00	0.00
<b>BHL *NEW*: 1270ft FNL &amp; 2310ft FEL of Sec 13</b>										
17,976.68	90.00	180.04	11,580.00	-7,761.00	-6,580.84	-34.90	6,580.86	0.01	0.00	-0.01

## Formations

MD (usft)	TVD (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,579.00	1,579.00	Rustler		0.00	
1,719.00	1,719.00	Salado		0.00	
3,189.08	3,189.00	Castille		0.00	
3,304.23	3,304.00	Yates		0.00	
3,698.77	3,698.00	Capitan Reef		0.00	
5,614.85	5,614.00	Top Delaware Sand		0.00	
5,879.85	5,879.00	Cherry Canyon		0.00	
6,964.85	6,964.00	Brushy Canyon		0.00	
8,834.85	8,834.00	Bone Spring Lime		0.00	
8,959.85	8,959.00	Avalon		0.00	
9,794.85	9,794.00	1st Bone Spring Sand		0.00	
10,072.85	10,072.00	2nd Bone Spring Carb		0.00	
10,374.85	10,374.00	2nd Bone Spring Sand		0.00	
10,914.85	10,914.00	3rd Bone Spring Carb		0.00	
11,339.34	11,329.00	3rd Bone Spring Sand		0.00	
11,695.08	11,554.00	3rd Bone Spring Sand Top Target		0.00	

# Planning Report



<b>Database:</b>	Database 1	<b>Local Co-ordinate Reference:</b>	Well BIG STAGG FED COM 603H
<b>Company:</b>	ASCENT ENERGY	<b>TVD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Project:</b>	LEA COUNTY, NEW MEXICO (NAD 83)	<b>MD Reference:</b>	KB 25' @ 3819.00usft (Original Well Elev)
<b>Site:</b>	SEC. 1 T21S R32E N.M.PM.	<b>North Reference:</b>	True
<b>Well:</b>	BIG STAGG FED COM 603H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	ORIGINAL WELLBORE		
<b>Design:</b>	PROPOSAL #1		

Plan Annotations				
MD (usft)	TVD (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
0.00	0.00	0.00	0.00	SHL: 30ft FSL & 2280ft FEL of Sec 1
3,000.00	3,000.00	0.00	0.00	START NUDGE (1.5"/100ft BUR)
3,200.00	3,199.91	2.89	-4.36	EOB TO 3" INC
3,688.40	3,687.64	17.02	-25.67	END OF TANGENT
3,888.40	3,887.55	19.91	-30.03	EOD TO VERTICAL
11,103.39	11,102.54	19.91	-30.03	KOP (12"/100ft BUR)
11,492.54	11,450.01	-130.09	-30.13	FTP: 100ft FNL & 2310ft FEL of Sec 12
11,853.39	11,580.00	-457.55	-30.36	HZ LP: 427.46ft FNL & 2310ft FEL of Sec 12
17,926.68	11,580.00	-6,530.84	-34.86	LTP: 1220ft FNL & 2310ft FEL of Sec 13
17,976.68	11,580.00	-6,580.84	-34.90	BHL *NEW*: 1270ft FNL & 2310ft FEL of Sec 13

# PECOS DISTRICT

## DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>Ascent Energy LLC</b>
<b>LEASE NO.:</b>	<b>NMNM127892</b>
<b>WELL NAME &amp; NO.:</b>	<b>Big Stagg Federal Com 603H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>30'/S &amp; 2280'/E</b>
<b>BOTTOM HOLE FOOTAGE:</b>	<b>1220'/N &amp; 2310'/E</b>
<b>LOCATION:</b>	<b>Section 1, T.21 S., R.32 E., NMPM</b>
<b>COUNTY:</b>	<b>Lea County, New Mexico</b>

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input type="radio"/> None	<input type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input checked="" type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

### A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Bone Spring** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

### B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **1665 feet** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of

- 24 hours in the Potash Area** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The **9-5/8** inch Intermediate 1 casing shall be set at approximately **3800 feet** and the minimum required fill of cement behind the Intermediate 1 casing is:

### **Option 1**

- Cement to surface. If cement does not circulate see B.1.a, c-d above.  
**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

### **Option 2**

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
  - b. Second stage above DV tool:
    - Cement to surface. If cement does not circulate, contact the appropriate BLM office.  
**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**
- ❖ In R111 Potash Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- ❖ In Capitan Reef Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- ❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:  
**(Use this for 3 string wells in the Capitan Reef, if 4 string well ensure FW based mud used across the capitan interval)**

- Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
- Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.

3. The minimum required fill of cement behind the **7-5/8 inch** Intermediate 2 casing is:

**Option 1**

- Cement to surface. If cement does not circulate see B.1.a, c-d above.  
**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

**Option 2**

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- Second stage above DV tool:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.  
**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

**Excess is at 20% for the Intermediate 2 Casing. Additional cement may be needed.**

4. The minimum required fill of cement behind the **5-1/2 inch** production casing is:

**Option 1**

- Cement should tie-back at least **50 feet** on top of Capitan Reef top. If cement does not circulate see B.1.a, c-d above.

**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

## **Option 2**

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. Second stage above DV tool:
  - Cement should tie-back at least **50 feet** on top of Capitan Reef top. If cement does not circulate see B.1.a, c-d above.  
**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

## **C. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

## **D. SPECIAL REQUIREMENT (S)**

### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

## B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of **4** hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including

lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**YJ 02/20/2020**



### H<sub>2</sub>S Drilling Operations Plan

- a. All personnel will be trained in H<sub>2</sub>S working conditions as required by Onshore Order 6 before drilling out of the surface casing.
- b. Two briefing areas will be established. Each briefing area will be  $\geq 150'$  from the wellhead, perpendicular from one another, and easily entered and exited. See H<sub>2</sub>S page 5 for more details.
- c. H<sub>2</sub>S Safety Equipment/Systems:
  - i. Well Control Equipment
    - Flare line will be  $\geq 150'$  from the wellhead and ignited by a flare gun.
    - Beware of SO<sub>2</sub> created by flaring.
    - Choke manifold will have a remotely operated choke.
    - Mud gas separator
  - ii. Protective Equipment for Personnel
    - Every person on site will wear a personal H<sub>2</sub>S and SO<sub>2</sub> monitor at all times while on site. Monitors will not be worn on hard hats. Monitors will be worn on the front of the waist or chest.
    - One self-contained breathing apparatus (SCBA) 30-minute rescue pack will be at each briefing area. Two 30-minute SCBA packs will be stored in the safety trailer.
    - Four work/escape packs will be on the rig floor. Each pack will have a sufficiently long hose to allow unimpaired work activity.
    - Four emergency escape packs will be in the doghouse for emergency evacuation.
    - Hand signals will be used when wearing protective breathing apparatus.
    - Stokes litter or stretcher
    - Two full OSHA compliant body harnesses
    - A 100' long x 5/8" OSHA compliant rope
    - One 20-pound ABC fire extinguisher
  - iii. H<sub>2</sub>S Detection & Monitoring Equipment
    - Every person on site will wear a personal H<sub>2</sub>S and SO<sub>2</sub> monitor at all times while on site. Monitors will not be worn on hard hats. Monitors will be worn on the front of the waist or chest.

- A stationary detector with three sensors will be in the doghouse.
- Sensors will be installed on the rig floor, bell nipple, and at the end of the flow line or where drilling fluids are discharged.
- Visual alarm will be triggered at 10 ppm.
- Audible alarm will be triggered at 10 ppm.
- Calibration will occur at least every 30 days. Gas sample tubes will be kept in the safety trailer.

iv. Visual Warning System

- A color-coded H<sub>2</sub>S condition sign will be set at each pad entrance.
- Color-coded condition flag will be installed to indicate current H<sub>2</sub>S conditions.
- Two wind socks will be installed that will be visible from all sides.

v. Mud Program

- A water based mud with a pH of  $\geq 10$  will be maintained to control corrosion, H<sub>2</sub>S gas returns to the surface, and minimize sulfide stress cracking and embrittlement.
- Drilling mud containing H<sub>2</sub>S gas will be degassed at an optimum location for the rig configuration.
- This gas will be piped into the flare system.
- Enough mud additives will be on site to scavenge and/or neutralize H<sub>2</sub>S where formation pressures are unknown.

vi. Metallurgy

- All equipment that has the potential to be exposed to H<sub>2</sub>S will be suitable for H<sub>2</sub>S service.
- Equipment that will meet these metallurgical standards include the drill string, casing, wellhead, BOP assembly, casing head and spool, rotating head, kill lines, choke, choke manifold and lines, valves, mud-gas separators, DST tools, test units, tubing, flanges, and other related equipment (elastomer packings and seals).

vii. Communication from well site

- Cell phones and/or two-way radios will be used to communicate from the well site.

d. A remote-controlled choke, mud-gas separator, and a rotating head will be installed before drilling or testing any formation expected to contain H<sub>2</sub>S.

### Company Personnel to be Notified

Dean Gimbel, Vice President Completions	Office: (720) 710-8995
	Mobile: (303) 945-1323
Matt Ward, Chief Operations Officer	Mobile: (303) 506-6647
Ascent Emergency Contact Number	(303) 281-9951

### Local & County Agencies

Monument Fire Department	911 or (575) 393-4339
Hobbs Fire Marshal	(575) 391-8185
Lea County Sheriff (Lovington)	911 or (575) 396-3611
Lea County Emergency Management (Lovington)	(575) 396-8602
Lea Regional Medical Center Hospital (Hobbs)	(575) 492-5000

### State Agencies

NM State Police (Hobbs)	(575) 392-5588
NM Oil Conservation (Hobbs)	(575) 370-3186
NM Oil Conservation (Santa Fe)	(505) 476-3440
NM Dept. of Transportation (Roswell)	(575) 637-7201

### Federal Agencies

BLM Carlsbad Field Office	(575) 234-5972
BLM Hobbs Field Station	(575) 393-3612
National Response Center	(800) 424-8802
US EPA Region 6 (Dallas)	(800) 887-6063
	(214) 665-6444

### Veterinarians

Dal Paso Animal Hospital (Hobbs)	(575) 397-2286
Hobbs Animal Clinic & Pet Care (Hobbs)	(575) 392-5563
Great Plains Veterinary Clinic & Hospital (Hobbs)	(575) 392-5513

### Residents within 2 miles

No residents are within 2 miles.

### Air Evacuation

Med Flight Air Ambulance (Albuquerque)	(800) 842-4431
Lifeguard (Albuquerque)	(888) 866-7256

SECTION 1, TOWNSHIP 21 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
SITE MAP

EL. 3788.6'

NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83). BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE. ELEVATION VALUES ARE NAVD 88.

700'

flare line (straight)  
& flare >150'  
from well head

30'

N89°30'24"E

500.06 FT

EL. 3791.8'

windsocks on  
rig floor & at  
mud tanks

125' NORTH  
OFFSET  
EL. 3792.2'

EL. 3793.8'

499.96 FT

235' WEST  
OFFSET  
EL. 3790.8'

BIG STAGG FED COM 603H

PROPOSED  
BIG STAGG  
FED COM

laydown  
(V-door)  
to east

ELEV. = 3794.0'  
5.740± ACRES

LAT. = 32.5007660°N (NAD83)  
LONG. = 103.6272207°W  
NMSP EAST (FT)  
N = 546630.20  
E = 759028.33

PROPOSED  
BIG STAGG  
FED COM 503H

TOP SOIL AREA

N00°21'04"W

secondary egress  
safety briefing area  
>150' from  
well head

PRIMARY safety briefing area  
>150' from well head &  
egress (exit) route

highest ground  
to the southeast

warning signs  
& windsock

prevailing winds  
blow from south

EL. 3787.3' S89°30'52"W

375' SOUTH  
OFFSET  
EL. 3792.8'

500.04 FT EL. 3797.9'

PROPOSED 50 L.F.  
ACCESS ROAD

PROPOSED 50 L.F.  
ACCESS ROAD

PROPOSED ACCESS ROAD

EL. 3786.3'

700'

EL. 3800.7'

DIRECTIONS TO LOCATION

FROM U.S. HWY 62-180 AND STATE ROAD 176 GO EAST ON STATE ROAD 176 6.4 MILES, TURN RIGHT ON CALICHE ROAD AND GO SOUTH 0.5 MILE, THEN RIGHT AND GO SOUTHWEST 1.05 MILES TO A ROAD SOUTHEAST 0.2 MILE, THEN EAST 0.35 MILE, THEN NORTH 50' TO THE SOUTHWEST CORNER.

warning signs  
& windsock

I, FILMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFICATE NO. 12789, AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY CONTRIBUTES TO THE BEST OF MY KNOWLEDGE AND BELIEF TO THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

9/13/19

0 10 50 100 200  
SCALE 1" = 100'

ASCENT ENERGY, LLC  
**BIG STAGG FED COM 603H**  
LOCATED 30 FT. FROM THE SOUTH LINE  
AND 2280 FT. FROM THE EAST LINE OF  
SECTION 1, TOWNSHIP 21 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

SEPTEMBER 13, 2019

SURVEY NO. 7467A

MADRON SURVEYING, INC.

301 SOUTH CANAL  
(575) 234-3341

CARLSBAD, NEW MEXICO

# Ascent Energy, LLC

Big Stagg Fed Com Pad  
H<sub>2</sub>S Contingency Plan:  
2 Mile Radius Map

Section 1, Township 21S, Range 32E  
Lea County, New Mexico

 Surface Hole Location



1:27,000  
0 0.25 0.5 1  
Miles




NAD 1983 New Mexico State Plane East  
FIPS 3001 Feet



Prepared by Permits West, Inc., June 17, 2019  
for Ascent Energy LLC





**Schematic Closed Loop Drilling Rig\***

1. Pipe Rack
2. Drill Rig
3. House Trailers/ Offices
4. Generator/Fuel/Storage
5. Overflow-Frac Tank
6. Skids
7. Roll Offs
8. Hopper or Centrifuge
9. Mud Tanks
10. Loop Drive
11. Generator (only for use with centrifuge)

\*Not drawn to scale: Closed loop system requires at least 30 feet beyond mud tanks. Ideally 60 feet would be available



**Above: Centrifugal Closed Loop System**



Closed Loop Drilling System: Mud tanks to right (1)  
 Hopper in air to settle out solids (2)  
 Water return pipe (3)  
 Shaker between hopper and mud tanks (4)  
 Roll offs on skids (5)

Flow Chart for Drilling Fluids and Solids

